



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

### Usage guidelines


Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

### About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>





nudica  
QM  
23  
978  
1913

mm.







# ANATOMY

## DESCRIPTIVE AND APPLIED

BY

HENRY GRAY, F.R.S.

FELLOW OF THE ROYAL COLLEGE OF SURGEONS; LECTURER ON ANATOMY AT ST. GEORGE'S  
HOSPITAL MEDICAL SCHOOL, LONDON

A NEW AMERICAN

FROM THE EIGHTEENTH ENGLISH EDITION

*THOROUGHLY REVISED AND RE-EDITED*

WITH THE BASLE ANATOMICAL NOMENCLATURE  
IN ENGLISH

BY

ROBERT HOWDEN, M.A., M.B., C.M.

PROFESSOR OF ANATOMY IN THE UNIVERSITY OF DURHAM, ENGLAND

---

Illustrated with 1126 Engravings



LEA & FEBIGER  
PHILADELPHIA AND NEW YORK  
1913

Medical.  
QM  
23  
.G78  
1913

Entered according to the Act of Congress, in the year 1913, by  
LEA & FEBIGER  
in the Office of the Librarian of Congress. All rights reserved.

THE FIRST EDITION OF THIS WORK

WAS DEDICATED TO

**SIR BENJAMIN COLLINS BRODIE, BART., F.R.S., D.C.L.**

IN ADMIRATION OF

HIS GREAT TALENTS

AND IN REMEMBRANCE OF

MANY ACTS OF KINDNESS SHOWN TO THE ORIGINAL

AUTHOR OF THE BOOK

FROM AN

EARLY PERIOD OF HIS PROFESSIONAL CAREER





# PREFACE.

THE outstanding modification in the text of this edition is the use of the Basle nomenclature. Except in one or two instances, this nomenclature has been adopted in its entirety; in most cases English translations of the Latin terms are employed, but in those cases where the Latin terms have become fixed by routine usage it has been deemed desirable to retain them. Where the Basle nomenclature differs materially from the older terminology, the latter has been added in brackets, and for further convenience a glossary is appended showing (a) the terms adopted in the text, (b) the Basle, and (c) the old terminology.

The paragraphs on Surface Anatomy, which in previous editions were appended separately to the descriptions of the various structures, have been collected and recast into a special chapter—an arrangement which admits of more easy reference.

The section on Histology has been shortened. The elementary tissues are described in it, but the complex tissues are considered along with the organs to which they are specially related. The whole text has been thoroughly revised and, where necessary, rewritten.

About two hundred new engravings have been added; some of them replace older figures, but many are additional, and the majority are drawn from original preparations.

The notes on Applied Anatomy have been revised by A. J. JEX-BLAKE, M.A., M.B., B.Ch., F.R.C.P., Assistant Physician to St. George's Hospital, London, and W. FEDDE FEDDEN, M.S., F.R.C.S., Assistant Surgeon and Lecturer on Surgical Anatomy in St. George's Hospital, London, England.

I am deeply indebted to Dr. J. ACKWORTH MENZIES, Lecturer on Physiology, and to Drs. J. DUNLOP LICKLEY and J. C. BOILEAU GRANT, Demonstrators of Anatomy in this University. Dr. Menzies revised the histological part of the book, and furnished a number of microscopic preparations for drawings. Dr. Lickley helped to revise the text, arranged the chapter on Surface Anatomy and Surface Markings, and passed the book through the press. Dr. Grant prepared the dissections for the new illustrations and assisted in the revision of the text.

I am also indebted to that skilled anatomical artist Mr. Sydney T. Sewell, who made the drawings for the new illustrations and who spared no pains to produce clear and accurate figures.

ROBERT HOWDEN.

UNIVERSITY OF DURHAM COLLEGE OF MEDICINE,  
NEWCASTLE-UPON-TYNE, 1913.



## PUBLISHERS' NOTE.

---

BOOKS, like men, have characters that can be analyzed to a certain point, but beyond or below lies a quality, subtle as life, and incapable of analysis or imitation, which is called personality. The greater the author, and the more intense his mental action in creating his book, the more it partakes of this element. This principle, so clear as to be almost axiomatic, is illustrated to the fullest extent in the work in hand. Henry Gray combined two faculties, either one sufficient to make his name famous. He was a great anatomist and a great teacher. He possessed a thorough knowledge of anatomy and an equal insight into the best methods of imparting it to other minds. His text was unequalled in clearness, and he united with it a series of incomparable illustrations. He devised the method of engraving the names of the parts directly upon them, thereby exhibiting at a glance not only their nomenclature, but also their position, extent, and relations. His work, still unique in this respect, was also the first to employ colors. Summing all, it is hardly to be wondered at that students and teachers alike find their labors reduced and the permanence of knowledge increased by the use of this book.

On its original appearance, over half a century ago, *Gray* immediately took the leading place, and it has not only maintained its position in its own subject, but has also become the best-known work in all medical literature. It is incomparably the greatest text-book in medicine, measured by the number of students who use it, and it is unique also in being the one work which is certain to be carried from college to afford guidance in the basic questions underlying practice.

The consequent demand is evidenced in the number of editions, which collectively represent the labors of many of the leading anatomists since the early death of its talented author. In this new revision every line has been carefully considered, any possible obscurity has been clarified, the latest accessions to anatomical knowledge have been introduced, and much has been rewritten. Care has been exercised to make the text a homogeneous, sequential, and complete presentation of the subject, meeting every need of the student, physician, or surgeon.

As directions are given for dissecting, this volume will serve every requirement of the student throughout his course. The Basle Anatomical Nomenclature in English has been used in the text and on the engravings, this being preferable to the Latin form in the judgment of such eminent anatomists as Professor Howden and Professor Mall. A Glossary exhibiting the three accepted nomenclatures in parallel columns will be found a great convenience. The Table of Contents is so arranged as to give a complete conspectus of anatomy, a feature of obvious value. The whole book is thoroughly organized in its headings and the sequence of subjects, so that the student receives his knowledge of the parts in their anatomical dependence.

As a teaching instrument the new *Gray's Anatomy* embodies all that careful thought and unstinted expenditure can combine in a text-book.



# CONTENTS.

## HISTOLOGY.

<i>The Animal Cell.</i>		Cartilage	47
Protoplasm	33	Hyaline Cartilage	47
Nucleus	34	White Fibrocartilage	49
Reproduction of Cells	34	Yellow or Elastic Fibrocartilage	50
Prophase	35	Bone	50
Metaphase	36	Structure and Physical Properties	50
Anaphase	36	Periosteum	51
Telophase	36	Marrow	51
		Vessels and Nerves of Bone	52
		Ossification	56
		Applied Anatomy	59
<i>Epithelium.</i>			
Simple Epithelium	37	<i>The Circulating Fluids.</i>	
Simple Squamous or Pavement Epithelium	37	Blood	61
Columnar or Cylindrical Epithelium	37	General Composition of the Blood	61
Glandular Epithelium	37	Lymph	64
Ciliated Epithelium	37		
Stratified Epithelium	39	<i>The Muscular Tissue.</i>	
Transitional Epithelium	40	Striped or Voluntary Muscle	64
		Vessels and Nerves of Striped Muscle	67
<i>Connective Tissue.</i>		Unstriated Plain or Involuntary Muscle	67
The Connective Tissues Proper	40	Cardiac Muscular Tissue	68
Areolar Tissue	40	Development of Muscle Fibres	69
Adipose Tissue	42		
White Fibrous Tissue	43	<i>The Nervous Tissue.</i>	
Yellow Elastic Tissue	44	Neuroglia	70
Mucous Tissue	44	Nerve Cells	70
Retiform or Reticular Tissue	44	Nerve Fibres	73
Basement Membranes	45	Wallerian Degeneration	76
Vessels and Nerves of Connective Tissue	46	Non-medullated Fibres	76
Pigment	46		
Applied Anatomy	46		
Development of Connective Tissue	47		

## EMBRYOLOGY.

<i>The Ovum.</i>		<i>Separation of the Embryo</i>		92
Yolk	78	<i>The Yolk-sac</i>		93
Germinal Vesicle	78	<i>Development of the Fetal Membranes and Placenta.</i>		
Coverings of the Ovum	79	The Allantois	93	
Maturation of the Ovum	79	The Amnion	94	
		The Umbilical Cord and Body-stalk	96	
<i>The Spermatozoön</i>		Implantation or Imbedding of the Ovum	97	
	80	The Decidua	98	
<i>Fertilization of the Ovum</i>		The Chorion	99	
	82	The Placenta	100	
<i>Segmentation of the Fertilized Ovum.</i>		Fetal Portion	100	
The Primitive Streak; Formation of the		Maternal Portion	100	
Mesoderm	86	Separation of the Placenta	101	
Ectoderm	87			
Entoderm	87	<i>Development of the Parieties.</i>		
Mesoderm	88	The Skeleton	102	
		The Vertebral Column	102	
<i>The Neural Groove and Tube</i>		The Ribs	104	
	88			
<i>The Notochord</i>				
	90			
<i>The Primitive Segments</i>				
	91			





The Frontal Bone	233	The Scapula	304
Squama	234	The Spine	306
Orbital or Horizontal Part	235	The Acromion	306
The Temporal Bone	237	The Coracoid Process	307
The Squama	237	Applied Anatomy	309
Mastoid Portion	239	The Humerus	309
Petrous Portion	241	Upper Extremity	309
Tympanic Part	243	The Head	309
Styloid Process	244	The Anatomical Neck	309
The Sphenoidal Bone	245	The Greater Tubercle	309
Body	246	The Lesser Tubercle	309
The Great Wings	248	The Body or Shaft	311
The Small Wings	249	The Lower Extremity	312
Pterygoid Processes	250	Applied Anatomy	313
The Sphenoidal Conchæ	250	The Ulna	314
Ethmoidal bone	251	The Upper Extremity	315
Cribriform plate	252	The Olecranon	315
Perpendicular Plate	252	The Coronoid Process	315
Labyrinth or Lateral Mass	253	The Semilunar Notch	315
Sutural or Wormian Bones	255	The Radial Notch	318
Applied Anatomy	255	The Body or Shaft	318
		The Lower Extremity	318
<i>The Facial Bones.</i>		The Radius	319
The Nasal Bones	255	The Upper Extremity	320
The Maxillæ (Upper Jaw)	256	The Body or Shaft	320
The Maxillary Sinus or Antrum of High-		The Lower Extremity	321
more	259	Applied Anatomy of the Ulna and Radius	321
The Zygomatic Process	260		
The Frontal Process	260	<i>The Hand.</i>	
The Alveolar Process	260	The Carpus	323
The Palatine Process	260	Common Characteristics of the Carpal	
Changes Produced in the Maxilla by Age	262	Bones	323
The Lacrimal Bone	263	Bones of the Proximal Row	323
The Zygomatic Bone	263	The Navicular Bone	323
The Palatine Bone	265	The Lunate Bone	323
The Horizontal Part	266	The Triangular Bone	324
The Vertical Part	266	The Pisiform Bone	326
The Pyramidal Process or Tuberosity	267	Bones of the Distal Row	326
The Orbital Process	267	The Greater Multangular Bone	326
The Sphenoidal Process	268	The Lesser Multangular Bone	327
The Inferior Nasal Concha	268	The Capitate Bone	327
The Vomer	269	The Hamate Bone	328
Applied Anatomy	271	The Metacarpus	329
The Mandible (Lower Jaw)	271	Common Characteristics of the Meta-	
Changes Produced in the Mandible by		carpal Bones	329
Age	275	Characteristics of the Individual Meta-	
The Hyoid Bone	275	carpal Bones	329
Applied Anatomy	277	The First Metacarpal Bone	329
		The Second Metacarpal Bone	329
<i>The Exterior of the Skull.</i>		The Third Metacarpal Bone	330
Norma Verticalis	277	The Fourth Metacarpal Bone	330
Norma Basalis	278	The Fifth Metacarpal Bone	330
Norma Lateralis	281	The Phalanges of the Hand	331
The Temporal Fossa	282	Ossification of the Bones of the Hand	331
The Infratemporal Fossa	283	Applied Anatomy of the Bones of the Hand	332
The Pterygopalatine Fossa	284		
Norma Occipitalis	284	<i>The Bones of the Lower Extremity.</i>	
Norma Frontalis	285	The Hip Bone	333
The Orbits	286	The Ilium	333
		The Body	333
<i>The Interior of the Skull.</i>		The Ala	333
Inner Surface of the Skull-cap	288	The Ischium	336
Under Surface of the Base of the Skull	288	The Body	336
The Anterior Fossa	288	The Superior Ramus	337
The Middle Fossa	290	The Inferior Ramus	337
The Posterior Fossa	291	The Pubis	337
The Nasal Cavities	292	The Body	337
Anterior Nasal Aperture	294	The Superior Ramus	337
Differences in the Skull Due to Age	294	The Inferior Ramus	338
Sexual Differences in the Skull	295	The Acetabulum	339
Craniology	295	The Obturator Foramen	339
Applied Anatomy	297	The Pelvis	340
		The Greater or False Pelvis	340
		The Lesser or True Pelvis	340
		Axes	342
		Position of the Pelvis	342
		Differences between Male and Female	
		Pelves	343
		Applied Anatomy	344
		The Femur	345
		The Upper Extremity	345
		The Head	345
		The Neck	345
		The Trochanters	346
<i>THE EXTREMITIES.</i>			
<i>The Bones of the Upper Extremity.</i>			
The Clavicle	301		
The Sternal Extremity	303		
The Acromial Extremity	303		
Applied Anatomy	303		



<b>Articulations of the Pelvis—</b>		<b>Intercarpal Articulations—</b>	
Ligaments Connecting the Sacrum and		Articulations of the Distal Row of	
Ischium	404	Carpal Bones	427
The Sacrotuberous Ligament	404	The Dorsal Ligaments	427
The Sacrospinous Ligament	405	The Volar Ligaments	427
Sacrococcygeal Symphysis	406	The Interosseous Ligaments	427
The Anterior Sacrococcygeal Liga-		Articulations of the Two Rows of	
ment	406	Carpal Bones with Each Other	427
The Posterior Sacrococcygeal Liga-		The Volar Ligaments	428
ment	406	The Dorsal Ligaments	428
The Lateral Sacrococcygeal Liga-		The Collateral Ligaments	428
ment	406	Carpometacarpal Articulations	429
The Intertarticular Ligaments	406	Carpometacarpal Articulation of the	
The Pubic Symphysis	406	Trunk	429
The Anterior Pubic Ligament	407	Articulations of the Other Four Meta-	
The Posterior Pubic Ligament	407	carpal Bones with the Carpus	429
The Superior Pubic Ligament	407	The Dorsal Ligaments	429
The Arcuate Pubic Ligament	407	The Volar Ligaments	429
The Intertubercle Fribrocartilaginous		The Interosseous Ligaments	429
Lamina	407	Intermetacarpal Articulations	430
Mechanism of the Pelvis	408	The Transverse Metacarpal Ligament	430
		Metacarpophalangeal Articulations	430
		The Volar Ligaments	430
		The Collateral Ligaments	430
		Articulations of the Digits	431
<b>ARTICULATIONS OF THE UPPER EXTREMITY.</b>		<b>ARTICULATIONS OF THE LOWER EXTREMITY.</b>	
Sternoclavicular Articulation	409	Coxal Articulation or Hip-joint	432
The Articular Capsule	410	The Articular Capsule	432
The Anterior Sternoclavicular Ligament	410	The Iliofemoral Ligament	433
The Posterior Sternoclavicular Liga-		The Pubocapsular Ligament	433
ment	410	The Ischiocapsular Ligament	433
The Intercavicular Ligament	410	The Ligamentum Teres Femoris	434
The Costoclavicular Ligament	410	The Glenoidal Labrum	434
The Articular Disk	410	The Transverse Acetabular Ligament	434
Applied Anatomy	411	Applied Anatomy	437
Acromioclavicular Articulation	411	The Knee-joint	438
The Articular Capsule	411	The Articular Capsule	438
The Superior Acromioclavicular Liga-		The Ligamentum Patellae	439
ment	411	The Oblique Popliteal Ligament	439
The Inferior Acromioclavicular Liga-		The Tibial Collateral Ligament	439
ment	412	The Fibular Collateral Ligament	440
The Articular Disk	412	The Cruciate Ligaments	441
The Coracoclavicular Ligament	412	The Anterior Cruciate Ligament	441
The Trapezoid Ligament	412	The Posterior Cruciate Ligament	441
The Conoid Ligament	412	The Menisci	441
Applied Anatomy	413	The Medial Meniscus	442
The Ligaments of the Scapula	413	The Lateral Meniscus	442
The Coracoacromial Ligament	413	The Transverse Ligament	442
The Superior Transverse Ligament	413	Bursae	443
The Inferior Transverse Ligament	413	Applied Anatomy	446
Humeral Articulation or Shoulder-joint	414	Articulations between the Tibia and Fibula.	447
The Articular Capsule	414	Tibiofibular Articulation	448
The Coracohumeral Ligament	415	The Articular Capsule	448
Glenohumeral Ligaments	415	The Anterior Ligament	448
The Transverse Humeral Ligament	415	The Posterior Ligament	448
The Glenoidal Labrum	415	Interosseous Membrane	448
Bursae	415	Tibiofibular Syndesmosis	448
Applied Anatomy	417	The Anterior Ligament	448
Elbow-joint	418	The Posterior Ligament	448
The Anterior Ligament	418	The Interosseous Ligament	449
The Posterior Ligament	418	The Interosseous Ligament	449
The Ulnar Collateral Ligament	418	Talocrural Articulation or Ankle-joint	449
The Radial Collateral Ligament	419	The Articular Capsule	449
Applied Anatomy	421	The Deltoid Ligament	450
Radioulnar Articulation	422	The Anterior Talofibular Ligament	450
Proximal Radioulnar Articulation	422	The Posterior Talofibular Ligament	451
The Annular Ligament	422	The Calcaneofibular Ligament	451
Applied Anatomy	423	Applied Anatomy	452
Middle Radioulnar Union	423	Intertarsal Articulations	452
The Oblique Cord	423	Talocalcaneal Articulation	452
The Interosseous Membrane	423	The Articular Capsule	452
Distal Radioulnar Articulation	423	The Anterior Talocalcaneal Liga-	
The Volar Radioulnar Ligament	424	ment	452
The Dorsal Radioulnar Ligament	424	The Posterior Talocalcaneal Liga-	
The Articular Disk	424	ment	453
Radiocarpal Articulation or Wrist-joint	425	The Lateral Talocalcaneal Liga-	
The Volar Radiocarpal Ligament	426	ment	453
The Dorsal Radiocarpal Ligament	426	The Medial Talocalcaneal Liga-	
The Ulnar Collateral Ligament	426	ment	453
The Radial Collateral Ligament	426	The Interosseous Talocalcaneal	
Applied Anatomy	426	Ligament	453
Intercarpal Articulations	427	Talocalcaneonavicular Articulation	454
Articulations of the Proximal Row of			
Carpal Bones	427		
The Dorsal Ligaments	427		
The Volar Ligaments	427		
The Interosseous Ligaments	427		

Intertarsal Articulations—		Intertarsal Articulations	
Talocalcaneonavicular Articulation—		Cuboideonavicular Articulation—	
The Articular Capsule	454	The Interosseous Ligament	
The Dorsal Talonavicular Ligament	454	Intercuneiform and Cuneocuboid Articulation	
Calcaneocuboid Articulation	454	The Dorsal Ligaments	
The Articular Capsule	454	The Plantar Ligaments	
The Dorsal Calcaneocuboid Ligament	454	The Interosseous Ligaments	
The Bifurcated Ligament	454	Applied Anatomy	
The Long Plantar Ligament	454	Tarsometatarsal Articulations	
The Plantar Calcaneocuboid Ligament	454	The Dorsal Ligaments	
The Ligaments Connecting the Calcaneus and Navicular	455	The Plantar Ligaments	
The Plantar Calcaneonavicular Ligament	455	The Interosseous Ligaments	
Applied Anatomy	456	Intermetatarsal Articulations	
Cuneonavicular Articulation	456	The Dorsal Ligaments	
The Dorsal Ligaments	456	The Plantar Ligaments	
The Plantar Ligaments	456	The Interosseous Ligaments	
Cuboideonavicular Articulation	457	The Transverse Metatarsal Ligament	
The Dorsal Ligament	457	Metatarsophalangeal Articulations	
The Plantar Ligament	457	The Plantar Ligaments	
		The Collateral Ligaments	
		Articulations of the Digits	
		Arches of the Foot	

## MYOLOGY.

Applied Anatomy of Muscles	462	Masseter—	
<i>Tendons, Aponeuroses, and Fasciæ.</i>		Relations	
Tendons	463	Temporal Fascia	
Aponeuroses	463	Dissection	
Fasciæ	463	Temporalis	
		Relations	
		Dissection	
		Pterygoideus Externus	
		Relations	
		Pterygoideus Internus	
		Relations	
THE FASCIE AND MUSCLES OF THE HEAD.		THE FASCIE AND MUSCLES OF THE ANTERIOR LATERAL REGION OF THE NECK.	
<i>The Muscles of the Scalp.</i>		<i>The Superficial Cervical Muscle.</i>	
Dissection	464	Dissection	
The Skin of the Scalp	465	Superficial Fascia	
The Superficial Fascia	465	Platysma	
Epicranius	465		
Occipitalis	466		
Frontalis	466		
Galea Aponeurotica	466		
Applied Anatomy	466		
<i>The Muscles of the Eyelid.</i>		<i>The Lateral Cervical Muscles.</i>	
Dissection	467	The Fascia Colli	
Orbicularis Oculi	467	Applied Anatomy	
Corrugator	468	Sternocleidomastoideus	
<i>The Muscles of the Nose.</i>		Triangles of the Neck	
Procerus	469	Relations	
Nasalis	469	Applied Anatomy	
Depressor Septi	469		
Dilator Naris Posterior	469	<i>The Supra- and Infrahyoid Muscles.</i>	
Dilator Naris Anterior	469	Dissection	
<i>The Muscles of the Mouth.</i>		Digastricus	
Dissection	469	Relations	
Quadratus Labii Superioris	469	Stylohyoideus	
Caninus	470	The Stylohyoid Ligament	
Zygomaticus	470	Mylohyoideus	
Mentalis	470	Relations	
Quadratus Labii Inferioris	470	Dissection	
Triangularis	470	Geniohyoideus	
Buccinator	470	Dissection	
Relations	470	Sternohyoideus	
Pterygomandibular Raphé	471	Sternothyroideus	
Orbicularis Oris	471	Thyrohyoideus	
Risorius	472	Omohyoideus	
<i>The Muscles of Mastication.</i>		<i>The Anterior Vertebral Muscles.</i>	
Parotidomasseteric Fascia	472	Longus Colli	
Masseter	472	Longus Capitis	
		Rectus Capitis Anterior	
		Rectus Capitis Lateralis	

*The Lateral Vertebral Muscles.*

Scalenus Anterior	484
Relations	484
Scalenus Medius	484
Relations	485
Scalenus Posterior	485

THE FASCIAE AND MUSCLES OF THE TRUNK.

*The Deep Muscles of the Back.*

Dissection of the Muscles of the Back by Layers	485
The Lumbodorsal Fascia	486
Splenius Capitis	486
Splenius Cervicis	487
Sacrospinalis	488
Iliocostalis Lumborum	488
Iliocostalis Dorsi	488
Iliocostalis Cervicis	488
Longissimus Dorsi	488
Longissimus Cervicis	488
Longissimus Capitis	489
Spinalis Dorsi	489
Spinalis Cervicis	489
Spinalis Capitis	489
Semispinalis Dorsi	489
Semispinalis Cervicis	489
Semispinalis Capitis	489
Multifidus	489
Rotatores	490
Interspinales	490
Extensor Coccygis	490
Intertransversarii	490

*The Suboccipital Muscles.*

Rectus Capitis Posterior Major	491
Rectus Capitis Posterior Minor	491
Obliquus Capitis Inferior	491
Obliquus Capitis Superior	491
The Suboccipital Triangle	491
Applied Anatomy	492

*The Muscles of the Thorax.*

Intercostal Fascia	492
Intercostales	492
Intercostales Externi	492
Intercostales Interni	492
Subcostales	492
Transversus Thoracis	492
Levatores Costarum	493
Serratus Posterior Superior	493
Serratus Posterior Inferior	493
Diaphragma	493
Medial Lumbocostal Arch	495
Lateral Lumbocostal Arch	495
The Crura	495
The Central Tendon	495
Openings in the Diaphragma	495
Relations	496
Mechanism of Respiration	497

*The Muscles and Fascia of the Abdomen.*

The Antero-lateral Muscles of the Abdomen	498
Dissection	498
The Superficial Fascia	498
Obliquus Externus Abdominis	499
Aponeurosis of the Obliquus Externus Abdominis	499
Subcutaneous Inguinal Ring	500
The Intercrural Fibres	501
The Inguinal Ligament	501
The Lacunar Ligament	502
The Reflected Inguinal Ligament	502
Ligament of Cooper	502
Dissection	503
Obliquus Internus Abdominis	503
Cremaster	504
Dissection	504

The Antero-lateral Muscles of the Abdomen—

Transversus Abdominis	504
Inguinal Aponeurotic Falx	505
Dissection	505
Rectus Abdominis	506
Pyramidalis	507
The Linea Alba	507
The Lineae Semilunares	507
The Transversalis Fascia	508
The Abdominal Inguinal Ring	508
The Inguinal Canal	508
Extraperitoneal Connective Tissue	509
The Deep Crural Arch	509
The Posterior Muscles of the Abdomen	510
The Fascia Covering the Quadratus Lumborum	510
Quadratus Lumborum	510

*The Muscles and Fascia of the Pelvis.*

Pelvic Fascia	510
Levator Ani	513
Relations	514
Coccygeus	514

*The Muscles and Fascia of the Perineum.*

Muscles of the Anal Region	515
The Superficial Fascia	515
The Deep Fascia	515
Ischiorectal Fossa	515
Applied Anatomy	516
The Corrugator Cutis Ani	516
Sphincter Ani Externus	516
Sphincter Ani Internus	516

The Muscles of the Urogenital Region in the Male

Superficial Fascia	517
The Central Tendinous Point of the Perineum	518
Bulbocavernosus	518
Ischiocavernosus	518
The Deep Fascia	519
Transversus Perinaei Profundus	520
Sphincter Urethrae Membranaceae	520

The Muscles of the Urogenital Region in the Female

Transversus Perinaei Superficialis	520
Bulbocavernosus	520
Ischiocavernosus	521
Transversus Perinaei Profundus	521

THE FASCIA AND MUSCLES OF THE UPPER EXTREMITY.

*The Muscles Connecting the Upper Extremity to the Vertebral Column.*

Superficial Fascia	522
Deep Fascia	522
Trapezius	522
Latissimus Dorsi	524
Rhomboideus Major	525
Rhomboideus Minor	525
Levator Scapulae	525

*The Muscles Connecting the Upper Extremity to the Anterior and Lateral Thoracic Walls.*

Dissection of Pectoral Region and Axilla	525
Superficial Fascia	526
Applied Anatomy	526
Pectoralis Major	526
Relations	528
Dissection	528
Coracoclavicular Fascia	528
Pectoralis Minor	528
Relations	528
Subclavius	528
Relations	529
Serratus Anterior	529
Relations	530
Applied Anatomy	530

*The Muscles and Fasciæ of the Shoulder.*

Dissection	530
Deep Fascia	530
Deltoidæus	530
Relations	531
Applied Anatomy	531
Dissection	531
Subscapular Fascia	531
Subscapularis	531
Dissection	532
Supraspinatous Fascia	532
Supraspinatus	532
Infraspinatous Fascia	533
Infraspinatus	533
Teres Minor	533
Teres Major	533

*The Muscles and Fasciæ of the Arm.*

Dissection	533
Brachial Fascia	534
Coracobrachialis	534
Relations	534
Biceps Brachii	534
Relations	535
Brachialis	535
Relations	535
Applied Anatomy	535
Triceps Brachii	535
Applied Anatomy	535

*The Muscles and Fasciæ of the Forearm.*

Dissection	536
Antibrachial Fascia	536
The Volar Antibrachial Muscles	537
The Superficial Group	537
Pronator Teres	537
Applied Anatomy	537
Flexor Carpi Radialis	537
Palmaris Longus	538
Flexor Carpi Ulnaris	539
Flexor Digitorum Sublimis	539
The Deep Group	539
Dissection	539
Flexor Digitorum Profundus	540
Fibrous Sheaths of the Flexor	
Tendons	540
Flexor Pollicis Longus	540
Pronator Quadratus	540
The Dorsal Antibrachial Muscles	542
The Superficial Group	542
Dissection	542
Brachioradialis	542
Extensor Carpi Radialis Longus	542
Extensor Carpi Radialis Brevis	542
Extensor Digitorum Communis	544
Extensor Digiti Quinti Proprius	544
Extensor Carpi Ulnaris	544
Anconæus	544
The Deep Group	544
Supinator	544
Abductor Pollicis Longus	545
Extensor Pollicis Brevis	545
Extensor Pollicis Longus	545
Extensor Indicis Proprius	546
Applied Anatomy	546

*The Muscles and Fasciæ of the Hand.*

Dissection	546
Volar Carpal Ligament	547
Transverse Carpal Ligament	547
The Mucous Sheaths of the Tendons on the	
Front of the Wrist	548
Dorsal Carpal Ligament	550
The Mucous Sheaths of the Tendons on the	
Back of the Wrist	550
Palmar Aponeurosis	550
Applied Anatomy	551
The Lateral Volar Muscles	552
Abductor Pollicis Brevis	552
Opponens Pollicis	553
Flexor Pollicis Brevis	553

*The Lateral Volar Muscles—*  
Adductor Pollicis (Obliquus)  
Adductor Pollicis (Transversus)*The Medial Volar Muscles*

Palmaris Brevis	
Abductor Digiti Quinti	
Flexor Digiti Quinti Brevis	
Opponens Digiti Quinti	

*The Intermediate Muscles*

Lumbricales	
Interossei	
Interossei Dorsales	
Interossei Volares	

*Applied Anatomy of the Muscles of the*  
*Upper Extremity**THE MUSCLES AND FASCIÆ OF THE LOWER*  
*EXTREMITY.**The Muscles and Fasciæ of the Iliac Region*

Dissection	
The Fascia Covering the Psoas and Iliacus	
Psoas Major	
Relations	
Psoas Minor	
Iliacus	
Relations	
Applied Anatomy	

*The Muscles and Fasciæ of the Thigh.**The Anterior Femoral Muscles*

Dissection	
Superficial Fascia	
Deep Fascia	
The Fossa Ovalis	
Tensor Fasciæ Latae	
Sartorius	
Relations	
Quadriceps Femoris	
Rectus Femoris	
Vastus Lateralis	
Vastus Medialis	
Vastus Intermedius	
Articularis Genu	
Applied Anatomy	

*The Medial Femoral Muscles*

Dissection	
Gracilis	
Pectineus	
Relations	
Adductor Longus	
Relations	
Adductor Brevis	
Relations	
Adductor Magnus	
Relations	
Applied Anatomy	

*The Muscles of the Gluteal Region*

Dissection	
Glutæus Maximus	
Bursæ	
Relations	
Dissection	
Glutæus Medius	
Glutæus Minimus	
Piriformis	
Relations	

*Obturator Membrane**Dissection**Obturator Internus**Relations**Gemelli**Gemellus Superior**Gemellus Inferior**Quadratus Femoris**Obturator Externus**The Posterior Femoral Muscles**Dissection**Biceps Femoris**Semitendinosus**Semimembranosus**Applied Anatomy*

*The Muscles and Fasciæ of the Leg.*

*The Fasciæ Around the Ankle.*

The Anterior Crural Muscles . . . . .	576	Transverse Crural Ligament . . . . .	584
Dissection . . . . .	576	Cruciate Crural Ligament . . . . .	584
Deep Fascia . . . . .	576	Lacinate Ligament . . . . .	585
Dissection . . . . .	576	Peroneal Retinacula . . . . .	585
Tibialis Anterior . . . . .	576	The Mucous Sheaths of the Tendons Around the Ankle . . . . .	586
Extensor Hallucis Longus . . . . .	577		
Extensor Digitorum Longus . . . . .	577	<i>The Muscles and Fasciæ of the Foot.</i>	
Peronæus Tertius . . . . .	578	The Dorsal Muscle of the Foot . . . . .	586
The Posterior Crural Muscles . . . . .	578	Extensor Digitorum Brevis . . . . .	586
Dissection . . . . .	578	The Plantar Muscles of the Foot . . . . .	586
The Superficial Group . . . . .	578	Plantar Aponeurosis . . . . .	586
Gastrocnemius . . . . .	578	The First Layer . . . . .	587
Relations . . . . .	578	Dissection . . . . .	587
Soleus . . . . .	579	Abductor Hallucis . . . . .	587
Relations . . . . .	579	Flexor Digitorum Brevis . . . . .	588
Tendo Calcaneus . . . . .	579	Fibrous Sheaths of the Flexor Tendons . . . . .	588
Plantaris . . . . .	579	Abductor Digiti Quinti . . . . .	588
The Deep Group . . . . .	579	Dissection . . . . .	588
Dissection . . . . .	579	The Second Layer . . . . .	589
Deep Transverse Fascia . . . . .	580	Quadratus Plantæ . . . . .	589
Dissection . . . . .	581	Lumbricales . . . . .	589
Popliteus . . . . .	581	Dissection . . . . .	589
Relations . . . . .	581	The Third Layer . . . . .	589
Flexor Hallucis Longus . . . . .	581	Flexor Hallucis Brevis . . . . .	589
Relations . . . . .	581	Adductor Hallucis . . . . .	589
Flexor Digitorum Longus . . . . .	581	Flexor Digiti Quinti Brevis . . . . .	590
Relations . . . . .	582	The Fourth Layer . . . . .	590
Tibialis Posterior . . . . .	582	Interossei . . . . .	590
Relations . . . . .	582	Interossei Dorsales . . . . .	591
The Lateral Crural Muscles . . . . .	582	Interossei Plantares . . . . .	591
Dissection . . . . .	582	Applied Anatomy of the Muscles of the Lower Extremity . . . . .	592
Peronæus Longus . . . . .	582		
Peronæus Brevis . . . . .	583		
Applied Anatomy . . . . .	583		

ANGIOLOGY.

Structure of Arteries . . . . .	596	Right Atrium . . . . .	606
Capillaries . . . . .	598	Sinus Venarum . . . . .	606
Sinusoids . . . . .	599	Auricula . . . . .	606
Structure of Veins . . . . .	599	Dissection . . . . .	607
		Right Ventricle . . . . .	608
		Dissection . . . . .	609
		Left Atrium . . . . .	610
		Auricula . . . . .	610
		Dissection . . . . .	611
		Left Ventricle . . . . .	611
		Ventricular Septum . . . . .	612
		Structure of the Heart . . . . .	613
		Applied Anatomy . . . . .	614
		The Cardiac Cycle and the Actions of the Valves . . . . .	615
		Applied Anatomy . . . . .	615
		<i>Peculiarities in the Vascular System in the Fetus.</i>	
		Fetal Circulation . . . . .	616
		Changes in the Vascular System at Birth . . . . .	618

THE ARTERIES.

Applied Anatomy . . . . .	619	<i>The Arch of the Aorta.</i>	
The Pulmonary Artery . . . . .	620	Relations . . . . .	623
Relations . . . . .	620	Applied Anatomy . . . . .	624
Applied Anatomy . . . . .	621	The Innominate Artery . . . . .	625
		Relations . . . . .	625
		Branches . . . . .	625
		Thyreoidæ Ima . . . . .	626
		Applied Anatomy . . . . .	626
		THE ARTERIES OF THE HEAD AND NECK.	
		<i>The Common Carotid Artery.</i>	
		Relations . . . . .	627
		Peculiarities . . . . .	628

THE AORTA.

*The Ascending Aorta.*

Relations . . . . .	622
Branches . . . . .	622
The Coronary Arteries . . . . .	622
Right Coronary Artery . . . . .	622
Left Coronary Artery . . . . .	623
Applied Anatomy . . . . .	623





The Thoracic Aorta—		The Adductor Canal	713
Applied Anatomy	683	Relations of the Femoral Artery	713
Branches	685	Peculiarities of the Femoral Artery	714
Pericardial	685	Applied Anatomy	715
Bronchial	685	Branches	715
Esophageal	685	Superficial Epigastric Artery	715
Mediastinal	685	Superficial Iliac Circumflex Artery	716
Intercoastal Arteries	685	Superficial External Pudendal Artery	716
Branches	686	Deep External Pudendal Artery	716
Applied Anatomy	686	Muscular	716
Subcostal Arteries	686	Profunda Femoris Artery	716
Superior Phrenic	686	Relations	716
The Abdominal Aorta	686	Peculiarities	716
Relations	687	Branches	716
Applied Anatomy	687	Highest Genicular Artery	718
Branches	688		
The Celiac Artery	688		
Relations	688		
The Superior Mesenteric Artery	691		
Dissection	692		
Branches	692		
The Inferior Mesenteric Artery	694		
Dissection	695		
Branches	695		
Applied Anatomy	696		
The Middle Suprarenal Arteries	696		
The Renal Arteries	696		
The Internal Spermatic Arteries	697		
The Ovarian Arteries	697		
The Inferior Phrenic Arteries	697		
The Lumbar Arteries	698		
The Middle Sacral Artery	698		
<i>The Common Iliac Arteries.</i>			
Peculiarities	700		
Applied Anatomy	700		
The Hypogastric Artery	700		
Peculiarities	700		
Applied Anatomy	701		
Branches	701		
Superior Vesical Artery	701		
Middle Vesical Artery	701		
Inferior Vesical Artery	701		
Middle Hemorrhoidal Artery	701		
Uterine Artery	701		
Vaginal Artery	702		
Obturator Artery	702		
Branches	702		
Peculiarities	703		
Internal Pudendal Artery	703		
Relations	703		
Peculiarities	704		
Branches	704		
Inferior Gluteal Artery	706		
Branches	706		
Lateral Sacral Arteries	707		
Superior Gluteal Artery	707		
Applied Anatomy	708		
The External Iliac Artery	708		
Relations	708		
Applied Anatomy	708		
Branches	709		
Inferior Epigastric Artery	709		
Branches	709		
Peculiarities	709		
Applied Anatomy	710		
Deep Iliac Circumflex Artery	710		
<i>THE ARTERIES OF THE LOWER EXTREMITY.</i>			
<i>The Femoral Artery.</i>			
The Femoral Sheath	710		
The Femoral Triangle	712		
		<i>The Popliteal Fossa.</i>	
		Dissection	718
		Boundaries	718
		Contents	718
		The Popliteal Artery	718
		Relations	719
		Peculiarities	719
		Applied Anatomy	719
		Branches	720
		Superior Muscular	720
		Sural Arteries	720
		Cutaneous Branches	720
		Superior Genicular Arteries	720
		Middle Genicular Artery	720
		Inferior Genicular Arteries	721
		The Anastomosis Around the Knee-joint	721
		The Anterior Tibial Artery	722
		Relations	722
		Peculiarities	722
		Applied Anatomy	722
		Branches	722
		Posterior Tibial Recurrent Artery	722
		Fibular Artery	723
		Anterior Tibial Recurrent Artery	723
		Muscular Branches	723
		Anterior Medial Malleolar Artery	723
		Anterior Lateral Malleolar Artery	723
		The Arteria Dorsalis Pedis	724
		Relations	724
		Peculiarities	724
		Applied Anatomy	724
		Branches	724
		Lateral Tarsal Artery	724
		Medial Tarsal Artery	724
		Arcuate Artery	724
		Deep Plantar Artery	725
		The Posterior Tibial Artery	725
		Relations	725
		Peculiarities	725
		Applied Anatomy	725
		Branches	726
		Peroneal Artery	726
		Peculiarities	726
		Branches	726
		Nutrient Artery	726
		Muscular Branches	727
		Posterior Medial Malleolar Artery	727
		Communicating Branch	727
		Medial Calcaneal	727
		Medial Plantar Artery	727
		Lateral Plantar Artery	727
		Applied Anatomy	728
		Branches	728

## THE VEINS.

THE PULMONARY VEINS	730	<i>The Veins of the Head and Neck.</i>	
THE SYSTEMIC VEINS.		The Veins of the Exterior of the Head and Face	732
<i>The Veins of the Heart.</i>		The Frontal Vein	732
Coronary Sinus	730	The Supraorbital Vein	733
Tributaries	730	The Angular Vein	733
		The Anterior Facial Vein	733



The Right Lymphatic Duct	772
Tributaries	773
Applied Anatomy	773
 THE LYMPHATICS OF THE HEAD, FACE, AND NECK.	
The Lymph Glands of the Head	774
The Occipital Glands	774
The Posterior Auricular Glands	774
The Anterior Auricular Glands	775
The Parotid Glands	775
The Facial Glands	775
The Deep Facial Glands	775
The Lingual Glands	775
The Retropharyngeal Glands	776
The Lymphatic Vessels of the Scalp	776
The Lymphatic Vessels of the Auricula and External Acoustic Meatus	776
The Lymphatic Vessels of the Face	776
The Lymphatic Vessels of the Nasal Cavities	776
The Lymphatic Vessels of the Mouth	777
The Lymphatic Vessels of the Palatine Tonsil	777
The Lymphatic Vessels of the Tongue	778
The Lymph Glands of the Neck	778
The Submaxillary Glands	778
The Submental or Suprahoid Glands	778
The Superficial Cervical Glands	778
The Anterior Cervical Glands	778
The Deep Cervical Glands	778
The Lymphatic Vessels of the Skin and Muscles of the Neck	779
 THE LYMPHATICS OF THE UPPER EXTREMITY.	
The Lymph Glands of the Upper Extremity	779
The Superficial Lymph Glands	779
The Deep Lymph Glands	780
The Axillary Glands	780
Applied Anatomy	781
The Lymphatic Vessels of the Upper Extremity	781
The Superficial Lymphatic Vessels	781
The Deep Lymphatic Vessels	782
 THE LYMPHATICS OF THE LOWER EXTREMITY.	
The Lymph Glands of the Lower Extremity	782
The Anterior Tibial Gland	782
The Popliteal Glands	782
The Inguinal Glands	783
Applied Anatomy	784
The Lymphatic Vessels of the Lower Extremity	784
The Superficial Lymphatic Vessels	784
The Deep Lymphatic Vessels	785
 THE LYMPHATICS OF THE ABDOMEN AND PELVIS.	
The Lymph Glands of the Abdomen and Pelvis	785
The Parietal Glands	786
The External Iliac Glands	786
The Common Iliac Glands	786
The Epigastric Glands	786
The Iliac Circumflex Glands	786
The Hypogastric Glands	786
The Sacral Glands	787
The Lumbar Glands	787
The Lymphatic Vessels of the Abdomen and Pelvis	787
The Superficial Vessels	787
The Deep Vessels	787
The Lymphatic Vessels of the Perineum and External Genitals	787
 The Visceral Glands	
The Gastric Glands	788
The Hepatic Glands	788
The Pancreaticocolic Glands	788
The Superior Mesenteric Glands	789
The Mesenteric Glands	789
Applied Anatomy	789
The Ileocolic Glands	789
The Mesocolic Glands	791
The Inferior Mesenteric Glands	791
The Lymphatic Vessels of the Abdominal and Pelvic viscera	791
The Lymphatic Vessels of the Subdiaphragmatic Portions of the Digestive Tube	791
The Lymphatic Vessels of the Stomach	792
The Lymphatic Vessels of the Duodenum	792
The Lymphatic Vessels of the Jejunum and Ileum	792
The Lymphatic Vessels of the Vermiform Process and Cecum	792
The Lymphatic Vessels of the Colon	792
The Lymphatic Vessels of the Anus, Anal Canal, and Rectum	792
The Lymphatic Vessels of the Liver	792
The Lymphatic Vessels of the Gall-bladder	793
The Lymphatic Vessels of the Pancreas	793
The Lymphatic Vessels of the Spleen and Suprarenal Glands	793
The Lymphatic Vessels of the Urinary Organs	793
The Lymphatic Vessels of the Kidney	793
The Lymphatic Vessels of the Ureter	793
The Lymphatic Vessels of the Bladder	793
The Lymphatic Vessels of the Prostate	794
The Lymphatic Vessels of the Urethra	794
The Lymphatic Vessels of the Reproductive Organs	794
The Lymphatic Vessels of the Testes	794
The Lymphatic Vessels of the Ductus Deferens	794
The Lymphatic Vessels of the Ovary	795
The Lymphatic Vessels of the Uterine Tube	795
The Lymphatic Vessels of the Uterus	795
The Lymphatic Vessels of the Vagina	795
 THE LYMPHATICS OF THE THORAX.	
The Parietal Lymph Glands	796
The Sternal Glands	796
The Intercoastal Glands	797
The Diaphragmatic Glands	797
The Superficial Lymphatic Vessels of the Thoracic Wall	797
The Lymphatic Vessels of the Mammae	797
The Deep Lymphatic Vessels of the Thoracic Wall	797
The Visceral Lymph Glands	798
The Anterior Mediastinal Glands	798
The Posterior Mediastinal Glands	798
The Tracheobronchial Glands	798
Applied Anatomy	798
The Lymphatic Vessels of the Thoracic Viscera	799
The Lymphatic Vessels of the Heart	799
The Lymphatic Vessels of the Lungs	799
The Lymphatic Vessels of the Pleura	800
The Lymphatic Vessels of the Thymus	800
The Lymphatic Vessels of the Esophagus	800

## NEUROLOGY.

Structure of the Peripheral Nerves and Ganglia . . . . .	801	The Diencephalon— The Optic Tracts . . . . .	
		The Third Ventricle . . . . .	
		The Interpeduncular Fossa . . . . .	
THE MEDULLA SPINALIS OR SPINAL CORD.		The Telencephalon . . . . .	
Dissection . . . . .	805	The Cerebral Hemispheres . . . . .	
Enlargements . . . . .	808	The Longitudinal Cerebral Fissure . . . . .	
Fissures and Sulci . . . . .	808	The Surfaces of the Cerebral Hemispheres . . . . .	
The Anterior Median Fissure . . . . .	808	The Lateral Cerebral Fissure . . . . .	
The Posterior Median Sulcus . . . . .	808	The Central Sulcus . . . . .	
The Internal Structure of the Medulla Spinalis . . . . .	808	The Parietooccipital Fissure . . . . .	
The Gray Substance . . . . .	809	The Calcarine Fissure . . . . .	
Structure of the Gray Substance . . . . .	810	The Cingulate Sulcus . . . . .	
The White Substance . . . . .	814	The Collateral Fissure . . . . .	
Nerve Fasciculi . . . . .	814	The Sulcus Circularis . . . . .	
Roots of the Spinal Nerves . . . . .	818	The Lobes of the Hemispheres . . . . .	
The Anterior Nerve Root . . . . .	819	The Frontal Lobe . . . . .	
The Posterior Root . . . . .	819	The Parietal Lobe . . . . .	
Applied Anatomy . . . . .	820	The Occipital Lobe . . . . .	
		The Temporal Lobe . . . . .	
		The Insula . . . . .	
		The Limbic Lobe . . . . .	
THE ENCEPHALON OR BRAIN.		The Rhinencephalon . . . . .	
Dissection . . . . .	821	The Olfactory Lobe . . . . .	
General Considerations and Divisions . . . . .	821	The Interior of the Cerebral Hemispheres . . . . .	
<i>The Rhombencephalon or Hind-brain.</i>		The Corpus Callosum . . . . .	
The Medulla Oblongata . . . . .	822	The Lateral Ventricles . . . . .	
The Anterior Median Fissure . . . . .	822	The Fornix . . . . .	
The Posterior Median Fissure . . . . .	822	The Interventricular Foramen . . . . .	
Internal Structure of the Medulla Oblongata . . . . .	826	The Anterior Commissure . . . . .	
The Cerebrospinal Fasciculi . . . . .	826	The Septum Pellucidum . . . . .	
Gray Substance of the Medulla Oblongata . . . . .	829	The Choroid Plexus of the Lateral Ventricle . . . . .	
Restiform Bodies . . . . .	830	Structure of the Cerebral Hemispheres . . . . .	
Formatio Reticularis . . . . .	832	Structure of the Cerebral Cortex . . . . .	
Applied Anatomy . . . . .	833	Special Types of Cerebral Cortex . . . . .	
The Pons . . . . .	833	Weight of Encephalon . . . . .	
Structure . . . . .	834	Cerebral Localization . . . . .	
Applied Anatomy . . . . .	836	Applied Anatomy . . . . .	
The Cerebellum . . . . .	836		
Lobes of the Cerebellum . . . . .	836	<i>The Motor and Sensory Tracts.</i>	
Internal Structure of the Cerebellum . . . . .	839	The Motor Tract . . . . .	
The White Substance . . . . .	839	The Sensory Tract . . . . .	
Projection Fibres . . . . .	840	Applied Anatomy . . . . .	
The Gray Substance . . . . .	842		
Microscopic Appearance of the Cortex . . . . .	842	<i>The Meninges of the Brain and Medulla Spinalis</i>	
Applied Anatomy . . . . .	844	The Dura Mater . . . . .	
The Fourth Ventricle . . . . .	845	The Cerebral Dura Mater . . . . .	
Angles . . . . .	845	Processes . . . . .	
Lateral Boundaries . . . . .	845	Structure . . . . .	
Choroid Plexuses . . . . .	846	The Spinal Dura Mater . . . . .	
Openings in the Roof . . . . .	847	Structure . . . . .	
Rhomboid Fossa . . . . .	847	The Arachnoid . . . . .	
<i>The Mesencephalon or Mid-brain.</i>		The Cerebral Part . . . . .	
The Cerebral Peduncles . . . . .	848	The Spinal Part . . . . .	
Structure of the Cerebral Peduncles . . . . .	849	Structure . . . . .	
The Gray Substance . . . . .	850	The Subarachnoid Cavity . . . . .	
The White Substance . . . . .	851	The Subarachnoid Cisternæ . . . . .	
The Corpora Quadrigemina . . . . .	853	The Arachnoid Granulations . . . . .	
Structure of the Corpora Quadrigemina . . . . .	854	Structure . . . . .	
The Cerebral Aqueduct . . . . .	854	The Pia Mater . . . . .	
<i>The Prosencephalon or Fore-brain.</i>		The Cerebral Pia Mater . . . . .	
The Diencephalon . . . . .	855	The Spinal Pia Mater . . . . .	
The Thalamencephalon . . . . .	855	The Ligamentum Denticulatum . . . . .	
Structure . . . . .	856	Applied Anatomy . . . . .	
Connections . . . . .	857		
The Metathalamus . . . . .	858	THE CEREBRAL NERVES.	
The Epithalamus . . . . .	859	<i>The Olfactory Nerves.</i>	
The Hypothalamus . . . . .	860	Applied Anatomy . . . . .	
Applied Anatomy . . . . .	862		
The Optic Chiasma . . . . .	862	<i>The Optic Nerve.</i>	
		The Optic Tract . . . . .	
		The Optic Chiasma . . . . .	
		Applied Anatomy . . . . .	

<i>The Oculomotor Nerve.</i>			<i>The Ganglion Nodosum—</i>	
Applied Anatomy . . . . .	913		The Auricular Branch . . . . .	941
<i>The Trochlear Nerve.</i>			The Pharyngeal Branch . . . . .	942
Applied Anatomy . . . . .	914		The Superior Laryngeal Nerve . . . . .	942
<i>The Trigeminal Nerve.</i>			The Recurrent Nerve . . . . .	942
The Semilunar Ganglion . . . . .	914		The Superior Cardiac Branches . . . . .	942
The Ophthalmic Nerve . . . . .	915		The Inferior Cardiac Branches . . . . .	943
The Lacrimal Nerve . . . . .	915		The Anterior Bronchial Branches . . . . .	943
The Frontal Nerve . . . . .	916		The Posterior Bronchial Branches . . . . .	943
The Nasociliary Nerve . . . . .	916		The Esophageal Branches . . . . .	943
The Ciliary Ganglion . . . . .	917		The Gastric Branches . . . . .	943
The Maxillary Nerve . . . . .	917		The Coeliac Branches . . . . .	943
Branches . . . . .	917		The Hepatic Branches . . . . .	943
The Middle Meningeal Nerve . . . . .	917		Applied Anatomy of the Vagus Nerve . . . . .	943
The Zygomatic Nerve . . . . .	917		<i>The Accessory Nerve.</i>	
The Sphenopalatine . . . . .	918		The Cerebral Part . . . . .	944
The Posterior Superior Alveolar . . . . .	918		The Spinal Part . . . . .	945
The Middle Superior Alveolar . . . . .	919		Applied Anatomy . . . . .	945
The Anterior Superior Alveolar . . . . .	919		<i>The Hypoglossal Nerve.</i>	
The Inferior Palpebral . . . . .	919		Branches of Communication . . . . .	946
The External Nasal . . . . .	919		Branches of Distribution . . . . .	947
The Superior Labial . . . . .	919		The Meningeal Branches . . . . .	947
The Sphenopalatine Ganglion . . . . .	919		The Descending Ramus . . . . .	947
The Mandibular Nerve . . . . .	921		The Thyroid Branch . . . . .	947
Branches . . . . .	921		The Muscular Branches . . . . .	947
The Nervus Spinosus . . . . .	921		THE SPINAL NERVES.	
The Internal Pterygoid Nerve . . . . .	921		Nerve Roots . . . . .	948
The Masseteric Nerve . . . . .	921		The Anterior Root . . . . .	948
The Deep Temporal Nerves . . . . .	922		The Posterior Root . . . . .	948
The Buccinator Nerve . . . . .	922		The Spinal Ganglia . . . . .	948
The External Pterygoid Nerve . . . . .	922		Structure . . . . .	949
The Auriculotemporal Nerve . . . . .	923		Applied Anatomy . . . . .	950
The Lingual Nerve . . . . .	923		Divisions of the Spinal Nerves . . . . .	951
The Inferior Alveolar Nerve . . . . .	923		The Posterior Divisions . . . . .	951
The Otic Ganglion . . . . .	924		The Cervical Nerves . . . . .	951
The Submaxillary Ganglion . . . . .	925		The Thoracic Nerves . . . . .	952
Applied Anatomy of the Trigeminal Nerve . . . . .	925		The Lumbar Nerves . . . . .	953
Trigeminal Nerve Reflexes . . . . .	925		The Sacral Nerves . . . . .	953
<i>The Abducent Nerve.</i>			The Coccygeal Nerve . . . . .	954
Applied Anatomy . . . . .	929		The Anterior Divisions . . . . .	954
<i>The Facial Nerve.</i>			The Cervical Nerves . . . . .	954
The Greater Superficial Petrosal Nerve . . . . .	931		The Cervical Plexus . . . . .	954
The Nerve to the Stapedius . . . . .	932		Great Auricular Nerve . . . . .	956
The Chorda Tympani Nerve . . . . .	932		Cutaneous Cervical Nerve . . . . .	957
The Posterior Auricular Nerve . . . . .	933		Supraclavicular Nerves . . . . .	957
The Digastric Branch . . . . .	933		Communicantes Cervicales . . . . .	957
The Stylohyoid Branch . . . . .	933		Phrenic Nerve . . . . .	957
The Temporal Branches . . . . .	933		Applied Anatomy . . . . .	958
The Zygomatic Branches . . . . .	933		The Brachial Plexus . . . . .	958
The Buccal Branches . . . . .	933		Relations . . . . .	959
The Mandibular Branch . . . . .	933		Dorsal Scapular Nerve . . . . .	960
The Cervical Branch . . . . .	933		Suprascapular Nerve . . . . .	960
Applied Anatomy . . . . .	933		Nerve to Subclavius . . . . .	960
<i>The Acoustic Nerve.</i>			Long Thoracic Nerve . . . . .	960
The Vestibular Root . . . . .	935		Anterior Thoracic Nerves . . . . .	961
The Cochlear Root . . . . .	935		Subscapular Nerves . . . . .	960
Applied Anatomy . . . . .	936		Thoracodorsal Nerve . . . . .	960
<i>The Glossopharyngeal Nerve.</i>			Axillary Nerve . . . . .	960
The Superior Ganglion . . . . .	938		Musculocutaneous Nerve . . . . .	962
The Petrosal Ganglion . . . . .	939		Medial Antibrachial Cuta- neous Nerve . . . . .	964
The Tympanic Nerve . . . . .	939		Medial Brachial Cuta- neous Nerve . . . . .	964
The Carotid Branches . . . . .	939		Median Nerve . . . . .	965
The Pharyngeal Branches . . . . .	940		Radial Nerve . . . . .	968
The Muscular Branches . . . . .	940		Applied Anatomy . . . . .	970
The Tonsillar Branches . . . . .	940		The Thoracic Nerves . . . . .	972
The Lingual Branches . . . . .	940		First Thoracic Nerve . . . . .	972
<i>The Vagus Nerve.</i>			Upper Thoracic Nerves . . . . .	972
The Jugular Ganglion . . . . .	941		Lower Thoracic Nerves . . . . .	973
The Ganglion Nodosum . . . . .	941		Applied Anatomy . . . . .	974
The Meningeal Branch . . . . .	941		The Lumbosacral Plexus . . . . .	974
			The Lumbar Nerves . . . . .	974
			The Lumbar Plexus . . . . .	975
			Iliohypogastric Nerve . . . . .	976
			Ilioinguinal Nerve . . . . .	977
			Genitofemoral Nerve . . . . .	977

Divisions of the Spinal Nerves—			
The Anterior Divisions—			
The Lumbosacral Plexus—			
The Lumbar Nerves—			
The Lumbar Plexus—			
Lateral Femoral Cutaneous Nerve	977		
Obturator Nerve	979		
Accessory Obturator Nerve	980		
Femoral Nerve	980		
Saphenous Nerve	981		
The Sacral and Coccygeal Nerves	982		
The Sacral Plexus	982		
Relations	982		
Nerve to Quadratus Femoris and Gemellus Inferior	984		
Nerve to Obturator Internus and Gemellus Superior	984		
Nerve to Piriformis	984		
Superior Gluteal Nerve	984		
Inferior Gluteal Nerve	985		
Posterior Femoral Cutaneous Nerve	985		
Sciatic Nerve	986		
Tibial Nerve	987		
Lateral Plantar Nerve	989		
Common Peroneal Nerve	989		
Deep Peroneal Nerve	990		
Superficial Peroneal Nerve	990		
The Pudendal Plexus	991		
Perforating Cutaneous Nerve	991		
Pudendal Nerve	991		
Anococcygeal Nerve	992		
Applied Anatomy	992		
THE SYMPATHETIC NERVES.			
The Sympathetic Trunks	995		
Connections with the Spinal Nerves	995		
			<i>The Cephalic Portion of the Sympathetic System.</i>
			The Internal Carotid Plexus
			The Cavernous Plexus
			<i>The Cervical Portion of the Sympathetic System.</i>
			The Superior Cervical Ganglion
			Branches
			The Middle Cervical Ganglion
			Branches
			The Inferior Cervical Ganglion
			Branches
			<i>The Thoracic Portion of the Sympathetic System.</i>
			The Greater Splanchnic Nerve
			The Lesser Splanchnic Nerve
			The Lowest Splanchnic Nerve
			<i>The Abdominal Portion of the Sympathetic System</i>
			<i>The Pelvic Portion of the Sympathetic System</i>
			<i>The Great Plexuses of the Sympathetic System</i>
			The Cardiac Plexus
			The Coeliac Plexus
			Phrenic Plexus
			Hepatic Plexus
			Lienal Plexus
			Superior Gastric Plexus
			Suprarenal Plexus
			Renal Plexus
			Spermatic Plexus
			Applied Anatomy
			Superior Mesenteric Plexus
			Abdominal Aortic Plexus
			Inferior Mesenteric Plexus
			The Hypogastric Plexus
			The Pelvic Plexuses
			Applied Anatomy

## THE ORGANS OF THE SENSES AND THE COMMON INTEGUMENT

THE PERIPHERAL ORGANS OF THE SPECIAL SENSES.			
<i>The Organs of Taste.</i>			
Structure	1007		
<i>The Organ of Smell.</i>			
The External Nose	1008		
Structure	1008		
The Nasal Cavity	1010		
The Lateral Wall	1010		
The Medial Wall	1012		
The Mucous Membrane	1012		
Structure	1012		
The Accessory Sinuses of the Nose	1014		
The Frontal Sinuses	1014		
The Ethmoidal Air Cells	1014		
The Sphenoidal Sinuses	1014		
The Maxillary Sinus	1015		
Applied Anatomy of the Nose	1015		
<i>The Organ of Sight.</i>			
The Tunics of the Eye	1017		
The Fibrous Tunic	1017		
The Sclera	1017		
Structure	1018		
The Cornea	1018		
Structure	1019		
			<i>The Tunics of the Eye—</i>
			Dissection
			The Vascular Tunic
			The Choroid
			Structure
			Dissection
			The Ciliary Body
			Structure
			The Iris
			Structure
			Membrana Pupillaris
			The Retina
			Structure
			The Refracting Media
			The Aqueous Humor
			The Vitreous Body
			The Crystalline Lens
			Structure
			Applied Anatomy of the Organ of Sight
			The Accessory Organs of the Eye
			The Ocular Muscles
			Dissection
			Levator Palpebrae Superioris
			The Recti
			Obliquus Oculi Superior
			Obliquus Oculi Inferior
			The Fascia Bulb
			The Orbital Fascia
			Applied Anatomy
			The Eyebrows
			The Eyelids



**The Accessory Organs of the Eye—**

<b>The Eyelids—</b>	
The Lateral Palpebral Commissure	1038
The Eyelashes	1038
Structure of the Eyelids	1039
<b>The Tarsal Glands</b>	1040
Structure	1040
<b>The Conjunctiva</b>	1040
The Palpebral Portion	1040
The Bulbar Portion	1041
<b>The Lacrimal Apparatus</b>	1041
The Lacrimal Gland	1041
Structure	1041
The Lacrimal Ducts	1041
The Lacrimal Sac	1042
Structure	1042
The Nasolacrimal Duct	1042
Applied Anatomy	1042

*The Organ of Hearing.*

<b>The External Ear</b>	1043
The Auricula or Pinna	1044
Structure	1044
The External Acoustic Meatus	1046
Relations	1047
Applied Anatomy	1048
<b>The Middle Ear or Tympanic Cavity</b>	1049
The Tegumental Wall or Roof	1049
The Jugular Wall or Floor	1049
The Membranous or Lateral Wall	1049
The Tympanic Membrane	1050
Structure	1050
The Labyrinthine or Medial Wall	1050
The Mastoid or Posterior Wall	1051
The Carotid or Anterior Wall	1052
The Auditory Tube	1052
<b>The Auditory Ossicles</b>	1053
The Malleus	1053
The Incus	1054
The Stapes	1054
Articulations of the Auditory Ossicles	1054
Ligaments of the Ossicles	1054
The Muscles of the Tympanic Cavity	1055

**The Auditory Ossicles—**

<b>The Muscles of the Tympanic Cavity—</b>	
The Tensor Tympani	1055
The Stapedius	1055
Applied Anatomy	1056
<b>The Internal Ear or Labyrinth</b>	1057
The Osseous Labyrinth	1057
The Vestibule	1058
The Bony Semicircular Canals	1058
The Cochlea	1059
The Membranous Labyrinth	1061
The Utricle	1062
The Saccule	1062
The Semicircular Ducts	1062
Structure	1063
The Ductus Cochlearis	1063
The Basilar Membrane	1065
Hair Cells	1067
Applied Anatomy	1068

*Peripheral Terminations of Nerves of General Sensations.*

Free Nerve-endings	1069
Special End-organs	1069
End-bulbs of Krause	1069
Tactile Corpuscles of Grandry	1069
Pacinian Corpuscles	1069
Corpuscles of Golgi and Mazzoni	1069
Tactile Corpuscles of Wagner and Meissner	1070
Neurotendinous Spindles	1070
Neuromuscular Spindles	1070

**THE COMMON INTEGUMENT.**

The Epidermis, Cuticle, or Scarf Skin	1071
The Corium, Cutis Vera, Dermis, or True Skin	1074

*The Appendages of the Skin.*

The Nails	1075
The Hairs	1075
The Sebaceous Glands	1077
The Sudoriferous or Sweat Glands	1078

**SPLANCHNOLOGY.****THE RESPIRATORY APPARATUS.***The Larynx.*

<b>The Cartilages of the Larynx</b>	1079
The Thyroid Cartilage	1080
The Cricoid Cartilage	1081
The Arytenoid Cartilage	1081
The Corniculate Cartilages	1081
The Cuneiform Cartilages	1082
The Epiglottis	1082
Structure	1082
<b>The Ligaments of the Larynx</b>	1082
The Extrinsic Ligaments	1082
The Intrinsic Ligaments	1083
<b>The Interior of the Larynx</b>	1085
The Ventricular Folds	1085
The Vocal Folds	1086
The Ventricle of the Larynx	1086
The Rima Glottidis	1087
<b>The Muscles of the Larynx</b>	1088
Cricothyroideus	1088
Cricoaerytaenoideus Posterior	1088
Cricoaerytaenoideus Lateralis	1088
Arytaenoideus	1088
Thyreoarytaenoideus	1089

*The Trachea and Bronchi.*

Relations	1092
The Right Bronchus	1092
The Left Bronchus	1092
Structure	1092
Applied Anatomy	1093

*The Pleuræ.*

Reflections of the Pleura	1095
Pulmonary Ligament	1097
Structure of Pleura	1097
Applied Anatomy	1098

*The Mediastinal Cavity.*

Superior Mediastinal Cavity	1098
Anterior Mediastinal Cavity	1100
Middle Mediastinal Cavity	1101
Posterior Mediastinal Cavity	1101
Applied Anatomy	1101

*The Lungs.*

The Apex of the Lungs	1101
The Base of the Lungs	1102
Surfaces of the Lungs	1102
Borders of the Lungs	1103
Fissures and Lobes of the Lungs	1104
The Root of the Lung	1105
Divisions of the Bronchi	1105
Structure of the Lungs	1106
Applied Anatomy	1108

**THE DIGESTIVE APPARATUS.***The Mouth.*

The Vestibule of the Mouth	1110
The Mouth Cavity Proper	1110
Structure	1110
The Lips	1110



<b>The Kidneys—</b>			<b><i>The Female Genital Organs.</i></b>	
Borders	1209		The Ovaries	1243
Extremities	1209		The Epoöphoron	1244
Fixation of the Kidney	1209		The Paröphoron	1245
General Structure of the Kidney	1210		Structure	1245
Applied Anatomy	1214		Vesicular Ovarian Follicles	1245
<b>The Ureters</b>	1216		Applied Anatomy	1246
The Ureter Proper	1216		The Uterine Tube	1247
Structure	1217		Structure	1247
Applied Anatomy	1218		Applied Anatomy	1247
<b>The Urinary Bladder</b>	1218		The Uterus	1248
The Empty Bladder	1218		The Body	1249
The Distended Bladder	1219		The Cervix	1249
The Bladder in the Child	1220		The Interior of the Uterus	1250
The Female Bladder	1221		The Ligaments of the Uterus	1250
The Ligaments of the Bladder	1221		Structure	1252
The Interior of the Bladder	1222		Applied Anatomy	1254
Structure	1223		The Vagina	1255
Applied Anatomy	1224		Relations	1255
<b>The Male Urethra</b>	1225		Structure	1255
The Prostatic Portion	1225		The External Organs	1256
The Membranous Portion	1226		The Mons Pubis	1256
The Cavernous Portion	1226		The Labia Majora	1256
Structure	1226		The Labia Minora	1257
Applied Anatomy	1226		The Clitoris	1257
<b>The Female Urethra</b>	1228		The Vestibule	1257
Structure	1228		The Bulb of the Vestibule	1257
			The Greater Vestibular Glands	1258
<b><i>The Male Genital Organs.</i></b>			The Mammae	1258
The Testes and their Coverings	1228		The Mammary Papilla or Nipple	1258
The Scrotum	1228		Structure	1258
The Intercrural Fascia	1229		Applied Anatomy	1260
The Cremaster Muscle	1229			
The Infundibuliform Fascia	1229		<b>THE DUCTLESS GLANDS.</b>	
The Tunica Vaginalis	1229		<b><i>The Thyroid Gland.</i></b>	
The Inguinal Canal	1229		Structure	1262
The Spermatic Cord	1229		Applied Anatomy	1263
Structure of the Spermatic Cord	1230			
Applied Anatomy	1230		<b><i>The Parathyroid Glands.</i></b>	
The Testes	1230		Structure	1264
The Epididymis	1231		Applied Anatomy	1264
Appendages of the Testis and Epididymis	1231			
The Tunica Vaginalis	1231		<b><i>The Thymus.</i></b>	
The Tunica Albuginea	1232		Structure	1264
The Tunica Vasculosa	1232		Applied Anatomy	1266
Structure	1232			
Applied Anatomy	1234		<b><i>The Spleen.</i></b>	
<b>The Ductus Deferens</b>	1235		Structure	1264
The Ductuli Aberrantes	1236		Applied Anatomy	1266
Paradidymis	1236			
Structure	1236		<b><i>The Suprarenal Glands.</i></b>	
<b>The Vesiculæ Seminales</b>	1236		Relations	1270
Structure	1237		Structure	1271
Applied Anatomy	1237		Applied Anatomy	1272
<b>The Ejaculatory Ducts</b>	1237			
Structure	1237		<b><i>The Carotid Skeins</i></b>	1273
<b>The Penis</b>	1237		<b><i>The Coccygeal Skein</i></b>	1273
The Corpora Cavernosa Penis	1238			
The Corpus Cavernosum Urethrae	1238			
Structure of the Penis	1239			
Applied Anatomy	1240			
<b>The Prostate</b>	1241			
Structure	1241			
Applied Anatomy	1242			
<b>The Bulbourethral Glands</b>	1242			
Structure	1243			

## SURFACE ANATOMY AND SURFACE MARKINGS.

<b><i>Surface Anatomy of the Head and Neck.</i></b>		<b>The Cranium—</b>	
The Bones	1275	Bony Landmarks	1279
The Joints and Muscles	1276	The Brain	1280
The Arteries	1278	Vessels	1282
		The Face	1282
<b><i>Surface Markings of Special Regions of the Head and Neck.</i></b>		External Maxillary Artery	1282
		Trigeminal Nerve	1283
		Parotid Gland	1283
		The Nose	1284
The Cranium	1279	The Mouth	1284
The Scalp	1279	The Eye	1287

The Ear	1288	Descending Colon	
The Tympanic Antrum	1289	Iliac Colon	
The Neck	1289	Liver	
Muscles	1290	Pancreas	
Arteries	1290	Spleen	
Veins	1291	Kidneys	
Nerves	1291	Ureters	
Submaxillary Gland	1291	Vessels	
		Nerves	
<i>Surface Anatomy of the Back.</i>		<i>Surface Anatomy of the Perineum.</i>	
Bones	1291	Skin	
Muscles	1292	Bones	
		Muscles and Ligaments	
<i>Surface Markings of the Back.</i>		<i>Surface Markings of the Perineum.</i>	
Bony Landmarks	1293	Rectum and Anal Canal	
Medulla Spinalis	1293	Male Urogenital Organs	
Spinal Nerves	1295	Female Urogenital Organs	
<i>Surface Anatomy of the Thorax.</i>		<i>Surface Anatomy of the Upper Extremity.</i>	
Bones	1295	Skin	
Muscles	1295	Bones	
Mamma	1296	Articulations	
		Muscles	
<i>Surface Markings of the Thorax.</i>		Arteries	
Bony Landmarks	1296	Veins	
Diaphragma	1297	Nerves	
Surface Lines	1297		
Pleuræ	1297	<i>Surface Markings of the Upper Extremity.</i>	
Lungs	1298	Bony Landmarks	
Trachea	1299	Articulations	
Esophagus	1299	Muscles	
Heart	1300	Mucous Sheaths	
Arteries	1300	Arteries	
Veins	1300	Nerves	
<i>Surface Anatomy of the Abdomen.</i>		<i>Surface Anatomy of the Lower Extremity.</i>	
Skin	1301	Skin	
Bones	1301	Bones	
Muscles	1301	Articulations	
Vessels	1301	Muscles	
Viscera	1301	Arteries	
		Veins	
		Nerves	
<i>Surface Markings of the Abdomen.</i>		<i>Surface Markings of the Lower Extremity</i>	
Bony Landmarks	1303	Bony Landmarks	
Muscles	1303	Articulations	
Surface Lines	1303	Muscles	
Stomach	1305	Arteries	
Duodenum	1306	Veins	
Small Intestine	1306	Nerves	
Cecum and Vermiform Process	1307		
Ascending Colon	1307		
Transverse Colon	1307		

# INTRODUCTION.

**T**HE term *human anatomy* comprises a consideration of the various structures which make up the human organism. In a restricted sense it deals merely with the parts which form the fully developed individual and which can be rendered evident to the naked eye by various methods of dissection. Regarded from such a standpoint it may be studied by two methods: (1) the various structures may be separately considered—**systematic anatomy**; or (2) the organs and tissues may be studied in relation to one another—**topographical** or **regional anatomy**.

It is, however, of much advantage to add to the facts ascertained by naked-eye dissection those obtained by the use of the microscope. This introduces two fields of investigation, viz., the study of the minute structure of the various component parts of the body—**histology**—and the study of the human organism in its immature condition, *i. e.*, the various stages of its intrauterine development from the fertilized ovum up to the period when it assumes an independent existence—**embryology**. Owing to the difficulty of obtaining material illustrating all the stages of this early development, gaps must be filled up by observations on the development of lower forms—**comparative embryology**, or by a consideration of adult forms in the line of human ancestry—**comparative anatomy**. The direct application of the facts of human anatomy to the various pathological conditions which may occur constitutes the subject of **applied anatomy**. Finally, the appreciation of structures on immediately underlying the surface of the body is frequently made the subject of special study—**surface anatomy**.

**SYSTEMATIC ANATOMY.**—The various systems of which the human body is composed are grouped under the following headings:

1. **Osteology**—the bony system or skeleton.
2. **Syndesmology**—the articulations or joints.
3. **Myology**—the muscles. In the description of the muscles it is convenient to include that of the fasciæ which are so intimately connected with them.
4. **Angiology**—the vascular system, comprising the heart, bloodvessels, lymphatic vessels, and lymph glands.

5. **Neurology**—the nervous system. The organs of sense may be included in this system.

6. **Splanchnology**—the visceral system. Topographically the viscera form two groups, viz., the thoracic viscera and the abdominopelvic viscera. The heart, a thoracic viscus, is best considered with the vascular system. The rest of the viscera may be grouped according to their functions: (a) the **respiratory apparatus**; (b) the **digestive apparatus**; (c) the **urogenital apparatus**. Strictly speaking, the third subgroup should include only such components of the urogenital apparatus as are included within the abdominopelvic cavity, but it

is convenient to study under this heading certain parts which lie in relation to the surface of the body, *e. g.*, the testes and the external organs of generation.

For descriptive purposes the body is supposed to be in the erect posture, with the arms hanging by the sides and the palms of the hands directed forward. The *median plane* is a vertical antero-posterior plane, passing through the centre of the trunk. This plane will pass approximately through the sagittal suture of the skull, and hence any plane parallel to it is termed a *sagittal plane*. A vertical plane at right angles to the median plane passes, roughly speaking, through the central part of the coronal suture or through a line parallel to it; such a plane is known as a *frontal plane* or sometimes as a *coronal plane*. A plane at right angles to both the median and frontal planes is termed a *transverse plane*.

The terms *anterior* or *ventral*, and *posterior* or *dorsal*, are employed to indicate the relation of parts to the front or back of the body or limbs, and the terms *superior* or *cephalic*, and *inferior* or *caudal*, to indicate the relative levels of different structures; structures nearer to or farther from the median plane are referred to as *medial* or *lateral* respectively.

The terms *superficial* and *deep* are strictly confined to descriptions of the relative depth from the surface of the various structures; *external* and *internal* are reserved almost entirely for describing the walls of cavities or of hollow viscera. In the case of the limbs the words *proximal* and *distal* refer to the relative distance from the attached end of the limb.

# DESCRIPTIVE AND APPLIED ANATOMY.

## HISTOLOGY.

### THE ANIMAL CELL (Fig. 1).

ALL the tissues and organs of the body originate from a microscopic structure (the **fertilized ovum**), which consists of a soft jelly-like material enclosed in a membrane and containing a vesicle or small spherical body inside which are one or more denser spots. This may be regarded as a complete cell. All the solid tissues consist largely of cells essentially similar to it in nature but differing in external form.




FIG. 1.—Diagram of a cell. (Modified from Wilson.)

In the higher organisms a cell may be defined as “a nucleated mass of protoplasm of microscopic size.” Its two essentials, therefore, are: a soft jelly-like material, similar to that found in the ovum, and usually styled **protoplasm**, and a small spherical body imbedded in it, and termed a **nucleus**. Some of the unicellular protozoa contain no nuclei but granular particles which, like true nuclei, stain with basic dyes. The other constituents of the ovum, viz., its limiting membrane and the denser spot contained in the nucleus, called the **nucleolus**, are not essential to the type cell, and in fact many cells exist without them.

**Protoplasm** (*cytoplasm*) is a material probably of variable constitution during life, but yielding on its disintegration bodies chiefly of proteid nature. Lecithin and cholesterin are constantly found in it, as well as inorganic salts, chief among which are the phosphates and chlorides of potassium, sodium, and calcium. It is of a semifluid viscid consistence, and in the living condition appears to be homo-

geneous and structureless. When, however, cells have been "fixed" by reagents a fibrillar or granular appearance can often be made out under a high power of the microscope. The fibrils are usually arranged in a network or reticulum, to which the term **spongioplasm** is applied, the clear substance in the meshes being termed **hyaloplasm**. A granular appearance is often caused by the knots of the network; but, in addition to these, protoplasm frequently contains true granules, some of which are proteid in nature and probably essential constituents; others are fat, glycogen, or pigment granules, and are regarded as adventitious material taken in from without, and hence are styled cell-inclusions or **paraplasm**. The size and shape of the meshes of the spongioplasm vary in different cells and in different parts of the same cell. The relative amounts of spongioplasm and hyaloplasm also vary in different cells, the latter preponderating in the young cell and the former increasing at the expense of the hyaloplasm as the cell grows. The peripheral layer of a cell is in all cases modified, either by the formation of a definite **cell membrane** as in the ovum, or more frequently in the case of animal cells, by a transformation, probably chemical in nature, which is only recognizable by the fact that the surface of the cell behaves as a semipermeable membrane.

**Nucleus.**—The nucleus is a minute body, imbedded in the protoplasm, and usually of a spherical or oval form, its size having little relation to that of the cell. It is surrounded by a well-defined wall, the **nuclear membrane**; this encloses the **nuclear substance** (*nuclear matrix*), which is composed of a homogeneous material or **karyoplasm** containing a network or **karyomitome**. The former is probably of the same nature as the hyaloplasm of the cell, but the latter, which forms also the wall of the nucleus, differs from the spongioplasm of the cell substance. It consists of fibres or filaments arranged in a reticular manner. These filaments are composed of a homogeneous material known as **linin**, which stains with acid dyes and contains embedded in its substance particles which have a strong affinity for basic dyes. These basiphil granules have been named **chromatin** or **basichromatin** and owe their staining properties to the presence of nucleic acid.

Within the nuclear matrix are one or more highly refracting bodies, termed **nucleoli**, connected with the nuclear membrane by the nuclear filaments. They are regarded as being of two kinds. Some are mere local condensations ("net-knots") of the chromatin; these are irregular in shape and are termed **pseudo-nucleoli**; others are distinct bodies differing from the pseudo-nucleoli both in nature and chemical composition; they may be termed **true nucleoli**, and are usually found in resting cells. The true nucleoli are oxyphil, *i. e.*, they stain with acid dyes.

Most living cells contain, in addition to their protoplasm and nucleus, a small particle which usually lies near the nucleus and is termed the **centrosome**. In the middle of the centrosome is a minute body called the **centriole**, and surrounding this is a clear spherical mass known as the **centrosphere**. The protoplasm surrounding the centrosphere is frequently arranged in radiating fibrillar rows of granules, forming what is termed the **attraction sphere**.

**Reproduction of Cells.**—Reproduction of cells is effected either by **direct** or by **indirect division**. In reproduction by **direct division** the nucleus becomes constricted in its centre, assuming an hour-glass shape, and then divides into two. This is followed by a cleavage or division of the whole protoplasmic mass of the cell; and thus two daughter cells are formed, each containing a nucleus. These daughter cells are at first smaller than the original mother cell; but they grow, and the process may be repeated in them, so that multiplication may take place rapidly. **Indirect division** or **karyokinesis** (*karyomitosis*) has been observed in all the tissues—generative cells, epithelial tissue, connective tissue, muscular tissue, and nerve tissue. It is possible that cell division may always take place by the indirect method, and that in those cases in which direct division has been described the intermediate stages may not have been seen, owing to the process occurring more rapidly than usual.



The process of indirect cell division is characterized by a series of complex changes in the nucleus, leading to its subdivision; this is followed by cleavage of the cell protoplasm. Starting with the nucleus in the quiescent or **resting stage**, these changes may be briefly grouped under the four following phases (Fig. 2).




FIG. 2.—Diagram showing the changes which occur in the centrosomes and nucleus of a cell in the process of mitotic division. (Schäfer.) I to IV, prophase; V and VI, metaphase; VII and VIII, anaphase.

1. **Prophase.**—The nuclear network of chromatin filaments assumes the form of a twisted *skein* or *spirem*, while the nuclear membrane and nucleolus disappear. The convoluted skein of chromatin divides into a definite number of V-shaped segments or **chromosomes**. The number of chromosomes varies in different animals, but is constant for all the cells in an animal of any given species; in man the number is given by Flemming and Duesberg as twenty-four.<sup>1</sup> Coincidentally with or preceding these changes the centriole, which usually lies by the side of the nucleus, undergoes subdivision, and the two resulting centrioles, each surrounded by a centrosphere, are seen to be connected by a spindle of delicate achromatic fibres

<sup>1</sup> Dr. J. Duesberg, *Anat. Anz.*, Band xxviii, S. 475.

the **achromatic spindle**. The centrioles move away from each other—one toward either extremity of the nucleus—and the fibrils of the achromatic spindle are correspondingly lengthened. A line encircling the spindle midway between its extremities or **poles** is named the **equator**, and around this the V-shaped chromosomes arrange themselves in the form of a star, thus constituting the **mother star** or **monaster**.

2. **Metaphase**.—Each V-shaped chromosome now undergoes longitudinal cleavage into two equal parts or **daughter chromosomes**, the cleavage commencing at the apex of the V and extending along its divergent limbs. The daughter chromosomes, thus separated, travel in opposite directions along the fibrils of the achromatic spindle toward the centrioles, around which they group themselves, and thus two star-like figures are formed, one at either pole of the achromatic spindle. This constitutes the **diaster**.

3. **Anaphase**.—The daughter chromosomes now arrange themselves into a *skein* or *spirem*, and eventually form the network of chromatin which is characteristic of the resting nucleus. The nuclear membrane and nucleolus are also differentiated during this phase. The cell protoplasm begins to appear constricted around the equator of the achromatic spindle, where double rows of granules are also sometimes seen. The constriction deepens and the original cell gradually becomes divided.

4. **Telophase**.—In this stage the cell is completely divided into two new cells, each with its own nucleus and centrosome, which assume the ordinary positions occupied by such structures in the resting stage.

### EPITHELIUM.

All the surfaces of the body—the external surface of the skin, the internal surfaces of the digestive, respiratory, and genito-urinary tracts, the closed serous cavities, the inner coats of the vessels, the acini and ducts of all secreting and excreting glands, the ventricles of the brain and the central canal of the medulla spinalis—are covered by one or more layers of simple cells, called **epithelium** or **epithelial cells**. These cells are also present in the terminal parts of the organs of special sense, and in some other structures, such as the hypophysis cerebri and the thyroid gland. They serve various purposes, in some cases forming a protective layer, in others acting as agents in secretion and excretion, and again in others being concerned in the elaboration of the organs of special sense. Thus, in the skin, the main purpose served by the epithelium (here called the **epidermis**) is that of protection. As the surface is worn away by the agency of friction new cells are supplied, and thus the true skin and the vessels and nerves which it contains are defended from damage. In the gastro-intestinal mucous membrane and its glands, the epithelial cells appear to be the principal agents in preparing the digestive secretions, and in selecting and modifying materials for absorption. In other situations (as the nose, fauces, and respiratory passages) an important office of the epithelial cells appears to be to maintain an equable temperature by the moisture with which they keep the surface always slightly lubricated. In the serous cavities they also keep the opposed layers moist, and thus facilitate their movements on each other. Finally, in all internal parts, they ensure a perfectly smooth surface.

Epithelium consists of one or more layers of cells usually supported on a basement membrane and united together by an interstitial cement substance which appears to be similar in chemical composition to the matrix or ground substance of the connective tissues. It is naturally grouped into two classes according as to whether there is a single layer of cells (**simple epithelium**), or more than one (**stratified epithelium** and **transitional epithelium**).

**Simple Epithelium.**—The different varieties of simple epithelium are squamous or pavement, columnar, glandular, and ciliated.

**Simple Squamous or Pavement Epithelium** (Fig. 3) is composed of flat, nucleated scales of different shapes, usually polygonal, and varying in size. These cells fit together by their edges, like the tiles of a mosaic pavement. The nucleus is generally flattened, but may be spheroidal; the flattening depends upon the thinness of the cell. The protoplasm of the cell presents a fine reticulum or honey-combed network, which gives to the cell the appearance of granulation. This kind of epithelium forms the lining of the air-sacs of the lungs. The so-called **endothelium**, which covers the serous membranes, and which lines the heart, bloodvessels, and lymphatics, is also of the pavement type, being composed of a single layer of flattened transparent squamous cells, joined edge to edge in such a manner as to form a membrane of cells.




FIG. 3.—Simple pavement epithelium.




FIG. 4.—Columnar epithelial cells of the rabbit's intestine. (Schäfer.) *str.*, striated border; *n.*, nucleus.

**Columnar or Cylindrical Epithelium** (Fig. 4) is formed of cylindrical or rod-shaped cells set together so as to form a complete layer, resembling, when viewed in profile, a palisade. The cells have a prismatic figure, flattened from mutual pressure, and are set upright on the surface on which they are supported. Their protoplasm is always more or less reticulated, and fine longitudinal striæ may be seen in it; the nucleus of each is oval in shape and contains an intranuclear network. In the case of the intestinal villi, the outer free border of each of these cells is distinctly marked off from the rest of the protoplasm, and contains well-defined vertical striations. Columnar epithelium covers the mucous membrane and nearly the whole gastro-intestinal tract and its glands, the greater part of the male urethra, the ductus deferens, the prostate, the bulbo-urethral glands of Cowper, and the vestibular glands of Bartholin. In a modified form it also covers the ovary.

**Goblet or chalice cells** are modified columnar cells. The goblet cell appears to be formed by an alteration in shape of a columnar cell (ciliated or otherwise) consequent on the formation of granules, which consist of a substance called **mucigen**, in the interior of the cell. This distends the upper part of the cell, while the nucleus is pressed down toward its deep part, until the cell bursts and the mucus is discharged on to the surface of the mucous membrane (Fig. 5), the cell then assuming the shape of an open cup or chalice.

**Glandular Epithelium** (Fig. 6) is composed of polyhedral, columnar, or cubical cells. As in other forms of epithelial cells, the protoplasm shows a fine reticulum, which gives to the cells the appearance of granulation. Granular cells are found in the terminal recesses of secreting glands, and the protoplasm of the cells usually contains the materials which the cells secrete.

**Ciliated Epithelium** (Fig. 7) generally inclines to the columnar shape. It is distinguished by the presence of minute processes, like hairs or eyelashes (cilia) standing up from the free surface. The cilia (Fig. 8) at their points of attachment

to the free border of the cell possess small nodular enlargements (**basal knobs of Engelmann**); within the cell they converge, and according to some authorities meet at or near the attraction sphere. If the cells be examined during life or immediately on removal from the living body (for which in the human subject the removal of a nasal polypus offers a convenient opportunity) in a weak solution of salt, the cilia will be seen in lashing motion; and if the cells be separated, they will often be seen to be moved about in the field by this ciliary action.



FIG. 5.—Goblet cells of frog.  $\times 500$ .



FIG. 6.—Isolated liver cells of rabbit.  $\times 500$ .




FIG. 7.—Ciliated epithelium from trachea of kitten.  $\times 255$ .




FIG. 8.—Isolated ciliated cell (semidiagrammatic).




FIG. 9.—Stratified epithelium from the esophagus.

The situations in which ciliated epithelium is found in the human body are: the respiratory tract from the nose downward to the smallest ramifications of the bronchial tubes, except the lower part of the pharynx and the surfaces of the vocal folds; the tympanic cavity and auditory tube; the uterine tube and the body of the uterus; the vasa efferentia, coni vasculosi and the first part of the ductus deferens; the ventricles of the brain and the central canal of the medulla spinalis.

**Stratified Epithelium** (Fig. 9).—Stratified epithelium consists of several layers of cells varying greatly in shape. The cells of the deepest layer are for the most part columnar, and are placed vertically on the basement membrane; above these are several layers of polyhedral cells, which as they approach the surface become more and more compressed, until the superficial ones are found to consist of flattened scales (Fig. 10), the margins of which overlap one another so as to present an imbricated appearance. The protoplasm of the superficial cells is completely converted into a horny substance termed **keratin**. An intermediate body, **eleidin**, is often present in the deeper layers of this superficial portion; it exists in the form of coarse granules, and is especially well seen in the stratum granulosum of the epidermis (Fig. 11). The most superficial layers lose their nuclei, die, and are thrown or worn off.




FIG. 10.—Epithelial cells from the oral cavity of man.  $\times 350$ . a, large; b, middle sized; c, the same with two nuclei.




FIG. 11.—Portion of epidermis from a section of the skin of the finger. (Ranvier.)

The cells of the deeper layers of stratified squamous epithelium are called **prickle cells**; they possess short, fine fibrils, which pass from their margins to those of neighboring cells, serving to connect them together. They are not closely joined together by cement-substance, but are separated from each other by intercellular channels, across which the fibrils may be seen bridging. When a cell is isolated, it appears to be covered over with a number of short spines, in consequence of the fibrils being broken through. These cells were first described by Max Schultze and Virchow, and it was believed by them that the cells were dovetailed together. Martyn subsequently showed that this was not the case and that the prickles were attached to each other by their apices; and Delépine believes the prickles to be parts of fibrils forming internuclear bundles between the nuclei of the cells of an epithelium in a state of active growth.

Stratified epithelium is found in the skin, in the conjunctiva, in the mucous membrane of the nose, excepting the olfactory portion, and in the mucous membrane of the mouth, lower part of the pharynx, and œsophagus.

**Transitional Epithelium.**—Transitional epithelium occurs in the ureters and urinary bladder. Here the cells of the most superficial layer are large and flat-




FIG. 12.—Transitional epithelium.

ttened, with depressions on their under surfaces, to fit on to the rounded ends of the cells of the second layer, which are pear-shaped, the apices touching the basement membrane. Between the tapering points of the cells of the second layer is a third variety of cells of smaller size than those of the other two layers (Fig. 12).

### CONNECTIVE TISSUES.

The term **connective tissue** includes a number of tissues which support and connect the other tissues of the body; they are composed of cells separated from one another by an intercellular material. The connective tissues may differ considerably from each other in appearance, but they present many points of relationship, and are, moreover, developed from the same layer of the embryo, the mesoderm. They are divided into three great groups: (1) the **connective tissues proper**, (2) **cartilage**, and (3) **bone**. The circulating fluids, although functionally and probably developmentally different from the others, are regarded by some histologists as a form of connective tissue, and are dealt with therefore in this section.

**The Connective Tissues Proper.**—Several varieties of connective tissue are recognized: (1) **Areolar tissue**. (2) **White fibrous tissue**. (3) **Yellow elastic tissue**. (4) **Mucous tissue**. (5) **Retiform tissue**. They are all composed of a homogeneous matrix, in which are imbedded cells and fibres—the latter of two kinds, white, and yellow or elastic. The distinction between the different varieties depends upon the relative preponderance of one or other kind of fibre, of cells, or of matrix.

**Areolar Tissue.**—This is so called because its meshes can be easily distended with air or fluid and thus separated into areolæ or spaces, which open freely into each other. Such spaces, however, do not exist in the natural condition of the body, the whole tissue forming one unbroken membrane composed of a number of interlacing fibres. The chief use of areolar tissue is to bind parts together, while by the laxity of its fibres, and the permeability of its areolæ, it allows them to move on each other, and affords a ready exit for inflammatory and other effused fluids. It is quite the most extensively distributed of all the tissues. It is found beneath the skin in a continuous layer all over the body, connecting it to the subjacent parts. In the same way it is situated beneath the mucous and serous membranes. It is also found between muscles, vessels, and nerves, forming investing sheaths for them, and connecting them with surrounding structures. In addition to this it is present in the interior of organs, binding together the various lobes and lobules of the compound glands, the various coats of the hollow viscera, the fibres of muscles, etc., and thus forms the most important connecting medium of the various structures or organs of which the body is made up. In many parts the areolæ or inter-spaces of areolar tissue are occupied by fat cells, constituting **adipose tissue**, which will presently be described.

Areolar tissue presents to the naked eye an appearance somewhat like spun silk. When stretched out, it is seen to consist of delicate soft elastic threads

interlacing with each other in every direction, and forming a network of extreme delicacy. When examined under the microscope (Fig. 13) it is found to be composed of **white fibres** and **yellow elastic fibres** intercrossing in all directions, and united together by a homogeneous cement or ground substance, the **matrix**, showing cell-spaces wherein lie the **connective tissue corpuscles**; these contain the protoplasm out of which the whole is developed and regenerated.



FIG. 13.—Subcutaneous tissue from a young rabbit. Highly magnified. (Schäfer.)

The **white fibres** are arranged in wavy bands or bundles of minute transparent homogeneous filaments or fibrillæ. The bundles have a tendency to split up longitudinally or send off slips to join neighboring bundles, and receive others in return, but the individual fibres are unbranched, and never join other fibres. The **yellow elastic fibres** have well-defined outlines and are considerably larger in size than the white fibrillæ, but vary much, being from 1 to 6 $\mu$  in diameter. They form bold and wide curves, branch, and freely anastomose with each other; they are homogeneous in appearance, and tend to curl up, especially at their broken ends.

The cells of areolar tissue are of four principal kinds: (1) Flattened **lamellar cells**, which may be either branched or unbranched. The branched lamellar cells are composed of clear cytoplasm, and contain oval nuclei; the processes of these cells may unite so as to form an open network, as in the cornea. The unbranched cells are joined edge to edge like the cells of an epithelium; the "tendon cells," presently to be described, are examples of this variety. (2) **Clasmatocytes**, large irregular cells characterized by the presence of granules or vacuoles in their protoplasm, and containing oval nuclei. (3) **Granule cells** (*Mastzellen*), which are ovoid or spheroidal in shape. They are formed of a soft protoplasm, containing granules which are basiphil in character. (4) **Plasma cells** of Waldeyer, usually spheroidal and distinguished by containing a vacuolated protoplasm. The vacuoles are filled

with fluid, and the protoplasm between the spaces is clear, with occasionally a few scattered basiphil granules.

In addition to these four typical forms of connective-tissue corpuscles, areolar tissue may be seen to possess **wandering cells**, *i. e.*, leucocytes which have emigrated from the neighboring vessels; in some instances, as in the choroid coat of the eye, cells filled with granules of pigment (**pigment cells**) are found.

The cells lie in spaces in the ground substance between the bundles of fibres, and these spaces may be brought into view by treating the tissue with nitrate of silver and exposing it to the light. This will color the ground substance and leave the cell-spaces unstained.

**Adipose Tissue.**—In almost all parts of the body the ordinary areolar tissue contains a variable quantity of fat. The principal situations where it is not found are the subcutaneous tissue of the eyelids, of the penis and scrotum, of the labia minora; within the cavity of the cranium; and in the lungs, except near their roots. The distribution of adipose tissue is not uniform; in some parts it is in great abundance, as in the subcutaneous tissue, especially of the abdomen, around the kidneys, and in some other situations. Lastly, fat enters largely into the formation of the marrow of bones.




FIG. 14.—Adipose tissue. Highly magnified. *a*, star-like appearance, from crystallization of fatty acids.

Adipose tissue consists of small vesicles, **fat cells**, lodged in the meshes of areolar tissue. Fat cells (Fig. 14) vary in size, but are of about the average diameter of  $50\mu$ ; each consists of an exceedingly delicate protoplasmic membrane, filled with fatty matter, which is liquid during life, but becomes solidified after death. They are round or spherical where they have not been subjected to pressure; otherwise they assume a more or less polygonal outline. A nucleus is always present under the cell membrane and can be easily demonstrated by staining with hematoxylin; in the natural condition it is so compressed by the contained oily matter as to be scarcely recognizable. The fat cells are contained in clusters in the areolæ of fine connective tissue, and are held together mainly by the network of capillary blood-vessels which is distributed to them.

Chemically the oily material in the cells is composed of the fats, olein, palmitin, and stearin, which are glycerin compounds with fatty acids. Sometimes fat crystals form in the cells after death (Fig. 14, *a*). By boiling the tissue in ether or strong alcohol the fat may be extracted from the vesicles, leaving them empty and shrunken.

Fat may be first detected in the human embryo about the fourteenth week. The fat cells are formed by the transformation of connective-tissue corpuscles.



Small droplets of oil are formed in the protoplasm, and these coalesce to produce a larger drop, which increases until it distends the corpuscles, the remaining protoplasm and the nucleus being displaced toward the periphery of the cell (Fig. 15).




FIG. 15.—Development of fat. (Klein and Noble Smith) a, minute artery; b, minute vein; c, capillary bloodvessels in the course of formation; they are not yet completely hollowed out, there being still left in them protoplasmic septa; the ground substance, containing numerous nucleated cells, some of which are more distinctly branched and flattened than others, and appear therefore more spindle-shaped.




FIG. 16.—White fibres of areolar tissue.  $\times 400$ . (Sharpey.)




FIG. 17.—Tendon of mouse's tail, stained with logwood, showing chains of cells between the tendon bundles. (From Quain's "Anatomy." E. A. Schäfer.)




FIG. 18.—Transverse section of tendon of rat.  $\times 120$ .

**White Fibrous Tissue** (Fig. 16) is a true connecting structure, and serves three purposes in the animal economy. In the form of ligaments it binds bones together; in the form of tendons it connects muscles to bones or other structures; and it constitutes investing or protecting structures to various organs in the form of membranes. Examples of such membranes are to be found in the muscular fasciæ or sheaths, the periosteum, and the perichondrium; the investments of the various glands (such as the tunica albuginea testis, the capsule of the kidney, etc.); the investing sheaths of the nerves (*epineurium*), and of various organs, as the penis and the eye. In white fibrous tissue, as its name implies, the white fibres predomi-

nate; the matrix is apparent only as a cement-substance, the yellow elastic fibres are comparatively few, while the tissue cells are arranged in a special manner. It presents to the naked eye the appearance of silvery white glistening fibres, covered over with a quantity of loose flocculent tissue which binds the fibres together and carries the bloodvessels. It is not possessed of any elasticity, and only the very slightest extensibility; it is exceedingly strong, so that upon the application of any external violence, a bone with which it is connected may fracture before the fibrous tissue gives way. In ligaments and tendons the bundles of fibres run parallel with each other; in membranes they intersect one another. The cells found in white fibrous tissue are often called **tendon cells**. They are situated on the surfaces of groups of bundles and are quadrangular in shape, arranged in rows, in single file, each cell being separated from its neighbors by a narrow line of cement-substance. The nucleus is generally situated at one end of the cell, the nucleus



FIG. 19.—Elastic fibres.  $\times 200$ .  
(Sharpey.)

of the adjoining cell being in close proximity to it (Fig. 17). The tendon cells have wing-like processes which pass between the bundles of fibres, giving a stellate appearance in transverse section (Fig. 18). Upon the addition of acetic acid white fibrous tissue swells up into a glassy looking indistinguishable mass. When boiled in water it is converted almost completely into gelatin, the white fibres being composed of the albuminoid **collagen**, which is often regarded as the anhydride of gelatin.

**Yellow Elastic Tissue.**—In certain parts of the body a tissue is found which when viewed in mass is of a yellowish color, and is possessed of great elasticity, so that it is capable of considerable extension, and when the extending force is withdrawn returns at once to its original condition. This is *yellow elastic tissue*; it may be regarded as a connective tissue in which the yellow elastic fibres have developed to the practical exclusion of the other elements. It is found in the ligamenta flava, in the vocal folds, in the mucous membrane of the trachea and bronchi, in the coats of the bloodvessels, especially the larger arteries, and to a very considerable extent in the hyothyroid, cricothyroid, and stylohyoid ligaments. It is also found in the ligamentum nuchae of the lower animals (Fig. 19). In some parts where the fibres are broad and large and the network close, the tissue presents the appearance of a membrane, with gaps or perforations corresponding to the intervening spaces. This is to be found in the inner coat of the arteries, and to it the name of **fenestrated membrane** has been given by Henle. The yellow elastic fibres remain unaltered by acetic acid; chemically they are composed of the albuminoid body **elastin**.

**Mucous Tissue.**—Mucous tissue exists chiefly in the “jelly of Wharton,” which forms the bulk of the umbilical cord, but is also found in other situations in the fetus, chiefly as a stage in the development of connective tissue. It consists of a matrix, largely made up of mucin, in which are nucleated cells with branching and anastomosing processes (Fig. 20). Few fibres are seen in typical mucous tissue, although at birth the umbilical cord shows a considerable development of fibres. In the adult the vitreous humor of the eye is a persistent form of mucous tissue, in which there are no fibres, and from which the cells have disappeared, leaving only the mucinous ground substance.

**Retiform or Reticular Tissue** (Fig. 21) is found extensively in many parts of the body, constituting the framework of some organs and entering into the construction of many mucous membranes. It is a variety of connective tissue, in which

the intercellular or ground substance has, in great measure, disappeared, and is replaced by fluid. It is apparently composed almost entirely of extremely fine bundles of white fibrous tissue, forming an intricate network, and chemically it yields gelatin. The fibres are covered and concealed in places by flattened branched connective tissue cells. In many situations the interstices of the network are filled with rounded lymph-corpuscles, and the tissue is then termed **lymphoid** or **adenoid tissue**.



FIG. 20.—Mucous tissue from the umbilical cord of the human fetus of four months.




FIG. 21.—Retiform tissue, from a lymph gland.

**Basement Membranes**, formerly described as homogeneous membranes, are in most cases really a form of connective tissue. They constitute the supporting membrane, or **membrana propria**, on which is placed the epithelium of mucous membranes or secreting glands, and they are also found in other situations. By

means of staining with nitrate of silver they may be shown to consist usually of flattened cells in close apposition, and joined together by their edges, thus forming an example of an epithelioid arrangement of connective tissue cells. In some situations the cells, instead of adhering by their edges, give off branching processes which join with similar processes of other cells, and so form a network rather than a continuous membrane. Some basement membranes are composed of elastic tissue, as in the cornea, others are merely condensed matrix.

**Vessels and Nerves of Connective Tissue.**—The *bloodvessels* of connective tissue are very few—that is to say, there are few actually destined for the tissue itself, although many vessels carrying blood to other structures may permeate one of its forms, the areolar tissue. In white fibrous tissue the bloodvessels usually run parallel to the longitudinal bundles and between them, sending transverse communicating branches across; in some forms, as in the periosteum and dura mater they are fairly numerous. In yellow elastic tissue, the bloodvessels also run between the fibres, and do not penetrate them. *Lymphatic vessels* are very numerous in most forms of connective tissue, especially in the areolar tissue beneath the skin and the mucous and serous surfaces. They are also found in abundance in the sheaths of tendons, as well as in the tendons themselves. *Nerves* are to be found in the white fibrous tissue, where they end in a special manner; but it is doubtful whether any nerves end in areolar tissue; at all events, they have not yet been demonstrated, and the tissue is possessed of very little sensibility.

**Pigment.**—In various parts of the body pigment is found; most frequently in epithelial cells and in the cells of connective tissue. Pigmented **epithelial cells** are found in the external layer of the retina, on the posterior surface of the iris,

in the olfactory region of the nose, and in the membranous labyrinth of the ear. Pigment is likewise found in the cells of the deeper layers of the cuticle and in the hairs; in the skin of the colored races it is abundantly present, but in the white races it is well-marked only in the areolæ around the nipples and in irregular colored patches.

In the **connective tissue cells** pigment is frequently met with in the lower vertebrates. In man it is found in the choroid coat of the eye (Fig. 22), and in the iris of all but the light blue eyes and the albino. It is also occasionally met with in the cells of retiform tissue and in the pia mater of the upper part of the medulla spinalis. The cells are characterized by their large size and by branched processes, which are also filled with granules. In the retina the pro-



FIG. 22.—Pigment cells from the choroid coat of the eyeball.

cesses of the cells can be withdrawn or protruded under the influence of light in order to protect the delicate rods and cones. The pigment (**melanin**) consists of dark brown or black granules of very small size closely packed together within the cells, but not invading the nucleus. Occasionally the pigment is yellow, and when occurring in the cells of the cuticle constitutes "freckles." In the retina another variety of pigment occurs, known as **rhodopsin** or **visual purple**, which is bleached on exposure to light.

**Applied Anatomy.**—Abnormal pigmentation of the skin may be congenital, when it often takes the form of dark brown or black nevi (*moles*), scattered over a greater or smaller area of the body. It may also result from the prolonged consumption of various drugs, particularly of salts of silver or arsenic, being most marked wherever the skin is exposed to the action of light.

Progressive darkening or bronzing of the skin is also highly suggestive of Addison's disease, which commonly follows destruction or tuberculosis of the suprarenal glands; it is then most obvious in regions where the skin is normally pigmented or is subjected to pressure or irritation from the clothes. Pigmentation is also associated with certain disorders of the skin, of the female genitalia, and of the thyroid gland, and with the later stages of wasting diseases such as cancer and phthisis. It does not yield to any medical treatment as a rule.

**Development of Connective Tissue.**—Connective tissue is developed from cells of the mesoderm. These cells multiply and form a syncytium containing many nuclei. Later the protoplasm increases rapidly in amount, and in the vicinity of each nucleus is differentiated into two parts: (1) a portion surrounding the nucleus and forming ultimately the cytoplasm of the connective tissue cell; (2) an outlying portion in which fibrillation takes place. Both the white and the yellow elastic fibres are laid down in the same manner.

**Cartilage.**—Cartilage is a non-vascular structure which is found in various parts of the body—in adult life chiefly in the joints, in the parietes of the thorax, and in various tubes, such as the trachea and bronchi, nose, and ears, which require to be kept permanently open. In the fetus, at an early period, the greater part of the skeleton is cartilaginous; as this cartilage is afterward replaced by bone, it is called **temporary**, in contradistinction to that which remains unossified during the whole of life, and is called **permanent**.

Cartilage is divided, according to its minute structure, into **hyaline cartilage**, **white fibrocartilage**, and **yellow or elastic fibrocartilage**. Besides these varieties met with in the adult human subject, there is a variety called **cellular cartilage**, which consists entirely, or almost entirely, of cells, separated from each other by their capsules only, which in this kind of cartilage are extremely well-marked. Cellular cartilage is found in the external ears of rats, mice, and some other animals, and is present in the notochord of the human embryo, but is not found in any other human structure. The various cartilages in the body are also classified, according to their functions and positions, into **articular**, **interarticular**, **costal**, and **membraniform**.

**Hyaline Cartilage.**—Hyaline cartilage consists of a gristly mass of a firm consistence, but of considerable elasticity and pearly bluish color. Except where it coats the articular ends of bones, it is covered externally by a fibrous membrane, the **perichondrium**, from the vessels of which it imbibes its nutritive fluids, being itself destitute of bloodvessels. It contains no nerves. Its intimate structure is very simple. If a thin slice be examined under the microscope, it will be found to consist of cells of a rounded or bluntly angular form, lying in groups of two or more in a granular or almost homogeneous matrix (Fig. 23).




FIG. 23.—Human cartilage cells from the cricoid cartilage.  
× 350

The cells, when arranged in groups of two or more, have generally straight outlines where they are in contact with each other, and in the rest of their circumference are rounded. They consist of clear translucent protoplasm in which fine interlacing filaments and minute granules are sometimes present; imbedded in this are one or two round nuclei, having the usual intranuclear network. The cells are contained in cavities in the matrix, called **cartilage lacunæ**; around these the matrix is arranged in concentric lines, as if it had been formed in successive portions around the cartilage cells. This constitutes the so-called **capsule of the space**. Each lacuna is generally occupied by a single cell, but during the division of the cells it may contain two, four, or eight cells.

The matrix is transparent and apparently without structure, or else presents a

dimly granular appearance, like ground glass. Some observers have shown that the matrix of hyaline cartilage, and especially of the articular variety, after prolonged maceration, can be broken up into fine fibrils. These fibrils are probably of the same nature, chemically, as the white fibres of connective tissue. It is believed by some histologists that the matrix is permeated by a number of fine channels, which connect the lacunæ with each other, and that these canals communicate with the lymphatics of the perichondrium, and thus the structure is permeated by a current of nutrient fluid.

**Articular cartilage, costal cartilage, and temporary cartilage** are all of the hyaline variety. They present differences in the size, shape, and arrangement of their cells.

In **Articular Cartilage** (Fig. 24), which shows no tendency to ossification, the matrix is finely granular; the cells and nuclei are small, and are disposed parallel to the surface in the superficial part, while nearer to the bone they are arranged in vertical rows. Articular cartilages have a tendency to split in a vertical direction; in disease this tendency becomes very manifest. The free surface of articular cartilage, where it is exposed to friction, is not covered by perichondrium, although a layer of connective tissue continuous with that of the synovial membrane can be




FIG. 24.—Vertical section of articular cartilage.




FIG. 25.—Costal cartilage from a man, aged seventy-six years, showing the development of fibrous structure in the matrix. In several portions of the specimen two or three generations of cells are seen enclosed in a parent cell wall. Highly magnified.

traced in the adult over a small part of its circumference, and here the cartilage cells are more or less branched and pass insensibly into the branched connective tissue corpuscles of the synovial membrane. Articular cartilage forms a thin incrustation upon the joint surfaces of the bones, and its elasticity enables it to break the force of concussions, while its smoothness affords ease and freedom of movement. It varies in thickness according to the shape of the articular surface on which it lies; where this is convex the cartilage is thickest at the centre, the reverse being the case on concave articular surfaces. It appears to derive its nutriment partly from the vessels of the neighboring synovial membrane and partly from those of the bone upon which it is implanted. Toynebee has shown that the minute vessels of the cancellous tissue as they approach the articular lamella dilate and form arches, and then return into the substance of the bone.

In **Costal Cartilage** the cells and nuclei are large, and the matrix has a tendency to fibrous striation, especially in old age (Fig. 25). In the thickest parts of the costal cartilages a few large vascular channels may be detected. This appears,

at first sight, to be an exception to the statement that cartilage is a non-vascular tissue, but is not so really, for the vessels give no branches to the cartilage substance itself, and the channels may rather be looked upon as involutions of the perichondrium. The xiphoid process and the cartilages of the nose, larynx, and trachea (except the epiglottis and corniculate cartilages of the larynx, which are composed of elastic fibrocartilage) resemble the costal cartilages in microscopic characteristics. The arytenoid cartilage of the larynx shows a transition from hyaline cartilage at its base to elastic cartilage at the apex.

The hyaline cartilages, especially in adult and advanced life, are prone to calcify—that is to say, to have their matrix permeated by calcium salts without any appearance of true bone. The process of calcification occurs frequently, in such cartilages as those of the trachea and in the costal cartilages, where it may be succeeded by conversion into true bone.

**White Fibrocartilage.**—White fibrocartilage consists of a mixture of white fibrous tissue and cartilaginous tissue in various proportions; to the former of these constituents it owes its flexibility and toughness, and to the latter its elasticity. When examined under the microscope it is found to be made up of fibrous connective tissue arranged in bundles, with cartilage cells between the bundles; the cells to a certain extent resemble tendon cells, but may be distinguished from them by being surrounded by a concentrically striated area of cartilage matrix and by being less flattened (Fig. 26). The white fibrocartilages admit of arrangement into four groups—**interarticular**, **connecting**, **circumferential**, and **stratiform**.




FIG. 26.—White fibrocartilage from an intervertebral fibrocartilage.

1. The **Interarticular Fibrocartilages** (*menisci*) are flattened fibrocartilaginous plates, of a round, oval, triangular, or sickle-like form, interposed between the articular cartilages of certain joints. They are free on both surfaces, usually thinner toward the centre than at the circumference, and held in position by the attachment of their margins and extremities to the surrounding ligaments. The synovial membranes of the joints are prolonged over them. They are found in the temporomandibular, sternoclavicular, acromioclavicular, wrist, and knee joints—*i. e.*, in those joints which are most exposed to violent concussion and subject to frequent movement. Their uses are to obliterate the intervals between opposed surfaces in their various motions; to increase the depths of the articular surfaces and give ease to the gliding movements; to moderate the effects of great pressure and deaden the intensity of the shocks to which the parts may be subjected. Humphry has pointed out that these interarticular fibrocartilages serve an important purpose in increasing the varieties of movement in a joint. Thus in the knee joint there are two kinds of motion, *viz.*, angular movement and rotation, although it is a hinge joint, in which, as a rule, only one variety of motion is permitted; the former movement takes place between the condyles of the femur and the interarticular cartilages, the latter between the cartilages and the head of the tibia. So, also, in the temporomandibular joint, the movements of opening and shutting the mouth take place between the fibrocartilage and the mandible, the grinding movement between the mandibular fossa and the fibrocartilage, the latter moving with the mandible.



2. The **Connecting Fibrocartilages** are interposed between the bony surfaces of those joints which admit of only slight mobility, as between the bodies of the vertebræ. They form disks which are closely adherent to the opposed surfaces. Each disk is composed of concentric rings of fibrous tissue, with cartilaginous laminae interposed, the former tissue predominating toward the circumference, the latter toward the centre.

3. The **Circumferential Fibrocartilages** consist of rims of fibrocartilage, which surround the margins of some of the articular cavities, *e. g.*, the glenoidal labrum of the hip, and of the shoulder; they serve to deepen the articular cavities and to protect their edges.

4. The **Stratiform Fibrocartilages** are those which form a thin coating to osseous grooves through which the tendons of certain muscles glide. Small masses of fibrocartilage are also developed in the tendons of some muscles, where they glide over bones, as in the tendons of the Peronæus longus and Tibialis posterior.

**Yellow or Elastic Fibrocartilage** is found in the human body in the auricles of the external ear, the auditory tubes, the corniculate cartilages of the larynx, and the

epiglottis. It consists of cartilage cells and a matrix, the latter being pervaded by a network of yellow elastic fibres, branching and anastomosing in all directions, except immediately around each cell, where there is a variable amount of non-fibrillated hyaline, intercellular substance (Fig. 27). The fibres resemble those of yellow elastic tissue, both in appearance and in being unaffected by acetic acid; and according to Rollett their continuity with the elastic fibres of the neighboring tissue is demonstrable.

The distinguishing feature of cartilage chemically is that it yields on boiling a substance called **chondrin**, very similar to gelatin, but differing from it in several of its reactions. It is now believed that chondrin is not a simple body, but




FIG. 27.—Yellow or elastic fibrocartilage from epiglottis of cat.

a mixture of gelatin with mucinoid substances, chief among which, perhaps, is a compound termed **chondro-mucoid**.

**Bone.—Structure and Physical Properties.**—Bone is one of the hardest structures of the animal body; it possesses also a certain degree of toughness and elasticity. Its color, in a fresh state, is pinkish-white externally, and deep red within. On examining a section of any bone, it is seen to be composed of two kinds of tissue, one of which is dense in texture, like ivory, and is termed **compact tissue**; the other consists of slender fibres and lamellæ, which join to form a reticular structure; this, from its resemblance to lattice-work, is called **cancellous tissue**. The compact tissue is always placed on the exterior of the bone, the cancellous in the interior. The relative quantity of these two kinds of tissue varies in different bones, and in different parts of the same bone, according as strength or lightness is requisite. Close examination of the compact tissue shows it to be extremely porous, so that the difference in structure between it and the cancellous tissue depends merely upon the different amount of solid matter, and the size and number of spaces in each; the cavities are small in the compact tissue and the solid matter between



them abundant, while in the cancellous tissue the spaces are large and the solid matter is in smaller quantity.

Bone during life is permeated by vessels, and is enclosed, except where it is coated with articular cartilage, in a fibrous membrane, the **periosteum**, by means of which many of these vessels reach the hard tissue. If the periosteum be stripped from the surface of the living bone, small bleeding points are seen which mark the entrance of the periosteal vessels; and on section during life every part of the bone exudes blood from the minute vessels which ramify in it. The interior of each of the long bones of the limbs presents a cylindrical cavity filled with marrow and lined by a highly vascular areolar structure, called the **medullary membrane** or **internal periosteum**.

**Periosteum.**—The periosteum adheres to the surface of each of the bones in nearly every part, but not to cartilaginous extremities. When strong tendons or ligaments are attached to a bone, the periosteum is incorporated with them. It consists of two layers closely united together, the outer one formed chiefly of connective tissue, containing occasionally a few fat cells; the inner one, of elastic fibres of the finer kind, forming dense membranous networks, which can be again separated into several layers. In young bones the periosteum is thick and very vascular, and is intimately connected at either end of the bone with the epiphysial cartilage, but less closely with the body of the bone, from which it is separated by a layer of soft tissue, containing a number of **granular corpuscles** or **osteoblasts**, by which ossification proceeds on the exterior of the young bone. Later in life the periosteum is thinner and less vascular, and the osteoblasts are converted into an epithelioid layer on the deep surface of the periosteum. The periosteum serves as a **nidus** for the ramification of the vessels previous to their distribution in the bone; hence the liability of bone to exfoliation or necrosis when denuded of this membrane by injury or disease. Fine nerves and lymphatics, which generally accompany the arteries, may also be demonstrated in the periosteum.

**Marrow.**—The marrow not only fills up the cylindrical cavities in the bodies of the long bones, but also occupies the spaces of the cancellous tissue and extends into the larger bony canals (Haversian canals) which contain the bloodvessels. It differs in composition in different bones. In the bodies of the long bones the marrow is of a *yellow* color, and contains, in 100 parts, 96 of fat, 1 of areolar tissue and vessels, and 3 of fluid with extractive matter; it consists of a basis of connective tissue supporting numerous bloodvessels and cells, most of which are fat cells but some are “marrow cells,” such as occur in the red marrow to be immediately described. In the flat and short bones, in the articular ends of the long bones, in the bodies of the vertebræ, in the cranial diploë, and in the sternum and ribs the marrow is of a *red* color, and contains, in 100 parts, 75 of water, and 25 of solid matter consisting of cell-globulin, nucleoprotein, extractives, salts, and only a small proportion of fat. The red marrow consists of a small quantity of connective tissue, bloodvessels, and numerous cells (Fig. 28), some few of which are fat cells, but the great majority are roundish nucleated cells, the true “marrow cells” of Kölliker. These marrow cells proper, or **myelocytes**, resemble in appearance lymphoid corpuscles, and like them are amoeboid; they generally have a hyaline protoplasm, though some show granules either oxyphil or basiphil in reaction. A number of eosinophil cells are also present. Among the marrow cells may be seen smaller cells, which possess a slightly pinkish hue; these are the **erythroblasts** or **normoblasts**, from which the red corpuscles of the adult are derived, and which may be regarded as descendants of the nucleated colored corpuscles of the embryo. **Giant cells** (*myeloplaxes*, *osteoclasts*), large, multinucleated, protoplasmic masses, are also to be found in both sorts of adult marrow, but more particularly in red marrow. They were believed by Kölliker to be concerned in the absorption of bone matrix, and hence the name which he gave to them—**osteoclasts**. They

excavate in the bone small shallow pits or cavities, which are named *Howship's foveolæ*, and in these they are found lying.

**Vessels and Nerves of Bone.**—The bloodvessels of bone are very numerous. Those of the compact tissue are derived from a close and dense network of vessels ramifying in the periosteum. From this membrane vessels pass into the minute orifices in the compact tissue, and run through the canals which traverse its substance. The cancellous tissue is supplied in a similar way, but by less numerous and larger vessels, which, perforating the outer compact tissue, are distributed to the cavities of the spongy portion of the bone. In the long bones, numerous apertures may be seen at the ends near the articular surfaces; some of these give passage to the arteries of the larger set of vessels referred to; but the most numerous and largest apertures are for some of the veins of the cancellous tissue, which emerge apart from the arteries. The marrow in the body of a long bone is supplied by one large artery (or sometimes more), which enters the bone at the nutrient foramen




FIG. 28.—Human bone marrow. Highly magnified.

(situated in most cases near the centre of the body), and perforates obliquely the compact structure. The *medullary* or *nutrient* artery, usually accompanied by one or two veins, sends branches upward and downward, which ramify in the medullary membrane, and give twigs to the adjoining canals. The ramifications of this vessel anastomose with the arteries of the cancellous and compact tissues. In most of the flat, and in many of the short spongy bones, one or more large apertures are observed, which transmit to the central parts of the bone vessels corresponding to the nutrient arteries and veins. The **veins** emerge from the long bones in three places (Kölliker): (1) one or two large veins accompany the artery; (2) numerous large and small veins emerge at the articular extremities; (3) many small veins pass out of the compact substance. In the flat cranial bones the veins are large, very numerous, and run in tortuous canals in the diploic tissue, the sides of the canals being formed by thin lamellæ of bone, perforated here and there for the passage of branches from the adjacent cancelli. The same condition is also found in all cancellous tissue, the veins being enclosed and supported by osseous

material, and having exceedingly thin coats. When a bone is divided, the vessels remain *patulous*, and do not contract in the canals in which they are contained. **Lymphatic vessels**, in addition to those found in the periosteum, have been traced by Cruikshank into the substance of bone, and Klein describes them as running in the Haversian canals. **Nerves** are distributed freely to the periosteum, and accompany the nutrient arteries into the interior of the bone. They are said by Kölliker to be most numerous in the articular extremities of the long bones, in the vertebræ, and in the larger flat bones.

**Minute Anatomy.**—A transverse section of dense bone may be cut with a saw and ground down until it is sufficiently thin.

If this be examined with a rather low power the bone will be seen to be mapped out into a number of circular districts each consisting of a central hole surrounded by a number of concentric rings. These districts are termed **Haversian systems**; the central hole is an **Haversian canal**, and the rings are layers of bony tissue arranged concentrically around the central canal, and termed **lamellæ**. Moreover, on closer examination it will be found that between these lamellæ, and therefore also arranged concentrically around the central canal, are a number of




FIG. 29.—Transverse section of compact tissue of bone. Magnified. (Sharpey.)

little dark spots, the **lacunæ**, and that these lacunæ are connected with each other and with the central Haversian canal by a number of fine dark lines, which radiate like the spokes of a wheel and are called **canaliculi**. Filling in the irregular intervals which are left between these circular systems are other lamellæ, with their lacunæ and canaliculi running in various directions, but more or less curved (Fig. 29); they are termed **interstitial lamellæ**. Again, other lamellæ, found on the surface of the bone, are arranged parallel to its circumference; they are termed **circumferential**, or by some authors **primary** or **fundamental lamellæ**, to distinguish them from those laid down around the axes of the Haversian canals, which are then termed **secondary** or **special lamellæ**.

The **Haversian canals**, seen in a transverse section of bone as round holes at or about the centre of each Haversian system, may be demonstrated to be true canals if a longitudinal section be made (Fig. 30). It will then be seen that the canals run parallel with the longitudinal axis of the bone for a short distance and then branch and communicate. They vary considerably in size, some being as much as 0.12 mm. in diameter; the average size is, however, about 0.05 mm. Near the medullary cavity the canals are larger than those near the surface of the bone.

Each canal contains one or two bloodvessels, with a small quantity of delicate connective tissue and some nerve filaments. In the larger ones there are also lymphatic vessels, and cells with branching processes which communicate, through the canaliculi, with the branched processes of certain bone cells in the substance of the bone. Those canals near the surface of the bone open upon it by minute orifices, and those near the medullary cavity open in the same way into this space, so that the whole of the bone is permeated by a system of bloodvessels running through the bony canals in the centres of the Haversian systems.

The **lamellæ** are thin plates of bony tissue encircling the central canal, and may be compared, for the sake of illustration, to a number of sheets of paper pasted one over another around a central hollow cylinder. After macerating a piece of bone in dilute mineral acid, these lamellæ may be stripped off in a




FIG. 30.—Section parallel to the surface from the body of the femur.  $\times 100$ . a, Haversian canals; b, lacunæ seen from the side; c, others seen from the surface in lamellæ, which are cut horizontally.




FIG. 31.—Perforating fibres, human parietal bone, decalcified. (H. Müller.) a, perforating fibres *in situ*; b, fibres drawn out of their sockets; c, sockets.

longitudinal direction as thin films. If one of these be examined with a high power of the microscope, it will be found to be composed of a finely reticular structure, made up of very slender transparent fibres, decussating obliquely; and coalescing at the points of intersection; these fibres are composed of fine fibrils identical with those of white connective tissue. The intercellular matrix between the fibres is impregnated by calcareous deposit which the acid dissolves. In many places the various lamellæ may be seen to be held together by tapering fibres, which run obliquely through them, pinning or bolting them together; they were first described by Sharpey, and were named by him **perforating fibres** (Fig. 31).

The **Lacunæ** are situated between the lamellæ, and consist of a number of oblong spaces. In an ordinary microscopic section, viewed by transmitted light, they appear as fusiform opaque spots. Each lacuna is occupied during life by a branched cell, termed a **bone-cell** or **bone-corpuscle**, the processes from which extend into the canaliculi (Fig. 32).

The **Canaliculi** are exceedingly minute channels, crossing the lamellæ and connecting the lacunæ with neighboring lacunæ and also with the Haversian canal. From the Haversian canal a number of canaliculi are given off, which radiate from it, and open into the first set of lacunæ between the first and second lamellæ. From these lacunæ a second set of canaliculi is given off; these run outward to the

next series of lacunæ, and so on until the periphery of the Haversian system is reached; here the canaliculi given off from the last series of lacunæ do not communicate with the lacunæ of neighboring Haversian systems, but after passing outward for a short distance form loops and return to their own lacunæ. Thus every part of an Haversian system is supplied with nutrient fluids derived from the vessels in the Haversian canal and distributed through the canaliculi and lacunæ.

The **bone cells** are contained in the lacunæ, which, however, they do not completely fill. They are flattened nucleated branched cells, homologous with those of connective tissue; the branches, especially in young bones, pass into the canaliculi from the lacunæ.

In thin plates of bone (as in the walls of the spaces of cancellous tissue) the Haversian canals are absent, and the canaliculi open into the spaces of the cancellous tissue (medullary spaces), which thus have the same function as the Haversian canals.

**Chemical Composition.**—Bone consists of an **animal** and an **earthy** part intimately combined together.




FIG. 32.—Nucleated bone cells and their processes, contained in the bone lacunæ and their canaliculi respectively. From a section through the vertebra of an adult mouse. (Klein and Noble Smith.)




FIG. 33.—Transverse section of body of human fibula, decalcified.  $\times 250$ .

The **animal** part may be obtained by immersing a bone for a considerable time in dilute mineral acid, after which process the bone comes out exactly the same shape as before, but perfectly flexible, so that a long bone (one of the ribs, for example) can easily be tied in a knot. If now a transverse section is made (Fig. 33) the same general arrangement of the Haversian canals, lamellæ, lacunæ, and canaliculi is seen.

The **earthy** part may be separately obtained by calcination, by which the animal matter is completely burnt out. The bone will still retain its original form, but it will be white and brittle, will have lost about one-third of its original weight, and will crumble down with the slightest force. The earthy matter is composed chiefly of calcium phosphate, forming about 66.7 per cent. of the weight



of the bone; it confers on bone its hardness and rigidity, while the animal matter (*ossein*) determines its tenacity.

**Ossification.**—Some bones are preceded by membrane, such as those forming the roof and sides of the skull; others, such as the bones of the limbs, are preceded by rods of cartilage. Hence two kinds of ossification are described: the **intra-membranous** and the **intracartilaginous**.

**INTRAMEMBRANOUS OSSIFICATION.**—In the case of bones which are developed in membrane, no cartilaginous mould precedes the appearance of the bony tissue. The membrane which occupies the place of the future bone is of the nature of connective tissue, and ultimately forms the periosteum; it is composed of fibres and granular cells in a matrix. The peripheral portion is more fibrous, while, in the interior the cells or *osteoblasts* predominate; the whole tissue is richly supplied with bloodvessels. At the outset of the process of bone formation a little network of spicules is noticed radiating from the point or centre of ossification. These rays consist at their growing points of a network of fine clear fibres and granular corpuscles with an intervening ground substance (Fig. 34). The fibres are termed




FIG. 34.—Part of the growing edge of the developing parietal bone of a fetal cat. (After J. Lawrence.)

**osteogenetic fibres**, and are made up of fine fibrils differing little from those of white fibrous tissue. The membrane soon assumes a dark and granular appearance from the deposition of calcareous granules in the fibres and in the intervening matrix, and in the calcified material some of the granular corpuscles or osteoblasts are enclosed. By the fusion of the calcareous granules the tissue again assumes a more transparent appearance, but the fibres are no longer so distinctly seen. The involved osteoblasts form the corpuscles of the future bone, the spaces in which they are enclosed constituting the lacunæ. As the osteogenetic fibres grow out to the periphery they continue to calcify, and give rise to fresh bone spicules. Thus a network of bone is formed, the meshes of which contain the bloodvessels and a delicate connective tissue crowded with osteoblasts. The bony trabeculae thicken by the addition of fresh layers of bone formed by the osteoblasts on their surface, and the meshes are correspondingly encroached upon. Subsequently successive layers of bony tissue are deposited under the periosteum and around the larger vascular channels which become the Haversian canals, so that the bone increases much in thickness.

**INTERCARTILAGINOUS OSSIFICATION.**—Just before ossification begins the mass is entirely cartilaginous, and in a long bone, which may be taken as an example, the process commences in the centre and proceeds toward the extremities, which for some time remain cartilaginous. Subsequently a similar process commences in one or more places in those extremities and gradually extends through them. The extremities do not, however, become joined to the body of the bone by bony tissue until growth has ceased; between the body and either extremity a layer of cartilaginous tissue termed the **epiphysial cartilage** persists for a definite period.

The first step in the ossification of the cartilage is that the cartilage cells, at the point where ossification is commencing and which is termed a **centre of ossification**, enlarge and arrange themselves in rows (Fig. 35). The matrix in which they are imbedded increases in quantity, so that the cells become further separated from each other. A deposit of calcareous material now takes place in this matrix, between the rows of cells, so that they become separated from each other by longitudinal columns of calcified matrix, presenting a granular and opaque appearance. Here and there the matrix between two cells of the same row also becomes calcified, and transverse bars of calcified substance stretch across from one calcareous column to another. Thus there are longitudinal groups of the cartilage cells enclosed in oblong cavities, the walls of which are formed of calcified matrix which cuts off all nutrition from the cells; the cells, in consequence, atrophy, leaving spaces called the **primary areolæ**.

At the same time that this process is going on in the centre of the solid bar of cartilage, certain changes are taking place on its surface. This is covered by a very vascular membrane, the **perichondrium**, entirely similar to the embryonic connective tissue already described as constituting the basis of membrane bone; on the inner surface of this—that is to say, on the surface in contact with the cartilage—are gathered the formative cells, the **osteoblasts**. By the agency of these cells a thin layer of bony tissue is formed between the perichondrium and the cartilage, by the *intramembranous* mode of ossification just described. There are then, in this first stage of ossification, two processes going on simultaneously: in the centre of the cartilage the formation of a number of oblong spaces, formed of calcified matrix and containing the withered cartilage cells, and on the surface of the cartilage the formation of a layer of true membrane bone. The second stage consists in the prolongation into the cartilage of processes of the deeper or osteogenetic layer of the perichondrium, which has now become periosteum (Fig. 35, *ir*). The processes consist of bloodvessels and




FIG. 35.—Section of fetal bone of cat. *ir*. Irruption of the subperiosteal tissue. *p*. Fibrous layer of the periosteum. *o*. Layer of osteoblasts. *im*. Subperiosteal bony deposit. (From Quain's "Anatomy," E. A. Schäfer.)

cells—osteoblasts, or bone-formers, and osteoclasts, or bone-destroyers. The latter are similar to the giant cells (myeloplaxes) found in marrow, and they excavate passages through the new-formed bony layer by absorption, and pass through it into the calcified matrix (Fig. 36). Wherever these processes come in contact with the calcified walls of the primary areolæ they absorb them, and thus cause a fusion of the original cavities and the formation of larger spaces, which are termed the **secondary areolæ** or **medullary spaces**. These secondary spaces become filled with embryonic marrow, consisting of osteoblasts and vessels, derived, in the manner described above, from the osteogenetic layer of the periosteum (Fig. 36).

Thus far there has been traced the formation of enlarged spaces (secondary areolæ), the perforated walls of which are still formed by calcified cartilage matrix, containing an embryonic marrow derived from the processes sent in from the osteogenetic layer of the periosteum, and consisting of bloodvessels and osteoblasts. The walls of these secondary areolæ are at this time of only inconsiderable thickness, but they become thickened by the deposition of layers of true bone on their surface. This process takes place in the following manner: Some of the osteoblasts of the embryonic marrow, after undergoing rapid division, arrange themselves as an epithelioid layer on the surface of the wall of the space (Fig. 37). This layer of osteoblasts forms a bony stratum, and thus the wall of the space becomes gradually covered with a layer of




FIG. 36.—Part of a longitudinal section of the developing femur of a rabbit. *a*. Flattened cartilage cells. *b*. Enlarged cartilage cells. *c*, *d*. Newly formed bone. *e*. Osteoblasts. *f*. Giant cells or osteoclasts. *g*, *h*. Shrunken cartilage cells. (From "Atlas of Histology," Klein and Noble Smith.)




FIG. 37.—Osteoblasts and osteoclasts on trabecula of lower jaw of calf embryo. (Kölliker.)

true osseous substance in which some of the bone-forming cells are included as bone corpuscles. The next stage in the process consists in the removal of these primary bone spicules by the osteoclasts. One of these giant cells may be found lying in a Howship's foveola at the free end of each spicule. The removal of the primary spicules goes on *pari passu* with the formation of permanent bone by the periosteum, and in this way the medullary cavity of the body of the bone is formed.

This series of changes has been gradually proceeding toward the end of the body of the bone, so that in the ossifying bone all the changes described above may be seen in different parts, from the true bone at the centre of the body to the hyaline cartilage at the extremities.



While the ossification of the cartilaginous body is extending toward the articular ends, the cartilage immediately in advance of the osseous tissue continues to grow until the length of the adult bone is reached.

During the period of growth the articular end, or epiphysis, remains for some time entirely cartilaginous, then a bony centre appears, and initiates in it the process of intracartilaginous ossification; but this process never extends to any great distance. The epiphysis remains separated from the body by a narrow cartilaginous layer for a definite time. This layer ultimately ossifies, the distinction between body and epiphysis is obliterated, and the bone assumes its completed form and shape. The same remarks also apply to such processes of bone as are separately ossified, *e. g.*, the trochanters of the femur. The bones therefore continue to grow until the body has acquired its full stature. They increase in length by ossification continuing to extend behind the epiphysal cartilage, which goes on growing in advance of the ossifying process. They increase in circumference by deposition of new bone, from the deeper layer of the periosteum, on their external surface, and at the same time an absorption takes place from within, by which the medullary cavities are increased.

The permanent bone formed by the periosteum when first laid down is cancellous in structure. Later the osteoblasts contained in its spaces become arranged in the concentric layers characteristic of the Haversian systems, and are included as bone corpuscles.

The number of ossific centres varies in different bones. In most of the short bones ossification commences at a single point near the centre, and proceeds toward the surface. In the long bones there is a central point of ossification for the body or diaphysis: and one or more for each extremity, the epiphysis. That for the body is the first to appear. The times of union of the epiphyses with the body vary inversely with the dates at which their ossifications began (with the exception of the fibula) and regulate the direction of the nutrient arteries of the bones. Thus, the nutrient arteries of the bones of the arm and forearm are directed toward the elbow, since the epiphyses at this joint become united to the bodies before those at the opposite extremities. In the lower limb, on the other hand, the nutrient arteries are directed away from the knee: that is, upward in the femur, downward in the tibia and fibula; and in them it is observed that the upper epiphysis of the femur, and the lower epiphyses of the tibia and fibula, unite first with the bodies. Where there is only one epiphysis, the nutrient artery is directed toward the other end of the bone; as toward the acromial end of the clavicle, toward the distal ends of the metacarpal bone of the thumb and the metatarsal bone of the great toe, and toward the proximal ends of the other metacarpal and metatarsal bones.

Parsons<sup>1</sup> groups epiphyses under three headings, viz.: (1) **pressure epiphyses**, appearing at the articular ends of the bones and transmitting "the weight of the body from bone to bone;" (2) **traction epiphyses**, associated with the insertion of muscles and "originally sesamoid structures though not necessarily sesamoid bones;" and (3) **atavistic epiphyses**, representing parts of the skeleton, which at one time formed separate bones, but which have lost their function, "and only appear as separate ossifications in early life."

**Applied Anatomy.**—It has been stated above that the bones increase firstly *in length* by ossification continuing to extend in the epiphysal cartilage, which goes on growing in advance of the ossifying process; and secondly, *in circumference* by deposition of new bone from the deeper layer of the periosteum, on the external surface.

A careful study of osseous development is of the very greatest utility in the proper understanding of bone disease; and, moreover, an accurate knowledge of the blood supply of a long bone

<sup>1</sup> Jour. of Anat. and Phys., vols. xxxviii, xxxix, and xlii.

has also many important bearings. The outer portion of the compact tissue being supplied by periosteal vessels, which reach the bone through muscular attachments, it follows that where the muscular structures are well developed, and therefore amply supplied with blood, the periosteum will also be well-nourished and the bones proportionately well-developed in girth; this is well seen in strong muscular men with well-marked ridges on the bones. Conversely, if the muscular development be poor, the bones are correspondingly thin and light, and if from any cause a limb has been paralyzed from early childhood, the whole of the bones of that extremity are remarkable for their extreme thinness—that is to say, the periosteal blood supply has been insufficient to nourish that membrane, and consequently very little fresh osseous tissue has been added to the bones from the outside.

The best example of this condition is seen in connection with the disease known as *infantile paralysis*, where a limb becomes paralyzed at a very early period of childhood, where the muscles become flaccid and atonic, and where the blood supply is in consequence very greatly diminished. In such cases, although the limb does continue to grow in length from the epiphysal lines, its length is considerably less than on the normal side, owing to the imperfect nutrition; but the most striking feature about all the long bones of the limb is their remarkable tenuity, little or no addition having been made to their circumferences.

In cases where the periosteum has been separated from the compact tissue by extensive injury or inflammatory exudation, necrosis or death of the underlying portion of bone takes place owing to its blood supply having been cut off, and the dead portion or *sequestrum* has to be separated and subsequently cast off.

Cases, however, occur where the inflammatory process affects the whole or a great portion of the diaphysis of a long bone, and here extensive death of the affected portion takes place, and the condition goes by the name of *acute infective periostitis*. Where this occurs the body of the bone dies very rapidly, especially if the single nutrient artery be thrombosed at the same time. The pus which has formed beneath the periosteum is set free by timely incision, or bursts on the surface; the periosteum then falls back on the necrosed diaphysis and rapidly forms a layer of new periosteal bone, surrounding the sequestrum. This layer is called the *involucrum*, and the openings in it through which the pus escapes the *cloacæ*. When the inflammatory process affects mainly the medullary canal, the condition is spoken of as *osteomyelitis*, and the two conditions very frequently coexist, and then go by the name of *acute infective necrosis of bone* or *acute diaphysitis*. When the medullary cavity is filled with pus, septic thrombosis of the veins in the Haversian canals takes place, and there is a very great danger of septic emboli being displaced and carried into the general circulation, thus setting up a fatal *pyemia*. In fact, pyemia is more frequently due to septic bone conditions than to any other cause.

In the pre-antiseptic days, pyemia frequently resulted from amputations, where the medullary canal of a long bone was opened by the saw cut. Osteomyelitis ensued, and if the patient survived, a tubular sequestrum of the divided shaft subsequently separated.

A proper knowledge of the epiphyses is of the utmost possible importance, and greatly simplifies many of the problems in the pathology of bone disease.

Speaking generally, the long bones have at either end an epiphysis from the cartilage of which growth occurs, and hence the body of the bone increases in length from both ends. In every case, however, one epiphysis is the more active, and also continues in its activity for a longer time. This *actively growing epiphysis* is always the one from which the nutrient foramen in the diaphysis points, and it unites to the diaphysis at a later date. It follows, therefore, that the increase in length of a bone is largely dependent on this epiphysis, and hence anything which interferes with the growth from this epiphysal line at any time prior to the union of the epiphysis with the diaphysis must result in a cessation of growth in length of that bone. Thus when dealing with disease in the neighborhood of this actively growing epiphysis very great care should be taken not to excise or destroy its line of union with the diaphysis. These epiphyses are particularly prone to become the seat of tuberculous disease, which especially tends to attack the soft, highly vascular cancellous tissue.

Again, the actively growing epiphysal plate is the portion of a long bone which is in the vast majority of cases affected by tumor growth in bone, whether it be innocent or malignant, the former (*e. g.*, osteoma) usually appearing about puberty, and the latter (*e. g.*, sarcoma) usually toward the end of the active period of epiphysal growth.

Epiphysal growth, moreover, has to be considered by the surgeon when he is about to amputate in a child. If the amputation is being performed through a bone, the actively growing epiphysis of which is at the upper end, and which will continue to grow for several years (*e. g.*, humerus and tibia), it will be necessary to make allowance for this and to cut the flaps long; as otherwise, owing to continued growth, the sawn end of the bone will ultimately project through the stump, and a condition known as "conical stump" will result. This requires removal of a further portion of the bone.

An inflammatory condition termed *acute epiphysitis* also occurs, although it is not so frequent as the acute infective conditions of the diaphysis, owing to the freer blood supply of the epiphysis;

in late years it has been shown that acute epiphysitis in children is very frequently the result of a pneumococcal infection, and it may pass on to complete separation of the epiphysis. In this connection it is worthy of note that some of the epiphysial lines lie entirely within the capsules of their corresponding joints, in other cases entirely without the capsules; and it must follow that in the former case epiphysial disease, acute or chronic, becomes, *ipso facto*, practically synonymous with disease of that joint. The best examples of intra-articular epiphyses are those for the head of the femur and head of the humerus, and the vast majority of all cases of tuberculous disease of the hip start as a tuberculous epiphysitis about the intra-articular epiphysial plate of the femur; again cases of acute septic arthritis of the shoulder or hip joints generally have their origins in these intra-articular epiphysial lines, and often result in separation of the affected epiphysis. Those of the other class, or extra-articular epiphyses, when diseased, do not tend to involve the neighboring joint so readily; and it should be the surgeon's duty to keep the disease from involving the joint. For example, the trochanteric epiphysis of the femur is extra-articular as regards the hip-joint, and the epiphysial line of the head of the tibia is well below the level of the knee-joint, and should a chronic tuberculous abscess form in the latter situation, it should be attacked from the outside before it has time to spread up and involve the cartilage of the head of the tibia. It is therefore of great surgical interest to note in every case the relations which the various epiphysial lines bear to their respective joint capsules.

A knowledge of the exact periods when the epiphyses become joined to the shaft is often of great importance in medicolegal inquiries. It also aids the surgeon in the diagnosis of many of the injuries to which the joints are liable; for it not infrequently happens that, on the application of severe force to a joint, the epiphysis becomes separated from the diaphysis, and such injuries may be mistaken for fracture or dislocation.

### THE CIRCULATING FLUIDS.

The circulating fluids of the body are the **blood** and the **lymph**.

**Blood.**—The blood is an opaque, rather viscid fluid, of a bright red or scarlet color when it flows from the arteries, of a dark red or purple color when it flows from the veins. It is salt to the taste, and has a peculiar faint odor and an alkaline reaction. Its specific gravity is about 1.06, and its temperature is generally about 37° C., though varying slightly in different parts of the body.

**General Composition of the Blood.**—Blood consists of a faintly yellow fluid, the **plasma** or **liquor sanguinis**, in which are suspended numerous minute particles, the **blood corpuscles**, the majority of which are colored and give to the blood its red tint. If a drop of blood be placed in a thin layer on a glass slide and examined under the microscope, a number of these corpuscles will be seen floating in the plasma.

The **Blood Corpuscles** are of three kinds: (1) **colored corpuscles** or **erythrocytes**; (2) **colorless corpuscles** or **leucocytes**; (3) **blood platelets**.

1. **Colored or red corpuscles** (*erythrocytes*), when examined under the microscope, are seen to be circular disks, biconcave in profile. The disk has no nucleus, but, in consequence of its biconcave shape, presents, according to the alterations of focus under an ordinary high power, a central part, sometimes bright, sometimes




FIG. 38.—Human red blood corpuscles. Highly magnified. *a*. Seen from the surface. *b*. Seen in profile and forming rouleaux. *c*. Rendered spherical by water. *d*. Rendered crenate by salt solution.

dark, which has the appearance of a nucleus (Fig. 38, *a*). It is to the aggregation of the red corpuscles that the blood owes its red hue, although when examined by transmitted light their color appears to be only a faint reddish yellow. The corpuscles vary slightly in size even in the same drop of blood, but the average

diameter of each is about  $7.5\mu$ ,<sup>1</sup> and the thickness about  $2\mu$ . Besides these there are found certain smaller corpuscles of about one-half of the size just indicated; these are termed **microcytes**, and are very scarce in normal blood; in diseased conditions (*e. g.*, anemia), however, they are more numerous. The number of red corpuscles in the blood is enormous; between 4,000,000 and 5,000,000 are contained in a cubic millimetre. Power states that the red corpuscles of an adult would present an aggregate surface of about 3000 square yards.

If the web of a living frog's foot be spread out and examined under the microscope the blood is seen to flow in a continuous stream through the vessels, and the corpuscles show no tendency to adhere to each other or to the wall of the vessel. Doubtless the same is the case in the human body; but when human blood is drawn and examined on a slide without reagents the corpuscles tend to collect into heaps like rouleaux of coins (Fig. 38, *b*). It has been suggested that this phenomenon may be explained by alteration in surface tension. During life the red corpuscles may be seen to change their shape under pressure so as to adapt themselves, to some extent, to the size of the vessel. They are, however, highly elastic, and speedily recover their shape when the pressure is removed. They are readily influenced by the medium in which they are placed. In water they swell up, lose their shape, and become globular (*endosmosis*) (Fig. 38, *c*). Subsequently the hemoglobin is dissolved out, and the envelope can barely be distinguished as a faint circular outline. Solutions of salt or sugar, denser than the plasma, give them a stellate or crenated appearance (*exosmosis*) (Fig. 38, *d*), but the usual shape may be restored by diluting the solution to the same tonicity as the plasma. The crenated outline may be produced as the first effect of the passage of an electric shock: subsequently, if sufficiently strong, the shock ruptures the envelope. A solution of salt, isotonic with the plasma, merely separates the blood corpuscles mechanically, without changing their shape. Two views are held with regard to the structure of the erythrocytes. The older view, that of Rollett, supposes that the corpuscle consists of a sponge work or stroma permeated by a solution of hemoglobin. Schäfer, on the other hand, believes that the hemoglobin solution is contained within an envelope or membrane, and the facts stated above with regard to the osmotic behavior of the erythrocyte support this belief. The envelope consists mainly of lecithin, cholesterol, and nucleoprotein.

The **colorless corpuscles** or **leucocytes** are of various sizes, some no larger, others smaller, than the red corpuscles. In human blood, however, the majority are rather larger than the red corpuscles, and measure about  $10\mu$  in diameter. On the average from 7000 to 12,000 leucocytes are found in each cubic millimetre of blood.

They consist of minute masses of nucleated protoplasm, and exhibit several varieties, which are differentiated from each other chiefly by the occurrence or non-occurrence of granules in their protoplasm, and by the staining reactions of these granules when present (Fig. 39). (1) The most numerous (60 per cent.) and important are irregular in shape, possessed of the power of amoeboid movement, and are characterized by nuclei which often consist of two or three parts (multipartite) connected together by fine threads of chromatin. The protoplasm is clear, and contains a number of very fine granules, which stain with acid dyes, such as eosin, or with neutral dyes, and are therefore called **oxyphil** or **neutrophil** (Fig. 39, *P*). These cells are termed the **polymorphonuclear leucocytes**. (2) A second variety comprises from 1 to 4 per cent. of the leucocytes; they are larger than the previous kind, and are made up of coarsely granular protoplasm, the granules being highly refractile and grouped around single nuclei of horse-shoe shape (Fig. 39, *E*). The granules stain deeply with eosin, and the cells are there-

<sup>1</sup> A micromillimetre ( $\mu$ ) is 1/1000 of a millimetre or 1/25000 of an inch.

40 mm. Their breadth varies in man from 0.01 to 0.1 mm. As a rule, the fibres do not divide or anastomose; but occasionally, especially in the tongue and facial muscles, they may be seen to divide into several branches. In the substance of the muscle, the fibres end by tapering extremities which are joined to the ends of other fibres by the sarcolemma. At the tendinous end of the muscle the sarcolemma appears to blend with a small bundle of fibres, into which the tendon becomes subdivided, while the muscular substance ends abruptly and can be readily made to retract from the point of junction. The areolar tissue between the fibres appear to be prolonged more or less into the tendon, so as to form a kind of sheath around the tendon bundles for a longer or shorter distance. When muscular fibres are attached to skin or mucous membranes, their fibres become continuous with those of the areolar tissue.



FIG. 42.—Transverse section of human striped muscle fibres.  
× 255.



FIG. 43.—Striped muscle fibres from tongue of cat.  
× 250.

The **sarcolemma**, or tubular sheath of the fibre, is a transparent, elastic, and apparently homogeneous membrane of considerable toughness, so that it sometimes remains entire when the included substance is ruptured. On the internal surface of the sarcolemma in mammalia, and also in the substance of the fibre in frogs, elongated nuclei are seen, and in connection with these is a little granular protoplasm.

Upon examination of a voluntary muscular fibre by transmitted light, it is found to be marked by alternate light and dark bands or striæ, which pass transversely across the fibre (Fig. 43). When examined by polarized light the dark bands are found to be doubly refracting (anisotropic), while the clear stripes are singly refracting (isotropic). The dark and light bands are of nearly equal breadth, and alternate with great regularity; they vary in breadth from about 1 to  $2\mu$ . If the surface be carefully focussed, rows of granules will be detected at the points of junction of the dark and light bands, and very fine longitudinal lines may be seen running through the dark bands and joining these granules together. By treating the specimen with certain reagents (*e. g.*, chloride of gold) fine lines may be seen running transversely between the granules and uniting them together. This appearance is believed to be due to a reticulum or network of interstitial substance lying between the contractile portions of the muscle. The longitudinal striation gives the fibre the appearance of being made up of a bundle of fibrils which have been termed **sarcostyles** or **muscle columns**, and if the fibre be hardened in alcohol, it can be broken up longitudinally and the sarcostyles separated from each other (Fig. 44.) The reticulum, with its longitudinal and transverse meshes, is called **sarcoplasm**.

In a transverse section, the muscular fibre is seen to be divided into a number of areas, called the **areas of Cohnheim**, more or less polyhedral in shape and consisting of the transversely divided sarcostyles, surrounded by transparent sarcoplasm (Fig. 42).

Upon closer examination, and by somewhat altering the focus, the appearances become more complicated, and are susceptible of various interpretations. The




FIG. 44.—A. Portion of a medium-sized human muscular fibre. Magnified nearly 800 diameters. B. Separated bundles of fibrils, equally magnified. a, a, Larger, and b, b, smaller collections. c, c, Still smaller. d, d, The smallest which could be detached.

transverse striation, which in Fig. 43 appears as a mere alternation of dark and light bands, is resolved into the appearance seen in Fig. 44, which shows a series of broad dark bands, separated by light bands, each of which is divided into two by a dark dotted line. This line is termed **Dobie's line** or **Krause's membrane** (Fig. 45, *k*), because it was believed by Krause to be an actual membrane, continuous with the sarcolemma, and dividing the light band into two compartments. In addition to the membrane of Krause, fine clear lines may be made out, with a sufficiently high power, crossing the centre of the dark band; these are known as the **lines of Hensen** (Fig. 45, *H*).

Schäfer has worked out the minute anatomy of muscular fibre, particularly in the wing muscles of insects, which are peculiarly adapted for this

purpose on account of the large amount of interstitial sarcoplasm which separates the sarcostyles. In the following description that given by Schäfer will be closely followed.




FIG. 45.—Diagram of a sarcomere. (After Schäfer.) A. In moderately extended condition. B. In a contracted condition. *k*, *k*. Membranes of Krause. *H*. Line or plane of Hensen. *S.E.* Poriferous sarcous element.

A sarcostyle may be said to be made up of successive portions, each of which is termed a **sarcomere**. The sarcomere is situated between two membranes of Krause and consists of (1) a central dark part, which forms a portion of the dark band of the whole fibre, and is named a **sarcous element**. This sarcous element really consists of two parts, superimposed one on the top of the other, and when the fibre is stretched these two parts become separated from each other at the line of Hensen

(Fig. 45, *A*). (2) On either side of this central dark portion is a clear layer, most visible when the fibre is extended; this is situated between the dark centre and the membrane of Krause, and when the sarcomeres are joined together to form the sarcostyle, constitutes the light band of the striated muscular fibre.

When the sarcostyle is extended, the clear intervals are well-marked and plainly to be seen; when, on the other hand, the sarcostyle is contracted, that is to say, when the muscle is in a state of contraction, these clear portions are very small or they may have disappeared altogether (Fig. 45, *B*). When the sarcostyle is stretched to its full extent, not only is the clear portion well-marked, but the dark portion—the sarcous element—is separated into its two constituents along the line of Hensen. The sarcous element does not lie free in the sarcomere, for when the sarcostyle is stretched, so as to render the clear portion visible, very fine lines, which are probably septa, may be seen running through it from the sarcous element to the membrane of Krause.

Schäfer explains these phenomena in the following way: He considers that each sarcous element is made up of a number of longitudinal channels, which open into the clear part toward the membrane of Krause but are closed at the line of Hensen. When the muscular fibre is contracted the *clear* part of the muscular substance is driven into these channels or tubes, and is therefore hidden from sight, but at the same time it swells up the sarcous element and widens and shortens the sarcomere. When, on the other hand, the fibre is extended, this clear substance is driven out of the tubes and collects between the sarcous element and the membrane of Krause, and gives the appearance of the light part between these two structures; by this means it elongates and narrows the sarcomere.

If this view be true, it is a matter of great interest, and, as Schäfer has shown, harmonizes the contraction of muscle with the amœboid action of protoplasm. In an amœboid cell, there is a framework of spongioplasm, which stains with hematoxylin and similar reagents, enclosing in its meshes a clear substance, hyaloplasm, which will not stain with these reagents. Under stimulation the hyaloplasm passes into the pores of the spongioplasm; without stimulation it tends to pass out as in the formation of pseudopodia. In muscle there is the same thing, viz., a framework of spongioplasm staining with hematoxylin—the substance of the sarcous element—and this encloses a clear hyaloplasm, the clear substance of the sarcomere, which resists staining with this reagent. During contraction of the muscle—*i. e.*, stimulation—this clear substance passes into the pores of the spongioplasm; while during extension of the muscle—*i. e.*, when there is no stimulation—it tends to pass out of the spongioplasm.

In this way the contraction is brought about: under stimulation the protoplasmic material (the clear substance of the sarcomere) recedes into the sarcous element, causing the sarcomere to widen out and shorten. The contraction of the muscle is merely the sum total of this widening out and shortening of these bodies.

**Vessels and Nerves of Striped Muscle.**—The capillaries of striped muscle are very abundant, and form a sort of rectangular network, the branches of which run longitudinally in the endomysium between the muscular fibres, and are joined at short intervals by transverse anastomosing branches. In the red muscles of the rabbit dilatations occur on the transverse branches of the capillary network. The larger vascular channels, arteries and veins, are found only in the perimysium, between the muscular fasciculi. Nerves are profusely distributed to striped muscle. Their mode of termination is described on page 803. The existence of lymphatic vessels in striped muscle has not been ascertained, though they have been found in tendons and in the sheaths of the muscles.


**Unstriped, Plain, or Involuntary Muscle.**—Unstriped, plain, or involuntary muscle is found in the following situations: in the lower half of the œsophagus and the whole of the remainder of the gastro-intestinal tube; in the trachea and bronchi;

in the gall-bladder and common bile duct; in the large ducts of the salivary and pancreatic glands; in the pelvis and calices of the kidney, the ureter, bladder, and urethra; in the female sexual organs—viz., the ovary, the uterine tubes, the uterus (enormously developed in pregnancy), the vagina, the broad ligaments, and the corpora cavernosa of the clitoris; in the male sexual organs—viz., the dartos of the scrotum, the ductus deferens and epididymis, the vesiculæ seminales, the prostate, and the corpora cavernosa of the penis and urethra; in the capsule and trabeculæ of the spleen; in the mucous membranes, forming the muscularis mucosæ; in the skin, forming the Arrectores pilorum, and also in the sweat glands; in the arteries, veins, and lymphatics; in the iris and the ciliary muscle.

Plain or unstriated muscle is made up of spindle-shaped cells, called **contractile fibre cells**, collected into bundles and held together by a cement substance (Fig. 46). These bundles are further aggregated into larger fasciculi, or flattened bands, and bound together by ordinary connective tissue.

The **contractile fibre cells** are elongated, spindle-shaped, nucleated cells of various sizes, averaging from  $40$  to  $80\mu$  in length, and  $6$  to  $7\mu$  in breadth. On transverse section they are more or less polyhedral in shape, from mutual pressure. Each presents a faint longitudinal striation and consists of an elastic cell wall containing a central bundle of fibrillæ, representing the contractile substance, and an oval or rod-like nucleus, which includes, within a membrane, a fine net-work communicating at the poles of the nucleus with the contractile fibres (Klein). The fibres are attached to one another by a certain amount of interstitial cement substance which reduces nitrate of silver, but in some regions, *e. g.*, the muscular coats of the intestines, the muscle cells are also connected by "bridges" similar to those which occur in the prickle cells of the epidermis. Unstriated muscle, except the ciliary muscle, is not under the control of the will, neither is the contraction rapid nor does it, as a rule, involve the whole muscle, as is the case with the voluntary muscles. The membranes which are composed of unstriated muscle slowly contract in a part of their extent, generally under the influence of a mechanical stimulus, as that of distension or of cold; and then the contracted part slowly relaxes while another portion of the membrane takes up the contraction. This peculiarity of action is most strongly marked in the intestines, constituting their **vermicular motion**.

FIG. 46.—Muscle fibres from small intestine. (Schäfer.) A. Complete cell. B. Broken cell showing delicate external layer.



**Cardiac Muscular Tissue.**—The fibres of the heart differ very remarkably from those of other striped muscles. They are smaller by one-third, and their transverse striæ are by no means so well-marked. They show faint longitudinal striation. The fibres are made up of distinct quadrangular cells, joined end to end so as to form a syncytium (Fig. 47). Each cell contains a clear oval nucleus, situated near its centre. The extremities of the cells have a tendency to branch or divide, the subdivisions uniting with offsets from other cells, and thus producing an anastomosis of the fibres. The connective tissue between the bundles of fibres is much less than in ordinary striped muscle, and no sarcolemma has been proved to exist.



**Purkinje Fibres** (Fig. 48).—Between the endocardium and the ordinary cardiac muscle are found, imbedded in a small amount of connective tissue, peculiar fibres known as **Purkinje fibres**. They are found in certain mammals and in birds, and can be best seen in the sheep's heart, where they form a considerable portion of the moderator band and also appear as gelatinous-looking strands on the inner walls of the atria and ventricles. They also occur in the human heart associated with the terminal distributions of the bundle of His (see p. 614). The fibres are very much larger in size than the cardiac cells and differ from them in several ways. In longitudinal section they are quadrilateral in shape, being about twice as long as they are broad. The central portion of each fibre contains one or more nuclei and is made up of granular protoplasm, with no indication of striations, while the peripheral portion is clear and has distinct transverse striations. The fibres are intimately connected with each other, possess no definite sarcolemma, and do not branch.




FIG. 47.—Anastomosing muscular fibres of the heart seen in a longitudinal section. On the right the limits of the separate cells with their nuclei are exhibited somewhat diagrammatically.




FIG. 48.—Purkinje fibres from the sheep's heart.

The **Bundle of His** (see p. 614) is composed of cells which differ from ordinary cardiac muscle cells in being more spindle-shaped. They are, moreover, more loosely arranged and have a richer vascular supply than the rest of the heart muscle.

**Development of Muscle Fibres.**—Voluntary muscular fibres are developed from the mesoderm, the embryonic cells of which elongate, show multiplication of nuclei, and eventually become striated; the striation is first obvious at the side of the fibres, spreads around the circumference, and ultimately extends to the centre. The nuclei, at first situated centrally, gradually pass out to assume their final position immediately beneath the sarcolemma. In the case of involuntary muscle the mesodermal cell assumes a pointed shape at the extremities and becomes flattened, the nucleus also lengthening out to its permanent rod-like form.

## THE NERVOUS TISSUE.

The **nervous tissues** of the body comprise the **brain**, the **medulla spinalis** or **spinal cord**, the **cerebral**, **spinal**, and **sympathetic nerves**, and the **ganglia** connected with them.

The nervous tissues are composed of **nerve cells** and their various processes, together with a supporting tissue called **neuroglia**, which, however, is found only in the brain and medulla spinalis. Certain long processes of the nerve cells are of special importance, and it is convenient to consider them apart from the cells; they are known as **nerve fibres**.

To the naked eye a difference is obvious between certain portions of the brain and medulla spinalis, viz., the **gray substance** and the **white substance**. The gray substance is largely composed of nerve cells, while the white substance contains only their long processes, the nerve fibres. It is in the former that nervous impressions are received, stored, and transformed into efferent impulses, and by the latter that they are conducted. Hence the gray substance forms the essential constituent of all the ganglionic centres, both those in the isolated ganglia and those aggregated in the brain and medulla spinalis; while the white substance forms the bulk of the commissural portions of the nerve centres and the peripheral nerves.




FIG. 49.—Neuroglia cells of brain shown by Golgi's method. (After Andriezen.) A. Cell with branched processes B. Spider cell with unbranched processes.

**Neuroglia.**—Neuroglia, the peculiar ground substance in which are imbedded the true nervous constituents of the brain and medulla spinalis, consists of cells and fibres. Some of the cells are stellate in shape, with ill-defined cell body, and their fine processes become neuroglia fibres, which extend radially and unbranched (Fig. 49, B) among the nerve cells and fibres which they aid in supporting. Other cells give off fibres which branch repeatedly (Fig. 49, A). Some of the fibres start from the epithelial cells lining the ventricles of the brain and central canal of the medulla spinalis, and pass through the nervous tissue, branching repeatedly to end in slight enlargements on the pia mater. Thus, neuroglia is evidently a connective tissue in function but is not so in development; it is ectodermal in origin, whereas all connective tissues are mesodermal.

**Nerve Cells** (Fig. 50).—Nerve cells are largely aggregated in the gray substance of the brain and medulla spinalis, but smaller collections of these cells also form the swellings, called ganglia, seen on many nerves. These latter are found chiefly upon the spinal and cerebral nerve roots and in connection with the sympathetic nerves.

The nerve cells vary in shape and size, and have one or more processes. They may be divided for purposes of description into three groups, according to the number of processes which they possess: (1) **Unipolar cells**, which are found in the spinal ganglia; the single process, after a short course, divides in a T-shaped

manner (Fig. 50, *E*). (2) **Bipolar cells**, also found in the spinal ganglia (Fig. 51), when the cells are in an embryonic condition. They are best demonstrated in the spinal ganglia of fish. Sometimes the processes come off from opposite poles of




FIG. 50.—Various forms of nerve cells. *A*. Pyramidal cell. *B*. Small multipolar cell, in which the axon quickly divides into numerous branches. *C*. Small fusiform cell. *D* and *E*. Ganglion cells (*E* shows T-shaped division of axon). *ax*. Axon. *c*. Capsule.




FIG. 51.—Bipolar nerve cell from the spinal ganglion of the pike. (After Kölliker.)




FIG. 52.—Motor nerve cell from ventral horn of medulla spinalis of rabbit. (After Nissl.) The angular and spindle-shaped Nissl bodies are well shown.

the cell, and the cell then assumes a spindle shape; in other cells both processes emerge at the same point. In some cases where two fibres are apparently connected with a cell, one of the fibres is really derived from an adjoining nerve cell and is passing to end in a ramification around the ganglion cell, or, again, it may be coiled spirally around the nerve process which is issuing from the cell. (3) **Multipolar cells**, which are pyramidal or stellate in shape, and

characterized by their large size and by the numerous processes which issue from them. The processes are of two kinds: one of them is termed the **axis-cylinder process** or **axon** because it becomes the axis-cylinder of a nerve fibre

(Figs. 52, 53, 54). The others are termed the **protoplasmic processes** or **dendrons**; they begin to divide and subdivide as soon as they emerge from the cell, and finally end in minute twigs and become lost among the other elements of the nervous tissue.

The body of the nerve cell, known as the **cyton**, consists of a finely fibrillated protoplasmic material, of a reddish or yellowish-brown color, which occasionally presents patches of a deeper tint, caused by the aggregation of pigment granules at one side of the nucleus, as in the substantia nigra and locus caeruleus of the brain. The protoplasm also contains peculiar angular granules, which stain deeply




FIG. 53.—Pyramidal cell from the cerebral cortex of a mouse. (After Ramón y Cajal.)




FIG. 54.—Cell of Purkinje from the cerebellum. Golgi method. (Cajal.) a. Axon. b. Collateral. c and d. Dendrons.

with basic dyes, such as methylene blue; these are known as **Nissl's granules** (Fig. 52). They extend into the dendritic processes but not into the axis-cylinder; the small clear area at the point of exit of the axon is termed the **cone of origin**. These granules disappear (*chromatolysis*) during fatigue or after prolonged stimulation of the nerve fibres connected with the cells. They are supposed to represent a store of nervous energy, and in various mental diseases are deficient or absent. The nucleus is, as a rule, a large, well-defined, spherical body, often presenting an intranuclear network, and containing a well-marked nucleolus.

In addition to the protoplasmic network described above, each nerve cell may be shown to have delicate neurofibrils running through its substance (Fig. 55); these fibrils are continuous with the fibrils of the axon, and are believed to convey nerve impulses. Golgi has also described an extracellular network, which is probably a supporting structure.

**Nerve Fibres.**—Nerve fibres are found universally in the peripheral nerves and in the white substance of the brain and medulla spinalis. They are of two kinds—viz., **medullated** or **white fibres**, and **non-medullated** or **gray fibres**.




FIG. 55.—Nerve cells of kitten, showing neurofibrils. (Cajal.) a. Axon. b. Cyton. c. Nucleus. d. Neurofibrils.

The **medullated fibres** form the white part of the brain and medulla spinalis, and also the greater part of every cerebral and spinal nerve, and give to these structures their opaque, white aspect. When perfectly fresh they appear to be homogeneous; but soon after removal from the body each fibre presents, when examined by transmitted light, a double outline or contour, as if consisting of two parts (Fig. 56). The central portion is named the **axis-cylinder**; around this is a sheath of fatty material, staining black with osmic acid, named the **white substance of Schwann** or **medullary sheath**, which gives to the fibre its double contour, and the whole is enclosed in a delicate membrane, the **neurolemma**, **primitive sheath**, or **nucleated sheath of Schwann** (Fig. 58).

The **axis-cylinder** is the essential part of the nerve fibre, and is always present; the medullary sheath and the neurolemma are occasionally absent, especially at the origin and termination of the nerve fibre. The axis-cylinder undergoes no interruption from its origin in the nerve centre to its peripheral termination, and

must be regarded as a direct prolongation of a nerve cell. It constitutes about one-half or one-third of the nerve fibre, being greater in proportion in the fibres of the central organs than in those of the nerves. It is quite transparent, and is therefore indistinguishable in a perfectly fresh and natural state of the nerve. It is made up of exceedingly fine fibrils, which stain darkly with gold chloride




FIG. 56.—Medullated nerve fibres. (Bidder and Volkmann.)




FIG. 57.—Longitudinal and transverse sections of medullated nerve fibre of frog, showing node of Ranvier, medullary segments and fibrils of axis cylinder. Osmic acid. (Biedermann.)



FIG. 58.—Diagram of medullated nerve fibres stained with osmic acid.  $\times 425$ . (Schäfer.) R. Nodes of Ranvier. a. Neurolemma. c. Nucleus.

(Fig. 57), and at its termination may be seen to break up into these fibrillæ. The fibrillæ have been termed the **primitive fibrillæ of Schultze**. The axis-cylinder is said by some to be enveloped in a special reticular sheath, which separates it from the medullary sheath, and is composed of a substance called **neurokeratin**. The more common opinion is that this network or reticulum is contained in the white



matter of Schwann, and by some it is believed to be produced by the action of the reagents employed to show it.

The **medullary sheath**, or **white matter of Schwann** (Fig. 57), is regarded as being a fatty matter in a fluid state, which insulates and protects the essential part of the nerve—the axis-cylinder. It varies in thickness, in some forming a layer of extreme thinness, so as to be scarcely distinguishable, in others forming about one-half the nerve fibre. The variation in diameter of the nerve fibres (from 2 to  $16\mu$ ) depends mainly upon the amount of the white substance, though the axis cylinder also varies within certain limits. The medullary sheath undergoes interruptions in its continuity at regular intervals, giving to the fibre the appearance of constriction at these points: these are known as the **nodes of Ranvier** (Figs. 57 and 58). The portion of nerve fibre between two nodes is called an **internodal segment**. The neurolemma or primitive sheath is not interrupted at the nodes, but passes over them as a continuous membrane. If the fibre be treated with silver nitrate the reagent penetrates the neurolemma at the nodes, and on exposure to light reduction takes place, giving rise to the appearance of black crosses, **Ranvier's crosses**, on the axis-cylinder. There may also be seen transverse lines beyond the nodes termed




FIG. 59.—Medullated nerve fibres stained with silver nitrate.




FIG. 60.—A small nervous branch from the sympathetic of a mammal. *a*. Two medullated nerve fibres among a number of gray nerve fibres, *b*.

Frommann's lines (Fig. 59); the significance of these is not understood. In addition to these interruptions oblique clefts may be seen in the medullary sheath, subdividing it into irregular portions, which are termed **medullary segments**, or **segments of Lantermann** (Fig. 57); there is reason to believe that these clefts are artificially produced in the preparation of the specimens. Medullated nerve fibres, when examined in the fresh condition, frequently present a beaded or varicose appearance: this is due to manipulation and pressure causing the oily matter to collect into drops; and in consequence of the extreme delicacy of the primitive sheath, even slight pressure will cause the transudation of the fatty matter, which collects as drops of oil outside the membrane.

The **neurolemma** or **primitive sheath** presents the appearance of a delicate, structureless membrane. Here and there beneath it, and situated in depressions in the white matter of Schwann, are nuclei surrounded by a small amount of protoplasm. The nuclei are oval and somewhat flattened, and bear a definite relation to the nodes of Ranvier, one nucleus generally lying in the centre of each internode. The primitive sheath is not present in all medullated nerve fibres, being absent in those fibres which are found in the brain and medulla spinalis.

**Wallerian Degeneration.**—When nerve fibres are cut across, the central ends of the fibres degenerate as far as the first node of Ranvier; but the peripheral ends degenerate simultaneously throughout their whole length. The axons break up into fragments and become surrounded by drops of fatty substance which are formed from the breaking down of the medullary sheath. The nuclei of the primitive sheath proliferate, and finally absorption of the axons and fatty substance occurs. If the cut ends of the nerve be sutured together regeneration of the nerve fibres takes place by the downgrowth of axons from the central end of the nerve. At one time it was believed that the regeneration was peripheral in origin, but this has been disproved, the proliferated nuclei in the peripheral portions taking part merely in the formation of the so-called scaffolding along which the new axons pass.

**Non-medullated Fibres.**—Most of the fibres of the sympathetic system, and some of the cerebrospinal, consist of the **gray or gelatinous nerve fibres** (*fibres of Remak*) (Fig. 60). Each of these consists of an axis-cylinder to which nuclei are applied at intervals. These nuclei are believed to be in connection with a delicate sheath corresponding with the neurolemma of the medullated nerve fibre. In external appearance the non-medullated nerve fibres are semitransparent and gray or yellowish gray. The individual fibres vary in size, generally averaging about half the size of the medullated fibres.



# EMBRYOLOGY.

THE term **Embryology**, in its widest sense, is applied to the various changes which take place during the growth of an animal from the egg to the adult condition: it is, however, usually restricted to the phenomena which occur before birth. Embryology may be studied from two aspects: (1) that of **ontogeny**, which deals only with the development of the individual; and (2) that of **phylogeny**, which concerns itself with the evolutionary history of the animal kingdom.

In vertebrate animals the development of a new being can only take place when a female germ cell or **ovum** has been fertilized by a male germ cell or **spermatozoön**. The ovum is a nucleated cell, and all the complicated changes by which the various tissues and organs of the body are formed from it, after it has been fertilized, are the result of two general processes, viz., **segmentation** and **differentiation** of cells. Thus, the fertilized ovum undergoes repeated segmentation into a number of cells which at first closely resemble one another, but are, sooner or later, differentiated into two groups: (1) **somatic cells**, the function of which is to build up the various tissues of the body; and (2) **germinal cells**, which become imbedded in the sexual glands—the ovaries in the female and the testes in the male—and are destined for the perpetuation of the species.

Having regard to the main purpose of this work, it is impossible, in the space available in this section, to describe fully, or illustrate adequately, all the phenomena which occur in the different stages of the development of the human body. Only the principal facts are given, and the student is referred for further details to one or other of the text-books<sup>1</sup> on human embryology.

## THE OVUM.

The ova are developed from the primitive germ cells which are imbedded in the substance of the ovaries. Each primitive germ cell gives rise, by repeated divisions, to a number of smaller cells termed **oögonia**, from which the **ova** or **primary oöcytes** are developed.

Human ova are extremely minute, measuring about 0.2 mm. in diameter, and are enclosed within the egg follicles of the ovaries; as a rule each follicle contains a single ovum, but sometimes two or more are present.<sup>2</sup> By the enlargement and subsequent rupture of a follicle at the surface of the ovary, an ovum is liberated and conveyed by the uterine tube to the cavity of the uterus. Unless it be fertilized it undergoes no further development and is discharged from the uterus, but if fertilization take place it is retained within the uterus and is developed into a new being.

In appearance and structure the ovum (Fig. 61) differs little from an ordinary cell, but distinctive names have been applied to its several parts; thus, the cell substance is known as the **yolk** or **oöplasm**, the nucleus as the **germinal vesicle**, and the nucleolus as the **germinal spot**. The ovum is enclosed within a thick, trans-

<sup>1</sup> *Manual of Human Embryology*, Keibel and Mall; *Handbuch der vergleichenden und experimentellen Entwicklungslehre der Wirbeltiere*, Oskar Hertwig; *Lehrbuch der Entwicklungsgeschichte*, Bonnet; *The Physiology of Reproduction*, Marshall.

<sup>2</sup> See description of the ovary on a future page.

parent envelope, the **zona striata** or **zona pellucida**, adhering to the outer surface of which are several layers of cells, derived from those of the follicle and collectively constituting the **corona radiata**.

**Yolk.**—The yolk comprises (1) the **cytoplasm** of the ordinary animal cell with its spongioplasm and hyaloplasm; this is frequently termed the **formative yolk**; (2) the **nutritive yolk** or **deutoplasm**, which consists of numerous rounded granules of fatty and albuminoid substances imbedded in the cytoplasm. In the mammalian ovum the nutritive yolk is extremely small in amount, and is of service in nourishing the embryo in the early stages of its development only, whereas in the egg of the bird there is sufficient to supply the chick with nutriment throughout




FIG. 61.—Human ovum examined fresh in the liquor folliculi. (Waldeyer.) The zona pellucida is seen as a thick clear girdle surrounded by the cells of the corona radiata. The egg itself shows a central granular deutoplasmic area and a peripheral clear layer, and encloses the germinal vesicle, in which is seen the germinal spot.

the whole period of incubation. The nutritive yolk not only varies in amount, but in its mode of distribution within the egg; thus, in some animals it is almost uniformly distributed throughout the cytoplasm; in some it is centrally placed and is surrounded by the cytoplasm; in others it is accumulated at the lower pole of the ovum, while the cytoplasm occupies the upper pole. A **centrosome** and **centriole** are present and lie in the immediate neighborhood of the nucleus.

**Germinal Vesicle.**—The germinal vesicle or nucleus is a large spherical body which at first occupies a nearly central position, but becomes eccentric as the growth of the ovum proceeds. Its structure is that of an ordinary cell-nucleus, viz., it consists of a reticulum or karyomitome, the meshes of which are filled with

karyoplasm, while connected with, or imbedded in, the reticulum are a number of chromatin masses or chromosomes, which may present the appearance of a skein or may assume the form of rods or loops. The nucleus is enclosed by a delicate nuclear membrane, and contains in its interior a well-defined nucleolus or germinal spot.

**Coverings of the Ovum.**—The *zona striata* or *zona pellucida* (Fig. 61) is a thick membrane, which, under the higher powers of the microscope, is seen to be radially striated. It persists for some time after fertilization has occurred, and may serve for protection during the earlier stages of segmentation. It is not yet determined whether the *zona striata* is a product of the cytoplasm of the ovum or of the cells of the *corona radiata*, or both.

The *corona radiata* (Fig. 61) consists of two or three strata of cells; they are derived from the cells of the follicle, and adhere to the outer surface of the *zona striata* when the ovum is set free from the follicle; the cells are radially arranged around the *zona*, those of the innermost layer being columnar in shape. The cells of the *corona radiata* soon disappear; in some animals they secrete, or are replaced by, a layer of adhesive protein, which may assist in protecting and nourishing the ovum.

The phenomena attending the discharge of the ova from the follicles belong more to the ordinary functions of the ovary than to the general subject of embryology, and are therefore described with the anatomy of the ovaries.<sup>1</sup>




FIG. 62.—Formation of polar bodies in *Asterias glacialis*. (Slightly modified from Hertwig.) In *I* the polar spindle (*sp*) has advanced to the surface of the egg. In *II* a small elevation (*pb¹*) is formed which receives half of the spindle. In *III* the elevation is constricted off, forming the first polar body (*pb¹*), and a second spindle is formed. In *IV* is seen a second elevation which in *V* has been constricted off as the second polar body (*pb²*). Out of the remainder of the spindle (*f.pn* in *VI*) the female pronucleus is developed.

**Maturation of the Ovum.**—Before an ovum can be fertilized it must undergo a process of **maturation** or **ripening**. This takes place previous to or immediately after its escape from the follicle, and consists essentially of an unequal subdivision of the ovum (Fig. 62) first into two and then into four cells. Three of the four cells are small, incapable of further development, and are termed **polar bodies** or **polocytes**, while the fourth is large, and constitutes the **mature ovum**. The process of maturation has not been observed in the human ovum, but has been carefully studied in the ova of some of the lower animals, to which the following description applies.

It was pointed out on page 35 that the number of chromosomes found in the nucleus is constant for all the cells in an animal of any given species, and that in man the number is probably twenty-four. This applies not only to the somatic

<sup>1</sup> See description of the ovary on a future page.

cells but to the primitive ova and their descendants. For the purpose of illustrating the process of maturation a species may be taken in which the number of nuclear chromosomes is four (Fig. 36). If an ovum from such be observed at the beginning of the maturation process it will be seen that the number of its chromosomes is apparently reduced to two. In reality, however, the number is doubled, since each chromosome consists of four granules grouped to form a **tetrad**. During the metaphase (see page 36) each tetrad divides into two **dyads**, which are equally distributed between the nuclei of the two cells formed by the first division of the ovum. One of the cells is almost as large as the original ovum, and is named the **secondary oöcyte**; the other is small, and is termed the **first polar body**. The secondary oöcyte now undergoes subdivision, during which each dyad divides and contributes a single chromosome to the nucleus of each of the two resulting cells.




FIG. 63.—Diagram showing the reduction in number of the chromosomes in the process of maturation of the ovum.

This second division is also unequal, producing a large cell which constitutes the **mature ovum**, and a small cell, the **second polar body**. The first polar body frequently divides while the second is being formed, and as a final result four cells are produced, viz., the mature ovum and three polar bodies, each of which contains two chromosomes, *i. e.*, one-half the number present in the nuclei of the somatic cells of members of the same species. The nucleus of the mature ovum is termed the **female pronucleus**.

### THE SPERMATOZOÖN.

The **spermatozoa** or **male germ cells** are developed in the testes and are present in enormous numbers in the seminal fluid. Each consists of a small but greatly modified cell. The human spermatozoön possesses a **head**, a **neck**, a **connecting piece** or **body**, and a **tail** (Fig. 64).

The **head** is oval or elliptical, but flattened, so that when viewed in profile it is pear-shaped. Its anterior two-thirds are covered by a layer of modified proto-

plasm, which is named the **head-cap**. This, in some animals, *e. g.*, the salamander, is prolonged into a barbed spear-like process or **perforator**, which probably facilitates the entrance of the spermatozoön into the ovum. The posterior part of the head exhibits an affinity for certain reagents, and presents a transversely striated appearance, being crossed by three or four dark bands. In some animals a central rod-like filament extends forward for about two-thirds of the length of the head, while in others a rounded body is seen near its centre. The head contains a mass of chromatin, and is generally regarded as the nucleus of the cell surrounded by a thin envelope.




FIG. 64.—Human spermatozoön. Diagrammatic. A. Surface view. B. Profile view. In C the head, neck, and connecting piece are more highly magnified.

The **neck** is less constricted in the human spermatozoön than in those of some of the lower animals. The **anterior centriole**, represented by two or three rounded particles, is situated at the junction of the head and neck, and behind it is a band of homogeneous substance.

The **connecting piece** or **body** is rod-like, and is limited behind by a **terminal disc**. The **posterior centriole** is placed at the junction of the body and neck and, like the anterior, consists of two or three rounded particles. From this centriole an **axial filament**, surrounded by a sheath, runs backward through the body and tail. In the body the sheath of the axial filament is encircled by a **spiral thread**, around which is an envelope containing mitochondria granules, and termed the **mitochondria sheath**.

The **tail** is of great length, and consists of the axial thread or filament, surrounded by its sheath, which may contain a spiral thread or may present a striated appearance. The terminal portion or **end-piece** of the tail consists of the axial filament only.

Krause gives the length of the human spermatozoön as between  $52\mu$  and  $62\mu$ , the head measuring 4 to  $5\mu$ , the connecting piece  $6\mu$ , and the tail from  $41\mu$  to  $52\mu$ .

By virtue of their tails, which act as propellers, the spermatozoa are capable of free movement, and if placed in favorable surroundings, *e. g.*, in the female passages, will retain their vitality and power of fertilizing for several days. In certain animals, *e. g.*, bats, it has been proved that spermatozoa retained in the female passages for several months are capable of fertilizing.




FIG. 65.—Scheme showing analogies in the process of maturation of the ovum and the development of the spermatozoa (young spermatozoa).

The spermatozoa are developed from the primitive germ cells which have become imbedded in the testes, and the stages of their development are very similar to those of the maturation of the ovum. The primary germ cells undergo division and produce a number of cells termed **spermatogonia**, and from these the **primary spermatocytes** are derived. Each primary spermatocyte divides into two **secondary spermatocytes**, and each secondary spermatocyte into two **spermatids** or young spermatozoa; from this it will be seen that a primary spermatocyte gives rise to **four** spermatozoa. On comparing this process with that of the maturation of the ovum (Fig. 65) it will be observed that the primary spermatocyte gives rise to two cells, the secondary spermatocytes, and the primary oöcyte to two cells, the secondary oöcyte and the first polar body. Again, the two secondary spermatocytes by their subdivision give origin to four spermatozoa, and the secondary oöcyte and first polar body to four cells, the mature ovum and three polar bodies. In the development of the spermatozoa, as in the maturation of the ovum, there is a reduction of the nuclear chromosomes to one-half of those present in the primary spermatocyte. But here the similarity ends, for it must be noted that the four spermatozoa are of equal size, and each is capable of fertilizing a mature ovum, whereas the three polar bodies are not only very much smaller than the mature ovum but are incapable of further development, and may be regarded as abortive ova.

#### FERTILIZATION OF THE OVUM.

Fertilization consists in the union of the spermatozoön with the mature ovum (Fig. 66). Nothing is known regarding the fertilization of the human ovum, but

the various stages of the process have been studied in other mammals, and from the knowledge so obtained it is believed that fertilization of the human ovum takes place in the lateral or ampullary part of the uterine tube, and the ovum is then conveyed along the tube to the cavity of the uterus—a journey probably occupying seven or eight days and during which the ovum loses its corona radiata and zona striata and undergoes segmentation. Sometimes the fertilized ovum is arrested in the uterine tube, and there undergoes development, giving rise to a *tubal pregnancy*; or it may fall into the abdominal cavity and produce an *abdominal pregnancy*. Occasionally the ovum is not expelled from the follicle when the latter ruptures, but is fertilized within the follicle and produces what is known as an *ovarian pregnancy*. Under normal conditions only one spermatozoön enters the




FIG. 66.—The process of fertilization in the ovum of a mouse. (After Sobotta.)

yolk and takes part in the process of fertilization. At the point where the spermatozoön is about to pierce, the yolk is drawn out into a conical elevation, termed the *cone of attraction*. As soon as the spermatozoön has entered the yolk, the peripheral portion of the latter is transformed into a membrane, the *vitelline membrane* which prevents the passage of additional spermatozoa. Occasionally a second spermatozoön may enter the yolk, thus giving rise to a condition of *polyspermy*: when this occurs the ovum usually develops in an abnormal manner and gives rise to a monstrosity. Having pierced the yolk, the spermatozoön loses its tail, while its head and connecting piece assume the form of a nucleus containing a cluster of chromosomes. This constitutes the *male pronucleus*, and associated with it there are a centriole and centrosome. The male pronucleus passes more deeply into the yolk, and coincidentally with this the granules of the cytoplasm surrounding it becomes radially arranged. The male and female pronuclei migrate toward each other, and,

meeting near the centre of the yolk, fuse to form a new nucleus, the **segmentation nucleus**, which therefore contains both male and female nuclear substance; the former transmits the individualities of the male ancestors, the latter those of the female ancestors, to the future embryo. By the union of the male and female pronuclei the number of chromosomes, is restored to that which is present in the nuclei of the somatic cells.

### SEGMENTATION OF THE FERTILIZED OVUM.

The early segmentation of the human ovum has not yet been observed, but judging from what is known to occur in other mammals it may be regarded as certain that the process starts immediately after the ovum has been fertilized, *i. e.*, while the ovum is in the uterine tube. The segmentation nucleus exhibits the usual mitotic changes, and these are succeeded by a division of the ovum into two cells of nearly equal size.<sup>1</sup> The process is repeated again and again, so that the two cells are succeeded by four, eight, sixteen, thirty-two, and so on, with the result that a mass of cells is found within the zona striata, and to this mass the term




FIG. 67.—First stages of segmentation of a mammalian ovum. Semidiagrammatic. (From a drawing by Allen Thomson.) *z.p.* Zona striata. *p.gl.* Polar bodies. *a.* Two-cell stage. *b.* Four-cell stage. *c.* Eight-cell stage. *d, e.* Morula stage.

**morula** is applied (Fig. 67). The segmentation of the mammalian ovum may not take place in the regular sequence of two, four, eight, etc., since one of the two first formed cells may subdivide more rapidly than the other, giving rise to a three- or a five-cell stage. The cells of the morula are at first closely aggregated, but soon they become arranged into an outer or peripheral layer, the **trophoblast**, which does not contribute to the formation of the embryo proper, and an **inner cell-mass**, from which the embryo is developed. Fluid collects between the trophoblast and the greater part of the inner cell-mass, and thus the morula is converted into

<sup>1</sup> In the mammalian ova the nutritive yolk or deutoplasm is small in amount and uniformly distributed throughout the cytoplasm; such ova undergo *complete* division during the process of segmentation, and are therefore termed *holoblastic*. In the ova of birds, reptiles, and fishes where the nutritive yolk forms by far the larger portion of the egg, the cleavage is limited to the formative yolk, and is therefore only *partial*; such ova are termed *meroblastic*. Again, it has been observed, in some of the lower animals, that the pronuclei do not fuse but merely lie in apposition. At the commencement of the segmentation process the chromosomes of the two pronuclei group themselves around the equator of the nuclear spindle and then divide; an equal number of male and female chromosomes travel to the opposite poles of the spindle, and thus the male and female pronuclei subscribe equal shares of chromatin to the nuclei of the two cells which result from the subdivision of the fertilized ovum.



a vesicle, the **blastodermic vesicle** (Fig. 68). The inner cell-mass remains in contact, however, with the trophoblast at one pole of the ovum; this is named the **embryonic pole**, since it indicates the situation where the future embryo will be developed. The cells of the trophoblast become differentiated into two strata: an outer, termed the **syncytium** or **syncytiotrophoblast**, so named because it consists of a layer of protoplasm studded with nuclei, but showing no evidence of subdivision into cells; and an inner layer, the **cytotrophoblast** or **layer of Langhans**, in which




FIG. 68.—Blastodermic vesicle of *Vespertilio murinus*. (After van Beneden.)




FIG. 69.—Section through embryonic disk of *Vespertilio murinus*. (After van Beneden.)




FIG. 70.—Section through embryonic area of *Vespertilio murinus* to show the formation of the amniotic cavity. (After van Beneden.)

the cell outlines are defined. As already stated, the cells of the trophoblast do not contribute to the formation of the embryo proper; they form the ectoderm of the chorion and play an important part in the development of the placenta. On the deep surface of the inner cell-mass a layer of flattened cells, the **entoderm**, is differentiated and quickly assumes the form of a small sac, the **yolk-sac**. Spaces appear between the remaining cells of the mass (Fig. 69), and by the enlargement and coalescence of these spaces a cavity, termed the **amniotic cavity** (Fig. 70), is gradually

developed. The floor of this cavity is formed by the **embryonic disk** composed of a layer of prismatic cells, the **embryonic ectoderm**, derived from the inner cell-mass and lying in apposition with the entoderm.

**The Primitive Streak; Formation of the Mesoderm.**—The embryonic disk becomes oval and then pear-shaped, the wider end being directed forward. Near the narrow, posterior end an opaque streak, the **primitive streak** (Figs. 71 and 72), makes its appearance and extends along the middle of the disk for about one-half of its length; at the anterior end of the streak there is a knob-like thickening termed **Hensen's knot**. A shallow groove, the **primitive groove**, appears on the surface of the streak, and the anterior end of this groove communicates by means of an aperture, the **blastopore**, with the yolk-sac. The primitive streak is produced by a thickening of the axial part of the ectoderm, the cells of which multiply, grow downward, and blend with those of the subjacent entoderm (Fig. 73). From the sides of the primitive streak a third layer of cells, the **mesoderm**, extends lateralward between the ectoderm and entoderm; the caudal end of the primitive streak forms the cloacal membrane.




FIG. 71.—Surface view of embryo of a rabbit. (After Kölliker.) *arg.* Embryonic disk. *pr.* Primitive streak.

The extension of the mesoderm takes place throughout the whole of the embryonic and extra-embryonic areas of the ovum, except in certain regions. One of these is seen immediately in front of the neural tube. Here the mesoderm extends forward in the form of two crescentic masses, which meet in the middle line so as




FIG. 72.—Surface view of embryo of *Hylobates concolor*. (After Selenka.) The amnion has been opened to expose the embryonic disk.

to enclose behind them an area which is devoid of mesoderm. Over this area the ectoderm and entoderm come into direct contact with each other and constitute a thin membrane, the **buccopharyngeal membrane**, which forms a septum between the primitive mouth and pharynx. In front of the buccopharyngeal area, where the lateral crescents of mesoderm fuse in the middle line, the pericardium is

afterward developed, and this region is therefore designated the **pericardial area**. A second region where the mesoderm is absent, at least for a time, is that immediately in front of the pericardial area. This is termed the **proamniotic area**, and is the region where the **proamnion** is developed; in man, however, a proamnion is apparently never formed. A third region is at the hind end of the embryo where the ectoderm and entoderm come into apposition and form the **cloacal membrane**.




FIG. 73.—Series of transverse sections through the embryonic disk of *Tarsius*. (After Hubrecht.) Section *I* passes through the disk, in front of Hensen's knot and shows only the ectoderm and entoderm. Sections *II*, *III*, and *IV* pass through Hensen's knot, which is seen in *V* tapering away into the primitive streak. In *III*, *IV*, and *V* the mesoderm is seen springing from the keel-like thickening of the ectoderm, which in *III* and *IV* is observed to be continuous into the entoderm.

The blastoderm now consists of three layers, named from without inward: ectoderm, mesoderm, and entoderm; each has distinctive characteristics and gives rise to certain tissues of the body.<sup>1</sup>

**Ectoderm.**—The ectoderm consists of columnar cells, which are, however, somewhat flattened or cubical toward the margin of the embryonic disk. It forms the whole of the nervous system, the epidermis of the skin, the lining cells of the sebaceous, sudoriferous, and mammary glands, the hairs and nails, the epithelium of the nose and adjacent air sinuses, and that of the cheeks and roof of the mouth. From it also are derived the enamel of the teeth, and the anterior lobe of the hypophysis cerebri, the epithelium of the cornea, conjunctiva, and lacrimal glands, and the neuro-epithelium of the sense organs.

**Entoderm.**—The entoderm consists at first of flattened cells, which subsequently become columnar. It forms the epithelial lining of the whole of the digestive tube excepting part of the mouth and pharynx and the terminal part of the rectum

<sup>1</sup> The mode of formation of the germ layers in the human ovum has not yet been observed; in the youngest known human ovum (viz., that described by Bryce and Teacher), all three layers are already present and the mesoderm is split into its two layers. The extra-embryonic coelom is of considerable size, and scattered mesodermal strands are seen stretching between the mesoderm of the yolk-sac and that of the chorion.

(which are lined by involutions of the ectoderm), the lining cells of all the glands which open into the digestive tube, including those of the liver and pancreas, the epithelium of the auditory tube and tympanic cavity, of the trachea, bronchi, and air cells of the lungs, of the urinary bladder and part of the urethra, and that which lines the follicles of the thyroid gland and thymus.

**Mesoderm.**—The mesoderm consists of loosely arranged branched cells surrounded by a considerable amount of intercellular fluid. From it the remaining tissues of the body are developed. The endothelial lining of the heart and blood-vessels and the blood corpuscles are, however, regarded by some as being of entodermal origin.




FIG. 74.—A series of transverse sections through an embryo of the dog. (After Bonnet.) Section I is the most anterior. In V the neural plate is spread out nearly flat. The series shows the uprising of the neural folds to form the neural canal. *a*, Aorta; *c*, Intermediate cell mass. *ect*, Ectoderm. *ent*, Entoderm. *h*, *h*, Rudiments of endothelial heart tubes. In III, IV, and V the scattered cells represented between the ectoderm and splanchnic layer of mesoderm are the vasoformative cells which give origin in front, according to Bonnet, to the heart tubes; *h*; *l.p.* Lateral plate still undivided in I, II, and III; in IV and V split into somatic (*sm*) and splanchnic (*sp*) layers of mesoderm. *mes*, Mesoderm. *p*, Pericardium. *so*, Primitive segment.

As the mesoderm develops between the ectoderm and entoderm it is separated into lateral halves by the neural tube and notochord, presently to be described. A longitudinal groove appears on the dorsal surface of either half and divides it into a medial column, the **paraxial mesoderm**, lying on the side of the neural tube, and a lateral portion, the **lateral mesoderm**. The mesoderm in the floor of the groove connects the paraxial with the lateral mesoderm and is known as the **intermediate cell-mass**; in it the genito-urinary organs are developed. The lateral mesoderm splits into two layers, an outer or **somatic**, which becomes applied to the inner surface of the ectoderm, and with it forms the **somatopleure**; and an inner or **splanchnic**, which adheres to the entoderm, and with it forms the **splanchnopleure** (Fig. 74). The space between the two layers of the lateral mesoderm is termed the **coelom**.

## THE NEURAL GROOVE AND TUBE.

In front of the primitive streak two longitudinal ridges, caused by a folding up of the ectoderm, make their appearance, one on either side of the middle line (Fig. 74). These are named the **neural folds**; they commence some little distance behind the anterior end of the embryonic disk, where they are continuous with each other, and from there gradually extend backward, one on either side of the anterior end of the primitive streak. Between these folds is a shallow median groove, the **neural groove** (Figs. 74, 75). The groove gradually deepens as the neural folds become elevated, and ultimately the folds meet and coalesce in the middle line and convert the groove into a closed tube, the **neural tube** or **canal** (Fig. 76), the ectodermal wall of which forms the rudiment of the nervous system. By the coalescence of the neural folds over the anterior end of the primitive streak, the blastopore no longer opens on the surface but into the closed canal of the neural




FIG. 75.—Human embryo—length, 2 mm. Dorsal view, with the amnion laid open.  $\times 30$ . (After Graf Spee.)

tube, and thus a transitory communication, the **neurenteric canal**, is established between the neural tube and the primitive digestive tube. The coalescence of the neural folds occurs first in the region of the hind-brain, and from there extends forward and backward; toward the end of the third week the front opening (anterior neuropore) of the tube finally closes at the anterior end of the future brain, and forms a recess which is in contact, for a time, with the overlying ectoderm; the hinder part of the neural groove presents for a time a rhomboidal shape, and to this expanded portion the term *sinus rhomboidalis* has been applied (Fig. 76). Before the neural groove is closed a ridge of ectodermal cells appears along the prominent margin of each neural fold; this is termed the **neural crest** or **ganglion ridge**, and from it the spinal and cerebral nerve ganglia and the ganglia of the sympathetic nervous system are developed. By the upward growth of the mesoderm the neural tube is ultimately separated from the overlying ectoderm.

The cephalic end of the neural groove exhibits several dilatations, which, when the tube is closed, assume the form of three vesicles; these constitute the three **primary cerebral vesicles**, and correspond respectively to the future **prosencephalon**

(fore-brain), **mesencephalon** (mid-brain), and **rhombencephalon** (hind-brain) (Fig. 76). The walls of the vesicles are developed into the nervous tissue and neuroglia of the brain, and their cavities are modified to form its ventricles. The remainder of the tube forms the **medulla spinalis** or **spinal cord**; from its ectodermal wall the nervous and neuroglial elements of the medulla spinalis are developed while the cavity persists as the central canal.




FIG. 76.—Chick embryo of thirty-three hours' incubation, viewed from the dorsal aspect.  $\times 30$ .  
(From Duval's "Atlas d'Embryologie.")

### THE NOTOCHORD.

The notochord (Fig. 77) consists of a rod of cells situated on the ventral aspect of the neural tube; it constitutes the foundation of the axial skeleton, since around it the segments of the vertebral column are formed. Its appearance synchronizes



with that of the neural tube. On the ventral aspect of the neural groove an axial thickening of the entoderm takes place; this thickening assumes the appearance of a furrow—the **chordal furrow**—the margins of which come into contact, and so convert it into a solid rod of cells—the **notochord**—which is then separated from the entoderm. It extends throughout the entire length of the future vertebral




FIG. 77.—Transverse section of a chick embryo of forty-five hours' incubation. (Balfour.)

column, and reaches as far as the anterior end of the mid-brain, where it ends in a hook-like extremity in the region of the future dorsum sellae of the sphenoid bone. It lies at first between the neural tube and the entoderm of the yolk-sac, but soon becomes separated from them by the mesoderm, which grows medialward and surrounds it. From the mesoderm surrounding the neural tube and notochord, the skull and vertebral column, and the membranes of the brain and medulla spinalis are developed.

### THE PRIMITIVE SEGMENTS.

Toward the end of the second week transverse segmentation of the paraxial mesoderm begins, and it is converted into a series of well-defined, more or less cubical masses, the **primitive segments** (Figs. 76, 77, 78), which occupy the entire length of the trunk on either side of the middle line from the occipital region of the head. Each segment contains a central cavity—**myocœl**—which, however, is soon filled with angular and spindle-shaped cells.

The primitive segments lie immediately under the ectoderm on the lateral aspect of the neural tube and notochord, and are connected to the lateral mesoderm by the **intermediate cell-mass**. Those of the trunk may be arranged in the following groups, viz.: cervical 8, thoracic 12, lumbar 5, sacral 5, and coccygeal from 5 to 8. Those of the occipital region of the head are usually described as being four in number. In mammals primitive segments of the head can only be recognized in the occipital region, but a study of the lower vertebrates leads to the belief that they are present also in the anterior part of the head, and that altogether nine segments are represented in the cephalic region.




FIG. 78.—Dorsum of human embryo, 2.11 mm. in length. (After Eternod.)

## SEPARATION OF THE EMBRYO.

The embryo increases rapidly in size, but the circumference of the embryonic disk, or line of meeting of the embryonic and amniotic parts of the ectoderm, is of relatively slow growth and gradually comes to form a constriction between the embryo and the greater part of the yolk-sac. By means of this constriction, which corresponds to the future umbilicus, a small part of the yolk-sac is enclosed within the embryo and constitutes the primitive digestive tube.

The embryo increases more rapidly in length than in width, and its cephalic and caudal ends soon extend beyond the corresponding parts of the circumference of the embryonic disk and are bent in a ventral direction to form the **cephalic** and **caudal folds** respectively (Figs. 84 and 85). The cephalic fold is first formed, and




FIG. 79.—Section through the embryo which is represented in Fig. 75. (After Graf Spee.)

as the proamniotic area (page 87) lying immediately in front of the pericardial area (page 87) forms the anterior limit of the circumference of the embryonic disk, the forward growth of the head necessarily carries with it the posterior end of the pericardial area, so that this area and the buccopharyngeal membrane are folded back under the head of the embryo which now encloses a diverticulum of the yolk-sac named the **fore-gut**. The caudal end of the embryo is at first connected to the chorion by a band of mesoderm called the **body-stalk**, but with the formation of the caudal fold the body-stalk assumes a ventral position; a diverticulum of the yolk-sac extends into the tail fold and is termed the **hind-gut**. Between the fore-gut and the hind-gut there exists for a time a wide opening into the yolk-sac, but the latter is gradually reduced to a small pear-shaped sac (sometimes termed the **umbilical vesicle**), and the channel of communication is at the same time narrowed and elongated to form a tube called the **vitelline duct**.



### THE YOLK-SAC.

The yolk-sac (Figs. 79 and 80) is situated on the ventral aspect of the embryo; it is lined by entoderm, outside of which is a layer of mesoderm. It is filled with fluid, the **vitelline fluid**, which possibly may be utilized for the nourishment of the embryo during the earlier stages of its existence. Blood is conveyed to the wall of the sac by the primitive aortæ, and after circulating through a wide-meshed capillary plexus, is returned by the vitelline veins to the tubular heart of the embryo. This constitutes the **vitelline circulation**, and by means of it nutritive material is absorbed from the yolk-sac and conveyed to the embryo. At the end of the fourth week the yolk-sac presents the appearance of a small pear-shaped vesicle (umbilical vesicle) opening into the digestive tube by a long narrow tube, the **vitelline duct**. The vesicle can be seen in the after-birth as a small, somewhat oval-shaped body whose diameter varies from 1 mm. to 5 mm.; it is situated between the amnion and the chorion and may lie on or at a varying distance from the placenta. As a rule the duct undergoes complete obliteration during the seventh week, but in about three per cent. of cases its proximal part persists as a diverticulum from the small intestine, **Meckel's diverticulum**, which is situated about three or four feet above the ileocolic junction, and may be attached by a fibrous cord to the abdominal wall at the umbilicus. Sometimes a narrowing of the lumen of the ileum is seen opposite the site of attachment of the duct.




FIG. 80.—Human embryo from thirty-one to thirty-four days. (Hie.)

### DEVELOPMENT OF THE FETAL MEMBRANES AND THE PLACENTA.

**The Allantois** (Figs. 82 to 85).—The allantois arises as a tubular diverticulum of the posterior part of the yolk-sac; when the hind-gut is developed the allantois is carried backward with it and then opens into the cloaca or terminal part of the hind-gut: it grows out into the body-stalk, a mass of mesoderm which lies below and around the tail end of the embryo. The diverticulum is lined by entoderm and covered by mesoderm, and in the latter are carried the allantoic or umbilical vessels.

In reptiles, birds, and many mammals the allantois becomes expanded into a vesicle which projects into the extra-embryonic cœlom. If its further development be traced in the bird, it is seen to project to the right side of the embryo, and, gradually expanding, it spreads over its dorsal surface as a flattened sac between the amnion and the serosa, and extending in all directions, ultimately surrounds the yolk. Its outer wall becomes applied to and fuses with the serosa, which lies immediately inside the shell membrane. Blood is carried to the allantoic sac by the two allantoic or umbilical arteries, which are continuous with the primitive aortæ, and after circulating through the allantoic capillaries, is returned to the primitive heart by the two umbilical veins. In this way the allantoic circulation, which is of the utmost importance in connection with the respiration and nutrition

of the chick, is established. Oxygen is taken from, and carbonic acid is given up to the atmosphere through the egg-shell, while nutritive materials are at the same time absorbed by the blood from the yolk.




FIG. 81.—Diagram showing earliest observed stage of human ovum.




FIG. 82.—Diagram illustrating early formation of allantois and differentiation of body-stalk.

In man and other primates the nature of the allantois is entirely different from that just described. Here it exists merely as a narrow, tubular diverticulum of the hind-gut, and never assumes the form of a vesicle outside the embryo. With the formation of the amnion the embryo is, in most animals, entirely separated from the chorion, and is only again united to it when the allantoic mesoderm spreads over and becomes applied to its inner surface. The human embryo, on the other hand, as was pointed out by His, is never wholly separated from the chorion, its tail end being from the first connected with the chorion by means of a thick band of mesoderm, named the **body-stalk** (Bauchstiel); into this stalk the tube of the allantois extends (Fig. 79).




FIG. 83.—Diagram showing later stage of allantoic development with commencing constriction of the yolk-sac.




FIG. 84.—Diagram showing the expansion of amnion and delimitation of the umbilicus.

**The Amnion.**—The amnion is a membranous sac which surrounds and protects the embryo. It is developed in reptiles, birds, and mammals, which are hence called "Amniota;" but not in amphibia and fishes, which are consequently termed "Anamnia."

In the human embryo the earliest stages of the formation of the amnion have not been observed; in the youngest embryo which has been studied the amnion was already present as a closed sac (Figs. 81 and 88), and, as indicated on page 85,

appears in the inner cell-mass as a cavity. This cavity is roofed in by a single stratum of flattened, ectodermal cells, the **amniotic ectoderm**, and its floor consists of the prismatic ectoderm of the embryonic disk—the continuity between the roof and floor being established at the margin of the embryonic disk. Outside the amniotic ectoderm is a thin layer of mesoderm, which is continuous with that of the somatopleure and is connected by the body-stalk with the mesodermal lining of the chorion.

When first formed the amnion is in contact with the body of the embryo, but about the fourth or fifth week fluid (*liquor amnii*) begins to accumulate within it. This fluid increases in quantity and causes the amnion to expand and ultimately to adhere to the inner surface of the chorion, so that the extra-embryonic part of the coelom is obliterated. The liquor amnii increases in quantity up to the sixth or seventh month of pregnancy, after which it diminishes somewhat; at the end of pregnancy it amounts to about 1 litre. It allows of the free movements of the fetus during the later stages of pregnancy, and also protects it by diminishing the risk of injury from without. It contains less than 2 per cent. of solids, consisting of




FIG. 85.—Diagram illustrating a later stage in the development of the umbilical cord.




FIG. 86.—Diagram of a transverse section, showing the mode of formation of the amnion in the chick. The amniotic folds have nearly united in the middle line. (From Quain's Anatomy.) Ectoderm, blue; mesoderm, red; entoderm and notochord, black.

urea and other extractives, inorganic salts, a small amount of protein, and frequently a trace of sugar. That some of the liquor amnii is swallowed by the fetus is proved by the fact that epidermal debris and hairs have been found among the contents of the fetal alimentary canal.

In reptiles, birds, and many mammals the amnion is developed in the following manner: At the point of constriction where the primitive digestive tube of the embryo joins the yolk-sac a reflection of folding upward of the somatopleure takes place. This, the **amniotic fold** (Fig. 86), first makes its appearance at the cephalic extremity, and subsequently at the caudal end and sides of the embryo, and gradually rising more and more, its different parts meet and fuse over the dorsal aspect of the embryo, and enclose a cavity, the **amniotic cavity**. After the fusion of the edges of the amniotic fold, the two layers of the fold become completely separated, the inner forming the **amnion**, the outer the **false amnion** or **serosa**. The space between the amnion and the serosa constitutes the extra-embryonic coelom, and for a time communicates with the embryonic coelom.




FIG. 87.—Model of human embryo 1.3 mm. long. (After Eternod.)

**The Umbilical Cord and Body-stalk.**—The umbilical cord (Fig. 85) attaches the fetus to the placenta; its length at full time, as a rule, is about equal to the length of the fetus, *i. e.*, about 50 cm., but it may be greatly diminished or increased. The rudiment of the umbilical cord is represented by the tissue which connects the rapidly growing embryo with the extra-embryonic area of the ovum. Included in this tissue are the body-stalk and the vitelline duct—the former containing the allantoic diverticulum and the umbilical vessels, the latter forming the communication between the digestive tube and the yolk-sac. The body-stalk is the posterior segment of the embryonic area, and is attached to the chorion. It consists of a plate of mesoderm covered by thickened ectoderm on which a trace of the neural groove can be seen, indicating its continuity with the embryo. Running through its mesoderm are the two umbilical arteries and the two umbilical veins, together with the canal of the allantois—the last being lined by entoderm (Fig. 87). Its dorsal surface is covered by the amnion, while its ventral surface is bounded by the extra-embryonic coelom, and is in contact with the vitelline duct and yolk-sac. With the rapid elongation of the embryo and the formation of the tail fold, the body stalk comes to lie on the ventral surface of the embryo (Figs. 84 and 85), where its mesoderm blends with that of the yolk-sac and the vitelline duct. The lateral leaves of somatopleure then grow round on each side, and, meeting on the ventral



aspect of the allantois, enclose the vitelline duct and vessels, together with a part of the extra-embryonic coelom; the latter is ultimately obliterated. The cord is covered by a layer of ectoderm which is continuous with that of the amnion, and its various constituents are enveloped by embryonic gelatinous tissue, **jelly of Wharton**. The vitelline vessels and duct, together with the right umbilical vein, undergo atrophy and disappear; and thus the cord, at birth, contains a pair of umbilical arteries and one (the left) umbilical vein.




FIG. 88.—Section through ovum imbedded in the uterine decidua. Semidiagrammatic. (After Peters.) *am.* Amniotic cavity. *b.c.* Blood-clot. *b.s.* Body-stalk. *ect.* Embryonic ectoderm. *ent.* Entoderm. *mes.* Mesoderm. *m.v.* Maternal vessels. *tr.* Trophoblast. *u.e.* Uterine epithelium. *u.g.* Uterine glands. *y.s.* Yolk-sac.

**Implantation or Imbedding of the Ovum.**—As described (page 82), fertilization of the ovum occurs in the lateral or ampullary end of the uterine tube and is immediately followed by segmentation. On reaching the cavity of the uterus the segmented ovum adheres like a parasite to the uterine mucous membrane, destroys the epithelium over the area of contact, and excavates for itself a cavity in the mucous membrane in which it becomes imbedded. In the ovum described by Bryce and Teacher<sup>1</sup> the point of entrance was visible as a small gap closed by a mass of fibrin and leucocytes; in the ovum described by Peters<sup>2</sup> the opening was covered by a mushroom-shaped mass of fibrin and blood-clot (Fig. 88), the narrow stalk of which plugged the aperture in the mucous membrane. Soon, however, all trace of the opening is lost and the ovum is then completely surrounded by the uterine mucous membrane.

The structure actively concerned in the process of excavation is the trophoblast of the ovum, which possesses the power of dissolving and absorbing the uterine

<sup>1</sup> Contribution to the study of the early development and imbedding of the human ovum, 1908.

<sup>2</sup> Die Einbettung des menschlichen Eies, 1899.

tissues. The trophoblast proliferates rapidly and forms a network of branching processes which cover the entire ovum and invade and destroy the maternal tissues and open into the maternal bloodvessels, with the result that the spaces in the trophoblastic network are filled with maternal blood; these spaces communicate freely with one another and become greatly distended and form the **intervillous space**.

**The Decidua.**—Before the fertilized ovum reaches the uterus, the mucous membrane of the body of the uterus undergoes important changes and is then

known as the **decidua**. The thickness and vascularity of the mucous membrane are greatly increased; its glands are elongated and open on its free surface by funnel-shaped orifices, while their deeper portions are tortuous and dilated into irregular spaces. The interglandular tissue is also increased in quantity, and is crowded with large round, oval, or polygonal cells, termed **decidual cells**. These changes are well advanced by the second month of pregnancy, when the mucous membrane consists of the following strata (Fig. 89): (1) **stratum compactum**, next the free surface; in this the uterine glands are only slightly expanded, and are lined by columnar cells; (2) **stratum spongiosum**, in which the gland tubes are greatly dilated and very tortuous, and are ultimately separated from one another by only a small amount of interglandular tissue, while their lining cells are flattened or cubical; (3) a thin **unaltered** or **boundary layer**, next the uterine muscular fibres, containing the deepest parts of the uterine glands, which are not dilated, and are lined with columnar epithelium; it is from this epithelium that the epithelial lining of the uterus is regenerated after pregnancy. Distinctive names are applied to different portions of the decidua. The part which covers in the ovum is named the **decidua capsularis**; the portion which intervenes between the ovum and the uterine wall is named the **decidua basalis** or **decidua placentalis**; it is here that the placenta is subsequently




FIG. 89.—Diagrammatic sections of the uterine mucous membrane: A. The non-pregnant uterus. B. The pregnant uterus, showing the thickened mucous membrane and the altered condition of the uterine glands. (Kundrat and Engelmann.)

developed. The part of the decidua which lines the remainder of the body of the uterus is known as the **decidua vera** or **decidua parietalis**.

Coincidentally with the growth of the embryo, the decidua capsularis is thinned and extended (Fig. 90) and the space between it and the decidua vera is gradually obliterated, so that by the third month of pregnancy the two are in contact. By

the fifth month of pregnancy the decidua capsularis has practically disappeared, while during the succeeding months the decidua vera also undergoes atrophy, owing to the increased pressure. The glands of the stratum compactum are obliterated, and their epithelium is lost. In the stratum spongiosum the glands are compressed and appear as slit-like fissures, while their epithelium undergoes degeneration. In the unaltered or boundary layer, however, the glandular epithelium retains a columnar or cubical form.

**The Chorion** (Figs. 80 to 85).—The chorion consists of two layers: an outer formed by the primitive ectoderm or trophoblast, and an inner by the somatic mesoderm; with this latter the amnion is in contact. The trophoblast is made up of an internal layer of cubical or prismatic cells, the **cytotrophoblast** or **layer of Langhans**, and an external layer of richly nucleated protoplasm devoid of cell boundaries, the **syncytiotrophoblast**. It undergoes rapid proliferation and forms numerous processes, the **chorionic villi**, which invade and destroy the uterine




FIG. 90.—Sectional plan of the gravid uterus in the third and fourth month. (Modified from Wagner.)

decidua and at the same time absorb from it nutritive materials for the growth of the embryo. The chorionic villi are at first small and non-vascular, and consist of trophoblast only, but they increase in size and ramify, while the mesoderm, carrying branches of the umbilical vessels, grows into them, and in this way they are vascularized. Blood is carried to the villi by the branches of the umbilical arteries, and after circulating through the capillaries of the villi, is returned to the embryo by the umbilical veins. Until about the end of the second month of pregnancy the villi cover the entire chorion, and are almost uniform in size (Fig. 82), but after this they develop unequally. The greater part of the chorion is in contact with the decidua capsularis (Fig. 90), and over this portion the villi, with their contained vessels, undergo atrophy, so that by the fourth month scarcely a trace of them is left, and hence this part of the chorion becomes smooth, and is named the **chorion laeve**; as it takes no share in the formation of the placenta, it is also named the non-placental part of the chorion. On the other hand, the villi on that part of the chorion which is in contact with the decidua placentalis increase

greatly in size and complexity, and hence this part is named the **chorion frondosum** (Fig. 85).

**The Placenta.**—The placenta connects the fetus to the uterine wall, and is the organ by means of which the nutritive, respiratory, and excretory functions of the fetus are carried on. It is composed of **fetal** and **maternal** portions.

**Fetal Portion.**—The fetal portion of the placenta consists of the villi of the chorion frondosum; these branch repeatedly, and increase enormously in size.

These greatly ramified villi are suspended in the intervillous space, and are bathed in maternal blood, which is conveyed to the space by the uterine arteries and carried away by the uterine veins. A branch of an umbilical artery enters each villus and ends in a capillary plexus from which the blood is drained by a tributary of the umbilical vein. The vessels of the villus are surrounded by a thin layer of mesoderm consisting of gelatinous connective tissue, which is covered by two strata of ectodermal cells derived from the trophoblast: the deeper stratum, next the mesodermic tissue, represents the cytotrophoblast or layer of Langhans; the superficial, in contact




FIG. 91.—Diagram to illustrate the first phase of the placenta. (After Peters.) *b.l.* Blood lacuna. *ca.* Maternal capillary. *dc.* Decidua. *mes.* Mesoderm. *sy.* Syncytiotrophoblast. *tr.* Cytotrophoblast.

with the maternal blood, the syncytiotrophoblast (Figs. 91 and 92). After the fifth month the two strata of cells are replaced by a single layer of somewhat flattened cells.




FIG. 92.—Diagram to illustrate the second phase of the placenta. (After Peters.) The mesodermic core has now invaded the strands of the trophoblast, and is beginning to branch. *ca.* Maternal capillary. *core.* Core of villus. *fib.* Fibrinous material deposited at junction of trophoblast with decidua. *mcp.* Endothelium of maternal capillary. *mes.* Mesoderm. *sy.* Syncytiotrophoblast. *vs.* Intervillous space.

**Maternal Portion.**—The maternal portion of the placenta is formed by the decidua placentalis containing the intervillous space. As already explained, this space is produced by the enlargement and intercommunication of the spaces in the trophoblastic network. The changes involve the disappearance of the greater portion of the stratum compactum, but the deeper part of this layer persists and is condensed to form what is known as the **basal plate**. Between this plate and the uterine muscular fibres are the stratum spongiosum and the boundary layer;



through these and the basal plate the uterine arteries and veins pass to and from the intervillous space. The endothelial lining of the uterine vessels ceases at the point where they terminate in the intervillous space which is lined by the syncytiotrophoblast. Portions of the stratum compactum persist and are condensed to form a series of septa, which extend from the basal plate through the thickness of the placenta and subdivide it into the lobules or **cotyledons** seen on the uterine surface of the detached placenta.

The fetal and maternal blood currents traverse the placenta, the former passing through the bloodvessels of the placental villi and the latter through the intervillous space (Fig. 93). The two currents do not intermingle, being separated from each other by the delicate walls of the villi. Nevertheless, the fetal blood is able to absorb, through the walls of the villi, oxygen and nutritive materials from the maternal blood, and give up to the latter its waste products. The blood, so purified, is carried back to the fetus by the umbilical vein. It will thus be seen that the placenta not only establishes a mechanical connection between the mother and the fetus, but subserves for the latter the purposes of nutrition, respiration, and excretion. In favor of the view that the placenta possesses certain selective powers may be mentioned the fact that glucose is more plentiful in the maternal than in the fetal blood. It is interesting to note also that the proportion of iron, and of lime and potash, in the fetus is increased during the last months of pregnancy. Further, there is evidence that the maternal leucocytes may migrate into the fetal blood, since leucocytes are much more numerous in the blood of the umbilical vein than in that of the umbilical arteries.

The placenta is usually attached near the fundus uteri, and more frequently on the posterior than on the anterior wall of the uterus. It may, however, occupy a lower position and, in rare cases, its site is close to the orificium internum uteri, which it may occlude, thus giving rise to the condition known as *placenta praevia*.

**Separation of the Placenta.**—After the child is born, the placenta and membranes are expelled from the uterus as the *after-birth*. The separation of the placenta from the uterine wall takes place through the stratum spongiosum, and necessarily causes rupture of the uterine vessels. The orifices of the torn vessels are, however, closed by the firm contraction of the uterine muscular fibres, and thus *postpartum hemorrhage* is controlled. The epithelial lining of the uterus is regenerated by the proliferation and extension of the epithelium which lines the persistent portions of the uterine glands in the unaltered layer of the decidua.

The expelled placenta appears as a discoid mass which weighs about 450 gm. and has a diameter of from 15 to 20 cm. Its average thickness is about 3 cm., but this diminishes rapidly toward the circumference of the disk, which is continuous with the membranes. Its uterine surface is divided by a series of fissures into lobules or **cotyledons**, the fissures containing the remains of the septa which extended




FIG. 93.—Scheme of placental circulation.

between the maternal and fetal portions. Most of these septa end in irregular or pointed processes; others, especially those near the edge of the placenta, pass through its thickness and are attached to the chorion. In the early months these septa convey branches of the uterine arteries which open into the intervillous space on the surfaces of the septa. The fetal surface of the placenta is smooth, being closely invested by the amnion. Seen through the latter, the chorion presents a mottled appearance, consisting of gray, purple, or yellowish areas. The umbilical cord is usually attached near the centre of the placenta, but may be inserted anywhere between the centre and the margin; in some cases it is inserted into the membranes, *i. e.*, the **velamentous insertion**. From the attachment of the cord the larger branches of the umbilical vessels radiate under the amnion, the veins being deeper and larger than the arteries. The remains of the vitelline duct and yolk-sac may be sometimes observed beneath the amnion, close to the cord, the former as an attenuated thread, the latter as a minute sac.

On section, the placenta presents a soft, spongy appearance, caused by the greatly branched villi; surrounding them is a varying amount of maternal blood giving the dark red color to the placenta. Many of the larger villi extend from the chorionic to the decidual surface, while others are attached to the septa which separate the cotyledons; but the great majority of the villi hang free in the intervillous space.

The further growth of the embryo will be best understood from a description of the principal facts relating to the development of the chief systems of which the body consists.

#### DEVELOPMENT OF THE PARIETES.

**The Skeleton.**—The skeleton is of mesodermal origin, and may be divided into (a) that of the trunk (**axial skeleton**), comprising the vertebral column, skull, ribs, and sternum, and (b) that of the limbs (**appendicular skeleton**).

**The Vertebral Column.**—The notochord (Fig. 77) is a temporary structure and forms a central axis, around which the segments of the vertebral column are developed.<sup>1</sup> It is derived from the entoderm, and consists of a rod of cells, which lies on the ventral aspect of the neural tube and reaches from the anterior end of the mid-brain to the extremity of the tail. On either side of it is a column of paraxial mesoderm which becomes subdivided into a number of more or less cubical segments, the **primitive segments** (Figs. 77 and 78). These are separated from one another by **intersegmental septa** and are arranged symmetrically on either side of the neural tube and notochord: to every segment a spinal nerve is distributed. At first each segment contains a central cavity, the **myocoel**, but this is soon filled with a core of angular and spindle-shaped cells. The cells of the segment become differentiated into three groups, which form respectively the cutis-plate or dermatome, the muscle-plate or myotome, and the sclerotome (Fig. 94). The **cutis-plate** is placed on the lateral and dorsal aspect of the myocoel, and from it the true skin of the corresponding segment is derived; the **muscle-plate** is situated on the medial side of the cutis-plate and furnishes the muscles of the segment. The cells of the **sclerotome** are largely derived from those forming the core of the myocoel, and lie next the notochord. Fusion of the individual sclerotomes in an antero-posterior direction soon takes place, and thus a continuous strand of cells, the **sclerotogenous layer**, is formed along the ventro-lateral aspects of the neural tube. The cells of this layer proliferate rapidly, and extending medialward surround the notochord; at the same time they grow backward on the lateral aspects of the neural tube and eventually surround it, and thus the notochord and neural tube are enveloped

<sup>1</sup> In the amphioxus the notochord persists and forms the only representative of a skeleton in that animal.

by a continuous sheath of mesoderm, which is termed the **membranous vertebral column**. In this mesoderm the original segments are still distinguishable, but each is now differentiated into two portions, an anterior, consisting of loosely arranged cells, and a posterior, of more condensed tissue (Fig. 95, *A* and *B*). Between the two portions the rudiment of the intervertebral fibrocartilage is laid down (Fig. 95, *C*). Cells from the posterior mass grow into the intervals between the myotomes (Fig. 95, *B* and *C*) of the corresponding and succeeding segments, and extend both dorsally and ventrally; the dorsal extensions surround the neural tube and represent the future vertebral arch, while the ventral extend into the body-wall as the costal processes. The hinder part of the posterior mass joins the anterior mass of the succeeding segment to form the vertebral body. Each vertebral body is therefore a composite of two segments, being formed from the posterior portion of one segment and the anterior part of that immediately behind it. The vertebral




FIG. 94.—Transverse section of a human embryo of the third week to show the differentiation of the primitive segment. (Kollmann.) *ao.* Aorta. *m.p.* Muscle-plate. *n.c.* Neural canal. *sc.* Sclerotome. *s.p.* cutis-plate.




FIG. 95.—Scheme showing the manner in which each vertebral centrum is developed from portions of two adjacent segments.

and costal arches are derivatives of the posterior part of the segment in front of the intersegmental septum with which they are associated.

This stage is succeeded by that of the **cartilaginous vertebral column**. In the fourth week two cartilaginous centres make their appearance, one on either side of the notochord; these extend around the notochord and form the body of the cartilaginous vertebra. A second pair of cartilaginous foci appear in the lateral parts of the vertebral bow, and grow backward on either side of the neural tube to form the cartilaginous vertebral arch, and a separate cartilaginous centre appears for each costal process. By the eighth week the cartilaginous arch has fused with the body, and in the fourth month the two halves of the arch are joined on the dorsal aspect of the neural tube. The spinous process is developed from the junction of the two halves of the vertebral arch. The transverse process grows out from the vertebral arch behind the costal process.

In the upper cervical vertebræ a band of mesodermal tissue connects the ends of the vertebral arches across the ventral surfaces of the intervertebral fibrocartilages. This is termed the **hypochordal bar** or **brace**; in all except the first it is transitory and disappears by fusing with the fibrocartilages. In the atlas, however, the entire bow persists and undergoes chondrification; it develops into the anterior arch of the bone, while the cartilage representing the body of the atlas forms the dens or odontoid process which fuses with the body of the second cervical vertebra.




FIG. 96.—Sagittal section through an intervertebral fibrocartilage and adjacent parts of two vertebræ of an advanced sheep's embryo. (Kölliker.)

The portions of the notochord which are surrounded by the bodies of the vertebræ atrophy, and ultimately disappear, while those which lie in the centres of the intervertebral fibrocartilages undergo enlargement, and persist throughout life as the central **nucleus pulposus** of the fibrocartilages (Fig. 96).

**The Ribs.**—The ribs are formed from the ventral or costal processes of the primitive vertebral bows, the processes extending between the muscle-plates. In the *thoracic region* of the vertebral column the costal processes grow lateralward to form a series of arches, the **primitive costal arches**. As already described, the transverse process grows out behind the vertebral end of each arch. It is at first connected to the costal process by continuous mesoderm, but this becomes differentiated later to form the costotransverse ligament; between the costal process and the tip of the transverse process the costotransverse joint is formed by absorption. The costal process becomes separated from the vertebral bow by the development of the costocentral joint. In the *cervical vertebræ* (Fig. 97) the transverse process forms the posterior boundary of the foramen transversarium, while the costal process corresponding to the head and neck of the rib fuses with the

body of the vertebra, and forms the antero-lateral boundary of the foramen. The distal portions of the primitive costal arches remain undeveloped; occasionally the arch of the seventh cervical vertebra undergoes greater development, and by the formation of costovertebral joints is separated off as a rib. In the *lumbar region* the distal portions of the primitive costal arches fail; the proximal portions fuse with the transverse processes to form the transverse processes of descriptive anatomy. Occasionally a movable rib is developed in connection with the first lumbar vertebra. In the *sacral region* costal processes are developed only in connection with the upper three, or it may be four, vertebræ; the processes of adjacent segments fuse with one another to form the lateral parts of the sacrum. The *coccygeal vertebræ* are devoid of costal processes.




FIG. 97.—Diagrams showing the portions of the adult vertebræ derived respectively from the bodies, vertebral arches, and costal processes of the embryonic vertebræ. The bodies are represented in yellow, the vertebral arches in red, and the costal processes in blue.

**The Sternum.**—The ventral ends of the ribs become united to one another by a longitudinal bar termed the **sternal plate**, and opposite the first seven pairs of ribs these sternal plates fuse in the middle line to form the manubrium and body of the sternum. The xiphoid process is formed by a backward extension of the sternal plates.

**The Skull.**—Up to a certain stage the development of the skull corresponds with that of the vertebral column; but it is modified later in association with the expansion of the brain-vesicles, the formation of the organs of smell, sight, and hearing, and the development of the mouth and pharynx.

The notochord extends as far forward as the anterior end of the mid-brain, and becomes partly surrounded by mesoderm (Fig. 98). The posterior part of this mesodermal investment corresponds with the basilar part of the occipital bone, and shows a subdivision into four segments, which are separated by the roots of the hypoglossal nerve. The mesoderm then extends over the brain-vesicles, and thus the




FIG. 98.—Sagittal section of cephalic end of notochord. (Keibel.)

entire brain is enclosed by a mesodermal investment, which is termed the **membranous cranium**. From the inner layer of this the bones of the skull and the membranes of the brain are developed; from the outer layer the muscles, bloodvessels, true skin, and subcutaneous tissues of the scalp. In the shark and dog-fish this membranous cranium undergoes complete chondrification, and forms the cartilaginous skull or **chondrocranium** of these animals. In mammals, on the other hand, the process of chondrification is limited to the base of the skull—the roof and sides being covered in by membrane. Thus the bones of the base of the skull are preceded by cartilage, those of the roof and sides by membrane. The posterior part of the base of the skull is developed around the notochord, and exhibits a segmented

condition analogous to that of the vertebral column, while the anterior part arises in front of the notochord and shows no regular segmentation. The base of the skull may therefore be divided into (a) a **chordal** or **vertebral**, and (b) a **prechordal** or **prevertebral** portion.




FIG. 99.—Diagrams of the cartilaginous cranium. (Wiedersheim.)

In the lower vertebrates two pairs of cartilages are developed, viz., a pair of parachordal cartilages, one on either side of the notochord; and a pair of prechordal cartilages, the *trabeculae cranii*, in front of the notochord (Fig. 99). The **parachordal cartilages** (Fig. 99) unite to form a basilar plate, from which the cartilaginous part of the occipital bone and the basi-sphenoid are developed. On the lateral aspects of the parachordal cartilages the auditory vesicles are situated,



and the mesoderm enclosing them is soon converted into cartilage, forming the **cartilaginous ear-capsules**. These cartilaginous ear-capsules, which are of an oval shape, fuse with the sides of the basilar plate, and from them arise the petrous and mastoid portions of the temporal bones. The **trabeculae cranii** (Fig. 99) are two curved bars of cartilage which embrace the hypophysis cerebri; their posterior ends soon unite with the basilar plate, while their anterior ends join to form the **ethmoidal plate**, which extends forward between the fore-brain and the olfactory pits. Later the trabeculae meet and fuse below the hypophysis, forming the floor




FIG. 100.—Model of the chondrocranium of a human embryo, 8 cm. long. (Hertwig. The membrane bones are not represented.

of the fossa hypophyseos and so cutting off the anterior lobe of the hypophysis from the stomodeum. The median part of the ethmoidal plate forms the bony and cartilaginous parts of the nasal septum. From the lateral margins of the trabeculae cranii three processes grow out on either side. The anterior forms the ethmoidal labyrinth and the lateral and alar cartilages of the nose; the middle gives rise to the small wing of the sphenoid, while from the posterior the great wing and lateral pterygoid plate of the sphenoid are developed (Figs. 100, 101). The bones of the vault are of membranous formation, and are termed **dermal** or **covering bones**. They are partly developed from the mesoderm of the membranous

cranium, and partly from that which lies outside the entoderm of the fore-gut. They comprise the upper part of the occipital squama (interparietal), the squamæ and tympanic parts of the temporals, the parietals, the frontal, the vomer, the medial pterygoid plates, and the bones of the face. Some of them remain distinct throughout life, *e. g.*, parietal and frontal, while others join with the bones of the chondrocranium, *e. g.*, interparietal, squamæ of temporals, and medial pterygoid plates.

Recent observations have shown that, in mammals, the basi-cranial cartilage, both in the chordal and prechordal regions of the base of the skull, is developed as a single plate which extends from behind forward. In man, however, its posterior part shows an indication of being developed from two chondrifying centres which fuse rapidly in front and below. The anterior and posterior thirds of the cartilage surround the notochord, but its middle third lies on the dorsal aspect of the notochord, which in this region is placed between the cartilage and the wall of the pharynx.




FIG. 101.—The same model as shown in Fig. 100 from the left side. Certain of the membrane bones of the right side are represented in yellow.

**The Branchial or Visceral Arches and Pharyngeal Pouches.**—In the lateral walls of the anterior part of the fore-gut five *pharyngeal pouches* appear (Fig. 104); each of the upper four pouches is prolonged into a dorsal and a ventral diverticulum. Over these pouches corresponding indentations of the ectoderm occur, forming what are known as the **branchial or outer pharyngeal grooves**. The intervening mesoderm is pressed aside and the ectoderm comes for a time into contact with the entodermal lining of the fore-gut, and the two layers unite along the floors of the grooves to form thin **closing membranes** between the fore-gut and the exterior. Later the mesoderm again penetrates between the entoderm and the ectoderm. In gill-bearing animals the closing membranes disappear, and the grooves become complete clefts, the **gill-clefts**, opening from the pharynx on to the exterior; perforation, however, does not occur in birds or mammals. The grooves separate a series of rounded bars or arches, the **branchial or visceral arches**, in which thickening of the mesoderm takes place (Figs. 102 and 103). The dorsal ends of these arches are attached to the sides of the head, while the ventral extremities ultimately meet in the middle line of the neck. In all, six arches make their appearance,



but of these only the first four are visible externally. The first arch is named the mandibular, and the second the hyoid; the others have no distinctive names. In each arch a cartilaginous bar, consisting of right and left halves, is developed, and with each of these there is one of the primitive aortic arches.




FIG. 102.—Embryo between eighteen and twenty-one days. (His.)




FIG. 103.—Head end of human embryo, about the end of the fourth week. (From model by Peter.)

The **mandibular arch** lies between the first branchial groove and the stomodeum; from it are developed the lower lip, the mandible, the muscles of mastication, and the anterior part of the tongue. Its cartilaginous bar is formed by what are known as **Meckel's cartilages** (right and left) (Fig. 105). The dorsal ends of these cartilages are connected with the ear-capsules and are ossified to form two of the bones of the middle ear, the malleus and incus; the ventral ends meet each other in the region of the symphysis menti, and are usually regarded as undergoing ossification to form that portion of the mandible which contains the incisor teeth. The intervening part of the cartilage disappears; the portion immediately adjacent to the malleus and incus is replaced by fibrous membrane, which constitutes the spheno-mandibular ligament, while from the connective tissue covering the remainder of the cartilage the greater part of the mandible is ossified. From the dorsal ends of the mandibular arch a triangular process, the **maxillary process**, grows forward on either side and forms the cheek and lateral part of the upper lip. The **second or hyoid arch** assists in forming the side and front of the neck. From its cartilage are developed the styloid process, stylohyoid ligament, and lesser cornu of the hyoid bone. The cartilage of the **third arch** gives origin to the greater cornu of the hyoid bone. The ventral ends of the second and third arches unite with those of the opposite side, and form a transverse band, from which the body of




FIG. 104.—Floor of pharynx of embryo shown in Fig. 103.

the hyoid bone and the posterior part of the tongue are developed. The ventral portions of the cartilages of the **fourth** and **fifth** arches unite to form the thyroid cartilage; from the cartilages of the **sixth** arch the cricoid and arytenoid cartilages and the cartilages of the trachea are developed. The mandibular and hyoid arches grow more rapidly than those behind them, with the result that the latter




FIG. 105.—Head and neck of a human embryo eighteen weeks old, with Meckel's cartilage and hyoid bar exposed. (After Kölliker.)

become, to a certain extent, telescoped within the former, and a deep depression, the **sinus cervicalis**, is formed on either side of the neck. This sinus is bounded in front by the hyoid arch, and behind by the thoracic wall; it is ultimately obliterated by the fusion of its walls.




FIG. 106.—Under surface of the head of a human embryo about twenty-nine days old. (After His.)

From the first branchial groove the concha auriculæ and external acoustic meatus are developed, while around the groove there appear, on the mandibular and hyoid arches, a number of swellings from which the auricula or pinna is formed. The first pharyngeal pouch is prolonged dorsally to form the auditory tube and the tympanic cavity; the closing membrane between the mandibular and hyoid arches

is invaded by mesoderm, and forms the tympanic membrane. No traces of the second, third, and fourth branchial grooves persist. The inner part of the second pharyngeal pouch is named the *sinus tonsillaris*; in it the tonsil is developed, above which a trace of the sinus persists as the supratonsillar fossa. The fossa of Rosenmüller or lateral recess of the pharynx is by some regarded as a persistent part of the second pharyngeal pouch, but it is probably developed as a secondary formation. From the third pharyngeal pouch the thymus arises as an entodermal diverticulum on either side, and from the fourth pouches small diverticula project and become incorporated with the thymus, but in man these diverticula probably never form true thymus tissue. The parathyroids also arise as diverticula from the third and fourth pouches. From the fifth pouches the ultimobranchial bodies originate and are enveloped by the lateral prolongations of the median thyroid rudiment; they do not, however, form true thyroid tissue, nor are any traces of them found in the human adult.




FIG. 107.—Head end of human embryo of about thirty to thirty-one days. (From model by Peter.)




FIG. 108.—Same embryo as shown in Fig. 107, with front wall of pharynx removed.

**The Nose and Face.**—During the third week two areas of thickened ectoderm, the **olfactory areas**, appear immediately under the fore-brain in the anterior wall of the stomodeum, one on either side of a region termed the **fronto-nasal process** (Fig. 106). By the upgrowth of the surrounding parts these areas are converted into pits, the **olfactory pits**, which indent the fronto-nasal process and divide it into a **medial** and two **lateral nasal processes** (Fig. 107). The rounded lateral angles of the medial process constitute the **globular processes** of His. The olfactory pits form the rudiments of the nasal cavities, and from their ectodermal lining the epithelium of the nasal cavities, with the exception of that of the inferior meatuses, is derived. The globular processes are prolonged backward as plates, termed the **nasal laminae**: these laminae are at first some distance apart, but, gradually approaching, they ultimately fuse and form the nasal septum; the processes themselves meet in the middle line, and form the premaxillae and the philtrum or central part of the upper lip (Fig. 110). The depressed part of the medial nasal process between the globular processes forms the lower part of the nasal septum or **columella**; while above this is seen a prominent angle, which becomes the future

apex (Figs. 107, 108), and still higher a flat area, the future bridge, of the nose. The lateral nasal processes form the alæ of the nose.

Continuous with the dorsal end of the mandibular arch, and growing forward from its cephalic border, is a triangular process, the **maxillary process**, the ventral extremity of which is separated from the mandibular arch by a > shaped notch (Fig. 106). The maxillary process forms the lateral wall and floor of the orbit, and in it are ossified the zygomatic bone and the greater part of the maxilla; it meets with the lateral nasal process, from which, however, it is separated for a time by a groove, the **naso-optic furrow**, that extend from the furrow encircling the eyeball to the olfactory pit. The maxillary processes ultimately fuse with the lateral nasal and globular processes, and form the lateral parts of the upper lip and the posterior boundaries of the nares (Figs. 109, 110). From the third to the fifth month the nares are filled by masses of epithelium, on the breaking down and disappearance of which the permanent openings are produced. The maxillary process also gives rise to the lower portion of the lateral wall of the nasal cavity.



FIG. 109.—Head of a human embryo of about eight weeks, in which the nose and mouth are formed. (His.)




FIG. 110.—Diagram showing the regions of the adult face and neck related to the fronto-nasal process and the branchial arches.

The roof of the nose and the remaining parts of the lateral wall, viz., the ethmoidal labyrinth, the inferior nasal concha, the lateral cartilage, and the lateral crus of the alar cartilage, are developed in the lateral nasal process. By the fusion of the maxillary and nasal processes in the roof of the stomodeum the **primitive palate** (Fig. 111) is formed, and the olfactory pits extend backward above it. The posterior end of each pit is closed by an epithelial membrane, the **bucconasal membrane**, formed by the apposition of the nasal and stomodeal epithelium. By the rupture of these membranes the **primitive choanæ** or openings between the olfactory pits and the stomodeum are established. The floor of the nasal cavity is completed by the development of a pair of shelf-like **palatine processes** which extend medialward from the maxillary processes (Figs. 112 and 113); these coalesce with each other in the middle line, and constitute the entire palate, except a small part in front which is formed by the premaxillary bones. Two apertures persist for a time between the palatine processes and the premaxillæ and represent the permanent channels which in the lower animals connect the nose and mouth. The union of the parts which form the palate commences in front, the premaxillary and palatine processes joining in the eighth week, while the region of the future hard palate is completed by the ninth, and that of the soft palate by the eleventh week. By

the completion of the palate the **permanent choanæ** are formed and are situated a considerable distance behind the primitive choanæ. The deformity known as cleft palate results from a non-union of the palatine processes, and that of hare-lip through a non-union of the maxillary and globular processes (see page 299). The nasal cavity becomes divided by a vertical septum, which extends downward and backward from the medial nasal process and nasal laminae, and unites below with the palatine processes. Into this septum a plate of cartilage extends from




FIG. 111.—Primitive palate of a human embryo of thirty-seven to thirty-eight days. (From model by Peter.)  
On the left side the lateral wall of the nasal cavity has been removed.

the under aspect of the ethmoid plate of the chondrocranium. The anterior part of this cartilaginous plate persists as the septal cartilage of the nose and the medial crus of the alar cartilage, but the posterior and upper parts are replaced by the vomer and perpendicular plate of the ethmoid. On either side of the nasal septum, at its lower and anterior part, the ectoderm is invaginated to form a blind pouch or diverticulum, which extends backward and upward into the nasal septum and




FIG. 112 —The roof of the mouth of a human embryo, aged about two and a half months, showing the mode of formation of the palate. (His.)

is supported by a curved plate of cartilage. These pouches form the rudiments of the **vomero-nasal organs** of Jacobson, which open below, close to the junction of the premaxillary and maxillary bones.

**The Limbs.**—The limbs begin to make their appearance in the third week as small elevations or buds at the side of the trunk (Fig. 114). Prolongations from the muscle- and cutis-plates of several primitive segments extend into each bud, and carry with them the anterior divisions of the corresponding spinal nerves.



The nerves supplying the limbs indicate the number of primitive segments which contribute to their formation—the upper limb being derived from seven, viz., fourth cervical to second thoracic inclusive, and the lower limb from ten, viz., twelfth thoracic to fourth sacral inclusive. The axial part of the mesoderm of the limb-bud becomes condensed and converted into its cartilaginous skeleton, and by the ossification of this the bones of the limbs are formed. By the sixth week the three chief divisions of the limbs are marked off by furrows—the upper into arm, forearm, and hand; the lower into thigh, leg, and foot (Fig. 115). The limbs are at first directed backward nearly parallel to the long axis of the trunk, and each presents two surfaces and two borders. Of the surfaces, one—the future *flexor* surface of the limb—is directed ventrally; the other, the *extensor* surface, dorsally; one border, the *preaxial*, looks forward toward the cephalic end of the embryo, and the other, the *postaxial*, backward toward the caudal end. The lateral epicondyle of the humerus, the radius, and the thumb lie along the preaxial border




FIG. 113.—Frontal section of nasal cavities of a human embryo 28 mm. long. (Kollmann.)

of the upper limb; and the medial epicondyle of the femur, the tibia, and the great toe along the corresponding border of the lower limb. The preaxial part is derived from the anterior segments, the postaxial from the posterior segments of the limb-bud; and this explains, to a large extent, the innervation of the adult limb, the nerves of the more anterior segments being distributed along the preaxial (radial or tibial), and those of the more posterior along the postaxial (ulnar or fibular) border of the limb. The limbs next undergo a rotation or torsion through an angle of  $90^\circ$  around their long axes the rotation being effected almost entirely at the limb girdles. In the upper limb the rotation is outward and forward; in the lower limb, inward and backward. As a consequence of this rotation the preaxial (radial) border of the fore-limb is directed lateralward, and the preaxial (tibial) border of the hind-limb is directed medialward; thus the flexor surface of the fore-limb is turned forward, and that of the hind-limb backward.

## DEVELOPMENT OF THE JOINTS.

The mesoderm from which the different parts of the skeleton are formed at first shows no differentiation into masses corresponding with the individual bones. Thus continuous cores of mesoderm form the axes of the limb-buds and a continuous column of mesoderm the future vertebral column. The first indications of the bones and joints are circumscribed condensations of the mesoderm; these condensed parts become chondrified and finally ossified to form the bones of the skeleton. The intervening non-condensed portions consist at first of undifferentiated mesoderm, which may develop in one of three directions. It may be converted into fibrous tissue as in the case of the skull bones, a synarthrodial joint being the result, or it may become partly cartilaginous, in which case an amphiarthrodial joint is formed. Again, it may become looser in texture and a cavity ultimately appear in its midst; the cells lining the sides of this cavity form a synovial membrane and thus a diarthrodial joint is developed.




FIG. 114.—Human embryo from thirty-one to thirty-four days. (His.)




FIG. 115.—Embryo of about six weeks. (His.)

The tissue surrounding the original mesodermal core forms fibrous sheaths for the developing bones, *i. e.*, periosteum and perichondrium, which are continued between the ends of the bones over the synovial membrane as the capsules of the joints. These capsules are not of uniform thickness, so that in them may be recognized especially strengthened band which are described as ligaments. This, however, is not the only method of formation of ligaments. In some cases by modification of, or derivations from, the tendons surrounding the joint, additional ligamentous bands are provided to further strengthen the articulations.

In several of the movable joints the mesoderm which originally existed between the ends of the bones does not become completely absorbed—a portion of it persists and forms an articular disk. These disks may be intimately associated in their development with the muscles surrounding the joint, *e. g.*, the menisci of the knee-joint, or with cartilaginous elements, representatives of skeletal structures, which are vestigial in human anatomy, *e. g.*, the articular disk of the sterno-clavicular joint.

### DEVELOPMENT OF THE MUSCLES.

The voluntary muscles are developed from the myotomes of the primitive segments. Portions of the myotomes retain their position on the sides of the neural tube, where they may remain distinct from each other and form the short muscles of the vertebral column, or fuse with corresponding portions of neighboring myotomes to form the Sacrospinales and their continuations. Other portions of the myotomes extend into the trunk wall, where again they may retain their segmental condition, as in the Intercostales, or may fuse with adjacent segments to form the flat muscles of the abdominal wall. Finally, portions of the myotomes wander into the limb-buds and there undergo fusions and alterations in form to produce the limb muscles. The original segmental character of the limb muscles is therefore lost, but their segmental nerve supplies are retained. Some of the limb muscles expand and migrate secondarily toward the mid-dorsal line, *e. g.*, Trapezius and Latissimus dorsi, or toward the mid-ventral line, *e. g.*, Pectoralis major. Again, muscles may migrate in a cephalic direction, *e. g.*, the facial muscles which are derived from the hyoid arch, or in a caudal direction, *e. g.*, the Serratus anterior. In all cases the muscles carry with them the segmental nerves of the myotomes from which they were originally derived; two examples of this will suffice, *viz.*, the Diaphragma, which is derived from the third and fourth and the Serratus anterior, from the fifth, sixth, and seventh cervical segments as is indicated by their nerves of supply. In man and the higher vertebrates many of the derivatives of the myotomes degenerate and are converted into aponeuroses, *e. g.*, galea aponeurotica, and the aponeuroses of the abdominal muscles, or ligaments, *e. g.*, sacrotuberous ligament and fibular collateral ligament of the knee.

The involuntary muscles are derived from the splanchnopleure mesoderm.

### DEVELOPMENT OF THE SKIN, GLANDS, AND SOFT PARTS.

The epidermis and its appendages, consisting of the hairs, nails, sebaceous and sweat glands, are developed from the ectoderm, while the corium or true skin is of mesodermal origin, being derived from the cutis-plates of the primitive segments. About the fifth week the epidermis consists of two layers of cells, the deeper one corresponding to the rete mucosum. The subcutaneous fat appears about the fourth month, and the papillæ of the true skin about the sixth. A considerable desquamation of epidermis takes place during fetal life, and this desquamated epidermis, mixed with sebaceous secretion, constitutes the *vernix caseosa*, with which the skin is smeared during the last three months of fetal life. The nails are formed at the third month, and begin to project from the epidermis about the sixth. The hairs appear between the third and fourth months in the form of solid downgrowths of the deeper layer of the epidermis, the growing extremities of which become inverted by papillary projections from the corium. The central cells of the solid downgrowths undergo alteration to form the hair, while the peripheral cells are retained to form the lining cells of the hair-follicle. About the fifth month the fetal hairs (*lanugo*) appear, first on the head and then on the other parts; they drop off after birth, and give place to the permanent hairs. The cellular structures of the sudoriferous and sebaceous glands are formed from the ectoderm, while the connective tissue and bloodvessels are derived from the mesoderm.

The *mamma* is also formed partly from mesoderm and partly from ectoderm—its bloodvessels and connective tissue being derived from the former, its cellular elements from the latter. Its first rudiment is seen about the third month, in the



form of a number of small inward projections of the ectoderm, which invade the mesoderm; from these, secondary tracts of cellular elements radiate and subsequently give rise to the epithelium of the glandular follicles and ducts. The development of the follicles, however, remains imperfect, except in the parous female.

### DEVELOPMENT OF THE NERVOUS SYSTEM AND SENSE ORGANS.

The entire nervous system is of ectodermal origin, and its first rudiment is seen in the neural groove which extends along the dorsal aspect of the embryo (Fig. 75). By the elevation and ultimate fusion of the neural folds, the groove is converted into the neural tube (Fig. 77). The anterior end of the neural tube becomes expanded to form the three primary brain-vesicles; the cavity of the tube is subsequently modified to form the ventricular cavities of the brain, and the central canal of the medulla spinalis; from the wall the nervous elements and the neuroglia of the brain and medulla spinalis are developed.




FIG. 116.—Section of medulla spinalis of a four weeks' embryo. (Hia.)

**The Medulla Spinalis.**—At first the wall of the neural tube is composed of a single layer of columnar ectodermal cells. Soon the side-walls become thickened, while the dorsal and ventral parts remain thin, and are named the **roof- and floor-plates** (Figs. 116, 118). A transverse section of the tube at this stage presents an oval outline, while its lumen has the appearance of a slit. The cells which constitute the wall of the tube proliferate rapidly, lose their cell-boundaries and form a syncytium. This syncytium consists at first of dense protoplasm with closely packed nuclei, but later it opens out and forms a looser meshwork with the cellular strands arranged in a radiating manner from the central canal. Three layers may now be defined—an internal or ependymal, an intermediate or mantle, and an external or marginal. The **ependymal layer** is ultimately converted into the ependyma of the central canal; the processes of its cells pass outward toward the periphery of the medulla spinalis. The **marginal layer** is devoid of nuclei, and later forms the supporting framework for the white funiculi of the medulla spinalis. The **mantle layer** represents the whole of the future gray columns of the medulla

spinalis; in it the cells are differentiated into two sets, viz., (a) **spongioblasts** or **young neuroglia cells**, and (b) **germinal cells**, which are the parents of the **neuroblasts** or **young nerve cells** (Fig. 117). The spongioblasts are at first connected to one another by filaments of the syncytium; in these, fibrils are developed, so that as the




FIG. 117.—Transverse section of the medulla spinalis of a human embryo at the beginning of the fourth week. (After His.) The left edge of the figure corresponds to the lining of the central canal.

neuroglial cells become defined they exhibit their characteristic mature appearance with multiple processes proceeding from each cell. The germinal cells are large, round or oval, and first make their appearance between the ependymal cells on the sides of the central canal. They increase rapidly in number, so that by the




FIG. 118.—Transverse sections through the medullae spinales of human embryos. A. Aged about four and a half weeks. B. Aged about three months. (His.)

fourth week they form an almost continuous layer on each side of the tube. No germinal cells are found in the roof- or floor-plates; the roof-plate retains, in certain regions of the brain, its epithelial character; elsewhere, its cells become spongioblasts. By subdivision the germinal cells give rise to the neuroblasts or young

nerve cells, which migrate outward from the sides of the central canal into the mantle layer and neural crest, and at the same time become pear-shaped; the tapering part of the cell undergoes still further elongation, and forms the axis-cylinder of the cell.

The lateral walls of the medulla spinalis continue to increase in thickness, and the canal widens out near its dorsal extremity, and assumes a somewhat lozenge-shaped appearance. The widest part of the canal serves to subdivide the lateral wall of the neural tube into a **dorsal** or **alar**, and a **ventral** or **basal lamina** (Fig. 118), a subdivision which extends forward into the brain. At a later stage the ventral part of the canal widens out, while the dorsal part is first reduced to a mere slit and then becomes obliterated by the approximation and fusion of its walls; the ventral part of the canal persists and forms the central canal of the adult medulla spinalis. The caudal end of the canal exhibits a conical expansion which is known as the **terminal ventricle**.

The ventral part of the mantle layer becomes thickened, and on cross-section appears as a triangular patch between the marginal and ependymal layers. This thickening is the rudiment of the anterior column of gray substance, and contains many neuroblasts, the axis-cylinders of which pass out through the marginal layer and form the anterior roots of the spinal nerves (Figs. 116, 118). The thickening of the mantle layer gradually extends in a dorsal direction, and forms the posterior column of gray substance. The axons of many of the neuroblasts in the alar lamina run forward, and cross in the floor-plate to the opposite side of the medulla spinalis; these form the rudiment of the anterior white commissure.

About the end of the fourth week nerve fibres begin to appear in the marginal layer. The first to develop are the short intersegmental fibres from the neuroblasts in the mantle zone, and the fibres of the dorsal nerve roots which grow into the medulla spinalis from the cells of the spinal ganglia. By the sixth week these dorsal root fibres form a well-defined **oval bundle** in the peripheral part of the alar lamina; this bundle gradually increases in size, and spreading toward the middle line forms the rudiment of the posterior funiculus. The long intersegmental fibres begin to appear about the third month and the cerebrospinal fibres about the fifth month. All nerve fibres are at first destitute of medullary sheaths. Different groups of fibres receive their sheaths at different times—the dorsal and ventral nerve roots about the fifth month, the cerebrospinal fibres after the ninth month.

By the growth of the anterior columns of gray substance, and by the increase in size of the anterior funiculi, a furrow is formed between the lateral halves of the cord anteriorly; this gradually deepens to form the anterior median fissure. The mode of formation of the posterior septum is somewhat uncertain. Many believe that it is produced by the growing together of the walls of the posterior part of the central canal and by the development from its ependymal cells of a septum of fibrillated tissue which separates the future funiculi graciles.

Up to the third month of fetal life the medulla spinalis occupies the entire length of the vertebral canal, and the spinal nerves pass outward at right angles to the medulla spinalis. From this time onward, the vertebral column grows more rapidly than the medulla spinalis, and the latter, being fixed above through its continuity with the brain, gradually assumes a higher position within the canal. By the sixth month its lower end reaches only as far as the upper end of the sacrum; at birth it is on a level with the third lumbar vertebra, and in the adult with the lower border of the first or upper border of the second lumbar vertebra. A delicate filament, the **filum terminale**, extends from its lower end as far as the coccyx.

**The Spinal Nerves.**—Each spinal nerve is attached to the medulla spinalis by an anterior or ventral and a posterior or dorsal root.

The fibres of the anterior roots are formed by the axons of the neuroblasts which lie in the ventral part of the mantle layer; these axons grow out through the

overlying marginal layer and become grouped to form the anterior nerve root (Fig. 117).

The fibres of the posterior roots are developed from the cells of the spinal ganglia. Before the neural groove is closed to form the neural tube a ridge of ectodermal cells, the **ganglion ridge** or **neural crest** (Fig. 119), appears along the prominent margin of each neural fold. When the folds meet in the middle line the two ganglion ridges fuse and form a wedge-shaped area along the line of closure of the tube. The cells of this area proliferate rapidly opposite the primitive segments and then migrate in a lateral and ventral direction to the sides of the neural tube, where they ultimately form a series of oval-shaped masses, the future spinal ganglia. These ganglia are arranged symmetrically on the two sides of the neural tube and, except in the region of the tail, are equal in number to the primitive segments. The cells of the ganglia, like the cells of the mantle layer, are of two kinds, viz., **spongioblasts** and **neuroblasts**. The spongioblasts develop into the neuroglial cells of the ganglia. The neuroblasts are at first round or oval in shape, but soon assume the form of spindles the extremities of which gradually elongate into central and

peripheral processes. The central processes grow medialward and, becoming connected with the neural tube, constitute the fibres of the posterior nerve roots, while the peripheral processes grow lateralward to mingle with the fibres of the anterior root in the spinal nerve. As development proceeds the original bipolar form of the cells changes; the two processes become approximated until they ultimately arise from a single stem in a T-shaped manner. Only in the ganglia of the acoustic nerve is the bipolar form retained. More recent observers hold, however, that the T-form is derived from the branching of a single process which grows out from the cell.

The anterior or ventral and the posterior or dorsal nerve roots join immediately beyond the spinal ganglion to form the **spinal nerve**, which then divides into anterior, posterior, and visceral divisions. The anterior and posterior divisions proceed directly to their areas of distribution without further association with ganglion cells (Fig. 120). The visceral divisions are distributed to the thoracic, abdominal, and pelvic viscera, to reach which they pass through the sympathetic trunk, and many of the fibres form arborizations around the ganglion cells of this trunk. Visceral branches are not given off from all the spinal nerves; they form two groups, viz., (a) **thoracico-lumbar**, from the first or second thoracic, to the second or third lumbar nerves; and (b) **pelvic**, from the second and third, or third and fourth sacral nerves.

**The Brain.**—The brain is developed from the anterior end of the neural tube, which at an early period becomes expanded into three vesicles, the primary cerebral vesicles (Fig. 76). These are marked off from each other by intervening constrictions, and are named the **prosencephalon** or **fore-brain**, the **mesencephalon** or **mid-brain**, and the **rhombencephalon** or **hind-brain**—the last being continuous with the medulla spinalis. As the result of unequal growth of these different parts three flexures are formed and the embryonic brain becomes bent on itself




FIG. 119.—Two stages in the development of the neural crest in the human embryo. (Lenhossék.)

in a somewhat zigzag fashion; the two earliest flexures are concave ventrally and are associated with corresponding flexures of the whole head. The first flexure appears in the region of the mid-brain, and is named the **ventral cephalic flexure** (Fig. 125). By means of it the fore-brain is bent in a ventral direction around the anterior end of the notochord and fore-gut, with the result that the floor of the fore-brain comes to lie almost parallel with that of the hind-brain. This flexure causes the mid-brain to become, for a time, the most prominent part of




FIG. 120.—Reconstruction of peripheral nerves of a human embryo of 10.2 mm. (After His.) The abducent nerve is not labelled, but is seen passing forward to the eye under the mandibular and maxillary nerves.

the brain, since its dorsal surface corresponds with the convexity of the curve. The second bend appears at the junction of the hind-brain and medulla spinalis. This is termed the **cervical flexure** (Fig. 127), and increases from the third to the end of the fifth week, when the hind-brain forms nearly a right angle with the medulla spinalis; after the fifth week erection of the head takes place and the cervical flexure diminishes and disappears. The third bend is named the **pontine flexure** (Fig. 127), because it is found in the region of the future pons Varoli. It differs

from the other two in that (a) its convexity is forward, and (b) it does not affect the head. The lateral walls of the brain-tube, like those of the medulla spinalis, are divided by internal furrows into alar or dorsal and basal or ventral laminae (Fig. 121).




FIG. 121.—Diagram to illustrate the alar and basal laminae of brain vesicles. (His.)




FIG. 122.—Transverse section of medulla oblongata of human embryo.  $\times 32$ . (Kollmann.)

**The Rhombencephalon or Hind-brain.**—The cavity of the hind-brain becomes the fourth ventricle. At the time when the ventral cephalic flexure makes its appearance, the length of the hind-brain exceeds the combined lengths of the other two vesicles. Immediately behind the mid-brain it exhibits a marked constriction, the *isthmus rhombencephali* (Fig. 125, *Isthmus*), which is best seen when the brain is viewed from the dorsal aspect. From the isthmus the anterior medullary velum




FIG. 123.—Transverse section of medulla oblongata of human embryo. (After His.)

and the brachia conjunctiva of the cerebellum are formed. It is customary to divide the rest of the hind-brain into two parts, viz., an upper, called the **metencephalon**, and a lower, the **myelencephalon**. The cerebellum is developed by a thickening of the roof, and the pons by a thickening in the floor and lateral walls of the metencephalon. The floor and lateral walls of the myelencephalon are



thickened to form the medulla oblongata; its roof remains thin, and, retaining to a great extent its epithelial nature, is expanded in a lateral direction. Later, by the growth and backward extension of the cerebellum, the roof is folded inward toward the cavity of the fourth ventricle; it assists in completing the dorsal wall of this cavity, and is also invaginated to form the ependymal covering of its choroid plexuses. Above it is continuous with the posterior medullary velum; below, with the obex and ligulae.




FIG. 124.—Hind-brain of a human embryo of three months—viewed from behind and partly from left side. (From model by His.)




FIG. 125.—Exterior of brain of human embryo of four and a half weeks. (From model by His.)

The development of the **medulla oblongata** resembles that of the medulla spinalis, but at the same time exhibits one or two interesting modifications. On transverse section the myelencephalon at an early stage is seen to consist of two lateral walls, connected across the middle line by floor- and roof-plates (Figs. 122 and 123). Each lateral wall consists of an alar and a basal lamina, separated by an internal furrow, the remains of which are represented in the adult brain by the sulcus limitans on the rhomboid fossa. The contained cavity is more or less triangular in outline, the base being formed by the roof-plate, which is thin and greatly expanded transversely. Pear-shaped neuroblasts are developed in the alar and basal laminae, and their narrow stalks are elongated to form the axis-cylinders of the nerve fibres. Opposite the furrow or boundary between the alar and basal laminae a bundle of nerve fibres attaches itself to the outer surface of the alar lamina. This is named the **tractus solitarius** (Fig. 123), and is formed by the sensory fibres of the glossopharyngeal and vagus nerves. It is the homologue of the **oval bundle** seen in the medulla spinalis, and, like it, is developed by an ingrowth of fibres from the ganglia of the neural crest. At first it is applied to the outer surface of the alar lamina, but it soon becomes buried, owing to the growth over it of the neighboring parts. By the fifth week the dorsal part of the alar lamina bends in a lateral direction along its entire length, to form what is termed the **rhombic lip** (Figs. 123, 124). Within a few days this lip becomes applied to, and unites

with, the outer surface of the main part of the alar lamina, and so covers in the tractus solitarius and also the spinal root of the trigeminal nerve; the nodulus and flocculus of the cerebellum are developed from the rhombic lip.

Neuroblasts accumulate in the mantle layer; those in the basal lamina correspond with the cells in the anterior gray column of the medulla spinalis, and, like them, give origin to motor nerve fibres; in the medulla oblongata they are, however, arranged in groups or nuclei, instead of forming a continuous column. From the alar lamina and its rhombic lip, neuroblasts migrate into the basal lamina, and become aggregated to form the olivary nuclei, while many send their axis-cylinders through the floor-plate to the opposite side, and thus constitute the rudiment of the raphé of the medulla oblongata. By means of this thickening of the ventral portion, the motor nuclei are buried deeply in the interior, and, in the adult, are found close to the rhomboid fossa. This is still further accentuated: (a) by the




FIG. 126.—Brain of human embryo of four and a half weeks, showing interior of fore-brain. (From model by His.)

development of the pyramids, which are formed about the fourth month by the downward growth of the motor fibres from the cerebral cortex; and (b) by the fibres which pass to and from the cerebellum. On the rhomboid fossa a series of six temporary furrows appears; these are termed the **rhombic grooves**. They bear a definite relationship to certain of the cerebral nerves; thus, from before backward the first and second grooves overlie the nucleus of the trigeminal; the third, the nucleus of the facial; the fourth, that of the abducent; the fifth, that of the glossopharyngeal; and the sixth, that of the vagus.

The **pons** is developed from the ventro-lateral wall of the metencephalon by a process similar to that which has been described for the medulla oblongata.

The **cerebellum** is developed in the roof of the anterior part of the hind-brain (Figs. 124 to 129). The alar laminae of this region become thickened to form two

lateral plates which soon fuse in the middle line and produce a thick lamina which roofs in the upper part of the cavity of the hind-brain vesicle; this constitutes the rudiment of the cerebellum, the outer surface of which is originally smooth and convex. The fissures of the cerebellum appear first in the vermis and floccular region, and traces of them are found during the third month; the fissures on the cerebellar hemispheres do not appear until the fifth month. The primitive fissures are not developed in the order of their relative size in the adult—thus the horizontal sulcus in the fifth month is merely a shallow groove. The best marked of the early fissures are: (a) the **fissura prima** between the developing culmen and declive, and (b) the **fissura secunda** between the future pyramid and uvula. The flocculus and nodule are developed from the rhombic lip, and are therefore recognizable as separate portions before any of the other cerebellar lobules. The groove produced by the bending over of the rhombic lip is here known as the



**floccular fissure**; when the two lateral walls fuse, the right and left floccular fissures join in the middle line and their central part becomes the **post-nodular fissure**.

On the ventricular surface of the cerebellar lamina a transverse furrow, the **incisura fastigii**, appears, and deepens to form the tent-like recess of the roof of the fourth ventricle. The rudiment of the cerebellum at first projects in a dorsal direction; but, by the backward growth of the cerebrum, it is folded downward and somewhat flattened, and the thin roof-plate of the fourth ventricle, originally continuous with the posterior border of the cerebellum, is projected inward toward the cavity of the ventricle.

**The Mesencephalon or Mid-brain.**—The mid-brain (Figs. 125 to 129) exists for a time as a thin-walled cavity of some size, and is separated from the isthmus rhomencephali behind, and from the fore-brain in front, by slight constrictions. Its cavity becomes relatively reduced in diameter, and forms the cerebral aqueduct of the adult brain. Its basal laminæ increase in thickness to form the cerebral peduncles, which are at first of small size, but rapidly enlarge after the fourth month.




FIG. 127.—Exterior of brain of human embryo of five weeks. (From model by His.)

The neuroblasts of these laminæ are grouped in relation to the sides and floor of the cerebral aqueduct, and constitute the nuclei of the oculomotor and trochlear nerves, and of the mesencephalic root of the trigeminal nerve. By a similar thickening process its alar laminæ are developed into the quadrigeminal lamina. The dorsal part of the wall for a time undergoes expansion, and presents an internal median furrow and a corresponding external ridge; these, however, disappear, and the latter is replaced by a groove. Subsequently two oblique furrows extend medialward and backward, and the thickened lamina is thus subdivided into the superior and inferior colliculi.

**The Prosencephalon or Fore-brain.**—A transverse section of the early fore-brain shows the same parts as are displayed in similar sections of the medulla spinalis and medulla oblongata, viz., a pair of thick lateral walls connected by thin floor- and roof-plates. Moreover, each lateral wall exhibits a division into a dorsal or alar and a ventral or basal lamina separated internally by a furrow termed the **sulcus**

of **Monro**. This sulcus ends anteriorly at the medial end of the optic stalk, and in the adult brain is retained as a slight groove extending backward from the interventricular foramen to the cerebral aqueduct.

At a very early period—in some animals before the closure of the cranial part of the neural tube—two lateral diverticula, the **optic vesicles**, appear, one on either side of the fore-brain; for a time they communicate with the cavity of the fore-brain by relatively wide openings. The peripheral parts of the vesicles expand, while the proximal parts are reduced to tubular stalks, the **optic stalks**. The optic vesicle gives rise to the retina and the epithelium on the back of the ciliary body and iris; the optic stalk is invaded by nerve fibres to form the optic nerve. The fore-brain then grows forward, and from the alar laminae of this front portion the cerebral hemispheres originate as diverticula which rapidly expand to form two large pouches, one on either side. The cavities of these diverticula are the rudiments of the lateral ventricles; they communicate with the median part of the fore-brain cavity by relatively wide openings, which ultimately form the interventricular




FIG. 128.—Interior of brain of human embryo of five weeks. (From model by His.)

foramen. The median portion of the wall of the fore-brain vesicle consists of a thin lamina, the **lamina terminalis** (Figs. 129, 132), which stretches from the interventricular foramen to the recess at the base of the optic stalk. The anterior part of the fore-brain, including the rudiments of the cerebral hemispheres, is named the **telencephalon**, and its posterior portion is termed the **diencephalon**; both of these contribute to the formation of the third ventricle.

**The Diencephalon.**—From the alar lamina of the diencephalon, the thalamus, metathalamus, and epithalamus are developed. The **thalamus** (Figs. 125 to 129) arises as a thickening which involves the anterior two-thirds of the alar lamina. The two thalami are visible, for a time, on the surface of the brain, but are subsequently hidden by the cerebral hemispheres which grow backward over them. The thalami extend medialward and gradually narrow the cavity between them into a slit-like aperture which forms the greater part of the third ventricle; their medial surfaces ultimately adhere, in part, to each other, and the **intermediate**

mass of the ventricle is developed across the area of contact. The **metathalamus** comprises the geniculate bodies which originate as slight outward bulgings of the alar lamina. In the adult the lateral geniculate body appears as an eminence on the lateral part of the posterior end of the thalamus, while the medial is situated on the lateral aspect of the mesencephalon. The **epithalamus** includes the pineal body, the posterior commissure, and the trigonum habenulae. The pineal body arises as an upward evagination of the roof-plate immediately in front of the mid-brain; this evagination becomes solid with the exception of its proximal part, which persists as the recessus pinealis. In lizards the pineal evagination is elongated into a stalk, and its peripheral extremity is expanded into a vesicle, in which a rudimentary lens and retina are formed; the stalk becomes solid and nerve fibres make their appearance in it, so that in these animals the pineal body forms a rudimentary eye. The posterior commissure is formed by the ingrowth of fibres into the depression behind and below the pineal evagination, and the trigonum habenulae is developed in front of the pineal recess.




FIG. 129.—Median sagittal section of brain of human embryo of three months. (From model by His.)

From the basal laminæ of the diencephalon the **pars mamillaria hypothalami** is developed; this comprises the corpora mamillaria and the posterior part of the tuber cinereum. The corpora mamillaria arise as a single thickening, which becomes divided into two by a median furrow during the third month.

The roof-plate of the diencephalon, in front of the pineal body, remains thin and epithelial in character, and is subsequently invaginated by the choroid plexuses of the third ventricle.

**The Telencephalon.**—This consists of a median portion and two lateral diverticula. The median portion forms the anterior part of the cavity of the third ventricle, and is closed below and in front by the lamina terminalis. The lateral diverticula consist of outward pouchings of the alar laminæ; the cavities represent the lateral ventricles, and their walls become thickened to form the nervous

matter of the cerebral hemispheres. The roof-plate of the telencephalon remains thin, and is continuous in front with the lamina terminalis and behind with the roof-plate of the diencephalon. In the basal laminæ and floor-plate the **pars optica hypothalami** is developed; this comprises the anterior part of the tuber cinereum, the infundibulum and posterior lobe of the hypophysis, and the optic chiasma. The anterior part of the tuber cinereum is derived from the posterior part of the floor of the telencephalon; the infundibulum and posterior lobe of the hypophysis arise as a downward diverticulum from the floor. The most dependent part of the diverticulum becomes solid and forms the posterior lobe of the hypophysis; the anterior lobe of the hypophysis is developed from a diverticulum of the ectodermal lining of the stomodeum (page 166). The optic chiasma is formed by the meeting and partial decussation of the optic nerves, which subsequently grow backward as the optic tracts and end in the diencephalon.

The **cerebral hemispheres** arise as diverticula of the alar laminæ of the telencephalon (Figs. 125 to 129); they increase rapidly in size and ultimately overlap the structures developed from the mid- and hind-brains. This great expansion

of the hemispheres is a characteristic feature of the brains of mammals, and attains its maximum development in the brain of man. Elliott-Smith divides each cerebral hemisphere into three fundamental parts, viz., the **rhinencephalon**, the **corpus striatum**, and the **neopallium**.

The **rhinencephalon** (Fig. 130) represents the oldest part of the telencephalon, and forms almost the whole of the hemisphere in fishes, amphibians, and reptiles. In man it is feebly developed in comparison with the rest of the hemisphere, and comprises the following parts, viz., the olfactory lobe (con-




Fig. 130.—Inferior surface of brain of embryo at beginning of fourth month. (From Kollmann.)

sisting of the olfactory tract and bulb and the trigonum olfactorium), the anterior perforated substance, the septum pellucidum, the subcallosal, supracallosal, and dentate gyri, the fornix, the hippocampus, and the uncus. The rhinencephalon appears as a longitudinal elevation, with a corresponding internal furrow, on the under surface of the hemisphere close to the lamina terminalis; it is separated from the lateral surface of the hemisphere by a furrow, the **external rhinal fissure**, and is continuous behind with that part of the hemisphere, which will ultimately form the anterior end of the temporal lobe. The elevation becomes divided by a groove into an anterior and a posterior part. The anterior grows forward as a hollow stalk the lumen of which is continuous with the anterior part of the ventricular cavity. During the third month the stalk becomes solid and forms the rudiment of the olfactory bulb and tract; a strand of gelatinous tissue in the interior of the bulb indicates the position of the original cavity. From the posterior part the anterior perforated substance and the pyriform lobe are developed; at the beginning of the fourth month the latter forms a curved elevation continuous behind with the medial surface of the temporal lobe, and consisting, from before backward, of the **gyrus olfactorius lateralis**, **gyrus ambiens**, and **gyrus semilunaris**, parts which



in the adult brain are represented by the lateral root of the olfactory tract and the uncus. The position and connections of the remaining portions of the rhinencephalon are described with the anatomy of the brain.

The **corpus striatum** (Figs. 126 and 128) appears in the fourth week as a triangular thickening of the floor of the telencephalon between the optic recess and the interventricular foramen, and continuous behind with the thalamic part of the diencephalon. It increases in size, and by the second month is seen as a swelling in the floor of the future lateral ventricle; this swelling reaches as far as the posterior end of the primitive hemisphere, and when this part of the hemisphere grows backward and downward to form the temporal lobe, the posterior part of the corpus striatum is carried into the roof of the inferior horn of the ventricle, where it is seen as the tail of the caudate nucleus in the adult brain. During the fourth and fifth months the corpus striatum becomes incompletely subdivided by the fibres of the internal capsule into two masses, an inner, the **caudate nucleus**, and an outer, the **lentiform nucleus**. In front, the corpus striatum is continuous with the anterior perforated substance; laterally it is confluent for a time with that portion of the wall of the vesicle which is developed into the insula, but this continuity is subsequently interrupted by the fibres of the external capsule.




FIG. 131.—Diagrammatic coronal section of brain to show relations of neopallium. (After His.) Cs, Corpus striatum. Th, Thalamus.

The **neopallium** (Fig. 131) forms the remaining, and by far the greater, part of the cerebral hemisphere. It consists, at an early stage, of a relatively large, more or less hemispherical cavity—the primitive **lateral ventricle**—enclosed by a thin wall from which the cortex of the hemisphere is developed. The vesicle expands in all directions, but more especially upward and backward, so that by the third month the hemispheres cover the diencephalon, by the sixth they overlap the mid-brain, and by the eighth the hind-brain.

The median lamina uniting the two hemispheres does not share in their expansion, and thus the hemispheres are separated by a deep cleft, the forerunner of the longitudinal fissure, and this cleft is occupied by a septum of mesodermal tissue which constitutes the primitive **falx cerebri**. Coincidentally with the expansion

sion of the vesicle, its cavity is drawn out into three prolongations which represent the horns of the future lateral ventricle; the hinder end of the vesicle is carried downward and forward and forms the inferior horn; the posterior horn is produced somewhat later, in association with the backward growth of the occipital lobe of the hemisphere. The roof-plate of the primitive fore-brain remains thin and of an epithelial character; it is invaginated into the lateral ventricle along the medial wall of the hemisphere. This invagination constitutes the choroidal fissure, and extends from the interventricular foramen to the posterior end of the vesicle. Mesodermal tissue, continuous with that of the primitive falx cerebri, and carrying bloodvessels with it, spreads between the two layers of the invaginated fold and forms the rudiment of the tela choroidea; the margins of the tela become highly vascular and form the choroid plexuses which for some months almost completely fill the ventricular cavities; the tela at the same time invaginates the epithelial roof of the diencephalon to form the choroid plexuses of the third ventricle. By the downward and forward growth of the posterior end of the vesicle to form the temporal lobe the choroidal fissure finally reaches from the interventricular foramen to the extremity of the inferior horn of the ventricle.




FIG. 132.—Median sagittal section of brain of human embryo of four months. (Marchand.)

Parallel with but above and in front of the choroidal fissure the medial wall of the cerebral vesicle becomes folded outward and gives rise to the **hippocampal fissure** on the medial surface and to a corresponding elevation, the **hippocampus**, within the ventricular cavity. The gray or ganglionic covering of the wall of the vesicle ends at the inferior margin of the fissure is a thickened edge; beneath this the marginal or reticular layer (future white substance) is exposed and its lower thinned edge is continuous with the epithelial invagination covering the choroid plexus (Fig. 131). As a result of the later downward and forward growth of the temporal lobe the hippocampal fissure and the parts associated with it extend from the interventricular foramen to the end of the inferior horn of the ventricle. The thickened edge of gray substance becomes the gyrus dentatus, the fasciola cinerea and the supra- and subcallosal gyri, while the free edge of the white substance forms the fimbria hippocampi and the body and crus of the fornix. The corpus callosum is developed within the arch of the hippocampal fissure, and the upper part of the fissure forms, in the adult brain, the callosal fissure on the medial surface of the hemisphere.

**The Commissures** (Fig. 132).—The development of the posterior commissure has already been referred to (page 127). The great commissures of the hemispheres, viz., the **corpus callosum**, the **fornix**, and **anterior commissure**, arise from the lamina terminalis. About the fourth month a small thickening appears in this lamina, immediately in front of the interventricular foramen. The lower part of this thickening is soon constricted off, and fibres appear in it to form the anterior commissure. The upper part continues to grow with the hemispheres, and is invaded by two sets of fibres. Transverse fibres, extending between the hemispheres, pass into its dorsal part, which is now differentiated as the corpus callosum (in rare cases the corpus callosum is not developed). Into the ventral part longitudinal fibres from the hippocampus pass to the lamina terminalis, and through that structure to the corpora mamillaria; these fibres constitute the fornix. A small portion, lying antero-inferiorly between the corpus callosum and fornix, is not invaded by the commissural fibres; it remains thin, and later a cavity, the cavity of the septum pellucidum, forms in its interior.

**Fissures and Sulci**.—The outer surface of the cerebral hemisphere is at first smooth, but later it exhibits a number of elevations or convolutions, separated from each other by fissures and sulci, most of which make their appearance during the sixth or seventh months of fetal life. The term *fissure* is applied to such grooves as involve the entire thickness of the cerebral wall, and thus produce corresponding eminences in the ventricular cavity, while the *sulci* affect only the superficial part of the wall, and therefore leave no impressions in the ventricle. The fissures comprise the **choroidal** and **hippocampal** already described, and two others, viz., the **calcarine** and **collateral**, which produce the swellings known respectively as the **calcar avis** and the **collateral eminence** in the ventricular cavity. Of the sulci the following may be referred to, viz., the **central sulcus** (*fissure of Rolando*), which is developed in two parts; the **intraparietal sulcus** in four parts; and the **cingulate sulcus** in two or three parts. The **lateral cerebral** or **Sylvian fissure** differs from all the other fissures in its mode of development. It appears about the third month as a depression, the **Sylvian fossa**, on the lateral surface of the hemisphere (Fig. 133); this fossa corresponds with the position of the corpus striatum, and its floor is moulded to form the insula. The intimate connection which exists between the cortex of the insula and the subjacent corpus striatum prevents this part of the hemisphere wall from expanding at the same rate as the portions which surround it. The neighboring parts of the hemisphere therefore gradually grow over and cover in the insula, and constitute the temporal, parietal, frontal, and orbital opercula of the adult brain. The frontal and orbital opercula are the last to form, but by the end of the first year after birth the insula is completely submerged by the approximation of the opercula. The fissures separating the opposed margins of the opercula constitute the composite lateral cerebral fissure.

If a section across the wall of the hemisphere about the sixth week be examined microscopically it will be found to consist of a thin marginal or reticular layer, a thick endymal layer, and a thin intervening mantle layer. Neuroblasts from the




FIG. 133.—Outer surface of cerebral hemisphere of human embryo of about five months.

ependymal and mantle layers migrate into the deep part of the marginal layer and form the cells of the cerebral cortex. The nerve fibres which form the underlying white substance of the hemispheres consist at first of outgrowths from the cells of the corpora striata and thalami; later the fibres from the cells of the cortex are added. Medullation of these fibres begins about the time of birth and continues until puberty.

A summary of the parts derived from the brain vesicles is given in the following table:

Rhombencephalon or Hind-brain	1. Myelencephalon	Medulla oblongata Lower part of fourth ventricle.
	2. Metencephalon	Pons Cerebellum Intermediate part of fourth ventricle.
	3. Isthmus rhomb- encephali	Anterior medullary velum Brachia conjunctiva cerebelli. Upper part of fourth ventricle.
Mesencephalon or Mid-brain		Cerebral peduncles Lamina quadrigemina Cerebral aqueduct.
Prosencephalon or Fore-brain	1. Diencephalon	Thalamus Metathalamus Epithalamus Pars mamillaria hypo- thalami Posterior part of third ventricle.
	2. Telencephalon	Anterior part of third ventricle Pars optica hypo- thalami Cerebral hemispheres Lateral ventricles Interventricular foramen.

**The Cerebral Nerves.**—With the exception of the olfactory, optic, and acoustic nerves, which will be especially considered, the cerebral nerves are developed in a similar manner to the spinal nerves (see page 119). The sensory or afferent nerves are derived from the cells of the ganglion rudiments of the neural crest. The central processes of these cells grow into the brain and form the roots of the nerves, while the peripheral processes extend outward and constitute their fibres of distribution (Fig. 120). It has been seen, in considering the development of the medulla oblongata (page 123), that the *tractus solitarius* (Fig. 135), derived from the fibres which grow inward from the ganglion rudiments of the glossopharyngeal and vagus nerves, is the homologue of the **oval bundle** in the cord which had its origin in the posterior nerve roots. The motor or efferent nerves arise as outgrowths of the neuroblasts situated in the basal laminae of the mid- and hind-brain. While, however, the spinal motor nerve roots arise in one series from the basal lamina, the cerebral motor nerves are grouped into two sets, according as they spring from the medial or lateral parts of the basal lamina. To the former set belong the oculomotor, trochlear, abducent, and hypoglossal nerves; to the



latter, the accessory and the motor fibres of the trigeminal, facial, glossopharyngeal, vagus nerves (Figs. 134, 135).

**The Sympathetic System.**—The ganglion cells of the sympathetic system are derived from the cells of the neural crests. As these crests move forward along the sides of the neural tube and become segmented off to form the spinal ganglia, certain cells detach themselves from the ventral margins of the crests and migrate toward the sides of the aorta, where some of them are grouped to form the ganglia of the sympathetic trunks, while others undergo a further migration and form the ganglia of the prevertebral and visceral plexuses. The ciliary, sphenopalatine, otic, and submaxillary ganglia which are found on the branches of the trigeminal nerve are formed by groups of cells which have migrated from the part of the neural crest which gives rise to the semilunar ganglion. Some of the cells of the ciliary ganglion are said to migrate from the neural tube along the oculomotor nerve.




FIG. 134.—Transverse section of medulla oblongata of human embryo.  $\times 32$ . (Kollmann.)

**Chromaffin Organs.**—The tissue from which the sympathetic ganglia are formed is at first a syncytium of cells termed sympatho-chromaffin cells, but later two kinds of cells become differentiated from it; the smaller cells (sympathoblasts) are transformed into the sympathetic nerve cells, the larger become chromaffin cells, and, separating from the others, accumulate to form the chromaffin organs.




FIG. 135.—Transverse section of medulla oblongata of human embryo. (After His.)

In the gangliated trunk of the sympathetic the chromaffin bodies are situated in depressions in the ganglia. In connection with certain, but not all, of the secondary plexuses of the sympathetic system chromaffin organs are found; the largest members of this series are the **aortic bodies**, which lie along the sides of the abdominal aorta between the superior mesenteric and common iliac arteries; to this group

belong also the **carotid skeins**. After birth the chromaffin organs degenerate and can no longer be isolated by gross dissection, but chromaffin tissue can be recognized with the microscope in the sites originally occupied by them.

**The Suprarenal Glands.**—Each suprarenal gland consists of a cortical portion derived from the coelomic epithelium and a medullary portion originally composed of sympatho-chromaffin tissue. The cortical portion is first recognizable about




FIG. 136.—Transverse section of head of chick embryo of forty-eight hours' incubation. (Duval.)

the beginning of the fourth week as a series of buds from the coelomic cells at the root of the mesentery. Later it becomes completely separated from the coelomic epithelium and forms a suprarenal ridge projecting into the coelom between the mesonephros and the root of the mesentery. Into this cortical portion cells from the neighboring masses of sympatho-chromaffin tissue migrate along the line of its central vein to reach and form the medullary portion of the gland.

**The Nose.**—The development of the nose has already been considered (pages 111, 112).

The **olfactory nerves** are developed from the cells of the ectoderm which lines the olfactory pits; these cells undergo proliferation and give rise to what are termed the **olfactory cells** of the nose. The axons of the olfactory cells grow into the overlying olfactory bulb and form the olfactory nerves.

**The Eye.**—The eyes begin to develop as a pair of diverticula from the lateral aspects of the fore-brain. These diverticula make their appearance before the closure of the anterior end of the neural tube; after the closure of the tube they are




FIG. 137.—Transverse section of head of chick embryo of fifty-two hours' incubation. (Duval.)

known as the **optic vesicles**. They project toward the sides of the head, and the peripheral part of each expands to form a hollow bulb, while the proximal part remains narrow and constitutes the **optic stalk** (Figs. 136, 137). The ectoderm overlying the bulb becomes thickened, invaginated, and finally severed from the ectodermal covering of the head as a vesicle of cells, the **lens vesicle**, which constitutes the rudiment of the crystalline lens. The outer wall of the bulb becomes thickened and invaginated, and the bulb is thus converted into a cup, the **optic cup**,

consisting of two strata of cells (Fig. 137). These two strata are continuous with each other at the cup margin, which ultimately overlaps the front of the lens and reaches as far forward as the future aperture of the pupil. The invagination is not limited to the outer wall of the bulb, but involves also its postero-inferior surface and extends in the form of a groove for some distance along the optic stalk, so that, for a time, a gap or fissure, the **choroidal fissure**, exists in the lower part of the cup (Fig. 138). Through the groove and fissure the mesoderm extends into the optic stalk and cup, and in this mesoderm a bloodvessel is developed; during the seventh week the groove and fissure are closed and the vessel forms the central artery of the retina. Sometimes the choroidal fissure persists, and when this occurs the choroid and iris in the region of the fissure remain undeveloped, giving rise to the condition known as *coloboma* of the choroid or iris.




FIG. 138.—Optic cup and choroidal fissure seen from below, from a human embryo of about four weeks. (Kollmann.)

The **retina** is developed from the optic cup. The outer stratum of the cup persists as a single layer of cells which assume a columnar shape, acquire pigment, and form the pigmented layer of the retina; the pigment first appears in the cells near the edge of the cup. The cells of the inner stratum proliferate and form a layer of considerable thickness from which the nervous elements and the sustentacular fibres of the retina, together with a portion of the vitreous body, are developed. In that portion of the cup which overlaps the lens the inner stratum is not differentiated into nervous elements, but forms a layer of columnar cells which is applied to the pigmented layer, and these two strata form the **pars ciliaris** and **pars iridica retinae**.

The cells of the inner or retinal layer of the optic cup become differentiated into spongioblasts and germinal cells, and the latter by their subdivisions give rise to neuroblasts. From the spongioblasts the sustentacular fibres of Müller, the outer and inner limiting membranes, together with the groundwork of the molecular layers of the retina are formed. The neuroblasts become arranged to form the ganglionic and nuclear layers. The layer of rods and cones is first developed in the central part of the optic cup, and from there gradually extends toward the cup margin. All the layers of the retina are completed by the eighth month of fetal life.

The optic stalk is converted into the **optic nerve** by the obliteration of its cavity and the growth of nerve fibres into it. Most of these fibres are centripetal, and grow backward into the optic stalk from the nerve cells of the retina, but a few extend in the opposite direction and are derived from nerve cells in the brain. The fibres of the optic nerve receive their medullary sheaths about the tenth week after

belong also the **carotid skeins**. After birth the chromaffin organs degenerate and can no longer be isolated by gross dissection, but chromaffin tissue can be recognized with the microscope in the sites originally occupied by them.

**The Suprarenal Glands.**—Each suprarenal gland consists of a cortical portion derived from the coelomic epithelium and a medullary portion originally composed of sympatho-chromaffin tissue. The cortical portion is first recognizable about




FIG. 136.—Transverse section of head of chick embryo of forty-eight hours' incubation. (Duval.)

the beginning of the fourth week as a series of buds from the coelomic cells at the root of the mesentery. Later it becomes completely separated from the coelomic epithelium and forms a suprarenal ridge projecting into the coelom between the mesonephros and the root of the mesentery. Into this cortical portion cells from the neighboring masses of sympatho-chromaffin tissue migrate along the line of its central vein to reach and form the medullary portion of the gland.

**The Nose.**—The development of the nose has already been considered (pages 111, 112).

The **olfactory nerves** are developed from the cells of the ectoderm which lines the olfactory pits; these cells undergo proliferation and give rise to what are termed the **olfactory cells** of the nose. The axons of the olfactory cells grow into the overlying olfactory bulb and form the olfactory nerves.

**The Eye.**—The eyes begin to develop as a pair of diverticula from the lateral aspects of the fore-brain. These diverticula make their appearance before the closure of the anterior end of the neural tube; after the closure of the tube they are




FIG. 137.—Transverse section of head of chick embryo of fifty-two hours' incubation. (Duval.)

known as the **optic vesicles**. They project toward the sides of the head, and the peripheral part of each expands to form a hollow bulb, while the proximal part remains narrow and constitutes the **optic stalk** (Figs. 136, 137). The ectoderm overlying the bulb becomes thickened, invaginated, and finally severed from the ectodermal covering of the head as a vesicle of cells, the **lens vesicle**, which constitutes the rudiment of the crystalline lens. The outer wall of the bulb becomes thickened and invaginated, and the bulb is thus converted into a cup, the **optic cup**,

consisting of two strata of cells (Fig. 137). These two strata are continuous with each other at the cup margin, which ultimately overlaps the front of the lens and reaches as far forward as the future aperture of the pupil. The invagination is not limited to the outer wall of the bulb, but involves also its postero-inferior surface and extends in the form of a groove for some distance along the optic stalk, so that, for a time, a gap or fissure, the **choroidal fissure**, exists in the lower part of the cup (Fig. 138). Through the groove and fissure the mesoderm extends into the optic stalk and cup, and in this mesoderm a bloodvessel is developed; during the seventh week the groove and fissure are closed and the vessel forms the central artery of the retina. Sometimes the choroidal fissure persists, and when this occurs the choroid and iris in the region of the fissure remain undeveloped, giving rise to the condition known as *coloboma* of the choroid or iris.




FIG. 138.—Optic cup and choroidal fissure seen from below, from a human embryo of about four weeks. (Kollmann.)

The **retina** is developed from the optic cup. The outer stratum of the cup persists as a single layer of cells which assume a columnar shape, acquire pigment, and form the pigmented layer of the retina; the pigment first appears in the cells near the edge of the cup. The cells of the inner stratum proliferate and form a layer of considerable thickness from which the nervous elements and the sustentacular fibres of the retina, together with a portion of the vitreous body, are developed. In that portion of the cup which overlaps the lens the inner stratum is not differentiated into nervous elements, but forms a layer of columnar cells which is applied to the pigmented layer, and these two strata form the **pars ciliaris** and **pars iridica retinae**.

The cells of the inner or retinal layer of the optic cup become differentiated into spongioblasts and germinal cells, and the latter by their subdivisions give rise to neuroblasts. From the spongioblasts the sustentacular fibres of Müller, the outer and inner limiting membranes, together with the groundwork of the molecular layers of the retina are formed. The neuroblasts become arranged to form the ganglionic and nuclear layers. The layer of rods and cones is first developed in the central part of the optic cup, and from there gradually extends toward the cup margin. All the layers of the retina are completed by the eighth month of fetal life.

The optic stalk is converted into the **optic nerve** by the obliteration of its cavity and the growth of nerve fibres into it. Most of these fibres are centripetal, and grow backward into the optic stalk from the nerve cells of the retina, but a few extend in the opposite direction and are derived from nerve cells in the brain. The fibres of the optic nerve receive their medullary sheaths about the tenth week after



birth. The **optic chiasma** is formed by the meeting and partial decussation of the fibres of the two optic nerves. Behind the chiasma the fibres grow backward as the optic tracts to the thalami and mesencephalon.

The **crystalline lens** is developed from the lens vesicle, which recedes within the margin of the cup, and becomes separated from the overlying ectoderm by mesoderm. The cells forming the posterior wall of the vesicle lengthen and are converted into the lens fibres, which grow forward and fill up the cavity of the vesicle (Fig. 139). The cells forming the anterior wall retain their cellular character, and form the epithelium on the anterior surface of the adult lens. By the second month the lens is invested by a vascular mesodermal capsule, the **capsula vasculosa lentis**; the bloodvessels supplying the posterior part of this capsule are derived from the hyaloid artery; those for the anterior part from the anterior ciliary arteries; the portion of the capsule which covers the front of the lens is named the **pupillary**




FIG. 139.—Horizontal section through the eye of an eighteen days' embryo rabbit.  $\times 30$ . (Kölliker.)

**membrane.** By the sixth month all the vessels of the capsule are atrophied except the hyaloid artery, which disappears during the ninth month; the position of this artery is indicated in the adult by the hyaloid canal, which reaches from the optic disk to the posterior surface of the lens. With the loss of its bloodvessels the capsula vasculosa lentis disappears, but sometimes the pupillary membrane persists at birth, giving rise to the condition termed *congenital atresia of the pupil*.

The **vitreous body** is developed between the lens and the optic cup. The lens rudiment and the optic vesicle are at first in contact with each other, but after the closure of the lens vesicle and the formation of the optic cup the former withdraws itself from the retinal layer of the cup; the two, however, remain connected by a network of delicate protoplasmic processes. This network, derived partly from the cells of the lens and partly from those of the retinal layer of the cup, constitutes the primitive vitreous body (Figs. 140, 141). At first these protoplasmic processes spring from the whole of the retinal layer of the cup, but later are limited to the

ciliary region, where by a process of condensation they appear to form the zonula ciliaris. The mesoderm which enters the cup through the choroidal fissure and around the equator of the lens becomes intimately united with this reticular tissue, and contributes to form the vitreous body, which is therefore derived partly from the ectoderm and partly from the mesoderm.




FIG. 140.—Sagittal section of eye of human embryo of six weeks. (Kollmann.)

The **anterior chamber** of the eye appears as a cleft in the mesoderm separating the lens from the overlying ectoderm. The layer of mesoderm in front of the cleft forms the substantia propria of the cornea, that behind the cleft the stroma of the iris and the pupillary membrane. The fibres of the ciliary muscle are derived from the mesoderm, but those of the Sphincter and Dilatator pupillae are of ectodermal origin, being developed from the cells of the pupillary part of the optic cup.

The **sclera** and **choroid** are derived from the mesoderm surrounding the optic cup.

The **eyelids** are formed as small cutaneous folds (Figs. 139, 140), which about the middle of the third month come together and unite in front of the cornea. They remain united until about the end of the sixth month.

The **lacrimal sac** and **nasolacrimal duct** result from a thickening of the ectoderm in the groove, **nasöptic furrows**, between the lateral nasal and maxillary processes. This thickening forms a solid cord of cells which sinks into the mesoderm; during the third month the central cells of the cord break down, and a lumen, the nasolacrimal duct, is established. The lacrimal ducts arise as buds from the upper part



of the cord of cells and secondarily establish openings (*puncta lacrimalia*) on the margins of the lids. The **epithelium** of the cornea and conjunctiva, and that which lines the ducts and alveoli of the lacrimal gland, are of ectodermal origin, as are also the **eyelashes** and the lining cells of the glands which open on the lid-margins.




FIG. 141.—Section of developing eye of trout. (Szily.)

**The Ear.**—The first rudiment of the internal ear appears shortly after that of the eye, in the form of a patch of thickened ectoderm, the **auditory plate**, over the region of the hind-brain. The auditory plate becomes depressed and converted into the **auditory pit** (Fig. 142). The mouth of the pit is then closed, and thus a shut sac, the **auditory vesicle**, is formed (Fig. 143); from it the epithelial lining of the




FIG. 142.—Section through the head of a human embryo, about twelve days old, in the region of the hind brain. (Kollmann.)




FIG. 143.—Section through hind brain and auditory vesicles of an embryo more advanced than that of Fig. 142. (After His.)

membranous labyrinth is derived. The vesicle becomes pear-shaped, and the neck of the flask is obliterated (Fig. 144). From the vesicle certain diverticula are given off which form the various parts of the membranous labyrinth. One from the middle part forms the ductus and saccus endolymphaticus, another from the anterior end gradually elongates, and, forming a tube coiled on itself, becomes the

cochlear duct, the vestibular extremity of which is subsequently constricted to form the canalis reuniens. Three others appear as disk-like evaginations on the surface of the vesicle; the central parts of the walls of the disks coalesce and disappear, while the peripheral portions persist to form the semicircular ducts; of these the




FIG. 144.—Left auditory vesicle of a human embryo of four weeks, seen from the outer surface. (W. His, Jr.)




FIG. 145.—Left auditory vesicle of a human embryo of five weeks, seen from the outer surface. (W. His, Jr.)

superior is the first and the lateral the last to be completed (Figs. 145, 146). The central part of the vesicle represents the membranous vestibule, and is subdivided by a constriction into a smaller ventral part, the saccule, and a larger dorsal and posterior part, the utricle. This subdivision is effected by a fold which extends




FIG. 146.—Transverse section through head of fetal sheep, in the region of the labyrinth.  $\times 30$ . (After Boettcher.)

deeply into the proximal part of the ductus endolymphaticus, with the result that the utricle and saccule ultimately communicate with each other by means of a Y-shaped canal. The saccule opens into the cochlear duct, through the canalis reuniens, and the semicircular ducts communicate with the utricle (Fig. 147).

The mesodermal tissue surrounding the various parts of the epithelial labyrinth is converted into a cartilaginous ear-capsule, and this is finally ossified to form the bony labyrinth. Between the cartilaginous capsule and the epithelial structures is a stratum of mesodermal tissue which is differentiated into three layers, viz.,




FIG. 147.—Left membranous labyrinth of a human embryo of 30 mm. (From model by W. His, Jr.)

an outer, forming the periosteal lining of the bony labyrinth; an inner, in direct contact with the epithelial structures; and an intermediate, consisting of gelatinous tissue: by the absorption of this latter tissue the perilymphatic spaces are developed. The modiolus and osseous spiral lamina of the cochlea are not preformed in cartilage but are ossified directly from connective tissue.




FIG. 148.—Transverse section of the cochlear duct of a fetal cat. (After Boettcher and Ayres.)

The **middle ear** and **auditory tube** are developed from the first pharyngeal pouch. The entodermal lining of the dorsal end of this pouch is in contact with the ectoderm of the corresponding pharyngeal groove; by the extension of the mesoderm between these two layers the tympanic membrane is formed. During the sixth or

seventh month the tympanic antrum appears as an upward and backward expansion of the tympanic cavity. With regard to the exact mode of development of the ossicles of the middle ear there is some difference of opinion. The view generally held is that the **incus** and **malleus** are developed from the proximal end of the mandibular (Meckel's) cartilage (Fig. 105) and that the **stapes** is formed from the proximal end of the second arch. The malleus, with the exception of its anterior process, is ossified from a single centre which appears near the neck of the bone; the anterior process is ossified separately in membrane and joins the main part of the bone about the sixth month of fetal life. The incus is ossified from one centre which appears in the upper part of its long crus and ultimately extends into its lenticular process. The stapes first appears as a ring (*annulus stapedius*) encircling a small vessel, the stapedia artery, which subsequently undergoes atrophy; it is ossified from a single centre which appears in its base.

The **external acoustic meatus** is developed from the first branchial groove. The lower part of this groove extends inward as a funnel-shaped tube (primary meatus) from which the cartilaginous portion and a small part of the roof of the osseous portion of the meatus are developed. From the lower part of the funnel-shaped tube an epithelial lamina extends downward and inward along the inferior wall of the primitive tympanic cavity; by the splitting of this lamina the inner part of the meatus (secondary meatus) is produced, while the inner portion of the lamina forms the cutaneous stratum of the tympanic membrane. The **auricula** or **pinna** is developed by the gradual differentiation of six tubercles (Fig. 149) which appear around the margin of the first branchial groove. Two tubercles appear on the posterior edge of the mandibular arch; these represent the rudiments of the tragus and crus helix. Three are found on the hyoid arch, and indicate, from below upward, the lobule, antitragus, and antihelix. One arises above the groove, and grows downward behind the antitragus and antihelix; from it and its downward prolongation the upper part of the helix and the cauda helix are developed (Figs. 150, 151).

Some observers, however, maintain that the lowest tubercle on the hyoid arch becomes the antitragus, and that the lobule is developed later as an independent formation. The rudiment of the **acoustic nerve** appears about the end of the third week as a group of ganglion cells closely applied to the cephalic edge of the auditory vesicle. Whether these cells are derived from the ectoderm adjoining the auditory vesicle, or have migrated from the wall of the neural tube, is as yet uncertain. Each cell gives off a proximal fibre which passes into the neural tube, and a distal which is distributed to the epithelial cells of the auditory vesicle.




FIG. 149.—Tubercles from which the different parts of the auricula are developed. (His.) 1, 2. Tubercles on mandibular arch. 3. Tubercle above cleft. 3, c. Prolongation of 3 downward. 4, 5, 6. Tubercles on hyoid arch. o.v. Auditory vesicle.

## DEVELOPMENT OF THE VASCULAR SYSTEM

Bloodvessels first make their appearance in several scattered *vascular areas* (Fig. 152) which are developed simultaneously between the entoderm and the mesoderm of the yolk-sac, *i. e.*, outside the body of the embryo.<sup>1</sup> Here the cells become

<sup>1</sup> No definite statement can be made as to whether the earliest vessels are derived from the entoderm of the yolk-sac or from the mesoderm overlying it; the most recent view favors the entoderm as the original source of the blood corpuscles and endothelium of the vessels.

arranged into solid strands or cords which join to form a close-meshed network, the **area vasculosa**, which covers the whole yolk-sac. The peripheral cells of these




FIG. 150.—Left auriculæ of human embryos estimated at thirty-five and thirty-eight days respectively. (After His.)

strands become flattened and joined to each other by their edges to form the endothelium of the walls of the primitive bloodvessels. Fluid collects within the strands

and converts them into tubes, and the more centrally situated cells of the cell-cords are thus pushed to the sides of the vessels and appear as masses of loosely arranged cells projecting toward the lumen of the tube. These masses are termed **blood islands** (Fig. 153); their cells are detached to form the blood corpuscles. The earliest bloodvessels, therefore, are formed at several separate centres; from the walls of these vessels buds grow out, become vascularized and converted into new vessels, and join with those of neighboring areas to form a close meshwork. It is uncertain whether the vessels within the body of the embryo are extensions from this network (His) or whether they are of new formation. Most observers agree, however, that, after the aortæ have appeared,

no other independent vessels are laid down, *i. e.*, all new vessels are derived from preëxisting ones.



FIG. 151.—Auricula in a more advanced stage of development than those represented in Fig. 150.




FIG. 152.—Section through vascular area to show differentiation of primitive vascular cells. Diagrammatic.




FIG. 153.—Section through developing bloodvessel. Diagrammatic.

The red and the colorless corpuscles of the blood are all derived from the nucleated cells of the blood islands—**mesamœboid cells of Minot**—and the earliest blood corpuscles are thus all nucleated; they are also capable of subdivision and of



executing amoeboid movements. Some of these cells acquire coloring matter (*hemoglobin*); their nuclei disintegrate and are expelled and the non-nucleated red corpuscles result. Other mesamoeboid cells retain their nuclei; some remain in the blood as the leucocytes; others wander out into the tissues, particularly into the liver, lymphoid tissues, and marrow of the bones, where they form specialized masses from which the corpuscles of the blood are regenerated. From the mesamoeboid cells five chief forms are derived: (1) erythrocytes, (2) lymphocytes, (3) finely granular or neutrophil leucocytes, (4) coarsely granular or eosinophil leucocytes, (5) degenerating or basophil leucocytes.

The first rudiment of the heart appears as a pair of tubular vessels which are developed in the splanchnopleure of the pericardial area (Fig. 154). These are named the **primitive aortæ**, and a direct continuity is soon established between them and the vessels of the yolk-sac. Each receives anteriorly a vein—the **vitelline vein**—from the yolk-sac, and is prolonged backward on the lateral aspect of the notochord under the name of the **dorsal aorta**. The dorsal aortæ give branches to the yolk-sac, and are continued backward through the body-stalk as the umbilical arteries to the villi of the chorion.

Eternod<sup>1</sup> describes the circulation in an embryo which he estimated to be about thirteen days old (Fig. 155). The rudiment of the heart is situated immediately below the fore-gut and consists of a short stem. It gives off two vessels, the **primitive aortæ**, which run backward, one on either side of the notochord, and then pass into the body-stalk along which they are carried to the chorion. From the chorionic villi the blood is returned by a pair of umbilical veins which unite in the body-stalk




FIG. 154.—Transverse section through the region of the heart in a rabbit embryo of nine days.  $\times 80$ . (Kölliker.) *j, j.* Jugular veins. *ao.* Aorta. *ph.* Pharynx. *som.* Somatopleure. *bl.* Proamnion. *ect.* Ectoderm. *ent.* Entoderm. *p.* Pericardium. *spl.* Splanchnopleure. *ah.* Outer wall of heart. *ih.* Endothelial lining of heart. *e'.* Septum between heart tubes.




FIG. 155.—Diagram of the vascular channels in a human embryo of the second week. (After Eternod.) The red lines are the dorsal aortæ continued into the umbilical arteries. The red dotted lines are the ventral aortæ, and the blue dotted lines the vitelline veins.

to form a single vessel and subsequently encircle the mouth of the yolk-sac and open into the heart. At the junction of the yolk-sac and body-stalk each vein is joined by a branch from the vascular plexus of the yolk-sac. From his observations it seems that, in the human embryo, the chorionic circulation is established before that on the yolk-sac.




FIG. 156.—Human embryo of about fourteen days old with yolk-sac. (After His.)

By the forward growth and flexure of the head the pericardial area and the anterior portions of the primitive aortæ are folded backward on the ventral aspect of the fore-gut, and the original relation of the somatopleure and splanchnopleure




FIG. 157.—Head of chick embryo of about thirty-eight hours' incubation, viewed from the ventral surface.  $\times 26$ . (Duval)

layers of the pericardial area is reversed. Each primitive aorta now consists of a ventral and a dorsal part connected anteriorly by an arch (Fig. 156); these three parts are named respectively the anterior ventral aorta, the dorsal aorta, and the first cephalic arch. The vitelline veins which enter the embryo through the



anterior wall of the umbilical orifice are now continuous with the posterior ends of the anterior ventral aorta. With the formation of the tail-fold the posterior parts of the primitive aortæ are carried forward in a ventral direction to form the posterior ventral aortæ and primary caudal arches.<sup>1</sup> In the pericardial region the two primitive aortæ grow together, and fuse to form a single tubular heart (Fig. 157), the posterior end of which receives the two vitelline veins, while from its anterior end the two anterior ventral aortæ emerge.<sup>2</sup> The first cephalic arches pass through the mandibular arches, and behind them five additional pairs subsequently develop, so that altogether six pairs of aortic arches are formed; the fifth arches are very transitory vessels connecting the ventral aortæ with the dorsal ends of the sixth arches. By the rhythmical contraction of the tubular heart the blood is forced through the aortæ and bloodvessels of the vascular area, from which it is returned to the heart by the vitelline veins. This constitutes the **vitelline circulation** (Fig. 156), and by means of it nutriment is absorbed from the yolk vitellus.

The vitelline veins at first open separately into the posterior end of the tubular heart, but after a time their terminal portions fuse to form a single vessel. The vitelline veins ultimately drain the blood from the digestive tube, and are modified to form the portal vein. This is caused by the growth of the liver, which interrupts their direct continuity with the heart; and the blood returned by them circulates through the liver before reaching the heart.

With the atrophy of the yolk-sac the vitelline circulation diminishes and ultimately ceases, while an increasing amount of blood is carried through the umbilical arteries to the villi of the chorion. Subsequently, as the non-placental chorionic villi atrophy, their vessels disappear; and then the umbilical arteries convey the whole of their contents to the placenta, whence it is returned to the heart by the umbilical veins. In this manner the placental circulation is established, and by means of it nutritive materials are absorbed from, and waste products given up to, the maternal blood.

The umbilical veins, like the vitelline, undergo interruption in the developing liver, and the blood returned by them passes through this organ before reaching the heart. Ultimately the right umbilical vein shrivels up and disappears, as will be explained later (page 156).

During the occurrence of these changes great alterations take place in the primitive heart and bloodvessels.

**Further Development of the Heart.**—Between the endothelial lining and the outer wall of the heart there exists for a time an intricate trabecular network of mesodermal tissue from which, at a later stage, the muscoli papillares, chordæ tendineæ, and trabeculæ carneæ are developed. The simple tubular heart, already described, becomes elongated and bent on itself so as to form an S-shaped loop, the anterior part bending to the right and the posterior part to the left (Fig. 157). The intermediate portion arches transversely from left to right, and then turns sharply forward into the anterior part of the loop. Slight constrictions make their appearance in the tube and divide it from behind forward into five parts, viz.: (1) the **sinus venosus**; (2) the **primitive atrium**; (3) the **primitive ventricle**; (4) the **bulbus cordis**, and (5) the **truncus arteriosus** (Figs. 158, 159). The constriction between the atrium and ventricle constitutes the **atrial canal**, and indicates the site of the future atrioventricular valves.

The **sinus venosus** is at first situated in the septum transversum (a layer of mesoderm in which the liver and the central tendon of the Diaphragma are developed) behind the primitive atrium, and is formed by the union of the vitelline veins. The veins or ducts of Cuvier from the body of the embryo and the umbilical veins from the placenta subsequently open into it (Fig. 160). The sinus is at first

<sup>1</sup> Young and Robinson, *Journal of Anatomy and Physiology*, vol. xxxii.

<sup>2</sup> In most fishes and in the amphibia the heart originates as a single median tube.

place transversely, and opens by a median aperture into the primitive atrium. Soon, however, it assumes an oblique position, and becomes crescentic in form; its right half or horn increases more rapidly than the left, and the opening into the atrium now communicates with the right portion of the atrial cavity. The right horn and transverse portion of the sinus ultimately become incorporated with and form a part of the adult right atrium, the line of union between it and the auricula




FIG. 158.—Diagram to illustrate the simple tubular condition of the heart. (Drawn from Ecker-Ziegler model.)




FIG. 159.—Heart of human embryo of about fourteen days. (From model by His.)

being indicated in the interior of the atrium by a vertical crest, the **crista terminalis** of His. The left horn, which ultimately receives only the left duct of Cuvier, persists as the coronary sinus (Fig. 161). The vitelline and umbilical veins are soon replaced by a single vessel, the **inferior vena cava**, and the three veins (inferior vena cava and right and left Cuvierian ducts) open into the dorsal aspect of the atrium by a common slit-like aperture (Fig. 162). The upper part of this aperture represents the opening of the permanent superior vena cava, the lower that of the inferior




FIG. 160.—Heart of human embryo of about fifteen days. (Reconstruction by His.)

vena cava, and the intermediate part the orifice of the coronary sinus. The slit-like aperture lies obliquely, and is guarded by two halves, the **right** and **left venous valves**; above the opening these unite with each other and are continuous with a fold named the **septum spurium**; below the opening they fuse to form a triangular thickening—the **spina vestibuli**. The right venous valve is retained; a small septum, the **sinus septum**, grows from the posterior wall of the sinus venosus to fuse

with the valve and divide it into two parts—an upper, the valve of the inferior vena cava, and a lower, the valve of the coronary sinus (Fig. 165). The extreme




FIG. 161.—Dorsal surface of heart of human embryo of thirty-five days. (From model by His.)




FIG. 162.—Interior of dorsal half of heart from a human embryo of about thirty days. (From model by His.)

upper portion of the right venous valve, together with the septum spurium, form the crista terminalis already mentioned. The upper and middle thirds of the left

venous valve disappear; the lower third is continued into the spina vestibuli, and later fuses with the septum secundum of the atria and takes part in the formation of the limbus fossae ovalis.




FIG. 163.—Heart showing expansion of the atria. (Drawn from Ecker-Zeigler model.)

The atrial canal is at first a short straight tube connecting the atrial with the ventricular portion of the heart, but its growth is relatively slow, and it becomes overlapped by the atria and ventricles so that its position on the surface of the heart is indicated only by an annular constriction (Fig. 163). Its lumen is reduced to a transverse slit, and two thickenings appear, one on its dorsal and another on its




FIG. 164.—Interior of dorsal half of heart of human embryo of about thirty-five days. (From model by His.)

ventral wall. These thickenings, or **endocardial cushions** (Fig. 162) as they are termed, project into the canal, and, meeting in the middle line, unite to form the **septum intermedium** which divides the canal into two channels, the future right and left atrioventricular orifices.



The **primitive atrium** grows rapidly and partially encircles the *bulbus cordis*; the groove against which the *bulbus cordis* lies is the first indication of a division into right and left atria. The cavity of the primitive atrium becomes subdivided into right and left chambers by a septum, the **septum primum** (Fig. 162), which grows downward into the cavity. For a time the atria communicate with each other by an opening, the **ostium primum of Born**, below the free margin of the septum. This opening is closed by the union of the septum primum with the septum intermedium, and the communication between the atria is reestablished through an opening which is developed in the upper part of the septum primum; this opening is known as the **foramen ovale** (*ostium secundum of Born*) and persists until birth. A second septum, the **septum secundum** (Figs. 164, 165), semilunar in shape, grows downward from the upper wall of the atrium immediately to the right of the primary septum and foramen ovale. Shortly after birth it fuses with the primary septum, and by this means the foramen ovale is closed, but sometimes the fusion is incomplete and the upper part of the foramen remains patent. The *limbus fossae*




FIG. 165.—Same heart as in Fig. 164, opened on right side. (From model by His.)

ovalis denotes the free margin of the septum secundum. Issuing from each lung is a pair of pulmonary veins; each pair unites to form a single vessel, and these in turn join in a common trunk which opens into the left atrium. Subsequently the common trunk and the two vessels forming it expand and form the vestibule or greater part of the atrium, the expansion reaching as far as the openings of the four vessels, so that in the adult all four veins open separately into the left atrium.

The **primitive ventricle** becomes divided by a septum, the **septum inferius** or **ventricular septum** (Figs. 162, 164, 165), which grows upward from the lower part of the ventricle, its position being indicated on the surface of the heart by a furrow. Its dorsal part increases more rapidly than its ventral portion, and fuses with the dorsal part of the septum intermedium. For a time an interventricular foramen exists above its ventral portion (Fig. 165), but this foramen is ultimately closed by the fusion of the aortic septum with the ventricular septum.

When the heart assumes its S-shaped form the *bulbus cordis* lies ventral to and in front of the primitive ventricle. The adjacent walls of the *bulbus cordis* and ventricle approximate, fuse, and finally disappear, and the *bulbus cordis* now

communicates freely with the right ventricle, while the junction of the bulbus with the truncus arteriosus is brought directly ventral to and applied to the atrial canal.




FIG. 166.—Diagrams to illustrate the transformation of the bulbus cordis. (Keith.) Ao. Truncus arteriosus. Au. Atrium. B. Bulbus cordis. RV. Right ventricle. LV. Left ventricle. P. Pulmonary artery.

By the upgrowth of the ventricular septum the bulbus cordis is in great measure separated from the left ventricle, but remains an integral part of the right ventricle, of which it forms the infundibulum (Fig. 166).




FIG. 167.—Diagrams to show the development of the septum of the aortic bulb and of the ventricles. (Born.)

The **truncus arteriosus** and **bulbus cordis** are divided by the **aortic septum** (Fig. 167). This makes its appearance in three portions. (1) Two distal ridge-like




FIG. 168.—Transverse sections through the aortic bulb to show the growth of the aortic septum. The lowest section is on the left, the highest on the right of the figure. (After His.)

thickenings project into the lumen of the tube; these increase in size, and ultimately meet and fuse to form a septum, which takes a spiral course toward the proximal

end of the truncus arteriosus. It divides the distal part of the truncus into two vessels, the aorta and pulmonary artery, which lie side by side above, but near the heart the pulmonary artery is in front of the aorta. (2) Four endocardial cushions appear in the proximal part of the truncus arteriosus in the region of the future semilunar valves; the manner in which these are related to the aortic septum is described below. (3) Two endocardial thickenings—anterior and posterior—develop in the bulbus cordis and unite to form a short septum; this joins above with the aortic septum and below with the ventricular septum. The septum grows down into the ventricle as an oblique partition, which ultimately blends with the ventricular septum in such a way as to bring the bulbus cordis into communication with the pulmonary artery, and through the latter with the sixth pair of aortic arches; while the left ventricle is brought into continuity with the aorta, which communicates with the remaining aortic arches.




FIG. 169.—Profile view of a human embryo estimated at twenty or twenty-one days old. (After His.)

**The Valves of the Heart.**—The atrioventricular valves are developed in relation to the atrial canal. By the upward expansion of the bases of the ventricles the canal becomes invaginated into the ventricular cavities. The invaginated margin forms the rudiments of the lateral cusps of the atrioventricular valves; the mesial or septal cusps of the valves are developed as downward prolongations of the septum intermedium (Fig. 164). The aortic and pulmonary semilunar valves are formed from four endocardial thickenings—an anterior, a posterior, and two lateral—



which appear at the proximal end of the truncus arteriosus. As the aortic septum grows downward it divides each of the lateral thickenings into two, thus giving rise to six thickenings—the rudiments of the semilunar valves—three at the aortic and three at the pulmonary orifice (Fig. 168).

**Further Development of the Arteries.**—Recent observations show that practically none of the main vessels of the adult arise as such in the embryo. In the site of each vessel a capillary network forms, and by the enlargement of definite paths in this the larger arteries and veins are developed. The branches of the main arteries are not always simple modifications of the vessels of the capillary network, but may arise as new outgrowths from the enlarged stem.




FIG. 170.—Scheme of the aortic arches and their destination. (Modified from Kollmann.)

It has been seen (page 145) that each primitive aorta consists of a ventral and a dorsal part which are continuous through the first aortic arch. The dorsal aortæ at first run backward separately on either side of the notochord, but about the third week they fuse from about the level of the fourth thoracic to that of the fourth lumbar segment to form a single trunk, the descending aorta. The first aortic arches run through the mandibular arches, and behind them five additional pairs are developed within the visceral arches; so that, in all, six pairs of aortic arches are formed (Figs. 169, 170). The first and second arches pass between the ventral and dorsal aortæ, while the others arise at first by a common trunk from the truncus arteriosus, but end separately in the dorsal aortæ. As the neck elongates, the ventral aortæ are drawn out, and the third and fourth arches arise directly from these vessels.

In fishes these arches persist and give off branches to the gills, in which the blood is oxygenated. In mammals some of them remain as permanent structures, while others disappear or become obliterated (Fig. 170).

**The Anterior Ventral Aortæ.**—These persist on both sides. The right forms (a) the innominate artery, (b) the right common and external carotid arteries. The left gives rise to (a) the short portion of the aortic arch, which reaches from the

origin of the innominate artery to that of the left common carotid artery; (b) the left common and external carotid arteries.

**The Aortic Arches.**—The first and second arches disappear early, but the dorsal end of the second gives origin to the stapedial artery (Fig. 171), a vessel which atrophies in man but persists in some mammals. It passes through the ring of the stapes and divides into supraorbital, infraorbital, and mandibular branches which follow the three divisions of the trigeminal nerve. The infraorbital and mandibular arise from a common stem, the terminal part of which anastomoses with




FIG. 171.—Diagram showing the origins of the main branches of the carotid arteries. (Founded on Tandler.)

the external carotid. On the obliteration of the stapedial artery this anastomosis enlarges and forms the internal maxillary artery, and the branches of the stapedial artery are now branches of this vessel. The common stem of the infraorbital and mandibular branches passes between the two roots of the auriculotemporal nerve and becomes the middle meningeal artery; the original supraorbital branch of the stapedial is represented by the orbital twigs of the middle meningeal. The third aortic arch constitutes the commencement of the internal carotid artery, and is therefore named the carotid arch. The fourth right arch forms the right subclavian as far as the origin of its internal mammary branch; while the fourth left arch constitutes the arch of the aorta between the origin of the left carotid artery and the termination of the ductus arteriosus. The fifth arch disappears on both sides. The sixth right arch disappears; the sixth left arch gives off the pulmonary

arteries and forms the ductus arteriosus; this duct remains pervious during the whole of fetal life, but is obliterated a few days after birth. His showed that in the early embryo the right and left arches each gives a branch to the lungs, but that later both pulmonary arteries take origin from the left arch.

**The Dorsal Aortæ.**—In front of the third aortic arches the dorsal aortæ persist and form the continuations of the internal carotid arteries; these arteries pass to the brain and each divides into an anterior and a posterior branch, the former giving off the ophthalmic and the anterior and middle cerebral arteries, while the latter turns back and joins the cerebral part of the vertebral artery. Behind the third arch the right dorsal aorta disappears as far as the point where the two dorsal aortæ fuse to form the descending aorta. The part of the left dorsal aorta between the third and fourth arches disappears, while the remainder persists to form the descending part of the arch of the aorta. A constriction, the **aortic isthmus**, is sometimes seen in the aorta between the origin of the left subclavian and the attachment of the ductus arteriosus.

Sometimes the right subclavian artery arises from the aortic arch distal to the origin of the left subclavian and passes upward and to the right behind the trachea and œsophagus. This condition may be explained by the persistence of the right dorsal aorta and the obliteration of the fourth right arch.

In birds the fourth right arch forms the arch of the aorta; in reptiles the fourth arch on both sides persists and gives rise to the double aortic arch in these animals.

The heart originally lies on the ventral aspect of the pharynx, immediately behind the stomodeum. With the elongations of the neck and the development of the lungs it recedes within the thorax, and, as a consequence, the anterior ventral aortæ are drawn out and the original position of the fourth and fifth arches is greatly modified. Thus, on the right side the fourth recedes to the root of the neck, while on the left side it is withdrawn within the thorax. The recurrent nerves originally pass to the larynx under the sixth pair of arches, and are therefore pulled backward with the descent of these structures, so that in the adult the left nerve hooks around the ligamentum arteriosum; owing to the disappearance of the fifth and the sixth right arches the right nerve hooks around that immediately above them, *i. e.*, the commencement of the subclavian artery. Segmental arteries arise from the primitive dorsal aortæ and course between successive segments. The seventh segmental artery is of special interest, since it forms the lower end of the vertebral artery and, when the forelimb bud appears, sends a branch to it (the subclavian artery). From the seventh segmental arteries the entire left subclavian and the greater part of the right subclavian are formed. The second pair of segmental arteries accompany the hypoglossal nerves to the brain and are named the hypoglossal arteries. Each sends forward a branch which forms the cerebral part of the vertebral artery and anastomoses with the posterior branch of the internal carotid. The two vertebrals unite on the ventral surface of the hind-brain to form the basilar artery. Later the hypoglossal artery atrophies and the vertebral is connected with the first segmental artery. The cervical part of the vertebral is developed from a longitudinal anastomosis between the first seven segmental arteries, so that the seventh of these ultimately becomes the source of the artery. As a result of the growth of the upper limb the subclavian artery increases greatly in size and the vertebral then appears to spring from it.

Recent observations show that several segmental arteries contribute branches to the upper limb-bud and form in it a free capillary anastomosis. Of these branches, only one, *viz.*, that derived from the seventh segmental artery, persists to form the subclavian artery. The subclavian artery is prolonged into the limb under the names of the axillary and brachial arteries, and these together constitute the arterial stem for the upper arm, the direct continuation of this stem in the forearm is the volar interosseous artery. A branch which accompanies the median nerve

soon increases in size and forms the main vessel (median artery) of the forearm, while the volar interosseous diminishes. Later the radial and ulnar arteries are developed as branches of the brachial part of the stem and coincidently with their enlargement the median artery recedes; occasionally it persists as a vessel of some considerable size and then accompanies the median nerve into the palm of the hand.

The primary arterial stem for the lower limb is formed by the inferior gluteal (sciatic) artery, which accompanies the sciatic nerve along the posterior aspect of the thigh to the back of the knee, whence it is continued as the peroneal artery. This arrangement exists in reptiles and amphibians. The femoral artery arises later as a branch of the common iliac, and, passing down the front and medial side of the thigh to the bend of the knee, joins the inferior gluteal artery. The femoral quickly enlarges, and, coincidently with this, the part of the inferior gluteal immediately above the knee undergoes atrophy. The anterior and posterior tibial arteries are branches of the main arterial stem.




FIG. 172.—The liver and the veins in connection with it, of a human embryo, twenty-four or twenty-five days old; as seen from the ventral surface. (After His.)

**Further Development of the Veins.**—The formation of the great veins of the embryo may be best considered by dividing them into two groups, **visceral** and **parietal**.

**The Visceral Veins.**—The visceral veins are the two **vitelline** or **omphalomesenteric veins** bringing the blood from the yolk-sac, and the two **umbilical veins** returning the blood from the placenta; these four veins open close together into the sinus venosus.

The **Vitelline Veins** run upward at first in front, and subsequently on either side of the intestinal canal. They unite on the ventral aspect of the canal, and beyond this are connected to one another by two anastomotic branches, one on the dorsal, and the other on the ventral aspect of the duodenal portion of the intestine, which is thus encircled by two venous rings (Fig. 172); into the middle or dorsal anastomosis the superior mesenteric vein opens. The portions of the veins above the upper ring become interrupted by the developing liver and broken up by it into a plexus of small capillary-like vessels termed **sinusoids** (Minot). The branches conveying the blood to this plexus are named the **venae advehentes**, and become

the branches of the portal vein; while the vessels draining the plexus into the sinus venosus are termed the *venae revehentes*, and form the future hepatic veins (Figs. 172, 173). Ultimately the left vena revehens no longer communicates directly with the sinus venosus, but opens into the right vena revehens. The persistent part of the upper venous ring, above the opening of the superior mesenteric vein, forms the trunk of the portal vein.




FIG. 173.—Human embryo with heart and anterior body-wall removed to show the sinus venosus and its tributaries. (After His.)

The two **Umbilical Veins** fuse early to form a single trunk in the body-stalk, but remain separate within the embryo and pass forward to the sinus venosus in the side walls of the body. Like the vitelline veins, their direct connection with the sinus venosus becomes interrupted by the developing liver, and thus at this stage the whole of the blood from the yolk-sac and placenta passes through the substance of the liver before it reaches the heart. The right umbilical and right vitelline veins shrivel and disappear; the left umbilical, on the other hand, becomes enlarged and opens into the upper venous ring of the vitelline veins; with the atrophy of the yolk-sac the left vitelline vein also undergoes atrophy and disappears. Finally a direct branch is established between this ring and the right hepatic vein; this branch is named the **ductus venosus**, and, enlarging rapidly, it forms a wide channel through which most of the blood, returned from the placenta, is carried direct to the heart without passing through the liver. A small proportion of the blood from the placenta is, however, conveyed from the left umbilical vein to the liver through the left vena advehens. The left umbilical vein and the ductus venosus undergo atrophy and obliteration after birth, and form respectively the ligamentum teres and ligamentum venosum of the liver.

**The Parietal Veins.**—The first indication of a parietal system consists in the appearance of two short transverse veins, the **ducts of Cuvier**, which open, one on either side, into the sinus venosus. Each of these ducts receives an ascending and descending vein. The ascending veins return the blood from the parietes of the trunk and from the Wolffian bodies, and are called **cardinal veins**. The descending veins return the blood from the head, and are called **primitive jugular veins** (Fig. 174). The blood from the lower limbs is collected by the right and left iliac and hypogastric veins, which, in the earlier stages of development, open into the corresponding right and left cardinal veins; later, a transverse branch (the left common iliac vein) is developed between the lower parts of the two cardinal veins (Fig. 176), and through this the blood is carried into the right cardinal vein. The portion of the left cardinal vein below the left renal vein atrophies and disappears up to the point of entrance of the left spermatic vein; the portion above the left renal vein persists as the hemiazygos and accessory hemiazygos veins and the lower portion of the highest left intercostal vein. The right cardinal vein




FIG. 174.—Scheme of arrangement of parietal veins.




FIG. 175.—Scheme showing early stages of development of the inferior vena cava.

which now receives the blood from both lower extremities, forms a large venous trunk along the posterior abdominal wall; up to the level of the renal veins it forms the lower part of the inferior vena cava. Above the level of the renal veins the right cardinal vein persists as the azygos vein and receives the right intercostal veins, while the hemiazygos veins are brought into communication with it by the development of transverse branches in front of the vertebral column (Figs. 176, 177).

**Inferior Vena Cava.**—The development of the inferior vena cava is associated with the formation of two veins, the **subcardinal veins** (Figs. 174, 175). These lie parallel to, and on the ventral aspect of, the cardinal veins, and originate as longitudinal anastomosing channels which link up the tributaries from the mesentery to the cardinal veins; they communicate with the cardinal veins above and below, and also by a series of transverse branches. The two subcardinals are for a time connected with each other in front of the aorta by cross branches, but these disappear and are replaced by a single transverse channel at the level where the renal veins join the cardinals, and at the same level a cross communication is

established on either side between the cardinal and subcardinal (Fig. 175). The portion of the right subcardinal behind this cross communication disappears, while that in front, *i. e.*, the prerenal part, forms a connection with the ductus venosus




FIG. 176.—Diagram showing development of main cross branches between jugulars and between cardinals.

at the point of opening of the hepatic veins, and, rapidly enlarging, receives the blood from the postrenal part of the right cardinal through the cross communica-




FIG. 177.—Diagram showing completion of development of the parietal veins.

tion referred to. In this manner a single trunk, the **inferior vena cava** (Fig. 177), is formed, and consists of the proximal part of the ductus venosus, the prerenal part of the right subcardinal vein, the postrenal part of the right cardinal vein, and the



cross branch which joins these two veins. The left subcardinal disappears, except the part immediately in front of the renal vein, which is retained as the left supra-renal vein. The spermatic (or ovarian) vein opens into the postrenal part of the corresponding cardinal vein. This portion of the right cardinal, as already explained, forms the lower part of the inferior vena cava, so that the right spermatic opens directly into that vessel. The postrenal segment of the left cardinal disappears, with the exception of the portion between the spermatic and renal vein, which is retained as the terminal part of the left spermatic vein.

In consequence of the atrophy of the Wolffian bodies the cardinal veins diminish in size; the primitive jugular veins, on the other hand, become enlarged, owing to the rapid development of the head and brain. They are further augmented by receiving the veins (subclavian) from the upper extremities, and so come to form

the chief veins of the Cuvierian ducts; these ducts gradually assume an almost vertical position in consequence of the descent of the heart into the thorax. The right and left Cuvierian ducts are originally of the same diameter, and are frequently termed the right and left superior *venæ cavæ*. By the development of a transverse branch, the left innominate vein between the two primitive jugular veins, the blood is carried across from the left to the right primitive jugular (Figs. 176, 177). The portion of the right primitive jugular vein between the left innominate and the azygos vein forms the upper part of the superior vena cava of the adult; the lower part of this vessel, *i. e.*, below the entrance of the azygos vein, is formed by the right Cuvierian duct. Below the origin of the transverse branch the left




FIG. 178.—Diagram of veins of head of an embryo four weeks old. (After Mall.)




FIG. 179.—Diagram of veins of head of an embryo five weeks old. (After Mall.)

primitive jugular vein and left Cuvierian duct atrophy, the former constituting the upper part of the highest left intercostal vein, while the latter is represented by the ligament of the left vena cava, *vestigial fold of Marshall*, and the oblique vein of the left atrium, *oblique vein of Marshall* (Fig. 177). Both right and left superior *venæ cavæ* are present in some animals, and are occasionally found in the adult human being. The oblique vein of the left atrium passes downward across the back of the left atrium to open into the coronary sinus, which, as already indicated, represents the persistent left horn of the sinus venosus.

The primitive jugular veins drain the blood from the brain, and their proximal parts form the internal jugular veins. The distal portion of each has been named the *vena capitis medialis* (Fig. 178); it runs on the medial side of the auditory

vesicle and cerebral nerve roots, and the portion of it situated in the neighborhood of the trigeminal nerve becomes the cavernous sinus. The greater part of the *vena capitis medialis* is replaced, however, by the *vena capitis lateralis* (Fig. 179), which is developed on the lateral aspect of the cerebral nerves from the trigeminal to the hypoglossal. This vein receives three principal tributaries, viz., the anterior cerebral vein from the eye, fore-brain, and mid-brain, the middle cerebral vein




FIG. 180.—Diagram of veins of head at the beginning of the third month. (After Mall.)

from the cerebellum, and the posterior cerebral vein from the lower part of the hind-brain. At this stage, therefore, practically the whole of the blood from the brain is drained into the *vena capitis lateralis*, which leaves the skull in company with the facial nerve and opens into the internal jugular vein. The terminal branches of the two anterior cerebral veins anastomose in the middle line and thus form the




FIG. 181.—Diagram of veins of head of an older embryo. (After Mall.)

superior sagittal sinus (Fig. 180). By the backward growth of the cerebral hemispheres this sinus comes to anastomose with the middle and posterior cerebral veins, the latter of which leaves the skull through the jugular foramen; this last anastomosis forms the greater part of the transverse sinus. The *vena capitis lateralis* undergoes atrophy; the middle cerebral vein forms the superior petrosal sinus (Fig. 181). The inferior petrosal sinus is a later formation. The external jugular vein

at first drains the region behind the ear (posterior auricular) and enters the primitive jugular as a lateral tributary. A group of veins from the face and lingual region converge to form a common vein, the *linguo-facial*,<sup>1</sup> which also terminates in the primitive jugular. Later, cross communications develop between the external jugular and the *linguo-facial*, with the result that the posterior group of facial veins is transferred to the external jugular.

**Peculiarities of the Fetal Heart.**—In early fetal life the heart is placed directly under the head and is relatively of large size. Later it assumes its position in the thorax, but lies at first in the middle line; toward the end of pregnancy it gradually becomes oblique in direction. The atrial portion is at first larger than the ventricular part, and the two atria communicate freely through the *foramen ovale*. In consequence of the communication through the *ductus arteriosus*, between the pulmonary artery and the aorta, the contents of the right ventricle are mainly carried into the latter vessel instead of to the lungs, and hence the wall of the right ventricle is as thick as that of the left. At the end of fetal life, however, the left ventricle is thicker than the right, a difference which becomes more and more emphasized after birth.

The fetal circulation and the changes which take place in the circulation after birth are described on pages 616 to 618.




FIG. 182.—Scheme showing relative positions of primary lymph sacs based on the description given by Florence Sabin.

**The Lymphatic Vessels.**—The lymphatic system begins as a series of sacs<sup>2</sup> at the points of junction of certain of the embryonic veins. These lymph-sacs are developed by the confluence of numerous venous capillaries, which at first lose their connections with the venous system, but subsequently, on the formation of the sacs, regain them. The lymphatic system is therefore developmentally an offshoot of the venous system, and the lining walls of its vessels are always endothelial.

In the human embryo the lymph sacs from which the lymphatic vessels are derived are six in number; two paired, the jugular and the posterior lymph-sacs; and two unpaired, the retroperitoneal and the cisterna chyli. In lower mammals

<sup>1</sup> Lewis, *American Journal of Anatomy*, February, 1909, No. 1, vol. ix.

<sup>2</sup> Sabin, *ibid.*

an additional pair, subclavian, is present, but in the human embryo these are merely extensions of the jugular sacs.

The position of the sacs is as follows: (1) jugular sac, the first to appear, at the junction of the subclavian vein with the primitive jugular; (2) posterior sac, at the junction of the iliac vein with the cardinal; (3) retroperitoneal, in the root of the mesentery near the suprarenal glands; (4) cisterna chyli, opposite the third and fourth lumbar vertebræ (Fig. 182). From the lymph-sacs the lymphatic vessels bud out along fixed lines corresponding more or less closely to the course of the embryonic bloodvessels. Both in the body-wall and in the wall of the intestine,<sup>1</sup> the deeper plexuses are the first to be developed; by continued growth of these the vessels in the superficial layers are gradually formed. The thoracic duct is probably formed from anastomosing outgrowths from the jugular sac and cisterna chyli. At its connection with the cisterna chyli it is at first double, but the two vessels soon join.

All the lymph-sacs except the cisterna chyli are, at a later stage, divided up by slender connective tissue bridges and transformed into groups of lymph glands. The lower portion of the cisterna chyli is similarly converted, but its upper portion remains as the adult cisterna.




FIG. 183.—Diagram of a sagittal section of a mammalian embryo. Very early. (After Quain.)

#### DEVELOPMENT OF THE DIGESTIVE AND RESPIRATORY APPARATUS.

**The Digestive Tube.**—As already indicated (page 92), the primitive digestive tube consists of two parts, viz.: (1) the **fore-gut**, within the cephalic flexure, and dorsal to the heart; and (2) the **hind-gut**, within the caudal flexure (Figs. 183, 184). Between these is the wide opening of the yolk-sac, which is gradually narrowed and reduced to a small foramen leading into the vitelline duct. At first the fore-gut and hind-gut end blindly. The anterior end of the fore-gut is separated from

<sup>1</sup> Heuer, *American Journal of Anatomy*, vol. ix, No. 1, February, 1909.

the stomodeum by the buccopharyngeal membrane (Fig. 184); the hind-gut ends in the cloaca, which is closed by the cloacal membrane.

**The Mouth.**—The mouth is developed partly from the stomodeum, and partly from the floor of the anterior portion of the fore-gut. By the growth of the head end of the embryo, and the formation of the cephalic flexure, the pericardial area and the buccopharyngeal membrane come to lie on the ventral surface of the embryo. With the further expansion of the brain, and the forward bulging of the pericardium, the buccopharyngeal membrane is depressed between these two prominences. This depression constitutes the **stomodeum** (Fig. 184). It is lined by ectoderm, and is separated from the anterior end of the fore-gut by the buccopharyngeal membrane. This membrane is devoid of mesoderm, being formed by the apposition of the stomodeal ectoderm with the fore-gut entoderm; at the end of the third week it disappears, and thus a communication is established




FIG. 184.—Human embryo about fifteen days old. Brain and heart represented from right side. Digestive tube and yolk sac in median section. (After His.)

between the mouth and the future pharynx. No trace of the membrane is found in the adult; and the communication just mentioned must not be confused with the permanent isthmus faucium. The lips, teeth, and gums are formed from the walls of the stomodeum, but the tongue is developed in the floor of the pharynx.

The visceral arches extend in a ventral direction between the stomodeum and the pericardium; and with the completion of the mandibular arch and the formation of the maxillary processes, the mouth assumes the appearance of a pentagonal orifice. The orifice is bounded in front by the fronto-nasal process, behind by the mandibular arch, and laterally by the maxillary processes (Fig. 185). With the inward growth and fusion of the palatine processes (Figs. 112, 113), the stomodeum is divided into an upper nasal, and a lower buccal part. Along the free margins of the processes bounding the mouth cavity a shallow groove appears; this is termed the **primary labial groove**, and from the bottom of it a downgrowth of

ectoderm takes place into the underlying mesoderm. The central cells of the ectodermal downgrowth degenerate and a **secondary labial groove** is formed; by the deepening of this, the lips and cheeks are separated from the alveolar processes of the maxillæ and mandible.

**The Salivary Glands.**—The salivary glands arise as buds from the epithelial lining of the mouth; the parotid appears during the fourth week in the angle between the maxillary process and the mandibular arch; the submaxillary appears in the sixth week, and the sublingual during the ninth week in the hollow between the tongue and the mandibular arch.




FIG. 185.—Head end of human embryo of about thirty to thirty-one days. (From model by Peter.)

**The Tongue** (Figs. 186 to 188).—The tongue is developed in the floor of the pharynx, and consists of an anterior or buccal and a posterior or pharyngeal part which are separated in the adult by the V-shaped sulcus terminalis. During the third week there appears, immediately behind the ventral ends of the two halves of the mandibular arch, a rounded swelling named the **tuberculum impar**, which was described by His as undergoing enlargement to form the buccal part of the tongue. More recent researches, however, show that this part of the tongue is mainly, if not entirely, developed from a pair of lateral swellings which rise from

the inner surface of the mandibular arch and meet in the middle line. The tuberculum impar is said to form the central part of the tongue immediately in front of the foramen cecum, but Hammar insists that it is purely a transitory structure and forms no part of the adult tongue. From the ventral ends of the fourth arch




FIG. 186.—Floor of pharynx of human embryo about twenty-six days old. (From model by Peter.)




FIG. 187.—Floor of pharynx of human embryo of about the end of the fourth week. (From model by Peter.)

there arises a second and larger elevation, in the centre of which is a median groove or furrow. This elevation was named by His the **furcula**, and is at first separated from the tuberculum impar by a depression, but later by a ridge, the **copula**, formed by the forward growth and fusion of the ventral ends of the second and third arches. The posterior or pharyngeal part of the tongue is developed from

the copula, which extends forward in the form of a V, so as to embrace between its two limbs the buccal part of the tongue. At the apex of the V a pit-like invagination occurs, to form the thyroid gland, and this depression is represented in the adult by the **foramen cecum** of the tongue. In the adult the union of the anterior and posterior parts of the tongue is marked by the V-shaped **sulcus terminalis**, the apex of which is at the foramen cecum, while the two limbs run lateralward and forward, parallel to, but a little behind, the vallate papillæ.

**The Thyroid Gland.**—The thyroid gland is developed from a median diverticulum (Fig. 189), which appears about the fourth week on the summit of the tuberculum impar, but later is found in the furrow immediately behind the tuberculum (Fig. 186). It grows downward and backward as a tubular duct, which bifurcates and subsequently subdivides into a series of cellular cords, from which the isthmus and lateral lobes of the thyroid gland are developed. As already stated (page 111), the ultimobranchial bodies from the fifth pharyngeal pouches are enveloped by the lateral lobes of the thyroid gland; they undergo atrophy and do not form true thyroid tissue. The connection of the diverticulum with the pharynx is termed the **thyroglossal duct**; its continuity is subsequently interrupted, and it undergoes degeneration, its upper end being represented by the foramen cecum of the tongue, and its lower by the pyramidal lobe of the thyroid gland.




FIG. 188.—Floor of pharynx of human embryo about thirty days old. (From model by Peter.)




FIG. 189.—Scheme showing development of branchial epithelial bodies. (Modified from Kohn.) I, II, III, IV. Branchial pouches.

**The Palatine Tonsils.**—The palatine tonsils are developed from the dorsal angles of the second branchial pouches. The entoderm which lines these pouches grows in the form of a number of solid buds into the surrounding mesoderm. These buds become hollowed out by the degeneration and casting off of their central cells, and by this means the tonsillar crypts are formed. Lymphoid cells accumulate around the crypts, and become grouped to form the lymphoid follicles; the latter, however, are not well-defined until after birth.

**The Thymus.**—The thymus appears in the form of two flask-shaped entodermal diverticula, which arise, one on either side, from the third branchial pouch (Fig. 189), and extend lateralward and backward into the surrounding mesoderm in front of the ventral aortæ. Here they meet and become joined to one another by connective tissue, but there is never any fusion of the thymus tissue proper. The pharyngeal opening of each diverticulum is soon obliterated, but the neck of the flask persists for some time as a cellular cord. By further proliferation of the cells lining the flask, buds of cells are formed, which become surrounded and isolated



by the invading mesoderm. In the latter, numerous lymphoid cells make their appearance, and are aggregated to form lymphoid follicles. These lymphoid cells are probably derivatives of the entodermal cells which lined the original diverticula and their subdivisions. Additional portions of thymus tissue are sometimes developed from the fourth branchial pouches. Thymus continues to grow until the time of puberty and then begins to atrophy.

**The Parathyroid Bodies.**—The parathyroid bodies are developed as outgrowths from the third and fourth branchial pouches (Fig. 189).

A pair of diverticula arise from the fifth branchial pouch and form what are termed the **ultimobranchial bodies** (Fig. 189): these fuse with the thyroid gland, but probably contribute no true thyroid tissue.

**The Hypophysis Cerebri.**—This in the adult consists of a large anterior, and a small posterior, lobe: the former is derived from the ectoderm of the stomodeum, the latter from the floor of the fore-brain. About the fourth week there appears a pouch-like diverticulum of the ectodermal lining of the roof of the stomodeum. This diverticulum, **pouch of Rathke** (Fig. 190), is the rudiment of the anterior lobe of the hypophysis; it extends upward in front of the cephalic end of the notochord and the remnant of the buccopharyngeal membrane and comes into contact with the under surface of the fore-brain. It is then constricted off to form a closed vesicle, but remains for a time connected to the ectoderm of the stomodeum by a solid cord of cells. Masses of epithelial cells form on either side and in the front




FIG. 190.—Vertical sections of the heads of early embryos of the rabbit. Magnified. (From Mihalkovica.) A. From an embryo 5 mm. long. B. From an embryo 6 mm. long. C. Vertical section of the anterior end of the notochord and hypophysis, etc., from an embryo 16 mm. long. In A the buccopharyngeal membrane is still present. In B it is in the process of disappearing, and the stomodeum now communicates with the primitive pharynx. am. Amnion. c. Fore-brain. ch. Notochord. f. Anterior extremity of fore-gut. i. h. Heart. if. Infundibulum. m. Wall of brain cavity. mc. Mid-brain. mo. Hind-brain. p. Original position of hypophyseal diverticulum. py. ph. Pharynx. sp.e. Sphenothmoidal. bc. Central. sp.o. Sphenoccipital parts of basis cranii. tha. Thalamus.

wall of the vesicle, and by the growth between these of a stroma from the mesoderm the development of the anterior lobe is completed. The upwardly directed hypophyseal involution becomes applied to the antero-lateral aspect of a downwardly directed diverticulum from the base of the fore-brain (page 128). This diverticulum constitutes the future infundibulum in the floor of the third ventricle while its inferior extremity becomes modified to form the posterior lobe of the hypophysis. In some of the lower animals the posterior lobe contains nerve cells and nerve fibres, but in man and the higher vertebrates these are replaced by connective tissue. A canal, **craniopharyngeal canal**, is sometimes found extending

from the anterior part of the fossa hypophyseos of the sphenoid bone to the under surface of the skull, and marks the original position of Rathke's pouch; while at




FIG. 191.—Sketches in profile of two stages in the development of the human digestive tube. (His.)  
A  $\times 30$ . B  $\times 20$ .

the junction of the septum of the nose with the palate traces of the stomodeal end are occasionally present (Frazer).

**The Further Development of the Digestive Tube.**—The upper part of the fore-gut becomes dilated to form the pharynx (Fig. 184), in relation to which the branchial arches are developed (see page 108); the succeeding part remains tubular, and with the descent of the stomach is elongated to form the œsophagus. About the fourth week a fusiform dilatation, the future stomach, makes its appearance, and beyond this the gut opens freely into the yolk-sac (Fig. 191, *A* and *B*). The opening is at first wide, but is gradually narrowed into a tubular stalk, the **yolk-stalk** or **vitelline duct**. Between the stomach and the mouth of the yolk-sac the liver diverticulum appears. From the stomach to the rectum the alimentary canal is attached to the notochord by a band of mesoderm, from which the common mesentery of the gut is subsequently developed. The stomach has an additional attachment, viz., to the ventral abdominal wall as far as the umbilicus by the septum transversum. The cephalic portion of the septum takes part in the formation of the Diaphragma, while the caudal portion into which the liver grows forms the **ventral mesogastrium** (Fig. 193). The stomach undergoes a further dilatation, and its two curvatures can be recognized (Figs. 191, *B*, and 192), the greater directed toward the vertebral




FIG. 192.—Front view of two successive stages in the development of the digestive tube. (His.)

column and the lesser toward the anterior wall of the abdomen, while its two surfaces look to the right and left respectively. Behind the stomach the gut undergoes great elongation, and forms a V-shaped loop which projects downward and forward; from the bend or angle of the loop the vitelline duct passes to the umbilicus (Fig. 193). For a time a considerable part of the loop extends beyond the abdominal cavity into the umbilical cord, but by the end of the third month it is withdrawn within the cavity. With the lengthening of the tube, the mesoderm, which attaches it to the future vertebral column and carries the bloodvessels for the supply of the gut, is thinned and drawn out to form the **posterior common mesentery**. The portion of this mesentery attached to the greater curvature of the stomach is named the **dorsal mesogastrium**, and the part which suspends the colon is termed the **mesocolon** (Fig. 194). About the sixth week a diverticulum of the gut appears just behind the opening of the vitelline duct, and indicates the future cecum and vermiform process. The part of the loop on the distal side of the cecal diverticulum increases in diameter and forms the future ascending and transverse portions of the large intestine. Until the fifth month the cecal diverticulum has a uniform calibre, but from this time onward its distal part

remains rudimentary and forms the vermiform process, while its proximal part expands to form the cecum. Changes also take place in the shape and position of the stomach. Its dorsal part or greater curvature, to which the dorsal meso-




FIG. 193.—The primitive mesentery of a six weeks' human embryo, half schematic. (Kollmann.)

gastrium is attached, grows much more rapidly than its ventral part or lesser curvature to which the ventral mesogastrium is fixed. Further, the greater curvature is carried downward and to the left, so that the right surface of the stomach is




FIG. 194.—Abdominal part of digestive tube and its attachment to the primitive or common mesentery. Human embryo of six weeks. (After Toldt.)

now directed backward and the left surface forward (Fig. 195), a change in position which explains why the left vagus nerve is found on the front, and the right vagus on the back of the stomach. The dorsal mesogastrium being attached to the greater

curvature must necessarily follow its movements, and hence it becomes greatly elongated and drawn lateralward and ventralward from the vertebral column, and, as in the case of the stomach, the right surfaces of both the dorsal and ventral mesogastria are now directed backward, and the left forward. In this way a pouch, the *bursa omentalis*, is formed behind the stomach, and this increases in size as the digestive tube undergoes further development; the entrance to the pouch constitutes the future *foramen epiploicum* or *foramen of Winslow*. The duodenum is developed from that part of the tube which immediately succeeds the stomach; it undergoes little elongation, being more or less fixed in position by the liver and




FIG. 195.—Reconstruction of a human embryo of 17 mm. (After Mall.)

pancreas, which arise as diverticula from it. The duodenum is at first suspended by a mesentery, and projects forward in the form of a loop. The loop and its mesentery are subsequently displaced by the transverse colon, so that the right surface of the duodenal mesentery is directed backward, and, adhering to the parietal peritoneum, is lost. The remainder of the digestive tube becomes greatly elongated, and as a consequence the tube is coiled on itself, and this elongation demands a corresponding increase in the width of the intestinal attachment of the mesentery, which becomes folded.

At this stage the small and large intestines are attached to the vertebral column

by a common mesentery, the coils of the small intestine falling to the right of the middle line, while the large intestine lies on the left side.<sup>1</sup>

The gut is now rotated upon itself, so that the large intestine is carried over in front of the small intestine, and the cecum is placed immediately below the liver; about the sixth month the cecum descends into the right iliac fossa, and the large intestine forms an arch consisting of the ascending, transverse, and descending portions of the colon—the transverse portion crossing in front of the duodenum and lying just below the greater curvature of the stomach; within this arch the coils of the small intestine are disposed (Fig. 197). Sometimes the downward progress of the cecum is arrested, so that in the adult it may be found lying immediately below the liver instead of in the right iliac region.




FIG. 196.—Diagrams to illustrate two stages in the development of the digestive tube and its mesentery. The arrow indicates the entrance to the bursa omentalis.

Further changes take place in the bursa omentalis and in the common mesentery, and give rise to the peritoneal relations seen in the adult. The bursa omentalis, which at first reaches only as far as the greater curvature of the stomach, grows downward to form the greater omentum, and this downward extension lies in front of the transverse colon and the coils of the small intestine (Fig. 198). Above, before the pleuro-peritoneal opening is closed, the bursa omentalis sends up a diverticulum on either side of the œsophagus; the left diverticulum soon disappears, but the right is constricted off and persists in most adults as a small sac lying within the thorax on the right side of the lower end of the œsophagus. The anterior layer of the transverse mesocolon is at first distinct from the posterior layer of the greater omentum, but ultimately the two blend, and hence the greater omentum appears as if attached to the transverse colon (Fig. 199). The mesenteries of the ascending and descending parts of the colon disappear in the majority of cases, while that of the small intestine assumes the oblique attachment characteristic of its adult condition.

<sup>1</sup> Sometimes this condition persists throughout life, and it is then found that the duodenum does not cross from the right to the left side of the vertebral column, but lies entirely on the right side of the median plane, where it is continued into the jejunum; the arteries to the small intestine (*aa. intestinales*) also arise from the right instead of the left side of the superior mesenteric artery.



The lesser omentum is formed, as indicated above, by a thinning of the mesoderm or **ventral mesogastrium**, which attaches the stomach and duodenum to the anterior abdominal wall. By the subsequent growth of the liver this leaf of mesoderm is divided into two parts, viz., the lesser omentum between the stomach and liver, and the falciform and coronary ligaments between the liver and the abdominal wall and Diaphragma (Fig. 198).

**The Rectum and Anal Canal.**—The hind-gut is at first prolonged backward into the body-stalk as the tube of the allantois; but, with the growth and flexure of the tail-end of the embryo, the body-stalk, with its contained allantoic tube, is carried forward to the ventral aspect of the body, and consequently a bend is formed at the junction of the hind-gut and allantois. This bend becomes dilated into a pouch, which constitutes the **entodermal cloaca**; into its dorsal part the hind-gut opens, and from its ventral part the allantois passes forward. At a later stage the Wolffian and Müllerian ducts open into its ventral portion. The cloaca is, for a time, shut



FIG. 197.—Final disposition of the intestines and their vascular relations. (Jonnescq.) A. Aorta. H. Hepatic artery. M, Col. Branches of superior mesenteric artery. m, m'. Branches of inferior mesenteric artery. S. Splenic artery.




FIG. 198.—Schematic figure of the bursa omentalis, etc. Human embryo of eight weeks. (Kollmann.)

off from the anterior by a membrane, the **cloacal membrane**, formed by the apposition of the ectoderm and entoderm, and reaching, at first, as far forward as the future umbilicus. Behind the umbilicus, however, the mesoderm subsequently extends to form the lower part of the abdominal wall and symphysis pubis. By the growth of the surrounding tissues the cloacal membrane comes to lie at the bottom of a depression, which is lined by ectoderm and named the **ectodermal cloaca** (Fig. 200).

The entodermal cloaca is divided into a dorsal and a ventral part by means of a partition, the **urorectal septum** (Fig. 201), which grows downward from the ridge separating the allantoic from the cloacal opening of the intestine and ultimately fuses with the cloacal membrane and divides it into an anal and a urogenital part. The dorsal part of the cloaca forms the rectum, and the anterior part of the urogenital sinus and bladder. For a time a communication named the **cloacal duct** exists between the two parts of the cloaca below the urorectal septum; this duct



occasionally persists as a passage between the rectum and urethra. The anal canal is formed by an invagination of the ectoderm behind the urorectal septum.




FIG. 199.—Diagrams to illustrate the development of the greater omentum and transverse mesocolon.




FIG. 200.—Tail end of human embryo from fifteen to eighteen days old. (From model by Keibel.)




FIG. 201.—Cloaca of human embryo from twenty-five to twenty-seven days old. (From model by Keibel.)




FIG. 202.—Tail end of human embryo, from eight and a half to nine weeks old. (From model by Keibel.)

This invagination is termed the **proctodæum**, and it meets with the entoderm of the hind-gut and forms with it the **anal membrane**. By the absorption of this membrane the anal canal becomes continuous with the rectum (Fig. 202). A small part of the hind-gut projects backward beyond the anal membrane; it is named the **post-anal gut** (Fig. 200), and usually becomes obliterated and disappears.<sup>1</sup>

**The Liver.**—The liver arises in the form of a diverticulum or hollow outgrowth from the ventral surface of that portion of the gut which afterward becomes the descending part of the duodenum (Figs. 191, 203). This diverticulum is lined by entoderm, and grows upward and forward into the septum transversum, a mass of mesoderm between the vitelline duct and the pericardial cavity, and there gives off two solid buds of cells which represent the right and the left lobes of the liver. The solid buds of cells grow into columns or cylinders, termed the **hepatic cylinders**, which branch and anastomose to form a close meshwork. This network invades the vitelline and umbilical veins, and breaks up these vessels into a series of capillary-like vessels termed **sinusoids** (Minot), which ramify in the meshes of the cellular network and ultimately form the venous capillaries of the liver. By the continued




FIG. 203.—Liver with the septum transversum. Human embryo 3 mm. long. (After model and figure by His.)

growth and ramification of the hepatic cylinders the mass of the liver is gradually formed. The original diverticulum from the duodenum forms the common bile-duct, and from this the cystic duct and gall-bladder arise as a solid outgrowth which later acquires a lumen. The opening of the common duct is at first in the ventral wall of the duodenum; later, owing to the rotation of the gut, the opening is carried to the left and then dorsalward to the position it occupies in the adult.

As the liver undergoes enlargement, both it and the ventral mesogastrium of the fore-gut are gradually differentiated from the septum transversum; and from the under surface of the latter the liver projects downward into the abdominal cavity. By the growth of the liver the ventral mesogastrium is divided into two parts, of which the anterior forms the falciform and coronary ligaments, and the posterior the lesser omentum. About the third month the liver almost fills the abdominal cavity, and its left lobe is nearly as large as its right. From this period

<sup>1</sup> Consult, in this connection, the following article: "A Contribution to the Morphology of the Human Urino-genital Tract," by D. Berry Hart, M.D., F.R.C.P.E., *Journal of Anatomy and Physiology*, April, 1901, vol. xxxv.

the relative development of the liver is less active, more especially that of the left lobe, which actually undergoes some degeneration and becomes smaller than the right; but up to the end of fetal life the liver remains relatively larger than in the adult.

**The Pancreas** (Figs. 204, 205).—The pancreas is developed in two parts, a dorsal and a ventral. The former arises as a diverticulum from the dorsal aspect of the duodenum a short distance above the hepatic diverticulum, and, growing upward and backward into the dorsal mesogastrium, forms a part of the head and uncinete process and the whole of the body and tail of the pancreas. The ventral




FIG. 204.—Pancreas of a human embryo of five weeks. (Kollmann.)




FIG. 205.—Pancreas of a human embryo at end of sixth week. (Kollmann.)

part appears in the form of a diverticulum from the primitive bile-duct and forms the remainder of the head and uncinete process of the pancreas. The duct of the dorsal part (accessory pancreatic duct) therefore opens independently into the duodenum, while that of the ventral part (pancreatic duct) opens with the common bile-duct. About the sixth week the two parts of the pancreas meet and fuse and a communication is established between their ducts. After this has occurred the terminal part of the accessory duct, *i. e.*, the part between the duodenum and the point of meeting of the two ducts, undergoes little or no enlargement, while




FIG. 206.—Schematic and enlarged cross-section through the body of a human embryo in the region of the mesogastrium. Beginning of third month. (Toldt.)

the pancreatic duct increases, in size and forms, the main duct of the gland. The opening of the accessory duct into the duodenum is sometimes obliterated, and even when it remains patent it is probable that the whole of the pancreatic secretion is conveyed through the pancreatic duct.

At first the pancreas is directed upward and backward between the two layers of the dorsal mesogastrium, which give to it a complete peritoneal investment, and its surfaces look to the right and left. With the change in the position of the stomach the dorsal mesogastrium is drawn downward and to the left, and the right side of the pancreas is directed backward and the left forward (Fig. 206). The

right surface becomes applied to the posterior abdominal wall, and the peritoneum which covered it undergoes absorption (Fig. 207); and thus, in the adult, the gland appears to lie behind the peritoneal cavity.




FIG. 207.—Section through same region as in Fig. 206, at end of third month. (Toldt.)

**The Spleen** (Fig. 194).—Although the spleen belongs to the group of ductless glands, its development may be conveniently referred to here. It appears about the fifth week as a localized thickening of the mesoderm in the dorsal mesogastrium above the tail of the pancreas. With the change in position of the stomach the spleen is carried to the left, and comes to lie behind the stomach and in contact with the left kidney. The part of the dorsal mesogastrium which intervened between the spleen and the greater curvature of the stomach forms the gastro-splenic ligament.




FIG. 208.—The head and neck of a human embryo thirty-two days old, seen from the ventral surface. The floor of the mouth and pharynx have been removed. (His.)

**The Respiratory Organs.**—The rudiment of the respiratory organs appear as a median longitudinal groove in the ventral wall of the pharynx. The groove deepens and its lips fuse to form a septum which grows from below upward and converts the groove into a tube, the **laryngo-tracheal tube** (Fig. 208), the cephalic end of which opens into the pharynx by a slit-like aperture formed by the persistent anterior part of the groove. The tube is lined by entoderm from which the epithelial lining of the respiratory tract is developed. The cephalic part of the tube



becomes the larynx, and its next succeeding part the trachea, while from its caudal end two lateral outgrowths, the right and left lung buds, arise, and from them the bronchi and lungs are developed. The first rudiment of the larynx consists of two **arytenoid swellings**, which appear, one on either side of the cephalic end of the laryngo-tracheal groove, and are continuous in front of the groove with a transverse ridge (**furcula of His**) which lies between the ventral ends of the third branchial arches and from which the epiglottis is subsequently developed (Figs. 187, 188). After the separation of the trachea from the oesophagus, the arytenoid swellings come into contact with one another and with the back of the epiglottis, and the entrance to the larynx assumes the form of a T-shaped cleft, the margins of the cleft adhere to one another and the laryngeal entrance is for a time occluded. The mesodermal wall of the tube becomes condensed to form the cartilages of the larynx and trachea. The arytenoid swellings are differentiated into the arytenoid and corniculate cartilages, and the folds joining them to the epiglottis form the aryepiglottic folds in which the cuneiform cartilages are developed as derivatives of the epiglottis. The thyroid cartilage appears as two lateral plates, each chondrified from two centres and united in the mid-ventral line by membrane in which an additional centre of chondrification develops. The cricoid cartilage arises from two cartilaginous centres, which soon unite ventrally and gradually extend and ultimately fuse on the dorsal aspect of the tube.

J. Ernest Frazer<sup>1</sup> has made an important investigation on the development of the larynx, and the following are his main conclusions:

The opening of the pulmonary diverticulum lies between the two fifth arch masses and behind a "central mass" in the middle line—the proximal end of the diverticulum is compressed between the fifth arch masses. The fifth arch is joined by the fourth to form a "lateral mass" on each side of the opening, and these "lateral masses" grow forward and overlap the central mass and so form a secondary transverse cavity, which is really a part of the cavity of the pharynx. The two parts of the cavity of the larynx are separated in the adult by a line drawn back along the vocal fold and then upward along the border of the arytenoid eminence to the interarytenoid notch. The arytenoid and cricoid are developed in the fifth arch mass. The thyroid is primarily a fourth arch derivative, and if it has a fifth arch element this is a later addition. The epiglottis is derived from the "central mass," and has a third arch element in its oral and upper aspect; the arch value of the "central mass" is doubtful.



FIG. 209.—Lung buds from a human embryo of about four weeks, showing commencing lobulations. (His.)




FIG. 210.—Lungs of a human embryo more advanced in development. (His.)

The right and left lung buds grow out behind the ducts of Cuvier, and are at first symmetrical, but their ends soon become lobulated, three lobules appearing on the right, and two on the left; these subdivisions are the early indications of the corresponding lobes of the lungs (Figs. 209, 210). The buds undergo further subdivision and ramification, and ultimately end in minute expanded extremities—the infundibula of the lung. After the sixth month the air-sacs begin to make their appearance on the infundibula in the form of minute pouches. The pulmonary arteries are derived from the sixth aortic arches. During the course of their development the lungs migrate in a caudal direction, so that by the time of birth

<sup>1</sup> Journal of Anatomy and Physiology, vol. xlii.

the bifurcation of the trachea is opposite the fourth thoracic vertebra. As the lungs grow they project into that part of the coelom which will ultimately form the pleural cavities, and the superficial layer of the mesoderm enveloping the lung rudiment expands on the growing lung and is converted into the pulmonary pleura.

### DEVELOPMENT OF THE BODY CAVITIES.

In the human embryo described by Peters the mesoderm outside the embryonic disk is split into two layers enclosing an extra-embryonic coelom; there is no trace of an intra-embryonic coelom. At a later stage four cavities are formed within the embryo, viz., one on either side within the mesoderm of the pericardial area, and one in either lateral mass of the general mesoderm. All these are at first independent of each other and of the extra-embryonic coelom, but later they become continuous. The two cavities in the general mesoderm unite on the ventral aspect of the gut and form the pleuro-peritoneal cavity, which becomes continuous with the remains of the extra-embryonic coelom around the umbilicus; the two cavities in the pericardial area rapidly join to form a single pericardial cavity, and from this two lateral




FIG. 211.—Figure obtained by combining several successive sections of a human embryo of about the fourth week (From Kollmann.) The upper arrow is in the pleuroperitoneal opening, the lower in the pleuropericardial.

diverticula extend caudalward to open into the pleuro-peritoneal cavity (Fig. 211). Between the two latter diverticula is a mass of mesoderm containing the ducts of Cuvier, and this is continuous ventrally with the mesoderm in which the umbilical veins are passing to the sinus venosus. A septum of mesoderm thus extends across the body of the embryo. It is attached in front to the body-wall between the pericardium and umbilicus; behind to the body-wall at the level of the second cervical segment; laterally it is deficient where the pericardial and pleuro-peritoneal cavities communicate, while it is perforated in the middle line by the foregut. This partition is termed the **septum transversum**, and is at first a bulky plate of tissue. As development proceeds the dorsal end of the septum is carried gradually caudalward, and when it reaches the fifth cervical segment muscular tissue with the phrenic nerve grow into it. It continues to recede, however, until it reaches the position of the adult Diaphragma on the bodies of the upper lumbar vertebræ. As already described (page 174), the liver buds grow into the septum transversum and undergo development there.

The lung buds meantime have grown out from the fore-gut, and project laterally into the forepart of the pleuro-peritoneal cavity; the developing stomach and liver

are imbedded in the septum transversum; caudal to this the intestines project into the back part of the pleuro-peritoneal cavity (Fig. 212). Owing to the descent of the dorsal end of the septum transversum the lung buds come to lie above the




FIG. 212.—Upper part of coelom of human embryo of 6.8 mm., seen from behind. (From model by Piper.)

septum and thus pleural and peritoneal portions of the pleuro-peritoneal cavity (still, however, in free communication with one another) may be recognized; the pericardial cavity opens into the pleural part.

The ultimate separation of the permanent cavities from one another is effected by the growth of a ridge of tissue on either side from the mesoderm surrounding




FIG. 213.—Diagram of transverse section through rabbit embryo. (After Keith.)

the duct of Cuvier (Figs. 211, 212). The front part of this ridge grows across and obliterates the pleuro-pericardial opening; the hinder part grows across the pleuro-peritoneal opening.



With the continued growth of the lungs the pleural cavities are pushed forward in the body-wall toward the ventral median line, thus separating the pericardium from the lateral thoracic walls (Fig. 213). The further development of the peritoneal cavity has been described with the development of the digestive tube (page 168 *et seq.*).




FIG. 214.—The thoracic aspect of the Diaphragm of a newly born child in which the communication between the peritoneum and pleura has not been closed on the left side; the position of the opening is marked on the right side by the spinocostal hiatus. (After Keith.)

#### DEVELOPMENT OF THE URINARY AND GENERATIVE ORGANS.

The urinary and generative organs are developed from the intermediate cell-mass which is situated between the primitive segments and the lateral plates of mesoderm. The permanent organs of the adult are preceded by a set of structures which are purely embryonic, and which with the exception of the ducts disappear almost entirely before the end of fetal life. These embryonic structures are on either side; the **pronephros**, the **mesonephros**, the **metanephros**, and the **Wolffian** and **Müllerian ducts**. The pronephros disappears very early; the structural elements of the mesonephros mostly degenerate, but in their place is developed the genital gland in association with which the Wolffian duct remains as the duct of the male genital gland, the Müllerian as that of the female; some of the tubules of the metanephros form part of the permanent kidney.

**The Pronephros and Wolffian Duct.**—In the outer part of the intermediate cell-mass, immediately under the ectoderm, in the region from the fifth cervical to the third thoracic segments, a series of short evaginations from each segment grow dorsalward and extend caudalward, fusing successively from before backward to form the **pronephric duct**. This continues to grow caudalward until it opens into the ventral part of the cloaca; beyond the pronephros it is termed the **Wolffian duct**.

The original evaginations form a series of transverse tubules each of which communicates by means of a funnel-shaped ciliated opening with the coelomic cavity, and in the course of each duct a glomerulus also is developed. Secondary glomeruli are formed ventral to each of the others, and the complete group constitutes the **pronephros**. The pronephros undergoes rapid atrophy and disappears.

**The Mesonephros, Müllerian Duct, and Genital Gland.**—On the medial side of the Wolffian duct, from the sixth cervical to the third lumbar segments, a series of tubules, the **Wolffian tubules** (Fig. 215), is developed; at a later stage in development they increase in number by outgrowths from the original tubules. These tubules first appear as solid masses of cells, which later become hollowed in the

centre; one end grows toward and finally opens into the Wolffian duct, the other dilates and is invaginated by a tuft of capillary bloodvessels to form a glomerulus. The tubules collectively constitute the **mesonephros** or **Wolffian body** (Figs. 195, 216). By the fifth or sixth week this body forms an elongated spindle-shaped structure, termed the **urogenital fold** (Fig. 215), which projects into the coelomic cavity at the side of the dorsal mesentery, reaching from the septum transversum




FIG. 215.—Section of the urogenital fold of a chick embryo of the fourth day. (Waldeyer.)

in front to the fifth lumbar segment behind; in this fold the reproductive glands are developed. The Wolffian bodies persist and form the permanent kidneys in fishes and amphibians, but in reptiles, birds, and mammals, they atrophy and for the most part disappear coincidently with the development of the permanent kidneys. The atrophy begins during the sixth or seventh week and rapidly proceeds, so that by the beginning of the fifth month only the ducts and a few of the tubules remain.

In the male the Wolffian duct persists, and forms the tube of the epididymis, the ductus deferens and the ejaculatory duct, while the seminal vesicle arises during the third month as a lateral diverticulum from its hinder end. A large part of the head end of the mesonephros atrophies and disappears; of the remainder the anterior tubules form the efferent ducts of the testis; while the posterior tubules are represented by the ductuli aberrantes, and by the paradidymis, which is sometimes found in front of the spermatic cord above the head of the epididymis (Fig. 219, C).

In the female the Wolffian bodies and ducts atrophy. The remains of the Wolffian tubules are represented by the **epoöphoron** or **organ of Rosenmüller**, and the **paroöphoron**, two small collections of rudimentary blind tubules which are situated in the mesosalpinx (Fig. 217). The lower part of the Wolffian duct




FIG. 216.—Enlarged view from the front of the left Wolffian body before the establishment of the distinction of sex. (From Farre, after Kobelt.) a, b, c, d. Tubular structure of the Wolffian body. e. Wolffian duct. f. Its upper extremity. g. Its termination in z, the urogenital sinus. h. The duct of Müller. i. Its upper, funnel-shaped extremity. k. Its lower end, terminating in the urogenital sinus. l. The genital gland.

disappears, while the upper part persists as the longitudinal duct of the epoöphoron or duct of Gärtner<sup>1</sup> (Fig. 219, B).

**The Müllerian Ducts.**—Shortly after the formation of the Wolffian ducts a second pair of ducts is developed; these are named the **Müllerian ducts**. Each arises on the lateral aspect of the corresponding Wolffian duct as a tubular invagination of the cells lining the coelom (Fig. 215). The orifice of the invagination




FIG. 217.—Broad ligament of adult, showing epoöphoron. (From Farre, after Kobelt.) *a, a.* Epoöphoron formed from the upper part of the Wolffian body. *b.* Remains of the uppermost tubes sometimes forming appendices. *c.* Middle set of tubes. *d.* Some lower atrophied tubes. *e.* Atrophied remains of the Wolffian duct. *f.* The terminal bulb or hydatid. *h.* The uterine tube, originally the duct of Müller. *i.* Appendix attached to the extremity. *l.* The ovary.

remains patent, and undergoes enlargement and modification to form the abdominal ostium of the uterine tube. The ducts pass backward lateral to the Wolffian ducts, but toward the posterior end of the embryo they cross to the medial side of these ducts, and thus come to lie side by side between and behind the latter—the four ducts forming what is termed the **genital cord** (Fig. 218). The Müllerian ducts end in an epithelial elevation, the **Müllerian eminence**, on the ventral part of the cloaca between the orifices of the Wolffian ducts; at a later date they open into the cloaca in this situation.




FIG. 218.—Urogenital sinus of female human embryo of eight and a half to nine weeks old. (From model by Keibel)

In the male the Müllerian ducts atrophy, but traces of their anterior ends are represented by the **appendices testis** (*hydatids of Morgagni*), while their terminal fused portions form the utriculus in the floor of the prostatic portion of the urethra (Fig. 219, C).


In the female the Müllerian ducts persist and undergo further development. The portions which lie in the genital core fuse to form the uterus and vagina; the parts in front of this cord remain separate, and each forms the corresponding uterine tube—the abdominal ostium of which is developed from the anterior extremity of the original tubular invagination from the coelom (Fig. 219, B). The

fusion of the Müllerian ducts begins in the third month, and the septum formed by their fused medial walls disappears from below upward, and thus the cavities


<sup>1</sup> Berry Hart (*op. cit.*) has described the Wolffian ducts as ending at the site of the future hymen in bulbous enlargements, which he has named the *Wolffian bulbs*; and states that the hymen is formed by these bulbs, "aided by a special involution from below of the cells lining the urogenital sinus." He further believes that "the lower third of the vagina is due to the coalescence of the upper portion of the urogenital sinus and the lower ends of the Wolffian ducts," and that "the epithelial lining of the vagina is derived from the Wolffian bulbs." He also regards the colliculus seminalis of the male urethra as being formed from the lower part of the Wolffian ducts.

FIG. 219.—Diagrams to show the development of male and female generative organs from a common type. (Allen Thomson.)


A.—Diagram of the primitive urogenital organs in the embryo previous to sexual distinction. 3. Ureter. 4. Urinary bladder. 5. Trachus. *cl.* Cloaca. *cp.* Elevation which becomes clitoris or penis. *i.* Lower part of the intestine. *ls.* Fold of integument from which the labia majora or scrotum are formed. *m, m.* Right and left Müllerian ducts uniting together and running with the Wolffian ducts in *gc.* the genital cord. *ot.* The genital ridge from which either the ovary or testis is formed. *ug.* Sinus urogenitalis. *W.* Left Wolffian body. *w, w.* Right and left Wolffian ducts.



B.—Diagram of the female type of sexual organs. *C.* Greater vestibular gland, and immediately above it the urethra. *cc.* Corpus cavernosum clitoridis. *dG.* Remains of the left Wolffian duct, such as give rise to the duct of Gärtner, represented by dotted lines; that of the right side is marked *w.* *f.* The abdominal opening of the left uterine tube. *g.* Round ligament, corresponding to gubernaculum. *h.* Situation of the hymen. *i.* Lower part of the intestine. *l.* Labium major. *n.* Labium minus. *o.* The left ovary. *po.* Epophoron. *ac.* Corpus cavernosum urethrae. *u.* Uterus. The uterine tube of the right side is marked *m.* *v.* Vulva. *va.* Vagina. *W.* Scattered remains of Wolffian tubes near it (paraphoron of Waldeyer).



C.—Diagram of the male type of sexual organs. *C.* Bulbo-urethral gland of one side. *cp.* Corpora cavernosa penis cut short. *z.* Caput epididymis. *g.* The gubernaculum. *i.* Lower part of the intestine. *m.* Müllerian duct, the upper part of which remains as the hydatid of Morgagni; the lower part, represented by a dotted line descending to the prostatic utricle, constitutes the occasionally existing cornu and tube of the uterus masculinus. *pr.* The prostate. *s.* Scrotum. *sp.* Corpus cavernosum urethrae. *t.* Testis in the place of its original formation. *t'* together with the dotted lines above, indicates the direction in which the testis and epididymis descend from the abdomen into the scrotum. *vd.* Ductus deferens. *vh.* Ductus aberrans. *va.* The vesicula seminalis. *W.* Scattered remains of the Wolffian body, constituting the organ of Giralde's, or the paraphymus of Waldeyer.



of the vagina and uterus are produced. About the fifth month an annular constriction marks the position of the neck of the uterus, and after the sixth month the walls of the uterus begin to thicken. For a time the vagina is represented by a solid rod of epithelial cells. A ring-like outgrowth of this epithelium occurs at the lower end of the uterus and marks the future vaginal fornices; about the fifth or sixth month the lumen of the vagina is produced by the breaking down of the central cells of the epithelium. The hymen represents the remains of the Müllerian eminence.

**Genital Glands.**—The first appearance of the genital gland is essentially the same in the two sexes, and consists in a thickening of the epithelial layer which lines the peritoneal cavity on the medial side of the urogenital fold (Fig. 215). The thick plate of epithelium extends deeply, pushing before it the mesoderm and forming a distinct projection. This is termed the **genital ridge** (Fig. 215), and from it the testis in the male and the ovary in the female are developed. At first the mesonephros and genital ridge are suspended by a common mesentery, but as the embryo grows the genital ridge gradually becomes pinched off from the mesonephros, with which it is at first continuous, though it still remains connected to the remnant of this body by a fold of peritoneum, the **mesorchium** or **mesovarium** (Fig. 220). About the seventh week the distinction of sex in the genital ridge begins to be perceptible.




FIG. 220.—Transverse section of human embryo eight and a half to nine weeks old. (From model by Keibel.)

**The Ovary.**—The ovary, thus formed from the genital ridge, is at first a mass of cells derived from the coelomic epithelium; later the mass is differentiated into a central part or medulla (Fig. 221) covered by a surface layer, the **germinal epithelium**. Between the cells of the germinal epithelium a number of larger cells, the **primitive ova**, are found, and these are carried into the subjacent stroma by bud-like ingrowths (**genital cords**) of the germinal epithelium (Fig. 222). The surface epithelium ultimately forms the permanent epithelial covering of this organ; it soon loses its connection

with the central mass, and a tunica albuginea develops between them. The ova are chiefly derived from the cells of the central mass; these are separated from one another by the growth of connective tissue in an irregular manner; each ovum assumes a covering of connective tissue (follicle) cells, and in this way the rudiments of the ovarian follicles are formed (Fig. 222). According to Beard the primitive ova are early set apart during the segmentation of the ovum and migrate into the germinal ridge.

Waldeyer taught that the primitive germ cells are derived from the "germinal epithelium," covering the genital ridge. Beard,<sup>1</sup> on the other hand, maintains that in the skate they are not derived from this epithelium, but are probably formed during the later stages of cell cleavage, before there is any trace of an embryo; and a similar view was advanced by Nussbaum as to their origin in amphibia. Beard says: "At the close of segmentation many of the future germ cells lie in the segmentation cavity just beneath the site of the future embryo, and there is no doubt they subsequently wander into it." The germ cells, "after they enter the resting phase, are

<sup>1</sup> Journal of Anatomy and Physiology, vol. xxxviii.

sharply marked off from the cells of the embryo by entire absence of mitoses among them." They can be further recognized by their irregular form and amœboid processes, and by the fact




FIG. 221.—Longitudinal section of ovary of cat embryo of 9.4 cm. long. Schematic. (After Cœrt.)

that their cytoplasm has no affinity for ordinary stains, but assumes a brownish tinge when treated by osmic acid. The path along which they travel into the embryo is a very definite one, viz., "from the yolk sac upward between the splanchnopleure and gut in the hinder portion of the




FIG. 222.—Section of the ovary of a newly born child. (Waldeyer.)

embryo." This pathway, named by Beard the **germinal path**, "leads them directly to the position which they ought finally to take up in the 'germinal ridge' or nidus." A considerable number



apparently never reach their proper destination, since "vagrant germ cells are found in all sorts of places, but more particularly on the mesentery." Some of these may possibly find their way into the germinal ridge; some probably undergo atrophy, while others may persist and become the seat of dermoid tumors.

**The Testis.**—The testis is developed in much the same way as the ovary. Like the ovary, in its earliest stages it consists of a central mass of epithelium covered by a surface epithelium. In the central mass a series of cords appear (Fig. 223), and the periphery of the mass is converted into the tunica albuginea, thus excluding the surface epithelium from any part in the formation of the tissue of the testis. The cords of the central mass run together toward the future hilus and form a network which ultimately becomes the rete testis. From the cords the seminiferous tubules are developed, and between them connective tissue septa extend. The seminiferous tubules become connected with outgrowths from the Wolffian body, which, as before mentioned, form the efferent ducts of the testis.

**Descent of the Testes.**—The testes, at an early period of fetal life, are placed at the back part of the abdominal cavity, behind the peritoneum, and each is attached by a peritoneal fold, the **mesorchium**, to the mesonephros. From the front of the mesonephros a fold of peritoneum termed the **inguinal fold** grows forward to meet and fuse with a peritoneal fold, the **inguinal crest**, which grows backward from the antero-lateral abdominal wall. The testis thus acquires an indirect connection with the anterior abdominal wall; and at the same time a portion of the peritoneal cavity lateral to these fused folds is marked off as the future saccus vaginalis. In the inguinal crest a peculiar structure, the **gubernaculum testis**, makes its appearance. This is at first a slender band, extending from that part of the skin of the groin which afterward forms the scrotum through the inguinal




FIG. 223.—Section of a genital cord of a human embryo 3.5 cm. long. (Felix and Bühler.)

canal to the body and epididymis of the testis. As development advances, the peritoneum enclosing the gubernaculum forms two folds, one above the testis and the other below it. The one above the testis is the **plica vascularis**, and contains ultimately the internal spermatic vessels; the one below, the **plica gubernatrix**, contains the lower part of the gubernaculum, which has now grown into a thick cord; it ends below at the abdominal inguinal ring in a tube of peritoneum, the **saccus vaginalis**, which protrudes itself down the inguinal canal. By the fifth month the lower part of the gubernaculum has become a thick cord, while the upper part has disappeared. The lower part now consists of a central core of unstriated muscle fibre, and outside this of a firm layer of striped elements, connected, behind the peritoneum, with the abdominal wall. As the scrotum develops, the main portion of the lower end of the gubernaculum is carried, with the skin to which it is attached, to the bottom of this pouch; other bands are carried to the medial side of the thigh and to the perineum. The tube of peritoneum constituting the saccus vaginalis projects itself downward into the inguinal canal, and emerges at the cutaneous inguinal ring, pushing before it a part of the Obliquus internus and the aponeurosis of the Obliquus externus, which form respectively

the Cremaster muscle and the intercrural fascia. It forms a gradually elongating pouch, which eventually reaches the bottom of the scrotum, and behind this pouch the testis is drawn by the growth of the body of the fetus, for the gubernaculum does not grow commensurately with the growth of other parts, and therefore the testis, being attached by the gubernaculum to the bottom of the scrotum, is prevented from rising as the body grows, and is drawn first into the inguinal canal and eventually into the scrotum. It seems certain also that the gubernacular cord becomes shortened as development proceeds, and this assists in causing the testis to reach the bottom of the scrotum. By the end of the eighth month the testis has reached the scrotum, preceded by the saccus vaginalis, which communicates by its upper extremity with the peritoneal cavity. Just before birth the upper part of the saccus vaginalis usually becomes closed, and this obliteration extends gradually downward to within a short distance of the testis. The process of peritoneum surrounding the testis is now entirely cut off from the general peritoneal cavity and constitutes the *tunica vaginalis*.

**Descent of the Ovaries.**—In the female there is also a gubernaculum, which effects a considerable change in the position of the ovary, though not so extensive a change as in that of the testis. The gubernaculum in the female lies in contact with the fundus of the uterus and contracts adhesions to this organ, and thus the ovary is prevented from descending below this level. The part of the gubernaculum between the ovary and the uterus becomes ultimately the proper ligament of the ovary, while the part between the uterus and the labium majus forms the round ligament of the uterus. A pouch of peritoneum analogous to the saccus vaginalis in the male accompanies it along the inguinal canal: it is called the **canal of Nuck**. In rare cases the gubernaculum may fail to contract adhesions to the uterus, and then the ovary descends through the inguinal canal into the labium majus, and under these circumstances its position resembles that of the testis.




FIG. 224.—Tail end of human embryo twenty-five to twenty-nine days old. (From model by Keibel.)



FIG. 225.—Tail end of human embryo thirty-two to thirty-three days old. (From model by Keibel.)

**The Metanephros and the Permanent Kidney.**—The rudiments of the permanent kidneys make their appearance about the end of the first or the beginning of the second month. Each kidney has a two-fold origin, part arising from the metanephros, and part as a diverticulum from the hind-end of the Wolffian duct, close to where the latter opens into the cloaca (Figs. 224, 225). The metanephros arises in the intermediate cell mass, caudal to the mesonephros, which it resembles in structure. The diverticulum from the Wolffian duct grows dorsalward and forward along the posterior abdominal wall, where its blind extremity expands and subsequently divides into several buds, which form the rudiments of the pelvis and calices of the kidney; by continued growth and subdivision it gives rise to the collecting tubules of the kidney. The proximal portion of the diverticulum becomes the ureter. The secretory tubules are developed from the

metanephros, which is moulded over the growing end of the diverticulum from the Wolffian duct. The tubules of the metanephros, unlike those of the pronephros and mesonephros, do not open into the Wolffian duct. One end expands to form a glomerulus, while the rest of the tubule rapidly elongates to form the convoluted and straight tubules, the loops of Henle, and the connecting tubules; these last

join and establish communications with the collecting tubules derived from the ultimate ramifications of the diverticulum from the Wolffian duct. The mesoderm around the tubules becomes condensed to form the connective tissue of the kidney. The ureter opens at first into the hind-end of the Wolffian duct; after the sixth week it separates from the Wolffian duct, and opens independently into the part of the cloaca which ultimately becomes the bladder (Figs. 226, 227).

The secretory tubules of the kidney become arranged into pyramidal masses or lobules, and the lobulated condition of the kidneys exists for some time after birth, while traces of

it may be found even in the adult. The kidney of the ox and many other animals remains lobulated throughout life.

**The Urinary Bladder.**—The bladder is formed partly from the entodermal cloaca and partly from the ends of the Wolffian ducts; the allantois takes no share in its formation. After the separation of the rectum from the dorsal part of the




FIG. 226.—Tail end of human embryo; from eight and a half to nine weeks old. (From model by Keibel.)




FIG. 227.—Primitive kidney and bladder, from a reconstruction. (After Schreiner.)

cloaca (p. 172), the ventral part becomes subdivided into three portions: (1) an anterior **vesico-urethral portion**, continuous with the allantois—into this portion the Wolffian ducts open; (2) an intermediate narrow channel, the **pelvic portion**; and (3) a posterior **phallic portion**, closed externally by the urogenital membrane (Fig. 227). The second and third parts together constitute the **urogenital sinus**. The

vesico-urethral portion absorbs the ends of the Wolffian ducts and the associated ends of the renal diverticula, and these give rise to the trigone of the bladder and part of the prostatic urethra. The remainder of the vesico-urethral portion forms the body of the bladder and part of the prostatic urethra; its apex is prolonged to the umbilicus as a narrow canal, which later is obliterated and becomes the medial umbilical ligament (urachus).




FIG. 228.—Stages in the development of the external sexual organs in the male and female. (Drawn from the Ecker-Ziegler models.)

**The Prostate.**—The prostate originally consists of two separate portions, each of which arises as a series of diverticular buds from the epithelial lining of the urogenital sinus and vesico-urethral part of the cloaca, between the third and fourth months. These buds become tubular, and form the glandular substance of the two lobes, which ultimately meet and fuse behind the urethra and also extend on to its ventral aspect. The isthmus or middle lobe is formed as an extension of the lateral

lobes between the common ejaculatory ducts and the bladder. **Skene's ducts** in the female urethra are regarded as the homologues of the prostatic glands.

The **bulbo-urethral glands of Cowper** in the male, and **greater vestibular glands of Bartholin** in the female, also arise as diverticula from the epithelial lining of the urogenital sinus.

**The External Organs of Generation** (Fig. 228).—As already stated (page 172), the cloacal membrane, composed of ectoderm and entoderm, originally reaches from the umbilicus to the tail. The mesoderm extends to the midventral line for some distance behind the umbilicus, and forms the lower part of the abdominal wall; it ends below in a prominent swelling, the **cloacal tubercle**. Behind this tubercle the urogenital part of the cloacal membrane separates the ingrowing sheets of mesoderm.

The first rudiment of the penis (or clitoris) is a structure termed the **phallus**; it is derived from the phallic portion of the cloaca which has extended on to the end and sides of the under surface of the cloacal tubercle. The terminal part of the phallus representing the future glans becomes solid; the remainder, which is hollow, is converted into a longitudinal groove by the absorption of the urogenital membrane.

*In the female* a deep groove forms around the phallus and separates it from the rest of the cloacal tubercle, which is now termed the **genital tubercle**. The sides of the genital tubercle grow backward as the **genital swellings**, which ultimately form the labia majora; the tubercle itself becomes the mons pubis. The labia minora arise by the continued growth of the lips of the groove on the under surface of the phallus; the remainder of the phallus forms the clitoris.

*In the male* the early changes are similar, but the pelvic portion of the cloaca undergoes much greater development, pushing before it the phallic portion. The genital swellings extend around between the pelvic portion and the anus, and form a scrotal area; during the changes associated with the descent of the testes this area is drawn out to form the scrotal sacs. The penis is developed from the phallus. As in the female, the urogenital membrane undergoes absorption, forming a channel on the under surface of the phallus; this channel extends only as far forward as the corona glandis.

The **corpora cavernosa** of the penis (or clitoris) and of the urethra arise from the mesodermal tissue in the phallus; they are at first dense structures, but later vascular spaces appear in them, and they gradually become cavernous.

The **prepuce** in both sexes is formed by the growth of a solid plate of ectoderm into the superficial part of the phallus; on coronal section this plate presents the shape of a horseshoe. By the breaking down of its more centrally situated cells the plate is split into two lamellæ, and a cutaneous fold, the prepuce, is liberated and forms a hood over the glans. "Adherent prepuce is not an adhesion really, but a hindered central desquamation" (Berry Hart, *op. cit.*).

**The Urethra.**—As already described, in both sexes the phallic portion of the cloaca extends on to the under surface of the cloacal tubercle as far forward as the apex. At the apex the walls of the phallic portion come together and fuse, the lumen is obliterated, and a solid plate, the **urethral plate**, is formed. The remainder of the phallic portion is for a time tubular, and then, by the absorption of the urogenital membrane, it establishes a communication with the exterior; this opening is the **primitive urogenital ostium**, and it extends forward to the corona glandis.

*In the female* this condition is largely retained; the portion of the groove on the clitoris broadens out while the body of the clitoris enlarges, and thus the adult urethral opening is situated behind the base of the clitoris.

*In the male*, by the greater growth of the pelvic portion of the cloaca a longer urethra is formed, and the primitive ostium is carried forward with the phallus, but it still ends at the corona glandis. Later it closes from behind forward. Mean-

while the urethral plate of the glans breaks down centrally to form a median groove continuous with the primitive ostium. This groove also closes from behind forward, so that the external urethral opening is shifted forward to the end of the glans.

## THE FORM OF THE EMBRYO AT DIFFERENT STAGES OF ITS GROWTH.

**First Week.**—During this period the ovum is in the uterine tube. Having been fertilized in the upper part of the tube, it slowly passes down, undergoing segmentation, and reaches the uterus. Peters<sup>1</sup> described a specimen, the age of which he reckoned as from three to four days. It was imbedded in the decidua on the posterior wall of the uterus and enveloped by a decidua capsularis, the central part of which, however, consisted merely of a layer of fibrin. The ovum was in the form of a sac, the outer wall of which consisted of a layer of trophoblast; inside this was a thin layer of mesoderm composed of round, oval, and spindle-shaped cells. Numerous villous processes—some consisting of trophoblast only, others possessing a core of mesoderm—projected from the surface of the ovum into the surrounding decidua. Inside this sac the rudiment of the embryo was found in the form of a patch of ectoderm, covered by a small but completely closed amnion. It possessed a minute yolk-sac and was surrounded by mesoderm, which was connected by a band to that lining the trophoblast (Fig. 88).<sup>2</sup>




FIG. 229.—Human embryo about fifteen days old. (His.)

**Second Week.**—By the end of this week the ovum has increased considerably in size, and the majority of its villi are vascularized. The embryo has assumed a definite form, and its cephalic and caudal extremities are easily distinguished. The neural folds are partly united. The embryo is more completely separated from the yolk-sac, and the paraxial mesoderm is being divided into the primitive segments (Fig. 229).

**Third Week.**—By the end of the third week the embryo is strongly curved, and the primitive segments number about thirty. The primary divisions of the brain are visible, and the optic and auditory vesicles are formed. Four branchial grooves are present: the stomodeum is well-marked, and the buccopharyngeal membrane has disappeared. The rudiments of the limbs are seen as short buds, and the Wolffian bodies are visible (Fig. 230).

**Fourth Week.**—The embryo is markedly curved on itself, and when viewed in profile is almost circular in outline. The cerebral hemispheres appear as hollow buds, and the elevations which form the rudiments of the auricula are visible. The limbs now appear as oval flattened projections (Fig. 231).

**Fifth Week.**—The embryo is less curved and the head is relatively of large size. Differentiation of the limbs into their segments occurs. The nose forms a short, flattened projection. The cloacal tubercle is evident (Fig. 232).

<sup>1</sup> Die Einbettung des menschlichen Eies, 1899.

<sup>2</sup> Bryce and Teacher (*Early Development and Imbedding of the Human Ovum*, 1908) have described an ovum which they regard as thirteen to fourteen days old. In it the two vesicles, the amnion and yolk-sac, were present, but there was no trace of a layer of embryonic ectoderm. They are of opinion that the age of Peters' ovum has been understated, and estimate it as between thirteen and one-half and fourteen and one-half days.



**Sixth Week.**—The curvature of the embryo is further diminished. The branchial grooves—except the first—have disappeared, and the rudiments of the fingers and toes can be recognized (Fig. 233).




FIG. 230.—Human embryo between eighteen and twenty-one days old. (His.)

**Seventh and Eighth Weeks.**—The flexure of the head is gradually reduced and the neck is somewhat lengthened. The upper lip is completed and the nose is more prominent. The nostrils are directed forward and the palate is not completely developed. The eyelids are present in the shape of folds above and below the eye, and the different parts of the auricula are distinguishable. By the end of the second month the fetus measures from 28 to 30 mm. in length (Fig. 234).




FIG. 231.—Human embryo, twenty-seven to thirty days old. (His.)

**Third Month.**—The head is extended and the neck is lengthened. The eyelids meet and fuse, remaining closed until the end of the sixth month. The limbs are well-developed and nails appear on the digits. The external generative organs are so far differentiated that it is possible to distinguish the sex. By the end of this month the length of the fetus is about 7 cm., but if the legs be included it is from 9 to 10 cm.

**Fourth Month.**—The loop of gut which projected into the umbilical cord is withdrawn within the fetus. The hairs begin to make their appearance. There is a general increase in size so that by the end of the fourth month the fetus is from 12 to 13 cm. in length, but if the legs be included it is from 16 to 20 cm.

**Fifth Month.**—It is during this month that the first movements of the fetus are usually observed. The eruption of hair on the head commences, and the *vernix caseosa* begins to be deposited. By the end of this month the total length of the fetus, including the legs, is from 25 to 27 cm.




FIG. 232.—Human embryo, thirty-one to thirty-four days old. (His.)

**Sixth Month.**—The body is covered by fine hairs (*lanugo*) and the deposit of *vernix caseosa* is considerable. The papillæ of the skin are developed and the free border of the nail projects from the corium of the dermis. Measured from vertex to heels, the total length of the fetus at the end of this month is from 30 to 32 cm.




FIG. 233.—Human embryo of about six weeks. (His.)




FIG. 234.—Human embryo about eight and a half weeks old. (His.)

**Seventh Month.**—The pupillary membrane atrophies and the eyelids are open. The testis descends with the vaginal sac of the peritoneum. From vertex to heels the total length at the end of the seventh month is from 35 to 36 cm. The weight is a little over three pounds.

**Eighth Month.**—The skin assumes a pink color and is now entirely coated with vernix caseosa, and the lanugo begins to disappear. Subcutaneous fat has been developed to a considerable extent, and the fetus presents a plump appearance. The total length, *i. e.*, from head to heels, at the end of the eighth month is about 40 cm., and the weight varies between four and one-half and five and one-half pounds.

**Ninth Month.**—The lanugo has largely disappeared from the trunk. The umbilicus is almost in the middle of the body and the testes are in the scrotum. At full time the fetus weighs from six and one-half to eight pounds, and measures from head to heels about 50 cm.

# OSTEOLOGY.

THE general framework of the body is built up mainly of a series of bones, supplemented, however, in certain regions by pieces of cartilage; the bony part of the framework constitutes the **skeleton**.

In comparative anatomy the term skeleton has a wider application, since in some of the lower animals hard, protecting and supporting structures are developed in association with the integumentary system. In such animals the skeleton is described as consisting of an internal or deep skeleton, the **endoskeleton**, and an external or superficial, the **exoskeleton**. In the human subject the exoskeleton is extremely rudimentary, its only important representatives being the nails and the enamel of the teeth. The term skeleton is, therefore, confined to the endoskeleton, and this is divisible into an **axial** part, which includes that of the head and trunk, and an **appendicular** part, which comprises that of the extremities or limbs.

In the skeleton of the adult there are 206 distinct bones, as follows:—

Axial Skeleton	{	Vertebral column . . . . .	26	
		Skull . . . . .	22	
		Hyoid bone . . . . .	1	
		Ribs and sternum . . . . .	25	
			—	74
Appendicular Skeleton	{	Upper extremities . . . . .	64	
		Lower extremities . . . . .	62	
			—	126
Auditory ossicles . . . . .				6
Total . . . . .				206

The patellæ are included in this enumeration, but the smaller sesamoid bones are not reckoned.

Bones are divisible into four classes: *Long, Short, Flat, and Irregular*.

**Long Bones.**—The long bones are found in the limbs, and each consists of a body or shaft and two extremities. The **body**, or **diaphysis** is cylindrical, with a central cavity termed the **medullary canal**; the wall consists of dense, compact tissue of considerable thickness in the middle part of the body, but becoming thinner toward the extremities; within the medullary canal is some cancellous tissue, scanty in the middle of the body but greater in amount toward the ends. The **extremities** are generally expanded, for the purposes of articulation and to afford broad surfaces for muscular attachment. They are usually developed from separate centres of ossification termed **epiphyses**, and consist of cancellous tissue surrounded by thin compact bone. The medullary canal and the spaces in the cancellous tissue are filled with marrow. The long bones are not straight, but curved, the curve generally taking place in two planes, thus affording greater strength to the bone. The bones belonging to this class are: the **clavicle, humerus, radius, ulna, femur, tibia, fibula, metacarpals, metatarsals, and phalanges**.

**Short Bones.**—Where a part of the skeleton is intended for strength and compactness combined with limited movement, it is constructed of a number of short bones, as in the *carpus* and *tarsus*. These consist of cancellous tissue covered by a thin crust of compact substance. The *patellæ*, together with the other sesamoid bones, are by some regarded as short bones.

**Flat Bones.**—Where the principal requirement is either extensive protection or the provision of broad surfaces for muscular attachment, the bones are expanded into broad, flat plates, as in the *skull* and the *scapula*. These bones are composed of two thin layers of compact tissue enclosing between them a variable quantity of cancellous tissue. In the cranial bones, the layers of compact tissue are familiarly known as the *tables of the skull*; the outer one is thick and tough; the inner is thin, dense, and brittle, and hence is termed the *vitreous table*. The intervening cancellous tissue is called the *diploë*, and this, in certain regions of the skull, becomes absorbed so as to leave spaces filled with air (*air-sinuses*) between the two tables. The flat bones are: the *occipital*, *parietal*, *frontal*, *nasal*, *lacrima*, *vomer*, *scapula*, *os coxæ* (*hip bone*), *sternum*, *ribs*, and, according to some, the *patella*.

**Irregular Bones.**—The irregular bones are such as, from their peculiar form, cannot be grouped under the preceding heads. They consist of cancellous tissue enclosed within a thin layer of compact bone. The irregular bones are: the *vertebræ*, *sacrum*, *coccyx*, *temporal*, *sphenoid*, *ethmoid*, *zygomatic*, *maxilla*, *mandible*, *palatine*, *inferior nasal concha*, and *hyoid*.

**Surfaces of Bones.**—If the surface of a bone be examined, certain eminences and depressions are seen. These eminences and depressions are of two kinds: articular and non-articular. Well-marked examples of *articular eminences* are found in the heads of the humerus and femur; and of *articular depressions* in the glenoid cavity of the scapula, and the acetabulum of the hip bone. *Non-articular eminences* are designated according to their form. Thus, a broad, rough, uneven elevation is called a *tuberosity*, *protuberance*, or *process*, a small, rough prominence, a *tubercle*; a sharp, slender pointed eminence, a *spine*; a narrow, rough elevation, running some way along the surface, a *ridge*, *crest*, or *line*. *Non-articular depressions* are also of variable form, and are described as *fossæ*, *pits*, *depressions*, *grooves*, *furrows*, *fissures*, *notches*, etc. These non-articular eminences and depressions serve to increase the extent of surface for the attachment of ligaments and muscles, and are usually well-marked in proportion to the muscularity of the subject; the grooves, fissures, and notches transmit tendons, vessels, or nerves.

The minute structure, growth, and composition of bone are described on pages 50 to 59.

### THE VERTEBRAL COLUMN (COLUMNA VERTEBRALIS; SPINAL COLUMN).

The *vertebral column* is a flexuous and flexible column, formed of a series of bones called *vertebræ*.

The *vertebræ* are thirty-three in number, and are grouped under the names *cervical*, *thoracic*, *lumbar*, *sacral*, and *coccygeal*, according to the regions they occupy; there are seven in the cervical region, twelve in the thoracic, five in the lumbar, five in the sacral, and four in the coccygeal.

This number is sometimes increased by an additional vertebra in one region, or it may be diminished in one region, the deficiency being supplied by an additional vertebra in another. The number of cervical *vertebræ* is, however, very rarely increased or diminished.

The *vertebræ* in the upper three regions of the column remain distinct throughout life, and are known as *true* or *movable* *vertebræ*; those of the sacral and

coccygeal regions, on the other hand, are termed **false** or **fixed** vertebræ, because they are united with one another in the adult to form two bones—five forming the upper bone or **sacrum**, and four the terminal bone or **coccyx**.

With the exception of the first and second cervical, the true or movable vertebræ present certain common characteristics which are best studied by examining one from the middle of the thoracic region.

### GENERAL CHARACTERISTICS OF A VERTEBRA.

A **typical vertebra** consists of two essential parts—viz., an anterior segment, the **body**, and a posterior part, the **vertebral** or **neural arch**; these enclose a foramen, the **vertebral foramen**. The vertebral arch consists of a pair of **pedicles** and a pair of **laminae**, and supports **seven processes**—viz., four **articular**, two **transverse**, and one **spinous**.

When the vertebræ are articulated with each other the bodies form a strong pillar for the support of the head and trunk, and the vertebral foramina constitute a canal for the protection of the medulla spinalis (*spinal cord*), while between every pair of vertebræ are two apertures, the **intervertebral foramina**, one on either side, for the transmission of the spinal nerves and vessels.

**Body** (*corpus vertebrae*).—The body is the largest part of a vertebra, and is more or less cylindrical in shape. Its upper and lower surfaces are flattened and rough, and give attachment to the intervertebral fibrocartilages, and each presents a rim around its circumference. In front, the body is convex from side to side and concave from above downward. Behind, it is flat from above downward and slightly concave from side to side. Its anterior surface presents a few small apertures, for the passage of nutrient vessels; on the posterior surface is a single large, irregular aperture, or occasionally more than one, for the exit of the basi-vertebral veins from the body of the vertebra.

**Pedicles** (*radices arcus vertebrae*).—The pedicles are two short, thick processes, which project backward, one on either side, from the upper part of the body, at the junction of its posterior and lateral surfaces. The concavities above and below the pedicles are named the **vertebral notches**; and when the vertebræ are articulated, the notches of each contiguous pair of bones form the intervertebral foramina, already referred to.

**Laminae**.—The laminae are two broad plates directed backward and medialward from the pedicles. They fuse in the middle line posteriorly, and so complete the posterior boundary of the vertebral foramen. Their upper borders and the lower parts of their anterior surfaces are rough for the attachment of the *ligamenta flava*.

**Processes**.—**Spinous Process** (*processus spinosus*).—The spinous process is directed backward and downward from the junction of the laminae, and serves for the attachment of muscles and ligaments.

**Articular Processes**.—The articular processes, two superior and two inferior, spring from the junctions of the pedicles and laminae. The superior project upward, and their articular surfaces are directed more or less backward; the inferior project downward, and their surfaces look more or less forward.

**Transverse Processes** (*processus transversi*).—The transverse processes, two in number, project one at either side from the point where the lamina joins the pedicle, between the superior and inferior articular processes. They serve for the attachment of muscles and ligaments.

**Structure of a Vertebra** (Fig. 235).—The body is composed of cancellous tissue, covered by a thin coating of compact bone; the latter is perforated by numerous orifices, some of large size



for the passage of vessels; the interior of the bone is traversed by one or two large canals, for the reception of veins, which converge toward a single large, irregular aperture, or several small apertures, at the posterior part of the body. The arch and processes projecting from it have thick coverings of compact tissue.




FIG. 235.—Sagittal section of a lumbar vertebra.

### The Cervical Vertebrae (Vertebrae Cervicales).

The **cervical vertebrae** (Fig. 236) are the smallest of the true vertebrae, and can be readily distinguished from those of the thoracic or lumbar regions by the presence of a foramen in each transverse process. The

first, second, and seventh present exceptional features and must be separately described; the following characteristics are common to the remaining four.

The **body** is small, and broader from side to side than from before backward. The **anterior and posterior surfaces** are flattened and of equal depth; the former is placed on a lower level than the latter, and its inferior border is prolonged downward, so as to overlap the upper and forepart of the vertebra below. The **upper surface** is concave transversely, and presents a projecting lip on either side; the **lower surface** is concave from before backward, convex from side to side, and presents laterally shallow concavities which receive the corresponding projecting lips of the subjacent vertebra. The **pedicles** are directed lateralward and backward,




FIG. 236.—A cervical vertebra.

and are attached to the body midway between its upper and lower borders, so that the superior vertebral notch is as deep as the inferior, but it is, at the same time, narrower. The **laminae** are narrow, and thinner above than below; the **vertebral foramen** is large, and of a triangular form. The **spinous process** is short and bifid, the two divisions being often of unequal size. The **superior and inferior articular processes** on either side are fused to form an articular pillar, which projects lateralward from the junction of the pedicle and lamina. The articular facets are flat and of an oval form: the superior look backward, upward, and slightly medialward; the inferior forward, downward, and slightly lateralward. The **transverse processes** are each pierced by the **foramen transversarium**, which, in the upper six vertebrae, gives passage to the vertebral artery and vein and a plexus of sympa-

thetic nerves. Each process consists of an anterior and a posterior part. The **anterior** portion is the homologue of the rib in the thoracic region, and is therefore named the **costal process** or **costal element**: it arises from the side of the body, is directed lateralward in front of the foramen, and ends in a tubercle, the **tuberculum anterius**. The **posterior** part, the true transverse process, springs from the vertebral arch behind the foramen, and is directed forward and lateralward; it ends in a flattened vertical tubercle, the **tuberculum posterius**. These two parts are joined, outside the foramen, by a bar of bone which exhibits a deep sulcus on its upper surface for the passage of the corresponding spinal nerve.<sup>1</sup>

Chassaignac first pointed out that the common carotid artery can be easily compressed against the anterior tubercle of the transverse process of the sixth cervical vertebra, and therefore this tubercle is named the *tuberculum caroticum* or *Chassaignac's tubercle*. It also constitutes an important guide to the vertebral artery which enters the foramen transversarium of this vertebra.




FIG. 237.—First cervical vertebra, or atlas.

**First Cervical Vertebra.**—The first cervical vertebra (Fig. 237) is named the **atlas** because it supports the globe of the head. Its chief peculiarity is that it has no body, and this is due to the fact that the body of the atlas has fused with that of the next vertebra. Its other peculiarities are that it has no spinous process, is ring-like, and consists of an anterior and a posterior arch and two lateral masses. The **anterior arch** forms about one-fifth of the ring: its anterior surface is convex, and presents at its centre the **anterior tubercle** for the attachment of the Longus colli muscles; posteriorly it is concave, and marked by a smooth, oval or circular facet (*fovea dentis*), for articulation with the odontoid process (*dens*) of the axis. The upper and lower borders respectively give attachment to the anterior atlanto-occipital membrane and the anterior atlantoaxial ligament; the former connects it with the occipital bone above, and the latter with the axis below. The **posterior arch** forms about two-fifths of the circumference of the ring: it ends behind in the **posterior tubercle**, which is the rudiment of a spinous process and gives origin to the Recti capitis posteriores minores. The diminutive size of this process prevents any interference with the movements between the atlas and the skull. The posterior part of the arch presents above and behind a rounded edge for the attachment of the posterior atlantoöccipital membrane, while immediately behind each superior articular process is a groove (*sulcus arteriae vertebralis*), sometimes converted into a foramen by a delicate bony spiculum which arches backward from the posterior end of the superior articular process. This groove represents the superior vertebral notch, and serves for the transmission of the vertebral artery, which, after ascending through the foramen in the transverse

<sup>1</sup> The *costal element* of a cervical vertebra not only includes the portion which springs from the side of the body, but the anterior and posterior tubercles and the bar of bone which connects them (Fig. 97).

process, winds around the lateral mass in a direction backward and medialward; it also transmits the suboccipital (first spinal) nerve. On the under surface of the posterior arch, behind the articular facets, are two shallow grooves, the **inferior vertebral notches**. The lower border gives attachment to the posterior atlanto-axial ligament, which connects it with the axis. The **lateral masses** are the most bulky and solid parts of the atlas, in order to support the weight of the head. Each carries two articular facets, a superior and an inferior. The **superior facets** are of large size, oval, concave, and approach each other in front, but diverge behind: they are directed upward, medialward, and a little backward, each forming a cup for the corresponding condyle of the occipital bone, and are admirably adapted to the nodding movements of the head. Not infrequently they are partially subdivided by indentations which encroach upon their margins. The **inferior articular facets** are circular in form, flattened or slightly convex and directed downward and medialward, articulating with the axis, and permitting the rotatory movements of the head. Just below the medial margin of each superior facet is a small tubercle, for the attachment of the transverse atlantal ligament which stretches across the ring of the atlas and divides the vertebral foramen into two unequal parts—the anterior or smaller receiving the odontoid process of the axis, the posterior transmitting the medulla spinalis and its membranes. This part of the vertebral canal is of considerable size, much greater than is required for the accommodation of the medulla spinalis, and hence lateral displacement of the atlas may occur without compression of this structure. The **transverse processes** are large; they project lateralward and downward from the lateral masses, and serve for the attachment of muscles which assist in rotating the head. They are long, and their anterior and posterior tubercles are fused into one mass; the foramen transversarium is directed from below, upward and backward.




FIG. 238.—Second cervical vertebra, epistropheus, or axis.

**Second Cervical Vertebra.**—The second cervical vertebra (Fig. 238) is named the **epistropheus** or **axis** because it forms the pivot upon which the first vertebra, carrying the head, rotates. The most distinctive characteristic of this bone is the strong odontoid process which rises perpendicularly from the upper surface of the body. The **body** is deeper in front than behind, and prolonged downward anteriorly so as to overlap the upper and fore part of the third vertebra. It presents in front a median longitudinal ridge, separating two lateral depressions for the attachment of the Longus colli muscles. Its under surface is concave from before backward and convex from side to side. The **dens** or **odontoid process** exhibits a slight constriction or neck, where it joins the body. On its anterior surface is an oval or nearly circular facet for articulation with that on the anterior arch

of the atlas. On the back of the neck, and frequently extending on to its lateral surfaces, is a shallow groove for the transverse atlantal ligament which retains the process in position. The **apex** is pointed, and gives attachment to the middle alar ligament; below the apex the process is somewhat enlarged, and presents on either side a rough impression for the attachment of the lateral alar ligament; these ligaments connect the process to the occipital bone. The internal structure of the odontoid process is more compact than that of the body. The **pedicles** are broad and strong, especially in front, where they coalesce with the sides of the body and the root of the odontoid process. They are covered above by the superior articular surfaces. The **laminae** are thick and strong, and the vertebral foramen large, but smaller than that of the atlas. The **transverse processes** are very small, and each ends in a single tubercle; each is perforated by the foramen transversarium, which is directed obliquely upward and lateralward. The **superior articular surfaces** are round, slightly convex, directed upward and lateralward, and are supported on the body, pedicles, and transverse processes. The **inferior articular surfaces** have the same direction as those of the other cervical vertebræ. The **superior vertebral notches** are very shallow, and lie behind the articular processes; the **inferior** lie in front of the articular processes, as in the other cervical vertebræ. The **spinous process** is large, very strong, deeply channelled on its under surface, and presents a bifid, tuberculated extremity.

**The Seventh Cervical Vertebra** (Fig. 239).—The most distinctive characteristic of this vertebra is the existence of a long and prominent spinous process, hence the name **vertebra prominens**. This process is thick, nearly horizontal in direction, not bifurcated, but terminating in a tubercle to which the lower end of the ligamentum nuchae is attached. The **transverse processes** are of considerable size, their posterior roots are large and prominent, while the anterior are small and faintly marked; the upper surface of each has usually a shallow sulcus for the eighth spinal nerve, and its extremity seldom presents more than a trace of bifurcation. The foramen transversarium may be as large as that in the other cervical vertebræ, but is generally smaller on one or both sides; occasionally it is double, sometimes it is absent. On the left side it occasionally gives passage to the vertebral artery; more frequently the vertebral vein traverses it on both sides; but the usual arrangement is for both artery and vein to pass in front of the transverse process, and not through the foramen. Sometimes the anterior root of the transverse process attains a large size and exists as a separate bone, which is known as a **cervical rib**.



FIG. 239.—Seventh cervical vertebra.

### The Thoracic Vertebræ (Vertebrae Thoracales).

The **thoracic vertebræ** (Fig. 240) are intermediate in size between those of the cervical and lumbar regions; they increase in size from above downward the

upper vertebræ being much smaller than those in the lower part of the region. They are distinguished by the presence of facets on the sides of the bodies for articulation with the heads of the ribs, and facets on the transverse processes of all, except the eleventh and twelfth, for articulation with the tubercles of the ribs.

The **bodies** in the middle of the thoracic region are heart-shaped, and as broad in the antero-posterior as in the transverse direction. At the ends of the thoracic region they resemble respectively those of the cervical and lumbar vertebræ. They are slightly thicker behind than in front, flat above and below, convex from side to side in front, deeply concave behind, and slightly constricted laterally and in front. They present, on either side, two costal demi-facets, one above, near the root of the pedicle, the other below, in front of the inferior vertebral notch; these are covered with cartilage in the recent state, and, when the vertebræ are articulated with one another, form, with the intervening intervertebral fibro-cartilages, oval surfaces for the reception of the heads of the ribs. The **pedicles** are directed backward and slightly upward, and the inferior vertebral notches are of large size, and deeper than in any other region of the vertebral column.




FIG. 240.—A thoracic vertebra.

The **laminæ** are broad, thick, and imbricated—that is to say, they overlap those of subjacent vertebræ like tiles on a roof. The **vertebral foramen** is small, and of a circular form. The **spinous process** is long, triangular on coronal section, directed obliquely downward, and ends in a tuberculated extremity. These processes overlap from the fifth to the eighth, but are less oblique in direction above and below.<sup>1</sup> The **superior articular processes** are thin plates of bone projecting upward from the junctions of the pedicles and laminæ; their articular facets are practically flat, and are directed backward and a little lateralward and upward. The **inferior articular processes** are fused to a considerable extent with the laminæ, and project but slightly beyond their lower borders; their facets are directed forward and a little medialward and downward. The **transverse processes** arise from the arch behind the superior articular processes and pedicles; they are thick, strong, and of considerable length, directed obliquely backward and lateralward,

<sup>1</sup> In quadrupeds the majority of the spinous processes of the thoracic vertebræ project upward and backward, while those of the lumbar region are directed upward and forward. The change in inclination is effected in one of the lower thoracic vertebræ, the spine of which points almost directly upward. This vertebra is known as the *anticlinal*, and in man its representative is the eleventh thoracic.

and each ends in a clubbed extremity, on the front of which is a small, concave surface, for articulation with the tubercle of a rib.

The *first, ninth, tenth, eleventh, and twelfth* thoracic vertebræ present certain peculiarities, and must be specially considered (Fig. 241).




FIG. 241.—Peculiar thoracic vertebræ.

The **First Thoracic Vertebra** has, on either side of the **body**, an entire articular facet for the head of the first rib, and a demi-facet for the upper half of the head of the second rib. The body is like that of a cervical vertebra, being broad transversely; its upper surface is concave, and lipped on either side. The **superior articular surfaces** are directed upward and backward; the **spinous process** is thick, long, and almost horizontal. The **transverse processes** are long, and the upper vertebral notches are deeper than those of the other thoracic vertebræ.



The **Ninth Thoracic Vertebra** may have no demi-facets below. In some subjects however, it has two demi-facets on either side; when this occurs the tenth has only demi-facets at the upper part.

The **Tenth Thoracic Vertebra** has (except in the cases just mentioned) an entire articular facet on either side, which is placed partly on the lateral surface of the pedicle.

In the **Eleventh Thoracic Vertebra** the body approaches in its form and size to that of the lumbar vertebræ. The articular facets for the heads of the ribs are of large size, and placed chiefly on the pedicles, which are thicker and stronger in this and the next vertebra than in any other part of the thoracic region. The **spinous process** is short, and nearly horizontal in direction. The **transverse processes** are very short, tuberculated at their extremities, and have no articular facets.

The **Twelfth Thoracic Vertebra** has the same general characteristics as the eleventh, but may be distinguished from it by its inferior articular surfaces being convex and directed lateralward, like those of the lumbar vertebræ; by the general form of the body, laminae, and spinous process, in which it resembles the lumbar vertebræ; and by each transverse process being subdivided into three elevations, the superior, inferior, and lateral tubercles: the superior and inferior correspond to the mamillary and accessory processes of the lumbar vertebræ. Traces of similar elevations are found on the transverse processes of the tenth and eleventh thoracic vertebræ.




FIG. 242.—A lumbar vertebra seen from the side.

### The Lumbar Vertebræ (Vertebrae Lumbales).

The **lumbar vertebræ** (Figs. 242 and 243) are the largest segments of the movable part of the vertebral column, and can be distinguished by the absence of a foramen in the transverse process, and by the absence of facets on the sides of the body.

The **body** is large, wider from side to side than from before backward, and a little thicker in front than behind. It is flattened or slightly concave above and below, concave behind, and deeply constricted in front and at the sides. The **pedicles** are very strong, directed backward from the upper part of the body; consequently, the inferior vertebral notches are of considerable depth. The **laminae** are broad, short, and strong; the **vertebral foramen** is triangular, larger than in the thoracic, but smaller than in the cervical region. The **spinous process** is thick, broad, and somewhat quadrilateral; it projects backward and ends in a rough, uneven border, thickest below where it is occasionally notched. The **superior** and **inferior articular processes** are well-defined, projecting respectively upward and downward from the junctions of pedicles and laminae. The facets

on the superior processes are concave, and look backward and medialward; those on the inferior are convex, and are directed forward and lateralward. The former are wider apart than the latter, since in the articulated column the inferior articular processes are embraced by the superior processes of the subjacent vertebra. The **transverse processes** are long, slender, and horizontal in the upper three lumbar vertebræ; they incline a little upward in the lower two. In the upper three vertebræ they arise from the junctions of the pedicles and laminæ, but in the lower two they are set farther forward and spring from the pedicles and posterior parts of the bodies. They are situated in front of the articular processes instead of behind them as in the thoracic vertebræ, and are homologous with the ribs. Of the three tubercles noticed in connection with the transverse processes of the lower thoracic




FIG. 243.—A lumbar vertebra viewed obliquely from above.

vertebræ, the superior one is connected in the lumbar region with the back part of the superior articular process, and is named the **mamillary process**; the inferior is situated at the back part of the base of the transverse process, and is called the **accessory process** (Fig. 243). Although in man these are comparatively small, in some animals they attain considerable size, and serve to lock the vertebræ more closely together.

The **Fifth Lumbar Vertebra** is characterized by its body being much deeper in front than behind, which accords with the prominence of the sacrovertebral articulation; by the smaller size of its spinous process; by the wide interval between the inferior articular processes; and by the thickness of its transverse processes, which spring from the body as well as from the pedicles.

#### The Sacral and Coccygeal Vertebræ.

The **sacral and coccygeal vertebræ** consist at an early period of life of nine separate segments which are united in the adult, so as to form two bones, five entering into the formation of the sacrum, four into that of the coccyx. Sometimes the coccyx consists of five bones; occasionally the number is reduced to three.

**The Sacrum** (*os sacrum*).—The sacrum is a large, triangular bone, situated in the lower part of the vertebral column and at the upper and back part of the pelvic cavity, where it is inserted like a wedge between the two hip bones; its upper part or base articulates with the last lumbar vertebra, its apex with the coccyx. It is curved upon itself and placed very obliquely, its base projecting forward and forming the **prominent sacrovertebral angle** when articulated with the last lumbar vertebra; its central part is projected backward, so as to give increased capacity to the pelvic cavity. The sacrum is rather narrower at the level of the second segment than at the level of the third. It presents for examination a pelvic, a dorsal, and two lateral surfaces, a base, an apex, and a central canal.




FIG. 244.—Sacrum, pelvic surface.

**Pelvic Surface** (*facies pelvina*).—The pelvic surface (Fig. 244) is concave from above downward, and slightly so from side to side. Its middle part is crossed by four **transverse ridges**, the positions of which correspond with the original planes of separation between the five segments of the bone. The portions of bone intervening between the ridges are the bodies of the sacral vertebræ. The body of the first segment is of large size, and in form resembles that of a lumbar vertebra; the succeeding ones diminish from above downward, are flattened from before backward, and curved so as to accommodate themselves to the form of the sacrum, being concave in front, convex behind. At the ends of the ridges are seen the **anterior sacral foramina**, four in number on either side, somewhat rounded in form diminishing in size from above downward, and directed lateralward and forward; they give exit to the anterior divisions of the sacral nerves and entrance to the lateral sacral arteries. Lateral to these foramina are the **lateral parts of the sacrum**, each consisting of five separate segments at an early period of life; in the adult,

these are blended with the bodies and with each other. Each lateral part is traversed by four broad, shallow grooves, which lodge the anterior divisions of the sacral nerves, and are separated by prominent ridges of bone which give origin to the Piriformis muscle.

If a sagittal section be made through the centre of the sacrum (Fig. 246), the bodies are seen to be united at their circumferences by bone, wide intervals being left centrally, which, in the recent state, are filled by the intervertebral fibrocartilages. In some bones this union is more complete between the lower than the upper segments.




FIG. 245.—Sacrum, dorsal surface.

**Dorsal Surface** (*facies dorsalis*).—The dorsal surface (Fig. 245) is convex and narrower than the pelvic. In the middle line it displays a crest, the **middle sacral crest**, surmounted by three or four tubercles, the rudimentary spinous processes of the upper three or four sacral vertebræ. On either side of the middle sacral crest is a shallow groove, the **sacral groove**, which gives origin to the Multifidus, the floor of the groove being formed by the united laminae of the corresponding vertebræ. The laminae of the fifth sacral vertebra, and sometimes those of the fourth, fail to meet behind, and thus a **hiatus** or deficiency occurs in the posterior wall of the sacral canal. On the lateral aspect of the sacral groove is a linear series of tubercles produced by the fusion of the articular processes which together form the indistinct **sacral articular crests**. The articular processes of the first sacral vertebra are large and oval in shape; their facets are concave from side to side, look backward and medialward, and articulate with the facets on the inferior processes of the fifth lumbar vertebra. The tubercles which represent the inferior articular processes of the fifth sacral vertebra are prolonged downward as rounded processes, which are named the **sacral cornua**, and are connected to the cornua

of the coccyx. Lateral to the articular processes are the four **posterior sacral foramina**; they are smaller in size and less regular in form than the anterior, and transmit the posterior divisions of the sacral nerves. On the lateral side of the posterior sacral foramina is a series of tubercles, which represent the transverse processes of the sacral vertebrae, and form the **lateral crests** of the sacrum. The transverse tubercles of the first sacral vertebra are large and very distinct; they, together with the transverse tubercles of the second vertebra, give attachment to the horizontal parts of the posterior sacroiliac ligaments; those of the third vertebra give attachment to the oblique fasciculi of the posterior sacroiliac ligaments; and those of the fourth and fifth to the sacrotuberous ligaments.

**Lateral Surface.**—The lateral surface is broad above, but narrowed into a thin edge below. The upper half presents in front an ear-shaped surface, the **auricular surface** for articulation with the ilium. Behind it is a rough surface, the **sacral tuberosity**, on which are three deep and uneven impressions, for the attachment of the posterior sacroiliac ligament. The lower half is thin, and ends in a projection called the **inferior lateral angle**; medial to this angle is a notch, which is converted into a foramen by the transverse process of the first piece of the coccyx, and transmits the anterior division of the fifth sacral nerve. The thin lower half of the lateral surface gives attachment to the sacrotuberous and sacrospinous ligaments, to some fibres of the Gluteus maximus behind, and to the Coccygeus in front.

**Base** (*basis oss. sacri*).—The base of the sacrum, which is broad and expanded, is directed upward and forward. In the middle is a large oval articular surface, the upper surface of the body of the first sacral vertebra, which is connected with the under surface of the body of the last lumbar vertebra by an intervertebral fibrocartilage. Behind this is the large triangular orifice of the sacral canal, which is completed by the laminae and spinous process of the first sacral vertebra. The superior articular processes project from it on either side; they are oval, concave, directed backward and medialward, like the superior articular processes of a lumbar vertebra. They are attached to the body of the first sacral vertebra and to the alae by short thick pedicles; on the upper surface of each pedicle is a vertebral notch, which forms the lower part of the foramen between the last lumbar and first sacral vertebrae. On either side of the body is a large triangular surface, which supports the Psoas major and the lumbosacral trunk, and in the articulated pelvis is continuous with the iliac fossa. This is called the **ala**; it is slightly concave from side to side, convex from before backward, and gives attachment to a few of the fibres of the Iliacus. The posterior fourth of the ala represents the transverse process, and its anterior three-fourths the costal process of the first sacral segment.

**Apex** (*apex oss. sacri*).—The apex is directed downward, and presents an oval facet for articulation with the coccyx.

**Vertebral Canal** (*canalis sacralis; sacral canal*).—The vertebral canal (Fig. 246) runs throughout the greater part of the bone; above, it is triangular in form; below, its posterior wall is incomplete, from the non-development of the laminae and spinous processes. It lodges the sacral nerves, and its walls are perforated by the anterior and posterior sacral foramina through which these nerves pass out.

**Structure.**—The sacrum consists of cancellous tissue enveloped by a thin layer of compact bone.

**Articulations.**—The sacrum articulates with *four* bones; the last lumbar vertebra above, the coccyx below, and the hip bone on either side.


**Differences in the Sacrum of the Male and Female.**—In the female the sacrum is shorter and wider than in the male; the lower half forms a greater angle with the upper; the upper half is nearly straight, the lower half presenting the greatest amount of curvature. The bone is also directed more obliquely backward; this increases the size of the pelvic cavity and renders the sacrovertebral angle more prominent. In the male the curvature is more evenly distributed over the whole length of the bone, and is altogether greater than in the female.



**Variations.**—The sacrum, in some cases, consists of six pieces; occasionally the number is reduced to four. Sometimes the uppermost transverse tubercles are not joined to the rest of the ala on one or both sides, or the sacral canal may be open throughout a considerable part of its length, in consequence of the imperfect development of the laminæ and spinous processes. The sacrum, also, varies considerably with respect to its degree of curvature.



FIG. 246.—Median sagittal section of the sacrum.



Anterior Surface



Posterior surface

FIG. 247.—Coccyx.

**The Coccyx** (*os coccygis*).—The coccyx (Fig. 247) is usually formed of four rudimentary vertebræ; the number may however be increased to five or diminished to three. In each of the first three segments may be traced a rudimentary body and articular and transverse processes; the last piece (sometimes the third) is a mere nodule of bone. All the segments are destitute of pedicles, laminæ, and spinous processes. The first is the largest; it resembles the lowest sacral vertebra, and often exists as a separate piece; the last three diminish in size from above downward, and are usually fused with one another. Owing to the gradual diminution in the size of the segments, the coccyx is triangular in form, and presents for examination an anterior and a posterior surface, two borders, a base, and an apex.

**Surfaces.**—The **anterior surface** is slightly concave, and marked with three transverse grooves which indicate the junctions of the different segments. It gives attachment to the anterior sacrococcygeal ligament and the Levatores ani, and supports part of the rectum. The **posterior surface** is convex, marked by transverse grooves similar to those on the anterior surface, and presents on either side a linear row of tubercles, the rudimentary articular processes of the coccygeal vertebræ. Of these, the superior pair are large, and are called the **coccygeal cornua**; they



project upward, and articulate with the cornua of the sacrum, and on either side complete the foramen for the transmission of the posterior division of the fifth sacral nerve.

**Borders.**—The lateral borders are thin, and exhibit a series of small eminences, which represent the transverse processes of the coccygeal vertebræ. Of these, the first is the largest; it is flattened from before backward, and often ascends to join the lower part of the thin lateral edge of the sacrum, thus completing the foramen for the transmission of the anterior division of the fifth sacral nerve; the others diminish in size from above downward, and are often wanting. The borders of the coccyx are narrow, and give attachment on either side to the sacrotuberous and sacrospinous ligaments, to the Coccygeus in front of the ligaments, and to the Glutæus maximus behind them.

**Base.**—The base presents an oval surface for articulation with the sacrum.

**Apex.**—The apex is rounded, and has attached to it the tendon of the Sphincter ani externus. It may be bifid, and is sometimes deflected to one or other side.

**Ossification of the Vertebral Column.**—Each vertebra is ossified from three primary centres (Fig. 248), two for the vertebral arch and one for the body.<sup>1</sup> Ossification of the vertebral arches begins in the upper cervical vertebræ about the seventh or eighth week of fetal life, and gradually extends down the column. The ossific granules first appear in the situations where the transverse processes afterward project, and spread backward to the spinous process forward into the pedicles, and lateralward into the transverse and articular processes. Ossification of the bodies begins about the eighth week in the lower thoracic region, and subsequently extends upward and downward along the column. The centre for the body does not give rise to the whole of the body of the adult vertebra, the postero-lateral portions of which are ossified by extensions from the vertebral arch centres. The body of the vertebra during the first few years of life shows, therefore, two synchondroses, **neurocentral synchondroses**, traversing it along the planes of junction of the three centres (Fig. 249). In the thoracic region, the facets for the heads of the ribs lie behind the neurocentral synchondroses and are ossified from the centres for the vertebral arch. At birth the vertebra consists of three pieces, the body and the halves of the vertebral arch. During the first year the halves of the arch unite behind, union taking place first in the lumbar region and then extending upward through the thoracic and cervical regions. About the third year the bodies of the upper cervical vertebræ are joined to the arches on either side; in the lower lumbar vertebræ the union is not completed until the sixth year. Before puberty, no other changes occur, excepting a gradual increase of these primary centres, the upper and under surfaces of the bodies and the ends of the transverse and spinous processes being cartilaginous. About the sixteenth year (Fig. 249), five secondary centres appear, one for the tip of each transverse process, one for the extremity of the spinous process, one for the upper and one for the lower surface of the body (Fig. 250). These fuse with the rest of the bone about the age of twenty-five.

Exceptions to this mode of development occur in the first, second, and seventh cervical vertebræ, and in the lumbar vertebræ.

**Atlas.**—The atlas is usually ossified from *three* centres (Fig. 251). Of these, one appears in each lateral mass about the seventh week of fetal life, and extends backward; at birth, these portions of bone are separated from one another behind by a narrow interval filled with cartilage. Between the third and fourth years they unite either directly or through the medium of a separate centre developed in the cartilage. At birth, the anterior arch consists of cartilage; in this a separate centre appears about the end of the first year after birth, and joins the lateral masses from the sixth to the eighth year—the lines of union extending across the anterior portions of the superior articular facets. Occasionally there is no separate centre, the anterior arch being formed by the forward extension and ultimate junction of the two lateral masses; sometimes this arch is ossified from two centres, one on either side of the middle line.

**Epistropheus or Axis.**—The axis is ossified from *five* primary and *two* secondary centres (Fig. 252). The body and vertebral arch are ossified in the same manner as the corresponding parts in the other vertebræ, viz., one centre for the body, and two for the vertebral arch. The centres for the arch appear about the seventh or eighth week of fetal life, that for the body about the fourth or fifth month. The dens or odontoid process consists originally of a continuation upward of the cartilaginous mass, in which the lower part of the body is formed. About the sixth month of fetal life, two centres make their appearance in the base of this process: they are placed laterally, and join before birth to form a conical bilobed mass deeply cleft above; the interval

<sup>1</sup> A vertebra is occasionally found in which the body consists of two lateral portions—a condition which proves that the body is sometimes ossified from two primary centres, one on either side of the middle line.

between the sides of the cleft and the summit of the process is formed by a wedge-shaped piece of cartilage. The base of the process is separated from the body by a cartilaginous disk, which

FIG. 248.—Ossification of a vertebra  
By 3 primary centres



FIG. 249.

By 3 secondary centres




FIG. 250.

By 2 additional plates




FIG. 251.—Atlas.

By 3 centres




FIG. 252.—Axis.

By 7 centres




FIG. 253.—Lumbar vertebra.



gradually becomes ossified at its circumference, but remains cartilaginous in its centre until advanced age. In this cartilage, rudiments of the lower epiphysial lamella of the atlas and the upper epiphysial lamella of the axis may sometimes be found. The apex of the odontoid process has a separate centre which appears in the second and joins about the twelfth year; this is the upper epiphysial lamella of the atlas. In addition to these there is a secondary centre for a thin epiphysial plate on the under surface of the body of the bone.

Additional centres for costal elements\*

At birth



FIG. 254

At 4½ yrs.



FIG. 255

Two epiphysial plates for each lateral surface\*

At 25th year




FIG. 256.—Ossification of the sacrum.

**The Seventh Cervical Vertebra.**—The anterior or costal part of the transverse process of this vertebra is sometimes ossified from a separate centre which appears about the sixth month of

fetal life, and joins the body and posterior part of the transverse process between the fifth and sixth years. Occasionally the costal part persists as a separate piece, and, becoming lengthened lateralward and forward, constitutes what is known as a *cervical rib*. Separate ossific centres have also been found in the costal processes of the fourth, fifth, and sixth cervical vertebrae.

**Lumbar Vertebrae.**—The lumbar vertebrae (Fig. 253) have each *two* additional centres, for the mamillary processes. The transverse process of the first lumbar is sometimes developed as a separate piece, which may remain permanently ununited with the rest of the bone, thus forming a lumbar rib—a peculiarity, however, rarely met with.

**Sacrum** (Figs. 254 to 257).—The body of each sacral vertebra is ossified from a primary centre and *two* epiphysal plates, one for its upper and another for its under surface, while each vertebral arch is ossified from two centres.

The anterior portions of the *lateral parts* have *six* additional centres, two for each of the first three vertebrae; these represent the costal elements, and make their appearance above and lateral to the anterior sacral foramina (Figs. 254, 255).

On each *lateral surface* two epiphysal plates are developed (Figs. 256, 257): one for the auricular surface, and another for the remaining part of the thin lateral edge of the bone.<sup>1</sup>

**PERIODS OF OSSIFICATION.**—About the eighth or ninth week of fetal life, ossification of the central part of the body of the first sacral vertebra commences, and is rapidly followed by deposit

of ossific matter in the second and third; ossification does not commence in the bodies of the lower two segments until between the fifth and eighth months of fetal life. Between the sixth and eighth months ossification of the vertebral arches takes place; and about the same time the costal centres for the lateral parts make their appearance. The junctions of the vertebral arches with the bodies take place in the lower vertebrae as early as the second year, but are not effected in the uppermost until the fifth or sixth year. About the sixteenth year the epiphysal




FIG. 257.—Base of young sacrum.

plates for the upper and under surfaces of the bodies are formed; and between the eighteenth and twentieth years, those for the lateral surfaces make their appearance. The bodies of the sacral vertebrae are, during early life, separated from each other by intervertebral fibrocartilages, but about the eighteenth year the two lowest segments become united by bone, and the process of bony union gradually extends upward, with the result that between the twenty-fifth and thirtieth years of life all the segments are united. On examining a sagittal section of the sacrum, the situations of the intervertebral fibrocartilages are indicated by a series of oval cavities (Fig. 246).

**Coccyx.**—The coccyx is ossified from *four* centres, one for each segment. The ossific nuclei make their appearance in the following order: in the first segment between the first and fourth years; in the second between the fifth and tenth years; in the third between the tenth and fifteen years; in the fourth between the fourteenth and twentieth years. As age advances, the segments unite with one another, the union between the first and second segments being frequently delayed until after the age of twenty-five or thirty. At a late period of life, especially in females, the coccyx often fuses with the sacrum.

### THE VERTEBRAL COLUMN AS A WHOLE.

The vertebral column is situated in the median line, as the posterior part of the trunk; its average length in the male is about 71 cm. Of this length the cervical part measures 12.5 cm., the thoracic about 28 cm., the lumbar 18 cm., and the sacrum and coccyx 12.5 cm. The female column is about 61 cm. in length.

**Curves.**—Viewed laterally (Fig. 258), the vertebral column presents several curves, which correspond to the different regions of the column, and are called cervical, thoracic, lumbar, and pelvic. The **cervical** curve, convex forward, begins

<sup>1</sup> The ends of the spinous processes of the upper three sacral vertebrae are sometimes developed from separate epiphyses, and Fawcett (Anatomischer Anzeiger, 1907, Band xxx) states that a number of epiphysal nodules may be seen in the sacrum at the age of eighteen years. These are distributed as follows: One for each of the mamillary processes of the first sacral vertebra; twelve—six on either side—in connection with the costal elements (two each for the first and second and one each for the third and fourth) and eight for the transverse processes—four on either side—one each for the first, third, fourth, and fifth. He is further of opinion that the lower part of each lateral surface of the sacrum is formed by the extension and union of the third and fourth "costal" and fourth and fifth "transverse" epiphyses.

at the apex of the odontoid process, and ends at the middle of the second thoracic vertebra; it is the least marked of all the curves. The **thoracic** curve, concave forward, begins at the middle of the second and ends at the middle of the twelfth thoracic vertebra. Its most prominent point behind corresponds to the spinous process of the seventh thoracic vertebra. The **lumbar** curve is more marked in the female than in the male; it begins at the middle of the last thoracic vertebra, and ends at the sacrovertebral angle. It is convex anteriorly, the convexity of the lower three vertebræ being much greater than that of the upper two. The **pelvic** curve begins at the sacrovertebral articulation, and ends at the point of the coccyx; its concavity is directed downward and forward. The thoracic and pelvic curves are termed **primary** curves, because they alone are present during fetal life. The cervical and lumbar curves are compensatory or secondary, and are developed after birth, the former when the child is able to hold up its head (at three or four months), and to sit upright (at nine months), the latter at twelve or eighteen months, when the child begins to walk.

The vertebral column has also a slight **lateral** curvature, the convexity of which is directed toward the right side. This may be produced by muscular action, most persons using the right arm in preference to the left, especially in making long-continued efforts, when the body is curved to the right side. In support of this explanation it has been found that in one or two individuals who were left-handed, the convexity was to the left side. By others this curvature is regarded as being produced by the aortic arch and upper part of the descending thoracic aorta—a view which is supported by the fact that in cases where the viscera are transposed and the aorta is on the right side, the convexity of the curve is directed to the left side.

**Surfaces.** — **Anterior Surface.** — When viewed from in front, the width of the bodies of the vertebræ is seen to increase from the second cervical to the first thoracic; there is then a slight diminution in the next three vertebræ; below this there is again a gradual and progressive increase in width




FIG. 258.—Lateral view of the vertebral column.

as low as the sacrovertebral angle. From this point there is a rapid diminution, to the apex of the coccyx.

**Posterior Surface.**—The posterior surface of the vertebral column presents in the median line the spinous processes. In the cervical region (with the exception of the second and seventh vertebræ) these are short and horizontal, with bifid extremities. In the upper part of the thoracic region they are directed obliquely downward; in the middle they are almost vertical, and in the lower part they are nearly horizontal. In the lumbar region they are nearly horizontal. The spinous processes are separated by considerable intervals in the lumbar region, by narrower intervals in the neck, and are closely approximated in the middle of the thoracic region. Occasionally one of these processes deviates a little from the median line—a fact to be remembered in practice, as irregularities of this sort are attendant also on fractures or displacements of the vertebral column. On either side of the spinous processes is the **vertebral groove** formed by the laminae in the cervical and lumbar regions, where it is shallow, and by the laminae and transverse processes in the thoracic region, where it is deep and broad; these grooves lodge the deep muscles of the back. Lateral to the vertebral grooves are the articular processes, and still more laterally the transverse processes. In the thoracic region, the transverse processes stand backward, on a plane, considerably behind that of the same processes in the cervical and lumbar regions. In the cervical region, the transverse processes are placed in front of the articular processes, lateral to the pedicles and between the intervertebral foramina. In the thoracic region they are posterior to the pedicles, intervertebral foramina, and articular processes. In the lumbar region they are in front of the articular processes, but behind the intervertebral foramina.

**Lateral Surfaces.**—The lateral surfaces are separated from the posterior surface by the articular processes in the cervical and lumbar regions, and by the transverse processes in the thoracic region. They present, in front, the sides of the bodies of the vertebræ, marked in the thoracic region by the facets for articulation with the heads of the ribs. More posteriorly are the intervertebral foramina, formed by the juxtaposition of the vertebral notches, oval in shape, smallest in the cervical and upper part of the thoracic regions, and gradually increasing in size to the last lumbar. They transmit the spinal nerves and are situated between the transverse processes in the cervical region, and in front of them in the thoracic and lumbar regions.

**Base.**—The base of that portion of the vertebral column which is made up of the twenty-four movable vertebræ is formed by the under surface of the body of the fifth lumbar vertebræ; and the **summit**, by the upper surface of the atlas.

**Vertebral Canal.**—The vertebral canal follows the different curves of the column; it is large and triangular in those parts of the column which enjoy the greatest freedom of movement, viz., the cervical and lumbar regions; and is small and rounded in the thoracic region, where motion is more limited.

**Applied Anatomy.**—Occasionally the coalescence of the laminae is not completed, and consequently a cleft is left in the arches of the vertebræ, through which a protrusion of the spinal membranes (*dura mater* and *arachnoid*), and generally of the *medulla spinalis* itself, takes place, constituting the malformation known as *spina bifida*. This condition is most common in the lumbosacral region, but it may occur in the thoracic or cervical region, or the arches throughout the whole length of the canal may remain incomplete.

The construction of the movable part of the vertebral column of a number of pieces, securely connected together and enjoying only a slight degree of movement between any two individual pieces, but permitting of a very considerable range as a whole, allows a sufficient degree of mobility without any material diminution of strength. The many joints of which the column is composed, together with the very varied movements to which it is subjected, render it liable to sprains; but, so closely are the individual vertebræ articulated that these sprains are rarely severe, and an amount of violence sufficiently great to produce tearing of the ligaments would tend rather to cause a dislocation or fracture. The further safety of the column and its slight liability to

injury are provided for by its disposition in curves instead of in a straight line. For it is an elastic column, and must bend before it breaks; under these circumstances, being made up of three curves, it represents three columns, and greater force is required to produce bending of a short column than of a longer one that is equal to it in breadth and material. Again, the safety of the column is largely provided for by the presence between the bodies of the intervertebral fibrocartilages, which act as buffers in counteracting the effects of violent jars or shocks.

*Fracture dislocation* of the vertebral column may be caused by direct or indirect violence. Fractures from indirect violence are the more common, and here the bodies of the vertebræ are compressed, while the arches are torn asunder; in fracture from direct violence, on the other hand, the arches are compressed and the bodies of the vertebræ separated from each other. It will therefore be seen that in both classes of injury the medulla spinalis is the part least likely to be injured, and may escape damage even where there has been considerable lesion of the bony framework. When a fracture dislocation is produced by indirect violence, the displacement is almost always the same; the upper segment being driven forward on the lower, so that the medulla spinalis is compressed between the body of the vertebra below and the arch of the vertebra above.

*Diseases of the Vertebral Column.*—Spinal caries, or tuberculous disease affecting the cancellous tissue of the bodies of the vertebræ, is a very common condition. When the bodies, having been destroyed, begin to fall together, the spinous processes are necessarily thrown backward and stand out prominently, especially if the disease affect the thoracic region, which is most commonly the case. The condition then goes by the name of *angular curvature*, and great rigidity of the muscles in the affected region accompanies it. Pressure, by the inflammatory thickenings of the disease, is apt to involve the spinal nerves in the affected region, giving rise to peripheral pains, and if the disease be in the lower thoracic vertebræ the pains are referred to the epigastric or umbilical regions, and often the chief thing complained of is "belly ache." Chronic abscess formation in spinal caries is very frequent, and it nearly always forms in front of the vertebral bodies. When the disease is in the lower thoracic region, the abscess usually tracks down behind the Diaphragma and enters the Psoas sheath, forming the well-known *psoas abscess*, which may present above the inguinal ligament, or may pass beneath it into the thigh. In other cases the abscess takes a backward course between the transverse processes and presents as a *thoracic or lumbar abscess*; if the disease affect the cervical region of the vertebral column, a *post-pharyngeal abscess* results.

*Lateral curvature of the vertebral column* is a common affection in girls who are outgrowing their strength and who sit or stand long at lessons, and is due to the uneven transmission of weight down the column. In addition to the lateral displacement of the spinous processes there is a marked rotation of the bodies of the vertebræ, the displacement of which is far in excess of that of the spinous processes. When the curve is severe and the bones have actually become distorted, the condition is past cure.

*Kyphosis* is an affection in which there is an increase in the normal thoracic curve, and is due to bending forward of the upper part of the body carrying the weight of the head. It is seen in rickety children, in rapidly growing adolescents, in senile conditions, and in certain diseases, such as osteoarthritis and osteitis deformans. In the senile kyphosis often met with in aged laborers, the head is firmly fixed and bent forward and downward on to the chest, and the vertebral column is curved and rigid. The ribs are immobilized, the chest is flattened antero-posteriorly, and breathing becomes almost entirely abdominal. *Postmortem*, bony ankylosis of the ligaments and capsules of the intervertebral joints is found, with ossification of the ligamenta flava, inter-spinal and other ligaments.

It may be noted that in marked cases of spinal deformity the trachea and aorta follow closely along the line of a spinal curvature occurring in their vicinity, whereas the œsophagus between the tracheal bifurcation and the stomach often passes like a bowstring across the concavity of the curve.

*Lordosis*, on the other hand, is an exaggeration of the normal lumbar curve, the trunk being thrown backward. This is always a compensatory curve, and occurs when, from any cause such as pregnancy or tumors, the abdomen is enlarged. It is more strongly marked in cases of disease of the hip-joint where the joint is permanently retained in a flexed position, so that in order to bring the foot down to the ground the pelvis has to be tilted forward, and this is accomplished by an increase of the normal lumbar curve.

*Laminectomy.*—The operation of laminectomy is performed in cases of pressure on the medulla spinalis, where the continuity of the nerve tracts has not been completely destroyed. It consists of cutting down on and removing the laminæ and spinous processes in the affected region, so as to relieve the medulla spinalis from pressure; but it is useless in cases of complete destruction of this structure. Laminectomy is chiefly performed (1) for fracture dislocation; (2) for localized pressure in cases of spinal caries, the object here being to remove the laminæ against which the medulla spinalis is pressed by the inflammatory mass; and (3) for the removal of tumors growing inside the vertebral canal and compressing the medulla spinalis. If such cases be taken early, very satisfactory results are obtained.



## THE THORAX.

The skeleton of the **thorax** or **chest** is an osseo-cartilaginous cage, containing and protecting the principal organs of respiration and circulation. It is conical in shape, being narrow above and broad below, flattened from before backward, and longer behind than in front. It is somewhat reniform on transverse section on account of the projection of the vertebral bodies into the cavity.

**Boundaries.**—The **posterior surface** is formed by the twelve thoracic vertebræ and the posterior parts of the ribs. It is convex from above downward, and presents on either side of the middle line a deep groove, in consequence of the lateral and backward direction which the ribs take from their vertebral extremities to their angles. The **anterior surface**, formed by the sternum and costal cartilages, is flattened or slightly convex, and inclined from above downward and forward. The **lateral surfaces** are convex; they are formed by the ribs, separated from each other by the intercostal spaces, eleven in number, which are occupied by the Intercostal muscles and membranes.

The **upper opening** of the thorax is reniform in shape, being broader from side to side than from before backward. It is formed by the first thoracic vertebra behind, the upper margin of the sternum in front, and the first rib on either side. It slopes downward and forward, so that the anterior part of the opening is on a lower level than the posterior. Its antero-posterior diameter is about 5 cm., and its transverse diameter about 10 cm. The **lower opening** is formed by the twelfth thoracic vertebra behind, by the eleventh and twelfth ribs at the sides, and in front by the cartilages of the tenth, ninth, eighth, and seventh ribs, which ascend on either side and form an angle, the **subcostal angle**, into the apex of which the xiphoid process projects. The lower opening is wider transversely than from before backward, and slopes obliquely downward and backward, it is closed by the Diaphragma which forms the floor of the thorax.

The thorax of the female differs from that of the male as follows: 1. Its capacity is less. 2. The sternum is shorter. 3. The upper margin of the sternum is on a level with the lower part of the body of the third thoracic vertebra, whereas in the male it is on a level with the lower part of the body of the second. 4. The upper ribs are more movable, and so allow a greater enlargement of the upper part of the thorax.

### The Sternum (Breast Bone).

The **sternum** (Figs. 259 to 261) is an elongated, flattened bone, forming the middle portion of the anterior wall of the thorax. Its upper end supports the clavicles, and its margins articulate with the cartilages of the first seven pairs of ribs. It consists of three parts, named from above downward, the **manubrium**, the **body** or **gladiolus**, and the **xiphoid process**; in early life the body consists of four segments or *sternebrae*. In its natural position the inclination of the bone is oblique from above, downward and forward. It is slightly convex in front and concave behind; broad above, becoming narrowed at the point where the manubrium joins the body, after which it again widens a little to below the middle of the body, and then narrows to its lower extremity. Its average length in the adult is about 17 cm., and is rather greater in the male than in the female.

**Manubrium** (*manubrium sterni*).—The manubrium is of a somewhat quadrangular form, broad and thick above, narrow below at its junction with the body.

**Surfaces.**—Its **anterior surface**, convex from side to side, concave from above downward, is smooth, and affords attachment on either side to the sternal origins of the Pectoralis major and Sternocleidomastoideus. In well-marked bones the ridges limiting the attachments of these muscles are very distinct. Its **posterior**

**surface**, concave and smooth, affords attachment on either side to the Sternal-hyoideus and Sternothyroideus.

**Borders.**—The **superior border** is the thickest and presents at its centre the **jugular or presternal notch**; on either side of the notch is an oval articular surface, directed upward, backward, and lateralward, for articulation with the sternal end of the




FIG. 259.—Anterior surface of sternum and costal cartilages.

clavicle. The **inferior border**, oval and rough, is covered in a recent state with a thin layer of cartilage, for articulation with the body. The **lateral borders** are each marked above by a depression for the first costal cartilage, and below by a small facet, which, with a similar facet on the upper angle of the body, forms a notch for the reception of the costal cartilage of the second rib. Between the depression

for the first costal cartilage and the demi-facet for the second is a narrow, curved edge, which slopes from above downward and medialward.

**Body** (*corpus sterni*; *gladiolus*).—The body, considerably longer, narrower, and thinner than the manubrium, attains its greatest breadth close to the lower end.

**Surfaces.**—Its **anterior surface** is nearly flat, directed upward and forward, and marked by three transverse ridges which cross the bone opposite the third, fourth, and fifth articular depressions.<sup>1</sup> It affords attachment on either side to the sternal origin of the Pectoralis major. At the junction of the third and fourth pieces of the body is occasionally seen an orifice, the **sternal foramen**, of varying size and form. The **posterior surface**, slightly concave, is also marked by three transverse lines, less distinct, however, than those in front; from its lower part, on either side, the Transversus thoracis takes origin.




FIG. 260.—Posterior surface of sternum.




FIG. 261.—Lateral border of sternum.

**Borders.**—The **superior border** is oval and articulates with the manubrium, the junction of the two forming the **sternal angle** (*angulus Ludovici*<sup>2</sup>). The **inferior border** is narrow, and articulates with the xiphoid process. Each **lateral border** (Fig. 261), at its superior angle, has a small facet, which with a similar facet on the manubrium, forms a cavity for the cartilage of the second rib; below this are four angular depressions which receive the cartilages of the third, fourth, fifth, and sixth ribs, while the inferior angle has a small facet, which, with a corresponding one on the xiphoid process, forms a notch for the cartilage of the seventh rib. These articular depressions are separated by a series of curved interarticular intervals, which diminish in length from above downward, and correspond to

<sup>1</sup> Paterson (The Human Sternum, 1904), who examined 524 specimens, points out that these ridges are altogether absent in 26.7 per cent.; that in 69 per cent. a ridge exists opposite the third costal attachment; in 39 per cent. opposite the fourth; and in 4 per cent. only, opposite the fifth.

<sup>2</sup> Named after the French surgeon Antoine Louis, 1723–1792. The Latin name *angulus Ludovici* is not infrequently mistranslated into English as "the angle of Ludwig."




FIG. 262.—Ossification of the sternum.




FIG. 263




FIG. 264.—Peculiarities.




FIG. 265

the intercostal spaces. Most of the cartilages belonging to the true ribs, as will be seen from the foregoing description, articulate with the sternum at the lines of junction of its primitive component segments. This is well seen in many of the lower animals, where the parts of the bone remain ununited longer than in man.

**Xiphoid Process** (*processus xiphoideus; ensiform or xiphoid appendix*).—The xiphoid process is the smallest of the three pieces: it is thin and elongated, cartilaginous in structure in youth, but more or less ossified at its upper part in the adult.

**Surfaces.**—Its **anterior surface** affords attachment on either side to the anterior costoxiphoid ligament and a small part of the Rectus abdominis; its **posterior surface**, to the posterior costoxiphoid ligament and to some of the fibres of the Diaphragma and Transversus thoracis, its **lateral borders**, to the aponeuroses of the abdominal muscles. Above, it articulates with the lower end of the body, and on the front of each superior angle presents a facet for part of the cartilage of the seventh rib; below, by its pointed extremity, it gives attachment to the linea alba. The xiphoid process varies much in form; it may be broad and thin, pointed, bifid, perforated, curved, or deflected considerably to one or other side.

**Structure.**—The sternum is composed of highly vascular cancellous tissue, covered by a thin layer of compact bone which is thickest in the manubrium between the articular facets for the clavicles.

**Ossification.**—The sternum originally consists of two cartilaginous bars, situated one on either side of the median plane and connected with the cartilages of the upper nine ribs of its own side. These two bars fuse with each other along the middle line to form the cartilaginous sternum which is ossified from *six* centres: one for the manubrium, four for the body, and one for the xiphoid process (Fig. 262). The ossific centres appear in the intervals between the articular depressions for the costal cartilages, in the following order: in the manubrium and first piece of the body, during the sixth month; in the second and third pieces of the body, during the seventh month of fetal life; in its fourth piece, during the first year after birth; and in the xiphoid process, between the fifth and eighteenth years. The centres make their appearance at the upper parts of the segments, and proceed gradually downward.<sup>1</sup> To these may be added the occasional existence of two small episternal centres, which make their appearance one on either side of the jugular notch; they are probably vestiges of the episternal bone of the monotremata and lizards. Occasionally some of the segments are formed from more than one centre, the number and position of which vary (Fig. 264). Thus, the first piece may have two, three, or even six centres. When two are present, they are generally situated one above the other, the upper being the larger; the second piece has seldom more than one; the third, fourth, and fifth pieces are often formed from two centres placed laterally, the irregular union of which explains the rare occurrence of the sternal foramen (Fig. 265), or of the vertical fissure which occasionally intersects this part of the bone; these conditions are further explained by the manner in which the cartilaginous sternum is formed. Union of the various centres of the body begins about puberty, and proceeds from below upward (Fig. 263); by the age of twenty-five they are all united. The xiphoid process may become joined to the body before the age of thirty, but this occurs more frequently after forty; on the other hand, it sometimes remains ununited in old age. In advanced life the manubrium is occasionally joined to the body by bone. When this takes place, however, the bony tissue is generally only superficial, the central portion of the intervening cartilage remaining unossified.

**Articulations.**—The sternum articulates on either side with the clavicle and upper seven costal cartilages.

### The Ribs (Costae).

The **ribs** are elastic arches of bone, which form a large part of the thoracic skeleton. They are twelve in number on either side; but this number may be increased by the development of a cervical or lumbar rib, or may be diminished to eleven. The first seven are connected behind with the vertebral column, and in front, through the intervention of the costal cartilages, with the sternum (Fig. 259); they are called **true** or **vertebro-sternal ribs**.<sup>2</sup> The remaining five are **false**

<sup>1</sup> Out of 141 sterna between the time of birth and the age of sixteen years, Paterson (*op. cit.*) found the fourth or lowest centre for the body present only in thirty-eight cases—i. e., 26.9 per cent.

<sup>2</sup> Sometimes the eighth rib cartilage articulates with the sternum; this condition occurs more frequently on the right than on the left side.

ribs; of these, the first three have their cartilages attached to the cartilage of the rib above (**vertebro-chondral**): the last two are free at their anterior extremities




FIG. 266.—A central rib of the left side. Inferior aspect.

and are termed **floating** or **vertebral ribs**. The ribs vary in their direction, the upper ones being less oblique than the lower; the obliquity reaches its maximum at the ninth rib, and gradually decreases from that rib to the twelfth. The ribs are situated one below the other in such a manner that spaces called **intercostal spaces** are left between them. The length of each space corresponds to that of the adjacent ribs and their cartilages; the breadth is greater in front than behind, and between the upper than the lower ribs. The ribs increase in length from the first to the seventh, below which they diminish to the twelfth. In breadth they decrease from above downward; in the upper ten the greatest breadth is at the sternal extremity.

**Common Characteristics of the Ribs** (Figs. 266, 267).—A rib from the middle of the series should be taken in order to study the common characteristics of these bones.

Each rib has two extremities, a **posterior** or **vertebral**, and an **anterior** or **sternal**, and an intervening portion—the **body** or **shaft**.

**Posterior Extremity.**—The **posterior** or **vertebral extremity** presents for examination a **head**, **neck**, and **tubercle**.

The **head** is marked by a kidney-shaped articular surface, divided by a horizontal crest into two facets for articulation with the depression formed by the junction of the bodies of two contiguous thoracic vertebræ; the upper facet is the smaller; to the crest is attached the interarticular ligament.

The **neck** is the flattened portion which extends lateralward from the head; it is about 2.5 cm. long, and is placed in front of the transverse process of the lower of the two vertebræ with which the head articulates. Its **anterior surface** is flat and smooth, its **posterior** rough for the attachment of the ligament of the



neck, and perforated by numerous foramina. Of its two borders the **superior** presents a rough crest (*crista colli costae*) for the attachment of the anterior costotransverse ligament; its **inferior border** is rounded. On the posterior surface at the junction of the neck and body, and nearer the lower than the upper border, is an eminence—the **tubercle**; it consists of an articular and a non-articular portion. The *articular portion*, the lower and more medial of the two, presents a small, oval surface for articulation with the end of the transverse process of the lower of the two vertebræ to which the head is connected. The *non-articular portion* is a rough elevation, and affords attachment to the ligament of the tubercle. The tubercle is much more prominent in the upper than in the lower ribs.

**Body.**—The **body** or **shaft** is thin and flat, with two surfaces, an external and an internal; and two borders, a superior and an inferior. The **external surface** is convex, smooth, and marked, a little in front of the tubercle, by a prominent line, directed downward and lateralward; this gives attachment to a tendon of the *Iliocostalis*, and is called the **angle**. At this point the rib is bent in two directions, and at the same time twisted on its long axis. If the rib be laid upon its lower border, the portion of the body in front of the angle rests upon this border, while the portion behind the angle is bent medialward and at the same time tilted upward; as the





FIG. 267.—A central rib of the left side, viewed from behind.

result of the twisting, the external surface, behind the angle, looks downward, and in front of the angle, slightly upward. The distance between the angle and the tubercle is progressively greater from the second to the tenth ribs. The portion between the angle and the tubercle is rounded, rough, and irregular, and serves for the attachment of the *Longissimus dorsi*. The external surface presents, toward its sternal end, an oblique line, the **anterior angle**. The **internal surface** is concave, smooth, directed a little upward behind the angle, a little downward in front of it, and is marked by a ridge which commences at the lower extremity of the head; this ridge is strongly marked as far as the angle, and gradually becomes lost at the junction of the anterior and middle thirds of the bone. Between it and the inferior border is a groove, the **costal groove**, for the intercostal vessels and nerve. At the back part of the bone, this groove belongs to the inferior border, but just in front of the angle, where it is deepest and broadest, it is on the internal surface. The superior edge of the groove is rounded and serves for the attachment of an *Intercostalis internus*; the inferior edge corresponds to the lower margin of the rib, and gives attachment to an *Intercostalis externus*. Within the groove are seen the orifices of numerous small foramina for nutrient vessels

which traverse the shaft obliquely from before backward. The **superior border**, thick and rounded, is marked by an external and an internal lip, more distinct behind than in front, which serve for the attachment of *Intercostales externus* and *internus*. The **inferior border** is thin, and has attached to it an *Intercostalis externus*.

**Anterior Extremity.**—The **anterior or sternal extremity** is flattened, and presents a porous, oval, concave depression, into which the costal cartilage is received.



FIGS. 268 to 272.—Peculiar ribs.

**Peculiar Ribs.**—The first, second, tenth, eleventh, and twelfth ribs present certain variations from the common characteristics described above, and require special consideration.

**First Rib.**—The first rib (Fig. 268) is the most curved and usually the shortest of all the ribs; it is broad and flat, its surfaces looking upward and downward, and its borders inward and outward. The **head** is small, rounded, and possesses

only a single articular facet, for articulation with the body of the first thoracic vertebra. The **neck** is narrow and rounded. The **tubercle**, thick and prominent, is placed on the outer border. There is *no angle*, but at the tubercle the rib is slightly bent, with the convexity upward, so that the head of the bone is directed downward. The **upper surface** of the body is marked by two shallow grooves, separated from each other by a slight ridge prolonged internally into a tubercle, the **scalene tubercle**, for the attachment of the *Scalenus anterior*; the anterior groove transmits the subclavian vein, the posterior the subclavian artery and the lowest trunk of the brachial plexus.<sup>1</sup> Behind the posterior groove is a rough area for the attachment of the *Scalenus medius*. The **under surface** is smooth, and destitute of a costal groove. The **outer border** is convex, thick, and rounded, and at its posterior part gives attachment to the first digitation of the *Serratus anterior*; the **inner border** is concave, thin, and sharp, and marked about its centre by the scalene tubercle. The **anterior extremity** is larger and thicker than that of any of the other ribs.

**Second Rib.**—The second rib (Fig. 269) is much longer than the first, but has a very similar curvature. The non-articular portion of the **tubercle** is occasionally only feebly marked. The **angle** is slight, and situated close to the tubercle. The **body** is not twisted, so that both ends touch any plane surface upon which it may be laid; but there is a bend, with its convexity upward, similar to, though smaller than that found in the first rib. The body is not flattened horizontally like that of the first rib. Its **external surface** is convex, and looks upward and a little outward; near the middle of it is a rough eminence for the origin of the lower part of the first and the whole of the second digitation of the *Serratus anterior*; behind and above this is attached the *Scalenus posterior*. The **internal surface**, smooth, and concave, is directed downward and a little inward: on its posterior part there is a short costal groove.

**Tenth Rib.**—The tenth rib (Fig. 270) has only a single articular facet on its head.

**Eleventh and Twelfth Ribs.**—The eleventh and twelfth ribs (Figs. 271 and 272) have each a single articular facet on the head, which is of rather large size; they have *no necks or tubercles*, and are pointed at their anterior ends. The eleventh has a slight angle and a shallow costal groove. The twelfth has neither; it is much shorter than the eleventh, and its head is inclined slightly downward. Sometimes the twelfth rib is even shorter than the first.

**Structure.**—The ribs consist of highly vascular cancellous tissue, enclosed in a thin layer of compact bone.

**Ossification.**—Each rib, with the exception of the last two, is ossified from *four* centres; a primary centre for the body, and three epiphysial centres; one for the head and one each for the articular and non-articular parts of the tubercle. The eleventh and twelfth ribs have each only *two* centres, those for the tubercles being wanting. Ossification begins near the angle toward the end of the second month of fetal life, and is seen first in the sixth and seventh ribs. The epiphyses for the head and tubercle make their appearance between the sixteenth and twentieth years, and are united to the body about the twenty-fifth year. Fawcett<sup>2</sup> states that "in all probability there is usually no epiphysis on the non-articular part of the tuberosity below the sixth or seventh rib.

### The Costal Cartilages (*Cartilagine Costales*).

The **costal cartilages** (Fig. 259) are bars of hyaline cartilage which serve to prolong the ribs forward and contribute very materially to the elasticity of the walls of the thorax. The first seven pairs are connected with the sternum; the next three are each articulated with the lower border of the cartilage of the preceding rib; the last two have pointed extremities, which end in the wall of the abdomen. Like the ribs, the costal cartilages vary in their length, breadth, and

<sup>1</sup> Anat. Anzeiger, 1910, Band xxxvi.

<sup>2</sup> Journal of Anatomy and Physiology, vol. xlv.

direction. They increase in length from the first to the seventh, then gradually decrease to the twelfth. Their breadth, as well as that of the intervals between them, diminishes from the first to the last. They are broad at their attachments to the ribs, and taper toward their sternal extremities, excepting the first two, which are of the same breadth throughout, and the sixth, seventh, and eighth, which are enlarged where their margins are in contact. They also vary in direction: the first descends a little, the second is horizontal, the third ascends slightly, while the others are angular, following the course of the ribs for a short distance, and then ascending to the sternum or preceding cartilage. Each costal cartilage presents two surfaces, two borders, and two extremities.

**Surfaces.**—The **anterior surface** is convex, and looks forward and upward: that of the first gives attachment to the costoclavicular ligament and the Subclavius muscle; those of the first six or seven at their sternal ends, to the Pectoralis major. The others are covered by, and give partial attachment to, some of the flat muscles of the abdomen. The **posterior surface** is concave, and directed backward and downward; that of the first gives attachment to the Sternothyroideus, those of the third to the sixth inclusive to the Transversus thoracis, and the six or seven inferior ones to the Transversus abdominis and the Diaphragma.

**Borders.**—Of the two borders the **superior** is concave, the **inferior** convex; they afford attachment to the Intercostales interni: the upper border of the sixth gives attachment also to the Pectoralis major. The inferior borders of the sixth, seventh, eighth, and ninth cartilages present heel-like projections at the points of greatest convexity. These projections carry smooth oblong facets which articulate respectively with facets on slight projections from the upper borders of the seventh, eighth, ninth, and tenth cartilages.

**Extremities.**—The **lateral end** of each cartilage is continuous with the osseous tissue of the rib to which it belongs. The **medial end** of the first is continuous with the sternum; the medial ends of the six succeeding ones are rounded and are received into shallow concavities on the lateral margins of the sternum. The medial ends of the eighth, ninth, and tenth costal cartilages are pointed, and are connected each with the cartilage immediately above. Those of the eleventh and twelfth are pointed and free. In old age the costal cartilages are prone to undergo superficial ossification.

**Applied Anatomy.**—Fracture of the sternum is by no means common, owing, no doubt, to the elasticity of the ribs and their cartilages which support it like so many springs. The fracture usually occurs in the upper half of the body. Dislocation of the body from the manubrium may take place, and is sometimes described as a fracture.

The bone is frequently the seat of gummatous tumors and not uncommonly is affected with caries.

The ribs are frequently broken, though from their connections and shape they are able to withstand great force, yielding under the injury and recovering themselves like a spring. The middle ribs are the most liable to fracture. The first and to a less extent the second, being protected by the clavicle, are rarely fractured; and the eleventh and twelfth on account of their loose and floating condition enjoy a like immunity. The fracture generally occurs from indirect violence, from forcible compression of the chest wall, and the bone then gives way at its weakest part, i. e., just in front of the angle. But the ribs may also be broken by direct violence, in which case the bone is driven inward at the point struck. Fracture of the ribs is frequently complicated with some injury to the viscera contained within the thorax or upper part of the abdominal cavity; this is most likely to occur in fractures from direct violence.

Fracture of the costal cartilages or separation of the cartilages from the ribs, may also take place, though they are comparatively rare injuries. In workmen the pressure of tools may displace the xiphoid process inward.

The ribs are frequently the seat of tuberculous disease, with the formation of a chronic abscess in the chest wall. This may not immediately overlie the carious portion of rib, as the pus is often directed a considerable distance along the costal groove before appearing beneath the integument.

Resection of a portion of a rib is often required in order to give efficient drainage to an empyema; this is referred to in the description of the respiratory organs.

*Cervical ribs* derived from the seventh cervical vertebra (page 201) are of not infrequent occurrence, and are important clinically because they may give rise to obscure nervous or vascular symptoms. The cervical rib may be a mere epiphysis articulating only with the transverse process of the vertebra, but more commonly it consists of a defined head, neck, and tubercle, with or without a body. It extends lateralward, or forward and lateralward, into the posterior triangle of the neck, where it may terminate in a free end or may join the first thoracic rib, the first costal cartilage, or the sternum.<sup>1</sup> It varies much in shape, size, direction, and mobility. If it reach far enough forward, part of the brachial plexus and the subclavian artery and vein cross over it, and are apt to suffer compression in so doing. Pressure on the artery may obstruct the circulation so much that arterial thrombosis results, causing gangrene of the finger tips. Pressure on the nerves is commoner, and affects the eighth cervical and first thoracic nerves, causing paralysis of the muscles they supply, and neuralgic pains and paresthesia in the area of skin to which they are distributed: no oculopupillary changes are to be found. If these symptoms be severe, removal of the rib or as much of it as causes pressure on the vessels and nerves is called for. The operation is not free from difficulty, and has been followed by paralysis of the muscles and by subclavian aneurism, due to injuries inflicted in the course of the operation.

The *thorax* is frequently found to be altered in shape in certain diseases.

In *rickets*, the ends of the ribs, where they join the costal cartilages, become enlarged, giving rise to the so-called "rickety rosary," which in mild cases is only found on the internal surface of the thorax. Lateral to these enlargements the softened ribs sink in, so as to present a groove passing downward and lateralward on either side of the sternum. This bone is forced forward by the bending of the ribs, and the antero-posterior diameter of the chest is increased. The ribs affected are the second to the eighth, the lower ones being prevented from falling in by the presence of the liver, stomach, and spleen; and when the abdomen is distended, as it often is in rickets, the lower ribs may be pushed outward, causing a transverse groove (Harrison's sulcus) just above the costal arch. This deformity or forward projection of the sternum, often asymmetrical, is known as *pigeon breast*, and may be taken as evidence of active or old rickets except in cases of primary spinal curvature. In many instances it is associated in children with obstruction in the upper air passages, due to enlarged tonsils or adenoid growths. In some rickety children or adults, and also in others who give no history or further evidence of having had rickets, an opposite condition obtains. The lower part of the sternum and often the xiphoid process as well are deeply depressed backward, producing an oval hollow in the lower sternal and upper epigastric regions. This is known as *funnel breast* (German, *Trichterbrust*); it never appears to produce the least disturbance of any of the vital functions. The *phthisical chest* is often long and narrow, and with great obliquity of the ribs and projection of the scapulæ. In *pulmonary emphysema* the chest is enlarged in all its diameters, and presents on section an almost circular outline. It has received the name of the *barrel-shaped chest*. In severe cases of *lateral curvature of the vertebral column* the thorax becomes much distorted. In consequence of the rotation of the bodies of the vertebrae which takes place in this disease, the ribs opposite the convexity of the dorsal curve become extremely convex behind, being thrown out and bulging, and at the same time flattened in front, so that the two ends of the same rib are almost parallel. Coincidentally with this the ribs on the opposite side, on the concavity of the curve, are sunk and depressed behind, and bulging and convex in front.

It is commonly said that in tuberculosis of the lungs the chest is characteristically "flat," that is to say, that the ratio of its antero-posterior to its transverse diameter is less than the normal. But by careful measurement in a large number of cases, Woods Hutchinson has shown that this is not so. Taking the transverse diameter of the chest at the nipple level as = 100, he finds that in the normal adult man between the ages of twenty and forty-four the antero-posterior diameter = 71. In 82 phthisical subjects it was = 79.5, and in 30 "flat-chested" persons was = 80. He explains the error as an optical illusion, due to rolling forward of the shoulders in the "flat chested;" the back is seen to be correspondingly rounded and protuberant, while the forward position of the shoulders and clavicles lends an appearance of flattening to the chest.

More or less shrinkage of one side of the thorax is often seen as a consequence of adhesive pleurisy, in which the pulmonary and parietal pleuræ adhere closely to one another and the lung becomes collapsed and fibrosed. If this process be at all complete, great deformity of the chest results, the ribs on the affected side falling in, together with obliteration of the intercostal spaces; the contents of the mediastinal cavity are pulled over toward the affected side, the other lung becomes emphysematous compensatorily. The vertebral column becomes scoliotic, with the concavity of the curve toward the affected side.

## THE SKULL.

The *skull* is supported on the summit of the vertebral column, and is of an oval shape, wider behind than in front. It is composed of a series of flattened

<sup>1</sup> W. Thorburn, *The Medical Chronicle*, Manchester, 1907, 4th series, xiv, No. 3.

or irregular bones which, with one exception (the mandible), are immovably jointed together. It is divisible into two parts: (1) the **cranium**, which lodges and protects the brain, consists of eight bones, and (2) the **skeleton of the face**, of fourteen, as follows:

Skull, 22 bones	{	Cranium, 8 bones	{	Occipital.
				Two Parietals.
	{	Face, 14 bones	{	Frontal.
				Two Temporals.
				Sphenoidal.
				Ethmoidal.
				Two Nasals.
				Two Maxillæ.
				Two Lacrimals.
				Two Zygomatics.
				Two Palatines.
				Two Inferior Nasal Conchæ.
				Vomer.
				Mandible.

In the Basle nomenclature, certain bones developed in association with the nasal capsule, viz., the inferior nasal conchæ, the lacrimals, the nasals, and the vomer, are grouped as cranial and not as facial bones.

The hyoid bone, situated at the root of the tongue and attached to the base of the skull by ligaments, is described in this section.

## THE CRANIAL BONES (OSSA CRANII).

### The Occipital Bone (Os Occipitale).

The **occipital bone** (Figs. 273, 274), situated at the back and lower part of the **cranium**, is trapezoid in shape and curved on itself. It is pierced by a large oval aperture, the **foramen magnum**, through which the cranial cavity communicate with the vertebral canal.

The curved, expanded plate behind the foramen magnum is named the **squama**; the thick, somewhat quadrilateral piece in front of the foramen is called the **basilar part**, whilst on either side of the foramen is the **lateral portion**.

**The Squama** (*squama occipitalis*).—The squama, situated above and behind the foramen magnum, is curved from above downward and from side to side.

**Surfaces.**—The **external surface** is convex and presents midway between the summit of the bone and the foramen magnum a prominence, the **external occipital protuberance**. Extending lateralward from this on either side are two curved lines, one a little above the other. The upper, often faintly marked, is named the **highest nuchal line**, and to it the galea aponeurotica is attached. The lower is termed the **superior nuchal line**. That part of the squama which lies above the highest nuchal lines is named the **planum occipitale**, and is covered by the Occipitalis muscle; that below, termed the **planum nuchale**, is rough and irregular for the attachment of several muscles. From the external occipital protuberance a ridge or crest, the **median nuchal line**, often faintly marked, descends to the foramen magnum, and affords attachment to the ligamentum nuchæ; running from the middle of this line across either half of the nuchal plane is the **inferior nuchal line**. Several muscles are attached to the outer surface of the squama, thus: the superior nuchal line gives origin to the Occipitalis and Trapezius, and insertion



to the Sternocleidomastoideus and Splenius capitis: into the surface between the superior and inferior nuchal lines the Semispinalis capitis and the Obliquus capitis superior are inserted, while the inferior nuchal line and the area below it receive the insertions of the Recti capitis posteriores major and minor. The posterior atlantoöccipital membrane is attached around the postero-lateral part of the foramen magnum, just outside the margin of the foramen.




FIG. 273.—Occipital bone. Outer surface.

The **internal surface** is deeply concave and divided into four fossæ by a **cruciate eminence**. The upper two fossæ are triangular and lodge the occipital lobes of the cerebrum; the lower two are quadrilateral and accommodate the hemispheres of the cerebellum. At the point of intersection of the four divisions of the cruciate eminence is the **internal occipital protuberance**. From this protuberance the upper division of the cruciate eminence runs to the superior angle of the bone, and on one side of it (generally the right) is a deep groove, the **sagittal sulcus**, which lodges the hinder part of the superior sagittal sinus; to the margins of this sulcus the falx cerebri is attached. The lower division of the cruciate eminence is prominent, and is named the **internal occipital crest**; it bifurcates near the foramen magnum and gives attachment to the falx cerebelli; in the attached margin of this falx is the occipital sinus, which is sometimes duplicated. In the upper part of the internal occipital crest, a small depression is sometimes distinguishable; it is termed the **vermian fossa** since it is occupied by part of the vermis of the cerebellum. Transverse grooves, one on either side, extend from the internal occipital protuberance to the lateral angles of the bone; those grooves accommodate the transverse sinuses, and their prominent margins give attachment to the tentorium cerebelli. The groove on the right side is usually larger than that on the left, and is

continuous with that for the superior sagittal sinus. Exceptions to this condition are, however, not infrequent; the left may be larger than the right or the two may be almost equal in size. The angle of union of the superior sagittal and transverse sinuses is named the **confluence of the sinuses** (*torcular Herophili*<sup>1</sup>), and its position is indicated by a depression situated on one or other side of the protuberance.




FIG. 274.—Occipital bone. Inner surface.

**Lateral Parts** (*pars lateralis*).—The lateral parts are situated at the sides of the foramen magnum; on their under surfaces are the **condyles** for articulation with the superior facets of the atlas. The condyles are oval or reniform in shape, and their anterior extremities, directed forward and medialward, are closer together than their posterior, and encroach on the basilar portion of the bone; the posterior extremities extend back to the level of the middle of the foramen magnum. The articular surfaces of the condyles are convex from before backward and from side to side, and look downward and lateralward. To their margins are attached the capsules of the atlantoöccipital articulations, and on the medial side of each is a rough impression or tubercle for the alar ligament. At the base of either condyle the bone is tunnelled by a short canal, the **hypoglossal canal** (*ante*<sup>s</sup> a *condyloid foramen*). This begins on the cranial surface of the bone immediately above the foramen magnum, and is directed lateralward and forward above

<sup>1</sup> The columns of blood coming in different directions were supposed to be pressed together at this point (as a wine press).

condyle. It may be partially or completely divided into two by a spicule of bone; it gives exit to the hypoglossal or twelfth cerebral nerve, and entrance to a meningeal branch of the ascending pharyngeal artery. Behind either condyle is a depression, the **condyloid fossa**, which receives the posterior margin of the superior facet of the atlas when the head is bent backward; the floor of this fossa is sometimes perforated by the **condyloid canal**, through which an emissary vein passes from the transverse sinus. Extending lateralward from the posterior half of the condyle is a quadrilateral plate of bone, the **jugular process**, excavated in front by the **jugular notch**, which, in the articulated skull, forms the posterior part of the jugular foramen. The jugular notch may be divided into two by a bony spicule, the **intra-jugular process**, which projects lateralward above the hypoglossal canal. The under surface of the jugular process is rough, and gives attachment to the Rectus capitis lateralis muscle and the lateral atlantooccipital ligament; from this surface an eminence, the **paramastoid process**, sometimes projects downward, and may be of sufficient length to reach, and articulate with, the transverse process of the atlas. Laterally the jugular process presents a rough quadrilateral or triangular area which is joined to the jugular surface of the temporal bone by a plate of cartilage; after the age of twenty-five this plate tends to ossify.

The **upper surface** of the lateral part presents an oval eminence, the **jugular tubercle**, which overlies the hypoglossal canal and is sometimes crossed by an oblique groove for the glossopharyngeal, vagus, and accessory nerves. On the upper surface of the jugular process is a deep groove which curves medialward and forward and is continuous with the jugular notch. This groove lodges the terminal part of the transverse sinus, and opening into it, close to its medial margin, is the orifice of the condyloid canal.

**Basilar Part** (*pars basilaris*).—The basilar part extends forward and upward from the foramen magnum, and presents *in front* an area more or less quadrilateral in outline. In the young skull this area is rough and uneven, and is joined to the body of the sphenoid by a plate of cartilage. By the twenty-fifth year this cartilaginous plate is ossified, and the occipital and sphenoid form a continuous bone.

**Surfaces**.—On its **lower surface**, about 1 cm. in front of the foramen magnum, is the **pharyngeal tubercle** which gives attachment to the fibrous raphé of the pharynx. On either side of the middle line the Longus capitis and Rectus capitis anterior are inserted, and immediately in front of the foramen magnum the anterior atlantooccipital membrane is attached.

The **upper surface** presents a broad, shallow groove which inclines upward and forward from the foramen magnum; it supports the medulla oblongata, and near the margin of the foramen magnum gives attachment to the membrana tectoria. On the lateral margins of this surface are faint grooves for the inferior petrosal sinuses.

**Foramen Magnum**.—The foramen magnum is a large oval aperture with its long diameter antero-posterior; it is wider behind than in front where it is encroached upon by the condyles. It transmits the medulla oblongata and its membranes, the accessory nerves, the vertebral arteries, the anterior and posterior spinal arteries, and the membrana tectoria and alar ligaments.

**Angles**.—The **superior angle** of the occipital bone articulates with the occipital angles of the parietal bones and, in the fetal skull, corresponds in position with the **anterior fontanelle**. The **inferior angle** is fused with the body of the sphenoid. The **lateral angles** are situated at the extremities of the grooves for the transverse sinuses: each is received into the interval between the mastoid angle of the parietal and the mastoid part of the temporal.

**Borders**.—The **superior borders** extend from the superior to the lateral angles: anteriorly deeply serrated for articulation with the occipital borders of the parietals, sinus form by this union the **lambdoidal suture**. The **inferior borders** extend from the g

the lateral angles to the inferior angle; the upper half of each articulates with the mastoid portion of the corresponding temporal, the lower half with the petrous part of the same bone. These two portions of the inferior border are separated from one another by the jugular process, the notch on the anterior surface of which forms the posterior part of the jugular foramen.

**Structure.**—The occipital, like the other cranial bones, consists of two compact lamellæ, called the *outer* and *inner tables*, between which is the cancellous tissue or diploë; the bone is especially thick at the ridges, protuberances, condyles, and anterior part of the basilar part; in the inferior fossæ it is thin, semitransparent, and destitute of diploë.

**Ossification** (Fig. 275).—The planum occipitale of the squama is developed in membrane, and may remain separate throughout life when it constitutes the *interparietal* bone; the rest of the bone is developed in cartilage. The number of nuclei for the planum occipitale is usually given as four, two appearing near the middle line about the second month, and two some little distance from the middle line about the third month of fetal life. The planum nuchale of the squama is ossified from two centres, which appear about the seventh week of fetal life and soon unite to form a single piece. Union of the upper and lower portions of the squama takes place in the third month of fetal life. An occasional centre (Kerckring) appears in the posterior margin of the foramen magnum during the fifth month; this forms a separate ossicle (sometimes double) which unites with the rest of the squama before birth. Each of the lateral parts begins to ossify from a single centre during the eighth week of fetal life. The basilar portion is ossified from two centres, one in front of the other; these appear about the sixth week of fetal life and rapidly coalesce. Mall<sup>1</sup> states that the planum occipitale is ossified from two centres and the basilar portion from one. About the fourth year the squama and the two lateral portions unite, and about the sixth year the bone consists of a single piece. Between the eighteenth and twenty-fifth years the occipital and sphenoid become united, forming a single bone.

**Articulations.**—The occipital articulates with *six* bones: the two parietals, the two temporals, the sphenoid, and the atlas.




FIG. 275.—Occipital bone at birth.

### The Parietal Bone (Os Parietale).

The **parietal bones** form, by their union, the sides and roof of the cranium. Each bone is irregularly quadrilateral in form, and has two surfaces, four borders, and four angles.

**Surfaces.**—The **external surface** (Fig. 276) is convex, smooth, and marked near the centre by an eminence, the **parietal eminence** (*tuber parietale*), which indicates the point where ossification commenced. Crossing the middle of the bone in an arched direction are two curved lines, the **superior** and **inferior temporal lines**; the former gives attachment to the temporal fascia, and the latter indicates the upper limit of the muscular origin of the Temporalis. Above these lines the bone is covered by the *galea aponeurotica*; below them it forms part of the temporal fossa, and affords attachment to the Temporalis muscle. At the back part and close to the upper or sagittal border is the **parietal foramen**, which transmits a vein to the superior sagittal sinus, and sometimes a small branch of the occipital artery; it is not constantly present, and its size varies considerably.

<sup>1</sup> American Journal of Anatomy, 1906, vol. v.



The **internal surface** (Fig. 277) is concave; it presents depressions corresponding to the cerebral convolutions, and numerous furrows for the ramifications of the middle meningeal vessel;<sup>1</sup> the latter run upward and backward from the sphenoidal angle, and from the central and posterior part of the **squamous border**. Along the upper margin is a shallow groove, which, together with that on the opposite parietal, forms a channel, the **sagittal sulcus**, for the superior sagittal sinus; the edges of the sulcus afford attachment to the falx cerebri. Near the groove are several depressions, best marked in the skulls of old persons, for the **arachnoid granulations** (*Pacchionian bodies*). In the groove is the internal opening of the parietal foramen when that aperture exists.




FIG. 276.—Left parietal bone. Outer surface.

**Borders.**—The **sagittal border**, the longest and thickest, is dentated and articulates with its fellow of the opposite side, forming the sagittal suture. The **squamous border** is divided into three parts: of these, the anterior is thin and pointed, bevelled at the expense of the outer surface, and overlapped by the tip of the great wing of the sphenoid; the middle portion is arched, bevelled at the expense of the outer surface, and overlapped by the squama of the temporal; the posterior part is thick and serrated for articulation with the mastoid portion of the temporal. The **frontal border** is deeply serrated, and bevelled at the expense of the outer surface above and of the inner below; it articulates with the frontal bone, forming one-half of the **coronal suture**. The **occipital border**, deeply denticulated, articulates with the occipital, forming one-half of the **lambdoidal suture**.

<sup>1</sup> Journal of Anatomy and Physiology, 1912, vol. xlv.

**Angles.**—The **frontal angle** is practically a right angle, and corresponds with the point of meeting of the sagittal and coronal sutures; this point is named the **bregma**; in the fetal skull and for about a year and a half after birth this region is membranous, and is called the **anterior fontanelle**. The **sphenoidal angle**, thin and acute, is received into the interval between the frontal bone and the great wing of the sphenoid. Its inner surface is marked by a deep groove, sometimes a canal, for the anterior divisions of the middle meningeal artery. The **occipital angle** is rounded and corresponds with the point of meeting of the sagittal and lambdoidal sutures—a point which is termed the **lambda**; in the fetus this part of the skull is membranous, and is called the **posterior fontanelle**. The **mastoid angle** is truncated; it articulates with the occipital bone and with the mastoid portion of the temporal, and presents on its inner surface a broad, shallow groove which lodges part of the transverse sinus. The point of meeting of this angle with the occipital and the mastoid part of the temporal is named the **asterion**.




FIG. 277.—Left parietal bone. Inner surface.

**Ossification.**—The parietal bone is ossified in membrane from a single centre, which appears at the parietal eminence about the eighth week of fetal life. Ossification gradually extends in a radial manner from the centre toward the margins of the bone; the angles are consequently the parts last formed, and it is here that the fontanelles exist. Occasionally the parietal bone is divided into two parts, upper and lower, by an antero-posterior suture.

**Articulations.**—The parietal articulates with *five* bones: the opposite parietal, the occipital, frontal, temporal, and sphenoid.

### The Frontal Bone (*Os Frontale*).

The **frontal bone** resembles a cockle-shell in form, and consists of two portions—a **vertical** portion, the **squama**, corresponding with the region of the forehead;



and an **orbital** or **horizontal** portion, which enters into the formation of the roofs of the orbital and nasal cavities.

**Squama** (*squama frontalis*).—**Surfaces**.—The **external surface** (Fig. 278) of this portion is convex and usually exhibits, in the lower part of the middle line, the remains of the **frontal** or **metopic suture**; in infancy this suture divides the bone into two, a condition which may persist throughout life. On either side of this suture, about 3 cm. above the supraorbital margin, is a rounded elevation, the **frontal eminence** (*tuber frontale*). These eminences vary in size in different individuals, are occasionally unsymmetrical, and are especially prominent in young skulls; the surface of the bone above them is smooth, and covered by the galea aponeurotica. Below the frontal eminences, and separated from them by a shallow groove, are two arched elevations, the **superciliary arches**; these are prominent medially, and




FIG. 278.—Frontal bone. Outer surface.

are joined to one another by a smooth elevation named the **glabella**. They are larger in the male than in the female, and their degree of prominence depends to some extent on the size of the frontal air sinuses;<sup>1</sup> prominent ridges are, however, occasionally associated with small air sinuses. Beneath each superciliary arch is a curved and prominent margin, the **supraorbital margin**, which forms the upper boundary of the base of the orbit, and separates the squama from the orbital portion of the bone. The lateral part of this margin is sharp and prominent, affording to the eye, in that situation, considerable protection from injury; the medial part is rounded. At the junction of its medial and intermediate thirds is

<sup>1</sup> Some confusion is occasioned to students commencing the study of anatomy by the name "sinus" having been given to two different kinds of space connected with the skull. It may be as well, therefore, to state here that the "sinuses" in the interior of the cranium which produce the grooves on the inner surfaces of the bones are venous channels which convey the blood from the brain, while the "sinuses" external to the cranial cavity (the frontal, sphenoidal, ethmoidal, and maxillary) are hollow spaces in the bones themselves; they communicate with the nasal cavities and contain air.

a notch, sometimes converted into a foramen, the **supraorbital notch** or **foramen**, which transmits the supraorbital vessels and nerve. A small aperture in the upper part of the notch transmits a vein from the diploë to join the supraorbital vein. The supraorbital margin ends laterally in the **zygomatic process**, which is strong and prominent, and articulates with the zygomatic bone. Running upward and backward from this process is a well-marked line, the **temporal line**, which divides into the **upper** and **lower temporal lines**, continuous, in the articulated skull, with the corresponding lines on the parietal bone. The area below and behind the temporal line forms the anterior part of the temporal fossa, and gives origin to the Temporalis muscle. Between the supraorbital margins the squama projects downward to a level below that of the zygomatic processes; this portion is known as the **nasal part** and presents a rough, uneven interval, the **nasal notch**, which articulates on either side of the middle line with the nasal bone, and laterally with the frontal process of the maxilla and with the lacrimal. The term **nasion** is applied to the middle of the frontonasal suture. From the centre of the notch the **nasal process** projects downward and forward beneath the nasal bones and frontal processes of the maxillæ, and supports the bridge of the nose. The nasal process ends below in a sharp **spine**, and on either side of this is a small grooved surface which enters into the formation of the roof of the corresponding nasal cavity. The spine forms part of the septum of the nose, articulating in front with the crest of the nasal bones and behind with the perpendicular plate of the ethmoid.

The **internal surface** (Fig. 279) of the squama is concave and presents in the upper part of the middle line a vertical groove, the **sagittal sulcus**, the edges of which unite below to form a ridge, the **frontal crest**; the sulcus lodges the superior sagittal sinus, while its margins and the crest afford attachment to the falx cerebri. The crest ends below in a small notch which is converted into a foramen, the **foramen cecum**, by articulation with the ethmoid. This foramen varies in size in different subjects, and is frequently impervious; when open, it transmits a vein from the nose to the superior sagittal sinus. On either side of the middle line the bone presents depressions for the convolutions of the brain, and numerous small furrows for the anterior branches of the middle meningeal vessels. Several small, irregular fossæ may also be seen on either side of the sagittal sulcus, for the reception of the arachnoid granulations.

**Orbital or Horizontal Part** (*pars orbitalis*).—This portion consists of two thin triangular plates, the **orbital plates**, which form the vaults of the orbits, and are separated from one another by a median gap, the **ethmoidal notch**.

**Surfaces.**—The **inferior surface** (Fig. 279) of each orbital plate is smooth and concave, and presents, laterally, under cover of the zygomatic process, a shallow depression, the **lacrima fossa**, for the lacrimal gland; near the nasal part is a depression, the **fovea trochlearis**, or occasionally a small **trochlear spine**, for the attachment of the cartilaginous pulley of the Obliquus oculi superior. The **superior surface** is convex, and marked by depressions for the convolutions of the frontal lobes of the brain, and faint grooves for the meningeal branches of the ethmoidal vessels.

The **ethmoidal notch** separates the two orbital plates; it is quadrilateral, and filled, in the articulated skull, by the cribriform plate of the ethmoid. The margins of the notch present several half-cells which, when united with corresponding half-cells on the upper surface of the ethmoid, complete the ethmoidal air cells. Two grooves cross these edges transversely; they are converted into the **anterior** and **posterior ethmoidal canals** by the ethmoid, and open on the medial wall of the orbit. The anterior canal transmits the nasociliary nerve and anterior ethmoidal vessels, the posterior, the posterior ethmoidal nerve and vessels. In front of the ethmoidal notch, on either side of the frontal spine, are the openings of the **frontal air sinuses**. These are two irregular cavities, which extend backward, upward,

and lateralward for a variable distance between the two tables of the skull; they are separated from one another by a thin bony septum, which often deviates to one or other side, with the result that the sinuses are rarely symmetrical. Absent at birth, they are usually fairly well-developed between the seventh and eighth years, but only reach their full size after puberty. They vary in size in different persons, and are larger in men than in women.<sup>1</sup> They are lined by mucous membrane, and each communicates with the corresponding nasal cavity by means of a passage called the **frontonasal duct**.




FIG. 279.—Frontal bone. Inner surface.

**Borders.**—The border of the squama is thick, strongly serrated, bevelled at the expense of the inner table above, where it rests upon the parietal bones, and at the expense of the outer table on either side, where it receives the lateral pressure of those bones; this border is continued below into a triangular, rough surface, which articulates with the great wing of the sphenoid. The posterior borders of the orbital plates are thin and serrated, and articulate with the small wings of the sphenoid.

**Structure.**—The squama and the zygomatic processes are very thick, consisting of diploic tissue contained between two compact laminae; the diploic tissue is absent in the regions occupied by the frontal air sinuses. The orbital portion is thin, translucent, and composed entirely of compact bone; hence the facility with which instruments can penetrate the cranium through this part of the orbit; when the frontal sinuses are exceptionally large they may extend backward for a considerable distance into the orbital portion, which in such cases also consists of only two tables.

<sup>1</sup> Aldren Turner (*The Accessory Sinuses of the Nose*, 1901) gives the following measurements for a sinus of average size: height,  $1\frac{1}{4}$  inches; breadth, 1 inch; depth from before backward, 1 inch.

**Ossification** (Fig. 280).—The frontal bone is ossified in membrane from *two primary* centres, one for each half, which appear toward the end of the second month of fetal life, one above each supraorbital margin. From each of these centres ossification extends upward to form the corresponding half of the squama, and backward to form the orbital plate. The spine is ossified from a pair of *secondary* centres, on either side of the middle line; similar centres appear in the nasal part and zygomatic processes. At birth the bone consists of two pieces, separated by the frontal suture, which is usually obliterated, except at its lower part, by the eighth year, but occasionally persists throughout life. It is generally maintained that the development of the frontal sinuses begins at the end of the first or beginning of the second year, but Onodi's recent researches indicate that development begins at birth. The sinuses are of considerable size by the seventh or eighth year, but do not attain their full proportions until after puberty.

**Articulations.**—The frontal articulates with *twelve* bones: the sphenoid, the ethmoid, the two parietals, the two nasals, the two maxillæ, the two lacrimals, and the two zygomatics.




FIG. 280.—Frontal bone at birth.

### The Temporal Bone (*Os Temporale*).

The **temporal bones** are situated at the sides and base of the skull. Each consists of five parts, viz., the **squama**, the **petrous**, **mastoid**, and **tympanic parts**, and the **styloid process**.

**The Squama** (*squama temporalis*).—The squama forms the anterior and upper part of the bone, and is scale-like, thin, and translucent.

**Surfaces.**—Its **outer surface** (Fig. 281) is smooth and convex; it affords attachment to the Temporalis muscle, and forms part of the temporal fossa; on its hinder part is a vertical groove for the middle temporal artery. A curved line, the **temporal line**, or **supramastoid crest**, runs backward and upward across its posterior part; it serves for the attachment of the temporal fascia, and limits the origin of the Temporalis muscle. The boundary between the squama and the mastoid portion of the bone, as indicated by traces of the original suture, lies about 1 cm. below this line. Projecting from the lower part of the squama is a long, arched process, the **zygomatic process**. This process is at first directed lateralward, its two surfaces looking upward and downward; it then appears as if twisted inward upon itself, and runs forward, its surfaces now looking medialward and lateralward. The superior border is long, thin, and sharp, and serves for the attachment of the temporal fascia; the inferior, short, thick, and arched, has attached to it some fibres of the Masseter. The lateral surface is convex and subcutaneous; the medial is concave, and affords attachment to the Masseter. The anterior end is deeply serrated and articulates with the zygomatic bone. The posterior end is connected to the squama by two roots, the **anterior** and **posterior roots**. The posterior root, a prolongation of the upper border, is strongly marked; it runs backward above the external acoustic meatus, and is continuous with the temporal line. The anterior root, continuous with the lower border, is short but broad and strong; it is directed medialward and ends in a rounded eminence, the **articular tubercle** (*eminentia articularis*). This tubercle forms the front boundary of the mandibular fossa, and in the recent state is covered with cartilage. In front of the articular tubercle is a small triangular area which assists in forming the infratemporal fossa; this area is separated from the outer surface of the squama by a ridge which is continuous behind with the anterior root of the zygomatic process, and in front, in the





The **internal surface** of the squama (Fig. 282) is concave; it presents depressions corresponding to the convolutions of the temporal lobe of the brain, and grooves for the branches of the middle meningeal vessels.

**Borders.**—The **superior border** is thin, and bevelled at the expense of the internal table, so as to overlap the squamous border of the parietal bone, forming with it the squamosal suture. Posteriorly, the superior border forms an angle, the **parietal notch**, with the mastoid portion of the bone. The **antero-inferior border** is thick, serrated, and bevelled at the expense of the inner table above and of the outer below, for articulation with the great wing of the sphenoid.

**Mastoid Portion** (*pars mastoidea*).—The mastoid portion forms the posterior part of the bone.




FIG. 282.—Left temporal bone. Inner surface.

**Surfaces.**—Its **outer surface** (Fig. 281) is rough, and gives attachment to the Occipitalis and Auricularis posterior. It is perforated by numerous foramina; one of these, of large size, situated near the posterior border, is termed the **mastoid foramen**; it transmits a vein to the transverse sinus and a small branch of the occipital artery to the dura mater. The position and size of this foramen are very variable; it is not always present; sometimes it is situated in the occipital bone, or in the suture between the temporal and the occipital. The mastoid portion is continued below into a conical projection, the **mastoid process**, the size and form of which vary somewhat; it is larger in the male than in the female. This process serves for the attachment of the Sternocleidomastoideus, Splenius capitis, and Longissimus capitis. On the medial side of the process is a deep groove, the **mastoid notch** (*digastric fossa*), for the attachment of the Digastricus; medial to this is a shallow furrow, the **occipital groove**, which lodges the occipital artery.



The **inner surface** of the mastoid portion presents a deep, curved groove, the **sigmoid sulcus**, which lodges part of the transverse sinus; in it may be seen the opening of the mastoid foramen. The groove for the transverse sinus is separated from the innermost of the mastoid air cells by a very thin lamina of bone, and even this may be partly deficient.

**Borders.**—The **superior border** of the mastoid portion is broad and serrated, for articulation with the mastoid angle of the parietal. The **posterior border**, also serrated, articulates with the inferior border of the occipital between the lateral angle and jugular process. Anteriorly the mastoid portion is fused with the descending process of the squama above; below it enters into the formation of the external acoustic meatus and the tympanic cavity.




FIG. 283.—Coronal section of right temporal bone.

A section of the mastoid process (Fig. 283) shows it to be hollowed out into a number of spaces, the **mastoid cells**, which exhibit the greatest possible variety as to their size and number. At the upper and front part of the process they are large and irregular and contain air, but toward the lower part they diminish in size, while those at the apex of the process are frequently quite small and contain marrow; occasionally they are entirely absent, and the mastoid is then solid throughout. In addition to these a large irregular cavity is situated at the upper and front part of the bone. It is called the **tympanic antrum**, and must be distinguished from the mastoid cells, though it communicates with them. Like the mastoid cells it is filled with air and lined by a prolongation of the mucous membrane of the tympanic cavity, with which it communicates. The tympanic antrum is bounded above by a thin plate of bone, the **tegmen tympani**, which separates it from the middle fossa of the base of the skull; below by the mastoid process; laterally by the squama just below the temporal line, and medially by the lateral semicircular canal of the internal ear which projects into its cavity. It opens in front into that portion of the tympanic cavity which is known as the **attic** or **epitympanic**

**recess.** The tympanic antrum is a cavity of some considerable size at the time of birth; the mastoid air cells may be regarded as diverticula from the antrum, and begin to appear at or before birth; by the fifth year they are well-marked, but their development is not completed until toward puberty.

**Petrous Portion** (*pars petrosa* [*pyramis*]).—The petrous portion or pyramid is pyramidal and is wedged in at the base of the skull between the sphenoid and occipital. Directed medialward, forward, and a little upward, it presents for examination a base, an apex, three surfaces, and three angles, and contains, in its interior, the essential parts of the organ of hearing.

**Base.**—The base is fused with the internal surfaces of the squama and mastoid portion.

**Apex.**—The apex, rough and uneven, is received into the angular interval between the posterior border of the great wing of the sphenoid and the basilar part of the occipital; it presents the anterior or internal orifice of the carotid canal, and forms the postero-lateral boundary of the foramen lacrum.

**Surfaces.**—The **anterior surface** forms the posterior part of the middle fossa of the base of the skull, and is continuous with the inner surface of the squamous portion, to which it is united by the **petrosquamous suture**, remains of which are distinct even at a late period of life. It is marked by depressions for the convolutions of the brain, and presents six points for examination: (1) near the centre, an **eminence** (*eminentia arcuata*) which indicates the situation of the superior semicircular canal; (2) in front of and a little lateral to this eminence, a depression indicating the position of the tympanic cavity: here the layer of bone which separates the tympanic from the cranial cavity is extremely thin, and is known as the **tegmen tympani**; (3) a shallow groove, sometimes double, leading lateralward and backward to an oblique opening, the **hiatus of the facial canal**, for the passage of the greater superficial petrosal nerve and the petrosal branch of the middle meningeal artery; (4) lateral to the hiatus, a smaller opening, occasionally seen, for the passage of the lesser superficial petrosal nerve; (5) near the apex of the bone, the termination of the carotid canal, the wall of which in this situation is deficient in front; (6) above this canal the shallow **trigeminal impression** for the reception of the semilunar ganglion.

The **posterior surface** (Fig. 282) forms the front part of the posterior fossa of the base of the skull, and is continuous with the inner surface of the mastoid portion. Near the centre is a large orifice, the **internal acoustic meatus**, the size of which varies considerably; its margins are smooth and rounded, and it leads into a short canal, about 1 cm. in length, which runs lateralward. It transmits the facial and acoustic nerves and the internal auditory branch of the basilar artery. The lateral end of the canal is closed by a vertical plate, which is divided by a horizontal crest, the **crista falciformis**, into two unequal portions (Fig. 284). Each portion is further subdivided by a vertical ridge into an anterior and a posterior part. In the portion beneath the crista falciformis are three sets of foramina; one group, just below the posterior part of the crest, situated in the **area cribrosa media**, consists of several small openings for the nerves to the saccule; below and




FIG. 284.—Diagrammatic view of the fundus of the right internal acoustic meatus. (Testut.) 1. Crista falciformis. 2. Area facialis, with (2') internal opening of the facial canal. 3. Ridge separating the area facialis from the area cribrosa superior. 4. Area cribrosa superior, with (4') openings for nerve filaments. 5. Anterior inferior cribriform area, with (5') the tractus spiralis foraminosus, and (5'') the canalis centralis of the cochlea. 6. Ridge separating the tractus spiralis foraminosus from the area cribrosa media. 7. Area cribrosa media, with (7') orifices for nerves to saccule. 8. Foramen singulare.

behind this area is the **foramen singulare**, or opening for the nerve to the posterior semicircular duct; in front of and below the first is the **tractus spiralis foraminosus**, consisting of a number of small spirally arranged openings, which encircle the **canalis centralis cochleae**; these openings together with this central canal transmit the nerves to the cochlea. The portion above the crista falciformis presents behind, the **area cribrosa superior**, pierced by a series of small openings, for the passage of the nerves to the utricle and the superior and lateral semicircular ducts, and, in front, the **area facialis**, with one large opening, the commencement of the canal for the facial nerve (**aquaeductus Fallopi**). Behind the internal acoustic meatus is a small slit almost hidden by a thin plate of bone, leading to a canal, the **aquaeductus vestibuli**, which transmits the ductus endolymphaticus together with a small artery and vein. Above and between these two openings is an irregular depression which lodges a process of the dura mater and transmits a small vein; in the infant this depression is represented by a large fossa, the **subarcuate fossa**, which extends backward as a blind tunnel under the superior semicircular canal.




FIG. 285.—Left temporal bone. Inferior surface.

The **inferior surface** (Fig. 285) is rough and irregular, and forms part of the exterior of the base of the skull. It presents eleven points for examination: (1) near the apex is a rough surface, quadrilateral in form, which serves partly for the attachment of the Levator veli palatini and the cartilaginous portion of the auditory tube, and partly for connection with the basilar part of the occipital bone through the intervention of some dense fibrous tissue; (2) behind this is the large circular aperture of the **carotid canal**, which ascends at first vertically, and then, making a bend, runs horizontally forward and medialward; it transmits into the cranium the internal carotid artery, and the carotid plexus of nerves; (3) medial to the opening for the carotid canal and close to its posterior border, in front of

the jugular fossa, is a triangular depression; at the apex of this is a small opening, the *aquaeductus cochleae*, which lodges a tubular prolongation of the dura mater and transmits a vein from the cochlea to join the internal jugular; (4) behind these openings is a deep depression, the *jugular fossa*, of variable depth and size in different skulls; it lodges the bulb of the internal jugular vein; (5) in the bony ridge dividing the carotid canal from the jugular fossa is the small *inferior tympanic canaliculus* for the passage of the tympanic branch of the glossopharyngeal nerve; (6) in the lateral part of the jugular fossa is the *mastoid canaliculus* for the entrance of the auricular branch of the vagus nerve; (7) behind the jugular fossa is a quadrilateral area, the *jugular surface*, covered with cartilage in the recent state, and articulating with the jugular process of the occipital bone; (8) extending backward from the carotid canal is the *vaginal process*, a sheath-like plate of bone, which divides behind into two laminae; the lateral lamina is continuous with the tympanic part of the bone, the medial with the lateral margin of the jugular surface; (9) between these laminae is the *styloid process*, a sharp spine, about 2.5 cm. in length; (10) between the styloid and mastoid processes is the *stylomastoid foramen*; it is the termination of the facial canal, and transmits the facial nerve and stylomastoid artery; (11) situated between the tympanic portion and the mastoid process is the tympanomastoid fissure, for the exit of the auricular branch of the vagus nerve.

**Angles.**—The *superior angle*, the longest, is grooved for the superior petrosal sinus, and gives attachment to the tentorium cerebelli; at its medial extremity is a notch, in which the trigeminal nerve lies. The *posterior angle* is intermediate in length between the superior and the anterior. Its medial half is marked by a sulcus, which forms, with a corresponding sulcus on the occipital bone, the channel for the inferior petrosal sinus. Its lateral half presents an excavation—the *jugular fossa*—which, with the jugular notch on the occipital, forms the *jugular foramen*; an eminence occasionally projects from the centre of the fossa, and divides the foramen into two. The *anterior angle* is divided into two parts—a lateral joined to the squama by a suture (*petrosquamous*), the remains of which are more or less distinct; a medial, free, which articulates with the spinous process of the sphenoid.

At the angle of junction of the petrous part and the squama are two canals, one above the other, and separated by a thin plate of bone, the *septum canalis musculotubarii* (*processus cochleariformis*); both canals lead into the tympanic cavity. The upper one (*semicanalis m. tensoris tympani*) transmits the Tensor tympani, the lower one (*semicanalis tubae auditivae*) forms the bony part of the auditory tube.

The tympanic cavity, auditory ossicles, and internal ear, are described with the organ of hearing.

**Tympanic Part** (*pars tympanica*).—The tympanic part is a curved plate of bone lying below the squama and in front of the mastoid process.

**Surfaces.**—Its *postero-superior surface* is concave, and forms the anterior wall, the floor, and part of the posterior wall of the bony external acoustic meatus. Medially, it presents a narrow furrow, the *tympanic sulcus*, for the attachment of the tympanic membrane. Its *antero-inferior surface* is quadrilateral and slightly concave; it constitutes the posterior boundary of the mandibular fossa, and is in contact with the retromandibular part of the parotid gland.

**Borders.**—Its *lateral border* is free and rough, and gives attachment to the cartilaginous part of the external acoustic meatus. Internally, the tympanic part is fused with the petrous portion, and appears in the retreating angle between it and the squama, where it lies below and lateral to the orifice of the auditory tube. Posteriorly, it blends with the squama and mastoid part, and forms the anterior boundary of the tympanomastoid fissure. Its *upper border* fuses laterally with the back of the postglenoid process, while medially it bounds the petro-

tympanic fissure. The medial part of the lower border is thin and sharp; its lateral part splits to enclose the root of the styloid process, and is therefore named the **vaginal process**. The central portion of the tympanic part is thin, and in a considerable percentage of skulls is perforated by a hole, the **foramen of Huschke**.

The **external acoustic meatus** is nearly 2 cm. long and is directed inward and slightly forward: at the same time it forms a slight curve, so that the floor of the canal is convex upward. In sagittal section it presents an oval or elliptical shape with the long axis directed downward and slightly backward. Its anterior wall and floor and the lower part of its posterior wall are formed by the tympanic part; the roof and upper part of the posterior wall by the squama. Its inner end is closed, in the recent state, by the tympanic membrane; the upper limit of its outer orifice is formed by the posterior root of the zygomatic process, immediately below which there is sometimes seen a small spine, the **suprameatal spine**, situated at the upper and posterior part of the orifice.

**Styloid Process** (*processus styloideus*).—The styloid process is slender, pointed, and of varying length; it projects downward and forward, from the under surface of the temporal bone. Its proximal part (*tympanohyal*) is ensheathed by the vaginal process of the tympanic portion, while its distal part (*stylohyal*) gives attachment to the stylohyoid and stylomandibular ligaments, and to the Styloglossus, Stylohyoideus, and Stylopharyngeus muscles. The stylohyoid ligament extends from the apex of the process to the lesser cornu of the hyoid bone, and in some instances is partially, in others completely, ossified.




FIG. 286.—The three principal parts of the temporal bone at birth. 1. Outer surface of petromastoid part. 2. Outer surface of tympanic ring. 3. Inner surface of squama.

**Structure.**—The structure of the squama is like that of the other cranial bones: the mastoid portion is spongy, and the petrous portion dense and hard.

**Ossification.**—The temporal bone is ossified from *eight* centres, exclusive of those for the internal ear and the tympanic ossicles, viz., one for the squama including the zygomatic process, one for the tympanic part, four for the petrous and mastoid parts, and two for the styloid process. Just before the close of fetal life (Fig. 286) the temporal bone consists of three principal parts: 1. The *squama* is ossified in membrane from a single nucleus, which appears near the root of the zygomatic process about the second month. 2. The *petromastoid* part is developed from four centres, which make their appearance in the cartilaginous ear capsule about the fifth or sixth month. One (*prootic*) appears in the neighborhood of the eminentia arcuata, spreads in front and above the internal acoustic meatus and extends to the apex of the bone; it forms part of the cochlea, vestibule, superior semicircular canal, and medial wall of the tympanic cavity. A second (*opisthotic*) appears at the promontory on the medial wall of the tympanic cavity and surrounds the fenestra cochleae; it forms the floor of the tympanic cavity and vestibule, surrounds the carotid canal, invests the lateral and lower part of the cochlea, and spreads medially below the internal

acoustic meatus. A third (*pterotic*) roofs in the tympanic cavity and antrum; while the fourth (*epiotic*) appears near the posterior semicircular canal and extends to form the mastoid process (Vrolik). 3. The *tympanic ring* is an incomplete circle, in the concavity of which is a groove, the tympanic sulcus, for the attachment of the circumference of the tympanic membrane. This ring expands to form the tympanic part, and is ossified in membrane from a single centre which appears about the third month. The *styloid process* is developed from the proximal part of the cartilage of the second branchial or hyoid arch by two centres: one for the proximal part, the *tympanohyal*, appears before birth; the other, comprising the rest of the process, is named the *stylohyal*, and does not appear until after birth. The tympanic ring unites with the squama shortly before birth; the petromastoid part and squama join during the first year, and the tympanohyal portion of the styloid process about the same time (Figs. 287, 288). The stylohyal does not unite with the rest of the bone until after puberty, and in some skulls never at all.




FIG. 287.—Temporal bone at birth.  
Outer aspect.




FIG. 288.—Temporal bone at birth. Inner aspect.

The chief subsequent changes in the temporal bone apart from increase in size are: (1) The tympanic ring extends outward and backward to form the tympanic part. This extension does not, however, take place at an equal rate all around the circumference of the ring, but occurs most rapidly on its anterior and posterior portions, and these outgrowths meet and blend, and thus, for a time, there exists in the floor of the meatus a foramen, the *foramen of Huschke*; this foramen is usually closed about the fifth year, but may persist throughout life. (2) The mandibular fossa is at first extremely shallow, and looks lateralward as well as downward; it becomes deeper and is ultimately directed downward. Its change in direction is accounted for as follows. The part of the squama which forms the fossa lies at first below the level of the zygomatic process. As, however, the base of the skull increases in width, this lower part of the squama is directed horizontally inward to contribute to the middle fossa of the skull, and its surfaces therefore come to look upward and downward; the attached portion of the zygomatic process also becomes everted, and projects like a shelf at right angles to the squama. (3) The mastoid portion is at first quite flat, and the styломastoid foramen and rudimentary styloid process lie immediately behind the tympanic ring. With the development of the air cells the outer part of the mastoid portion grows downward and forward to form the mastoid process, and the styloid process and styломastoid foramen now come to lie on the under surface. The descent of the foramen is necessarily accompanied by a corresponding lengthening of the facial canal. (4) The downward and forward growth of the mastoid process also pushes forward the tympanic part, so that the portion of it which formed the original floor of the meatus and contained the foramen of Huschke is ultimately found in the anterior wall. (5) The fossa subarcuata becomes filled up and almost obliterated.

**Articulations.**—The temporal articulates with *five* bones: occipital, parietal, sphenoid, mandible, and zygomatic.

### The Sphenoidal Bone (Os Sphenoidal; Sphenoid Bone).

The **sphenoidal bone** is situated at the base of the skull in front of the temporals and basilar part of the occipital. It somewhat resembles a bat with its wings



extended, and is divided into a median portion or body, two great and two small wings extending outward from the sides of the body, and two pterygoid processes which project from it below.

**Body** (*corpus sphenoidalis*).—The body, more or less cubical in shape, is hollowed out in its interior to form two large cavities, the **sphenoidal air sinuses**, which are separated from each other by a septum.

**Surfaces.**—The **superior surface** of the body (Fig. 289) presents in front a prominent spine, the **ethmoidal spine**, for articulation with the cribriform plate of the ethmoid; behind this is a smooth surface slightly raised in the middle line, and grooved on either side for the olfactory lobes of the brain. This surface is bounded behind by a ridge, which forms the anterior border of a narrow, transverse groove, the **chiasmatic groove** (*optic groove*), above and behind which lies the optic chiasma; the groove ends on either side in the **optic foramen**, which transmits the optic nerve and ophthalmic artery into the orbital cavity. Behind the chiasmatic groove is an olive-like elevation, the **tuberculum sellae**; and still more posteriorly, a deep depression, the **sella turcica**, the deepest part of which lodges the hypophysis




FIG. 289.—Sphenoidal bone. Upper surface.

cerebri and is known as the **fossa hypophyseos**. The anterior boundary of the sella turcica is completed by two small eminences, one on either side, called the **middle clinoid processes**, while the posterior boundary is formed by a square-shaped plate of bone, the **dorsum sellae**, ending at its superior angles in two tubercles, the **posterior clinoid processes**, the size and form of which vary considerably in different individuals. The posterior clinoid processes deepen the sella turcica, and give attachment to the tentorium cerebelli. On either side of the dorsum sellae is a notch for the passage of the abducent nerve, and below the notch a sharp process, the **petrosal process**, which articulates with the apex of the petrous portion of the temporal bone, and forms the medial boundary of the foramen lacerum. Behind the dorsum sellae is a shallow depression, the **clivus**, which slopes obliquely backward, and is continuous with the groove on the basilar portion of the occipital bone; it supports the upper part of the pons.

The **lateral surfaces** of the body are united with the great wings and the medial pterygoid plates. Above the attachment of each great wing is a broad groove, curved something like the italic letter *f*; it lodges the internal carotid artery and

the cavernous sinus, and is named the **carotid groove**. Along the posterior part of the lateral margin of this groove, in the angle between the body and great wing, is a ridge of bone, called the **lingula**.

The **posterior surface**, quadrilateral in form (Fig. 291), is joined, during infancy and adolescence, to the basilar part of the occipital bone by a plate of cartilage. Between the eighteenth and twenty-fifth years this becomes ossified, ossification commencing above and extending downward.

The **anterior surface** of the body (Fig. 290) presents, in the middle line, a vertical crest, the **sphenoidal crest**, which articulates with the perpendicular plate of the ethmoid, and forms part of the septum of the nose. On either side of the crest is an irregular opening leading into the corresponding **sphenoidal air sinus**. These sinuses are two large, irregular cavities hollowed out of the interior of the body of the bone, and separated from one another by a bony septum, which is commonly bent to one or the other side. They vary considerably in form and size,<sup>1</sup> are seldom symmetrical, and are often partially subdivided by irregular bony laminae.




FIG. 290.—Sphenoidal bone. Anterior and inferior surfaces.

Occasionally, they extend into the basilar part of the occipital nearly as far as the foramen magnum. They begin to be developed before birth, and are of a considerable size by the age of six. They are partially closed, in front and below, by two thin, curved plates of bone, the **sphenoidal conchae** (see page 250), leaving in the articulated skull a round opening at the upper part of each sinus by which it communicates with the upper and back part of the nasal cavity and occasionally with the posterior ethmoidal air cells. The lateral margin of the anterior surface is serrated, and articulates with the lamina papyracea of the ethmoid, completing the posterior ethmoidal cells; the lower margin articulates with the orbital process of the palatine bone, and the upper with the orbital plate of the frontal bone.

The **inferior surface** presents, in the middle line, a triangular spine, the **sphenoidal rostrum**, which is continuous with the sphenoidal crest on the anterior surface, and is received in a deep fissure between the alae of the vomer. On either side of the rostrum is a projecting lamina, the **vaginal process**, directed medialward from the base of the medial pterygoid plate, with which it will be described.

<sup>1</sup> Aldren Turner (*op. cit.*) gives the following as their average measurements: vertical height,  $\frac{1}{8}$  inch; antero-posterior depth,  $\frac{1}{3}$  inch; transverse breadth,  $\frac{3}{4}$  inch.

**The Great Wings** (*alae magnae*).—The great wings, or **ali-sphenoids**, are two strong processes of bone, which arise from the sides of the body, and are curved upward, lateralward, and backward; the posterior part of each projects as a triangular process which fits into the angle between the squama and the petrous portion of the temporal and presents at its apex a downwardly directed process, the **spina angularis** (*sphenoidal spine*).

**Surfaces.**—The **superior** or **cerebral surface** of each great wing (Fig. 289) forms part of the middle fossa of the skull; it is deeply concave, and presents depressions for the convolutions of the temporal lobe of the brain. At its anterior and medial part is a circular aperture, the **foramen rotundum**, for the transmission of the maxillary nerve. Behind and lateral to this is the **foramen ovale**, for the transmission of the mandibular nerve, the accessory meningeal artery, and sometimes the lesser superficial petrosal nerve.<sup>1</sup> Medial to the foramen ovale, a small aperture, the **foramen Vesalii**, may occasionally be seen opposite the root of the pterygoid process; it opens below near the scaphoid fossa, and transmits a small vein from the cavernous sinus. Lastly, in the posterior angle, near to and in front of the spine, is a short canal, sometimes double, the **foramen spinosum**, which transmits the middle meningeal vessels and a recurrent branch from the mandibular nerve.




FIG. 291.—Sphenoidal bone. Upper and posterior surfaces.

The **lateral surface** (Fig. 290) is convex, and divided by a transverse ridge, the **infratemporal crest**, into two portions. The superior or temporal portion, convex from above downward, concave from before backward, forms a part of the temporal fossa, and gives attachment to the Temporalis; the inferior or infratemporal, smaller in size and concave, enters into the formation of the infratemporal fossa, and, together with the infratemporal crest, affords attachment to the Pterygoideus externus. It is pierced by the foramen ovale and foramen spinosum, and at its posterior part is the spina angularis, which is frequently grooved on its medial surface for the chorda tympani nerve. To the spina angularis are attached the sphenomandibular ligament and the Tensor veli palatini. Medial to the anterior extremity of the infratemporal crest is a triangular process which serves to increase

<sup>1</sup> The lesser superficial petrosal nerve sometimes passes through a special canal (*canaliculus innominatus* of Arnold) situated medial to the foramen spinosum.

the attachment of the *Pterygoideus externus*; extending downward and medialward from this process on to the front part of the lateral pterygoid plate is a ridge which forms the anterior limit of the infratemporal surface, and, in the articulated skull, the posterior boundary of the pterygomaxillary fissure.

The **orbital surface** of the great wing (Fig. 290), smooth, and quadrilateral in shape, is directed forward and medialward and forms the posterior part of the lateral wall of the orbit. Its upper serrated edge articulates with the orbital plate of the frontal. Its inferior rounded border forms the postero-lateral boundary of the inferior orbital fissure. Its medial sharp margin forms the lower boundary of the superior orbital fissure and has projecting from about its centre a little tubercle which gives attachment to the inferior head of the *Rectus lateralis oculi*; at the upper part of this margin is a notch for the transmission of a recurrent branch of the lacrimal artery. Its lateral margin is serrated and articulates with the zygomatic bone. Below the medial end of the superior orbital fissure is a grooved surface, which forms the posterior wall of the pterygopalatine fossa, and is pierced by the foramen rotundum.

**Margin** (Fig. 289).—Commencing from behind, that portion of the circumference of the great wing which extends from the body to the spine is irregular. Its medial half forms the anterior boundary of the foramen lacerum, and presents the posterior aperture of the pterygoid canal for the passage of the corresponding nerve and artery. Its lateral half articulates, by means of a synchondrosis, with the petrous portion of the temporal, and between the two bones on the under surface of the skull, is a furrow, the *sulcus tubae*, for the lodgement of the cartilaginous part of the auditory tube. In front of the spine the circumference presents a concave, serrated edge, bevelled at the expense of the inner table below, and of the outer table above, for articulation with the temporal squama. At the tip of the great wing is a triangular portion, bevelled at the expense of the internal surface, for articulation with the sphenoidal angle of the parietal bone; this region is named the *pterion*. Medial to this is a triangular, serrated surface, for articulation with the frontal bone; this surface is continuous medially with the sharp edge, which forms the lower boundary of the superior orbital fissure, and laterally with the serrated margin for articulation with the zygomatic bone.

**The Small Wings** (*alae parvae*).—The small wings or *orbito-sphenoids* are two thin triangular plates, which arise from the upper and anterior parts of the body, and, projecting lateralward, end in sharp points (Fig. 289).

**Surfaces**.—The **superior surface** of each is flat, and supports part of the frontal lobe of the brain. The **inferior surface** forms the back part of the roof of the orbit, and the upper boundary of the **superior orbital fissure**. This fissure is of a triangular form, and leads from the cavity of the cranium into that of the orbit: it is bounded *medially* by the body; *above*, by the small wing; *below*, by the medial margin of the orbital surface of the great wing; and is completed *laterally* by the frontal bone. It transmits the oculomotor, trochlear, and abducent nerves, the three branches of the ophthalmic division of the trigeminal nerve, some filaments from the cavernous plexus of the sympathetic, the orbital branch of the middle meningeal artery, a recurrent branch from the lacrimal artery to the dura mater, and the ophthalmic vein.

**Borders**.—The **anterior border** is serrated for articulation with the frontal bone. The **posterior border**, smooth and rounded, is received into the lateral fissure of the brain; the medial end of this border forms the **anterior clinoid process**, which gives attachment to the tentorium cerebelli; it is sometimes joined to the middle clinoid process by a spicule of bone, and when this occurs the termination of the groove for the internal carotid artery is converted into a foramen (*carotico-clinoid*). The small wing is connected to the body by two roots, the upper thin and flat,

the lower thick and triangular; between the two roots is the **optic foramen**, for the transmission of the optic nerve and ophthalmic artery.

**Pterygoid Processes** (*processus pterygoidei*).—The pterygoid processes, one on either side, descend perpendicularly from the regions where the body and great wings unite. Each process consists of a medial and a lateral plate, the upper parts of which are fused anteriorly; a vertical sulcus, the **pterygopalatine groove**, descends on the front of the line of fusion. The plates are separated below by an angular cleft, the **pterygoid fissure**, the margins of which are rough for articulation with the pyramidal process of the palatine bone. The two plates diverge behind and enclose between them a V-shaped fossa, the **pterygoid fossa**, which contains the Pterygoideus internus and Tensor veli palatini. Above this fossa is a small, oval, shallow depression, the **scaphoid fossa**, which gives origin to the Tensor veli palatini. The anterior surface of the pterygoid process is broad and triangular near its root, where it forms the posterior wall of the pterygopalatine fossa and presents the anterior orifice of the pterygoid canal.

**Lateral Pterygoid Plate**.—The **lateral pterygoid plate** is broad, thin, and everted; its **lateral surface** forms part of the medial wall of the infratemporal fossa, and gives attachment to the Pterygoideus externus; its **medial surface** forms part of the pterygoid fossa, and gives attachment to the Pterygoideus internus.

**Medial Pterygoid Plate**.—The medial pterygoid plate is narrower and longer than the lateral; it curves lateralward at its lower extremity into a hook-like process, the **pterygoid hamulus**, around which the tendon of the Tensor veli palatini glides. The **lateral surface** of this plate forms part of the pterygoid fossa, the **medial surface** constitutes the lateral boundary of the choana or posterior aperture of the corresponding nasal cavity. Superiorly the medial plate is prolonged on to the under surface of the body as a thin lamina, named the **vaginal process**, which articulates in front with the sphenoidal process of the palatine and behind this with the ala of the vomer. The angular prominence between the posterior margin of the vaginal process and the medial border of the scaphoid fossa is named the **pterygoid tubercle**, and immediately above this is the posterior opening of the pterygoid canal. On the under surface of the vaginal process is a furrow, which is converted into a canal by the sphenoidal process of the palatine bone, for the transmission of the pharyngeal branch of the internal maxillary artery and the pharyngeal nerve from the sphenopalatine ganglion. The pharyngeal aponeurosis is attached to the entire length of the posterior edge of the medial plate, and the Constrictor pharyngis superior takes origin from its lower third. Projecting backward from near the middle of the posterior edge of this plate is an angular process, the **processus tubarius**, which supports the pharyngeal end of the auditory tube. The anterior margin of the plate articulates with the posterior border of the vertical part of the palatine bone.

**The Sphenoidal Conchæ** (*conchæ sphenoidales; sphenoidal turbinated processes*).—The sphenoidal conchæ are two thin, curved plates, situated at the anterior and lower part of the body of the sphenoid. An aperture of variable size exists in the anterior wall of each, and through this the sphenoidal sinus opens into the nasal cavity. Each is irregular in form, and tapers to a point behind, being broader and thinner in front. Its upper surface is concave, and looks toward the cavity of the sinus; its under surface is convex, and forms part of the roof of the corresponding nasal cavity. Each bone articulates in front with the ethmoid, laterally with the palatine; its pointed posterior extremity is placed above the vomer, and is received between the root of the pterygoid process laterally and the rostrum of the sphenoid medially. A small portion of the sphenoidal concha sometimes enters into the formation of the medial wall of the orbit, between the lamina papyracea of the ethmoid in front, the orbital plate of the palatine below, and the frontal bone above.

**Ossification.**—Until the seventh or eighth month of fetal life the body of the sphenoid consists of two parts, viz., one in front of the tuberculum sellae, the *presphenoid*, with which the small wings are continuous; the other, comprising the sella turcica and dorsum sellae, the *postsphenoid*, with which are associated the great wings, and pterygoid processes. The greater part of the bone is ossified in cartilage. There are fourteen centres in all, *six* for the presphenoid and *eight* for the postsphenoid.

**Presphenoid.**—About the ninth week of fetal life an ossific centre appears for each of the small wings (orbitosphenoids) just lateral to the optic foramen; shortly afterward two nuclei appear in the presphenoid part of the body. The sphenoidal conchæ are each developed from a centre which makes its appearance about the fifth month;<sup>1</sup> at birth they consist of small triangular laminae, and it is not until the third year that they become hollowed out and cone-shaped; about the fourth year they fuse with the labyrinths of the ethmoid, and between the ninth and twelfth years they unite with the sphenoid.

**Postsphenoid.**—The first ossific nuclei are those for the great wings (ali-sphenoids). One makes its appearance in each wing between the foramen rotundum and foramen ovale about the eighth week. The orbital plate and that part of the sphenoid which is found in the temporal fossa, as well as the lateral pterygoid plate, are ossified in membrane (Fawcett<sup>2</sup>). Soon after, the centres for the postsphenoid part of the body appear, one on either side of the sella turcica, and become blended together about the middle of fetal life. Each medial pterygoid plate (with the exception of its hamulus) is ossified in membrane, and its centre probably appears about the ninth or tenth week; the hamulus becomes chondrified during the third month, and almost at once undergoes ossification (Fawcett<sup>3</sup>). The medial joins the lateral pterygoid plate about the sixth month. About the fourth month a centre appears for each lingula and speedily joins the rest of the bone.

The presphenoid is united to the postsphenoid about the eighth month, and at birth the bone is in three pieces (Fig. 292): a central, consisting of the body and small wings, and two lateral, each comprising a great wing and pterygoid process. In the first year after birth the great wings and body unite, and the small wings extend inward above the anterior part of the body, and, meeting with each other in the middle line, form an elevated smooth surface, termed the *jugum sphenoidale*. By the twenty-fifth year the sphenoid and occipital are completely fused. Between the pre- and postsphenoid there are occasionally seen the remains of a canal, the *canalis craniopharyngeus*, through which, in early fetal life, the hypophyseal diverticulum of the buccal ectoderm is transmitted (see page 166).



FIG. 292.—Sphenoidal bone at birth. Posterior aspect.

The sphenoidal sinuses are present as minute cavities at the time of birth (Onodi), but do not attain their full size until after puberty.

Certain intrinsic ligaments are attached to the sphenoid. The more important of these are: the *pterygospinous*, stretching between the spina angularis and the lateral pterygoid plate (see *cervical fascia*); the *interclinoid*, a fibrous process joining the anterior to the posterior clinoid process; and the *caroticoclinoid*, connecting the anterior to the middle clinoid process. These ligaments occasionally ossify.

**Articulations.**—The sphenoid articulates with *twelve* bones: four single, the vomer, ethmoid, frontal, and occipital; and four paired, the parietal, temporal, zygomatic, and palatine.<sup>4</sup>

### The Ethmoidal Bone (Os Ethmoidale; Ethmoid Bone).

The **ethmoidal bone** is exceedingly light and spongy, and cubical in shape; it is situated at the anterior part of the base of the cranium, between the two orbits, at the roof of the nose, and contributes to each of these cavities. It consists of four parts: a **horizontal or cribriform plate**, forming part of the base of the cranium; a **perpendicular plate**, constituting part of the nasal septum; and two **lateral masses or labyrinths**.

<sup>1</sup> According to Cleland, each sphenoidal concha is ossified from four centres.

<sup>2</sup> *Journal of Anatomy and Physiology*, 1910, vol. xiv.

<sup>3</sup> *Anatomischer Anzeiger*, March, 1905.

<sup>4</sup> It also sometimes articulates with the tuberosity of the maxilla (see page 257).



**Cribiform Plate** (*lamina cribrosa; horizontal lamina*).—The cribriform plate (Fig. 293) is received into the ethmoidal notch of the frontal bone and roofs in the nasal cavities. Projecting upward from the middle line of this plate is a thick, smooth, triangular process, the **crista galli**, so called from its resemblance to a cock's comb. Its posterior border, long, thin, and slightly curved, serves for the




FIG. 293.—Ethmoidal bone from above.

attachment of the falx cerebri. Its anterior border, short and thick, articulates with the frontal bone, and presents two small projecting **alæ**, which are received into corresponding depressions in the frontal bone and complete the foramen cecum. Its sides are smooth, and sometimes bulging from the presence of a small air sinus in the interior. On either side of the crista galli, the cribriform plate is narrow and deeply grooved; it supports the olfactory bulb and is perforated by foramina for the passage of the olfactory nerves. The foramina in the middle of the groove are small and transmit the nerves to the

roof of the nasal cavity; those at the medial and lateral parts of the groove are larger—the former transmit the nerves to the upper part of the nasal septum, the latter those to the superior nasal concha. At the front part of the cribriform plate, on either side of the crista galli, is a small fissure which is occupied by a process of dura mater. Lateral to this fissure is a notch or foramen which transmits the nasociliary nerve; from this notch a groove extends backward to the anterior ethmoidal foramen.




FIG. 294.—Perpendicular plate of ethmoid. Shown by removing the right labyrinth.

**Perpendicular Plate** (*lamina perpendicularis; vertical plate*).—The perpendicular plate (Figs. 294, 295) is a thin, flattened lamina, polygonal in form, which descends from the under surface of the cribriform plate, and assists in forming the septum of the nose; it is generally deflected a little to one or other side. The **anterior border**

articulates with the spine of the frontal bone and the crest of the nasal bones. The **posterior border** articulates by its upper half with the sphenoidal crest, by its lower with the vomer. The **inferior border** is thicker than the posterior, and serves for the attachment of the septal cartilage of the nose. The surfaces of the plate are smooth, except above, where numerous grooves and canals are seen; these lead from the medial foramina on the cribriform plate and lodge filaments of the olfactory nerves.

The **Labyrinth** or **Lateral Mass** (*labyrinthus ethmoidalis*) consists of a number of thin-walled cellular cavities, the **ethmoidal cells**, arranged in three groups, *anterior, middle, and posterior*, and interposed between two vertical plates of bone; the lateral plate forms part of the orbit, the medial, part of the corresponding nasal cavity. In the disarticulated bone many of these cells are opened into, but when the bones are articulated, they are closed in at every part, except where they open into the nasal cavity.

**Surfaces.**—The **upper surface** of the labyrinth (Fig. 293) presents a number of half-broken cells, the walls of which are completed, in the articulated skull, by the edges of the ethmoidal notch of the frontal bone. Crossing this surface are two grooves, converted into canals by articulation with the frontal; they are the **anterior** and **posterior ethmoidal canals**, and open on the inner wall of the orbit. The **posterior surface** presents large irregular cellular cavities, which are closed in by articulation with the sphenoidal concha and orbital process of the palatine. The **lateral surface** (Fig. 296) is formed of a thin, smooth, oblong plate, the **lamina papyracea** (*os planum*), which covers in the middle and posterior ethmoidal cells




FIG. 295.—Ethmoidal bone from behind.




FIG. 296.—Ethmoidal bone from the right side.

and forms a large part of the medial wall of the orbit; it articulates above with the orbital plate of the frontal bone, below with the maxilla and orbital process of the palatine, in front with the lacrimal, and behind with the sphenoid.

In front of the lamina papyracea are some broken air cells which are overlapped and completed by the lacrimal bone and the frontal process of the maxilla. A curved lamina, the **uncinate process**, projects downward and backward from this part of the labyrinth; it forms a small part of the medial wall of the maxillary sinus, and articulates with the ethmoidal process of the inferior nasal concha.

The **medial surface** of the labyrinth (Fig. 297) forms part of the lateral wall of the corresponding nasal cavity. It consists of a thin lamella, which descends from the under surface of the cribriform plate, and ends below in a free, convoluted margin, the **middle nasal concha**. It is rough, and marked above by numerous grooves, directed nearly vertically downward from the cribriform plate; they lodge branches of the olfactory nerves, which are distributed to the mucous membrane covering the superior nasal concha. The back part of the surface is subdivided by a narrow oblique fissure, the **superior meatus** of the nose, bounded above by a thin, curved plate, the **superior nasal concha**; the posterior ethmoidal cells open into this meatus. Below, and in front of the superior meatus, is the convex




FIG. 297.—Lateral wall of nasal cavity, showing ethmoidal bone in position.

surface of the middle nasal concha; it extends along the whole length of the medial surface of the labyrinth, and its lower margin is free and thick. The lateral surface of the middle concha is concave, and assists in forming the **middle meatus** of the nose. The middle ethmoidal cells open into the central part of this meatus, and a sinuous passage, termed the **infundibulum**, extends upward and forward through the labyrinth and communicates with the anterior ethmoidal cells, and in about 50 per cent. of skulls is continued upward as the frontonasal duct into the frontal sinus.

**Ossification.**—The ethmoid is ossified in the cartilage of the nasal capsule by *three* centres: one for the perpendicular plate, and one for each labyrinth.

The labyrinths are first developed, ossific granules making their appearance in the region of the lamina papyracea between the fourth and fifth months of fetal life, and extending into the conchæ. At birth, the bone consists of the two labyrinths, which are small and ill-developed. During the first year after birth, the perpendicular plate and crista galli begin to ossify from a single centre, and are joined to the labyrinths about the beginning of the second year. The cribriform plate is ossified partly from the perpendicular plate and partly from the labyrinths. The development of the ethmoidal cells begins during fetal life.

**Articulations.**—The ethmoid articulates with *fifteen* bones: four of the cranium—the frontal, the sphenoid, and the two sphenoidal conchæ; and eleven of the face—the two nasals, two maxillæ, two lacrimals, two palatines, two inferior nasal conchæ, and the vomer.

**Sutural or Wormian<sup>1</sup> Bones.**—In addition to the usual centres of ossification of the cranium, others may occur in the course of the sutures, giving rise to irregular, isolated bones, termed *sutural* or *Wormian bones*. They occur most frequently in the course of the lambdoidal suture, but are occasionally seen at the fontanelles, especially the posterior. One, the *pterion ossicle*, sometimes exists between the sphenoidal angle of the parietal and the great wing of the sphenoid. They have a tendency to be more or less symmetrical on the two sides of the skull, and vary much in size. Their number is generally limited to two or three; but more than a hundred have been found in the skull of an adult hydrocephalic subject.

**Applied Anatomy.**—An arrest in the ossifying process may give rise to deficiencies, gaps, or fissures in the cranium, which are of importance from a medicolegal point of view, as they are liable to be mistaken for fractures. The fissures generally extend from the margins toward the centre of a bone, but the gaps may be found in the middle as well as at the edges. In course of time they may become filled with thin laminæ of bone. In many of these cases, however, the gaps must be regarded as due to absorption of bone already formed rather than as congenital deficiencies; this is especially the case when they appear in the centre of a bone such as the parietal, the ossification of which has already been described as occurring in a regular manner radiating from one centre. The condition is most commonly seen in very badly nourished children affected with congenital syphilis, and is called *craniotabes*.

## THE FACIAL BONES (OSSA FACIÆ).

### The Nasal Bones (Ossa Nasalia).

The **nasal bones** are two small oblong bones, varying in size and form in different individuals; they are placed side by side at the middle and upper part of the face,




FIG. 298.—Articulation of nasal and lacrimal bones with maxilla.

and form, by their junction, “the bridge” of the nose (Fig. 334). Each has two surfaces and four borders.

<sup>1</sup> Ole Worm, Professor of Anatomy at Copenhagen, 1624–1639, was erroneously supposed to have given the first detailed description of these bones.

**Surfaces.**—The **outer surface** (Fig. 299) is concavoconvex from above downward, convex from side to side; it is covered by the Procerus and Compressor naris, and perforated about its centre by a foramen, for the transmission of a small vein. The **inner surface** (Fig. 300) is concave from side to side, and is traversed from above downward, by a groove for the passage of a branch of the nasociliary nerve.

**Borders.**—The **superior border** is narrow, thick, and serrated for articulation with the nasal notch of the frontal bone. The **inferior border** is thin, and gives attachment to the lateral cartilage of the nose; near its middle is a notch which marks the end of the groove just referred to. The **lateral border** is serrated, bevelled at the expense of the inner surface above, and of the outer below, to articulate with the frontal process of the maxilla. The **medial border**, thicker above than below, articulates with its fellow of the opposite side, and is prolonged behind into a vertical crest, which forms part of the nasal septum: this crest articulates, from above downward, with the spine of the frontal, the perpendicular plate of the ethmoid, and the septal cartilage of the nose.



FIG. 299.—Right nasal bone. Outer surface.




FIG. 300.—Right nasal bone. Inner surface.

**Ossification.**—Each bone is ossified from *one* centre, which appears at the beginning of the third month of fetal life in the membrane overlying the front part of the cartilaginous nasal capsule.

**Articulations.**—The nasal articulates with four bones: two of the cranium, the frontal and ethmoid, and two of the face, the opposite nasal and the maxilla.

### The Maxillæ (Upper Jaw).

The **maxillæ** are the largest bones of the face, excepting the mandible, and form, by their union, the whole of the upper jaw. Each assists in forming the boundaries of three cavities, viz., the roof of the mouth, the floor and lateral wall of the nose and the floor of the orbit; it also enters into the formation of two fossæ, the infratemporal and pterygopalatine, and two fissures, the inferior orbital and pterygomaxillary.

Each bone consists of a body and four processes—zygomatic, frontal, alveolar, and palatine.

**The Body** (*corpus maxillæ*).—The body is somewhat pyramidal in shape, and contains a large cavity, the **maxillary sinus** (*antrum of Highmore*). It has four surfaces—an anterior, a posterior or infratemporal, a superior or orbital, and a medial or nasal.

**Surfaces.**—The **anterior surface** (Fig. 301) is directed forward and lateralward. It presents at its lower part a series of eminences corresponding to the positions of the roots of the teeth. Just above those of the incisor teeth is a depression, the **incisive fossa**, which gives origin to the Depressor alae nasi; to the alveolar border below the fossa is attached a slip of the Orbicularis oris; above and a little lateral to it, the Nasalis arises. Lateral to the incisive fossa is another depression,



the **canine fossa**; it is larger and deeper than the incisive fossa, and is separated from it by a vertical ridge, the **canine eminence**, corresponding to the socket of the canine tooth; the canine fossa gives origin to the Caninus. Above the fossa is the **infraorbital foramen**, the end of the infraorbital canal; it transmits the infraorbital vessels and nerve. Above the foramen is the margin of the orbit, which affords attachment to part of the *Quadratus labii superioris*. Medially, the anterior surface is limited by a deep concavity, the **nasal notch**, the margin of which gives attachment to the *Dilatator naris posterior* and ends below in a pointed process, which with its fellow of the opposite side forms the **anterior nasal spine**.




FIG. 301.—Left maxilla. Outer surface.

The **infratemporal surface** (Fig. 301) is convex, directed backward and lateralward, and forms part of the infratemporal fossa. It is separated from the anterior surface by the zygomatic process and by a strong ridge, extending upward from the socket of the first molar tooth. It is pierced about its centre by the apertures of the **alveolar canals**, which transmit the posterior superior alveolar vessels and nerves. At the lower part of this surface is a rounded eminence, the **maxillary tuberosity**, especially prominent after the growth of the wisdom tooth; it is rough on its lateral side for articulation with the pyramidal process of the palatine bone and in some cases articulates with the lateral pterygoid plate of the sphenoid. It gives origin to a few fibres of the *Pterygoideus internus*. Immediately above this is a smooth surface, which forms the anterior boundary of the pterygopalatine fossa, and presents a groove, for the maxillary nerve; this groove is directed lateralward and slightly upward, and is continuous with the infraorbital groove on the orbital surface.

The **orbital surface** (Fig. 301) is smooth and triangular, and forms the greater part of the floor of the orbit. It is bounded *medially* by an irregular margin which in front presents a notch, the **lacrimal notch**; behind this notch the margin articulates with the lacrimal, the lamina papyracea of the ethmoid and the orbital process of the palatine. It is bounded *behind* by a smooth rounded edge which forms the anterior margin of the inferior orbital fissure, and sometimes articulates at its lateral extremity with the orbital surface of the great wing of the sphenoid.



It is limited *in front* by part of the circumference of the orbit, which is continuous medially with the frontal process, and laterally with the zygomatic process. Near the middle of the posterior part of the orbital surface is the **infraorbital groove**, for the passage of the infraorbital vessels and nerve. The groove begins at the middle of the posterior border, where it is continuous with that near the upper edge of the infratemporal surface, and, passing forward, ends in a canal, which subdivides into two branches. One of the canals, the **infraorbital canal**, opens just below the margin of the orbit; the other, which is smaller, runs downward in the substance of the anterior wall of the maxillary sinus, and transmits the anterior superior alveolar vessels and nerve to the front teeth of the maxilla. From the back part of the infraorbital canal, a second small canal is sometimes given off; it runs downward in the lateral wall of the sinus, and conveys the middle alveolar nerve to the premolar teeth. At the medial and forepart of the orbital surface, just lateral to the lacrimal groove, is a depression, which gives origin to the *Obliquus oculi inferior*.




FIG. 302.—Left maxilla. Nasal surface.

The **nasal surface** (Fig. 302) presents a large, irregular opening leading into the maxillary sinus. At the upper border of this aperture are some broken air cells, which, in the articulated skull, are closed in by the ethmoid and lacrimal bones. Below the aperture is a smooth concavity which forms part of the inferior meatus of the nasal cavity, and behind it is a rough surface for articulation with the perpendicular part of the palatine bone; this surface is traversed by a groove, commencing near the middle of the posterior border and running obliquely downward and forward; the groove is converted into a canal, the **pterygopalatine canal**, by the palatine bone. In front of the opening of the sinus is a deep groove, the **lacrimal groove**, which is converted into the nasolacrimal canal, by the lacrimal bone and inferior nasal concha; this canal opens into the inferior meatus of the nose and transmits the nasolacrimal duct. More anteriorly is an oblique ridge, the **conchal crest**, for articulation with the inferior nasal concha. The shallow concavity above this ridge forms part of the atrium of the middle meatus of the nose, and that below it, part of the inferior meatus.

**The Maxillary Sinus or Antrum of Highmore** (*sinus maxillaris*).—The maxillary sinus is a large pyramidal cavity, within the body of the maxilla: its **apex**, directed lateralward, is formed by the zygomatic process; its **base**, directed medialward, by the lateral wall of the nose. Its walls are everywhere exceedingly thin, and correspond to the nasal orbital, anterior, and infratemporal surfaces of the body of the bone. Its **nasal wall**, or **base**, presents, in the disarticulated bone, a large, irregular aperture, communicating with the nasal cavity. In the articulated skull this aperture is much reduced in size by the following bones: the uncinæ process of the ethmoid above, the ethmoidal process of the inferior nasal concha below, the vertical part of the palatine behind, and a small part of the lacrimal above and in front (Figs. 302, 303); the sinus communicates with the middle meatus of the nose, generally by two small apertures left between the above-mentioned bones. In the recent state, usually only one small opening exists, near the upper




FIG. 303.—Left maxillary sinus opened from the exterior.

part of the cavity; the other is closed by mucous membrane. On the **posterior wall** are the **alveolar canals**, transmitting the posterior superior alveolar vessels and nerves to the molar teeth. The **floor** is formed by the alveolar process of the maxilla, and, if the sinus be of an average size, is on a level with the floor of the nose; if the sinus be large it reaches below this level.

Projecting into the floor of the antrum are several conical processes, corresponding to the roots of the first and second molar teeth;<sup>1</sup> in some cases the floor is perforated by the fangs of the teeth. The infraorbital canal usually projects into the cavity as a well-marked ridge extending from the roof to the anterior wall; additional ridges are sometimes seen in the posterior wall of the cavity, and

<sup>1</sup> The number of teeth whose roots are in relation with the floor of the antrum is variable. The sinus "may extend so as to be in relation to all the teeth of the true maxilla, from the canine to the *dens sapientiae*." (Salter.)

are caused by the alveolar canals. The size of the cavity varies in different skulls, and even on the two sides of the same skull.<sup>1</sup>

**Applied Anatomy.**—The extreme thinness of the walls of this cavity affords an explanation of the fact that a tumor growing from the maxillary sinus and encroaching upon the adjacent parts may push up the floor of the orbit, and displace the eyeball; may project into the nose; may protrude forward on to the cheek; or may make its way backward into the infratemporal fossa, or downward into the mouth.

**The Zygomatic Process** (*processus zygomaticus; malar process*).—The zygomatic process is a rough triangular eminence, situated at the angle of separation of the anterior, zygomatic, and orbital surfaces. *In front* it forms part of the anterior surface; *behind*, it is concave, and forms part of the infratemporal fossa; *above*, it is rough and serrated for articulation with the zygomatic bone; while *below*, it presents the prominent arched border which marks the division between the anterior and infratemporal surfaces.

**The Frontal Process** (*processus frontalis; nasal process*).—The frontal process is a strong plate, which projects upward, medialward, and backward, by the side of the nose, forming part of its lateral boundary. Its *lateral surface* is smooth, continuous with the anterior surface of the body, and gives attachment to the Quadratus labii superioris, the Orbicularis oculi, and the medial palpebral ligament. Its *medial surface* forms part of the lateral wall of the nasal cavity; at its upper part is a rough, uneven area, which articulates with the ethmoid, closing in the anterior ethmoidal cells; below this is an oblique ridge, the **ethmoidal crest**, the posterior end of which articulates with the middle nasal concha, while the anterior part is termed the **agger nasi**; the crest forms the upper limit of the atrium of the middle meatus. The *upper border* articulates with the frontal bone and the *anterior* with the nasal; the *posterior border* is thick, and hollowed into a groove, which is continuous below with the lacrimal groove on the nasal surface of the body: by the articulation of the medial margin of the groove with the anterior border of the lacrimal a corresponding groove on the lacrimal is brought into continuity, and together they form the **lacrimal fossa** for the lodgement of the lacrimal sac. The lateral margin of the groove is named the **anterior lacrimal crest**, and is continuous below with the orbital margin; at its junction with the orbital surface is a small tubercle, the **lacrimal tubercle**, which serves as a guide to the position of the lacrimal sac.

**The Alveolar Process** (*processus alveolaris*).—The alveolar process is the thickest and most spongy part of the bone. It is broader behind than in front, and excavated into deep cavities for the reception of the teeth. These cavities are eight in number, and vary in size and depth according to the teeth they contain. That for the canine tooth is the deepest; those for the molars are the widest, and are subdivided into minor cavities by septa; those for the incisors are single, but deep and narrow. The Buccinator arises from the outer surface of this process, as far forward as the first molar tooth. When the maxillæ are articulated with each other, their alveolar processes together form the **alveolar arch**; the centre of the anterior margin of this arch is named the **alveolar point**.

**The Palatine Process** (*processus palatinus; palatal process*).—The palatine process, thick and strong, is horizontal and projects medialward from the nasal surface of the bone. It forms a considerable part of the floor of the nose and the roof of the mouth and is much thicker in front than behind. Its *inferior surface* (Fig. 304) is concave, rough and uneven, and forms, with the palatine process of the opposite bone, the anterior three-fourths of the hard plate. It is perforated by numerous foramina for the passage of the nutrient vessels; is channelled at the

<sup>1</sup> Aldren Turner (*op. cit.*) gives the following measurements as those of an average sized sinus: vertical height opposite first molar tooth, 1½ inch; transverse breadth, 1 inch; and antero-posterior depth, 1¼ inch.

back part of its lateral border by a groove, sometimes a canal, for the transmission of the descending palatine vessels and the anterior palatine nerve from the sphenopalatine ganglion; and presents little depressions for the lodgement of the palatine glands. When the two maxillæ are articulated, a funnel-shaped opening, the **incisive foramen**, is seen in the middle line, immediately behind the incisor teeth. In this opening the orifices of two lateral canals are visible; they are named the **incisive canals** or **foramina of Stensen**; through each of them passes the terminal branch of the descending palatine artery and the nasopalatine nerve. Occasionally two additional canals are present in the middle line; they are termed the **foramina of Scarpa**, and when present transmit the nasopalatine nerves, the left passing through the anterior, and the right through the posterior canal. On the under surface of the palatine process, a delicate linear suture, well seen in young skulls, may sometimes be noticed extending lateralward and forward on either side from




FIG. 304.—The bony palate and alveolar arch.

the incisive foramen to the interval between the lateral incisor and the canine tooth. The small part in front of this suture constitutes the **premaxilla** (*os incisivum*), which in most vertebrates forms an independent bone; it includes the whole thickness of the alveolus, the corresponding part of the floor of the nose and the anterior nasal spine, and contains the sockets of the incisor teeth. The *upper surface* of the palatine process is concave from side to side, smooth, and forms the greater part of the floor of the nasal cavity. It presents, close to its medial margin, the upper orifice of the incisive canal. The *lateral border* of the process is incorporated with the rest of the bone. The *medial border* is thicker in front than behind, and is raised above into a ridge, the **nasal crest**, which, with the corresponding ridge of the opposite bone, forms a groove for the reception of the vomer. The front part of this ridge rises to a considerable height, and is named the **incisor crest**; it is prolonged forward into a sharp process, which forms, together with a similar

process of the opposite bone, the **anterior nasal spine**. The *posterior border* is serrated for articulation with the horizontal part of the palatine bone.

**Ossification.**—The maxilla is ossified in membrane. Mall<sup>1</sup> and Fawcett<sup>2</sup> maintain that it is ossified from *two* centres only, one for the maxilla proper and one for the premaxilla. These centres appear during the sixth week of fetal life and unite in the beginning of the third month, but the suture between the two portions persists on the palate until nearly middle life. Mall states that the frontal process is developed from both centres. The maxillary sinus appears as a shallow groove on the nasal surface of the bone about the fourth month of fetal life, but does not reach its full size until after the second dentition. The maxilla was formerly described as ossifying from six centres, viz., one, the *orbitonasal*, forms that portion of the body of the bone which lies medial to the infraorbital canal, including the medial part of the floor of the orbit and the lateral wall of the nasal cavity; a second, the *zygomatic*, gives origin to the portion which lies lateral to the infraorbital canal, including the zygomatic process; from a third, the *palatine*, is developed the palatine process posterior to the incisive canal together with the adjoining part of the nasal wall; a fourth, the *premaxillary*, forms the incisive bone which carries the incisor



FIG. 305.—Anterior surface of maxilla at birth.



FIG. 306.—Inferior surface of maxilla at birth.




FIG. 307.—Nasal surface of maxilla at birth.

teeth and corresponds to the premaxilla of the lower vertebrates;<sup>3</sup> a fifth, the *nasal*, gives rise to the frontal process and the portion above the canine tooth; and a sixth, the *infravomerine*, lies between the palatine and premaxillary centres and beneath the vomer; this centre, together with the corresponding centre of the opposite bone, separates the incisive canals from each other.

**Articulations.**—The maxilla articulates with *nine* bones: two of the cranium, the frontal and ethmoid, and seven of the face, viz., the nasal, zygomatic, lacrimal, inferior nasal concha, palatine, vomer, and its fellow of the opposite side. Sometimes it articulates with the orbital surface, and sometimes with the lateral pterygoid plate of the sphenoid.

#### CHANGES PRODUCED IN THE MAXILLA BY AGE.

At birth the transverse and antero-posterior diameters of the bone are each greater than the vertical. The frontal process is well-marked and the body of the bone consists of little more than the alveolar process, the teeth sockets reaching almost to the floor of the orbit. The maxillary sinus presents the appearance of a furrow on the lateral wall of the nose. In the adult the vertical diameter is the greatest, owing to the development of the alveolar process and the increase in size of the sinus. In old age the bone reverts in some measure to the infantile condition; its height is diminished, and after the loss of the teeth the alveolar process is absorbed, and the lower part of the bone contracted and reduced in thickness.

<sup>1</sup> American Journal of Anatomy, 1906, vol. v.

<sup>2</sup> Journal of Anatomy and Physiology, 1911, vol. xlv.

<sup>3</sup> Some anatomists believe that the premaxillary bone is ossified by two centres (see page 299).



### The Lacrimal Bone (*Os Lacrimale*).

The **lacrimal bone**, the smallest and most fragile bone of the face, is situated at the front part of the medial wall of the orbit (Fig. 309). It has two surfaces and four borders.

**Surfaces.**—The **lateral or orbital surface** (Fig. 308) is divided by a vertical ridge, the **posterior lacrimal crest**, into two parts. In front of this crest is a longitudinal groove, the **lacrimal sulcus** (*sulcus lacrimonalis*), the inner margin of which unites with the frontal process of the maxilla, and the lacrimal fossa is thus completed. The upper part of this fossa lodges the lacrimal sac, the lower part, the nasolacrimal duct. The portion behind the crest is smooth, and forms part of the medial wall of the orbit. The crest, with a part of the orbital surface immediately behind it, gives origin to the lacrimal part of the *Orbicularis oculi* and ends below in a small, hook-like projection, the **lacrimal hamulus**, which articulates with the lacrimal tubercle of the maxilla, and completes the upper orifice of the lacrimal canal; it sometimes exists as a separate piece, and is then called the **lesser lacrimal bone**.

The **medial or nasal surface** presents a longitudinal furrow, corresponding to the crest on the lateral surface. The area in front of this furrow forms part of the middle meatus of the nose; that behind it articulates with the ethmoid, and completes some of the anterior ethmoidal cells.

**Borders.**—Of the **four borders** the **anterior** articulates with the frontal process of the maxilla; the **posterior** with the lamina papyracea of the ethmoid; the **superior** with the frontal bone. The **inferior** is divided by the lower edge of the posterior lacrimal crest into two parts: the posterior part articulates with the orbital plate of the maxilla; the anterior is prolonged downward as the **descending process**, which articulates with the lacrimal process of the inferior nasal concha, and assists in forming the canal for the nasolacrimal duct.



FIG. 308.—Left lacrimal bone. Orbital surface. Enlarged.

**Ossification.**—The lacrimal is ossified from a single centre, which appears about the twelfth week in the membrane covering the cartilaginous nasal capsule.

**Articulations.**—The lacrimal articulates with **four bones**: two of the cranium, the frontal and ethmoid, and two of the face, the maxilla and the inferior nasal concha.

### The Zygomatic Bone (*Os Zygomaticum*; **Malar Bone**).

The **zygomatic bone** is small and quadrangular, and is situated at the upper and lateral part of the face: it forms the prominence of the cheek, part of the lateral wall and floor of the orbit, and parts of the temporal and infratemporal fossae (Fig. 309). It presents a malar and a temporal surface; four processes, the frontosphenoidal, orbital, maxillary, and temporal; and four borders.

**Surfaces.**—The **malar surface** (Fig. 310) is convex and perforated near its centre by a small aperture, the **zygomaticofacial foramen**, for the passage of the zygomaticofacial nerve and vessels; below this foramen is a slight elevation, which gives origin to the *Zygomaticus*.

The **temporal surface** (Fig. 311), directed backward and medialward, is concave, presenting medially a rough, triangular area, for articulation with the maxilla, and laterally a smooth, concave surface, the upper part of which forms the anterior boundary of the temporal fossa, the lower a part of the infratemporal fossa. Near the centre of this surface is the **zygomaticotemporal foramen** for the transmission of the zygomaticotemporal nerve.



**Processes.**—The **frontosphenoidal process** is thick and serrated, and articulates with the zygomatic process of the frontal bone. On its orbital surface, just within the orbital margin and about 11 mm. below the zygomaticofrontal suture is a tubercle of varying size and form, but present in 95 per cent. of skulls (Whitnall<sup>1</sup>).




FIG. 309.—Left zygomatic bone in situ.

The **orbital process** is a thick, strong plate, projecting backward and medialward from the orbital margin. Its *antero-medial surface* forms, by its junction with the orbital surface of the maxilla and with the great wing of the sphenoid, part of the floor and lateral wall of the orbit. On it are seen the orifices of two canals,




FIG. 310.—Left zygomatic bone. Malar surface.




FIG. 311.—Left zygomatic bone. Temporal surface.

the **zygomatico-orbital foramina**; one of these canals opens into the temporal fossa, the other on the malar surface of the bone; the former transmits the zygomatico-temporal, the latter the zygomaticofacial nerve. Its *postero-lateral surface*, smooth

<sup>1</sup> Journal of Anatomy and Physiology, vol. xlv. The structures attached to this tubercle are: (1) the check ligament of the Rectus lateralis; (2) the lateral end of the aponeurosis of the Levator palpebrae superioris; (3) the suspensory ligament of the eye (Lockwood); and (4) the lateral extremities of the superior and inferior tarsi.

and convex, forms parts of the temporal and infratemporal fossæ. Its *anterior margin*, smooth and rounded, is part of the circumference of the orbit. Its *superior margin*, rough, and directed horizontally, articulates with the frontal bone behind the zygomatic process. Its *posterior margin* is serrated for articulation, with the great wing of the sphenoid and the orbital surface of the maxilla. At the angle of junction of the sphenoidal and maxillary portions, a short, concave, non-articular part is generally seen; this forms the anterior boundary of the inferior orbital fissure: occasionally, this non-articular part is absent, the fissure then being completed by the junction of the maxilla and sphenoid, or by the interposition of a small sutural bone in the angular interval between them. The **maxillary process** presents a rough, triangular surface which articulates with the maxilla. The **temporal process**, long, narrow, and serrated, articulates with the zygomatic process of the temporal.

**Borders.**—The **antero-superior** or **orbital border** is smooth, concave, and forms a considerable part of the circumference of the orbit. The **antero-inferior** or **maxillary border** is rough, and bevelled at the expense of its inner table, to articulate with the maxilla; near the orbital margin it gives origin to the *Quadratus labii superioris*. The **postero-superior** or **temporal border**, curved like an italic letter *f*, is continuous above with the commencement of the temporal line, and below with the upper border of the zygomatic arch; the temporal fascia is attached to it. The **postero-inferior** or **zygomatic border** affords attachment by its rough edge to the *Masseter*.

**Ossification.**—The zygomatic bone is generally described as ossifying from three centres—one for the malar and two for the orbital portion; these appear about the eighth week and fuse about the fifth month of fetal life. Mall describes it as being ossified from one centre which appears just beneath and to the lateral side of the orbit. After birth, the bone is sometimes divided by a horizontal suture into an upper larger, and a lower smaller division. In some quadrumana the zygomatic bone consists of two parts, an orbital and a malar.

**Articulations.**—The zygomatic articulates with *four* bones: the frontal, sphenoidal, temporal, and maxilla.




FIG. 312.—Articulation of left palatine bone with maxilla.

### The Palatine Bone (*Os Palatinum*; **Palate Bone**).

The **palatine bone** is situated at the back part of the nasal cavity between the maxilla and the pterygoid process of the sphenoid (Fig. 312). It contributes to the walls of three cavities: the floor and lateral wall of the nasal cavity, the

roof of the mouth, and the floor of the orbit; it enters into the formation of two fossæ, the **pterygopalatine** and **pterygoid fossæ**; and one fissure, the **inferior orbital fissure**. The palatine bone somewhat resembles the letter L, and consists of a horizontal and a vertical part and three outstanding processes—viz., the pyramidal process, which is directed backward and lateralward from the junction of the two parts, and the orbital and sphenoidal processes, which surmount the vertical part, and are separated by a deep notch, the sphenopalatine notch.

**The Horizontal Part** (*pars horizontalis*; *horizontal plate*) (Figs. 313, 314.).—The horizontal part is quadrilateral, and has two surfaces and four borders.

**Surfaces.**—The **superior surface**, concave from side to side, forms the back part of the floor of the nasal cavity. The **inferior surface**, slightly concave and rough, forms, with the corresponding surface of the opposite bone, the posterior fourth of the hard palate. Near its posterior margin may be seen a more or less marked transverse ridge for the attachment of part of the aponeurosis of the Tensor veli palatini.




FIG. 313.—Left palatine bone. Nasal aspect. Enlarged.




FIG. 314.—Left palatine bone. Posterior aspect. Enlarged.

**Borders.**—The **anterior border** is serrated, and articulates with the palatine process of the maxilla. The **posterior border** is concave, free, and serves for the attachment of the soft palate. Its medial end is sharp and pointed, and, when united with that of the opposite bone, forms a projecting process, the **posterior nasal spine** for the attachment of the Musculus uvulae. The **lateral border** is united with the lower margin of the perpendicular part, and is grooved by the lower end of the pterygopalatine canal. The **medial border**, the thickest, is serrated for articulation with its fellow of the opposite side; its superior edge is raised into a ridge, which, united with the ridge of the opposite bone, forms the **nasal crest** for articulation with the posterior part of the lower edge of the vomer.

**The Vertical Part** (*pars perpendicularis*; *perpendicular plate*) (Figs. 313, 314).—The vertical part is thin, of an oblong form, and presents two surfaces and four borders.

**Surfaces.**—The **nasal surface** exhibits at its lower part a broad, shallow depression, which forms part of the inferior meatus of the nose. Immediately above this is a well-marked horizontal ridge, the **conchal crest**, for articulation with the inferior nasal concha; still higher is a second broad, shallow depression, which

forms part of the middle meatus, and is limited above by a horizontal crest less prominent than the inferior, the **ethmoidal crest**, for articulation with the middle nasal concha. Above the ethmoidal crest is a narrow, horizontal groove, which forms part of the superior meatus.

The **maxillary surface** is rough and irregular throughout the greater part of its extent, for articulation with the nasal surface of the maxilla; its upper and back part is smooth where it enters into the formation of the pterygopalatine fossa; it is also smooth in front, where it forms the posterior part of the medial wall of the maxillary sinus. On the posterior part of this surface is a deep vertical groove, converted into the **pterygopalatine canal**, by articulation with the maxilla; this canal transmits the descending palatine vessels, and the anterior palatine nerve.

**Borders.**—The **anterior border** is thin and irregular; opposite the conchal crest is a pointed, projecting lamina, the **maxillary process**, which is directed forward, and closes in the lower and back part of the opening of the maxillary sinus. The **posterior border** (Fig. 314) presents a deep groove, the edges of which are serrated for articulation with the medial pterygoid plate of the sphenoid. This border is continuous above with the sphenoidal process; below it expands into the pyramidal process. The **superior border** supports the orbital process in front and the sphenoidal process behind. These processes are separated by the **sphenopalatine notch**, which is converted into the **sphenopalatine foramen** by the under surface of the body of the sphenoid. In the articulated skull this foramen leads from the pterygopalatine fossa into the posterior part of the superior meatus of the nose, and transmits the sphenopalatine vessels and the superior nasal and nasopalatine nerves. The **inferior border** is fused with the lateral edge of the horizontal part, and immediately in front of the pyramidal process is grooved by the lower end of the pterygopalatine canal.

**The Pyramidal Process or Tuberosity** (*processus pyramidalis*).—The pyramidal process projects backward and lateralward from the junction of the horizontal and vertical parts, and is received into the angular interval between the lower extremities of the pterygoid plates. On its **posterior surface** is a smooth, grooved, triangular area, limited on either side by a rough articular furrow. The furrows articulate with the pterygoid plates, while the grooved intermediate area completes the lower part of the pterygoid fossa and gives origin to a few fibres of the Pterygoideus internus. The anterior part of the **lateral surface** is rough, for articulation with the tuberosity of the maxilla; its posterior part consists of a smooth triangular area which appears, in the articulated skull, between the tuberosity of the maxilla and the lower part of the lateral pterygoid plate, and completes the lower part of the infratemporal fossa. On the **base** of the pyramidal process, close to its union with the horizontal part, are the lesser palatine foramina for the transmission of the posterior and middle palatine nerves.

**The Orbital Process** (*processus orbitalis*).—The orbital process is placed on a higher level than the sphenoidal, and is directed upward and lateralward from the front of the vertical part, to which it is connected by a constricted neck. It presents five surfaces, which enclose an air cell. Of these surfaces, three are articular and two non-articular. The articular surfaces are: (1) the **anterior** or **maxillary**, directed forward, lateralward, and downward, of an oblong form, and rough for articulation with the maxilla; (2) the **posterior** or **sphenoidal**, directed backward, upward, and medialward; it presents the opening of the air cell, which usually communicates with the sphenoidal sinus; the margins of the opening are serrated for articulation with the sphenoidal concha; (3) the **medial** or **ethmoidal**, directed forward, articulates with the labyrinth of the ethmoid. In some cases the air cell opens on this surface of the bone and then communicates with the posterior ethmoidal cells. More rarely it opens on both surfaces, and then communicates with the posterior ethmoidal cells and the sphenoidal sinus. The non-articular

surfaces are: (1) the **superior** or **orbital**, directed upward and lateralward; it is triangular in shape, and forms the back part of the floor of the orbit; and (2) the **lateral**, of an oblong form, directed toward the pterygopalatine fossa; it is separated from the orbital surface by a rounded border, which enters into the formation of the inferior orbital fissure.

**The Sphenoidal Process** (*processus sphenoidalis*).—The sphenoidal process is a thin, compressed plate, much smaller than the orbital, and directed upward and medialward. It presents three surfaces and two borders. The **superior surface** articulates with the root of the pterygoid process and the under surface of the sphenoidal concha, its medial border reaching as far as the ala of the vomer; it presents a groove which contributes to the formation of the pharyngeal canal. The **medial surface** is concave, and forms part of the lateral wall of the nasal cavity. The **lateral surface** is divided into an articular and a non-articular portion: the former is rough, for articulation with the medial pterygoid plate; the latter is smooth, and forms part of the pterygopalatine fossa. The **anterior border** forms the posterior boundary of the sphenopalatine notch. The **posterior border**, serrated at the expense of the outer table, articulates with the medial pterygoid plate.

The orbital and sphenoidal processes are separated from one another by the **sphenopalatine notch**. Sometimes the two processes are united above, and form between them a complete foramen (Fig. 313), or the notch may be crossed by one or more spicules of bone, giving rise to two or more foramina.

**Ossification**.—The palatine bone is ossified in membrane from a single centre, which makes its appearance about the sixth or eighth week of fetal life at the angle of junction of the two parts of the bone. From this point ossification spreads medialward to the horizontal part, downward into the pyramidal process, and upward into the vertical part. Some authorities describe the bone as ossifying from four centres: one for the pyramidal process and portion of the vertical part behind the pterygopalatine groove; a second for the rest of the vertical and the horizontal parts; a third for the orbital, and a fourth for the sphenoidal process. At the time of birth the height of the vertical part is about equal to the transverse width of the horizontal part, whereas in the adult the former measures about twice as much as the latter.

**Articulations**.—The palatine articulates with *six* bones: the sphenoid, ethmoid, maxilla, inferior nasal concha, vomer, and opposite palatine.

### **The Inferior Nasal Concha (Concha Nasalis Inferior; Inferior Turbinate Bone).**

The **inferior nasal concha** extends horizontally along the lateral wall of the nasal cavity (Fig. 315) and consists of a lamina of spongy bone, curled upon itself like a scroll. It has two surfaces, two borders, and two extremities.

The **medial surface** (Fig. 316) is convex, perforated by numerous apertures, and traversed by longitudinal grooves for the lodgement of vessels. The **lateral surface** is concave (Fig. 317), and forms part of the inferior meatus. Its **upper border** is thin, irregular, and connected to various bones along the lateral wall of the nasal cavity. It may be divided into three portions: of these, the anterior articulates with the conchal crest of the maxilla; the posterior with the conchal crest of the palatine; the middle portion presents three well-marked processes, which vary much in their size and form. Of these, the anterior or **lacrimal process** is small and pointed and is situated at the junction of the anterior fourth with the posterior three-fourths of the bone: it articulates, by its apex, with the descending process of the lacrimal bone, and, by its margins, with the groove on the back of the frontal process of the maxilla, and thus assists in forming the canal for the nasolacrimal duct. Behind this process a broad, thin plate, the **ethmoidal process**, ascends to join the uncinat process of the ethmoid; from its lower border a thin lamina, the **maxillary process**, curves downward and lateralward; it articulates with the maxilla and forms a part of the medial wall of the maxillary sinus. The **inferior border** is free, thick, and cellular in structure, more especially in the middle



of the bone. Both **extremities** are more or less pointed, the posterior being the more tapering.




FIG. 315.—Lateral wall of right nasal cavity showing inferior concha *in situ*.

**Ossification.**—The inferior nasal concha is ossified from a single centre, which appears about the fifth month of fetal life in the lateral wall of the cartilaginous nasal capsule.

**Articulations.**—The inferior nasal concha articulates with *four* bones: the ethmoid, maxilla, lacrimal, and palatine.




FIG. 316.—Right inferior nasal concha. Medial surface.



FIG. 317.—Right inferior nasal concha. Lateral surface.

### The Vomer.

The **vomer** is situated in the median plane, but its anterior portion is frequently bent to one or other side. It is thin, somewhat quadrilateral in shape, and forms the hinder and lower part of the nasal septum (Fig. 318); it has two surfaces and four borders. The **surfaces** (Fig. 319) are marked by small furrows for blood-vessels, and on each is the **nasopalatine groove**, which runs obliquely downward and forward, and lodges the nasopalatine nerve and vessels. The **superior border**, the thickest, presents a deep furrow, bounded on either side by a horizontal projecting ala of bone; the furrow receives the rostrum of the sphenoid, while the



margins of the alæ articulate with the vaginal processes of the medial pterygoid plates of the sphenoid behind, and with the sphenoidal processes of the palatine bones in front. The **inferior border** articulates with the crest formed by the maxillæ and palatine bones. The **anterior border** is the longest and slopes downward and




FIG. 318.—Median wall of left nasal cavity showing vomer *in situ*.

forward. Its upper half is fused with the perpendicular plate of the ethmoid; its lower half is grooved for the inferior margin of the septal cartilage of the nose. The **posterior border** is free, concave, and separates the choanæ. It is thick and bifid above, thin below.




FIG. 319.—The vomer.

is formed in which the cartilage is lodged. As growth proceeds, the union of the lamellæ extends upward and forward, and at the same time the intervening plate of cartilage undergoes absorption. By the age of puberty the lamellæ are almost completely united to form a median plate, but evidence of the bilaminar origin of the bone is seen in the everted alæ of its upper border and the groove on its anterior margin.

**Ossification.**—At an early period the septum of the nose consists of a plate of cartilage, the *ethmovomerine cartilage*. The postero-superior part of this cartilage is ossified to form the perpendicular plate of the ethmoid; its antero-inferior portion persists as the septal cartilage, while the vomer is ossified in the membrane covering its postero-inferior part. Two ossific centres, one on either side of the middle line, appear about the eighth week of fetal life in this part of the membrane, and hence the vomer consists primarily of two lamellæ. About the third month these unite below, and thus a deep groove

**Articulations.**—The vomer articulates with *six* bones: two of the cranium, the sphenoid and ethmoid; and four of the face, the two maxillæ and the two palatine bones; it also articulates with the septal cartilage of the nose.

**Applied Anatomy.**—The surfaces of the vomer are covered by mucous membrane, which is intimately connected with the periosteum, little, if any, submucous connective tissue intervening. Hence polypi are rarely found growing from this surface, though they frequently grow from the lateral walls of the nasal cavities, where the submucous tissue is abundant.

### The Mandible (Mandibula; Inferior Maxillary Bone; Lower Jaw).

The **mandible**, the largest and strongest bone of the face, serves for the reception of the lower teeth. It consists of a curved, horizontal portion, the **body**, and two perpendicular portions, the **rami**, which unite with the ends of the body nearly at right angles.

**The Body** (*corpus mandibulae*).—The body is curved somewhat like a horseshoe, and has two surfaces and two borders.




FIG. 320.—Mandible. Outer surface. Side view.

**Surfaces.**—The **external surface** (Fig. 320) is marked in the median line by a faint ridge, indicating the **symphysis** or line of junction of the two pieces of which the bone is composed at an early period of life. This ridge divides below and encloses a triangular eminence, the **mental protuberance**, the base of which is depressed in the centre but raised on either side to form the **mental tubercle**. On either side of the symphysis, just below the incisor teeth, is a depression, the **incisive fossa**, which gives origin to the Mentalis and a small portion of the Orbicularis oris. Below the second premolar tooth, on either side, midway between the upper and lower borders of the body, is the **mental foramen**, for the passage of the mental vessels and nerve. Running backward and upward from each mental tubercle is a faint ridge, the **oblique line**, which is continuous with the anterior border of the ramus; it affords attachment to the Quadratus labii inferioris and Triangularis; the Platysma is attached below it.

The **internal surface** (Fig. 321) is concave from side to side. Near the lower part of the symphysis is a pair of laterally placed spines, termed the **mental spines**, which give origin to the Genioglossi. Immediately below these is a second pair of spines, or more frequently a median ridge or impression, for the origin of the

Geniohyoidei. In some cases the mental spines are fused to form a single eminence, in others they are absent and their position is indicated merely by an irregularity of the surface. Above the mental spines a median foramen and furrow are sometimes seen; they mark the line of union of the halves of the bone. Below the mental spines, on either side of the middle line, is an oval depression for the attachment of the anterior belly of the Digastricus. Extending upward and backward on either side from the lower part of the symphysis is the **mylohyoid line**, which gives origin to the Mylohyoideus; the posterior part of this line, near the alveolar margin, gives attachment to a small part of the Constrictor pharyngis superior, and to the pterygomandibular raphé. Above the anterior part of this line is a smooth triangular area against which the sublingual gland rests, and below the hinder part, an oval fossa for the submaxillary gland.




FIG. 321.—Mandible. Inner surface. Side view.

**Borders.**—The **superior** or **alveolar border**, wider behind than in front, is hollowed into cavities, for the reception of the teeth; these cavities are sixteen in number, and vary in depth and size according to the teeth which they contain. To the outer lip of the superior border, on either side, the Buccinator is attached as far forward as the first molar tooth. The **inferior border** is rounded, longer than the superior, and thicker in front than behind; at the point where it joins the lower border of the ramus a shallow groove; for the external maxillary artery, may be present.

**The Ramus** (*ramus mandibulae; perpendicular portions*).—The ramus is quadrilateral in shape, and has two surfaces, four borders, and two processes.

**Surfaces.**—The **lateral surface** (Fig. 320) is flat and marked by oblique ridges at its lower part; it gives attachment throughout nearly the whole of its extent to the Masseter. The **medial surface** (Fig. 321) presents about its centre the oblique **mandibular foramen**, for the entrance of the inferior alveolar vessels and nerve. The margin of this opening is irregular; it presents in front a prominent ridge, surmounted by a sharp spine, the **lingula mandibulae**, which gives attachment to the sphenomandibular ligament; at its lower and back part is a notch from which the **mylohyoid groove** runs obliquely downward and forward, and lodges the mylohyoid vessels and nerve. Behind this groove is a rough surface, for the insertion

of the Pterygoideus internus. The **mandibular canal** runs obliquely downward and forward in the ramus, and then horizontally forward in the body, where it is placed under the alveoli and communicates with them by small openings. On arriving at the incisor teeth, it turns back to communicate with the mental foramen, giving off two small canals which run to the cavities containing the incisor teeth. In the posterior two-thirds of the bone the canal is situated nearer the internal surface of the mandible; and in the anterior third, nearer its external surface. It contains the inferior alveolar vessels and nerve, from which branches are distributed to the teeth. The **lower border** of the ramus is thick, straight, and continuous with the inferior border of the body of the bone. At its junction with the posterior border is the **angle of the mandible**, which may be either inverted or everted and is marked by rough, oblique ridges on each side, for the attachment of the Masseter laterally, and the Pterygoideus internus medially; the stylomandibular ligament is attached to the angle between these muscles. The **anterior border** is thin above, thicker below, and continuous with the oblique line. The **posterior border** is thick, smooth, rounded, and covered by the parotid gland. The **upper border** is thin, and is surmounted by two processes, the **coronoid** in front and the **condyloid** behind, separated by a deep concavity, the **mandibular notch**.

The **Coronoid Process** (*processus coronoideus*) is a thin, triangular eminence, which is flattened from side to side and varies in shape and size. Its **anterior border** is convex and is continuous below with the anterior border of the ramus; its **posterior border** is concave and forms the anterior boundary of the mandibular notch. Its **lateral surface** is smooth, and affords insertion to the Temporalis and Masseter. Its **medial surface** gives insertion to the Temporalis, and presents a ridge which begins near the apex of the process and runs downward and forward to the inner side of the last molar tooth. Between this ridge and the anterior border is a grooved triangular area, the upper part of which gives attachment to the Temporalis, the lower part to some fibres of the Buccinator.

The **Condyloid Process** (*processus condyloideus*) is thicker than the coronoid, and consists of two portions: the **condyle**, and the constricted portion which supports it, the **neck**. The **condyle** presents an articular surface for articulation with the articular disk of the temporomandibular joint; it is convex from before backward and from side to side, and extends farther on the posterior than on the anterior surface. Its long axis is directed medialward and slightly backward, and if prolonged to the middle line will meet that of the opposite condyle near the anterior margin of the foramen magnum. At the lateral extremity of the condyle is a small tubercle for the attachment of the temporomandibular ligament. The **neck** is flattened from before backward, and strengthened by ridges which descend from the forepart and sides of the condyle. Its posterior surface is convex; its anterior presents a depression for the attachment of the Pterygoideus externus.

The **mandibular notch**, separating the two processes, is a deep semilunar depression, and is crossed by the masseteric vessels and nerve.

**Ossification.**—The mandible is ossified in the fibrous membrane covering the outer surfaces of Meckel's cartilages. These cartilages form the cartilaginous bar of the mandibular arch (see p. 109), and are two in number, a right and a left. Their proximal or cranial ends are connected with the ear capsules, and their distal extremities are joined to one another at the symphysis by mesodermal tissue. They run forward immediately below the condyles and then, bending downward, lie in a groove near the lower border of the bone; in front of the canine tooth they incline upward to the symphysis. From the proximal end of each cartilage the malleus and incus, two of the bones of the middle ear, are developed; the next succeeding portion, as far as the lingula, is replaced by fibrous tissue, which persists to form the sphenomandibular ligament. Between the lingula and the canine tooth the cartilage disappears, while the portion of it below and behind the incisor teeth becomes ossified and incorporated with this part of the mandible.

Ossification takes place in the membrane covering the outer surface of the ventral end of Meckel's cartilage (Figs. 322 to 325), and each half of the bone is formed from a single centre

which appears, near the mental foramen, about the sixth week of fetal life. By the tenth week the portion of Meckel's cartilage which lies below and behind the incisor teeth is surrounded and invaded by the membrane bone. Somewhat later, accessory nuclei of cartilage make their appear-




FIG. 322.—Mandible of human embryo of 24 mm. long. Outer aspect. (From model by Low.)




FIG. 323.—Mandible of human embryo of 24 mm. long. Inner aspect. (From model by Low.)

ance, viz., a wedge-shaped nucleus in the condyloid process and extending downward through the ramus; a small strip along the anterior border of the coronoid process; and smaller nuclei in the front part of both alveolar walls and along the front of the lower border of the bone. These accessory nuclei possess no separate ossific centres, but are invaded by the surrounding membrane




FIG. 324.—Mandible of human embryo of 95 mm. long. Outer aspect. Nuclei of cartilage stippled. (From model by Low.)

bone and undergo absorption. The inner alveolar border, usually described as arising from a separate ossific centre (*splenic centre*), is formed in the human mandible by an ingrowth from the main mass of the bone. At birth the bone consists of two parts, united by a fibrous symphysis, in which ossification takes place during the first year.




FIG. 325.—Mandible of human embryo of 95 mm. long. Inner aspect. Nuclei of cartilage stippled. (From model by Low.)

The foregoing description of the ossification of the mandible is based on the researches of Low<sup>1</sup> and Fawcett,<sup>2</sup> and differs somewhat from that usually given.

**Articulations.**—The mandible articulates with the *two* temporal bones.

<sup>1</sup> Proceedings of the Anatomical and Anthropological Society of the University of Aberdeen, 1905, and Journal of Anatomy and Physiology, vol. xlv.

<sup>2</sup> Journal of the American Medical Association, September 2, 1905.

## CHANGES PRODUCED IN THE MANDIBLE BY AGE.

**At birth** (Fig. 326), the body of the bone is a mere shell, containing the sockets of the two incisor, the canine, and the two deciduous molar teeth, imperfectly partitioned off from one another. The mandibular canal is of large size, and runs near the lower border of the bone; the mental foramen opens beneath the socket of the first deciduous molar tooth. The angle is obtuse ( $175^\circ$ ), and the condyloid portion is nearly in line with the body. The coronoid process is of comparatively large size, and projects above the level of the condyle.

**After birth** (Fig. 327), the two segments of the bone become joined at the symphysis, from below upward, in the first year; but a trace of separation may be visible in the beginning of the second year, near the alveolar margin. The body becomes elongated in its whole length, but more especially behind the mental foramen, to provide space for the three additional teeth developed in this part. The depth of the body increases owing to increased growth of the alveolar part, to afford room for the roots of the teeth, and by thickening of the subdental portion which enables the jaw to withstand the powerful action of the masticatory muscles; but the alveolar portion is the deeper of the two, and, consequently, the chief part of the body lies above the oblique line. The mandibular canal, after the second dentition, is situated just above the level of the mylohyoid line; and the mental foramen occupies the position usual to it in the adult. The angle becomes less obtuse, owing to the separation of the jaws by the teeth; about the fourth year it is  $140^\circ$ .

**In the adult** (Fig. 328), the alveolar and subdental portions of the body are usually of equal depth. The mental foramen opens midway between the upper and lower borders of the bone, and the mandibular canal runs nearly parallel with the mylohyoid line. The ramus is almost vertical in direction, the angle measuring from  $110^\circ$  to  $120^\circ$ .

**In old age** (Fig. 329), the bone becomes greatly reduced in size, for with the loss of the teeth the alveolar process is absorbed, and, consequently, the chief part of the bone is below the oblique line. The mandibular canal, with the mental foramen opening from it, is close to the alveolar border. The ramus is oblique in direction, the angle measures about  $140^\circ$ , and the neck of the condyle is more or less bent backward.

## The Hyoid Bone (Os Hyoideum; Lingual Bone).

The **hyoid bone** is shaped like a horseshoe, and is suspended from the tips of the styloid processes of the temporal bones by the stylohyoid ligaments. It consists of five segments, viz., a body, two **greater cornua**, and two **lesser cornua**.

**The Body or Basihyal** (*corpus oss. hyoidei*).—The body or central part is of a quadrilateral form. Its **anterior surface** (Fig. 330) is convex and directed forward and upward. It is crossed in its upper half by a well-marked transverse ridge with a slight downward convexity, and in many cases a vertical median ridge divides it into two lateral halves. The portion of the vertical ridge above the transverse line is present in a majority of specimens, but the lower portion is evident only in rare cases. The anterior surface gives insertion to the Geniohyoideus in the greater part of its extent both above and below the transverse ridge; a portion of the origin of the Hyoglossus notches the lateral margin of the Geniohyoideus attachment. Below the transverse ridge the Mylohyoideus, Sternohyoideus, and Omohyoideus are inserted. The **posterior surface** is smooth, concave, directed backward and downward, and separated from the epiglottis by the hyothyroid membrane and a quantity of loose areolar tissue; a bursa intervenes between it and the hyothyroid membrane. The **superior border** is rounded, and gives attachment to the hyothyroid membrane and some aponeurotic fibres of the Genioglossus. The **inferior border** affords insertion medially to the Sternohyoideus and laterally to the Omohyoideus and occasionally a portion of the Thyrohyoideus. It also gives attachment to the Levator glandulae thyroideae, when this muscle is present. In early life the **lateral borders** are connected to the greater cornua by synchondroses; after middle life usually by bony union.

**The Greater Cornua or Thyrohyals** (*cornua majora*).—The greater cornua project backward from the lateral borders of the body; they are flattened from above downward and diminish in size from before backward; each ends in a tubercle to which is fixed the lateral hyothyroid ligament. The **upper surface** is rough





FIG. 326.—At birth.




FIG. 327.—In childhood.




FIG. 328.—In the adult.



FIG. 329.—In old age.  
Side view of the mandible at different periods of life.

close to its lateral border, for muscular attachments: the largest of these are the origins of the Hyoglossus and Constrictor pharyngis medius which extend along the whole length of the cornu; the Digastricus and Stylohyoideus have small insertions in front of these near the junction of the body with the cornu. To the medial border the hyothyroid membrane is attached, while the anterior half of the lateral border gives insertion to the Thyrohyoideus.

**The Lesser Cornua or Ceratohyals** (*cornua minora*).—The lesser cornua are two small, conical eminences, attached by their bases to the angles of junction between the body and greater cornua. They are connected to the body of the bone

by fibrous tissue, and occasionally to the greater cornua by distinct diarthrodial joints, which usually persist throughout life, but occasionally become ankylosed.

The lesser cornua are situated in the line of the transverse ridge on the body and appear to be morphological continuations of it (Parsons<sup>1</sup>). The apex of each cornu gives attachment to the stylohyoid ligament;<sup>2</sup> the Chondroglossus rises from the medial side of the base.




FIG. 330.—Hyoid bone. Anterior surface. Enlarged.

**Ossification.**—The hyoid is ossified from six centres: two for the body, and one for each cornu. Ossification commences in the greater cornua toward the end of fetal life, in the body shortly afterward, and in the lesser cornua during the first or second year after birth.

**Applied Anatomy.**—The hyoid bone is occasionally fractured, generally from direct violence, as in hanging, forcible grasping of the throat in garroting or throttling, or by a blow. The fracture generally occurs about the junction of the greater cornu with the body of the bone, but sometimes takes place through the latter; since the muscles of the tongue have important connections with this bone, there is great pain upon any attempt being made to move the tongue, as in speaking or swallowing.

## THE EXTERIOR OF THE SKULL.

The skull as a whole may be viewed from different points, and the views so obtained are termed the *normæ* of the skull; thus, it may be examined from above (*norma verticalis*), from below (*norma basalis*), from the side (*norma lateralis*), from behind (*norma occipitalis*), or from the front (*norma frontalis*).

**Norma Verticalis.**—When viewed from above the outline presented varies greatly in different skulls; in some it is more or less oval, in others more nearly circular. The surface is traversed by three sutures, viz.: (1) the **coronal sutures**, nearly transverse in direction, between the frontal and parietals; (2) the **sagittal sutures**, medially placed, between the parietal bones, and deeply serrated in its anterior two-thirds; and (3) the upper part of the **lambdoidal suture**, between the parietals and the occipital. The point of junction of the sagittal and coronal suture is named the **bregma**, that of the sagittal and lambdoid sutures, the **lambda**; they indicate respectively the positions of the anterior and posterior fontanelles in the fetal skull. On either side of the sagittal suture are the **parietal eminence** and **parietal**

<sup>1</sup> See article on "The Topography and Morphology of the Human Hyoid Bone," by F. G. Parsons, *Journal of Anatomy and Physiology*, vol. xliii.

<sup>2</sup> These ligaments in many animals are distinct bones, and in man may undergo partial ossification.

**foramen**—the latter, however, is frequently absent on one or both sides. The skull is often somewhat flattened in the neighborhood of the parietal foramina, and the term **obelion** is applied to that point of the sagittal suture which is on a level with the foramina. In front is the **glabella**, and on its lateral aspects are the **superciliary arches**, and above these the **frontal eminences**. Immediately above the glabella may be seen the remains of the **frontal suture**; in a small percentage of skulls this suture persists and extends along the middle line to the bregma. Passing backward and upward from the zygomatic processes of the frontal bone are the **temporal lines**, which mark the upper limits of the temporal fossæ. The zygomatic arches may or may not be seen projecting beyond the anterior portions of these lines.

**Norma Basalis** (Fig. 331).—The inferior surface of the base of the skull, exclusive of the mandible, is bounded in front by the incisor teeth in the maxillæ; behind, by the superior nuchal lines of the occipital; and laterally by the alveolar arch, the lower border of the zygomatic bone, the zygomatic arch and an imaginary line extending from it to the mastoid process and extremity of the superior nuchal line of the occipital. It is formed by the palatine processes of the maxillæ and palatine bones, the vomer, the pterygoid processes, the under surfaces of the great wings, spinous processes, and part of the body of the sphenoid, the under surfaces of the squamæ and mastoid and petrous portions of the temporals, and the under surface of the occipital bone. The anterior part or hard palate projects below the level of the rest of the surface, and is bounded in front and laterally by the alveolar arch containing the sixteen teeth of the maxillæ. Immediately behind the incisor teeth is the **incisive foramen**. In this foramen are two lateral apertures, the openings of the **incisive canals** (*foramina of Stensen*) which transmit the anterior branches of the descending palatine vessels, and the nasopalatine nerves. Occasionally two additional canals are present in the incisive foramen; they are termed the **foramina of Scarpa** and are situated in the middle line; when present they transmit the nasopalatine nerves. The vault of the hard palate is concave, uneven, perforated by numerous foramina, marked by depressions for the palatine glands, and traversed by a crucial suture formed by the junction of the four bones of which it is composed. In the young skull a suture may be seen extending on either side from the incisive foramen to the interval between the lateral incisor and canine teeth, and marking off the *os incisivum* or premaxillary bone. At either posterior angle of the hard palate is the **greater palatine foramen**, for the transmission of the descending palatine vessels and anterior palatine nerve; and running forward and medialward from it a groove, for the same vessels and nerve. Behind the posterior palatine foramen is the **pyramidal process of the palatine bone**, perforated by one or more **lesser palatine foramina**, and marked by the commencement of a transverse ridge, for the attachment of the tendinous expansion of the *Tensor veli palatini*. Projecting backward from the centre of the posterior border of the hard palate is the **posterior nasal spine**, for the attachment of the *Musculus uvulae*. Behind and above the hard palate are the **choanæ**, measuring about 2.5 cm. in their vertical and 1.25 cm. in their transverse diameters. They are separated from one another by the vomer, and each is bounded above by the body of the sphenoid, below by the horizontal part of the palatine bone, and laterally by the medial pterygoid plate of the sphenoid. At the superior border of the vomer may be seen the expanded alæ of this bone, receiving between them the rostrum of the sphenoid. Near the lateral margins of the alæ of the vomer, at the roots of the pterygoid processes, are the **pharyngeal canals**. The pterygoid process presents near its base the **pterygoid canal**, for the transmission of a nerve and artery. The medial pterygoid plate is long and narrow; on the lateral side of its base is the **scaphoid fossa**, for the origin of the *Tensor veli palatini*, and at its lower extremity the **hamulus**, around which the tendon of this muscle turns. The lateral pterygoid

plate is broad; its lateral surface forms the medial boundary of the infratemporal fossa, and affords attachment to the Pterygoideus externus.




FIG. 331.—Base of skull. Inferior surface.

Behind the nasal cavities is the basilar portion of the occipital bone, presenting near its centre the **pharyngeal tubercle** for the attachment of the fibrous raphé of the pharynx, with depressions on either side for the insertions of the Rectus capitis anterior and Longus capitis. At the base of the lateral pterygoid plate is the **foramen ovale**, for the transmission of the mandibular nerve, the accessory meningeal artery, and sometimes the lesser superficial petrosal nerve; behind this are the **foramen spinosum** which transmits the middle meningeal vessels, and the prominent **spina angularis** (*sphenoidal spine*), which gives attachment to the sphenomandibular ligament and the Tensor veli palatini. Lateral to the spina angularis is the **mandibular fossa**, divided into two parts by the **petrotympanic fissure**; the anterior portion, concave, smooth, bounded in front by the **articular tubercle**, serves for the articulation of the condyle of the mandible; the posterior portion, rough and bounded behind by the tympanic part of the temporal, is sometimes occupied by a part of the parotid gland. Emerging from between the laminæ of the vaginal process of the tympanic part is the **styloid process**; and at the base of this process is the **stylomastoid foramen**, for the exit of the facial nerve, and entrance of the stylomastoid artery. Lateral to the stylomastoid foramen, between the tympanic part and the mastoid process, is the **tympanomastoid fissure**, for the auricular branch of the vagus. Upon the medial side of the mastoid process is the **mastoid notch** for the posterior belly of the Digastricus, and medial to the notch, the **occipital groove** for the occipital artery. At the base of the medial pterygoid plate is a large and somewhat triangular aperture, the **foramen lacerum**, bounded in front by the great wing of the sphenoid, behind by the apex of the petrous portion of the temporal bone, and medially by the body of the sphenoid and basilar portion of the occipital bone; it presents in front the posterior orifice of the **pterygoid canal**; behind, the aperture of the **carotid canal**. The lower part of this opening is filled up in the recent state by a fibrocartilaginous plate, across the upper or cerebral surface of which the internal carotid artery passes. Lateral to this aperture is a groove, the **sulcus tubæ auditivæ**, between the petrous part of the temporal and the great wing of the sphenoid. This sulcus is directed lateralward and backward from the root of the medial pterygoid plate and lodges the cartilaginous part of the auditory tube; it is continuous behind with the canal in the temporal bone which forms the bony part of the same tube. At the bottom of this sulcus is a narrow cleft, the **petrosphenoidal fissure**, which is occupied, in the recent condition, by a plate of cartilage. Behind this fissure is the under surface of the petrous portion of the temporal bone, presenting, near its apex, the quadrilateral rough surface, part of which affords attachment to the Levator veli palatini; lateral to this surface is the orifice of the **carotid canal**, and medial to it, the depression leading to the **aquaeductus cochleæ**, the former transmitting the internal carotid artery and the carotid plexus of the sympathetic, the latter serving for the passage of a vein from the cochlea. Behind the carotid canal is the **jugular foramen**, a large aperture, formed in front by the petrous portion of the temporal, and behind by the occipital; it is generally larger on the right than on the left side, and may be subdivided into three compartments. The anterior compartment transmits the inferior petrosal sinus; the intermediate, the glossopharyngeal, vagus, and accessory nerves; the posterior, the transverse sinus and some meningeal branches from the occipital and ascending pharyngeal arteries. On the ridge of bone dividing the carotid canal from the jugular foramen is the **inferior tympanic canaliculus** for the transmission of the tympanic branch of the glossopharyngeal nerve; and on the wall of the jugular foramen, near the root of the styloid process, is the **mastoid canaliculus** for the passage of the auricular branch of the vagus nerve. Extending forward from the jugular foramen to the foramen lacerum is the **petrooccipital fissure** occupied, in the recent state, by a plate of cartilage. Behind the basilar portion of the occipital bone is the **foramen magnum**, bounded laterally by the occipital



condyles, the medial sides of which are rough for the attachment of the alar ligaments. Lateral to each condyle is the **jugular process** which gives attachment to the Rectus capitis lateralis muscle and the lateral atlantooccipital ligament. The **foramen magnum** transmits the medulla oblongata and its membranes, the accessory nerves, the vertebral arteries, the anterior and posterior spinal arteries, and the ligaments connecting the occipital bone with the axis. The mid-points on the anterior and posterior margins of the foramen magnum are respectively termed the **basion** and the **opisthion**. In front of each condyle is the canal for the passage of the hypoglossal nerve and a meningeal artery. Behind each condyle is the **condyloid fossa**, perforated on one or both sides by the condyloid canal, for the transmission of a vein from the transverse sinus. Behind the foramen magnum is the **median nuchal line** ending above at the **external occipital protuberance**, while on either side are the **superior and inferior nuchal lines**; these, as well as the surfaces of bone between them, are rough for the attachment of the muscles which are enumerated on pages 227 and 228.




FIG. 332.—Side view of the skull.

**Norma Lateralis** (Fig. 332).—When viewed from the side the skull is seen to consist of the cranium above and behind, and of the face below and in front. The cranium is somewhat ovoid in shape, but its contour varies in different cases and depends largely on the length and height of the skull and on the degree of prominence of the superciliary arches and frontal eminences. Entering into its formation are the frontal, the parietal, the occipital, the temporal, and the great wing of the sphenoid. These bones are joined to one another and to the zygomatic by the follow-



ing sutures: the **zygomaticotemporal** between the zygomatic process of the temporal and the temporal process of the zygomatic; the **zygomaticofrontal** uniting the zygomatic bone with the zygomatic process of the frontal; the sutures surrounding the great wing of the sphenoid, viz., the **sphenozygomatic** in front, the **sphenofrontal** and **sphenoparietal** above, and the **sphenosquamosal** behind. The sphenoparietal suture varies in length in different skulls, and is absent in those cases where the frontal articulates with the temporal squama. The point corresponding with the posterior end of the sphenoparietal suture is named the **pterion**; it is situated about 3 cm. behind, and a little above the level of the zygomatic process of the frontal bone.

The **squamosal suture** arches backward from the pterion and connects the temporal squama with the lower border of the parietal: this suture is continuous behind with the short, nearly horizontal **parietomastoid suture**, which unites the mastoid process of the temporal with the region of the mastoid angle of the parietal. Extending from above downward and forward across the cranium are the **coronal** and **lambdoidal sutures**; the former connects the parietals with the frontal, the latter, the parietals with the occipital. The lambdoidal suture is continuous below with the **occipitomastoid suture** between the occipital and the mastoid portion of the temporal. In or near the last suture is the **mastoid foramen**, for the transmission of an emissary vein. The point of meeting of the parietomastoid, occipitomastoid, and lambdoidal sutures is known as the **asterion**. Immediately above the orbital margin is the **superciliary arch**, and, at a higher level, the **frontal eminence**. Near the centre of the parietal bone is the **parietal eminence**. Posteriorly is the **external occipital protuberance**, from which the superior nuchal line may be followed forward to the mastoid process. Arching across the side of the cranium are the **temporal lines**, which mark the upper limit of the temporal fossa.

**The Temporal Fossa** (*fossa temporalis*).—The temporal fossa is bounded above and behind by the temporal lines, which extend from the zygomatic process of the frontal bone upward and backward across the frontal and parietal bones, and then curve downward and forward to become continuous with the supramastoid crest and the posterior root of the zygomatic arch. The point where the upper temporal line cuts the coronal suture is named the **stephanion**. The temporal fossa is bounded in *front* by the frontal and zygomatic bones, and opening on the back of the latter is the **zygomaticotemporal foramen**. *Laterally* the fossa is limited by the zygomatic arch, formed by the zygomatic and temporal bones; *below*, it is separated from the infratemporal fossa by the **infratemporal crest** on the great wing of the sphenoid, and by a ridge, continuous with this crest, which is carried backward across the temporal squama to the anterior root of the zygomatic process. In front and below, the fossa communicates with the orbital cavity through the **inferior orbital** or **sphenomaxillary fissure**. The floor of the fossa is deeply concave in front and convex behind, and is formed by the zygomatic, frontal, parietal, sphenoid, and temporal bones. It is traversed by vascular furrows; one, usually well-marked, runs upward above and in front of the external acoustic meatus, and lodges the middle temporal artery. Two others, frequently indistinct, may be observed on the anterior part of the floor, and are for the anterior and posterior deep temporal arteries. The temporal fossa contains the Temporalis muscle and its vessels and nerves, together with the zygomaticotemporal nerve.

The **zygomatic arch** is formed by the zygomatic process of the temporal and the temporal process of the zygomatic, the two being united by an oblique suture; the tendon of the Temporalis passes medial to the arch to gain insertion into the coronoid process of the mandible. The zygomatic process of the temporal arises by two roots, an anterior, directed inward in front of the mandibular fossa, where it expands to form the articular tubercle, and a posterior, which runs backward above the external acoustic meatus and is continuous with the supramastoid

crest. The upper border of the arch gives attachment to the temporal fascia; the lower border and medial surface give origin to the Masseter.

Below the posterior root of the zygomatic arch is the elliptical orifice of the **external acoustic meatus**, bounded in front, below, and behind by the tympanic part of the temporal bone; to its outer margin the cartilaginous segment of the external acoustic meatus is attached. The small triangular area between the posterior root of the zygomatic arch and the postero-superior part of the orifice is termed the **suprameatal triangle**, on the anterior border of which a small spinous process, the **suprameatal spine**, is sometimes seen. Between the tympanic part and the articular tubercle is the **mandibular fossa**, divided into two parts by the petrotympanic fissure. The anterior and larger part of the fossa articulates with the condyle of the mandible and is limited behind by the external acoustic meatus: the posterior part sometimes lodges a portion of the parotid gland. The styloid process extends downward and forward for a variable distance from the lower part of the tympanic part, and gives attachment to the Styloglossus, Stylohyoideus, and Stylopharyngeus, and to the stylohyoid and stylomandibular ligaments. Projecting downward behind the external acoustic meatus is the mastoid process, to the outer surface of which the Sternocleidomastoideus, Splenius capitis, and Longissimus capitis are attached.




FIG. 333.—Left infratemporal fossa.

**The Infratemporal Fossa** (*fossa infratemporalis*; *zygomatic fossa*) (Fig. 333).—The infratemporal fossa is an irregularly shaped cavity, situated below and medial to the **zygomatic arch**. It is bounded, in *front*, by the infratemporal surface of the maxilla and the ridge which descends from its zygomatic process; *behind*, by the articular tubercle of the temporal and the spina angularis of the sphenoid; *above*, by the great wing of the sphenoid below the infratemporal crest, and by the under surface of

the temporal squama; *below*, by the alveolar border of the maxilla; *medially*, by the lateral pterygoid plate. It contains the lower part of the Temporalis, the Pterygoidei internus and externus, the internal maxillary vessels, and the mandibular and maxillary nerves. The **foramen ovale** and **foramen spinosum** open on its roof, and the **alveolar canals** on its anterior wall. At its upper and medial part are two fissures, which together form a T-shaped fissure, the horizontal limb being named the inferior orbital, and the vertical one the pterygomaxillary.

The **inferior orbital fissure** (*fissura orbitalis inferior*; *sphenomaxillary fissure*), horizontal in direction, opens into the lateral and back part of the orbit. It is bounded *above* by the lower border of the orbital surface of the great wing of the sphenoid; *below*, by the lateral border of the orbital surface of the maxilla and the orbital process of the palatine bone; *laterally*, by a small part of the zygomatic bone;<sup>1</sup> *medially*, it joins at right angles with the pterygomaxillary fissure. Through the inferior orbital fissure the orbit communicates with the temporal, infratemporal, and pterygopalatine fossæ; the fissure transmits the maxillary nerve and its zygomatic branch, the infraorbital vessels, the ascending branches from the sphenopalatine ganglion, and a vein which connects the inferior ophthalmic vein with the pterygoid venous plexus.

The **pterygomaxillary fissure** is vertical, and descends at right angles from the medial end of the preceding; it is a triangular interval, formed by the divergence of the maxilla from the pterygoid process of the sphenoid. It connects the infratemporal with the pterygopalatine fossa, and transmits the terminal part of the internal maxillary artery.

**The Pterygopalatine Fossa** (*fossa pterygopalatina*; *sphenomaxillary fossa*).—The pterygopalatine fossa is a small, triangular space at the angle of junction of the inferior orbital and pterygomaxillary fissures, and placed beneath the apex of the orbit. It is bounded *above* by the under surface of the body of the sphenoid and by the orbital process of the palatine bone; *in front*, by the infratemporal surface of the maxilla; *behind*, by the base of the pterygoid process and lower part of the anterior surface of the great wing of the sphenoid; *medially*, by the vertical part of the palatine bone with its orbital and sphenoidal processes. This fossa communicates with the orbit by the inferior orbital fissure, with the nasal cavity by the sphenopalatine foramen, and with the infratemporal fossa by the pterygomaxillary fissure. Five foramina open into it. Of these, three are on the posterior wall, viz., the **foramen rotundum**, the **pterygoid canal**, and the **pharyngeal canal**, in this order downward and medialward. On the medial wall is the **sphenopalatine foramen**, and below is the superior orifice of the **pterygopalatine canal**. The fossa contains the maxillary nerve, the sphenopalatine ganglion, and the terminal part of the internal maxillary artery.

**Norma Occipitalis.**—When viewed from behind the cranium presents a more or less circular outline. In the middle line is the posterior part of the **sagittal suture** connecting the parietal bones; extending downward and lateralward from the hinder end of the sagittal suture is the deeply serrated **lambdoidal suture** joining the parietals to the occipital and continuous below with the **parietomastoid** and **occipitomastoid sutures**; it frequently contains one or more sutural bones. Near the middle of the occipital squama is the **external occipital protuberance** or **inion**, and extending lateralward from it on either side is the superior nuchal line, and above this the faintly marked highest nuchal line. The part of the squama above the inion and highest lines is named the **planum occipitale**, and is covered by the Occipitalis muscle; the part below is termed the **planum nuchale**, and is divided by the median nuchal line which runs downward and forward from the inion to the foramen magnum; this ridge gives attachment to the ligamentum nuchae. The

<sup>1</sup> Occasionally the maxilla and the sphenoid articulate with each other at the anterior extremity of this fissure; the zygomatic is then excluded from it.

muscles attached to the planum nuchale are enumerated on p. 227. Below and in front are the mastoid processes, convex laterally and grooved medially by the mastoid notches. In or near the occipitomastoid suture is the **mastoid foramen** for the passage of the mastoid emissary vein.




FIG. 334.—The skull from the front.

**Norma Frontalis** (Fig. 334).—When viewed from the front the skull exhibits a somewhat oval outline, limited *above* by the frontal bone, *below* by the body of the mandible, and *laterally* by the zygomatic bones and the mandibular rami. The upper part, formed by the frontal squama, is smooth and convex. The lower part, made up of the bones of the face, is irregular; it is excavated laterally by the orbital cavities, and presents in the middle line the **anterior nasal aperture** leading to the nasal cavities, and below this the transverse slit between the upper and lower dental arcades. *Above*, the **frontal eminences** stand out more or less prominently, and beneath these are the **superciliary arches**, joined to one another in the middle by the **glabella**. On and above the glabella a trace of the **frontal suture** sometimes persists; beneath it is the frontonasal suture, the mid-point of which is termed the **nasion**. Behind and below the frontonasal suture the frontal articulates with the frontal process of the maxilla and with the lacrimal. Arching transversely below

the superciliary arches is the upper part of the margin of the orbit, thin and prominent in its lateral two-thirds, rounded in its medial third, and presenting, at the junction of these two portions, the **supraorbital notch** or **foramen** for the supra-orbital nerve and vessels. The supraorbital margin ends laterally in the zygomatic process which articulates with the zygomatic bone, and from it the temporal line extends upward and backward. Below the frontonasal suture is the bridge of the nose, convex from side to side, concavo-convex from above downward, and formed by the two nasal bones supported in the middle line by the perpendicular plate of the ethmoid, and laterally by the frontal processes of the maxillæ which are prolonged upward between the nasal and lacrimal bones and form the lower and medial part of the circumference of each orbit. Below the nasal bones and between the maxillæ is the anterior aperture of the nose, pyriform in shape, with the narrow end directed upward. Laterally this opening is bounded by sharp margins, to which the lateral and alar cartilages of the nose are attached; *below*, the margins are thicker and curve medialward and forward to end in the **anterior nasal spine**. On looking into the nasal cavity, the bony septum which separates the nasal cavities presents, in front, a large triangular deficiency; this, in the recent state, is filled up by the cartilage of the nasal septum; on the lateral wall of each nasal cavity the anterior part of the inferior nasal concha is visible. Below and lateral to the anterior nasal aperture are the anterior surfaces of the maxillæ, each perforated, near the lower margin of the orbit, by the **infraorbital foramen** for the passage of the infraorbital nerve and vessels. Below and medial to this foramen is the canine eminence separating the incisor from the canine fossa. Beneath these fossæ are the alveolar processes of the maxillæ containing the upper teeth, which overlap the teeth of the mandible in front. The zygomatic bone on either side forms the prominence of the cheek, the lower and lateral portion of the orbital cavity, and the anterior part of the zygomatic arch. It articulates medially with the maxilla, behind with the zygomatic process of the temporal, and above with the great wing of the sphenoid and the zygomatic process of the frontal; it is perforated by the **zygomaticofacial foramen** for the passage of the zygomaticofacial nerve. On the body of the mandible is a median ridge, indicating the position of the symphysis; this ridge divides below to enclose the mental protuberance, the lateral angles of which constitute the mental tubercles. Below the incisor teeth is the **incisive fossa**, and beneath the second premolar tooth the **mental foramen** which transmits the mental nerve and vessels. The oblique line runs upward from the mental tubercle and is continuous behind with the anterior border of the ramus. The posterior border of the ramus runs downward and forward from the condyle to the angle, which is frequently more or less everted.

**The Orbits** (*orbitæ*) (Fig. 334).—The orbits are two quadrilateral pyramidal cavities, situated at the upper and anterior part of the face, their bases being directed forward and lateralward, and their apices backward and medialward, so that their long axes, if continued backward, would meet over the body of the sphenoid. Each presents for examination a **roof**, a **floor**, a **medial** and a **lateral wall**, a **base**, and an **apex**.

The **roof** is concave, directed downward, and slightly forward, and formed in *front* by the orbital plate of the frontal; *behind* by the small wing of the sphenoid. It presents *medially* the **trochlear fovea** for the attachment of the cartilaginous pulley of the Obliquus oculi superior; *laterally*, the **lacrimal fossa** for the lacrimal gland; and *posteriorly*, the suture between the frontal bone and the small wing of the sphenoid.

The **floor** is directed upward and lateralward, and is of less extent than the roof; it is formed chiefly by the orbital surface of the maxilla; in *front* and *laterally*, by the orbital process of the zygomatic bone, and *behind* and *medially*, to a small extent, by the orbital process of the palatine. At its medial angle is the upper



opening of the nasolacrimal canal, immediately to the lateral side of which is a depression for the origin of the *Obliquus oculi inferior*. On its lateral part is the suture between the maxilla and zygomatic bone, and at its posterior part that between the maxilla and the orbital process of the palatine. Running forward near the middle of the floor is the **infraorbital groove**, ending in front in the infra-orbital canal and transmitting the infraorbital nerve and vessels.

The **medial wall** (Fig. 335) is nearly vertical, and is formed from before backward by the frontal process of the maxilla, the lacrimal, the lamina papyracea of the ethmoid, and a small part of the body of the sphenoid in front of the optic foramen. Sometimes the sphenoidal concha forms a small part of this wall (see page 250). It exhibits three vertical sutures, viz., the lacrimomaxillary, lacrimo-ethmoidal, and sphenomaxillary. In front is seen the **lacrimal groove**, which lodges the lacrimal sac, and behind the groove is the **posterior lacrimal crest**, from which




FIG. 335.—Medial wall of left orbit.

the lacrimal part of the *Orbicularis oculi* arises. At the junction of the medial wall and the roof are the frontomaxillary, frontolacrimal, frontoethmoidal, and sphenofrontal sutures. The point of junction of the anterior border of the lacrimal with the frontal is named the **dacryon**. In the frontoethmoidal suture are the **anterior and posterior ethmoidal foramina**, the former transmitting the nasociliary nerve and anterior ethmoidal vessels, the latter the posterior ethmoidal nerve and vessels.

The **lateral wall**, directed medialward and forward, is formed by the orbital process of the zygomatic and the orbital surface of the great wing of the sphenoid; these are united by the sphenozygomatic suture which terminates below at the front end of the inferior orbital fissure. On the orbital process of the zygomatic bone are the orbital tubercle (Whitnall) and the orifices of one or two canals which transmit the branches of the zygomatic nerve. Between the roof and the lateral



wall, near the apex of the orbit, is the **superior orbital fissure**. Through this fissure the oculomotor, the trochlear, the ophthalmic division of the trigeminal, and the abducent nerves enter the orbital cavity, also some filaments from the cavernous plexus of the sympathetic and the orbital branches of the middle meningeal artery. Passing backward through the fissure are the ophthalmic vein and the recurrent branch from the lacrimal artery to the dura mater. The lateral wall and the floor are separated posteriorly by the **inferior orbital fissure** which transmits the maxillary nerve and its zygomatic branch, the infraorbital vessels, and the ascending branches from the sphenopalatine ganglion.

The **base** of the orbit, quadrilateral in shape, is formed *above* by the supra-orbital arch of the frontal bone, in which is the **supraorbital notch** or **foramen** for the passage of the supraorbital vessels and nerve; *below* by the zygomatic bone and maxilla, united by the zygomaticomaxillary suture; laterally by the zygomatic bone and the zygomatic process of the frontal joined by the zygomaticofrontal suture; medially by the frontal bone and the frontal process of the maxilla united by the frontomaxillary suture.

The **apex**, situated at the back of the orbit, corresponds to the optic foramen<sup>1</sup> a short, cylindrical canal, which transmits the optic nerve and ophthalmic artery.

It will thus be seen that there are nine openings communicating with each orbit, viz., the optic foramen, superior and inferior orbital fissures, supraorbital foramen, infraorbital canal, anterior and posterior ethmoidal foramina, zygomatic foramen, and the canal for the nasolacrimal duct.

### THE INTERIOR OF THE SKULL.

In order to study the interior of the skull the skull-cap should be removed by a saw-cut carried around the cranium about the level of the frontal eminences and the upper limits of the squamosal sutures, cutting the occipital bone about 2.5 cm. above the external protuberance.

**Inner Surface of the Skull-cap.**—The inner surface of the skull-cap is concave and presents depressions for the convolutions of the cerebrum, together with numerous furrows for the lodgement of branches of the meningeal vessels. Along the middle line is a longitudinal groove, narrow in front, where it commences at the frontal crest, but broader behind; it lodges the superior sagittal sinus, and its margins afford attachment to the falx cerebri. On either side of it are several depressions for the arachnoid granulations, and at its back part, the openings of the **parietal foramina** when these are present. It is crossed, in front, by the **coronal suture**, and behind by the **lambdoidal**, while the **sagittal** lies in the medial plane between the parietal bones.

**Upper Surface of the Base of the Skull** (Fig. 336).—The upper surface of the base of the skull or floor of the cranial cavity presents three fossæ, called the **anterior**, **middle**, and **posterior cranial fossæ**.

**Anterior Fossa** (*fossa cranii anterior*).—The floor of the anterior fossa is formed by the orbital plates of the frontal, the cribriform plate of the ethmoid, and the small wings and front part of the body of the sphenoid; it is limited behind by the posterior borders of the small wings of the sphenoid and by the anterior margin of the chiasmatic groove. It is traversed by the **frontoethmoidal**, **sphenoethmoidal**, and **sphenofrontal sutures**. Its lateral portions roof in the orbital cavities and support the frontal lobes of the cerebrum; they are convex and marked by depressions for the brain convolutions, and grooves for branches of the meningeal vessels.

<sup>1</sup> Some anatomists describe the apex of the orbit as corresponding with the medial end of the superior orbital fissure. It seems better, however, to adopt the statement in the text, since the ocular muscles take origin around the optic foramen, and diverge from it to the bulb of the eye.

The central portion corresponds with the roof of the nasal cavity, and is markedly depressed on either side of the crista galli. It presents, in and near the median




FIG. 336.—Base of the skull. Upper surface.

line, from before backward, the commencement of the **frontal crest** for the attachment of the **falx cerebri**; the **foramen cecum**, between the frontal bone and the crista galli of the ethmoid, which usually transmits a small vein from the nasal cavity

to the superior sagittal sinus; behind the foramen cecum, the **crista galli**, the free margin of which affords attachment to the falx cerebri; on either side of the crista galli, the **olfactory groove** formed by the cribriform plate, which supports the olfactory bulb and presents foramina for the transmission of the olfactory nerves, and in front a slit-like opening for the nasociliary nerve. Lateral to either olfactory groove are the internal openings of the **anterior and posterior ethmoidal foramina**; the anterior, situated about the middle of the lateral margin of the olfactory groove, transmits the anterior ethmoidal vessels and the nasociliary nerve; the nerve runs in a groove along the lateral edge of the cribriform plate to the slit-like opening above mentioned; the posterior ethmoidal foramen opens at the back part of this margin under cover of the projecting lamina of the sphenoid, and transmits the posterior ethmoidal vessels and nerve. Farther back in the middle line is the **ethmoidal spine**, bounded behind by a slight elevation separating two shallow longitudinal grooves which support the olfactory lobes. Behind this is the anterior margin of the chiasmatic groove, running lateralward on either side to the upper margin of the optic foramen.

**The Middle Fossa** (*fossa cranii media*).—The middle fossa, deeper than the preceding, is narrow in the middle, and wide at the sides of the skull. It is bounded in *front* by the posterior margins of the small wings of the sphenoid, the anterior clinoid processes, and the ridge forming the anterior margin of the chiasmatic groove; *behind*, by the superior angles of the petrous portions of the temporals and the dorsum sellae; *laterally* by the temporal squamæ, sphenoidal angles of the parietals, and great wings of the sphenoid. It is traversed by the **squamosal, sphenoparietal, sphenosquamosal, and sphenopetrosal sutures**.

The middle part of the fossa presents, in *front*, the **chiasmatic groove** and **tuberculum sellae**; the chiasmatic groove ends on either side at the **optic foramen**, which transmits the optic nerve and ophthalmic artery to the orbital cavity. Behind the optic foramen the **anterior clinoid process** is directed backward and medialward and gives attachment to the tentorium cerebelli. Behind the tuberculum sellae is a deep depression, the **sella turcica**, containing the **fossa hypophyseos**, which lodges the hypophysis, and presents on its anterior wall the **middle clinoid processes**. The sella turcica is bounded posteriorly by a quadrilateral plate of bone, the **dorsum sellae**, the upper angles of which are surmounted by the **posterior clinoid processes**: these afford attachment to the tentorium cerebelli, and below each is a notch for the abducent nerve. On either side of the sella turcica is the **carotid groove**, which is broad, shallow, and curved somewhat like the italic letter *f*. It begins behind at the foramen lacerum, and ends on the medial side of the anterior clinoid process, where it is sometimes converted into a foramen (*carotico-clinoid*) by the union of the anterior with the middle clinoid process; posteriorly, it is bounded laterally by the **lingula**. This groove lodges the cavernous sinus and the internal carotid artery, the latter being surrounded by a plexus of sympathetic nerves.

The lateral parts of the middle fossa are of considerable depth, and support the temporal lobes of the brain. They are marked by depressions for the brain convolutions and traversed by furrows for the anterior and posterior branches of the middle meningeal vessels. These furrows begin near the foramen spinosum, and the anterior runs forward and upward to the sphenoidal angle of the parietal, where it is sometimes converted into a bony canal; the posterior runs lateralward and backward across the temporal squama and passes on to the parietal near the middle of its lower border. The following apertures are also to be seen. In front is the **superior orbital fissure**, bounded above by the small wing, below, by the great wing, and medially, by the body of the sphenoid; it is usually completed laterally by the orbital plate of the frontal bone. It transmits to the orbital cavity the oculomotor, the trochlear, the ophthalmic division of the trigeminal, and the abducent nerves, some filaments from the cavernous plexus of the

sympathetic, and the orbital branch of the middle meningeal artery; and from the orbital cavity a recurrent branch from the lacrimar artery to the dura mater, and the ophthalmic veins. Behind the medial end of the superior orbital fissure is the **foramen rotundum**, for the passage of the maxillary nerve. Behind and lateral to the foramen rotundum is the **foramen ovale**, which transmits the mandibular nerve, the accessory meningeal artery, and the lesser superficial petrosal nerve.<sup>1</sup> Medial to the foramen ovale is the **foramen Vesalii**, which varies in size in different individuals, and is often absent; when present, it opens below at the lateral side of the scaphoid fossa, and transmits a small vein. Lateral to the foramen ovale is the **foramen spinosum**, for the passage of the middle meningeal vessels, and a recurrent branch from the mandibular nerve. Medial to the foramen ovale is the **foramen lacerum**; in the recent state the lower part of this aperture is filled up by a layer of fibrocartilage, while its upper and inner parts transmit the internal carotid artery surrounded by a plexus of sympathetic nerves. The nerve of the pterygoid canal and a meningeal branch from the ascending pharyngeal artery pierce the layer of fibrocartilage. On the anterior surface of the petrous portion of the temporal bone are seen the eminence caused by the projection of the superior semicircular canal; in front of and a little lateral to this a depression corresponding to the roof of the tympanic cavity; the groove leading to the **hiatus of the facial canal**, for the transmission of the greater superficial petrosal nerve and the petrosal branch of the middle meningeal artery; beneath it, the smaller groove, for the passage of the lesser superficial petrosal nerve; and, near the apex of the bone, the depression for the semilunar ganglion and the orifice of the carotid canal.

**The Posterior Fossa** (*fossa cranii posterior*).—The posterior fossa is the largest and deepest of the three. It is formed by the dorsum sellae and clivus of the sphenoid, the occipital, the petrous and mastoid portions of the temporals, and the mastoid angles of the parietal bones; it is crossed by the **occipitomastoid** and the **parietomastoid sutures**, and lodges the cerebellum, pons, and medulla oblongata. It is separated from the middle fossa in and near the median line by the dorsum sellae of the sphenoid and on either side by the superior angle of the petrous portion of the temporal bone. This angle gives attachment to the tentorium cerebelli, is grooved for the superior petrosal sinus, and presents at its medial end a notch upon which the trigeminal nerve rests. The fossa is limited behind by the grooves for the transverse sinuses. In its centre is the **foramen magnum**, on either side of which is a rough tubercle for the attachment of the alar ligaments; a little above this tubercle is the canal, which transmits the hypoglossal nerve and a meningeal branch from the ascending pharyngeal artery. In front of the foramen magnum the basilar portion of the occipital and the posterior part of the body of the sphenoid form a grooved surface which supports the medulla oblongata and pons; in the young skull these bones are joined by a synchondrosis. This grooved surface is separated on either side from the petrous portion of the temporal by the **petro-occipital fissure**, which is occupied in the recent state by a plate of cartilage; the fissure is continuous behind with the jugular foramen, and its margins are grooved for the inferior petrosal sinus. The **jugular foramen** is situated between the lateral part of the occipital and the petrous part of the temporal. The anterior portion of this foramen transmits the inferior petrosal sinus; the posterior portion, the transverse sinus and some meningeal branches from the occipital and ascending pharyngeal arteries; and the intermediate portion, the glossopharyngeal, vagus, and accessory nerves. Above the jugular foramen is the **internal acoustic meatus**, for the facial and acoustic nerves and internal auditory artery; behind and lateral to this is the slit-like opening leading into the aqueductus vestibuli, which lodges the ductus endolymphaticus; while between these, and near the superior angle of

<sup>1</sup> See footnote, page 248.

the petrous portion, is a small triangular depression, the remains of the fossa subarcuata, which lodges a process of the dura mater and occasionally transmits a small vein. Behind the foramen magnum are the **inferior occipital fossæ**, which support the hemispheres of the cerebellum, separated from one another by the **internal occipital crest**, which serves for the attachment of the falx cerebelli, and lodges the occipital sinus. The posterior fossæ are surmounted by the deep grooves for the **transverse sinuses**. Each of these channels, in its passage to the jugular foramen, grooves the occipital, the mastoid angle of the parietal, the mastoid portion of the temporal, and the jugular process of the occipital, and ends at the back part of the jugular foramen. Where this sinus grooves the mastoid portion of the temporal, the orifice of the **mastoid foramen** may be seen; and, just previous to its termination, the **condyloid canal** opens into it; neither opening is constant.




FIG. 337.—Medial wall of left nasal fossa.

**The Nasal Cavity** (*cavum nasi*; *nasal fossa*).—The nasal cavities are two irregular spaces, situated one on either side of the middle line of the face, extending from the base of the cranium to the roof of the mouth, and separated from each other by a thin vertical septum. They open on the face through the pear-shaped **anterior nasal aperture**, and their posterior openings or **choanæ** communicate, in the recent state, with the nasal part of the pharynx. They are much narrower above than below, and in the middle than at their anterior or posterior openings: their depth, which is considerable, is greatest in the middle. They communicate with the frontal, ethmoidal, sphenoidal, and maxillary sinuses. Each cavity is bounded by a **roof**, a **floor**, a **medial** and a **lateral wall**.

The **roof** (Figs. 337, 338) is horizontal in its central part, but slopes downward in front and behind; it is formed in *front* by the nasal bone and the spine of the frontal; in the *middle*, by the cribriform plate of the ethmoid; and *behind*, by the body of the sphenoid, the sphenoidal concha, the ala of the vomer and the sphenoidal process of the palatine bone. In the cribriform plate of the ethmoid



are the foramina for the olfactory nerves, and on the posterior part of the roof is the opening into the sphenoidal sinus.

The **floor** is flattened from before backward and concave from side to side. It is formed by the palatine process of the maxilla and the horizontal part of the palatine bone; near its anterior end is the opening of the incisive canal.

The **medial wall** (*septum nasi*) (Fig. 337), is frequently deflected to one or other side, more often to the left than to the right. It is formed, in *front*, by the crest of the nasal bones and frontal spine; in the *middle*, by the perpendicular plate of the ethmoid; *behind*, by the vomer and the rostrum of the sphenoid; *below*, by the crest of the maxillæ and palatine bones. It presents, in front, a large, *triangular notch*, which receives the cartilage of the septum; and behind, the *free edge* of the vomer. Its surface is marked by numerous furrows for vessels and nerves and by the grooves for the nasopalatine nerve, and is traversed by sutures connecting the bones of which it is formed.




FIG. 338.—Roof, floor, and lateral wall of left nasal cavity.

The **lateral wall** (Fig. 338) is formed, in front, by the frontal process of the maxilla and by the lacrimal bone; in the middle, by the ethmoid, maxilla, and inferior nasal concha; behind, by the vertical plate of the palatine bone, and the medial pterygoid plate of the sphenoid. On this wall are three irregular antero-posterior passages, termed the superior, middle, and inferior meatuses of the nose. The **superior meatus**, the smallest of the three, occupies the middle third of the lateral wall. It lies between the superior and middle nasal conchæ; the **spheno-palatine foramen** opens into it behind, and the **posterior ethmoidal cells** in front. The sphenoidal sinus opens into a recess, the **sphenoethmoidal recess**, which is placed above and behind the superior concha. The **middle meatus** is situated between the middle and inferior conchæ, and extends from the anterior to the posterior end of the latter. The lateral wall of this meatus can be satisfactorily studied only after the removal of the middle concha. On it is a curved fissure, the **hiatus semilunaris**,



limited below by the edge of the uncinat process of the ethmoid and above by an elevation named the **bullæ ethmoidalis**; the middle ethmoidal cells are contained within this bullæ and open on or near to it. Through the hiatus semilunaris the meatus communicates with a curved passage termed the **infundibulum**, which communicates in front with the anterior ethmoidal cells and in rather more than fifty per cent. of skulls is continued upward as the **frontonasal duct** into the frontal air-sinus; when this continuity fails, the frontonasal duct opens directly into the anterior part of the meatus. Below the bullæ ethmoidalis and hidden by the uncinat process of the ethmoid is the opening of the maxillary sinus (**ostium maxillare**); an accessory opening is frequently present above the posterior part of the inferior nasal concha. The **inferior meatus**, the largest of the three, is the space between the inferior concha and the floor of the nasal cavity. It extends almost the entire length of the lateral wall of the nose, is broader in front than behind, and presents anteriorly the lower orifice of the **nasolacrimal canal**.

The **Anterior Nasal Aperture** (Fig. 334) is a heart-shaped or pyriform opening, whose long axis is vertical, and narrow end upward; in the recent state it is much contracted by the lateral and alar cartilages of the nose. It is bounded *above* by the inferior borders of the nasal bones; *laterally* by the thin, sharp margins which separate the anterior from the nasal surfaces of the maxillæ; and *below* by the same borders, where they curve medialward to join each other at the anterior nasal spine.

The **choanæ** are each bounded *above* by the under surface of the body of the sphenoid and ala of the vomer; *below*, by the posterior border of the horizontal part of the palatine bone; *laterally*, by the medial pterygoid plate; they are separated from each other by the posterior border of the vomer.

#### DIFFERENCES IN THE SKULL DUE TO AGE.

**At birth** the skull is large in proportion to the other parts of the skeleton, but its facial portion is small, and equals only about one-eighth of the bulk of the cranium as compared with one-half in the adult. The frontal and parietal eminences are prominent, and the greatest width of the skull is at the level of the latter; on the other hand, the glabella, superciliary arches, and mastoid processes are not developed. Ossification of the skull bones is not completed, and many of them, *e. g.*, the occipital, temporals, sphenoid, frontal, and mandible, consist of more than one piece. Unossified membranous intervals, termed **fontanelles**, are seen at the angles of the parietal bones; these fontanelles are six in number: two, an anterior and a posterior, are situated in the middle line, and two, an antero-lateral and a postero-lateral, on either side.




FIG. 339.—Skull at birth showing anterior and posterior fontanelles.




FIG. 340.—The lateral fontanelles.

The **anterior** or **bregmatic fontanelle** (Fig. 339) is the largest, and is placed at the junction of the sagittal, coronal, and frontal sutures; it is lozenge-shaped, and measures about 4 cm. in its antero-posterior and 2.5 cm. in its transverse diameter. The **posterior fontanelle** is triangular

in form and is situated at the junction of the sagittal and lambdoidal sutures. The *lateral fontanelles* (Fig. 340) are small, irregular in shape, and correspond respectively with the sphenoidal and mastoid angles of the parietal bones. An additional fontanelle is sometimes seen in the sagittal suture at the region of the obelion. The fontanelles are usually closed by the growth and extension of the bones which surround them, but sometimes they are the sites of separate ossific centres which develop into sutural bones. The posterior and lateral fontanelles are obliterated within a month or two after birth, but the anterior is not completely closed until about the middle of the second year.

The smallness of the face at birth is mainly accounted for by the rudimentary condition of the maxillæ and mandible, the non-eruption of the teeth, and the small size of the maxillary air sinuses and nasal cavities. At birth the nasal cavities lie almost entirely between the orbits, and the lower border of the anterior nasal aperture is only a little below the level of the orbital floor. With the eruption of the deciduous teeth there is an enlargement of the face and jaws, and these changes are still more marked after the second dentition.

The skull grows rapidly from birth to the seventh year, by which time the foramen magnum and petrous parts of the temporals have reached their full size and the orbital cavities are only a little smaller than those of the adult. Growth is slow from the seventh year until the approach of puberty, when a second period of activity occurs: this results in an increase in all directions, but it is especially marked in the frontal and facial regions, where it is associated with the development of the air sinuses.

Obliteration of the sutures of the vault of the skull takes place as age advances. This process may commence between the ages of thirty and forty, and is first seen on the inner surface, and some ten years later on the outer surface of the skull. The dates given are, however, only approximate, as it is impossible to state with anything like accuracy the time at which the sutures are closed. Obliteration usually occurs first in the posterior part of the sagittal suture, next in the coronal, and then in the lambdoidal.

In old age the skull generally becomes thinner and lighter, but in a small proportion of cases it increases in thickness and weight, owing to an hypertrophy of the inner table. The most striking feature of the old skull is the diminution in the size of the maxillæ and mandible consequent on the loss of the teeth and the absorption of the alveolar processes. This is associated with a marked reduction in the vertical measurement of the face and with an alteration in the angles of the mandible.

#### SEXUAL DIFFERENCES IN THE SKULL.

Until the age of puberty there is little difference between the skull of the female and that of the male. The skull of an adult female is, as a rule, lighter and smaller, and its cranial capacity about 10 per cent. less, than that of the male. Its walls are thinner and its muscular ridges less strongly marked; the glabella, superciliary arches, and mastoid processes are less prominent, and the corresponding air sinuses are small or rudimentary. The upper margin of the orbit is sharp, the forehead vertical, the frontal and parietal eminences prominent, and the vault somewhat flattened. The contour of the face is more rounded, the facial bones are smoother, and the maxillæ and mandible and their contained teeth smaller. From what has been said it will be seen that more of the infantile characteristics are retained in the skull of the adult female than in that of the adult male. A well-marked male or female skull can easily be recognized as such, but in some cases the respective characteristics are so indistinct that the determination of the sex may be difficult or impossible.

#### CRANIOLOGY.

Skulls vary in size and shape, and the term *craniology* is applied to the study of these variations. The capacity of the cranial cavity constitutes a good index of the size of the brain which it contained, and is most conveniently arrived at by filling the cavity with shot and measuring the contents in a graduated vessel. Skulls may be classified according to their capacities as follows:

1. *Microcephalic*, with a capacity of less than 1350 c.cm.—*e. g.*, those of native Australians and Andaman Islanders.
2. *Mesocephalic*, with a capacity of from 1350 c.cm. to 1450 c.cm.—*e. g.*, those of African negroes and Chinese.
3. *Megacephalic*, with a capacity of over 1450 c.cm.—*e. g.*, those of Europeans, Japanese, and Eskimos.

In comparing the shape of one skull with that of another it is necessary to adopt some definite position in which the skulls should be placed during the process of examination. They should be so placed that a line carried through the lower margin of the orbit and upper margin of the external acoustic meatus is in the horizontal plane. The normæ of one skull can then be compared with those of another, and the differences in contour and surface form noted. Further,

it is necessary that the various linear measurements used to determine the shape of the skull should be made between definite and easily localized points on its surface. The principal points may be divided into two groups: (1) those in the median plane, and (2) those on either side of it.

**The Points in the Median Plane** are the:

*Mental Point.* The most prominent point of the chin.

*Alveolar Point* or *Prosthion.* The central point of the anterior margin of the upper alveolar arch.

*Subnasal Point.* The middle of the lower border of the anterior nasal aperture, at the base of the anterior nasal spine.

*Nasion.* The central point of the frontonasal suture.

*Glabella.* The point in the middle line at the level of the superciliary arches.

*Ophryon.* The point in the middle line of the forehead at the level where the temporal lines most nearly approach each other.

*Bregma.* The meeting point of the coronal and sagittal sutures.

*Obelion.* A point in the sagittal suture on a level with the parietal foramina.

*Lambda.* The point of junction of the sagittal and lambdoidal sutures.

*Occipital Point.* The point in the middle line of the occipital bone farthest from the glabella.

*Inion.* The external occipital protuberance.

*Opisthion.* The mid-point of the posterior margin of the foramen magnum.

*Basion.* The mid-point of the anterior margin of the foramen magnum.

**The Points on Either Side of the Median Plane** are the:

*Gonion.* The outer margin of the angle of the mandible.

*Dacryon.* The point of union of the antero-superior angle of the lacrimal with the frontal bone and the frontal process of the maxilla.

*Stephanion.* The point where the temporal line intersects the coronal suture.

*Pterion.* The point where the great wing of the sphenoid joins the sphenoidal angle of the parietal.

*Auricular Point.* The centre of the orifice of the external acoustic meatus.

*Asterion.* The point of meeting of the lambdoidal, mastooccipital, and mastoparietal sutures.

The *horizontal circumference* of the cranium is measured in a plane passing through the glabella (Turner) or the ophryon (Flower) in front, and the occipital point behind; it averages about 50 cm. in the female and 52.5 cm. in the male.

The *occipitofrontal* or *longitudinal arc* is measured from the nasion over the middle line of the vertex to the opisthion: while the *basinasal length* is the distance between the basion and the nasion. These two measurements, plus the antero-posterior diameter of the foramen magnum, represent the *vertical circumference* of the cranium.

The *length* is measured from the glabella to the occipital point, while the *breadth* or greatest transverse diameter is usually found near the external acoustic meatus. The proportion of breadth to length  $\frac{(\text{breadth} \times 100)}{\text{length}}$  is termed the *cephalic index* or *index of breadth*.

The *height* is usually measured from the basion to the bregma, and the proportion of height to length  $\frac{(\text{height} \times 100)}{\text{length}}$  constitutes the *vertical* or *height index*.

In studying the face the principal points to be noticed are the proportion of its length and breadth, the shape of the orbits and of the anterior nasal aperture, and the degree of projection of the jaws.

The *length of the face* may be measured from the ophryon or nasion to the chin, or, if the mandible be wanting, to the alveolar point; while its *width* is represented by the distance between the zygomatic arches. By comparing the length with the width of the face, skulls may be divided into two groups; *dolichofacial* or *leptoprosop*e (long faced) and *brachyfacial* or *chemoprosop*e (short faced).

The *orbital index* signifies the proportion which the orbital height bears to the orbital width, thus:

$$\frac{\text{orbital height} \times 100}{\text{orbital width}}$$

The *nasal index* expresses the proportion which the width of the anterior nasal aperture bears to the height of the nose, the latter being measured from the nasion to the lower margin of the nasal aperture, thus:

$$\frac{\text{nasal width} \times 100}{\text{nasal height}}$$

The degree of projection of the jaws is determined by the *gnathic* or *alveolar index*, which represents the proportion between the basialveolar and basinasal lengths, thus:

$$\frac{\text{basialveolar length} \times 100}{\text{basinasal length}}$$

The following table, modified from that given by Duckworth,<sup>1</sup> illustrates how these different indices may be utilized in the classification of skulls:

Index.	Classification.	Nomenclature.	Examples.
1. Cephalic	Below 75 Between 75 and 80 Above 80	Dolichocephalic Mesaticephalic Brachycephalic	Kaffirs and Native Australians. Europeans and Chinese. Mongolians and Andamans.
2. Orbital	Below 84 Between 84 and 89 Above 89	Microseme Mesoseme Megaseme	Tasmanians and Native Australians. Europeans. Chinese and Polynesians.
3. Nasal	Below 48 Between 48 and 53 Above 53	Leptorhine Mesorhine Platyrrhine	Europeans. Japanese and Chinese. Negroes and Native Australians.
4. Gnathic	Below 98 Between 98 and 103 Above 103	Orthognathous Mesognathous Prognathous	Europeans. Chinese and Japanese. Native Australians.

**Applied Anatomy.**—Occasionally a protrusion of the brain or its membranes may take place through one of the sutures, owing to non-closure. When the protrusion consists of membranes only, and is filled with cerebrospinal fluid, it is called a *meningocele*; when it consists of brain as well as membranes, it is termed an *encephalocele*. These malformations are usually found in the middle line, and most frequently at the back of the head, the protrusion taking place between the centres of ossification of the occipital squama (see p. 231). They generally occur through the upper part of the vertical fissure, which is the last to close, but not uncommonly through the lower part, when the foramen magnum may be incomplete. More rarely these protrusions are met with in other situations, as in the sagittal, lambdoidal, and other sutures, or through abnormal gaps at the sides or base of the skull.

The chief function of the skull is to protect the brain, and therefore those portions of the skull which are most exposed to external violence are thicker than those which are shielded from injury by overlying muscles. Thus, the skull-cap is thick and dense, whereas the temporal squamæ, being protected by the temporales muscles, and the inferior occipital fossæ, being shielded by the muscles at the back of the neck, are thin and fragile. Fracture of the skull is further prevented by its elasticity, its rounded shape, and its construction of a number of secondary elastic arches, each made up of a single bone. The manner in which vibrations are transmitted through the bones of the skull is also of importance as regards its protective mechanism, at all events as far as the base is concerned. In the vault, the bones being of a fairly equal thickness and density, vibrations are transmitted in a uniform manner in all directions, but in the base, owing to the varying thickness and density of the bones, this is not so; and therefore in this situation there are special buttresses which serve to carry the vibrations in certain definite directions. At the front of the skull, on either side, is the ridge which separates the anterior from the middle fossa of the base; and behind, the ridge or buttress which separates the middle from the posterior fossa; and if any violence is applied to the vault, the vibrations would be carried along these buttresses to the sella turcica, where they meet. This part has been termed the "centre of resistance," and here there is a special protective mechanism to guard the brain. The subarachnoid cavity at the base of the brain is dilated, and the cerebrospinal fluid which fills it acts as a water cushion to shield the brain from injury. In like manner, when violence is applied to the base of the skull, as in falls upon the feet, the vibrations are carried backward through the occipital crest, and forward through the basilar part of the occipital and body of the sphenoid to the vault of the skull.

Fractures of the skull are best considered as affecting either the vault or the base. Fractures of the vault generally involve the whole thickness of the bone; but sometimes the inner table alone is fractured, and portions of it driven inward. As a rule, in fractures of the skull, the inner table is more splintered and comminuted than the outer, and this is due to several causes. It is thinner and more brittle; the force of the violence as it passes inward becomes broken up, and is more diffused by the time it reaches the inner table; the bone being in the form of an arch bends as a whole and spreads out, and thus presses the particles together on the convex surface of the arch, i. e., the outer table, and forces them asunder on the concave surface or inner table; and, lastly, there is nothing firm under the inner table to support it and oppose the force. Fractures of the vault may be either simple, or starred and comminuted, and the fragments may be depressed or elevated. Cases of fracture with elevation of the fractured portion are uncommon, and can only be produced by direct wound. In comminuted fracture, a portion of the skull is

<sup>1</sup> *Morphology and Anthropology*, by W. L. H. Duckworth, M.A., Cambridge University Press.

broken into several pieces, the lines of fracture radiating from a centre where the chief impact of the blow was felt; if the fracture is also depressed, a fissure circumscribes the radiating lines, enclosing a portion of the skull. If this area is circular it is termed a "pond" fracture, and has probably been caused by a round instrument, as a life preserver or hammer; if elliptical in shape it is termed a "gutter" fracture, and owes its shape to the instrument which has produced it, as a poker. Fracture of the outer table alone only occurs in the region of the frontal sinuses where the two tables are completely separated.

Fractures of the base of the skull may be produced by *indirect* or *direct* violence. I. In cases of the former class the violence is applied to the vertex or some part of the cranial convexity, as when a person falls from a height on to his head and a fracture of the base results. The mechanism of this form of fracture was formerly explained by the doctrine of *contre-coup*, i. e., that the force was transmitted from one side of the skull to the other; but this view is no longer held, and there are at the present day two theories as to the mode of causation of these fractures. (a) According to Aran's theory of *irradiation* all fractures of the base are produced by a fissure, which starts from the point of injury and radiates to the base. There can be little doubt that many cases of fracture of the base, especially of the middle fossæ, are caused in this way, but it is insufficient to explain all, since instances have been met with of fracture of the base of the skull in which there has been no fracture of the vault. (b) To explain these cases, another theory, known as the *compression* or *bursting* theory, has been suggested. If a hollow, elastic sphere is compressed from above downward, it will bulge laterally, and, if the compression is sufficient, it will eventually burst in the situation where it bulges. Now, the skull is an elastic sphere, and when compression is applied to it, its diameter will be reduced along the line of greatest pressure and will therefore be increased in other directions, and may increase to such an extent that bursting occurs. In a hollow elastic sphere of uniform thickness, the bulging and subsequent bursting take place at the equatorial line midway between the two points of compression; but the skull is not of uniform thickness, and therefore the bulging and subsequent bursting take place at the weakest part.

II. Direct violence may be applied to the base of the skull in several different ways: by the impact of the vertebral column against the condyles of the occipital bone, in falls on the buttocks or feet; by the condyle of the mandible being driven against the mandibular fossa, in blows or falls on the chin; by the thrusting of a pointed instrument through the orbit or nose; by gunshot wounds through the mouth; and by a fall or a stab on the back of the head.

In the majority of cases the fracture is compound. The most common place for fracture of the base to occur is through the middle fossa, and here the fissure usually takes a fairly definite course. Starting from the point struck, which is generally somewhere in the neighborhood of the parietal eminence, it runs downward through the parietal and the temporal squama and across the petrous portion, frequently traversing and implicating the internal acoustic meatus, to the foramen lacerum. From this it may pass across the body of the sphenoid, through the sella turcica, to the foramen lacerum of the other side, and may indeed travel around the whole cranium, so as to completely separate the anterior from the posterior part. The course of the fracture explains the symptoms to which fracture in this region may give rise: thus, if the fissure pass across the internal acoustic meatus, injury to the facial and acoustic nerves may result, with consequent facial paralysis and deafness; or the tubular prolongation of the arachnoid around these nerves in the meatus may be torn and thus permit of the escape of the cerebrospinal fluid should there be a communication between the internal ear and the tympanic cavity together with rupture of the tympanic membrane, as is frequently the case: again, if the fissure pass across the sella turcica and the mucoperiosteum covering the under surface of the body of the sphenoid is torn, blood will find its way into the pharynx and be swallowed, and after a time vomiting of blood will result. Fractures of the anterior fossa, involving the bones forming the roof of the orbit and nasal cavity, are generally the result of blows on the forehead; but fracture of the cribriform plate of the ethmoid may be a complication of fracture of the nasal bone. When the fracture implicates the roof of the orbit, the blood finds its way into this cavity, and, travelling forward, appears as a subconjunctival ecchymosis. If the roof of the nasal cavity be fractured, the blood escapes from the nose. In rare cases there may be also escape of cerebrospinal fluid from the nose, should the dura mater and arachnoid have been torn. In fractures of the posterior fossa, extravasation of blood may appear at the nape of the neck, beneath the muscles attached to the superior nuchal line of the occipital bone.

*Diseases of the Skull.*—An inflammatory condition affecting the bones and the pericranium together is generally caused by septic infection either of a scalp wound exposing and bruising the bone, or of a compound fracture, and is termed *septic osteomyelitis*. Occasionally it may occur independently of injury, and then follows the same course, and is due to the same causes as acute infective osteomyelitis in the long bones.

The most common chronic disease of the skull is due to syphilis. In *acquired syphilis* the disease usually occurs as *nodes*, which arise most commonly in the pericranium, but may also arise in the diploë, or more rarely on the inner surface of the skull. The formation of *gummata* under the periosteum generally leads to *caries*, which may be either limited, if the gumma is

localized, or widespread if the gumma is diffuse. The caries is often complicated by *necrosis*, for a condition of sclerosis is frequently set up in the surrounding bone, and the vessels in the Haversian canals become compressed and the vitality of the bone is interfered with; hence we often find a central necrosing area surrounded by a zone of caries. Large carious sequestra may be thrown off after prolonged suppuration, leaving considerable areas of the dura mater exposed. A common result of syphilitic disease of the skull is the production of large hard masses of bone on its surface, which give it a tuberculated appearance; in other cases, the skull presents a curious worm-eaten appearance; this is due to the fact that the osteogenetic powers of the pericranium are small and the formation of bone on the surface slight. In *hereditary syphilis*, in addition to the formation of gummata, which are usually of the subperiosteal variety, atrophic or hypertrophic changes may take place. In the atrophic cases the bone becomes abnormally thin, or even perforated. In the hypertrophic cases, a deposit of porous bone takes place around the anterior fontanelle; these deposits are separated by the coronal and sagittal sutures and are known as *Parrot's nodes*; such a skull has received the name of *natiform*, from its fancied resemblance to the buttocks.

Hypertrophic changes also occur in the skull in *ostitis deformans*, *acromegaly*, *leontiasis ossea*, and in *rickets*. In rickety cases the skull becomes enlarged from the formation of periosteal outgrowths of soft tissue on the outer side of the skull. These deposits are very rich in blood-vessels, and occur between the ridges of the cranial bones and their centres of ossification, and are symmetrically arranged—often about the anterior fontanelle. The anterior fontanelle itself, instead of closing between the eighteenth and twenty-fourth months, as it normally does, remains patent in rickets until the third or even the sixth year. The general shape of the skull alters. The forehead is high and square, with prominent frontal eminences, and the head tends to be cubical or box-shaped; the enlargement of the head in rickets appears to be greater than it really is because the development of the facial bones is retarded. The base of the nose may appear sunken, from retarded development of the basis cranii. In marked cases of rickets these changes in the shape of the skull are permanent. In congenital hydrocephalus, or enlargement of the head due to the presence of excess of fluid in the ventricles of the brain, the cranium becomes globular, and its bones are thin and atrophic. They are often widely separated, the intervening fontanelles being much enlarged and partially filled in by numerous sutural bones; the atrophy of the cranium and brain may be so extreme that the light of a candle may be plainly visible through the whole thickness of the enlarged head.

The tympanic antrum, situated in the mastoid portion of the temporal bone, is often the seat of suppuration as a result of infection extending backward from the tympanic cavity. In such cases, the surgeon has to open the antrum in order to give exit to the pus; this he does by introducing his gouge in the suprameatal triangle (see p. 238). A line is drawn horizontally through the upper border of the bony external acoustic meatus, and a second vertically through the posterior wall of the meatus, and the gouge is applied in the angle where these two lines intersect; if the instrument be introduced at a higher level it will open the middle fossa of the skull. It is to be carried in the direction of the external acoustic meatus—inward, forward, and a little upward—for the distance of from 1 to 1.5 cm., when the antrum will be reached. In some cases of middle-ear trouble, septic thrombosis of the transverse sinus takes place, and it becomes necessary to work backward and explore the sinus.

In connection with the bones of the face a common malformation is *cleft palate*. The cleft usually starts posteriorly, and its most elementary form is a bifid uvula; or the cleft may extend through the soft palate; or the posterior part of the whole of the hard palate may be involved, the cleft extending as far forward as the incisive foramen. In the severest forms, the cleft extends through the alveolus and passes between the incisive or premaxillary bone and the rest of the maxilla; that is to say, between the lateral incisor and canine teeth. In some instances, the cleft runs between the central and lateral incisor teeth; and this has induced some anatomists to believe that the premaxillary bone is developed from two centres (Fig. 341) and not from one, as was stated on p. 262. The medial segment, bearing a central incisor, is called an *endognathion*; the lateral segment, bearing the lateral incisor, is called a *mesognathion*. The cleft may affect one or both sides; if the latter, the central part is frequently displaced forward and remains united to the septum of the nose, the deficiency in the alveolus being complicated with a cleft in the lip (hare-lip). On examining a cleft palate in which the alveolus is not implicated, the cleft will generally appear to be in the median line, but occasionally is unilateral and in some cases bilateral. To understand this it must be borne in mind that three processes are concerned in the formation of the palate—the palatine processes of the two maxillæ, which grow in horizontally and unite in the middle line, and the ethmovomerine process, which grows downward from the base of the skull and frontonasal process to unite with the palatine processes in the middle line. In




FIG. 341.—The premaxilla and its sutures. (After Albrecht.)



those cases where the palatine processes fail to unite with each other and with the medial process, the cleft of the palate is median; where one palatine process unites with the medial septum, the other failing to do so, the cleft in the palate is unilateral. In some cases where the palatine processes fail to meet in the middle, the ethmiovomerine process grows downward between them and thus produces a bilateral cleft. Occasionally there may be a hole in the middle line of the hard palate, the anterior part of the hard and the soft palate being perfect; this is rare, because, as a rule, the union of the various processes progresses from before backward, and therefore the posterior part of the palate is more frequently defective than the anterior.

The bones of the face are sometimes fractured as the result of direct violence. Those most commonly broken are the nasal bones and the mandible; the latter is by far the most frequently fractured of all the facial bones. Fracture of the *nasal* bone is for the most part transverse, and takes place about 1.25 cm. from the free margin. The broken portion may be displaced backward or more generally to one side by the force which produced the lesion. The *zygomatic* bone is probably never broken alone—that is to say, without fracture of some of the other bones of the face. The *zygomatic arch* is occasionally fractured, and when this occurs as a result of direct violence the fragments may be displaced inward. Fractures of the *maxilla* may vary much in degree, from the chipping off of a portion of the alveolar arch, to an extensive comminution of the whole bone from severe violence, as the kick of a horse. The most common situation for a fracture of the *mandible* is in the neighborhood of the canine tooth, as at this spot the bone is weakened by the deep socket for the root of this tooth; it is next most frequently fractured at the angle; then at the symphysis; and finally the neck of the condyle or the coronoid process may be broken. Occasionally a double fracture may occur, one in either half of the bone. The fractures are usually compound, from laceration of the mucous membrane covering the gums. Displacement readily occurs and is difficult to rectify; it results in inequality in the line of the teeth and is commonly due to the muscles attached in the region of the symphysis dragging this portion downward.

The maxilla and the mandible are frequently the seat of necrosis; but the disease more often affects the lower than the upper jaw. It may be the result of periostitis from tooth irritation, injury, or the action of some specific poison, as syphilis, or from salivation by mercury; it sometimes occurs in children after attacks of the exanthematous fevers, and a special form occurs from the action of the fumes of phosphorus in persons engaged in the manufacture of matches. In the vast majority of cases, however, it is of dental origin.

Tumors originate in the jaw bones not infrequently, and may be either innocent or malignant. In the maxilla, cysts may occur in the antrum; or in either jaw in connection with the teeth; those connected with the roots of fully developed teeth are known as dental cysts; those connected with unerupted teeth, dentigerous cysts. Malignant tumors show a marked degree of malignancy when occurring in the maxilla. The results of distention of the walls of the maxillary antrum are given on page 260.

The maxilla sometimes requires removal for tumors or other conditions. In order to remove it, the patient should be placed in the recumbent position, in a good light, with the head and shoulders just raised. The central incisor tooth on the affected side is then extracted. One incision is begun just below the medial canthus of the eye and passes along the side of the nose, around the ala, and down the middle line of the upper lip into the mouth. A second incision is made from the commencement of the first, along the lower border of the orbit as far as the prominence of the zygomatic bone. The flap thus formed is reflected, so as to expose the bone. The periosteum attached along the lower margin of the orbit is now to be incised, and with the handle of the scalpel the periosteum covering the floor of the orbit is raised from the bone; for in all cases it is essential that this fibrous layer should not be removed. The mouth is now widely opened with a gag, and the mucous membrane covering the hard palate incised down to the bone in the middle line, and the soft palate separated from the hard. The surgeon having first separated the ala of the nose from its bony attachment, proceeds to divide the connections of the bone with the other bones of the face. They are (1) the junction with the zygomatic bone, the line of section being carried into the inferior orbital fissure; (2) the frontal process of the maxilla; a small portion of its upper extremity, connected with the nasal bone in front, the lacrimal bone behind, and the frontal bone above, being left; (3) the connection with the opposite maxilla and with the palatine bone in the roof of the mouth. The bone is now firmly grasped with lion-forceps; and by means of a rocking movement upward and downward, the remaining attachments of the orbital plate with the ethmoid, and of the back of the bone with the palatine, are broken through. Occasionally, in removing the maxilla, it will be found that the orbital plate can be saved, and this should always be done if possible. A horizontal saw-cut should then be made just below the infraorbital foramen.

## THE EXTREMITIES.

The **extremities**, or **limbs**, are long, jointed appendages, each of which is connected to the trunk by one end, and is free in the rest of its extent. They are

four in number: an upper pair, connected with the thorax and subservient mainly to prehension; and a lower pair, connected with the vertebral column and intended for support and locomotion. Both pairs are constructed after one common type, but certain differences are observed between the upper and lower, dependent on the peculiar offices they have to perform.

The bones by which the upper and lower limbs are attached to the trunk constitute respectively the shoulder and pelvic girdles. The **shoulder girdle** or **girdle of the superior extremity** is formed by the scapulæ and clavicles, and is imperfect in front and behind. In front, however, it is completed by the upper end of the sternum, with which the medial ends of the clavicles articulate. Behind, it is widely imperfect, the scapulæ being connected to the trunk by muscles only. The **pelvic girdle** or **girdle of the inferior extremity** is formed by the hip bones, which articulate with each other in front, at the symphysis pubis. It is imperfect behind, but the gap is filled in by the upper part of the sacrum. The pelvic girdle, with the sacrum, is a complete ring, massive and comparatively rigid, in marked contrast to the lightness and mobility of the shoulder girdle.

### THE BONES OF THE UPPER EXTREMITY (OSSA EXTREMITATIS SUPERIORIS).

#### The Clavicle (Clavicula; Collar Bone).

The **clavicle** (Figs. 342, 343) forms the anterior portion of the shoulder girdle. It is a long bone, curved somewhat like the italic letter *f*, and placed nearly horizontally at the upper and anterior part of the thorax, immediately above the first rib. It articulates medially with the manubrium sterni, and laterally with the acromion of the scapula.<sup>1</sup> It presents a double curvature, the convexity being directed forward at the sternal end, and the concavity at the scapular end. Its lateral third is flattened from above downward, while its medial two-thirds is of a rounded or prismatic form.




FIG. 342.—Left clavicle. Superior surface.

**Lateral Third.**—The lateral third has two surfaces, an upper and a lower; and two borders, an anterior and a posterior.

**Surface.**—The **upper surface** is flat, rough, and marked by impressions for the attachments of the Deltoides in front, and the Trapezius behind; between these impressions a small portion of the bone is subcutaneous. The **under surface** is flat. At its posterior border, near the point where the prismatic joins with the flattened portion, is a rough eminence, the **coracoid tuberosity** (*conoid tubercle*); this, in the natural position of the bone, surmounts the coracoid process of the

<sup>1</sup> The clavicle acts especially as a fulcrum to enable the muscles to give lateral motion to the arm. It is accordingly absent in those animals whose fore-limbs are used only for progression, but is present for the most part in animals whose anterior extremities are clawed and used for prehension, though in some of them—as, for instance, in a large number of the carnivora—it is merely a rudimentary bone suspended among the muscles, and not articulating with either the scapula or sternum.

scapula, and gives attachment to the conoid ligament. From this tuberosity an oblique ridge, the **oblique** or **trapezoid ridge**, runs forward and lateralward, and afford attachment to the trapezoid ligament.

**Borders.**—The **anterior border** is concave, thin, and rough, and gives attachment to the Deltoides; at its medial part there is frequently a tubercle, the **deltoid tubercle**. The **posterior border** is convex, rough, thicker than the anterior, and gives attachment to the Trapezius.

**Medial Two-thirds.**—The medial two-thirds constitute the prismatic portion of the bone, which is curved so as to be convex in front, concave behind, and is marked by three borders, separating three surfaces.

**Borders.**—The **anterior border** is continuous with the anterior margin of the flat portion. Its lateral part is smooth, and corresponds to the interval between the attachments of the Pectoralis major and Deltoides; its medial part forms the lower boundary of an elliptical surface for the attachment of the clavicular portion of the Pectoralis major, and approaches the posterior border of the bone. The **superior border** is continuous with the posterior margin of the flat portion, and separates the anterior from the posterior surface. Smooth and rounded laterally, it becomes rough toward the medial third for the attachment of the Sternocleidomastoideus, and ends at the upper angle of the sternal extremity. The **posterior** or **subclavian border** separates the posterior from the inferior surface, and extends from the coracoid tuberosity to the costal tuberosity; it forms the posterior boundary of the groove for the Subclavius, and gives attachment to a layer of cervical fascia which envelops the Omohyoideus.

*Articular capsule*

*Articular capsule*




FIG. 343.—Left clavicle. Inferior surface.

**Surfaces.**—The **anterior surface** is included between the superior and anterior borders. Its lateral part looks upward, and is continuous with the superior surface of the flattened portion; it is smooth, convex, and nearly subcutaneous, being covered only by the Platysma. Medially it is divided by a narrow subcutaneous area into two parts: a lower, elliptical in form, and directed forward, for the attachment of the Pectoralis major; and an upper for the attachment of the Sternocleidomastoideus. The **posterior** or **cervical surface** is smooth, and looks backward toward the root of the neck. It is limited, above, by the superior border; below, by the subclavian border; medially, by the margin of the sternal extremity; and laterally, by the coracoid tuberosity. It is concave medio-laterally, and is in relation, by its lower part, with the transverse scapular vessels. This surface, at the junction of the curves of the bone, is also in relation with the brachial plexus of nerves and the subclavian vessels. It gives attachment, near the sternal extremity, to part of the Sternohyoideus; and presents, near the middle, an oblique foramen directed lateralward, which transmits the chief nutrient artery of the bone. Sometimes there are two foramina on the posterior surface, or one on the posterior and another on the inferior surface. The **inferior** or **subclavian surface** is

bounded, in front, by the anterior border; behind, by the subclavian border. It is narrowed medially, but gradually increases in width laterally, and is continuous with the under surface of the flat portion. On its medial part is a broad rough surface, the **costal tuberosity** (*rhomboid impression*), rather more than 2 cm. in length, for the attachment of the costoclavicular ligament. The rest of this surface is occupied by a groove, which gives attachment to the Subclavius; the coracoclavicular fascia, which splits to enclose the muscle, is attached to the margins of the groove. Not infrequently this groove is subdivided longitudinally by a line which gives attachment to the intermuscular septum of the Subclavius.

**The Sternal Extremity** (*extremitas sternalis; internal extremity*).—The sternal extremity of the clavicle is triangular in form, directed medialward, and a little downward and forward; it presents an articular facet, concave from before backward, convex from above downward, which articulates with the manubrium sterni through the intervention of an articular disk. The lower part of the facet is continued on to the inferior surface of the bone as a small semi-oval area for articulation with the cartilage of the first rib. The circumference of the articular surface is rough, for the attachment of numerous ligaments; the upper angle gives attachment to the articular disk.

**The Acromial Extremity** (*extremitas acromialis; outer extremity*).—The acromial extremity presents a small, flattened, oval surface directed obliquely downward, for articulation with the acromion of the scapula. The circumference of the articular facet is rough, especially above, for the attachment of the acromioclavicular ligaments.

In the female, the clavicle is generally shorter, thinner, less curved, and smoother than in the male. In those persons who perform considerable manual labor it becomes thicker and more curved, and its ridges for muscular attachment are prominently marked.

**Structure.**—The clavicle consists of cancellous tissue, enveloped by a compact layer, which is much thicker in the intermediate part than at the extremities of the bone.

**Ossification.**—The clavicle begins to ossify before any other bone in the body; it is ossified from three centres—viz., two primary centres, a medial and a lateral, for the body,<sup>1</sup> which appear during the fifth or sixth week of fetal life; and a secondary centre for the sternal end, which appears about the eighteenth or twentieth year, and unites with the rest of the bone about the twenty-fifth year.

**Applied Anatomy.**—The clavicle is very frequently fractured, since it is much exposed to violence, and is the only bony connection between the upper limb and the trunk, acting as a buttress to keep the point of the shoulder away from the thorax. It is, moreover, slender, and is very superficial. It may be broken by direct or indirect violence. The most common cause is, however, indirect violence, as the result of force applied to the hand or shoulder, and the bone then gives way at the junction of its lateral with its intermediate third, that is to say, at the junction of the two curves, for this is its weakest part. The fracture is generally oblique, and the displacement of the lateral fragment is downward, forward, and medialward. The deformity is mainly due to the weight of the arm acting upon the fragment when the buttress-like action of the bone is gone, assisted by the muscles which pass from the thorax to the upper extremity. The medial fragment, as a rule, is little displaced. Beneath the bone the main vessels of the upper limb and the great nerve cords of the brachial plexus lie on the first rib and are liable to be wounded, especially in fracture from direct violence, when the force of the blow drives the broken ends inward. Fortunately the subclavius intervenes between these structures and the clavicle, and often protects them from injury.

The clavicle is occasionally the seat of sarcomatous tumors, rendering the operation of excision of the entire bone necessary. This is an operation of considerable difficulty and danger. It is best performed by exposing the bone freely, disarticulating at the acromial end, and turning it forward. The removal of the lateral part is comparatively easy, but resection of the medial part is fraught with difficulty, the main danger being the risk of wounding the great veins which are in relation with its deep surface.

Great deformity of the clavicle may be met with in rickets, the natural curvatures of the bone being exaggerated until it takes on an S-shape, and "green-stick" fracture is not uncommonly seen associated therewith.

<sup>1</sup> Mall, *American Journal of Anatomy*, vol. v; Fawcett, *Journal of Anatomy and Physiology*, vol. xlvii.



intervening ridge afford attachment to the Serratus anterior. At the upper part of the fossa is a transverse depression, where the bone appears to be bent on itself along a line at right angles to and passing through the centre of the glenoid cavity, forming a considerable angle, called the **subscapular angle**; this gives greater strength to the body of the bone by its arched form, while the summit of the arch serves to support the spine and acromion.




FIG. 345.—Left scapula. Dorsal surface.

The **dorsal surface** (Fig. 345) is arched from above downward, and is subdivided into two unequal parts by the spine; the portion above the spine is called the **supraspinatous fossa**, and that below it the **infraspinatous fossa**.



The **supraspinatous fossa**, the smaller of the two, is concave, smooth, and broader at its vertebral than at its humeral end; its medial two-thirds give origin to the Supraspinatus.

The **infraspinatous fossa** is much larger than the preceding; toward its vertebral margin a shallow concavity is seen at its upper part; its centre presents a prominent convexity, while near the axillary border is a deep groove which runs from the upper toward the lower part. The medial two-thirds of the fossa give origin to the Infraspinatus; the lateral third is covered by this muscle.

The dorsal surface is marked near the axillary border by an elevated ridge, which runs from the lower part of the glenoid cavity, downward and backward to the vertebral border, about 2.5 cm. above the inferior angle. The ridge serves for the attachment of a fibrous septum, which separates the Infraspinatus from the Teres major and Teres minor. The surface between the ridge and the axillary border is narrow in the upper two-thirds of its extent, and is crossed near its centre by a groove for the passage of the scapular circumflex vessels; it affords attachment to the Teres minor. Its lower third presents a broader, somewhat triangular surface, which gives origin to the Teres major, and over which the Latis-simus dorsi glides; frequently the latter muscle takes origin by a few fibres from this part. The broad and narrow portions above alluded to are separated by an oblique line, which runs from the axillary border, downward and backward, to meet the elevated ridge: to it is attached a fibrous septum which separates the Teres muscles from each other.

**The Spine** (*spina scapulae*).—The spine is a prominent plate of bone, which crosses obliquely the medial four-fifths of the dorsal surface of the scapula at its upper part, and separates the supra- from the infraspinatous fossa. It begins at the vertical border by a smooth, triangular area over which the tendon of insertion of the lower part of the Trapezius glides, and, gradually becoming more elevated, ends in the acromion, which overhangs the shoulder-joint. The spine is triangular, and flattened from above downward, its apex being directed toward the vertebral border. It presents two surfaces and three borders. Its **superior surface** is concave; it assists in forming the supraspinatous fossa, and gives origin to part of the Supraspinatus. Its **inferior surface** forms part of the infraspinatous fossa, gives origin to a portion of the Infraspinatus, and presents near its centre the orifice of a nutrient canal. Of the three borders, the **anterior** is attached to the dorsal surface of the bone; the **posterior**, or **crest of the spine**, is broad, and presents two lips and an intervening rough interval. The Trapezius is attached to the superior lip, and a rough tubercle is generally seen on that portion of the spine which receives the tendon of insertion of the lower part of this muscle. The Deltoideus is attached to the whole length of the inferior lip. The interval between the lips is subcutaneous and partly covered by the tendinous fibres of these muscles. The **lateral border**, or **base**, the shortest of the three, is slightly concave; its edge, thick and round, is continuous above with the under surface of the acromion, below with the neck of the scapula. It forms the medial boundary of the **great scapular notch**, which serves to connect the supra- and infraspinatous fossæ.

**The Acromion**.—The acromion forms the summit of the shoulder, and is a large, somewhat triangular or oblong process, flattened from behind forward, projecting at first lateralward, and then curving forward and upward, so as to overhang the glenoid cavity. Its **superior surface**, directed upward, backward, and lateralward, is convex, rough, and gives attachment to some fibres of the Deltoideus, and in the rest of its extent is subcutaneous. Its **inferior surface** is smooth and concave. Its **lateral border** is thick and irregular, and presents three or four tubercles for the tendinous origins of the Deltoideus. Its **medial border**, shorter than the lateral, is concave, gives attachment to a portion of the Trapezius, and presents about its centre a small, oval surface for articulation with the acromial end of the clavicle.

Its **apex**, which corresponds to the point of meeting of these two borders in front, is thin, and has attached to it the coracoacromial ligament.

**Borders.**—Of the *three* borders of the scapula, the **superior** is the shortest and thinnest; it is concave, and extends from the medial angle to the base of the coracoid process. At its lateral part is a deep, semicircular notch, the **scapular notch**, formed partly by the base of the coracoid process. This notch is converted into a foramen by the superior transverse ligament, and serves for the passage of the suprascapular nerve; sometimes the ligament is ossified. The adjacent part of the superior border affords attachment to the Omohyoideus. The **axillary border** is the thickest of the three. It begins above at the lower margin of the glenoid cavity, and inclines obliquely downward and backward to the inferior angle. Immediately below the glenoid cavity is a rough impression, the **infraglenoid tuberosity**, about 2.5 cm. in length, which gives origin to the long head of the *Triiceps brachii*; in front of this is a longitudinal groove, which extends as far as the lower third of this border, and affords origin to part of the *Subscapularis*. The inferior third is thin and sharp, and serves for the attachment of a few fibres of the *Teres major* behind, and of the *Subscapularis* in front. The **vertebral border** is the longest of the three, and extends from the medial to the inferior angle. It is arched, intermediate in thickness between the superior and the axillary borders, and the portion of it above the spine forms an obtuse angle with the part below. This border presents an anterior and a posterior lip, and an intermediate narrow area. The anterior lip affords attachment to the *Serratus anterior*; the posterior lip, to the *Supraspinatus* above the spine, the *Infraspinatus* below; the area between the two lips, to the *Levator scapulae* above the triangular surface at the commencement of the spine, to the *Rhomboideus minor* on the edge of that surface, and to the *Rhomboideus major* below it; this last is attached by means of a fibrous arch, connected above to the lower part of the triangular surface at the base of the spine, and below to the lower part of the border.

**Angles.**—Of the *three* angles, the **medial**, formed by the junction of the superior and vertebral borders, is thin, smooth, rounded, inclined somewhat lateralward, and gives attachment to a few fibres of the *Levator scapulae*. The **inferior angle**, thick and rough, is formed by the union of the vertebral and axillary borders; its dorsal surface affords attachment to the *Teres major* and frequently to a few fibres of the *Latissimus dorsi*. The **lateral angle** is the thickest part of the bone, and is sometimes called the head of the scapula. On it is a shallow pyriform, articular surface, the **glenoid cavity**, which is directed lateralward and forward and articulates with the head of the humerus; it is broader below than above and its vertical diameter is the longest. The surface is covered with cartilage in the recent state; and its margins, slightly raised, give attachment to a fibrocartilaginous structure, the **glenoidal labrum**, which deepens the cavity. At its apex is a slight elevation, the **supraglenoid tuberosity**, to which the long head of the *Biceps brachii* is attached. The **neck** of the scapula is the slightly constricted portion which surrounds the head; it is more distinct below and behind than above and in front.

**The Coracoid Process** (*processus coracoideus*).—The coracoid process is a thick curved process attached by a broad base to the upper part of the neck of the scapula; it runs at first upward and medialward; then, becoming smaller, it changes its direction, and projects forward and lateralward. The ascending portion, flattened from before backward, presents in front a smooth concave surface, across which the *Subscapularis* passes. The horizontal portion is flattened from above downward; its upper surface is convex and irregular, and gives attachment to the *Pectoralis minor*; its under surface is smooth; its medial and lateral borders are rough; the former gives attachment to the *Pectoralis minor* and the latter to the coracoacromial ligament; the apex is embraced by the conjoined tendon of origin of the

Coracobrachialis and short head of the Biceps brachii and gives attachment to the coracoclavicular fascia. On the medial part of the root of the coracoid process is a rough impression for the attachment of the conoid ligament; and running from it obliquely forward and lateralward, on to the upper surface of the horizontal portion, is an elevated ridge for the attachment of the trapezoid ligament.

**Structure.**—The head, processes, and the thickened parts of the bone, contain cancellous tissue; the rest consists of a thin layer of compact tissue. The central part of the supraspinatous fossa and the upper part of the infraspinatous fossa, but especially the former, are usually so thin as to be semitransparent; occasionally the bone is found wanting in this situation, and the adjacent muscles are separated only by fibrous tissue.

**Ossification** (Fig. 346).—The scapula is ossified from *seven* or more centres: one for the body, two for the coracoid process, two for the acromion, one for the vertebral border, and one for the inferior angle.




FIG. 346.—Plan of ossification of the scapula. From seven centres.

Ossification of the body begins about the second month of fetal life, by the formation of an irregular quadrilateral plate of bone, immediately behind the glenoid cavity. This plate extends so as to form the chief part of the bone, the spine growing up from its dorsal surface about the third month. At birth, a large part of the scapula is osseous, but the glenoid cavity, the coracoid process, the acromion, the vertebral border, and the inferior angle are cartilaginous. From the fifteenth to the eighteenth month after birth, ossification takes place in the middle of the coracoid process, which as a rule becomes joined with the rest of the bone about the fifteenth year. Between the fourteenth and twentieth years, ossification of the remaining parts takes place in quick succession, and usually in the following order; first, in the root of the coracoid process, in the form of a broad scale; secondly, near the base of the acromion; thirdly, in the inferior angle and contiguous part of the vertebral border; fourthly, near the extremity of the acromion; fifthly, in the vertebral border. The base of the acromion is formed by an extension from the spine; the two separate nuclei of the acromion unite, and then join with the extension from the spine. The upper third of the glenoid cavity is ossified from a separate centre (subcoracoid), which makes its appearance between the tenth and eleventh years and joins between the sixteenth and the eighteenth. Further, an epiphysial plate appears for the lower part of the glenoid cavity, while the tip of the

coracoid process frequently presents a separate nucleus. These various epiphyses are joined to the bone by the twenty-fifth year. Failure of bony union between the acromion and spine sometimes occurs, the junction being effected by fibrous tissue, or by an imperfect articulation; in some cases of supposed fracture of the acromion with ligamentous union, it is probable that the detached segment was never united to the rest of the bone.

**Articulations.**—The scapula articulates with the humerus and clavicle.

**Applied Anatomy.**—Fractures of the body of the scapula are rare, owing to the mobility of the bone, the thick layers of muscles by which it is encased, and the elasticity of the ribs on which it rests. Fracture of the neck is also uncommon. The most frequent course of a fracture is from the scapular notch to the infraglenoid tuberosity, and it derives its principal interest from its simulation of a subglenoid dislocation of the humerus. The diagnosis can be made by noting the alteration in the position of the coracoid process. The acromion is more frequently broken than any other part of the bone, and fibrous union is very liable to follow.

The presence of "winged scapulæ" (*scapulæ alatae*) described in thin persons of feeble muscular development in whom the lower angles of the blade bones project unduly, is due partly to abnormal roundness of the thoracic wall ("barrel-shaped chest," p. 226), and partly to weakness and flaccidity of the Latissimus dorsi and Serratus anterior. The shoulders are held low in these subjects, and the clavicles slope downward and forward, carrying with them the scapulæ, which fit ill to the posterior wall of the chest and so tend to project from it.

Tumors of various kinds grow from the scapula. Of the innocent form probably the osteomata are the most common. When an osteoma grows from the venter of the scapula, as it sometimes does, it is of the compact variety, such as usually grows from membrane-formed bones, as the bones of the skull. Sarcomatous tumors sometimes grow from the scapula, and may necessitate removal of the bone, with or without amputation of the upper limb. The bone may be excised by a T-shaped incision, and the flaps being reflected, the removal is commenced from the vertebral border, so that the subscapular vessels which lie along the axillary border are among the last structures divided, and can be readily secured.

### The Humerus (Arm Bone).

The humerus (Figs. 347, 348) is the longest and largest bone of the upper extremity; it is divisible into a **body** and **two extremities**.

**Upper Extremity.**—The upper extremity consists of a large rounded *head* joined to the body by a constricted portion called the **neck**, and two eminences, the **greater** and **lesser tubercles**.

**The Head** (*caput humeri*).—The head, nearly hemispherical in form,<sup>1</sup> is directed upward, medialward, and a little backward, and articulates with the glenoid cavity of the scapula. The circumference of its articular surface is slightly constricted, and is termed the **anatomical neck**, in contradistinction to a constriction below the tubercles called the **surgical neck** which is frequently the seat of fracture. Fracture of the anatomical neck rarely occurs.

The **Anatomical Neck** (*collum anatomicum*) is obliquely directed, forming an obtuse angle with the body. It is best marked in the lower half of its circumference; in the upper half it is represented by a narrow groove separating the head from the tubercles. It affords attachment to the articular capsule of the shoulder-joint, and is perforated by numerous vascular foramina.

**The Greater Tubercle** (*tuberculum majus; greater tuberosity*).—The greater tubercle is situated lateral to the head and lesser tubercle. Its upper surface is rounded and marked by three flat impressions: the highest of these gives insertion to the Supraspinatus; the middle to the Infraspinatus; the lowest one, and the body of the bone for about 2.5 cm. below it, to the Teres minor. The lateral surface of the greater tubercle is convex, rough, and continuous with the lateral surface of the body.

**The Lesser Tubercle** (*tuberculum minus; lesser tuberosity*).—The lesser tubercle, although smaller, is more prominent than the greater: it is situated in front, and

<sup>1</sup> Though the head is nearly hemispherical in form, its margin, as Humphry has shown, is by no means a true circle. Its greatest diameter is, from the top of the intertubercular groove in a direction downward, medialward, and backward. Hence it follows that the greatest elevation of the arm can be obtained by rolling the articular surface in this direction—that is to say, obliquely upward, lateralward, and forward.




FIG. 347.—Left humerus. Anterior view.

is directed medialward and forward. Above and in front it presents an impression for the insertion of the tendon of the Subscapularis.

The tubercles are separated from each other by a deep groove, the **intertubercular groove** (*bicipital groove*), which lodges the long tendon of the Biceps brachii and transmits a branch of the anterior humeral circumflex artery to the shoulder-joint. It runs obliquely downward, and ends near the junction of the upper with the middle third of the bone. In the recent state its upper part is covered with a thin layer of cartilage, lined by a prolongation of the synovial membrane of the shoulder-joint; its lower portion gives insertion to the tendon of the Latissimus dorsi. It is deep and narrow above, and becomes shallow and a little broader as it descends. Its lips are called, respectively, the **crests of the greater and lesser tubercles** (*bicipital ridges*), and form the upper parts of the anterior and medial borders of the body of the bone.

**The Body or Shaft** (*corpus humeri*).—The body is almost cylindrical in the upper half of its extent, prismatic and flattened below, and has three borders and three surfaces.

**Borders.**—The **anterior border** runs from the front of the greater tubercle above to the coracoid fossa below, separating the antero-medial from the antero-lateral surface. Its upper part is a prominent ridge, the crest of the greater tubercle; it serves for the insertion of the tendon of the Pectoralis major. About its centre it forms the anterior boundary of the deltoid tuberosity; below, it is smooth and rounded, affording attachment to the Brachialis.

The **lateral border** runs from the back part of the greater tubercle to the lateral epicondyle, and separates the antero-lateral from the posterior surface. Its upper half is rounded and indistinctly marked, serving for the attachment of the lower part of the insertion of the Teres minor, and below this giving origin to the lateral head of the Triceps brachii; its centre is traversed by a broad but shallow oblique depression, the **radial sulcus** (*musculospiral groove*). Its lower part forms a prominent, rough margin, a little curved from behind forward, the **lateral supracondylar ridge**, which presents an anterior lip for the origin of the Brachioradialis above, and Extensor carpi radialis longus below, a posterior lip for the Triceps brachii, and an **intermediate ridge** for the attachment of the lateral intermuscular septum.




FIG. 348.—Left humerus. Posterior view.



The **medial border** extends from the lesser tubercle to the medial epicondyle. Its upper third consists of a prominent ridge, the **crest of the lesser tubercle**, which gives insertion to the tendon of the *Teres major*. About its centre is a slight impression for the insertion of the *Coracobrachialis*, and just below this is the entrance of the nutrient canal, directed downward; sometimes there is a second nutrient canal at the commencement of the radial sulcus. The inferior third of this border is raised into a slight ridge, the **medial supracondylar ridge**, which becomes very prominent below; it presents an anterior lip for the origins of the *Brachialis* and *Pronator teres*, a posterior lip for the medial head of the *Triceps brachii*, and an intermediate ridge for the attachment of the medial intermuscular septum.

**Surfaces.**—The **antero-lateral surface** is directed lateralward above, where it is smooth, rounded, and covered by the *Deltoides*; forward and lateralward below, where it is slightly concave from above downward, and gives origin to part of the *Brachialis*. About the middle of this surface is a rough, triangular elevation, the **deltoid tuberosity** for the insertion of the *Deltoides*; below this is the **radial sulcus**, directed obliquely from behind, forward, and downward, and transmitting the radial nerve and profunda artery.

The **antero-medial surface**, less extensive than the antero-lateral, is directed medialward above, forward and medialward below; its upper part is narrow, and forms the floor of the intertubercular groove which gives insertion to the tendon of the *Latissimus dorsi*; its middle part is slightly rough for the attachment of some of the fibres of the tendon of insertion of the *Coracobrachialis*; its lower part is smooth, concave from above downward, and gives origin to the *Brachialis*.<sup>1</sup>

The **posterior surface** appears somewhat twisted, so that its upper part is directed a little medialward, its lower part backward and a little lateralward. Nearly the whole of this surface is covered by the lateral and medial heads of the *Triceps brachii*, the former arising above, the latter below the radial sulcus.

**The Lower Extremity.**—The lower extremity is flattened from before backward, and curved slightly forward; it ends below in a broad, articular surface, which is divided into two parts by a slight ridge. Projecting on either side are the lateral and medial epicondyles. The **articular surface** extends a little lower than the epicondyles, and is curved slightly forward; its medial extremity occupies a lower level than the lateral. The lateral portion of this surface consists of a smooth, rounded eminence, named the **capitulum of the humerus**; it articulates with the cup-shaped depression on the head of the radius, and is limited to the front and lower part of the bone. On the medial side of this eminence is a shallow groove, in which is received the medial margin of the head of the radius. Above the front part of the capitulum is a slight depression, the **radial fossa**, which receives the anterior border of the head of the radius, when the forearm is flexed. The medial portion of the articular surface is named the **trochlea**, and presents a deep depression between two well-marked borders; it is convex from before backward, concave from side to side, and occupies the anterior, lower, and posterior parts of the extremity. The lateral border separates it from the groove which articulates with the margin of the head of the radius. The medial border is thicker, of greater length, and consequently more prominent, than the lateral. The grooved portion of the articular surface fits accurately within the semilunar notch of the ulna; it is broader and deeper on the posterior than on the anterior aspect of the bone, and is inclined

<sup>1</sup> A small, hook-shaped process of bone, the *supracondylar process*, varying from 2 to 20 mm. in length, is not infrequently found projecting from the antero-medial surface of the body of the humerus 5 cm. above the medial epicondyle. It is curved downward and forward, and its pointed end is connected to the medial border, just above the medial epicondyle, by a fibrous band, which gives origin to a portion of the *Pronator teres*; through the arch completed by this fibrous band the median nerve and brachial artery pass, when these structures deviate from their usual course. Sometimes the nerve alone is transmitted through it, or the nerve may be accompanied by the ulnar artery, in cases of high division of the brachial. A well-marked groove is usually found behind the process, in which the nerve and artery are lodged. This arch is the homologue of the supracondylar foramen found in many animals, and probably serves in them to protect the nerve and artery from compression during the contraction of the muscles in this region.

obliquely downward and forward toward the medial side. Above the front part of the trochlea is a small depression, the **coronoid fossa**, which receives the coronoid process of the ulna during flexion of the forearm. Above the back part of the trochlea is a deep triangular depression, the **olecranon fossa**, in which the summit of the olecranon is received in extension of the forearm. These fossæ are separated from one another by a thin, transparent lamina of bone, which is sometimes perforated by a **supratrochlear foramen**; they are lined in the recent state by the synovial membrane of the elbow-joint, and their margins afford attachment to the anterior and posterior ligaments of this articulation. The **lateral epicondyle** is a small, tuberculated eminence, curved a little forward, and giving attachment to the radial collateral ligament of the elbow-joint, and to a tendon common to the origin of the Supinator and some of the Extensor muscles. The **medial epicondyle**, larger and more prominent than the lateral, is directed a little backward; it gives attachment to the ulnar collateral ligament of the elbow-joint, to the Pronator teres, and to a common tendon of origin of some of the Flexor muscles of the forearm; the ulnar nerve runs in a groove on the back of this epicondyle. The epicondyles are continuous above with the supracondylar ridges.

**Structure.**—The extremities consist of cancellous tissue, covered with a thin, compact layer (Fig. 349); the body is composed of a cylinder of compact tissue, thicker at the centre than toward the extremities, and contains a large medullary canal which extends along its whole length.

**Ossification** (Figs. 350, 351).—The humerus is ossified from *eight* centres, one for each of the following parts: the body, the head, the greater tubercle, the lesser tubercle, the capitulum, the trochlea, and one for each epicondyle. The centre for the body appears near the middle of the bone in the eighth week of fetal life, and soon extends toward the extremities. At birth the humerus is ossified in nearly its whole length, only the extremities remaining cartilaginous. During the first year, sometimes before birth, ossification commences in the head of the bone, and during the third year the centre for the greater tubercle, and during the fifth that for the lesser tubercle, make their appearance. By the sixth year the centres for the head and tubercles have joined, so as to form a single large epiphysis, which fuses with the body about the twentieth year. The lower end of the humerus is ossified as follows. At the end of the second year ossification begins in the capitulum, and extends medialward, to form the chief part of the articular end of the bone; the centre for the medial part of the trochlea appears about the age of twelve. Ossification begins in the medial epicondyle about the fifth year, and in the lateral about the thirteenth or fourteenth year. About the sixteenth or seventeenth year, the lateral epicondyle and both portions of the articulating surface, having already joined, unite with the body, and at the eighteenth year the medial epicondyle becomes joined to it.

**Articulations.**—The humerus articulates with the scapula, ulna, and radius.

**Applied Anatomy.**—There are several points of surgical interest connected with the ossification of the humerus. The upper end, though the first to ossify, is the last to join the body, and the length of the bone is mainly due to growth from the upper epiphysial plate. Hence, in cases of amputation of the arm in young subjects, the humerus continues to grow considerably, and the end of the bone which immediately after the operation was covered with a thick cushion of soft tissue begins to project, thinning the soft parts and rendering the stump conical. This may necessitate the removal of about 5 cm. of the bone, and even after this operation a recurrence of the conical stump may take place. The region of the upper epiphysis, moreover, is the common site for the growth of tumors, both innocent and malignant.

Fractures of the humerus present several points of surgical interest. The bone may be broken by direct or indirect violence, like the other long bones, but, in addition to this, it is probably more frequently fractured by muscular action than any other bone of this class. It is usually




FIG. 349.—Longitudinal section of head of left humerus.

the body, just below the insertion of the Deltoides, which is thus broken, and the accident has been known to happen from throwing a stone. Fractures of the upper end may take place either through the anatomical or surgical neck, or a separation of the greater tubercle may occur. Fracture of the anatomical neck is a very rare accident; in fact, it is doubted by some whether it ever occurs. Fracture of the surgical neck of the bone is not uncommon, and impaction may occur; on the other hand, the upper end of the lower fragment may be displaced into the axilla and may damage the vessels or nerves. The fracture somewhat closely simulates dislocation of the shoulder-joint, but can be distinguished by the fact that the head of the bone remains in its normal position and the great tubercle still forms the most prominent point of the shoulder. Separation of the upper epiphysis sometimes occurs in the young subject, and is marked by a characteristic deformity, consisting in the presence of an abrupt projection at the front of the joint some short distance below the coracoid process, caused by the upper end of the diaphysis. In fractures of



FIG. 350.—Plan of ossification of the humerus.




FIG. 351.—Epiphysal lines of humerus in a young adult. Anterior aspect. The lines of attachment of the articular capsules are in blue.

the body of the humerus the lesion may take place at any point, but appears to be more common in the lower than the upper part of the bone. The points of interest in connection with these fractures are: (1) that the radial nerve may be injured as it lies in the groove on the bone, or may become involved in the callus which is subsequently thrown out; and (2) the frequency of non-union, which is believed to be more common in the humerus than in any other bone. An important distinction to make in fractures of the lower end is between those that involve the elbow-joint and those which do not; the former are always serious, as they may lead to impairment of the utility of the limb; they include the T-shaped fracture and oblique fractures which involve the articular surface. Those which do not involve the joint are the transverse fracture above the epicondyles, and the so-called epitrochlear fracture, where the tip of the medial epicondyle is broken off, generally from direct violence.

### The Ulna (Elbow Bone).

The **ulna** (Figs. 353, 354) is a long bone, prismatic in form, placed at the medial side of the forearm, parallel with the radius. It is divisible into a **body** and **two extremities**. Its upper extremity, of great thickness and strength, forms

a large part of the elbow-joint; the bone diminishes in size from above downward, its lower extremity being very small, and excluded from the wrist-joint by the interposition of an articular disk.

**The Upper Extremity** (*proximal extremity*) (Fig. 352).—The upper extremity presents two curved processes, the **olecranon** and the **coronoid process**; and two concave, articular cavities, the **semilunar** and **radial notches**.

**The Olecranon** (*olecranon process*).—The olecranon is a large, thick, curved eminence, situated at the upper and back part of the ulna. It is bent forward at the summit so as to present a prominent lip which is received into the olecranon fossa of the humerus in extension of the forearm. Its **base** is contracted where it joins the body and the narrowest part of the upper end of the ulna. Its **posterior surface**, directed backward, is triangular, smooth, subcutaneous, and covered by a bursa. Its **superior surface** is of quadrilateral form, marked behind by a rough impression for the insertion of the Triceps brachii; and in front, near the margin, by a slight transverse groove for the attachment of part of the posterior ligament of the elbow-joint. Its **anterior surface** is smooth, concave, and forms the upper part of the semilunar notch. Its **borders** present continuations of the groove on the margin of the superior surface; they serve for the attachment of ligaments, viz., the back part of the ulnar collateral ligament medially, and the posterior ligament laterally. From the medial border a part of the Flexor carpi ulnaris arises; while to the lateral border the Anconaeus is attached.

**The Coronoid Process** (*processus coronoideus*).—The coronoid process is a triangular eminence projecting forward from the upper and front part of the ulna. Its **base** is continuous with the body of the bone, and of considerable strength. Its **apex** is pointed, slightly curved upward, and inflexion of the forearm is received into the coronoid fossa of the humerus. Its **upper surface** is smooth, concave, and forms the lower part of the semilunar notch. Its **antero-inferior surface** is concave, and marked by a rough impression for the insertion of the Brachialis. At the junction of this surface with the front of the body is a rough eminence, the **tuberosity of the ulna**, which gives insertion to a part of the Brachialis; to the lateral border of this tuberosity the oblique cord is attached. Its **lateral surface** presents a narrow, oblong, articular depression, the **radial notch**. Its **medial surface**, by its prominent, free margin, serves for the attachment of part of the ulnar collateral ligament. At the front part of this surface is a small rounded eminence for the origin of one head of the Flexor digitorum sublimis; behind the eminence is a depression for part of the origin of the Flexor digitorum profundus; descending from the eminence is a ridge which gives origin to one head of the Pronator teres. Frequently, the Flexor pollicis longus arises from the lower part of the coronoid process by a rounded bundle of muscular fibres.

**The Semilunar Notch** (*incisura semilunaris; greater sigmoid cavity*).—The semilunar notch is a large depression, formed by the olecranon and the coronoid process, and serving for articulation with the trochlea of the humerus. About the middle of either side of this notch is an indentation, which contracts it somewhat, and




FIG. 352.—Upper extremity of left ulna.  
Lateral aspect.




FIG. 333.—Bones of left forearm. Anterior aspect.




FIG. 354.—Bones of left forearm. Posterior aspect.



indicates the junction of the olecranon and the coronoid process. The notch is concave from above downward, and divided into a medial and a lateral portion by a smooth ridge running from the summit of the olecranon to the tip of the coronoid process. The medial portion is the larger, and is slightly concave transversely; the lateral is convex above, slightly concave below.

**The Radial Notch** (*incisura radialis; lesser sigmoid cavity*).—The radial notch is a narrow, oblong, articular depression on the lateral side of the coronoid process; it receives the circumferential articular surface of the head of the radius. It is concave from before backward, and its prominent extremities serve for the attachment of the annular ligament.

**The Body or Shaft** (*corpus ulnae*).—The body at its upper part is prismatic in form, and curved so as to be convex behind and lateralward; its central part is straight; its lower part is rounded, smooth, and bent a little lateralward. It tapers gradually from above downward, and has three borders and three surfaces.

**Borders.**—The **volar border** (*margo volaris; anterior border*) begins above at the prominent medial angle of the coronoid process, and ends below in front of the styloid process. Its upper part, well-defined, and its middle portion, smooth and rounded, give origin to the Flexor digitorum profundus; its lower fourth serves for the origin of the Pronator quadratus. This border separates the volar from the medial surface.

The **dorsal border** (*margo dorsalis; posterior border*) begins above at the apex of the triangular subcutaneous surface at the back part of the olecranon, and ends below at the back of the styloid process; it is well-marked in the upper three-fourths, and gives attachment to an aponeurosis which affords a common origin to the Flexor carpi ulnaris, the Extensor carpi ulnaris, and the Flexor digitorum profundus; its lower fourth is smooth and rounded. This border separates the medial from the dorsal surface.

The **interosseous crest** (*crista interossea; external or interosseous border*) begins above by the union of two lines, which converge from the extremities of the radial notch and enclose between them a triangular space for the origin of part of the Supinator; it ends below at the head of the ulna. Its upper part is sharp, its lower fourth smooth and rounded. This crest gives attachment to the interosseous membrane, and separates the volar from the dorsal surface.

**Surfaces.**—The **volar surface** (*facies volaris; anterior surface*), much broader above than below, is concave in its upper three-fourths, and gives origin to the Flexor digitorum profundus; its lower fourth, also concave, is covered by the Pronator quadratus. The lower fourth is separated from the remaining portion by a ridge, directed obliquely downward and medialward, which marks the extent of origin of the Pronator quadratus. At the junction of the upper with the middle third of the bone is the nutrient canal, directed obliquely upward.

The **dorsal surface** (*facies dorsalis; posterior surface*) directed backward and lateralward, is broad and concave above; convex and somewhat narrower in the middle; narrow, smooth, and rounded below. On its upper part is an oblique ridge, which runs from the dorsal end of the radial notch, downward to the dorsal border; the triangular surface above this ridge receives the insertion of the Anconaeus, while the upper part of the ridge affords attachment to the Supinator. Below this the surface is subdivided by a longitudinal ridge, sometimes called the **perpendicular line**, into two parts: the medial part is smooth, and covered by the Extensor carpi ulnaris; the lateral portion, wider and rougher, gives origin from above downward to the Supinator, the Abductor pollicis longus, the Extensor pollicis longus, and the Extensor indicis proprius.

The **medial surface** (*facies medialis; internal surface*) is broad and concave above, narrow and convex below. Its upper three-fourths give origin to the Flexor digitorum profundus; its lower fourth is subcutaneous.

**The Lower Extremity** (*distal extremity*).—The lower extremity of the ulna is small, and presents two eminences; the lateral and larger is a rounded, articular eminence, termed the head of the ulna; the medial, narrower and more projecting, is a non-articular eminence, the styloid process. The **head** presents an articular surface, part of which, of an oval or semilunar form, is directed downward, and articulates with the upper surface of the triangular articular disk which separates it from the wrist-joint; the remaining portion, directed lateralward, is narrow, convex, and received into the ulnar notch of the radius. The **styloid process** projects from the medial and back part of the bone; it descends a little lower than the head, and its rounded end affords attachment to the ulnar collateral ligament of the wrist-joint. The head is separated from the styloid process by a depression for the attachment of the apex of the triangular articular disk, and behind, by a shallow groove for the tendon of the Extensor carpi ulnaris.




FIG. 355.—Plan of ossification of the ulna. From three centres.




FIG. 356.—Epiphysial lines of ulna in a young adult. Lateral aspect. The lines of attachment of the articular capsules are in blue.

**Structure.**—The structure of the ulna is similar to that of the other long bones.

**Ossification** (Figs. 355, 356).—The ulna is ossified from *three* centres: one each for the body, the inferior extremity, and the top of the olecranon. Ossification begins near the middle of the body, about the eighth week of fetal life, and soon extends through the greater part of the bone. At birth the ends are cartilaginous. About the fourth year, a centre appears in the middle of the head, and soon extends into the styloid process. About the tenth year, a centre appears in the olecranon near its extremity, the chief part of this process being formed by an upward extension of the body. The upper epiphysis joins the body about the sixteenth, the lower about the twentieth year.

**Articulations.**—The ulna articulates with the humerus and radius.

### The Radius.

The **radius** (Figs. 353, 354) is situated on the lateral side of the ulna, which exceeds it in length and size. Its upper end is small, and forms only a small part of the elbow-joint; but its lower end is large, and forms the chief part of the wrist-

joint. It is a long bone, prismatic in form and slightly curved longitudinally. It has a body and two extremities.

**The Upper Extremity** (*proximal extremity*).—The upper extremity presents a head, neck, and tuberosity. The **head** is of a cylindrical form, and on its upper surface is a shallow cup or fovea for articulation with the capitulum of the humerus. The circumference of the head is smooth; it is broad medially where it articulates with the radial notch of the ulna, narrow in the rest of its extent, which is embraced by the annular ligament. The head is supported on a round, smooth, and constricted portion called the **neck**, on the back of which is a slight ridge for the insertion of part of the Supinator. Beneath the neck, on the medial side, is an eminence, the **radial tuberosity**; its surface is divided into a posterior, rough portion, for the insertion of the tendon of the Biceps brachii, and an anterior, smooth portion, on which a bursa is interposed between the tendon and the bone.

**The Body or Shaft** (*corpus radii*).—The body is prismoid in form, narrower above than below, and slightly curved, so as to be convex lateralward. It presents three borders and three surfaces.

**Borders.**—The **volar border** (*margo volaris; anterior border*) extends from the lower part of the tuberosity above to the anterior part of the base of the styloid process below, and separates the volar from the lateral surface. Its upper third is prominent, and from its oblique direction has received the name of the **oblique line of the radius**; it gives origin to the Flexor digitorum sublimis and Flexor pollicis longus; the surface above the line gives insertion to part of the Supinator. The middle third of the volar border is indistinct and rounded. The lower fourth is prominent, and gives insertion to the Pronator quadratus, and attachment to the dorsal carpal ligament; it ends in a small tubercle, into which the tendon of the Brachioradialis is inserted.

The **dorsal border** (*margo dorsalis; posterior border*) begins above at the back of the neck, and ends below at the posterior part of the base of the styloid process; it separates the posterior from the lateral surface. It is indistinct above and below, but well-marked in the middle third of the bone.

The **interosseous crest** (*crista interossea; internal or interosseous border*) begins above, at the back part of the tuberosity, and its upper part is rounded and indistinct; it becomes sharp and prominent as it descends, and at its lower part divides into two ridges which are continued to the anterior and posterior margins of the ulnar notch. To the posterior of the two ridges the lower part of the interosseous membrane is attached, while the triangular surface between the ridges gives insertion to part of the Pronator quadratus. This crest separates the volar from the dorsal surface, and gives attachment to the interosseous membrane.

**Surface.**—The **volar surface** (*facies volaris; anterior surface*) is concave in its upper three-fourths, and gives origin to the Flexor pollicis longus; it is broad and flat in its lower fourth, and affords insertion to the Pronator quadratus. A prominent ridge limits the insertion of the Pronator quadratus below, and between this and the inferior border is a triangular rough surface for the attachment of the volar radiocarpal ligament. At the junction of the upper and middle thirds of the volar surface is the nutrient foramen, which is directed obliquely upward.

The **dorsal surface** (*facies dorsalis; posterior surface*) is convex, and smooth in the upper third of its extent, and covered by the Supinator. Its middle third is broad, slightly concave, and gives origin to the Abductor pollicis longus above, and the Extensor pollicis brevis below. Its lower third is broad, convex, and covered by the tendons of the muscles which subsequently run in the grooves on the lower end of the bone.

The **lateral surface** (*facies lateralis; external surface*) is convex throughout its entire extent. Its upper third gives insertion to the Supinator. About its centre is a rough ridge, for the insertion of the Pronator teres. Its lower part is narrow, and covered by the tendons of the Abductor pollicis longus and Extensor pollicis brevis.

**The Lower Extremity.**—The lower extremity is large, of quadrilateral form, and provided with two articular surfaces—one below, for the carpus, and another at the medial side, for the ulna. The carpal articular surface is triangular, concave, smooth, and divided by a slight antero-posterior ridge into two parts. Of these, the lateral, triangular, articulates with the navicular bone; the medial, quadrilateral, with the lunate bone. The articular surface for the ulna is called the **ulnar notch (sigmoid cavity) of the radius**; it is narrow, concave, smooth, and articulates with the head of the ulna. These two articular surfaces are separated by a prominent ridge, to which the base of the triangular articular disk is attached; this disk separates the wrist-joint from the distal radioulnar articulation. This end of the bone has three non-articular surfaces—volar, dorsal, and lateral. The **volar surface**, rough and irregular, affords attachment to the volar radiocarpal ligament. The **dorsal surface** is convex, affords attachment to the dorsal radiocarpal ligament, and is marked by three grooves. Enumerated from the lateral side, the first groove is broad, but shallow, and subdivided into two by a slight ridge; the lateral of these two transmits the tendon of the Extensor carpi radialis longus, the medial the tendon of the Extensor carpi radialis brevis. The second is deep but narrow, and bounded laterally by a sharply defined ridge; it is directed obliquely from above downward and lateralward, and transmits the tendon of the Extensor pollicis longus. The third is broad, for the passage of the tendons of the Extensor indicis proprius and Extensor digitorum communis. The **lateral surface** is prolonged obliquely downward into a strong, conical projection, the **styloid process**, which gives attachment by its base to the tendon of the Brachioradialis, and by its apex to the radial collateral ligament of the wrist-joint. The lateral surface of this process is marked by a flat groove, for the tendons of the Abductor pollicis longus and Extensor pollicis brevis.

**Structure.**—The structure of the radius is like that of the other long bones.

**Ossification** (Figs. 357, 358).—The radius is ossified from *three* centres: one for the body, and one for either extremity. That for the body makes its appearance near the centre of the bone, during the eighth week of fetal life. About the end of the second year, ossification commences in the lower end; and at the fifth year, in the upper end. The upper epiphysis fuses with the body at the age of seventeen or eighteen years, the lower about the age of twenty. An additional centre sometimes found in the radial tuberosity, appears about the fourteenth or fifteenth year.

**Articulations.**—The radius articulates with *four* bones: the humerus, ulna, navicular, and lunate.

**Applied Anatomy of the Ulna and Radius.**—The two bones of the forearm are more often broken together, than is either the radius or ulna separately. It is therefore convenient to consider in the first instance the fractures of both bones and subsequently the principal fractures which take place in either bone. Fractures of both bones may be produced by either direct or indirect violence, though more commonly by direct violence. When indirect force is applied to the forearm the radius as a rule gives way, though both bones may suffer. Fracture from indirect force generally takes place somewhere about the middle of the bones, while that from direct violence may occur at any part, but is most frequent in the lower half of the bones. The fracture is usually transverse, but may be more or less oblique. A point of interest in connection with these fractures is the tendency for the two bones to unite across the interosseous membrane; the limb should therefore be put up in a position midway between supination and pronation, which is not only the most comfortable position, but also separates the bones most widely from each other. Anterior and posterior splints are applied in these cases, and should be rather wider than the limb, so as to prevent any side pressure on the bones.

The special fractures of the ulna are: (1) Fracture of the olecranon, which is usually caused by direct violence, by falls on the elbow with the forearm flexed, but occasionally by muscular action in sudden contraction of the Triceps brachii; the most common site of this fracture is at the constricted portion where the olecranon joins the body of the bone, and the fracture is usually transverse; but any part may be broken, and even a thin shell may be torn off. Fractures from direct violence are occasionally comminuted. If the fibrous structures around the process are not torn the displacement is slight, otherwise the olecranon may be drawn up for a very considerable distance. (2) Fracture of the coronoid process may occur as a complication of dislocation backward of the bones of the forearm, but it is doubtful if it ever takes place as an uncomplicated injury. (3) Fractures of the body of the ulna may occur at any part, but usually take place at

or a little below the middle of the bone. They are generally the result of direct violence, but may occur as a complication of dislocation of the radius. (4) The styloid process may be knocked off by direct violence.

Fractures of the radius may consist of: (1) Fracture of the head of the bone; this for the most part takes place in conjunction with some other lesion, but may occur as an uncomplicated injury. (2) Fracture of the neck also may occur, but is usually complicated with other injury. (3) Fractures of the body of the radius are very common, and may take place at any part of the bone. They may be caused by direct or indirect violence. In fracture of the upper third of the body—that is to say, above the insertion of the Pronator teres—the displacement is very great. The upper fragment is strongly supinated by the biceps and supinator and flexed by the biceps; while the lower fragment is pronated and drawn toward the ulna by the two pronators. If such a fracture be put up in the ordinary position, midway between supination and pronation, the bone will unite with the upper fragment in a position of supination, and the lower one in the mid-position, and thus considerable impairment of the movement of supination will result; the limb should therefore be put up with the forearm supinated. (4) The most important fracture of the




FIG. 357.—Plan of ossification of the radius.  
From three centres.



FIG. 358.—Epiphysal lines of radius in a young adult. Anterior aspect. The line of attachment of the articular capsule of the wrist-joint is in blue.

radius is that of the lower end (*Colles' fracture*). The fracture is transverse, and generally takes place about 2.5 cm. from the lower extremity. It is caused by falls on the palm of the hand, and is an injury of advanced life, occurring more frequently in the female than in the male. In consequence of the manner in which the fracture is caused, the upper fragment is driven into the lower, and impaction commonly is the result; excess of violence may, however, disimpact, the lower fragment being split into two or more pieces, so that no fixation occurs. Separation of the lower epiphysis of the radius may take place in the young. This injury and *Colles' fracture* may be distinguished from other injuries in this neighborhood—especially dislocation of the wrist, with which they are liable to be confounded—by observing the relative positions of the styloid processes of the ulna and radius. In the natural conditions of parts, with the arm hanging by the side, the styloid process of the radius is on a lower level than that of the ulna. After fracture or separation of the epiphysis the styloid process of the radius is on the same level as, or on a higher level than, that of the ulna, whereas it would be unaltered in position in dislocation. Reduction in the case of *Colles' fracture* is usually easily effected by traction on the hand, the limb being subsequently splinted with the hand deflected toward the ulnar side.

## THE HAND.

The skeleton of the hand (Figs. 359, 360) is subdivided into three segments: the **carpus** or **wrist bones**; the **metacarpus** or **bones of the palm**; and the **phalanges** or **bones of the digits**.

The Carpus (*Ossa Carpi*).

The **carpal bones**, eight in number, are arranged in two rows. Those of the proximal row, from the radial to the ulnar side, are named the **navicular**, **lunate**, **triangular**, and **pisiform**; those of the distal row, in the same order, are named the **greater multangular**, **lesser multangular**, **capitate**, and **hamate**.

**Common Characteristics of the Carpal Bones.**—Each bone (excepting the pisiform) presents six surfaces. Of these the *volar* or *anterior* and the *dorsal* or *posterior* surfaces are rough, for ligamentous attachment; the dorsal surfaces being the broader, except in the navicular and lunate. The *superior* or *proximal*, and *inferior* or *distal* surfaces are articular, the superior generally convex, the inferior concave; the *medial* and *lateral* surfaces are also articular where they are in contact with contiguous bones, otherwise they are rough and tuberculated. The structure in all is similar, viz., cancellous tissue enclosed in a layer of compact bone.

**Bones of the Proximal Row** (*upper row*).—**The Navicular Bone** (*os naviculare manus*; *scaphoid bone*) (Fig. 361).—The navicular bone is the largest bone of the proximal row, and has received its name from its fancied resemblance to a boat. It is situated at the radial side of the carpus, its long axis being from above downward, lateralward, and forward. The **superior surface** is convex, smooth, of triangular shape, and articulates with the lower end of the radius. The **inferior surface**, directed downward, lateralward, and backward, is also smooth, convex, and triangular, and is divided by a slight ridge into two parts, the lateral articulating with the greater multangular, the medial with the lesser multangular. On the **dorsal surface** is a narrow, rough groove, which runs the entire length of the bone, and serves for the attachment of ligaments. The **volar surface** is concave above, and elevated at its lower and lateral part into a rounded projection, the **tubercle**, which is directed forward and gives attachment to the transverse carpal ligament and sometimes origin to a few fibres of the Abductor pollicis brevis. The **lateral surface** is rough and narrow, and gives attachment to the radial collateral ligament of the wrist. The **medial surface** presents two articular facets; of these, the superior or smaller is flattened of semilunar form, and articulates with the lunate bone; the inferior or larger is concave, forming with the lunate a concavity for the head of the capitate bone.

**Articulations.**—The navicular articulates with *five* bones: the radius proximally, greater and lesser multangulans distally, and capitate and lunate medially.

**The Lunate Bone** (*os lunatum*; *semilunar bone*) (Fig. 362).—The lunate bone may be distinguished by its deep concavity and crescentic outline. It is situated in the centre of the proximal row of the carpus, between the navicular and triangular. The **superior surface**, convex and smooth, articulates with the radius. The **inferior surface** is deeply concave, and of greater extent from before backward than transversely: it articulates with the head of the capitate, and, by a long, narrow facet (separated by a ridge from the general surface), with the hamate. The **dorsal** and **volar surfaces** are rough, for the attachment of ligaments, the former being the broader, and of a somewhat rounded form. The **lateral surface** presents a narrow, flattened, semilunar facet for articulation with the navicular. The **medial surface** is marked by a smooth, quadrilateral facet, for articulation with the triangular.

**Articulations.**—The lunate articulates with *five* bones: the radius proximally, capitate and hamate distally, navicular laterally, and triangular medially.



**The Triangular Bone** (*os triquetrum*; *cuneiform bone*) (Fig. 363).—The triangular bone may be distinguished by its pyramidal shape, and by an oval isolated facet for articulation with the pisiform bone. It is situated at the upper and ulnar side of the carpus. The **superior surface** presents a medial, rough, non-articular portion, and a lateral convex articular portion which articulates with the triangular articular disk of the wrist. The **inferior surface**, directed lateralward, is concave, sinuously curved, and smooth for articulation with the hamate. The **dorsal surface** is rough




FIG. 359.—Bones of the left hand. Volar surface.

for the attachment of ligaments. The **volar surface** presents, on its medial part, an oval facet, for articulation with the pisiform; its lateral part is rough for ligamentous attachment. The **lateral surface**, the base of the pyramid, is marked by a flat, quadrilateral facet, for articulation with the lunate. The **medial surface**, the summit of the pyramid, is pointed and roughened, for the attachment of the ulnar collateral ligament of the wrist.




FIG. 360.—Bones of the left hand. Dorsal surface.

**Articulations.**—The triangular articulates with *three* bones: the lunate laterally, the pisiform in front, the hamate distally; and with the triangular articular disk which separates it from the lower end of the ulna.




FIG. 361.—The left navicular bone.

**The Pisiform Bone** (*os pisiforme*) (Fig. 364).—The pisiform bone may be known by its small size, and by its presenting a single articular facet. It is situated on a plane anterior to the other carpal bones and is spheroidal in form. Its **dorsal**




FIG. 362.—The left lunate bone.

**surface** presents a smooth, oval facet, for articulation with the triangular: this facet approaches the superior, but not the inferior border of the bone. The **volar surface** is rounded and rough, and gives attachment to the transverse carpal ligament,




FIG. 363.—The left triangular bone.




FIG. 364.—The left pisiform bone.

and to the Flexor carpi ulnaris and Abductor digiti quinti. The **lateral** and **medial surfaces** are also rough, the former being concave, the latter usually convex.

**Articulation.**—The pisiform articulates with *one* bone, the triangular.





FIG. 365.—The left greater multangular bone.

**Bones of the Distal Row** (*lower row*).—The **Greater Multangular Bone** (*os multangulum majus; trapezium*) (Fig. 365).—The greater multangular bone may be distinguished by a deep groove on its volar surface. It is situated at the radial

side of the carpus, between the navicular and the first metacarpal bone. The **superior surface** is directed upward and medialward; medially it is smooth, and articulates with the navicular; laterally it is rough and continuous with the lateral surface. The **inferior surface** is oval, concave from side to side, convex from before backward, so as to form a saddle-shaped surface for articulation with the base of the first metacarpal bone. The **dorsal surface** is rough. The **volar surface** is narrow and rough. At its upper part is a deep groove, running from above obliquely downward and medialward; it transmits the tendon of the Flexor carpi radialis, and is bounded laterally by an oblique ridge. This surface gives origin to the Opponens pollicis and to the Abductor and Flexor pollicis brevis; it also affords attachment to the transverse carpal ligament. The **lateral surface** is broad and rough, for the attachment of ligaments. The **medial surface** presents two facets; the upper, large and concave, articulates with the lesser multangular; the lower, small and oval, with the base of the second metacarpal.

**Articulations.**—The greater multangular articulates with *four* bones: the navicular proximally, the first metacarpal distally, and the lesser multangular and second metacarpal medially.

**The Lesser Multangular Bone** (*os multangulum minus*; *trapezoid bone*) (Fig. 366).—The lesser multangular is the smallest bone in the distal row. It may be known by its wedge-shaped form, the broad end of the wedge constituting the dorsal, the narrow end the volar surface; and by its having four articular facets touching each other, and separated by sharp edges. The **superior surface**, quadrilateral, smooth, and slightly concave, articulates with the navicular. The **inferior surface** articulates with the proximal end of the second metacarpal bone; it is convex from side to side, concave from before backward and subdivided by an elevated ridge into two unequal facets. The **dorsal and volar surfaces** are rough for the attachment of ligaments, the former being the larger of the two. The **lateral surface**, convex and smooth, articulates with the greater multangular. The **medial surface** is concave and smooth in front, for articulation with the capitate; rough behind, for the attachment of an interosseous ligament.




FIG. 366.—The left lesser multangular bone.

**Articulations.**—The lesser multangular articulates with *four* bones: the navicular proximally, second metacarpal distally, greater multangular laterally, and capitate medially.




FIG. 367.—The left capitate bone.

**The Capitate Bone** (*os capitatum*; *os magnum*) (Fig. 367).—The capitate bone is the largest of the carpal bones, and occupies the centre of the wrist. It presents, above, a rounded portion or head, which is received into the concavity formed by

the navicular and lunate; a constricted portion or neck; and below this, the body. The **superior surface** is round, smooth, and articulates with the lunate. The **inferior surface** is divided by two ridges into three facets, for articulation with the second, third, and fourth metacarpal bones, that for the third being the largest. The **dorsal surface** is broad and rough. The **volar surface** is narrow, rounded, and rough, for the attachment of ligaments and a part of the Adductor pollicis obliquus. The **lateral surface** articulates with the lesser multangular by a small facet at its anterior inferior angle, behind which is a rough depression for the attachment of an interosseous ligament. Above this is a deep, rough groove, forming part of the neck, and serving for the attachment of ligaments; it is bounded superiorly by a smooth, convex surface, for articulation with the navicular. The **medial surface** articulates with the hamate by a smooth, concave, oblong facet, which occupies its posterior and superior parts; it is rough in front, for the attachment of an interosseous ligament.

**Articulations.**—The capitate articulates with *seven* bones: the navicular and lunate proximally, the second, third, and fourth metacarpals distally, the lesser multangular on the radial side, and the hamate on the ulnar side.




FIG. 368.—The left hamate bone.

**The Hamate Bone** (*os hamatum*; *unciform bone*) (Fig. 368).—The hamate bone may be readily distinguished by its wedge-shaped form, and the hook-like process which projects from its volar surface. It is situated at the medial and lower angle of the carpus, with its base downward, resting on the fourth and fifth metacarpal bones, and its apex directed upward and lateralward. The **superior surface**, the apex of the wedge, is narrow, convex, smooth, and articulates with the lunate. The **inferior surface** articulates with the fourth and fifth metacarpal bones, by concave facets which are separated by a ridge. The **dorsal surface** is triangular and rough for ligamentous attachment. The **volar surface** presents, at its lower and ulnar side, a curved, hook-like process, the **hamulus**, directed forward and lateralward. This process gives attachment, by its apex, to the transverse carpal ligament and the Flexor carpi ulnaris; by its medial surface to the Flexor brevis and Opponens digiti quinti; its lateral side is grooved for the passage of the Flexor tendons into the palm of the hand. It is one of the four eminences on the front of the carpus to which the transverse carpal ligament of the wrist is attached; the others being the pisiform medially, the oblique ridge of the greater multangular, and the tubercle of the navicular laterally. The **medial surface** articulates with the triangular bone by an oblong facet, cut obliquely from above, downward and medialward. The **lateral surface** articulates with the capitate by its upper and posterior part, the remaining portion being rough, for the attachment of ligaments.

**Articulations.**—The hamate articulates with *five* bones: the lunate proximally, the fourth and fifth metacarpals distally, the triangular medially, the capitate laterally.



### The Metacarpus.

The **metacarpus** consists of five cylindrical bones which are numbered from the lateral side (*ossa metacarpalia I-V*); each consists of a body and two extremities.

**Common Characteristics of the Metacarpal Bones.**—**The Body** (*corpus; shaft*).—The body is prismoid in form, and curved, so as to be convex in the longitudinal direction behind, concave in front. It presents three surfaces: medial, lateral, and dorsal. The **medial** and **lateral surfaces** are concave, for the attachment of the Interossei, and separated from one another by a prominent anterior ridge. The **dorsal surface** presents in its distal two-thirds a smooth, triangular, flattened area which is covered in the recent state, by the tendons of the Extensor muscles. This surface is bounded by two lines, which commence in small tubercles situated on either side of the digital extremity, and, passing upward, converge and meet some distance above the centre of the bone and form a ridge which runs along the rest of the dorsal surface to the carpal extremity. This ridge separates two sloping surfaces for the attachment of the Interossei dorsales. To the tubercles on the digital extremities are attached the collateral ligaments of the metacarpophalangeal joints.

The **Base** or **Carpal Extremity** (*basis*) is of a cuboidal form, and broader behind than in front: it articulates with the carpus, and with the adjoining metacarpal bones; its **dorsal** and **volar surfaces** are rough, for the attachment of ligaments.

The **Head** or **Digital Extremity** (*capitulum*) presents an oblong surface markedly convex from before backward, less so transversely, and flattened from side to side; it articulates with the proximal phalanx. It is broader, and extends farther upward, on the volar than on the dorsal aspect, and is longer in the antero-posterior than in the transverse diameter. On either side of the head is a tubercle for the attachment of the collateral ligament of the metacarpophalangeal joint. The **dorsal surface**, broad and flat, supports the Extensor tendons; the **volar surface** is grooved in the middle line for the passage of the Flexor tendons, and marked on either side by an articular eminence continuous with the terminal articular surface.

**Characteristics of the Individual Metacarpal Bones.**—**The First Metacarpal Bone** (*os metacarpale I; metacarpal bone of the thumb*) (Fig. 369) is shorter and stouter than the others, diverges to a greater degree from the carpus, and its volar surface is directed toward the palm. The **body** is flattened and broad on its dorsal surface, and does not present the ridge which is found on the other metacarpal bones; its volar surface is concave from above downward. On its radial border is inserted the Opponens pollicis; its ulnar border gives origin to the lateral head of the first Interosseus dorsalis. The **base** presents a concavo-convex surface, for articulation with the greater multangular; it has no facets on its sides, but on its radial side is a tubercle for the insertion of the Abductor pollicis longus. The **head** is less convex than those of the other metacarpal bones, and is broader from side to side than from before backward. On its volar surface are two articular eminences, of which the lateral is the larger, for the two sesamoid bones in the tendons of the Flexor pollicis brevis.

**The Second Metacarpal Bone** (*os metacarpale II; metacarpal bone of the index finger*) (Fig. 370) is the longest, and its base the largest, of the four remaining bones. Its **base** is prolonged upward and medialward, forming a prominent ridge.



FIG. 369.—The first metacarpal.  
(Left.)



It presents four articular facets: three on the upper surface and one on the ulnar side. Of the facets on the upper surface the intermediate is the largest and is concave from side to side, convex from before backward for articulation with the lesser multangular; the lateral is small, flat and oval for articulation with the greater multangular; the medial, on the summit of the ridge, is long and narrow for articulation with the capitate. The facet on the ulnar side articulates with the third metacarpal. The Extensor carpi radialis longus is inserted on the dorsal surface and the Flexor carpi radialis on the volar surface of the base.




FIG. 370.—The second metacarpal. (Left.)



FIG. 371.—The third metacarpal. (Left.)

**The Third Metacarpal Bone** (*os metacarpale III*; *metacarpal bone of the middle finger*) (Fig. 371) is a little smaller than the second. The dorsal aspect of its base presents on its radial side a pyramidal eminence, the **styloid process**, which extends upward behind the capitate; immediately distal to this is a rough surface for the attachment of the Extensor carpi radialis brevis. The carpal articular facet is concave behind, flat in front, and articulates with the capitate. On the radial side is a smooth, concave facet for articulation with the second metacarpal, and on the ulnar side two small oval facets for the fourth metacarpal.

**The Fourth Metacarpal Bone** (*os metacarpale IV*; *metacarpal bone of the ring finger*) (Fig. 372) is shorter and smaller than the third. The base is small and quadrilateral; its superior surface presents two facets, a large one medially for articulation with the hamate, and a small one laterally for the capitate. On the radial side are two oval facets, for articulation with the third metacarpal; and on the ulnar side a single concave facet, for the fifth metacarpal.

**The Fifth Metacarpal Bone** (*os metacarpale V*; *metacarpal bone of the little finger*) (Fig. 373) presents on its base one facet on its superior surface, which is concavo-convex and articulates with the hamate, and one on its radial side, which articulates with the fourth metacarpal. On its ulnar side is a prominent tubercle for the insertion of the tendon of the Extensor carpi ulnaris. The dorsal surface of the body is divided by an oblique ridge, which extends from near the ulnar side of the base to the radial side of the head. The lateral part of this surface serves for the attach-

ment of the fourth Interosseus dorsalis; the medial part is smooth, triangular, and covered by the Extensor tendons of the little finger.




FIG. 372.—The fourth metacarpal. (Left.)




FIG. 373.—The fifth metacarpal. (Left.)

**Articulations.**—Besides their phalangeal articulations, the metacarpal bones articulate as follows: the first with the greater multangular; the second with the greater multangular, lesser multangular, capitate and third metacarpal; the third with the capitate and second and fourth metacarpals; the fourth with the capitate, hamate, and third and fifth metacarpals; and the fifth with the hamate and fourth metacarpal.

### The Phalanges of the Hand (*Phalanges Digitorum Manus*).

The **phalanges** are fourteen in number, three for each finger, and two for the thumb. Each consists of a body and two extremities. The **body** tapers from above downward, is convex posteriorly, concave in front from above downward, flat from side to side; its sides are marked by rough ridges which give attachment to the fibrous sheaths of the Flexor tendons. The **proximal extremities** of the bones of the first row present oval, concave articular surfaces, broader from side to side than from before backward. The **proximal extremity** of each of the bones of the second and third rows presents a double concavity separated by a median ridge. The **distal extremities** are smaller than the proximal, and each ends in two condyles separated by a shallow groove; the articular surface extends farther on the volar than on the dorsal surface, a condition best marked in the bones of the first row.

The **ungual phalanges** are convex on their dorsal and flat on their volar surfaces; they are recognized by their small size, and by a roughened, elevated surface of a horseshoe form on the volar surface of the distal extremity of each which serves to support the sensitive pulp of the finger.

**Articulations.**—In the four fingers the phalanges of the first row articulate with those of the second row and with the metacarpals; the phalanges of the second row with those of the first and third rows, and the unguinal phalanges with those of the second row. In the thumb, which has only two phalanges, the first phalanx articulates by its proximal extremity with the metacarpal bone and by its distal with the unguinal phalanx.

**Ossification of the Bones of the Hand.**—The **carpal bones** are each ossified from a single centre, and ossification proceeds in the following order (Fig. 374): in the capitate and hamate, during the first year, the former preceding the latter; in the triangular, during the third year; in the lunate and greater multangular, during the fifth year, the former preceding the latter; in the navicular, during the sixth year; in the lesser multangular, during the eighth year; and in the pisiform, about the twelfth year.



seat of tuberculous disease. The metacarpal bones and the phalanges are sometimes broken from direct violence. There are two diseases of the metacarpal bones and phalanges which require special mention on account of their frequent occurrence. One is tuberculous dactylitis, consisting in a deposit of tuberculous material in the medullary canal, expansion of the bone, with subsequent caseation and necrosis. The other is chondroma, which is perhaps more commonly found in connection with the metacarpal bones and phalanges than with any other bones. The tumors are usually multiple, and spring from beneath the periosteum about the epiphysial plate.

## THE BONES OF THE LOWER EXTREMITY (OSSA EXTREMITATIS INFERIORIS).

### The Hip Bone (Os Coxae; Innominate Bone).

The **hip bone** is a large, flattened, irregularly shaped bone, constricted in the centre and expanded above and below. It meets its fellow on the opposite side in the middle line in front, and together they form the sides and anterior wall of the pelvic cavity. It consists of three parts, the **ilium**, **ischium**, and **pubis**, which are distinct from each other in the young subject, but are fused in the adult; the union of the three parts takes place in and around a large cup-shaped articular cavity, the **acetabulum**, which is situated near the middle of the outer surface of the bone. The **ilium**, so-called because it supports the flank, is the superior broad and expanded portion which extends upward from the acetabulum. The **ischium** is the lowest and strongest portion of the bone; it proceeds downward from the acetabulum, expands into a large tuberosity, and then, curving forward, forms, with the pubis, a large aperture, the **obturator foramen**. The **pubis** extends medialward and downward from the acetabulum and articulates in the middle line with the bone of the opposite side: it forms the front of the pelvis and supports the external organs of generation.

**The Ilium** (*os ilii*).—The ilium is divisible into two parts, the **body** and the **ala**; the separation is indicated on the internal surface by a curved line, the **arcuate line**, and on the external surface by the margin of the acetabulum.

**The Body** (*corpus oss. ilii*).—The body enters into the formation of the acetabulum, of which it forms rather less than two-fifths. Its **external surface** is partly articular, partly non-articular; the articular segment forms part of the lunate surface of the acetabulum, the non-articular portion contributes to the acetabular fossa. The **internal surface** of the body is part of the wall of the lesser pelvis and gives origin to some fibres of the Obturator internus. Below, it is continuous with the pelvic surfaces of the ischium and pubis, only a faint line indicating the place of union.

**The Ala** (*ala oss. ilii*).—The ala is the large expanded portion which bounds the greater pelvis laterally. It presents for examination two surfaces—an external and an internal—a crest, and two borders—an anterior and a posterior. The **external surface** (Fig. 375), known as the **dorsum ilii**, is directed backward and lateralward behind, and downward and lateralward in front. It is smooth, convex in front, deeply concave behind; bounded above by the crest, below by the upper border of the acetabulum, in front and behind by the anterior and posterior borders. This surface is crossed in an arched direction by three lines—the posterior, anterior, and inferior gluteal lines. The **posterior gluteal line** (*superior curved line*), the shortest of the three, begins at the crest, about 5 cm. in front of its posterior extremity; it is at first distinctly marked, but as it passes downward to the upper part of the greater sciatic notch, where it ends, it becomes less distinct, and is often altogether lost. Behind this line is a narrow semilunar surface, the upper part of which is rough and gives origin to a portion of the Glutaeus maximus; the lower part is smooth and has no muscular fibres attached to it. The **anterior gluteal line** (*middle curved line*), the longest of the three, begins at the crest, about 4 cm. behind its

anterior extremity, and, taking a curved direction downward and backward, ends at the upper part of the greater sciatic notch. The space between the anterior and posterior gluteal lines and the crest is concave, and gives origin to the *Glutæus medius*. Near the middle of this line a nutrient foramen is often seen. The **inferior gluteal line** (*inferior curved line*), the least distinct of the three, begins in





FIG. 375.—Right hip bone. External surface.

front at the notch on the anterior border, and, curving backward and downward, ends near the middle of the greater sciatic notch. The surface of bone included between the anterior and inferior gluteal lines is concave from above downward, convex from before backward, and gives origin to the *Glutæus minimus*. Between the inferior gluteal line and the upper part of the acetabulum is a rough, shallow groove, from which the reflected tendon of the *Rectus femoris* arises.

The **internal surface** (Fig. 376) of the ala is bounded above by the crest, below, by the arcuate line; in front and behind, by the anterior and posterior borders. It presents a large, smooth, concave surface, called the **iliac fossa**, which gives origin to the Iliacus and is perforated at its inner part by a nutrient canal; and below this a smooth, rounded border, the **arcuate line**, which runs downward, forward, and medialward. Behind the iliac fossa is a rough surface, divided into two



**FIG. 376.**—Right hip bone. Internal surface.

portions, an anterior and a posterior. The **anterior surface** (*auricular surface*), so called from its resemblance in shape to the ear, is coated with cartilage in the recent state, and articulates with a similar surface on the side of the sacrum. The posterior portion, known as the **iliac tuberosity**, is elevated and rough, for the attachment of the posterior sacroiliac ligaments and for the origins of the *Sacrospinalis* and *Multifidus*. Below and in front of the auricular surface is the



**preauricular sulcus**, more commonly present and better marked in the female than in the male; to it is attached the pelvic portion of the anterior sacroiliac ligament.

The **crest** of the ilium is convex in its general outline but is sinuously curved, being concave inward in front, concave outward behind. It is thinner at the centre than at the extremities, and ends in the **anterior** and **posterior superior iliac spines**. The surface of the crest is broad, and divided into external and internal lips, and an intermediate line. About 5 cm. behind the anterior superior iliac spine there is a prominent tubercle on the outer lip. To the external lip are attached the Tensor fasciae latae, Obliquus externus abdominis, and Latissimus dorsi, and along its whole length the fascia lata; to the intermediate line the Obliquus internus abdominis; to the internal lip, the fascia iliaca, the Transversus abdominis, Quadratus lumborum, Sacrospinalis, and Iliacus.

The **anterior border** of the ala is concave. It presents two projections, separated by a notch. Of these, the uppermost, situated at the junction of the crest and anterior border, is called the **anterior superior iliac spine**; its outer border gives attachment to the fascia lata, and the Tensor fasciae latae, its inner border, to the Iliacus; while its extremity affords attachment to the inguinal ligament and gives origin to the Sartorius. Beneath this eminence is a notch from which the Sartorius takes origin and across which the lateral femoral cutaneous nerve passes. Below the notch is the **anterior inferior iliac spine**, which ends in the upper lip of the acetabulum; it gives attachment to the straight tendon of the Rectus femoris and to the iliofemoral ligament of the hip-joint. Medial to the anterior inferior spine is a broad, shallow groove, over which the Iliacus and Psoas major pass. This groove is bounded medially by an eminence, the **iliopectineal eminence**, which marks the point of union of the ilium and pubis.

The **posterior border** of the ala, shorter than the anterior, also presents two projections separated by a notch, the **posterior superior iliac spine** and the **posterior inferior iliac spine**. The former serves for the attachment of the oblique portion of the posterior sacroiliac ligaments and the Multifidus; the latter corresponds with the posterior extremity of the auricular surface. Below the posterior inferior spine is a deep notch, the **greater sciatic notch**.

**The Ischium** (*os ischii*).—The ischium forms the lower and back part of the hip bone. It is divisible into three portions—a **body** and **two rami**.

**The Body** (*corpus oss. ischii*).—The body enters into and constitutes a little more than two-fifths of the acetabulum. Its **external surface** forms part of the lunate surface of the acetabulum and a portion of the acetabular fossa. Its **internal surface** is part of the wall of the lesser pelvis; it gives origin to some fibres of the Obturator internus. Its anterior border projects as the **posterior obturator tubercle**; from its posterior border there extends backward a thin and pointed triangular eminence, the **ischial spine**, more or less elongated in different subjects. The external surface of the spine gives attachment to the Gemellus superior, its internal surface to the Coccygeus, Levator ani, and the pelvic fascia; while to the pointed extremity the sacrospinous ligament is attached. Above the spine is a large notch, the **greater sciatic notch**, converted into a foramen by the sacrospinous ligament; it transmits the Piriformis, the superior and inferior gluteal vessels and nerves, the sciatic and posterior femoral cutaneous nerves, the internal pudendal vessels, and nerve, and the nerves to the Obturator internus and Quadratus femoris. Of these, the superior gluteal vessels and nerve pass out above the Piriformis, the other structures below it. Below the spine is a smaller notch, the **lesser sciatic notch**; it is smooth, coated in the recent state with cartilage, the surface of which presents two or three ridges corresponding to the subdivisions of the tendon of the Obturator internus, which winds over it. It is converted into a foramen by the sacrotuberous and sacrospinous ligaments, and transmits the tendon of the

Obturator internus, the nerve which supplies that muscle, and the internal pudendal vessels and nerve.

**The Superior Ramus** (*ramus superior oss. ischii; descending ramus*).—The superior ramus projects downward and backward from the body and presents for examination three surfaces: external, internal, and posterior. The **external surface** is quadrilateral in shape. It is bounded *above* by a groove which lodges the tendon of the Obturator externus; *below*, it is continuous with the inferior ramus; in *front* it is limited by the posterior margin of the obturator foramen; *behind*, a prominent margin separates it from the posterior surface. In front of this margin the surface gives origin to the Quadratus femoris, and anterior to this to some of the fibres of origin of the Obturator externus; the lower part of the surface gives origin to part of the Adductor magnus. The **internal surface** forms part of the bony wall of the lesser pelvis. In *front* it is limited by the posterior margin of the obturator foramen. *Below*, it is bounded by a sharp ridge which gives attachment to a falciform prolongation of the sacrotuberous ligament, and, more anteriorly, gives origin to the Transversus perinaei and Ischiocavernosus. *Posteriorly* the ramus forms a large swelling, the **tuberosity of the ischium**, which is divided into two portions: a lower, rough, somewhat triangular part, and an upper, smooth, quadrilateral portion. The lower portion is subdivided by a prominent longitudinal ridge, passing from base to apex, into two parts; the outer gives attachment to the Adductor magnus, the inner to the sacrotuberous ligament. The upper portion is subdivided into two areas by an oblique ridge, which runs downward and outward; from the upper and outer area the Semimembranosus arises; from the lower and inner, the long head of the Biceps femoris and the Semitendinosus.

**The Inferior Ramus** (*ramus inferior oss. ischii; ascending ramus*).—The inferior ramus is the thin, flattened part of the ischium, which ascends from the superior ramus, and joins the inferior ramus of the pubis—the junction being indicated in the adult by a raised line. The **outer surface** is uneven for the origin of the Obturator externus and some of the fibres of the Adductor magnus; its **inner surface** forms part of the anterior wall of the pelvis. Its **medial border** is thick, rough, slightly everted, forms part of the outlet of the pelvis, and presents two ridges and an intervening space. The ridges are continuous with similar ones on the inferior ramus of the pubis: to the outer is attached the deep layer of the superficial perineal fascia (*fascia of Colles*), and to the inner the inferior fascia of the urogenital diaphragm. If these two ridges be traced downward, they will be found to join with each other just behind the point of origin of the Transversus perinaei; here the two layers of fascia are continuous behind the posterior border of the muscle. To the intervening space, just in front of the point of junction of the ridges, the Transversus perinaei is attached, and in front of this a portion of the crus penis vel clitoridis and the Ischiocavernosus. Its **lateral border** is thin and sharp, and forms part of the medial margin of the obturator foramen.

**The Pubis** (*os pubis*).—The pubis, the anterior part of the hip bone, is divisible into a **body**, a **superior** and an **inferior ramus**.

**The Body** (*corpus oss. pubis*).—The body forms one-fifth of the acetabulum, contributing by its **external surface** both to the lunate surface and the acetabular fossa. Its **internal surface** enters into the formation of the wall of the lesser pelvis and gives origin to a portion of the Obturator internus.

**The Superior Ramus** (*ramus superior oss. pubis; ascending ramus*).—The superior ramus extends from the body to the median plane where it articulates with its fellow of the opposite side. It is conveniently described in two portions,—viz., a medial flattened part and a narrow lateral prismoid portion.

The **Medial Portion** of the superior ramus, formerly described as the body of the pubis, is somewhat quadrilateral in shape, and presents for examination two surfaces and three borders. The **anterior surface** is rough, directed downward and

outward, and serves for the origin of various muscles. The Adductor longus arises from the upper and medial angle, immediately below the crest; lower down, the Obturator externus, the Adductor brevis, and the upper part of the Gracilis take origin. The **posterior surface**, convex from above downward, concave from side to side, is smooth, and forms part of the anterior wall of the pelvis. It gives origin to the Levator ani and Obturator internus, and attachment to the puboprostatic ligaments and to a few muscular fibres prolonged from the bladder. The **upper border** presents a prominent tubercle, the **pubic tubercle** (*pubic spine*), which projects forward; the inferior crus of the **subcutaneous inguinal ring** (*external abdominal ring*), and the **inguinal ligament** (*Poupart's ligament*) are attached to it. Passing upward and lateralward from the pubic tubercle is a well-defined ridge, forming a part of the pectineal line which marks the brim of the lesser pelvis: to it are attached a portion of the **inguinal falx** (*conjoined tendon of Obliquus internus and Transversus*), the **lacunar ligament** (*Gimbernat's ligament*), and the **reflected inguinal ligament** (*triangular fascia*). Medial to the pubic tubercle is the **crest**, which extends from this process to the medial end of the bone. It affords attachment to the inguinal falx, and to the Rectus abdominis and Pyramidalis. The point of junction of the crest with the medial border of the bone is called the **angle**; to it, as well as to the symphysis, the superior crus of the subcutaneous inguinal ring is attached. The **medial border** is articular; it is oval, and is marked by eight or nine transverse ridges, or a series of nipple-like processes arranged in rows, separated by grooves; they serve for the attachment of a thin layer of cartilage, which intervenes between it and the interpubic fibrocartilaginous lamina. The **lateral border** presents a sharp margin, the **obturator crest**, which forms part of the circumference of the obturator foramen and affords attachment to the obturator membrane.

The **Lateral Portion** of the ascending ramus has three surfaces: superior, inferior, and posterior. The **superior surface** presents a continuation of the pectineal line, already mentioned as commencing at the pubic tubercle. In front of this line, the surface of bone is triangular in form, wider laterally than medially, and is covered by the Pectineus. The surface is bounded, laterally, by a rough eminence, the **iliopectineal eminence**, which serves to indicate the point of junction of the ilium and pubis, and below by a prominent ridge which extends from the acetabular notch to the pubic tubercle. The **inferior surface** forms the upper boundary of the obturator foramen, and presents, laterally, a broad and deep, oblique groove, for the passage of the obturator vessels and nerve; and medially, a sharp margin, the **obturator crest**, forming part of the circumference of the obturator foramen, and giving attachment to the obturator membrane. The **posterior surface** constitutes part of the anterior boundary of the lesser pelvis. It is smooth, convex from above downward, and affords origin to some fibres of the Obturator internus.

The **Inferior Ramus** (*ramus inferior oss. pubis; descending ramus*).—The inferior ramus is thin and flattened. It passes lateralward and downward from the medial end of the superior ramus; it becomes narrower as it descends and joins with the inferior ramus of the ischium below the obturator foramen. Its **anterior surface** is rough, for the origin of muscles—the Gracilis along its medial border, a portion of the Obturator externus where it enters into the formation of the obturator foramen, and between these two, the Adductores brevis and magnus, the former being the more medial. The **posterior surface** is smooth, and gives origin to the Obturator internus, and, close to the medial margin, to the Constrictor urethrae. The **medial border** is thick, rough, and everted, especially in females. It presents two ridges, separated by an intervening space. The ridges extend downward, and are continuous with similar ridges on the inferior ramus of the ischium; to the external is attached the fascia of Colles, and to the internal the inferior fascia of the urogenital diaphragm. The **lateral border** is thin and sharp, forms part of the

circumference of the obturator foramen, and gives attachment to the obturator membrane.

**The Acetabulum** (*cotyloid cavity*).—The acetabulum is a deep, cup-shaped, hemispherical depression, directed downward, lateralward, and forward. It is formed medially by the pubis, above by the ilium, laterally and below by the ischium; a little less than two-fifths is contributed by the ilium, a little more than two-fifths by the ischium, and the remaining fifth by the pubis. It is bounded by a prominent uneven rim, which is thick and strong above, and serves for the attachment of the **glenoidal labrum** (*cotyloid ligament*), which contracts its orifice, and deepens the surface for articulation. It presents below a deep notch, the **acetabular notch**, which is continuous with a circular non-articular depression, the **acetabular fossa**, at the bottom of the cavity: this depression is perforated by numerous apertures, and lodges a mass of fat. The notch is converted into a foramen by the transverse ligament; through the foramen nutrient vessels and nerves enter the joint; the margins of the notch serve for the attachment of the *ligamentum teres*. The rest of the acetabulum is formed by a curved articular surface, the **lunate surface**, for articulation with the head of the femur.

By eight centres { Three primary (Ilium, Ischium, and Pubis)  
Five secondary



FIG. 377.—Plan of ossification of the hip bone. The three primary centres unite through a Y-shaped piece about puberty. Epiphyses appear about puberty, and unite about twenty-fifth year.

**The Obturator Foramen** (*foramen obturatum; thyroid foramen*).—The obturator foramen is a large aperture, situated between the ischium and pubis. In the male it is large and of an oval form, its longest diameter slanting from before backward; in the female it is smaller, and more triangular. It is bounded by a thin, uneven margin, to which a strong membrane is attached, and presents, superiorly, a deep groove, the **obturator groove**, which runs from the pelvis obliquely medialward and downward. This groove is converted into a canal by a ligamentous band, a specialized part of the obturator membrane, attached to two tubercles: one, the **posterior obturator tubercle**, on the medial border of the ischium, just in front of the acetabular notch; the other, the **anterior obturator tubercle**, on the

obturator crest of the superior ramus of the pubis. Through the canal the obturator vessels and nerve pass out of the pelvis.

**Structure.**—The thicker parts of the bone consist of cancellous tissue, enclosed between two layers of compact tissue; the thinner parts, as at the bottom of the acetabulum and centre of the iliac fossa, are usually semitransparent, and composed entirely of compact tissue.

**Ossification** (Fig. 377).—The hip bone is ossified from *eight* centres: *three* primary—one each for the ilium, ischium, and pubis; and *five* secondary—one each for the crest of the ilium, the anterior inferior spine (said to occur more frequently in the male than in the female), the tuberosity of the ischium, the pubic symphysis (more frequent in the female than in the male), and one or more for the Y-shaped piece at the bottom of the acetabulum. The centres appear in the following order: in the lower part of the ilium, immediately above the greater sciatic notch, about the eighth or ninth week of fetal life; in the superior ramus of the ischium, about the third month; in the superior ramus of the pubis, between the fourth and fifth months. At birth, the three primary centres are quite separate, the crest, the bottom of the acetabulum, the ischial tuberosity, and the inferior rami of the ischium and pubis being still cartilaginous. By the seventh or eighth year, the inferior rami of the pubis and ischium are almost completely united by bone. About the thirteenth or fourteenth year, the three primary centres have extended their growth into the bottom of the acetabulum, and are there separated from each other by a Y-shaped portion of cartilage, which now presents traces of ossification, often by two or more centres. One of these, the *os acetabuli*, appears about the age of twelve, between the ilium and pubis, and fuses with them about the age of eighteen; it forms the pubic part of the acetabulum. The ilium and ischium then become joined, and lastly the pubis and ischium, through the intervention of this Y-shaped portion. At about the age of puberty, ossification takes place in each of the remaining portions, and they join with the rest of the bone between the twentieth and twenty-fifth years. Separate centres are frequently found for the pubic tubercle and the ischial spine, and for the crest and angle of the pubis.

**Articulations.**—The hip bone articulates with its fellow of the opposite side, and with the sacrum and femur.

### The Pelvis.

The **pelvis**, so called from its resemblance to a basin, is a bony ring, interposed between the movable vertebræ of the vertebral column which it supports, and the lower limbs upon which it rests; it is stronger and more massively constructed than the wall of the cranial or thoracic cavities, and is composed of four bones: the two **hip bones** laterally and in front and the **sacrum** and **coccyx** behind.

The pelvis is divided by an oblique plane passing through the prominence of the sacrum, the arcuate and pectineal lines, and the upper margin of the symphysis pubis, into the greater and the lesser pelvis. The circumference of this plane is termed the **linea terminalis** or **pelvic brim**.

**The Greater or False Pelvis** (*pelvis major*).—The greater pelvis is the expanded portion of the cavity situated above and in front of the pelvic brim. It is bounded on either side by the ilium; in *front* it is incomplete, presenting a wide interval between the anterior borders of the ilia, which is filled up in the recent state by the parietes of the abdomen; behind is a deep notch on either side between the ilium and the base of the sacrum. It supports the intestines, and transmits part of their weight to the anterior wall of the abdomen.

**The Lesser or True Pelvis** (*pelvis minor*).—The lesser pelvis is that part of the pelvic cavity which is situated below and behind the pelvic brim. Its bony walls are more complete than those of the greater pelvis. For convenience of description, it is divided into an **inlet** bounded by the superior circumference, and **outlet** bounded by the inferior circumference, and a **cavity**.

**The Superior Circumference.**—The superior circumference forms the brim of the pelvis, the included space being called the **superior aperture** or **inlet** (*apertura pelvis [minoris] superior*) (Fig. 378). It is formed laterally by the pectineal and arcuate lines, in front by the crests of the pubes, and behind by the anterior margin of the base of the sacrum and sacrovertebral angle. The superior aperture is somewhat heart-shaped, obtusely pointed in front, diverging on either side, and encroached upon behind by the projection forward of the promontory of the sacrum. It has

three principal diameters: antero-posterior, transverse, and oblique. The **antero-posterior or conjugate diameter** extends from the sacrovertebral angle to the symphysis pubis; its average measurement is about 110 mm. in the female. The **transverse diameter** extends across the greatest width of the superior aperture, from the middle of the brim on one side to the same point on the opposite; its average measurement is about 135 mm. in the female. The **oblique diameter** extends from the iliopectineal eminence of one side to the sacroiliac articulation of the opposite side; its average measurement is about 125 mm. in the female




FIG. 378.—Diameters of superior aperture of lesser pelvis (female).

The **cavity** of the lesser pelvis is bounded in front and below by the pubic symphysis and the superior rami of the pubes; above and behind, by the pelvic surfaces of the sacrum and coccyx, which, curving forward above and below, contract the superior and inferior apertures of the cavity; laterally, by a broad, smooth, quadrangular area of bone, corresponding to the inner surfaces of the body and superior ramus of the ischium and that part of the ilium which is below the arcuate line. From this description it will be seen that the cavity of the lesser pelvis is a short, curved canal, considerably deeper on its posterior than on its anterior wall. It contains, in the recent subject, the pelvic colon, rectum, bladder, and some of the organs of generation. The rectum is placed at the back of the pelvis, in the curve of the sacrum and coccyx; the bladder is in front, behind the pubic symphysis. In the female, the uterus and vagina occupy the interval between these viscera.

**The Lower Circumference.**—The lower circumference of the pelvis is very irregular; the space enclosed by it is named the **inferior aperture or outlet** (*apertura pelvis [minoris] inferior*) (Fig. 379), and is bounded behind by the point of the coccyx, and laterally by the ischial tuberosities. These eminences are separated by three notches: one in front, the **pubic arch**, formed by the convergence of the inferior rami of the ischium and pubis on either side. The other notches, one on either side, are formed by the sacrum and coccyx behind, the ischium in front, and the ilium above; they are called the **sciatic notches**; in the natural state they are converted into foramina by the sacrotuberous and sacrospinous ligaments. When the ligaments are *in situ*, the inferior aperture of the pelvis is lozenge-shaped, bounded, in front, by the pubic arcuate ligament and the inferior rami of the pubes and ischia; laterally, by the ischial tuberosities; and behind, by the sacrotuberous ligaments and the tip of the coccyx.



The diameters of the outlet of the pelvis are two, antero-posterior and transverse. The **antero-posterior diameter** extends from the tip of the coccyx to the lower part of the pubic symphysis; its measurement is from 90 to 115 mm. in the female. It varies with the length of the coccyx, and is capable of increase or diminution, on account of the mobility of that bone. The **transverse diameter**, measured between the posterior parts of the ischial tuberosities, is about 115 mm. in the female.<sup>1</sup>




FIG. 379.—Diameters of inferior aperture of lesser pelvis (female).

**Axes** (Fig. 380).—A line at right angles to the plane of the superior aperture at its centre would, if prolonged, pass through the umbilicus above and the middle of the coccyx below; the axis of the superior aperture is therefore directed downward and backward. The axis of the inferior aperture, produced upward, would touch the base of the sacrum, and is also directed downward, and slightly backward. The axis of the cavity—*i. e.*, an axis at right angles to a series of planes between those of the superior and inferior apertures—is curved like the cavity itself: this curve corresponds to the concavity of the sacrum and coccyx, the extremities being indicated by the central points of the superior and inferior apertures. A knowledge of the direction of these axes serves to explain the course of the fetus in its passage through the pelvis during parturition.




FIG. 380.—Median sagittal section of pelvis.

**Position of the Pelvis** (Fig. 380).—In the erect posture, the pelvis is placed obliquely with regard to the trunk: the plane of the superior aperture forms an angle of from  $50^{\circ}$  to  $60^{\circ}$ , and that of the inferior aperture one of about  $15^{\circ}$  with the horizontal plane. The pelvic surface of the symphysis pubis looks upward and backward, the concavity of the sacrum and coccyx downward and forward. The position of the pelvis in the erect posture may be indicated by holding it so that the anterior superior iliac spines and the front of the top of the symphysis pubis are in the same vertical plane.

<sup>1</sup> The measurements of the pelvis given above are fairly accurate, but different figures are given by various authors no doubt due mainly to differences in the physique and stature of the population from whom the measurements have been taken.

**Differences between the Male and Female Pelves.**—The *female* pelvis (Fig. 382) is distinguished from that of the *male* (Fig. 381) by its bones being more delicate and its depth less. The whole pelvis is less massive, and its muscular




FIG. 381.—Male pelvis.

impressions are slightly marked. The ilia are less sloped, and the anterior iliac spines more widely separated; hence the greater lateral prominence of the hips. The preauricular sulcus is more commonly present and better marked. The supe-




FIG. 382.—Female pelvis.

rior aperture of the lesser pelvis is larger in the female than in the male; it is more nearly circular, and its obliquity is greater. The cavity is shallower and wider; the sacrum is shorter, wider, and its upper part is less curved; the obturator

foramina are triangular in shape and smaller in size than in the male. The inferior aperture is larger and the coccyx more movable. The sciatic notches are wider and shallower, and the spines of the ischia project less inward. The acetabula are smaller and look more distinctly forward (Derry<sup>1</sup>). The ischial tuberosities and the acetabula are wider apart, and the former are more everted. The pubic symphysis is less deep, and the pubic arch is wider and more rounded than in the male, where it is an angle rather than an arch.

The size of the pelvis varies not only in the two sexes, but also in different members of the same sex, and does not appear to be influenced in any way by the height of the individual. Women of short stature, as a rule, have broad pelves. Occasionally the pelvis is equally contracted in all its dimensions, so much so that all its diameters measure 12.5 mm. less than the average, and this even in well-formed women of average height. The principal divergences, however, are found at the superior aperture, and affect the relation of the antero-posterior to the transverse diameter. Thus the superior aperture may be elliptical either in a transverse or an antero-posterior direction, the transverse diameter in the former, and the antero-posterior in the latter, greatly exceeding the other diameters; in other instances it is almost circular.

In the fœtus, and for several years after birth, the pelvis is small in proportion to that of the adult, and the projection of the sacrovertebral angle less marked. The characteristic differences between the male and female pelvis are distinctly indicated as early as the fourth month of fetal life.

**Applied Anatomy.**—There is arrest of development in the bones of the pelvis in cases of extroversion of the bladder; the anterior part of the pelvic girdle is deficient, the superior rami of the pubes are imperfectly developed, and the symphysis is absent. "The pubic bones are separated to the extent of from two to four inches, the superior rami shortened and directed forward, and the obturator foramen diminished in size, narrowed, and turned outward. The iliac bones are straightened out more than normal. The sacrum is very peculiar. The lateral curve, instead of being concave, is flattened out or even convex, with the iliosacral facets turned more outward than normal, while the vertical curve is straightened."<sup>2</sup>

Fractures of the pelvis are divided into those of the greater and those of the lesser pelvis. Fractures of the greater pelvis vary in extent; a small portion of the crest may be broken, or one of the spinous processes may be torn off, or the bone may be extensively comminuted. This latter accident is the result of some crushing violence, and may be complicated with fracture of the lesser pelvis. These cases may be accompanied by injury to the intestine as it lies in the hollow of the bone, or to the iliac vessels as they course along the margin of the lesser pelvis. A fracture of the lesser pelvis generally occurs through the superior ramus of the pubis and the inferior ramus of the ischium, as these are the weakest parts of the bony ring, and may be caused either by crushing violence applied in an antero-posterior direction, when the fracture occurs from direct force, or by compression laterally, when the acetabula are pressed together and the bone gives way in the same place from indirect violence. Sometimes both sides of the pelvis are fractured, and it is in these cases that the contained viscera are likely to be injured: the urethra, the bladder, the rectum, the small intestines, the vagina, and even the uterus, have all been lacerated by displaced fragments. Fractures of the acetabulum are occasionally met with; either a portion of the rim may be broken off, or a fracture may take place through the bottom of the cavity, and the head of the femur be driven into the pelvic cavity. Separation of the Y-shaped cartilage at the bottom of the acetabulum may also occur in the young subject, splitting the bone into its three portions.

The coccyx is not infrequently displaced forward to nearly a right angle with the sacrum by a kick or by a fall backward. The condition is attended with great pain in walking and on making any expiratory effort, such as coughing, defecation, etc., because the Coccygei and Levatores ani which form the pelvic diaphragm are attached to this bone. Such injuries often give rise to severe persistent pain, which is exceedingly intractable and difficult of cure. The condition is known as *coccygodynia* and for its relief removal of the coccyx has been practised.

The pelvic bones often undergo important deformity in *rickets*, the effects of which in the adult woman may interfere seriously with child-bearing. The deformity is due mainly to the weight of the trunk, which presses on the sacrovertebral angle and greatly increases it, so that the antero-posterior diameter of the pelvis is diminished, and may measure as little as 40 mm.,

<sup>1</sup> Journal of Anatomy and Physiology, vol. xliii.

<sup>2</sup> Wood, Heath's Dictionary of Practical Surgery, i, 426.

the entrance into the pelvis becoming reniform. In other cases all the pelvic bones give way, so that a general diminution in all the diameters of the pelvis results, the pelvic entrance becoming triangular or asymmetrical. If the pubic symphysis be forced forward, the rickety pelvis may even come to resemble closely the deformed pelvis of *osteomalacia*; in this disease the weight of the trunk causes an increase in the sacrovertebral angle, and a lessening of the antero-posterior diameter of the superior aperture, and at the same time the pressure of the heads of the femora on the acetabula causes these cavities, with the adjacent bone, to be pushed upward and backward, so that the oblique diameters of the pelvis are also diminished, and the cavity of the pelvis assumes a triradiate shape, with the symphysis pubis pushed forward.

### The Femur (Thigh Bone).

The **femur** (Figs. 384, 385), the longest and strongest bone in the skeleton, is almost perfectly cylindrical in the greater part of its extent. In the erect posture it is not vertical, being separated above from its fellow by a considerable interval, which corresponds to the breadth of the pelvis, but inclining gradually downward and medialward, so as to approach its fellow toward its lower part, for the purpose of bringing the knee-joint near the line of gravity of the body. The degree of this inclination varies in different persons, and is greater in the female than in the male, on account of the greater breadth of the pelvis. The femur, like other long bones, is divisible into a **body** and **two extremities**.




FIG. 383.—Upper extremity of right femur viewed from behind and above.

**The Upper Extremity** (*proximal extremity*, Fig. 383).—The upper extremity presents for examination a **head**, a **neck**, a **greater** and a **lesser trochanter**.

**The Head** (*caput femoris*).—The head which is globular and forms rather more than a hemisphere, is directed upward, medialward, and a little forward, the greater part of its convexity being above and in front. Its surface is smooth, coated with cartilage in the recent state, except over an ovoid depression, the **fovea capitis femoris**, which is situated a little below and behind the centre of the head, and gives attachment to the ligamentum teres.

**The Neck** (*collum femoris*).—The neck is a flattened pyramidal process of bone, connecting the head with the body, and forming with the latter a wide angle opening medialward. The angle is widest in infancy, and becomes lessened during growth, so that at puberty it forms a gentle curve from the axis of the body of the bone. In the adult, the neck forms an angle of about  $125^\circ$  with the body, but this varies in inverse proportion to the development of the pelvis and the stature. In




FIG. 384.—Right femur. Anterior surface.

the female, in consequence of the increased width of the pelvis, the neck of the femur forms more nearly a right angle with the body than it does in the male. The angle decreases during the period of growth, but after full growth has been attained it does not usually undergo any change, even in old age; it varies considerably in different persons of the same age. It is smaller in short than in long bones, and when the pelvis is wide. In addition to projecting upward and medialward from the body of the femur, the neck also projects somewhat forward; the amount of this forward projection is extremely variable, but on an average is from  $12^{\circ}$  to  $14^{\circ}$ .

The neck is flattened from before backward, contracted in the middle, and broader laterally than medially. The vertical diameter of the lateral half is increased by the obliquity of the lower edge, which slopes downward to join the body at the level of the lesser trochanter, so that it measures one-third more than the antero-posterior diameter. The medial half is smaller and of a more circular shape. The **anterior surface** of the neck is perforated by numerous vascular foramina. Along the upper part of the line of junction of the anterior surface with the head is a shallow groove, best marked in elderly subjects; this groove lodges the orbicular fibres of the capsule of the hip-joint. The **posterior surface** is smooth, and is broader and more concave than the anterior: the posterior part of the capsule of the hip-joint is attached to it about 1 cm. above the intertrochanteric crest. The **superior border** is short and thick, and ends laterally at the greater trochanter; its surface is perforated by large foramina. The **inferior border**, long and narrow, curves a little backward, to end at the lesser trochanter.

**The Trochanters.**—The trochanters are prominent processes which



afford leverage to the muscles that rotate the thigh on its axis. They are two in number, the greater and the lesser.

The **Greater Trochanter** (*trochanter major; great trochanter*) is a large, irregular, quadrilateral eminence, situated at the junction of the neck with the upper part of the body. It is directed a little lateralward and backward, and, in the adult, is about 1 cm. lower than the head. It has two surfaces and four borders. The **lateral surface**, quadrilateral in form, is broad, rough, convex, and marked by a diagonal impression, which extends from the postero-superior to the antero-inferior angle, and serves for the insertion of the tendon of the Glutaeus medius. Above the impression is a triangular surface, sometimes rough for part of the tendon of the same muscle, sometimes smooth for the interposition of a bursa between the tendon and the bone. Below and behind the diagonal impression is a smooth, triangular surface, over which the tendon of the Glutaeus maximus plays, a bursa being interposed. The **medial surface**, of much less extent than the lateral, presents at its base a deep depression, the **trochanteric fossa** (*digital fossa*), for the insertion of the tendon of the Obturator externus, and above and in front of this an impression for the insertion of the Obturator internus and Gemelli. The **superior border** is free; it is thick and irregular, and marked near the centre by an impression for the insertion of the Piriformis. The **inferior border** corresponds to the line of junction of the base of the trochanter with the lateral surface of the body; it is marked by a rough, prominent, slightly curved ridge, which gives origin to the upper part of the Vastus lateralis. The **anterior border** is prominent and some-




FIG. 385.—Right femur. Posterior surface.



what irregular; it affords insertion at its lateral part to the *Glutaeus minimus*. The **posterior border** is very prominent and appears as a free, rounded edge, which bounds the back part of the trochanteric fossa.

The **Lesser Trochanter** (*trochanter minor; small trochanter*) is a conical eminence, which varies in size in different subjects; it projects from the lower and back part of the base of the neck. From its apex three well-marked borders extend; two of these are above—a **medial** continuous with the lower border of the neck, a **lateral** with the intertrochanteric crest; the **inferior border** is continuous with the middle division of the *linea aspera*. The **summit** of the trochanter is rough, and gives insertion to the tendon of the *Psoas major*.

A prominence, of variable size, occurs at the junction of the upper part of the neck with the greater trochanter, and is called the **tubercle of the femur**; it is the point of meeting of five muscles: the *Glutaeus minimus* laterally, the *Vastus lateralis* below, and the tendon of the *Obturator internus* and two *Gemelli* above. Running obliquely downward and medialward from the tubercle is the **intertrochanteric line** (*spiral line of the femur*); it winds around the medial side of the body of the bone, below the lesser trochanter, and ends about 5 cm. below this eminence in the *linea aspera*. Its upper half is rough, and affords attachment to the ilio-femoral ligament of the hip-joint; its lower half is less prominent, and gives origin to the upper part of the *Vastus medialis*. Running obliquely downward and medialward from the summit of the greater trochanter on the posterior surface of the neck is a prominent ridge, the **intertrochanteric crest**. Its upper half forms the posterior border of the greater trochanter, and its lower half runs downward and medialward to the lesser trochanter. A slight ridge is sometimes seen commencing about the middle of the intertrochanteric crest, and reaching vertically downward for about 5 cm. along the back part of the body: it is called the **linea quadrata**, and gives attachment to the *Quadratus femoris* and a few fibres of the *Adductor magnus*. Generally there is merely a slight thickening about the middle of the intertrochanteric crest, marking the attachment of the upper part of the *Quadratus femoris*.

**The Body or Shaft** (*corpus femoris*).—The body, almost cylindrical in form, is a little broader above than in the centre, broadest and somewhat flattened from before backward below. It is slightly arched, so as to be convex in front, and concave behind, where it is strengthened by a prominent longitudinal ridge, the **linea aspera**. It presents for examination three borders, separating three surfaces. Of the three borders, one, the *linea aspera*, is posterior, one is medial, and the other, lateral.

The **linea aspera** (Fig. 385) is a prominent longitudinal ridge or crest, on the middle third of the bone, presenting a medial and a lateral lip, and a narrow rough, intermediate line. Above, the *linea aspera* is prolonged by three ridges. The lateral ridge is very rough, and runs almost vertically upward to the base of the greater trochanter. It is termed the **gluteal tuberosity**, and gives attachment to part of the *Glutaeus maximus*: its upper part is often elongated into a roughened crest, on which a more or less well-marked, rounded tubercle, the **third trochanter**, is occasionally developed. The intermediate ridge or **pectineal line** is continued to the base of the lesser trochanter and gives attachment to the *Pectineus*; the medial ridge is lost in the intertrochanteric line; between these two a portion of the *Iliacus* is inserted. Below, the *linea aspera* is prolonged into two ridges, enclosing between them a triangular area, the **popliteal surface**, upon which the popliteal artery rests. Of these two ridges, the lateral is the more prominent, and descends to the summit of the lateral condyle. The medial is less marked, especially at its upper part, where it is crossed by the femoral artery. It ends below at the summit of the medial condyle, in a small tubercle, the **adductor tubercle**, which affords insertion to the tendon of the *Adductor magnus*.

From the **medial lip** of the linea aspera and its prolongations above and below, the Vastus medialis arises; and from the **lateral lip** and its upward prolongation, the Vastus lateralis takes origin. The Adductor magnus is inserted into the linea aspera, and to its lateral prolongation above, and its medial prolongation below. Between the Vastus lateralis and the Adductor magnus two muscles are attached—viz., the Gluteus maximus inserted above, and the short head of the Biceps femoris arising below. Between the Adductor magnus and the Vastus medialis four muscles are inserted: the Iliacus and Pectineus above; the Adductor brevis and Adductor longus below. The linea aspera is perforated a little below its centre by the nutrient canal, which is directed obliquely upward.

The other two *borders* of the femur are only slightly marked: the **lateral border** extends from the antero-inferior angle of the greater trochanter to the anterior extremity of the lateral condyle; the **medial border** from the intertrochanteric line, at a point opposite the lesser trochanter, to the anterior extremity of the medial condyle.

The **anterior surface** includes that portion of the shaft which is situated between the lateral and medial borders. It is smooth, convex, broader above and below than in the centre. From the upper three-fourths of this surface the Vastus intermedius arises; the lower fourth is separated from the muscle by the intervention of the synovial membrane of the knee-joint and a bursa; from the upper part of it the Articularis genu takes origin. The **lateral surface** includes the portion between the lateral border and the linea aspera; it is continuous above with the corresponding surface of the greater trochanter, below with that of the lateral condyle: from its upper three-fourths the Vastus intermedius takes origin. The **medial surface** includes the portion between the medial border and the linea aspera; it is continuous above with the lower border of the neck, below with the medial side of the medial condyle: it is covered by the Vastus medialis.




FIG. 386.—Lower extremity of right femur viewed from below.

**The Lower Extremity** (*distal extremity*, Fig. 386).—The lower extremity, larger than the upper, is somewhat cuboid in form, but its transverse diameter is greater than its antero-posterior; it consists of two oblong eminences known as the **condyles**. In front, the condyles are but slightly prominent, and are separated from one another by a smooth shallow articular depression called the **patellar surface**; behind, they project considerably, and the interval between them forms a deep notch, the **intercondyloid fossa**. The **lateral condyle** is the more prominent and is the broader both in its antero-posterior and transverse diameters, the **medial condyle** is the longer and, when the femur is held with its body perpendicular, projects to a lower level. When, however, the femur is in its natural oblique position the lower surfaces of the two condyles lie practically in the same horizontal plane. The condyles are not quite parallel with one another; the long axis of the lateral is almost

directly antero-posterior, but that of the medial runs backward and medialward. Their opposed surfaces are small, rough, and concave, and form the walls of the intercondyloid fossa. This fossa is limited above by a ridge, the **intercondyloid line**, and below by the central part of the posterior margin of the patellar surface. The posterior cruciate ligament of the knee-joint is attached to the lower and front part of the medial wall of the fossa and the anterior cruciate ligament to an impression on the upper and back part of its lateral wall. Each condyle is surmounted by an elevation, the epicondyle. The **medial epicondyle** is a large convex eminence to which the tibial collateral ligament of the knee-joint is attached. At its upper part is the adductor tubercle, already referred to, and behind it is a rough impression which gives origin to the medial head of the Gastrocnemius. The **lateral epicondyle**, smaller and less prominent than the medial, gives attachment to the fibular collateral ligament of the knee-joint. Directly below it is a small depression from which a smooth well-marked groove curves obliquely upward and backward to the posterior extremity of the condyle. This groove is separated from the articular surface of the condyle by a prominent lip across which a second, shallower groove runs vertically downward from the depression. In the recent state these grooves are covered with cartilage. The Popliteus arises from the depression; its tendon lies in the oblique groove when the knee is flexed and in the vertical groove when the knee is extended. Above and behind the lateral epicondyle is an area for the origin of the lateral head of the Gastrocnemius, above and to the medial side of which the Plantaris arises.

The **articular surface** of the lower end of the femur occupies the anterior, inferior, and posterior surfaces of the condyles. Its front part is named the **patellar surface** and articulates with the patella; it presents a median groove which extends downward to the intercondyloid fossa and two convexities, the lateral of which is broader, more prominent, and extends farther upward than the medial. The lower and posterior parts of the articular surface constitute the **tibial surfaces** for articulation with the corresponding condyles of the tibia and menisci. These surfaces are separated from one another by the intercondyloid fossa and from the patellar surface by faint grooves which extend obliquely across the condyles. The lateral groove is the better marked; it runs lateralward and forward from the front part of the intercondyloid fossa, and expands to form a triangular depression. When the knee-joint is fully extended, the triangular depression rests upon the anterior portion of the lateral meniscus, and the medial part of the groove comes into contact with the medial margin of the lateral articular surface of the tibia in front of the lateral tubercle of the tibial intercondyloid eminence. The medial groove is less distinct than the lateral. It does not reach as far as the intercondyloid fossa and therefore exists only on the medial part of the condyle; it receives the anterior edge of the medial meniscus when the knee-joint is extended. Where the groove ceases laterally the patellar surface is seen to be continued backward as a semilunar area close to the anterior part of the intercondyloid fossa; this semilunar area articulates with the medial vertical facet of the patella in forced flexion of the knee-joint. The tibial surfaces of the condyles are convex from side to side and from before backward. Each presents a double curve, its posterior segment being an arc of a circle, its anterior, part of a cycloid.<sup>1</sup>

**Structure.**—The body of the femur is a cylinder of compact tissue, hollowed by a large medullary canal. The wall of the cylinder is of great thickness and density in the middle third of the body, where the bone is narrowest and the medullary canal best formed; but above and below this the wall becomes thinner, while the medullary canal is gradually filled up by cancellous tissue, so that the upper (Fig. 387) and lower ends of the body, and the articular extremities more especially, consist of cancellous tissue, invested by a thin compact layer.

<sup>1</sup> A *cycloid* is a curve traced by a point in the circumference of a wheel when the wheel is rolled along in a straight line.

The cancelli in the ends of the femur are disposed along the lines of greatest pressure and tension. In the upper end (Fig. 388) the chief lamellæ are arranged in the following manner. A series of bony planes at right angles to the articular surface of the head converge to a central



FIG. 387.—Longitudinal section of head and neck of femur.

dense wedge, which presents few and dense cancelli. The wedge is supported by strong lamellæ, which extend to the sides of the neck and are especially marked along its upper and lower borders. Any force therefore applied to the head of the femur is transmitted directly to the central wedge and thence to the junction of the neck with the body. This junction is especially strengthened by a series of dense lamellæ which extend from the lesser trochanter to the lateral end of the superior border of the neck; this arrangement will obviously oppose considerable resistance to either tensile or shearing force. A smaller bar stretching across the junction of the greater trochanter with the neck and body resists the shearing force of the muscles attached to this prominence. These two bars, one at the junction of body and neck, the other at the junction of body and greater trochanter, form the upper layers of a series of arches which extend across between the sides of the body and transmit to the body forces applied to the upper end of the bone. In the cancellous tissue of the neck is a thin vertical plate of bone, the *calcar femorale*, which springs from the compact wall of the body in the region of the linea aspera. Medially it is attached to the interior surface of the posterior wall of the neck of the bone; laterally it continues the plane of the posterior wall of the neck into the greater trochanter where it shades off into the general cancellous tissue. It is thus situated in a plane anterior to the intertrochanteric crest and to the base of the lesser trochanter (Fig. 389).




FIG. 388.—Scheme showing disposition of principal cancellous lamellæ in upper extremity of femur.

In the lower end, the cancelli spring on all sides from the inner surface of the cylinder, and descend in a perpendicular direction to the articular surface, the cancelli being strongest and having a more accurately perpendicular course above the condyles. In addition to this, there



are horizontal planes of cancellous tissue, so that the spongy tissue in this situation presents an appearance of being mapped out into a series of cubical areas.

**Articulations.**—The femur articulates with *three* bones: the hip bone, tibia, and patella.

**Ossification** (Figs. 390, 391, 392).—The femur is ossified from *five* centres: one for the body, one for the head, one for each trochanter, and one for the lower extremity. Of all the long bones, except the clavicle, it is the first to show traces of ossification; this commences in the middle of the body, at about the seventh week of fetal life, and rapidly extends upward and downward. The centres in the epiphyses appear in the following order: in the lower end of the bone, at the ninth month of fetal life (from this centre the condyles and epicondyles are formed); in the head, at the end of the first year after birth; in the greater trochanter, during the fourth year; and in the lesser trochanter, between the thirteenth and fourteenth years. The order in which the epiphyses are joined to the body is the reverse of that of their appearance; they are not united until after puberty, the lesser trochanter being first joined, then the greater, then the head, and, lastly, the inferior extremity, which is not united until the twentieth year.




FIG. 389.—Oblique section of upper extremity of femur showing calcar femorale.




FIG. 390.—Plan of ossification of the femur. From five centres.

**Applied Anatomy.**—The lower end of the femur is the only epiphysis in which ossification has commenced at the time of birth. The presence of this ossific centre is, therefore, a proof, in a newly born child found dead, that the child has arrived at the full period of uterogestation, and is always relied upon in medicolegal investigations. The position of the epiphysial plate should be carefully noted. It is on a level with the adductor tubercle, and the epiphysis does not, therefore, form the whole of the cartilage-clad portion of the lower end of the bone. It is essential to bear this point in mind in performing excision of the knee, since growth in length of the femur takes place chiefly from the lower epiphysis, and any interference with the epiphysial cartilage in a young child would involve such ultimate shortening of the limb, from want of growth, as to render the limb almost useless. Separation of the lower epiphysis may take place up to the age

of twenty, at which time it becomes completely joined to the body of the bone; but, as a matter of fact, few cases occur after the age of sixteen or seventeen. The epiphysis of the head of the femur is the seat of origin, in a large number of cases, of tuberculous disease of the hip-joint. In the majority of cases the disease begins in the highly vascular and growing tissue at the end of the body in the neighborhood of the epiphysial cartilage, and extends into the joint. The epiphysis for the head is entirely intracapsular.

Fractures of the femur are divided, like those of the other long bones, into fractures of the upper end; of the body; and of the lower end. The fractures of the upper end may be classified into (1) fracture of the neck; (2) fracture at the junction of the neck with the greater trochanter; (3) fracture of the greater trochanter; and (4) separation of the epiphysis, either of the head or of the greater trochanter. The first of these, fracture of the neck, is usually termed *intracapsular* fracture, but this is scarcely a correct designation, as, owing to the attachment of the articular capsule, the fracture is partly within and partly without the capsule when the fracture occurs at the lower part of the neck. It generally takes place in old people, principally women, and




FIG. 391.—Epiphysial lines of femur in a young adult. Anterior aspect. The lines of attachment of the articular capsules are in blue.




FIG. 392.—Epiphysial lines of femur in a young adult. Posterior aspect. The lines of attachment of the articular capsules are in blue.

usually from a very slight degree of indirect violence. Probably the main cause of its occurrence in old people is the senile degenerative change which takes place in the bone. Merkel believes that it is mainly due to the absorption of the *calcar femorale*. As a rule the fragments become united by fibrous tissue, but frequently no union takes place, and the opposed surfaces become smooth and eburnated.

Fractures at the junction of the neck with the greater trochanter are usually termed *extra-capsular*, but this designation is also incorrect, as the fracture is partly within the capsule, owing to its attachment in front to the intertrochanteric line, which is situated below the line of fracture. These fractures are produced by direct violence to the greater trochanter, as from a fall laterally on the hip. From the manner in which the accident is caused the neck of the bone is driven into the trochanter, where it may remain impacted, or the trochanter may be split into two or more fragments, disimpaction resulting.

Fractures of the body may occur at any part, but the most usual situation is at or near the centre of the bone. They may be caused by direct or indirect violence. Fractures of the upper third of the body are almost always the result of indirect violence, while those of the lower third



are the result, for the most part, of direct violence. Fractures of the body are generally oblique, but they may be transverse, longitudinal, or spiral. The transverse fracture occurs most frequently in children. The fractures of the lower end of the femur include transverse fracture above the condyles, the most common; and this may be complicated by a vertical fracture between the condyles, constituting the T-shaped fracture. In these cases the popliteal artery is in danger of being wounded. Oblique fracture separating either the medial or lateral condyle, and a longitudinal incomplete fracture between the condyles, may also take place.

The femur as well as the other bones of the leg is frequently the seat of acute osteomyelitis in children. This is no doubt due to their greater exposure to injury, which is often the exciting cause of this disease. Necrosis of portions of the diaphysis frequently ensues, especially in the region of the popliteal surface of the femur, and the disease may continue for years, great trouble being experienced with discharging sinuses which periodically close and reopen to allow of the exit of a piece of dead bone.

Tumors are not infrequently found growing from the femur: the most common forms being sarcoma which may grow either from the periosteum or from the medullary tissue within the interior of the bone, and exostosis which commonly originates in the neighborhood of the epiphysal cartilage of the lower end. The periosteal sarcomata of the femur and most of the central growths are usually of a very high degree of malignancy, although the "myeloid" growth, which is of but low malignancy, may also be found. The region of the lower epiphysal line is by far the commoner seat for all these tumors, and it should be noted that the lower epiphysis has the longest period of active growth, and that these tumors usually appear toward the end of the period of active growth of the bone.

Sarcomata about the upper end of the femur are seen occasionally, but very rarely in comparison with those at the lower end. Secondary carcinoma also occurs in this bone, most commonly due to a primary focus in the breast, and spontaneous fracture of the bone may take place in these cases.

### The Patella (Knee Cap).

The **patella** (Figs. 393, 394) is a flat, triangular bone, situated on the front of the knee-joint. It is usually regarded as a sesamoid bone, developed in the tendon of the Quadriceps femoris, and resembles these bones (1) in being developed in a tendon; (2) in its centre of ossification presenting a knotty or tuberculated outline; (3) in being composed mainly of dense cancellous tissue. It serves to protect the front of the joint, and increases the leverage of the Quadriceps femoris by making it act at a greater angle. It has an anterior and a posterior surface three borders, and an apex.



FIG. 393.—Right patella.  
Anterior surface.



FIG. 394.—Right patella.  
Posterior surface.

**Surfaces.**—The **anterior surface** is convex, perforated by small apertures for the passage of nutrient vessels, and marked by numerous rough, longitudinal striæ. This surface is covered, in the recent state, by an expansion from the tendon of the Quadriceps femoris, which is continuous below with the superficial fibres of the ligamentum patellæ. It is separated from the integument by a bursa. The **posterior surface** presents above a smooth, oval, articular area, divided into two facets by a vertical ridge; the ridge corresponds to the groove on the patellar surface of the femur, and the facets to the medial and lateral parts of the same surface; the lateral facet is the broader and deeper. Below the articular surface is a rough, convex, non-articular area, the lower half of which gives attachment to the ligamentum patellæ; the upper half is separated from the head of the tibia by adipose tissue.

**Borders.**—The **base** or **superior border** is thick, and sloped from behind, downward, and forward: it gives attachment to that portion of the Quadriceps femoris which is derived from the Rectus femoris and Vastus intermedius. The **medial** and **lateral borders** are thinner and converge below: they give attachment to those

portions of the Quadriceps femoris which are derived from the Vasti lateralis and medialis.

**Apex.**—The apex is pointed, and gives attachment to the ligamentum patellae.

**Structure.**—The patella consists of a nearly uniform dense cancellous tissue, covered by a thin compact lamina. The cancelli immediately beneath the anterior surface are arranged parallel with it. In the rest of the bone they radiate from the articular surface toward the other parts of the bone.

**Ossification.**—The patella is ossified from a single centre, which usually makes its appearance in the second or third year, but may be delayed until the sixth year. More rarely, the bone is developed by two centres, placed side by side. Ossification is completed about the age of puberty.

**Articulation.**—The patella articulates with the femur.

**Applied Anatomy.**—The main surgical interest about the patella is in connection with fractures, which are of frequent occurrence. They are most often produced by muscular action—that is to say, by violent contraction of the quadriceps femoris while the limb is in a position of semi-flexion, so that the bone is snapped across the condyles of the femur and the fracture is transverse. Fracture of the patella is also produced by direct violence, such as falls on the knee, and here the fracture is usually stellate and the bone comminuted. Owing to the displacement of the fragments, and the difficulty there is in maintaining them in apposition, union takes place by fibrous tissue which may subsequently stretch, producing wide separation of the fragments and permanent lameness. Truly satisfactory results after this fracture are generally only to be obtained by opening the joint and wiring the fragments together, and this is especially so when there is marked separation of the fragments owing to laceration of the retinacula.

It is an anatomical possibility, if the fracture involve only the lower and non-articular part of the bone, for this to take place without injury to the synovial membrane and without involving the cavity of the knee-joint.

### The Tibia (Shin Bone).

The **tibia** (Figs. 396, 397) is situated at the medial side of the leg, and, excepting the femur, is the longest bone of the skeleton. It is prismoid in form, expanded above, where it enters into the knee-joint, contracted in the lower third, and again enlarged but to a lesser extent below. In the male, its direction is vertical, and parallel with the bone of the opposite side; but in the female it has a slightly oblique direction downward and lateralward, to compensate for the greater obliquity of the femur. It has a **body** and **two extremities**.

**The Upper Extremity** (*proximal extremity*).

—The upper extremity is large, and expanded into two eminences, the **medial** and **lateral condyles**. The **superior articular surface** presents two smooth articular facets (Fig. 395). The medial facet, oval in shape, is slightly concave from side to side, and from before backward. The lateral, nearly circular, is

concave from side to side, but slightly convex from before backward, especially at its posterior part, where it is prolonged on to the posterior surface for a short distance. The central portions of these facets articulate with the condyles of the femur, while their peripheral portions support the menisci of the knee-joint, which here intervene between the two bones. Between the articular facets, but nearer the posterior than the anterior aspect of the bone, is the **intercondyloid eminence** (*spine of tibia*), surmounted on either side by a prominent tubercle, on to the sides of which the articular facets are prolonged; in front of and behind the intercondyloid eminence are rough depressions for the attachment of the anterior and posterior cruciate ligaments and the menisci. The **anterior surfaces** of the condyles are continuous with one another, forming a large somewhat




FIG. 395.—Upper surface of right tibia.




FIG. 396.—Bones of the right leg. Anterior surface.

flattened area; this area is triangular, broad above, and perforated by large vascular foramina; narrow below where it ends in a large oblong elevation, the **tuberosity of the tibia**, which gives attachment to the ligamentum patellae; a bursa intervenes between the deep surface of the ligament and the part of the bone immediately above the tuberosity. *Posteriorly*, the condyles are separated from each other by a shallow depression, the **posterior intercondylar fossa**, which gives attachment to part of the posterior cruciate ligament of the knee-joint. The **medial condyle** presents posteriorly a deep transverse groove, for the insertion of the tendon of the Semimembranosus. Its *medial surface* is convex, rough, and prominent; it gives attachment to the tibial collateral ligament. The **lateral condyle** presents posteriorly a flat articular facet, nearly circular in form, directed downward, backward, and lateralward, for articulation with the head of the fibula. Its *lateral surface* is convex, rough, and prominent in front: on it is an eminence, situated on a level with the upper border of the tuberosity and at the junction of its anterior and lateral surfaces, for the attachment of the iliotibial band. Just below this a part of the Extensor digitorum longus takes origin and a slip from the tendon of the Biceps femoris is inserted.

#### The Body or Shaft (*corpus tibiae*).

—The body has three borders and three surfaces.

**Borders.**—The **anterior crest** or **border**, the most prominent of the three, commences above at the tuberosity, and ends below at the anterior margin of the medial malleolus. It is sinuous and prominent in the upper two-thirds of its extent, but smooth and rounded below; it gives attachment to the deep fascia of the leg.

The **medial border** is smooth and rounded above and below, but more prominent in the centre; it begins at the back part of the medial condyle, and ends at the posterior border of the medial malleolus; its upper part gives attachment to the tibial collateral ligament of the knee-joint to the extent of about 5 cm., and insertion to some fibres of the Popliteus; from its middle third some fibres of the Soleus and Flexor digitorum longus take origin.

The **interosseous crest or lateral border** is thin and prominent, especially its central part, and gives attachment to the interosseous membrane; it commences above in front of the fibular articular facet, and bifurcates below, to form the boundaries of a triangular rough surface, for the attachment of the interosseous ligament connecting the tibia and fibula.

**Surfaces.**—The **medial surface** is smooth, convex, and broader above than below; its upper third, directed forward and medialward, is covered by the aponeurosis derived from the tendon of the Sartorius, and by the tendons of the Gracilis and Semitendinosus, all of which are inserted nearly as far forward as the anterior crest; in the rest of its extent it is subcutaneous.

The **lateral surface** is narrower than the medial; its upper two-thirds present a shallow groove for the origin of the Tibialis anterior; its lower third is smooth, convex, curves gradually forward to the anterior aspect of the bone, and is covered by the tendons of the Tibialis anterior, Extensor hallucis longus, and Extensor digitorum longus; arranged in this order from the medial side.

The **posterior surface** (Fig. 397) presents, at its upper part, a prominent ridge, the **popliteal line**, which extends obliquely downward from the back part of




FIG. 397.—Bones of the right leg. Posterior surface.

the articular facet for the fibula to the medial border, at the junction of its upper and middle thirds; it marks the lower limit of the insertion of the Popliteus, serves for the attachment of the fascia covering this muscle, and gives origin to part of the Soleus, Flexor digitorum longus, and Tibialis posterior. The triangular area, above this line, gives insertion to the Popliteus. The middle third of the posterior surface is divided by a vertical ridge into two parts; the ridge begins at the popliteal line and is well-marked above, but indistinct below; the medial and broader portion gives origin to the Flexor digitorum longus, the lateral and narrower to part of the Tibialis posterior. The remaining part of the posterior surface is smooth and covered by the Tibialis posterior, Flexor digitorum longus, and Flexor hallucis longus. Immediately below the popliteal line is the **nutrient foramen**, which is large and directed obliquely downward.

**The Lower Extremity** (*distal extremity*).—The lower extremity, much smaller than the upper, presents five surfaces; it is prolonged downward on its medial side as a strong process, the **medial malleolus**.

**Surfaces.**—The **inferior articular surface** is quadrilateral, and smooth for articulation with the talus. It is concave from before backward, broader in front than behind, and traversed from before backward by a slight elevation, separating two depressions. It is continuous with that on the medial malleolus.




FIG. 398.—Plan of ossification of the tibia. From three centres.




FIG. 399.—Epiphysal lines of tibia and fibula in a young adult. Anterior aspect.

The **anterior surface** of the lower extremity is smooth and rounded above, and covered by the tendons of the Extensor muscles; its lower margin presents a rough transverse depression for the attachment of the articular capsule of the ankle-joint.

The **posterior surface** is traversed by a shallow groove directed obliquely downward and medialward, continuous with a similar groove on the posterior surface of the talus and serving for the passage of the tendon of the Flexor hallucis longus.

The **lateral surface** presents a triangular rough depression for the attachment of the inferior interosseous ligament connecting it with the fibula; the lower part

of this depression is smooth, covered with cartilage in the recent state, and articulates with the fibula. The surface is bounded by two prominent borders, continuous above with the interosseous crest; they afford attachment to the anterior and posterior ligaments of the lateral malleolus.

The **medial surface** is prolonged downward to form a strong pyramidal process, flattened from without inward—the **medial malleolus**. The *medial surface* of this process is convex and subcutaneous; its *lateral or articular surface* is smooth and slightly concave, and articulates with the talus; its *anterior border* is rough, for the attachment of the anterior fibres of the deltoid ligament of the ankle-joint; its *posterior border* presents a broad groove, the **malleolar sulcus**, directed obliquely downward and medialward, and occasionally double; this sulcus lodges the tendons of the Tibialis posterior and Flexor digitorum longus. The *summit* of the medial malleolus is marked by a rough depression behind, for the attachment of the deltoid ligament.

**Structure.**—The structure of the tibia is like that of the other long bones. The compact wall of the body is thickest at the junction of the middle and lower thirds of the bone.

**Ossification.**—The tibia is ossified from *three centres* (Figs. 398, 399): one for the body and one for either extremity. Ossification begins in the centre of the body, about the seventh week of fetal life, and gradually extends toward the extremities. The centre for the upper epiphysis appears before or shortly after birth; it is flattened in form, and has a thin tongue-shaped process in front, which forms the tuberosity (Fig. 399); that for the lower epiphysis appears in the second year. The lower epiphysis joins the body at about the eighteenth, and the upper one joins about the twentieth year. Two additional centres occasionally exist, one for the tongue-shaped process of the upper epiphysis, which forms the tuberosity, and one for the medial malleolus.

**Articulations.**—The tibia articulates with three bones: the femur, fibula, and talus.

### The Fibula (Calf Bone).

The **fibula** (Figs. 396, 397) is placed on the lateral side of the tibia, with which it is connected above and below. It is the smaller of the two bones, and, in proportion to its length, the most slender of all the long bones. Its upper extremity is small, placed toward the back of the head of the tibia, below the level of the knee-joint, and excluded from the formation of this joint. Its lower extremity inclines a little forward, so as to be on a plane anterior to that of the upper end; it projects below the tibia, and forms the lateral part of the ankle-joint. The bone has a **body** and **two extremities**.

**The Upper Extremity or Head** (*capitulum fibulae; proximal extremity*).—The upper extremity is of an irregular quadrate form, presenting above a flattened articular surface, directed upward, forward, and medialward, for articulation with a corresponding surface on the lateral condyle of the tibia. On the lateral side is a thick and rough prominence continued behind into a pointed eminence, the **apex** (*styloid process*), which projects upward from the posterior part of the head. The prominence, at its upper and lateral part, gives attachment to the tendon of the Biceps femoris and to the fibular collateral ligament of the knee-joint, the ligament dividing the tendon into two parts. The remaining part of the circumference of the head is rough, for the attachment of muscles and ligaments. It presents in front a tubercle for the origin of the upper and anterior fibres of the Peroneus longus, and a surface for the attachment of the anterior ligament of the head; and behind, another tubercle, for the attachment of the posterior ligament of the head and the origin of the upper fibres of the Soleus.

**The Body or Shaft** (*corpus fibulae*).—The body presents four borders—the antero-lateral, the antero-medial, the postero-lateral, and the postero-medial; and four surfaces—*anterior, posterior, medial, and lateral*.

**Borders.**—The **antero-lateral border** begins above in front of the head, runs vertically downward to a little below the middle of the bone, and then curving somewhat lateralward, bifurcates so as to embrace a triangular subcutaneous surface



immediately above the lateral malleolus. This border gives attachment to an intermuscular septum, which separates the Extensor muscles on the anterior surface of the leg from the Peronaei longus and brevis on the lateral surface.

The **antero-medial border**, or **interosseous crest**, is situated close to the medial side of the preceding, and runs nearly parallel with it in the upper third of its extent, but diverges from it in the lower two-thirds. It begins above just beneath the head of the bone (sometimes it is quite indistinct for about 2.5 cm. below the head), and ends at the apex of a rough triangular surface immediately above the articular facet of the lateral malleolus. It serves for the attachment of the interosseous membrane, which separates the Extensor muscles in front from the Flexor muscles behind.

The **postero-lateral border** is prominent; it begins above at the apex, and ends below in the posterior border of the lateral malleolus. It is directed lateralward above, backward in the middle of its course, backward, and a little medialward below, and gives attachment to an aponeurosis which separates the Peronaei on the lateral surface from the Flexor muscles on the posterior surface.

The **postero-medial border**, sometimes called the **oblique line**, begins above at the medial side of the head, and ends by becoming continuous with the interosseous crest at the lower fourth of the bone. It is well-marked and prominent at the upper and middle parts of the bone. It gives attachment to an aponeurosis which separates the Tibialis posterior from the Soleus and Flexor hallucis longus.

**Surfaces.**—The **anterior surface** is the interval between the antero-lateral and antero-medial borders. It is extremely narrow and flat in the upper third of its extent; broader and grooved longitudinally in its lower third; it serves for the origin of three muscles: the Extensor digitorum longus, Extensor hallucis longus, and Peronaeus tertius.

The **posterior surface** is the space included between the postero-lateral and the postero-medial borders; it is continuous below with the triangular area above the articular surface of the lateral malleolus; it is directed backward above, backward and medialward at its middle, directly medialward below. Its upper third is rough, for the origin of the Soleus; its lower part presents a triangular surface, connected to the tibia by a strong interosseous ligament; the intervening part of the surface is covered by the fibres of origin of the Flexor hallucis longus. Near the middle of this surface is the nutrient foramen, which is directed downward.

The **medial surface** is the interval included between the antero-medial and the postero-medial borders. It is grooved for the origin of the Tibialis posterior.

The **lateral surface** is the space between the antero-lateral and postero-lateral borders. It is broad, and often deeply grooved; it is directed lateralward in the upper two-thirds of its course, backward in the lower third, where it is continuous with the posterior border of the lateral malleolus. This surface gives origin to the Peronaei longus and brevis.

**The Lower Extremity or Lateral Malleolus** (*malleolus lateralis; distal extremity; external malleolus*).—The lower extremity is of a pyramidal form, and somewhat flattened from side to side; it descends to a lower level than the medial malleolus. The **lateral surface** is convex, subcutaneous, and continuous with the triangular, subcutaneous surface on the lateral side of the body. The **medial surface** (Fig. 400) presents in front a smooth triangular surface, convex from above downward, which articulates with a corresponding surface on the lateral side of the talus. Behind and beneath the articular surface is a rough depression, which gives attachment to the posterior talofibular ligament. The **anterior border** is thick and rough, and marked below by a depression for the attachment of the anterior talofibular ligament. The **posterior border** is broad and presents the shallow **malleolar sulcus**, for the passage of the tendons of the Peronaei longus and brevis. The **summit** is rounded, and give attachment to the calcaneofibular ligament.

**Articulations.**—The fibula articulates with two bones: the tibia and talus.

**Ossification.**—The fibula is ossified from *three* centres (Fig. 401): one for the body, and one for either end. Ossification begins in the body about the eighth week of fetal life, and extends toward the extremities. At birth the ends are cartilaginous. Ossification commences in the lower end in the second year, and in the upper about the fourth year. The lower epiphysis, the first to ossify, unites with the body about the twentieth year; the upper epiphysis joins about the twenty-fifth year.

**Applied Anatomy of the Tibia and Fibula.**—In fractures of the bones of the leg, both bones are generally involved, but either bone may be broken separately, the fibula more frequently than the tibia. Fracture of both bones may be caused by either direct or indirect violence. When it occurs from indirect force, the fracture in the tibia is at the junction of the middle and lower thirds of the bone. Many causes conduce to render this the weakest part of the bone. The fracture of the fibula is usually at a rather higher level. These fractures present great variety, both as regards their direction and condition. They may be oblique, transverse, longitudinal, or spiral. When oblique, they are for the most part the result of indirect violence, and the direction of the fracture is downward, forward, and medialward in many cases, but may be downward and lateralward, or downward and backward. When transverse, the fracture is often at the upper part of the bone, and is the result of direct violence. The spiral fracture of the tibia generally starts as a vertical fissure, involving the ankle-joint, and is associated with fracture of the fibula higher up. It is the result of torsion, from twisting of the body while the foot is fixed.




FIG. 400.—Lower extremity of right fibula. Medial aspect.



FIG. 401.—Plan of ossification of the fibula. From three centres.

Fractures of the tibia alone are almost always the result of direct violence, except where the malleolus is broken off by twists of the foot. Fractures of the fibula alone may arise from indirect or direct force, those of the lower end being usually the result of the former, and those higher up being caused by a direct blow on the part.

The tibia is the bone which is most commonly and most extensively distorted in rickets. It bends at the junction of the middle and lower third, its weakest part, and presents a curve forward with generally some lateral displacement.

The tibia is more often the seat of acute infective necrosis than any other bone in the body, and with the formation of the sequestrum, a large amount of new bony material is thrown out by the periosteum. The sequence of events in this disease can be very closely followed in the case of the tibia, and it is not uncommon to find a patient from whom the whole diaphysis of the tibia has been removed, going about with a new bone entirely of periosteal formation. Chronic bone abscess is more frequently met with in the cancellous tissue of the head or lower end of the tibia than in any other bone in the body. These abscesses are very chronic, and in most cases the result of tuberculous osteitis, although they are sometimes due to the organisms of suppuration or even the *Bacillus typhosus*.

## THE FOOT.

The skeleton of the foot (Figs. 403 and 404) consists of three parts: the **tarsus**, **metatarsus**, and **phalanges**.

The Tarsus (*Ossa Tarsi*).

The **tarsal bones** are seven in number, viz., the **calcaneus**, **talus**, **cuboid**, **navicular**, and the **first**, **second**, and **third cuneiforms**.




FIG. 402.—The left calcaneus. A. Postero-lateral view. B. Antero-medial view.

**The Calcaneus** (*os calcis*) (Fig. 402).—The calcaneus is the largest of the tarsal bones. It is situated at the lower and back part of the foot, serving to transmit the weight of the body to the ground, and forming a strong lever for the muscles of the calf. It is irregularly cuboidal in form, having its long axis directed forward and lateralward; it presents for examination six surfaces.

**Surfaces.**—The **superior surface** extends behind on to that part of the bone which projects backward to form the heel. This varies in length in different individuals,




FIG. 403.—Bones of the right foot. Dorsal surface.




Fig. 404.—Bones of the right foot. Plantar surface.



is convex from side to side, concave from before backward, and supports a mass of fat placed in front of the tendo calcaneus. In front of this area is a large usually somewhat oval-shaped facet, the **posterior articular surface**, which looks upward and forward; it is convex from behind forward, and articulates with the posterior calcaneal facet on the under surface of the talus. It is bounded anteriorly by a deep depression which is continued backward and medialward in the form of a groove, the **calcaneal sulcus**. In the articulated foot this sulcus lies below a similar one on the under surface of the talus, and the two form a canal (**sinus tarsi**) for the lodgement of the interosseous talocalcaneal ligament. In front and to the medial side of this groove is an elongated facet, concave from behind forward, and with its long axis directed forward and lateralward. This facet is frequently divided into two by a notch: of the two, the posterior, and larger is termed the **middle articular surface**; it is supported on a projecting process of bone, the **sustentaculum tali**, and articulates with the middle calcaneal facet on the under surface of the talus; the **anterior articular surface** is placed on the anterior part of the body, and articulates with the anterior calcaneal facet on the talus. The upper surface, anterior and lateral to the facets, is rough for the attachment of ligaments and for the origin of the Extensor digitorum brevis.

The **inferior or plantar surface** is uneven, wider behind than in front, and convex from side to side; it is bounded posteriorly by a transverse elevation, the **calcaneal tuberosity**, which is depressed in the middle and prolonged at either end into a process; the **lateral process**, small, prominent, and rounded, gives origin to part of the Abductor digiti quinti; the **medial process**, broader and larger, gives attachment, by its prominent medial margin, to the Abductor hallucis, and in front to the Flexor digitorum brevis and the plantar aponeurosis; the depression between the processes gives origin to the Abductor digiti quinti. The rough surface in front of the processes gives attachment to the long plantar ligament, and to the lateral head of the Quadratus plantae; while to a prominent tubercle nearer the anterior part of this surface, as well as to a transverse groove in front of the tubercle, is attached the plantar calcaneocuboid ligament.

The **lateral surface** is broad behind and narrow in front, flat and almost subcutaneous; near its centre is a tubercle, for the attachment of the calcaneofibular ligament. At its upper and anterior part, this surface gives attachment to the lateral talocalcaneal ligament; and in front of the tubercle it presents a narrow surface marked by two oblique grooves. The grooves are separated by an elevated ridge, or tubercle, the **trochlear process (peroneal tubercle)**, which varies much in size in different bones. The **superior groove** transmits the tendon of the Peroneus brevis; the **inferior groove**, that of the Peroneus longus.

The **medial surface** is deeply concave; it is directed obliquely downward and forward, and serves for the transmission of the plantar vessels and nerves into the sole of the foot; it affords origin to part of the Quadratus plantae. At its upper and forepart is a horizontal eminence, the **sustentaculum tali**, which gives attachment to a slip of the tendon of the Tibialis posterior. This eminence is concave above, and articulates with the middle calcaneal articular surface of the talus; below, it is grooved for the tendon of the Flexor hallucis longus; its anterior margin gives attachment to the plantar calcaneonavicular ligament, and its medial, to a part of the deltoid ligament of the ankle-joint.

The **anterior or cuboid articular surface** is of a somewhat triangular form. It is concave from above downward and lateralward, and convex in a direction at right angles to this. Its medial border gives attachment to the plantar calcaneonavicular ligament.

The **posterior surface** is prominent, convex, wider below than above, and divisible into three areas. The lowest of these is rough, and covered by the fatty and fibrous tissue of the heel; the middle, also rough, gives insertion to the tendo calcaneus



and Plantaris; while the highest is smooth, and is covered by a bursa which intervenes between it and the tendo calcaneus.

**Articulations.**—The calcaneus articulates with two bones: the talus and cuboid.




FIG. 405.—The left talus. A. Supero-lateral view. B. Infero-medial view. C. Inferior view.

**The Talus** (*astragalus*; *ankle bone*) (Fig. 405).—The talus is the second largest of the tarsal bones. It occupies the middle and upper part of the tarsus, supporting the tibia above, resting upon the calcaneus below, articulating on either side with the malleoli, and in front with the navicular. It consists of a **body**, a **neck**, and a **head**.

**The Body (*corpus tali*).**—The superior surface of the body presents, behind, a smooth trochlear surface, the *trochlea*, for articulation with the tibia. The trochlea is broader in front than behind, convex from before backward, slightly concave from side to side: in front it is continuous with the upper surface of the neck of the bone.

The inferior surface presents two articular areas, the posterior and middle calcaneal surfaces, separated from one another by a deep groove, the *sulcus tali*. The groove runs obliquely forward and lateralward, becoming gradually broader and deeper in front: in the articulated foot it lies above a similar groove upon the upper surface of the calcaneus, and forms, with it, a canal (*sinus tarsi*) filled up in the recent state by the interosseous talocalcaneal ligament. The **posterior calcaneal articular surface** is large and of an oval or oblong form. It articulates with the corresponding facet on the upper surface of the calcaneus,<sup>1</sup> and is deeply concave in the direction of its long axis which runs forward and lateralward at an angle of about 45° with the median plane of the body. The **middle calcaneal articular surface** is small, oval in form and slightly convex; it articulates with the upper surface of the sustentaculum tali of the calcaneus.

The **medial surface** presents at its upper part a pear-shaped articular facet for the medial malleolus, continuous above with the trochlea; below the articular surface is a rough depression for the attachment of the deep portion of the deltoid ligament of the ankle-joint.

The **lateral surface** carries a large triangular facet, concave from above downward, for articulation with the lateral malleolus; its anterior half is continuous above with the trochlea; and in front of it is a rough depression for the attachment of the anterior talofibular ligament. Between the posterior half of the lateral border of the trochlea and the posterior part of the base of the fibular articular surface is a triangular facet (Fawcett<sup>2</sup>) which comes into contact with the transverse inferior tibiofibular ligament during flexion of the ankle-joint; below the base of this facet is a groove which affords attachment to the posterior talofibular ligament.

The **posterior surface** is narrow, and traversed by a groove running obliquely downward and medialward, and transmitting the tendon of the Flexor hallucis longus. Lateral to the groove is a prominent tubercle, the **posterior process**, to which the posterior talofibular ligament is attached; this process is sometimes separated from the rest of the talus, and is then known as the *os trigonum*. Medial to the groove is a second smaller tubercle.

**The Neck (*collum tali*).**—The neck is directed forward and medialward, and comprises the constricted portion of the bone between the body and the oval head. Its **upper and medial surfaces** are rough, for the attachment of ligaments; its **lateral surface** is concave and is continuous below with the deep groove for the interosseous talocalcaneal ligament.

**The Head (*caput tali*).**—The head looks forward and medialward; its **anterior articular or navicular surface** is large, oval, and convex. Its **inferior surface** has two facets, which are best seen in the recent condition. The medial, situated in front of the middle calcaneal facet, is convex, triangular, or semi-oval in shape, and rests on the plantar calcaneonavicular ligament; the lateral, named the **anterior calcaneal articular surface**, is somewhat flattened, and articulates with the facet on the upper surface of the anterior part of the calcaneus.

**Articulations.**—The talus articulates with *four* bones: tibia, fibula, calcaneus, and navicular.

**The Cuboid Bone (*os cuboideum*)** (Fig. 406).—The cuboid bone is placed on the lateral side of the foot, in front of the calcaneus, and behind the fourth and fifth metatarsal bones. It is of a pyramidal shape, its base being directed medialward.

<sup>1</sup> Sewell (*Journal of Anatomy and Physiology*, vol. xxxviii) pointed out that in about 10 per cent. of bones a small triangular facet, continuous with the posterior calcaneal facet, is present at the junction of the lateral surface of the body with the posterior wall of the sulcus tali.

<sup>2</sup> Edinburgh Medical Journal, 1895.

**Surfaces.**—The **dorsal surface**, directed upward and lateralward, is rough, for the attachment of ligaments. The **plantar surface** presents in front a deep groove, the **peroneal sulcus**, which runs obliquely forward and medialward; it lodges the tendon of the Peroneus longus, and is bounded behind by a prominent ridge, to which the long plantar ligament is attached. The ridge ends laterally in an eminence, the **tuberosity**, the surface of which presents an oval facet; on this facet glides the sesamoid bone or cartilage frequently found in the tendon of the Peroneus longus. The surface of bone behind the groove is rough, for the attachment of the plantar calcaneocuboid ligament, a few fibres of the Flexor hallucis brevis, and a fasciculus from the tendon of the Tibialis posterior. The **lateral surface** presents a deep notch formed by the commencement of the peroneal sulcus. The




FIG. 406.—The left cuboid. A. Antero-medial view. B. Postero-lateral view.

**posterior surface** is smooth, triangular, and concavo-convex, for articulation with the anterior surface of the calcaneus; its infero-medial angle projects backward as a process which underlies and supports the anterior end of the calcaneus. The **anterior surface**, of smaller size, but also irregularly triangular, is divided by a vertical ridge into two facets: the medial, quadrilateral in form, articulates with the fourth metatarsal; the lateral, larger and more triangular, articulates with the fifth. The **medial surface** is broad, irregularly quadrilateral, and presents at its middle and upper part a smooth oval facet, for articulation with the third cuneiform; and behind this (occasionally) a smaller facet, for articulation with the navicular; it is rough in the rest of its extent, for the attachment of strong interosseous ligaments.

**Articulations.**—The cuboid articulates with *four* bones: the calcaneus, third cuneiform, and fourth and fifth metatarsals; occasionally with a fifth, the navicular.




FIG. 407.—The left navicular. A. Antero-lateral view. B. Postero-medial view.

**The Navicular Bone** (*os naviculare pedis*; *scaphoid bone*) (Fig. 407).—The navicular bone is situated at the medial side of the tarsus, between the talus behind and the cuneiform bones in front.

**Surfaces.**—The **anterior surface** is convex from side to side, and subdivided by two ridges into three facets, for articulation with the three cuneiform bones. The **posterior surface** is oval, concave, broader laterally than medially, and articulates with the rounded head of the talus. The **dorsal surface** is convex from side to side, and rough for the attachment of ligaments. The **plantar surface** is irregular, and also rough for the attachment of ligaments. The **medial surface** presents a rounded **tuberosity**, the lower part of which gives attachment to part of the tendon of the Tibialis posterior. The **lateral surface** is rough and irregular for the attachment of ligaments, and occasionally presents a small facet for articulation with the cuboid bone.

**Articulations.**—The navicular articulates with *four* bones: the talus and the three cuneiforms; occasionally with a fifth, the cuboid.

**The First Cuneiform Bone** (*os cuneiform, primum; internal cuneiform*) (Fig. 408).—The first cuneiform bone is the largest of the three cuneiforms. It is situated at the medial side of the foot, between the navicular behind and the base of the first metatarsal in front.

**Surfaces.**—The **medial surface** is subcutaneous, broad, and quadrilateral; at its anterior plantar angle is a smooth oval impression, into which part of the tendon of the Tibialis anterior is inserted; in the rest of its extent it is rough for the attachment of ligaments. The **lateral surface** is concave, presenting, along its superior and posterior borders a narrow L-shaped surface, the vertical limb and posterior part of the horizontal limb




FIG. 408.—The left first cuneiform. A. Antero-medial view. B. Postero-lateral view.

of which articulate with the second cuneiform, while the anterior part of the horizontal limb articulates with the second metatarsal bone; the rest of this surface is rough for the attachment of ligaments and part of the tendon of the Peroneus longus. The **anterior surface**, kidney-shaped and much larger than the posterior, articulates with the first metatarsal bone. The **posterior surface** is triangular, concave, and articulates with the most medial and largest of the three facets on the anterior surface of the navicular. The **plantar surface** is rough, and forms the base of the wedge; at its back part is a tuberosity for the insertion of part of the tendon of the Tibialis posterior. It also gives insertion in front to part of the tendon of the Tibialis anterior. The **dorsal surface** is the narrow end of the wedge, and is directed upward and lateralward; it is rough for the attachment of ligaments.

**Articulations.**—The first cuneiform articulates with *four* bones: the navicular, second cuneiform, and first and second metatarsals.

**The Second Cuneiform Bone** (*os cuneiforme secundum; middle cuneiform*) (Fig. 409).—The second cuneiform bone, the smallest of the three, is of very regular wedge-like form, the thin end being directed downward. It is situated between the other two cuneiforms, and articulates with the navicular behind, and the second metatarsal in front.

**Surfaces.**—The **anterior surface**, triangular in form, and narrower than the posterior, articulates with the base of the second metatarsal bone. The **posterior surface**, also triangular, articulates with the intermediate facet on the anterior surface

of the navicular. The **medial surface** carries an L-shaped articular facet, running along the superior and posterior borders, for articulation with the first cuneiform, and is rough in the rest of its extent for the attachment of ligaments. The **lateral**




FIG. 409.—The left second cuneiform. A. Antero-medial view. B. Postero-lateral view.

**Articulations.**—The second cuneiform articulates with *four* bones: the navicular, first and third cuneiforms, and second metatarsal.

**The Third Cuneiform Bone** (*os cuneiforme tertium; external cuneiform*) (Fig. 410).—The third cuneiform bone, intermediate in size between the two preceding, is wedge-shaped, the base being uppermost. It occupies the centre of the front row of the tarsal bones, between the second cuneiform medially, the cuboid laterally, the navicular behind, and the third metatarsal in front.

**Surfaces.**—The **anterior surface**, triangular in form, articulates with the third metatarsal bone. The **posterior surface** articulates with the lateral facet on the anterior surface of the navicular, and is rough below for the attachment of ligamentous fibres. The **medial surface** presents an anterior and a posterior articular facet, separated by a rough depression: the anterior, sometimes divided, articulates with the lateral side of the base of the second metatarsal bone; the posterior skirts




FIG. 410.—The left third cuneiform. A. Postero-medial view. B. Antero-lateral view.

the posterior border, and articulates with the second cuneiform; the rough depression gives attachment to an interosseous ligament. The **lateral surface** also presents two articular facets, separated by a rough non-articular area; the anterior facet, situated at the superior angle of the bone, is small and semi-oval in shape, and articulates with the medial side of the base of the fourth metatarsal bone; the posterior and larger one is triangular or oval, and articulates with the cuboid; the rough, non-articular area serves for the attachment of an interosseous ligament. The three facets for articulation with the three metatarsal bones are continuous with one another; those for articulation with the second cuneiform and navicular are also continuous, but that for articulation with the cuboid is usually separate. The **dorsal surface** is of an oblong form, its postero-lateral angle being prolonged backward. The **plantar surface** is a rounded margin, and serves for the attachment

of part of the tendon of the Tibialis posterior, part of the Flexor hallucis brevis, and ligaments.

**Articulations.**—The third cuneiform articulates with *six* bones: the navicular, second cuneiform, cuboid, and second, third, and fourth metatarsals.

### The Metatarsus.

The **metatarsus** consists of five bones which are numbered from the medial side (*ossa metatarsalia* I.-V.); each presents for examination a **body** and **two extremities**.

**Common Characteristics of the Metatarsal Bones.**—The body is prismoid in form, tapers gradually from the tarsal to the phalangeal extremity, and is curved longitudinally, so as to be concave below, slightly convex above. The **base** or **posterior extremity** is wedge-shaped, articulating proximally with the tarsal bones, and by its sides with the contiguous metatarsal bones: its dorsal and plantar surfaces are rough for the attachment of ligaments. The **head** or **anterior extremity** presents a convex articular surface, oblong from above downward, and extending farther backward below than above. Its sides are flattened, and on each is a depression, surmounted by a tubercle, for ligamentous attachment. Its plantar surface is grooved antero-posteriorly for the passage of the Flexor tendons, and marked on either side by an articular eminence continuous with the terminal articular surface.



FIG. 411.—The first metatarsal. (Left.)




FIG. 412.—The second metatarsal. (Left.)

**Characteristics of the Individual Metatarsal Bones.**—The **First Metatarsal Bone** (*os metatarsale I*; *metatarsal bone of the great toe*) (Fig. 411).—The first metatarsal bone is remarkable for its great thickness, and is the shortest of the metatarsal bones. The **body** is strong, and of well-marked prismoid form. The **base** presents, as a rule, no articular facets on its sides, but occasionally on the lateral side there is an oval facet, by which it articulates with the second metatarsal. Its proximal articular surface is of large size and kidney-shaped; its



of the navicular. The **medial surface** carries an L-shaped articular facet, running along the superior and posterior borders, for articulation with the first cuneiform, and is rough in the rest of its extent for the attachment of ligaments. The **lateral**




FIG. 409.—The left second cuneiform. A. Antero-medial view. B. Postero-lateral view.

**surface** presents posteriorly a smooth facet for articulation with the third cuneiform bone. The **dorsal surface** forms the base of the wedge; it is quadrilateral and rough for the attachment of ligaments. The **plantar surface**, sharp and tuberculated, is also rough for the attachment of ligaments, and for the insertion of a slip from the tendon of the Tibialis posterior.

**Articulations.**—The second cuneiform articulates with *four* bones: the navicular, first and third cuneiforms, and second metatarsal.

**The Third Cuneiform Bone** (*os cuneiforme tertium*; *external cuneiform*) (Fig. 410).—The third cuneiform bone, intermediate in size between the two preceding, is wedge-shaped, the base being uppermost. It occupies the centre of the front row of the tarsal bones, between the second cuneiform medially, the cuboid laterally, the navicular behind, and the third metatarsal in front.

**Surfaces.**—The **anterior surface**, triangular in form, articulates with the third metatarsal bone. The **posterior surface** articulates with the lateral facet on the anterior surface of the navicular, and is rough below for the attachment of ligamentous fibres. The **medial surface** presents an anterior and a posterior articular facet, separated by a rough depression: the anterior, sometimes divided, articulates with the lateral side of the base of the second metatarsal bone; the posterior skirts




FIG. 410.—The left third cuneiform. A. Postero-medial view. B. Antero-lateral view.

the posterior border, and articulates with the second cuneiform; the rough depression gives attachment to an interosseous ligament. The **lateral surface** also presents two articular facets, separated by a rough non-articular area; the anterior facet, situated at the superior angle of the bone, is small and semi-oval in shape, and articulates with the medial side of the base of the fourth metatarsal bone; the posterior and larger one is triangular or oval, and articulates with the cuboid; the rough, non-articular area serves for the attachment of an interosseous ligament. The three facets for articulation with the three metatarsal bones are continuous with one another; those for articulation with the second cuneiform and navicular are also continuous, but that for articulation with the cuboid is usually separate. The **dorsal surface** is of an oblong form, its postero-lateral angle being prolonged backward. The **plantar surface** is a rounded margin, and serves for the attachment

of part of the tendon of the Tibialis posterior, part of the Flexor hallucis brevis, and ligaments.

**Articulations.**—The third cuneiform articulates with *six* bones: the navicular, second cuneiform, cuboid, and second, third, and fourth metatarsals.

### The Metatarsus.

The **metatarsus** consists of five bones which are numbered from the medial side (*ossa metatarsalia* I.–V.); each presents for examination a **body** and **two** **extremities**.

**Common Characteristics of the Metatarsal Bones.**—The body is prismoid in form, tapers gradually from the tarsal to the phalangeal extremity, and is curved longitudinally, so as to be concave below, slightly convex above. The **base** or **posterior extremity** is wedge-shaped, articulating proximally with the tarsal bones, and by its sides with the contiguous metatarsal bones: its dorsal and plantar surfaces are rough for the attachment of ligaments. The **head** or **anterior extremity** presents a convex articular surface, oblong from above downward, and extending farther backward below than above. Its sides are flattened, and on each is a depression, surmounted by a tubercle, for ligamentous attachment. Its plantar surface is grooved antero-posteriorly for the passage of the Flexor tendons, and marked on either side by an articular eminence continuous with the terminal articular surface.




FIG. 411.—The first metatarsal. (Left.)




FIG. 412.—The second metatarsal. (Left.)

**Characteristics of the Individual Metatarsal Bones.**—**The First Metatarsal Bone** (*os metatarsale I*; *metatarsal bone of the great toe*) (Fig. 411).—The first metatarsal bone is remarkable for its great thickness, and is the shortest of the metatarsal bones. The **body** is strong, and of well-marked prismoid form. The **base** presents, as a rule, no articular facets on its sides, but occasionally on the lateral side there is an oval facet, by which it articulates with the second metatarsal. Its proximal articular surface is of large size and kidney-shaped; its

circumference is grooved, for the tarsometatarsal ligaments, and medially gives insertion to part of the tendon of the *Tibialis anterior*; its plantar angle presents a rough oval prominence for the insertion of the tendon of the *Peroneus longus*. The **head** is large; on its plantar surface are two grooved facets, on which glide sesamoid bones; the facets are separated by a smooth elevation.

**The Second Metatarsal Bone** (*os metatarsale II*) (Fig. 412).—The second metatarsal bone is the longest of the metatarsal bones, being prolonged backward into the recess formed by the three cuneiform bones. Its **base** is broad above, narrow and rough below. It presents four articular surfaces: one behind, of a triangular form, for articulation with the second cuneiform; one at the upper part of its medial surface, for articulation with the first cuneiform; and two on its lateral surface, an upper and lower, separated by a rough non-articular interval. Each of these lateral articular surfaces is divided into two by a vertical ridge; the two anterior facets articulate with the third metatarsal; the two posterior (sometimes continuous) with the third cuneiform. A fifth facet is occasionally present for articulation with the first metatarsal; it is oval in shape, and is situated on the medial side of the body near the base.




FIG. 413.—The third metatarsal. (Left.)




FIG. 414.—The fourth metatarsal. (Left.)

**The Third Metatarsal Bone** (*os metatarsale III*) (Fig. 413).—The third metatarsal bone articulates proximally, by means of a triangular smooth surface, with the third cuneiform; medially, by two facets, with the second metatarsal; and laterally, by a single facet, with the fourth metatarsal. This last facet is situated at the dorsal angle of the base.

**The Fourth Metatarsal Bone** (*os metatarsale IV*) (Fig. 414).—The fourth metatarsal bone is smaller in size than the preceding; its **base** presents an oblique quadrilateral surface for articulation with the cuboid; a smooth facet on the medial side, divided by a ridge into an anterior portion for articulation with the third metatarsal, and a posterior portion for articulation with the third cuneiform; on the lateral side a single facet, for articulation with the fifth metatarsal.

**The Fifth Metatarsal Bone** (*os metatarsale V*) (Fig. 415).—The fifth metatarsal bone is recognized by a rough eminence, the **tuberosity**, on the lateral side of its

base. The **base** articulates behind, by a triangular surface cut obliquely in a transverse direction, with the cuboid; and medially, with the fourth metatarsal. On the medial part of its dorsal surface is inserted the tendon of the *Peronaeus tertius* and on the dorsal surface of the tuberosity that of the *Peronaeus brevis*. A strong band of the plantar aponeurosis connects the projecting part of the tuberosity with the lateral process of the tuberosity of the calcaneus. The plantar surface of the base is grooved for the tendon of the *Abductor digiti quinti*, and gives origin to the *Flexor digiti quinti brevis*.



FIG. 415.—The fifth metatarsal. (Left.)

**Articulations.**—The base of each metatarsal bone articulates with one or more of the tarsal bones, and the head with one of the first row of phalanges. The first metatarsal articulates with the first cuneiform, the second with all three cuneiforms, the third with the third cuneiform, the fourth with the third cuneiform and the cuboid, and the fifth with the cuboid.

### The Phalanges of the Foot (*Phalanges Digitorum Pedis*).

The **phalanges** of the foot correspond, in number and general arrangement, with those of the hand; there are two in the great toe, and three in each of the other toes. They differ from them, however, in their size, the bodies being much reduced in length, and, especially in the first row, laterally compressed.

**First Row.**—The phalanges of the first row closely resemble those of the hand. The **body** of each is compressed from side to side, convex above, concave below. The **base** is concave; and the **head** presents a trochlear surface for articulation with the second phalanx.

**Second Row.**—The phalanges of the second row are remarkably small and short, but rather broader than those of the first row.

The **ungual phalanges**, in form, resemble those of the fingers; but they are smaller and are flattened from above downward; each presents a broad base for articulation with the corresponding bone of the second row, and an expanded distal extremity for the support of the nail and end of the toe.

**Articulations.**—In the second, third, fourth, and fifth toes the phalanges of the first row articulate behind with the metatarsal bones, and in front with the second phalanges, which in their turn articulate with the first and third: the unguinal phalanges articulate with the second. In

the great toe the first phalanx articulates proximally with the metatarsal bone and distally with the ungual phalanx.

**Ossification of the Bones of the Foot** (Fig. 416).—The tarsal bones are each ossified from a single centre, excepting the calcaneus, which has an epiphysis for its posterior extremity.<sup>1</sup> The centres make their appearance in the following order: calcaneus at the sixth month of fetal life; talus, about the seventh month; cuboid, at the ninth month; third cuneiform, during the first year; first cuneiform, in the third year; second cuneiform and navicular, in the fourth year. The epiphysis for the posterior extremity of the calcaneus appears at the tenth year, and unites with the rest of the bone soon after puberty. The posterior process of the talus is sometimes ossified from a separate centre, and may remain distinct from the main mass of the bone, when it is named the *os trigonum*.




FIG. 416.—Plan of ossification of the foot.

The metatarsal bones are each ossified from two centres: one for the body, and one for the head, of the second, third, fourth, and fifth metatarsals; one for the body, and one for the base, of the first metatarsal.<sup>1</sup> Ossification commences in the centre of the body about the ninth week, and extends toward either extremity. The centre for the base of the first metatarsal appears about the third year; the centres for the heads of the other bones between the fifth and eighth years; they join the bodies between the eighteenth and twentieth years.

The phalanges are each ossified from two centres: one for the body, and one for the base. The centre for the body appears about the tenth week, that for the base between the fourth and tenth years; it joins the body about the eighteenth year.

<sup>1</sup> As was noted in the first metacarpal (see footnote, page 332), so in the first metatarsal, there is often a second epiphysis for its head.

### Comparison of the Bones of the Hand and Foot.

The hand and foot are constructed on somewhat similar principles, each consisting of a proximal part, the carpus or the tarsus, a middle portion, the metacarpus, or the metatarsus, and a terminal portion, the phalanges. The proximal part consists of a series of more or less cubical bones which allow a slight amount of gliding on one another and are chiefly concerned in distributing forces transmitted to or from the bones of the arm or leg. The middle part is made up of slightly movable long bones which assist the carpus or tarsus in distributing forces and also give greater breadth for the reception of such forces. The separation of the individual bones from one another allows of the attachments of the Interossei and protects the dorsi-palmar and dorsi-plantar vascular anastomoses. The terminal portion is the most movable, and its separate elements enjoy a varied range of movements, the chief of which are flexion and extension.

The function of the hand and foot are, however, very different, and the general similarity between them is greatly modified to meet these requirements. Thus the foot forms a firm basis of support for the body in the erect posture, and is therefore more solidly built up and its component parts are less movable on each other than those of the hand. In the case of the phalanges the difference is readily noticeable; those of the foot are smaller and their movements are more limited than those of the hand. Very much more marked is the difference between the metacarpal bone of the thumb and the metatarsal bone of the great toe. The metacarpal bone of the thumb is constructed to permit of great mobility, is directed at an acute angle from that of the index finger, and is capable of a considerable range of movements at its articulation with the carpus. The metatarsal bone of the great toe assists in supporting the weight of the body, is constructed with great solidity, lies parallel with the other metatarsals, and has a very limited degree of mobility. The carpus is small in proportion to the rest of the hand, is placed in line with the forearm, and forms a transverse arch, the concavity of which constitutes a bed for the Flexor tendons and the palmar vessels and nerves. The tarsus forms a considerable part of the foot, and is placed at right angles to the leg, a position which is almost peculiar to man, and has relation to his erect posture. In order to allow of their supporting the weight of the body with the least expenditure of material the tarsus and a part of the metatarsus are constructed in a series of arches (Figs. 417, 418), the disposition of which will be considered after the articulations of the foot have been described.

**Applied Anatomy.**—Considering the injuries to which the foot is subjected, it is surprising how seldom the tarsal bones are fractured. This is no doubt due to the fact that the tarsus is composed of a number of bones, articulated by a considerable extent of surface, and joined together by very strong ligaments which serve to break the force of violence applied to this part of the body. When fracture does occur, these bones being composed for the most part of a soft cancellous structure, covered only by a thin shell of compact tissue, are often extensively comminuted, especially as most of the fractures are produced by direct violence; and, as there is only a very scanty amount of soft parts over the bones, the fractures are very often compound, and amputation is often necessary.

When fracture occurs in the anterior group of tarsal bones, it is almost invariably the result of direct violence; but fractures of the posterior group—that is, of the calcaneus and talus—are usually produced by falls from a height on to the feet.

In club-foot (*talipes*), especially in congenital cases, the bones of the tarsus become altered in shape and size, and displaced from their proper positions. This is principally the case in congenital talipes equinovarus, in which the head of the talus becomes twisted and atrophied, and a similar condition may be present in the other bones, more especially the navicular. The tarsal bones are peculiarly liable to become the seat of tuberculous caries following comparatively trivial injuries, especially as they are not maintained in a condition of rest to the same extent as some other parts of the body after similar injuries. Caries of the calcaneus or talus may remain limited to the one bone for a long period, but when one of the other bones is affected, the remainder



frequently become involved, since the disease spreads through the large and complicated synovial membrane which is more or less common to these bones.

Amputation of the foot is often required either for injury or disease. The principal amputations are as follows: (1) Syme's: amputation at the ankle-joint by a heel flap, with removal of




FIG. 417.—Skeleton of foot. Medial aspect.

the malleoli and sometimes a thin slice from the lower end of the tibia. (2) Pirogoff's: amputation of the whole of the tarsal bones (except the posterior part of the calcaneus), and a thin slice from the tibia and fibula, including the two malleoli. The sawn surface of the calcaneus is then turned up and united to the cut surface of the tibia. (3) Subastragalar: amputation of the foot below the talus through the joint between it and the calcaneus.



FIG. 418.—Skeleton of foot. Lateral aspect.

The bones of the tarsus occasionally require removal individually. This is especially the case with the talus for tuberculous disease limited to that bone; or the talus may require excision in cases of subastragalar dislocation, or in cases of inveterate talipes. The cuboid has been removed for the same reason.

Fractures of the metatarsal bones and phalanges are nearly always the result of direct violence, and in the majority of cases the injury is caused by severe crushing accidents, necessitating amputation. The metatarsal bones, and especially that of the great toe, are frequently diseased, either in tuberculous subjects or in patients with perforating ulcer of the foot.

### The Sesamoid Bones (*Ossa Sesamoidea*).

**Sesamoid bones** are small more or less rounded masses embedded in certain tendons and usually related to joint surfaces. Their functions probably are to modify pressure, to diminish friction, and occasionally to alter the direction of a muscle pull. That they are not developed to meet certain physical requirements in the adult is evidenced by the fact that they are present as cartilaginous nodules in the fetus, and in greater numbers than in the adult. They must be regarded, according to Thilenius, as integral parts of the skeleton phylogenetically inherited.<sup>1</sup>

<sup>1</sup> *Morpholog. Arbeiten*, 1906, v, 309.

Physical necessities probably come into play in selecting and in regulating the degree of development of the original cartilaginous nodules. Nevertheless, irregular nodules of bone may appear as the result of intermittent pressure in certain regions, *e. g.*, the "rider's bone," which is occasionally developed in the Adductor muscles of the thigh.

Sesamoid bones are invested by the fibrous tissue of the tendons, except on the surfaces in contact with the parts over which they glide, where they present smooth articular facets.

In the upper extremity the sesamoid bones of the joints are found only on the palmar surface of the hand. Two, of which the medial is the larger, are constant at the metacarpophalangeal joint of the thumb; one is frequently present in the corresponding joint of the little finger, and one (or two) in the same joint of the index finger. Sesamoid bones are also found occasionally at the metacarpophalangeal joints of the middle and ring fingers, at the interphalangeal joint of the thumb and at the distal interphalangeal joint of the index finger.

In the lower extremity the largest sesamoid bone of the joints is the patella, developed in the tendon of the Quadriceps femoris. On the plantar aspect of the foot, two, of which the medial is the larger, are always present at the metatarsophalangeal joint of the great toe; one sometimes at the metatarsophalangeal joints of the second and fifth toes, one occasionally at the corresponding joint of the third and fourth toes, and one at the interphalangeal joint of the great toe.

Sesamoid bones apart from joints are seldom found in the tendons of the upper limb; one is sometimes seen in the tendon of the Biceps brachii opposite the radial tuberosity. They are, however, present in several of the tendons of the lower limb, *viz.*, one in the tendon of the Peroneus longus, where it glides on the cuboid; one, appearing late in life, in the tendon of the Tibialis anterior, opposite the smooth facet of the first cuneiform bone; one in the tendon of the Tibialis posterior, opposite the medial side of the head of the talus; one in the lateral head of the Gastrocnemius, behind the lateral condyle of the femur; and one in the tendon of the Psoas major, where it glides over the pubis. Sesamoid bones are found occasionally in the tendon of the Gluteus maximus, as it passes over the greater trochanter, and in the tendons which wind around the medial and lateral malleoli.



# SYNDESMOLOGY.

---

THE bones of the skeleton are joined to one another at different parts of their surfaces, and such connections are termed **Joints** or **Articulations**. Where the joints are *immovable*, as in the articulations between practically all the bones of the skull, the adjacent margins of the bones are almost in contact, being separated merely by a thin layer of fibrous membrane, named the **sutural ligament**. In certain regions at the base of the skull this fibrous membrane is replaced by a layer of cartilage. Where *slight movement* combined with great strength is required, the osseous surfaces are united by tough and elastic **fibrocartilages**, as in the joints between the vertebral bodies, and in the interpubic articulation. In the *freely movable* joints the surfaces are completely separated; the bones forming the articulation are expanded for greater convenience of mutual connection, covered by **cartilage** and enveloped by **capsules** of fibrous tissue. The cells lining the interior of the fibrous capsule form an imperfect membrane—the **synovial membrane**—which secretes a lubricating fluid. The joints are strengthened by strong fibrous bands called **ligaments**, which extend between the bones forming the joint.

**Bone.**—Bone constitutes the fundamental element of all the joints. In the long bones, the extremities are the parts which form the articulations; they are generally somewhat enlarged; and consist of spongy cancellous tissue with a thin coating of compact substance. In the flat bones, the articulations usually take place at the edges; and in the short bones at various parts of their surfaces. The layer of compact bone which forms the joint surface, and to which the articular cartilage is attached, is called the **articular lamella**. It differs from ordinary bone tissue in that it contains no Haversian canals, and its lacunæ are larger and have no canaliculi. The vessels of the cancellous tissue, as they approach the articular lamella, turn back in loops, and do not perforate it; this layer is consequently denser and firmer than ordinary bone, and is evidently designed to form an unyielding support for the articular cartilage.

**Articular Cartilage.**—Articular cartilage, which covers the articular surfaces of bones, and **fibrocartilages**, which enters into the structure of some of the joints, are described in the section on Histology (pages 47 and 48).

**Ligaments.**—Ligaments are composed mainly of bundles of **white fibrous tissue** placed parallel with, or closely interlaced with one another, and present a white, shining, silvery appearance. They are pliant and flexible, so as to allow perfect freedom of movement, but strong, tough, and inextensible, so as not to yield readily to applied force. Some ligaments consist entirely of **yellow elastic tissue**, as the ligamenta flava which connect together the laminæ of adjacent vertebræ, and the ligamentum nuchæ in the lower animals. In these cases the elasticity of the ligament is intended to act as a substitute for muscular power.

**The Articular Capsules.**—The articular capsules form complete envelopes for the freely movable joints. Each capsule consists of two strata—an **external** (*stratum fibrosum*) composed of white fibrous tissue, and an **internal** (*stratum synoviale*) which is a secreting layer, and is usually described separately as the synovial membrane.

The **fibrous capsule** is attached to the whole circumference of the articular end of each bone entering into the joint, and thus entirely surrounds the articulation.

The **synovial membrane** invests the inner surface of the fibrous capsule, and is reflected over any tendons passing through the joint cavity, as the tendon of the Popliteus in the knee, and the tendon of the Biceps brachii in the shoulder. It is composed of a thin, delicate, connective tissue, with branched connective-tissue corpuscles. Its secretion is thick, viscid, and glairy, like the white of an egg, and is hence termed **synovia**. In the fetus this membrane is said, by Toynbee, to be continued over the surfaces of the cartilages; but in the adult such a continuation is wanting, excepting at the circumference of the cartilage, upon which it encroaches for a short distance and to which it is firmly attached. In some of the joints the synovial membrane is thrown into folds which pass across the cavity; they are especially distinct in the knee. In other joints there are flattened folds, subdivided at their margins into fringe-like processes which contain convoluted vessels. These folds generally project from the synovial membrane near the margin of the cartilage, and lie flat upon its surface. They consist of connective tissue, covered with endothelium, and contain fat cells in variable quantities, and, more rarely, isolated cartilage cells; the larger folds often contain considerable quantities of fat.

Closely associated with synovial membrane, and therefore conveniently described in this section, are the mucous sheaths of tendons and the mucous bursæ.

**Mucous sheaths** (*vaginae mucosae*) serve to facilitate the gliding of tendons in fibroosseous canals. Each sheath is arranged in the form of an elongated closed sac, one layer of which adheres to the wall of the canal, and the other is reflected upon the surface of the enclosed tendon. These sheaths are chiefly found surrounding the tendons of the Flexor and Extensor muscles of the fingers and toes as they pass through fibroosseous canals in or near the hand and foot.

**Bursæ mucosae** are interposed between surfaces which glide upon each other. They consist of closed sacs containing a minute quantity of clear viscid fluid, and may be grouped, according to their situations, under the headings *subcutaneous*, *submuscular*, *subfacial*, and *subtendinous*.

### CLASSIFICATION OF JOINTS.

The articulations are divided into three classes: **synarthroses** or immovable, **amphiarthroses** or slightly movable, and **diarthroses** or freely movable, joints.

**Synarthroses** (*immovable articulations*).—Synarthroses include all those articulations in which the surfaces of the bones are in almost direct contact, fastened together by intervening connective tissue or hyaline cartilage, and in which there is no appreciable motion, as in the joints between the bones of the skull, excepting those of the mandible. There are four varieties of synarthrosis: **sutura**, **schindylesis**, **gomphosis**, and **synchondrosis**.




FIG. 419.—Section across the sagittal suture.




FIG. 420.—Section through occipitosphonoid synchondrosis of an infant.

**Sutura**.—Sutura is that form of articulation where the contiguous margins of the bones are united by a thin layer of fibrous tissue; it is met with only in the skull (Fig. 419). When the margins of the bones are connected by a series of processes, and indentations interlocked together, the articulation is termed a **true suture**

(*sutura vera*); and of this there are three varieties: *sutura dentata*, *serrata*, and *limbosa*. The margins of the bones are not in direct contact, being separated by a thin layer of fibrous tissue, continuous externally with the pericranium, internally with the dura mater. The *sutura dentata* is so called from the tooth-like form of the projecting processes, as in the suture between the parietal bones. In the *sutura serrata* the edges of the bones are serrated like the teeth of a fine saw, as between the two portions of the frontal bone. In the *sutura limbosa*, there is besides the interlocking, a certain degree of bevelling of the articular surfaces, so that the bones overlap one another, as in the suture between the parietal and frontal bones. When the articulation is formed by roughened surfaces placed in apposition with one another, it is termed a **false suture** (*sutura notha*), of which there are two kinds: the *sutura squamosa*, formed by the overlapping of contiguous bones by broad bevelled margins, as in the squamosal suture between the temporal and parietal, and the *sutura harmonia*, where there is simple apposition of contiguous rough surfaces, as in the articulation between the maxillæ, or between the horizontal parts of the palatine bones.

**Schindylesis.**—Schindylesis is that form of articulation in which a thin plate of bone is received into a cleft or fissure formed by the separation of two laminæ in another bone, as in the articulation of the rostrum of the sphenoid and perpendicular plate of the ethmoid with the vomer, or in the reception of the latter in the fissure between the maxillæ and between the palatine bones.

**Gomphosis.**—Gomphosis is articulation by the insertion of a conical process into a socket; this is not illustrated by any articulation between bones, properly so called, but is seen in the articulations of the roots of the teeth with the alveoli of the mandible and maxillæ.

**Synchondrosis.**—Where the connecting medium is cartilage the joint is termed a synchondrosis (Fig. 420). This is a temporary form of joint, for the cartilage is converted into bone before adult life. Such joints are found between the epiphyses and bodies of long bones, between the occipital and the sphenoid at, and for some years after, birth, and between the petrous portion of the temporal and the jugular process of the occipital.

**Amphiarthroses** (*slightly movable articulations*).—In these articulations the contiguous bony surfaces are either connected by broad flattened disks of fibrocartilage, of a more or less complex structure, as in the articulations between the bodies of the vertebræ; or are united by an interosseous ligament, as in the inferior tibiofibular articulation. The first form is termed a **symphysis** (Fig. 421), the second a **syndesmosis**.




FIG. 421.—Diagrammatic section of a symphysis.

**Diarthroses** (*freely movable articulations*).

—This class includes the greater number

of the joints in the body. In a diarthrodial joint the contiguous bony surfaces are covered with articular cartilage, and connected by ligaments lined by synovial membrane (Fig. 422). The joint may be divided, completely or incompletely, by an **articular disk** or **meniscus**, the periphery of which is continuous with the fibrous capsule while its free surfaces are covered by synovial membrane (Fig. 423).

The varieties of joints in this class have been determined by the kind of motion permitted in each. There are two varieties in which the movement is uniaxial, that is to say, all movements take place around one axis. In one form, the **ginglymus**, this axis is, practically speaking, transverse; in the other, the **trochoid** or **pivot-joint**, it is longitudinal. There are two varieties where the movement is biaxial, or around two horizontal axes at right angles to each other, or at any intervening



axis between the two. These are the **condyloid** and the **saddle-joint**. There is one form where the movement is polyaxial, the **enarthrosis** or **ball-and-socket joint**; and finally there are the **arthrodia** or **gliding joints**.




FIG. 422.—Diagrammatic section of a diarthrodial joint.




FIG. 423.—Diagrammatic section of a diarthrodial joint, with an articular disc.

**Ginglymus or Hinge-joint.**—In this form the articular surfaces are moulded to each other in such a manner as to permit motion only in one plane, forward and backward, the extent of motion at the same time being considerable. The direction which the distal bone takes in this motion is seldom in the same plane as that of the axis of the proximal bone; there is usually a certain amount of deviation from the straight line during flexion. The articular surfaces are connected together by strong collateral ligaments, which form their chief bond of union. The best examples of ginglymus are the interphalangeal joints and the joint between the humerus and ulna; the knee- and ankle-joints are less typical, as they allow a slight degree of rotation or of side-to-side movement in certain positions of the limb.

**Trochoid or Pivot-joint** (*articulatio trochoidea*; *rotary joint*).—Where the movement is limited to rotation, the joint is formed by a pivot-like process turning within a ring, or a ring on a pivot, the ring being formed partly of bone, partly of ligament. In the proximal radioulnar articulation, the ring is formed by the radial notch of the ulna and the annular ligament; here, the head of the radius rotates within the ring. In the articulation of the odontoid process of the axis with the atlas the ring is formed in front by the anterior arch, and behind by the transverse ligament of the atlas; here, the ring rotates around the odontoid process.

**Condyloid Articulation** (*articulatio ellipsoidea*).—In this form of joint, an ovoid articular surface, or condyle, is received into an elliptical cavity in such a manner as to permit of flexion, extension, adduction, abduction, and circumduction, but no axial rotation. The wrist-joint is an example of this form of articulation.

**Articulation by Reciprocal Reception** (*articulatio sellaris*; *saddle-joint*).—In this variety the opposing surfaces are reciprocally concavo-convex. The movements are the same as in the preceding form; that is to say, flexion, extension, adduction, abduction, and circumduction are allowed; but no axial rotation. The best example of this form is the carpometacarpal joint of the thumb.

**Enarthrosis** (*ball-and-socket joints*).—Enarthrosis is a joint in which the distal bone is capable of motion around an indefinite number of axes, which have one common centre. It is formed by the reception of a globular head into a cup-like cavity, hence the name "ball-and-socket." Examples of this form of articulation are found in the hip and shoulder.

**Arthrodia** (*gliding joints*) is a joint which admits of only gliding movement; it is formed by the apposition of plane surfaces, or one slightly concave, the other slightly convex, the amount of motion between them being limited by the ligaments

or osseous processes surrounding the articulation. It is the form present in the joints between the articular processes of the vertebræ, the carpal joints, except that of the capitate with the navicular and lunate, and the tarsal joints with the exception of that between the talus and the navicular.

### THE KINDS OF MOVEMENT ADMITTED IN JOINTS.

The movements admissible in joints may be divided into four kinds: **gliding** and **angular movements**, **circumduction**, and **rotation**. These movements are often, however, more or less combined in the various joints, so as to produce an infinite variety, and it is seldom that only one kind of motion is found in any particular joint.

**Gliding Movement.**—Gliding movement is the simplest kind of motion that can take place in a joint, one surface gliding or moving over another without any angular or rotatory movement. It is common to all movable joints; but in some, as in most of the articulations of the carpus and tarsus, it is the only motion permitted. This movement is not confined to plane surfaces, but may exist between any two contiguous surfaces, of whatever form.

**Angular Movement.**—Angular movement occurs only between the long bones, and by it the angle between the two bones is increased or diminished. It may take place: (1) forward and backward, constituting flexion and extension; or (2) toward and from the median plane of the body, or, in the case of the fingers or toes, from the middle line of the hand or foot, constituting adduction and abduction. The strictly ginglymoid or hinge-joints admit of flexion and extension only. Abduction and adduction, combined with flexion and extension, are met with in the more movable joints; as in the hip, the shoulder, the wrist, and the carpometacarpal joint of the thumb.

**Circumduction.**—Circumduction is that form of motion which takes place between the head of a bone and its articular cavity, when the bone is made to circumscribe a conical space; the base of the cone is described by the distal end of the bone, the apex is in the articular cavity; this kind of motion is best seen in the shoulder- and hip-joints.

**Rotation.**—Rotation is a form of movement in which a bone moves around a central axis without undergoing any displacement from this axis; the axis of rotation may lie in a separate bone, as in the case of the pivot formed by the odontoid process of the axis vertebræ around which the atlas turns; or a bone may rotate around its own longitudinal axis, as in the rotation of the humerus at the shoulder-joint; or the axis of rotation may not be quite parallel to the long axis of the bone, as in the movement of the radius on the ulna during pronation and supination of the hand, where it is represented by a line connecting the centre of the head of the radius above with the centre of the head of the ulna below.

**Ligamentous Action of Muscles.**—The movements of the different joints of a limb are combined by means of the long muscles passing over more than one joint. These, when relaxed and stretched to their greatest extent, act as elastic ligaments in restraining certain movements of one joint, except when combined with corresponding movements of the other—the latter movements being usually in the opposite direction. Thus the shortness of the hamstring muscles prevents complete flexion of the hip, unless the knee-joint is also flexed so as to bring their attachments nearer together. The uses of this arrangement are threefold: (1) It coördinates the kinds of movements which are the most habitual and necessary, and enables them to be performed with the least expenditure of power. (2) It enables the short muscles which pass over only one joint to act upon more than one. (3) It provides the joints with ligaments which, while they are of very great power in resisting movements to an extent incompatible with the mechanism of the joint, at the same time spontaneously yield when necessary.

**Applied Anatomy.**—W. W. Keen points out how important it is "that the surgeon should remember this ligamentous action of muscles in making passive motion—for instance, at the wrist

after Colles' fracture. If the fingers be extended, the wrist can be flexed to a right angle. If, however, they be first flexed as in 'making a fist,' flexion at the wrist is quickly limited to from forty to fifty degrees in different persons, and is very painful beyond that point. Hence passive motion here should be made with the fingers extended. In the leg, when flexing the hip, the knee should be flexed."

The articulations may be grouped into those of the trunk, and those of the upper and lower extremities.

## ARTICULATIONS OF THE TRUNK.

These may be divided into the following groups, viz.:

- |                                    |  |
|------------------------------------|--|
| I. Of the Vertebral Column.        | VI. Of the Cartilages of the Ribs with the |
| II. Of the Atlas with the Axis.    | Sternum, and with Each Other.              |
| III. Of the Vertebral Column with  | VII. Of the Sternum.                       |
| the Cranium.                       | VIII. Of the vertebral Column with the     |
| IV. Of the Mandible.               | Pelvis.                                    |
| V. Of the Ribs with the Vertebrae. | IX. Of the Pelvis.                         |

### I. Articulations of the Vertebral Column.

The articulations of the vertebral column consist of (1) a series of amphiarthrodial joints between the vertebral bodies, and (2) a series of diarthrodial joints between the vertebral arches.

1. **Articulations of Vertebral Bodies** (*intercentral ligaments*).—The articulations between the bodies of the vertebrae are amphiarthrodial joints, and the individual vertebrae move only slightly on each other. When, however, this slight degree of movement between the pairs of bones takes place in all the joints of the vertebral column, the total range of movement is very considerable. The ligaments of these articulations are the following:

The Anterior Longitudinal.      The Posterior Longitudinal.  
The Intervertebral Fibrocartilages.

**The Anterior Longitudinal Ligament** (*ligamentum longitudinale anterius; anterior common ligament*) (Figs. 424, 435).—The anterior longitudinal ligament is a broad and strong band of fibres, which extends along the anterior surfaces of the bodies of the vertebrae, from the axis to the sacrum. It is broader below than above, thicker in the thoracic than in the cervical and lumbar regions, and somewhat thicker opposite the bodies of the vertebrae than opposite the intervertebral fibrocartilages. It is attached, above, to the body of the axis, where it is continuous with the anterior atlantoaxial ligament, and extends down as far as the upper part of the front of the sacrum. It consists of dense longitudinal fibres, which are intimately adherent to the intervertebral fibrocartilages and the prominent margins of the vertebrae, but not to the middle parts of the bodies. In the latter situation the ligament is thick and serves to fill up the concavities on the anterior surfaces, and to make the front of the vertebral column more even. It is composed of several layers of fibres, which vary in length, but are closely interlaced with each other. The most superficial fibres are the longest and extend between four or five vertebrae. A second, subjacent set extends between two or three vertebrae; while a third set, the shortest and deepest, reaches from one vertebra to the next. At the sides of the bodies the ligament consists of a few short fibres which pass from one vertebra to the next, separated from the concavities of the vertebral bodies by oval apertures for the passage of vessels.

**The Posterior Longitudinal Ligament** (*ligamentum longitudinale posterius*; *posterior common ligament*) (Figs. 424, 425).—The posterior longitudinal ligament is situated within the vertebral canal, and extends along the posterior surfaces of the bodies




FIG. 424.—Median sagittal section of two lumbar vertebrae and their ligaments.

of the vertebrae, from the body of the axis, where it is continuous with the *membrana tectoria*, to the sacrum. It is broader above than below, and thicker in the thoracic than in the cervical and lumbar regions. In the situation of the intervertebral fibrocartilages and contiguous margins of the vertebrae, where the ligament is more intimately adherent, it is broad, and in the thoracic and lumbar regions presents a series of dentations with intervening concave margins; but it is narrow and thick over the centres of the bodies, from which it is separated by the basivertebral veins. This ligament is composed of smooth, shining, longitudinal fibres, denser and more compact than those of the anterior ligament, and consists of superficial layers occupying the interval between three or four vertebrae, and deeper layers which extend between adjacent vertebrae.

**The Intervertebral Fibrocartilages** (*fibrocartilagineae intervertebrales*; *intervertebral disks*) (Figs. 424, 436).—The intervertebral fibrocartilages are interposed between the adjacent surfaces of the bodies of the vertebrae, from the axis to the sacrum, and form the chief bonds of connection between the vertebrae. They vary in shape, size, and thickness, in different parts of the vertebral column. In *shape* and *size* they correspond with the surfaces of the bodies between which they are placed, except in the cervical region, where they are slightly smaller from side to side than the corresponding bodies. In *thickness* they vary




FIG. 425.—Posterior longitudinal ligament, in the thoracic region.

not only in the different regions of the column, but in different parts of the same fibrocartilage; they are thicker in front than behind in the cervical and lumbar regions, and thus contribute to the anterior convexities of these parts of the column; while they are of nearly uniform thickness in the thoracic region, the anterior concavity of this part of the column being almost entirely owing to the shape of the vertebral bodies. The intervertebral fibrocartilages constitute about one-fourth of the length of the vertebral column, exclusive of the first two vertebræ; but this amount is not equally distributed between the various bones, the cervical and lumbar portions having, in proportion to their length, a much greater amount than the thoracic region, with the result that these parts possess greater pliancy and freedom of movement. The intervertebral fibrocartilages are adherent, by their surfaces, to thin layers of hyaline cartilage which cover the upper and under surfaces of the bodies of the vertebræ; in the lower cervical vertebræ, however, small joints lined by synovial membrane are occasionally present between the upper surfaces of the bodies and the margins of the fibrocartilages on either side. By their circumferences the intervertebral fibrocartilages are closely connected in front to the anterior, and behind to the posterior, longitudinal ligaments. In the thoracic region they are joined laterally, by means of the inter-articular ligaments, to the heads of those ribs which articulate with two vertebræ.

**Structure of the Intervertebral Fibrocartilages.**—Each is composed, at its circumference, of laminæ of fibrous tissue and fibrocartilage, forming the *annulus fibrosus*; and, at its centre, of a soft, pulpy, highly elastic substance, of a yellowish color, which projects considerably above the surrounding level when the disk is divided horizontally. This pulpy substance (*nucleus pulposus*), especially well-developed in the lumbar region, is the remains of the notochord. The laminæ are arranged concentrically; the outermost consist of ordinary fibrous tissue, the others of white fibrocartilage. The laminæ are not quite vertical in their direction, those near the circumference being curved outward and closely approximated; while those nearest the centre curve in the opposite direction, and are somewhat more widely separated. The fibres of which each lamina is composed are directed, for the most part, obliquely from above downward, the fibres of adjacent laminæ passing in opposite directions and varying in every layer; so that the fibres of one layer are directed across those of another, like the limbs of the letter X. This laminar arrangement belongs to about the outer half of each fibrocartilage. The pulpy substance presents no such arrangement, and consists of a fine fibrous matrix, containing angular cells united to form a reticular structure.

**Applied Anatomy.**—When an aneurism presses on the vertebral column, the vertebral bodies are often deeply eroded by the tumor, while the intervertebral fibrocartilages remain intact. The fibrocartilages are the first to be destroyed, however, in tuberculosis of the vertebral column, where, as not infrequently happens, the disease begins in the fibrocartilages, and spreads thence to the bodies of the two adjoining vertebræ simultaneously.

**2. Articulations of Vertebral Arches.**—The joints between the articular processes of the vertebræ belong to the arthrodial variety and are enveloped by capsules lined by synovial membranes; while the laminæ spinous and transverse processes are connected by the following ligaments:

The Ligamenta Flava.  
The Supraspinal.

The Ligamentum Nuchæ.  
The Interspinal.

The Intertransverse.

**The Articular Capsules** (*capsulae articulares; capsular ligaments*) (Fig. 424).—The articular capsules are thin and loose, and are attached to the margins of the articular processes of adjacent vertebræ. They are longer and looser in the cervical than in the thoracic and lumbar regions.

**The Ligamenta Flava** (*ligamenta subflava*) (Fig. 426).—The ligamenta flava connect the laminæ of adjacent vertebræ, from the axis to the first segment of the sacrum. They are best seen from the interior of the vertebral canal; when looked at from the outer surface they appear short, being overlapped by the laminæ. Each ligament

consists of two lateral portions which commence one on either side of the roots of the articular processes, and extend backward to the point where the laminae meet to form the spinous process; the posterior margins of the two portions are in contact and to a certain extent united, slight intervals being left for the passage of small vessels. Each consists of yellow elastic tissue, the fibres of which, almost perpendicular in direction, are attached to the anterior surface of the lamina above, some distance from its inferior margin, and to the posterior surface and upper margin of the lamina below. In the cervical region the ligaments are thin, but broad and long; they are thicker in the thoracic region, and thickest in the lumbar region. Their marked elasticity serves to preserve the upright posture, and to assist the vertebral column in resuming it after flexion.

**The Supraspinal Ligament** (*ligamentum supraspinale*; *supraspinous ligament*) (Fig. 424).—The supraspinal ligament is a strong fibrous cord, which connects together the apices of the spinous processes from

the seventh cervical vertebra to the sacrum; at the points of attachment to the tips of the spinous processes fibrocartilage is developed in the ligament. It is thicker and broader in the lumbar than in the thoracic region, and intimately blended, in both situations, with the neighboring fascia. The most superficial fibres of this ligament extend over three or four vertebrae; those more deeply seated pass between two or three vertebrae; while the deepest connect the spinous processes of neighboring vertebrae. Between the spinous processes it is continuous with the interspinal ligaments. It is continued upward to the external occipital protuberance and median nuchal line, as the *ligamentum nuchae*.

**The Ligamentum Nuchae.**—The *ligamentum nuchae* is a fibrous membrane, which, in the neck, represents the supraspinal ligaments of the lower vertebrae. It extends from the external occipital protuberance and median nuchal line to the spinous process of the seventh cervical vertebra. From its anterior border a fibrous lamina is given off, which is attached to the posterior tubercle of the atlas, and to the spinous processes of the cervical vertebrae, and forms a septum between the muscles on either side of the neck. In man it is merely the rudiment of an important elastic ligament, which, in some of the lower animals, serves to sustain the weight of the head.

**The Interspinal Ligaments** (*ligamenta interspinalia*; *interspinous ligaments*) (Fig. 424).—The interspinal ligaments thin and membranous, connect adjoining spinous processes and extend from the root to the apex of each process. They meet the *ligamenta flava* in front and the supraspinal ligament behind. They are narrow and elongated in the thoracic region; broader, thicker, and quadrilateral in form in the lumbar region; and only slightly developed in the neck.

**The Intertransverse Ligaments** (*ligamenta intertransversaria*).—The intertransverse ligaments are interposed between the transverse processes. In the cervical region they consist of a few irregular, scattered fibres; in the thoracic region they are rounded cords intimately connected with the deep muscles of the back; in the lumbar region they are thin and membranous.




FIG. 426.—Vertebral arches of three thoracic vertebrae viewed from the front.



**Movements.**—The movements permitted in the vertebral column are: *flexion*, *extension*, *lateral movement*, *circumduction*, and *rotation*.

In *flexion*, or movement forward, the anterior longitudinal ligament is relaxed, and the intervertebral fibrocartilages are compressed in front; while the posterior longitudinal ligament, the ligamenta flava, and the inter- and supraspinal ligaments are stretched, as well as the posterior fibres of the intervertebral fibrocartilages. The interspaces between the laminae are widened, and the inferior articular processes glide upward, upon the superior articular processes of the subjacent vertebrae. Flexion is the most extensive of all the movements of the vertebral column, and is freest in the lumbar region.

In *extension*, or movement backward, an exactly opposite disposition of the parts takes place. This movement is limited by the anterior longitudinal ligament, and by the approximation of the spinous processes. It is freest in the cervical region.

In *lateral movement*, the sides of the intervertebral fibrocartilages are compressed, the extent of motion being limited by the resistance offered by the surrounding ligaments. This movement may take place in any part of the column, but is freest in the cervical and lumbar regions.

*Circumduction* is very limited, and is merely a succession of the preceding movements.

*Rotation* is produced by the twisting of the intervertebral fibrocartilages; this, although only slight between any two vertebrae, allows of a considerable extent of movement when it takes place in the whole length of the column, the front of the upper part of the column being turned to one or other side. This movement occurs to a slight extent in the cervical region, is freer in the upper part of the thoracic region, and absent in the lumbar region.

The extent and variety of the movements are influenced by the shape and direction of the articular surfaces. In the *cervical* region the upward inclination of the superior articular surfaces allows of free flexion and extension. Extension can be carried farther than flexion; at the upper end of the region it is checked by the locking of the posterior edges of the superior atlantal facets in the condyloid fossae of the occipital bone; at the lower end it is limited by a mechanism whereby the inferior articular processes of the seventh cervical vertebra slip into grooves behind and below the superior articular processes of the first thoracic. Flexion is arrested just beyond the point where the cervical convexity is straightened; the movement is checked by the apposition of the projecting lower lips of the bodies of the vertebrae with the shelving surfaces on the bodies of the subjacent vertebrae. Lateral flexion and rotation are free in the cervical region; they are, however, always combined. The upward and medial inclinations of the superior articular surfaces impart a rotatory movement during lateral flexion, while pure rotation is prevented by the slight medial slope of these surfaces.

In the *thoracic* region, notably in its upper part, all the movements are limited in order to reduce interference with respiration to a minimum. The almost complete absence of an upward inclination of the superior articular surfaces prohibits any marked flexion, while extension is checked by the contact of the inferior articular margins with the laminae, and the contact of the spinous processes with one another. The mechanism between the seventh cervical and the first thoracic vertebrae, which limits extension of the cervical region, will also serve to limit flexion of the thoracic region when the neck is extended. Rotation is free in the thoracic region: the superior articular processes are segments of a cylinder whose axis is in the mid-ventral line of the vertebral bodies. The direction of the articular facets would allow of free lateral flexion, but this movement is considerably limited in the upper part of the region by the resistance of the ribs and sternum.

In the *lumbar* region flexion and extension are free. Flexion can be carried farther than extension, and is possible to just beyond the straightening of the lumbar curve; it is, therefore, greatest at the lowest part where the curve is sharpest. The inferior articular facets are not in close apposition with the superior facets of the subjacent vertebrae, and on this account a considerable amount of lateral flexion is permitted. For the same reason a slight amount of rotation can be carried out, but this is so soon checked by the interlocking of the articular surfaces that it is negligible.

The principal muscles which produce *flexion* are the Sternocleidomastoideus, Longus capitis, and Longus colli; the Scaleri; the abdominal muscles and the Psoas major. *Extension* is produced by the intrinsic muscles of the back, assisted in the neck by the Splenius, Semispinales dorsi and cervicis, and the Multifidus. *Lateral* motion is produced by the intrinsic muscles of the back by the Splenius, the Scaleri, the Quadratus lumborum, and the Psoas major, the muscles of one side only acting; and *rotation* by the action of the following muscles of one side only, viz., the Sternocleidomastoideus, the Longus capitis, the Scaleri, the Multifidus, the Semispinalis capitis, and the abdominal muscles.

## II. Articulation of the Atlas with the Epistropheus or Axis (Articulatio Atlantoepistrophica).

The articulation of the atlas with the axis is of a complicated nature, comprising no fewer than four distinct joints. There is a pivot articulation between

the odontoid process of the axis and the ring formed by the anterior arch and the transverse ligament of the atlas (see Fig. 429); here there are two joints: one between the posterior surface of the anterior arch of the atlas and the front of the odontoid process; the other between the anterior surface of the ligament and the back of the process. Between the articular processes of the two bones there is on either side an arthrodial or gliding joint. The ligaments connecting these bones are:

Two Articular Capsules.  
The Anterior Atlantoaxial.

The Posterior Atlantoaxial.  
The Transverse.

**The Articular Capsules** (*capsulae articulares; capsular ligaments*).—The articular capsules are thin and loose, and connect the margins of the lateral masses of the atlas with those of the posterior articular surfaces of the axis. Each is strengthened at its posterior and medial part by an **accessory ligament**, which is attached below to the body of the axis near the base of the odontoid process, and above to the lateral mass of the atlas near the transverse ligament.




FIG. 427.—Anterior atlantooccipital membrane and atlantoaxial ligament.

**The Anterior Atlantoaxial Ligament** (Fig. 427).—This ligament is a strong membrane, fixed, *above*, to the lower border of the anterior arch of the atlas; *below*, to the front of the body of the axis. It is strengthened in the middle line by a rounded cord, which connects the tubercle on the anterior arch of the atlas to the body of the axis, and is a continuation upward of the anterior longitudinal ligament. The ligament is in relation, in front, with the Longi capitis.

**The Posterior Atlantoaxial Ligament** (Fig. 428).—This ligament is a broad, thin membrane attached, *above*, to the lower border of the posterior arch of the atlas; *below*, to the upper edges of the laminae of the axis. It supplies the place of the ligamenta flava, and is in relation, *behind*, with the Obliqui capitis inferiores.

**The Transverse Ligament of the Atlas** (*ligamentum transversum atlantis*) (Figs. 429, 430, 431).—The transverse ligament of the atlas is a thick, strong band, which arches across the ring of the atlas, and retains the odontoid process in contact with the anterior arch. It is concave in front, convex behind, broader and thicker in

the middle than at the ends, and firmly attached on either side to a small tubercle on the medial surface of the lateral mass of the atlas. As it crosses the odontoid process, a small fasciculus (*crus superius*) is prolonged upward, and another (*crus inferius*) downward, from the superficial or posterior fibres of the ligament. The




FIG. 428.—Posterior atlanto-occipital membrane and atlantoaxial ligament.

former is attached to the basilar part of the occipital bone, in close relation with the membrana tectoria; the latter is fixed to the posterior surface of the body of the axis; hence, the whole ligament is named the **cruciate ligament of the atlas**. The transverse ligament divides the ring of the atlas into two unequal parts: of these, the posterior and larger serves for the transmission of the medulla spinalis




FIG. 429.—Articulation between odontoid process and atlas.

and its membranes and the accessory nerves; the anterior and smaller contains the odontoid process. The neck of the odontoid process is constricted where it is embraced posteriorly by the transverse ligament, so that this ligament suffices to retain the odontoid process in position after all the other ligaments have been divided.




FIG. 430.—Membrana tectoria, transverse, and alar ligaments.




FIG. 431.—Median sagittal section through the occipital bone and first three cervical vertebrae. (Spalteholz.)



**Synovial Membranes.**—There is a synovial membrane for each of the four joints; the joint cavity between the odontoid process and the transverse ligament is often continuous with those of the atlantoöccipital articulations.

The opposed articular surfaces of the atlas and axis are not reciprocally curved; both surfaces are convex in their long axes. When, therefore, the upper facet glides forward on the lower it

**Movements.**—This joint allows the rotation of the atlas (and, with it, the skull) upon the axis, the extent of rotation being limited by the alar ligaments.

also descends; the fibres of the articular capsule are relaxed in a vertical direction, and will then permit of movement in an antero-posterior direction. By this means a shorter capsule suffices and the strength of the joint is materially increased.<sup>1</sup>

The principal muscles by which these movements are produced are the Sternocleidomastoideus and Semispinalis capitis of one side, acting with the Longus capitis, Splenius, Longissimus capitis, Rectus capitis posterior major, and Obliqui capitis superior and inferior of the other side.

### III. Articulations of the Vertebral Column with the Cranium.

The ligaments connecting the vertebral column with the cranium may be divided into two sets: those uniting the atlas with the occipital bone, and those connecting the axis with the occipital bone.

**Articulation of the Atlas with the Occipital Bone** (*articulatio atlantooccipitalis*).

—The articulation between the atlas and the occipital bone consists of a pair of condyloid joints. The ligaments connecting the bones are:

Two Articular Capsules.

The Anterior Atlantoöccipital  
membrane.

The Posterior Atlantoöccipital  
membrane.

Two Lateral Atlantoöccipital.

**The Articular Capsules** (*capsulae articulares; capsular ligaments*).—The articular capsules surround the condyles of the occipital bone, and connect them with the articular processes of the atlas: they are thin and loose.

**The Anterior Atlantoöccipital Membrane** (*membrana atlantooccipitalis anterior; anterior atlantoöccipital ligament*) (Fig. 427).—The anterior atlantoöccipital membrane is broad and composed of densely woven fibres, which pass between the anterior margin of the foramen magnum above, and the upper border of the anterior arch of the atlas below; laterally, it is continuous with the articular capsules; in front, it is strengthened in the middle line by a strong, rounded cord, which connects the basilar part of the occipital bone to the tubercle on the anterior arch of the atlas. This membrane is in relation in *front* with the Recti capitis anteriores, *behind* with the alar ligaments.

**The Posterior Atlantoöccipital Membrane** (*membrana atlantooccipitalis posterior; posterior atlantoöccipital ligament*) (Fig. 428).—The posterior atlantoöccipital membrane, broad but thin, is connected above, to the posterior margin of the foramen magnum; below, to the upper border of the posterior arch of the atlas. On either side this membrane is defective below, over the groove for the vertebral artery, and forms with this groove an opening for the entrance of the artery and the exit of the suboccipital nerve. The free border of the membrane, arching over the artery and nerve, is sometimes ossified. The membrane is in relation, *behind*, with the Recti capitis posteriores minores and Obliqui capitis superiores; in *front*, with the dura mater of the vertebral canal, to which it is intimately adherent.

**The Lateral Ligaments.**—The lateral ligaments are thickened portions of the articular capsules, reinforced by bundles of fibrous tissue, and are directed obliquely upward and medialward; they are attached above to the jugular processes of the occipital bone, and below, to the bases of the transverse processes of the atlas.

<sup>1</sup> Corner ("The Physiology of the Atlanto-axial Joints," *Journal of Anatomy and Physiology*, vol. xli) states that the movements which take place at these articulations are of a complex nature. The first part of the movement is an eccentric or asymmetrical one; the atlanto-axial joint of the side to which the head is moved is fixed, or practically fixed, by the muscles of the neck, and forms the centre of the movement, while the opposite atlantal facet is carried downward and forward on the corresponding axial facet. The second part of the movement is centric and symmetrical, the odontoid process forming the axis of the movement.

**Synovial Membranes.**—There are two synovial membranes: one lining each of the articular capsules. The joints frequently communicate with that between the posterior surface of the odontoid process and the transverse ligament of the atlas.

**Movements.**—The movements permitted in this joint are (a) flexion and extension, which give rise to the ordinary forward and backward nodding of the head, and (b) slight lateral motion to one or other side. *Flexion* is produced mainly by the action of the *Longi capitis* and *Recti capitis anteriores*; *extension* by the *Recti capitis posteriores major* and *minor*, the *Obliquus superior*, the *Semispinalis capitis*, *Splenius capitis*, *Sternocleidomastoideus*, and upper fibres of the *Trapezius*. The *Recti laterales* are concerned in the *lateral movement*, assisted by the *Trapezius*, *Splenius capitis*, *Semispinalis capitis*, and the *Sternocleidomastoideus* of the same side, all acting together.

#### Ligaments Connecting the Axis with the Occipital Bone.—

The *Membrana Tectoria*.

Two *Alar*.

The *Apical Odontoid*.

**The *Membrana Tectoria* (*occipitoaxial ligament*)** (Figs. 430, 431).—The *membrana tectoria* is situated within the vertebral canal. It is a broad, strong band, which covers the odontoid process and its ligaments, and appears to be a prolongation upward of the posterior longitudinal ligament of the vertebral column. It is fixed, below, to the posterior surface of the body of the axis, and, expanding as it ascends, is attached to the basilar groove of the occipital bone, in front of the foramen magnum, where it blends with the cranial dura mater. Its anterior surface is in relation with the transverse ligament of the atlas, and its posterior surface with the dura mater.

**The *Alar Ligaments* (*ligamenta alaria; odontoid ligaments*)** (Fig. 430).—The alar ligaments are strong, rounded cords, which arise one on either side of the upper part of the odontoid process, and, passing obliquely upward and lateralward, are inserted into the rough depressions on the medial sides of the condyles of the occipital bone. In the triangular interval between these ligaments is another fibrous cord, the *apical odontoid ligament* (Fig. 431), which extends from the tip of the odontoid process to the anterior margin of the foramen magnum, being intimately blended with the deep portion of the anterior atlantooccipital membrane and superior crus of the transverse ligament of the atlas. It is regarded as a rudimentary intervertebral fibrocartilage, and in it traces of the notochord may persist. The alar ligaments limit rotation of the cranium and therefore receive the name of *check ligaments*.

In addition to the ligaments which unite the atlas and axis to the skull, the *ligamentum nuchae* (page 387) must be regarded as one of the ligaments connecting the vertebral column with the cranium.

**Applied Anatomy.**—The ligaments which unite the component parts of the vertebral column together are so strong, and the bones are so interlocked by the arrangement of their articulating processes, that dislocation is very uncommon, and, indeed, except in the upper part of the neck, rarely occurs unless accompanied by fracture. Dislocation of the occipital bone from the atlas has been recorded only in one or two cases; but dislocation of the atlas from the axis, with rupture of the transverse ligament, is much more common; it is the mode in which death is produced in many cases of execution by hanging. In the lower part of the neck—that is, below the third cervical vertebra—dislocation unattended by fracture occasionally takes place.

#### IV. Articulation of the Mandible (*Articulatio Mandibularis; Temporo-mandibular Articulation*).

This is a ginglymo-arthrodial joint; the parts entering into its formation on either side are: the anterior part of the mandibular fossa of the temporal bone and the articular tubercle above; and the condyle of the mandible below. The ligaments of the joint are the following:

The *Articular Capsule*.

The *Sphenomandibular*.

The *Temporomandibular*.

The *Articular Disk*.

The *Stylomandibular*.



**The Articular Capsule** (*capsula articularis*; *capsular ligament*).—The articular capsule is a thin, loose envelope, attached above to the circumference of the mandibular fossa and the articular tubercle immediately in front; below, to the neck of the condyle of the mandible.




FIG. 432.—Articulation of the mandible. Lateral aspect.

**The Temporomandibular Ligament** (*ligamentum temporomandibulare*; *external lateral ligament*) (Fig. 432).—The temporomandibular ligament consists of two




FIG. 433.—Articulation of the mandible. Medial aspect.




FIG. 434.—Sagittal section of the articulation of the mandible.

short, narrow fasciculi, one in front of the other, attached, above, to the lateral surface of the zygomatic arch and to the tubercle on its lower border; below,

to the lateral surface and posterior border of the neck of the mandible. It is broader above than below, and its fibres are directed obliquely downward and backward. It is covered by the parotid gland, and by the integument.

**The Sphenomandibular Ligament** (*ligamentum sphenomandibulare; internal lateral ligament*) (Fig. 433).—The sphenomandibular ligament is a flat, thin band which is attached above to the spina angularis of the sphenoid bone, and, becoming broader as it descends, is fixed to the lingula of the mandibular foramen. Its lateral surface is in relation, above, with the Pterygoideus externus; lower down, it is separated from the neck of the condyle by the internal maxillary vessels; still lower, the inferior alveolar vessels and nerve and a lobule of the parotid gland lie between it and the ramus of the mandible. Its medial surface is in relation with the Pterygoideus internus.

**The Articular Disk** (*discus articularis; interarticular fibrocartilage; articular meniscus*) (Fig. 434).—The articular disk is a thin, oval plate, placed between the condyle of the mandible and the mandibular fossa. Its upper surface is concavo-convex from before backward, to accommodate itself to the form of the mandibular fossa and the articular tubercle. Its under surface, in contact with the condyle, is concave. Its circumference is connected to the articular capsule; and in front to the tendon of the Pterygoideus externus. It is thicker at its periphery, especially behind, than at its centre. The fibres of which it is composed have a concentric arrangement, more apparent at the circumference than at the centre. It divides the joint into two cavities, each of which is furnished with a synovial membrane.

**The Synovial Membranes.**—The synovial membranes, two in number, are placed one above, and the other below, the articular disk. The upper one, the larger and looser of the two, is continued from the margin of the cartilage covering the mandibular fossa and articular tubercle on to the upper surface of the disk. The lower one passes from the under surface of the disk to the neck of the condyle, being prolonged a little farther downward behind than in front. The articular disk is sometimes perforated in its centre, and the two cavities then communicate with each other.

**The Stylomandibular Ligament** (*ligamentum stylomandibulare; stylomaxillary ligament*) (Fig. 433).—The stylomandibular ligament is a specialized band of the cervical fascia, which extends from near the apex of the styloid process of the temporal bone to the angle and posterior border of the ramus of the mandible, between the Masseter and Pterygoideus internus. This ligament separates the parotid from the submaxillary gland, and from its deep surface some fibres of the Styloglossus take origin. Although classed among the ligaments of the temporomandibular joint, it can only be considered as accessory to it.

The **nerves** of the temporomandibular joint are derived from the auriculotemporal and masseteric branches of the mandibular nerve, the **arteries** from the superficial temporal branch of the external carotid.

**Movements.**—The movements permitted in this articulation are extensive. Thus, the mandible may be depressed or elevated, or carried forward or backward; a slight amount of side-to-side movement is also permitted. It must be borne in mind that there are two distinct joints in this articulation—one between the condyle and the articular disk, and another between the disk and the mandibular fossa. When the mouth is but slightly opened, as during ordinary conversation, the movement is confined to the lower of the two joints. On the other hand, when the mouth is opened more widely, both joints are concerned in the movement; in the lower joint the movement is of a hinge-like character, the condyle moving around a transverse axis on the disk, while in the upper joint the movement is of a gliding character, the disk, together with the condyle, gliding forward on to the articular tubercle, around an axis which passes through the mandibular foramina. These two movements take place simultaneously, the condyle and disk move forward on the eminence, and at the same time the condyle revolves on the disk. In shutting the mouth the reverse action takes place; the disk glides back, carrying the condyle with it, and this at the same time moves back to its former position. When the mandible is carried horizontally forward, as in protruding the lower incisor teeth in front of the upper, the movement takes place principally in the upper joint, the disk and the condyle gliding forward on the mandibular fossa

and articular tubercle. The grinding or chewing movement is produced by one condyle, with its disk, gliding alternately forward and backward, while the other condyle moves simultaneously in the opposite direction; at the same time the condyle undergoes a vertical rotation on the disk. One condyle advances and rotates, the other condyle recedes and rotates, in alternate succession.

The mandible is *depressed* by its own weight, assisted by the Platysma, the Digastricus, the Mylohyoideus, and the Geniohyoideus. It is *elevated* by the Masseter, Pterygoideus internus, and the anterior part of the Temporalis. It is drawn *forward* by the simultaneous action of the Pterygoidei internus and externus, the superficial fibres of the Masseter and the anterior fibres of the Temporalis; and *backward* by the deep fibres of the Masseter and the posterior fibres of the Temporalis. The grinding movement is caused by the alternate action of the Pterygoidei of either side.

**Applied Anatomy.**—The mandible is dislocated only in one direction, viz., forward. The accident is caused by violence or by muscular action. When the mouth is open, the condyle is situated on the articular tubercle, and any sudden violence, or even a sudden muscular spasm, as during a convulsive yawn, may displace the condyle forward into the infratemporal fossa. The displacement may be unilateral or bilateral. Reduction is accomplished by depressing the jaw with the thumbs placed on the last molar teeth, and at the same time elevating the chin. The downward pressure overcomes the spasm of the Masseter, Temporalis, and Pterygoideus internus, and elevation of the chin throws the condyle backward; the above-mentioned muscles then draw the condyle back into its normal position.

In close relation to the condyle of the mandible are the external acoustic meatus and the tympanic cavity; any force, therefore, applied to the bone is liable to be attended with damage to these parts, or inflammation in the joint may extend to them; or on the other hand inflammation of the tympanic cavity may involve the articulation and cause its destruction, thus leading to ankylosis of the joint. The joint is also occasionally the seat of osteoarthritis, causing great suffering during efforts of mastication. A peculiar affection sometimes attacks the neck and condyle of the mandible, consisting in hypertrophy and elongation of these parts and consequent protrusion of the chin to the opposite side.

## V. Costovertebral Articulations (Articulationes Costovertebrales).

The articulations of the ribs with the vertebral column may be divided into two sets, one connecting the heads of the ribs with the bodies of the vertebræ, another uniting the necks and tubercles of the ribs with the transverse processes.

1. **Articulations of the Heads of the Ribs** (*articulationes capitulorum; costocentral articulations*) (Fig. 435).—These constitute a series of gliding or arthrodial joints, and are formed by the articulation of the heads of the typical ribs with the facets on the contiguous margins of the bodies of the thoracic vertebræ and with the intervertebral fibrocartilages between them; the first, tenth, eleventh, and twelfth ribs each articulate with a single vertebra. The ligaments of the joints are:

The Articular Capsule.

The Radiate.

The Interarticular.

**The Articular Capsule** (*capsula articularis; capsular ligament*).—The articular capsule surrounds the joint, being composed of short, strong fibres, connecting the head of the rib with the circumference of the articular cavity formed by the intervertebral fibrocartilage and the adjacent vertebræ. It is most distinct at the upper and lower parts of the articulation; some of its upper fibres pass through the intervertebral foramen to the back of the intervertebral fibrocartilage, while its posterior fibres are continuous with the ligament of the neck of the rib.

**The Radiate Ligament** (*ligamentum capituli costae radiatum; anterior costovertebral or stellate ligament*).—The radiate ligament connects the anterior part of the head of each rib with the side of the bodies of two vertebræ, and the intervertebral fibrocartilage between them. It consists of three flat fasciculi, which are attached to the anterior part of the head of the rib, just beyond the articular surface. The superior fasciculus ascends and is connected with the body of the vertebra above; the inferior one descends to the body of the vertebra below; the middle one, the smallest and least distinct, is horizontal and is attached to the intervertebral fibrocartilage. The radiate ligament is in relation, in *front*, with the thoracic

ganglia of the sympathetic trunk, the pleura, and, on the right side, with the azygos vein; *behind*, with the interarticular ligament and synovial membranes.

In the case of the first rib, this ligament is not divided into three fasciculi, but its fibres are attached to the body of the last cervical vertebra, as well as to that of the first thoracic. In the articulations of the heads of the tenth, eleventh, and twelfth ribs, each of which articulates with a single vertebra, the triradiate arrangement does not exist; but the fibres of the ligament in each case are connected to the vertebra above, as well as to that with which the rib articulates.




FIG. 435.—Costovertebral articulations. Anterior view.

**The Interarticular Ligament** (*ligamentum capituli costae interarticulare*; *interarticular ligament*).—The interarticular ligament is situated in the interior of the joint. It consists of a short band of fibres, flattened from above downward, attached by one extremity to the crest separating the two articular facets on the head of the rib, and by the other to the intervertebral fibrocartilage; it divides the joint into two cavities. In the joints of the first, tenth, eleventh, and twelfth ribs, the interarticular ligament does not exist; consequently, there is but one cavity in each of these articulations. This ligament is the homologue of the *ligamentum conjugale* present in some mammals, and uniting the heads of opposite ribs, across the back of the intervertebral fibrocartilage.

**Synovial Membranes.**—There are two synovial membranes in each of the articulations where an interarticular ligament exists, one above and one below this structure; but only one in those joints where there are single cavities.

**2. Costotransverse Articulations** (*articulationes costotransversariae*) (Fig. 436).—The articular portion of the tubercle of the rib forms with the articular surface on the adjacent transverse process an arthrodiar joint.

In the eleventh and twelfth ribs this articulation is wanting.

The ligaments of the joint are:

The Articular Capsule.

The Posterior Costotransverse.

The Anterior Costotransverse.

The Ligament of the Neck of the Rib.

The Ligament of the Tubercle of the Rib.

**The Articular Capsule** (*capsula articularis*; *capsular ligament*).—The articular capsule is a thin membrane attached to the circumferences of the articular surfaces, and lined by a synovial membrane.




FIG. 436.—Costotransverse articulation. Seen from above.




FIG. 437.—Section of the costotransverse joints from the third to the ninth inclusive. Contrast the concave facets on the upper with the flattened facets on the lower transverse processes.

**The Anterior Costotransverse Ligament** (*ligamentum costotransversarium anterius*; *anterior superior ligament*).—The anterior costotransverse ligament is attached below to the sharp crest on the upper border of the neck of the rib, and passes obliquely upward and lateralward to the lower border of the transverse process immediately above. It is in relation, in front, with the intercostal vessels and nerves; its medial border is thickened and free, and bounds an aperture which transmits the posterior branches of the intercostal vessels and nerves; its lateral border is continuous with a thin aponeurosis, which covers the *Intercostalis externus*.

The first rib has no anterior costotransverse ligament. A band of fibres, the **lumbocostal ligament**, in series with the anterior costotransverse ligaments, connects the neck of the twelfth rib to the base of the transverse process of the first lumbar vertebra; it is merely a thickened portion of the posterior layer of the lumbodorsal fascia.

**The Posterior Costotransverse Ligament** (*ligamentum costotransversarium posterius*).—The posterior costotransverse ligament is a feeble band which is attached below to the neck of

the rib and passes upward and medialward to the base of the transverse process and lateral border of the inferior articular process of the vertebra above.

**The Ligament of the Neck of the Rib** (*ligamentum colli costae; middle costotransverse or interosseous ligament*).—The ligament of the neck of the rib consists of short but strong fibres, connecting the rough surface on the back of the neck of the rib with the anterior surface of the adjacent transverse process. A rudimentary ligament may be present in the case of the eleventh and twelfth ribs.

**The Ligament of the Tubercle of the Rib** (*ligamentum tuberculi costae; posterior costotransverse ligament*).—The ligament of the tubercle of the rib is a short but thick and strong fasciculus, which passes obliquely from the apex of the transverse process to the rough non-articular portion of the tubercle of the rib. The ligaments attached to the upper ribs ascend from the transverse processes; they are shorter and more oblique than those attached to the inferior ribs, which descend slightly.

**Movements.**—The heads of the ribs are so closely connected to the bodies of the vertebrae by the radiate and interarticular ligaments that only slight gliding movements of the articular surfaces on one another can take place. Similarly, the strong ligaments binding the necks and tubercles of the ribs to the transverse processes limit the movements of the costotransverse joints to slight gliding, the nature of which is determined by the shape and direction of the articular surfaces (Fig. 437). In the upper six ribs the articular surfaces on the tubercles are oval in shape and convex from above downward; they fit into corresponding concavities on the *anterior surfaces* of the transverse processes, so that upward and downward movements of the tubercles are associated with rotation of the rib neck on its long axis. In the seventh, eighth, ninth, and tenth ribs the articular surfaces on the tubercles are flat, and are directed obliquely downward, medialward, and backward. The surfaces with which they articulate are placed on the *upper margins* of the transverse processes; when, therefore, the tubercles are drawn up they are at the same time carried backward and medialward. The two joints, costocentral and costotransverse, move simultaneously and in the same directions, the total effect being that the neck of the rib moves as if on a single joint, of which the costocentral and costotransverse articulations form the ends. In the upper six ribs the neck of the rib moves but slightly upward and downward; its chief movement is one of rotation around its own long axis, rotation backward being associated with depression, rotation forward with elevation. In the seventh, eighth, ninth, and tenth ribs the neck of the rib moves upward, backward, and medialward, or downward, forward, and lateralward; very slight rotation accompanies these movements.

## VI. Sternocostal Articulations (*Articulationes Sternocostales; Costosternal Articulations*) (Fig. 438)

The articulations of the cartilages of the true ribs with the sternum are arthrodial joints, with the exception of the first, in which the cartilage is directly united with the sternum, and which is, therefore, a synarthrodial articulation. The ligaments connecting them are:

The Articular Capsules.

The Interarticular Sternocostal.

The Radiate Sternocostal.

The Costoxiphoid.

**The Articular Capsules** (*capsulae articulares; capsular ligaments*).—The articular capsules surround the joints between the cartilages of the true ribs and the sternum. They are very thin, intimately blended with the radiate sternocostal ligaments, and strengthened at the upper and lower parts of the articulations by a few fibres, which connect the cartilages to the side of the sternum.

**The Radiate Sternocostal Ligaments** (*ligamenta sternocostalia radiata; chondrosternal or sternocostal ligaments*).—These ligaments consist of broad and thin membranous bands that radiate from the front and back of the sternal ends of the cartilages of the true ribs to the anterior and posterior surfaces of the sternum. They are composed of fasciculi which pass in different directions. The **superior fasciculi** ascend obliquely, the **inferior fasciculi** descend obliquely, and the **middle fasciculi** run horizontally. The superficial fibres are the longest; they intermingle with the fibres of the ligaments above and below them, with those of the opposite



side, and in front with the tendinous fibres of origin of the Pectoralis major, forming a thick fibrous membrane (*membrana sterni*) which envelopes the sternum. This is more distinct at the lower than at the upper part of the bone.

**The Interarticular Sternocostal Ligament** (*ligamentum sternocostale interarticulare; interarticular chondrosternal ligament*).—This ligament is found constantly only between the second costal cartilages and the sternum. The cartilage of the *second*




FIG. 438.—Sternocostal and interchondral articulations. Anterior view.

*rib* is connected with the sternum by means of an interarticular ligament, attached by one end to the cartilage of the rib, and by the other to the fibrocartilage which unites the manubrium and body of the sternum. This articulation is provided with two synovial membranes. Occasionally the cartilage of the *third rib* is connected with the first and second pieces of the body of the sternum by an interarticular ligament. Still more rarely, similar ligaments are found in the other four

joints of the series. - In the lower two the ligament sometimes completely obliterates the cavity, so as to convert the articulation into an amphiarthrosis.

**The Costoxiphoid Ligaments** (*ligamenta costoxiphoidea; chondroxiphoid ligaments*). - These ligaments connect the anterior and posterior surfaces of the seventh costal cartilage, and sometimes those of the sixth, to the front and back of the xiphoid process. They vary in length and breadth in different subjects; those on the back of the joint are less distinct than those in front.

**Synovial Membranes.**—There is no synovial membrane between the first costal cartilage and the sternum, as this cartilage is directly continuous with the manubrium. There are two in the articulation of the second costal cartilage and generally one in each of the other joints; but those of the sixth and seventh sternocostal joints are sometimes absent; where an interarticular ligament is present, there are two synovial cavities. After middle life the articular surfaces lose their polish, become roughened, and the synovial membranes apparently disappear. In old age, the cartilages of most of the ribs become continuous with the sternum, and the joint cavities are consequently obliterated.

**Movements.**—Slight gliding movements are permitted in the sternocostal articulations.

**Interchondral Articulations** (*articulationes interchondrales; articulations of the cartilages of the ribs with each other*) (Fig. 438).—The contiguous borders of the sixth, seventh, and eighth, and sometimes those of the ninth and tenth, costal cartilages articulate with each other by small, smooth, oblong facets. Each articulation is enclosed in a thin articular capsule, lined by synovial membrane and strengthened laterally and medially by ligamentous fibres (*interchondral ligaments*) which pass from one cartilage to the other. Sometimes the fifth costal cartilages, more rarely the ninth and tenth, articulate by their lower borders with the adjoining cartilages by small oval facets; more frequently the connection is by a few ligamentous fibres.

**Costochondral Articulations.**—The lateral end of each costal cartilage is received into a depression in the sternal end of the rib, and the two are held together by the periosteum.

## VII. Articulation of the Manubrium and Body of the Sternum.

The manubrium is united to the body of the sternum either by an amphiarthrodial joint—a piece of fibrocartilage connecting the segments—or by a diarthrodial joint, in which the articular surface of each bone is clothed with a lamina of cartilage. In the latter case, the cartilage covering the body is continued without interruption on to the cartilages of the facets for the second ribs. Rivington found the diarthrodial form of joint in about one-third of the specimens examined by him, Maisonneuve more frequently. It appears to be rare in childhood, and is formed, in Rivington's opinion, from the amphiarthrodial form, by absorption. The diarthrodial joint seems to have no tendency to ossify, while the amphiarthrodial is more liable to do so, and has been found ossified as early as thirty-four years of age. The two segments are further connected by *anterior and posterior intersternal ligaments* consisting of longitudinal fibres.

**Mechanism of the Thorax.**—Each rib possesses its own range and variety of movements, but the movements of all are combined in the respiratory excursions of the thorax. Each rib may be regarded as a lever the fulcrum of which is situated immediately outside the costotransverse articulation, so that when the body of the rib is elevated the neck is depressed and *vice versa*; from the disproportion in length of the arms of the lever a slight movement at the vertebral end of the rib is greatly magnified at the anterior extremity.

The anterior ends of the ribs lie on a lower plane than the posterior; when therefore the body of the rib is elevated the anterior extremity is thrust also forward. Again, the middle of the body of the rib lies in a plane below that passing through the two extremities, so that when the body is elevated relatively to its ends it is at the same time carried outward from the median plane of the thorax. Further, each rib forms the segment of a curve which is greater than that of the rib immediately above, and therefore the elevation of a rib increases the transverse diameter of the thorax in the plane to which it is raised. The modifications of the rib movements at their vertebral ends have already been described (page 399). Further modifications result from the

attachments of their anterior extremities, and it is convenient therefore to consider separately the movements of the ribs of the three groups—vertebrosternal, vertebrochondral, and vertebral.




FIG. 439.—Lateral view of first and seventh ribs in position, showing the movements of the sternum and ribs in A, ordinary expiration; B, quiet inspiration; C, deep inspiration.

in this way the transverse thoracic diameter is increased. Elevation of the third, fourth, fifth, and sixth ribs raises and thrusts forward their anterior extremities, the greater part of the movement being effected by the rotation of the rib neck backward. The thrust of the anterior extremities carries forward and upward the body of the sternum, which moves on the joint

*Vertebrosternal Ribs* (Figs. 439, 440).—The first rib differs from the others of this group in that its attachment to the sternum is a rigid one; this is counterbalanced to some extent by the fact that its head possesses no interarticular ligament, and is therefore more movable. The first pair of ribs with the manubrium sterni move as a single piece, the anterior portion being elevated by rotatory movements at the vertebral extremities. In normal quiet respiration the movement of this arc is practically nil; when it does occur the anterior part is raised and carried forward, increasing the antero-posterior and transverse diameters of this region of the chest. The movement of the second rib is also slight in normal respiration, as its anterior extremity is fixed to the manubrium, and prevented therefore from moving upward. The sternocostal articulation, however, allows the middle of the body of the rib to be drawn up, and




FIG. 440.—Diagram showing the axes of movement (A B and C D) of a vertebrosteral rib. The interrupted lines indicate the position of the rib in inspiration.




FIG. 441.—Diagram showing the axis of movement (A B) of a vertebrochondral rib. The interrupted lines indicate the position of the rib in inspiration.

between it and the manubrium, and thus the antero-posterior thoracic diameter is increased. This movement is, however, soon arrested, and the elevating force is then expended in raising the middle part of the body of the rib and everting its lower border; at the same time the

costochondral angle is opened out. By these latter movements a considerable increase in the transverse diameter of the thorax is effected.

**Vertebrochondral Ribs** (Fig. 441).—The seventh rib is included with this group, as it conforms more closely to their type. While the movements of these ribs assist in enlarging the thorax for respiratory purposes, they are also concerned in increasing the upper abdominal space for viscera displaced by the action of the Diaphragma. The costal cartilages articulate with one another, so that each pushes up that above it, the final thrust being directed to pushing forward and upward the lower end of the body of the sternum. The amount of elevation of the anterior extremities is limited on account of the very slight rotation of the rib neck. Elevation of the shaft is accompanied by an outward and backward movement; the outward movement everts the anterior end of the rib and opens up the subcostal angle, while the backward movement pulls back the anterior extremity and counteracts the forward thrust due to its elevation; this latter is most noticeable in the lower ribs, which are the shortest. The total result is a considerable increase in the transverse and a diminution in the median antero-posterior diameter of the upper part of the abdomen; at the same time, however, the lateral antero-posterior diameters of the abdomen are increased.

**Vertebral Ribs.**—Since these ribs have free anterior extremities and only costocentral articulations with no interarticular ligaments, they are capable of slight movements in all directions. When the other ribs are elevated these are depressed and fixed to form points of action for the Diaphragma.




FIG. 442.—Articulations of pelvis and hip. Anterior view.

### VIII. Articulation of the Vertebral Column with the Pelvis.

The ligaments connecting the fifth lumbar vertebra with the sacrum are similar to those which join the movable segments of the vertebral column with each other—viz.: 1. The continuation downward of the anterior and posterior longitudinal ligaments. 2. The intervertebral fibrocartilage, connecting the body of the fifth lumbar to that of the first sacral vertebra and forming an amphiarthrodial joint. 3. Ligamenta flava, uniting the laminae of the fifth lumbar vertebra with those of the first sacral. 4. Capsules connecting the articular processes and forming a double arthrodia. 5. Inter- and supraspinal ligaments.

On either side an additional ligament, the **iliolumbar**, connects the pelvis with the vertebral column.

**The Iliolumbar Ligament** (*ligamentum iliolumbale*) (Fig. 442).—The iliolumbar ligament is attached above to the lower and front part of the transverse process of the fifth lumbar vertebra. It radiates as it passes lateralward and is attached by two main bands to the pelvis. The lower bands run to the base of the sacrum, blending with the anterior sacroiliac ligament; the upper is attached to the crest of the ilium immediately in front of the sacroiliac articulation, and is continuous above with the lumbodorsal fascia. In *front*, it is in relation with the Psoas major; *behind*, with the muscles occupying the vertebral groove; *above*, with the Quadratus lumborum.

### IX. Articulations of the Pelvis.

The ligaments connecting the bones of the pelvis with each other may be divided into four groups: 1. Those connecting the sacrum and ilium. 2. Those passing between the sacrum and ischium. 3. Those uniting the sacrum and coccyx. 4. Those between the two pubic bones.

1. **Sacroiliac Articulation** (*articulatio sacroiliaca*).—The sacroiliac articulation is an amphiarthrodial joint, formed between the auricular surfaces of the sacrum and the ilium. The articular surface of each bone is covered with a thin plate of cartilage, thicker on the sacrum than on the ilium. These cartilaginous plates are in close contact with each other, and to a certain extent are united together by irregular patches of softer fibrocartilage, and at their upper and posterior part by fine interosseous fibres. In a considerable part of their extent, especially in advanced life, they are separated by a space containing a synovia-like fluid, and hence the joint presents the characteristics of a diarthrosis. The ligaments of the joint are:

The Anterior Sacroiliac.

The Posterior Sacroiliac.

The Interosseous.

**The Anterior Sacroiliac Ligament** (*ligamentum sacroiliacum anterius*) (Fig. 442).—The anterior sacroiliac ligament consists of numerous thin bands, which connect the anterior surface of the lateral part of the sacrum to the margin of the auricular surface of the ilium and to the preauricular sulcus.

**The Posterior Sacroiliac Ligament** (*ligamentum sacroiliacum posterius*) (Fig. 443).—The posterior sacroiliac ligament is situated in a deep depression between the sacrum and ilium behind; it is strong and forms the chief bond of union between the bones. It consists of numerous fasciculi, which pass between the bones in various directions. The upper part (**short posterior sacroiliac ligament**) is nearly horizontal in direction, and passes from the first and second transverse tubercles on the back of the sacrum to the tuberosity of the ilium. The lower part (**long posterior sacroiliac ligament**) is oblique in direction; it is attached by one extremity to the third transverse tubercle of the back of the sacrum, and by the other to the posterior superior spine of the ilium.

**The Interosseous Sacroiliac Ligament** (*ligamentum sacroiliacum interosseum*).—This ligament lies deep to the posterior ligament, and consists of a series of short, strong fibres connecting the tuberosities of the sacrum and ilium.

#### 2. Ligaments Connecting the Sacrum and Ischium (Fig. 443).

The Sacrotuberous.

The Sacrospinous.

**The Sacrotuberous Ligament** (*ligamentum sacrotuberosum*; *great or posterior sacrosciatic ligament*).—The sacrotuberous ligament is situated at the lower and back part of the pelvis. It is flat, and triangular in form; narrower in the middle than at the ends; attached by its broad base to the posterior inferior spine of the

ilium, to the fourth and fifth transverse tubercles of the sacrum, and to the lower part of the lateral margin of that bone and the coccyx. Passing obliquely downward, forward, and lateralward, it becomes narrow and thick, but at its insertion into the inner margin of the tuberosity of the ischium, it increases in breadth, and is prolonged forward along the inner margin of the ramus, as the **falciform process**, the free concave edge of which gives attachment to the obturator fascia; one of its surfaces is turned toward the perineum, the other toward the Obturator internus. The lower border of the ligament is directly continuous with the tendon of origin of the long head of the Biceps femoris, and by many is believed to be the proximal end of this tendon, cut off by the projection of the tuberosity of the ischium.




FIG. 443.—Articulations of pelvis and hip. Posterior view.

**Relations.**—The *posterior surface* of this ligament gives origin, by its whole extent, to the *Glutæus maximus*. Its *anterior surface* is in part united to the sacrospinous ligament. Its *upper border* forms, above, the posterior boundary of the greater sciatic foramen, and, below, the posterior boundary of the lesser sciatic foramen. Its *lower border* forms part of the boundary of the perineum. It is pierced by the coccygeal nerve and the coccygeal branch of the inferior gluteal artery.

**The Sacrospinous Ligament** (*ligamentum sacrospinosum*; *small or anterior sacro-sciatic ligament*).—The sacrospinous ligament is thin, and triangular in form; it is attached by its apex to the spine of the ischium, and medially, by its broad base, to the lateral margins of the sacrum and coccyx, in front of the sacrotuberous ligament with which its fibres are intermingled.

**Relations.**—It is in relation, *anteriorly*, with the *Coccygeus* muscle, to which it is closely connected; *posteriorly*, it is covered by the sacrotuberous ligament, and crossed by the internal pudendal vessels and nerve. Its *upper border* forms the lower boundary of the greater sciatic foramen; its *lower border*, part of the margin of the lesser sciatic foramen.



These two ligaments convert the sciatic notches into foramina. The **greater sciatic foramen** is bounded, in *front* and *above*, by the posterior border of the hip bone; *behind*, by the sacrotuberous ligament; and *below*, by the sacrospinous ligament. It is partially filled up, in the recent state, by the Piriformis which leaves the pelvis through it. Above this muscle, the superior gluteal vessels and nerve emerge from the pelvis; and below it, the inferior gluteal vessels and nerve, the internal pudendal vessels and nerve, the sciatic and posterior femoral cutaneous nerves, and the nerves to the Obturator internus and Quadratus femoris make their exit from the pelvis. The **lesser sciatic foramen** is bounded, in *front*, by the tuberosity of the ischium; *above*, by the spine of the ischium and sacrospinous ligament; *behind*, by the sacrotuberous ligament. It transmits the tendon of the Obturator internus, its nerve, and the internal pudendal vessels and nerve.

**3. Sacrococcygeal Symphysis** (*symphysis sacrococcygea*; *articulation of the sacrum and coccyx*).—This articulation is an amphiarthrodial joint, formed between the oval surface at the apex of the sacrum, and the base of the coccyx. It is homologous with the joints between the bodies of the vertebræ, and is connected by similar ligaments. They are:

The Anterior Sacrococcygeal.	The Lateral Sacrococcygeal.
The Posterior Sacrococcygeal.	The Interposed Fibrocartilage.
The Interarticular.	

**The Anterior Sacrococcygeal Ligament** (*ligamentum sacrococcygeum anterius*).—This consists of a few irregular fibres, which descend from the anterior surface of the sacrum to the front of the coccyx, blending with the periosteum.

**The Posterior Sacrococcygeal Ligament** (*ligamentum sacrococcygeum posterius*).—This is a flat band, which arises from the margin of the lower orifice of the sacral canal, and descends to be inserted into the posterior surface of the coccyx. This ligament completes the lower and back part of the sacral canal, and is divisible into a short deep portion and a longer superficial part. It is in relation, behind, with the Glutæus maximus.

**The Lateral Sacrococcygeal Ligament** (*ligamentum sacrococcygeum laterale*; *inter-transverse ligament*).—The lateral sacrococcygeal ligament exists on either side and connects the transverse process of the coccyx to the lower lateral angle of the sacrum; it completes the foramen for the fifth sacral nerve.

A disk of **fibrocartilage** is interposed between the contiguous surfaces of the sacrum and coccyx; it differs from those between the bodies of the vertebræ in that it is thinner, and its central part is firmer in texture. It is somewhat thicker in front and behind than at the sides. Occasionally the coccyx is freely movable on the sacrum, most notably during pregnancy; in such cases a synovial membrane is present.

The **Interarticular Ligaments** are thin bands, which unite the cornua of the two bones.

The different segments of the coccyx are connected together by the extension downward of the anterior and posterior sacrococcygeal ligaments, thin annular disks of fibrocartilage being interposed between the segments. In the adult male, all the pieces become ossified together at a comparatively early period; but in the female, this does not commonly occur until a later period of life. At more advanced age the joint between the sacrum and coccyx is obliterated.

**Movements.**—The movements which take place between the sacrum and coccyx, and between the different pieces of the latter bone, are forward and backward; they are very limited. Their extent increases during pregnancy.

**4. The Pubic Symphysis** (*symphysis ossium pubis*; *articulation of the pubic bones*) (Fig. 444).—The articulation between the pubic bones is an amphiarthrodial joint, formed between the two oval articular surfaces of the bones. The ligaments of this articulation are:

The Anterior Pubic.	The Superior Pubic.
The Posterior Pubic.	The Arcuate Pubic.
The Interpubic Fibrocartilaginous Lamina.	

**The Anterior Pubic Ligament** (Fig. 442).—The anterior pubic ligament consists of several superimposed layers, which pass across the front of the articulation. The superficial fibres pass obliquely from one bone to the other, decussating and forming an interlacement with the fibres of the aponeuroses of the *Obliqui externi* and the medial tendons of origin of the *Recti abdominis*. The deep fibres pass transversely across the symphysis, and are blended with the fibrocartilaginous lamina.

**The Posterior Pubic Ligament.**—The posterior pubic ligament consists of a few thin, scattered fibres, which unite the two pubic bones posteriorly.

**The Superior Pubic Ligament** (*ligamentum pubicum superius*).—The superior pubic ligament connects together the two pubic bones superiorly, extending laterally as far as the pubic tubercles.




FIG. 444.—Symphysis pubis exposed by a coronal section.

**The Arcuate Pubic Ligament** (*ligamentum arcuatum pubis*; *inferior pubic or subpubic ligament*).—The arcuate pubic ligament is a thick, triangular arch of ligamentous fibres, connecting together the two pubic bones below, and forming the upper boundary of the pubic arch. *Above*, it is blended with the interpubic fibrocartilaginous lamina; *laterally*, it is attached to the inferior rami of the pubic bones; *below*, it is free, and is separated from the fascia of the urogenital diaphragm by an opening through which the deep dorsal vein of the penis passes into the pelvis.

**The Interpubic Fibrocartilaginous Lamina** (*lamina fibrocartilaginea interpubica*; *interpubic disk*).—The interpubic fibrocartilaginous lamina connects the opposed surfaces of the pubic bones. Each of these surfaces is covered by a thin layer of hyaline cartilage firmly joined to the bone by a series of nipple-like processes which accurately fit into corresponding depressions on the osseous surfaces. These opposed cartilaginous surfaces are connected together by an intermediate lamina of fibrocartilage which varies in thickness in different subjects. It often contains a cavity in its interior, probably formed by the softening and absorption of the fibrocartilage, since it rarely appears before the tenth year of life and is not lined

by synovial membrane. This cavity is larger in the female than in the male, but it is very doubtful whether it enlarges, as was formerly supposed, during pregnancy. It is most frequently limited to the upper and back part of the joint; it occasionally reaches to the front, and may extend the entire length of the cartilage. It may be easily demonstrated when present by making a coronal section of the symphysis pubis near its posterior surface (Fig. 444).




FIG. 445.—Coronal section of anterior sacral segment.

**Mechanism of the Pelvis.**—The pelvic girdle supports and protects the contained viscera and affords surfaces for the attachments of the trunk and lower limb muscles. Its most important mechanical function, however, is to transmit the weight of the trunk and upper limbs to the lower extremities.

It may be divided into two arches by a vertical plane passing through the acetabular cavities; the posterior of these arches is the one chiefly concerned in the function of transmitting the weight. Its essential parts are the upper three sacral vertebrae and two strong pillars of bone running from the sacroiliac articulations to the acetabular cavities. For the reception and diffusion of the weight each acetabular cavity is strengthened by two additional bars running toward




FIG. 446.—Coronal section of middle sacral segment.

the pubis and ischium. In order to lessen concussion in rapid changes of distribution of the weight, joints (sacroiliac articulations) are interposed between the sacrum and the iliac bones; an accessory joint (pubic symphysis) exists in the middle of the anterior arch. The sacrum forms the summit of the posterior arch; the weight transmitted falls on it at the lumbosacral articulation and, theoretically, has a component in each of two directions. One component of the force is expended in driving the sacrum downward and backward between the iliac bones, while the other thrusts the upper end of the sacrum downward and forward toward the pelvic cavity.

The movements of the sacrum are regulated by its form. Viewed as a whole, it presents the shape of a wedge with its base upward and forward. The first component of the force is therefore acting against the resistance of the wedge, and its tendency to separate the iliac bones is resisted by the sacroiliac and iliolumbar ligaments and by the ligaments of the pubic symphysis.

If a series of coronal sections of the sacroiliac joints be made, it will be found possible to divide

the articular portion of the sacrum into three segments: anterior, middle, and posterior. In the **anterior segment** (Fig. 445), which involves the first sacral vertebra, the articular surfaces show slight sinuositities and are almost parallel to one another; the distance between their dorsal margins is, however, slightly greater than that between their ventral margins. This segment therefore presents a slight wedge shape with the truncated apex downward. The **middle segment** (Fig. 446) is a narrow band across the centres of the articulations. Its dorsal width is distinctly greater than its ventral, so that the segment is more definitely wedge-shaped, the truncated apex being again directed downward. Each articular surface presents in the centre a marked concavity from above downward, and into this a corresponding convexity of the iliac articular surface fits, forming an interlocking mechanism. In the **posterior segment** (Fig. 447) the ventral width is greater than the dorsal, so that the wedge form is the reverse of those of the other segments—i.e., the truncated apex is directed upward. The articular surfaces are only slightly concave.



FIG. 447.—Coronal section of posterior sacral segment.

Dislocation downward and forward of the sacrum by the second component of the force applied to it is prevented therefore by the middle segment, which interposes the resistance of its wedge shape and that of the interlocking mechanism on its surfaces; a rotatory movement, however, is produced by which the anterior segment is tilted downward and the posterior upward; the axis of this rotation passes through the dorsal part of the middle segment. The movement of the anterior segment is slightly limited by its wedge form, but chiefly by the posterior and interosseous sacroiliac ligaments; that of the posterior segment is checked to a slight extent by its wedge form, but the chief limiting factors are the sacrotuberous and sacrospinous ligaments. In all these movements the effect of the sacroiliac and iliolumbar ligaments and the ligaments of the symphysis pubis in resisting the separation of the iliac bones must be recognized.

During pregnancy the pelvic joints and ligaments are relaxed, and capable therefore of more extensive movements. When the fetus is being expelled the force is applied to the front of the sacrum. Upward dislocation is again prevented by the interlocking mechanism of the middle segment. As the fetal head passes the anterior segment the latter is carried upward, enlarging the antero-posterior diameter of the pelvic inlet; when the head reaches the posterior segment this also is pressed upward against the resistance of its wedge, the movement only being possible by the laxity of the joints and the stretching of the sacrotuberous and sacrospinous ligaments.

## ARTICULATIONS OF THE UPPER EXTREMITY.

The articulations of the Upper Extremity may be arranged as follows:

- |                                  |                         |
|----------------------------------|-------------------------|
| I. Sternoclavicular.             | VI. Wrist.              |
| II. Acromioclavicular.           | VII. Intercarpal.       |
| III. Shoulder.                   | VIII. Carpometacarpal.  |
| IV. Elbow.                       | IX. Intermetacarpal.    |
| V. Radioulnar.                   | X. Metacarpophalangeal. |
| XI. Articulations of the Digits. |                         |

### I. Sternoclavicular Articulation (*Articulatio Sternoclavicularis*) (Fig. 448).

The sternoclavicular articulation is a double arthrodiar joint. The parts entering into its formation are the sternal end of the clavicle, the upper and lateral part of the manubrium sterni, and the cartilage of the first rib. The articular surface of the clavicle is much larger than that of the sternum, and is invested with a layer of cartilage,<sup>1</sup> which is considerably thicker than that on the latter bone. The ligaments of this joint are:

- |                                 |                      |
|---------------------------------|----------------------|
| The Articular Capsule.          | The Interclavicular. |
| The Anterior Sternoclavicular.  | The Costoclavicular. |
| The Posterior Sternoclavicular. | The Articular Disk.  |

<sup>1</sup> According to Bruch, the sternal end of the clavicle is covered by a tissue which is fibrous rather than cartilaginous in structure.

**The Articular Capsule** (*capsula articularis*; *capsular ligament*).—The articular capsule surrounds the articulation and varies in thickness and strength. In front and behind it is of considerable thickness, and forms the anterior and posterior sternoclavicular ligaments; but above, and especially below, it is thin and partakes more of the character of areolar than of true fibrous tissue.

**The Anterior Sternoclavicular Ligament** (*ligamentum sternoclaviculare anterior*).—The anterior sternoclavicular ligament is a broad band of fibres, covering the anterior surface of the articulation; it is attached *above* to the upper and front part of the sternal end of the clavicle, and, passing obliquely downward and medialward, is attached below to the front of the upper part of the manubrium sterni. This ligament is covered by the sternal portion of the Sternocleidomastoideus and the integument; *behind*, it is in relation with the capsule, the articular disk, and the two synovial membranes.




FIG. 448.—Sternoclavicular articulation. Anterior view.

**The Posterior Sternoclavicular Ligament** (*ligamentum sternoclaviculare posterius*).—The posterior sternoclavicular ligament is a similar band of fibres, covering the posterior surface of the articulation; it is attached *above* to the upper and back part of the sternal end of the clavicle, and, passing obliquely downward and medialward, is fixed below to the back of the upper part of the manubrium sterni. It is in relation, in *front*, with the articular disk and synovial membranes; *behind*, with the Sternohyoideus and Sternothyreoides.

**The Interclavicular Ligament** (*ligamentum interclaviculare*).—This ligament is a flattened band, which varies considerably in form and size in different individuals, it passes in a curved direction from the upper part of the sternal end of one clavicle to that of the other, and is also attached to the upper margin of the sternum. It is in relation, in *front*, with the integument and Sternocleidomastoidei; *behind*, with the Sternothyreoides.

**The Costoclavicular Ligament** (*ligamentum costoclaviculare*; *rhomboid ligament*).—This ligament is short, flat, strong, and rhomboid in form. Attached below to the upper and medial part of the cartilage of the first rib, it ascends obliquely backward and lateralward, and is fixed above to the costal tuberosity on the under surface of the clavicle. It is in relation, in *front*, with the tendon of origin of the Subclavius; *behind*, with the subclavian vein.

**The Articular Disk** (*discus articularis*).—The articular disk is flat and nearly circular, interposed between the articulating surfaces of the sternum and clavicle. It is attached, *above*, to the upper and posterior border of the articular surface of the clavicle; *below*, to the cartilage of the first rib, near its junction with the sternum; and by its circumference to the interclavicular and anterior and posterior sterno-

clavicular ligaments. It is thicker at the circumference, especially its upper and back part, than at its centre. It divides the joint into two cavities, each of which is furnished with a synovial membrane.

**Synovial Membranes.**—Of the two synovial membranes found in this articulation, the lateral is reflected from the sternal end of the clavicle, over the adjacent surface of the articular disk, and around the margin of the facet on the cartilage of the first rib; the medial is attached to the margin of the articular surface of the sternum and clothes the adjacent surface of the articular disk; the latter is the larger of the two.

**Movements.**—This articulation admits of a limited amount of motion in nearly every direction—upward, downward, backward, forward, as well as circumduction. When these movements take place in the joint, the clavicle in its motion carries the scapula with it, this bone gliding on the outer surface of the chest. This joint therefore forms the centre from which all movements of the supporting arch of the shoulder originate, and is the only point of articulation of the shoulder girdle with the trunk. The movements attendant on elevation and depression of the shoulder take place between the clavicle and the articular disk, the bone rotating upon the ligament on an axis drawn from before backward through its own articular facet; when the shoulder is moved forward and backward, the clavicle, with the articular disk rolls to and fro on the articular surface of the sternum, revolving, with a sliding movement, around an axis drawn nearly vertically through the sternum; in the circumduction of the shoulder, which is compounded of these two movements, the clavicle revolves upon the articular disk and the latter, with the clavicle, rolls upon the sternum.<sup>1</sup> Elevation of the shoulder is limited principally by the costoclavicular ligament; depression, by the interclavicular ligament and articular disk. The muscles which raise the shoulder are the upper fibres of the Trapezius, the Levator scapulae, and the clavicular head of the Sternocleidomastoideus, assisted to a certain extent by the Rhomboidei, which pull the vertebral border of the scapula backward and upward and so raise the shoulder. The depression of the shoulder is principally effected by gravity assisted by the Subclavius, Pectoralis minor and lower fibres of the Trapezius. The shoulder is drawn backward by the Rhomboidei and the middle and lower fibres of the Trapezius, and forward by the Serratus anterior and Pectoralis minor.

**Applied Anatomy.**—The strength of this joint mainly depends upon its ligaments, and it is owing to these, and to the fact that the force of the blow is usually transmitted along the long axis of the clavicle, that dislocation rarely occurs, and that the bone is broken rather than displaced. When dislocation does occur, the course which the displaced bone takes depends more upon the direction in which the violence is applied than upon the anatomical construction of the joint; it may be either forward, backward, or upward. Should it be displaced backward it may cause pressure on the trachea. The chief point worthy of note, as regards the construction of the joint, in connection with dislocation, is the fact that, owing to the shape of the articular surfaces, and the strength of the joint mainly depending upon the ligaments, the displacement when reduced is very liable to recur, and hence it is extremely difficult to keep the end of the bone in its proper place.

## II. Acromioclavicular Articulation (*Articulatio Acromioclavicularis*; *Scapulo-clavicular Articulation*) (Fig. 449).

The acromioclavicular articulation is an arthrodial joint between the acromial end of the clavicle and the medial margin of the acromion of the scapula. Its ligaments are:

The Articular Capsule.	The Articular Disk.
The Superior Acromioclavicular.	The Coracoclavicular { Trapezoid and Conoid.
The Inferior Acromioclavicular.	

**The Articular Capsule** (*capsula articularis*; *capsular ligament*).—The articular capsule completely surrounds the articular margins, and is strengthened above and below by the superior and inferior acromioclavicular ligaments.

**The Superior Acromioclavicular Ligament** (*ligamentum acromioclaviculare*).—This ligament is a quadrilateral band, covering the superior part of the articulation, and extending between the upper part of the acromial end of the clavicle and the adjoining part of the upper surface of the acromion. It is composed of parallel fibres, which interlace with the aponeuroses of the Trapezius and Deltoideus; below, it is in contact with the articular disk when this is present.

<sup>1</sup> Humphry, On the Human Skeleton, page 402.



**The Inferior Acromioclavicular Ligament.**—This ligament is somewhat thinner than the preceding; it covers the under part of the articulation, and is attached to the adjoining surfaces of the two bones. It is in relation, *above*, in rare cases with the articular disk; *below*, with the tendon of the Supraspinatus.

**The Articular Disk** (*discus articularis*).—The articular disk is frequently absent in this articulation. When present, it generally only partially separates the articular surfaces, and occupies the upper part of the articulation. More rarely, it completely divides the joint into two cavities.

**The Synovial Membrane.**—There is usually only one synovial membrane in this articulation, but when a complete articular disk is present, there are two.




FIG. 449.—The left shoulder and acromioclavicular joints, and the proper ligaments of the scapula.

**The Coracoclavicular Ligament** (*ligamentum coracoclaviculare*) (Fig. 449).—This ligament serves to connect the clavicle with the coracoid process of the scapula. It does not properly belong to this articulation, but is usually described with it, since it forms a most efficient means of retaining the clavicle in contact with the acromion. It consists of two fasciculi, called the **trapezoid** and **conoid ligaments**.

**The Trapezoid Ligament** (*ligamentum trapezoideum*), the anterior and lateral fasciculus, is broad, thin, and quadrilateral: it is placed obliquely between the coracoid process and the clavicle. It is attached, *below*, to the upper surface of the coracoid process; *above*, to the oblique ridge on the under surface of the clavicle. Its anterior border is free; its posterior border is joined with the conoid ligament, the two forming, by their junction, an angle projecting backward.

**The Conoid Ligament** (*ligamentum conoideum*), the posterior and medial fasciculus, is a dense band of fibres, conical in form, with its base directed upward. It is attached by its apex to a rough impression at the base of the coracoid process, medial to the trapezoid ligament; above, by its expanded base, to the coracoid

tuberosity on the under surface of the clavicle, and to a line proceeding medialward from it for 1.25 cm. These ligaments are in relation, in *front*, with the Subclavius and Deltoideus; *behind*, with the Trapezius.

**Movements.**—The movements of this articulation are of two kinds: (1) a gliding motion of the articular end of the clavicle on the acromion; (2) rotation of the scapula forward and backward upon the clavicle. The extent of this rotation is limited by the two portions of the coracoclavicular ligament, the trapezoid limiting rotation forward, and the conoid backward.

The acromioclavicular joint has important functions in the movements of the upper extremity. It has been well pointed out by Humphry, that if there had been no joint between the clavicle and scapula, the circular movement of the scapula on the ribs (as in throwing the shoulders backward or forward) would have been attended with a greater alteration in the direction of the shoulder than is consistent with the free use of the arm in such positions, and it would have been impossible to give a blow straight forward with the full force of the arm; that is to say, with the combined force of the scapula, arm, and forearm. "This joint," as he happily says, "is so adjusted as to enable either bone to turn in a hinge-like manner upon a vertical axis drawn through the other, and it permits the surfaces of the scapula, like the baskets in a roundabout swing, to look the same way in every position, or nearly so." Again, when the whole arch formed by the clavicle and scapula rises and falls (in elevation or depression of the shoulder), the joint between these two bones enables the scapula still to maintain its lower part in contact with the ribs.

**Applied Anatomy.**—The acromioclavicular joint owes its security mainly to the coracoclavicular ligament, which limits the amount of movement of the acromial end of the clavicle either upward, backward, or forward. Owing to the slanting shape of the articular surfaces of this joint, dislocation generally occurs upward; that is to say, the acromial end of the clavicle is displaced above the acromion of the scapula. The displacement is often incomplete, on account of the strong coracoclavicular ligaments, which remain unturned. The same difficulty exists, as in the sternoclavicular dislocation, in maintaining the ends of the bone in position after reduction.

## THE LIGAMENTS OF THE SCAPULA.

The ligaments of the scapula (Fig. 449) are:

Coracoacromial, Superior and Inferior Transverse.

**The Coracoacromial Ligament** (*ligamentum coracoacromiale*).—This ligament is a strong triangular band, extending between the coracoid process and the acromion. It is attached, by its apex, to the summit of the acromion just in front of the articular surface for the clavicle; and by its broad base to the whole length of the lateral border of the coracoid process. This ligament, together with the coracoid process and the acromion, forms a vault for the protection of the head of the humerus. It is in relation, *above*, with the clavicle and under surface of the Deltoideus; *below*, with the tendon of the Supraspinatus, a bursa being interposed. Its lateral border is continuous with a dense lamina that passes beneath the Deltoideus upon the tendons of the Supraspinatus and Infraspinatus. The ligament is sometimes described as consisting of two marginal bands and a thinner intervening portion, the two bands being attached respectively to the apex and the base of the coracoid process, and joining together at the acromion. When the Pectoralis minor is inserted, as occasionally is the case, into the capsule of the shoulder-joint instead of into the coracoid process, it passes between these two bands, and the intervening portion of the ligament is then deficient.

**The Superior Transverse Ligament** (*ligamentum transversum scapulae superius; transverse or suprascapular ligament*).—This ligament converts the scapular notch into a foramen. It is a thin and flat fasciculus, narrower at the middle than at the extremities, attached by one end to the base of the coracoid process, and by the other to the medial end of the scapular notch. The suprascapular nerve runs through the foramen; the transverse scapular vessels cross over the ligament. The ligament is sometimes ossified.

**The Inferior Transverse Ligament** (*ligamentum transversum scapulae inferius; spinoglenoid ligament*).—This ligament is a weak membranous band, situated

behind the neck of the scapula and stretching from the lateral border of the spine to the margin of the glenoid cavity. It forms an arch under which the transverse scapular vessels and suprascapular nerve enter the infraspinatus fossa.

### III. Humeral Articulation or Shoulder-joint (*Articulatio Humeri*) (Fig. 449).

The shoulder-joint is an enarthrodial or ball-and-socket joint. The bones entering into its formation are the hemispherical head of the humerus and the shallow glenoid cavity of the scapula, an arrangement which permits of very considerable movement, while the joint itself is protected against displacement by the tendons which surround it. The ligaments do not maintain the joint surfaces in apposition, because when they alone remain the humerus can be separated to a considerable extent from the glenoid cavity; their use, therefore, is to limit




FIG. 450.—Capsule of shoulder-joint (distended). Anterior aspect.

the amount of movement. The joint is protected above by an arch, formed by the coracoid process, the acromion, and the coracoacromial ligament. The articular cartilage on the head of the humerus is thicker at the centre than at the circumference, the reverse being the case with the articular cartilage of the glenoid cavity. The ligaments of the shoulder are:

The Articular Capsule.  
The Coracohumeral.

The Glenohumeral.  
The Transverse Humeral.

The Glenoidal Labrum.<sup>1</sup>

**The Articular Capsule** (*capsula articularis*; *capsular ligament*) (Fig. 450).—The articular capsule completely encircles the joint, being attached, above, to the circumference of the glenoid cavity beyond the glenoidal labrum; below, to the anatomical neck of the humerus, approaching nearer to the articular cartilage above than in the rest of its extent. It is thicker above and below than elsewhere,

<sup>1</sup> The long tendon of origin of the biceps brachii also acts as one of the ligaments of this joint. See the observations on page 383, on the function of the muscles passing over more than one joint.

and is so remarkably loose and lax, that it has no action in keeping the bones in contact, but allows them to be separated from each other more than 2.5 cm., an evident provision for that extreme freedom of movement which is peculiar to this articulation. It is strengthened, *above*, by the Supraspinatus; *below*, by the long head of the Triceps brachii; *behind*, by the tendons of the Infraspinatus and Teres minor; and in *front*, by the tendon of the Subscapularis. There are usually three openings in the capsule. One anteriorly, below the coracoid process, establishes a communication between the joint and a bursa beneath the tendon of the Subscapularis. The second, which is not constant, is at the posterior part, where an opening sometimes exists between the joint and a bursal sac under the tendon of the Infraspinatus. The third is between the tubercles of the humerus, for the passage of the long tendon of the Biceps brachii.

**The Coracohumeral Ligament** (*ligamentum coracohumerale*).—This ligament is a broad band which strengthens the upper part of the capsule. It arises from the lateral border of the coracoid process, and passes obliquely downward and lateralward to the front of the greater tubercle of the humerus, blending with the tendon of the Supraspinatus. This ligament is intimately united to the capsule by its hinder and lower border; but its anterior and upper border presents a free edge, which overlaps the capsule.

**Glenohumeral Ligaments.**—In addition to the coracohumeral ligament, three supplemental bands, which are named the **glenohumeral ligaments**, strengthen the capsule. These may be best seen by opening the capsule at the back of the joint and removing the head of the humerus. One on the medial side of the joint passes from the medial edge of the glenoid cavity to the lower part of the lesser tubercle of the humerus. A second at the lower part of the joint extends from the under edge of the glenoid cavity to the under part of the anatomical neck of the humerus. A third at the upper part of the joint is fixed above to the apex of the glenoid cavity close to the root of the coracoid process, and passing downward along the medial edge of the tendon of the Biceps brachii, is attached below to a small depression above the lesser tubercle of the humerus. In addition to these, the capsule is strengthened in front by two bands derived from the tendons of the Pectoralis major and Teres major respectively.

**The Transverse Humeral Ligament** (Fig. 450) is a broad band passing from the lesser to the greater tubercle of the humerus, and always limited to that portion of the bone which lies above the epiphysial line. It converts the intertubercular groove into a canal, and is the homologue of the strong process of bone which connects the summits of the two tubercles in the musk ox.

**The Glenoidal Labrum** (*labrum glenoidale; glenoid ligament*) is a fibrocartilaginous rim attached around the margin of the glenoid cavity. It is triangular on section, the base being fixed to the circumference of the cavity, while the free edge is thin and sharp. It is continuous above with the tendon of the long head of the Biceps brachii, which gives off two fasciculi to blend with the fibrous tissue of the labrum. It deepens the articular cavity, and protects the edges of the bone.

**Synovial Membrane.**—The synovial membrane is reflected from the margin of the glenoid cavity over the labrum; it is then reflected over the inner surface of the capsule, and covers the lower part and sides of the anatomical neck of the humerus as far as the articular cartilage on the head of the bone. The tendon of the long head of the Biceps brachii passes through the capsule and is enclosed in a tubular sheath of synovial membrane, which is reflected upon it from the summit of the glenoid cavity and is continued around the tendon into the intertubercular groove as far as the surgical neck of the humerus (Fig. 450). The tendon thus traverses the articulation, but it is not contained within the synovial cavity.

**Bursæ.**—The bursæ in the neighborhood of the shoulder-joint are the following: (1) A constant bursa is situated between the tendon of the Subscapularis muscle and the capsule; it communicates with the synovial cavity through an opening in the front of the capsule; (2) a bursa which occasionally communicates with the joint is sometimes found between the tendon of the Infraspinatus and the capsule; (3) a large bursa exists between the under surface of the Deltoideus

and the capsule, but does not communicate with the joint; this bursa is prolonged under the acromion and coracoacromial ligament, and intervenes between these structures and the capsule; (4) a large bursa is situated on the summit of the acromion; (5) a bursa is frequently found between the coracoid process and the capsule; (6) a bursa exists beneath the Coracobrachialis; (7) one lies between the Teres major and the long head of the Triceps brachii; (8) one is placed in front of, and another behind, the tendon of the Latissimus dorsi.

The **muscles** in relation with the joint are, *above*, the Supraspinatus; *below*, the long head of the Triceps brachii; *in front*, the Subscapularis; *behind*, the Infraspinatus and Teres minor; *within*, the tendon of the long head of the Biceps brachii. The Deltoideus covers the articulation in front, behind, and laterally.

The **arteries** supplying the joint are articular branches of the anterior and posterior humeral circumflex, and transverse scapular.

The **nerves** are derived from the axillary and suprascapular.

**Movements.**—The shoulder-joint is capable of every variety of movement, flexion, extension, abduction, adduction, circumduction, and rotation. The humerus is *flexed* (drawn forward) by the Pectoralis major, anterior fibres of the Deltoideus, Coracobrachialis, and when the forearm is flexed, by the Biceps brachii; *extended* (drawn backward) by the Latissimus dorsi, Teres major, posterior fibres of the Deltoideus, and, when the forearm is extended, by the Triceps brachii; it is *abducted* by the Deltoideus and Supraspinatus; it is *adducted* by the Subscapularis, Pectoralis major, Latissimus dorsi, and Teres major, and by the weight of the limb; it is *rotated outward* by the Infraspinatus and Teres minor; and it is *rotated inward* by the Subscapularis, Latissimus dorsi, Teres major, Pectoralis major, and the anterior fibres of the Deltoideus.

The most striking peculiarities in this joint are: (1) The large size of the head of the humerus in comparison with the depth of the glenoid cavity, even when this latter is supplemented by the glenoidal labrum. (2) The looseness of the capsule of the joint. (3) The intimate connection of the capsule with the muscles attached to the head of the humerus. (4) The peculiar relation of the tendon of the long head of the Biceps brachii to the joint.

It is in consequence of the relative sizes of the two articular surfaces, and the looseness of the articular capsule, that the joint enjoys such free movement in all directions. When these movements of the arm are arrested in the shoulder-joint by the contact of the bony surfaces, and by the tension of the fibres of the capsule, together with that of the muscles acting as accessory ligaments, the arm can be carried considerably farther by the movements of the scapula, involving, of course, motion at the acromio- and sternoclavicular joints. These joints are therefore to be regarded as accessory structures to the shoulder-joint (see pages 411 and 413). The extent of the scapular movements is very considerable, especially in extreme elevation of the arm, a movement best accomplished when the arm is thrown somewhat forward and outward, because the margin of the head of the humerus is by no means a true circle; its greatest diameter is from the intertubercular groove, downward, medialward, and backward, and the greatest elevation of the arm can be obtained by rolling its articular surface in the direction of this measurement. The great width of the central portion of the humeral head also allows of very free horizontal movement when the arm is raised to a right angle, in which movement the arch formed by the acromion, the coracoid process and the coracoacromial ligament, constitutes a sort of supplemental articular cavity for the head of the bone.

The looseness of the capsule is so great that the arm will fall about 2.5 cm. from the scapula when the muscles are dissected from the capsule, and an opening made in it to counteract the atmospheric pressure. The movements of the joint, therefore, are not regulated by the capsule so much as by the surrounding muscles and by the pressure of the atmosphere, an arrangement which "renders the movements of the joint much more easy than they would otherwise have been, and permits a swinging, pendulum-like vibration of the limb when the muscles are at rest" (Humphry). The fact, also, that in all ordinary positions of the joint the capsule is not put on the stretch, enables the arm to move freely in all directions. Extreme movements are checked by the tension of appropriate portions of the capsule, as well as by the interlocking of the bones. Thus it is said that "abduction is checked by the contact of the great tuberosity with the upper edge of the glenoid cavity; adduction by the tension of the coracohumeral ligament" (Beaunis et Bouchard). Cleland<sup>1</sup> maintains that the limitations of movement at the shoulder-joint are due to the structure of the joint itself, the glenoidal labrum fitting, in different positions of the elevated arm, into the anatomical neck of the humerus.

The scapula is capable of being moved upward and downward, forward and backward, or, by a combination of these movements, circumducted on the wall of the chest. The muscles which *raise* the scapula are the upper fibres of the Trapezius, the Levator scapulae, and the Rhomboidei; those which *depress* it are the lower fibres of the Trapezius, the Pectoralis minor, and, through the clavicle, the Subclavius. The scapula is drawn *backward* by the Rhomboidei and the middle and lower fibres of the Trapezius, and *forward* by the Serratus anterior and Pectoralis minor, assisted, when the arm is fixed, by the Pectoralis major. The mobility of the scapula is very

<sup>1</sup> Journal of Anatomy and Physiology, 1867, i, 85.

considerable, and greatly assists the movements of the arm at the shoulder-joint. Thus, in raising the arm from the side, the *Deltoides* and *Supraspinatus* can only lift it to a right angle with the trunk, the further elevation of the limb being effected by the *Trapezius* and *Serratus anterior* moving the scapula on the wall of the chest. This mobility is of special importance in ankylosis of the shoulder-joint, the movements of this bone compensating to a very great extent for the immobility of the joint.

Catheart<sup>1</sup> has pointed out that in abducting the arm and raising it above the head, the scapula rotates throughout the whole movement with the exception of a short space at the beginning and at the end; that the humerus moves on the scapula not only while passing from the hanging to the horizontal position, but also in travelling upward as it approaches the vertical above; that the clavicle moves not only during the second half of the movement but in the first as well, though to a less extent—i. e., the scapula and clavicle are concerned in the first stage as well as in the second; and that the humerus is partly involved in the second as well as chiefly in the first.

The intimate union of the tendons of the *Supraspinatus*, *Infraspinatus*, *Teres minor* and *Subscapularis* with the capsule, converts these muscles into elastic and spontaneously acting ligaments of the joint.

The peculiar relations of the tendon of the long head of the *Biceps brachii* to the shoulder-joint appear to subserve various purposes. In the first place, by its connection with both the shoulder and elbow the muscle harmonizes the action of the two joints, and acts as an elastic ligament in all positions, in the manner previously discussed (see page 383). It strengthens the upper part of the articular cavity, and prevents the head of the humerus from being pressed up against the acromion, when the *Deltoides* contracts; it thus fixes the head of the humerus as the centre of motion in the glenoid cavity. By its passage along the intertubercular groove it assists in steadying the head of the humerus in the various movements of the arm. When the arm is raised from the side it assists the *Supraspinatus* and *Infraspinatus* in rotating the head of the humerus in the glenoid cavity. It also holds the head of the bone firmly in contact with the glenoid cavity, and prevents its slipping over its lower edge, or being displaced by the action of the *Latissimus dorsi* and *Pectoralis major*, as in climbing and many other movements.

**Applied Anatomy.**—Owing to the construction of the shoulder-joint and the freedom of movement which it enjoys, as well as in consequence of its exposed situation, it is more frequently dislocated than any other joint. Dislocation occurs when the arm is abducted, and when, therefore, the head of the humerus presses against the lower and front part of the capsule, which is the thinnest and least supported part of the ligament. The rent in the capsule almost invariably takes place in this situation, and through it the head of the bone escapes, so that the dislocation in most instances is primarily subglenoid. The head of the bone does not usually remain in this situation, between the tendons of the *Subscapularis* and the *Triceps brachii*, but generally assumes some other position, which varies according to the direction and amount of force producing the dislocation and the relative strength of the muscles in front of and behind the joint. As the muscles at the back are stronger than those in front, and especially since the long head of the *Triceps brachii* prevents the bone from passing backward, dislocation forward is much the more common. The most frequent position which the head of the humerus ultimately assumes is on the front of the neck of the scapula, beneath the coracoid process, and hence named subcoracoid. Occasionally, in consequence of a greater amount of force being brought to bear on the limb, the head is driven farther medialward, and rests on the upper part of the front of the chest, beneath the clavicle (subclavicular). Sometimes it remains in the position in which it was primarily displaced, resting on the axillary border of the scapula (subglenoid), and rarely it passes backward and remains in the *infraspinatus fossa*, beneath the spine (subspinous).

The shoulder-joint may be the seat of any of those inflammatory affections, either acute or chronic, which attack joints, though perhaps less frequently than some other articulations of equal size and importance. Acute synovitis may result from injury, rheumatism, or pyemia, or may follow secondarily on acute epiphysitis in infants. It is attended with effusion into the joint, and when this occurs the capsule is evenly distended, and the contour of the joint rounded. Special projections may occur at the sites of the openings in the capsule. Thus a swelling may appear just medial to the lesser tubercle, from effusion into the bursa beneath the *Subscapularis*; or, again, a swelling which is sometimes bilobed may be seen in the interval between the *Deltoides* and *Pectoralis major*, from effusion into the diverticulum which runs down the intertubercular groove with the tendon of the *Biceps brachii*. The effusion into the joint cavity can be best ascertained by examination from the axilla, where a soft, elastic, fluctuating swelling can usually be felt. In cases of septic synovitis, where incision is required, the opening should be made in front, over the most prominent point of the swelling. After the pus has been evacuated a counter-opening should be made behind, so as to ensure efficient drainage.

Tuberculous arthritis not infrequently attacks the shoulder-joint, and may lead to total destruction of the articulation, when ankylosis may result, or long-protracted suppuration may necessitate

<sup>1</sup> *Journal of Anatomy and Physiology*, 1884, vol. xviii.



excision. This joint is also one of those which is most liable to be the seat of osteoarthritis, and may also be affected in gout and rheumatism; or in locomotor ataxia, when it becomes the seat of Charcot's disease.

Ankylosis is occasionally met with in the shoulder-joint as the result of destructive changes. The ankylosis usually takes place with the arm in a dependent position, and any attempt to raise the arm is attended by a rotation of the scapula on the wall of the chest.

Excision of the shoulder-joint may be required in cases of arthritis (especially the tuberculous form) which have gone on to destruction of the articulation; in compound dislocations and fractures, particularly those arising from gunshot injuries, in which there has been extensive injury to the head of the bone; in some cases of old unreduced dislocation, where there is much pain. The operation is best performed by making an incision from the middle of the coracoacromial ligament down the arm for about 7 or 8 cm.; this will expose the intertubercular groove containing the tendon of the Biceps brachii, which should be hooked out of the way. The capsule is freely opened, and the muscles attached to the greater and lesser tubercles of the humerus are stripped off with the capsule, without dividing their attachments to the latter. The head of the bone can then be thrust out of the wound and sawn off; or divided with a narrow saw *in situ* and subsequently removed. The section should be made, if possible, just below the articular surface, so as to leave the bone as long as possible.

#### IV. Elbow-joint (*Articulatio Cubiti*) (Figs. 451, 452).

The elbow-joint is a ginglymus or hinge-joint. The trochlea of the humerus is received into the semilunar notch of the ulna, and the capitulum of the humerus articulates with the fovea on the head of the radius. The articular surfaces are connected together by a **capsule**, which is thickened medially and laterally, and, to a less extent, in front and behind. These thickened portions are usually described as distinct ligaments under the following names:

The Anterior.  
The Posterior.

The Ulnar Collateral.  
The Radial Collateral.

**The Anterior Ligament** (Fig. 451).—The anterior ligament is a broad and thin fibrous layer covering the anterior surface of the joint. It is attached to the *front* of the medial epicondyle and to the front of the humerus immediately above the coronoid and radial fossæ; *below*, to the anterior surface of the coronoid process of the ulna and to the annular ligament (page 422), being continuous on either side with the collateral ligaments. Its superficial fibres pass obliquely from the medial epicondyle of the humerus to the annular ligament. The middle fibres, vertical in direction, pass from the upper part of the coronoid depression and become partly blended with the preceding, but are inserted mainly into the anterior surface of the coronoid process. The deep or transverse set intersects these at right angles. This ligament is in relation, in *front*, with the Brachialis, except at its most lateral part.

**The Posterior Ligament** (Fig. 452).—This posterior ligament is thin and membranous, and consists of transverse and oblique fibres. *Above*, it is attached to the humerus immediately behind the capitulum and close to the medial margin of the trochlea, to the margins of the olecranon fossa, and to the back of the lateral epicondyle some little distance from the trochlea. *Below*, it is fixed to the upper and lateral margins of the olecranon, to the posterior part of the annular ligament, and to the ulna behind the radial notch. The transverse fibres form a strong band which bridges across the olecranon fossa; under cover of this band a pouch of synovial membrane and a pad of fat project into the upper part of the fossa when the joint is extended. In the fat are a few scattered fibrous bundles, which pass from the deep surface of the transverse band to the upper part of the fossa. This ligament is in relation, *behind*, with the tendon of the Triceps brachii and the Anconæus.

**The Ulnar Collateral Ligament** (*ligamentum collaterale ulnare; internal lateral ligament*) (Fig. 451).—This ligament is a thick triangular band consisting of two

portions, an anterior and posterior united by a thinner intermediate portion. The **anterior portion**, directed obliquely forward, is attached, *above*, by its apex, to the front part of the medial epicondyle of the humerus; and, *below*, by its broad base to the medial margin of the coronoid process. The **posterior portion**, also of triangular form, is attached, *above*, by its apex, to the lower and back part of the medial epicondyle; *below*, to the medial margin of the olecranon. Between these two bands a few intermediate fibres descend from the medial epicondyle to blend with a *transverse band* which bridges across the notch between the olecranon and the coronoid process. This ligament is in relation with the Triceps brachii and Flexor carpi ulnaris and the ulnar nerve, and gives origin to part of the Flexor digitorum sublimis.




FIG. 451.—Left elbow-joint, showing anterior and ulnar collateral ligaments.




FIG. 452.—Left elbow-joint, showing posterior and radial collateral ligaments.

**The Radial Collateral Ligament** (*ligamentum collaterale radiale*; *external lateral ligament*) (Fig. 452).—This ligament is a short and narrow fibrous band, less distinct than the ulnar collateral, attached, *above*, to a depression below the lateral epicondyle of the humerus; *below*, to the annular ligament, some of its most posterior fibres passing over that ligament, to be inserted into the lateral margin of the ulna. It is intimately blended with the tendon of origin of the Supinator.

**Synovial Membrane** (Figs. 453, 454).—The synovial membrane is very extensive. It extends from the margin of the articular surface of the humerus, and lines the coronoid, radial and olecranon fossæ on that bone; it is reflected over the deep surface of the capsule and forms a pouch between the radial notch, the deep surface of the annular ligament, and the circumference of the head of the radius. Projecting between the radius and ulna into the cavity is a crescentic fold of

synovial membrane, suggesting the division of the joint into two; one the humeroradial, the other the humeroulnar.

Between the capsule and the synovial membrane are three masses of fat: the largest, over the olecranon fossa, is pressed into the fossa by the Triceps brachii during the flexion; the second, over the coronoid fossa, and the third, over the radial fossa, are pressed by the Brachialis into their respective fossæ during extension.

The **muscles** in relation with the joint are, in *front*, the Brachialis; *behind*, the Triceps brachii and Anconæus; *laterally*, the Supinator, and the common tendon of origin of the Extensor muscles; *medially*, the common tendon of origin of the Flexor muscles, and the Flexor carpi ulnaris.

The **arteries** supplying the joint are derived from the anastomosis between the profunda and the superior and inferior ulnar collateral branches of the brachial, with the anterior, posterior, and interosseous recurrent branches of the ulnar, and the recurrent branch of the radial. These vessels form a complete anastomotic network around the joint.



FIG. 453.—Capsule of elbow-joint (distended).  
Anterior aspect.



FIG. 454.—Capsule of elbow-joint (distended).  
Posterior aspect.

The **nerves** of the joint are a twig from the ulnar, as it passes between the medial condyle and the olecranon; a filament from the musculocutaneous, and two from the median.

**Movements.**—The elbow-joint comprises three different portions—viz., the joint between the ulna and humerus, that between the head of the radius and the humerus, and the proximal radioulnar articulation, described below. All these articular surfaces are enveloped by a common synovial membrane, and the movements of the whole joint should be studied together. The combination of the movements of flexion and extension of the forearm with those of pronation and supination of the hand, which is ensured by the two being performed at the same joint, is essential to the accuracy of the various minute movements of the hand.

The portion of the joint between the ulna and humerus is a simple hinge-joint, and allows of movements of flexion and extension only. Owing to the obliquity of the trochlea of the humerus, this movement does not take place in the antero-posterior plane of the body of the humerus.

When the forearm is extended and supinated, the axes of the arm and forearm are not in the same line; the arm forms an obtuse angle with the forearm, the hand and forearm being directed lateralward. During flexion, however, the forearm and the hand tend to approach the middle line of the body, and thus enable the hand to be easily carried to the face. The accurate adaptation of the trochlea of the humerus, with its prominences and depressions, to the semilunar notch of the ulna, prevents any lateral movement. *Flexion* is produced by the action of the Biceps brachii and Brachialis, assisted by the Brachioradialis and the muscles arising from the medial condyle of the humerus; *extension*, by the Triceps brachii and Anconaeus, assisted by the Extensors of the wrist, the Extensor digitorum communis, and the Extensor digiti quinti proprius.

The joint between the head of the radius and the capitulum of the humerus is an arthrodial joint. The bony surfaces would of themselves constitute an enarthrosis and allow of movement in all directions, were it not for the annular ligament, by which the head of the radius is bound to the radial notch of the ulna, and which prevents any separation of the two bones laterally. It is to the same ligament that the head of the radius owes its security from dislocation, which would otherwise tend to occur, from the shallowness of the cup-like surface on the head of the radius. In fact, but for this ligament, the tendon of the Biceps brachii would be liable to pull the head of the radius out of the joint. The head of the radius is not in complete contact with the capitulum of the humerus in all positions of the joint. The capitulum occupies only the anterior and inferior surfaces of the lower end of the humerus, so that in complete extension a part of the radial head can be plainly felt projecting at the back of the articulation. In full flexion the movement of the radial head is hampered by the compression of the surrounding soft parts, so that the freest rotatory movement of the radius on the humerus (pronation and supination) takes place in semiflexion, in which position the two articular surfaces are in most intimate contact. Flexion and extension of the elbow-joint are limited by the tension of the structures on the front and back of the joint; the limitation of flexion is also aided by the soft structures of the arm and forearm coming into contact.

In any position of flexion or extension, the radius, carrying the hand with it, can be rotated in the proximal radioulnar joint. The hand is directly articulated to the lower surface of the radius only, and the ulnar notch on the lower end of the radius travels around the lower end of the ulna. The latter bone is excluded from the wrist-joint by the articular disk. Thus, rotation of the head of the radius around an axis passing through the centre of the radial head of the humerus imparts circular movement to the hand through a very considerable arc.

**Applied Anatomy.**—From the great breadth of the joint, and the manner in which the articular surfaces are interlocked, and also on account of the strong collateral ligaments and the support which the joint derives from the mass of muscles attached to each epicondyle of the humerus, lateral displacement of the bones is very uncommon; whereas antero-posterior dislocation, on account of the shortness of the antero-posterior diameter, the weakness of the anterior and posterior ligaments, and the want of support of muscles, occurs much more frequently. Dislocation backward takes place when the forearm is in a position of extension, and forward when in a position of flexion. For, in the extended position, the coronoid process is not locked into the coronoid fossa, and loses its grip to a certain extent, whereas the olecranon is in the olecranon fossa, and entirely prevents displacement forward. On the other hand, during flexion, the coronoid process is in the coronoid fossa, and prevents dislocation backward, while the olecranon, having left the olecranon fossa, is not so efficient in preventing a forward displacement. When lateral dislocation does take place it is generally incomplete. Dislocation of the elbow-joint is of common occurrence in children, far more common than dislocation of any other articulation. As a rule, in young persons, the application of any severe violence to a joint is more likely to produce a fracture of bone than dislocation. In lesions of this joint there is often very great difficulty in ascertaining the exact nature of the injury.

The elbow-joint is occasionally the seat of acute synovitis. The joint-cavity then becomes distended with fluid, the bulging showing itself principally around the olecranon, in consequence of the laxness of the posterior ligament. Again, there is often some swelling just above the head of the radius, in the line of the radiohumeral joint, or the whole elbow may assume a fusiform appearance. There is not generally much swelling at the front of the joint, though sometimes deep-seated fulness beneath the Brachialis may be noted. When suppuration occurs the abscess usually points at one or other border of the Triceps brachii; occasionally the pus discharges itself in front, near the insertion of the Brachialis. In cases of suppurative synovitis, incisions should be made into the joint on either side of the olecranon, care being taken to avoid wounding the ulnar nerve on the medial side. Chronic synovitis, usually of tuberculous origin, is of common occurrence in the elbow-joint; in such cases the forearm tends to assume the position of semiflexion, which is that of greatest ease and relaxation of ligaments. It should be borne in mind that if ankylosis occur in this or the extended position, the limb will not be nearly so useful as if ankylosed in a position of rather less than a right angle. The elbow-joint is also sometimes affected with osteoarthritis, but less commonly than some of the larger joints.

Excision of the elbow is principally required for one of three conditions—viz., tuberculous arthritis, injury and its results, or faulty ankylosis—but may be necessary for some other rarer

conditions, such as disorganizing arthritis after pyemia and unreduced dislocations. The results of the operation are, as a rule, more favorable than those of excision of any other joint, especially in any of the first three conditions mentioned above. The operation is best performed by a vertical incision down the back of the joint; a straight incision is made about 10 cm. long, the mid-point of which is on a level with and a little to the medial side of the tip of the olecranon. This incision is made down to the bone, through the substance of the Triceps brachii. The operator, guarding the soft parts with his thumb-nail, separates them from the bone with the point of his knife. In doing this there are two structures which he should carefully avoid: the ulnar nerve, which as it courses down between the medial epicondyle and the olecranon lies parallel but a little medial to his incision; and the prolongation of the Triceps brachii into the deep fascia of the forearm over the Anconaeus. Having cleared the bones and divided the collateral and posterior ligaments, the forearm is strongly flexed and the ends of the bones turned out and sawn off. The turning out of the ends of the bones is rendered easier by first cutting off the olecranon with a pair of cutting bone forceps. The section of the humerus should be through the base of the epicondyles, that of the ulna and radius should be just below the level of the radial notch of the ulna and the neck of the radius. In this operation the object is to obtain such union as shall allow free motion of the bones of the forearm; and, therefore, passive movements must be commenced early—that is to say, about the tenth day. It is most important to maintain the continuity of the Triceps brachii with the deep fascia of the forearm, so as to obtain good power of extension in the new joint.

### V. Radioulnar Articulations (*Articulatio Radioulnaris*).

The articulation of the radius with the ulna is effected by ligaments which connect together the extremities as well as the bodies of these bones. The ligaments may, consequently, be subdivided into three sets: 1, those of the proximal radioulnar articulation; 2, the middle radioulnar ligaments; 3, those of the distal radioulnar articulation.

**Proximal Radioulnar Articulation** (*articulatio radioulnaris proximalis; superior radioulnar joint*).—This articulation is a trochoid or pivot-joint between the circumference of the head of the radius and the ring formed by the radial notch of the ulna and the annular ligament.




FIG. 455.—Annular ligament of radius, from above. The head of the radius has been sawn off and the bone dislodged from the ligament.

**The Annular Ligament** (*ligamentum annulare radii; orbicular ligament*) (Fig. 455).—This ligament is a strong band of fibres, which encircles the head of the radius, and retains it in contact with the radial notch of the ulna. It forms about four-fifths of the osseo-fibrous ring, and is attached to the anterior and posterior margins of the radial notch; a few of its lower fibres are continued around below the cavity and form at this level a complete fibrous ring. Its upper border blends with the anterior and posterior ligaments of the elbow, while from its lower border a thin

loose membrane passes to be attached to the neck of the radius; a thickened band which extends from the inferior border of the annular ligament below the radial notch to the neck of the radius is known as the **quadrate ligament**. The **superficial surface** of the annular ligament is strengthened by the radial collateral ligament of the elbow, and affords origin to part of the Supinator. Its **deep surface** is smooth, and lined by synovial membrane, which is continuous with that of the elbow-joint.

**Movements.**—The movements allowed in this articulation are limited to rotatory movements of the head of the radius within the ring formed by the annular ligament and the radial notch of the ulna; rotation forward being called *pronation*; rotation backward, *supination*. Supination is performed by the Biceps brachii and Supinator, assisted to a slight extent by the Extensor muscles of the thumb. Pronation is performed by the Pronator teres and Pronator quadratus.

**Applied Anatomy.**—Dislocation of the head of the radius alone is a not uncommon accident, and occurs most frequently in young persons from falls on the hand when the forearm is extended and supinated, the head of the bone being displaced forward. It is attended by rupture of the annular ligament. Occasionally a peculiar injury, which is supposed to be a subluxation, occurs in young children in lifting them from the ground by the hand or forearm. It is believed that the head of the radius is displaced downward in the annular ligament, the upper border of which becomes folded over the head of the radius, between it and the capitulum of the humerus. The forearm becomes fixed in a position of semiflexion, midway between supination and pronation, and great pain is complained of upon any attempt to move the joint. The synovial membrane of the proximal radioulnar joint is directly continuous with that of the elbow-joint, and, therefore, any septic or tuberculous disease which affects the latter also involves the former joint. The proximal radioulnar joint is always removed in an excision of the elbow (see p. 422).

**Middle Radioulnar Union.**—The shafts of the radius and ulna are connected by the Oblique Cord and the Interosseous Membrane.

**The Oblique Cord** (*chorda obliqua*; *oblique ligament*) (Fig. 451).—The oblique cord is a small, flattened band, extending downward and lateralward, from the lateral side of the tubercle of the ulna at the base of the coronoid process to the radius a little below the radial tuberosity. Its fibres run in the opposite direction to those of the interosseous membrane. It is sometimes wanting.

**The Interosseous Membrane** (*membrana interossea antebrachii*).—The interosseous membrane is a broad and thin plane of fibrous tissue descending obliquely downward and medialward, from the interosseous crest of the radius to that of the ulna; the lower part of the membrane is attached to the posterior of the two lines into which the interosseous crest of the radius divides. It is deficient above, commencing about 2.5 cm. beneath the tuberosity of the radius; is broader in the middle than at either end; and presents an oval aperture a little above its lower margin for the passage of the volar interosseous vessels to the back of the forearm. This membrane serves to connect the bones, and to increase the extent of surface for the attachment of the deep muscles. Between its upper border and the oblique cord is a gap, through which the dorsal interosseous vessels pass. Two or three fibrous bands are occasionally found on the dorsal surface of this membrane; they descend obliquely from the ulna toward the radius, and have consequently a direction contrary to that of the other fibres. The membrane is in relation, in *front*, by its upper three-fourths, with the Flexor pollicis longus on the radial side, and with the Flexor digitorum profundus on the ulnar, lying in the interval between which are the volar interosseous vessels and nerve; by its lower fourth with the Pronator quadratus; *behind*, with the Supinator, Abductor pollicis longus, Extensor pollicis brevis, Extensor pollicis longus, Extensor indicis proprius; and, near the wrist, with the volar interosseous artery and dorsal interosseous nerve.

**Distal Radioulnar Articulation** (*articulatio radioulnaris distalis*; *inferior radio-ulnar joint*).—This is a pivot-joint formed between the head of the ulna and the ulnar notch on the lower end of the radius. The articular surfaces are connected together by the following ligaments:

The Volar Radioulnar.

The Dorsal Radioulnar.

The Articular Disk.



**The Volar Radioulnar Ligament** (*anterior radioulnar ligament*) (Fig. 456).—This ligament is a narrow band of fibres extending from the anterior margin of the ulnar notch of the radius to the front of the head of the ulna.




FIG. 456.—Ligaments of wrist. Anterior view

**The Dorsal Radioulnar Ligament** (*posterior radioulnar ligament*) (Fig. 457).—This ligament extends between corresponding surfaces on the dorsal aspect of the articulation.




FIG. 457.—Ligaments of wrist. Posterior view.

**The Articular Disk** (*discus articularis; triangular fibrocartilage*) (Fig. 458).—The articular disk is triangular in shape, and is placed transversely beneath the head of the ulna, binding the lower ends of the ulna and radius firmly together. Its

periphery is thicker than its centre, which is occasionally perforated. It is attached by its apex to a depression between the styloid process and the head of the ulna; and by its base, which is thin, to the prominent edge of the radius, which separates the ulnar notch from the carpal articular surface. Its margins are united to the ligaments of the wrist-joint. Its **upper surface**, smooth and concave, articulates with the head of the ulna, forming an arthrodial joint; its **under surface**, also concave and smooth, forms part of the wrist-joint and articulates with the triangular bone and medial part of the lunate. Both surfaces are clothed by synovial membrane; the upper, by that of the distal radioulnar articulation, the under, by that of the wrist.




FIG. 458.—Vertical section through the articulations at the wrist, showing the synovial cavities.

**Synovial Membrane** (Fig. 458).—The synovial membrane of this articulation is extremely loose, and extends upward as a recess (*recessus sacciformis*) between the radius and the ulna.

**Movements.**—The movements in the distal radioulnar articulation consist of rotation of the lower end of the radius around an axis which passes through the centre of the head of the ulna. When the radius rotates forward, *pronation* of the forearm and hand is the result; and when backward, *supination*. It will thus be seen that in pronation and supination the radius describes the segment of a cone, the axis of which extends from the centre of the head of the radius to the middle of the head of the ulna. In this movement the head of the ulna is not stationary, but describes a curve in a direction opposite to that taken by the head of the radius. This, however, is not to be regarded as a rotation of the ulna—the curve which the head of this bone describes is due to a combined antero-posterior and rotatory movement, the former taking place almost entirely at the elbow-joint, the latter at the shoulder-joint.

## VI. Radiocarpal Articulation or Wrist-joint (*Articulatio Radiocarpea*) (Figs. 456, 457).

The wrist-joint is a condyloid articulation. The parts forming it are the lower end of the radius and under surface of the articular disk above; and the navicular, lunate, and triangular bones below. The articular surface of the radius and the under surface of the articular disk form together a transversely elliptical concave surface, the **receiving cavity**. The superior articular surfaces of the navicular, lunate, and triangular form a smooth convex surface, the **condyle**, which is received

into the concavity. The joint is surrounded by a capsule, strengthened by the following ligaments:

The Volar Radiocarpal.  
The Dorsal Radiocarpal.

The Ulnar Collateral.  
The Radial Collateral.

**The Volar Radiocarpal Ligament** (*ligamentum radiocarpeum volare; anterior ligament*) (Fig. 456).—This ligament is a broad membranous band, attached above to the anterior margin of the lower end of the radius, to its styloid process, and to the front of the lower end of the ulna; its fibres pass downward and medialward to be inserted into the volar surfaces of the navicular, lunate, and triangular bones, some being continued to the capitate. In addition to this broad membrane, there is rounded fasciculus, superficial to the rest, which reaches from the base of the styloid process of the ulna to the lunate and triangular bones. The ligament is perforated by apertures for the passage of vessels, and is in relation, in *front*, with the tendons of the Flexor digitorum profundus and Flexor pollicis longus; *behind*, it is closely adherent to the anterior border of the articular disk of the distal radioulnar articulation.

**The Dorsal Radiocarpal Ligament** (*ligamentum radiocarpeum dorsale; posterior ligament*) (Fig. 457).—The dorsal radiocarpal ligament less thick and strong than the volar, is attached, *above*, to the posterior border of the lower end of the radius; its fibres are directed obliquely downward and medialward, and are fixed, *below*, to the dorsal surfaces of the navicular, lunate, and triangular, being continuous with those of the dorsal intercarpal ligaments. It is in relation, *behind*, with the Extensor tendons of the fingers; in *front*, it is blended with the articular disk.

**The Ulnar Collateral Ligament** (*ligamentum collaterale carpi ulnare; internal lateral ligament*) (Fig. 456).—The ulnar collateral ligament is a rounded cord, attached above to the end of the styloid process of the ulna, and dividing below into two fasciculi, one of which is attached to the medial side of the triangular bone, the other to the pisiform and transverse carpal ligament.

**The Radial Collateral Ligament** (*ligamentum collaterale carpi radiale; external lateral ligament*) (Fig. 456).—The radial collateral ligament extends from the tip of the styloid process of the radius to the radial side of the navicular, some of its fibres being prolonged to the greater multangular bone and the transverse carpal ligament. It is in relation with the radial artery, which separates the ligament from the tendons of the Abductor pollicis longus and Extensor pollicis brevis.

**Synovial Membrane** (Fig. 458).—The synovial membrane lines the deep surfaces of the ligaments above described, extending from the margin of the lower end of the radius and articular disk above to the margins of the articular surfaces of the carpal bones below. It is loose and lax, and presents numerous folds, especially behind.

The wrist-joint is covered in front by the Flexor, and behind by the Extensor tendons.

The **arteries** supplying the joint are the volar and dorsal carpal branches of the radial and ulnar, the volar and dorsal metacarpals, and some ascending branches from the deep volar arch.

The **nerves** are derived from the ulnar and dorsal interosseous.

**Movements**.—The movements permitted in this joint are flexion, extension, abduction, adduction, and circumduction. They will be studied with those of the carpus, with which they are combined.

**Applied Anatomy**.—The wrist-joint is rarely dislocated, its strength depending mainly upon the numerous strong tendons which surround the articulation. Its security is further provided for by the number of small bones of which the carpus is made up, and which are united by very strong ligaments. The slight movements which take place between the several bones serve to break the jars that result from falls or blows on the hand. Dislocation backward, which is the more common, simulates to a considerable extent Colles' fracture of the radius, and is liable to be mistaken for it. The differential diagnosis can be easily made by observing the relative positions of the styloid processes of the radius and the ulna. In the natural condition the styloid process of the radius is on a lower level, *i. e.*, nearer the ground, when the arm hangs by the side than that of the ulna, and this relationship is not disturbed in dislocation. In Colles' fracture the styloid process of the radius is on the same level as, or even a higher level than, that of the ulna.

The wrist-joint is occasionally the seat of acute synovitis. When the joint cavity is distended with fluid, the swelling is greatest on the dorsal aspect of the wrist, showing a general fulness, with some bulging between the tendons. The inflammation is prone to extend to the intercarpal joints and to attack also the sheaths of the tendons in the neighborhood. Chronic inflammation of the wrist is generally tuberculous, and often leads to similar disease in the mucous sheaths of adjacent tendons and the intercarpal joints, with resulting ankylosis.

## VII. Intercarpal Articulations (*Articulationes Intercarpeae*; Articulations of the Carpus).

These articulations may be subdivided into three sets:

1. The Articulations of the Proximal Row of Carpal Bones.
2. The Articulations of the Distal Row of Carpal Bones.
3. The Articulations of the Two Rows with each Other.

**Articulations of the Proximal Row of Carpal Bones.**—These are arthrodial joints. The navicular, lunate, and triangular are connected by dorsal, volar, and interosseous ligaments.

**The Dorsal Ligaments** (*ligamenta intercarpea dorsalia*).—The dorsal ligaments, two in number, are placed transversely behind the bones of the first row; they connect the navicular and lunate, and the lunate and triangular.

**The Volar ligaments** (*ligamenta intercarpea volaria*; *palmar ligaments*).—The volar ligaments, also two, connect the navicular and lunate, and the lunate and triangular; they are less strong than the dorsal, and placed very deeply behind the Flexor tendons and the volar radiocarpal ligament.

**The Interosseous Ligaments** (*ligamenta intercarpea interossea*) (Fig. 458).—The interosseous ligaments are two narrow bundles, one connecting the lunate with the navicular, the other joining it to the triangular. They are on a level with the superior surfaces of these bones, and their upper surfaces are smooth, and form part of the convex articular surface of the wrist-joint.

The ligaments connecting the pisiform bone are the articular capsule and the two volar ligaments.

The **articular capsule** is a thin membrane which connects the pisiform to the triangular; it is lined by synovial membrane.

The two **volar ligaments** are strong fibrous bands; one, the **pisohamate ligament**, connects the pisiform to the hamate, the other, the **pisometacarpal ligament**, joins the pisiform to the base of the fifth metacarpal bone (Fig. 456). These ligaments are, in reality, prolongations of the tendon of the Flexor carpi ulnaris.

**Articulations of the Distal Row of Carpal Bones.**—These also are arthrodial joints; the bones are connected by dorsal, volar, and interosseous ligaments.

**The Dorsal Ligaments** (*ligamenta intercarpea dorsalia*).—The dorsal ligaments, three in number, extend transversely from one bone to another on the dorsal surface, connecting the greater with the lesser multangular, the lesser multangular with the capitate, and the capitate with the hamate.

**The Volar Ligaments** (*ligamenta intercarpea volaria*; *palmar ligaments*).—The volar ligaments, also three, have a similar arrangement on the volar surface.

**The Interosseous Ligaments** (*ligamenta intercarpea interossea*).—The three interosseous ligaments are much thicker than those of the first row; one is placed between the capitate and the hamate, a second between the capitate and the lesser multangular, and a third between the greater and lesser multangulars. The first is much the strongest, and the third is sometimes wanting.

**Articulations of the Two Rows of Carpal Bones with Each Other.**—The joint between the navicular, lunate, and triangular on the one hand, and the second row of carpal bones on the other, is named the **midcarpal joint**, and is made up of three distinct portions: in the centre the head of the capitate and the superior

surface of the hamate articulate with the deep cup-shaped cavity formed by the navicular and lunate, and constitute a sort of ball-and-socket joint. On the radial side the greater and lesser multangulares articulate with the navicular, and on the ulnar side the hamate articulates with the triangular, forming gliding joints.

The ligaments are: volar, dorsal, ulnar and radial collateral.

**The Volar Ligaments** (*ligamenta intercarpea volaria; anterior or palmar ligaments*).—The volar ligaments consist of short fibres, which pass, for the most part, from the volar surfaces of the bones of the first row to the front of the capitate.

**The Dorsal Ligaments** (*ligamenta intercarpea dorsalia; posterior ligaments*).—The dorsal ligaments consist of short, irregular bundles passing between the dorsal surfaces of the bones of the first and second rows.

**The Collateral Ligaments** (*lateral ligaments*).—The collateral ligaments are very short; one is placed on the radial, the other on the ulnar side of the carpus; the former, the stronger and more distinct, connects the navicular and greater multangular, the latter the triangular and hamate; they are continuous with the collateral ligaments of the wrist-joint. In addition to these ligaments, a slender interosseous band sometimes connects the capitate and the navicular.

**Synovial Membrane.**—The synovial membrane of the carpus is very extensive (Fig. 458), and bounds a synovial cavity of very irregular shape. The upper portion of the cavity intervenes between the under surfaces of the navicular, lunate, and triangular bones and the upper surfaces of the bones of the second row. It sends two prolongations upward—between the navicular and lunate, and the lunate and triangular—and three prolongations downward between the four bones of the second row. The prolongation between the greater and lesser multangulares, or that between the lesser multangular and capitate, is, owing to the absence of the interosseous ligament, often continuous with the cavity of the carpometacarpal joints, sometimes of the second, third, fourth, and fifth metacarpal bones, sometimes of the second and third only. In the latter condition the joint between the hamate and the fourth and fifth metacarpal bones has a separate synovial membrane. The synovial cavities of these joints are prolonged for a short distance between the bases of the metacarpal bones. There is a separate synovial membrane between the pisiform and triangular.

**Movements.**—The articulation of the hand and wrist considered as a whole involves four articular surfaces: (a) the inferior surfaces of the radius and articular disk; (b) the superior surfaces of the navicular, lunate, and triangular, the pisiform having no essential part in the movement of the hand; (c) the S-shaped surface formed by the inferior surfaces of the navicular, lunate, and triangular; (d) the reciprocal surface formed by the upper surfaces of the bones of the second row. These four surfaces form two joints: (1) a proximal, the wrist-joint proper; and (2) a distal, the mid-carpal joint.

1. The wrist-joint proper is a true condyloid articulation, and therefore all movements but rotation are permitted. Flexion and extension are the most free, and of these a greater amount of extension than of flexion is permitted, since the articulating surfaces extend farther on the dorsal than on the volar surfaces of the carpal bones. In this movement the carpal bones rotate on a transverse axis drawn between the tips of the styloid processes of the radius and ulna. A certain amount of adduction (or ulnar flexion) and abduction (or radial flexion) is also permitted. The former is considerably greater in extent than the latter on account of the shortness of the styloid process of the ulna, abduction being soon limited by the contact of the styloid process of the radius with the greater multangular. In this movement the carpus revolves upon an antero-posterior axis drawn through the centre of the wrist.<sup>1</sup> Finally, circumduction is permitted by the combined and consecutive movements of adduction, extension, abduction, and flexion. No rotation is possible, but the effect of rotation is obtained by the pronation and supination of the radius on the ulna. The movement of *flexion* is performed by the Flexor carpi radialis, the Flexor carpi ulnaris, and the Palmaris longus; *extension* by the Extensores carpi radiales longus and brevis and the Extensor carpi ulnaris; *adduction* (ulnar flexion) by the Flexor carpi ulnaris and the Extensor carpi ulnaris; and *abduction* (radial flexion) by the Abductor pollicis longus, the Extensors of the thumb, and the Extensores carpi radiales longus and brevis and the Flexor carpi radialis. When the fingers are extended, flexion of the wrist is performed by the Flexores carpi radialis and ulnaris and extension by the Extensor digitorum communis. When the fingers are flexed, flexion of the wrist is performed by the Flexores digitorum sublimis and profundus, and extension by the Extensores carpi radiales and ulnaris.

<sup>1</sup> H. M. Johnston (Journal of Anatomy and Physiology, vol. xli) maintains that in ulnar and radial flexion only slight lateral movement occurs at the radiocarpal joint, and that in complete flexion and extension of the hand there is a small degree of ulnar flexion at the radiocarpal joint.

2. The chief movements permitted in the mid-carpal joint are flexion and extension and a slight amount of rotation. In flexion and extension, which are the movements most freely enjoyed, the greater and lesser multangulars on the radial side and the hamate on the ulnar side glide forward and backward on the navicular and triangular respectively, while the head of the capitate and the superior surface of the hamate rotate in the cup-shaped cavity of the navicular and lunate. Flexion at this joint is freer than extension. A very trifling amount of rotation is also permitted, the head of the capitate rotating around a vertical axis drawn through its own centre, while at the same time a slight gliding movement takes place in the lateral and medial portions of the joint.

### VIII. Carpometacarpal Articulations (*Articulationes Carpometacarpeae*).

#### **Carpometacarpal Articulation of the Thumb** (*articulatio carpometacarpea pollicis*).

—This is a joint of reciprocal reception between the first metacarpal and the greater multangular; it enjoys great freedom of movement on account of the configuration of its articular surfaces, which are saddle-shaped. The joint is surrounded by a capsule, which is thick but loose, and passes from the circumference of the base of the metacarpal bone to the rough edge bounding the articular surface of the greater multangular; it is thickest laterally and dorsally, and is lined by synovial membrane.

**Movements.**—In this articulation the movements permitted are flexion and extension in the plane of the palm of the hand, abduction and adduction in a plane at right angles to the palm, circumduction, and opposition. It is by the movement of opposition that the tip of the thumb is brought into contact with the volar surfaces of the slightly flexed fingers. This movement is effected through the medium of a small sloping facet on the anterior lip of the saddle-shaped articular surface of the greater multangular. The Flexor muscles pull the corresponding part of the articular surface of the metacarpal bone on to this facet, and the movement of opposition is then carried out by the Adductors.

Flexion of this joint is produced by the Flexores pollicis longus and brevis, assisted by the Opponens pollicis and the Adductor pollicis. Extension is effected mainly by the abductor pollicis longus, assisted by the Extensores pollicis longus and brevis. Adduction is carried out by the Adductor; abduction mainly by the Abductores pollicis longus and brevis, assisted by the Extensors.

**Articulations of the Other Four Metacarpal Bones with the Carpus** (*articulationes carpometacarpeae*).—The joints between the carpus and the second, third, fourth, and fifth metacarpal bones are arthrodial. The bones are united by dorsal, volar, and interosseous ligaments.

**The Dorsal Ligaments** (*ligamenta carpometacarpea dorsalia*).—The dorsal ligaments, the strongest and most distinct, connect the carpal and metacarpal bones on their dorsal surfaces. The second metacarpal bone receives two fasciculi, one from the greater, the other from the lesser multangular; the third metacarpal receives two, one each from the lesser multangular and capitate; the fourth two, one each from the capitate and hamate; the fifth receives a single fasciculus from the hamate, and this is continuous with a similar ligament on the volar surface, forming an incomplete capsule.

**The Volar Ligaments** (*ligamenta carpometacarpea volaria; palmar ligaments*).—The volar ligaments have a somewhat similar arrangement, with the exception of those of the third metacarpal, which are three in number: a lateral one from the greater multangular, situated superficial to the sheath of the tendon of the Flexor carpi radialis; and intermediate one from the capitate; and a medial one from the hamate.

**The Interosseous Ligaments.**—The interosseous ligaments consist of short, thick fibres, and are limited to one part of the carpometacarpal articulation; they connect the contiguous inferior angles of the capitate and hamate with the adjacent surfaces of the third and fourth metacarpal bones.

**Synovial Membrane.**—The synovial membrane is a continuation of that of the intercarpal joints. Occasionally, the joint between the hamate and the fourth and fifth metacarpal bones has a separate synovial membrane.



The synovial membranes of the wrist and carpus (Fig. 458) are thus seen to be five in number. The *first* passes from the lower end of the ulnar to the ulnar notch of the radius, and lines the upper surface of the articular disk. The *second* passes from the articular disk and the lower end of the radius above, to the bones of the first row below. The *third*, the most extensive, passes between the contiguous margins of the two rows of carpal bones, and sometimes, in the event of one of the interosseous ligaments being absent, between the bones of the second row to the carpal extremities of the second, third, fourth, and fifth metacarpal bones. The *fourth* extends from the margin of the greater multangular to the metacarpal bone of the thumb. The *fifth* runs between the adjacent margins of the triangular and pisiform bones. Occasionally the fourth and fifth carpometacarpal joints have a separate synovial membrane.

**Movements.**—The movements permitted in the carpometacarpal articulations of the fingers are limited to slight gliding of the articular surfaces upon each other, the extent of which varies in the different joints. The metacarpal bone of the little finger is most movable, then that of the ring finger; the metacarpal bones of the index and middle fingers are almost immovable.

#### **IX. Intermetacarpal Articulations (Articulationes Intermetacarpeae; Articulations of the Metacarpal Bones with Each Other).**

The bases of the second, third, fourth and fifth metacarpal bones articulate with one another by small surfaces covered with cartilage, and are connected together by dorsal, volar, and interosseous ligaments.

The *dorsal* (*ligamenta basium oss. metacarp. dorsalia*) and *volar ligaments* (*ligamenta basium oss. metacarp. volaria; palmar ligaments*) pass transversely from one bone to another on the dorsal and volar surfaces. The *interosseous ligaments* (*ligamenta basium oss. metacarp. interossea*) connect their contiguous surfaces, just distal to their collateral articular facets.

The *synovial membrane* for these joints is continuous with that of the carpometacarpal articulations.

**The Transverse Metacarpal Ligament** (*ligamentum capitulorum [oss. metacarpalium] transversum*) (Fig. 459).—This ligament is a narrow fibrous band, which runs across the volar surfaces of the heads of the second, third, fourth and fifth metacarpal bones, connecting them together. It is blended with the volar (glenoid) ligaments of the metacarpophalangeal articulations. Its volar surface is concave where the Flexor tendons pass over it; behind it the tendons of the Interossei pass to their insertions.

#### **X. Metacarpophalangeal Articulations (Articulationes Metacarpophalangeae; Metacarpophalangeal Joints) (Figs. 459, 460).**

These articulations are of the condyloid kind, formed by the reception of the rounded heads of the metacarpal bones into shallow cavities on the proximal ends of the first phalanges, with the exception of that of the thumb, which presents more of the characters of a ginglymoid joint. Each joint has a volar and two collateral ligaments.

**The Volar Ligaments** (*glenoid ligaments of Cruveilhier; palmar or vaginal ligaments*).—The volar ligaments are thick, dense, fibrocartilaginous structures, placed upon the volar surfaces of the joints in the intervals between the collateral ligaments, to which they are connected; they are loosely united to the metacarpal bones, but are very firmly attached to the bases of the first phalanges. Their volar surfaces are intimately blended with the transverse metacarpal ligament, and present grooves for the passage of the Flexor tendons, the sheaths surrounding which are connected to the sides of the grooves. Their deep surfaces form parts of the articular facets for the heads of the metacarpal bones, and are lined by synovial membranes.

**The Collateral Ligaments** (*ligamenta collateralia; lateral ligaments*).—The collateral ligaments are strong, rounded cords, placed on the sides of the joints; each is attached by one extremity to the posterior tubercle and adjacent depres-

sion on the side of the head of the metacarpal bone, and by the other to the contiguous extremity of the phalanx.

The dorsal surfaces of these joints are covered by the expansions of the Extensor tendons, together with some loose areolar tissue which connects the deep surfaces of the tendons to the bones.




FIG. 459.—Metacarpophalangeal articulation and articulations of digit. Volar aspect.




FIG. 460.—Metacarpophalangeal articulation and articulations of digit. Ulnar aspect.

**Movements.**—The movements which occur in these joints are flexion, extension, adduction, abduction, and circumduction; the movements of abduction and adduction are very limited, and cannot be performed when the fingers are flexed.

## XI. Articulations of the Digits (*Articulationes Digitorum Manus*; **Interphalangeal Joints**) (Figs. 459, 460).

The interphalangeal articulations are hinge-joints; each has a volar and two collateral ligaments. The arrangement of these ligaments is similar to those in the metacarpophalangeal articulations. The Extensor tendons supply the place of posterior ligaments.

**Movements.**—The only movements permitted in the interphalangeal joints are flexion and extension; these movements are more extensive between the first and second phalanges than between the second and third. The amount of flexion is very considerable, but extension is limited by the volar and collateral ligaments.

**Muscles Acting on the Joints of the Digits.**—Flexion of the metacarpophalangeal joints of the fingers is effected by the *Flexores digitorum sublimis* and *profundus*, *Lumbricales*, and *Interossei*, assisted in the case of the little finger by the *Flexor digiti quinti brevis*. Extension is produced

by the Extensor digitorum communis, Extensor indicis proprius, and Extensor digiti quinti proprius.

Flexion of the interphalangeal joints of the fingers is accomplished by the Flexor digitorum profundus acting on the proximal and distal joints and by the Flexor digitorum sublimis acting on the proximal joints. Extension is effected mainly by the Lumbricales and Interossei, the long Extensors having little or no action upon these joints.

Flexion of the metacarpophalangeal joint of the thumb is effected by the Flexores pollicis longus and brevis; extension by the Extensores pollicis longus and brevis. Flexion of the interphalangeal joint is accomplished by the Flexor pollicis longus, and extension by the Extensor pollicis longus.

## ARTICULATIONS OF THE LOWER EXTREMITY.

The articulations of the Lower Extremity comprise the following:

- |                                  |                            |
|----------------------------------|----------------------------|
| I. Hip.                          | V. Intertarsal.            |
| II. Knee.                        | VI. Tarsometatarsal.       |
| III. Tibiofibular.               | VII. Intermetatarsal.      |
| IV. Ankle.                       | VIII. Metatarsophalangeal. |
| IX. Articulations of the Digits. |                            |

### I. Coxal Articulation or Hip-joint (Articulatio Coxae).

This articulation is an enarthrodial or ball-and-socket joint, formed by the reception of the head of the femur into the cup-shaped cavity of the acetabulum. The articular cartilage on the head of the femur, thicker at the centre than at the circumference, covers the entire surface with the exception of the fovea capitis femoris, to which the ligamentum teres is attached; that on the acetabulum forms an incomplete marginal ring, the lunate surface. Within the lunate surface there is a circular depression devoid of cartilage, occupied in the recent state by a mass of fat, covered by synovial membrane. The ligaments of the joint are:

- |                           |                               |
|---------------------------|-------------------------------|
| The Articular Capsule.    | The Pubocapsular.             |
| The Iliofemoral.          | The Ligamentum Teres Femoris. |
| The Ischiocapsular.       | The Glenoidal Labrum.         |
| The Transverse Acetabular |                               |

**The Articular Capsule** (*capsula articularis; capsular ligament*) (Figs. 442, 443).—The articular capsule is strong and dense. *Above*, it is attached to the margin of the acetabulum 5 to 6 mm. beyond the glenoidal labrum behind; but in *front*, it is attached to the outer margin of the labrum, and, opposite to the notch where the margin of the cavity is deficient, it is connected to the transverse ligament, and by a few fibres to the edge of the obturator foramen. It surrounds the neck of the femur, and is attached, in *front*, to the intertrochanteric line; *above*, to the base of the neck; *behind*, to the neck, about 1.25 cm. above the intertrochanteric crest; *below*, to the lower part of the neck, close to the lesser trochanter. From its femoral attachment some of the fibres are reflected upward along the neck as longitudinal bands, termed **retinacula**. The capsule is much thicker at the upper and forepart of the joint, where the greatest amount of resistance is required; behind and below, it is thin and loose. It consists of two sets of fibres, circular and longitudinal. The circular fibres, **zona orbicularis**, are most abundant at the lower and back part of the capsule (Fig. 463), and form a sling or collar around the neck of the femur. Anteriorly they blend with the deep surface of the iliofemoral ligament, and gain an attachment to the anterior inferior iliac spine. The longitudinal fibres are greatest in amount at the upper and front part of the capsule, where they are reinforced by distinct bands, or accessory ligaments, of which the most important is the **iliofemoral ligament**. The other accessory bands are known

as the **pubocapsular** and the **ischiocapsular ligaments**. The external surface of the capsule is rough, covered by numerous muscles, and separated in front from the Psoas major and Iliacus by a bursa, which not infrequently communicates by a circular aperture (Fig. 442) with the cavity of the joint.

**The Iliofemoral Ligament** (*ligamentum iliofemorale*; *Y-ligament*; *ligament of Bigelow*) (Fig. 461).—The iliofemoral ligament is a band of great strength which lies in front of the joint; it is intimately connected with the capsule, and serves to strengthen it in this situation. It is attached, *above*, to the lower part of the anterior inferior iliac spine; *below*, it divides into two bands, one of which passes downward and is fixed to the lower part of the intertrochanteric line; the other is directed downward and lateralward and is attached to the upper part of the




FIG. 461.—Right hip-joint from the front. (Spalteholz.)

same line. Between the two bands is a thinner part of the capsule. In some cases there is no division, and the ligament spreads out into a flat triangular band which is attached to the whole length of the intertrochanteric line. This ligament is frequently called the Y-shaped ligament of Bigelow; and its upper band is sometimes named the **iliotrochanteric ligament**.

**The Pubocapsular Ligament** (*ligamentum pubocapsulare*; *pubofemoral ligament*).—This ligament is attached, *above*, to the obturator crest and the superior ramus of the pubis; *below*, it blends with the capsule and with the deep surface of the vertical band of the iliofemoral ligament.

**The Ischiocapsular Ligament** (*ligamentum ischiocapsulare*; *ischiocapsular band*; *ligament of Bertin*).—The ischiocapsular ligament consists of a triangular band of strong fibres, which spring from the ischium below and behind the acetabulum, and blend with the circular fibres of the capsule.

**The Ligamentum Teres Femoris** (Fig. 462).—The ligamentum teres femoris is a triangular, somewhat flattened band implanted by its apex into the antero-superior part of the fovea capitis femoris; its base is attached by two bands, one into either side of the acetabular notch, and between these bony attachments it blends with the transverse ligament. It is ensheathed by the synovial membrane, and varies greatly in strength in different subjects; occasionally only the synovial fold exists, and in rare cases even this is absent. The ligament is made tense when the thigh is semiflexed and the limb then adducted or rotated outward; it is, on the other hand, relaxed when the limb is abducted. It has, however, but little influence as a ligament.




FIG. 462.—Left hip-joint, opened by removing the floor of the acetabulum from within the pelvis.

**The Glenoidal Labrum** (*labrum glenoidale*; *cotyloid ligament*).—The glenoidal labrum is a fibrocartilaginous rim attached to the margin of the acetabulum, the cavity of which it deepens; at the same time it protects the edge of the bone, and fills up the inequalities of its surface. It bridges over the notch as the **transverse ligament**, and thus forms a complete circle, which closely surrounds the head of the femur and assists in holding it in its place. It is triangular on section, its base being attached to the margin of the acetabulum, while its opposite edge is free and sharp. Its two surfaces are invested by synovial membrane, the external one being in contact with the capsule, the internal one being inclined inward so as to narrow the acetabulum, and embrace the cartilaginous surface of the head of the femur. It is much thicker above and behind than below and in front, and consists of compact fibres.

**The Transverse Acetabular Ligament** (*ligamentum transversum acetabuli*; *transverse ligament*).—This ligament is in reality a portion of the glenoidal labrum, though differing from it in having no cartilage cells among its fibres. It consists of strong,



flattened fibres, which cross the acetabular notch, and convert it into a foramen through which the nutrient vessels enter the joint.

**Synovial Membrane** (Fig. 463).—The synovial membrane is very extensive. Commencing at the margin of the cartilaginous surface of the head of the femur, it covers the portion of the neck which is contained within the joint; from the neck it is reflected on the internal surface of the capsule, covers both surfaces of the glenoidal labrum and the mass of fat contained in the depression at the bottom of the acetabulum, and ensheathes the ligamentum teres as far as the head of the femur. The joint cavity sometimes communicates through a hole in the capsule between the vertical band of the iliofemoral ligament and the pubocapsular ligament with a bursa situated on the deep surfaces of the Psoas major and Iliacus.




FIG. 463.—Capsule of hip-joint (distended). Posterior aspect.

The **muscles** in relation with the joint are, in *front*, the Psoas major and Iliacus, separated from the capsule by a bursa; *above*, the reflected head of the Rectus femoris and Glutaeus minimus, the latter being closely adherent to the capsule; *medially*, the Obturator externus and Pectineus; *behind*, the Piriformis, Gemellus superior, Obturator internus, Gemellus inferior, Obturator externus, and Quadratus femoris (Fig. 464).

The **arteries** supplying the joint are derived from the obturator, medial femoral circumflex, and superior and inferior gluteals.

The **nerves** are articular branches from the sacral plexus, sciatic, obturator, accessory obturator, and a filament from the branch of the femoral supplying the Rectus femoris.

**Movements.**—The movements of the hip are very extensive, and consist of flexion, extension, adduction, abduction, circumduction, and rotation.

The length of the neck of the femur and its inclinations to the body of the bone have the effect of converting the angular movements of flexion, extension, adduction, and abduction partially into rotatory movements in the joint. Thus when the thigh is flexed or extended, the head of the femur, on account of the *medial* inclination of the neck, rotates within the acetabulum with only a slight amount of gliding to and fro. The *forward* slope of the neck similarly affects the movements of adduction and abduction. Conversely rotation of the thigh which is permitted by the *upward* inclination of the neck, is not a simple rotation of the head of the femur in the acetabulum, but is accompanied by a certain amount of gliding.



The hip-joint presents a very striking contrast to the shoulder-joint in the much more complete mechanical arrangements for its security and for the limitation of its movements. In the shoulder, as has been seen, the head of the humerus is not adapted at all in size to the glenoid cavity, and is hardly restrained in any of its ordinary movements by the capsule. In the hip-joint, on the contrary, the head of the femur is closely fitted to the acetabulum for an area extending over nearly half a sphere, and at the margin of the bony cup it is still more closely embraced by the glenoidal labrum, so that the head of the femur is held in its place by that ligament even when the fibres of the capsule have been quite divided. The iliofemoral ligament is the strongest of all the ligaments in the body, and is put on the stretch by any attempt to extend the femur beyond a straight line with the trunk. That is to say, this ligament is the chief agent in maintaining the erect position without muscular fatigue; for a vertical line passing through the centre of gravity of the trunk falls behind the centres of rotation in the hip-joints, and therefore the pelvis tends to fall backward, but is prevented by the tension of the iliofemoral ligaments. The security of the joint may be provided for also by the two bones being directly united through the ligamentum teres; but it is doubtful whether this ligament has much influence upon the mechanism




FIG. 464.—Structures surrounding right hip-joint.

of the joint. When the knee is flexed, flexion of the hip-joint is arrested by the soft parts of the thigh and abdomen being brought into contact, and when the knee is extended, by the action of the hamstring muscles; extension is checked by the tension of the iliofemoral ligament; adduction by the thighs coming into contact; adduction with flexion by the lateral band of the iliofemoral ligament and the lateral part of the capsule; abduction by the medial band of the iliofemoral ligament and the pubocapsular ligament; rotation outward by the lateral band of the iliofemoral ligament; and rotation inward by the ischiocapsular ligament and the hinder part of the capsule. The muscles which *flex* the femur on the pelvis are the Psoas major, Iliacus, Rectus femoris, Sartorius, Pectineus, Adductores longus and brevis, and the anterior fibres of the Glutaei medius and minimus. *Extension* is mainly performed by the Glutaeus maximus, assisted by the hamstring muscles and the ischial head of the Adductor magnus. The thigh is *adducted* by the Adductores magnus, longus, and brevis, the Pectineus, the Gracilis, and lower part of the Glutaeus maximus, and *abducted* by the Glutaei medius and minimus, and the upper part of the Glutaeus maximus. The muscles which *rotate* the thigh *inward* are the Glutaeus minimus and the anterior fibres of the Glutaeus medius, the Tensor fasciae latae and the Iliacus and Psoas major; while

those which rotate it *outward* are the posterior fibres of the Glutaeus medius, the Piriformis, Obturatores externus and internus, Gemelli superior and inferior, Quadratus femoris, Glutaeus maximus, the Adductores longus, brevis, and magnus, and the Pectineus, and the Sartorius.

**Applied Anatomy.**—In dislocation of the hip, "the head of the thigh bone may rest at any point around its socket" (Bryant); but whatever position it ultimately assumes, the primary displacement is generally downward and medialward, the capsule giving way at its weakest—that is, its lower and medial—part. The situation that the head of the bone subsequently assumes is determined by the degree of flexion or extension, and of outward or inward rotation of the thigh at the moment of luxation, influenced, no doubt, by the iliofemoral ligament, which is not easily ruptured. When, for instance, the head of the bone is forced backward, this ligament forms a fixed axis, around which the head of the bone rotates, and is thus driven on to the dorsum of the ilium. The iliofemoral ligament also influences the position of the thigh in the various dislocations; in the dislocations backward it is tense, and produces inversion of the limb; in the dislocation on to the pubis, it is relaxed, and therefore allows the external rotators to evert the thigh; while in dislocation into the obturator foramen it is tense, and produces flexion. The muscles inserted into the upper part of the femur, with the exception of the Obturator internus, have very little direct influence in determining the position of the head of the bone. Bigelow, however, has endeavored to show that the Obturator internus is the principal agent in deciding whether, in the backward dislocations, the head of the bone shall be ultimately lodged on the dorsum of the ilium, or in or near the greater sciatic notch; in both dislocations the head passes, in the first instance, in the same direction; but, as Bigelow asserts, in the displacement on to the dorsum the head of the bone travels up behind the acetabulum, in front of the muscle; while in the dislocation into the greater sciatic notch the head passes behind the muscle, and is prevented from reaching the dorsum, in consequence of the tendon of the muscle arching over the neck of the bone, and it therefore remains in the neighborhood of the notch. Bigelow distinguishes these two forms of dislocation by describing them as dislocations backward, "above and below" the Obturator internus.

The iliofemoral ligament is rarely torn in dislocations of the hip, and this fact is taken advantage of by the surgeon in reducing these dislocations by manipulation. It is made to act as the fulcrum to a lever, of which the long arm is the body of the femur, and the short arm the neck of the bone (Fig. 465).

The hip-joint is rarely the seat of acute synovitis from injury, on account of its deep position and its thick covering of soft parts. Acute inflammation may, and does, frequently occur as the result of bacterial infections, as in rheumatism, pyemia, etc. When, in these cases, effusion takes place, and the joint is distended with fluid, the swelling is not very easy to detect on account of the thickness of the capsule and the depth of the articulation. It is principally to be found on the front of the joint, just medial to the iliofemoral ligament; or behind, at the lower and back part. In these two places the capsule is thinner than elsewhere. Disease of the hip-joint is much oftener of a chronic character, and is usually of tuberculous origin. It begins usually in the bone, and, in most cases, in the growing, highly vascular tissue in the neighborhood of the epiphysal cartilage of the femoral head. In this respect it differs very materially from tuberculous arthritis of the knee, where the disease usually commences in the synovial membrane.

In chronic hip disease the affected limb assumes an altered position, the cause of which it is important to understand. In the early stage of a typical case, the limb is flexed, abducted, and rotated outward. In this position all the ligaments of the joint are relaxed; the front of the capsule by flexion; the lateral band of the iliofemoral ligament by abduction; and the medial band of this ligament and the back of the capsule by rotation outward. It is, therefore, the position of greatest ease. The condition is not quite obvious at first, upon examining a patient. If the patient be laid in the supine position, the affected limb will be found to be extended and parallel with the other. But it will be seen that the pelvis is tilted downward on the diseased side and the limb apparently longer than its fellow, and that the lumbar portion of the vertebral column is arched forward (lordosis). The condition is thus explained: a limb which is flexed and abducted is obviously useless for progression, and in order to overcome the difficulty the



FIG. 465.—Hip-joint, showing the iliofemoral ligament. (After Bigelow.)

patient depresses the affected side of his pelvis, thus producing parallelism of his limbs, and at the same time rotates his pelvis on its transverse horizontal axis, so as to direct the limb downward, instead of forward. In the later stages of the disease the limb becomes flexed and adducted and inverted. This position probably depends upon muscular action, at all events as regards the adduction. The Adductor muscles are supplied by the obturator nerve, which also largely supplies the joint. These muscles are therefore thrown into reflex spasm by the irritation of the peripheral terminations of this nerve in the inflamed articulation.

Osteoarthritis is common in the hip-joint, and more so in the male than in the female, in whom the knee-joint is more frequently affected. It is a disease of middle age or advanced life. When much deformity is associated with chronic osteoarthritis the condition is spoken of as *arthritis deformans of the hip*, or *morbus coxae senilis*. The head of the femur is worn away, and after it often the neck too, until a new irregular articular surface is produced, around which a new formation of bone occurs, and also about the edges of the acetabulum, which is widened and eroded by a similar chronic process. Pain in the joint, shortening of the limb, and great limitation of movement result, with much creaking and grating when the joint is moved.

Congenital dislocation is more commonly met with in the hip-joint than in any other articulation. The displacement usually takes place on to the dorsum ilii. It gives rise to extreme lordosis and a waddling gait is noticed as soon as the child commences to walk.

Excision of the hip may be required for disease or for injury, especially gunshot. It may be performed either by an anterior or a posterior incision. The former entails less interference with important structures, especially muscles, than the latter, but permits of less efficient drainage. In the operation from the front, an incision is made 8 to 10 cm. in length, starting immediately below and lateral to the anterior superior iliac spine, downward between the Sartorius and Tensor fasciae latae, to the neck of the bone, dividing the capsule at its upper part. The neck of the femur is then divided, and the head of the bone extracted. All diseased tissue is carefully removed with a sharp spoon or scissors, and the cavity thoroughly flushed out with a hot antiseptic or sterile fluid. The posterior method consists in making an incision 8 to 10 cm. long commencing midway between the top of the greater trochanter and the iliac crest, and extending down the posterior border of the trochanter. The muscles are detached from the greater trochanter, and the capsule opened freely. The head and neck are freed from the soft parts and as much affected bone removed as is thought necessary. The head of the bone is then levered out of the acetabulum.

## II. The Knee-joint (*Articulatio Genu*).

The knee-joint was formerly described as a ginglymus or hinge-joint, but is really of a much more complicated character. It must be regarded as consisting of three articulations in one: two condyloid joints, one between each condyle of the femur and the corresponding meniscus and condyle of the tibia; and a third between the patella and the femur, partly arthrodial, but not completely so, since the articular surfaces are not mutually adapted to each other, so that the movement is not a simple gliding one. This view of the construction of the knee-joint receives confirmation from the study of the articulation in some of the lower mammals, where, corresponding to these three subdivisions, three synovial cavities are sometimes found, either entirely distinct or only connected together by small communications. This view is further rendered probable by the existence in the middle of the joint of the two cruciate ligaments, which must be regarded as the collateral ligaments of the medial and lateral joints. The existence of the patellar fold of synovial membrane would further indicate a tendency to separation of the synovial cavity into two minor sacs, one corresponding to the lateral and the other to the medial joint.

The bones are connected together by the following ligaments:

The Articular Capsule.	The Anterior Cruciate.
The Ligamentum Patellae.	The Posterior Cruciate.
The Oblique Popliteal.	The Medial and Lateral Menisci.
The Tibial Collateral.	The Transverse.
The Fibular Collateral.	The Coronary.

**The Articular Capsule** (*capsula articularis*; *capsular ligament*) (Fig. 466).—The articular capsule consists of a thin, but strong, fibrous membrane which is strengthened in almost its entire extent by bands inseparably connected with it. Above

and in front, beneath the tendon of the Quadriceps femoris, it is represented only by the synovial membrane. Its chief strengthening bands are derived from the fascia lata and from the tendons surrounding the joint. In front, expansions from the Vasti and from the fascia lata and its iliotibial band fill in the intervals between the anterior and collateral ligaments, constituting the **medial and lateral patellar retinacula**. Behind the capsule consists of vertical fibres which arise from the condyles and from the sides of the intercondyloid fossa of the femur; the posterior part of the capsule is therefore situated on the sides of and in front of the cruciate ligaments, which are thus excluded from the joint cavity. Behind the cruciate ligaments is the oblique popliteal ligament which is augmented by fibres derived from the tendon of the Semimembranosus. Laterally, a prolongation from the iliotibial band fills in the interval between the oblique popliteal and the fibular collateral ligaments, and partly covers the latter. Medially, expansions from the Sartorius and Semimembranosus pass upward to the tibial collateral ligament and strengthen the capsule.

**The Ligamentum Patellae (anterior ligament)** (Fig. 466).—The ligamentum patellae is the central portion of the common tendon of the Quadriceps femoris, which is continued from the patella to the tuberosity of the tibia. It is a strong, flat, ligamentous band, about 8 cm. in length, attached, *above*, to the apex and adjoining margins of the patella and the rough depression on its posterior surface; *below*, to the tuberosity of the tibia; its superficial fibres are continuous over the front of the patella with those of the tendon of the Quadriceps femoris. The medial and lateral portions of the tendon of the Quadriceps pass down on either side of the patella, to be inserted into the upper extremity of the tibia on either side of the tuberosity; these portions merge into the capsule, as stated above, forming the medial and lateral patellar retinacula. The posterior surface of the ligamentum patellae is separated from the synovial membrane of the joint by a large infrapatellar pad of fat, and from the tibia by a bursa.

**The Oblique Popliteal Ligament** (*ligamentum popliteum obliquum; posterior ligament*) (Fig. 467).—This ligament is a broad, flat, fibrous band, formed of fasciculi separated from one another by apertures for the passage of vessels and nerves. It is attached above to the upper margin of the intercondyloid fossa and posterior surface of the femur close to the articular margins of the condyles, and below to the posterior margin of the head of the tibia. Superficial to the main part of the ligament is a strong fasciculus, derived from the tendon of the Semimembranosus and passing from the back part of the medial condyle of the tibia obliquely upward and lateralward to the back part of the lateral condyle of the femur. The oblique popliteal ligament forms part of the floor of the popliteal fossa, and the popliteal artery rests upon it.

**The Tibial Collateral Ligament** (*ligamentum collaterale tibiale; internal lateral ligament*) (Fig. 466).—The tibial collateral is a broad, flat, membranous band, situated nearer to the back than to the front of the joint. It is attached, *above*, to the medial




FIG. 466.—Right knee-joint. Anterior view.

condyle of the femur immediately below the adductor tubercle; *below*, to the medial condyle and medial surface of the body of the tibia. The fibres of the posterior part of the ligament are short and incline backward as they descend; they are inserted into the tibia above the groove for the Semimembranosus. The anterior part of the ligament is a flattened band, about 10 cm. long, which inclines forward as it descends. It is inserted into the medial surface of the body of the tibia about 2.5 cm. below the level of the condyle. It is crossed, at its lower part, by the tendons of the Sartorius, Gracilis, and Semitendinosus, a bursa being interposed. Its deep surface covers the inferior medial genicular vessels and nerve and the anterior portion of the tendon of the Semimembranosus, with which it is connected by a few fibres; it is intimately adherent to the medial meniscus.




FIG. 467.—Right knee-joint. Posterior view.




FIG. 468.—Right knee-joint, from the front, showing interior ligaments.

**The Fibular Collateral Ligament** (*ligamentum collaterale fibulare; external lateral or long external lateral ligament*) (Fig. 469).—The fibular collateral is a strong, rounded, fibrous cord, attached, *above*, to the back part of the lateral condyle of the femur, immediately above the groove for the tendon of the Popliteus; *below*, to the lateral side of the head of the fibula, in front of the styloid process. The greater part of its lateral surface is covered by the tendon of the Biceps femoris; the tendon, however, divides at its insertion into two parts, which are separated by the ligament. Deep to the ligament are the tendon of the Popliteus, and the inferior lateral genicular vessels and nerve. The ligament has no attachment to the lateral meniscus.

An inconstant bundle of fibres, the **short fibular collateral ligament**, is placed behind and parallel with the preceding, attached, *above*, to the lower and back part of the lateral condyle of the femur; *below*, to the summit of the styloid process of the fibula. Passing deep to it are the tendon of the Popliteus, and the inferior lateral genicular vessels and nerve.



**The Cruciate Ligaments** (*ligamenta cruciata genu; crucial ligaments*).—The cruciate ligaments are of considerable strength, situated in the middle of the joint, nearer to its posterior than to its anterior surface. They are called *cruciate* because they cross each other somewhat like the lines of the letter X; and have received the names **anterior** and **posterior**, from the position of their attachments to the tibia.

**The Anterior Cruciate Ligament** (*ligamentum cruciatum anterius; external crucial ligament*) (Fig. 468) is attached to the depression in front of the intercondyloid eminence of the tibia, being blended with the anterior extremity of the lateral meniscus; it passes upward, backward, and lateralward, and is fixed into the medial and back part of the lateral condyle of the femur.




FIG. 469.—Left knee-joint from behind, showing interior ligaments.

**The Posterior Cruciate Ligament** (*ligamentum cruciatum posterius; internal crucial ligament*) (Fig. 469) is stronger, but shorter and less oblique in its direction, than the anterior. It is attached to the posterior intercondyloid fossa of the tibia, and to the posterior extremity of the lateral meniscus; and passes upward, forward, and medialward, to be fixed into the lateral and front part of the medial condyle of the femur.

**The Menisci** (*semilunar fibrocartilages*) (Fig. 470).—The menisci are two crescentic lamellæ, which serve to deepen the surfaces of the head of the tibia for articulation with the condyles of the femur. The peripheral border of each meniscus is thick, convex, and attached to the inside of the capsule of the joint; the opposite border is thin, concave, and free. The upper surfaces of the menisci are concave, and in contact with the condyles of the femur; their lower surfaces are flat, and rest upon the head of the tibia; both surfaces are smooth, and invested by synovial membrane. Each meniscus covers approximately the peripheral two-thirds of the corresponding articular surface of the tibia.



The **medial meniscus** (*meniscus medialis*; *internal semilunar fibrocartilage*) is nearly semicircular in form, a little elongated from before backward, and broader behind than in front; its anterior end, thin and pointed, is attached to the anterior intercondyloid fossa of the tibia, in front of the anterior cruciate ligament; its posterior end is fixed to the posterior intercondyloid fossa of the tibia, between the attachments of the lateral meniscus and the posterior cruciate ligament.




FIG. 470.—Head of right tibia seen from above, showing menisci and attachments of ligaments.

The **lateral meniscus** (*meniscus lateralis*; *external semilunar fibrocartilage*) is nearly circular and covers a larger portion of the articular surface than the medial one. It is grooved laterally for the tendon of the Popliteus, which separates it from the fibular collateral ligament. Its anterior end is attached in front of the intercondyloid eminence of the tibia, lateral to, and behind, the anterior cruciate ligament, with which it blends; the posterior end is attached behind the intercondyloid eminence of the tibia and in front of the posterior end of the medial meniscus. The anterior attachment of the lateral meniscus is twisted on itself so that its free margin looks backward and upward, its anterior end resting on a sloping shelf of bone on the front of the lateral process of the intercondyloid eminence. Close to its posterior attachment it sends off a strong fasciculus, the **ligament of Wrisberg** (Figs. 469, 470), which passes upward and medialward, to be inserted into the medial condyle of the femur, immediately behind the attachment of the posterior cruciate ligament. Occasionally a small fasciculus passes forward to be inserted into the lateral part of the anterior cruciate ligament. The lateral meniscus gives off from its anterior convex margin a fasciculus which forms the transverse ligament.

**The Transverse Ligament** (*ligamentum transversum genu*).—The transverse ligament connects the anterior convex margin of the lateral meniscus to the anterior end of the medial meniscus; its thickness varies considerably in different subjects, and it is sometimes absent.

The **coronary ligaments** are merely portions of the capsule, which connect the periphery of each meniscus with the margin of the head of the tibia.

**Synovial Membrane.**—The synovial membrane of the knee-joint is the largest and most extensive in the body. Commencing at the upper border of the patella, it forms a large cul-de-sac beneath the Quadriceps femoris (Figs. 471, 472) on the lower part of the front of the femur, and frequently communicates with a bursa interposed between the tendon and the front of the femur. The pouch of synovial membrane between the Quadriceps and front of the femur is supported, during the movements of the knee, by a small muscle, the *Articularis genu*, which

is inserted into it. On either side of the patella, the synovial membrane extends beneath the aponeuroses of the Vasti, and more especially beneath that of the Vastus medialis. Below the patella it is separated from the ligamentum patellae by a considerable quantity of fat, known as the **infrapatellar pad**. From the medial and lateral borders of the articular surface of the patella, reduplications of the synovial membrane project into the interior of the joint. These form two fringe-like folds termed the **alar folds**; below, these folds converge and are continued as a single band, the **patellar fold** (*ligamentum mucosum*), to the front of the intercondyloid fossa of the femur. On either side of the joint, the synovial membrane passes downward from the femur, lining the capsule to its point of attachment to the menisci; it may then be traced over the upper surfaces of these to their free borders, and thence along their under surfaces to the tibia (Figs. 472, 473).




FIG. 471.—Sagittal section of right knee-joint.

At the back part of the lateral meniscus it forms a cul-de-sac between the groove on its surface and the tendon of the Popliteus; it is reflected across the front of the cruciate ligaments, which are therefore situated outside the synovial cavity.

**Bursæ.**—The bursæ near the knee-joint are the following: In front there are *four* bursæ: a large one is interposed between the patella and the skin, a small one between the upper part of the tibia and the ligamentum patellae, a third between the lower part of the tuberosity of the tibia and the skin, and a fourth between the anterior surface of the lower part of the femur and the deep surface of the Quadriceps femoris, usually communicating with the knee-joint. Laterally there are *four* bursæ: (1) one (which sometimes communicates with the joint) between the lateral head of the Gastrocnemius and the capsule; (2) one between the fibular collateral ligament

and the tendon of the Biceps; (3) one between the fibular collateral ligament and the tendon of the Popliteus (this is sometimes only an expansion from the next bursa); (4) one between the tendon of the Popliteus and the lateral condyle of the femur, usually an extension from the synovial membrane of the joint. Medially, there are five bursæ: (1) one between the medial head of the Gastrocnemius and the capsule; this sends a prolongation between the tendon of the medial head of the Gastrocnemius and the tendon of the Semimembranosus and often communicates with the joint; (2) one superficial to the tibial collateral ligament, between it and the tendons of the Sartorius, Gracilis, and Semitendinosus; (3) one deep to the tibial collateral ligament, between it and the tendon of the Semimembranosus (this is sometimes only an expansion from the next bursa); (4) one between the tendon of the Semimembranosus and the head of the tibia; (5) occasionally there is a bursa between the tendons of the Semimembranosus and Semitendinosus.




FIG. 472.—Capsule of right knee-joint (distended). Lateral aspect.

**Structures Around the Joint.**—In front, and at the sides, is the Quadriceps femoris; laterally the tendons of the Biceps femoris and Popliteus and the common peroneal nerve; medially, the Sartorius, Gracilis, Semitendinosus, and Semimembranosus; behind, the popliteal vessels, and the tibial nerve, Popliteus, Plantaris, and medial and lateral heads of the Gastrocnemius, some lymph glands, and fat.

The **arteries** supplying the joint are the highest genicular (anastomotica magna), a branch of the femoral, the genicular branches of the popliteal, the recurrent branches of the anterior tibial, and the descending branch from the lateral femoral circumflex of the profunda femoris.

The **nerves** are derived from the obturator, femoral, tibial, and common peroneal.

**Movements.**—The movements which take place at the knee-joint are flexion and extension, and, in certain positions of the joint, internal and external rotation. The movements of flexion and extension at this joint differ from those in a typical hinge-joint, such as the elbow, in that (a) the axis around which motion takes place is not a fixed one, but shifts forward during extension and backward during flexion; (b) the commencement of flexion and the end of extension are accompanied by rotatory movements associated with the fixation of the limb in a position of

great stability. The movement from full flexion to full extension may therefore be described in three phases:

1. In the fully flexed condition the posterior parts of the femoral condyles rest on the corresponding portions of the meniscotibial surfaces, and in this position a slight amount of simple rolling movement is allowed.

2. During the passage of the limb from the flexed to the extended position a gliding movement is superposed on the rolling, so that the axis, which at the commencement is represented by a line through the inner and outer condyles of the femur, gradually shifts forward. In this part of the movement, the posterior two-thirds of the tibial articular surfaces of the two femoral condyles are involved, and as these have similar curvatures and are parallel to one another, they move forward equally.




FIG. 473.—Capsule of right knee-joint (distended). Posterior aspect.

3. The lateral condyle of the femur is brought almost to rest by the tightening of the anterior cruciate ligament; it moves, however, slightly forward and medialward, pushing before it the anterior part of the lateral meniscus. The tibial surface on the medial condyle is prolonged farther forward than that on the lateral, and this prolongation is directed lateralward. When, therefore, the movement forward of the condyles is checked by the anterior cruciate ligament, continued muscular action causes the medial condyle, dragging with it the meniscus, to travel backward and medialward, thus producing an internal rotation of the thigh on the leg. When the position of full extension is reached the lateral part of the groove on the lateral condyle is pressed against the anterior part of the corresponding meniscus, while the medial part of the groove rests on the articular margin in front of the lateral process of the tibial intercondyloid eminence. Into the groove on the medial condyle is fitted the anterior part of the medial meniscus, while the anterior cruciate ligament and the articular margin in front of the medial process of the tibial intercondyloid eminence are received into the forepart of the intercondyloid fossa of the femur. This third phase by which all these parts are brought into accurate apposition is known as the "screwing home," or locking movement of the joint.

The complete movement of flexion is the converse of that described above, and is therefore preceded by an external rotation of the femur which unlocks the extended joint.

The axes around which the movements of flexion and extension take place are not precisely at right angles to either bone; in flexion, the femur and tibia are in the same plane, but in extension the one bone forms an angle, opening lateralward with the other.



In addition to the rotatory movements associated with the completion of extension and the initiation of flexion, rotation inward or outward can be effected when the joint is partially flexed; these movements take place mainly between the tibia and the menisci, and are freest when the leg is bent at right angles with the thigh.

**Movements of Patella.**—The articular surface of the patella is indistinctly divided into seven facets—upper, middle, and lower horizontal pairs, and a medial perpendicular facet (Fig. 474).




FIG. 474.—Posterior surface of the right patella, showing diagrammatically the areas of contact with the femur in different positions of the knee.

When the knee is forcibly flexed, the medial perpendicular facet is in contact with the semilunar surface on the lateral part of the medial condyle; this semilunar surface is a prolongation backward of the medial part of the patellar surface. As the leg is carried from the flexed to the extended position, first the highest pair, then the middle pair, and lastly the lowest pair of horizontal facets is successively brought into contact with the patellar surface of the femur. In the extended position, when the Quadriceps femoris is relaxed, the patella lies loosely on the front of the lower end of the femur.

During flexion, the ligamentum patellae is put upon the stretch, and in extreme flexion the posterior cruciate ligament, the oblique popliteal, and collateral ligaments, and, to a slight extent, the anterior cruciate ligament, are relaxed. Flexion is checked during life by the contact of the leg with the thigh. When the knee-joint is fully extended the oblique popliteal and collateral ligaments,

the anterior cruciate ligament, and the posterior cruciate ligament, are rendered tense; in the act of extending the knee, the ligamentum patellae is tightened by the Quadriceps femoris, but in full extension with the heel supported it is relaxed. Rotation inward is checked by the anterior cruciate ligament; rotation outward tends to uncross and relax the cruciate ligaments, but is checked by the tibial collateral ligament. The main function of the cruciate ligament is to act as a direct bond between the tibia and femur and to prevent the former bone from being carried too far backward or forward. They also assist the collateral ligaments in resisting any bending of the joint to either side. The menisci are intended, as it seems, to adapt the surfaces of the tibia to the shape of the femoral condyles to a certain extent, so as to fill up the intervals which would otherwise be left in the varying positions of the joint, and to obviate the jars which would be so frequently transmitted up the limb in jumping or by falls on the feet; also to permit of the two varieties of motion, flexion and extension, and rotation, as explained above. The patella is a great defence to the front of the knee-joint, and distributes upon a large and tolerably even surface, during kneeling, the pressure which would otherwise fall upon the prominent ridges of the condyles; it also affords leverage to the Quadriceps femoris.

When standing erect in the attitude of "attention," the weight of the body falls in front of a line carried across the centres of the knee-joints, and therefore tends to produce overextension of the articulations; this, however, is prevented by the tension of the anterior cruciate, oblique popliteal, and collateral ligaments.

**Extension** of the leg on the thigh is performed by the Quadriceps femoris; *flexion* by the Biceps femoris, Semitendinosus, and Semimembranosus, assisted by the Gracilis, Sartorius, Gastrocnemius, Popliteus, and Plantaris. *Rotation outward* is effected by the Biceps femoris, and *rotation inward* by the Popliteus, Semitendinosus, and, to a slight extent, the Semimembranosus, the Sartorius, and the Gracilis. The Popliteus comes into action especially at the commencement of the movement of flexion of the knee; by its contraction the leg is rotated inward, or, if the tibia be fixed, the thigh is rotated outward, and the knee-joint is unlocked.

**Applied Anatomy.**—From a consideration of the construction of the knee-joint, it would at first sight appear to be one of the least secure joints in the body. It is formed between the two longest bones, and therefore the amount of leverage which can be brought to bear upon it is considerable; the articular surfaces are but ill-adapted to each other, and the range of motion which it enjoys is great. All these circumstances tend to render the articulation insecure; nevertheless on account of the powerful ligaments which bind the bones together, the joint is one of the strongest in the body, and dislocation from traumatism is a rare occurrence. When, on the other hand, the ligaments have been softened or destroyed by disease, partial displacement is liable to occur, and is frequently brought about by the action of the muscles.

One or other of the menisci may become displaced and nipped between the femur and tibia. The accident is produced by a twist of the leg when the knee is flexed, and is accompanied by a sudden pain and fixation of the knee in a flexed position. The meniscus may be displaced either medialward or lateralward; that is to say, either toward the tibial intercondyloid eminence, so that the cartilage becomes lodged in the intercondyloid fossa; or to one side, so that the cartilage projects beyond the margin of the two articular surfaces. The medial meniscus is much more commonly affected than the lateral.

Acute synovitis, the result of traumatism, is of frequent occurrence in the knee, on account of

the superficial position of the joint. When the cavity is distended with fluid, the swelling shows itself above and at the sides of the patella, reaching about 2.5 cm., occasionally 5 cm. or more, above the patellar surface of the femur, and extending a little higher under the Vastus medialis than under the Vastus lateralis. The lower level of the synovial membrane is just at the level of the head of the tibia. Chronic synovitis shows itself principally in the form of pulpy degeneration of the synovial membrane, the result of tuberculous infection. Syphilitic disease with gummatous infiltration of the synovial membrane may take place. The knee is one of the joints most commonly affected with osteoarthritis, and is more frequently the seat of this disease in women than in men. The occurrence of the so-called loose cartilages is almost confined to the knee, though they are occasionally met with in other joints. Many of them occur in cases of osteoarthritis, in which calcareous or cartilaginous material is formed in one of the synovial fringes and constitutes the foreign body, and may or may not become detached, only in the former case meriting the usual term, "loose" cartilage. In other cases they have their origin in the exudation of inflammatory lymph, and possibly, in some rare instances, a portion of the articular cartilage or one of the menisci becomes detached and constitutes the foreign body.

In inflammatory affections of the knee-joint, the position of greatest ease, and therefore the one which is always assumed, is that of slight flexion. In this position there is the most complete relaxation of ligamentous structures, and, therefore, the greatest diminution in the tension caused by the effusion. If this flexed position be maintained for any length of time, it becomes permanent from fibrous adhesions taking place, and the utility of the limb is materially impaired. Attention should therefore be paid by the surgeon to the position of the limb; and by carefully applied splints, with the leg in an extended position, this untoward result should be prevented. In cases of septic synovitis, incisions to evacuate the pus should be made vertically on either side of the patella, between it and the condyles of the femur.

Genu valgum, or knock-knee, is a common deformity of childhood. In this condition, as the patient stands, the medial condyles of the two femora are in contact, but the two medial malleoli are more or less widely separated from each other. When, however, the knees are flexed to a right angle, the two legs are practically parallel with each other. At the commencement of the disease there is a yielding of the tibial collateral ligament and other fibrous structures on the medial side of the joint; as a result of this there is a constant undue pressure of the lateral condyle of the tibia against the lateral condyle of the femur. This pressure causes arrest of growth, and, possibly, wasting of the lateral condyle, and a consequent tendency for the tibia to become separated from the medial condyle of the femur. Irregular overgrowth from the medial portion of the epiphysal line takes place, giving rise to apparent enlargement of the medial condyle of the femur, the line of the epiphysis becoming oblique, with a direction downward and medialward, instead of at right angles to the axis of the bone. If the deformity be marked, an osteotomy of the femur is required to correct it.

Excision of the knee-joint is most frequently required for tuberculous disease of this articulation, but is also practised in cases of disorganization of the knee from other causes. It is also occasionally called for in cases of injury, gunshot or otherwise. The operation is best performed by a horseshoe-shaped incision, starting from one femoral condyle, descending as low as the tuberosity of the tibia, and then carried upward to the other femoral condyle. The bone ends having been cleared, and in those cases where the operation is performed for tuberculous disease all pulpy tissue having been carefully removed, the section of the femur is first made. This should never include, in children, more than, at the most, two-thirds of the articular surface, otherwise the epiphysal cartilage will be involved, with disastrous results as regards the growth of the limb. Afterward a thin slice, not more than 1.25 cm., should be removed from the upper end of the tibia. If any diseased tissue still appears to be left in the bones, it should be removed with the gouge, rather than by a further section.

The bursæ about the knee-joint are sometimes the seat of enlargement. The bursa between the front of the patella and the skin is frequently affected in individuals who are in the habit of constantly kneeling, and the condition is then known as "housemaid's knee." The bursa beneath the Semimembranosus tendon also occasionally becomes enlarged, and forms a fluctuating swelling at the back of the knee. During extension, the swelling is firm and tense; but during flexion it becomes soft, and, as the bursa often communicates with the synovial cavity of the joint, the fluid it contains can be made to disappear by pressure when the knee is flexed. Extension of septic processes within the joint is apt to occur along the tendon sheath of the Popliteus, and this may lead to deep-seated suppuration in the popliteal fossa, often associated with septic thrombosis of the popliteal vein; when this occurs amputation of the limb is necessary.

### III. Articulations between the Tibia and Fibula.

The articulations between the tibia and fibula are effected by ligaments which connect the extremities and bodies of the bones. The ligaments may consequently



be subdivided into three sets: (1) those of the Tibiofibular articulation; (2) the interosseous membrane; (3) those of the Tibiofibular syndesmosis.

**Tibiofibular Articulation** (*articulatio tibiofibularis; superior tibiofibular articulation*).—This articulation is an arthrodial joint between the lateral condyle of the tibia and the head of the fibula. The contiguous surfaces of the bones present flat, oval facets covered with cartilage and connected together by an articular capsule and by anterior and posterior ligaments.

**The Articular Capsule** (*capsula articularis; capsular ligament*).—The articular capsule surrounds the articulation, being attached around the margins of the articular facets on the tibia and fibula; it is much thicker in front than behind.

**The Anterior Ligament** (*anterior superior ligament*).—The anterior ligament of the head of the fibula (Fig. 468) consists of two or three broad and flat bands, which pass obliquely upward from the front of the head of the fibula to the front of the lateral condyle of the tibia.

**The Posterior Ligament** (*posterior superior ligament*).—The posterior ligament of the head of the fibula (Fig. 469) is a single thick and broad band, which passes obliquely upward from the back of the head of the fibula to the back of the lateral condyle of the tibia. It is covered by the tendon of the Popliteus.

**Synovial Membrane.**—A synovial membrane lines the capsule; it is continuous with that of the knee-joint in occasional cases when the two joints communicate.

**Interosseous Membrane** (*membrana interossea cruris; middle tibiofibular ligament*).—An interosseous membrane extends between the interosseous crests of the tibia and fibula, and separates the muscles on the front from those on the back of the leg. It consists of a thin, aponeurotic lamina composed of oblique fibres, which for the most part run downward and lateralward; some few fibres, however, pass in the opposite direction. It is broader above than below. Its upper margin does not quite reach the tibiofibular joint, but presents a free concave border, above which is a large, oval aperture for the passage of the anterior tibial vessels to the front of the leg. In its lower part is an opening for the passage of the anterior peroneal vessels. It is continuous below with the interosseous ligament of the tibiofibular syndesmosis, and presents numerous perforations for the passage of small vessels. It is in relation, in *front*, with the Tibialis anterior, Extensor digitorum longus, Extensor hallucis proprius, Peroneus tertius, and the anterior tibial vessels and deep peroneal nerve; *behind*, with the Tibialis posterior and Flexor hallucis longus.

**Tibiofibular Syndesmosis** (*syndesmosis tibiofibularis; inferior tibiofibular articulation*).—This syndesmosis is formed by the rough, convex surface of the medial side of the lower end of the fibula, and a rough concave surface on the lateral side of the tibia. Below, to the extent of about 4 mm. these surfaces are smooth, and covered with cartilage, which is continuous with that of the ankle-joint. The ligaments are: anterior, posterior, inferior transverse, and interosseous.

**The Anterior Ligament** (*ligamentum malleoli lateralis anterior; anterior inferior ligament*).—The anterior ligament of the lateral malleolus (Fig. 476) is a flat, triangular band of fibres, broader below than above, which extends obliquely downward and lateralward between the adjacent margins of the tibia and fibula, on the front aspect of the syndesmosis. It is in relation, in *front*, with the Peroneus tertius, the aponeurosis of the leg, and the integument; *behind*, with the interosseous ligament; and lies in contact with the cartilage covering the talus.

**The Posterior Ligament** (*ligamentum malleoli lateralis posterior; posterior inferior ligament*).—The posterior ligament of the lateral malleolus (Fig. 476), smaller than the preceding, is disposed in a similar manner on the posterior surface of the syndesmosis.

**The Inferior Transverse Ligament.**—The inferior transverse ligament lies in front of the posterior ligament, and is a strong, thick band, of yellowish fibres which passes transversely across the back of the joint, from the lateral malleolus to the posterior border of the articular surface of the tibia, almost as far as its malleolar process. This ligament projects below the margin of the bones, and forms part of the articulating surface for the talus.

**The Interosseous Ligament.**—The interosseous ligament consists of numerous short, strong, fibrous bands, which pass between the contiguous rough surfaces of the tibia and fibula, and constitute the chief bond of union between the bones. It is continuous, above, with the interosseous membrane.

**Synovial Membrane.**—The synovial membrane associated with the small arthrodial part of this joint is continuous with that of the ankle-joint.

#### IV. Talocrural Articulation or Ankle-joint (*Articulatio Talocruralis; Tibiotarsal Articulation*).

The ankle-joint is a ginglymus, or hinge-joint. The structures entering into its formation are the lower end of the tibia and its malleolus, the malleolus of the fibula, and the transverse ligament, which together form a mortise for the reception of the upper convex surface of the talus and its medial and lateral facets. The bones are connected by the following ligaments:

The Articular Capsule.  
The Deltoid.

The Anterior Talofibular.  
The Posterior Talofibular.

The Calcaneofibular.

**The Articular Capsule** (*capsula articularis; capsular ligament*).—The articular capsule surrounds the joints, and is attached, *above*, to the borders of the articular surfaces of the tibia and malleoli; and *below*, to the talus around its upper articular surface.




FIG. 475.—Right talocrural intertarsal and tarsometatarsal articulations. Medial aspect.

The anterior part of the capsule (*anterior ligament*) (Fig. 475) is a broad, thin, membranous layer, attached, *above*, to the anterior margin of the lower end of

the tibia; *below*, to the talus, in front of its superior articular surface. It is in relation, in *front*, with the Extensor tendons of the toes, the tendons of the Tibialis anterior and Peroneus tertius, and the anterior tibial vessels and deep peroneal nerve.

The posterior part of the capsule (*posterior ligament*) is very thin, and consists principally of transverse fibres. It is attached, *above*, to the margin of the articular surface of the tibia, blending with the transverse ligament; *below*, to the talus behind its superior articular facet. Laterally, it is somewhat thickened, and is attached to the hollow on the medial surface of the lateral malleolus.

**The Deltoid Ligament** (*ligamentum deltoideum; internal lateral ligament*) (Fig. 475).—The deltoid ligament is a strong, flat, triangular band, attached, *above*, to the apex and anterior and posterior borders of the medial malleolus. It consists of two sets of fibres, superficial and deep. Of the superficial fibres the most anterior (*tibionavicular*) pass forward to be inserted into the tuberosity of the navicular bone, and immediately behind this they blend with the medial margin of the plantar calcaneonavicular ligament; the middle (*calcaneotibial*) descend almost perpendicularly to be inserted into the whole length of the sustentaculum tali of the calcaneus; the posterior fibres (*posterior talotibial*) pass backward and lateralward to be attached to the inner side of the talus, and to the prominent tubercle on its posterior surface, medial to the groove for the tendon of the Flexor hallucis longus. The deep fibres (*anterior talotibial*) are attached, *above*, to the tip of the medial malleolus, and, *below*, to the medial surface of the talus. The deltoid ligament is covered by the tendons of the Tibialis posterior and Flexor digitorum longus.

The anterior and posterior talofibular and the calcaneofibular ligaments were formerly described as the three fasciculi of the *external lateral ligament* of the ankle-joint.




FIG. 476.—Right talocrural, intertarsal and tarsometatarsal articulations. Lateral aspect.

**The Anterior Talofibular Ligament** (*ligamentum talofibulare anterius*) (Fig. 476).—The anterior talofibular ligament, the shortest of the three, passes from the anterior margin of the fibular malleolus, forward and medially, to the talus, in front of its lateral articular facet.

**The Posterior Talofibular Ligament** (*ligamentum talofibulare posterius*) (Fig. 476).—The posterior talofibular ligament, the strongest and most deeply seated, runs almost horizontally from the depression at the medial and back part of the fibular malleolus to a prominent tubercle on the posterior surface of the talus immediately lateral to the groove for the tendon of the Flexor hallucis longus.

**The Calcaneofibular Ligament** (*ligamentum calcaneofibulare*) (Fig. 476).—The calcaneofibular ligament, the longest of the three, is a narrow, rounded cord, running from the apex of the fibular malleolus downward and slightly backward to a tubercle on the lateral surface of the calcaneus. It is covered by the tendons of the Peronaei longus and brevis.




FIG. 477.—Capsule of left talocrural articulation (distended). Lateral aspect.

**Synovial Membrane** (Fig. 477).—The synovial membrane invests the deep surfaces of the ligaments, and sends a small process upward between the lower ends of the tibia and fibula.

**Relations.**—The tendons, vessels, and nerves in connection with the joint are, in *front*, from the medial side, the Tibialis anterior, Extensor hallucis proprius, anterior tibial vessels, deep peroneal nerve, Extensor digitorum longus, and Peronaeus tertius; *behind*, from the medial side, the Tibialis posterior, Flexor digitorum longus, posterior tibial vessels, tibial nerve, Flexor hallucis longus; and, in the groove behind the fibular malleolus, the tendons of the Peronaei longus and brevis.

The **arteries** supplying the joint are derived from the malleolar branches of the anterior tibial and the peroneal.

The **nerves** are derived from the deep peroneal and tibial.

**Movements.**—When the body is in the erect position, the foot is at right angles to the leg. The movements of the joint are those of dorsiflexion and extension; dorsiflexion consists in the approximation of the dorsum of the foot to the front of the leg, while in extension the heel is drawn up and the toes pointed downward. The malleoli tightly embrace the talus in all positions of the joint, so that any slight degree of side-to-side movement which may exist is simply due to stretching of the ligaments of the talofibular syndesmosis, and slight bending of the body of the fibula. The superior articular surface of the talus is broader in front than behind. In dorsiflexion, therefore, greater space is required between the two malleoli. This is obtained by a slight outward rotatory movement of the lower end of the fibula and a stretching of the ligaments of the syndesmosis; this lateral movement is facilitated by a slight gliding at the tibiofibular articulation, and possibly also by the bending of the body of the fibula. Of the ligaments, the deltoid is of very great power—so much so, that it usually resists a force which fractures the process of bone to which it is attached. Its middle portion, together with the calcaneofibular ligament, binds the bones of the leg firmly to the foot, and resists displacement in every direction. Its anterior and posterior fibres limit extension and flexion of the foot respectively, and the anterior fibres also limit abduction. The posterior talofibular ligament assists the calcaneofibular in

resisting the displacement of the foot backward, and deepens the cavity for the reception of the talus. The anterior talofibular is a security against the displacement of the foot forward, and limits extension of the joint.

The movements of inversion and eversion of the foot, together with the minute changes in form by which it is applied to the ground or takes hold of an object in climbing, etc., are mainly effected in the tarsal joints; the joint which enjoys the greatest amount of motion being that between the talus and calcaneus behind and the navicular and cuboid in front. This is often called the **transverse tarsal joint**, and it can, with the subordinate joints of the tarsus, replace the ankle-joint in a great measure when the latter has become ankylosed.

**Extension** of the foot upon the tibia and fibula is produced by the Gastrocnemius, Soleus, Plantaris, Tibialis posterior, Peronaei longus and brevis, Flexor digitorum longus, and Flexor hallucis longus; **dorsiflexion**, by the Tibialis anterior, Peronaeus tertius, Extensor digitorum longus, and Extensor hallucis proprius.<sup>1</sup>

**Applied Anatomy.**—As the ankle-joint is a very strong and powerful articulation, displacement of the talus from the tibiofibular mortise is a rare accident, and great force is required to produce it. Nevertheless, dislocation does occasionally occur, either antero-posteriorly or to one or other side. In the latter, which is the more common, fracture is a necessary accompaniment of the injury. The dislocation in these cases is somewhat peculiar, and is not a displacement in a horizontal direction, such as usually occurs in dislocations of ginglymoid joints, but the talus undergoes a partial rotation around an antero-posterior axis drawn through its own centre, so that the superior surface, instead of being directed upward, is inclined more or less medialward or lateralward according to the variety of the displacement.

The ankle-joint is more frequently sprained than any joint in the body, and this may lead to acute synovitis. In these cases, when the synovial sac is distended with fluid, the bulging appears principally in the front of the joint, beneath the anterior tendons, and on either side, between the Tibialis anterior and the deltoid ligament on the medial side, and between the Peronaeus tertius and the anterior talofibular ligament laterally. In addition to this, bulging often occurs posteriorly, and a fluctuating swelling may be detected on either side of the tendo calcaneus. A large proportion of so-called "sprains" of the ankle have been proved by x-ray examination to be some variety of fracture about the malleoli, with or without displacement.

Chronic synovitis may result from frequent sprains, and when once this joint has been sprained it is liable to a recurrence of the injury; or the synovitis may be tuberculous in its origin, the disease usually beginning in the talus and extending to the joint, though it may commence in the synovial membrane, the result probably of some slight strain in a tuberculous subject.

Excision of the ankle-joint is not often performed, since the foot after excision is often of very little use; far less useful, in fact, than it is after Syme's amputation, which is, therefore, a preferable operation in these cases. Further, disease of the ankle-joint is frequently associated with disease of the tarsal bones.

## V. Intertarsal Articulations (*Articulationes Intertarseae*; **Articulations of the Tarsus**).

**Talocalcaneal Articulation** (*articulatio talocalcanea*; *articulation of the calcaneus and astragalus*; *calcaneo-astragaloid articulation*).—The articulations between the calcaneus and talus are two in number—anterior and posterior. Of these, the anterior forms part of the talocalcaneonavicular joint, and will be described with that articulation. The posterior or talocalcaneal articulation is formed between the posterior calcaneal facet on the inferior surface of the talus, and the posterior facet on the superior surface of the calcaneus. It is an arthrodial joint, and the two bones are connected by an articular capsule and by anterior, posterior, lateral, medial, and interosseous talocalcaneal ligaments.

**The Articular Capsule** (*capsula articularis*).—The articular capsule envelops the joint, and consists for the most part of short fibres, which are split up into distinct slips; between these there is only a weak fibrous investment.

**The Anterior Talocalcaneal Ligament** (*ligamentum talocalcaneum anterius*; *anterior calcaneo-astragaloid ligament*) (Figs. 477, 480).—The anterior talocalcaneal ligament extends from the front and lateral surface of the neck of the talus to the superior surface of the calcaneus. It forms the posterior boundary of the

<sup>1</sup> The student must bear in mind that the Extensor digitorum longus and Extensor hallucis proprius are *extensors* of the toes, but *flexors* of the ankle; and that the Flexor digitorum longus and Flexor hallucis longus are *flexors* of the toes, but *extensors* of the ankle.



talocalcaneonavicular joint, and is sometimes described as the **anterior interosseous ligament**.

**The Posterior Talocalcaneal Ligament** (*ligamentum talocalcaneum posterius; posterior calcaneo-astragaloid ligament*) (Fig. 475).—The posterior talocalcaneal ligament connects the lateral tubercle of the talus with the upper and medial part of the calcaneus; it is a short band, and its fibres radiate from their narrow attachment to the talus.

**The Lateral Talocalcaneal Ligament** (*ligamentum talocalcaneum laterale; external calcaneo-astragaloid ligament*) (Figs. 477, 480).—The lateral talocalcaneal ligament is a short, strong fasciculus, passing from the lateral surface of the talus, immediately beneath its fibular facet to the lateral surface of the calcaneus. It is placed in front of, but on a deeper plane than, the calcaneofibular ligament, with the fibres of which it is parallel.

**The Medial Talocalcaneal Ligament** (*ligamentum talocalcaneum mediale; internal calcaneo-astragaloid ligament*).—The medial talocalcaneal ligament connects the medial tubercle of the back of the talus with the back of the sustentaculum tali. Its fibres blend with those of the plantar calcaneonavicular ligament.




Fig. 478.—Coronal section through right talocrural and talocalcaneal joints.

**The Interosseous Talocalcaneal Ligament** (*ligamentum talocalcaneum interosseum*) (Figs. 478, 480).—The interosseous talocalcaneal ligament forms the chief bond of union between the bones. It is, in fact, a portion of the united capsules of the talocalcaneonavicular and the talocalcaneal joints, and consists of two partially united layers of fibres, one belonging to the former and the other to the latter joint. It is attached, *above*, to the groove between the articular facets of the under surface of the talus; *below*, to a corresponding depression on the upper surface of the calcaneus. It is very thick and strong, being at least 2.5 cm. in breadth from side to side, and serves to bind the calcaneus and talus firmly together.



**Synovial Membrane** (Fig. 481).—The synovial membrane lines the capsule of the joint, and is distinct from the other synovial membranes of the tarsus.

**Movements.**—The movements permitted between the talus and calcaneus are limited to gliding of the one bone on the other backward and forward and from side to side.

**Talocalcaneonavicular Articulation** (*articulatio talocalcaneonavicularis*).—This articulation is an arthrodial joint: the rounded head of the talus being received into the concavity formed by the posterior surface of the navicular, the anterior articular surface of the calcaneus, and the upper surface of the plantar calcaneonavicular ligament. There are two ligaments in this joint: the articular capsule and the dorsal talonavicular.

**The Articular Capsule** (*capsula articularis*).—The articular capsule is imperfectly developed except posteriorly, where it is considerably thickened and forms, with a part of the capsule of the talocalcaneal joint, the strong interosseous ligament which fills in the canal formed by the opposing grooves on the calcaneus and talus, as above mentioned.

**The Dorsal Talonavicular Ligament** (*ligamentum talonaviculare dorsale; superior astragalonavicular ligament*) (Fig. 475).—This ligament is a broad, thin band, which connects the neck of the talus to the dorsal surface of the navicular bone; it is covered by the Extensor tendons. The plantar calcaneonavicular supplies the place of a plantar ligament for this joint.

**Synovial Membrane.**—The synovial membrane lines all parts of the capsule of the joint.

**Movements.**—This articulation permits of a considerable range of gliding movements; its feeble construction allows occasionally of dislocation of the other bones of the tarsus from the talus.

**Calcaneocuboid Articulation** (*articulatio calcaneocuboidea; articulation of the calcaneus with the cuboid*).—The ligaments connecting the calcaneus with the cuboid are five in number, viz., the articular capsule, the dorsal calcaneocuboid, part of the bifurcated, the long plantar, and the plantar calcaneocuboid.

**The Articular Capsule** (*capsula articularis*).—The articular capsule is an imperfectly developed investment, containing certain strengthened bands, which form the other ligaments of the joint.

**The Dorsal Calcaneocuboid Ligament** (*ligamentum calcaneocuboideum dorsale; superior calcaneocuboid ligament*) (Fig. 476).—The dorsal calcaneocuboid ligament is a thin but broad fasciculus, which passes between the contiguous surfaces of the calcaneus and cuboid, on the dorsal surface of the joint.

**The Bifurcated Ligament** (*ligamentum bifurcatum; internal calcaneocuboid; interosseous ligament*) (Fig. 476, 480).—The bifurcated ligament is a strong band, attached behind to the deep hollow on the upper surface of the calcaneus and dividing in front in a Y-shaped manner into a calcaneocuboid and a calcaneonavicular part. The calcaneocuboid part is fixed to the medial side of the cuboid and forms one of the principal bonds between the first and second rows of the tarsal bones. The calcaneonavicular part is attached to the lateral side of the navicular.

**The Long Plantar Ligament** (*ligamentum plantare longum; long calcaneocuboid ligament; superficial long plantar ligament*) (Fig. 479).—The long plantar ligament is the longest of all the ligaments of the tarsus: it is attached behind to the plantar surface of the calcaneus in front of the tuberosity, and in front to the tuberosity on the plantar surface of the cuboid bone, the more superficial fibres being continued forward to the bases of the second, third, and fourth metatarsal bones. This ligament converts the groove on the plantar surface of the cuboid into a canal for the tendon of the Peroneus longus.

**The Plantar Calcaneocuboid Ligament** (*ligamentum calcaneocuboideum plantare; short calcaneocuboid ligament; short plantar ligament*) (Fig. 479).—The plantar calcaneocuboid ligament lies nearer to the bones than the preceding, from which it is separated by a little areolar tissue. It is a short but wide band of great strength, and extends from the tubercle and the depression in front of it, on the forepart

of the plantar surface of the calcaneus, to the plantar surface of the cuboid behind the peroneal groove.

**Synovial Membrane.**—The synovial membrane lines the inner surface of the capsule and is distinct from that of the other tarsal articulations (Fig. 481).

**Movements.**—The movements permitted between the calcaneus and cuboid are limited to slight gliding movements of the bones upon each other.

The *transverse tarsal joint* is formed by the articulation of the calcaneus with the cuboid, and the articulation of the talus with the navicular. The movement which takes place in this joint is more extensive than that in the other tarsal joints, and consists of a sort of rotation by means of which the foot may be slightly flexed or extended, the sole being at the same time carried medially (inverted) or laterally (everted).

**The Ligaments Connecting the Calcaneus and Navicular.**—Though the calcaneus and navicular do not directly articulate, they are connected by two ligaments: the calcaneonavicular part of the bifurcated, and the plantar calcaneonavicular.

The calcaneonavicular part of the bifurcated ligament is described on page 454.

**The Plantar Calcaneonavicular Ligament** (*ligamentum calcaneonaviculare plantare; inferior or internal calcaneonavicular ligament; calcaneonavicular ligament*) (Fig. 480).—The plantar calcaneonavicular ligament is a broad and thick band of fibres, which connects the anterior margin of the sustentaculum tali of the calca-



FIG. 479.—Ligaments of plantar surface of the right foot.




FIG. 480.—Talocalcaneal and talocalcaneonavicular articulations exposed from above by removing the talus.

neus to the plantar surface of the navicular. This ligament not only serves to connect the calcaneus and navicular, but supports the head of the talus, forming part of the articular cavity in which it is received. The **dorsal surface** of the ligament presents a fibrocartilaginous facet, lined by the synovial membrane, and upon this a portion of the head of the talus rests. Its **plantar surface** is supported by the tendon of the Tibialis posterior; its **medial border** is blended with the forepart of the deltoid ligament of the ankle-joint.

**Applied Anatomy.**—The plantar calcaneonavicular ligament, by supporting the head of the talus, is principally concerned in maintaining the arch of the foot. When it yields, the head of the talus is pressed downward, medialward, and forward by the weight of the body, and the foot becomes flattened, expanded, and turned lateralward, and exhibits the condition known as *flat-foot*. This ligament contains a considerable amount of elastic fibres, so as to give elasticity to the arch and spring to the foot; hence it is sometimes called the “spring” ligament. It is supported, on its plantar surface, by the tendon of the Tibialis posterior, which spreads out at its insertion into a number of fasciculi, to be attached to most of the tarsal and metatarsal bones. This prevents undue stretching of the ligament, and is a protection against the occurrence of flat-foot; hence muscular weakness is, in most cases, the primary cause of the deformity.

**Cuneonavicular Articulation** (*articulatio cuneonavicularis; articulation of the navicular with the cuneiform bones*).—The navicular is connected to the three cuneiform bones by dorsal and plantar ligaments.

**The Dorsal Ligaments** (*ligamenta navicularicuneiformia dorsalia*).—The dorsal ligaments are three small bundles, one attached to each of the cuneiform bones. The bundle connecting the navicular with the first cuneiform is continuous around the medial side of the articulation with the plantar ligament which unites these two bones.

**The Plantar Ligaments** (*ligamenta navicularicuneiformia plantaria*).—The plantar ligaments have a similar arrangement to the dorsal, and are strengthened by slips from the tendon of the Tibialis posterior.




FIG. 481.—Oblique section of left intertarsal and tarsometatarsal articulations, showing the synovial cavities

**Synovial Membrane.**—The synovial membrane of these joints is part of the great tarsal synovial membrane (Fig. 481).

**Movements.**—Mere gliding movements are permitted between the navicular and cuneiform bones.

**Cuboideonavicular Articulation.**—The navicular bone is connected with the cuboid by dorsal, plantar, and interosseous ligaments.

**The Dorsal Ligament** (*ligamentum cuboideonaviculare dorsale*).—The dorsal ligament extends obliquely forward and lateralward from the navicular to the cuboid bone.

**The Plantar Ligament** (*ligamentum cuboideonaviculare plantare*).—The plantar ligament passes nearly transversely between these two bones.

**The Interosseous Ligament.**—The interosseous ligament consists of strong transverse fibres, and connects the rough non-articular portions of the adjacent surfaces of the two bones.

**Synovial Membrane.**—The synovial membrane of this joint is part of the great tarsal synovial membrane (Fig. 481).

**Movements.**—The movements permitted between the navicular and cuboid bones are limited to a slight gliding upon each other.

**Intercuneiform and Cuneocuboid Articulations.**—The three cuneiform bones and the cuboid are connected together by dorsal, plantar, and interosseous ligaments.

**The Dorsal Ligaments** (*ligamenta intercuneiformia dorsalia*).—The dorsal ligaments consist of three transverse bands: one connects the first with the second cuneiform, another the second with the third cuneiform, and another the third cuneiform with the cuboid.

**The Plantar Ligaments** (*ligamenta intercuneiformia plantaria*).—The plantar ligaments have a similar arrangement to the dorsal, and are strengthened by slips from the tendon of the *Tibialis posterior*.

**The Interosseous Ligaments** (*ligamenta intercuneiformia interossea*).—The interosseous ligaments consist of strong transverse fibres which pass between the rough non-articular portions of the adjacent surfaces of the bones.

**Synovial Membrane.**—The synovial membrane of these joints is part of the great tarsal synovial membrane (Fig. 481).

**Movements.**—The movements permitted between these bones are limited to a slight gliding upon each other.

**Applied Anatomy.**—In spite of the great strength of the ligaments which connect the tarsal bones together, dislocation at some of the tarsal joints does occasionally occur. When this takes place, it is most commonly in connection with the talus; for not only may this bone be dislocated from the tibia and fibula at the ankle-joint, but the other bones may be dislocated from it, the bone remaining *in situ* in the tibiofibular mortise. This constitutes what is known as the *subtalar* dislocation. Or, again, the talus may be dislocated from all its connections—from the tibia and fibula above, the calcaneus below, and the navicular in front—and may even undergo a rotation, on either a vertical or a horizontal axis. In the former case the long axis of the bone is directed across the joint, so that the head faces the articular surface on one or other malleolus; in the latter, the collateral surfaces are directed upward and downward, so that the superior surface faces to one or the other side. Reduction in these cases is often very difficult or impossible, and the displaced talus may require removal by open operation. Dislocation may also occur at the transverse tarsal joint, the anterior tarsal bones being luxated from the talus and calcaneus. The other tarsal bones are occasionally, though rarely, dislocated from their connections.

## VI. Tarsometatarsal Articulations (*Articulationes Tarsometatarsae*).

These are arthrodial joints. The bones entering into their formation are the first, second, and third cuneiforms, and the cuboid, which articulate with the bases of the metatarsal bones. The first metatarsal bone articulates with the first cuneiform; the second is deeply wedged in between the first and third cuneiforms articulating by its base with the second cuneiform; the third articulates with the third cuneiform; the fourth, with the cuboid and third cuneiform; and the fifth, with the cuboid. The bones are connected by dorsal, plantar, and interosseous ligaments.

**The Dorsal Ligaments** (*ligamenta tarsometatarsae dorsalia*).—The dorsal ligaments are strong, flat bands. The first metatarsal is joined to the first cuneiform by a broad, thin band; the second has three, one from each cuneiform bone; the third

has one from the third cuneiform; the fourth has one from the third cuneiform and one from the cuboid; and the fifth, one from the cuboid.

**The Plantar Ligaments** (*ligamenta tarsometatarsea plantaria*).—The plantar ligaments consist of longitudinal and oblique bands, disposed with less regularity than the dorsal ligaments. Those for the first and second metatarsals are the strongest; the second and third metatarsals are joined by oblique bands to the first cuneiform; the fourth and fifth metatarsals are connected by a few fibres to the cuboid.

**The Interosseous Ligaments** (*ligamenta cuneometatarsea interossia*).—The interosseous ligaments are three in number. The first is the strongest, and passes from the lateral surface of the first cuneiform to the adjacent angle of the second metatarsal. The second connects the third cuneiform with the adjacent angle of the second metatarsal. The third connects the lateral angle of the third cuneiform with the adjacent side of the base of the third metatarsal.

**Synovial Membrane** (Fig. 481).—The synovial membrane between the first cuneiform and the first metatarsal forms a distinct sac. The synovial membrane between the second and third cuneiforms behind, and the second and third metatarsal bones in front, is part of the great tarsal synovial membrane. Two prolongations are sent forward from it, one between the adjacent sides of the second and third, and another between those of the third and fourth metatarsal bones. The synovial membrane between the cuboid and the fourth and fifth metatarsal bones forms a distinct sac. From it a prolongation is sent forward between the fourth and fifth metatarsal bones.

**Movements**.—The movements permitted between the tarsal and metatarsal bones are limited to slight gliding of the bones upon each other.

**Nerve Supply**.—The intertarsal and tarsometatarsal joints are supplied by the deep peroneal nerve.

## VII. Intermetatarsal Articulations (*Articulationes Intermetatarsee*).

The base of the first metatarsal is not connected with that of the second by any ligaments; in this respect the great toe resembles the thumb.

The bases of the other four metatarsals are connected by the dorsal, plantar, and interosseous ligaments.

**The Dorsal Ligaments** (*ligamenta basium [oss. metatars.] dorsalia*) pass transversely between the dorsal surfaces of the bases of the adjacent metatarsal bones.

**The Plantar Ligaments** (*ligamenta basium [oss. metatars.] plantaria*).—The plantar ligaments have a similar arrangement to the dorsal.

**The Interosseous Ligaments** (*ligamenta basium [oss. metatars.] interossea*).—The interosseous ligaments consist of strong transverse fibres which connect the rough non-articular portions of the adjacent surfaces.

**Synovial Membranes** (Fig. 481).—The synovial membranes between the second and third, and the third and fourth metatarsal bones are part of the great tarsal synovial membrane; that between the fourth and fifth is a prolongation of the synovial membrane of the cuboideometatarsal joint.

**Movements**.—The movement permitted between the tarsal ends of the metatarsal bones is limited to a slight gliding of the articular surfaces upon one another.

The heads of all the metatarsal bones are connected together by the transverse metatarsal ligament.

**The Transverse Metatarsal Ligament**.—The transverse metatarsal ligament is a narrow band which runs across and connects together the heads of all the metatarsal bones; it is blended anteriorly with the plantar (glenoid) ligaments of the metatarsophalangeal articulations. Its plantar surface is concave where the Flexor tendons run below it; above it the tendons of the Interossei pass to their insertions. It differs from the transverse metacarpal ligament in that it connects the metatarsal to the others.

**The Synovial Membranes in the Tarsal and Tarsometatarsal Joints** (Fig. 481).—The synovial membranes found in the articulations of the tarsus and metatarsus are six in number: one for

the talocalcaneal articulation; a second for the talocalcaneonavicular articulation; a third for the calcaneocuboid articulation; and a fourth for the cuneonavicular, intercuneiform, and cuneocuboid articulations, the articulations of the second and third cuneiforms with the bases of the second and third metatarsal bones, and the adjacent surfaces of the bases of the second, third, and fourth metatarsal bones; a fifth for the first cuneiform with the metatarsal bone of the great toe; and a sixth for the articulation of the cuboid with the fourth and fifth metatarsal bones. A small synovial cavity is sometimes found between the contiguous surfaces of the navicular and cuboid bones.

### VIII. Metatarsophalangeal Articulations (*Articulationes Metatarsophalangeae*).

The metatarsophalangeal articulations are of the condyloid kind, formed by the reception of the rounded heads of the metatarsal bones in shallow cavities on the ends of the first phalanges.

The ligaments are the plantar and two collateral.

**The Plantar Ligaments** (*ligamenta accessoria plantaria; glenoid ligaments of Cruveilhier*).—The plantar ligaments are thick, dense, fibrous structures. They are placed on the plantar surfaces of the joints in the intervals between the collateral ligaments, to which they are connected; they are loosely united to the metatarsal bones, but very firmly to the bases of the first phalanges. Their plantar surfaces are intimately blended with the transverse metatarsal ligament, and grooved for the passage of the Flexor tendons, the sheaths surrounding which are connected to the sides of the grooves. Their deep surfaces form part of the articular facets for the heads of the metatarsal bones, and are lined by synovial membrane.

**The Collateral Ligaments** (*ligamenta collateralia; lateral ligaments*).—The collateral ligaments are strong, rounded cords, placed one on either side of each joint, and attached, by one end, to the posterior tubercle on the side of the head of the metatarsal bone, and, by the other, to the contiguous extremity of the phalanx.

The place of **dorsal ligaments** is supplied by the Extensor tendons on the dorsal surfaces of the joints.

**Movements**.—The movements permitted in the metatarsophalangeal articulations are flexion, extension, abduction, and adduction.

### IX. Articulations of the Digits (*Articulationes Digitorum Pedis; Articulations of the Phalanges*).

The interphalangeal articulations are ginglymoid joints, and each has a plantar and two collateral ligaments.

The arrangement of these ligaments is similar to that in the metatarsophalangeal articulations: the Extensor tendons supply the places of dorsal ligaments.

**Movements**.—The only movements permitted in the joints of the digits are flexion and extension; these movements are more extensive between the first and second phalanges than between the second and third. The amount of flexion is very considerable, but extension is limited by the plantar and collateral ligaments.

**Applied Anatomy**.—Gout peculiarly affects the metatarsophalangeal joint of the big toe, beginning with the deposit of sodium and calcium urates in the articular cartilages, and slow necrosis of the surrounding tissue. Later the circumarticular fibrous tissue becomes the seat of these gouty deposits, and considerable thickening and deformity may result. The other chief joint affections, such as rheumatism, gonorrhoeal arthritis, tuberculosis, or syphilis, seldom attack the big toe-joint; but septic arthritis associated with perforating ulcer of the foot is not uncommon.

### Arches of the Foot.

In order to allow it to support the weight of the body in the erect posture with the least expenditure of material, the foot is constructed of a series of arches formed by the tarsal and metatarsal bones, and strengthened by the ligaments and tendons of the foot.



The main arches are the **antero-posterior arches**, which may, for descriptive purposes, be regarded as divisible into two types—a medial and a lateral. The **medial arch** (see Fig. 417, page 376) is made up by the calcaneus, the talus, the navicular, the three cuneiforms, and the first, second, and third metatarsals. Its summit is at the superior articular surface of the talus, and its two extremities or piers, on which it rests in standing, are the tuberosity on the plantar surface of the calcaneus posteriorly and the heads of the first, second, and third metatarsal bones anteriorly. The chief characteristic of this arch is its elasticity, due to its height and to the number of small joints between its component parts. Its weakest part, *i. e.*, the part most liable to yield from overpressure, is the joint between the talus and navicular, but this portion is braced by the plantar calcaneonavicular ligament, which is elastic and is thus able to quickly restore the arch to its pristine condition when the disturbing force is removed. The ligament is strengthened medially by blending with the deltoid ligament of the ankle-joint, and is supported inferiorly by the tendon of the Tibialis posterior, which is spread out in a fan-shaped insertion and prevents undue tension of the ligament or such an amount of stretching as would permanently elongate it. The arch is further supported by the plantar aponeurosis, by the small muscles in the sole of the foot, by the tendons of the Tibialis anterior and posterior and Peroneus longus, and by the ligaments of all the articulations involved. The **lateral arch** (see Fig. 418, page 376) is composed of the calcaneus, the cuboid, and the fourth and fifth metatarsals. Its summit is at the talocalcaneal articulation, and its chief joint is the calcaneocuboid, which possesses a special mechanism for locking, and allows only a limited movement. The most marked features of this arch are its solidity and its slight elevation; two strong ligaments, the long plantar and the plantar calcaneocuboid, together with the Extensor tendons and the short muscles of the little toe, preserve its integrity.

While these medial and lateral arches may be readily demonstrated as the component antero-posterior arches of the foot, yet the **fundamental longitudinal arch** is contributed to by both, and consists of the calcaneus, cuboid, third cuneiform, and third metatarsal: all the other bones of the foot may be removed without destroying this arch.

In addition to the longitudinal arches the foot presents a series of **transverse arches**. At the posterior part of the metatarsus and the anterior part of the tarsus the arches are complete, but in the middle of the tarsus they present more the characters of half-domes the concavities of which are directed downward and medialward, so that when the medial borders of the feet are placed in apposition a complete tarsal dome is formed. The transverse arches are strengthened by the interosseous, plantar, and dorsal ligaments, by the short muscles of the first and fifth toes (especially the transverse head of the Adductor hallucis), and by the Peroneus longus, whose tendon stretches across between the piers of the arches.

# MYOLOGY.<sup>1</sup>

THE Muscles are connected with the bones, cartilages, ligaments, and skin, either directly, or through the intervention of fibrous structures called tendons or aponeuroses. Where a muscle is attached to bone or cartilage, the fibres end in blunt extremities upon the periosteum or perichondrium, and do not come into direct relation with the osseous or cartilaginous tissue. Where muscles are connected with its skin, they lie as a flattened layer beneath it, and are connected with its areolar tissue by larger or smaller bundles of fibres, as in the muscles of the face.

The muscles vary extremely in their form. In the limbs, they are of considerable length, especially the more superficial ones; they surround the bones, and constitute an important protection to the various joints. In the trunk, they are broad, flattened, and expanded, and assist in forming the walls of the trunk cavities. Hence the reason of the terms, *long*, *broad*, *short*, etc., used in the description of a muscle.

There is considerable variation in the arrangement of the fibres of certain muscles with reference to the tendons to which they are attached. In some muscles the fibres are parallel and run directly from their origin to their insertion; these are quadrilateral muscles, such as the Thyreo-hyoideus. A modification of these is found in the fusiform muscles, in which the fibres are not quite parallel, but slightly curved, so that the muscle tapers at either end; in their actions, however, they resemble the quadrilateral muscles. Secondly, in other muscles the fibres are convergent; arising by a broad origin, they converge to a narrow or pointed insertion. This arrangement of fibres is found in the triangular muscles—*e. g.*, the Temporalis. In some muscles, which otherwise would belong to the quadrilateral or triangular type, the origin and insertion are not in the same plane, but the plane of the line of origin intersects that of the line of insertion; such is the case in the Pectineus. Thirdly, in some muscles (*e. g.*, the Peronei) the fibres are oblique and converge, like the plumes of a quill pen, to one side of a tendon which runs the entire length of the muscle; such muscles are termed *unipennate*. A modification of this condition is found where oblique fibres converge to both sides of a central tendon; these are called *bipennate*, and an example is afforded in the Rectus femoris. Finally, there are muscles in which the fibres are arranged in curved bundles in one or more planes, as in the Sphincters. The arrangement of the fibres is of considerable importance in respect to the relative strength and range of movement of the muscle. Those muscles where the fibres are long and few in number have great range, but diminished strength; where, on the other hand, the fibres are short and more numerous, there is great power, but lessened range.

The names applied to the various muscles have been derived: (1) from their situation, as the Tibialis, Radialis, Ulnaris, Peronaeus; (2) from their direction, as the Rectus abdominis, Obliqui capitis, Transversus abdominis; (3) from their uses, as Flexors, Extensors, Abductors, etc.; (4) from their shape, as the Deltoideus,

<sup>1</sup> The muscles and fasciae are described conjointly, in order that the student may consider the arrangement of the latter in his dissection of the former. It is rare for the student of anatomy in this country to have the opportunity of dissecting the fasciae separately; and it is for this reason, as well as from the close connection that exists between the muscles and their investing sheaths, that they are considered together. Some general observations are first made on the anatomy of the muscles and fasciae, the special descriptions being given in connection with the different regions.

Rhomboideus; (5) from the number of their divisions, as the Biceps and Triceps; (6) from their points of attachment, as the Sternocleidomastoideus, Sternohyoideus, Sternothyroideus.

In the description of a muscle, the term *origin* is meant to imply its more fixed or central attachment; and the term *insertion* the movable point on which the force of the muscle is applied; but the origin is absolutely fixed in only a small number of muscles, such as those of the face which are attached by one extremity to immovable bones, and by the other to the movable integument; in the greater number, the muscle can be made to act from either extremity.

In the dissection of the muscles, attention should be directed to the exact *origin*, *insertion*, and *actions* of each, and to its more important *relations* with surrounding parts. While accurate knowledge of the points of attachment of the muscles is of great importance in the determination of their actions, it is not to be regarded as conclusive. The action of the muscle deduced from its attachments, or even by pulling on it in the dead subject, is not necessarily its action in the living. By pulling, for example, on the Brachioradialis in the cadaver the hand may be slightly supinated when in the prone position and slightly pronated when in the supine position, but there is no evidence that these actions are performed by the muscle during life. It is impossible for an individual to throw into action any one muscle; in other words, movements, not muscles, are represented in the central nervous system. To carry out a movement a definite combination of muscles is called into play, and the individual has no power either to leave out a muscle from this combination or to add one to it. One (or more) muscle of the combination is the chief moving force; when this muscle passes over more than one joint other muscles (*synergic muscles*) come into play to inhibit the movements not required; a third set of muscles (*fixation muscles*) fix the limb—*i. e.*, in the case of the limb-movements—and also prevent disturbances of the equilibrium of the body generally. As an example, the movement of the closing of the fist may be considered: (1) the prime movers are the Flexores digitorum, Flexor pollicis longus, and the small muscles of the thumb; (2) the synergic muscles are the Extensores carpi, which prevent flexion of the wrist; while (3) the fixation muscles are the Biceps and Triceps brachii, which steady the elbow and shoulder. A further point which must be borne in mind in considering the actions of muscles is that in certain positions a movement can be effected by gravity, and in such a case the muscles acting are the antagonists of those which might be supposed to be in action. Thus in flexing the trunk when no resistance is interposed the Sacrospinales contract to regulate the action of gravity, and the Recti abdominis are relaxed.<sup>1</sup>

By a consideration of the action of the muscles, the surgeon is able to explain the causes of displacement in various forms of fracture, and the causes which produce distortion in various deformities, and, consequently, to adopt appropriate treatment in each case. The relations, also, of some of the muscles, especially those in immediate apposition with the larger bloodvessels, and the surface markings they produce, should be remembered, as they form useful guides in the application of ligatures to those vessels.

The minute anatomy of muscular tissue is described on pages 64 to 69.

**Applied Anatomy.**—Degeneration of muscular tissue is important clinically, and is met with in two main conditions. In one, the degeneration is myopathic, or primary in the muscles themselves; in the other it is neuropathic, or secondary to some lesion of the nervous system—a hemorrhage into the brain, for example, or injury or inflammation of some part of the medulla spinalis or peripheral nerves. In either case more or less paralysis and atrophy of the affected muscles result. When the degeneration begins primarily in the muscles, however, it often happens that though the muscle fibres waste away, their place is taken by fibrous and fatty tissue to such an extent that the affected muscles increase in volume, and actually appear to hypertrophy.

<sup>1</sup> Consult in this connection the Croonian Lectures (1933) on "Muscular Movements and Their Representation in the Central Nervous System," by Charles E. Beevor, M.D.

Ossification of muscular tissue as a result of repeated strain or injury is not infrequent. It is oftenest found about the tendon of the Adductor longus and Vastus medialis in horsemen, or in the Pectoralis major and Deltoideus of soldiers. It may take the form of exostoses firmly fixed to the bone—*e. g.*, "rider's bone" on the femur—or of layers or spicules of bone lying in the muscles or their fasciæ and tendons. Busse states that these bony deposits are preceded by a hemorrhagic myositis due to injury, the effused blood organizing and being finally converted into bone. In the rarer disease, progressive myositis ossificans, there is an unexplained tendency for practically any of the voluntary muscles to become converted into solid and brittle bony masses which are completely rigid.

### TENDONS, APONEUROSES, AND FASCIÆ.

**Tendons** are white, glistening, fibrous cords, varying in length and thickness, sometimes round, sometimes flattened, and devoid of elasticity. They consist almost entirely of white fibrous tissue, the fibrils of which have an undulating course parallel with each other and are firmly united together. They are very sparingly supplied with bloodvessels, the smaller tendons presenting in their interior no trace of them. Nerves supplying tendons have special modifications of their terminal fibres, named organs of Golgi.

**Aponeuroses** are flattened or ribbon-shaped tendons, of a pearly white color, iridescent, glistening, and similar in structure to the tendons. They are only sparingly supplied with bloodvessels.

The tendons and aponeuroses are connected, on the one hand, with the muscles, and, on the other hand, with the movable structures, as the bones, cartilages ligaments, and fibrous membranes (for instance, the sclera). Where the muscular fibres are in a direct line with those of the tendon or aponeurosis, the two are directly continuous. But where the muscular fibres join the tendon or aponeurosis at an oblique angle, they end, according to Kölliker, in rounded extremities which are received into corresponding depressions on the surface of the latter, the connective tissue between the muscular fibres being continuous with that of the tendon. The latter mode of attachment occurs in all the penniform and bipenniform muscles, and in those muscles the tendons of which commence in a membranous form, as the Gastrocnemius and Soleus.

The **fasciæ** are fibroareolar or aponeurotic laminæ, of variable thickness and strength, found in all regions of the body, investing the softer and more delicate organs. During the process of development many of the cells of the mesoderm are differentiated into bones, muscles, vessels, etc.; the cells of the mesoderm which are not so utilized form an investment for these structures and are differentiated into the true skin and the fasciæ of the body. They have been subdivided, from the situations in which they occur, into superficial and deep.

The **superficial fascia** is found immediately beneath the integument over almost the entire surface of the body. It connects the skin with the deep fascia, and consists of fibroareolar tissue, containing in its meshes pellicles of fat in varying quantity. It varies in thickness in different parts of the body; in the groin it is so thick that it may be subdivided into several laminæ. Beneath the fatty layer there is generally another layer of superficial fascia, comparatively devoid of adipose tissue, in which the trunks of the subcutaneous vessels and nerves are found, as the superficial epigastric vessels in the abdominal region, the superficial veins in the forearm, the saphenous veins in the leg and thigh, and the superficial lymph glands. Certain cutaneous muscles also are situated in the superficial fascia, as the Platysma in the neck, and the Orbicularis oculi around the eyelids. This fascia is most distinct at the lower part of the abdomen, perineum, and extremities; it is very thin in those regions where muscular fibres are inserted into the integument, as on the side of the neck, the face, and around the margin of the anus. It is very dense in the scalp, in the palms of the hands, and soles of the feet, forming a fibro-fatty layer, which binds the integument firmly to the underlying structures.

The superficial fascia connects the skin to the subjacent parts, facilitates the movement of the skin, serves as a soft nidus for the passage of vessels and nerves to the integument, and retains the warmth of the body, since the fat contained in its areolæ is a bad conductor of heat.

The **deep fascia** is a dense, inelastic, fibrous membrane, forming sheaths for the muscles, and in some cases affording them broad surfaces for attachment. It consists of shining tendinous fibres, placed parallel with one another, and connected together by other fibres disposed in a rectilinear manner. It forms a strong investment which not only binds down collectively the muscles in each region, but gives a separate sheath to each, as well as to the vessels and nerves. The fasciæ are thick in unprotected situations, as on the lateral side of a limb, and thinner on the medial side. The deep fasciæ assist the muscles in their actions, by the degree of tension and pressure they make upon their surfaces; and, in certain situations, where they are strengthened by the presence in them of degenerated muscular fibres which have become converted into fibrous sheets, the degree of tension and pressure is regulated by the associated muscles, as, for instance, by the *Tensor fasciæ latae* and *Glutæus maximus* in the thigh, by the *Biceps* in the upper and lower extremities, and *Palmaris longus* in the hand. In the limbs, the fasciæ not only invest the entire limb, but give off septa which separate the various muscles, and are attached to the periosteum: these prolongations of fasciæ are usually spoken of as intermuscular septa.

The Fasciæ and Muscles may be arranged, according to the general division of the body, into those of the **head and neck**; of the **trunk**; of the **upper extremity**; and of the **lower extremity**.

## THE FASCIÆ AND MUSCLES OF THE HEAD.

### I. THE MUSCLE OF THE SCALP.

#### *Epicraniius.*

**Dissection** (Fig. 482).—The head being shaved, and a block placed beneath the back of the neck, make a vertical incision through the skin, commencing at the root of the nose in front,




FIG. 482.—Dissection of the head, face, and neck.

and terminating behind at the occipital protuberance; make a second incision in a horizontal direction along the forehead and around the side of the head, from the anterior to the posterior

extremity of the preceding. Raise the skin in front, from the subjacent muscle, from below upward; this must be done with extreme care, removing the integument from the outer surface of the vessels and the nerves which lie immediately beneath the skin.

**The Skin of the Scalp.**—This is thicker than in any other part of the body. It is intimately adherent to the superficial fascia, which attaches it firmly to the underlying aponeurosis and muscle. Movements of the muscle move the skin. The hair follicles are very closely set together, and extend throughout the whole thickness of the skin. It also contains a number of sebaceous glands.




FIG. 483.—Muscles of the head, face, and neck.

The **superficial fascia** in the cranial region is a firm, dense, fibro-fatty layer, intimately adherent to the integument, and to the Epicranii and its tendinous aponeurosis; it is continuous, behind, with the superficial fascia at the back of the neck; and, laterally, is continued over the temporal fascia. It contains between its layers the superficial vessels and nerves and much granular fat.

The **Epicranii** (*Occipitofrontalis*) (Fig. 483) is a broad, musculofibrous layer, which covers the whole of one side of the vertex of the skull, from the occipital



bone to the eyebrow. It consists of two parts, the Occipitalis and the Frontalis, connected by an intervening tendinous aponeurosis, the *galea aponeurotica*.

The **Occipitalis**, thin and quadrilateral in form, *arises* by tendinous fibres from the lateral two-thirds of the superior nuchal line of the occipital bone, and from the mastoid part of the temporal. It ends in the *galea aponeurotica*.

The **Frontalis** is thin, of a quadrilateral form, and intimately adherent to the superficial fascia. It is broader than the Occipitalis and its fibres are longer and paler in color. It has no bony attachments. Its medial fibres are continuous with those of the Procerus; its immediate fibres blend with the Corrugator and Orbicularis oculi; and its lateral fibres are also blended with the latter muscle over the zygomatic process of the frontal bone. From these attachments the fibres are directed upward, and join the *galea aponeurotica* below the coronal suture. The medial margins of the Frontales are joined together for some distance above the root of the nose; but between the Occipitales there is a considerable, though variable, interval, occupied by the *galea aponeurotica*.

The *galea aponeurotica* (*epicranial aponeurosis*) covers the upper part of the cranium; behind, it is attached, in the interval between the Occipitales, to the external occipital protuberance and highest nuchal lines of the occipital bone; in front, it forms a short and narrow prolongation between the Frontales. On either side it gives origin to the Auriculares anterior and superior; in this situation it loses its aponeurotic character, and is continued over the temporal fascia to the zygomatic arch as a layer of laminated areolar tissue. It is closely connected to the integument by the firm, dense, fibro-fatty layer which forms the superficial fascia of the scalp: it is attached to the pericranium by loose cellular tissue, which allows the aponeurosis, carrying with it the integument to move through a considerable distance.

**Nerves.**—The Frontalis is supplied by the temporal branches of the facial nerve, and the Occipitalis by the posterior auricular branch of the same nerve.

**Actions.**—The Frontales raise the eyebrows and the skin over the root of the nose, and at the same time draw the scalp forward, throwing the integument of the forehead into transverse wrinkles. The Occipitales draw the scalp backward. By bringing alternately into action the Frontales and Occipitales the entire scalp may be moved forward and backward. In the ordinary action of the muscles, the eyebrows are elevated, and at the same time the aponeurosis is fixed by the Occipitales, thus giving to the face the expression of surprise; if the action be exaggerated, the eyebrows are still further raised, and the skin of the forehead thrown into transverse wrinkles, as in the expression of fright or horror.

A thin muscular slip, the **Transversus nuchae**, is present in a considerable proportion (25 per cent.) of cases; it *arises* from the external occipital protuberance or from the superior nuchal line, either superficial or deep to the Trapezius; it is frequently *inserted* with the Auricularis posterior, but may join the posterior edge of the Sternocleidomastoideus.

**Applied Anatomy.**—From an anatomical point of view, the scalp consists of five layers, viz., the skin, subcutaneous tissue, Epicranium and its aponeurosis, subaponeurotic connective tissue, and pericranium. But from a surgical standpoint it is better to regard the first three of these structures as a single layer, since they are all intimately fused together, and when torn off in an accident, or turned down as a flap in a surgical operation, remain firmly connected to each other. In consequence of the dense character of the subcutaneous tissue, the amount of swelling which occurs as the result of inflammation is slight; and the edges of a wound which does not involve the Epicranium or its aponeurosis do not gape. The bloodvessels, also, which lie in this tissue, when wounded, do not contract and retract freely; and therefore the hemorrhage from scalp wounds is often very considerable, but can always be arrested by pressure—a matter of great importance, as it is often very difficult or impossible to pick up with forceps a wounded vessel in the scalp.

The subaponeurotic connective tissue is, from a surgical point of view, of considerable importance. It is loose and lax, and is easily torn through; and hence, when the scalp is wounded, this is the tissue which is torn when the flap is separated from the parts beneath. The vessels are contained in the flap, and there is little risk of sloughing, unless the vitality of the part has been

actually destroyed by the injury. In consequence of the loose nature of the subaponeurotic tissue, any septic inflammation is apt to assume a very diffuse form and spread over the skull, and, unless relieved by timely incisions, may lead to serious complications. Owing to the attachments of the aponeurosis to the zygomatic arch and highest nuchal line, subaponeurotic effusions sag down in these situations, but do not extend beyond to the infratemporal fossa or into the neck; anteriorly, however, where there is no definite attachment to bone, the effusion will pass down over the nose, and into the eyelids. When making incisions into the scalp, care should be taken to avoid the course of the main arteries.

The skin of the scalp is abundantly supplied with sebaceous and sudoriparous glands. The former are sometimes the seat of cystic enlargement, constituting the so-called *sebaceous cysts* or *wens*.

## II. THE MUSCLES OF THE EYELIDS.

The muscles of the eyelids are:

Levator palpebrae superioris. Orbicularis oculi. Corrugator.

**Dissection** (Fig. 482).—In order to expose the muscles of the face, continue the longitudinal incision made in the dissection of the Epicranium down the median line of the face to the tip of the nose, and from this point onward to the upper lip; and carry another incision along the margin of the lip to the angle of the mouth, and transversely across the face to the angle of the mandible. Then make an incision in front of the external ear, from the angle of the mandible upward to join the transverse incision made in exposing the Epicranium. These incisions include a square-shaped flap, which should be removed in the direction marked in the figure, with care, as the muscles at some points are intimately adherent to the integument.

The Levator palpebrae superioris is described with the Anatomy of the Eye.




FIG. 484.—Left orbicularis oculi, seen from behind.

The **Orbicularis oculi** (*Orbicularis palpebrarum*) (Fig. 484) arises from the nasal part of the frontal bone, from the frontal process of the maxilla in front of the lacrimal groove, and from the anterior surface and borders of a short fibrous band,

the **medial palpebral ligament**. From this origin, the fibres are directed lateralward, forming a broad and thin layer, which occupies the eyelids or palpebrae, surrounds the circumference of the orbit, and spreads over the temple, and downward on the cheek. The **palpebral portion** of the muscle is thin and pale; it *arises* from the bifurcation of the medial palpebral ligament, forms a series of concentric curves, and is *inserted* into the lateral palpebral raphé. The **orbital portion** is thicker and of a reddish color; its fibres form a complete ellipse without interruption at the lateral palpebral commissure; the upper fibres of this portion blend with the Frontalis and Corrugator. The **lacrimal part** (*Tensor tarsi*) is a small, thin muscle, about 6 mm. in breadth and 12 mm. in length, situated behind the medial palpebral ligament and lacrimal sac (Fig. 484). It *arises* from the posterior crest and adjacent part of the orbital surface of the lacrimal bone, and passing behind the lacrimal sac, divides into two slips, upper and lower, which are *inserted* into the superior and inferior tarsi medial to the puncta lacrimalia; occasionally it is very indistinct.

The **medial palpebral ligament** (*tendo oculi*), about 4 mm. in length and 2 mm. in breadth, is attached to the frontal process of the maxilla in front of the lacrimal groove. Crossing the lacrimal sac, it divides into two parts, upper and lower, each attached to the medial end of the corresponding tarsus. As the ligament crosses the lacrimal sac, a strong aponeurotic lamina is given off from its posterior surface; this expands over the sac, and is attached to the posterior lacrimal crest.

The **lateral palpebral raphé** is a much weaker structure than the medial palpebral ligament. It is attached to the margin of the frontosphenoidal process of the zygomatic bone, and passes medialward to the lateral commissure of the eyelids, where it divides into two slips, which are attached to the margins of the respective tarsi.

The **Corrugator**<sup>1</sup> (*Corrugator supercilii*) is a small, narrow, pyramidal muscle, placed at the medial end of the eyebrow, beneath the Frontalis and Orbicularis oculi. It *arises* from the medial end of the superciliary arch; and its fibres pass upward and lateralward, between the palpebral and orbital portions of the Orbicularis oculi, and are *inserted* into the deep surface of the skin, above the middle of the orbital arch.

**Nerves.**—The Orbicularis oculi and Corrugator are supplied by the facial nerve.

**Actions.**—The Orbicularis oculi is the sphincter muscle of the eyelids. The palpebral portion acts involuntarily, closing the lids gently, as in sleep or in blinking; the orbital portion is subject to the will. When the entire muscle is brought into action, the skin of the forehead, temple, and cheek is drawn toward the medial angle of the orbit, and the eyelids are firmly closed, as in photophobia. The skin thus drawn upon is thrown into folds, especially radiating from the lateral angle of the eyelids; these folds become permanent in old age, and form the so-called "crows' feet." The Levator palpebrae superioris is the direct antagonist of this muscle; it raises the upper eyelid and exposes the front of the bulb of the eye. Each time the eyelids are closed through the action of the Orbicularis, the medial palpebral ligament is tightened, the wall of the lacrimal sac is thus drawn lateralward and forward, so that a vacuum is made in it, and the tears are sucked along the lacrimal canals into it. The lacrimal part of the Orbicularis oculi draws the eyelids and the ends of the lacrimal canals medialward and compresses them against the surface of the globe of the eye, thus placing them in the most favorable situation for receiving the tears; it also compresses the lacrimal sac. The Corrugator draws the eyebrow downward and medialward, producing the vertical wrinkles of the forehead. It is the "frowning" muscle, and may be regarded as the principal muscle in the expression of suffering.

### III. THE MUSCLES OF THE NOSE (Fig. 483).

The muscles of the nose comprise:

Procerus.  
Nasalis.

Depressor septi.  
Dilatator naris posterior.

Dilatator naris anterior.

<sup>1</sup> The corrugator is not recognized as a separate muscle in the Basle Nomenclature.

The **Procerus** (*Pyramidalis nasi*) is a small pyramidal slip arising by tendinous fibres from the fascia covering the lower part of the nasal bone and upper part of the lateral nasal cartilage; it is *inserted* into the skin over the lower part of the forehead between the two eyebrows, its fibres decussating with those of the Frontalis.

The **Nasalis** (*Compressor naris*) consists of two parts, transverse and alar. The **transverse part** *arises* from the maxilla, above and lateral to the incisive fossa; its fibres proceed upward and medialward, expanding into a thin aponeurosis which is continuous on the bridge of the nose with that of the muscle of the opposite side, and with the aponeurosis of the Procerus. The **alar part** is attached by one end to the greater alar cartilage, and by the other to the integument at the point of the nose.

The **Depressor septi** (*Depressor alae nasi*) *arises* from the incisive fossa of the maxilla; its fibres ascend to be *inserted* into the septum and back part of the ala of the nose. It lies between the mucous membrane and muscular structure of the lip.

The **Dilatator naris posterior** is placed partly beneath the Quadratus labii superioris. It *arises* from the margin of the nasal notch of the maxilla, and from the lesser alar cartilages, and is *inserted* into the skin near the margin of the nostril.

The **Dilatator naris anterior** is a delicate fasciculus, passing from the greater alar cartilage to the integument near the margin of the nostril; it is situated in front of the preceding.

**Nerves.**—All the muscles of this group are supplied by the facial nerve.

**Actions.**—The Procerus draws down the medial angle of the eyebrows and produces transverse wrinkles over the bridge of the nose. The two Dilatores enlarge the aperture of the nares. Their action in ordinary breathing is to resist the tendency of the nostrils to close from atmospheric pressure, but in difficult breathing, as well as in some emotions, such as anger, they contract strongly. The Depressor septi is a direct antagonist of the other muscles of the nose, drawing the ala of the nose downward, and thereby constricting the aperture of the nares. The Nasalis depresses the cartilaginous part of the nose and draws the ala toward the septum.

#### IV. THE MUSCLES OF THE MOUTH.

The muscles of the mouth are:

Quadratus labii superioris.  
Caninus.  
Zygomaticus.  
Mentalis.

Quadratus labii inferioris.  
Triangularis.  
Buccinator.  
Orbicularis oris.

Risorius.

**Dissection.**—The dissection of these muscles may be considerably facilitated by filling the cavity of the mouth with tow, so as to distend the cheeks and lips; the mouth should then be closed by a few stitches and the integument carefully removed from the surface.

The **Quadratus labii superioris** is a broad sheet, the origin of which extends from the side of the nose to the zygomatic bone. Its medial fibres form the **angular head**, which *arises* by a pointed extremity from the upper part of the frontal process of the maxilla and passing obliquely downward and lateralward divides into two slips. One of these is *inserted* into the greater alar cartilage and skin of the nose; the other is prolonged into the lateral part of the upper lip, blending with the infraorbital head and with the Orbicularis oris. The intermediate portion or **infraorbital head** *arises* from the lower margin of the orbit immediately above the infraorbital foramen, some of its fibres being attached to the maxilla, others to the zygomatic bone. Its fibres converge, to be *inserted* into the muscular substance

of the upper lip between the angular head and the Caninus. The lateral fibres, forming the **zygomatic head**, *arise* from the malar surface of the zygomatic bone immediately behind the zygomaticomaxillary suture and pass downward and medialward to the upper lip.

The **Caninus** (*Levator anguli oris*) *arises* from the canine fossa, immediately below the infraorbital foramen; its fibres are *inserted* into the angle of the mouth, intermingling with those of the Zygomaticus, Triangularis, and Orbicularis oris.

The **Zygomaticus** (*Zygomaticus major*) *arises* from the zygomatic bone, in front of the zygomaticotemporal suture, and descending obliquely with a medial inclination, is *inserted* into the angle of the mouth, where it blends with the fibres of the Caninus, Orbicularis oris, and Triangularis.

**Nerves.**—This group of muscles is supplied by the facial nerve.

**Actions.**—The Quadratus labii superioris is the proper elevator of the upper lip, carrying it at the same time a little forward. Its angular head acts as a dilator of the naris; the infraorbital and zygomatic heads assist in forming the nasolabial furrow, which passes from the side of the nose to the upper lip and gives to the face an expression of sadness. When the whole muscle is in action it gives to the countenance an expression of contempt and disdain. The Quadratus labii superioris raises the angle of the mouth and assists the Caninus in producing the nasolabial furrow. The zygomaticus draws the angle of the mouth backward and upward, as in laughing.

The **Mentalis** (*Levator menti*) is a small conical fasciculus, situated at the side of the frenulum of the lower lip. It *arises* from the incisive fossa of the mandible, and descends to be *inserted* into the integument of the chin.

The **Quadratus labii inferioris** (*Depressor labii inferioris*; *Quadratus menti*) is a small quadrilateral muscle. It *arises* from the oblique line of the mandible, between the symphysis and the mental foramen, and passes upward and medialward, to be *inserted* into the integument of the lower lip, its fibres blending with the Orbicularis oris, and with those of its fellow of the opposite side. At its origin it is continuous with the fibres of the Platysma. Much yellow fat is intermingled with the fibres of this muscle.

The **Triangularis** (*Depressor anguli oris*) *arises* from the oblique line of the mandible, whence its fibres converge, to be *inserted*, by a narrow fasciculus, into the angle of the mouth. At its origin it is continuous with the Platysma, and at its insertion with the Orbicularis oris and Risorius; some of its fibres are directly continuous with those of the Caninus, and others are occasionally found crossing from the muscle of one side to that of the other; these latter fibres constitute the **Transversus menti**.

**Nerves.**—This group of muscles is supplied by the facial nerve.

**Actions.**—The Mentalis raises and protrudes the lower lip, and at the same time wrinkles the skin of the chin, expressing doubt or disdain. The Quadratus labii inferioris draws the lower lip directly downward and a little lateralward, as in the expression of irony. The Triangularis depresses the angle of the mouth, being the antagonist of the Caninus and Zygomaticus; acting with the Caninus, it will draw the angle of the mouth medialward.

The **Buccinator** (Fig. 485) is a thin quadrilateral muscle, occupying the interval between the maxilla and the mandible at the side of the face. It *arises* from the outer surfaces of the alveolar processes of the maxilla and mandible, corresponding to the three molar teeth; and behind, from the anterior border of the pterygomandibular raphe which separates it from the Constrictor pharyngis superior. The fibres converge toward the angle of the mouth, where the central fibres intersect each other, those from below being continuous with the upper segment of the Orbicularis oris, and those from above with the lower segment; the upper and lower fibres are continued forward into the corresponding lip without decussation.

**Relations.**—The Buccinator is covered by the buccopharyngeal fascia, and is in relation by its *superficial surface*, behind, with a large mass of fat, which separates it from the ramus of the mandible, the Masseter, and a small portion of the Temporalis; this fat has been named the

*suctorial pad*, because it is supposed to assist in the act of sucking. In front the superficial surface of the Buccinator is in relation with the Zygomaticus, Risorius, Caninus, Triangularis, and the parotid duct which pierces it opposite the second molar tooth of the maxilla; the external maxillary artery and anterior facial vein cross it from below upward; it is also crossed by the branches of the facial and buccinator nerves. The *deep surface* is in relation with the buccal glands and mucous membrane of the mouth.

The **pterygomandibular raphé** (*pterygomandibular ligament*) is a tendinous band of the buccopharyngeal fascia, attached by one extremity to the hamulus of the medial pterygoid plate, and by the other to the posterior end of the mylohyoid line of the mandible. Its *medial surface* is covered by the mucous membrane of the mouth. Its *lateral surface* is separated from the ramus of the mandible by a quantity of adipose tissue. Its *posterior border* gives attachment to the Constrictor pharyngis superior; its *anterior border*, to part of the Buccinator (Fig. 485).

The **Orbicularis oris** (Fig. 486) is not a simple sphincter muscle like the Orbicularis oculi; it consists of numerous strata of muscular fibres surrounding the orifice of the mouth but having different direction. It consists partly of fibres derived from the other facial muscles which are inserted into the lips, and partly of fibres proper to the lips. Of the former, a considerable number are derived from the Buccinator and form the deeper stratum of the Orbicularis. Some of the Buccinator fibres—namely, those near the middle of the muscle—decussate at the angle of the mouth, those arising from the maxilla passing to the lower lip,



FIG. 485.—Muscles of the pharynx and cheek.




FIG. 486.—Scheme showing arrangement of fibres of Orbicularis oris.

and those from the mandible to the upper lip. The uppermost and lowermost fibres of the Buccinator pass across the lips from side to side without decussation. Superficial to this stratum is a second, formed on either side by the Caninus and Triangularis, which cross each other at the angle of the mouth; those from the Caninus passing to the lower lip, and those from the Triangularis to the upper lip, along which they run, to be inserted into the skin near the median line. In addition to these there are fibres from the Quadratus labii superioris, the Zygomaticus, and the Quadratus labii inferioris; these intermingle with the transverse fibres above described, and have principally an oblique direction. The proper fibres of the lips are oblique, and pass from the under surface of the skin to the mucous membrane, through the thickness of the lip. Finally there are fibres by which the muscle is connected with the maxillæ and the septum of the nose above and with



the mandible below. In the upper lip these consist of two bands, lateral and medial, on either side of the middle line; the **lateral band** (*m. incisivus labii superioris*) arises from the alveolar border of the maxilla, opposite the lateral incisor tooth, and arching lateralward is continuous with the other muscles at the angle of the mouth; the **medial band** (*m. nasolabialis*) connects the upper lip to the back of the septum of the nose. The interval between the two medial bands corresponds with the depression, called the **philtrum**, seen on the lip beneath the septum of the nose. The additional fibres for the lower lip constitute a slip (*m. incisivus labii inferioris*) on either side of the middle line; this arises from the mandible, lateral to the Mentalis, and intermingles with the other muscles at the angle of the mouth.

The **Risorius** arises in the fascia over the Masseter and, passing horizontally forward, superficial to the Platysma, is inserted into the skin at the angle of the mouth (Fig. 483). It is a narrow bundle of fibres, broadest at its origin, but varies much in its size and form.

**Nerves.**—The muscles in this group are all supplied by the facial nerve.

**Actions.**—The Orbicularis oris in its ordinary action effects the direct closure of the lips; by its deep fibres, assisted by the oblique ones, it closely applies the lips to the alveolar arch. The superficial part, consisting principally of the decussating fibres, brings the lips together and also protrudes them forward. The Buccinators compress the cheeks, so that, during the process of mastication, the food is kept under the immediate pressure of the teeth. When the cheeks have been previously distended with air, the Buccinator muscles expel it from between the lips, as in blowing a trumpet; hence the name (*buccina*, a trumpet). The Risorius retracts the angle of the mouth, and produces an unpleasant grinning expression.

#### IV. THE MUSCLES OF MASTICATION.

The chief muscles of mastication are:

Masseter.

Pterygoideus externus.

Temporalis.

Pterygoideus internus.

**Parotidomasseteric Fascia** (*masseteric fascia*).—Covering the Masseter, and firmly connected with it, is a strong layer of fascia derived from the deep cervical fascia. Above, this fascia is attached to the lower border of the zygomatic arch, and behind, it invests the parotid gland.

The **Masseter** (Fig. 483) is a thick, somewhat quadrilateral muscle, consisting of two portions, superficial and deep. The **superficial portion**, the larger, *arises* by a thick, tendinous aponeurosis from the zygomatic process of the maxilla, and from the anterior two-thirds of the lower border of the zygomatic arch: its fibres pass downward and backward, to be *inserted* into the angle and lower half of the lateral surface of the ramus of the mandible. The **deep portion** is much smaller, and more muscular in texture; it *arises* from the posterior third of the lower border and from the whole of the medial surface of the zygomatic arch; its fibres pass downward and forward, to be *inserted* into the upper half of the ramus and the lateral surface of the coronoid process of the mandible. The deep portion of the muscle is partly concealed, in front, by the superficial portion; behind, it is covered by the parotid gland. The fibres of the two portions are continuous at their insertion.

**Relations.**—The Masseter is in relation by its *superficial surface* with the integument, Platysma, Risorius, Zygomaticus, the parotid gland and its accessory portion; the parotid duct, the branches of the facial nerve and the transverse facial vessels cross it. By its *deep surface*, it is in relation with the insertion of the Temporalis and the ramus of the mandible; a mass of fat separates it from the Buccinator and the buccinator nerve. The masseteric nerve and artery enter the muscle on its deep surface. Its *posterior margin* is overlapped by the parotid gland. Its *anterior margin* projects over the Buccinator and is crossed below by the anterior facial vein.

**Temporal Fascia.**—The temporal fascia covers the Temporalis muscle. It is a strong, fibrous investment, covered, laterally, by the Auricularis anterior and superior, by the galea aponeurotica, and by part of the Orbicularis oculi. The superficial temporal vessels and the auriculotemporal nerve cross it from below upward. Above, it is a single layer, attached to the entire extent of the superior temporal line; but below, where it is fixed to the zygomatic arch, it consists of two layers, one of which is inserted into the lateral, and the other into the medial border of the arch. A small quantity of fat, the orbital branch of the superficial temporal artery, and a filament from the zygomatic branch of the maxillary nerve, are contained between these two layers. It affords attachment by its deep surface to the superficial fibres of the Temporalis.

**Dissection.**—In order to expose the Temporalis, remove the temporal fascia, which may be effected by separating it at its attachment along the upper border of the zygoma and dissecting it upward from the surface of the muscle. The zygomatic arch should then be divided in front at its junction with the zygomatic bone, and behind near the external auditory meatus, and drawn downward with the Masseter, which should be detached from its insertion into the ramus and angle of the mandible. The whole extent of the Temporalis is then exposed.




FIG. 487.—The Temporalis; the zygomatic arch and Masseter have been removed.

The **Temporalis** (*Temporal muscle*) (Fig. 487) is a broad, radiating muscle, situated at the side of the head. It arises from the whole of the temporal fossa (except that portion of it which is formed by the zygomatic bone) and from the deep surface of the temporal fascia. Its fibres converge as they descend, and end in a tendon, which passes deep to the zygomatic arch and is inserted into the medial surface, apex, and anterior border of the coronoid process, and the anterior border of the ramus of the mandible nearly as far forward as the last molar tooth.

**Relations.**—The Temporalis is in relation by its *superficial surface* with the integument, the Auricularis anterior and superior, the temporal fascia, the superficial temporal vessels, the auriculotemporal nerve, the temporal branches of the facial and zygomatic nerves, the galea aponeurotica, the zygomatic arch, and the Masseter. By its *deep surface*, it is in relation with the temporal fossa, the Pterygoideus externus and part of the Buccinator, the internal maxillary artery, and its deep temporal branches, the deep temporal nerves, and the buccinator vessels and nerve. Behind the tendon are the masseteric vessels and nerve. Its *anterior border* is separated from the zygomatic bone by a mass of fat.

**Dissection.**—The Temporalis having been examined, saw through the base of the coronoid process and draw it upward, together with the Temporalis, which should be detached from the surface of the temporal fossa. Divide the ramus of the mandible just below the condyle, and also, by a transverse incision extending across the middle, just above the dental foramen; remove the fragment, and the Pterygoidei will be exposed.

The **Pterygoideus externus** (*External pterygoid muscle*) (Fig. 488) is a short, thick muscle, somewhat conical in form, which extends almost horizontally between the infratemporal fossa and the condyle of the mandible. It *arises* by two heads; an **upper** from the lower part of the lateral surface of the great wing of the sphenoid and from the infratemporal crest; a **lower** from the lateral surface of the lateral pterygoid plate. Its fibres pass horizontally backward and lateralward, to be *inserted* into a depression in front of the neck of the condyle of the mandible, and into the front margin of the articular disk of the temporomandibular articulation.




FIG. 488.—The Pterygoidei; the zygomatic arch and a portion of the ramus of the mandible have been removed.

**Relations.**—Its *superficial surface* is in relation with the ramus of the mandible, the internal maxillary artery, which crosses it,<sup>1</sup> the tendon of the Temporalis, and the Masseter. Its *deep surface* rests against the upper part of the Pterygoideus internus, the sphenomandibular ligament, the middle meningeal artery, and the mandibular nerve; its *upper border* is in relation with the temporal and masseteric branches of the mandibular nerve; its *lower border* with the lingual and inferior alveolar nerves. The buccal nerve and the internal maxillary artery pass between the two portions of the muscle (Fig. 488).

The **Pterygoideus internus** (*Internal pterygoid muscle*) (Fig. 488) is a thick, quadrilateral muscle. It *arises* from the medial surface of the lateral pterygoid plate and the grooved surface of the pyramidal process of the palatine bone; it has a second slip of origin from the lateral surfaces of the pyramidal process of the palatine and tuberosity of the maxilla. Its fibres pass downward, lateralward, and backward, and are *inserted*, by a strong tendinous lamina, into the lower and back part of the medial surface of the ramus and angle of the mandible, as high as the mandibular foramen.

**Relations.**—Its *lateral surface* is in relation with the ramus of the mandible, from which it is separated, at its upper part, by the Pterygoideus externus, the sphenomandibular ligament, the internal maxillary artery, the inferior alveolar vessels and nerve, the lingual nerve, and a process of the parotid gland. Its *medial surface* is in relation with the Tensor veli palatini, being separated from the Constrictor pharyngis superior by some areolar tissue.

<sup>1</sup> In many cases the artery will be found under cover of the muscle.

**Nerves.**—The muscles of mastication are supplied by the mandibular nerve.

**Actions.**—The Temporalis, Masseter, and Pterygoideus internus *raise* the mandible against the maxillæ with great force. The Pterygoideus externus assists in opening the mouth, but its main action is to draw forward the condyle and articular disk so that the mandible is protruded and the inferior incisors projected in front of the upper; in this action it is assisted by the Pterygoideus internus. The mandible is retracted by the posterior fibres of the Temporalis. If the Pterygoidei internus and externus of one side act, the corresponding side of the mandible is drawn forward while the opposite condyle remains comparatively fixed, and side-to-side movements, such as occur during the trituration of food, take place.

## THE FASCIAE AND MUSCLES OF THE ANTERO-LATERAL REGION OF THE NECK.

The antero-lateral muscles of the neck may be arranged into the following groups:

- |                          |                              |
|--------------------------|------------------------------|
| I. Superficial Cervical. | III. Supra- and Infra-hyoid. |
| II. Lateral Cervical.    | IV. Anterior Vertebral.      |
| V. Lateral Vertebral.    |                              |

### I. THE SUPERFICIAL CERVICAL MUSCLE.

#### Platysma.

**Dissection.**—A block having been placed at the back of the neck, and the face turned to the side opposite that to be dissected, so as to place the parts upon the stretch, make two transverse incisions, one from the chin, along the margin of the mandible, to the mastoid process, and the other along the upper border of the clavicle. Connect these by an oblique incision made in the course of the Sternocleidomastoideus, from the mastoid process to the sternum; the two flaps of integument having been removed in the direction shown in Fig. 482, the superficial fascia will be exposed.

The **Superficial Fascia** of the neck is a thin lamina investing the Platysma, and is hardly demonstrable as a separate membrane.

The **Platysma** (Fig. 483) is a broad sheet *arising* from the fascia covering the upper parts of the Pectoralis major and Deltoideus; its fibres cross the clavicle, and proceed obliquely upward and medialward along the side of the neck. The anterior fibres interlace, below and behind the symphysis menti, with the fibres of the muscle of the opposite side; the posterior fibres cross the mandible, some being inserted into the bone below the oblique line, others into the skin and subcutaneous tissue of the lower part of the face, many of these fibres blending with the muscles about the angle and lower part of the mouth. Sometimes fibres can be traced to the zygomaticus, or to the margin of the Orbicularis oculi. Beneath the Platysma, the external jugular vein descends from the angle of the mandible to the clavicle.

**Actions.**—When the entire Platysma is in action it produces a slight wrinkling of the surface of the skin of the neck in an oblique direction. Its anterior portion, the thickest part of the muscle, depresses the lower jaw; it also serves to draw down the lower lip and angle of the mouth in the expression of melancholy.

**Nerve.**—The Platysma is supplied by the cervical branch of the facial nerve.

### II. THE LATERAL CERVICAL MUSCLES.

The lateral muscles are:

Trapezius and Sternocleidomastoideus.

The Trapezius is described on page 522.



**The Fascia Colli** (*deep cervical fascia*) (Fig. 489).—The fascia colli lies under cover of the Platysma, and invests the neck; it also forms sheaths for the carotid vessels, and for the structures situated in front of the vertebral column.




FIG. 489.—Section of the neck at about the level of the sixth cervical vertebra. Showing the arrangement of the fascia colli.

The investing portion of the fascia is attached behind to the ligamentum nuchae and to the spinous process of the seventh cervical vertebra. It forms a thin investment to the Trapezius, and at the anterior border of this muscle is continued forward as a rather loose areolar layer, covering the posterior triangle of the neck, to the posterior border of the Sternocleidomastoideus, where it begins to assume the appearance of a fascial membrane. Along the hinder edge of the Sternocleidomastoideus it divides to enclose the muscle, and at the anterior margin again forms a single lamella, which covers the anterior triangle of the neck, and reaches forward to the middle line, where it is continuous with the corresponding part from the opposite side of the neck. In the middle line of the neck it is attached to the symphysis menti and the body of the hyoid bone.

*Above*, the fascia is attached to the superior nuchal line of the occipital, to the mastoid process of the temporal, and to the whole length of the inferior border of the body of the mandible. Opposite the angle of the mandible the fascia is very strong, and binds the anterior edge of the Sternocleidomastoideus firmly to that bone. Between the mandible and the mastoid process it ensheathes the parotid gland—the layer which covers the gland extends upward under the name of the **parotidomasseteric fascia** and is fixed to the zygomatic arch. From the part which passes under the parotid gland a strong band extends upward to the styloid process, forming the **stylomandibular ligament**. Two other bands may be defined: the **sphenomandibular** (page 395) and the **pterygospinous ligaments**. The **pterygospinous ligament** stretches from the upper part of the posterior border of the lateral pterygoid plate to the spinous process of the sphenoid. It occasionally ossifies, and in such cases, between its upper border and the base of the skull, a foramen is formed which transmits the branches of the mandibular nerve to the muscles of mastication.

*Below*, the fascia is attached to the acromion, the clavicle, and the manubrium sterni. Some little distance above the last it splits into two layers, superficial and deep. The former is attached to the anterior border of the manubrium, the latter to its posterior border and to the interclavicular ligament. Between these two layers is a slit-like interval, the **suprasternal space** (*space of Burns*); it contains a small quantity of areolar tissue, the lower portions of the anterior jugular veins and their transverse connecting branch, the sternal heads of the Sternocleidomastoidei, and sometimes a lymph gland.

The fascia which lines the deep surface of the Sternocleidomastoideus gives off the following processes: (1) A process envelops the tendon at the Omohyoideus, and binds it down to the sternum and first costal cartilage. (2) A strong sheath, the **carotid sheath**, encloses the carotid artery, internal jugular vein, and vagus nerve. (3) The **prevertebral fascia** extends medialward behind the carotid vessels, where it assists in forming their sheath, and passes in front of the prevertebral muscles. It forms the posterior limit of a fibrous compartment, which contains the larynx and trachea, the thyroid gland, and the pharynx and oesophagus. The prevertebral fascia is fixed above to the base of the skull, and below is continued into the thorax in front of the Longus colli muscles. Parallel to the carotid sheath and along its medial aspect the prevertebral fascia gives off a thin lamina, the **buccopharyngeal fascia**, which closely invests the Constrictor muscles of the pharynx, and is continued forward from the Constrictor pharyngis superior on to the Buccinator. It is attached to the prevertebral layer by loose connective tissue only, and thus an easily distended space, the **retropharyngeal space**, is found between them. This space is limited above by the base of the skull, while below it extends behind the oesophagus into the posterior mediastinal cavity of the thorax. The prevertebral fascia is prolonged downward and lateralward behind the carotid vessels and in front of the Scaleni, and forms a sheath for the brachial nerves and subclavian vessels in the posterior triangle of the neck; it is continued under the clavicle as the axillary sheath and is attached to the deep surface of the coracoclavicular fascia. Immediately above and behind the clavicle an areolar space exists between the investing layer and the sheath of the subclavian vessels, and in this space are found the lower part of the external jugular vein, the descending claviculæ nerves, the transverse scapular and transverse cervical vessels, and the inferior belly of the Omohyoideus muscle. This space is limited below by the fusion of the coracoclavicular fascia with the anterior wall of the axillary sheath. (4) The **pretracheal fascia** extends medially in front of the carotid vessels, and assists in forming the carotid sheath. It is continued behind the depressor muscles of the hyoid bone, and, after enveloping the thyroid gland, is prolonged in front of the trachea to meet the corresponding layer of the opposite side. Above, it is fixed to the hyoid bone, while below it is carried downward in front of the trachea and large vessels



at the root of the neck, and ultimately blends with the fibrous pericardium. This layer is fused on either side with the prevertebral fascia, and with it completes the compartment containing the larynx and trachea, the thyroid gland, and the pharynx and œsophagus.<sup>1</sup>

**Applied Anatomy.**—The deep cervical fascia is of considerable importance from a surgical point of view. The investing layer opposes the extension of abscesses toward the surface, and pus forming beneath it has a tendency to extend laterally. If the pus be contained in the anterior triangle, it may find its way into the anterior mediastinal cavity, in front of the layer of fascia which passes down into the thorax to blend with the pericardium; but owing to the less density and thickness of the fascia in this situation it more frequently finds its way to the surface and points above the sternum. Pus forming beneath the pretracheal layer would in all probability find its way into the posterior mediastinal cavity. Pus forming behind the prevertebral layer, in cases, for instance, of caries of the bodies of the cervical vertebræ, may extend toward the lateral part of the neck and point in the posterior triangle, or may perforate this layer of fascia and the buccopharyngeal fascia and point into the pharynx (*retropharyngeal abscess*).

In cases of cut throat, when the wound involves only the investing layer the injury is usually trivial, the special danger being injury to the external jugular vein, and the special complication, diffuse cellulitis. But where the second of the two layers is opened up, important structures may be injured, and serious results follow.

The sternal head of origin of the Sternocleidomastoideus is contained in the suprasternal space, so that this space is opened in division of this tendon. The lower part of the anterior jugular vein is also contained in the same space.

The **Sternocleidomastoideus** (*Sternomastoid muscle*) (Fig. 490) passes obliquely across the side of the neck. It is thick and narrow at its central part, but broader and thinner at either end. It *arises* from the sternum and clavicle by two heads. The **medial** or **sternal head** is a rounded fasciculus, tendinous in front, fleshy behind, which *arises* from the upper part of the anterior surface of the manubrium sterni, and is directed upward, lateralward, and backward. The **lateral** or **clavicular head**, composed of fleshy and aponeurotic fibres, *arises* from the superior border and anterior surface of the medial third of the clavicle; it is directed almost vertically upward. The two heads are separated from one another at their origins by a triangular interval, but gradually blend, below the middle of the neck, into a thick, rounded muscle which is *inserted*, by a strong tendon, into the lateral surface of the mastoid process, from its apex to its superior border, and by a thin aponeurosis into the lateral half of the superior nuchal line of the occipital bone.

The Sternocleidomastoideus varies much in its extent of origin from the clavicle: in some cases the clavicular may be as narrow as the sternal head; in others, as much as 7.5 cm. in breadth. When the clavicular origin is broad, it is occasionally subdivided into several slips, separated by narrow intervals. More rarely, the adjoining margins of the Sternocleidomastoideus and Trapezius have been found in contact.

**Triangles of the Neck.**—This muscle divides the quadrilateral area of the side of the neck into two triangles, an anterior and a posterior. The boundaries of the **anterior triangle** are, in *front*, the median line of the neck; *above*, the lower border of the body of the mandible, and an imaginary line drawn from the angle of the mandible to the Sternocleidomastoideus; *behind*, the anterior border of the Sternocleidomastoideus. The apex of the triangle is at the upper border of the sternum. The boundaries of the **posterior triangle** are, in *front*, the posterior border of the Sternocleidomastoideus; *below*, the middle third of the clavicle; *behind*, the anterior margin of the Trapezius. The apex corresponds with the meeting of the Sternocleidomastoideus and Trapezius on the occipital bone. The anatomy of these triangles will be more fully described with that of the vessels of the neck (p. 642).

**Relations.**—The *superficial surface* of the Sternocleidomastoideus is in relation with the integument and Platysma, from which it is separated by the external jugular vein, several of the superficial branches of the cervical plexus, and the investing layer of the deep cervical fascia. The *deep surface* of the muscle is in relation with the sternoclavicular articulation, the process of the deep cervical fascia which binds the inferior belly of the Omohyoideus to the sternum and clavicle, the Sternohyoideus, Sternothyreoideus, Omohyoideus, posterior belly of

<sup>1</sup> F. G. Parsons (Journal of Anatomy and Physiology, vol. xlv) regards the carotid sheath and the fascial planes in the neck as structures which are artificially produced by dissection.

the Digastricus, Levator scapulae, Splenius and Scaleni muscles, the common carotid artery, the internal and anterior jugular veins, the origins of the internal and external carotid arteries, the occipital, subclavian, transverse cervical, and transverse scapular arteries and veins, the phrenic, vagus, hypoglossal, descendens and communicantes hypoglossi nerves, the accessory nerve which pierces its upper third, the cervical plexus, the upper part of the brachial plexus, parts of the thyroid and parotid glands and their vessels, and the deep cervical lymph glands.

**Actions.**—When only one Sternocleidomastoideus acts, it draws the head toward the shoulder of the same side, assisted by the Splenius and the Obliquus capitis inferior of the opposite side. At the same time it rotates the head so as to carry the face toward the opposite side. Acting together from their sternoclavicular attachments the muscles will flex the cervical part of the vertebral column. If the head be fixed, the two muscles assist in elevating the thorax in forced inspiration.




FIG. 490.—Muscles of the neck. Lateral view.

**Nerves.**—The Sternocleidomastoideus is supplied by the accessory nerve and branches from the anterior divisions of the second and third cervical nerves.

**Applied Anatomy.**—The surgical anatomy of the Sternocleidomastoideus is of importance in connection with the deformity known as *wry-neck*, which is due to a contracted condition of this muscle. The *wry-neck* may be temporary, as the result of direct irritation of the muscle or of the nerves supplying it, and may occur in acute glandular enlargement, cellulitis of the neck, myositis of the muscle, or cervical caries. It may, however, be permanent, and is then most often due to injury to the muscle during birth, especially in breech presentations, rupture of the fibres and subsequent cicatricial contraction taking place. In these cases, division of the muscle is often necessary to effect a cure, and this may be done either subcutaneously or through an open wound. The subcutaneous method is thus performed; the external jugular and the jugular veins having been, if possible, defined, a tenotomy knife is introduced close above the tendon of origin of the muscle, about 1.25 cm. above the clavicle, and the tenal spine on flat behind the tendon and then turned forward, and the tendon divided from belowward, to while the muscle is put well upon the stretch by an assistant. The other tendon lies in connection in a similar manner. In dividing the clavicular origin, it is always desirable to tenotome along the posterior border, in order to avoid the external jugular vein. This is, however, much to be preferred, as being the more effectual and the less disfigured by the myeloid incisions are taken to keep the wound aseptic. The tendons of origin are freely of the Digastricus, a horizontal incision across the root of the neck and carefully divided; any tense br





from the tendon of the Digastricus on either side, to be attached to the body and greater cornu of the hyoid bone; this is termed the **suprahyoid aponeurosis**.

The Digastricus divides the anterior triangle of the neck into three smaller triangle (1) the **submaxillary triangle**, bounded above by the lower border of the body of the mandible, and a line drawn from its angle to the Sternocleidomastoideus, below by the posterior belly of the Digastricus and the Stylohyoideus, in front by the anterior belly of the Digastricus; (2) the **carotid triangle**, bounded above by the posterior belly of the Digastricus and Stylohyoideus, behind by the Sternocleidomastoideus, below by the Omohyoideus; (3) the **suprahyoid or submental triangle**, bounded laterally by the anterior belly of the Digastricus, medially by the middle line of the neck from the hyoid bone to the symphysis menti, and inferiorly by the body of the hyoid bone.

**Relations.**—The Digastricus is in relation by its *superficial surface* with the Platysma, Sternocleidomastoideus, part of the Splenius, Longissimus capitis, mastoid process, Stylohyoideus, and the parotid gland. The *deep surface* of the anterior belly lies on the Mylohyoideus; that of the posterior belly on the Styloglossus, Stylopharyngeus, and Hyoglossus muscles, the external carotid artery and its occipital, lingual, external maxillary, and ascending pharyngeal branches, the internal carotid artery, internal jugular vein, and hypoglossal nerve.

The **Stylohyoideus** (*Stylohyoid muscle*) is a slender muscle, lying in front of, and above, the posterior belly of the Digastricus. It *arises* from the back and lateral surface of the styloid process, near the base; and, passing downward and forward, is *inserted* into the body of the hyoid bone, at its junction with the greater cornu, and just above the Omohyoideus. It is perforated, near its insertion, by the tendon of the Digastricus.

The **Stylohyoid Ligament** (*ligamentum stylohyoideus*).—In connection with the Stylohyoideus muscle a ligamentous band, the **stylohyoid ligament**, may be described. It is a fibrous cord, which is attached to the tip of the styloid process of the temporal and the lesser cornu of the hyoid bone. It frequently contains a little cartilage in its centre, is often partially ossified, and in many animals forms a distinct bone, the **epihyal**.

The **Mylohyoideus** (*Mylohyoid muscle*), flat and triangular, is situated immediately above the anterior belly of the Digastricus, and forms, with its fellow of the opposite side, a muscular floor for the cavity of the mouth. It *arises* from the whole length of the mylohyoid line of the mandible, extending from the symphysis in front to the last molar tooth behind. The posterior fibres pass medialward and slightly downward, to be *inserted* into the body of the hyoid bone. The middle and anterior fibres are *inserted* into a median fibrous raphé extending from the symphysis menti to the hyoid bone, where they join at an angle with the fibres of the opposite muscle. This median raphé is sometimes wanting; the fibres of the two muscles are then continuous.

**Relations.**—The Mylohyoideus is in relation by its *superficial or under surface* with the Platysma, the anterior belly of the Digastricus, the suprahyoid aponeurosis, the superficial part of the submaxillary gland, the external maxillary and submental vessels, and the mylohyoid vessels and nerve. By its *deep or superior surface* it is in relation with the Geniohyoideus, part of the Hyoglossus, and the Styloglossus muscles, the hypoglossal and lingual nerves, the submaxillary ganglion, the sublingual gland, the deep portion of the submaxillary gland and the submaxillary duct, the lingual and sublingual vessels, and the buccal mucous membrane.

**Dissection.**—The Mylohyoideus should now be removed, in order to expose the muscles which lie beneath; this is effected by reflecting it from its attachments to the hyoid bone and mandible, and separating it by a vertical incision from its fellow of the opposite side.

The **Geniohyoideus** (*Geniohyoid muscle*) is a narrow muscle, situated above the medial border of the Mylohyoideus. It *arises* from the inferior mental spine on the back of the symphysis menti, and runs backward and slightly downward, to be *inserted* into the anterior surface of the body of the hyoid bone; it lies in contact with its fellow of the opposite side.

**Nerves.**—The Mylohyoideus and anterior belly of the Digastricus are supplied by the mylohyoid branch of the inferior alveolar; the Stylohyoideus and posterior belly of the Digastricus, by the facial; the Geniohyoideus, by the hypoglossal.

**Actions.**—These muscles perform two very important actions. During the act of deglutition they raise the hyoid bone, and with it the base of the tongue; when the hyoid bone is fixed by its depressors and those of the larynx, they depress the mandible. During the first act of deglutition, when the mass of food is being driven from the mouth into the pharynx, the hyoid bone and with it the tongue, is carried upward and forward by the anterior bellies of the Digastrici, the Mylohyoidei, and Geniohyoidei. In the second act, when the mass is passing through the pharynx, the direct elevation of the hyoid bone takes place by the combined action of all the muscles; and after the food has passed, the hyoid bone is carried upward and backward by the posterior bellies of the Digastrici and the Stylohyoidei, which assist in preventing the return of the food into the mouth.

The infrahyoid muscles are:

Sternohyoideus.  
Sternothyreoideus.

Thyreohyoideus.  
Omohyoideus.

**Dissection.**—The muscles in this region may be exposed by removing the deep fascia from the front of the neck. In order to see the entire extent of the Omohyoideus it is necessary to divide the Sternocleidomastoideus at its centre, and turn its ends aside, and to detach the Trapezius from the clavicle and scapula. This, however, should not be done until the Trapezius has been dissected.

The **Sternohyoideus** (*Sternohyoid muscle*) is a thin, narrow muscle, which *arises* from the posterior surface of the medial end of the clavicle, the posterior sternoclavicular ligament, and the upper and posterior part of the manubrium sterni. Passing upward and medialward, it is *inserted*, by short, tendinous fibres, into the lower border of the body of the hyoid bone. Below, this muscle is separated from its fellow by a considerable interval; but the two muscles come into contact with one another in the middle of their course, and from this upward, lie side by side. It sometimes presents, immediately above its origin, a transverse tendinous inscription.

The **Sternothyreoideus** (*Sternothyroid muscle*) is shorter and wider than the preceding muscle, beneath which it is situated. It *arises* from the posterior surface of the manubrium sterni, below the origin of the Sternohyoideus, and from the edge of the cartilage of the first rib, and sometimes that of the second rib, it is *inserted* into the oblique line on the lamina of the thyroid cartilage. This muscle is in close contact with its fellow at the lower part of the neck, but diverges somewhat as it ascends; it is occasionally traversed by a transverse or oblique tendinous inscription.

The **Thyreohyoideus** (*Thyrohyoid muscle*) is a small, quadrilateral muscle appearing like an upward continuation of the Sternothyreoideus. It *arises* from the oblique line on the lamina of the thyroid cartilage, and is *inserted* into the lower border of the greater cornu of the hyoid bone.

The **Omohyoideus** (*Omohyoid muscle*) consists of two fleshy bellies united by a central tendon. It *arises* from the upper border of the scapula, and occasionally from the superior transverse ligament which crosses the scapular notch, its extent of attachment to the scapula varying from a few millimetres to 2.5 cm. From this origin, the inferior belly forms a flat, narrow fasciculus, which inclines forward and slightly upward across the lower part of the neck, being bound down to the clavicle by a fibrous expansion; it then passes behind the Sternocleidomastoideus, becomes tendinous and changes its direction, forming an obtuse angle. It ends in the superior belly, which passes almost vertically upward, close to the lateral border of the Sternohyoideus, to be inserted into the lower border of the body of the hyoid bone, lateral to the insertion of the Sternohyoideus. The central tendon of this muscle varies much in length and form, and is held in position by a process of the deep cervical fascia, which sheaths it, and is prolonged down to be attached to the clavicle and first rib; it is by this means that the angular form of the muscle is maintained.

The inferior belly of the Omohyoideus divides the posterior triangle of the neck into an upper or **occipital triangle** and a lower or **subclavian triangle**, while its superior belly divides the anterior triangle into an upper or **carotid triangle** and a lower or **muscular triangle**.

**Nerves.**—The Thyreohyoideus is supplied by a branch from the hypoglossal nerve; the superior belly of the Omohyoideus by the descendens hypoglossi; the Sternohyoideus, Sternothyreodeus, and inferior belly of the Omohyoideus are supplied by branches from the loop between the descendens hypoglossi and descendens cervicalis.

**Actions.**—These muscles depress the larynx and hyoid bone, after they have been drawn up with the pharynx in the act of deglutition. The Omohyoidei not only depress the hyoid bone, but carry it backward and to one or the other side. They are concerned especially in prolonged inspiratory efforts; for by rendering the lower part of the cervical fascia tense they lessen the inward suction of the soft parts, which would otherwise compress the great vessels and the apices of the lungs. The Thyreohyoideus may act as an elevator of the thyroid cartilage, when the hyoid bone ascends, drawing the thyroid cartilage up behind the hyoid bone. The Sternothyreodeus acts as a depressor of the thyroid cartilage.

#### IV. THE ANTERIOR VERTEBRAL MUSCLES (Fig. 492).

The anterior vertebral muscles are:

Longus colli.

Longus capitis.

Rectus capitis anterior.

Rectus capitis lateralis.




FIG. 492.—The anterior vertebral muscles.

The **Longus colli** is situated on the anterior surface of the vertebral column, between the atlas and the third thoracic vertebra. It is broad in the middle, narrow and pointed at either end, and consists of three portions, a superior oblique,



an inferior oblique, and a vertical. The **superior oblique portion** *arises* from the anterior tubercles of the transverse processes of the third, fourth, and fifth cervical vertebræ; and, ascending obliquely with a medial inclination, is *inserted* by a narrow tendon into the tubercle on the anterior arch of the atlas. The **inferior oblique portion**, the smallest part of the muscle, *arises* from the front of the bodies of the first two or three thoracic vertebræ; and, ascending obliquely in a lateral direction, is *inserted* into the anterior tubercles of the transverse processes of the fifth and sixth cervical vertebræ. The **vertical portion** *arises*, below, from the front of the bodies of the upper three thoracic and lower three cervical vertebræ, and is *inserted* into the front of the bodies of the second, third, and fourth cervical vertebræ.

The **Longus capitis** (*Rectus capitis anticus major*), broad and thick above, narrow below, *arises* by four tendinous slips, from the anterior tubercles of the transverse processes of the third, fourth, fifth, and sixth cervical vertebræ, and ascends, converging toward its fellow of the opposite side, to be *inserted* into the inferior surface of the basilar part of the occipital bone.

The **Rectus capitis anterior** (*Rectus capitis anticus minor*) is a short, flat muscle, situated immediately behind the upper part of the Longus capitis. It *arises* from the anterior surface of the lateral mass of the atlas, and from the root of its transverse process, and passing obliquely upward and medialward, is *inserted* into the inferior surface of the basilar part of the occipital bone immediately in front of the foramen magnum.

The **Rectus capitis lateralis**, a short, flat muscle, *arises* from the upper surface of the transverse process of the atlas, and is *inserted* into the under surface of the jugular process of the occipital bone.

**Nerves.**—The Rectus capitis anterior and the Rectus capitis lateralis are supplied from the loop between the first and second cervical nerves; the Longus capitis, by branches from the first, second, and third cervical; the Longus colli, by branches from the second to the seventh cervical nerves.

**Actions.**—The Longus capitis and Rectus capitis anterior are the direct antagonists of the muscles at the back of the neck, serving to restore the head to its natural position after it has been drawn backward. These muscles also flex the head, and from their obliquity, rotate it, so as to turn the face to one or the other side. The Rectus lateralis, acting on one side, bends the head laterally. The Longus colli flexes and slightly rotates the cervical portion of the vertebral column.

## V. THE LATERAL VERTEBRAL MUSCLES (Fig. 492).

The lateral vertebral muscles are:

Scalenus anterior.

Scalenus medius.

Scalenus posterior.

The **Scalenus anterior** (*Scalenus anticus*) lies deeply at the side of the neck, behind the Sternocleidomastoideus. It *arises* from the anterior tubercles of the transverse processes of the third, fourth, fifth, and sixth cervical vertebræ, and descending, almost vertically, is *inserted* by a narrow, flat tendon into the scalene tubercle on the inner border of the first rib, and into the ridge on the upper surface of the rib in front of the subclavian groove.

**Relations.**—In front of the Scalenus anterior are the clavicle, the Subclavius, Sternocleidomastoideus, and Omohyoideus muscles, the transverse cervical, the transverse scapular, and ascending cervical arteries, the subclavian vein, and the phrenic nerve. By its *posterior surface*, it is in relation with the cords of the brachial plexus, the subclavian artery, and the pleura, which separate it from the Scalenus medius. Below, it is separated from the Longus colli by the vertebral artery, and above, from the Longus capitis, by the ascending cervical branch of the inferior thyroid artery.

The **Scalenus medius**, the largest and longest of the three Scaleni, *arises* from the posterior tubercles of the transverse processes of the lower six cervical

vertebræ, and descending along the side of the vertebral column, is *inserted* by a broad attachment into the upper surface of the first rib, between the tubercle and the subclavian groove.

**Relations.**—The *Scalenus medius* is in relation by its *anterior surface* with the *Sternocleidomastoideus*; it is crossed by the clavicle and the *Omohyoideus*; the subclavian artery and the cervical nerves separate it from the *Scalenus anterior*. *Lateral* to it are the *Levator scapulae* and the *Scalenus posterior*. The long thoracic nerve is formed in the substance of the *Scalenus medius* and emerges from it; the dorsal scapular nerve also pierces it.

The ***Scalenus posterior*** (*Scalenus posticus*), the smallest and most deeply seated of the three *Scaleni*, *arises*, by two or three separate tendons, from the posterior tubercles of the transverse processes of the lower two or three cervical vertebræ, and is *inserted* by a thin tendon into the outer surface of the second rib, behind the attachment of the *Serratus anterior*. It is occasionally blended with the *Scalenus medius*.

**Nerves.**—The *Scaleni* are supplied by branches from the second to the seventh cervical nerves.

**Actions.**—When the *Scaleni* act from above, they elevate the first and second ribs, and are, therefore, inspiratory muscles. Acting from below, they bend the vertebral column to one or other side; if the muscles of both sides act, the vertebral column is slightly flexed.

## THE FASCIAE AND MUSCLES OF THE TRUNK.

The muscles of the trunk may be arranged in six groups:

- |                              |                              |
|------------------------------|------------------------------|
| I. Deep Muscles of the Back. | IV. Muscles of the Abdomen.  |
| II. Suboccipital Muscles.    | V. Muscles of the Pelvis.    |
| III. Muscles of the Thorax.  | VI. Muscles of the Perineum. |

### I. THE DEEP MUSCLES OF THE BACK (Fig. 494).

The deep or intrinsic muscles of the back consist of a complex group of muscles extending from the pelvis to the skull. They are:

- |                    |                     |
|--------------------|---------------------|
| Splenius capitis.  | Multifidus.         |
| Splenius cervicis. | Rotatores.          |
| Sacrospinalis.     | Interspinales.      |
| Semispinalis.      | Intertransversarii. |

**Dissection of the Muscles of the Back by Layers** (Fig. 493).—*First Layer.*—Place the body in a prone position, with the arms extended over the sides of the table, and the thorax and abdomen supported by several blocks, so as to render the muscles tense. Then make an incision along the middle line of the back from the occipital protuberance to the coccyx. Make a transverse incision from the upper end of this to the mastoid process, and a third incision from its lower end, along the crest of the ilium to about its middle. This large intervening space should, for convenience of dissection, be subdivided by a fourth incision, extending obliquely from the spinous process of the last thoracic vertebra, upward and outward to the acromion process. This incision corresponds with the lower border of the *Trapezius* muscle. The flaps of integument are then to be removed in the direction shown in the figure.

*Second Layer.*—The *Trapezius* must be removed, in order to expose the second layer; to effect this, detach the muscle from its attachment to the clavicle and spine of the scapula, and turn it back toward the vertebral column.

*Third Layer.*—To bring into view the third layer of muscles, remove the whole of the second, together with the *Latissimus dorsi*, by cutting through the *Levator scapulae* and *Rhomboidei* muscles near their origin, and reflecting them downward, and by dividing the *Latissimus dorsi* in the middle by a vertical incision carried from its upper to its lower part, and reflecting the two halves of the muscle.

*Fourth Layer.*—To expose the muscles of the fourth layer, remove entirely the *Serrati* and the vertebral and lumbar fasciæ. Then detach the *Splenius* by separating its attachment to the spinous processes and reflecting it outward.

**Fifth Layer.**—Remove the muscles of the preceding layer by dividing and turning aside the Semispinalis capitis; then detach the Spinalis and Longissimus dorsi from their attachments, divide the Sacrospinalis at its connection below to the sacral lumbar vertebræ and turn it outward. The muscles filling up the interval between the spinous and transverse processes are then exposed.

**The Lumbodorsal Fascia** (*fascia lumbodorsalis*; *lumbar aponeurosis and vertebral fascia*).—The lumbodorsal fascia is a deep investing membrane which covers the deep muscles of the back of the trunk. *Above*, it passes in front of the Serratus posterior superior and is continuous with a similar investing layer on the back of the neck—the **nuchal fascia**.

In the thoracic region the lumbodorsal fascia is a thin fibrous lamina which serves to bind down the Extensor muscles of the vertebral column and to separate them from the muscles connecting the vertebral column to the upper extremity. It contains both longitudinal and transverse fibres, and is attached, **medially**, to the spinous processes of the thoracic vertebræ; **laterally** to the angles of the ribs.

In the lumbar region the fascia (*lumbar aponeurosis*) is in two layers, anterior and posterior (Fig. 494). The posterior layer is attached to the spinous processes of the lumbar and sacral vertebræ and to the supraspinal ligament; the anterior is attached, **medially**, to the tips of the transverse processes of the lumbar vertebræ and to the intertransverse ligaments, *below*, to the iliolumbar ligament, and *above*, to the lumbo-costal ligament. The two layers unite at the lateral margin of the Sacrospinalis, to form the tendon of origin of the Transversus abdominis.

The **Splenius capitis** (Fig. 516) arises from the lower half of the ligamentum nuchæ, from the spinous process of the seventh cervical vertebra, and from the spinous processes of the upper three or four thoracic vertebræ. The fibres of the muscle are directed upward and lateralward and




FIG. 493.—Dissection of the muscles of the back.

vertebra, and from the spinous processes of the upper three or four thoracic vertebræ. The fibres of the muscle are directed upward and lateralward and




FIG. 494.—Diagram of a transverse section of the posterior abdominal wall, to show the disposition of the lumbodorsal fascia.

are *inserted*, under cover of the Sternocleidomastoideus, into the mastoid process of the temporal bone, and into the rough surface on the occipital bone just below the lateral third of the superior nuchal line.

The **Rectus capitis posterior major** (*Rectus capitis posticus major*) arises by a pointed tendon from the spinous process of the axis, and, becoming broader as it ascends, is inserted into the lateral part of the inferior nuchal line of the occipital bone and the surface of the bone immediately below the line. As the muscles of the two sides pass upward and lateralward, they leave between them a triangular space, in which the *Recti capitis posteriores minores* are seen.

The **Rectus capitis posterior minor** (*Rectus capitis posticus minor*) arises by a narrow pointed tendon from the tubercle on the posterior arch of the atlas, and, widening as it ascends, is inserted into the medial part of the inferior nuchal line of the occipital bone and the surface between it and the foramen magnum.

The **Obliquus capitis inferior** (*Obliquus inferior*), the larger of the two Oblique muscles, arises from the apex of the spinous process of the axis, and passes lateralward and slightly upward, to be inserted into the lower and back part of the transverse process of the atlas.

The **Obliquus capitis superior** (*Obliquus superior*), narrow below, wide and expanded above, arises by tendinous fibres from the upper surface of the transverse process of the atlas, joining with the insertion of the preceding. It passes upward and medialward, and is inserted into the occipital bone, between the superior and inferior nuchal lines, lateral to the *Semispinalis capitis*.

**The Suboccipital Triangle.**—Between the Obliqui and the *Rectus capitis posterior major* is the **suboccipital triangle**. It is bounded, *above* and *medially*, by the *Rectus capitis posterior major*; *above* and *laterally*, by the *Obliquus capitis superior*; *below* and *laterally*, by the *Obliquus capitis inferior*. It is covered by a layer of dense fibro-fatty tissue, situated beneath the *Semispinalis capitis*. The floor is formed by the posterior occipitoatlantal membrane, and the posterior arch of the atlas. In the deep groove on the upper surface of the posterior arch of the atlas are the vertebral artery and the first cervical or suboccipital nerve.

**Nerves.**—The deep muscles of the back and the suboccipital muscles are supplied by the posterior primary divisions of the spinal nerves.

**Actions.**—The *Sacrospinalis* and its upward continuations and the *Spinales* serve to maintain the vertebral column in the erect posture; they also serve to bend the trunk backward when it is required to counterbalance the influence of any weight at the front of the body—as, for instance, when a heavy weight is suspended from the neck, or when there is any great abdominal distension, as in pregnancy or dropsy; the peculiar gait under such circumstances depends upon the vertebral column being drawn backward, by the counterbalancing action of the *Sacrospinales*. The muscles which form the continuation of the *Sacrospinales* on to the head and neck steady those parts and fix them in the upright position. If the *Iliocostalis lumborum* and *Longissimus* *torsi* of one side act, they serve to draw down the chest and vertebral column to the corresponding side. The *Iliocostales cervicis*, taking their fixed points from the cervical vertebrae, elevate those ribs to which they are attached; taking their fixed points from the ribs, both muscles help to extend the neck; while one muscle bends the neck to its own side. When both *Longissimi cervicis* act from below, they bend the neck backward. When both *Longissimi capitis* act from below, they bend the head backward; while, if only one muscle acts, the face is turned to the side on which the muscle is acting, and then the head is bent to the shoulder. The two *Recti* draw the head backward. The *Rectus capitis posterior major*, owing to its obliquity, rotates the skull, with the atlas, around the odontoid process, turning the face to the same side. The *Multifidus* acts successively upon the different parts of the column; thus, the sacrum furnishes a fixed point from which the fasciculi of this muscle acts upon the lumbar region; which in turn becomes the fixed point for the fasciculi moving the thoracic region, and so on throughout the entire length of the column. The *Multifidus* also serves to rotate the column, so that the front of the trunk is turned to the side opposite to that from which the muscle acts, this muscle being assisted in its action by the *Obliquus externus abdominis*. The *Obliquus capitis superior* draws the head backward and to its own side. The *Obliquus inferior* rotates the atlas, and with it the skull, around the odontoid process, turning the face to the same side. When the *Semispinales* of the two sides act together, they help to extend the vertebral column; when the muscles of only one side act, they rotate the thoracic and cervical parts of the column, turning the body to the opposite side. The *Semispinales capitis* draw the head directly backward; if one muscle acts, it draws the head to one side, and rotates it so that the face is turned to the opposite side. The *Interspinales* by approximating the spinous processes help to extend the column. The *Intertransversarii* approximate the transverse processes, and help to bend the column to one side. The *Rotatores* assist the *Multifidus* to rotate the vertebral column, so that the front of the trunk is turned to the side opposite to that from which the muscles act.

**Applied Anatomy.**—In cases of tuberculous caries of the vertebral bodies, and in other diseases affecting the vertebral column, rigidity of the spinal muscles is one of the earliest and most constant symptoms. A child with commencing spinal disease always maintains the affected portion of the column in a state of absolute rigidity, to prevent the inflamed structures from being moved against each other; this is one of the best examples of nature's method of producing rest of the affected part.

### III. THE MUSCLES OF THE THORAX.

The muscles belonging to this group are the

Intercostales externi.	Levatores costarum.
Intercostales interni.	Serratus posterior superior.
Subcostales.	Serratus posterior inferior.
Transversus thoracis.	Diaphragma.

**Intercostal Fasciæ.**—In each intercostal space thin but firm layers of fascia cover the outer surface of the *Intercostalis externus* and the inner surface of the *Intercostalis internus*; and a third, more delicate layer, is interposed between the two planes of muscular fibres. They are best marked in those situations where the muscular fibres are deficient, as between the *Intercostales externi* and sternum in front, and between the *Intercostales interni* and vertebral column behind.

The **Intercostales** (*Intercostal muscles*) (Fig. 520) are two thin planes of muscular and tendinous fibres occupying each of the intercostal spaces. They are named **external** and **internal** from their surface relations—the external being superficial to the internal.

The **Intercostales externi** (*External intercostals*) are *eleven* in number on either side. They extend from the tubercles of the ribs behind, to the cartilages of the ribs in front, where they end in thin membranes, the **anterior intercostal membranes**, which are continued forward to the sternum. Each *arises* from the lower border of a rib, and is *inserted* into the upper border of the rib below. In the two lower spaces they extend to the ends of the cartilages, and in the upper two or three spaces they do not quite reach the ends of the ribs. They are thicker than the *Intercostales interni*, and their fibres are directed obliquely downward and lateralward on the back of the thorax, and downward, forward, and medialward on the front.

The **Intercostales interni** (*Internal intercostals*) are also *eleven* in number on either side. They commence anteriorly at the sternum, in the interspaces between the cartilages of the true ribs, and at the anterior extremities of the cartilages of the false ribs, and extend backward as far as the angles of the ribs, whence they are continued to the vertebral column by thin aponeuroses, the **posterior intercostal membranes**. Each *arises* from the ridge on the inner surface of a rib, as well as from the corresponding costal cartilage, and is *inserted* into the upper border of the rib below. Their fibres are also directed obliquely, but pass in a direction opposite to those of the *Intercostales externi*.

The **Subcostales** (*Infracostales*) consist of muscular and aponeurotic fasciculi, which are usually well-developed only in the lower part of the thorax; each *arises* from the inner surface of one rib near its angle, and is *inserted* into the inner surface of the second or third rib below. Their fibres run in the same direction as those of the *Intercostales interni*.

The **Transversus thoracis** (*Triangularis sterni*) is a thin plane of muscular and tendinous fibres, situated upon the inner surface of the front wall of the chest (Fig. 496). It *arises* on either side from the lower third of the posterior surface of the body of the sternum, from the posterior surface of the xiphoid process, and from the sternal ends of the costal cartilages of the lower three or four true ribs. Its fibres diverge upward and lateralward, to be *inserted* by slips into the



lower borders and inner surfaces of the costal cartilages of the second, third, fourth, fifth, and sixth ribs. The lowest fibres of this muscle are horizontal in their direction, and are continuous with those of the *Transversus abdominis*; the intermediate fibres are oblique, while the highest are almost vertical. This muscle varies in its attachments, not only in different subjects, but on opposite sides of the same subject.

The **Levatores costarum** (Fig. 495), twelve in number on either side, are small tendinous and fleshy bundles, which arise from the ends of the transverse processes of the seventh cervical and upper eleven thoracic vertebrae; they pass obliquely downward and lateralward, like the fibres of the *Intercostales externi*, and each is inserted into the outer surface of the rib immediately below the vertebra from which it takes origin, between the tubercle and the angle (*Levatores costarum breves*). Each of the four lower muscles divides into two fasciculi, one of which is inserted as above described; the other passes down to the second rib below its origin (*Levatores costarum longi*).

The **Serratus posterior superior** (*Serratus posticus superior*) is a thin, quadrilateral muscle, situated at the upper and back part of the thorax. It arises by a thin and broad aponeurosis from the lower part of the ligamentum nuchae, from the spinous processes of the seventh cervical and upper two or three thoracic vertebrae and from the supraspinal ligament. Inclining downward and lateralward it becomes muscular, and is inserted, by four fleshy digitations, into the upper borders of the second, third, fourth, and fifth ribs, a little beyond their angles.

The **Serratus posterior inferior** (*Serratus posticus inferior*) (Fig. 516) is situated at the junction of the thoracic and lumbar regions: it is of an irregularly quadrilateral form, broader than the preceding, and separated from it by a wide interval. It arises by a thin aponeurosis from the spinous processes of the lower two thoracic and upper two or three lumbar vertebrae, and from the supraspinal ligament. Passing obliquely upward and lateralward, it becomes fleshy, and divides into four flat digitations, which are inserted into the inferior borders of the lower four ribs, a little beyond their angles. The thin aponeurosis of origin is intimately blended with the lumbodorsal fascia.

**Nerves.**—The muscles of this group are supplied by the intercostal nerves.

The **Diaphragma** (*Diaphragm*) (Figs. 497, 498) is a dome-shaped musculo-fibrous septum which separates the thoracic from the abdominal cavity, its convex upper surface forming the floor of the former, and its concave under surface the roof of the latter. Its peripheral part consists of muscular fibres which take origin from the circumference of the thoracic outlet and converge to be inserted into a central tendon.




FIG. 496.—Posterior surface of sternum and costal cartilages, showing *Transversus thoracis*.



The muscular fibres may be grouped according to their origins into three parts—sternal, costal, and lumbar. The **sternal part** arises by two fleshy slips from




FIG. 497.—Posterior half of Diaphragm. (Modified from model by His.)




FIG. 498.—The Diaphragm. Under surface

the back of the xiphoid process; the **costal part** from the inner surfaces of the cartilages and adjacent portions of the lower six ribs on either side, interdigitating with the *Transversus abdominis*; and the **lumbar part** from aponeurotic arches, named the lumbocostal arches, and from the lumbar vertebræ by two pillars or **crura**. There are two lumbocostal arches, a medial and a lateral, on either side.

The **Medial Lumbocostal Arch** (*arcus lumbocostalis medialis* [Halleri]; *internal arcuate ligament*) is a tendinous arch in the fascia covering the upper part of the *Psoas major*; medially, it is continuous with the lateral tendinous margin of the corresponding crus, and is attached to the side of the body of the first or second lumbar vertebra; laterally, it is fixed to the front of the transverse process of the first and, sometimes also, to that of the second lumbar vertebra.

The **Lateral Lumbocostal Arch** (*arcus lumbocostalis lateralis* [Halleri]; *external arcuate ligament*) arches across the upper part of the *Quadratus lumborum*, and is attached, medially, to the front of the transverse process of the first lumbar vertebra, and, laterally, to the tip and lower margin of the twelfth rib.

**The Crura.**—At their origins the crura are tendinous in structure, and blend with the anterior longitudinal ligament of the vertebral column. The **right crus**, larger and longer than the left, *arises* from the anterior surfaces of the bodies and intervertebral fibrocartilages of the upper three lumbar vertebræ, while the **left crus** *arises* from the corresponding parts of the upper two only. The medial tendinous margins of the crura pass forward and medialward, and meet in the middle line to form an arch across the front of the aorta; this arch is often poorly defined.

From this series of origins the fibres of the Diaphragma converge to be inserted into the central tendon. The fibres arising from the xiphoid process are very short, and occasionally aponeurotic; those from the medial and lateral lumbocostal arches, and more especially those from the ribs and their cartilages, are longer, and describe marked curves as they ascend and converge to their insertion. The fibres of the crura diverge as they ascend, the most lateral being directed upward and lateralward to the central tendon. The medial fibres of the right crus ascend on the left side of the oesophageal hiatus, and occasionally a fasciculus of the left crus crosses the aorta and runs obliquely through the fibres of the right crus toward the vena caval foramen (Low<sup>1</sup>).

**The Central Tendon.**—The central tendon of the Diaphragma is a thin but strong aponeurosis situated near the centre of the vault formed by the muscle, but somewhat closer to the front than to the back of the thorax, so that the posterior muscular fibres are the longer. It is situated immediately below the pericardium, with which it is partially blended. It is shaped somewhat like a trefoil leaf, consisting of three divisions or leaflets separated from one another by slight indentations. The right leaflet is the largest, the middle, directed toward the xiphoid process, the next in size, and the left the smallest. In structure the tendon is composed of several planes of fibres, which intersect one another at various angles and unite into straight or curved bundles—an arrangement which gives it additional strength.

**Openings in the Diaphragma.**—The Diaphragma is pierced by a series of apertures to permit of the passage of structures between the thorax and abdomen. Three large openings—the **aortic**, the **oesophageal**, and the **vena caval**—and a series of smaller ones are described.

The **aortic hiatus** is the lowest and most posterior of the large apertures; it lies at the level of the twelfth thoracic vertebra. Strictly speaking, it is not an aperture in the Diaphragma but an osseoaponeurotic opening between it and the vertebral column, and therefore behind the Diaphragma; occasionally some tendinous fibres prolonged across the bodies of the vertebræ from the medial parts of the lower ends of the crura pass behind the aorta, and thus convert the hiatus into a fibrous ring.

<sup>1</sup> *Journal of Anatomy and Physiology*, vol. xlii.

The hiatus is situated slightly to the left of the middle line, and is bounded in front by the crura, and behind by the body of the first lumbar vertebra. Through it pass the aorta, the azygos vein, and the thoracic duct; occasionally the azygos vein is transmitted through the right crus.

The **oesophageal hiatus** is situated in the muscular part of the Diaphragma at the level of the tenth thoracic vertebra, and is elliptical in shape. It is placed above, in front, and a little to the left of the aortic hiatus, and transmits the oesophagus, the vagus nerves, and some small oesophageal arteries.

The **vena caval foramen** is the highest of the three, and is situated about the level of the fibrocartilage between the eighth and ninth thoracic vertebræ. It is quadrilateral in form, and is placed at the junction of the right and middle leaflets of the central tendon, so that its margins are tendinous. It transmits the inferior vena cava, the wall of which is adherent to the margins of the opening, and some branches of the right phrenic nerve.

Of the **lesser apertures**, two in the right crus transmit the greater and lesser right splanchnic nerves; three in the left crus give passage to the greater and lesser left splanchnic nerves and the hemiazygos vein. The gangliated trunks of the sympathetic usually enter the abdominal cavity behind the Diaphragma, under the medial lumbocostal arches. The structures piercing the crura are sometimes utilized to divide each crus into three parts—medial, intermediate, and lateral. Between the medial and intermediate crura pass the hemiazygos vein and the splanchnic nerves; between the intermediate crus and the lateral crus (which consists of the fibres rising from the medial lumbocostal arch) the gangliated trunks pass.

On either side two small intervals exist at which the muscular fibres of the Diaphragma are deficient and are replaced by areolar tissue. One between the sternal and costal parts transmits the superior epigastric branch of the internal mammary artery and some lymphatics from the abdominal wall and convex surface of the liver. The other, between the fibres springing from the medial and lateral lumbocostal arches, is less constant; when this interval exists, the upper and back part of the kidney is separated from the pleura by areolar tissue only.

**Relations.**—The upper surface of the Diaphragma is in relation with three serous membranes, viz., on either side the pleura, which separates it from the base of the corresponding lung, and on the middle leaflet of the central tendon the pericardium, which intervenes between it and the heart. The central portion lies on a slightly lower level than the summits of the lateral portions. The greater part of the under surface is covered by the peritoneum. The right side is accurately moulded over the convex surface of the right lobe of the liver, the right kidney, and right suprarenal gland; the left over the left lobe of the liver, the fundus of the stomach, the spleen, the left kidney, and left suprarenal gland.

**Nerves.**—The Diaphragma is supplied by the phrenic and lower intercostal nerves.

**Actions.**—The Diaphragma is the principal muscle of inspiration, and presents the form of a dome concave toward the abdomen. The central part of the dome is tendinous, and the pericardium is attached to its upper surface; the circumference is muscular. During inspiration the lowest ribs are fixed, and from these and the crura the muscular fibres contract and draw downward and forward the central tendon with the attached pericardium. In this movement the curvature of the Diaphragma is scarcely altered, the dome moving downward nearly parallel to its original position and pushing before it the abdominal viscera. The descent of the abdominal viscera is permitted by the elasticity of the abdominal wall, but the limit of this is soon reached. The central tendon applied to the abdominal viscera then becomes a fixed point for the action of the Diaphragma, the effect of which is to elevate the lower ribs and through them to push forward the body of the sternum and the upper ribs. The right cupola of the Diaphragma, lying on the liver, has a greater resistance to overcome than the left, which lies over the stomach, but to compensate for this the right crus and the fibres of the right side generally are stronger than those of the left.

In all expulsive acts the Diaphragma is called into action to give additional power to each expulsive effort. Thus, before sneezing, coughing, laughing, crying, or vomiting, and previous to the expulsion of urine or feces, or of the fetus from the uterus, a deep inspiration takes place. The height of the Diaphragma is constantly varying during respiration; it also varies with the

degree of distension of the stomach and intestines and with the size of the liver. After a forced expiration the right cupola is on a level in front with the fourth costal cartilage, at the side with the fifth, sixth, and seventh ribs, and behind with the eighth rib; the left cupola is a little lower than the right. Halls Dally<sup>1</sup> states that the absolute range of movement between deep inspiration and deep expiration averages in the male and female 30 mm. on the right side and 28 mm. on the left; in quiet respiration the average movement is 12.5 mm. on the right side and 12 mm. on the left.

Skiagraphy shows that the height of the Diaphragma in the thorax varies considerably with the position of the body. It stands highest when the body is horizontal and the patient on his back, and in this position it performs the largest respiratory excursions with normal breathing. When the body is erect the dome of the Diaphragma falls, and its respiratory movements become smaller. The dome falls still lower when the sitting posture is assumed, and in this position its respiratory excursions are smallest. These facts may, perhaps, explain why it is that patients suffering from severe dyspnoea are most comfortable and least short of breath when they sit up. When the body is horizontal and the patient on his side, the two halves of the Diaphragma do not behave alike. The uppermost half sinks to a level lower even than when the patient sits, and moves little with respiration; the lower half rises higher in the thorax than it does when the patient is supine, and its respiratory excursions are much increased. In unilateral disease of the pleura or lungs analogous interference with the position or movement of the diaphragma can generally be observed skiagraphically.

It appears that the position of the Diaphragma in the thorax depends upon three main factors, viz.: (1) the elastic retraction of the lung tissue, tending to pull it upward; (2) the pressure exerted on its under surface by the viscera; this naturally tends to be a negative pressure, or downward suction, when the patient sits or stands, and positive, or an upward pressure, when he lies (3) the intra-abdominal tension due to the abdominal muscles. These are in a state of contraction in the standing position and not in the sitting; hence the Diaphragma, when the patient stands, is pushed up higher than when he sits.

The Intercostales interni and externi have probably no action in moving the ribs. They contract simultaneously and form strong elastic supports which prevent the intercostal spaces being pushed out or drawn in during respiration. The anterior portions of the Intercostales interni probably have an additional function in keeping the sternocostal and interchondral joint surfaces in apposition, the posterior parts of the Intercostales externi performing a similar function for the costovertebral articulations. The Levatores costarum being inserted near the fulcra of the ribs can have little action on the ribs; they act as rotators and lateral flexors of the vertebral column. The Transversus thoracis draws down the costal cartilages, and is therefore a muscle of expiration.

The Serrati are respiratory muscles. The Serratus posterior superior elevates the ribs and is therefore an inspiratory muscle. The Serratus posterior inferior draws the lower ribs downward and backward, and thus elongates the thorax; it also fixes the lower ribs, thus assisting the inspiratory action of the Diaphragma and resisting the tendency it has to draw the lower ribs upward and forward. It must therefore be regarded as a muscle of inspiration.

**Mechanism of Respiration.**—The respiratory movements must be examined during (a) quiet respiration, and (b) deep respiration.

**Quiet Respiration.**—The first and second pairs of ribs are fixed by the resistance of the cervical structures; the last pair, and through it the eleventh, by the Quadratus lumborum. The other ribs are elevated, so that the first two intercostal spaces are diminished while the others are increased in width. It has already been shown (p. 401) that elevation of the third, fourth, fifth, and sixth ribs leads to an increase in the antero-posterior and transverse diameters of the thorax; the vertical diameter is increased by the descent of the diaphragmatic dome so that the lungs are expanded in all directions except backward and upward. Elevation of the eighth, ninth, and tenth ribs is accompanied by a lateral and backward movement, leading to an increase in the transverse diameter of the upper part of the abdomen; the elasticity of the anterior abdominal wall allows a slight increase in the antero-posterior diameter of this part, and in this way the decrease in the vertical diameter of the abdomen is compensated and space provided for its displaced viscera. Expiration is effected by the elastic recoil of its walls and by the action of the abdominal muscles, which push back the viscera displaced downward by the Diaphragma.

**Deep Respiration.**—All the movements of quiet respiration are here carried out, but to a greater extent. In deep inspiration the shoulders and the vertebral borders of the scapulæ are fixed and the limb muscles, Trapezius, Serratus anterior, Pectorales, and Latissimus dorsi, are called into play. The Scaleni are in strong action, and the Sternocleidomastoidei also assist when the head is fixed by drawing up the sternum and by fixing the clavicles. The first rib is therefore no longer stationary, but, with the sternum, is raised; with it all the other ribs except the last are raised to a higher level. In conjunction with the increased descent of the Diaphragma this provides for a considerable augmentation of all the thoracic diameters. The anterior abdomi-

<sup>1</sup> Journal of Anatomy and Physiology, 1908, vol. xliii.



nal muscles come into action so that the umbilicus is drawn upward and backward, but this allows the Diaphragma to exert a more powerful influence on the lower ribs; the transverse diameter of the upper part of the abdomen is greatly increased and the subcostal angle opened out. The deeper muscles of the back, *e. g.*, the *Serrati posteriores superiores* and the *Sacrospinales* and their continuations, are also brought into action; the thoracic curve of the vertebral column is partially straightened, and the whole column, above the lower lumbar vertebræ, drawn backward. This increases the antero-posterior diameters of the thorax and upper part of the abdomen and widens the intercostal spaces. Deep expiration is effected by the recoil of the walls and by the contraction of the antero-lateral muscles of the abdominal wall, and the *Serrati posteriores inferiores* and *Transversus thoracis*.

Halls Dally (*op. cit.*) gives the following figures as representing the average changes which occur during deepest possible respiration. The manubrium sterni moves 30 mm. in an upward and 14 mm. in a forward direction; the width of the subcostal angle, at a level of 30 mm. below the articulation between the body of the sternum and the xiphoid process, is increased by 26 mm.; the umbilicus is retracted and drawn upward for a distance of 13 mm.

#### IV. THE MUSCLES AND FASCIAE OF THE ABDOMEN.

The muscles of the abdomen may be divided into two groups: (1) the **antero-lateral muscles**; (2) the **posterior muscles**.

##### 1. The Antero-lateral Muscles of the Abdomen.

The muscles of this group are:

Obliquus externus.  
Obliquus internus.

Transversus.  
Rectus.

Pyramidalis.

**Dissection** (Fig. 499).—To dissect the abdominal muscles, make a vertical incision from the ensiform cartilage to the symphysis pubis; a second incision from the umbilicus obliquely upward and outward to the outer surface of the thorax, as high as the lower border of the fifth or sixth rib; and a third, commencing midway between the umbilicus and pubes, transversely outward to the anterior superior iliac spine, and along the crest of the ilium as far as its posterior third. Then reflect the three flaps included between these incisions from within outward, in the lines of direction of the muscle fibres. If necessary, the abdominal cavity may be made tense by inflating the peritoneal cavity through the umbilicus.




FIG. 499.—Dissection of abdomen.

**The Superficial Fascia.**—The superficial fascia of the abdomen consists, over the greater part of the abdominal wall, of a single layer containing a variable amount of fat; but near the groin it is easily divisible into two layers, between which are found the superficial vessels and nerves and the superficial inguinal lymph glands.

The **superficial layer** (*fascia of Camper*) is thick, areolar in texture, and contains in its meshes a varying quantity of adipose tissue. Below, it passes over the inguinal ligament, and is continuous with the superficial fascia of the thigh. In the male, Camper's fascia is continued over the penis and outer surface of the spermatic cord to the scrotum, where it helps to form the dartos. As it passes to the scrotum it changes its characteristics, becoming thin, destitute of adipose tissue, and of a pale reddish color, and in the scrotum it acquires some involuntary muscular fibres. From the scrotum it may be traced backward into continuity with the superficial fascia of the

perineum. In the female, Camper's fascia is continued from the abdomen into the labia majora.

The **deep layer** (*fascia of Scarpa*) is thinner and more membranous in character than the superficial, and contains a considerable quantity of yellow elastic fibres. It is loosely connected by areolar tissue to the aponeurosis of the Obliquus externus abdominis, but in the middle line it is more intimately adherent to the linea alba and to the symphysis pubis, and is prolonged on to the dorsum of the penis, forming the fundiform ligament; above, it is continuous with the superficial fascia over the rest of the trunk; below and laterally, it blends with the fascia lata of the thigh a little below the inguinal ligament; medially and below, it is continued over the penis and spermatic cord to the scrotum, where it helps to form the dartos. From the scrotum it may be traced backward into continuity with the deep layer of the superficial fascia of the perineum (*fascia of Colles*). In the female, it is continued into the labia majora and thence to the fascia of Colles.

The **Obliquus externus abdominis** (*External or descending oblique muscle*) (Fig. 500), situated on the lateral and anterior parts of the abdomen, is the largest and the most superficial of the three flat muscles in this region. It is broad, thin, and irregularly quadrilateral, its muscular portion occupying the side, its aponeurosis the anterior wall of the abdomen. It *arises*, by eight fleshy digitations, from the external surfaces and inferior borders of the lower eight ribs; these digitations are arranged in an oblique line which runs downward and backward, the upper ones being attached close to the cartilages of the corresponding ribs, the lowest to the apex of the cartilage of the last rib, the intermediate ones to the ribs at some distance from their cartilages. The five superior serrations increase in size from above downward, and are received between corresponding processes of the Serratus anterior; the three lower ones diminish in size from above downward and receive between them corresponding processes from the Latissimus dorsi. From these attachments the fleshy fibres proceed in various directions. Those from the lowest ribs pass nearly vertically downward, and are inserted into the anterior half of the outer lip of the iliac crest; the middle and upper fibres, directed downward and forward, end in an aponeurosis, opposite a line drawn from the prominence of the ninth costal cartilage to the anterior superior iliac spine.

The **aponeurosis of the Obliquus externus abdominis** is a thin but strong membranous structure, the fibres of which are directed downward and medialward. It is joined with that of the opposite muscle along the middle line, and covers the whole of the front of the abdomen; *above*, it is covered by and gives origin to the lower fibres of the Pectoralis major; *below*, its fibres are closely aggregated together, and extend obliquely across from the anterior superior iliac spine to the pubic tubercle and the pectineal line. In the middle line, it interlaces with the aponeurosis of the opposite muscle, forming the **linea alba**, which extends from the xiphoid process to the symphysis pubis.

That portion of the aponeurosis which extends between the anterior superior iliac spine and the pubic tubercle is a thick band, folded inward, and continuous below with the fascia lata; it is called the **inguinal ligament**. The portion which is reflected from the inguinal ligament at the pubic tubercle is attached to the pectineal line and is called the **lacunar ligament**. From the point of attachment of the latter to the pectineal line, a few fibres pass upward and medialward, behind the medial crus of the subcutaneous inguinal ring, to the linea alba; they diverge as they ascend, and form a thin triangular fibrous band which is called the **reflected inguinal ligament**.

In the aponeurosis of the Obliquus externus, immediately above the crest of the pubis, is a triangular opening, the **subcutaneous inguinal ring**, formed by a separation of the fibres of the aponeurosis in this situation.

The following structures require further description, viz., the **subcutaneous**



inguinal ring, the intercrural fibres and fascia, and the inguinal, lacunar, and reflected inguinal ligaments.

**The Subcutaneous Inguinal Ring** (*annulus inguinalis subcutaneus*; *external abdominal ring*) (Fig. 501).—The subcutaneous inguinal ring is an interval in the aponeurosis of the Obliquus externus, just above and lateral to the crest of the pubis. The aperture is oblique in direction, somewhat triangular in form, and corresponds with the course of the fibres of the aponeurosis. It usually measures




FIG. 500.—The Obliquus externus abdominis.

from base to apex about 2.5 cm., and transversely about 1.25 cm. It is bounded *below* by the crest of the pubis; on either *side* by the margins of the opening in the aponeurosis, which are called the **crura of the ring**; and *above*, by a series of curved **intercrural fibres**. The **inferior crus** (*external pillar*) is the stronger and is formed by that portion of the inguinal ligament which is inserted into the pubic tubercle; it is curved so as to form a kind of groove, upon which, in the male, the spermatic cord rests. The **superior crus** (*internal pillar*) is a broad, thin, flat band, attached to the front of the symphysis pubis and interlacing with its fellow of the opposite side.

The subcutaneous inguinal ring gives passage to the spermatic cord and ilio-inguinal nerve in the male, and to the round ligament of the uterus and the ilioinguinal nerve in the female; it is much larger in men than in women, on account of the large size of the spermatic cord.

**The Intercrural Fibres** (*fibrae intercrurales; intercolumnar fibres*).—The intercrural fibres are a series of curved tendinous fibres, which arch across the lower part of the aponeurosis of the Obliquus externus, describing curves with the convexities downward. They have received their name from stretching across between the two crura of the subcutaneous inguinal ring, and they are much thicker and stronger




FIG. 501.—The subcutaneous inguinal ring.

at the inferior crus, where they are connected to the inguinal ligament, than superiorly, where they are inserted into the linea alba. The intercrural fibres increase the strength of the lower part of the aponeurosis, and prevent the divergence of the crura from one another; they are more strongly developed in the male than in the female.

As they pass across the subcutaneous inguinal ring, they are connected together by delicate fibrous tissue, forming a fascia, called the **intercrural fascia**. This intercrural fascia is continued down as a tubular prolongation around the spermatic cord and testis, and encloses them in a sheath; hence it is also called the **external spermatic fascia**. The subcutaneous inguinal ring is seen as a distinct aperture only after the intercrural fascia has been removed.

**The Inguinal Ligament** (*ligamentum inguinale* [Poupart]; *Poupart's ligament*) (Fig. 502).—The inguinal ligament is the lower border of the aponeurosis of the

**Obliquus externus**, and extends from the anterior superior iliac spine to the pubic tubercle. From this latter point it is reflected backward and lateralward to be attached to the pectineal line for about 1.25 cm., forming the **lacunar ligament**. Its general direction is convex downward toward the thigh, where it is continuous with the fascia lata. Its lateral half is rounded, and oblique in direction; its medial half gradually widens at its attachment to the pubis, is more horizontal in direction, and lies beneath the spermatic cord.

**The Lacunar Ligament** (*ligamentum lacunare* [Gimbernat]; *Gimbernat's ligament*) (Fig. 502).—The lacunar ligament is that part of the aponeurosis of the **Obliquus externus** which is reflected backward and lateralward, and is attached to the pectineal line. It is about 1.25 cm. long, larger in the male than in the female, almost horizontal in direction in the erect posture, and of a triangular form with the base




FIG. 502.—The inguinal and lacunar ligaments.

directed lateralward. Its base is concave, thin, and sharp, and forms the medial boundary of the femoral ring. Its apex corresponds to the pubic tubercle. Its posterior margin is attached to the pectineal line, and is continuous with the pectineal fascia. Its anterior margin is attached to the inguinal ligament. Its surfaces are directed upward and downward.

**The Reflected Inguinal Ligament** (*ligamentum inguinale reflexum* [Collesi]; *triangular fascia*).—The reflected inguinal ligament is a layer of tendinous fibres of a triangular shape, formed by an expansion from the lacunar ligament and the inferior crus of the subcutaneous inguinal ring. It passes medialward behind the spermatic cord, and expands into a somewhat fan-shaped band, lying behind the superior crus of the subcutaneous inguinal ring, and in front of the inguinal aponeurotic falx, and interlaces with the ligament of the other side of the linea alba.

**Ligament of Cooper.**—This is a strong fibrous band, which was first described by Sir Astley Cooper. It extends lateralward from the base of the lacunar ligament (Fig. 502) along the pectineal line, to which it is attached. It is strengthened by the pectineal fascia, and by a lateral expansion from the lower attachment of the linea alba (*admiculum lineae albae*).



**Dissection.**—Detach the Obliquus externus abdominis by dividing it across, just in front of its attachment to the ribs, as far as its posterior border, and separate it below from the crest of the ilium as far as the anterior superior spine; then separate the muscle carefully from the Obliquus internus abdominis, which lies beneath, and turn it toward the opposite side.

The **Obliquus internus abdominis** (*Internal or ascending oblique muscle*) (Fig. 503), thinner and smaller than the Obliquus externus, beneath which it lies, is of an irregularly quadrilateral form, and situated at the lateral and anterior parts of the abdomen. It *arises*, by fleshy fibres, from the lateral half of the grooved upper surface of the inguinal ligament, from the anterior two-thirds of the middle lip of the iliac crest, and from the posterior lamella of the lumbodorsal fascia. From this origin the fibres diverge; those from the inguinal ligament, few in number




FIG. 503.—The Obliquus internus abdominis.

and paler in color than the rest, arch downward and medialward across the spermatic cord in the male and the round ligament of the uterus in the female, and, becoming tendinous, are *inserted*, conjointly with those of the Transversus, into the crest of the pubis and medial part of the pectineal line behind the lacunar ligament, forming what is known as the **inguinal aponeurotic falx**. Those from the anterior third of the iliac origin are horizontal in their direction, and, becoming tendinous along the lower fourth of the linea semilunaris, pass in front of the Rectus abdominis to be inserted into the linea alba. Those arising from the middle third of the iliac origin run obliquely upward and medialward, and end in an aponeurosis; this divides at the lateral border of the Rectus into two lamellæ, which are continued forward, one in front of and the other behind this muscle, to the linea alba:

the posterior lamella has an attachment to the cartilages of the seventh, eighth, and ninth ribs. The most posterior fibres pass almost vertically upward, to be inserted into the inferior borders of the cartilages of the three lower ribs, being continuous with the *Intercostales interni*.

The **Cremaster** (Fig. 504) is a thin muscular layer, composed of a number of fasciculi which arise from the middle of the inguinal ligament where its fibres are continuous with those of the *Obliquus internus* and also occasionally with the *Transversus*. It passes along the lateral side of the spermatic cord, descends with it through the subcutaneous inguinal ring upon the front and sides of the cord, and forms a series of loops which differ in thickness and length in different subjects. At the upper part of the cord the loops are short, but they become in succession longer and longer, the longest reaching down as low as the testis, where a few are inserted into the tunica vaginalis. These loops are united together by areolar tissue, and form a thin covering over the cord and testis, the **cremasteric fascia**. The fibres ascend along the medial side of the cord, and are inserted by a small pointed tendon into the tubercle and crest of the pubis and into the front of the sheath of the *Rectus abdominis*.




FIG. 504.—The Cremaster.

**Dissection.**—Detach the *Obliquus internus abdominis* in order to expose the *Transversus abdominis* beneath. This may be effected by dividing the muscle, *above*, at its attachment to the ribs; *below*, at its connection with the inguinal ligament and the crest of the ilium;

and *behind*, by a vertical incision extending from the last rib to the crest of the ilium. The muscle should previously be made tense by drawing upon it with the fingers of the left hand, and if its division be carefully effected, the cellular interval between it and the *Transversus abdominis*, as well as the direction of the fibres of the latter muscle, will afford a clear guide to their separation; along the crest of the ilium the circumflex iliac vessels are interposed between them, and form an important guide in separating them. The muscle should then be thrown inward toward the linea alba.

The **Transversus abdominis** (*Transversalis muscle*) (Fig. 505), so called from the direction of its fibres, is the most internal of the flat muscles of the abdomen, being placed immediately beneath the *Obliquus internus*. It *arises*, by fleshy fibres, from the lateral third of the inguinal ligament, from the anterior three-fourths of the inner lip of the iliac crest, from the inner surfaces of the cartilages of the lower six ribs, interdigitating with the *Diaphragma*, and from the *lumbodorsal fascia*. The muscle ends in front in a broad aponeurosis, the lower fibres of which curve downward and medialward, and are *inserted*, together with those of the *Obliquus internus*, into the crest of the pubis and pectineal line, forming the inguinal aponeurotic falx. Throughout the rest of its extent the aponeurosis passes horizontally to the middle line, and is inserted into the linea alba; its upper three-fourths lie behind the *Rectus* and blend with the posterior lamella of the aponeurosis of the *Obliquus internus*; its lower fourth is in front of the *Rectus*.

The **inguinal aponeurotic falx** (*falx aponeurotica inguinalis*; *conjoined tendon of Internal oblique and Transversalis muscle*) of the Obliquus internus and Transversus is mainly formed by the lower part of the tendon of the Transversus, and is inserted into the crest of the pubis and pectineal line immediately behind the subcutaneous inguinal ring, serving to protect what would otherwise be a weak point in the abdominal wall. Lateral to the falx is a ligamentous band con-




FIG. 505.—The Transversus abdominis, Rectus abdominis, and Pyramidalis.

nected with the lower margin of the Transversus and extending down behind the inferior epigastric artery to the superior ramus of the pubis; it is termed the **interfoveolar ligament of Hesselbach** (Fig. 506) and sometimes contains a few muscular fibres.

**Dissection.**—To expose the Rectus abdominis muscle, open its sheath by a vertical incision extending from the costal arch to the pubis, and then reflect the two portions from the surface of the muscle, which is easily done, excepting at the lineae transversae, where so close an adhesion exists that the greatest care is requisite in separating them. Now raise the outer edge



of the muscle, in order to examine the posterior layer of the sheath. By dividing the muscle in the centre, and turning its lower part downward, the point where the posterior wall of the sheath terminates in a thin curved margin will be seen.

The **Rectus abdominis** (Fig. 505) is a long flat muscle, which extends along the whole length of the front of the abdomen, and is separated from its fellow of the opposite side by the linea alba. It is much broader, but thinner, above than below, and *arises* by two tendons; the lateral or larger is attached to the crest of the pubis, the medial interlaces with its fellow of the opposite side, and is connected with the ligaments covering the front of the symphysis pubis. The muscle is *inserted* by three portions of unequal size into the cartilages of the fifth, sixth, and seventh ribs. The upper portion, attached principally to the cartilage of the fifth rib, usually has some fibres of insertion into the anterior extremity of the rib itself. Some fibres are occasionally connected with the costoxiphoid ligaments, and the side of the xiphoid process.




FIG. 506.—The interfoveolar ligament, seen from in front. (Modified from Braune.

The Rectus is crossed by fibrous bands, three in number, which are named the **tendinous inscriptions**; one is usually situated opposite the umbilicus, one at the extremity of the xiphoid process, and the third about midway between the xiphoid process and the umbilicus. These inscriptions pass transversely or obliquely across the muscle in a zigzag course; they rarely extend completely through its substance and may pass only halfway across it; they are intimately adherent in front to the sheath of the muscle. Sometimes one or two additional inscriptions, generally incomplete, are present below the umbilicus.

The Rectus is enclosed in a sheath (Fig. 507) formed by the aponeuroses of the Obliqui and Transversus, which are arranged in the following manner. At the lateral margin of the Rectus, the aponeurosis of the Obliquus internus divides into two lamellæ, one of which passes in front of the Rectus, blending with the aponeurosis of the Obliquus externus, the other, behind it, blending with the aponeurosis of the Transversus, and these, joining again at the medial border of the Rectus, are inserted into the linea alba. This arrangement of the aponeurosis exists from the costal margin to midway between the umbilicus and symphysis pubis, where

the posterior wall of the sheath ends in a thin curved margin, the *linea semicircularis*, the concavity of which is directed downward: below this level the aponeuroses of all three muscles pass in front of the Rectus. The Rectus, in the situation where its sheath is deficient below, is separated from the peritoneum by the transversalis fascia (Fig. 508). Since the tendons of the Obliquus internus and Transversus only reach as high as the costal margin, it follows that above this level the sheath of the Rectus is deficient behind, the muscle resting directly on the cartilages of the ribs, and being covered merely by the tendon of the Obliquus externus.




FIG. 507.—Diagram of sheath of Rectus.

The *Pyramidalis* (Fig. 505) is a small triangular muscle, placed at the lower part of the abdomen, in front of the Rectus, and contained in the sheath of that muscle. It arises by tendinous fibres from the front of the pubis and the anterior pubic ligament; the fleshy portion of the muscle passes upward, diminishing in size as it ascends, and ends by a pointed extremity which is inserted into the linea alba, midway between the umbilicus and pubis. This muscle may be wanting on one or both sides; the lower end of the Rectus then becomes proportionately increased in size. Occasionally it is double on one side, and the muscles of the two sides are sometimes of unequal size. It may extend higher than the level stated.




FIG. 508.—Diagram of a transverse section through the anterior abdominal wall, below the linea semicircularis.

Besides the Rectus and Pyramidalis, the sheath of the Rectus contains the superior and inferior epigastric arteries, and the lower intercostal nerves.

**Nerves.**—The abdominal muscles are supplied by the lower intercostal nerves. The Obliquus internus and Transversus also receive filaments from the anterior branch of the iliohypogastric and sometimes from the ilioinguinal. The Cremaster is supplied by the external spermatic branch of the genitofemoral and the Pyramidalis usually by the twelfth thoracic.

**The Linea Alba.**—The linea alba is a tendinous raphé in the middle line of the abdomen, stretching between the xiphoid process and the symphysis pubis. It is placed between the medial borders of the Recti, and is formed by the blending of the aponeuroses of the Obliqui and Transversus. It is narrow below, corresponding to the linear interval existing between the Recti; but higher above, where these muscles diverge from one another. At its lower end the linea alba has a double attachment—its superficial fibres passing in front of the medial heads of the Recti to the symphysis pubis, while its deeper fibres form a triangular lamella, attached behind the Recti to the posterior lip of the crest of the pubis, and named the *admiriculum lineae albae*. It presents apertures for the passage of vessels and nerves; the umbilicus, which in the fetus is as an aperture and transmits the umbilical vessels, is closed in the adult.

**The Lineae Semilunares.**—The lineae semilunares are two curved tendinous lines placed one on either side of the linea alba. Each corresponds with the lateral border of the Rectus, extends from the cartilage of the ninth rib to the pubic tubercle, and is formed by the aponeurosis of the Obliquus internus at its line of division to enclose the Rectus, reinforced in front by that of the Obliquus externus, and behind by that of the Transversus.

**Actions.**—When the pelvis and thorax are fixed, the abdominal muscles compress the abdominal viscera by constricting the cavity of the abdomen, in which action they are materially assisted by the descent of the Diaphragma. By these means assistance is given in expelling the feces from the rectum, the urine from the bladder, the fetus from the uterus, and the contents of the stomach in vomiting.

If the pelvis and vertebral column be fixed, these muscles compress the lower part of the thorax, materially assisting expiration. If the pelvis alone be fixed, the thorax is bent directly forward, when the muscles of both sides act; when the muscles of only one side contract, the trunk is bent toward that side and rotated toward the opposite side.

If the thorax be fixed, the muscles, acting together, draw the pelvis upward, as in climbing; or, acting singly, they draw the pelvis upward, and bend the vertebral column to one side or the other. The Recti, acting from below, depress the thorax, and consequently flex the vertebral column; when acting from above, they flex the pelvis upon the vertebral column. The Pyramidales are tensors of the linea alba.

**The Transversalis Fascia.**—The transversalis fascia is a thin aponeurotic membrane which lies between the inner surface of the Transversus and the extraperitoneal fat. It forms part of the general layer of fascia lining the abdominal parietes, and is directly continuous with the iliac and pelvic fasciæ. In the inguinal region, the transversalis fascia is thick and dense in structure and is joined by fibres from the aponeurosis of the Transversus, but it becomes thin as it ascends to the Diaphragma, and blends with the fascia covering the under surface of this muscle. *Behind*, it is lost in the fat which covers the posterior surfaces of the kidneys. *Below*, it has the following attachments: *posteriorly*, to the whole length of the iliac crest, between the attachments of the Transversus and Iliacus; between the anterior superior iliac spine and the femoral vessels it is connected to the posterior margin of the inguinal ligament, and is there continuous with the iliac fascia. Medial to the femoral vessels it is thin and attached to the pubis and pectineal line, behind the inguinal aponeurotic falx, with which it is united; it descends in front of the femoral vessels to form the anterior wall of the femoral sheath. Beneath the inguinal ligament it is strengthened by a band of fibrous tissue, which is only loosely connected to the ligament, and is specialized as the **deep crural arch**. The spermatic cord in the male and the round ligament of the uterus in the female pass through the transversalis fascia at a spot called the **abdominal inguinal ring**. This opening is not visible externally, since the transversalis fascia is prolonged on these structures as the infundibuliform fascia.

**The Abdominal Inguinal Ring** (*annulus inguinalis abdominis; interna, or deep abdominal ring*).—The abdominal inguinal ring is situated in the transversalis fascia, midway between the anterior superior iliac spine and the symphysis pubis, and about 1.25 cm. above the inguinal ligament (Fig. 509). It is of an oval form, the long axis of the oval being vertical; it varies in size in different subjects, and is much larger in the male than in the female. It is bounded, *above* and *laterally*, by the arched lower margin of the Transversus; *below* and *medially*, by the inferior epigastric vessels. It transmits the spermatic cord in the male and the round ligament of the uterus in the female. From its circumference a thin funnel-shaped membrane, the **infundibuliform fascia**, is continued around the cord and testis, enclosing them in a distinct covering.

**The Inguinal Canal** (*canalis inguinalis; spermatic canal*).—The inguinal canal contains the spermatic cord and the ilioinguinal nerve in the male, and the round ligament of the uterus and the ilioinguinal nerve in the female. It is an oblique canal about 4 cm. long, slanting downward and medialward, and placed parallel with and a little above the inguinal ligament; it extends from the abdominal inguinal ring to the subcutaneous inguinal ring. It is bounded, *in front*, by the integument and superficial fascia, by the aponeurosis of the Obliquus externus throughout its whole length, and by the Obliquus internus in its lateral third; *behind*, by the reflected inguinal ligament, the inguinal aponeurotic falx, the transversalis fascia, the extraperitoneal connective tissue and the peritoneum; *above*,

by the arched fibres of Obliquus internus and Transversus abdominis; *below*, by the union of the transversalis fascia with the inguinal ligament, and at its medial end by the lacunar ligament.

**Extraperitoneal Connective Tissue.**—Between the inner surface of the general layer of the fascia which lines the interior of the abdominal and pelvic cavities, and the peritoneum, there is a considerable amount of connective tissue, termed the **extraperitoneal or subperitoneal connective tissue**.

The **parietal portion** lines the cavity in varying quantities in different situations. It is especially abundant on the posterior wall of the abdomen, and particularly around the kidneys, where it contains much fat. On the anterior wall of the abdomen, except in the pubic region, and on the lateral wall above the iliac crest, it is scanty, and here the transversalis fascia is more closely connected with the peritoneum. There is a considerable amount of extraperitoneal connective tissue in the pelvis.




FIG. 509.—The abdominal inguinal ring.

The **visceral portion** follows the course of the branches of the abdominal aorta between the layers of the mesenterics and other folds of peritoneum which connect the various viscera to the abdominal wall. The two portions are directly continuous with each other.

**The Deep Crural Arch.**—Curving over the external iliac vessels, at the spot where they become femoral, on the abdominal side of the inguinal ligaments and loosely connected with it, is a thickened band of fibres called the deep crural arch. It is apparently a thickening of the transversalis fascia joined laterally to the centre of the lower margin of the inguinal ligament, and arching across the front of the femoral sheath to be inserted by a broad attachment into the pubic tubercle and pectineal line, behind the inguinal aponeurotic falx. In some subjects this structure is not very prominently marked, and not infrequently it is altogether wanting.

## 2. The Posterior Muscles of the Abdomen.

Psoas major.  
Psoas minor.

Iliacus.  
Quadratus lumborum.

The Psoas major, the Psoas minor, and the Iliacus, with the fasciæ covering them, will be described with the muscles of the lower extremity (see page 559).

**The Fascia Covering the Quadratus Lumborum.**—This is a thin layer attached, *medially*, to the bases of the transverse processes of the lumbar vertebræ; *below*, to the iliolumbar ligament; *above*, to the apex and lower border of the last rib. The upper margin of this fascia, which extends from the transverse process of the first lumbar vertebra to the apex and lower border of the last rib, constitutes the lateral lumbocostal arch (page 495). Laterally, it blends with the lumbodorsal fascia, the anterior layer of which intervenes between the Quadratus lumborum and the Sacrospinalis.

The **Quadratus lumborum** (Fig. 495, page 487) is irregularly quadrilateral in shape, and broader below than above. It *arises* by aponeurotic fibres from the iliolumbar ligament and the adjacent portion of the iliac crest for about 5 cm., and is *inserted* into the lower border of the last rib for about half its length, and by four small tendons into the apices of the transverse processes of the upper four lumbar vertebræ. Occasionally a second portion of this muscle is found in front of the preceding. It *arises* from the upper borders of the transverse processes of the lower three or four lumbar vertebræ, and is *inserted* into the lower margin of the last rib. In front of the Quadratus lumborum are the colon, the kidney, the Psoas major and minor, and the Diaphragma; between the fascia and the muscle are the twelfth thoracic, ilioinguinal, and iliohypogastric nerves.

**Nerve Supply.**—The twelfth thoracic and first and second lumbar nerves supply this muscle.

**Actions.**—The Quadratus lumborum draws down the last rib, and acts as a muscle of inspiration by helping to fix the origin of the Diaphragma. If the thorax and vertebral column are fixed, it may act upon the pelvis, raising it toward its own side when only one muscle is put in action; and when both muscles act together, either from below or above, they flex the trunk.

## V. THE MUSCLES AND FASCIÆ OF THE PELVIS.

Obturator internus.  
Piriformis.

Levator ani.  
Coccygeus.

The muscles within the pelvis may be divided into two groups: (1) the Obturator internus and the Piriformis, which are muscles of the lower extremity, and will be described with these (pages 571 and 572); (2) the Levator ani and the Coccygeus, which together form the **pelvic diaphragm** and are associated with the pelvic viscera. The classification of the two groups under a common heading is convenient in connection with the fasciæ investing the muscles. These fasciæ are closely related to one another and to the deep fascia of the perineum, and in addition have special connections with the fibrous coverings of the pelvic viscera; it is customary therefore to describe them together under the term **pelvic fascia**.

**Pelvic Fascia.**—The fascia of the pelvis may be resolved into: (a) the facial sheaths of the Obturator internus, Piriformis, and pelvic diaphragm; (b) the fascia associated with the pelvic viscera.

The **fascia of the Obturator internus** covers the pelvic surface of, and is attached around the margin of the origin of, the muscle. *Above*, it is loosely connected to the back part of the arcuate line, and here it is continuous with the iliac fascia. In front of this, as it follows the line of origin of the Obturator internus, it gradually separates from the iliac fascia and the continuity between the two is retained only through the periosteum. It arches beneath the obturator vessels and nerve, completing the obturator canal, and at the front of the pelvis is attached to the back

of the superior ramus of the pubis. *Below*, the obturator fascia is attached to the falciform process of the sacrotuberous ligament and to the pubic arch, where it becomes continuous with the superior fascia of the urogenital diaphragm. *Behind*, it is prolonged into the gluteal region.

The internal pudendal vessels and pudendal nerve cross the pelvic surface of the Obturator internus and are enclosed in a special canal—**Alcock's canal**—formed by the obturator fascia.

The **fascia of the Piriformis** is very thin and is attached to the front of the sacrum and the sides of the greater sciatic foramen; it is prolonged on the muscle into the gluteal region. At its sacral attachment around the margins of the anterior sacral foramina it comes into intimate association with and ensheathes the nerves emerging from these foramina. Hence the sacral nerves are frequently described as lying behind the fascia. The internal iliac vessels and their branches, on the other hand, lie in the subperitoneal tissue in front of the fascia, and the branches to the gluteal region emerge in special sheaths of this tissue, above and below the Piriformis muscle.




FIG. 510.—Coronal section of pelvis, showing arrangement of fasciæ. Viewed from behind. (Diagrammatic.)

The **diaphragmatic part of the pelvic fascia** (Fig. 510) covers both surfaces of the Levatores ani. The inferior layer is known as the **anal fascia**; it is attached above to the obturator fascia along the line of origin of the Levator ani, while below it is continuous with the superior fascia of the urogenital diaphragm, and with the fascia on the Sphincter ani internus. The layer covering the upper surface of the pelvic diaphragm follows, above, the line of origin of the Levator ani and is therefore somewhat variable. In front it is attached to the back of the symphysis pubis about 2 cm. above its lower border. It can then be traced laterally across the back of the superior ramus of the pubis for a distance of about 1.25 cm., when it reaches the obturator fascia. It is attached to this fascia along a line which pursues a somewhat irregular course to the spine of the ischium. The irregularity of this line is due to the fact that the origin of the Levator ani, which in lower forms is from the pelvic brim, is in man lower down, on the obturator fascia. Tendinous fibres of origin of the muscle are therefore often found extending up toward, and in some cases reaching, the pelvic brim, and on these the fascia is carried.



It will be evident that the fascia covering that part of the Obturator internus which lies above the origin of the Levator ani is a composite fascia and includes the following: (a) the obturator fascia; (b) the fascia of the Levator ani; (c) degenerated fibres of origin of the Levator ani.

The lower margin of the fascia covering the upper surface of the pelvic diaphragm is attached along the line of insertion of the Levator ani.

At the level of a line extending from the lower part of the symphysis pubis to the spine of the ischium is a thickened whitish band in this upper layer of the diaphragmatic part of the pelvic fascia. It is termed the **tendinous arch or white line of the pelvic fascia**, and marks the line of attachment of the special fascia (*pars endopelvina fasciae pelvis*) which is associated with the pelvic viscera.




FIG. 511.—Median sagittal section of pelvis, showing arrangement of fasciae.

The **endopelvic part of the pelvic fascia** is continued over the various pelvic viscera (Fig. 511) to form for them fibrous coverings which will be described later (see section on Splanchnology). It is attached to the diaphragmatic part of the pelvic fascia along the tendinous arch, and has been subdivided in accordance with the viscera to which it is related. Thus its anterior part, known as the **vesical layer**, forms the anterior and lateral ligaments of the bladder. Its middle part crosses the floor of the pelvis between the rectum and vesiculae seminales as the **rectovesical layer**; in the female this is perforated by the vagina. Its posterior

portion passes to the side of the rectum; it forms a loose sheath for the rectum, but is firmly attached around the anal canal; this portion is known as the **rectal layer**.

The **Levator ani** (Fig. 512) is a broad, thin muscle, situated on the side of the pelvis. It is attached to the inner surface of the side of the lesser pelvis, and unites with its fellow of the opposite side to form the greater part of the floor of the pelvic cavity. It supports the viscera in this cavity, and surrounds the various structures which pass through it. It *arises*, in front, from the posterior surface of the superior ramus of the pubis lateral to the symphysis; behind, from the inner surface of the spine of the ischium; and between these two points, from the obturator fascia.




FIG. 512.—Left Levator ani from within.

Posteriorly, this fascial origin corresponds, more or less closely, with the tendinous arch of the pelvic fascia, but in front, the muscle arises from the fascia at a varying distance above the arch, in some cases reaching nearly as high as the canal for the obturator vessels and nerve. The fibres pass downward and backward to the middle line of the floor of the pelvis; the most posterior are inserted into the side of the last two segments of the coccyx; those placed more anteriorly unite with the muscle of the opposite side, in a median fibrous raphé (**anococcygeal**

**raphé**), which extends between the coccyx and the margin of the anus. The middle fibres are inserted into the side of the rectum, blending with the fibres of the Sphincter muscles; lastly, the anterior fibres descend upon the side of the prostate to unite beneath it with the muscle of the opposite side, joining with the fibres of the Sphincter ani externus and Transversus perinaei, at the central tendinous point of the perineum.

The anterior portion is occasionally separated from the rest of the muscle by connective tissue. From this circumstance, as well as from its peculiar relation with the prostate, which it supports as in a sling, it has been described as a distinct muscle, under the name of *Levator prostatae*. In the female the anterior fibres of the Levator ani descend upon the side of the vagina.

**Relations.**—By its *upper or pelvic surface*, with the diaphragmatic part of the pelvic fascia which separates it from the bladder, prostate, rectum, and peritoneum. By its *lower or perineal surface*, it forms the medial boundary of the ischioanal fossa, and is covered by the inferior layer of the diaphragmatic part of the pelvic fascia (*anal fascia*). Its *posterior border* is free and separated from the Coccygeus by areolar tissue. Its *anterior border* is separated from the muscle of the opposite side by a triangular space, through which the urethra, and in the female the vagina, pass from the pelvis.

The Levator ani may be divided into iliococcygeal and pubococcygeal parts.

The *Iliococcygeus* arises from the ischial spine and from the posterior part of the tendinous arch of the pelvic fascia, and is attached to the coccyx and anococcygeal raphé; it is usually thin, and may fail entirely, or be largely replaced by fibrous tissue. An accessory slip at its posterior part is sometimes named the *Iliosacralis*. The *Pubococcygeus* arises from the back of the pubis and from the anterior part of the obturator fascia, and "is directed backward almost horizontally along the side of the anal canal toward the coccyx and sacrum, to which it finds attachment. Between the termination of the vertebral column and the anus, the two Pubococcygei muscles come together and form a thick, fibromuscular layer lying on the raphé formed by the Iliococcygei" (Peter Thompson). The greater part of this muscle is inserted into the coccyx and into the last one or two pieces of the sacrum. This insertion into the vertebral column is, however, not admitted by all observers. The fibres which form a sling for the rectum are named the *Puborectalis* or *Sphincter recti*. They arise from the lower part of the symphysis pubis, and from the superior fascia of the urogenital diaphragm. They meet with the corresponding fibres of the opposite side around the lower part of the rectum, and form for it a strong sling.

**Nerve Supply.**—The Levator ani is supplied by a branch from the fourth sacral nerve and by a branch which is sometimes derived from the perineal, sometimes from the inferior hemorrhoidal division of the pudendal nerve.

The **Coccygeus** (Fig. 512) is situated behind the preceding. It is a triangular plane of muscular and tendinous fibres, arising by its apex from the spine of the ischium and sacrospinous ligament, and inserted by its base into the margin of the coccyx and into the side of the lowest piece of the sacrum. It assists the Levator ani and Piriformis in closing in the back part of the outlet of the pelvis.

**Nerve Supply.**—The Coccygeus is supplied by a branch from the fourth and fifth sacral nerves.

**Actions.**—The Levatores ani constrict the lower end of the rectum and vagina. They elevate and invert the lower end of the rectum after it has been protruded and everted during the expulsion of the feces. They are also muscles of forced expiration. The Coccygei pull forward and support the coccyx, after it has been pressed backward during defecation or parturition. The Levatores ani and Coccygei together form a muscular diaphragm which supports the pelvic viscera.

## VI. THE MUSCLES AND FASCIAE OF THE PERINEUM.

The perineum corresponds to the outlet of the pelvis. Its deep boundaries are—in *front*, the pubic arch and the arcuate ligament of the pubis; *behind*, the tip of the coccyx; and on either side the inferior rami of the pubis and ischium, and the sacrotuberous ligament. The space is somewhat lozenge-shaped and is limited on the surface of the body by the scrotum in front, by the buttocks behind, and laterally by the medial side of the thigh. A line drawn transversely across in front of the ischial tuberosities divides the space into two portions. The posterior contains the termination of the anal canal and is known as the **anal region**;

the anterior, which contains the external urogenital organs, is termed the **urogenital region**.

The muscles of the perineum may therefore be divided into two groups:

1. Those of the anal region.
2. Those of the urogenital region: A, In the male; B, In the female.

### 1. The Muscles of the Anal Region.

Corrugator cutis ani.      Sphincter ani externus.      Sphincter ani internus.

**The Superficial Fascia.**—The superficial fascia is very thick, areolar in texture, and contains much fat in its meshes. On either side a pad of fatty tissue extends deeply between the Levator ani and Obturator internus into a space known as the **ischiorectal fossa**.

**The Deep Fascia.**—The deep fascia forms the lining of the ischiorectal fossa; it comprises the anal fascia, and the portion of obturator fascia below the origin of Levator ani.




FIG. 513.—The perineum. The integument and superficial layer of superficial fascia reflected.

**Ischiorectal Fossa** (*fossa ischiorectalis*) (Fig. 513).—The fossa is somewhat prismatic in shape, with its base directed to the surface of the perineum, and its apex at the line of meeting of the obturator and anal fasciæ. It is bounded *medially* by the Sphincter ani externus and the anal fascia; *laterally*, by the tuberosity of the ischium and the obturator fascia; *anteriorly*, by the fascia of Colles covering the Transversus perinaei superficialis, and by the inferior fascia of the urogenital diaphragm; *posteriorly*, by the Glutæus maximus and the sacrotuberous ligament. Crossing the space transversely are the inferior hemorrhoidal vessels and nerves; at the back part are the perineal and perforating cutaneous branches of the pudendal plexus; while from the forepart the posterior scrotal (or labial) vessels and nerves emerge. The internal pudendal vessels and pudendal nerve lie in

Alcock's canal on the lateral wall. The fossa is filled with fatty tissue across which numerous fibrous bands extend from side to side.

**Applied Anatomy.**—Abscess in the ischiorectal fossa commonly occurs; it is most often the result of infection from the bowel, and is especially prone to occur in tuberculous subjects; occasionally it follows perforation by a foreign body which has been swallowed, such as a fish bone. The abscess may bulge at the side of the anus, at the border of *Glutaeus maximus*, or against the rectal wall. There is great pain on defecation. On examining the bowel, fulness on the side of the abscess may be detected. If left to itself the pus will find exit through the skin, or into the rectum between the two Sphincters; and the condition will degenerate into one of the varieties of fistula, owing to the constant pull of the Sphincter ani externus preventing closure of the walls of the cavity. These abscesses should be opened at the earliest possible moment, as they tend to track and burrow widely into the soft fat in the fossa, and also in the subcutaneous tissues. An incision should be made tangential to the anus over the region of the ischiorectal fossa, and should then be converted into a T, by making a second incision laterally at right angles to it, so that the wound may be kept open and may heal up from the bottom. Frequently, however, in spite of care, a fistula ensues which requires division of the Sphincter ani externus for its cure.

**The Corrugator Cutis Ani.**—Around the anus is a thin stratum of involuntary muscular fibre, which radiates from the orifice. *Medially* the fibres fade off into the submucous tissue, while *laterally* they blend with the true skin. By its contraction it raises the skin into ridges around the margin of the anus.

**The Sphincter ani externus** (*External sphincter ani*) (Fig 513) is a flat plane of muscular fibres, elliptical in shape and intimately adherent to the integument surrounding the margin of the anus. It measures about 8 to 10 cm. in length, from its anterior to its posterior extremity, and is about 2.5 cm. broad opposite the anus. It consists of two strata, superficial and deep. The *superficial*, constituting the main portion of the muscle, arises from a narrow tendinous band, the **anococcygeal raphé**, which stretches from the tip of the coccyx to the posterior margin of the anus; it forms two flattened planes of muscular tissue, which encircle the anus and meet in front to be inserted into the central tendinous point of the perineum, joining with the *Transversus perinaei superficialis*, the *Levator ani*, and the *Bulbocavernosus*. The *deeper portion* forms a complete sphincter to the anal canal. Its fibres surround the canal, closely applied to the Sphincter ani internus, and in front blend with the other muscles at the central point of the perineum. In a considerable proportion of cases the fibres decussate in front of the anus, and are continuous with the *Transversi perinaei superficiales*. Posteriorly, they are not attached to the coccyx, but are continuous with those of the opposite side behind the anal canal. The upper edge of the muscle is ill-defined, since fibres are given off from it to join the *Levator ani*.

**Nerve Supply.**—A branch from the fourth sacral and twigs from the inferior hemorrhoidal branch of the pudendal supply the muscle.

**Actions.**—The action of this muscle is peculiar. (1) It is, like other muscles, always in a state of tonic contraction, and having no antagonistic muscle it keeps the anal canal and orifice closed. (2) It can be put into a condition of greater contraction under the influence of the will, so as more firmly to occlude the anal aperture, in expiratory efforts unconnected with defecation. (3) Taking its fixed point at the coccyx, it helps to fix the central point of the perineum, so that the *Bulbocavernosus* may act from this fixed point.

**The Sphincter ani internus** (*Internal sphincter ani*) is a muscular ring which surrounds about 2.5 cm. of the anal canal; its inferior border is in contact with, but quite separate from, the Sphincter ani externus. It is about 5 mm. thick, and is formed by an aggregation of the involuntary circular fibres of the intestine. Its lower border is about 6 mm. from the orifice of the anus.

**Actions.**—Its action is entirely involuntary. It helps the Sphincter ani externus to occlude the anal aperture and aids in the expulsion of the feces.

S  
and  
play  
are, i  
of th  
the f



2. A. The Muscles of the Urogenital Region in the Male (Fig. 514).

Transversus perinaei superficialis.

Ischiocavernosus.

Bulbocavernosus.

Transversus perinaei profundus.

Sphincter urethrae membranaceae.

**Superficial Fascia.**—The superficial fascia of this region consists of two layers, superficial and deep.




FIG. 514.—Muscles of male perineum.

The superficial layer is thick, loose, areolar in texture, and contains in its meshes much adipose tissue, the amount of which varies in different subjects. In front, it is continuous with the dartos tunic of the scrotum; behind, with the subcutaneous areolar tissue surrounding the anus; and, on either side, with the same fascia on the inner sides of the thighs. In the middle line, it is adherent to the skin on the raphé, and to the deep layer of the superficial fascia.

The deep layer of superficial fascia (*fascia of Colles*) (Fig. 513) is thin, aponeurotic in structure, and of considerable strength, serving to bind down the muscles of the root of the penis. It is continuous, in front, with the dartos tunic, the deep fascia of the penis, the fascia of the spermatic cord, and Scarpa's fascia upon the



anterior wall of the abdomen; on *either side* it is firmly attached to the margins of the rami of the pubis and ischium, lateral to the crus penis and as far back as the tuberosity of the ischium; *posteriorly*, it curves around the Transversi perinaei superficiales to join the lower margin of the inferior fascia of the urogenital diaphragm. In the *middle line*, it is connected with the superficial fascia and with the median septum of the Bulbocavernosus. This fascia not only covers the muscles in this region, but at its back part sends upward a vertical septum from its deep surface, which separates the posterior portion of the subjacent space into two.

**The Central Tendinous Point of the Perineum.**—This is a fibrous point in the middle line of the perineum, between the urethra and anus, and about 1.25 cm. in front of the latter. At this point six muscles converge and are attached: viz., the Sphincter ani externus, the Bulbocavernosus, the two Transversi perinaei superficiales, and the anterior fibres of the Levatores ani.

The **Transversus perinaei superficialis** (*Transversus perinaei*; *Superficial transverse perineal muscle*) is a narrow muscular slip, which passes more or less transversely across the perineal space in front of the anus. It *arises* by tendinous fibres from the inner and forepart of the tuberosity of the ischium, and, running medialward, is inserted into the central tendinous point of the perineum, joining in this situation with the muscle of the opposite side, with the Sphincter ani externus behind, and with the Bulbocavernosus in front. In some cases, the fibres of the deeper layer of the Sphincter ani externus decussate in front of the anus and are continued into this muscle. Occasionally it gives off fibres, which join with the Bulbocavernosus of the same side.

**Actions.**—The simultaneous contraction of the two muscles serves to fix the central tendinous point of the perineum.

The **Bulbocavernosus** (*Ejaculator urinae*; *Accelerator urinae*) is placed in the middle line of the perineum, in front of the anus. It consists of two symmetrical parts, united along the median line by a tendinous raphé. It *arises* from the central tendinous point of the perineum and from the median raphé in front. Its fibres diverge like the barbs of a quill-pen; the most posterior form a thin layer, which is lost on the inferior fascia of the urogenital diaphragm; the middle fibres encircle the bulb and adjacent parts, of the corpus cavernosum urethrae, and join with the fibres of the opposite side, on the upper part of the corpus cavernosum urethrae, in a strong aponeurosis; the anterior fibres, spread out over the side of the corpus cavernosum penis, to be inserted partly into that body, anterior to the Ischiocavernosus, occasionally extending to the pubis, and partly ending in a tendinous expansion which covers the dorsal vessels of the penis. The latter fibres are best seen by dividing the muscle longitudinally, and reflecting it from the surface of the corpus cavernosum urethrae.

**Actions.**—This muscle serves to empty the canal of the urethra, after the bladder has expelled its contents; during the greater part of the act of micturition its fibres are relaxed, and it only comes into action at the end of the process. The middle fibres are supposed by Krause to assist in the erection of the corpus cavernosum urethrae, by compressing the erectile tissue of the bulb. The anterior fibres, according to Tyrrel, also contribute to the erection of the penis by compressing the deep dorsal vein of the penis as they are inserted into, and continuous with, the fascia of the penis.

The **Ischiocavernosus** (*Erector penis*) covers the crus penis. It is an elongated muscle, broader in the middle than at either end, and situated on the lateral boundary of the perineum. It *arises* by tendinous and fleshy fibres from the inner surface of the tuberosity of the ischium, behind the crus penis; and from the rami of the pubis and ischium on either side of the crus. From these points fleshy fibres succeed, and end in an aponeurosis which is *inserted* into the sides and under surface of the crus penis.

**Action.**—The Ischiocavernosus compresses the crus penis, and retards the return of the blood through the veins, and thus serves to maintain the organ erect.

Between the muscles just examined a triangular space exists, bounded medially by the Bulbocavernosus, laterally by the Ischiocavernosus, and behind by the Transversus perinaei superficialis; the floor is formed by the inferior fascia of the urogenital diaphragm. Running from behind forward in the space are the posterior scrotal vessels and nerves, and the perineal branch of the posterior femoral cutaneous nerve; the transverse perineal artery courses along its posterior boundary on the Transversus perinaei superficialis.

**The Deep Fascia.**—The deep fascia of the urogenital region forms an investment for the Transversus perinaei profundus and the Sphincter urethrae membranaceae, but within it lie also the deep vessels and nerves of this part, the whole forming a transverse septum which is known as the **urogenital diaphragm**. From its shape it is usually termed the **triangular ligament**, and is stretched almost horizontally across the pubic arch, so as to close in the front part of the outlet of the pelvis. It consists of two dense membranous laminæ (Fig. 515), which are united along their posterior borders, but are separated in front by intervening structures. The superficial of these two layers, the **inferior fascia of the urogenital diaphragm**, is triangular in shape, and about 4 cm. in depth. Its apex is directed forward, and is




FIG. 515.—Coronal section of anterior part of pelvis, through the pubic arch. Seen from in front. (Diagrammatic.)

separated from the arcuate pubic ligament by an oval opening for the transmission of the deep dorsal vein of the penis. Its lateral margins are attached on either side to the inferior rami of the pubis and ischium, above the crus penis. Its base is directed toward the rectum, and connected to the central tendinous point of the perineum. It is continuous with the deep layer of the superficial fascia behind the Transversus perinaei superficialis, and with the inferior layer of the diaphragmatic part of the pelvic fascia. It is perforated, about 2.5 cm. below the symphysis pubis, by the urethra, the aperture for which is circular and about 6 mm. in diameter by the arteries to the bulb and the ducts of the bulbourethral glands close to the urethral orifice; by the deep arteries of the penis, one on either side close to the pubic arch and about halfway along the attached margin of the fascia; by the dorsal arteries and nerves of the penis near the apex of the fascia. Its base is also perforated by the perineal vessels and nerves, while between its apex and the arcuate pubic ligament the deep dorsal vein of the penis passes upward into the pelvis.

If the inferior fascia of the urogenital diaphragm be detached on either side, the following structures will be seen between it and the superior fascia: the deep dorsal vein of the penis; the membranous portion of the urethra; the *Transversus perinaei profundus* and *Sphincter urethrae membranaceae* muscles; the bulbourethral glands and their ducts; the pudendal vessels and dorsal nerves of the penis; the arteries and nerves of the urethral bulb, and a plexus of veins.

The superior fascia of the urogenital diaphragm is continuous with the obturator fascia and stretches across the pubic arch. If the obturator fascia be traced medially after leaving the Obturator internus muscle, it will be found attached by some of its deeper or anterior fibres to the inner margin of the pubic arch, while its superficial or posterior fibres pass over this attachment to become continuous with the superior fascia of the urogenital diaphragm. Behind, this layer of the fascia is continuous with the inferior fascia and with the fascia of Colles; in front it is continuous with the fascial sheath of the prostate, and is fused with the inferior fascia to form the transverse ligament of the pelvis.

The *Transversus perinaei profundus* arises from the inferior rami of the ischium and runs to the median line, where it interlaces in a tendinous raphé with its fellow of the opposite side. It lies in the same plane as the *Sphincter urethrae membranaceae*; formerly the two muscles were described together as the *Constrictor urethrae*.

The *Sphincter urethrae membranaceae* surrounds the whole length of the membranous portion of the urethra, and is enclosed in the fasciae of the urogenital diaphragm. Its external fibres arise from the junction of the inferior rami of the pubis and ischium to the extent of 1.25 to 2 cm., and from the neighboring fasciae. They arch across the front of the urethra and bulbourethral glands, pass around the urethra, and behind it unite with the muscle of the opposite side, by means of a tendinous raphé. Its innermost fibres form a continuous circular investment for the membranous urethra.

**Actions.**—The muscles of both sides act together as a sphincter, compressing the membranous portion of the urethra. During the transmission of fluids they, like the *Bulbocavernosus*, are relaxed, and only come into action at the end of the process to eject the last drops of the fluid.

**Nerve Supply.**—The perineal branch of the pudendal nerve supplies this group of muscles.

## 2. B. The Muscles of the Urogenital Region in the Female (Fig. 515).

<i>Transversus perinaei superficialis.</i>	<i>Ischiocavernosus.</i>
<i>Bulbocavernosus.</i>	<i>Transversus perinaei profundus.</i>
<i>Sphincter urethrae membranaceae.</i>	

The *Transversus perinaei superficialis* (*Transversus perinaei*; *Superficial transverse perineal muscle*) in the female is a narrow muscular slip, which arises by a small tendon from the inner and forepart of the tuberosity of the ischium, and is inserted into the central tendinous point of the perineum, joining in this situation with the muscle of the opposite side, the *Sphincter ani externus* behind, and the *Bulbocavernosus* in front.

**Action.**—The simultaneous contraction of the two muscles serves to fix the central tendinous point of the perineum.

The *Bulbocavernosus* (*Sphincter vaginae*) surrounds the orifice of the vagina. It covers the lateral parts of the vestibular bulbs, and is attached posteriorly to the central tendinous point of the perineum, where it blends with the *Sphincter ani externus*. Its fibres pass forward on either side of the vagina to be inserted into the corpora cavernosa clitoridis, a fasciculus crossing over the body of the organ so as to compress the deep dorsal vein.

**Actions.**—The *Bulbocavernosus* diminishes the orifice of the vagina. The anterior fibres contribute to the erection of the clitoris, as they are inserted into and are continuous with the fascia of the clitoris, compressing the deep dorsal vein during the contraction of the muscle.

The **Ischiocavernosus** (*Erector clitoridis*) is smaller than the corresponding muscle in the male. It covers the unattached surface of the crus clitoridis. It is an elongated muscle, broader at the middle than at either end, and situated on the side of the lateral boundary of the perineum. It *arises* by tendinous and fleshy fibres from the inner surface of the tuberosity of the ischium, behind the crus clitoridis; from the surface of the crus; and from the adjacent portion of the ramus of the ischium. From these points fleshy fibres succeed, and end in an aponeurosis, which is inserted into the sides and under surface of the crus clitoridis.




FIG. 516.—Muscles of the female perineum. (Modified from a drawing by Peter Thompson.)

**Actions.**—The Ischiocavernosus compresses the crus clitoridis and retards the return of blood through the veins, and thus serves to maintain the organ erect.

The **fascia of the urogenital diaphragm** in the female is not so strong as in the male. It is attached to the pubic arch, its apex being connected with the arcuate pubic ligament. It is divided in the middle line by the aperture of the vagina, with the external coat of which it becomes blended, and in front of this is perforated by the urethra. Its posterior border is continuous, as in the male, with the deep layer of the superficial fascia around the Transversus perinaei superficialis.

Like the corresponding fascia in the male, it consists of two layers, between which are to be found the following structures: the deep dorsal vein of the clitoris, a portion of the urethra and the Constrictor urethra muscle, the larger vestibular glands and their ducts; the internal pudendal vessels and the dorsal nerves of the clitoris; the arteries and nerves of the bulbi vestibuli, and a plexus of veins.

The **Transversus perinaei profundus** *arises* from the inferior rami of the ischium and runs across to the side of the vagina. The Sphincter urethrae membranaceae (*Constrictor urethrae*), like the corresponding muscle on the male, consists of external and internal fibres. The *external* fibres arise on either side from the margin of the

inferior ramus of the pubis. They are directed across the pubic arch in front of the urethra, and pass around it to blend with the muscular fibres of the opposite side, between the urethra and vagina. The *innermost* fibres encircle the lower end of the urethra.

**Nerve Supply.**—The muscles of this group are supplied by the perineal branch of the pudendal.

## THE MUSCLES AND FASCIÆ OF THE UPPER EXTREMITY.

The muscles of the upper extremity are divisible into groups, corresponding with the different regions of the limb.

- |  |                            |
|--|----------------------------|
| I. Muscles Connecting the Upper Extremity to the Vertebral Column.                     |                            |
| II. Muscles Connecting the Upper Extremity to the Anterior and Lateral Thoracic Walls. |                            |
| III. Muscles of the Shoulder.  | V. Muscles of the Forearm. |
| IV. Muscles of the Arm.  | VI. Muscles of the Hand.   |

### I. THE MUSCLES CONNECTING THE UPPER EXTREMITY TO THE VERTEBRAL COLUMN.

The muscles of this group are:

- |                   |                    |
|-------------------|--------------------|
| Trapezius.        | Rhomboideus major. |
| Latissimus dorsi. | Rhomboideus minor. |
| Levator scapulae. |                    |

**Superficial Fascia.**—The superficial fascia of the back forms a layer of considerable thickness and strength, and contains a quantity of granular fat. It is continuous with the general superficial fascia.

**Deep Fascia.**—The deep fascia is a dense fibrous layer, attached above to the superior nuchal line of the occipital bone; in the middle line it is attached to the ligamentum nuchae and supraspinal ligament, and to the spinous processes of all the vertebræ below the seventh cervical; laterally, in the neck it is continuous with the deep cervical fascia; over the shoulder it is attached to the spine of the scapula and to the acromion, and is continued downward over the Deltoides to the arm; on the thorax it is continuous with the deep fascia of the axilla and chest, and on the abdomen with that covering the abdominal muscles; below, it is attached to the crest of the ilium.

The **Trapezius** (Fig. 517) is a flat, triangular muscle, covering the upper and back part of the neck and shoulders. It *arises* from the external occipital protuberance and the medial third of the superior nuchal line of the occipital bone, from the ligamentum nuchae, the spinous process of the seventh cervical, and the spinous processes of all the thoracic vertebræ, and from the corresponding portion of the supraspinal ligament. From this origin, the superior fibres proceed downward and lateralward, the inferior upward and lateralward, and the middle horizontally; the superior fibres are inserted into the posterior border of the lateral third of the clavicle; the middle fibres into the medial margin of the acromion, and into the superior lip of the posterior border of the spine of the scapula; the inferior fibres converge near the scapula, and end in an aponeurosis, which glides over the smooth triangular surface on the medial end of the spine, to be inserted into a tubercle at the apex of this smooth triangular surface. At its occipital origin, the Trapezius is connected to the bone by a thin fibrous lamina, firmly adherent to the skin. At the middle it is connected to the spinous processes by a broad semi-elliptical aponeurosis, which reaches from the sixth cervical to the third thoracic vertebræ, and forms, with that of the opposite muscle, a tendinous ellipse. The rest of the






FIG. 517.—Muscles connecting the upper extremity to the vertebral column.



muscle arises by numerous short tendinous fibres. The two Trapezius muscles together resemble a trapezium, or diamond-shaped quadrangle: two angles corresponding to the shoulders; a third to the occipital protuberance; and the fourth to the spinous process of the twelfth thoracic vertebra.

The clavicular *insertion* of this muscle varies in extent; it sometimes reaches as far as the middle of the clavicle, and occasionally may blend with the posterior edge of the Sternocleidomastoideus, or overlap it.

The **Latissimus dorsi** (Fig. 517) is a triangular, flat muscle, which covers the lumbar region and the lower half of the thoracic region, and is gradually contracted into a narrow fasciculus at its insertion into the humerus. It *arises* by tendinous fibres from the spinous processes of the lower six thoracic vertebræ and from the posterior layer of the lumbodorsal fascia (see page 486), by which it is attached to the spines of the lumbar and sacral vertebræ, to the supraspinal ligament, and to the posterior part of the crest of the ilium. It also *arises* by muscular fibres from the external lip of the crest of the ilium lateral to the margin of the Sacrospinalis, and from the three or four lower ribs by fleshy digitations, which are interposed between similar processes of the Obliquus abdominis externus (Fig. 500, page 500). From this extensive origin the fibres pass in different directions, the upper ones horizontally, the middle obliquely upward, and the lower vertically upward, so as to converge and form a thick fasciculus, which crosses the inferior angle of the scapula, and usually receives a few fibres from it. The muscle curves around the lower border of the Teres major, and is twisted upon itself, so that the superior fibres become at first posterior and then inferior, and the vertical fibres at first anterior and then superior. It ends in a quadrilateral tendon, about 7 cm. long, which passes in front of the tendon of the Teres major, and is inserted into the bottom of the intertubercular groove of the humerus; its insertion extends higher on the humerus than that of the tendon of the Pectoralis major. The lower border of its tendon is united with that of the Teres major, the surfaces of the two being separated near their insertions by a bursa; another bursa is sometimes interposed between the muscle and the inferior angle of the scapula. The tendon of the muscle gives off an expansion to the deep fascia of the arm.

A muscular slip, the **axillary arch**, varying from 7 to 10 cm. in length, and from 5 to 15 mm. in breadth, occasionally springs from the upper edge of the Latissimus dorsi about the middle of the posterior fold of the axilla, and crosses the axilla in front of the axillary vessels and nerves, to join the under surface of the tendon of the Pectoralis major, the Coracobrachialis, or the fascia over the Biceps brachii. This axillary arch crosses the axillary artery, just above the spot usually selected for the application of a ligature, and may mislead the surgeon during the operation. It is present in about 7 per cent. of subjects and may be easily recognized by the transverse direction of its fibres.

A fibrous slip usually passes from the lower border of the tendon of the Latissimus dorsi, near its insertion, to the long head of the Triceps brachii. This is occasionally muscular, and is the representative of the *Dorsoepitrochlearis brachii* of apes.

The lateral margin of the Latissimus dorsi is separated below from the Obliquus externus abdominis by a small triangular interval, the **lumbar triangle of Petit**, the base of which is formed by the iliac crest, and its floor by the Obliquus internus abdominis. Another triangle is situated behind the scapula. It is bounded above by the Trapezius, below by the Latissimus dorsi, and laterally by the vertebral border of the scapula; the floor is partly formed by the Rhomboideus major. If the scapula be drawn forward by folding the arms across the chest, and the trunk bent forward, parts of the sixth and seventh ribs and the interspace between them become subcutaneous and available for auscultation. The space is therefore known as the **triangle of auscultation**.

**Nerves.**—The Trapezius is supplied by the accessory nerve, and by branches from the third and fourth cervical nerves; the Latissimus dorsi by the sixth, seventh, and eighth cervical nerves through the thoracodorsal (long subscapular) nerve.

of use

The **Rhomboideus major** (Fig. 517) arises by tendinous fibres from the spinous processes of the second, third, fourth, and fifth thoracic vertebræ and the supra-spinal ligament, and is inserted into a narrow tendinous arch, attached above to the lower part of the triangular surface at the root of the spine of the scapula; below to the inferior angle, the arch being connected to the vertebral border by a thin membrane. When the arch extends, as it occasionally does, only a short distance, the muscular fibres are inserted directly into the scapula.

The **Rhomboideus minor** (Fig. 517) arises from the lower part of the ligamentum Duchae and from the spinous processes of the seventh cervical and first thoracic vertebræ. It is inserted into the base of the triangular smooth surface at the root of the spine of the scapula, and is usually separated from the Rhomboideus major by a slight interval, but the adjacent margins of the two muscles are occasionally united.

The **Levator scapulae** (*Levator anguli scapulae*) (Fig. 517) is situated at the back and side of the neck. It arises by tendinous slips from the transverse processes of the atlas and axis and from the posterior tubercles of the transverse processes of the third and fourth cervical vertebræ. It is inserted into the vertebral border of the scapula, between the medial angle and the triangular smooth surface at the root of the spine.

**Nerves.**—The Rhomboidei are supplied by the dorsal scapular nerve from the fifth cervical; the Levator scapulae by the third and fourth cervical nerves, and frequently by a branch from the dorsal scapular.

**Actions.**—The movements effected by the preceding muscles are numerous, as may be conceived from their extensive attachments. When the whole Trapezii is in action it retracts the scapula and braces back the shoulder; if the head be fixed, the upper part of the muscle will elevate the point of the shoulder, as in supporting weights; when the lower fibres contract they assist in depressing the scapula. The middle and lower fibres of the muscle rotate the scapula, causing elevation of the acromion. If the shoulders be fixed, the Trapezii, acting together, will draw the head directly backward; or if only one act, the head is drawn to the corresponding side.

When the Latissimus dorsi acts upon the humerus, it depresses and draws it backward, and at the same time rotates it inward. It is the muscle which is principally employed in giving a downward blow, as in felling a tree or in sabre practice. If the arm be fixed, the muscle may act in various ways upon the trunk; thus, it may raise the lower ribs and assist in forcible inspiration; or, if both arms be fixed, the two muscles may assist the abdominal muscles and Pectorales in suspending and drawing the trunk forward, as in climbing.

If the head be fixed, the Levator scapulae raises the medial angle of the scapula; if the shoulder be fixed, the muscle inclines the neck to the corresponding side and rotates it in the same direction. The Rhomboidei carry the inferior angle backward and upward, thus producing a slight rotation of the scapula upon the side of the chest, the Rhomboideus major acting especially on the inferior angle of the scapula, through the tendinous arch by which it is inserted. The Rhomboidei, acting together with the middle and inferior fibres of the Trapezii, will retract the scapula.

## II. THE MUSCLES CONNECTING THE UPPER EXTREMITY TO THE ANTERIOR AND LATERAL THORACIC WALLS.

The muscles of the anterior and lateral thoracic regions are:

Pectoralis major.  
Pectoralis minor.

Subclavius.  
Serratus anterior.

**Dissection of Pectoral Region and Axilla** (Fig. 38).—The arm being drawn away from the side nearly at right angles with the trunk and rotated outward, make a vertical incision through the integument in the median line of the thorax, from the upper to the lower part of the sternum; a second incision along the lower border of the Pectoralis major muscle, from the ensiform cartilage to the inner side of the axilla; a third, from the sternum along the clavicle, as far as its centre; and a fourth, from the middle of the clavicle obliquely downward, along the interspace between the Pectoralis major and Deltoideus muscles, as low as the fold of the axilla. The flap of integument is then to be dissected off in the direction indicated in the figure, but not entirely removed,

as it should be replaced on completing the dissection. If a transverse incision is now made from the lower end of the sternum to the side of the thorax, as far as the posterior fold of the axilla, and the integument reflected outward, the axillary space will be more completely exposed.

**Superficial Fascia.**—The superficial fascia of the anterior thoracic region is continuous with that of the neck and upper extremity above, and of the abdomen below. It encloses the mamma and gives off numerous septa which pass into the gland, supporting its various lobes. From the fascia over the front of the mamma, fibrous processes pass forward to the integument and papilla; these were called by Sir A. Cooper the *ligamenta suspensoria*.

**Pectoral Fascia.**—The pectoral fascia is a thin lamina, covering the surface of the Pectoralis major, and sending numerous prolongations between its fasciculi: it is attached, in the middle line, to the front of the sternum; above, to the clavicle; laterally and below it is continuous with the fascia of the shoulder, axilla, and thorax. It is very thin over the upper part of the Pectoralis major, but thicker in the interval between it and the Latissimus dorsi, where it closes in the axillary space and forms the *axillary fascia*; it divides at the lateral margin of the Latissimus dorsi into two layers, one of which passes in front of, and the other behind it; these proceed as far as the spinous processes of the thoracic vertebrae, to which they are




FIG. 518.—Dissection of the upper extremity.

attached. As the fascia leaves the lower edge of the Pectoralis major to cross the floor of the axilla it sends a layer upward under cover of the muscle; this lamina splits to envelop the Pectoralis minor, at the upper edge of which it is continuous with the coracoclavicular fascia. The hollow of the armpit, seen when the arm is abducted, is produced mainly by the traction of this fascia on the axillary floor, and hence the lamina is sometimes named the *suspensory ligament of the axilla*. At the lower part of the thoracic region the deep fascia is well-developed, and is continuous with the fibrous sheaths of the Recti abdominis.

**Applied Anatomy.**—In cases of suppuration in the axilla, the axillary fascia prevents the extension of the pus in a downward direction, and so it has a tendency to spread upward, beneath the Pectoral muscles, toward the root of the neck. Early evacuation is therefore necessary. The incision should be made midway between the anterior and posterior axillary folds, so as to avoid the lateral thoracic and subscapular vessels, and the edge of the knife should be directed away from the axillary vessels.

The **Pectoralis major** (Fig. 519) is a thick, triangular muscle, situated at the upper and forepart of the chest. It arises from the anterior surface of the sternal half of the clavicle; from half the breadth of the anterior surface of the sternum, as low down as the attachment of the cartilage of the sixth or seventh rib; from the cartilages of all the true ribs, with the exception, frequently, of the first or seventh, or both, and from the aponeurosis of the Obliquus externus abdominis. From this

extensive origin the fibres converge toward their insertion; those arising from the clavicle pass obliquely downward and lateralward, and are usually separated from the rest by a slight interval; those from the lower part of the sternum, and the cartilages of the lower true ribs, run upward and lateralward; while the middle fibres pass horizontally. They all end in a flat tendon, about 5 cm. broad, which is inserted into the crest of the greater tubercle of the humerus. This tendon consists of two laminae, placed one in front of the other, and usually blended together below. The anterior lamina, the thicker, receives the clavicular and the uppermost




FIG. 519.—Superficial muscles of the chest and front of the arm.

sternal fibres; they are inserted in the same order as that in which they arise: that is to say, the most lateral of the clavicular fibres are inserted at the upper part of the anterior lamina; the uppermost sternal fibres pass down to the lower part of the lamina which extends as low as the tendon of the Deltoideus and joins with it. The posterior lamina of the tendon receives the attachment of the greater part of the sternal portion and the deep fibres, *i. e.*, those from the costal cartilages. These deep fibres, and particularly those from the lower costal cartilages, ascend the higher, turning backward successively behind the superficial and upper ones,

so that the tendon appears to be twisted. The posterior lamina reaches higher on the humerus than the anterior one, and from it an expansion is given off which covers the intertubercular groove and blends with the capsule of the shoulder-joint. From the deepest fibres of this lamina at its insertion an expansion is given off which lines the intertubercular groove, while from the lower border of the tendon a third expansion passes downward to the fascia of the arm.

**Relations.**—The Pectoralis major is in relation by its *anterior surface* with the integument, the superficial fascia, the Platysma, the anterior and middle supraclavicular nerves, the mamma, and the deep fascia; by its *posterior surface*, with the sternum, the ribs and costal cartilages, the coracoclavicular fascia, the Subclavius, Pectoralis minor, Serratus anterior, and the Intercostales; it forms the anterior wall of the axillary space, and covers the axillary vessels and nerves and the Biceps brachii and Coracobrachialis. Its *upper border* lies parallel with the Deltoideus, from which it is separated by a slight interspace in which lie the cephalic vein and deltoid branch of the thoracoacromial artery. Its *lower border* forms the anterior fold of the axilla, being separated medially from the Latissimus dorsi by a considerable interval; but the two muscles gradually converge toward the lateral part of the space.

**Dissection.**—Detach the Pectoralis major by dividing the muscle along its attachment to the clavicle, and by making a vertical incision through its substance a little external to its line of attachment to the sternum and costal cartilages. The muscle should then be reflected outward, and its tendon carefully examined. The Pectoralis minor is now exposed, and immediately above it, in the interval between its upper border and the clavicle, a strong fascia, the coracoclavicular fascia.

**Coracoclavicular Fascia** (*fascia coracoclavicularis*; *costocoracoid membrane*; *clavipectoral fascia*).—The coracoclavicular fascia is a strong fascia situated under cover of the clavicular portion of the Pectoralis major. It occupies the interval between the Pectoralis minor and Subclavius, and protects the axillary vessels and nerves. Traced upward, it splits to enclose the Subclavius, and its two layers are attached to the clavicle, one in front of and the other behind the muscle; the latter layer fuses with the deep cervical fascia and with the sheath of the axillary vessels. Medially, it blends with the fascia covering the first two intercostal spaces, and is attached also to the first rib medial to the origin of the Subclavius. Laterally, it is very thick and dense, and is attached to the coracoid process. The portion extending from the first rib to the coracoid process is often whiter and denser than the rest, and is sometimes called the *costocoracoid ligament*. Below this it is thin, and at the upper border of the Pectoralis minor it splits into two layers to invest the muscle; from the lower border of the Pectoralis minor it is continued downward to join the axillary fascia, and lateralward to join the fascia over the short head of the Biceps brachii. The coracoclavicular fascia is pierced by the cephalic vein, thoracoacromial artery and vein, and external anterior thoracic nerve.

The **Pectoralis minor** (Fig. 520) is a thin, triangular muscle, situated at the upper part of the thorax, beneath the Pectoralis major. It *arises* from the upper margins and outer surfaces of the third, fourth, and fifth ribs, near their cartilage and from the aponeuroses covering the Intercostalis; the fibres pass upward and lateralward and converge to form a flat tendon, which is inserted into the medial border and upper surface of the coracoid process of the scapula.

**Relations.**—By its *anterior surface* it is in relation with the Pectoralis major, the lateral anterior thoracic nerve, and the pectoral branch of the thoracoacromial artery; by its *posterior surface*, with the ribs, Intercostales, Serratus anterior, the axillary space, and the axillary vessels and brachial plexus of nerves. Its *upper border* is separated from the clavicle by a narrow triangular interval occupied by the coracoclavicular fascia, behind which are the axillary vessels and nerves. Running parallel to the *lower border* of the muscle is the lateral thoracic artery, and piercing the muscle is the medial anterior thoracic nerve.

The **Subclavius** (Fig. 520) is a small triangular muscle, placed between the clavicle and the first rib. It *arises* by a short, thick tendon from the first rib and its cartilage at their junction, in front of the costoclavicular ligament; the fleshy



fibres proceed obliquely upward and lateralward, to be *inserted* into the groove on the under surface of the clavicle between the costoclavicular and conoid ligaments.

**Relations.**—Its *deep surface* is separated from the first rib by the subclavian vessels and brachial plexus of nerves. Its *anterior surface* is separated from the Pectoralis major by the coraco-clavicular fascia, which, with the clavicle, forms an osseofibrous sheath for the muscle.

The **Serratus anterior** (*Serratus magnus*) (Fig. 520) is a thin muscular sheet, situated between the ribs and the scapula at the upper and lateral part of the chest. It *arises* by fleshy digitations from the outer surfaces and superior borders of the upper eight or nine ribs, and from the aponeuroses covering the intervening Intercostales. Each digitation (except the first) arises from the




FIG. 520.—Deep muscles of the chest and front of the arm, with the boundaries of the axilla.

corresponding rib; the first springs from the first and second ribs; and from the fascia covering the first intercostal space. From this extensive attachment the fibres pass backward, closely applied to the chest-wall, and reach the vertebral border of the scapula, and are inserted into its ventral surface in the following manner. The first digitation is inserted into a triangular area on the ventral surface of the medial angle. The next two digitations spread out to form a thin, triangular sheet, the base of which is directed backward and is inserted into nearly the whole length of the ventral surface of the vertebral border. The lower five or six digitations converge to form a fan-shaped mass, the apex of which is inserted, by muscular and tendinous fibres, into a triangular impression on the ventral surface of the inferior angle. The lower four slips interdigitate at their origins with the upper five slips of the Obliquus externus abdominis.



**Relations.**—This muscle is partly covered, in front, by the Pectorales and by the mamma: behind, by the Subscapularis. The axillary vessels and nerves lie upon its upper part, while its deep surface rests upon the ribs and Intercostales.

**Nerves.**—The Pectoralis major is supplied by the medial and lateral anterior thoracic nerves; through these nerves the muscle receives filaments from all the spinal nerves entering into the formation of the brachial plexus; the Pectoralis minor receives its fibres from the eighth cervical and first thoracic nerves through the medial anterior thoracic nerve. The Subclavius is supplied by a filament from the fifth and sixth cervical nerves; the Serratus anterior is supplied by the long thoracic, which is derived from the fifth, sixth, and seventh cervical nerves.

**Actions.**—If the arm has been raised by the Deltoideus, the Pectoralis major will, conjointly with the Latissimus dorsi and Teres major, depress it to the side of the chest. If acting alone, it adducts and draws forward the arm, bringing it across the front of the chest, and at the same time rotates it inward. The Pectoralis minor depresses the point of the shoulder, drawing the scapula downward and medialward toward the thorax, and throwing the inferior angle backward. The Subclavius depresses the shoulder, carrying it downward and forward. When the arms are fixed, all three of these muscles act upon the ribs; drawing them upward and expanding the chest, and thus becoming very important agents in forced inspiration. The Serratus anterior, as a whole, carries the scapula forward, and at the same time raises the vertebral border of the bone. It is therefore concerned in the action of pushing. Its lower and stronger fibres move forward the lower angle and assist the Trapezius in rotating the bone at the sternoclavicular joint, and thus assist this muscle in raising the acromion and supporting weights upon the shoulder. It is also an assistant to the Deltoideus in raising the arm, inasmuch as during the action of this latter muscle it fixes the scapula and so steadies the glenoid cavity on which the head of the humerus rotates. After the Deltoideus has raised the arm to a right angle with the trunk, the Serratus anterior and the Trapezius, by rotating the scapula, raise the arm into an almost vertical position. It is possible that when the shoulders are fixed the lower fibres of the Serratus anterior may assist in raising and everting the ribs; but it is not the important inspiratory muscle it was formerly believed to be.

**Applied Anatomy.**—When the Serratus anterior is paralyzed, the vertebral border, and especially the lower angle of the scapula, leave the ribs and stand out prominently on the surface, giving a peculiar "winged" appearance to the back (p. 309). The patient is unable to raise the arm, and an attempt to do so is followed by a further projection of the lower angle of the scapula from the back of the thorax.

### III. THE MUSCLES AND FASCIAE OF THE SHOULDER.

In this group are included:

Deltoideus.  
Subscapularis.  
Supraspinatus.

Infraspinatus.  
Teres minor.  
Teres major.

**Dissection.**—After completing the dissection of the axilla, if the muscles of the back have been dissected, the upper extremity should be separated from the trunk. Saw through the clavicle at its centre, and then cut through the muscles which connect the scapula and arm with the trunk—viz., the Pectoralis minor in front, Serratus anterior at the side, and the Levator anguli, the Rhomboideus, Trapezius, and Latissimus dorsi behind. These muscles should be cleaned and traced to their respective insertions. Then make an incision through the integument, commencing at the outer third of the clavicle, and extending along the margin of that bone, the acromion process, and spine of the scapula; the integument should be dissected from above downward and outward, when the fascia covering the Deltoideus will be exposed (Fig. 518, No. 3).

**Deep Fascia.**—The deep fascia covering the Deltoideus invests the muscle, and sends numerous septa between its fasciculi. In front it is continuous with the fascia covering the Pectoralis major; behind, where it is thick and strong, with that covering the Infraspinatus; above, it is attached to the clavicle, the acromion, and the spine of the scapula; below, it is continuous with the deep fascia of the arm.

The **Deltoideus** (*Deltoid muscle*) (Fig. 519) is a large, thick, triangular muscle, which covers the shoulder-joint in front, behind, and laterally. It *arises* from the anterior border and upper surface of the lateral third of the clavicle; from the lateral margin

and upper surface of the acromion, and from the lower lip of the posterior border of the spine of the scapula, as far back as the triangular surface at its medial end. From this extensive origin the fibres converge toward their insertion, the middle passing vertically, the anterior obliquely backward and lateralward, the posterior obliquely forward and lateralward; they unite in a thick tendon, which is inserted into the deltoid prominence on the middle of the lateral side of the body of the humerus. At its *insertion* the muscle gives off an expansion to the deep fascia of the arm. This muscle is remarkably coarse in texture, and the arrangement of its fibres is somewhat peculiar; the central portion of the muscle—that is to say, the part arising from the acromion—consists of oblique fibres; these arise in a bipenniform manner from the sides of the tendinous intersections, generally four in number, which are attached above to the acromion and pass downward parallel to one another in the substance of the muscle. The oblique fibres thus formed are inserted into similar tendinous intersections, generally three in number, which pass upward from the insertion of the muscle and alternate with the descending septa. The portions of the muscle arising from the clavicle and spine of the scapula are not arranged in this manner, but are inserted into the margins of the inferior tendon.

**Relations.**—The Deltoides is in relation by its *superficial surface* with the integument, the superficial and deep fasciæ, Platysma, and posterior supraclavicular nerves. Its *deep surface* is separated from the capsule of the shoulder-joint by a large bursa, and covers the coracoid process, coracoacromial ligament, Pectoralis minor, Coracobrachialis, both heads of the Biceps brachii, the tendon of the Pectoralis major, the insertions of the Supraspinatus, Infraspinatus, and Teres minor, the long and lateral heads of the Triceps brachii, the humeral circumflex vessels, the axillary nerve, and the upper part of the body of the humerus. Its *anterior border* is separated at its upper part from the Pectoralis major by a narrow interval, which lodges the cephalic vein and deltoid branch of the thoracoacromial artery; lower down the two muscles are in close contact. Its *posterior border* rests on the Infraspinatus and Triceps.

**Nerves.**—The Deltoides is supplied by the fifth and sixth cervical through the axillary nerve.

**Actions.**—The Deltoides raises the arm from the side, so as to bring it at right angles with the trunk. Its anterior fibres, assisted by the Pectoralis major, draw the arm forward; and its posterior fibres, aided by the Teres major and Latissimus dorsi, draw it backward.

**Applied Anatomy.**—The Deltoides is very liable to atrophy, and in this condition dislocation of the shoulder-joints is simulated, as there is flattening of the shoulder and apparent prominence of the acromion; the distance also between the acromion and the head of the bone is increased, and the tips of the fingers can be inserted between them. Atrophy of the Deltoides may be due to disuse, such as follows chronic arthritis or permanent injury of the shoulder-joint. It also frequently results from degenerations occurring in the medulla spinalis, or injury to the axillary nerve ("crutch palsy"). The Deltoides, Supraspinatus, and Infraspinatus often escape in myopathic atrophies affecting the other muscles of the upper arm or shoulder in young persons.

**Dissection.**—Divide the Deltoides across, near its upper part, by an incision carried along the margin of the clavicle, the acromion process and spine of the scapula, and reflect it downward, when the structures under cover of it will be seen.

**Subscapular Fascia** (*fascia subscapularis*).—The subscapular fascia is a thin membrane attached to the entire circumference of the subscapular fossa, and affording attachment by its deep surface to some of the fibres of the Subscapularis.

The **Subscapularis** (Fig. 520) is a large triangular muscle which fills the subscapular fossa, and *arises* from its medial two-thirds and from the lower two-thirds of the groove on the axillary border of the bone. Some fibres *arise* from tendinous laminae which intersect the muscle and are attached to ridges on the bone; others from an aponeurosis, which separates the muscle from the Teres major and the long head of the Triceps brachii. The fibres pass lateralward, and, gradually converging, end in a tendon which is *inserted* into the lesser tubercle of the humerus and the front of the capsule of the shoulder-joint. The tendon of the muscle is separated from the neck of the scapula by a large bursa, which communicates with the cavity of the shoulder-joint through an aperture in the capsule.

**Relations.**—The *anterior surface* of this muscle forms a considerable part of the posterior wall of the axilla, and is in relation with the Serratus anterior, Coracobrachialis, and Biceps brachii, the axillary vessels and brachial plexus of nerves, and the subscapular vessels and nerves. Its *posterior surface* is in relation with the scapula and the capsule of the shoulder-joint. Its *lower border* is in contact with the Teres major and Latissimus dorsi.

**Nerves.**—The Subscapularis is supplied by the fifth and sixth cervical nerves through the upper and lower subscapular nerves.

**Actions.**—The Subscapularis rotates the head of the humerus inward; when the arm is raised, it draws the humerus forward and downward. It is a powerful defence to the front of the shoulder-joint, preventing displacement of the head of the humerus.

**Dissection.**—To expose these muscles, and to examine their insertion into the humerus, detach the Deltoides and Trapezius from their attachment to the spine of the scapula and acromion process. Remove the clavicle by dividing the ligaments connecting it with the coracoid process, and separate it at its articulation with the scapula; divide the acromion process near its root with a saw. The fragments being removed, the tendons of the posterior Scapular muscles will be fully exposed. A block should be placed beneath the shoulder-joint, so as to make the muscles tense.




FIG. 521.—Muscles on the dorsum of the scapula, and the Triceps brachii.

**Supraspinatous Fascia** (*fascia supraspinata*).—The supraspinatous fascia completes the osseofibrous case in which the Supraspinatus muscle is contained; it affords attachment, by its deep surface, to some of the fibres of the muscle. It is thick medially, but thinner laterally under the coracoacromial ligament.

The **Supraspinatus** (Fig. 521) occupies the whole of the supraspinatous fossa, arising from its medial two-thirds, and from the strong supraspinatous fascia. The muscular fibres converge to a tendon, which crosses the upper part of the shoulder-joint, and is inserted into the highest of the three impressions on the greater tubercle of the humerus; the tendon is intimately adherent to the capsule of the shoulder-joint.

**Infraspinatous Fascia** (*fascia infraspinata*).—The infraspinatous fascia is a dense fibrous membrane, covering the Infraspinatous muscle and fixed to the circumference of the infraspinatous fossa; it affords attachment, by its deep surface, to some fibres of that muscle. It is intimately attached to the deltoid fascia along the overlapping border of the Deltoideus.

The **Infraspinatus** (Fig. 521) is a thick triangular muscle, which occupies the chief part of the infraspinatous fossa; it *arises* by fleshy fibres from its medial two-thirds, and by tendinous fibres from the ridges on its surface; it also arises from the infraspinatous fascia which covers it, and separates it from the Teretes major and minor. The fibres converge to a tendon, which glides over the lateral border of the spine of the scapula, and, passing across the posterior part of the capsule of the shoulder-joint, is *inserted* into the middle impression on the greater tubercle of the humerus. The tendon of this muscle is sometimes separated from the capsule of the shoulder-joint by a bursa, which may communicate with the joint cavity.

The **Teres minor** (Fig. 521) is a narrow, elongated muscle, which *arises* from the dorsal surface of the axillary border of the scapula for the upper two-thirds of its extent, and from two aponeurotic laminæ, one of which separates it from the *Infraspinatus*, the other from the *Teres major*. Its fibres run obliquely upward and lateralward; the upper ones end in a tendon which is *inserted* into the lowest of the three impressions on the greater tubercle of the humerus; the lowest fibres are *inserted* directly into the humerus immediately below this impression. The tendon of this muscle passes across, and is united with, the posterior part of the capsule of the shoulder-joint.

The **Teres major** (Fig. 521) is a thick but somewhat flattened muscle, which *arises* from the oval area on the dorsal surface of the inferior angle of the scapula, and from the fibrous septa interposed between the muscle and the *Teres minor* and *Infraspinatus*; the fibres are directed upward and lateralward, and end in a flat tendon, about 5 cm. long, which is *inserted* into the crest of the lesser tubercle of the humerus. The tendon, at its insertion, lies behind that of the *Latissimus dorsi*, from which it is separated by a bursa, the two tendons being, however, united along their lower borders for a short distance.

**Nerves.**—The *Supraspinatus* and *Infraspinatus* are supplied by the fifth and sixth cervical nerves through the suprascapular nerve; the *Teres minor*, by the fifth cervical, through the axillary; and the *Teres major*, by the fifth and sixth cervical, through the lowest subscapular.

**Actions.**—The *Supraspinatus* assists the *Deltoideus* in raising the arm from the side of the trunk and fixes the head of the humerus in the glenoid cavity. The *Infraspinatus* and *Teres minor* rotate the head of the humerus outward; they also assist in carrying the arm backward. One of the most important uses of these three muscles is to protect the shoulder-joint, the *Supraspinatus* supporting it above, and the *Infraspinatus* and *Teres minor* behind. The *Teres major* assists the *Latissimus dorsi* in drawing the previously raised humerus downward and backward, and in rotating it inward; when the arm is fixed it may assist the *Pectorales* and the *Latissimus dorsi* in drawing the trunk forward.

#### IV. THE MUSCLES AND FASCIÆ OF THE ARM.

The muscles of the arm are:

Coracobrachialis.  
Biceps brachii.

Brachialis.  
Triceps brachii.

**Dissection.**—The arm being placed on the table, with the front surface uppermost, make a vertical incision through the integument along the middle line, from the clavicle to about two inches below the elbow-joint, where it should be joined by a transverse incision, extending from the inner to the outer side of the forearm; the two flaps being reflected on either side, the fascia should be examined (Fig. 518).

**Brachial Fascia** (*fascia brachii*; *deep fascia of the arm*).—The brachial fascia is continuous with that covering the Deltoides and the Pectoralis major, by means of which it is attached, above, to the clavicle, acromion, and spine of the scapula; it forms a thin, loose, membranous sheath for the muscles of the arm, and sends septa between them; it is composed of fibres disposed in a circular or spiral direction, and connected together by vertical and oblique fibres. It differs in thickness at different parts, being thin over the Biceps brachii, but thicker where it covers the Triceps brachii, and over the epicondyles of the humerus: it is strengthened by fibrous aponeuroses, derived from the Pectoralis major and Latissimus dorsi medially, and from the Deltoides laterally. On either side it gives off a strong intermuscular septum, which is attached to the corresponding supracondylar ridge and epicondyle of the humerus. The **lateral intermuscular septum** extends from the lower part of the crest of the greater tubercle, along the lateral supracondylar ridge, to the lateral epicondyle; it is blended with the tendon of the Deltoides, gives attachment to the Triceps brachii behind, to the Brachialis, Brachioradialis, and Extensor carpi radialis longus in front, and is perforated by the radial nerve and profunda branch of the brachial artery. The **medial intermuscular septum**, thicker than the preceding, extends from the lower part of the crest of the lesser tubercle of the humerus below the Teres major, along the medial supracondylar ridge to the medial epicondyle; it is blended with the tendon of the Coracobrachialis, and affords attachment to the Triceps brachii behind and the Brachialis in front. It is perforated by the ulnar nerve, the superior ulnar collateral artery, and the posterior branch of the inferior ulnar collateral artery. At the elbow, the deep fascia is attached to the epicondyles of the humerus and the olecranon of the ulna, and is continuous with the deep fascia of the forearm. Just below the middle of the arm, on its medial side, is an oval opening in the deep fascia, which transmits the basilic vein and some lymphatic vessels.

The **Coracobrachialis** (Fig. 520), the smallest of the three muscles in this region, is situated at the upper and medial part of the arm. It *arises* from the apex of the coracoid process, in common with the short head of the Biceps brachii, and from the intermuscular septum between the two muscles; it is *inserted* by means of a flat tendon into an impression at the middle of the medial surface and border of the body of the humerus between the origins of the Triceps brachii and Brachialis. It is perforated by the musculocutaneous nerve.

**Relations.**—The Coracobrachialis is in relation, in *front*, with the Pectoralis major above, and at its insertion with the brachial vessels and median nerve which cross it; *behind*, with the tendons of the Subscapularis, Latissimus dorsi, and Teres major, the medial head of the Triceps brachii, the humerus, and the anterior humeral circumflex vessels; by its *medial border*, with the third part of the axillary and upper part of the brachial artery and the median and musculocutaneous nerves; by its *lateral border*, with the short head of the Biceps brachii and Brachialis.

The **Biceps brachii** (*Biceps*; *Biceps flexor cubiti*) (Fig. 520) is a long fusiform muscle, placed on the front of the arm, and *arising* by two heads, from which circumstance it has received its name. The **short head** *arises* by a thick flattened tendon from the apex of the coracoid process, in common with the Coracobrachialis. The **long head** *arises* from the supraglenoid tuberosity at the upper margin of the glenoid cavity, and is continuous with the glenoidal labrum. This tendon, enclosed in a special sheath of the synovial membrane of the shoulder-joint, arches over the head of the humerus; it emerges from the capsule through an opening close to the humeral attachment of the ligament, and descends in the intertubercular groove; it is retained in the groove by the transverse humeral ligament and by a fibrous prolongation from the tendon of the Pectoralis major. Each tendon is succeeded by an elongated muscular belly, and the two bellies, although closely applied to each other, can readily be separated until within about 7.5 cm. of the elbow-joint. Here they end in a flattened tendon, which is inserted into the rough

posterior portion of the tuberosity of the radius, a bursa being interposed between the tendon and the front part of the tuberosity. As the tendon of the muscle approaches the radius it is twisted upon itself, so that its anterior surface becomes lateral and is applied to the tuberosity of the radius at its insertion. Opposite the bend of the elbow the tendon gives off, from its medial side, a broad aponeurosis, the *lacertus fibrosus* (*bicipital fascia*) which passes obliquely downward and medialward across the brachial artery, and is continuous with the deep fascia covering the origins of the Flexor muscles of the forearm (Fig. 519).

A third head to the Biceps brachii is occasionally found, arising at the upper and medial part of the Brachialis, with the fibres of which it is continuous, and inserted into the lacertus fibrosus and medial side of the tendon of the muscle. In most cases this additional slip lies behind the brachial artery in its course down the arm. In some instances the third head consists of two slips, which pass down, one in front of and the other behind the artery, concealing the vessel in the lower half of the arm.

**Relations.**—The Biceps brachii is overlapped above by the Pectoralis major and Deltoideus; in the rest of its extent it is covered by the superficial and deep fasciæ and the integument. It rests above on the shoulder-joint and upper part of the humerus; below, it lies on the Brachialis, the musculocutaneous nerve, and the Supinator. Its *medial border* is in relation with the Coracobrachialis, and overlaps the brachial vessels and median nerve; its *lateral border*, with the Deltoideus and Brachioradialis.

The **Brachialis** (*Brachialis anticus*) (Fig. 520) covers the front of the elbow-joint and the lower half of the humerus. It *arises* from the lower half of the front of the humerus, commencing above at the insertion of the Deltoideus, which it embraces by two angular processes. Its origin extends below to within 2.5 cm. of the margin of the articular surface. It also arises from the intermuscular septa, but more extensively from the medial than the lateral; it is separated from the lateral below by the Brachioradialis and Extensor carpi radialis longus. Its fibres converge to a thick tendon, which is *inserted* into the tuberosity of the ulna and the rough depression on the anterior surface of the coronoid process.

**Relations.**—The Brachialis is in relation, in *front*, with the Biceps brachii, the brachial vessels, musculocutaneous and median nerves; *behind*, with the humerus and front of the elbow-joint; by its *medial border*, with the Triceps brachii, ulnar nerve, and Pronator teres, from which it is separated by the intermuscular septum; by its *lateral border*, with the radial nerve, radial recurrent artery, the Brachioradialis and Extensor carpi radialis longus.

**Nerves.**—The Coracobrachialis, Biceps brachii and Brachialis are supplied by the musculocutaneous nerve; the Brachialis usually receives an additional filament from the radial. The Coracobrachialis receives its supply primarily from the seventh cervical, the Biceps brachii and Brachialis from the fifth and sixth cervical nerves.

**Actions.**—The Coracobrachialis draws the humerus forward and medialward, and at the same time assists in retaining the head of the bone in contact with the glenoid cavity. The Biceps brachii is a flexor of the elbow and, to a less extent, of the shoulder; it is also a powerful supinator, and serves to render tense the deep fascia of the forearm by means of the lacertus fibrosus given off from its tendon. The Brachialis is a flexor of the forearm, and forms an important defence to the elbow-joint. When the forearm is fixed, the Biceps brachii and Brachialis flex the arm upon the forearm, as in efforts of climbing.

**Applied Anatomy.**—The long tendon of the Biceps brachii is sometimes dislocated from the intertubercular groove. When this has taken place, the arm is fixed in a position of abduction, but the head of the humerus can be felt in its proper position. It can generally be replaced by flexing the forearm on the arm and rotating the limb. Rupture of the long tendon of the Biceps brachii may also take place.

The **Triceps brachii** (*Triceps*; *Triceps extensor cubiti*) (Fig. 521) is situated on the back of the arm, extending the entire length of the dorsal surface of the humerus. It is of large size, and arises by three heads (long, lateral, and medial), hence its name.

The **long head** *arises* by a flattened tendon from the infraglenoid tuberosity of the scapula, being blended at its upper part with the capsule of the shoulder-joint; the muscular fibres pass downward between the two other heads of the muscle, and join with them in the tendon of insertion.



The **lateral head** *arises* from the posterior surface of the body of the humerus, between the insertion of the Teres minor and the upper part of the groove for the radial nerve, and from the lateral border of the humerus and the lateral intermuscular septum; the fibres from this origin converge toward the tendon of insertion.

The **medial head** *arises* from the posterior surface of the body of the humerus, below the groove for the radial nerve; it is narrow and pointed above, and extends from the insertion of the Teres major to within 2.5 cm. of the trochlea: it also arises from the medial border of the humerus and from the back of the whole length of the medial intermuscular septum. Some of the fibres are directed downward to the olecranon, while others converge to the tendon of insertion.

The **tendon of the Triceps brachii** begins about the middle of the muscle: it consists of two aponeurotic laminae, one of which is subcutaneous and covers the back of the lower half of the muscle; the other is more deeply seated in the substance of the muscle. After receiving the attachment of the muscular fibres, the two lamellae join together above the elbow, and are inserted, for the most part, into the posterior portion of the upper surface of the olecranon; a band of fibres is, however, continued downward, on the lateral side, over the Anconaeus, to blend with the deep fascia of the forearm.

The long head of the Triceps brachii descends between the Teres minor and Teres major, dividing the triangular space between these two muscles and the humerus into two smaller spaces, one triangular, the other quadrangular (Fig. 521). The triangular space contains the scapular circumflex vessels; it is bounded by the Teres minor above, the Teres major below, and the scapular head of the Triceps laterally. The quadrangular space transmits the posterior humeral circumflex vessels and the axillary nerve; it is bounded by the Teres minor and capsule of the shoulder-joint above, the Teres major below, the long head of the Triceps brachii medially, and the humerus laterally.

The **Subanconaeus** is the name given to a few fibres which spring from the deep surface of the lower part of the Triceps brachii, and are inserted into the posterior ligament and synovial membrane of the elbow-joint.

**Nerves.**—The Triceps brachii is supplied by the seventh and eighth cervical nerves through the radial nerve.

**Actions.**—The Triceps brachii is the great extensor muscle of the forearm, and is the direct antagonist of the Biceps brachii and Brachialis. When the arm is extended, the long head of the muscle may assist the Teres major and Latissimus dorsi in drawing the humerus backward and in adducting it to the thorax. The long head supports the under part of the shoulder-joint. The Subanconaeus draws up the synovial membrane of the elbow-joint during extension of the forearm.

**Applied Anatomy.**—The continuity of the insertion of the Triceps brachii with the deep fascia of the forearm is of importance in the operation of excision of the elbow; it should always be carefully preserved from injury. By means of these fibres the patient is enabled to extend the forearm, a movement which would otherwise be accomplished mainly by gravity—that is to say, by allowing the forearm to drop by its own weight.

## V. THE MUSCLES AND FASCIAE OF THE FOREARM.

**Dissection.**—To dissect the forearm, place the limb in the position indicated in Fig. 518, make a vertical incision along the middle line from the elbow to the wrist, and a transverse incision at the extremity of this; the superficial structures being removed, the deep fascia of the forearm is exposed.

**Antibrachial Fascia** (*fascia antibrachii*; *deep fascia of the forearm*).—The antibrachial fascia continuous above with the brachial fascia, is a dense, membranous investment, which forms a general sheath for the muscles in this region; it is attached, *behind*, to the olecranon and dorsal border of the ulna, and gives off from its deep surface numerous intermuscular septa, which enclose each muscle separately. Over the Flexor tendons as they approach the wrist it is especially thickened, and forms the volar carpal ligament. This is continuous with the transverse carpal ligament, and forms a sheath for the tendon of the Palmaris longus which passes over the transverse carpal ligament to be inserted into the palmar aponeurosis. *Behind*,

near the wrist-joint, it is thickened by the addition of many transverse fibres, and forms the dorsal carpal ligament. It is much thicker on the dorsal than on the volar surface, and at the lower than at the upper part of the forearm, and is strengthened above by tendinous fibres derived from the Biceps brachii in front, and from the Triceps brachii behind. It gives origin to muscular fibres, especially at the upper part of the medial and lateral sides of the forearm, and forms the boundaries of a series of cone-shaped cavities, in which the muscles are contained. Besides the vertical septa separating the individual muscles, transverse septa are given off both on the volar and dorsal surfaces of the forearm, separating the deep from the superficial layers of muscles. Apertures exist in the fascia for the passage of vessels and nerves; one of these apertures of large size, situated at the front of the elbow, serves for the passage of a communicating branch between the superficial and deep veins.

The antibrachial or forearm muscles may be divided into a **volar** and a **dorsal** group.

### 1. The Volar Antibrachial Muscles.

These muscles are divided for convenience of description into two groups, superficial and deep.

#### The Superficial Group (Fig. 522).

Pronator teres.

Palmaris longus.

Flexor carpi radialis.

Flexor carpi ulnaris.

Flexor digitorum sublimis.

The muscles of this group take origin from the medial epicondyle of the humerus by a common tendon; they receive additional fibres from the deep fascia of the forearm near the elbow, and from the septa which pass from this fascia between the individual muscles.

The **Pronator teres** has two heads of origin—humeral and ulnar. The **humeral head**, the larger and more superficial, *arises* immediately above the medial epicondyle, and from the tendon common to the origin of the other muscles; also from the intermuscular septum between it and the Flexor carpi radialis and from the antibrachial fascia. The **ulnar head** is a thin fasciculus, which *arises* from the medial side of the coronoid process of the ulna, and joins the preceding at an acute angle. The median nerve enters the forearm between the two heads of the muscle, and is separated from the ulnar artery by the ulnar head. The muscle passes obliquely across the forearm, and ends in a flat tendon, which is inserted into a rough impression at the middle of the lateral surface of the body of the radius. The lateral border of the muscle forms the medial boundary of a triangular hollow situated in front of the elbow-joint and containing the brachial artery, median nerve, and tendon of the Biceps brachii.

**Applied Anatomy.**—This muscle, when suddenly brought into active use, as in the game of lawn tennis, is apt to be strained, producing slight swelling, tenderness, and pain on putting the muscle, into action. This is known as "lawn-tennis arm."

The **Flexor carpi radialis** lies on the medial side of the preceding muscle. It *arises* from the medial epicondyle by the common tendon; from the fascia of the forearm; and from the intermuscular septa between it and the Pronator teres laterally, the Palmaris longus medially, and the Flexor digitorum sublimis beneath. Slender and aponeurotic in structure at its commencement, it increases in size, and ends in a tendon which forms rather more than the lower half of its length. This tendon passes through a canal in the lateral part of the transverse carpal ligament and runs through a groove on the greater multangular bone; the groove is converted into a canal by fibrous tissue, and lined by a mucous sheath. The tendon is inserted into the base of the second metacarpal bone, and sends a slip to

the base of the third metacarpal bone. The radial artery, in the lower part of the forearm, lies between the tendon of this muscle and the Brachioradialis.

The **Palmaris longus** is a slender, fusiform muscle, lying on the medial side of the preceding. It *arises* from the medial epicondyle of the humerus by the common tendon, from the intermuscular septa between it and the adjacent muscles, and from the anti-brachial fascia. It ends in a slender,




FIG. 522.—Front of the left forearm. Superficial muscles.




FIG. 523.—Front of the left forearm. Deep muscles.

flattened tendon, which passes over the upper part of the transverse carpal ligament, and is *inserted* into the central part of the transverse carpal ligament and lower part of the palmar aponeurosis, frequently sending a tendinous slip to the short muscles of the thumb.

This muscle is often absent, and is subject to very considerable variations; it may be tendinous above and muscular below; or it may be muscular in the centre with a tendon above and below; or it may present two muscular bundles with a central tendon; or finally it may consist solely of a tendinous band. Just above the wrist, the median nerve lies close to the tendon, on its lateral and dorsal aspects.

The **Flexor carpi ulnaris** lies along the ulnar side of the forearm. It *arises* by two heads, humeral and ulnar, connected by a tendinous arch, beneath which the ulnar nerve and posterior ulnar recurrent artery pass. The **humeral head** *arises* from the medial epicondyle of the humerus by the common tendon; the **ulnar head** *arises* from the medial margin of the olecranon and from the upper two-thirds of the dorsal border of the ulna by an aponeurosis, common to it and the Extensor carpi ulnaris and Flexor digitorum profundus; and from the intermuscular septum between it and the Flexor digitorum sublimis. The fibres end in a tendon, which occupies the anterior part of the lower half of the muscle and is *inserted* into the pisiform bone, and is prolonged from this to the hamate and fifth metacarpal bones by the pisohamate and pisometacarpal ligaments; it is also attached by a few fibres to the transverse carpal ligament. The ulnar vessels and nerve lie on the lateral side of the tendon of this muscle, in the lower two-thirds of the forearm.

The **Flexor digitorum sublimis** is placed beneath the previous muscle; it is the largest of the muscles of the superficial group, and arises by three heads—humeral, ulnar, and radial. The **humeral head** *arises* from the medial epicondyle of the humerus by the common tendon, from the ulnar collateral ligament of the elbow-joint, and from the intermuscular septa between it and the preceding muscles. The **ulnar head** *arises* from the medial side of the coronoid process, above the ulnar origin of the Pronator teres (see Fig. 353, page 316). The **radial head** *arises* from the oblique line of the radius, extending from the radial tuberosity to the insertion of the Pronator teres. The muscle speedily separates into two planes of muscular fibres, superficial and deep: the superficial plane divides into two parts which end in tendons for the middle and ring fingers; the deep plane gives off a muscular slip to join the portion of the superficial plane which is associated with the tendon of the ring finger, and then divides into two parts, which end in tendons for the index and little fingers. As the four tendons thus formed pass beneath the transverse carpal ligament into the palm of the hand, they are arranged in pairs, the superficial pair going to the middle and ring fingers, the deep pair to the index and little fingers. The tendons diverge from one another in the palm and form dorsal relations to the superficial volar arch and digital branches of the median and ulnar nerves. Opposite the bases of the first phalanges each tendon divides into two slips to allow of the passage of the corresponding tendon of the Flexor digitorum profundus; the two slips then reunite and form a grooved channel for the reception of the accompanying tendon of the Flexor digitorum profundus. Finally the tendon divides and is inserted into the sides of the second phalanx about its middle.

#### The Deep Group (Fig. 523).

Flexor digitorum profundus.

Flexor pollicis longus.

Pronator quadratus.

**Dissection.**—Divide each of the superficial muscles at its centre, and turn either end aside; the deep layer of muscles, together with the median nerve and ulnar vessels, will then be exposed

The **Flexor digitorum profundus** is situated on the ulnar side of the forearm, immediately beneath the superficial Flexors. It *arises* from the upper three-fourths of the volar and medial surfaces of the body of the ulna, embracing the insertion of the Brachialis above, and extending below to within a short distance of the Pronator quadratus. It also arises from a depression on the medial side of the coronoid process; by an aponeurosis from the upper three-fourths of the dorsal border of the ulna, in common with the Flexor and Extensor carpi ulnaris; and from the ulnar half of the interosseous membrane. The muscle ends in four tendons which run under the transverse carpal ligament dorsal to the tendons of the Flexor digitorum sublimis. Opposite the first phalanges the tendons pass through the openings in the tendons of the Flexor digitorum sublimis, and are finally *inserted* into the bases of the last phalanges. The portion of the muscle for the index finger is usually distinct throughout, but the tendons for the middle, ring, and little fingers are connected together by areolar tissue and tendinous slips, as far as the palm of the hand.

**Fibrous Sheaths of the Flexor Tendons.**—After leaving the palm, the tendons of the Flexores digitorum sublimis and profundus lie in osseo-aponeurotic canals (Fig. 534), formed behind by the phalanges and in front by strong fibrous bands, which arch across the tendons, and are attached on either side to the margins of the phalanges. Opposite the middle of the proximal and second phalanges the bands (digital vaginal ligaments) are very strong, and the fibres are transverse; but opposite the joints they are much thinner, and consist of *annular* and *cruciate* ligamentous fibres. Each canal contains a mucous sheath, which is reflected on the contained tendons.

Within each canal the tendons of the Flexores digitorum sublimis and profundus are connected to each other, and to the phalanges, by slender, tendinous bands, called **vincula tendina** (Fig. 524). There are two sets of these; (*a*) the **vincula brevia**, which are two in number in each finger, and consist of triangular bands of fibres, one connecting the tendon of the Flexor digitorum sublimis to the front of the first interphalangeal joint and head of the first phalanx, and the other the tendon of the Flexor digitorum profundus to the front of the second interphalangeal joint and head of the second phalanx; (*b*) the **vincula longa**, which connect the under surfaces of the tendons of the Flexor digitorum profundus to those of the subjacent Flexor sublimis after the tendons of the former have passed through the latter.

Four small muscles, the Lumbricales, are connected with the tendons of the Flexor profundus in the palm. They will be described with the muscles of the hand (page 555).

The **Flexor pollicis longus** is situated on the radial side of the forearm, lying in the same plane as the preceding. It *arises* from the grooved volar surface of the body of the radius, extending from immediately below the tuberosity and oblique line to within a short distance of the Pronator quadratus. It *arises* also from the adjacent part of the interosseous membrane, and generally by a fleshy slip from the medial border of the coronoid process, or from the medial epicondyle of the humerus. The fibres end in a flattened tendon, which passes beneath the transverse carpal ligament, is then lodged between the lateral head of the Flexor pollicis brevis and the oblique part of the Adductor pollicis, and, entering an osseo-aponeurotic canal similar to those for the Flexor tendons of the fingers, is *inserted* into the base of the distal phalanx of the thumb. The volar interosseous nerve and vessels pass downward on the front of the interosseous membrane between the Flexor pollicis longus and Flexor digitorum profundus.

The **Pronator quadratus** is a small, flat, quadrilateral muscle, extending across the front of the lower parts of the radius and ulna. It *arises* from the pronator ridge on the lower part of the volar surface of the body of the ulna; from the medial

part of the volar surface of the lower fourth of the ulna; and from a strong aponeurosis which covers the medial third of the muscle. The fibres pass lateralward and slightly downward, to be inserted into the lower fourth of the lateral border and the volar surface of the body of the radius. The deeper fibres of the muscle are inserted into the triangular area above the ulnar notch of the radius—an attachment comparable with the origin of the Supinator from the triangular area below the radial notch of the ulna.




FIG. 524.—Tendons of forefinger and vincula tendina

**Nerves.**—All the muscles of the superficial layer are supplied by the median nerve, excepting the Flexor carpi ulnaris, which is supplied by the ulnar. The Pronator teres, the Flexor carpi radialis, and the Palmaris longus derive their supply primarily from the sixth cervical nerve; the Flexor digitorum sublimis from the seventh and eighth cervical and first thoracic nerves, and the Flexor carpi ulnaris from the eighth cervical and first thoracic. Of the deep layer, the Flexor digitorum profundus is supplied by the eighth cervical and first thoracic through the ulnar, and the volar interosseous branch of the median. The Flexor pollicis longus and Pronator quadratus are supplied by the eighth cervical and first thoracic through the volar interosseous branch of the median.

**Actions.**—These muscles act upon the forearm, the wrist, and hand. The Pronator teres rotates the radius upon the ulna, rendering the hand prone; when the radius is fixed, it assists in flexing the forearm. The Flexor carpi radialis is a flexor and abductor of the wrist; it also assists in pronating the hand, and in bending the elbow. The Flexor carpi ulnaris is a flexor and adductor of the wrist; it also assists in bending the elbow. The Palmaris longus is a flexor of the wrist-joint; it also assists in flexing the elbow. The Flexor digitorum sublimis flexes first the middle and then the proximal phalanges; it also assists in flexing the wrist and elbow. The Flexor digitorum profundus is one of the flexors of the phalanges. After the Flexor sublimis has bent the second phalanx, the Flexor profundus flexes the terminal one; but it cannot do so until after the contraction of the superficial muscle. It also assists in flexing the wrist. The



*Flexor pollicis longus* is a flexor of the phalanges of the thumb; when the thumb is fixed, it assists in flexing the wrist. The *Pronator quadratus* rotates the radius upon the ulna, rendering the hand prone.

## 2. The Dorsal Antibrachial Muscles.

These muscles are divided for convenience of description into two groups, superficial and deep.

### The Superficial Group (Fig. 525).

<i>Brachioradialis</i> .	<i>Extensor digitorum communis</i> .
<i>Extensor carpi radialis longus</i> .	<i>Extensor digiti quinti proprius</i> .
<i>Extensor carpi radialis brevis</i> .	<i>Extensor carpi ulnaris</i> .
<i>Anconaeus</i> .	

**Dissection.**—Divide the integument in the same manner as in the dissection of the volar anti-brachial region, and, after having examined the cutaneous vessels and nerves and deep fascia, remove all those structures. The muscles will then be exposed. The removal of the fascia will be considerably facilitated by detaching it from below upward. Great care should be taken to avoid cutting across the tendons of the muscles of the thumb, which cross obliquely the larger tendons running down the back of the radius.

The ***Brachioradialis*** (*Supinator longus*) is the most superficial muscle on the radial side of the forearm. It *arises* from the upper two-thirds of the lateral supracondylar ridge of the humerus, and from the lateral intermuscular septum, being limited above by the groove for the radial nerve. Interposed between it and the *Brachialis* are the radial nerve and the anastomosis between the anterior branch of the profunda artery and the radial recurrent. The fibres end above the middle of the forearm in a flat tendon, which is *inserted* into the lateral side of the base of the styloid process of the radius. The tendon is crossed near its insertion by the tendons of the *Abductor pollicis longus* and *Extensor pollicis brevis*; on its ulnar side is the radial artery.

The ***Extensor carpi radialis longus*** (*Extensor carpi radialis longior*) is placed partly beneath the *Brachioradialis*. It *arises* from the lower third of the lateral supracondylar ridge of the humerus, from the lateral intermuscular septum, and by a few fibres from the common tendon of origin of the *Extensor* muscles of the forearm. The fibres end at the upper third of the forearm in a flat tendon, which runs along the lateral border of the radius, beneath the *Abductor pollicis longus* and *Extensor pollicis brevis*; it then passes beneath the dorsal carpal ligament, where it lies in a groove on the back of the radius common to it and the *Extensor carpi radialis brevis*, immediately behind the styloid process. It is *inserted* into the dorsal surface of the base of the second metacarpal bone, on its radial side.

The ***Extensor carpi radialis brevis*** (*Extensor carpi radialis brevior*) is shorter and thicker than the preceding muscle, beneath which it is placed. It *arises* from the lateral epicondyle of the humerus, by a tendon common to it and the three following muscles; from the radial collateral ligament of the elbow-joint; from a strong aponeurosis which covers its surface; and from the intermuscular septa between it and the adjacent muscles. The fibres end about the middle of the forearm in a flat tendon, which is closely connected with that of the preceding muscle, and accompanies it to the wrist; it passes beneath the *Abductor pollicis longus* and *Extensor pollicis brevis*, then beneath the dorsal carpal ligament, and is *inserted* into the dorsal surface of the base of the third metacarpal bone on its radial side. Under the dorsal carpal ligament the tendon lies on the back of the radius in a shallow groove, to the ulnar side of that which lodges the tendon of the *Extensor carpi radialis, longus*, and separated from it by a faint ridge.

The tendons of the two preceding muscles pass through the same compartment of the dorsal carpal ligament in a single mucous sheath.




FIG. 525.—Posterior surface of the forearm. Superficial muscles.




FIG. 526.—Posterior surface of the forearm. Deep muscles.

The **Extensor digitorum communis** arises from the lateral epicondyle of the humerus, by the common tendon; from the intermuscular septa between it and the adjacent muscles, and from the antibrachial fascia. It divides below into four tendons, which pass, together with that of the Extensor indicis proprius, through a separate compartment of the dorsal carpal ligament, within a mucous sheath. The tendons then diverge on the back of the hand, and are inserted into the second and third phalanges of the fingers in the following manner. Opposite the metacarpophalangeal articulation each tendon is bound by fasciculi to the collateral ligaments and serves as the dorsal ligament of this joint; after having crossed the joint, it spreads out into a broad aponeurosis, which covers the dorsal surface of the first phalanx and is reinforced, in this situation, by the tendons of the Interossei and Lumbricalis. Opposite the first interphalangeal joint this aponeurosis divides into three slips; an intermediate and two collateral: the former is inserted into the base of the second phalanx; and the two collateral, which are continued onward along the sides of the second phalanx, unite by their contiguous margins, and are inserted into the dorsal surface of the last phalanx. As the tendons cross the interphalangeal joints, they furnish them with dorsal ligaments. The tendon to the index finger is accompanied by the Extensor indicis proprius, which lies on its ulnar side. On the back of the hand, the tendons to the middle, ring, and little fingers are connected by two obliquely placed bands, one from the third tendon passing downward and lateralward to the second tendon, and the other passing from the same tendon downward and medialward to the fourth. Occasionally the first tendon is connected to the second by a thin transverse band.

The **Extensor digiti quinti proprius** (*Extensor minimi digiti*) is a slender muscle placed on the medial side of the Extensor digitorum communis, with which it is generally connected. It arises from the common Extensor tendon by a thin tendinous slip, from the intermuscular septa between it and the adjacent muscles. Its tendon runs through a compartment of the dorsal carpal ligament behind the distal radio-ulnar joint, then divides into two as it crosses the hand, and finally joins the expansion of the Extensor digitorum communis tendon on the dorsum of the first phalanx of the little finger.

The **Extensor carpi ulnaris** lies on the ulnar side of the forearm. It arises from the lateral epicondyle of the humerus, by the common tendon; by an aponeurosis from the dorsal border of the ulna in common with the Flexor carpi ulnaris and the Flexor digitorum profundus; and from the deep fascia of the forearm. It ends in a tendon, which runs in a groove between the head and the styloid process of the ulna, passing through a separate compartment of the dorsal carpal ligament, and is inserted into the prominent tubercle on the ulnar side of the base of the fifth metacarpal bone.

The **Anconaeus** is a small triangular muscle which is placed on the back of the elbow-joint, and appears to be a continuation of the Triceps brachii. It arises by a separate tendon from the back part of the lateral epicondyle of the humerus; its fibres diverge and are inserted into the side of the olecranon, and upper fourth of the dorsal surface of the body of the ulna.

#### The Deep Group (Fig. 526).

Supinator.

Abductor pollicis longus.

Extensor pollicis brevis.

Extensor pollicis longus.

Extensor indicis proprius.

The **Supinator** (*Supinator brevis*) (Fig. 527) is a broad muscle, curved around the upper third of the radius. It consists of two planes of fibres, between which the deep branch of the radial nerve lies. The two planes arise in common—the superficial one by tendinous and the deeper by muscular fibres—from the lateral



epicondyle of the humerus; from the radial collateral ligament of the elbow-joint, and the annular ligament; from the ridge on the ulna, which runs obliquely downward from the dorsal end of the radial notch; from the triangular depression below the notch; and from a tendinous expansion which covers the surface of the muscle. The superficial fibres surround the upper part of the radius, and are inserted into the lateral edge of the radial tuberosity and the oblique line of the radius, as low down as the insertion of the Pronator teres. The upper fibres of the deeper plane form a sling-like fasciculus, which encircles the neck of the radius above the tuberosity and is attached to the back part of its medial surface; the greater part of this portion of the muscle is inserted into the dorsal and lateral surfaces of the body of the radius, midway between the oblique line and the head of the bone.

The **Abductor pollicis longus** (*Extensor oss. metacarpi pollicis*) lies immediately below the Supinator and is sometimes united with it. It arises from the lateral part of the dorsal surface of the body of the ulna below the insertion of the Anconeus, from the interosseous membrane, and from the middle third of the dorsal surface of the body of the radius. Passing obliquely downward and lateralward, it ends in a tendon, which runs through a groove on the lateral side of the lower end of the radius, accompanied by the tendon of the Extensor pollicis brevis, and is inserted into the radial side of the base of the first metacarpal bone. It occasionally gives off two slips near its insertion: one to the greater multangular bone and the other to blend with the origin of the Abductor pollicis brevis.

The **Extensor pollicis brevis** (*Extensor primi internodii pollicis*) lies on the medial side of, and is closely connected with, the Abductor pollicis

longus. It arises from the dorsal surface of the body of the radius below that muscle, and from the interosseous membrane. Its direction is similar to that of the Abductor pollicis longus, its tendon passing through the same groove on the lateral side of the lower end of the radius, to be inserted into the base of the first phalanx of the thumb.

The **Extensor pollicis longus** (*Extensor secundi internodii pollicis*) is much larger than the preceding muscle, the origin of which it partly covers. It arises from the lateral part of the middle third of the dorsal surface of the body of the ulna below the origin of the Abductor pollicis longus, and from the interosseous membrane. It ends in a tendon, which passes through a separate compartment in the dorsal carpal ligament, lying in a narrow, oblique groove on the back of the lower end of the radius. It then crosses obliquely the tendons of the Extensores carpi radialis longus and brevis, and is separated from the Extensor brevis pollicis by a




FIG. 527.—The Supinator.

triangular interval, in which the radial artery is found; and is finally *inserted* into the base of the last phalanx of the thumb. The radial artery is crossed by the tendons of the Abductor pollicis longus and of the Extensores pollicis longus and brevis.

The **Extensor indicis proprius** (*Extensor indicis*) is a narrow, elongated muscle, placed medial to, and parallel with, the preceding. It *arises*, from the dorsal surface of the body of the ulna below the origin of the Extensor pollicis longus, and from the interosseous membrane. Its tendon passes under the dorsal carpal ligament in the same compartment as that which transmits the tendons of the Extensor digitorum communis, and opposite the head of the second metacarpal bone, joins the ulnar side of the tendon of the Extensor digitorum communis which belongs to the index finger.

**Nerves.**—The Brachioradialis is supplied by the fifth and sixth, the Extensores carpi radialis longus and brevis by the sixth and seventh, and the Anconaeus by the seventh and eighth cervical nerves, through the radial nerve; the remaining muscles are innervated through the deep radial nerve, the Supinator being supplied by the sixth, and all the other muscles by the seventh cervical.

**Actions.**—The muscles of the lateral and dorsal aspects of the forearm, which comprise all the Extensor muscles and the Supinator, act upon the forearm, wrist, and hand; they are the direct antagonists of the Pronator and Flexor muscles. The Anconaeus assists the Triceps in extending the forearm. The Brachioradialis is a flexor of the elbow-joint, but only acts as such when the movement of flexion has been initiated by the Biceps brachii and Brachialis. The action of the Supinator is suggested by its name; it assists the Biceps in bringing the hand into the supine position. The Extensor carpi radialis longus extends the wrist and abducts the hand. It may also assist in bending the elbow-joint; at all events it serves to fix or steady this articulation. The Extensor carpi radialis brevis extends the wrist, and may also act slightly as an abductor of the hand. The Extensor carpi ulnaris extends the wrist, but when acting alone inclines the hand toward the ulnar side; by its continued action it extends the elbow-joint. The Extensor digitorum communis extends the phalanges, then the wrist, and finally the elbow. It acts principally on the proximal phalanges, the middle and terminal phalanges being extended mainly by the Interossei and Lumbricales. It tends to separate the fingers as it extends them. The Extensor digiti quinti proprius extends the little finger, and by its continued action assists in extending the wrist. It is owing to this muscle that the little finger can be extended or pointed while the others are flexed. The chief action of the Abductor pollicis longus is to carry the thumb laterally from the palm of the hand. By its continued action it helps to extend and abduct the wrist. The Extensor pollicis brevis extends the proximal phalanx, and the Extensor pollicis longus the terminal phalanx of the thumb; by their continued action they help to extend and abduct the wrist. The Extensor indicis proprius extends the index finger, and by its continued action assists in extending the wrist.

**Applied Anatomy.**—The tendons of the Abductor longus and Extensors of the thumb are liable to become strained, and their sheaths inflamed (*tenosynovitis*) after excessive exercise, producing a sausage-shaped swelling along the course of the tendons and giving a peculiar grating sensation to the touch when the muscles are put in action.

Paralysis of the Extensor muscles of the wrists and fingers, with its resulting "wrist drop," is common in acute or chronic lead poisoning. The Brachioradialis usually escapes in these cases, unless the muscles of the upper arm are paralyzed also. Usually the different Extensor muscles are unequally affected; thus the thumb, or index or little finger, may be but slightly implicated, and may recover rapidly while the Extensors of the other fingers or the wrist remain powerless. Some paresis is often shown by the Flexors of the fingers also, these muscles being thrown into a state of tremor whenever extension of the fingers is attempted. Atrophy often follows paralysis in lead poisoning.

## VI. THE MUSCLES AND FASCIAE OF THE HAND.

The muscles of the hand are subdivided into three groups: (1) those of the thumb, which occupy the radial side and produce the **thenar eminence**; (2) those of the little finger, which occupy the ulnar side and give rise to the **hypothelar eminence**; (3) those in the middle of the palm and between the metacarpal bones.

**Dissection** (Fig. 518).—Make a transverse incision across the front of the wrist, and a second across the heads of the metacarpal bones; connect the two by a vertical incision in the middle line, and continue it through the centre of the middle finger. The volar, transverse, and dorsal carpal ligaments and the palmar aponeurosis should then be dissected.



**Volar Carpal Ligament** (*ligamentum carpi volare*).—The volar carpal ligament is the thickened band of antibrachial fascia which extends from the radius to the ulna over the Flexor tendons as they enter the wrist.




FIG. 528.—Transverse section across distal ends of radius and ulna.

**Transverse Carpal Ligament** (*ligamentum carpi transversum*; *anterior annular ligament*) (Figs. 528, 529).—The transverse carpal ligament is a strong, fibrous band, which arches over the carpus, converting the deep groove on the front of the carpal bones into a tunnel, through which the Flexor tendons of the digits and the median nerve pass. It is attached, medially, to the pisiform and the




FIG. 529.—Transverse section across the wrist and digits.

hamulus of the hamate bone; laterally, to the tuberosity of the navicular, and to the medial part of the volar surface and the ridge of the greater multangular. It is continuous, above, with the volar carpal ligament; and below, with the palmar aponeurosis. It is crossed by the ulnar vessels and nerve, and the cutaneous branches of the median and ulnar nerves. At its lateral end is the tendon of the



*Flexor carpi radialis*, which lies in the groove on the greater multangular between the attachments of the ligament to the bone. On its volar surface the tendons of the *Palmaris longus* and *Flexor carpi ulnaris* are partly *inserted*; below, it gives origin to the short muscles of the thumb and little finger




FIG. 530.—The mucous sheaths of the tendons on the front of the wrist and digits.

**The Mucous Sheaths of the Tendons on the Front of the Wrist.**—Two sheaths envelop the tendons as they pass beneath the transverse carpal ligament, one for the *Flexores digitorum sublimis* and *profundus*, the other for the *Flexor pollicis longus* (Fig. 530). They extend into the forearm for about 2.5 cm. above the transverse carpal ligament, and occasionally communicate with each other under

the ligament. The sheath which surrounds the *Flexores digitorum* extends downward about half-way along the metacarpal bones, where it ends in blind diverticula around the tendons to the index, middle, and ring fingers. It is prolonged on the tendons to the little finger and usually communicates with the mucous




FIG. 531.—The mucous sheaths of the tendons on the back of the wrist.

sheath of these tendons. The sheath of the tendon of the *Flexor pollicis longus* is continued along the thumb as far as the insertion of the tendon. The mucous sheaths enveloping the terminal parts of the tendons of the *Flexores digitorum* have been described on page 540.



**Dorsal Carpal Ligament** (*ligamentum carpi dorsale; posterior annular ligament*) (Figs. 528, 529).—The dorsal carpal ligament is a strong, fibrous band, extending obliquely downward and medialward across the back of the wrist, and consisting of part of the deep fascia of the back of the forearm, strengthened by the addition of some transverse fibres. It is attached, *medially*, to the styloid process of the ulna and to the triangular and pisiform bones; *laterally*, to the lateral margin of the radius; and, in its passage across the wrist, to the ridges on the dorsal surface of the radius.

**The Mucous Sheaths of the Tendons on the Back of the Wrist.**—Between the dorsal carpal ligament and the bones six compartments are formed for the passage of tendons, each compartment having a separate mucous sheath. One is found in each of the following positions (Fig. 531): (1) on the lateral side of the styloid process, for the tendons of the Abductor pollicis longus and Extensor pollicis brevis; (2) behind the styloid process, for the tendons of the Extensores carpi radialis longus and brevis; (3) about the middle of the dorsal surface of the radius, for the tendon of the Extensor pollicis longus; (4) to the medial side of the latter, for the tendons of the Extensor digitorum communis and Extensor indicis proprius; (5) opposite the interval between the radius and ulna, for the Extensor digiti quinti proprius; (6) between the head and styloid process of the ulna, for the tendon of the Extensor carpi ulnaris. The sheaths lining these compartments extend from above the dorsal carpal ligament; those for the tendons of Abductor pollicis longus, Extensor brevis pollicis, Extensores carpi radialis, and Extensor carpi ulnaris stop immediately proximal to the bases of the metacarpal bones, while the sheaths for Extensor communis digitorum, Extensor indicis proprius, and Extensor digiti quinti proprius are prolonged to the junction of the proximal and intermediate thirds of the metacarpus.

**Palmar Aponeurosis** (*aponeurosis palmaris; palmar fascia*) (Fig. 532).—The palmar aponeurosis invests the muscles of the palm, and consists of central, lateral, and medial portions.

The **central portion** occupies the middle of the palm, is triangular in shape, and of great strength and thickness. Its apex is continuous with the lower margin of the transverse carpal ligament, and receives the expanded tendon of the Palmaris longus. Its base divides below into four slips, one for each finger. Each slip gives off superficial fibres to the skin of the palm and finger, those to the palm joining the skin at the furrow corresponding to the metacarpophalangeal articulations, and those to the fingers passing into the skin at the transverse fold at the bases of the fingers. The deeper part of each slip subdivides into two processes, which are inserted into the fibrous sheaths of the Flexor tendons. From the sides of these processes offsets are attached to the transverse metacarpal ligament. By this arrangement short channels are formed on the front of the heads of the metacarpal bones; through these the Flexor tendons pass. The intervals between the four slips transmit the digital vessels and nerves, and the tendons of the Lumbricales. At the points of division into the slips mentioned, numerous strong, transverse fasciculi bind the separate processes together. The central part of the palmar aponeurosis is intimately bound to the integument by dense fibroareolar tissue forming the superficial palmar fascia, and gives origin by its medial margin to the Palmaris brevis. It covers the superficial volar arch, the tendons of the Flexor muscles, and the branches of the median and ulnar nerves; and on either side it gives off a septum, which is continuous with the interosseous aponeurosis, and separates the intermediate from the collateral groups of muscles.

The **lateral and medial portions** of the palmar aponeurosis are thin, fibrous layers, which cover, on the radial side, the muscles of the ball of the thumb, and, on the ulnar side, the muscles of the little finger; they are continuous with the central portion and with the fascia on the dorsum of the hand.

The **Superficial Transverse Ligament of the Fingers** is a thin band of transverse fasciculi (Fig. 532); it stretches across the roots of the four fingers, and is closely attached to the skin of the clefts, and medially to the fifth metacarpal bone, forming a sort of rudimentary web. Beneath it the digital vessels and nerves pass to their destinations.




FIG. 532.—The palmar aponeurosis.

**Applied Anatomy.**—The palmar aponeurosis is liable to undergo contraction, producing a very inconvenient deformity, known as *Dupuytren's contraction*. The ring and little fingers are most frequently implicated, but the others may also be involved. The proximal phalanx is flexed and cannot be straightened, and the two distal phalanges become similarly flexed as the disease advances.

Owing to their constant exposure to injury and septic influences, the fingers are very liable to become the seat of serious inflammatory mischief. To this inflammation the term *paronychia* or *whilow* is given, and the affection may assume various degrees of severity. In the mildest cases the disease is confined to the superficial layer of the skin, and suppuration takes place beneath it. This is known as *subcuticular paronychia*, and is a comparatively simple condition, for an incision through the epidermis will at once relieve it. The only complication is that the pus may burrow under the nail, causing increased pain. A more severe condition is the *paronychia cellulosa*, in which the pulp of the end of the finger is involved. This is attended with intense throbbing pain, owing to the fact that the inflamed area is covered by thick and often horny epithelium, especially when the disease occurs in the laboring classes, as it so frequently does. In these cases, unless a timely incision is made, the inflammation is liable to involve the periosteum covering the phalanx, and *subperiosteal paronychia* is set up, which is followed by necrosis



of a part or the whole of the ungual phalanx. In other cases, the inflammation may involve the theca of the Flexor tendons, and a *thecal paronychia* may result. The inflammation then rapidly spreads up the sheath; but the extent will depend upon the particular digit involved. From the description of the Flexor sheaths given above, it will be evident that inflammation of the mucous sheaths of the thumb and little finger may prove a far more formidable affection than that of the other three digits, because the sheaths of these two digits communicate with the large mucous sheath which surrounds the Flexor tendons (p. 548), and the inflammation may extend into the palm of the hand and beneath the transverse carpal ligament into the forearm.

In order to relieve these conditions, free and early incisions are necessary, and must be made with discrimination, in order to avoid wounding important structures. In the pulp of the finger—*i. e.*, over the distal phalanx—the incision should be made in the middle line and down to the bone. In the rest of the finger, the incision should be made in the middle line over the phalanges, and not over the interphalangeal joints. In the palm of the hand, incisions may be made either on the distal or proximal side of the superficial volar arch. On the distal side the incisions should be made over the metacarpal bones, preferably those of the index and middle finger. On the proximal side, the safest line of incision is along the radial side of the hypothenar eminence, between the ulnar artery and nerve medially, and the median nerve laterally. When suppuration has extended under the transverse carpal ligament, and incisions are required in the forearm, the positions in which they should be made are over the tendons of the Flexor digitorum sublimis, between the median nerve and the ulnar artery, and over the tendon of the Flexor pollicis longus, between the radial artery and the tendon of the Flexor carpi radialis.

Chronic inflammation of the common flexor sheath is occasionally met with, constituting a disease known as *compound palmar ganglion*; it presents an hour-glass outline, with a swelling in front of the wrist and another in the palm of the hand, and a constriction, corresponding to the transverse carpal ligament, between the two. The fluid can be forced from the one swelling to the other under the ligament, and when this is done, a creaking sensation is sometimes perceived, from the presence of "melon-seed" bodies in the interior of the ganglion.

### 1. The Lateral Volar Muscles (Figs. 533, 534).

Abductor pollicis brevis.

Flexor pollicis brevis.

Opponens pollicis.

Adductor pollicis (obliquus).

Adductor pollicis (transversus).




FIG. 533.—The muscles of the thumb.

The **Abductor pollicis brevis** (*Abductor pollicis*) is a thin, flat muscle, placed immediately beneath the integument. It *arises* from the transverse carpal ligament, the tuberosity of the navicular, and the ridge of the greater multangular,





carpal ligament and the lower part of the ridge on the greater multangular bone; it passes along the radial side of the tendon of the Flexor pollicis longus, and, becoming tendinous, is *inserted* into the radial side of the base of the first phalanx of the thumb; in its tendon of insertion there is a sesamoid bone. The **medial** and **deeper portion** of the muscle is very small, and *arises* from the ulnar side of the first metacarpal bone between the Adductor pollicis (obliquus) and the lateral head of the first Interosseous dorsalis, and is *inserted* into the ulnar side of the base of the first phalanx with the Adductor pollicis (obliquus). The medial part of the Flexor brevis pollicis is sometimes described as the **first Interosseous volaris**.

The **Adductor pollicis (obliquus)** (*Adductor obliquus pollicis*) *arises* by several slips from the capitate bone, the bases of the second and third metacarpals, the intercarpal ligaments, and the sheath of the tendon of the Flexor carpi radialis. From this origin the greater number of fibres pass obliquely downward and converge to a tendon, which, uniting with the tendons of the medial portion of the Flexor pollicis brevis and the transverse part of the Adductor, is *inserted* into the ulnar side of the base of the first phalanx of the thumb, a sesamoid bone being present in the tendon. A considerable fasciculus, however, passes more obliquely beneath the tendon of the Flexor pollicis longus to join the lateral portion of the Flexor brevis and the Abductor pollicis brevis.

The **Adductor pollicis (transversus)** (*Adductor transversus pollicis*) (Fig. 533) is the most deeply seated of this group of muscles. It is of a triangular form arising by a broad base from the lower two-thirds of the volar surface of the third metacarpal bone; the fibres converge, to be *inserted* with the medial part of the Flexor pollicis brevis and the Adductor pollicis (obliquus) into the ulnar side of the base of the first phalanx of the thumb.

**Nerves.**—The Abductor brevis, Opponens, and lateral head of the Flexor pollicis brevis are supplied by the sixth and seventh cervical nerves through the median nerve; the medial head of the Flexor brevis, and the Adductor, by the eighth cervical through the ulnar nerve.

**Actions.**—The Abductor pollicis brevis draws the thumb forward in a plane at right angles to that of the palm of the hand. The Abductor pollicis is the opponent of this muscle, and approximates the thumb to the palm. The Opponens pollicis flexes the metacarpal bone, *i. e.*, draws it medialward over the palm; the Flexor pollicis brevis flexes and adducts the proximal phalanx.

## 2. The Medial Volar Muscles (Figs. 533, 534).

Palmaris brevis.

Abductor digiti quinti.

Flexor digiti quinti brevis.

Opponens digiti quinti.

The **Palmaris brevis** is a thin, quadrilateral muscle, placed beneath the integument of the ulnar side of the hand. It *arises* by tendinous fasciculi from the transverse carpal ligament and palmar aponeurosis; the fleshy fibres are inserted into the skin on the ulnar border of the palm of the hand.

The **Abductor digiti quinti** (*Abductor minimi digiti*) is situated on the ulnar border of the palm of the hand. It *arises* from the pisiform bone and from the tendon of the Flexor carpi ulnaris, and ends in a flat tendon, which divides into two slips; one is *inserted* into the ulnar side of the base of the first phalanx of the little finger; the other into the ulnar border of the aponeurosis of the Extensor digiti quinti proprius.

The **Flexor digiti quinti brevis** (*Flexor brevis minimi digiti*) lies on the same plane as the preceding muscle, on its radial side. It *arises* from the convex surface of the hamulus of the hamate bone, and the volar surface of the transverse carpal ligament, and is *inserted* into the ulnar side of the base of the first phalanx of the little finger. It is separated from the Abductor, at its origin, by the deep branches of the ulnar artery and nerve. This muscle is sometimes wanting; the Abductor is then, usually, of large size.

The **Opponens digiti quinti** (*Opponens minimi digiti*) (Fig. 533) is of a triangular form, and placed immediately beneath the preceding muscles. It *arises* from the convexity of the hamulus of the hamate bone, and contiguous portion of the transverse carpal ligament; it is inserted into the whole length of the metacarpal bone of the little finger, along its ulnar margin.

**Nerves.**—All the muscles of this group are supplied by the eighth cervical nerve through the ulnar nerve.

**Actions.**—The Abductor and Flexor digiti quinti brevis abduct the little finger from the ring finger and assist in flexing the proximal phalanx. The Opponens digiti quinti draws forward the fifth metacarpal bone, so as to deepen the hollow of the palm. The Palmaris brevis corrugates the skin on the ulnar side of the palm.

### 3. The Intermediate Muscles.

#### Lumbricales.

#### Interossei.

The **Lumbricales** (Fig. 534) are four small fleshy fasciculi, associated with the tendons of the Flexor digitorum profundus. The first and second *arise* from the radial sides and volar surfaces of the tendons of the index and middle fingers respectively; the third, from the contiguous sides of the tendons of the middle and ring fingers; and the fourth, from the contiguous sides of the tendons of the ring and little fingers. Each passes to the radial side of the corresponding finger, and opposite the metacarpophalangeal articulation is *inserted* into the tendinous expansion of the Extensor digitorum communis covering the dorsal aspect of the finger.



FIG. 535.—The Interossei dorsales of left hand.




FIG. 536.—The Interossei volares of left hand

The **Interossei** (Figs. 535, 536) are so named from occupying the intervals between the metacarpal bones, and are divided into two sets, a dorsal and a volar.

The **Interossei dorsales** (*Dorsal interossei*) are *four* in number, and occupy the intervals between the metacarpal bones. They are bipenniform muscles, each *arising* by two heads from the adjacent sides of the metacarpal bones, but more extensively from the metacarpal bone of the finger into which the muscle is inserted. They are inserted into the bases of the first phalanges and into the aponeuroses

of the tendons of the Extensor digitorum communis. Between the double origin of each of these muscles is a narrow triangular interval; through the first of these the radial artery passes; through each of the other three a perforating branch from the deep volar arch is transmitted.

The **first** or **Abductor indicis** is larger than the others. It is flat, triangular in form, and *arises* by two heads, separated by a fibrous arch for the passage of the radial artery from the dorsum to the palm of the hand. The lateral head *arises* from the proximal half of the ulnar border of the first metacarpal bone; the medial head, from almost the entire length of the radial border of the second metacarpal bone; the tendon is inserted into the radial side of the index finger. The **second** and **third** are inserted into the middle finger, the former into its radial, the latter into its ulnar side. The **fourth** is inserted into the ulnar side of the ring finger.

The **Interossei volares** (*Palmar interossei*), three in number, are smaller than the Interossei dorsales, and placed upon the volar surfaces of the metacarpal bones, rather than between them. Each *arises* from the entire length of the metacarpal bone of one finger, and is *inserted* into the side of the base of the first phalanx and aponeurotic expansion of the Extensor communis tendon to the same finger.

The **first** *arises* from the ulnar side of the second metacarpal bone, and is *inserted* into the same side of the first phalanx of the index finger. The **second** *arises* from the radial side of the fourth metacarpal bone, and is *inserted* into the same side of the ring finger. The **third** *arises* from the radial side of the fifth metacarpal bone, and is *inserted* into the same side of the little finger. From this account it may be seen that each finger is provided with two Interossei, with the exception of the little finger, in which the Abductor takes the place of one of the pair.

As already mentioned (p. 554), the medial head of the Flexor pollicis brevis is sometimes described as the **Interosseus volaris primus**.

**Nerves.**—The two lateral Lumbricales are supplied by the sixth and seventh cervical nerves, through the third and fourth digital branches of the median nerve; the two medial Lumbricales and all the Interossei are supplied by the eighth cervical nerve, through the deep palmar branch of the ulnar nerve. The third Lumbricalis frequently receives a twig from the median.

**Actions.**—The Interossei volares adduct the fingers to an imaginary line drawn longitudinally through the centre of the middle finger; and the Interossei dorsales abduct the fingers from that line. In addition to this the Interossei, in conjunction with the Lumbricales, flex the first phalanges at the metacarpophalangeal joints, and extend the second and third phalanges in consequence of their insertions into the expansions of the Extensor tendons. The Extensor digitorum communis is believed to act almost entirely on the first phalanges.

**Applied Anatomy.**—In considering the actions of the various muscles upon fractures of the upper extremity, the most common forms of injury have been selected both for illustration and description.

Fracture of the *middle of the clavicle* (Fig. 537) is usually attended with considerable displacement of the lateral fragment, which is drawn downward and medialward, and at the same time rotated, so that its lateral end is carried forward and its medial end backward.

The displacement is produced as follows: the lateral fragment is drawn *downward* by the weight of the arm, the Trapezius not being able to support this. It is drawn *medialward* by the Subclavius and Pectoralis minor, possibly assisted by the Pectoralis major and Latissimus dorsi; and is rotated on an axis drawn through its own centre by the Serratus anterior, which causes the scapula to rotate on the wall of the chest, and carries the acromion and the end of the lateral fragment of the clavicle forward, and so carries the medial end of the lateral portion backward. The causes of displacement having been ascertained, it is easy to apply the appropriate treatment. The lateral fragment is to be drawn lateralward, and, together with the scapula, raised to a level with the medial fragment, and retained in that position.

In fracture of the *acromial end of the clavicle*, between the conoid and trapezoid ligaments, only slight displacement occurs, as these ligaments, from their oblique insertion, serve to hold both portions of the bone in apposition. Fracture, also, of the *sternal end*, medial to the costo-clavicular ligament, is attended with only slight displacement, this ligament serving to retain the fragments in close apposition.

Fracture of the *acromion* is usually caused by violence applied to the upper and lateral part of the shoulder. There is great displacement; the lateral fragment being drawn downward by the weight of the arm, and rotated forward and medialward, so that it forms a right angle with the rest of the bone.

Fracture of the *surgical neck of the humerus* (Fig. 538) is very common. It is attended with considerable displacement, and its appearances correspond somewhat with those of dislocation of the head of the humerus into the axilla. The upper fragment remains in its place under the coracoacromial ligament; the lower is drawn medialward by the Pectoralis major, Latissimus dorsi, and Teres major; and the humerus is thrown obliquely from the side of the chest by the Deltoides, and occasionally elevated so as to cause the upper end of the lower fragment to project beneath and in front of the coracoid process. The deformity is reduced by fixing the shoulder, and drawing the arm lateralward and downward. To counteract the opposing muscles, and to keep the fragments in position, a cone-shaped pad should be placed in the axilla, and the arm bandaged to the side by a broad roller passed around the chest in such a manner that the elbow is carried slightly forward, so as to throw the upper end of the lower fragment backward and lateralward toward the head of the bone. The whole is then covered with a carefully moulded gutta-percha or poroplastic shoulder cap.



FIG. 537.—Fracture of the middle of the clavicle.



FIG. 538.—Fracture of the surgical neck of the humerus.

In fracture of the *body of the humerus* below the insertion of the Pectoralis major, Latissimus dorsi, and Teres major, and above the insertion of the Deltoides, there is also considerable deformity, the upper fragment being drawn medialward by the first-mentioned muscles, and the lower fragment upward and lateralward by the Deltoides. Shortening of the limb results, with a considerable prominence at the seat of fracture, from the fractured ends of the bone riding over one another, especially if the fracture take place in an oblique direction. The fragments may be brought into apposition by extension from the elbow, and retained in that position by adopting the same means as in the preceding injury.

In fracture of the *body of the humerus* immediately below the insertion of the Deltoides the amount of deformity depends greatly upon the direction of the fracture. If it occur in a transverse direction, only slight displacement takes place, the upper fragment being drawn a little forward; but in oblique fracture, the combined actions of the Biceps brachii and Brachialis in front and the Triceps brachii behind draw upward the lower fragment, causing it to glide over the upper, either backward or forward, according to the direction of the fracture. Simple extension reduces the deformity, and the application of a shoulder cap and splints to the arm will retain the fragments in apposition.

Fracture of the *humerus* (Fig. 539) immediately above the condyles deserves very attentive consideration, as the general appearances correspond somewhat with those produced by separation of the epiphysis of the humerus, and with those of dislocation of the radius and ulna backward. If the direction of the fracture is oblique, from above, downward and forward, the lower fragment is drawn upward by the Brachialis and Biceps brachii in front, and the Triceps brachii behind; and at the same time is drawn backward behind the upper fragment by the Triceps brachii. This fracture may be diagnosed from dislocation, by the increased mobility, the existence of crepitus, and the fact that the deformity is remedied by extension, but is reproduced on the



discontinuance of it. The age of the patient is of importance in distinguishing this form of injury from separation of the epiphysis. In some cases where the injury has been produced by falls on the elbow, the lower fragment is drawn upward and forward, causing a considerable prominence in front, the upper fragment projecting backward beneath the tendon of the *Triceps brachii*.

In fracture of the *olecranon* (Fig. 540) the detached fragment is displaced upward, by the action of the *Triceps brachii*, from 1 to 5 cm.; the prominence of the elbow is consequently lost, and a deep hollow is felt at the back part of the joint, which is much increased on flexing the limb. The patient at the same time loses, more or less, the power of extending the forearm. The treatment consists in wiring the fragments together; but if for some reason this operation is not desirable, they should be approximated by strapping or a figure-of-eight bandage, and the arm put up in an extended position in order to relax the *Triceps brachii*. Massage and passive movements must be employed early, for fear of ankylosis. Union, when wiring is not resorted to, is usually fibrous.




FIG. 539.—Fracture of the humerus above the condyles.




FIG. 540.—Fracture of the olecranon.

In fracture of the *radius* below the insertion of the *Biceps brachii*, but above the insertion of the *Pronator teres*, the upper fragment is strongly supinated by the *Biceps brachii* and *Supinator*, and at the same time drawn forward and flexed by the *Biceps brachii*; the lower fragment is pronated and drawn toward the ulna by both *Pronators*. Thus there is extreme displacement with very little deformity. In treating such a fracture the arm must be put up in a position of supination, otherwise union will take place with great impairment of the movements of the hand. In fractures of the radius below the insertion of the *Pronator teres* (Fig. 541), the upper



FIG. 541.—Fracture of the body of the radius.

fragment is drawn upward by the *Biceps brachii* and medialward by the *Pronator teres*, into a position midway between pronation and supination, and a degree of fulness in the upper half of the forearm is thus produced. The lower fragment is drawn downward toward the ulna and pronated by the *Pronator quadratus*; at the same time, the *Brachioradialis*, by elevating the styloid process, into which it is inserted, will serve to depress the upper end of the lower fragment still more toward the ulna. In order to relax the opposing muscles the forearm should be bent, and the limb placed in a position midway

between pronation and supination; the fracture is then easily reduced by extension from the wrist and elbow. Well-padded splints should be applied on both sides of the forearm from the elbow to the wrist.

In fracture of the *body of the ulna* the upper fragment retains its usual position, but the lower is drawn toward the radius by the *Pronator quadratus*, producing a well-marked depression at the seat of fracture, and some fulness on the dorsal and volar surfaces of the forearm. The fracture is easily reduced by extension from the wrist and elbow. The forearm should be flexed, and placed in a position midway between pronation and supination, and well-padded splints applied from the elbow to the ends of the fingers.

In fracture of the *bodies of the radius and ulna together*, the lower fragments are drawn upward, sometimes forward, sometimes backward, according to the direction of the fracture, by the combined actions of the Flexor and Extensor muscles, producing a degree of fulness on either the dorsal or volar surface of the forearm. At the same time the lower fragments are drawn into contact by the Pronator quadratus, the radius being in a state of pronation. The upper fragment of the radius is drawn upward and medialward by the Biceps brachii and Pronator teres to a higher level than the ulna; the upper portion of the ulna is slightly elevated by the Brachialis. The fracture may be reduced by extension from the wrist and elbow, and the forearm should be placed in the same position as in fracture of the ulna.




FIG. 542.—Fracture of the lower end of the radius.

In fracture of the *lower end of the radius* (Fig. 542) the displacement produced is very considerable, and bears some resemblance to dislocation of the carpus backward, from which it should be carefully distinguished. The lower fragment is displaced backward and upward, but this displacement is due to the force of the blow driving the portion of the bone into this position, and not to any muscular influence. The upper fragment projects forward, often lacerating the substance of the Pronator quadratus, and is drawn by this muscle into close contact with the lower end of the ulna, causing a projection on the volar surface of the forearm, immediately above the carpus, from the Flexor tendons being thrust forward. This fracture may be distinguished from dislocation by the relative positions of the styloid processes of the radius and ulna (the former of which is displaced upward in fracture) and by the deformity being removed on making sufficient extension, when crepitus may be occasionally detected. The age of the patient will assist in determining whether the injury is fracture or separation of the epiphysis. The treatment consists in flexing the forearm, and making powerful extension from the wrist and elbow, depressing at the same time the radial side of the hand, and retaining the parts in a position of adduction toward the ulnar side.

## THE MUSCLES AND FASCIÆ OF THE LOWER EXTREMITY.

The muscles of the lower extremity are subdivided into groups corresponding with the different regions of the limb.

- I. Muscles of the Iliac Region.
- II. Muscles of the Thigh.

- III. Muscles of the Leg.
- IV. Muscles of the Foot.

### I. THE MUSCLES AND FASCIÆ OF THE ILIAC REGION (Fig. 543).

Psoas major.

Psoas minor.

Iliacus.

**Dissection.**—No detailed description is required for the dissection of these muscles. On the removal of the viscera from the abdomen they are exposed, covered by the peritoneum and a thin layer of fascia, the iliac fascia.

The **Fascia Covering the Psoas and Iliacus** is thin above, and becomes gradually thicker below as it approaches the inguinal ligament.

The **portion covering the Psoas** is thickened *above* to form the medial lumbo-costal arch, which stretches from the transverse process of the first lumbar vertebra to the body of the second. *Medially*, it is attached by a series of arched processes






FIG. 543.—Muscles of the iliac and anterior femoral regions.

to the intervertebral fibrocartilages, and prominent margins of the bodies of the vertebræ, and to the upper part of the sacrum; the intervals left, opposite the constricted portions of the bodies, transmit the lumbar arteries and veins and filaments of the sympathetic trunk. *Laterally*, above the crest of the ilium, it is continuous with the fascia covering the front of the Quadratus lumborum (see page 510), while below the crest of the ilium it is continuous with the fascia covering the Iliacus.

The portions investing the Iliacus (*fascia iliaca; iliac fascia*) is connected, *laterally* to the whole length of the inner lip of the iliac crest; and *medially*, to the linea terminalis of the lesser pelvis, where it is continuous with the periosteum. At the iliopectineal eminence it receives the tendon of insertion of the Psoas minor, when that muscle exists. Lateral to the femoral vessels it is intimately connected to the posterior margin of the inguinal ligament, and is continuous with the transversalis fascia. Immediately lateral to the femoral vessels the iliac fascia is prolonged backward and medialward from the inguinal ligament as a band, the **iliopectineal fascia**, which is attached to the iliopectineal eminence. This fascia divides the space between the inguinal ligament and the hip bone into two lacunæ or compartments, the medial of which transmits the femoral vessels, the lateral the Psoas major and Iliacus and the femoral nerve. Medial to the vessels the iliac fascia is attached to the pectineal line behind the inguinal aponeurotic falx, where it is again continuous with the transversalis fascia. On the thigh the fasciæ of the Iliacus and Psoas form a single sheet termed the **iliopectineal fascia**. Where the external iliac vessels pass into the thigh, the fascia descends behind them, forming the posterior wall of the femoral sheath. The portion of the iliopectineal fascia which passes behind the femoral vessels is also attached to the pectineal line beyond the limits of the attachment of the inguinal aponeurotic falx; at this part it is continuous with the pectineal fascia. The external iliac vessels lie in front of the iliac fascia, but all the branches of the lumbar plexus are behind it; it is separated from the peritoneum by a quantity of loose areolar tissue.

The **Psoas major** (*Psoas magnus*) (Fig. 543) is a long fusiform muscle placed on the side of the lumbar region of the vertebral column and brim of the lesser pelvis. It *arises* (1)

from the anterior surfaces of the bases and lower borders of the transverse processes of all the lumbar vertebræ; (2) from the sides of the bodies and the corresponding intervertebral fibrocartilages of the last thoracic and all the lumbar vertebræ by five slips, each of which is attached to the adjacent upper and lower margins of two vertebræ, and to the intervertebral fibrocartilage; (3) from a series of tendinous arches which extend across the constricted parts of the bodies of the lumbar vertebræ between the previous slips; the lumbar arteries and veins, and filaments from the sympathetic trunk pass beneath these tendinous arches. The muscle proceeds downward across the brim of the lesser pelvis, and diminishing gradually in size, passes beneath the inguinal ligament and in front of the capsule of the hip-joint and ends in a tendon; the tendon receives nearly the whole of the fibres of the Iliacus and is *inserted* into the lesser trochanter of the femur. A large bursa which may communicate with the cavity of the hip-joint, separates the tendon from the pubis and the capsule of the joint.

**Relations.**—In the abdomen the Psoas major is in relation by its *anterior surface* with the medial lumbocostal arch, the fascia covering the muscle, the extraperitoneal fat and peritoneum, the kidney, Psoas minor, renal vessels, ureter, spermatic vessels, and genitofemoral nerve. In front of the right Psoas is the inferior vena cava and the terminal portion of the ileum, and in front of the left the iliac colon. By its *posterior surface* it is in relation with the transverse processes of the lumbar vertebræ, and the Quadratus lumborum. The lumbar plexus is situated in the posterior part of the substance of the muscle. By its *medial side*, the muscle is in relation with the bodies of the lumbar vertebræ, the lumbar arteries, the gangliated trunk of the sympathetic, and the lumbar lymph glands; with the inferior vena cava on the right, and the aorta on the left side, and along the brim of the pelvis with the external iliac artery.

In the thigh it is in relation, in *front*, with the fascia lata; *behind*, with the capsule of the hip-joint, from which it is separated by a bursa; by its *medial border*, with the Pectineus and medial circumflex femoral artery, and also with the femoral artery, which slightly overlaps it; by its *lateral border*, with the femoral nerve and Iliacus.

The **Psoas minor** (*Psoas parvus*) is a long slender muscle, placed in front of the Psoas major. It *arises* from the sides of the bodies of the twelfth thoracic and first lumbar vertebræ and from the fibrocartilage between them. It ends in a long flat tendon which is *inserted* into the pectineal line and iliopectineal eminence, and, by its lateral border, into the iliac fascia. This muscle is often absent.

The **Iliacus** is a flat, triangular muscle, which fills the iliac fossa. It *arises* from the upper two-thirds of this fossa, and from the inner lip of the iliac crest; behind, from the anterior sacroiliac and the iliolumbar ligaments, and base of the sacrum; in front, it reaches as far as the anterior superior and anterior inferior iliac spines, and the notch between them. The fibres converge to be inserted into the lateral side of the tendon of the Psoas major, some of them being prolonged on to the body of the femur for about 2.5 cm. below and in front of the lesser trochanter.<sup>1</sup>

**Relations.**—Within the abdomen the Iliacus is in relation by its *anterior surface* with the iliac fascia, which separates the muscle from the extraperitoneal fat and peritoneum, and with the lateral femoral cutaneous nerve; on the right side, with the cecum; on the left side, with the iliac colon; by its *posterior surface*, with the iliac fossa; by its *medial border*, with the Psoas major and femoral nerve.

In the thigh, it is in relation, by its *anterior surface*, with the fascia lata, Rectus femoris, Sartorius, and profunda femoris artery; behind, with the capsule of the hip-joint, a bursa common to it and the Psoas major being interposed.

**Nerves.**—The Psoas major is supplied by branches of the second and third lumbar nerve; the Psoas minor by a branch of the first lumbar nerve; and the Iliacus by branches of the second and third lumbar nerves through the femoral nerve.

**Actions.**—The Psoas major, acting from above, flexes the thigh upon the pelvis, being assisted by the Iliacus; acting from below, with the femur fixed, it bends the lumbar portion of the vertebral column forward and to its own side, and then, in conjunction with the Iliacus, tilts the pelvis forward. When the muscles of both sides are acting from below, they serve to maintain the

<sup>1</sup> The Psoas major and iliacus are sometimes regarded as a single muscle named the *Iliopsoas*.






FIG. 543.—Muscles of the iliac and anterior femoral regions.

to the intervertebral fibrocartilages, and prominent margins of the bodies of the vertebræ, and to the upper part of the sacrum; the intervals left, opposite the constricted portions of the bodies, transmit the lumbar arteries and veins and filaments of the sympathetic trunk. *Laterally*, above the crest of the ilium, it is continuous with the fascia covering the front of the *Quadratus lumborum* (see page 510), while below the crest of the ilium it is continuous with the fascia covering the *Iliacus*.

The portions investing the *Iliacus* (*fascia iliaca*; *iliac fascia*) is connected, *laterally* to the whole length of the inner lip of the iliac crest; and *medially*, to the linea terminalis of the lesser pelvis, where it is continuous with the periosteum. At the iliopectineal eminence it receives the tendon of insertion of the *Psoas minor*, when that muscle exists. Lateral to the femoral vessels it is intimately connected to the posterior margin of the inguinal ligament, and is continuous with the transversalis fascia. Immediately lateral to the femoral vessels the iliac fascia is prolonged backward and medialward from the inguinal ligament as a band, the *iliopectineal fascia*, which is attached to the iliopectineal eminence. This fascia divides the space between the inguinal ligament and the hip bone into two lacunæ or compartments, the medial of which transmits the femoral vessels, the lateral the *Psoas major* and *Iliacus* and the femoral nerve. Medial to the vessels the iliac fascia is attached to the pectineal line behind the inguinal aponeurotic falx, where it is again continuous with the transversalis fascia. On the thigh the fasciæ of the *Iliacus* and *Psoas* form a single sheet termed the *iliopectineal fascia*. Where the external iliac vessels pass into the thigh, the fascia descends behind them, forming the posterior wall of the femoral sheath. The portion of the iliopectineal fascia which passes behind the femoral vessels is also attached to the pectineal line beyond the limits of the attachment of the inguinal aponeurotic falx; at this part it is continuous with the pectineal fascia. The external iliac vessels lie in front of the iliac fascia, but all the branches of the lumbar plexus are behind it; it is separated from the peritoneum by a quantity of loose areolar tissue.

The ***Psoas major*** (*Psoas magnus*) (Fig. 543) is a long fusiform muscle placed on the side of the lumbar region of the vertebral column and brim of the lesser pelvis. It *arises* (1)

from the anterior surfaces of the bases and lower borders of the transverse processes of all the lumbar vertebræ; (2) from the sides of the bodies and the corresponding intervertebral fibrocartilages of the last thoracic and all the lumbar vertebræ by five slips, each of which is attached to the adjacent upper and lower margins of two vertebræ, and to the intervertebral fibrocartilage; (3) from a series of tendinous arches which extend across the constricted parts of the bodies of the lumbar vertebræ between the previous slips; the lumbar arteries and veins, and filaments from the sympathetic trunk pass beneath these tendinous arches. The muscle proceeds downward across the brim of the lesser pelvis, and diminishing gradually in size, passes beneath the inguinal ligament and in front of the capsule of the hip-joint and ends in a tendon; the tendon receives nearly the whole of the fibres of the Iliacus and is *inserted* into the lesser trochanter of the femur. A large bursa which may communicate with the cavity of the hip-joint, separates the tendon from the pubis and the capsule of the joint.

**Relations.**—In the abdomen the Psoas major is in relation by its *anterior surface* with the medial lumbocostal arch, the fascia covering the muscle, the extraperitoneal fat and peritoneum, the kidney, Psoas minor, renal vessels, ureter, spermatic vessels, and genitofemoral nerve. In front of the right Psoas is the inferior vena cava and the terminal portion of the ileum, and in front of the left iliac colon. By its *posterior surface* it is in relation with the transverse processes of the lumbar vertebræ, and the Quadratus lumborum. The lumbar plexus is situated in the posterior part of the substance of the muscle. By its *medial side*, the muscle is in relation with the bodies of the lumbar vertebræ, the lumbar arteries, the gangliated trunk of the sympathetic, and the lumbar lymph glands; with the inferior vena cava on the right, and the aorta on the left side, and along the brim of the pelvis with the external iliac artery.

In the thigh it is in relation, in *front*, with the fascia lata; *behind*, with the capsule of the hip-joint, from which it is separated by a bursa; by its *medial border*, with the Pectineus and medial circumflex femoral artery, and also with the femoral artery, which slightly overlaps it; by its *lateral border*, with the femoral nerve and Iliacus.

The **Psoas minor** (*Psoas parvus*) is a long slender muscle, placed in front of the Psoas major. It *arises* from the sides of the bodies of the twelfth thoracic and first lumbar vertebræ and from the fibrocartilage between them. It ends in a long flat tendon which is *inserted* into the pectineal line and iliopectineal eminence, and, by its lateral border, into the iliac fascia. This muscle is often absent.

The **Iliacus** is a flat, triangular muscle, which fills the iliac fossa. It *arises* from the upper two-thirds of this fossa, and from the inner lip of the iliac crest; behind, from the anterior sacroiliac and the iliolumbar ligaments, and base of the sacrum; in front, it reaches as far as the anterior superior and anterior inferior iliac spines, and the notch between them. The fibres converge to be inserted into the lateral side of the tendon of the Psoas major, some of them being prolonged on to the body of the femur for about 2.5 cm. below and in front of the lesser trochanter.<sup>1</sup>

**Relations.**—Within the abdomen the Iliacus is in relation by its *anterior surface* with the iliac fascia, which separates the muscle from the extraperitoneal fat and peritoneum, and with the lateral femoral cutaneous nerve; on the right side, with the cecum; on the left side, with the iliac colon; by its *posterior surface*, with the iliac fossa; by its *medial border*, with the Psoas major and femoral nerve.

In the thigh, it is in relation, by its *anterior surface*, with the fascia lata, Rectus femoris, Sartorius, and profunda femoris artery; behind, with the capsule of the hip-joint, a bursa common to it and the Psoas major being interposed.

**Nerves.**—The Psoas major is supplied by branches of the second and third lumbar nerve; the Psoas minor by a branch of the first lumbar nerve; and the Iliacus by branches of the second and third lumbar nerves through the femoral nerve.

**Actions.**—The Psoas major, acting from above, flexes the thigh upon the pelvis, being assisted by the Iliacus; acting from below, with the femur fixed, it bends the lumbar portion of the vertebral column forward and to its own side, and then, in conjunction with the Iliacus, tilts the pelvis forward. When the muscles of both sides are acting from below, they serve to maintain the

<sup>1</sup> The Psoas major and iliacus are sometimes regarded as a single muscle named the *Iliopsoas*.

erect posture by supporting the vertebral column and pelvis upon the femora, or in continued action bend the trunk and pelvis forward, as in raising the trunk from the recumbent posture.

The Psoas minor is a tensor of the iliac fascia.

**Applied Anatomy.**—There is no definite septum between the portions of fascia covering the Psoas and Iliacus respectively, and the fascia is only connected to the subjacent muscles by a quantity of loose connective tissue. When an abscess forms beneath this fascia, as it is very apt to do, the matter is contained in an osseofibrous cavity which is closed on all sides within the abdomen, and is open only at its lower part, where the fascia is prolonged over the muscles into the thigh.

Abscess within the sheath of the Psoas major (*psoas abscess*) is generally due to tuberculous caries of the bodies of the lower thoracic or the lumbar vertebræ. When the disease is in the thoracic region, the matter tracks down the posterior mediastinal cavity in front of the bodies of the vertebræ, and, passing beneath the medial lumbocostal arch, enters the sheath of the Psoas, down which it travels as far as the pelvic brim; it then gets beneath the iliac portion of the fascia, and fills up the iliac fossa. In consequence of the attachment of the fascia to the arcuate line, it rarely finds its way into the lesser pelvis, but passes by a narrow opening under the inguinal ligament into the thigh, lateral to the femoral vessels. It thus follows that a psoas abscess may be described as consisting of four parts: (1) a somewhat narrow channel at its upper part, in the psoas sheath; (2) a dilated sac in the iliac fossa; (3) a constricted neck under the inguinal ligament, and (4) a dilated sac in the upper part of the thigh. When the lumbar vertebræ are the seat of the disease, the matter finds its way directly into the substance of the Psoas. The muscular fibres are destroyed, and the nerves contained in the abscess are isolated and exposed in its interior; the iliac vessels which lie in front of the fascia remain intact, and the peritoneum seldom becomes implicated. All psoas abscesses do not, however, pursue this course; the matter may leave the sheath of the muscle above the crest of the ilium, and tracking backward may point in the loin (*lumbar abscess*); or it may point above the inguinal ligament in the inguinal region; or it may follow the course of the branches of the hypogastric vessels into the lesser pelvis, and, passing through the greater sciatic foramen, discharge itself on the back of the thigh.

## II. THE MUSCLES AND FASCIÆ OF THE THIGH.

### 1. The Anterior Femoral Muscles (Fig. 543).

Tensor fasciæ latae.  
Sartorius.

Quadriceps  
femoris.

{ Rectus femoris.  
Vastus lateralis.  
Vastus medialis.  
Vastus intermedius.

Articularis genu.

**Dissection.**—To expose the muscles and fasciæ in this region, make an incision along the inguinal ligament, from the anterior superior spine of the ilium to the spine of the pubis; a vertical incision from the centre of this, along the middle of the thigh to below the knee-joint; and a transverse incision from the inner to the outer side of the leg, at the lower end of the vertical incision. The flaps of integument having been removed, the superficial and deep fasciæ should be examined. The more advanced student should commence the study of this region by an examination of the anatomy of femoral hernia and femoral triangle, the incisions for the dissection of which are marked out in Fig. 544.

**Superficial Fascia.**—The superficial fascia forms a continuous layer over the whole of the thigh; it consists of areolar tissue containing in its meshes much fat, and may be separated into two or more layers, between which are found the superficial vessels and nerves. It varies in thickness in different parts of the limb; in the groin it is thick, and the two layers are separated from one another by the superficial inguinal lymph glands, the great saphenous vein, and several smaller vessels. The superficial layer is continuous above with the superficial fascia of the abdomen. The deep layer of the superficial fascia is a very thin, fibrous stratum, best marked on the medial side of the great saphenous vein and below the inguinal ligament. It is placed beneath the subcutaneous vessels and nerves and upon the surface of the fascia lata. It is intimately adherent to the fascia lata a little below the inguinal ligament. It covers the *fossa ovalis* (*saphenous opening*), being closely united to its circumference, and is connected to the sheath of the femoral vessels. The

portion of fascia covering this fossa is perforated by the great saphenous vein and by numerous blood and lymphatic vessels, hence it has been termed the **fascia cribrosa**, the openings for these vessels having been likened to the holes in a sieve. A large subcutaneous bursa is found in the superficial fascia over the patella.

**Deep Fascia.**—The deep fascia of the thigh is named, from its great extent, the **fascia lata**; it constitutes an investment for the whole of this region of the limb, but varies in thickness in different parts. Thus, it is thicker in the upper and lateral part of the thigh, where it receives a fibrous expansion from the Glutaeus maximus, and where the Tensor fasciae latae is inserted between its layers; it is very thin behind and at the upper and medial part, where it covers the Adductor muscles, and again becomes stronger around the knee, receiving fibrous expansions from the tendon of the Biceps femoris laterally, from the Sartorius medially, and from the Quadriceps femoris in front. The fascia lata is attached, above and behind, to the back of the sacrum and coccyx; laterally, to the iliac crest; in front, to the inguinal ligament, and to the superior ramus of the pubis; and medially, to the inferior ramus of the pubis, to the inferior ramus and tuberosity of the ischium, and to the lower border of the sacrotuberous ligament. From its attachment to the iliac crest it passes down over the Glutaeus medius to the upper border of the Glutaeus maximus, where it splits into two layers, one passing superficial to and the other beneath this muscle; at the lower border of the muscle the two layers reunite. Laterally, the fascia lata receives the greater part of the tendon of insertion of the Glutaeus maximus, and becomes proportionately thickened. The portion of the fascia lata attached to the front part of the iliac crest, and corresponding to the origin of the Tensor fasciae latae, extends down the lateral side of the thigh as two layers, one superficial to and the other beneath this muscle; at the lower end of the muscle these two layers unite and form a strong band, having first received the insertion of the muscle. This band is continued downward, under the name of the **iliotibial band** (*tractus iliotibialis*) and is attached to the lateral condyle of the tibia. The part of the iliotibial band which lies beneath the Tensor fasciae latae is prolonged upward to join the lateral part of the capsule of the hip-joint. Below, the fasciae lata is attached to all the prominent points around the knee-joint, viz., the condyles of the femur and tibia, and the head of the fibula. On either side of the patella it is strengthened by transverse fibres from the lower parts of the Vasti, which are attached to and support this bone. Of these the lateral are the stronger, and are continuous with the iliotibial band. The deep surface of the fascia lata gives off two strong intermuscular septa, which are attached to the whole length of the linea aspera and its prolongations above and below; the lateral and stronger one, which extends from the insertion of the Glutaeus maximus to the lateral condyle, separates the Vastus lateralis in front from the short head of the Biceps femoris behind, and gives




FIG. 544.—Dissection of lower extremity. Front view.



partial origin to these muscles; the medial and thinner one separates the Vastus medialis from the Adductores and Pectineus. Besides these there are numerous smaller septa, separating the individual muscles, and enclosing each in a distinct sheath.

**The Fossa Ovalis** (*saphenous opening*) (Fig. 545).—At the upper and medial part of the thigh, a little below the medial end of the inguinal ligament, is a large oval-shaped aperture in the fascia lata; it transmits the great saphenous vein, and other, smaller vessels, and is termed the **fossa ovalis**. The fascia cribrosa, which is pierced by the structures passing through the opening, closes the aperture and must be removed to expose it. The fascia lata in this part of the thigh is described as consisting of a superficial and a deep portion.




FIG. 545.—The fossa ovalis.

The **superficial portion** of the fascia lata is the part on the lateral side of the fossa ovalis. It is attached, *laterally*, to the crest and anterior superior spine of the ilium, to the whole length of the inguinal ligament, and to the pectineal line in conjunction with the lacunar ligament. From the tubercle of the pubis it is reflected downward and lateralward, as an arched margin, the **falciform margin**, forming the lateral boundary of the fossa ovalis; this margin overlies and is adherent to the anterior layer of the sheath of the femoral vessels: to its edge is attached the fascia cribrosa. The upward and medial prolongation of the falciform margin is named the **superior cornu**; its downward and medial prolongation, the **inferior cornu**. The latter is well-defined, and is continuous behind the great saphenous vein with the pectineal fascia.

The **deep portion** is situated on the medial side of the fossa ovalis, and at the lower margin of the fossa is continuous with the superficial portion; traced upward, it covers the Pectineus, Adductor longus, and Gracilis, and, passing behind the sheath of the femoral vessels, to which it is closely united, is continuous with the iliopectineal fascia, and is attached to the pectineal line.

From this description it may be observed that the superficial portion of the fascia lata lies in front of the femoral vessels, and the deep portion behind them, so that an apparent aperture exists between the two, through which the great saphenous passes to join the femoral vein.

The **Tensor fasciae latae** (*Tensor fasciae femoris*) arises from the anterior part of the outer lip of the iliac crest; from the outer surface of the anterior superior iliac spine, and part of the outer border of the notch below it, between the Glutaeus medius and Sartorius; and from the deep surface of the fascia lata. It is *inserted* between the two layers of the iliotibial band of the fascia lata about the junction of the middle and upper thirds of the thigh.

The **Sartorius**, the longest muscle in the body, is narrow and ribbon-like; it arises by tendinous fibres from the anterior superior iliac spine and the upper half of the notch below it. It passes obliquely across the upper and anterior part of the thigh, from the lateral to the medial side of the limb, then descends vertically, as far as the medial side of the knee, passing behind the medial condyle of the femur to end in a tendon. This curves obliquely forward and expands into a broad aponeurosis, which is *inserted*, in front of the Gracilis and Semitendinosus, into the upper part of the medial surface of the body of the tibia, nearly as far forward as the anterior crest. The upper part of the aponeurosis is curved backward over the upper edge of the tendon of the Gracilis so as to be inserted behind it. An offset, from its upper margin, blends with the capsule of the knee-joint, and another from its lower border, with the fascia on the medial side of the leg.

**Relations.**—The relations of this muscle to the femoral artery are important, as it constitutes the chief guide in tying the vessel. In the upper third of the thigh it forms the lateral side of a triangular space, the *femoral (Scarpa's) triangle*, the medial side of which is formed by the medial border of the Adductor longus, and the base, directed upward, by the inguinal ligament; the femoral artery passes perpendicularly through the middle of this space from its base to its apex. In the middle third of the thigh the femoral artery is contained in the *adductor (Hunter's) canal*, on the roof of which the Sartorius lies.

The **Quadriceps femoris** (*Quadriceps extensor*) includes the four remaining muscles on the front of the thigh. It is the great extensor muscle of the leg, forming a large fleshy mass which covers the front and sides of the femur. It is subdivided into separate portions, which have received distinctive names. One occupying the middle of the thigh, and connected above with the ilium, is called from its straight course the **Rectus femoris**. The other three lie in immediate connection with the body of the femur, which they cover from the trochanters to the condyles. The portion on the lateral side of the femur is termed the **Vastus lateralis**; that covering the medial side, the **Vastus medialis**; and that in front, the **Vastus intermedius**.

The **Rectus femoris** is situated in the middle of the front of the thigh; it is fusiform in shape, and its superficial fibres are arranged in a bipenniform manner, the deep fibres running straight down to the deep aponeurosis. It arises by two tendons: one, the anterior or straight, from the anterior inferior iliac spine; the other, the posterior or reflected, from a groove above the brim of the acetabulum. The two unite at an acute angle, and spread into an aponeurosis which is prolonged downward on the anterior surface of the muscle, and from this the muscular fibres arise. The muscle ends in a broad and thick aponeurosis which occupies the lower two-thirds of its posterior surface, and, gradually becoming narrowed into a flattened tendon, is *inserted* into the base of the patella.

The **Vastus lateralis** (*Vastus externus*) is the largest part of the Quadriceps femoris. It *arises* by a broad aponeurosis, which is attached to the upper part of the intertrochanteric line, to the anterior and inferior borders of the greater trochanter, to the lateral lip of the gluteal tuberosity, and to the upper half of the lateral lip of the linea aspera; this aponeurosis covers the upper three-fourths of the muscle, and from its deep surface many fibres take origin. A few additional fibres arise from the tendon of the Glutæus maximus, and from the lateral intermuscular septum between the Vastus lateralis and short head of the Biceps femoris. The fibres form a large fleshy mass, which is attached to a strong aponeurosis, placed on the deep surface of the lower part of the muscle: this aponeurosis becomes contracted and thickened into a flat tendon inserted into the lateral border of the patella, blending with the Quadriceps femoris tendon, and giving an expansion to the capsule of the knee-joint.

The Vastus medialis and Vastus intermedius appear to be inseparably united, but when the Rectus femoris has been reflected a narrow interval will be observed extending upward from the medial border of the patella between the two muscles, and the separation may be continued as far as the lower part of the intertrochanteric line, where, however, the two muscles are frequently continuous.

The **Vastus medialis** (*Vastus internus*) *arises* from the lower half of the intertrochanteric line, the medial lip of the linea aspera, the upper part of the medial supracondylar line, the tendons of the Adductor longus and the Adductor magnus and the medial intermuscular septum. Its fibres are directed downward and forward, and are chiefly attached to an aponeurosis which lies on the deep surface of the muscle and is *inserted* into the medial border of the patella and the Quadriceps femoris tendon, an expansion being sent to the capsule of the knee-joint.

The **Vastus intermedius** (*Crureus*) *arises* from the front and lateral surfaces of the body of the femur in its upper two-thirds and from the lower part of the lateral intermuscular septum. Its fibres end in a superficial aponeurosis, which forms the deep part of the Quadriceps femoris tendon.

The **tendons** of the different portions of the Quadriceps unite at the lower part of the thigh, so as to form a single strong tendon, which is inserted into the base of the patella, some few fibres passing over it to blend with the ligamentum patellæ. More properly, the patella may be regarded as a sesamoid bone, developed in the tendon of the Quadriceps; and the ligamentum patellæ, which is continued from the apex of the patella to the tuberosity of the tibia, as the proper tendon of insertion of the muscle, the medial and lateral patellar retinacula (see p. 439) being expansions from its borders. A bursa, which usually communicates with the cavity of the knee-joint, is situated between the femur and the portion of the Quadriceps tendon above the patella; another is interposed between the tendon and the upper part of the front of the tibia; and a third, the **prepatellar bursa**, is placed over the patella itself.

The **Articularis genu** (*Subcrureus*) is a small muscle, usually distinct from the Vastus intermedius, but occasionally blended with it; it *arises* from the anterior surface of the lower part of the body of the femur, and is inserted into the upper part of the synovial membrane of the knee-joint. It sometimes consists of several separate muscular bundles.

**Nerves.**—The Tensor fasciæ latae is supplied by the fourth and fifth lumbar and first sacral nerves through the superior gluteal nerve; the other muscles of this region, by the second, third, and fourth lumbar nerves, through the femoral nerve.

**Actions.**—The Tensor fasciæ latae is a tensor of the fascia lata; continuing its action, the oblique direction of its fibres enables it to abduct the thigh and to rotate it inward. In the erect posture, acting from below, it will serve to steady the pelvis upon the head of the femur; and by means of the iliotibial band it steadies the condyles of the femur on the articular surfaces of the tibia, and assists the Glutæus maximus in supporting the knee in the extended position. The Sartorius flexes the leg upon the thigh, and, continuing to act, flexes the thigh upon the pelvis; it next abducts and rotates the thigh outward. When the knee is bent, the Sartorius assists the Semitendinosus, Semimembranosus, and Popliteus in rotating the tibia inward. Taking its fixed point from the leg, it flexes the pelvis upon the thigh, and, if one muscle acts, assists

in rotating the pelvis. The Quadriceps femoris extends the leg upon the thigh. The Rectus femoris assists the Psoas major and Iliacus in supporting the pelvis and trunk upon the femur. It also assists in flexing the thigh on the pelvis, or if the thigh be fixed it will flex the pelvis. The Vastus medialis draws the patella medialward as well as upward.

**Applied Anatomy.**—A few fibres of the Rectus femoris are occasionally ruptured from severe strain. This accident is especially liable to occur during the games of football and baseball. The patient experiences a sudden pain in the part, as if he had been struck, and the Rectus stands out as is felt to be tense and rigid. The accident is often followed by considerable swelling from inflammatory effusion. Occasionally the Quadriceps femoris may be torn away from its insertion into the patella; or the ligamentum patellae may be ruptured about 2.5 cm. above the bone. This accident is caused in the same manner as fracture of the patella by muscular action, viz., by a violent muscular effort to prevent falling while the knee is in a position of semiflexion. A distinct gap can be felt above the patella, and, owing to the retraction of the muscular fibres, union may fail to take place.

## 2. The Medial Femoral Muscles.

Gracilis.  
Pectineus.

Adductor longus.  
Adductor brevis.

Adductor magnus.

**Dissection.**—These muscles are at once exposed by removing the fascia from the forepart and inner side of the thigh. The limb should be abducted, so as to render the muscles tense and easier of dissection.

The **Gracilis** (Fig. 543) is the most superficial muscle on the medial side of the thigh. It is thin and flattened, broad above, narrow and tapering below. It *arises* by a thin aponeurosis from the anterior margins of the lower half of the symphysis pubis and the upper half of the pubic arch. The fibres run vertically downward, and end in a rounded tendon, which passes behind the medial condyle of the femur, curves around the medial condyle of the tibia, where it becomes flattened, and is *inserted* into the upper part of the medial surface of the body of the tibia, below the condyle. A few of the fibres of the lower part of the tendon are prolonged into the deep fascia of the leg. At its insertion the tendon is situated immediately above that of the Semitendinosus, and its upper edge is overlapped by the tendon of the Sartorius, with which it is in part blended. It is separated from the tibial collateral ligament of the knee-joint, by a bursa common to it and the tendon of the Semitendinosus.

The **Pectineus** (Fig. 543) is a flat, quadrangular muscle, situated at the anterior part of the upper and medial aspect of the thigh. It *arises* from the pectineal line, and to a slight extent from the surface of bone in front of it, between the iliopectineal eminence and tubercle of the pubis, and from the fascia covering the anterior surface of the muscle; the fibres pass downward, backward, and lateralward, to be inserted into a rough line leading from the lesser trochanter to the *linea aspera*.

**Relations.**—It is in relation by its *anterior surface* with the fascia lata, which separates it from the femoral vessels and great saphenous vein; by its *posterior surface*, with the capsule of the hip-joint, the Adductor brevis, Obturator externus, and the anterior branch of the obturator nerve; by its *lateral border*, with the Psoas major and the medial femoral circumflex vessels; by its *medial border*, with the margin of the Adductor longus.

The **Adductor longus** (Fig. 546), the most superficial of the three Adductores, is a triangular muscle, lying in the same plane as the Pectineus. It *arises* by a flat, narrow tendon, from the front of the pubis, at the angle of junction of the crest with the symphysis; and soon expands into a broad fleshy belly. This passes downward, backward, and lateralward, and is *inserted*, by an aponeurosis, into the *linea aspera*, between the Vastus medialis and the Adductor magnus, with both of which it is usually blended.

**Relations.**—It is in relation by its *anterior surface* with the fascia lata, the Sartorius, and, near its insertion, with the femoral artery and vein; by its *posterior surface*, with the



Adductores brevis and magnus, the anterior branch of the obturator nerve, and near its insertion with the profunda femoris artery and vein; by its *lateral border*, with the Pectineus; by its *medial border*, with the Gracilis.




FIG. 546.—Deep muscles of the medial femoral region.

The **Adductor brevis** (Fig. 546) is situated immediately behind the two preceding muscles. It is somewhat triangular in form, and *arises* by a narrow origin from the outer surfaces of the superior and inferior rami of the pubis, between the Gracilis and Obturator externus. Its fibres, passing backward, lateralward, and downward, are *inserted*, by an aponeurosis, into the line leading from the lesser trochanter to the linea aspera and into the upper part of the linea aspera, immediately behind the Pectineus and upper part of the Adductor longus.

**Relations.**—It is in relation by its *anterior surface* with the Pectineus, Adductor longus, profunda femoris artery, and anterior branch of the obturator nerve; by its *posterior surface*, with the Adductor magnus, and posterior branch of the obturator nerve; by its *lateral border*, with the medial femoral circumflex artery, the Obturator externus, and conjoined tendon of the Psoas major and Iliacus; by its *medial border*, with the Gracilis and Adductor magnus. It is pierced near its insertion by the second, or first and second, perforating branches of the profunda femoris artery.

The **Adductor magnus** (Fig. 546) is a large triangular muscle, situated on the medial side of the thigh. It *arises* from a small part of the inferior ramus of the pubis, from the inferior ramus of the ischium, and from the outer margin of the inferior part of the tuberosity of the ischium. Those fibres which arise from the ramus of the pubis are short, horizontal in direction, and are inserted into the rough line leading from the greater trochanter to the linea aspera, medial to the Glutaeus maximus;<sup>1</sup> those from the ramus of the ischium are directed downward and lateralward with different degrees of obliquity, to be *inserted*, by means of a broad aponeurosis, into the linea aspera and the upper part of its medial prolongation below. The medial portion of the muscle, composed principally of the fibres arising from the tuberosity of the ischium, forms a thick fleshy mass consisting of coarse bundles which descend almost vertically, and end about the lower third of the thigh in a rounded tendon which is inserted into the adductor tubercle on the medial condyle of

<sup>1</sup> These uppermost fibres are sometimes described as a separate muscle—the *Adductor minimus*—which is situated somewhat anterior to the other parts of the muscle.

the femur, and is connected by a fibrous expansion to the line leading upward from the tubercle to the linea aspera. At the *insertion* of the muscle, there is a series of osseoponeurotic openings, formed by tendinous arches attached to the bone. The upper four openings are small, and give passage to the perforating branches of the profunda femoris artery. The lowest is of large size, and transmits the femoral vessels to the popliteal fossa.

**Relations.**—It is in relation by its *anterior surface* with the Pectineus, Adductores brevis and longus, the femoral and profunda vessels, and the posterior branch of the obturator nerve; by its *posterior surface*, with the sciatic nerve, the Gluteus maximus, Biceps femoris, Semitendinosus, and Semimembranosus. Its *superior border* lies parallel with the Quadratus femoris, the medial femoral circumflex artery passing between them. Its *medial border* is in relation with the Gracilis, Sartorius, and fascia lata.

**Nerves.**—The three Adductores and the Gracilis are supplied by the third and fourth lumbar nerves through the obturator nerve; the Adductor magnus receiving an additional branch from the sacral plexus through the sciatic. The Pectineus is supplied by the second, third, and fourth lumbar nerves through the femoral nerve, and by the third lumbar through the accessory obturator when this latter exists. Occasionally it receives a branch from the obturator nerve.<sup>1</sup>

**Actions.**—The Pectineus and three Adductores adduct the thigh powerfully; they are especially used in horse exercise, the sides of the saddle being grasped between the knees by the contraction of these muscles. In consequence of the obliquity of their insertions into the linea aspera, they rotate the thigh outward, assisting the external Rotators, and when the limb has been abducted, they draw it medialward, carrying the thigh across that of the opposite side. The Pectineus and Adductores brevis and longus assist the Psoas major and Iliacus in flexing the thigh upon the pelvis. In progression, all these muscles assist in drawing forward the lower limb. The Gracilis assists the Sartorius in flexing the leg and rotating it inward; it is also an adductor of the thigh. If the lower extremities be fixed, these muscles, taking their fixed points below, may act upon the pelvis, serving to maintain the body in an erect posture; or, if their action be continued, flex the pelvis forward upon the femur.

**Applied Anatomy.**—The Adductor longus is liable to be severely strained in those who ride much on horseback, or its tendon may be ruptured by suddenly gripping the saddle. Occasionally, especially in cavalry soldiers, the tendon becomes ossified, constituting the *rider's bone*.

### 3. The Muscles of the Gluteal Region (Fig. 548).

Gluteus maximus.  
Gluteus medius.  
Gluteus minimus.  
Piriformis.

Obturator internus.  
Gemellus superior.  
Gemellus inferior.  
Quadratus femoris.

Obturator externus.

**Dissection** (Fig. 547).—The subject should be turned on its face, a block placed beneath the pelvis to make the buttocks tense, and the limbs allowed to hang over the end of the table, with the foot inverted and the thigh abducted. Make an incision through the integument along the crest of the ilium to the middle of the sacrum, and thence downward to the tip of the coccyx, and carry a second incision from that point obliquely downward and outward to the outer side of the thigh, four inches below the great trochanter. The portion of integument included between these incisions is to be removed in the direction shown in the figure.

The **Gluteus maximus**, the most superficial muscle in the gluteal region, is a broad and thick fleshy mass of a quadrilateral shape, and forms the prominence of the nates. Its large size is one of the most characteristic features of the muscular system in man, connected as it is with the power he has of maintaining the trunk in the erect posture. The muscle is remarkably coarse in structure, being made up of fasciculi lying parallel with one another and collected together into large bundles separated by fibrous septa. It *arises* from the posterior gluteal line of the ilium, and the rough portion of bone including the crest, immediately above and behind it; from the posterior surface of the lower part of the sacrum and the

<sup>1</sup> The Pectineus may consist of two incompletely separated strata; the lateral or dorsal stratum, which is constant, is supplied by a branch from the femoral nerve, or in the absence of this branch by the accessory obturator nerve, the medial or ventral stratum, when present, is supplied by the obturator nerve.—A. M. Paterson. *Journal of Anatomy and Physiology*, xxvii, 43.



side of the coccyx; from the aponeurosis of the Sacrospinalis, the sacrotuberous ligament, and the fascia (gluteal aponeurosis) covering the Glutæus medius. The fibres are directed obliquely downward and lateralward; those forming the upper and larger portion of the muscle, together with the superficial fibres of the lower portion, end in a thick tendinous lamina, which passes across the greater trochanter, and is *inserted* into the iliotibial band of the fascia lata; the deeper fibres of the lower portion of the muscle are inserted into the gluteal tuberosity between the Vastus lateralis and Adductor magnus.

**Bursæ.**—Three **bursæ** are usually found in relation with the deep surface of this muscle. One of these, of large size, and generally multilocular, separates it from the greater trochanter; a second, often wanting, is situated on the tuberosity of the ischium; a third is found between the tendon of the muscle and that of the Vastus lateralis.

**Relations.**—The Glutæus maximus is in relation by its *superficial surface* with a thin fascia which separates it from the subcutaneous tissue; by its *deep surface*, from above downward, with the ilium, sacrum, coccyx, and sacrotuberous ligament, part of the Glutæus medius, Piriformis, Gemelli, Obturator internus, Quadratus femoris, the tuberosity of the ischium, greater trochanter, the origins of the Biceps femoris, Semitendinosus, Semimembranosus, and the Adductor magnus. The superficial part of the superior gluteal artery reaches the deep surface of the muscle by passing between the Piriformis and the Glutæus medius; the inferior gluteal and internal pudendal vessels and the sciatic, pudendal, and lateral femoral cutaneous nerves, and muscular branches from the sacral plexus, issue from the pelvis below the Piriformis. The first perforating artery and the terminal branches of the medial circumflex femoral artery are also found under cover of the lower part of the muscle. Its *upper border* is thin, and connected with the Glutæus medius by the gluteal aponeurosis. Its *lower border* is free and prominent, and is crossed by the fold of the nates.

**Dissection.**—Divide the Glutæus maximus near its origin by a vertical incision carried from its upper to its lower border; a cellular interval will be exposed, separating it from the Glutæus medius and Rotator muscles beneath. The upper portion of the muscle is to be altogether detached, and the lower portion turned outward; the loose areolar tissue filling up the interspace between the trochanter major and tuberosity of the ischium being removed, the parts already enumerated as exposed by the removal of this muscle will be seen.

The **Glutæus medius** is a broad, thick, radiating muscle, situated on the outer surface of the pelvis. Its posterior third is covered by the Glutæus maximus, its anterior two-thirds

by the gluteal aponeurosis, which separates it from the superficial fascia and integument. It *arises* from the outer surface of the ilium between the iliac crest and posterior gluteal line above, and the anterior gluteal line below; it also *arises* from the gluteal aponeurosis covering its outer surface. The fibres converge to a strong flattened tendon, which is *inserted* into the oblique ridge which runs downward and forward on the lateral surface of the greater trochanter. A bursa separates the tendon of the muscle from the surface of the trochanter over which it glides.

The **Glutæus minimus**, the smallest of the three Glutæi, is placed immediately beneath the preceding. It is fan-shaped, *arising* from the outer surface of the ilium,




FIG. 547.—Dissection of lower extremity. Posterior view.

between the anterior and inferior gluteal lines, and behind, from the margin of the greater sciatic notch. The fibres converge to the deep surface of a radiated aponeurosis, and this ends in a tendon which is inserted into an impression on the anterior border of the greater trochanter, and gives an expansion to the capsule of the hip-joint. A bursa is interposed between the tendon and the greater trochanter. Between the Glutaeus medius and Glutaeus minimus are the deep branches of the superior gluteal vessels and the superior gluteal nerve. The deep surface of the Glutaeus minimus is in relation with the reflected tendon of the Rectus femoris and the capsule of the hip-joint.

The **Piriformis** is a flat muscle, pyramidal in shape, lying almost parallel with the posterior margin of the Glutaeus medius. It is situated partly within the pelvis against its posterior wall, and partly at the back of the hip-joint. It arises from the front of the sacrum by three fleshy digitations, attached to the portions of bone between the first, second, third, and fourth anterior sacral foramina, and to the grooves leading from the foramina: a few fibres also arise from the margin of the greater sciatic foramen, and from the anterior surface of the sacrotuberous ligament. The muscle passes out of the pelvis through the greater sciatic foramen, the upper part of which it fills, and is inserted by a rounded tendon into the upper border of the greater trochanter behind, but often partly blended with, the common tendon of the Obturator internus and Gemelli.

**Relations.** — Within the pelvis the Piriformis is in relation by its anterior surface with the rectum (especially on the left side), the sacral plexus of nerves, and branches of the hypogastric vessels; and by its posterior surface




FIG. 548.—Muscles of the gluteal and posterior femoral regions.



with the sacrum. *Outside the pelvis*, its *anterior surface* is in contact with the posterior surface of the ischium and capsule of the hip-joint; and its *posterior surface*, with the Glutaeus maximus; its *upper border* is in relation with the Glutaeus medius, and the superior gluteal vessels and nerve; its *lower border*, with the Gemellus superior and Coccygeus, the inferior gluteal and internal pudendal vessels, and the sciatic, posterior femoral cutaneous, and pudendal nerves, and muscular branches from the sacral plexus, passing from the pelvis in the interval between the two muscles. The muscle is frequently pierced by the common peroneal nerve.

**Obturator Membrane** (Fig. 549).—The obturator membrane is a thin fibrous sheet, which almost completely closes the obturator foramen. Its fibres are arranged in interlacing bundles mainly transverse in direction; the uppermost bundle is attached to the obturator tubercles and completes the obturator canal for the passage of the obturator vessels and nerve. The membrane is attached to the sharp margin of the obturator foramen except at its lower lateral angle, where it is fixed to the pelvic surface of the inferior ramus of the ischium, *i. e.*, within the margin. Both obturator muscles are connected with this membrane.




FIG. 549.—The obturator membrane.

**Dissection.**—The next muscle, as well as the origin of the Piriformis, can only be seen when the pelvis is divided and the viscera removed.

The **Obturator internus** is situated partly within the lesser pelvis, and partly at the back of the hip-joint. It *arises* from the inner surface of the antero-lateral wall of the pelvis, where it surrounds the greater part of the obturator foramen, being attached to the inferior rami of the pubis and ischium, and at the side to the inner surface of the hip bone below and behind the pelvic brim, reaching from the upper part of the greater sciatic foramen above and behind to the obturator foramen below and in front. It also arises from the pelvic surface of the obturator membrane except in the posterior part, from the tendinous arch which completes the canal for the passage of the obturator vessels and nerve, and to a slight extent from the obturator fascia, which covers the muscle. The fibres converge rapidly toward the lesser sciatic foramen, and end in four or five tendinous bands, which are found

on the deep surface of the muscle; these bands are reflected at a right angle over the grooved surface of the ischium between its spine and tuberosity. This bony surface is covered by smooth cartilage, which is separated from the tendon by a bursa, and presents one or more ridges corresponding with the furrows between the tendinous bands. These bands leave the pelvis through the lesser sciatic foramen and unite into a single flattened tendon, which passes horizontally across the capsule of the hip-joint, and, after receiving the attachments of the Gemelli, is *inserted* into the forepart of the medial surface of the greater trochanter above the trochanteric fossa. A bursa, narrow and elongated in form, is usually found between the tendon and the capsule of the hip-joint; it occasionally communicates with the bursa between the tendon and the ischium.

**Relations.**—*Within the pelvis*, this muscle is in relation, by its *antero-lateral surface*, with the obturator membrane and inner surface of the anterior wall of the pelvis; by its *pelvic surface*, with the obturator fascia, and the origin of the Levator ani, and with the internal pudendal vessels and pudendal nerve which cross it. This surface forms the lateral boundary of the ischio-rectal fossa. *Outside the pelvis*, the muscle is covered by the Glutaeus maximus, crossed by the sciatic nerve, and rests on the back part of the hip-joint. When the tendon of the Obturator internus emerges from the lesser sciatic foramen it is overlapped both in front and behind by the two Gemelli which form a muscular canal for it; near its insertion the Gemelli pass in front of the tendon and form a groove in which it lies.

The **Gemelli** are two small muscular fasciculi, accessories to the tendon of the Obturator internus which is received into a groove between them.

The **Gemellus superior**, the smaller of the two, *arises* from the outer surface of the spine of the ischium, blends with the upper part of the tendon of the Obturator internus, and is *inserted* with it into the medial surface of the greater trochanter. It is sometimes wanting.

The **Gemellus inferior** *arises* from the upper part of the tuberosity of the ischium, immediately below the groove for the Obturator internus tendon. It blends with the lower part of the tendon of the Obturator internus, and is *inserted* with it into the medial surface of the greater trochanter.

The **Quadratus femoris** is a flat, quadrilateral muscle, between the Gemellus inferior and the upper margin of the Adductor magnus; it is separated from the latter by the terminal branches of the medial femoral circumflex vessels. It *arises* from the upper part of the external border of the tuberosity of the ischium, and is *inserted* into the upper part of the linea quadrata—that is, the line which extends vertically downward from the intertrochanteric crest. A bursa is often found between the front of this muscle and the lesser trochanter.

The **Obturator externus** (Fig. 550) is a flat, triangular muscle, which covers the outer surface of the anterior wall of the pelvis. It *arises* from the margin of bone immediately around the medial side of the obturator foramen, viz., from the rami of the pubis, and the inferior ramus of the ischium; it also arises from the medial two-thirds of the outer surface of the obturator membrane, and from the tendinous arch which completes the canal for the passage of the obturator vessels and nerves. The fibres springing from the pubic arch extend on to the inner surface of the bone, where they obtain a narrow origin between the margin of the foramen and the attachment of the obturator membrane. The fibres converge and pass backward, lateralward, and upward, and end in a tendon which runs across the back of the neck of the femur and lower part of the capsule of the hip-joint and is *inserted* into the trochanteric fossa of the femur. The obturator vessels lie between the muscle and the obturator membrane; the anterior branch of the obturator nerve reaches the thigh by passing in front of the muscle, and the posterior branch by piercing it.

**Nerves.**—The Glutaeus maximus is supplied by the fifth lumbar and first and second sacral nerves through the inferior gluteal nerve; the Glutaei medius and minimus by the fourth and

fifth lumbar and first sacral nerves through the superior gluteal; the Piriformis is supplied by the first and second sacral nerves; the Gemellus inferior and Quadratus femoris by the last lumbar and first sacral nerves; the Gemellus superior and Obturator internus by the first, second, and third sacral nerves, and the Obturator externus by the third and fourth lumbar nerves through the obturator.




FIG. 550.—The Obturator externus.

**Actions.**—When the Glutaeus maximus takes its fixed point from the pelvis, it extends the femur and brings the bent thigh into a line with the body. Taking its fixed point from below, it acts upon the pelvis, supporting it and the trunk upon the head of the femur; this is especially obvious in standing on one leg. Its most powerful action is to cause the body to regain the erect position after stooping, by drawing the pelvis backward, being assisted in this action by the Biceps femoris, Semitendinosus, and Semimembranosus. The Glutaeus maximus is a tensor of the fascia lata, and by its connection with the iliotibial band steadies the femur on the articular surfaces of the tibia during standing, when the Extensor muscles are relaxed. The lower part of the muscle also acts as an adductor and external rotator of the limb. The Glutaei medius and minimus abduct the thigh, when the limb is extended, and are principally called into action in supporting the body on one limb, in conjunction with the Tensor fasciae latae. Their anterior fibres, by drawing the greater trochanter forward, rotate the thigh inward, in which action they are also assisted by the Tensor fasciae latae. The remaining muscles are powerful external rotators of the thigh. In the sitting posture, when the thigh is flexed upon the pelvis, their action as rotators ceases, and they become abductors, with the exception of the Obturator externus, which still rotates the femur outward.

#### 4. The Posterior Femoral Muscles (Hamstring Muscles) (Fig. 548).

Biceps femoris.

Semitendinosus.

Semimembranosus.

**Dissection** (Fig. 547).—Make a vertical incision along the middle of the back of the thigh, from the lower fold of the buttock to about three inches below the back of the knee-joint, and there connect it with a transverse incision, carried from the inner to the outer side of the leg. Make a third incision transversely at the junction of the middle with the lower third of the thigh. The integument having been removed from the back of the knee, and the boundaries of the popliteal fossa having been examined, the removal of the integument from the remaining part of the thigh should be continued, when the fascia and muscles of this region will be exposed.

The **Biceps femoris** (*Biceps*) is situated on the posterior and lateral aspect of the thigh. It has two heads of origin; one, the **long head**, arises from the lower and inner impression on the back part of the tuberosity of the ischium, by a tendon common to it and the Semitendinosus, and from the lower part of the sacrotuberous ligament; the other, the **short head**, arises from the lateral lip of the linea aspera,

between the Adductor magnus and Vastus lateralis, extending up almost as high as the insertion of the Glutæus maximus; from the lateral prolongation of the linea aspera to withing 5 cm. of the lateral condyle; and from the lateral intermuscular septum. The fibres of the long head form a fusiform belly, which passes obliquely downward and lateralward across the sciatic nerve to end in an aponeurosis which covers the posterior surface of the muscle, and receives the fibres of the short head; this aponeurosis becomes gradually contracted into a tendon, which is *inserted* into the lateral side of the head of the fibula, and by a small slip into the lateral condyle of the tibia. At its insertion the tendon divides into two portions, which embrace the fibular collateral ligament of the knee-joint. From the posterior border of the tendon a thin expansion is given off to the fascia of the leg. The tendon of insertion of this muscle forms the lateral hamstring; the common peroneal nerve descends along its medial border.

The **Semitendinosus**, remarkable for the great length of its tendon of insertion, is situated at the posterior and medial aspect of the thigh. It *arises* from the lower and medial impression on the tuberosity of the ischium, by a tendon common to it and the long head of the Biceps femoris; it also arises from an aponeurosis which connects the adjacent surfaces of the two muscles to the extent of about 7.5 cm. from their origin. The muscle is fusiform and ends a little below the middle of the thigh in a long round tendon which lies along the medial side of the popliteal fossa; it then curves around the medial condyle of the tibia and passes over the tibial collateral ligament of the knee-joint, from which it is separated by a bursa, and is *inserted* into the upper part of the medial surface of the body of the tibia, nearly as far forward as its anterior crest. At its insertion it gives off from its lower border a prolongation to the deep fascia of the leg and lies behind the tendon of the Sartorius, and below that of the Gracilis, to which it is united. A tendinous intersection is usually observed about the middle of the muscle.

The **Semimembranosus**, so called from its membranous tendon of origin, is situated at the back and medial side of the thigh. It *arises* by a thick tendon from the upper and outer impression on the tuberosity of the ischium, above and lateral to the Biceps femoris and Semitendinosus, and is *inserted* into the groove on the back of the medial condyle of the tibia. The tendon of origin expands into an aponeurosis, which covers the upper part of the anterior surface of the muscle; from this aponeurosis muscular fibres arise, and converge to another aponeurosis which covers the lower part of the posterior surface of the muscle and contracts into the tendon of insertion. The tendon of insertion gives off certain fibrous expansions: one, of considerable size, passes upward and lateralward to be *inserted* into the back part of the lateral condyle of the femur, forming part of the oblique popliteal ligament of the knee-joint; a second is continued downward to the fascia which covers the Popliteus muscle; while a few fibres join the tibial collateral ligament of the joint and the fascia of the leg. The muscle overlaps the upper part of the popliteal vessels.

The tendons of insertion of the two preceding muscles form the medial hamstrings.

**Nerves.**—The muscles of this region are supplied by the fourth and fifth lumbar and the first, second, and third sacral nerves; the nerve to the short head of the Biceps femoris is derived from the common peroneal, the other muscles are supplied through the tibial nerve.

**Actions.**—The hamstring muscles flex the leg upon the thigh. When the knee is semiflexed, the Biceps femoris in consequence of its oblique direction rotates the leg slightly outward; and the Semitendinosus, and to a slight extent the Semimembranosus, rotate the leg inward, assisting the Popliteus. Taking their fixed point from below, these muscles serve to support the pelvis upon the head of the femur, and to draw the trunk directly backward, as in raising it from the stooping position or in feats of strength, when the body is thrown backward in the form of an arch. As already indicated on page 383, complete flexion of the hip cannot be effected unless the knee-joint is also flexed, on account of the shortness of the hamstring muscles.

**Applied Anatomy.**—In disease of the knee-joint, contraction of the hamstring tendons is a frequent complication; this causes flexion of the leg, and a partial dislocation of the tibia back-



ward, with a slight degree of rotation outward, probably due to the action of the Biceps femoris. The hamstring tendons occasionally require subcutaneous division in some forms of spurious ankylosis of the knee-joint dependent upon permanent contraction and rigidity of the muscles, or from contracture of the ligamentous and other tissues surrounding the joint, the result of disease. The relation of the common peroneal nerve, which lies in close apposition to the medial border of the tendon of the Biceps femoris, must always be borne in mind in dividing this tendon, and a free incision with exposure of the tendon, before division, is the safer proceeding.

### III. THE MUSCLES AND FASCIAE OF THE LEG.

The muscles of the leg may be divided into three groups: anterior, posterior, and lateral.

#### 1. The Anterior Crural Muscles (Fig. 551).

Tibialis anterior.

Extensor hallucis longus.

Extensor digitorum longus.

Peroneus tertius.

**Dissection** (Fig. 543).—The knee should be bent, a block placed beneath it, and the foot kept in an extended position; then make an incision through the integument in the middle line of the leg to the ankle, and continue it along the dorsum of the foot to the toes. Make a second incision transversely across the ankle, and a third in the same direction across the bases of the toes; remove the flaps of integument included between these incisions in order to examine the deep fascia of the leg.

**Deep Fascia** (*fascia cruris*).—The deep fascia of the leg forms a complete investment to the muscles, and is fused with the periosteum over the subcutaneous surfaces of the bones. It is continuous *above* with the fascia lata, and is attached around the knee to the patella, the ligamentum patellae, the tuberosity and condyles of the tibia, and the head of the fibula. *Behind*, it forms the popliteal fascia, covering in the popliteal fossa; here it is strengthened by transverse fibres, and perforated by the small saphenous vein. It receives an expansion from the tendon of the Biceps femoris laterally, and from the tendons of the Sartorius, Gracilis, Semitendinosus, and Semimembranosus medially; in *front*, it blends with the periosteum covering the subcutaneous surface of the tibia, and with that covering the head and malleolus of the fibula; below, it is continuous with the transverse crural and lacinate ligaments. It is thick and dense in the upper and anterior part of the leg, and gives attachment, by its deep surface, to the Tibialis anterior and Extensor digitorum longus; but thinner behind, where it covers the Gastrocnemius and Soleus. It gives off from its deep surface, on the lateral side of the leg, two strong intermuscular septa, the **anterior** and **posterior peroneal septa**, which enclose the Peronei longus and brevis, and separate them from the muscles of the anterior and posterior crural regions, and several more slender processes which enclose the individual muscles in each region. A broad transverse intermuscular septum, called the **deep transverse fascia of the leg**, intervenes between the superficial and deep posterior crural muscles.

**Dissection**.—Remove the fascia by dividing it in the same direction as the integument, excepting opposite the ankle, where it should be left entire. Commence the removal of the fascia from below, opposite the tendons, and detach it in the line of direction of the muscle fibres.

The **Tibialis anterior** (*Tibialis anticus*) is situated on the lateral side of the tibia; it is thick and fleshy above, tendinous below. It *arises* from the lateral condyle and upper half or two-thirds of the lateral surface of the body of the tibia; from the adjoining part of the interosseous membrane; from the deep surface of the fascia; and from the intermuscular septum between it and the Extensor digitorum longus. The fibres run vertically downward, and end in a tendon, which is apparent on the anterior surface of the muscle at the lower third of the leg. After passing through the most medial compartments of the transverse and cruciate crural

ligaments, it is *inserted* into the medial and under surface of the first cuneiform bone, and the base of the first metatarsal bone. This muscle overlaps the anterior tibial vessels and deep peroneal nerve in the upper part of the leg.

The **Extensor hallucis longus** (*Extensor proprius hallucis*) is a thin muscle, situated between the Tibialis anterior and the Extensor digitorum longus. It *arises* from the anterior surface of the fibula for about the middle two-fourths of its extent, medial to the origin of the Extensor digitorum longus; it also *arises* from the interosseous membrane to a similar extent. The anterior tibial vessels and deep peroneal nerve lie between it and the Tibialis anterior. The fibres pass downward, and end in a tendon, which occupies the anterior border of the muscle, passes through a distinct compartment in the cruciate crural ligament, crosses from the lateral to the medial side of the anterior tibial vessels near the bend of the ankle, and is *inserted* into the base of the distal phalanx of the great toe. Opposite the metatarsophalangeal articulation, the tendon gives off a thin prolongation on either side, to cover the surface of the joint. An expansion from the medial side of the tendon is usually inserted into the base of the proximal phalanx.

The **Extensor digitorum longus** is a penniform muscle, situated at the lateral part of the front of the leg. It *arises* from the lateral condyle of the tibia; from the upper three-fourths of the anterior surface of the body of the fibula; from the upper part of the interosseous membrane; from the deep surface of the fascia; and from the intermuscular septa between it and the Tibialis anterior on the medial, and the Peronei on the lateral side. Between it and the Tibialis anterior are the upper portions of the anterior tibial vessels and deep peroneal nerve. The tendon passes under the transverse and cruciate crural ligaments in company with the Peroneus tertius, and divides into four slips, which run forward on the dorsum of the foot, and are *inserted* into the second and third phalanges of the four lesser toes. The tendons to the second, third, and fourth toes are each joined, opposite the metatarsophalangeal articulation, on the lateral side by a tendon of the Extensor digitorum brevis. The tendons are inserted in the following manner: each receives a fibrous expansion from the Interossei and Lumbricalis, and then spreads out into a broad aponeurosis, which covers the dorsal surface of the first phalanx: this aponeurosis, at the articulation of the first with the second phalanx, divides into




FIG. 551.—Muscles of the front of the leg.

three slips—an intermediate, which is inserted into the base of the second phalanx; and two collateral slips, which, after uniting on the dorsal surface of the second phalanx, are continued onward, to be inserted into the base of the third phalanx.

The **Peronaeus tertius** is a part of the Extensor digitorum longus, and might be described as its fifth tendon. The fibres belonging to this tendon *arise* from the lower third or more of the anterior surface of the fibula; from the lower part of the interosseous membrane; and from an intermuscular septum between it and the Peronaeus brevis. The tendon, after passing under the transverse and cruciate crural ligaments in the same canal as the Extensor digitorum longus, is *inserted* into the dorsal surface of the base of the metatarsal bone of the little toe. This muscle is sometimes wanting.

**Nerves.**—These muscles are supplied by the fourth and fifth lumbar and first sacral nerves through the deep peroneal nerve.

**Actions.**—The Tibialis anterior and Peronaeus tertius are the direct flexors of the foot at the ankle-joint; the former muscle, when acting in conjunction with the Tibialis posterior, raises the medial border of the foot, *i. e.*, inverts the foot; and the latter, acting with the Peronaei brevis and longus, raises the lateral border of the foot, *i. e.*, everts the foot. The Extensor digitorum longus and Extensor hallucis longus extend the phalanges of the toes, and, continuing their action, flex the foot upon the leg. Taking their fixed points from below, in the erect posture, all these muscles serve to fix the bones of the leg in the perpendicular position, and give increased strength to the ankle-joint.

## 2. The Posterior Crural Muscles.

**Dissection** (Fig. 547).—Make a vertical incision along the middle line of the back of the leg, from the lower part of the popliteal fossa to the heel, connecting it below by a transverse incision extending between the two malleoli; the flaps of integument being removed, the fascia and muscles should be examined.

The muscles of the back of the leg are subdivided into two groups—superficial and deep. Those of the superficial group constitute a powerful muscular mass, forming the calf of the leg. Their large size is one of the most characteristic features of the muscular apparatus in man, and bears a direct relation to his erect attitude and his mode of progression.

### The Superficial Group (Fig. 552).

Gastrocnemius.

Soleus.

Plantaris.

The **Gastrocnemius** is the most superficial muscle, and forms the greater part of the calf. It *arises* by two heads, which are connected to the condyles of the femur by strong, flat tendons. The **medial** and **larger head** takes its origin from a depression at the upper and back part of the medial condyle and from the adjacent part of the femur. The **lateral head** *arises* from an impression on the side of the lateral condyle and from the posterior surface of the femur immediately above the lateral part of the condyle. Both heads, also, *arise* from the subjacent part of the capsule of the knee. Each tendon spreads out into an aponeurosis, which covers the posterior surface of that portion of the muscle to which it belongs. From the anterior surfaces of these tendinous expansions, muscular fibres are given off; those of the medial head being thicker and extending lower than those of the lateral. The fibres unite at an angle in the middle line of the muscle in a tendinous raphé, which expands into a broad aponeurosis on the anterior surface of the muscle, and into this the remaining fibres are inserted. The aponeurosis, gradually contracting, unites with the tenon of the Soleus, and forms with it the tendo calcaneus.

**Relations.**—The Gastrocnemius is in relation by its *superficial surface* with the fascia of the leg, which separates it from the small saphenous vein and the peroneal anastomotic, medial sural cutaneous, and sural nerves; the common peroneal nerve crosses the lateral head, lying partly under cover of the Biceps femoris. Its *deep surface* is in relation with the oblique popliteal ligament of the knee-joint, the Popliteus, Soleus, Plantaris, popliteal vessels, and tibial nerve. In

front of the tendon of the medial head is a bursa, which, in some cases, communicates with the cavity of the knee-joint. The tendon of the lateral head sometimes contains a sesamoid fibrocartilage or bone, where it plays over the corresponding condyle; and one is occasionally found in the tendon of the medial head.

The **Soleus** is a broad flat muscle situated immediately in front of the Gastrocnemius. It *arises* by tendinous fibres from the back of the head of the fibula, and from the upper third of the posterior surface of the body of the bone; from the popliteal line, and the middle third of the medial border of the tibia; some fibres also arise from a tendinous arch placed between the tibial and fibular origins of the muscle, in front of which the popliteal vessels and tibial nerve run. The fibres end in an aponeurosis which covers the posterior surface of the muscle, and, gradually becoming thicker and narrower, joins with the tendon of the Gastrocnemius, and forms with it the tendo calcaneus.

**Relations.**—By its *superficial surface* it is in relation with the Gastrocnemius and Plantaris; by its *deep surface*, with the Flexor digitorum longus, Flexor hallucis longus, Tibialis posterior, and posterior tibial vessels and nerve, from which it is separated by the deep transverse fascia of the leg.

The Gastrocnemius and Soleus together form a muscular mass which is occasionally described as the **Triceps surae**; its tendon of insertion is the tendo calcaneus.

**Tendo Calcaneus** (*tendo Achillis*).—The tendo calcaneus, the common tendon of the Gastrocnemius and Soleus, is the thickest and strongest in the body. It is about 15 cm. long, and begins near the middle of the leg, but receives fleshy fibres on its anterior surface, almost to its lower end. Gradually becoming contracted below, it is inserted into the middle part of the posterior surface of the calcaneus, a bursa being interposed between the tendon and the upper part of this surface. The tendon spreads out somewhat at its lower end, so that its narrowest part is about 4 cm. above its insertion. It is covered by the fascia and the integument, and is separated from the deep muscles and vessels by a considerable interval filled up with areolar and adipose tissue. Along its lateral side, but superficial to it, is the small saphenous vein.

The **Plantaris** is placed between the Gastrocnemius and Soleus. It *arises* from the lower part of the lateral prolongation of the linea aspera, and from the oblique popliteal ligament of the knee-joint. It forms a small fusiform belly, from 7 to 10 cm. long, ending in a long slender tendon which crosses obliquely between the two muscles of the calf, and runs along the medial border of the tendo calcaneus, to be *inserted* with it into the posterior part of the calcaneus. This muscle is sometimes double, and at other times wanting. Occasionally, its tendon is lost in the lacinate ligament, or in the fascia of the leg.

**Nerves.**—The Gastrocnemius and Soleus are supplied by the first and second sacral nerves, and the Plantaris by the fourth and fifth lumbar and first sacral nerves, through the tibial nerve.

**Actions.**—The muscles of the calf are the chief extensors of the foot at the ankle-joint. They possess considerable power, and are constantly called into use in standing, walking, dancing, and leaping; hence the large size they usually present. In walking, these muscles raise the heel from the ground; the body being thus supported on the raised foot, the opposite limb can be carried forward. In standing, the Soleus, taking its fixed point from below, steadies the leg upon the foot and prevents the body from falling forward. The Gastrocnemius, acting from below, serves to flex the femur upon the tibia, assisted by the Popliteus. The Plantaris is the rudiment of a large muscle which in some of the lower animals is continued over the calcaneus to be inserted into the plantar aponeurosis. In man it is an accessory to the Gastrocnemius, extending the ankle if the foot be free, or bending the knee if the foot be fixed.

#### The Deep Group (Fig. 553).

Popliteus.

Flexor hallucis longus.

Flexor digitorum longus.

Tibialis posterior.

**Dissection.**—Detach the Soleus from its attachment to the fibula and tibia, and turn it downward, when the deep layer of muscles is exposed, covered by the deep transverse fascia of the leg.



**Deep Transverse Fascia.**—The deep transverse fascia of the leg is a transversely placed, intermuscular septum, between the superficial and deep muscles of the




FIG. 552.—Muscles of the back of the leg.  
Superficial layer.



FIG. 553.—Muscles of the back of the leg.  
Deep layer.

back of the leg. At the sides it is connected to the margins of the tibia and fibula. Above, where it covers the Popliteus, it is thick and dense, and receives an expansion from the tendon of the Semimembranosus; it is thinner in the middle

of the leg; but *below*, where it covers the tendons passing behind the malleoli, it is thickened and continuous with the lacinate ligament.

**Dissection.**—This fascia should now be removed, commencing from below opposite the tendons, and detaching it from the muscles in the direction of their fibres.

The **Popliteus** is a thin, flat, triangular muscle, which forms the lower part of the floor of the popliteal fossa. It *arises* by a strong tendon about 2.5 cm. long, from a depression at the anterior part of the groove on the lateral condyle of the femur, and to a small extent from the oblique popliteal ligament of the knee-joint; and is *inserted* into the medial two-thirds of the triangular surface above the popliteal line on the posterior surface of the body of the tibia, and into the tendinous expansion covering the surface of the muscle.

**Relations.**—The tendon of the muscle is covered by that of the Biceps femoris and by the fibular collateral ligament of the knee-joint; it grooves the posterior border of the lateral meniscus, and is invested by the synovial membrane of the knee-joint. The fascia covering the muscle separates it from the Gastrocnemius, Plantaris, popliteal vessels, and tibial nerve. The deep surface of the muscle is in contact with the oblique popliteal ligament of the knee-joint and the back of the tibia.

The **Flexor hallucis longus** is situated on the fibular side of the leg. It *arises* from the inferior two-thirds of the posterior surface of the body of the fibula, with the exception of 2.5 cm. at its lowest part; from the lower part of the interosseous membrane; from an intermuscular septum between it and the Peronaei, laterally, and from the fascia covering the Tibialis posterior, medially. The fibres pass obliquely downward and backward, and end in a tendon which occupies nearly the whole length of the posterior surface of the muscle. This tendon lies in a groove which crosses the posterior surface of the lower end of the tibia, the posterior surface of the talus, and the under surface of the sustentaculum tali of the calcaneus; in the sole of the foot it runs forward between the two heads of the Flexor hallucis brevis, and is *inserted* into the base of the last phalanx of the great toe. The grooves on the talus and calcaneus, which contain the tendon of the muscle, are converted by tendinous fibres into distinct canals, lined by a mucous sheath. As the tendon passes forward in the sole of the foot, it is situated above, and crosses from the lateral to the medial side of the tendon of the Flexor digitorum longus, to which it is connected by a fibrous slip.

**Relations.**—The Flexor hallucis longus is in relation by its *superficial surface* with the Soleus and tendo calcaneus, from which it is separated by the deep transverse fascia; by its *deep surface*, with the fibula, Tibialis posterior, the peroneal vessels, the lower part of the interosseous membrane, and the ankle-joint; by its *lateral border*, with the Peronaei; by its *medial border*, with the Tibialis posterior and posterior tibial vessels and tibial nerve.

The **Flexor digitorum longus** is situated on the tibial side of the leg. At its origin it is thin and pointed, but it gradually increases in size as it descends. It *arises* from the posterior surface of the body of the tibia, from immediately below the popliteal line to within 7 or 8 cm. of its lower extremity, medial to the tibial origin of the Tibialis posterior; it also *arises* from the fascia covering the Tibialis posterior. The fibres end in a tendon, which runs nearly the whole length of the posterior surface of the muscle. This tendon passes behind the medial malleolus, in a groove, common to it and the Tibialis posterior, but separated from the latter by a fibrous septum, each tendon being contained in a special compartment lined by a separate mucous sheath. It passes obliquely forward and lateralward, superficial to the deltoid ligament of the ankle-joint, into the sole of the foot (Fig. 557), where it crosses below the tendon of the Flexor hallucis longus, and receives from it a strong tendinous slip. It then expands and is joined by the Quadratus plantae, and finally divides into four tendons, which are *inserted* into the bases of the last phalanges of the second, third, fourth, and fifth toes, each tendon passing through



an opening in the corresponding tendon of the Flexor digitorum brevis opposite the base of the first phalanx.

**Relations.**—In the leg this muscle is in relation by its *superficial surface* with the posterior tibial vessels and tibial nerve, and the deep transverse fascia which separates it from the Soleus; by its *deep surface*, with the tibia and Tibialis posterior. In the foot, it is covered by the Abductor hallucis and Flexor digitorum brevis, and crosses superficial to the Flexor hallucis longus.

The **Tibialis posterior** (*Tibialis posticus*) lies between the two preceding muscles, and is the most deeply seated of the muscles on the back of the leg. It begins above by two pointed processes, separated by an angular interval through which the anterior tibial vessels pass forward to the front of the leg. It *arises* from the whole of the posterior surface of the interosseous membrane, excepting its lowest part; from the lateral portion of the posterior surface of the body of the tibia, between the commencement of the popliteal line above and the junction of the middle and lower thirds of the body below; and from the upper two-thirds of the medial surface of the fibula; some fibres also arise from the deep transverse fascia, and from the intermuscular septa separating it from the adjacent muscles. In the lower fourth of the leg its tendon passes in front of that of the Flexor digitorum longus and lies with it in a groove behind the medial malleolus, but enclosed in a separate sheath; it next passes under the lacinate and over the deltoid ligament into the foot, and then beneath the plantar calcaneonavicular ligament. The tendon contains a sesamoid fibrocartilage, as it runs under the plantar calcaneonavicular ligament. It is *inserted* into the tuberosity of the navicular bone, and gives off fibrous expansions, one of which passes backward to the sustentaculum tali of the calcaneus, others forward and lateralward to the three cuneiforms, the cuboid, and the bases of the second, third, and fourth metatarsal bones.

**Relations.**—The Tibialis posterior is in relation by its *superficial surface* with the Soleus, from which it is separated by the deep transverse fascia, the Flexor digitorum longus, the posterior tibial vessels and tibial nerve, and the peroneal vessels; by its *deep surface*, with the interosseous membrane, the tibia, fibula, and ankle-joint.

**Nerves.**—The Popliteus is supplied by the fourth and fifth lumbar and first sacral nerves, the Flexor digitorum longus and Tibialis posterior by the fifth lumbar and first sacral, and the Flexor hallucis longus by the fifth lumbar and the first and second sacral nerves, through the tibial nerve.

**Actions.**—The Popliteus assists in flexing the leg upon the thigh; when the leg is flexed, it will rotate the tibia inward. It is especially called into action at the beginning of the act of bending the knee, inasmuch as it produces the slight inward rotation of the tibia which is essential in the early stage of this movement. The Tibialis posterior is a direct extensor of the foot at the ankle-joint; acting in conjunction with the Tibialis anterior, it turns the sole of the foot upward and medialward, *i. e.*, inverts the foot, antagonizing the Peronei, which turn it upward and lateralward (evert it). In the sole of the foot the tendon of the Tibialis posterior lies directly below the plantar calcaneonavicular ligament, and is therefore an important factor in maintaining the arch of the foot. The Flexor digitorum longus and Flexor hallucis longus are the direct flexors of the phalanges, and, continuing their action, extend the foot upon the leg; they assist the Gastrocnemius and Soleus in extending the foot, as in the act of walking, or in standing on tiptoe. In consequence of the oblique direction of its tendons the Flexor digitorum longus would draw the toes medialward, were it not for the Quadratus plantae, which is inserted into the lateral side of the tendon, and draws it to the middle line of the foot. Taking their fixed point from the foot, these muscles serve to maintain the upright posture by steadying the tibia and fibula perpendicularly upon the talus.

### 3. The Lateral Crural Muscles (Fig. 553).

Peroneus longus.

Peroneus brevis.

**Dissection.**—The muscles are readily exposed by removing the fascia covering their surface, from below upward, in the line of direction of their fibres.

The **Peroneus longus** is situated at the upper part of the lateral side of the leg, and is the more superficial of the two muscles. It *arises* from the head and

upper two-thirds of the lateral surface of the body of the fibula, from the deep surface of the fascia, and from the intermuscular septa between it and the muscles on the front and back of the leg; occasionally also by a few fibres from the lateral condyle of the tibia. Between its attachments to the head and to the body of the fibula there is a gap through which the common peroneal nerve passes to the front of the leg. It ends in a long tendon, which runs behind the lateral malleolus, in a groove common to it and the tendon of the *Peronaeus brevis*, behind which it lies; the groove is converted into a canal by the superior peroneal retinaculum, and the tendons in it are contained in a common mucous sheath. The tendon then extends obliquely forward across the lateral side of the calcaneus, below the trochlear process, and the tendon of the *Peronaeus brevis*, and under cover of the inferior peroneal retinaculum. It crosses the lateral side of the cuboid, and then runs on the under surface of that bone in a groove which is converted into a canal by the long plantar ligament; the tendon then crosses the sole of the foot obliquely, and is inserted into the lateral side of the base of the first metatarsal bone and the lateral side of the first cuneiform. Occasionally it sends a slip to the base of the second metatarsal bone. The tendon changes its direction at two points: first, behind the lateral malleolus; secondly, on the cuboid bone; in both of these situations the tendon is thickened, and, in the latter, a sesamoid fibrocartilage (sometimes a bone), is usually developed in its substance.

The *Peronaeus brevis* lies under cover of the *Peronaeus longus*, and is a shorter and smaller muscle. It arises from the lower two-thirds of the lateral surface of the body of the fibula; medial to the *Peronaeus longus*; and from the intermuscular septa separating it from the adjacent muscles on the front and back of the leg. The fibres pass vertically downward, and end in a tendon which runs behind the lateral malleolus along with but in front of that of the preceding muscle, the two tendons being enclosed in the same compartment, and lubricated by a common mucous sheath. It then runs forward on the lateral side of the calcaneus, above the trochlear process and the tendon of the *Peronaeus longus*, and is inserted into the tuberosity at the base of the fifth metatarsal bone, on its lateral side.

On the lateral surface of the calcaneus the tendons of the *Peronaei longus* and *brevis* occupy separate osseoponeurotic canals formed by the calcaneus and the perineal retinacula; each tendon is enveloped by a forward prolongation of the common mucous sheath.

**Nerves.**—The *Peronaei longus* and *brevis* are supplied by the fourth and fifth lumbar and first sacral nerves through the superficial peroneal nerve.

**Actions.**—The *Peronaei longus* and *brevis* extend the foot upon the leg, in conjunction with the *Tibialis posterior*, antagonizing the *Tibialis anterior* and *Peronaeus tertius*, which are flexors of the foot. The *Peronaeus longus* also everts the sole of the foot, and from the oblique direction of the tendon across the sole of the foot is an important agent in the maintenance of the transverse arch. Taking their fixed points below, the *Peronaei* serve to steady the leg upon the foot. This is especially the case in standing upon one leg, when the tendency of the superincumbent weight is to throw the leg medialward; the *Peronaeus longus* overcomes this tendency by drawing on the lateral side of the leg.

**Applied Anatomy.**—The student should now consider the positions of the tendons of the various muscles of the leg, their relation with the ankle-joint and surrounding bloodvessels, and especially their actions upon the foot, as their rigidity and contraction give rise to one or other of the kinds of deformity known as *club-foot*. The most simple and common deformity, and one that is rarely, if ever, congenital, is *talipes equinus*, the heel being raised by the rigidity and contraction of the *Gastrocnemius* so that the patient walks upon the ball of the foot. In *talipes varus* the foot is forcibly adducted and the medial side of the sole raised, sometimes to a right angle with the ground, by the action of the *Tibiales anterior* and *posterior*. In *talipes valgus* the lateral edge of the foot is raised by the *Peronaei*, and the patient walks on the medial side of the foot. In *talipes calcaneus* the toes are raised by the *Extensor* muscles, the heel is depressed and the patient walks upon it. Other varieties of deformity are met with, as *talipes equinovarus*, *equinovalgus*, and *calcaneovalgus*, whose names sufficiently indicate their nature. Of these, *talipes equinovarus* is the most common congenital form; the heel is raised by the tendo calcaneus, the medial border of the foot drawn upward by the *Tibialis anterior*, the anterior two-thirds twisted medialward

by the Tibialis posterior, and the arch increased by the contraction of the plantar aponeurosis, so that the patient walks on the middle of the lateral border of the foot. Each of these deformities may sometimes be successfully relieved by division of the opposing tendons and fascia; by this means the foot regains its proper position, and the tendons heal by the organization of lymph thrown out between the divided ends. The operation is easily performed by putting the contracted tendon upon the stretch, and dividing it by means of a narrow, sharp-pointed knife inserted beneath it.

Rupture of a few of the fibres of the Gastrocnemius, or rupture of the Plantaris tendon, not uncommonly occurs, especially in men somewhat advanced in life, from some sudden exertion, and frequently occurs during the game of lawn tennis, and is hence known as *lawn-tennis leg*. The accident is accompanied by a sudden pain, and produces a sensation as if the individual had been struck a violent blow on the part. The tendo calcaneus is also sometimes ruptured. It is stated that John Hunter ruptured his tendo calcaneus while dancing, at the age of forty. The bursa between the tendo calcaneus and the posterior surface of the calcaneus sometimes becomes inflamed, especially in pedestrians and "long-distance" walkers. It causes great and disabling pain, and entirely prevents the sufferer from continuing his walk.

### THE FASCIA AROUND THE ANKLE.

Fibrous bands, or thickened portions of the fascia, bind down the tendons in front of and behind the ankle in their passage to the foot. They comprise three ligaments, viz., the transverse crural, the cruciate crural, and the laciniate; and the superior and inferior peroneal retinacula.




FIG. 554.—The mucous sheaths of the tendons around the ankle. Lateral aspect.

**Transverse Crural Ligament** (*ligamentum transversum cruris*; upper part of *anterior annular ligament*) (Fig. 554).—The transverse crural ligament binds down the tendons of Extensor digitorum longus, Extensor hallucis longus, Peroneus tertius, and Tibialis anterior as they descend on the front of the tibia and fibula; under it are found also the anterior tibial vessels and deep peroneal nerve. It is attached laterally to the lower end of the fibula, and medially to the tibia; above it is continuous with the fascia of the leg.

**Cruciate Crural Ligament** (*ligamentum cruciatum cruris*; lower part of *anterior annular ligament*) (Figs. 554, 555).—The cruciate crural ligament is a Y-shaped band placed in front of the ankle-joint, the stem of the Y being attached laterally

to the upper surface of the calcaneus, in front of the depression for the interosseous talocalcaneal ligament; it is directed medialward as a double layer, one lamina passing in front of, and the other behind, the tendons of the Peroneus tertius and Extensor digitorum longus. At the medial border of the latter tendon these two layers join together, forming a compartment in which the tendons are enclosed. From the medial extremity of this sheath the two limbs of the Y diverge: one is directed upward and medialward, to be attached to the tibial malleolus, passing over the Extensor hallucis longus and the vessels and nerves, but enclosing the Tibialis anterior by a splitting of its fibres. The other limb extends downward and medialward, to be attached to the border of the plantar aponeurosis, and passes over the tendons of the Extensor hallucis longus and Tibialis anterior and also the vessels and nerves.




FIG. 555.—The mucous sheaths of the tendons around the ankle. Medial aspect.

**Lacinate Ligament** (*ligamentum lancinatum*; *internal annular ligament*).—The lacinate ligament is a strong fibrous band, extending from the tibial malleolus above to the margin of the calcaneus below, converting a series of bony grooves in this situation into canals for the passage of the tendons of the Flexor muscles and the posterior tibial vessels and tibial nerve into the sole of the foot. It is continuous by its upper border with the deep fascia of the leg, and by its lower border with the plantar aponeurosis and the fibres of origin of the Abductor hallucis muscle. Enumerated from the medial side, the four canals which it forms transmit the tendon of the Tibialis posterior; the tendon of the Flexor digitorum longus; the posterior tibial vessels and tibial nerve, which run through a broad space beneath the ligament; and lastly, in a canal formed partly by the talus, the tendon of the Flexor hallucis longus.

**Peroneal Retinacula.**—The peroneal retinacula are fibrous bands which bind down the tendons of the Peronei longus and brevis as they run across the lateral side of the ankle. The fibres of the **superior retinaculum** (*external annular ligament*) are attached *above* to the lateral malleolus and *below* to the lateral surface of the calcaneus. The fibres of the **inferior retinaculum** are continuous in *front* with those of the cruciate crural ligament; *behind* they are attached to the lateral surface of the calcaneus; some of the fibres are fixed to the peroneal trochlea, forming a septum between the tendons of the Peronei longus and brevis.





the tendon of the Flexor hallucis longus, and the Lumbricales. The long Flexor tendons diverge from each other at an acute angle; the Flexor hallucis longus runs along the inner side of the foot, on a plane superior to that of the Flexor digitorum longus, the direction of the latter being obliquely outward.

### The Second Layer (Fig. 557).

Quadratus plantae.

Lumbricales.

The **Quadratus plantae** (*Flexor accessorius*) is separated from the muscles of the first layer by the lateral plantar vessels and nerve. It *arises* by two heads, which are separated from each other by the long plantar ligament: the **medial or larger head** is muscular, and is attached to the medial concave surface of the calcaneus, below the groove which lodges the tendon of the Flexor hallucis longus; the **lateral head**, flat and tendinous, *arises* from the lateral border of the inferior surface of the calcaneus, in front of the lateral process of its tuberosity, and from the long plantar ligament. The two portions join at an acute angle, and end in a flattened band which is *inserted* into the lateral margin and upper and under surfaces of the tendon of the Flexor digitorum longus, forming a kind of groove, in which the tendon is lodged. It usually sends slips to those tendons of the Flexor digitorum longus which pass to the second, third, and fourth toes.

The **Lumbricales** are four small muscles, accessory to the tendons of the Flexor digitorum longus and numbered from the medial side of the foot; they *arise* from these tendons, as far back as their angles of division, each springing from two tendons, except the first. The muscles end in tendons, which pass forward on the medial sides of the four lesser toes, and are *inserted* into the expansions of the tendons of the Extensor digitorum longus on the dorsal surfaces of the first phalanges.

**Dissection.**—The Flexor tendons should be divided at the back part of the foot, and the Quadratus plantae at its origin, and drawn forward, in order to expose the third layer.

### The Third Layer (Fig. 558).

Flexor hallucis brevis.

Adductor hallucis.

Flexor digiti quinti brevis.

The **Flexor hallucis brevis** *arises*, by a pointed tendinous process, from the medial part of the under surface of the cuboid bone, from the contiguous portion of the third cuneiform, and from the prolongation of the tendon of the Tibialis posterior which is attached to that bone. It divides in front into two portions, which are inserted into the medial and lateral sides of the base of the first phalanx of the great toe, a sesamoid bone being present in each tendon at its insertion. The **medial portion** is blended with the Abductor hallucis previous to its insertion; the **lateral portion** with the Adductor hallucis; the tendon of the Flexor hallucis longus lies in a groove between them; the lateral portion is sometimes described as the **first Interosseous plantaris**.

The **Adductor hallucis** (*Adductor obliquus hallucis*) *arises* by two heads—oblique and transverse. The **oblique head** is a large, thick, fleshy mass, crossing the foot obliquely and occupying the hollow space under the first, second, third, and fourth metatarsal bones. It *arises* from the bases of the second, third, and fourth metatarsal bones, and from the sheath of the tendon of the Peroneus longus, and is *inserted*, together with the lateral portion of the Flexor hallucis brevis, into the lateral side of the base of the first phalanx of the great toe. The **transverse head** (*Transversus pedis*) is a narrow, flat fasciculus which *arises* from the plantar metatarsophalangeal ligaments of the third, fourth, and fifth toes (sometimes only from the third and fourth), and from the transverse ligament of the metatarsus. It is *inserted* into the lateral side of the base of the first phalanx of the great toe, its fibres blending with the tendon of insertion of the oblique head.



The Abductor, Flexor brevis, and Adductor of the great toe, like the similar muscles of the thumb, give off, at their insertions, fibrous expansions to blend with the tendons of the Extensor digitorum longus.




FIG. 557.—Muscles of the sole of the foot.  
Second layer.




FIG. 558.—Muscles of the sole of the foot.  
Third layer.

The **Flexor digiti quinti brevis** (*Flexor brevis minimi digiti*) lies under the metatarsal bone of the little toe, and resembles one of the Interossei. It *arises* from the base of the fifth metatarsal bone, and from the sheath of the Peroneus longus; its tendon is *inserted* into the lateral side of the base of the first phalanx of the fifth toe. Occasionally a few of the deeper fibres are inserted into the lateral part of the distal half of the fifth metatarsal bone; these are described by some as a distinct muscle, the **Opponens digiti quinti**.

#### The Fourth Layer.

##### Interossei.

The **Interossei** in the foot are similar to those in the hand, with this exception, that they are grouped around the middle line of the *second* digit, instead of that

of the *third*. They are seven in number, and consist of two groups, dorsal and plantar.

The **Interossei dorsales** (*Dorsal interossei*) (Fig. 559), *four* in number, are situated between the metatarsal bones. They are bipenniform muscles, each *arising* by two heads from the adjacent sides of the metatarsal bones between which it is placed; their tendons are *inserted* into the bases of the first phalanges, and into the aponeurosis of the tendons of the Extensor digitorum longus. In the angular interval left between the heads of each of the three lateral muscles, one of the perforating arteries passes to the dorsum of the foot; through the space between the heads of the first muscle the deep plantar branch of the dorsalis pedis artery enters the sole of the foot. The first is *inserted* into the medial side of the second toe; the other three are *inserted* into the lateral sides of the second, third, and fourth toes.




FIG. 559.—The Interossei dorsales. Left foot.



FIG. 560.—The Interossei plantares. Left foot.

The **Interossei plantares** (*Plantar interossei*) (Fig. 560), *three* in number, lie beneath rather than between the metatarsal bones, and each is connected with but one metatarsal bone. They *arise* from the bases and medial sides of the bodies of the third, fourth, and fifth metatarsal bones, and are *inserted* into the medial sides of the bases of the first phalanges of the same toes, and into the aponeuroses of the tendons of the Extensor digitorum longus.

**Nerves.**—The Flexor digitorum brevis, the Flexor hallucis brevis, the Abductor hallucis, and the first Lumbricalis are supplied by the medial plantar nerve; all the other muscles in the sole of the foot by the lateral plantar. The first Interosseous dorsalis frequently receives an extra filament from the medial branch of the deep peroneal nerve on the dorsum of the foot, and the second Interosseous dorsalis a twig from the lateral branch of the same nerve.

**Actions.**—All the muscles of the foot act upon the toes, and may be grouped as abductors, adductors, flexors, or extensors. The *abductors* are the Interossei dorsales, the Abductor hallucis, and the Abductor digiti quinti. The Interossei dorsales are abductors from an imaginary line passing through the axis of the second toe, so that the first muscle draws the second toe medialward, toward the great toe, the second muscle draws the same toe lateralward, and the third and fourth draw the third and fourth toes in the same direction. Like the Interossei in the hand, each assists in flexing the first phalanx and extending the second and third phalanges. The Abductor hallucis abducts the great toe from the second, and also flexes its proximal phalanx.

In the same way the action of the Abductor digiti quinti is twofold, as an abductor of this toe from the fourth, and also as a flexor of its proximal phalanx. The *adductors* are the Interossei plantares and the Adductor hallucis. The Interossei plantares adduct the third, fourth, and fifth toes toward the imaginary line passing through the second toe, and by means of their insertions into the aponeuroses of the Extensor tendons they assist in flexing the proximal phalanges and extending the middle and terminal phalanges. The oblique head of the Adductor hallucis is chiefly concerned in adducting the great toe toward the second one, but also assists in flexing this toe; the transverse head approximates all the toes and thus increases the curve of the transverse arch of the metatarsus. The *flexors* are the Flexor digitorum brevis, the Quadratus plantae, the Flexor hallucis brevis, the Flexor digiti quinti brevis, and the Lumbricales. The Flexor digitorum brevis flexes the second phalanges upon the first, and, continuing its action, flexes the first phalanges also, and brings the toes together. The Quadratus plantae assists the Flexor digitorum longus and converts the oblique pull of the tendons of that muscle into a direct backward pull upon the toes. The Flexor digiti quinti brevis flexes the little toe and draws its metatarsal bone downward and medialward. The Lumbricales, like the corresponding muscles in the hand, assist in flexing the proximal phalanges, and by their insertions into the tendons of the Extensor digitorum longus aid that muscle in straightening the middle and terminal phalanges. The Extensor digitorum brevis extends the first phalanx of the great toe and assists the long Extensor in extending the next three toes, and at the same time gives to the toes a lateral direction when they are extended.




FIG. 561.—Fracture of the neck of the femur within the articular capsule.

**Applied Anatomy.**—The student should now consider the effects produced by the action of the various muscles in fractures of the bones of the lower extremity. The more common forms of fracture are selected for illustration and description.

In fracture of the *neck of the femur inside the articular capsule* (Fig. 561), the characteristic signs are slight shortening of the limb, and eversion of the foot, neither of which may appear until some time after the injury. The eversion is caused by the weight of the limb rotating it outward. The shortening is produced by the contractions of all the muscles about the joint.

In fracture of the *femur just below the trochanters* (Fig. 562), the upper fragment is tilted forward almost at right angles with the pelvis, by the Psoas major and Iliacus; and, at the same time, everted and drawn laterally by the external rotator muscles and Glutaei, causing a marked prominence at the upper and lateral side of the thigh, and much pain from the bruising and laceration of the muscles. The limb is shortened, because the lower fragment is drawn upward by the Rectus femoris in front, and the Biceps femoris, Semimembranosus, and Semitendinosus behind; it is, at the same time, everted. This fracture may be reduced by relaxation of all the muscles involved, to effect which the limb should be put up with the thigh flexed on the pelvis and the leg on the thigh.

Oblique fracture of the femur *immediately above the condyles* (Fig. 563) is a formidable injury, and attended with considerable displacement. On examination of the limb, the lower fragment may be felt deep in the popliteal fossa, being drawn backward by the *Gastrocnemius*, and upward by the *Hamstrings* and *Rectus femoris*. The pointed end of the upper fragment is drawn medialward by the *Pectineus* and *Adductores*, and tilted forward by the *Psoas major* and *Iliacus*, piercing the *Rectus*, and occasionally the integument. Relaxation of these muscles, and direct approximation of the broken fragments, are effected by traction with the limb fully flexed. The greatest care is requisite in keeping the pointed extremity of the upper fragment in proper position; otherwise, after union of the fracture, the power of extension of the limb is partially destroyed, the *Rectus femoris* being held down by the fractured end of the bone.



FIG. 562.—Fracture of the femur below the trochanters.



FIG. 563.—Fracture of the femur above the condyles.

In transverse fracture of the *patella* (Fig. 564) the fragments are separated by the action of the *Quadriceps femoris* and by the effusion which takes place into the joint; the extent of separation of the two fragments depending upon the degree of laceration of the ligamentous structures around the bone.

In oblique fracture of the *body of the tibia* (Fig. 565), if the fracture has taken place obliquely from above, downward and forward, the fragments ride over one another, the lower fragment being drawn backward and upward by the powerful action of the muscles of the calf; the pointed extremity of the upper fragment projects forward immediately beneath the integument, often protruding through it, and rendering the fracture compound. If the direction of the fracture is the reverse of that shown in the figure, the pointed extremity of the lower fragment projects forward, rising up on the lower end of the upper one. By bending the knee, which relaxes the opposing muscles, and making extension from the ankle and counter-extension at the knee, the fragments may be brought into apposition. It is sometimes necessary, however, in compound fracture to remove a portion of the projecting bone with the saw before complete adaptation can be effected.

Fracture of the *fibula with dislocation of the foot lateralward*, commonly known as *Pott's fracture*, is one of the most frequent injuries in the region of the ankle-joint. The fibula is fractured about 7 or 8 cm. above the ankle; in addition to this the medial malleolus is broken off, or the deltoid ligament torn through, and the talus displaced from the corresponding surface of the tibia. The

foot is markedly everted, and the sharp edge of the upper end of the fractured malleolus presses strongly against the skin; at the same time, the heel is drawn up by the muscles of the calf. This injury can generally be reduced by flexing the leg at right angles with the thigh, which relaxes



FIG. 564.—Fracture of the patella.



FIG. 565.—Oblique fracture of the body of the tibia.

all the opposing muscles, and by making extension from the ankle and counter-extension at the knee. There is later a great tendency for the foot to fall backward at the ankle-joint, and constant supervision is required to counteract this.

# ANGIOLOGY.

THE vascular system is divided for descriptive purposes into (a) the **blood vascular system**, which comprises the heart and bloodvessels for the circulation of the blood; and (b) the **lymph vascular system**, consisting of lymph glands and lymphatic vessels, through which a colorless fluid, the **lymph**, circulates. It must be noted, however, that the two systems communicate with each other and are intimately associated developmentally.

The heart is the central organ of the blood vascular system, and consists of a hollow muscle; by its contraction the blood is pumped to all parts of the body through a complicated series of tubes, termed **arteries**. The arteries undergo enormous ramification in their course throughout the body, and end in minute vessels, called **arterioles**, which in their turn open into a close-meshed network of microscopic vessels, termed **capillaries**. After the blood has passed through the capillaries it is collected into a series of larger vessels, called **veins**, by which it is returned to the heart. The passage of the blood through the heart and bloodvessels constitutes what is termed the **circulation of the blood**, of which the following is an outline.<sup>1</sup>

The human heart is divided by septa into right and left halves, and each half is further divided into two cavities, an upper termed the **atrium** and a lower the **ventricle**. The heart therefore consists of four chambers, two, the right atrium and right ventricle, forming the right half, and two, the left atrium and left ventricle the left half. The right half of the heart contains venous or impure blood; the left, arterial or pure blood. The atria are receiving chambers, and the ventricles distributing ones. From the cavity of the left ventricle the pure blood is carried into a large artery, the **aorta**, through the numerous branches of which it is distributed to all parts of the body, with the exception of the lungs. In its passage through the capillaries of the body the blood gives up to the tissues the materials necessary for their growth and nourishment, and at the same time receives from the tissues the waste products resulting from their metabolism. In doing so it is changed from arterial into venous blood, which is collected by the veins and through them returned to the right atrium of the heart. From this cavity the impure blood passes into the right ventricle, and is thence conveyed through the **pulmonary arteries** to the lungs. In the capillaries of the lungs it again becomes arterialized, and is then carried to the left atrium by the **pulmonary veins**. From the left atrium it passes into the left ventricle, from which the cycle once more begins.

The course of the blood from the left ventricle through the body generally to the right side of the heart constitutes the greater or **systemic circulation**, while its passage from the right ventricle through the lungs to the left side of the heart is termed the lesser or **pulmonary circulation**.

It is necessary, however, to state that the blood which circulates through the spleen, pancreas, stomach, small intestine, and the greater part of the large intestine is not returned directly from these organs to the heart, but is conveyed by the **portal vein** to the liver. In the liver this vein divides, like an artery, and ultimately ends in capillary-like vessels (*sinusoids*), from which the rootlets of a series of veins, called the **hepatic veins**, arise; these carry the blood into the inferior vena cava,

<sup>1</sup> The composition of the blood is described on pp. 61 to 64.



whence it is conveyed to the right atrium. From this it will be seen that the blood contained in the portal vein passes through two sets of vessels: (1) the capillaries in the spleen, pancreas, stomach, etc., and (2) the sinusoids in the liver.

Speaking generally, the arteries may be said to contain pure and the veins impure blood. This is true of the systemic, but not of the pulmonary vessels, since it has been seen that the impure blood is conveyed from the heart to the lungs by the pulmonary arteries, and the pure blood returned from the lungs to the heart by the pulmonary veins. Arteries, therefore, must be defined as vessels which convey blood *from* the heart, and veins as vessels which return blood *to* the heart.

**Structure of Arteries** (Fig. 566).—The arteries are composed of three coats: an internal or endothelial coat (*tunica intima* of Kölliker); a middle or muscular coat (*tunica media*); and an external or connective-tissue coat (*tunica adventitia*).

The two inner coats together are very easily separated from the external, as by the ordinary operation of tying a ligature around an artery. If a fine string be tied forcibly upon an artery and then taken off, the external coat will be found undivided, but the two inner coats are divided in the track of the ligature and can easily be further dissected from the outer coat.

The **inner coat** (*tunica intima*) can be separated from the middle by a little maceration, or it may be stripped off in small pieces; but, on account of its friability, it cannot be separated as a complete membrane. It is a fine, transparent, colorless structure which is highly elastic, and, after death, is commonly corrugated into longitudinal wrinkles. The inner coat consists of: (1) A layer of pavement endothelium, the cells of which are polygonal, oval, or fusiform, and have very distinct round or oval nuclei. This endothelium is brought into view most distinctly by staining with nitrate of silver. (2) A subendothelial layer, consisting of delicate connective tissue with branched cells lying in the interspaces of the tissue; in arteries of less than 2 mm. in diameter the subendothelial layer consists of a single stratum of stellate cells, and the connective tissue is only largely developed in vessels of a considerable size. (3) An elastic or fenestrated layer, which consists of a membrane containing a net-work of elastic fibres, having principally a longitudinal direction, and in which, under the microscope, small elongated apertures or perforations may be seen, giving it a fenestrated appearance. It was therefore called by Henle the **fenestrated membrane**. This membrane forms the chief thickness of the inner coat, and can be separated into several layers, some of which present the appearance of a net-work of longitudinal elastic fibres, and others a more membranous character, marked by pale lines having a longitudinal direction. In minute arteries




FIG. 566.—Transverse section through a small artery and vein of the mucous membrane of the epiglottis of a child.  $\times 350$ . (Klein and Noble Smith.) A. Artery, showing the nucleated endothelium, *e*, which lines it; the vessel being contracted, the endothelial cells appear very thick. Underneath the endothelium is the wavy elastic lamina. The chief part of the wall of the vessel is occupied by the circular muscle coat *m*; the rod-shaped nuclei of the muscle cells are well seen. Outside this is *a*, part of the adventitia. This is composed of bundles of connective tissue fibres, shown in section, with the nuclei of the connective tissue corpuscles. The adventitia gradually merges into the surrounding connective tissue. V. Vein showing a thin endothelial membrane, *e*, raised accidentally from the intima, which on account of its delicacy is seen as a mere line on the media *m*. This latter is composed of a few circular unstriated muscle cells *a*. The adventitia, similar in structure to that of an artery.

the fenestrated membrane is a very thin layer; but in the larger arteries, and especially in the aorta, it has a very considerable thickness.

The **middle coat** (*tunica media*) is distinguished from the inner by its color and by the transverse arrangement of its fibres. In the smaller arteries it consists principally of plain muscle fibres in fine bundles, arranged in lamellæ and disposed circularly around the vessel. These lamellæ vary in number according to the size of the vessel; the smallest arteries having only a single layer (Fig. 567), and those slightly larger three or four layers. It is to this coat that the thickness of the wall of the artery is mainly due (Fig. 566A, *m*). In the larger arteries, as the iliac, femoral, and carotid, elastic fibres unite to form lamellæ which alternate with the layers of muscular fibres; these lamellæ are united to one another by elastic fibres which pass between the muscular bundles, and are connected with the fenestrated membrane of the inner coat (Fig. 568). In the largest arteries, as the aorta and innominate, the amount of elastic tissue is very considerable; in these vessels a few bundles of white connective tissue also have been found in

the middle coat. The muscle fibre cells are about  $50\mu$  in length and contain well-marked, rod-shaped nuclei, which are often slightly curved.

The **external coat** (*tunica adventitia*) consists mainly of fine and closely felted bundles of white connective tissue, but also contains elastic fibres in all but the smallest arteries. The elastic tissue is much more abundant next the tunica media, and it is sometimes described as forming here, between the adventitia and media, a special layer, the **tunica elastica externa** of Henle. This layer is most marked in arteries of medium size. In the largest vessels the external coat is relatively thin; but in small arteries it is of greater proportionate thickness. In the smaller arteries it consists of a single layer of white connective tissue and elastic fibres; while in the smallest arteries, just above the capillaries, the elastic fibres are wanting, and the connective tissue of which the coat is composed becomes more nearly homogeneous the nearer it approaches the capillaries, and is gradually reduced to a thin membranous envelope, which finally disappears.

Some arteries have extremely thin walls in proportion to their size; this is especially the case in those situated in the cavity of the cranium and vertebral canal, the difference depending on the thinness of the external and middle coats.

The arteries, in their distribution throughout the body, are included in thin fibro-areolar investments, which form their **sheaths**. The vessel is loosely connected with its sheath by delicate areolar tissue; and the sheath usually encloses the accompanying veins, and sometimes a nerve. Some arteries, as those in the cranium, are not included in sheaths.

All the larger arteries, like the other organs of the body, are supplied with bloodvessels. These




FIG. 567.—Small artery and vein, pia mater of sheep.  $\times 250$ . Surface view above the interrupted line; longitudinal section below. Artery in red; vein in blue.




FIG. 568.—Section of a medium-sized artery. (After Grünstein.)

nutrient vessels, called the **vasa vasorum**, arise from a branch of the artery, or from a neighboring vessel, at some considerable distance from the point at which they are distributed; they

ramify in the loose areolar tissue connecting the artery with its sheath, and are distributed to the external coat, but do not, in man, penetrate the other coats; in some of the larger mammals a few vessels have been traced into the middle coat. Minute veins return the blood from these vessels; they empty themselves into the vein or veins accompanying the artery. Lymphatic vessels are also present in the outer coat.

Arteries are also supplied with nerves, which are derived from the sympathetic, but may pass through the cerebrospinal nerves. They form intricate plexuses upon the surfaces of the larger trunks, and run along the smaller arteries as single filaments, or bundles of filaments which twist around the vessel and unite with each other in a plexiform manner. The branches derived from these plexuses penetrate the external coat and are distributed principally to the muscular tissue of the middle coat, and thus regulate, by causing the contraction and relaxation of this tissue the amount of blood sent to any part.

**The Capillaries.**—The smaller arterial branches (excepting those of the cavernous structure of the sexual organs, of the splenic pulp, and of the placenta) terminate in net-works of vessels which pervade nearly every tissue of the body. These vessels, from their minute size, are termed capillaries. They are interposed between the smallest branches of the arteries and the commencing veins, constituting a net-work, the branches of which maintain the same diameter throughout; the meshes of the net-work are more uniform in shape and size than those formed by the anastomoses of the small arteries and veins.

The *diameters* of the capillaries vary in the different tissues of the body, the usual size being about  $8\mu$ . The smallest are those of the brain and the mucous membrane of the intestines; and the largest those of the skin and the marrow of bone, where they are stated to be as large as  $20\mu$  in diameter. The *form* of the capillary net varies in the different tissues, the meshes being generally rounded or elongated.

The *rounded form of mesh* is most common, and prevails where there is a dense network, as in the lungs, in most glands and mucous membranes, and in the cutis; the meshes are not of an absolutely circular outline, but more or less angular, sometimes nearly quadrangular, or polygonal, or more often irregular.

*Elongated meshes* are observed in the muscles and nerves, the meshes resembling parallelograms in form, the long axis of the mesh running parallel with the long axis of the nerve or muscle. Sometimes the capillaries have a *looped arrangement*; a single vessel projecting from the common net-work and returning after forming one or more loops, as in the papillæ of the tongue and skin.

The number of the capillaries and the size of the meshes determine the degree of vascularity of a part. The closest network and the smallest interspaces are found in the lungs and in the choroid coat of the eye. In these situations the interspaces are smaller than the capillary vessels themselves. In the intertubular plexus of the kidney, in the conjunctiva, and in the cutis, the interspaces are from three to four times as large as the capillaries which form them; and in the brain from eight to ten times as large as the capillaries in their long diameters, and from four to six times as large in their transverse diameters. In the adventitia of arteries the width of the meshes is ten times that of the capillary vessels. As a general rule, the more active the function of the organ, the closer is its capillary net and the larger its supply of blood; the meshes of the network are very narrow in all growing parts, in the glands, and in the mucous membranes, wider in bones and ligaments which are comparatively inactive; bloodvessels are nearly altogether absent in tendons, in which very little organic change occurs after their formation. In the liver the capillaries take a more or less radial course toward the intralobular vein, and their walls are incomplete, so that the blood comes into direct contact with the liver cells. These vessels in the liver are not true capillaries but "sinusoids;" they are developed by the growth of columns of liver cells into the blood spaces of the embryonic organ.

**Structure.**—The wall of a capillary consists of a fine transparent endothelial layer, composed of cells joined edge to edge by an interstitial cement substance, and continuous with the endothelial cells which line the arteries and veins. When stained with nitrate of silver the edges which bound the epithelial cells are brought into view (Fig. 569). These cells are of large size and of an irregular polygonal or lanceolate shape, each containing an oval nucleus which may be displayed by carmine or hematoxylin. Between their edges, at various points of their meeting, roundish dark spots are sometimes seen, which have been described as stomata, though they are closed by intercellular substance. They have been believed to be the situations through which the colorless corpuscles of the blood, when migrating from the bloodvessels, emerge; but this view, though probable, is not universally accepted.

Kolossow describes these cells as having a rather more complex structure. He states that each consists of two parts: of hyaline ground plates, and of a protoplasmic granular part, in which is imbedded the nucleus, on the outside of the ground plates. The hyaline internal coat of the capillaries does not form a complete membrane, but consists of "plates" which are inelastic, and though in contact with each other are not continuous; when therefore the capillaries are subjected to intravascular pressure, the plates become separated from each other; the protoplasmic portions of the cells, on the other hand, are united together. In some organs, *e. g.*, the glomeruli

of the kidneys, intercellular cement cannot be demonstrated in the capillary wall and the cells are believed to form a syncytium.

In many situations a delicate sheath or envelope of branched nucleated connective tissue cells is found around the simple capillary tube, particularly in the larger ones; and in other places, especially in the glands, the capillaries are invested with retiform connective tissue.

**Sinusoids.**—In certain organs, viz., the heart, the liver, the suprarenal and parathyroid glands, the glomus caroticum and glomus coccygeum, the smallest bloodvessels present various differences from true capillaries. They are wider, with an irregular lumen, and have no connective tissue covering, their endothelial cells being in direct contact with the cells of the organ. Moreover, they are either arterial or venous and not intermediate as are the true capillaries. These vessels have been called *sinusoids* by Minot. They are formed by columns of cells or trabeculae pushing their way into a large bloodvessel or blood space and carrying its endothelium before them; at the same time the wall of the vessel or space grows out between the cell columns.

**Structure of Veins.**—The veins, like the arteries, are composed of three coats: internal, middle, and external; and these coats are, with the necessary modifications, analogous to the coats of the arteries; the internal being the endothelial, the middle the muscular, and the external the connective tissue or areolar (Fig. 570). The main difference between the veins and the arteries is in the comparative weakness of the middle coat in the former.

In the smallest veins the three coats are hardly to be distinguished (Fig. 567). The endothelium is supported on a membrane separable into two layers, the outer of which is the thicker, and consists of a delicate, nucleated membrane (*adventitia*), while the inner is composed of a network of longitudinal elastic fibres (*media*). In the veins next above these in size (0.4 mm. in diameter), according to Kölliker, a connective tissue layer containing numerous muscle fibres circularly disposed can be traced, forming the

middle coat, while the elastic and connective tissue elements of the outer coat become more distinctly perceptible. In the middle-sized veins the typical structure of these vessels becomes clear. The endothelium is of the same character as in the arteries, but its cells are more oval and less fusiform. It is supported by a connective tissue layer, consisting of a delicate net-work of branched cells, and external to this is a layer of elastic fibres disposed in the form of a net-work in place of the definite fenestrated membrane seen in the arteries. This constitutes the **internal coat**. The **middle coat** is composed of a thick layer of connective tissue with elastic fibres, intermixed, in some veins, with a transverse layer of muscular tissue. The white fibrous element is in considerable excess, and the elastic fibres are in much smaller proportion in the veins than in the arteries. The **outer coat** consists, as in the arteries, of areolar tissue, with longitudinal elastic fibres. In the largest veins the outer coat is from two to five times thicker than the middle coat, and contains a large number of longitudinal muscular fibres. These are most distinct in the inferior vena cava, especially at the termination of this vein in the heart, in the trunks of the hepatic veins, in all the large trunks of the portal vein, and in the external iliac, renal, and azygos veins. In the renal and portal veins they extend through the whole thickness of the outer coat, but in the other veins mentioned a layer of connective and elastic tissue is found external to the muscular fibres. All the large veins which open into the heart are covered for a short distance with a layer of striped muscular tissue continued on to them from the heart. Muscular tissue is wanting: (1) in the veins of the maternal part of the placenta; (2) in the venous sinuses of the dura mater and the veins of the pia mater of the brain and medulla spinalis; (3) in the veins of the retina; (4) in the veins of the cancellous tissue of bones; (5) in the venous spaces of the corpora cavernosa. The veins of the above-mentioned parts consist of an internal endothelial lining supported on one or more layers of areolar tissue.

Most veins are provided with valves which serve to prevent the reflux of the blood. Each valve is formed by a reduplication of the inner coat, strengthened by connective tissue and elastic fibres, and is covered on both surfaces with endothelium, the arrangement of which differs on the two surfaces. On the surface of the valve next the wall of the vein the cells are arranged transversely; while on the other surface, over which the current of blood flows, the cells are arranged longitudinally in the direction of the current. Most commonly two such valves are found placed opposite one another, more especially in the smaller veins or in the larger trunks at the point where they are joined by smaller branches; occasionally there are three and some-




FIG. 569.—Capillaries from the mesentery of a guinea-pig, after treatment with solution of nitrate of silver. a. Cells. b. Their nuclei.



times only one. The valves are semilunar. They are attached by their convex edges to the wall of the vein; the concave margins are free, directed in the course of the venous current, and lie in close apposition with the wall of the vein as long as the current of blood takes its natural course; if, however, any regurgitation takes place, the valves become distended, their opposed edges are brought into contact, and the current is interrupted. The wall of the vein on the cardiac side of the point of attachment of each valve is expanded into a pouch or sinus, which gives to the vessel, when injected or distended with blood, a knotted appearance. The valves are very numerous in the veins of the extremities, especially of the lower extremities, these vessels




FIG. 570.—Section of a medium-sized vein.

having to conduct the blood against the force of gravity. They are absent in the very small veins, *i. e.*, those less than 2 mm. in diameter, also in the venæ cavæ, hepatic, renal, uterine, and ovarian veins. A few valves are found in each spermatic vein, and one also at its point of junction with the renal vein or inferior vena cava respectively. The cerebral and spinal veins, the veins of the cancellated tissue of bone, the pulmonary veins, and the umbilical vein and its branches, are also destitute of valves. A few valves are occasionally found in the azygos and intercostal veins. Rudimentary valves are found in the tributaries of the portal venous system.

The veins, like the arteries, are supplied with nutrient vessels, **vasa vasorum**. Nerves also are distributed to them in the same manner as to the arteries, but in much less abundance.

### THE THORACIC CAVITY.

The heart and lungs are situated in the thorax, the walls of which afford them protection. The heart lies between the two lungs, and is enclosed within a fibrous bag, the **pericardium**, while each lung is invested by a serous membrane, the **pleura**. The skeleton of the thorax, and the shape and boundaries of the cavity, have already been described (page 216).

**The Cavity of the Thorax.**—The capacity of the cavity of the thorax does not correspond with its apparent size externally, because (1) the space enclosed by the lower ribs is occupied by some of the abdominal viscera; and (2) the cavity

extends above the anterior parts of the first ribs into the neck. The size of the thoracic cavity is constantly varying during life with the movements of the ribs and Diaphragma, and with the degree of distention of the abdominal viscera. From the collapsed state of the lungs as seen when the thorax is opened in the dead body, it would appear as if the viscera only partly filled the cavity, but during life there is no vacant space, that which is seen after death being filled up by the expanded lungs.

**The Upper Opening of the Thorax.**—The parts which pass through the upper opening of the thorax are, from before backward, in or near the middle line, the Sternohyoideus and Sternothyroideus muscles, the remains of the thymus, the inferior thyroid veins, the trachea, œsophagus, thoracic duct, and the Longus colli muscles; at the sides, the innominate artery, the left common carotid, left subclavian and internal mammary arteries and the costocervical trunks, the innominate veins, the vagus, cardiac, phrenic, and sympathetic nerves, the greater parts of the anterior divisions of the first thoracic nerves, and the recurrent nerve of the left side. The apex of each lung, covered by the pleura, also projects through this aperture, a little above the level of the sternal end of the first rib.

**The Lower Opening of the Thorax.**—The lower opening of the thorax is wider transversely than from before backward. It slopes obliquely downward and backward, so that the thoracic cavity is much deeper behind than in front. The Diaphragma (see page 493) closes the opening and forms the floor of the thorax. The floor is flatter at the centre than at the sides, and higher on the right side than on the left; in the dead body the right side reaches the level of the upper border of the fifth costal cartilage, while the left extends only to the corresponding part of the sixth costal cartilage. From the highest point on each side the floor slopes suddenly downward to the costal and vertebral attachments of the Diaphragma; this slope is more marked behind than in front, so that only a narrow space is left between the Diaphragma and the posterior wall of the thorax.

## THE PERICARDIUM.

The pericardium (Fig. 571) is a conical fibro-serous sac, in which the heart and the roots of the great vessels are contained. It is placed behind the sternum and the cartilages of the third, fourth, fifth, sixth, and seventh ribs of the left side, in the mediastinal cavity.

In front, it is separated from the anterior wall of the thorax, in the greater part of its extent, by the lungs and pleuræ; but a small area, somewhat variable in size, and usually corresponding with the left half of the lower portion of the body of the sternum and the medial ends of the cartilages of the fourth and fifth ribs of the left side, comes into direct relationship with the chest wall. The lower extremity of the thymus, in the child, is in contact with the front of the upper part of the pericardium. Behind, it rests upon the bronchi, the œsophagus, the descending thoracic aorta, and the posterior part of the mediastinal surface of each lung. Laterally, it is covered by the pleuræ, and is in relation with the mediastinal surfaces of the lungs; the phrenic nerve, with its accompanying vessels, descends between the pericardium and pleura on either side.

**Structure of the Pericardium.**—Although the pericardium is usually described as a single sac, an examination of its structure shows that it consists essentially of two sacs intimately connected with one another, but totally different in structure. The outer sac, known as the **fibrous pericardium**, consists of fibrous tissue. The inner sac, or **serous pericardium**, is a delicate membrane which lies within the fibrous sac and lines its walls; it is composed of a single layer of flattened cells resting on loose connective tissue. The heart invaginates the wall of the serous sac from above and behind, and practically obliterates its cavity, the space being a potential one, except in front, where a small interspace exists below the apex of the heart.



The **fibrous pericardium** forms a flask-shaped bag, the neck of which is closed by its fusion with the external coats of the great vessels, while its base is attached to the central tendon and to the muscular fibres of the left side of the Diaphragm. In some of the lower mammals the base is either completely separated from the Diaphragm or joined to it by some loose areolar tissue; in man much of its diaphragmatic attachment consists of loose fibrous tissue which can be readily broken down, but over a small area the central tendon of the Diaphragm and the pericardium are completely fused. Above, the fibrous pericardium not only blends with the external coats of the great vessels, but is continuous with the pretracheal layer of the deep cervical fascia. By means of these upper and lower connections it is securely anchored within the thoracic cavity. It is also attached to the posterior surface of the sternum by the **superior and inferior sternopericardiac ligaments**; the upper passing to the manubrium, and the lower to the xiphoid process. On either side of the ascending aorta it sends upward a diverticulum; that on the left




FIG. 571.—Posterior wall of the pericardial sac, showing the lines of reflection of the serous pericardium on the great vessels.

side, somewhat conical in shape, passes between the arch of the aorta and the pulmonary artery, toward the ligamentum arteriosum, where it ends in a cecal extremity which is attached by loose connective tissue to the ligament; that on the right side passes between the ascending aorta and superior vena cava, and also ends in a blind extremity.

The vessels receiving fibrous prolongations from this membrane are: the aorta, the superior vena cava, the right and left pulmonary arteries, and the four pulmonary veins. The inferior vena cava enters the pericardium through the central tendon of the Diaphragm, and receives no covering from the fibrous layer.

The **serous pericardium** is, as already stated, a closed sac which lines the fibrous pericardium and is invaginated by the heart; it therefore consists of a **visceral** and a **parietal portion**. The visceral portion, or **epicardium**, covers the heart and the great vessels, and from the latter is continuous with the parietal layer which lines the fibrous pericardium. The portion which covers the vessels is arranged in the form of two tubes. The aorta and pulmonary artery are enclosed in one tube, the **arterial mesocardium**. The superior and inferior venæ cavæ and the four pulmonary veins are enclosed in a second tube, the **venous mesocardium**, the attachment of which to the parietal layer presents the shape of an inverted U. The *cul-de-sac* enclosed between the limbs of the  $\cap$  lies behind the left atrium and is known as the **oblique sinus**, while the passage between the venous and arterial mesocardia—i. e., between the aorta and pulmonary artery in front and the atria behind—is termed the **transverse sinus**.

**The Ligament of the Left Vena Cava.**—Between the left pulmonary artery and subjacent pulmonary vein is a triangular fold of the serous pericardium; it is known as the **ligament of the left vena cava** (*vestigial fold of Marshall*). It is formed by the duplicature of the serous layer over the remnant of the lower part of the left superior vena cava (*duct of Cuvier*), which becomes obliterated during fetal life, and remains as a fibrous band stretching from the highest left intercostal vein to the left atrium, where it is continuous with a small vein, the **vein of the left atrium** (*oblique vein of Marshall*), which opens into the coronary sinus.

The **arteries** of the pericardium are derived from the internal mammary and its musculophrenic branch, and from the descending thoracic aorta.

The **nerves** of the pericardium are derived from the vagus and phrenic nerves, and the sympathetic trunks.

**Applied Anatomy.**—Effusion of fluid into the pericardial sac often occurs in acute rheumatism or pneumonia, or in patients with chronic vascular and renal disease, embarrassing the heart's action and giving rise to signs of cardiac distress, such as pallor, a rapid and feeble pulse, dyspnoea, and restlessness. On examination, the apical cardiac impulse is absent, or replaced by a more extensive indefinite and wavering pulsation; it may appear to be in the second, third, or fourth left space, and is then not an apex impulse, as Potain has stated, but due to the impact of some portion of the heart wall nearer its base. In children the precordial intercostal spaces may bulge outward. The most striking sign, however, is the great increase in all directions of the precordial dulness on percussion. This becomes pear-shaped, the stalk of the pear reaching up to about the left sternoclavicular articulation; the dulness also extends some distance to the right of the sternum, particularly in the fifth interspace (Rotch). The fluid collects mainly on either side of the heart, and below it, especially on the left side, where the Diaphragma can yield more readily to pressure than it can on the right. Ewart has drawn attention to the presence of a square patch of dulness over the base of the left lung behind, reaching up to the level of the ninth or tenth rib, and extending laterally as far as the inferior angle of the scapula; the underlying lung tissue gives the physical signs of compression or collapse.

Paracentesis of the pericardium is often required to relieve the urgent cardiac or respiratory distress in these cases, and should be performed without hesitation and before the patient is in *extremis*. It may also be required when the pericardium is filled with blood or pus, and as it is advisable to perform this operation without transfixing the pleura, the puncture should be made either in the fifth or sixth intercostal space on the left side and close to the sternum, so as to avoid wounding the internal mammary artery, which descends about 1.25 cm. from the sternal margin; or the needle may be entered at the left costoxiphoid angle and made to pass upward and backward behind the lower end of the body of the sternum into the pericardial sac. Curschmann,<sup>1</sup> however, argues that the heart itself necessarily lies almost in contact with the anterior wall of the thorax even in cases of the largest pericardial effusion, so that there is risk of piercing it if the puncture is made in the fourth or fifth left intercostal space within even so much as 5 to 8 cm. of the sternal margin. He therefore advises that in moderately large pericardial effusions the trocar should be inserted in the left mamillary line, or lateral to it if the effusion is very large, in the fifth or sixth interspace. In consequence of the uncertain and varying position of the anterior reflexion of the pleura, transfixion of the pleural sac cannot always be avoided. *Pericardiectomy* is required when the effusion is of a purulent nature. In this operation a portion of the fifth or sixth costal cartilage is excised. An incision is made along the left border of the sternum from the upper border of the fourth cartilage to the seventh. The fifth costal cartilage is now separated from the sternum by means of a gouge, great care being taken not to let the instrument slip and penetrate too deeply. The cartilage is then seized with lion forceps and raised, the tissues beneath it being peeled off, so as to avoid wounding the internal mammary artery or the pleura. The Transversus thoracis is now scratched through, with a director or the nail of the index finger, close to the sternum, and the pericardium felt for and opened, the finger guarding the pleura and left internal mammary artery.

<sup>1</sup> Therapie der Gegenwart, 1905.

**THE HEART (COR).**

The **heart** is a hollow muscular organ of a somewhat conical form; it lies between the lungs in the middle mediastinum and is enclosed in the pericardium (Fig. 572). It is placed obliquely in the chest behind the body of the sternum and adjoining parts of the rib cartilages, and projects farther into the left than into the right half of the thoracic cavity, so that about one-third of it is situated on the right and two-thirds on the left of the median plane.

**Size.**—The heart, in the adult, measures about 12 cm. in length, 8 to 9 cm. in breadth at the broadest part, and 6 cm. in thickness. Its weight, in the male, varies from 280 to 340 grams; in the female, from 230 to 280 grams. The heart continues to increase in weight and size up to an advanced period of life; this increase is more marked in men than in women.




FIG. 572.—Front view of heart and lungs.

**Component Parts.**—As has already been stated (page 595), the heart is subdivided by septa into right and left halves, and a constriction subdivides each half of the organ into two cavities, the upper cavity being called the **atrium**, the lower the **ventricle**. The heart therefore consists of four chambers, viz., right and left atria, and right and left ventricles.

The division of the heart into four cavities is indicated on its surface by grooves. The atria are separated from the ventricles by the **coronary sulcus** (*auriculo-ventricular groove*); this contains the trunks of the nutrient vessels of the heart, and is deficient in front, where it is crossed by the root of the pulmonary artery. The **interatrial groove**, separating the two atria, is scarcely marked on the posterior

surface, while anteriorly it is hidden by the pulmonary artery and aorta. The ventricles are separated by two grooves, one of which, the **anterior longitudinal sulcus**, is situated on the sternocostal surface of the heart, close to its left margin, the other **posterior longitudinal sulcus**, on the diaphragmatic surface near the right margin; these grooves extend from the base of the ventricular portion to a notch, the **incisura apicis cordis**, on the acute margin of the heart just to the right of the apex.

The **base** (*basis cordis*) (Fig. 573), directed upward, backward, and to the right, is separated from the fifth, sixth, seventh, and eighth thoracic vertebræ by the œsophagus, aorta, and thoracic duct. It is formed mainly by the left atrium, and, to a small extent, by the back part of the right atrium. Somewhat quadrilateral in form, it is in relation above with the bifurcation of the pulmonary artery,




FIG. 573.—Base and diaphragmatic surface of heart.

and is bounded below by the posterior part of the coronary sulcus, containing the coronary sinus. On the right it is limited by the sulcus terminalis of the right atrium, and on the left by the ligament of the left vena cava and the oblique vein of the left atrium. The four pulmonary veins, two on either side, open into the left atrium, while the superior vena cava opens into the upper, and the anterior vena cava into the lower, part of the right atrium.

**The Apex** (*apex cordis*).—The apex is directed downward, forward, and to the left, and is overlapped by the left lung and pleura: it lies behind the fifth left intercostal space, 8 to 9 cm. from the mid-sternal line, or about 4 cm. below and 2 mm. to the medial side of the left mammary papilla.

The **sternocostal surface** (Fig. 574) is directed forward, upward, and to the left. Its lower part is convex, formed chiefly by the right ventricle, and traversed near its left margin by the anterior longitudinal sulcus. Its upper part is separated from



**THE HEART (COR).**

The **heart** is a hollow muscular organ of a somewhat conical form; it lies between the lungs in the middle mediastinum and is enclosed in the pericardium (Fig. 572). It is placed obliquely in the chest behind the body of the sternum and adjoining parts of the rib cartilages, and projects farther into the left than into the right half of the thoracic cavity, so that about one-third of it is situated on the right and two-thirds on the left of the median plane.

**Size.**—The heart, in the adult, measures about 12 cm. in length, 8 to 9 cm. in breadth at the broadest part, and 6 cm. in thickness. Its weight, in the male, varies from 280 to 340 grams; in the female, from 230 to 280 grams. The heart continues to increase in weight and size up to an advanced period of life; this increase is more marked in men than in women.




FIG. 572.—Front view of heart and lungs.

**Component Parts.**—As has already been stated (page 595), the heart is subdivided by septa into right and left halves, and a constriction subdivides each half of the organ into two cavities, the upper cavity being called the **atrium**, the lower the **ventricle**. The heart therefore consists of four chambers, viz., right and left atria, and right and left ventricles.

The division of the heart into four cavities is indicated on its surface by grooves. The atria are separated from the ventricles by the **coronary sulcus** (*auriculo-ventricular groove*); this contains the trunks of the nutrient vessels of the heart, and is deficient in front, where it is crossed by the root of the pulmonary artery. The **interatrial groove**, separating the two atria, is scarcely marked on the posterior

surface, while anteriorly it is hidden by the pulmonary artery and aorta. The ventricles are separated by two grooves, one of which, the **anterior longitudinal sulcus**, is situated on the sternocostal surface of the heart, close to its left margin, the other **posterior longitudinal sulcus**, on the diaphragmatic surface near the right margin; these grooves extend from the base of the ventricular portion to a notch, the **incisura apicis cordis**, on the acute margin of the heart just to the right of the apex.

The **base** (*basis cordis*) (Fig. 573), directed upward, backward, and to the right, is separated from the fifth, sixth, seventh, and eighth thoracic vertebræ by the oesophagus, aorta, and thoracic duct. It is formed mainly by the left atrium, and, to a small extent, by the back part of the right atrium. Somewhat quadrilateral in form, it is in relation above with the bifurcation of the pulmonary artery,




FIG. 573.—Base and diaphragmatic surface of heart.

and is bounded below by the posterior part of the coronary sulcus, containing the coronary sinus. On the right it is limited by the sulcus terminalis of the right atrium, and on the left by the ligament of the left vena cava and the oblique vein of the left atrium. The four pulmonary veins, two on either side, open into the left atrium, while the superior vena cava opens into the upper, and the anterior vena cava into the lower, part of the right atrium.

**The Apex** (*apex cordis*).—The apex is directed downward, forward, and to the left, and is overlapped by the left lung and pleura: it lies behind the fifth left intercostal space, 8 to 9 cm. from the mid-sternal line, or about 4 cm. below and 2 mm. to the medial side of the left mammary papilla.

The **sternocostal surface** (Fig. 574) is directed forward, upward, and to the left. Its lower part is convex, formed chiefly by the right ventricle, and traversed near its left margin by the anterior longitudinal sulcus. Its upper part is separated from



the lower by the coronary sulcus, and is formed by the atria; it presents a deep concavity (Fig. 576), occupied by the ascending aorta and the pulmonary artery.

The **diaphragmatic surface** (Fig. 573), directed downward and slightly backward, is formed by the ventricles, and rests upon the central tendon and a small part of the left muscular portion of the Diaphragma. It is separated from the base by the posterior part of the coronary sulcus, and is traversed obliquely by the posterior longitudinal sulcus.

The **right margin** of the heart is long, and is formed by the right atrium above and the right ventricle below. The atrial portion is rounded and almost vertical; it is situated behind the third, fourth, and fifth right costal cartilages about 1.25 cm. from the margin of the sternum. The ventricular portion, thin and sharp, is named the **acute margin**; it is nearly horizontal, and extends from the sternal end of the sixth right costal cartilage to the apex of the heart.

The **left or obtuse margin** is shorter, full, and rounded: it is formed mainly by the left ventricle, but to a slight extent, above, by the left atrium. It extends from a point in the second left intercostal space, about 2.5 mm. from the sternal margin, obliquely downward, with a convexity to the left, to the apex of the heart.




FIG. 574.—Sternocostal surface of heart.

**Right Atrium** (*atrium dextrum*; *right auricle*).—The right atrium is larger than the left, but its walls are somewhat thinner, measuring about 2 mm.; its cavity is capable of containing about 57 c.c. It consists of two parts: a principal cavity, or **sinus venarum**, situated posteriorly, and an anterior, smaller portion, the **auricle**.

**Sinus Venarum** (*sinus venosus*).—The sinus venarum is the large quadrangular cavity placed between the two venæ cavæ. Its walls, which are extremely thin, are connected below with the right ventricle, and medially with the left atrium, but are free in the rest of their extent.

**Auricle** (*auricula dextra*; *right auricular appendix*).—The auricle is a small conical muscular pouch, the margins of which present a dentated edge. It projects from the upper and front part of the sinus forward and toward the left side, overlapping the root of the aorta.

The separation of the auricle from the sinus venarum is indicated externally by a groove, the **terminal sulcus**, which extends from the front of the superior vena cava to the front of the inferior vena cava, and represents the line of union of the sinus venosus of the embryo with the primitive atrium. On the inner wall of the atrium the separation is marked by a vertical, smooth, muscular ridge, the **terminal crest**. Behind the crest the internal surface of the atrium is smooth, while in front of it the muscular fibres of the wall are raised into parallel ridges resembling the teeth of a comb, and hence named the **musculi pectinati**.

**Dissection.**—To examine the interior of the auricle, an incision should be made along its right border from the entrance of the superior vena cava to that of the inferior vena cava. A second cut is to be made from the centre of the first incision to the tip of the auricle dextra, and the flap raised.




FIG. 575.—Interior of right side of heart.

Its interior (Fig. 575) presents the following parts for examination:

Openings	{	Superior vena cava.	Valves	{	Valve of the inferior vena cava.
		Inferior vena cava.			Valve of the coronary sinus.
		Coronary sinus.			
		Foramina venarum minimarum.			
		Atrioventricular.			
		Fossa ovalis.			
		Limbus fossae ovalis.			
		Intervenous tubercle.			
		Musculi pectinati.			
		Crista terminalis.			

The **superior vena cava** returns the blood from the upper half of the body, and opens into the upper and back part of the atrium, the direction of its orifice being downward and forward. Its opening has no valve.

The **inferior vena cava**, larger than the superior, returns the blood from the lower half of the body, and opens into the lowest part of the atrium, near the atrial septum, its orifice being directed upward and backward, and guarded by

a rudimentary valve, the **valve of the inferior vena cava** (*Eustachian valve*). The blood entering the atrium through the superior vena cava is directed downward and forward, *i. e.*, toward the atrioventricular orifice, while that entering through the inferior vena cava is directed upward and backward, toward the atrial septum. This is the normal direction of the two currents in fetal life.

The **coronary sinus** opens into the atrium, between the orifice of the inferior vena cava and the atrioventricular opening. It returns blood from the substance of the heart and is protected by a semicircular valve, the **valve of the coronary sinus** (*valve of Thebesius*).

The **foramina venarum minimarum** (*foramina Thebesii*) are the orifices of minute veins (*venae cordis minimae*), which return blood directly from the muscular substance of the heart.

The **atrioventricular opening** (*tricuspid orifice*) is the large oval aperture of communication between the atrium and the ventricle; it will be described with the right ventricle.

The **valve of the inferior vena cava** (*valvula venae cavae inferioris* [*Eustachii*]; *Eustachian valve*) is situated in front of the orifice of the inferior vena cava. It is semilunar in form, its convex margin being attached to the anterior margin of the orifice; its concave margin, which is free, ends in two cornua, of which the left is continuous with the anterior edge of the limbus fossae ovalis while the right is lost on the wall of the atrium. The valve is formed by a duplicature of the lining membrane of the atrium, containing a few muscular fibres. *In the fetus* this valve is of large size, and serves to direct the blood from the inferior vena cava, through the foramen ovale, into the left atrium. *In the adult* it occasionally persists, and may assist in preventing the reflux of blood into the inferior vena cava; more commonly it is small, and may present a cribriform or filamentous appearance; sometimes it is altogether wanting.

The **valve of the coronary sinus** (*valvula sinus coronarii* [*Thebesii*]; *Thebesian valve*) is a semicircular fold of the lining membrane of the atrium, at the orifice of the coronary sinus. It prevents the regurgitation of blood into the sinus during the contraction of the atrium. This valve may be double or it may be cribriform.

The **fossa ovalis** is an oval depression on the septal wall of the atrium, and corresponds to the situation of the foramen ovale in the fetus. It is situated at the lower part of the septum, above and to the left of the orifice of the inferior vena cava.

The **limbus fossae ovalis** (*annulus ovalis*) is the prominent oval margin of the fossa ovalis. It is most distinct above and at the sides of the fossa; below, it is deficient. A small slit-like valvular opening is occasionally found, at the upper margin of the fossa, leading upward beneath the limbus, into the left atrium; it is the remains of the fetal aperture between the two atria.

The **intervenous tubercle** (*tuberculum intervenosum*; *tubercle of Lower*) is a small projection on the posterior wall of the atrium, above the fossa ovalis. It is distinct in the hearts of quadrupeds, but in man is scarcely visible. It was supposed by Lower to direct the blood from the superior vena cava toward the atrioventricular opening.

**Right Ventricle** (*ventriculus dexter*).—The right ventricle is triangular in form, and extends from the right atrium to near the apex of the heart. Its antero-superior surface is rounded and convex, and forms the larger part of the sternocostal surface of the heart. Its under surface is flattened, rests upon the Diaphragma, and forms a small part of the diaphragmatic surface of the heart. Its posterior wall is formed by the ventricular septum, which bulges into the right ventricle, so that a transverse section of the cavity presents a semilunar outline. Its upper and left angle forms a conical pouch, the **conus arteriosus**, from which the pulmonary artery arises. A tendinous band, which may be named the *tendon of the conus arteriosus*, extends upward from the right atrioventricular fibrous

ring and connects the posterior surface of the conus arteriosus to the aorta. The wall of the right ventricle is thinner than that of the left, the proportion between them being as 1 to 3; it is thickest at the base, and gradually becomes thinner toward the apex. The cavity equals in size that of the left ventricle, and is capable of containing about 85 c.c.

**Dissection.**—To examine the interior of the right ventricle, its anterior wall should be turned downward and to the right in the form of a triangular flap. This is accomplished by making two incisions: (1) From the pulmonary artery to the apex of the ventricle parallel to, but a little to the right of, the anterior interatrial groove; (2) another, starting from the upper extremity, of the first and carried outward parallel to, but a little below, the atrioventricular groove, care being taken not to injure the atrioventricular opening.

Its interior (Fig. 575) presents the following parts for examination:

Openings { Right atrioventricular.  
Pulmonary artery.  
Trabeculae carneae.

Valves { Tricuspid.  
Pulmonary.  
Chordae tendineae.

The **right atrioventricular orifice** is the large oval aperture of communication between the right atrium and ventricle. Situated at the base of the ventricle, it measures about 4 cm. in diameter and is surrounded by a fibrous ring, covered by the lining membrane of the heart; it is considerably larger than the corresponding aperture on the left side, being sufficient to admit the ends of four fingers. It is guarded by the tricuspid valve.




FIG. 576.—Heart seen from above.



FIG. 577.—Base of ventricles exposed by removal of the atria.

The opening of the pulmonary artery is circular in form, and situated at the summit of the conus arteriosus, close to the ventricular septum. It is placed above and to the left of the atrioventricular opening, and is guarded by the pulmonary semilunar valves.

The **tricuspid valve** (*valvula tricuspidalis*) (Figs. 575, 577) consists of three somewhat triangular cusps or segments. The largest cusp is interposed between the atrioventricular orifice and the conus arteriosus and is termed the **anterior** or **infundibular cusp**. A second, the **posterior** or **marginal cusp**, is in relation to the right margin of the ventricle, and a third, the **medial** or **septal cusp**, to the ventricular septum. They are formed by duplicatures of the lining membrane of the heart, strengthened



by intervening layers of fibrous tissue: their central parts are thick and strong, their marginal portions thin and translucent, and in the angles between the latter small intermediate segments are sometimes seen. Their bases are attached to a fibrous ring surrounding the atrioventricular orifice and are also joined to each other so as to form a continuous annular membrane, while their apices project into the ventricular cavity. Their atrial surfaces, directed toward the blood current from the atrium, are smooth; their ventricular surfaces, directed toward the wall of the ventricle, are rough and irregular, and, together with the apices and margins of the cusps, give attachment to a number of delicate tendinous cords, the **chordae tendineae**.

The **trabeculae carneae** (*columnae carneae*) are rounded or irregular muscular columns which project from the whole of the inner surface of the ventricle, with the exception of the conus arteriosus. They are of three kinds: some are attached along their entire length on one side and merely form prominent ridges, others are fixed at their extremities but free in the middle, while a third set (*musculi papillares*) are continuous by their bases with the wall of the ventricle, while their apices give origin to the chordae tendineae which pass to be attached to the segments of the tricuspid valve. There are two papillary muscles, anterior and posterior: of these, the anterior is the larger, and its chordae tendineae are connected with the anterior and posterior cusps of the valve: the posterior papillary muscle sometimes consists of two or three parts; its chordae tendineae are connected with the posterior and medial cusps. In addition to these, some chordae tendineae spring directly from the ventricular septum, or from small papillary eminences on it, and pass to the anterior and medial cusps. A muscular band, well-marked in sheep and some other animals, frequently extends from the base of the anterior papillary muscle to the ventricular septum. From its attachments it may assist in preventing overdistension of the ventricle, and so has been named the **moderator band**.

The **pulmonary semilunar valves** (Fig. 576) are three in number, two in front and one behind, formed by duplicatures of the lining membrane, strengthened by fibrous tissue. They are attached, by their convex margins, to the wall of the artery, at its junction with the ventricle, their free borders being directed upward into the lumen of the vessel. The free and attached margins of each are strengthened by tendinous fibres, and the former presents, at its middle, a thickened nodule (*corpus Arantii*). From this nodule tendinous fibres radiate through the segment to its attached margin, but are absent from two narrow crescentic portions, the **lunulae**, placed one on either side of the nodule immediately adjoining the free margin. Between the semilunar valves and the wall of the pulmonary artery are three **pouches or sinuses** (*sinuses of Valsalva*).

**Dissection.**—In order to examine the interior of the left atrium, make an incision on the posterior surface of the atrium from the pulmonary veins on one side to those on the other, the incision being carried a little way into the vessels. Make another incision from the middle of the horizontal one to the auricula sinistra.

**Left Atrium** (*atrium sinistum; left auricle*).—The left atrium is rather smaller than the right, but its walls are thicker, measuring about 3 mm.; it consists, like the right, of two parts, a **principal cavity** and an **auricula**.

The **principal cavity** is cuboidal in form, and concealed, in front, by the pulmonary artery and aorta; in front and to the right it is separated from the right atrium by the atrial septum; opening into it on either side are the two pulmonary veins.

**Auricula** (*auricula sinistra; left auricular appendix*).—The auricula is somewhat constricted at its junction with the principal cavity; it is longer, narrower, and more curved than that of the right side, and its margins are more deeply indented. It is directed forward and toward the right and overlaps the root of the pulmonary artery.

The interior of the left atrium (Fig. 578) presents the following parts for examination:

Openings of the four pulmonary veins.  
Left atrioventricular opening.  
Musculi pectinati.

The **pulmonary veins**, four in number, open into the upper part of the posterior surface of the left atrium—two on either side of its middle line: they are not provided with valves. The two left veins frequently end by a common opening.

The **left atrioventricular opening** is the aperture between the left atrium and ventricle, and is rather smaller than the corresponding opening on the right side.

The **musculi pectinati**, fewer and smaller than in the right auricle, are confined to the inner surface of the auricula.

On the atrial septum may be seen a lunated impression, bounded below by a crescentic ridge, the concavity of which is turned upward. The depression is just above the fossa ovalis of the right atrium.



FIG. 578.—Interior of left side of heart.

**Dissection.**—To examine the interior of the left ventricle, make an incision a little to the left of the anterior interatrial groove from the base to the apex of the heart, and carry it up from thence, a little to the left of the posterior interatrial groove, nearly as far as the atrioventricular groove.

**Left Ventricle** (*ventriculus sinister*).—The left ventricle is longer and more conical in shape than the right, and on transverse section its concavity presents an oval or nearly circular outline. It forms a small part of the sternocostal surface and a considerable part of the diaphragmatic surface of the heart; it also forms the apex of the heart. Its walls are about three times as thick as those of the right ventricle.

Its interior (Fig. 578) presents the following parts for examination:

Openings	{ Left atrioventricular.	Valves	{ Bicuspid or Mitral.
	{ Aortic. }		{ Aortic.
Trabeculae carnae.		Chordae tendineae.	



The **left atrioventricular opening** (*mitral orifice*) is placed below and to the left of the aortic orifice. It is a little smaller than the corresponding aperture of the opposite side, admitting only two fingers. It is surrounded by a dense fibrous ring, covered by the lining membrane of the heart, and is guarded by the bicuspid or mitral valve.

The **aortic opening** is a circular aperture, in front and to the right of the atrioventricular, from which it is separated by the anterior cusp of the bicuspid valve. Its orifice is guarded by the **aortic semilunar valves**. The portion of the ventricle immediately below the aortic orifice is termed the **aortic vestibule**, and possesses fibrous instead of muscular walls.

The **bicuspid or mitral valve** (*valvula bicuspidalis* [*metralis*]) (Figs. 577, 578) is attached to the circumference of the left atrioventricular orifice in the same way that the tricuspid valve is on the opposite side. It consists of two triangular cusps, formed by duplicatures of the lining membrane, strengthened by fibrous tissue, and containing a few muscular fibres. The cusps are of unequal size, and are larger, thicker, and stronger than those of the tricuspid valve. The larger cusp is placed in front and to the right between the atrioventricular and aortic orifices, and is known as the **anterior or aortic cusp**; the smaller or **posterior cusp** is placed behind and to the left of the opening. Two smaller cusps are usually found at the angles of junction of the larger. The cusps of the bicuspid valve are furnished with chordae tendineae, which are attached in a manner similar to those on the right side; they are, however, thicker, stronger, and less numerous.




FIG. 579.—Aorta laid open to show the semilunar valves.

The **aortic semilunar valves** (Figs. 576, 579) are three in number, and surround the orifice of the aorta; two are posterior (right and left) and one anterior. They are similar in structure, and in their mode of attachment, to the pulmonary semilunar valves, but are larger, thicker, and stronger; the lunulae are more distinct, and the noduli or corpora Arantii thicker and more prominent. Opposite the valves the aorta presents slight dilatations, the **aortic sinuses** (*sinuses of Valsalva*), which are larger than those at the origin of the pulmonary artery.

The **trabeculae carneae** are of three kinds, like those upon the right side, but they are more numerous, and present a dense interlacement, especially at the apex, and upon the posterior wall of the ventricle. The **musculi papillares** are two in number, one being connected to the anterior, the other to the posterior wall; they are of large size, and end in rounded extremities from which the chordae tendineae arise. The chordae tendineae from each papillary muscle are connected to both cusps of the bicuspid valve.

**Ventricular Septum** (*septum ventriculorum; interventricular septum*) (Fig. 580).—The ventricular septum is directed obliquely backward and to the right, and is curved with the convexity toward the right ventricle: its margins correspond with the anterior and posterior longitudinal sulci. The greater portion of it is thick and muscular and constitutes the **muscular ventricular septum**, but its upper and posterior part, which separates the aortic vestibule from the lower part of the right atrium and upper part of the right ventricle, is thin and fibrous, and is termed the **membranous ventricular septum**. An abnormal communication may exist between the ventricles at this part owing to defective development of the membranous septum.

**Structure.**—The heart consists of muscular fibres, and of fibrous rings which serve for their attachment. It is covered by the visceral layer of the serous pericardium (**epicardium**), and lined by the **endocardium**. Between these two membranes is the muscular wall or **myocardium**.

The **endocardium** is a thin, smooth membrane which lines and gives the glistening appearance to the inner surface of the heart; it assists in forming the valves by its reduplications, and is continuous with the lining membrane of the large bloodvessels. It consists of connective tissue and elastic fibres, and is attached to the muscular structure by loose elastic tissue which contains bloodvessels and nerves; its free surface is covered by endothelial cells.




FIG. 580.—Section of the heart showing the ventricular septum.

The **fibrous rings** surround the atrioventricular and arterial orifices, and are stronger upon the left than on the right side of the heart. The atrioventricular rings serve for the attachment of the muscular fibres of the atria and ventricles, and for the attachment of the bicuspid and tricuspid valves. The left atrioventricular ring is closely connected, by its right margin, with the aortic arterial ring; between these and the right atrioventricular ring is a triangular mass of fibrous tissue, the **trigonum fibrosum**, which represents the *os cordis* seen in the heart of some of the larger animals, as the ox and elephant. Lastly, there is the tendinous band, already referred to (p. 608), on the posterior surface of the conus arteriosus.

The fibrous rings surrounding the arterial orifices serve for the attachment of the great vessels and semilunar valves. Each ring receives, by its ventricular margin, the attachment of some of the muscular fibres of the ventricles; its opposite margin presents three deep semicircular notches, to which the middle coat of the artery is firmly fixed. The attachment of the artery to its fibrous ring is strengthened by the external coat and serous membrane externally, and

by the endocardium internally. From the margins of the semicircular notches the fibrous structure of the ring is continued into the segments of the valves. The middle coat of the artery in this situation is thin, and the vessel is dilated to form the sinuses of the aorta and pulmonary artery.

The **muscular structure of the heart** consists of bands of fibres, which present an exceedingly intricate interlacement. They comprise (a) the fibres of the atria, (b) the fibres of the ventricles, and (c) the atrioventricular bundle of His.

The **fibres of the atria** are arranged in two layers—a superficial, common to both cavities, and a deep, proper to each. The **superficial fibres** are most distinct on the front of the atria, across the bases of which they run in a transverse direction, forming a thin and incomplete layer. Some of these fibres run into the atrial septum. The **deep fibres** consist of looped and annular fibres. The **looped fibres** pass upward over each atrium, being attached by their two extremities to the corresponding atrioventricular ring, in front and behind. The **annular fibres** surround the auriculae, and form annular bands around the terminations of the veins and around the fossa ovalis.

The **fibres of the ventricles** are arranged in a complex manner, and various accounts have been given of their course and connections; the following description is based on the work of McCallum.<sup>1</sup> They consist of superficial and deep layers, all of which, with the exception of two, are inserted into the papillary muscles of the ventricles. The **superficial layers** consist of the following: (a) Fibres which spring from the tendon of the conus arteriosus and sweep downward and toward the left across the anterior longitudinal sulcus and around the apex of the heart, where they pass upward and inward to terminate in the papillary muscles of the left ventricle; those arising from the upper half of the tendon of the conus arteriosus pass to the anterior papillary muscle, those from the lower half to the posterior papillary muscle and the papillary muscles of the septum. (b) Fibres which arise from the right atrioventricular ring and run diagonally across the diaphragmatic surface of the right ventricle and around its right border on to its costosternal surface, where they dip beneath the fibres just described, and, crossing the anterior longitudinal sulcus, wind around the apex of the heart and end in the posterior papillary muscle of the left ventricle. (c) Fibres which spring from the left atrioventricular ring, and, crossing the posterior longitudinal sulcus, pass successively into the right ventricle and end in its papillary muscles. The **deep layers** are three in number; they arise in the papillary muscles of one ventricle and, curving in an S-shaped manner, turn in at the longitudinal sulcus and end in the papillary muscles of the other ventricle. The layer which is most superficial in the right ventricle lies next the lumen of the left, and *vice versa*. Those of the first layer almost encircle the right ventricle and, crossing in the septum to the left, unite with the superficial fibres from the right atrioventricular ring to form the posterior papillary muscle. Those of the second layer have a less extensive course in the wall of the right ventricle, and a correspondingly greater course in the left, where they join with the superficial fibres from the anterior half of the tendon of the conus arteriosus to form the papillary muscles of the septum. Those of the third layer pass almost entirely around the left ventricle and unite with the superficial fibres from the lower half of the tendon of the conus arteriosus to form the anterior papillary muscle. Besides the layers just described there are two bands which do not end in papillary muscles. One springs from the right atrioventricular ring and crosses in the atrioventricular septum; it then encircles the deep layers of the left ventricle and ends in the left atrioventricular ring. The second band is apparently confined to the left ventricle; it is attached to the left atrioventricular ring, and encircles the portion of the ventricle adjacent to the aortic orifice.

The **atrioventricular bundle of His** is the only direct muscular connection known to exist between the atria and the ventricles. It arises in connection with two small collections of spindle-shaped cells, the sinoatrial and atrioventricular nodes. The **sinoatrial node** is situated on the anterior border of the opening of the superior vena cava; from it strands of fusiform fibres run under the endocardium of the wall of the atrium to the atrioventricular node. The **atrioventricular node** lies near the orifice of the coronary sinus in the annular and septal fibres of the right atrium; from it the atrioventricular bundle passes forward in the lower part of the membranous septum, and divides into right and left fasciculi. These run down in the right and left ventricles, one on either side of the ventricular septum, covered by endocardium. In the lower parts of the ventricles they break up into numerous strands which end in the papillary muscles and in the ventricular muscle generally. The greater portion of the atrioventricular bundle consists of narrow, somewhat fusiform fibres, but its terminal strands are composed of Purkinje fibres.

Dr. A. Morison<sup>2</sup> has shown that in the sheep and pig the atrioventricular bundle "is a great avenue for the transmission of nerves from the auricular to the ventricular heart; large and numerous nerve trunks entering the bundle and coursing with it." From these, branches pass off and form plexuses around groups of Purkinje cells, and from these plexuses fine fibrils go to innervate individual cells.

**Applied Anatomy.**—Clinical and experimental evidence go to prove that this bundle conveys the impulse to systolic contraction from the atrial septum to the ventricles, and much attention has recently been paid to it, because it appears to become fibrosed and to lose much of its

<sup>1</sup> Johns Hopkins Hospital Reports, vol. ix.

<sup>2</sup> Journal of Anatomy and Physiology, vol. xlv.

conducting power (heart-block) in many cases of Stokes-Adams' disease. This condition is characterized by a slow pulse, a tendency to syncopal or epileptiform seizures, and the fact that while the cardiac atria beat at a normal rate, the ventricles contract much less frequently.

**Vessels and Nerves.**—The *arteries* supplying the heart are the right and left coronary from the aorta; the *veins* end in the right atrium.

The *lymphatics* end in the thoracic and right lymphatic ducts.

The *nerves* are derived from the cardiac plexus, which are formed partly from the vagi, and partly from the sympathetic trunks. They are freely distributed both on the surface and in the substance of the heart, the separate nerve filaments being furnished with small ganglia.

**The Cardiac Cycle and the Actions of the Valves.**—By the contractions of the heart the blood is pumped through the arteries to all parts of the body. These contractions occur regularly and at the rate of about seventy per minute. Each wave of contraction or *period of activity* is followed by a *period of rest*, the two periods constituting what is known as a **cardiac cycle**.

Each cardiac cycle consists of three phases, which succeed each other as follows: (1) a short simultaneous contraction of both atria, termed the **atrial systole**, followed, after a slight pause, by (2) a simultaneous, but more prolonged, contraction of both ventricles, named the **ventricular systole**, and (3) a **period of rest**, during which the whole heart is relaxed. The atrial contraction commences around the venous openings, and sweeping over the atria forces their contents through the atrio-ventricular openings into the ventricles, regurgitation into the veins being prevented by the contraction of their muscular coats. When the ventricles contract, the tricuspid and bicuspid valves are closed, and prevent the passage of the blood back into the atria; the muscoli papillares at the same time are shortened, and, pulling on the chordae tendineae, prevent the inversion of the valves into the atria. As soon as the pressure in the ventricles exceeds that in the pulmonary artery and aorta, the valves guarding the orifices of these vessels are opened and the blood is driven from the right ventricle into the pulmonary artery and from the left into the aorta. The moment the systole of the ventricles ceases, the pressure of the blood in the pulmonary artery and aorta closes the pulmonary and aortic semilunar valves to prevent regurgitation of blood into the ventricles, the valves remaining shut until reopened by the next ventricular systole. During the period of rest the tension of the tricuspid and bicuspid valves is relaxed, and blood is flowing from the veins into the atria, being aspirated by negative intrathoracic pressure, and slightly also from the atria into the ventricles. The average duration of a cardiac cycle is about  $\frac{8}{10}$  of a second, made up as follows:

Atrial systole,  $\frac{1}{10}$ .

Atrial diastole,  $\frac{7}{10}$ .

Ventricular systole,  $\frac{3}{10}$ .

Ventricular diastole,  $\frac{5}{10}$ .

Total systole,  $\frac{4}{10}$ .

Complete diastole,  $\frac{4}{10}$ .

The rhythmical action of the heart is *muscular* in origin—that is to say, the heart muscle itself possesses the inherent property of contraction apart from any nervous stimulation. The more embryonic the muscle the better is it able to initiate and propagate the contraction wave; this explains why the normal systole of the heart starts at the entrance of the veins, for there the muscle is most embryonic in nature. At the atrioventricular junction there is a slight pause in the wave of muscular contraction. To obviate this as far as possible a peculiar band of marked embryonic type passes across the junction and so carries on the contraction wave to the ventricles. This band, composed of special fibres, is the atrioventricular bundle of His (p. 614). The nerves, although not concerned in originating the contractions of the heart muscle, play an important role in regulating their force and frequency in order to subserve the physiological needs of the organism.

**Applied Anatomy.**—Wounds of the heart are often immediately fatal, but not necessarily so. They may be non-penetrating, when death may occur from hemorrhage if one of the coronary vessels has been wounded, or subsequently from pericarditis. Even a penetrating wound is not necessarily fatal, as a considerable number of cases have been recorded in which the wound has been sutured successfully.

### PECULIARITIES IN THE VASCULAR SYSTEM OF THE FETUS.

The development of the heart and vascular system is described on pages 141 to 162.

The chief peculiarities of the fetal heart are the direct communication between the atria through the foramen ovale, and the large size of the valve of the inferior vena cava. Among other peculiarities the following may be noted. (1) In early fetal life the heart lies immediately below the mandibular arch, and as development proceeds it is gradually drawn within the thorax. (2) For a time the atrial portion exceeds the ventricular in size, and the walls of the ventricles are of equal thickness: toward the end of fetal life the ventricular portion becomes the larger and the wall of the left ventricle exceeds that of the right in thickness. (3) Its size is large as compared with that of the rest of the body, the proportion at the second month being 1 to 50, and at birth, 1 to 120, while in the adult the average is about 1 to 160.

The **foramen ovale**, situated at the lower part of the atrial septum, forms a free communication between the atria until the end of fetal life. A septum (*septum secundum*) grows down from the upper wall of the atrium to the right of the primary septum in which the foramen ovale is situated; shortly after birth it fuses with the primary septum and the foramen ovale is obliterated.

The **valve of the inferior vena cava** serves to direct the blood from that vessel through the foramen ovale into the left atrium.

The peculiarities in the arterial system of the fetus are the communication between the pulmonary artery and the aorta by means of the ductus arteriosus, and the continuation of the hypogastric arteries as the umbilical arteries to the placenta.

The **ductus arteriosus** is a short tube, about 1.25 cm. in length at birth, and of the diameter of a goose-quill. In the early condition it forms the continuation of the pulmonary artery, and opens into the aorta, just beyond the origin of the left subclavian artery; and so conducts the greater amount of the blood from the right ventricle into the aorta. When the branches of the pulmonary artery have become larger relatively to the ductus arteriosus, the latter is chiefly connected to the left pulmonary artery.

The **hypogastric arteries** run along the sides of the bladder and thence upward on the back of the anterior abdominal wall to the umbilicus; here they pass out of the abdomen and are continued as the **umbilical arteries** in the umbilical cord to the placenta. They convey the fetal blood to the placenta.

The peculiarities in the venous system of the fetus are the communications established between the placenta and the liver and portal vein, through the umbilical vein; and between the umbilical vein and the inferior vena cava through the ductus venosus.

**Fetal Circulation** (Fig. 581).—The fetal blood is returned from the placenta to the fetus by the umbilical vein. This vein enters the abdomen at the umbilicus, and passes upward along the free margin of the falciform ligament of the liver to the under surface of that organ, where it gives off two or three branches, one of large size to the left lobe, and others to the lobus quadratus and lobus caudatus. At the **porta hepatis** (*transverse fissure of the liver*) it divides into two branches: of these, the larger is joined by the portal vein, and enters the right lobe; the smaller is continued upward, under the name of the **ductus venosus**, and joins the inferior vena cava. The blood, therefore, which traverses the umbilical vein, passes to the inferior vena cava in three different ways. A considerable quantity circulates through the liver with the portal venous blood, before entering the inferior vena cava by the hepatic veins; some enters the liver directly, and is

carried to the inferior cava by the hepatic veins; the remainder passes directly into the inferior vena cava through the ductus venosus.

In the inferior vena cava, the blood carried by the ductus venosus and hepatic veins becomes mixed with that returning from the lower extremities and abdominal




FIG. 581.—Plan of the fetal circulation. In this plan the figured arrows represent the kind of blood, as well as the direction which it takes in the vessels. Thus—arterial blood is figured  $\rightarrow$ —; venous blood,  $\rightarrow$ —; mixed (arterial and venous) blood,  $\rightarrow$ —.

wall. It enters the right atrium, and, guided by the valve of the inferior vena cava, passes through the foramen ovale into the left atrium, where it mixes with a small quantity of blood returned from the lungs by the pulmonary veins. From the left atrium it passes into the left ventricle; and from the left ventricle into the aorta, by means of which it is distributed almost entirely to the head and upper



extremities, a small quantity being probably carried into the descending aorta. From the head and upper extremities the blood is returned by the superior vena cava to the right atrium, where it mixes with a small portion of the blood from the inferior vena cava. From the right atrium it descends into the right ventricle, and thence passes into the pulmonary artery. The lungs of the fetus being inactive, only a small quantity of the blood of the pulmonary artery is distributed to them by the right and left pulmonary arteries, and returned by the pulmonary veins to the left atrium: the greater part passes through the ductus arteriosus into the aorta, where it mixes with a small quantity of the blood transmitted by the left ventricle into the aorta. Through this vessel it descends, and is in part distributed to the lower extremities and the viscera of the abdomen and pelvis, but the greater amount is conveyed by the umbilical arteries to the placenta.

From the preceding account of the circulation of the blood in the fetus the following facts will be evident: (1) The placenta serves the purposes of nutrition and excretion, receiving the impure blood from the fetus, and returning it purified and charged with additional nutritive material. (2) Nearly the whole of the blood of the umbilical vein traverses the liver before entering the inferior vena cava; hence the large size of the liver, especially at an early period of fetal life. (3) The right atrium is the point of meeting of a double current, the blood in the inferior vena cava being guided by the valve of this vessel into the left atrium, while that in the superior vena cava descends into the right ventricle. At an early period of fetal life it is highly probable that the two streams are quite distinct; for the inferior vena cava opens almost directly into the left atrium, and the valve of the inferior vena cava would exclude the current from the right ventricle. At a later period, as the separation between the two atria becomes more distinct, it seems probable that some mixture of the two streams must take place. (4) The pure blood carried from the placenta to the fetus by the umbilical vein, mixed with the blood from the portal vein and inferior vena cava, passes almost directly to the arch of the aorta, and is distributed by the branches of that vessel to the head and upper extremities. (5) The blood contained in the descending aorta, chiefly derived from that which has already circulated through the head and limbs, together with a small quantity from the left ventricle, is distributed to the abdomen and lower extremities.

**Changes in the Vascular System at Birth.**—At birth, when respiration is established, an increased amount of blood from the pulmonary artery passes through the lungs, and the placental circulation is cut off. The foramen ovale is closed by about the tenth day after birth: the valvular fold above mentioned adheres to the margin of the foramen for the greater part of its circumference, but a slit-like opening is left between the two atria above, and this sometimes persists.

The **ductus arteriosus** begins to contract immediately after respiration is established, and is completely closed from the fourth to the tenth day; it ultimately degenerates into an impervious cord, the **ligamentum arteriosum**, which connects the left pulmonary artery to the arch of the aorta.

Of the **hypogastric arteries**, the parts extending from the sides of the bladder to the umbilicus become obliterated between the second and fifth days after birth, and project as fibrous cords, the **lateral umbilical ligaments**, toward the abdominal cavity, carrying on them folds of peritoneum.

The **umbilical vein** and **ductus venosus** are completely obliterated between the second and fifth days after birth; the former becomes the **ligamentum teres**, the latter the **ligamentum venosum**, of the liver.

## THE ARTERIES.

---

THE distribution of the systematic arteries is like a highly ramified tree, the common trunk of which, formed by the aorta, commences at the left ventricle, while the smallest ramifications extend to the peripheral parts of the body and the contained organs. Arteries are found in all parts of the body, except in the hairs, nails, epidermis, cartilages, and cornea; the larger trunks usually occupy the most protected situations, running, in the limbs, along the flexor surface, where they are less exposed to injury.

There is considerable variation in the mode of division of the arteries: occasionally a short trunk subdivides into several branches at the same point, as may be observed in the coeliac artery and the thyrocervical trunk: the vessel may give off several branches in succession, and still continue as the main trunk, as is seen in the arteries of the limbs; or the division may be dichotomous, as, for instance, when the aorta divides into the two common iliacs.

A branch of an artery is smaller than the trunk from which it arises; but if an artery divides into two branches, the combined sectional area of the two vessels is, in nearly every instance, somewhat greater than that of the trunk; and the combined sectional area of all the arterial branches greatly exceeds that of the aorta; so that the arteries collectively may be regarded as a cone, the apex of which corresponds to the aorta, and the base to the capillary system.

The arteries, in their distribution, communicate with one another, forming what are called **anastomoses**, and these communications are very free between the large as well as between the smaller branches. The anastomosis between trunks of equal size is found where great activity of the circulation is requisite, as in the brain; here the two vertebral arteries unite to form the basilar, and the two anterior cerebral arteries are connected by a short communicating trunk; it is also found in the abdomen, where the intestinal arteries have very ample anastomoses between their larger branches. In the limbs the anastomoses are most numerous and of largest size around the joints, the branches of an artery above uniting with branches from the vessels below. These anastomoses are of considerable interest to the surgeon, as it is by their enlargement that a **collateral circulation** is established after the application of a ligature to an artery. The smaller branches of arteries anastomose more frequently than the larger; and between the smallest twigs these anastomoses become so numerous as to constitute a close network that pervades nearly every tissue of the body.

Throughout the body generally the larger arterial branches pursue a fairly straight course, but in certain situations they are tortuous. Thus the external maxillary artery in its course over the face, and the arteries of the lips, are extremely tortuous to accommodate themselves to the movements of the parts. The uterine arteries are also tortuous, to accommodate themselves to the increase of size which the uterus undergoes during pregnancy.

**Applied Anatomy.**—All the arteries, and most of all the aorta, are liable to a degenerative process known as atheroma, arteriosclerosis, or, more recently, atherosclerosis (Marchand), that is of the greatest clinical importance. It is essentially a senile change, although it may begin at any age and is predisposed to by renal disease, gout, diabetes mellitus, lead poisoning, and a number of other morbid states, and results in the replacement of the arterial elastic tissue by

fibrous tissue. Its chief ill effects are two. In the first place, it is associated with a permanent and often considerable rise in the arterial blood pressure, entailing a corresponding hypertrophy of the heart; in the second, it weakens the vessel walls, rendering them more liable to rupture, while at the same time it is apt to lessen the calibre of the affected vessels.

The arteries are also frequently attacked by syphilis, which gives rise to inflammation and degeneration of their middle coats. Recent researches<sup>1</sup> go to prove that arterial aneurisms, other than those due to direct injury, occur almost solely in syphilitic patients.




FIG. 582.—Transverse section of thorax, showing relations of pulmonary artery.

### The Pulmonary Artery (*A. Pulmonalis*) (Fig. 582).

The **pulmonary artery** conveys the venous blood from the right ventricle of the heart to the lungs. It is a short, wide vessel, about 5 cm. in length and 3 cm. in diameter, *arising* from the conus arteriosus of the right ventricle. It extends obliquely upward and backward, passing at first in front and then to the left of the ascending aorta, as far as the under surface of the aortic arch, where it divides, about the level of the fibrocartilage between the fifth and sixth thoracic vertebræ, into right and left branches of nearly equal size.

**Relations.**—The whole of this vessel is contained within the pericardium. It is enclosed with the ascending aorta in a single tube of the visceral layer of the serous pericardium, which is continued upward upon them from the base of the heart. The fibrous layer of the pericardium is gradually lost upon the external coats of the two branches of the artery. In *front*, the pulmonary artery is separated from the anterior end of the second left intercostal space by the pleura and left lung, in addition to the pericardium; it rests at first upon the ascending aorta, and higher up lies in front of the left atrium on a plane posterior to the ascending aorta. On *either side* of its origin is the auricle of the corresponding atrium and a coronary artery, the left coronary artery passing, in the first part of its course, behind the vessel. The superficial part of the cardiac plexus lies above its bifurcation, between it and the arch of the aorta.

The **right branch of the pulmonary artery** (*ramus dexter a. pulmonalis*), longer and larger than the left, runs horizontally to the right, behind the ascending aorta and superior vena cava and in front of the right bronchus, to the root of the right

<sup>1</sup> C. U. Aitchison, Archives of the Pathological Institute of the London Hospital, 1908, ii, 1.

lung, where it divides into two branches. The lower and larger of these goes to the middle and lower lobes of the lung; the upper and smaller is distributed to the upper lobe.

The **left branch of the pulmonary artery** (*ramus sinister a. pulmonalis*), shorter and somewhat smaller than the right, passes horizontally in front of the descending aorta and left bronchus to the root of the left lung, where it divides into two branches, one for each lobe of the lung.

*Above*, it is connected to the concavity of the aortic arch by the ligamentum arteriosum, on the left of which is the left recurrent nerve, and on the right the superficial part of the cardiac plexus. *Below*, it is joined to the upper left pulmonary vein by the ligament of the left vena cava (page 159).

The terminal branches of the pulmonary arteries will be described with the anatomy of the lungs.

**Applied Anatomy.**—Stenosis of the pulmonary artery, either with, or, more rarely, without defective formation of the ventricular septum, is one of the commonest congenital defects of the heart. It may be due either to fetal endocarditis, or to maldevelopment of the bulbus cordis (p. 149).<sup>1</sup> As in most forms of congenital heart disease, the child is cyanosed (*morbis caeruleus*), especially when excited or on exertion, and rarely lives to grow up, commonly dying of heart failure in infancy, or of pulmonary tuberculosis or intercurrent disease in childhood. The chief signs of the condition are the loud, harsh systolic cardiac murmur best heard over the second left costal cartilage, cyanosis, clubbing of the finger tips, and the presence of an excess of red corpuscles in the blood.

Embolism of the pulmonary artery by a clot of blood coming from the right side of the heart in patients with heart disease, or from a thrombosed vein in cases, for example, of influenza, enteric fever, puerperal sepsis, or fractured limbs, is a common cause of sudden or rapid death. The patient may cry out with sudden excruciating pain in the precordia when the detached embolus lodges, and after a brief period of intense dyspnoea, pallor, and anguish, die.

## THE AORTA.

The **aorta** is the main trunk of a series of vessels which convey the oxygenated blood to the tissues of the body for their nutrition. It commences at the upper part of the left ventricle, where it is about 3 cm. in diameter, and after ascending for a short distance, arches backward and to the left side, over the root of the left lung; it then descends within the thorax on the left side of the vertebral column, passes into the abdominal cavity through the aortic hiatus in the Diaphragma, and ends, considerably diminished in size (about 1.75 cm. in diameter), opposite the lower border of the fourth lumbar vertebra, by dividing into the right and left common iliac arteries. Hence it is described in several portions, viz., the **ascending aorta**, the **arch of the aorta**, and the **descending aorta**, which last is again divided into the **thoracic** and **abdominal aortae**.

### THE ASCENDING AORTA (AORTA ASCENDENS) (Fig. 583).

The **ascending aorta** is about 5 cm. in length. It commences at the upper part of the base of the left ventricle, on a level with the lower border of the third costal cartilage behind the left half of the sternum; it passes obliquely upward, forward, and to the right, in the direction of the heart's axis, as high as the upper border of the second right costal cartilage, describing a slight curve in its course, and being situated, about 6 cm. behind the posterior surface of the sternum. At its origin it presents, opposite the segments of the aortic valve, three small dilatations called the **aortic sinuses**. At the union of the ascending aorta with the aortic arch

<sup>1</sup> Keith (Studies in Pathology, Aberdeen University, 1906) believes that the great majority of cases which are classified as congenital stenosis of the pulmonary or of the aortic orifices are, in reality, due to an arrest of development or malformation of the bulbus cordis.

the calibre of the vessel is increased, owing to a bulging of its right wall. This dilatation is termed the **bulb of the aorta**, and on transverse section presents a somewhat oval figure. The ascending aorta is contained within the pericardium, and is enclosed in a tube of the serous pericardium, common to it and the pulmonary artery.

**Relations.**—The ascending aorta is covered at its commencement by the trunk of the pulmonary artery and the right auricle, and, higher up, is separated from the sternum by the pericardium, the right pleura, the anterior margin of the right lung, some loose areolar tissue, and the remains of the thymus; *posteriorly*, it rests upon the left atrium and right pulmonary artery. On the *right side*, it is in relation with the superior vena cava and right atrium, the former lying partly behind it; on the *left side*, with the pulmonary artery.




FIG. 583.—The arch of the aorta, and its branches.

**Branches.**—The only branches of the ascending aorta are the two coronary arteries which supply the heart; they arise near the commencement of the aorta immediately above the attached margins of the semilunar valves.

**The Coronary Arteries.**—The **Right Coronary Artery** (*a. coronaria [cordis] dextra*) arises from the anterior aortic sinus. It passes at first between the conus arteriosus and the right auricle and then runs in the right portion of the coronary sulcus, coursing at first from the left to right and then on the diaphragmatic surface



of the heart from right to left as far as the posterior longitudinal sulcus, down which it is continued to the apex of the heart as the **posterior descending branch**. It gives off a large **marginal branch** which follows the acute margin of the heart and supplies branches to both surfaces of the right ventricle. It also gives twigs to the right atrium and to the part of the left ventricle which adjoins the posterior longitudinal sulcus.

The **Left Coronary Artery** (*a. coronaria [cordis] sinistra*), larger than the right, arises from the left posterior aortic sinus and divides into an anterior descending and a circumflex branch. The **anterior descending branch** passes at first behind the pulmonary artery and then comes forward between that vessel and the left auricle to reach the anterior longitudinal sulcus, along which it descends to the incisura apicis cordis; it gives branches to both ventricles. The **circumflex branch** follows the left part of the coronary sulcus, running first to the left and then to the right, reaching nearly as far as the posterior longitudinal sulcus; it gives branches to the left atrium and ventricle. There is a free anastomosis between the minute branches of the two coronary arteries in the substance of the heart.

**Peculiarities.**—These vessels occasionally arise by a common trunk, or their number may be increased to three, the additional branch being of small size. More rarely, there are two additional branches.

**Applied Anatomy.**—The sudden blocking of a coronary artery by an embolus, or its more gradual obstruction by arterial disease or thrombosis, is a common cause of sudden death in persons past middle age. If the obstruction to the passage of blood is incomplete, true *angina pectoris* may occur. In this condition the patient is suddenly seized with a spasm of agonizing pain in the precordial region and down the left arm, together with an indescribable sense of anguish. He may die in such an attack, or succumb a few hours or days later from heart failure, or survive a number of attacks.

### THE ARCH OF THE AORTA (ARCUS AORTAE; TRANSVERSE AORTA) (Fig. 583).

The **arch of the aorta** begins at the level of the upper border of the second sternocostal articulation of the right side, and runs at first upward, backward, and to the left in front of the trachea; it is then directed backward on the left side of the trachea and finally passes downward on the left side of the body of the fourth thoracic vertebra, at the lower border of which it becomes continuous with the descending aorta. It thus forms two curvatures: one with its convexity upward, the other with its convexity forward and to the left. Its upper border is usually about 2.5 cm. below the superior border to the manubrium sterni.

**Relations.**—The arch of the aorta is covered *anteriorly* by the pleurae and anterior margins of the lungs, and by the remains of the thymus. As the vessel runs backward its *left* side is in contact with the left lung and pleura. Passing downward on the left side of this part of the arch are four nerves; in order from before backward these are, the left phrenic, the lower of the superior cardiac branches of the left vagus, the superior cardiac branch of the left sympathetic, and the trunk of the left vagus. As the last nerve crosses the arch it gives off its recurrent branch, which hooks around below the vessel and then passes upward on its right side. The highest left intercostal vein runs obliquely upward and forward on the left side of the arch, between the phrenic and vagus nerves. On the *right* are the deep part of the cardiac plexus, the left recurrent nerve, the oesophagus, and the thoracic duct; the trachea lies behind and to the right of the vessel. *Above* are the innominate, left common carotid, and left subclavian arteries, which arise from the convexity of the arch and are crossed close to their origins by the left innominate vein. *Below* are the bifurcation of the pulmonary artery, the left bronchus, the ligamentum arteriosum, the superficial part of the cardiac plexus, and the left recurrent nerve. As already stated, the ligamentum arteriosum connects the commencement of the left pulmonary artery to the aortic arch.

Between the origin of the left subclavian artery and the attachment of the ductus arteriosus the lumen of the fetal aorta is considerably narrowed, forming what is termed the **aortic isthmus**, while immediately beyond the ductus arteriosus the vessel presents a fusiform dilation which His has named the **aortic spindle**—the



point of junction of the two parts being marked in the concavity of the arch by an indentation or angle. These conditions persist, to some extent, in the adult, where His found that the average diameter of the spindle exceeded that of the isthmus by 3 mm.

Distinct from this diffuse and moderate stenosis at the isthmus is the condition known as *coarctation of the aorta*, or marked stenosis often amounting to complete obliteration of its lumen, seen in adults and occurring at or near, oftenest a little below, the insertion of the ligamentum arteriosum into the aorta. According to Bonnet<sup>1</sup> this coarctation is never found in the fetus or at birth, and is due to an abnormal extension of the peculiar tissue of the ductus into the aortic wall, which gives rise to a simultaneous stenosis of both vessels as it contracts after birth—the ductus is usually obliterated in these cases. An extensive collateral circulation is set up, by the costocervicals, internal mammaries, and the descending branches of the transverse cervical above the stenosis, and below it by the first four aortic intercostals, the pericardiaco-phrenics, and the superior and inferior epigastrics.

**Peculiarities.**—The height to which the aorta rises in the thorax is usually about 2.5 cm. below the upper border of the sternum; but it may ascend nearly to the top of the bone. Occasionally it is found 4 cm., more rarely from 5 to 8 cm. below this point. Sometimes the aorta arches over the root of the right lung (right aortic arch) instead of over that of the left, and passes down on the right side of the vertebral column, a condition which is found in birds. In such cases all the thoracic and abdominal viscera are transposed. Less frequently the aorta, after arching over the root of the right lung, is directed to its usual position on the left side of the vertebral column; this peculiarity is not accompanied by transposition of the viscera. The aorta occasionally divides, as in some quadrupeds, into an ascending and a descending trunk, the former of which is directed vertically upward, and subdivides into three branches, to supply the head and upper extremities. Sometimes the aorta subdivides near its origin into two branches, which soon reunite. In one of these cases the oesophagus and trachea were found to pass through the interval between the two branches; this is the normal condition of the vessel in the reptilia.

**Applied Anatomy.**—Of all the vessels of the arterial system, the aorta, and more especially its arch, is most frequently the seat of disease; hence it is important to consider some of the consequences that may ensue from aneurism of this part.

Aneurism of the ascending aorta, in the situation of the aortic sinuses, in the great majority of cases, affects the anterior sinus; this is mainly owing to the fact that the regurgitation of blood upon the sinuses takes place chiefly on the anterior aspect of the vessel. As the aneurismal sac enlarges, it may compress any or all of the structures in immediate proximity with it, but chiefly projects toward the right anterior side; and, consequently, interferes mainly with those structures that have a corresponding relation with the vessel. If it project forward, it may destroy the sternum and the cartilages of the ribs, usually on the right side, and appear as a pulsating tumor on the front of the chest, just below the manubrium; or it may burst into the pericardium, or may compress, or open into the right lung, the trachea, bronchi, or oesophagus. In the majority of cases it bursts into the cavity of the pericardium, the patient suddenly drops down dead, and, upon a postmortem examination, the pericardial sac is found full of blood; or it may compress the right atrium, or the pulmonary artery, and adjoining part of the right ventricle, and open into one or the other of these parts. It may press upon the superior vena cava or the innominate veins, causing great venous engorgement. The face becomes livid and swollen, the right arm and anterior thoracic wall oedematous, and the congestion of the brain gives rise to headache and vertigo. An aneurism has occasionally perforated into the superior vena cava, setting up an arteriovenous aneurism. When this happens the patient suddenly becomes very short of breath, intensely congested and oedematous in the face and upper part of the body, and develops a palpable thrill and a continuous humming murmur, loudest during systole, over the sternum. Death follows a few days or weeks after such a perforation; and somewhat similar symptoms are occasioned when an aortic aneurism erodes and bursts into the pulmonary artery.

Regarding the arch of the aorta, the student is reminded that the vessel lies against the trachea, oesophagus, and thoracic duct; that the recurrent nerve winds around it; and that from its upper part are given off three large trunks, which supply the head, neck, and upper extremities. An aneurismal tumor taking origin from the posterior part of the vessel, its most usual site, may press upon the trachea and give rise to the sign known as *tracheal tugging*, impede the breathing, or produce cough, dyspnoea, bronchiectasis, hemoptysis, or stridulous breathing, or it may ultimately burst into that tube, producing fatal hemorrhage. Again, its pressure on the left recurrent nerve may give rise to symptoms of laryngeal paralysis; or it may press upon the thoracic duct and destroy life by inanition; or it may involve the oesophagus, producing dysphagia, and has not infrequently been mistaken for oesophageal stricture; or it may burst into the oesophagus, when fatal hemorrhage will occur. Compression or stretching of the sympathetic filaments

<sup>1</sup> Rev. de Méd., Paris, 1903.

may, in the former case, produce dilatation of the pupil; in the latter, contraction, if the conducting power is abolished, on the affected side. This has proved to be an important diagnostic sign in this disease. Again, the innominate artery, or the subclavian, or left carotid, may be so obstructed by clots as to produce a weakness, or even a disappearance, of the pulse in one or the other wrist, or in the left superficial temporal artery; or the tumor may present itself at or above the manubrium, generally either in the median line, or to the right of the sternum, and may simulate an aneurism of one of the arteries of the neck.

Many of the physical signs of an aortic aneurism may be simulated with extraordinary fidelity by the preternatural pulsation or throbbing of a distended and elastic aorta, when no true aneurismal dilatation exists. This condition may be met with in young persons with aortic reflux and greatly hypertrophied hearts, in patients who are of a neurotic or hysterical temperament, and in cases of Graves' disease or of marked anemia. The condition is known as dynamic dilatation of the aorta, and in no way threatens life.

**Branches** (Figs. 583, 584).—The branches given off from the arch of the aorta are three in number: the **innominate**, the **left common carotid**, and the **left subclavian**.

**Peculiarities.**—*Position of the Branches.*—The branches, instead of arising from the highest part of the arch, may spring from the commencement of the arch or upper part of the ascending aorta; or the distance between them at their origins may be increased or diminished, the most frequent change in this respect being the approximation of the left carotid toward the innominate artery.

The number of the primary branches may be reduced to one, or more commonly two; the left carotid arising from the innominate artery; or (more rarely) the carotid and subclavian arteries of the left side arising from a left innominate artery. But the number may be increased to four, from the right carotid and subclavian arteries arising directly from the aorta, the innominate being absent. In most of these latter cases the right subclavian has been found to arise from the left end of the arch; in other cases it is the second or third branch given off, instead of the first. Another common form in which there are four primary branches is that in which the left vertebral artery arises from the arch of the aorta between the left carotid and subclavian arteries. Lastly, the number of trunks from the arch may be increased to five or six; in these instances, the external and internal carotids arise separately from the arch, the common carotid being absent on one or both sides. In some few cases six branches have been found, and this condition is associated with the origin of both vertebral arteries from the arch.

**Number Usual, Arrangement Different.**—When the aorta arches over to the right side, the three branches have an arrangement the reverse of what is usual; the innominate artery is a left one, and the right carotid and subclavian arise separately. In other cases, where the aorta takes its usual course, the two carotids may be joined in a common trunk, and the subclavians arise separately from the arch, the right subclavian generally arising from the left end of the arch.

In some instances other arteries spring from the arch of the aorta. Of these the most common are the bronchial, one or both, and the thyroidea ima; but the internal mammary and the inferior thyroid have been seen to arise from this vessel.

### The Innominate Artery (*A. Anonyma*; *Brachiocephalic Artery*) (Fig. 583).

The **innominate artery** is the largest branch of the arch of the aorta, and is from 4 to 5 cm. in length. It *arises*, on a level with the upper border of the second right costal cartilage, from the commencement of the arch of the aorta, on a plane anterior to the origin of the left carotid; it ascends obliquely upward, backward, and to the right to the level of the upper border of the right sternoclavicular articulation, where it divides into the right common carotid and right subclavian arteries.

**Relations.**—*Anteriorly*, it is separated from the manubrium sterni by the Sternohyoideus and Sternothyroideus, the remains of the thymus, the left innominate and right inferior thyroid veins which cross its root, and sometimes the superior cardiac branches of the right vagus. *Posterior* to it is the trachea, which it crosses obliquely. On the *right side* are the right innominate vein, the superior vena cava, the right phrenic nerve, and the pleura; and on the *left side*, the remains of the thymus, the origin of the left common carotid artery, the inferior thyroid veins, and the trachea.

**Branches.**—The innominate artery usually gives off no branches; but occasionally a small branch, the **thyroidea ima**, arises from it. Sometimes it gives off a **thymic** or **bronchial** branch.

The **thyreoides ima** (*a. thyreoides ima*) ascends in front of the trachea to the lower part of the thyroid gland, which it supplies. It varies greatly in size, and appears to compensate for deficiency or absence of one of the other thyroid vessels. It occasionally arises from the aorta, the right common carotid, the subclavian or the internal mammary.

**Point of Division.**—The innominate artery sometimes divides above the level of the sterno-clavicular joint, less frequently below it.

**Position.**—When the aortic arch is on the right side, the innominate is directed to the left side of the neck.

**Collateral Circulation.**—Allan Burns demonstrated, on the dead subject, the possibility of the establishment of the collateral circulation after ligature of the innominate artery, by tying and dividing that artery. He then found that "Even coarse injection, impelled into the aorta, passed freely by the anastomosing branches into the arteries of the right arm, filling them and all the vessels of the head completely."<sup>1</sup> The branches by which this circulation would be carried on are very numerous; thus, all the communications across the middle line between the branches of the carotid arteries of opposite sides would be available for the supply of blood to the right side of the head and neck; while the anastomosis between the costocervical of the subclavian and the first aortic intercostal (see *infra* on the collateral circulation after obliteration of the thoracic aorta) would bring the blood, by a free and direct course, into the right subclavian. The numerous connections, also, between the intercostal arteries and the branches of the axillary and internal mammary arteries would, doubtless, assist in the supply of blood to the right arm, while the inferior epigastric from the external iliac would, by means of its anastomosis with the internal mammary, compensate for any deficiency in the vascularity of the wall of the chest.

**Applied Anatomy.**—Aneurism of the innominate artery not infrequently occurs as an accompaniment to aneurism of the arch of the aorta. It causes bulging of the right sternoclavicular articulation, pushing forward the Sternocleidomastoideus muscle and filling up the jugular notch. It produces serious pressure symptoms; from pressure on the innominate veins it may cause oedema of the upper extremities, and of the head and neck; from pressure on the trachea it produces dyspnoea; and from pressure on the right recurrent nerve, hoarseness and laryngeal cough.

Although the operation of tying the innominate artery has been performed by several surgeons, not many successes have been recorded. The chief danger of the operation appears to be the frequency of secondary hemorrhage; but in the present day, with the practice of aseptic surgery and our greater knowledge of the use of the ligature, more favorable results may be anticipated. The main obstacles to the operation are, the deep situation of the artery behind the sternum, and the number of important structures which surround it.

In order to apply a ligature to this vessel, the patient is to be placed upon his back with the thorax slightly raised, the head bent a little backward, and the right shoulder strongly depressed, so as to draw out the artery from behind the sternum into the neck. An incision 7 cm. or more in length is then made along the anterior border of the Sternocleidomastoideus, terminating at the sternal end of the clavicle. From this point, a second incision is carried about the same length along the upper border of the clavicle. The skin is then dissected back, and the *Platysma* divided; the sternal end of the Sternocleidomastoideus is now brought into view, and a director being passed beneath it, and close to its deep surface so as to avoid any small vessels, it is to be divided; in like manner the clavicular origin is to be divided throughout the whole or greater part of its attachment. By pressing aside any loose cellular tissue or vessels that may now appear, the Sternohyoideus and Sternothyreoides muscles will be exposed, and must be divided. The inferior thyroid veins may come into view, and must be carefully drawn either upward or downward, by means of a blunt hook, or tied with double ligatures and divided. After tearing through a strong fibrocellular lamina, the right common carotid is brought into view, and being traced downward, the innominate artery is reached. The left innominate vein should now be depressed; the right innominate vein, the internal jugular vein, and the vagus nerve drawn to the right side; and a curved aneurism needle may then be passed around the vessel, close to its surface, and in a direction from below upward and medially; care being taken to avoid the right pleural sac, the trachea, and cardiac nerves. The ligature should be applied to the artery as high as possible, in order to allow room between it and the aorta for the formation of the coagulum. The importance of avoiding the thyroid plexus of veins during the primary steps of the operation, and the pleural sac while including the vessel in the ligature, should be most carefully borne in mind.

<sup>1</sup> Surgical Anatomy of the Head and Neck, p. 62.

## THE ARTERIES OF THE HEAD AND NECK.

The principal arteries of supply to the head and neck are the two **common carotids**; they ascend in the neck and each divides into two branches, viz., (1) the **external carotid**, supplying the exterior of the head, the face, and the greater part of the neck; (2) the **internal carotid**, supplying to a great extent the parts within the cranial and orbital cavities.

### THE COMMON CAROTID ARTERY (A. CAROTIS COMMUNIS).

The **common carotid arteries** differ in length and in their mode of origin. The *right* begins at the bifurcation of the innominate artery behind the sternoclavicular joint and is confined to the neck. The *left* springs from the highest part of the arch of the aorta to the left of, and on a plane posterior to the innominate artery, and therefore consists of a thoracic and a cervical portion.

The **thoracic portion of the left common carotid artery** ascends from the arch of the aorta through the superior mediastinal cavity to the level of the left sternoclavicular joint, where it is continuous with the cervical portion.

**Relations.**—*In front*, it is separated from the manubrium sterni by the Sternohyoideus and Sternothyroideus, the anterior portions of the left pleura and lung, the left innominate vein, and the remains of the thymus; *behind*, it lies on the trachea, œsophagus, left recurrent nerve, and thoracic duct. To its *right side* below is the innominate artery, and above, the trachea, the inferior thyroid veins, and the remains of the thymus; to its *left side* are the left vagus and phrenic nerves, left pleura, and lung. The left subclavian artery is posterior and slightly lateral to it.

The **cervical portions** of the common carotids resemble each other so closely that one description will apply to both (Fig. 585). Each vessel passes obliquely upward, from behind the sternoclavicular articulation, to the level of the upper border of the thyroid cartilage, where it divides into the external and internal carotid arteries.

At the lower part of the neck the two common carotid arteries are separated from each other by a very narrow interval which contains the trachea; but at the upper part, the thyroid gland, the larynx and pharynx project forward between the two vessels. The common carotid artery is contained in a sheath, which is derived from the deep cervical fascia and encloses also the internal jugular vein and vagus nerve, the vein lying lateral to the artery, and the nerve between the artery and vein, on a plane posterior to both. On opening the sheath, each of these three structures is seen to have a separate fibrous investment.

**Relations.**—At the lower part of the neck the common carotid artery is very deeply seated, being *covered by* the integument, superficial fascia, Platysma, and deep cervical fascia, the Sternocleidomastoideus, Sternohyoideus, Sternothyroideus, and Omohyoideus; in the upper part of its course it is more superficial, being covered merely by the integument, the superficial fascia, Platysma, deep cervical fascia, and medial margin of the Sternocleidomastoideus. When the latter muscle is drawn backward, the artery is seen to be contained in a triangular space, the **carotid triangle**, bounded behind by the Sternocleidomastoideus, above by the Stylohyoideus and posterior belly of the Digastricus, and below by the superior belly of the Omohyoideus. This part of the artery is crossed obliquely, from its medial to its lateral side, by the sternocleidomastoid branch of the superior thyroid artery; it is also crossed by the superior and middle thyroid veins which end in the internal jugular; descending in front of its sheath is the descending branch of the hypoglossal nerve, this filament being joined by one or two branches from the cervical nerves, which cross the vessel obliquely. Sometimes the descending branch of the hypoglossal nerve is contained within the sheath. The superior thyroid vein crosses the artery near its termination, and the middle thyroid vein a little below the level of the cricoid cartilage; the anterior jugular vein crosses the artery just above the clavicle, but is separated from it by the Sternohyoideus and Sternothyroideus. *Behind*, the artery is separated from the transverse processes of the cervical vertebrae by the Longus colli and Longus capitis, the sympathetic trunk being interposed between it and the muscles. The inferior thyroid artery crosses behind the lower part of the vessel. *Medially*, it is in relation with the œsophagus, trachea, and thyroid gland (which overlaps it), the inferior thyroid artery and recurrent nerve being interposed; higher

up, with the larynx and pharynx. *Lateral* to the artery are the internal jugular vein and *vagus* nerve.

At the lower part of the neck, the right recurrent nerve crosses obliquely behind the artery; the right internal jugular vein diverges from the artery, but the left approaches and often overlaps the lower part of the artery.

Behind the angle of bifurcation of the common carotid artery is a reddish-brown oval body, known as the **glomus caroticum** (*carotid body*). It is similar in structure to the **glomus coccygeum** (*coccygeal body*) which is situated on the middle sacral artery.




FIG. 585.—Superficial dissection of the right side of the neck, showing the carotid and subclavian arteries.

**Peculiarities as to Origin.**—The *right common carotid* may arise above the level of the upper border of the sternoclavicular articulation; this variation occurs in about 12 per cent. of cases. In other cases the artery may arise as a separate branch from the arch of the aorta, or in conjunction with the left carotid. The *left common carotid* varies in its origin more than the right. In the majority of abnormal cases it arises with the innominate artery; if that artery is absent, the two carotids arise usually by a single trunk. It is rarely joined with the left subclavian, except in cases of transposition of the aortic arch.

**Peculiarities as to Point of Division.**—In the majority of abnormal cases this occurs higher than usual, the artery dividing opposite or even above the hyoid bone; more rarely, it occurs

below, opposite the middle of the larynx, or the lower border of the cricoid cartilage; one case is related by Morgagni, where the artery was only 4 cm. in length and divided at the root of the neck. Very rarely, the common carotid ascends in the neck without any subdivision, either the external or the internal carotid being wanting; and in a few cases the common carotid has been found to be absent, the external and internal carotids arising directly from the arch of the aorta. This peculiarity existed on both sides in some instances, on one side in others.

**Occasional Branches.**—The common carotid usually gives off no branch previous to its bifurcation, but it occasionally gives origin to the superior thyroid or its laryngeal branch, the ascending pharyngeal, the inferior thyroid, or, more rarely, the vertebral artery.

**Applied Anatomy.**—Aneurisms are not commonly met with on the common carotid; when they do occur they are usually situated low down at the root of the neck, or just below the point of bifurcation of the vessel. They do not frequently assume a large size, and are more commonly found on the right side. As they increase in size they displace the trachea and larynx, and therefore dyspnoea becomes a prominent symptom. Dysphagia also may be present from pressure on the oesophagus, especially if the aneurism is on the left side; and pressure on the recurrent nerve may produce hoarseness and laryngeal cough. Pressure on the sympathetic will cause pupillary changes—dilatation of the pupil when the sympathetic is irritated, contraction when it has become paralyzed—and may also give rise to unilateral sweating. Pressure on the superficial branches of the cervical plexus may give rise to pain in the head, face, and neck; pressure on the vagus to irregular action of the heart and to asthmatic attacks. It is important to bear in mind that an enlarged lymph gland in the superior carotid triangle, receiving a transmitted pulsation from the carotid artery, may simulate aneurism of that vessel, but may be distinguished from it by the character of the pulsation, which is not distensible.

Embolism of the left common carotid has been known to produce aphasia by interference with the blood supply of the brain.

*Digital compression* of the common carotid is sometimes required, and is best effected by compressing the vessel with the thumb against the anterior tubercle of the transverse process of the sixth cervical vertebra (see p. 199).

*Ligature* of the common carotid artery may be necessary in a case of wound of that vessel or its branches, in aneurism, or in a case of pulsating tumor of the orbit or skull. If the wound involves the trunk of the common carotid, it will be necessary to tie the artery above and below the wounded part. In cases of aneurism, the whole of the artery is accessible, and any part of it may be tied. When the case is such as to allow of a choice being made, the upper part of the carotid should be selected as the spot upon which to place a ligature, for the lower part of the vessel is placed very deeply in the neck, and is covered by three layers of muscles; moreover, on the left side, the internal jugular vein, in the great majority of cases, passes obliquely in front of it. The part of the vessel which is most favorable for the operation is that opposite the level of the cricoid cartilage. It occasionally happens that the carotid artery bifurcates below its usual position; if the artery be exposed at its point of bifurcation, both divisions of the vessel should be tied near their origin, in preference to tying the trunk of the artery near its termination; and if, in consequence of the entire absence of the common carotid, or from its early division, two arteries, the external and internal carotids, are met with, the ligature should be placed on that vessel which is found on compression to be connected with the diseased area.

In this operation, the direction of the vessel and the anterior margin of the Sternocleidomastoideus are the chief guides to its performance. The patient should be placed on his back with the head extended and turned slightly to the opposite side; an incision is to be made, 7 or 8 cm. long, in the direction of the anterior border of the Sternocleidomastoideus, so that the centre corresponds to the level of the cricoid cartilage. After dividing the integument, superficial fascia, Platysma, and deep fascia, the margins of the wound are held asunder by retractors, and the ramus descendens hypoglossi is now exposed, and must be avoided. The sheath of the vessel is to be raised by forceps, and opened to a small extent over the artery at its medial side. The internal jugular vein may present itself alternately distended and relaxed, and must be carefully avoided. The aneurism needle is passed from the lateral aspect, care being taken to keep the needle in close contact with the artery, and thus avoid the risk of injuring the internal jugular vein, or including the vagus nerve. Before the ligature is tied, it should be ascertained that nothing but the artery is included in it.

Ligature of the common carotid near the root of the neck is sometimes required in cases of aneurism of the upper part of the carotid, especially if the sac is of large size. It is best performed by dividing the sternal origin of the Sternocleidomastoideus, but may be done in some cases, if the aneurism is not of very large size, by an incision along the anterior border of the muscle, extending down to the sternoclavicular articulation, and by then retracting the muscle. The easiest and best plan, however, is to make an incision 5 to 7 cm. long down the lower part of the anterior border of the Sternocleidomastoideus to the sternoclavicular joint, and a second incision, starting from the termination of the first, along the upper border of the clavicle for about 5 cm. This incision is made through the superficial and deep fasciæ and the sternal origin of the muscle is exposed. This is to be divided on a director and turned up, with the superficial struc-



tures, as a triangular flap. Some loose connective tissue is to be divided or torn through, and the lateral border of the Sternohyoideus exposed. In doing this, care must be taken not to wound the anterior jugular vein, which crosses this muscle to reach the external jugular or subclavian vein. The Sternohyoideus and Sternothyroideus are to be drawn medialward by means of a retractor, and the sheath of the vessel exposed. This must be opened on its medial or tracheal side, so as to avoid the internal jugular vein. Special care is necessary on the left side, where the artery is commonly overlapped by the vein; on the right side there is usually an interval between the artery and the vein, and the risk of wounding the latter is less.

The common carotid artery, being a long vessel without any branches, is particularly suitable for the performance of Brasdor's operation for the cure of an aneurism of the lower part of the vessel. Brasdor's procedure consists in ligaturing the artery on the distal side of the aneurism, and in the case of the common carotid there are no branches given off from the vessel between the aneurism and the site of the ligature; hence the flow of blood through the sac of the aneurism is diminished, and cure takes place in the usual way by the deposit of laminated fibrin.

**Collateral Circulation.**—After ligature of the common carotid, the collateral circulation can be perfectly established, by the free communication which exists between the carotid arteries of opposite sides, both without and within the cranium, and by enlargement of the branches of the subclavian artery on the side corresponding to that on which the vessel has been tied. The chief communications outside the skull take place between the superior and inferior thyroid arteries, and the profunda cervicis and ramus descendens of the occipital; the vertebral takes the place of the internal carotid within the cranium.

### The External Carotid Artery (*A. Carotis Externa*) (Fig. 585).

The **external carotid artery** begins opposite the upper border of the thyroid cartilage, and, taking a slightly curved course, passes upward and forward, and then inclines backward to the space behind the neck of the mandible, where it divides into the superficial temporal and internal maxillary arteries. It rapidly diminishes in size in its course up the neck, owing to the number and large size of the branches given off from it. In the child, it is somewhat smaller than the internal carotid; but in the adult, the two vessels are of nearly equal size. At its origin, this artery is more superficial, and placed nearer the middle line than the internal carotid, and is contained within the carotid triangle.

**Relations.**—The external carotid artery is covered by the skin, superficial fascia, Platysma, deep fascia, and anterior margin of the Sternocleidomastoideus; it is crossed by the hypoglossal nerve, by the lingual, ranine, common facial, and superior thyroid veins; and by the Digastricus and Stylohyoideus; higher up it passes deeply into the substance of the parotid gland, where it lies deep to the facial nerve and the junction of the temporal and internal maxillary veins. *Medial* to it are the hyoid bone, the wall of the pharynx, the superior laryngeal nerve, and a portion of the parotid gland. *Lateral* to it, in the lower part of its course, is the internal carotid artery. *Posterior* to it, near its origin, is the superior laryngeal nerve; and higher up, it is separated from the internal carotid by the Styloglossus and Stylopharyngeus, the glossopharyngeal nerve, the pharyngeal branch of the vagus, and part of the parotid gland.

**Applied Anatomy.**—Ligature of the external carotid may be required in cases of wound of this vessel or of its branches when these cannot be tied, and in some cases of pulsating tumors of the scalp or face. It is also done as a preliminary measure to excision of the maxilla. The seat of election for ligature is between the origins of its superior thyroid and lingual branches, about a finger's breadth below the tip of the greater cornu of the hyoid bone. To tie the vessel, an incision is made from the angle of the mandible to the upper border of the thyroid cartilage, and the superficial tissues and the deep fascia divided. The anterior border of the Sternocleidomastoideus must be retracted and the lower border of the parotid gland raised, so as to expose the tendon of the Digastricus and the hypoglossal nerve, which cross the artery. The great difficulty in doing this is due to the plexus of veins derived from the superior thyroid and lingual veins, which overlie the artery. If necessary, these must be ligatured and divided. Care must be taken not to mistake the lingual and external maxillary, when they arise by a common trunk, as they sometimes do, for the external carotid. The needle is to be passed from the lateral to the medial side of the vessel, carefully avoiding the superior laryngeal nerve, which lies in close proximity to the artery. The circulation is at once reestablished by the free communication between most of the large branches of the artery (external maxillary, lingual, superior thyroid, occipital) and the corresponding arteries of the opposite side, and by the anastomosis of its branches with those of the internal carotid, and of the occipital with branches of the subclavian, etc.

**Branches.** The branches of the external carotid artery may be divided into four sets.

<i>Anterior.</i>	<i>Posterior.</i>	<i>Ascending.</i>	<i>Terminal.</i>
Superior Thyroid.	Occipital.	Ascending	Superficial Temporal.
Lingual.	Posterior Auricular.	Pharyngeal.	Internal Maxillary.
External Maxillary.			

1. The **superior thyroid artery** (*a. thyreoidea superior*) (Fig. 585) *arises* from the external carotid artery just below the level of the greater cornu of the hyoid bone and ends in the thyroid gland.

**Relations.**—From its origin under the anterior border of the Sternocleidomastoideus it runs upward and forward for a short distance in the carotid triangle, where it is covered by the skin, Platysma, and fascia; it then arches downward beneath the Omohyoideus, Sternohyoideus, and Sternothyroideus. To its medial side are the Constrictor pharyngis inferior and the external branch of the superior laryngeal nerve.

**Branches.**—It distributes twigs to the adjacent muscles, and numerous branches to the thyroid gland, anastomosing with its fellow of the opposite side, and with the inferior thyroid arteries. The branches to the gland are generally two in number; one, the larger, supplies principally the anterior surface; on the isthmus of the gland it anastomoses with the corresponding artery of the opposite side: a second branch descends on the posterior surface of the gland and anastomoses with the inferior thyroid artery.

Besides the arteries distributed to the muscles and to the thyroid gland, the branches of the superior thyroid are:

Hyoid.	Superior Laryngeal.
Sternocleidomastoid.	Cricothyroid.

The **Hyoid Branch** (*ramus hyoideus; infrahyoid branch*) is small and runs along the lower border of the hyoid bone beneath the Thyreohyoideus and anastomoses with the vessel of the opposite side.

The **Sternocleidomastoid Branch** (*ramus sternocleidomastoideus; sternomastoid branch*) runs downward and lateralward across the sheath of the common carotid artery, and supplies the Sternocleidomastoideus and neighboring muscles and integument; it frequently *arises* as a separate branch from the external carotid.

The **Superior Laryngeal Artery** (*a. laryngea superior*), larger than either of the preceding, accompanies the internal laryngeal branch of the superior laryngeal nerve, beneath the Thyreohyoideus; it pierces the hyothyroid membrane, and supplies the muscles, mucous membrane, and glands of the larynx, anastomosing with the branch from the opposite side.

The **Cricothyroid Branch** (*ramus cricothyreoideus*) is small and runs transversely across the cricothyroid membrane, communicating with the artery of the opposite side.

**Applied Anatomy.**—The superior thyroid, or one of its branches, is often divided in cases of cut throat, giving rise to considerable hemorrhage. In such cases, the artery should be secured, the wound being enlarged for that purpose, if necessary. The operation may be easily performed, the artery being very superficial, and the only structures of importance covering it being a few small veins. The operation of tying the superior thyroid artery in bronchocele has been performed, but the collateral circulation between this vessel and the artery of the opposite side, and the inferior thyroid, is so free that the operation has been given up, especially as better results are obtained by other means.

The position of the sternocleidomastoid branch is of importance in connection with the operation of ligature of the common carotid artery. It crosses and lies on the sheath of this vessel and may chance to be wounded in opening the sheath. The position of the cricothyroid branch should be remembered, as it may prove the source of troublesome hemorrhage during the operation of laryngotomy.

2. The **lingual artery** (*a. lingualis*) (Fig. 590) *arises* from the external carotid between the superior thyroid and external maxillary; it first runs obliquely upward and medialward to the greater cornu of the hyoid bone; it then curves downward

and forward, forming a loop which is crossed by the hypoglossal nerve, and passing beneath the Digastricus and Stylohyoideus it runs horizontally forward, beneath the Hyoglossus, and finally, ascending almost perpendicularly to the tongue, turns forward on its lower surface as far as the tip, under the name of the **profunda linguae**.

**Relations.**—Its first, or oblique, portion is superficial, and is contained within the carotid triangle; it rests upon the Constrictor pharyngis medius, and is covered by the Platysma and the fascia of the neck. Its second, or curved, portion also lies upon the Constrictor pharyngis medius, being covered at first by the tendon of the Digastricus and by the Stylohyoideus, and afterward by the Hyoglossus. Its third, or horizontal, portion lies between the Hyoglossus and Genioglossus. The fourth, or terminal part, under the name of the **profunda linguae** (*ranine artery*) runs along the under surface of the tongue to its tip; here it is superficial, being covered only by the mucous membrane; above it is the Longitudinalis inferior, and on the medial side the Genioglossus. The hypoglossal nerve crosses the first part of the lingual artery, but is separated from the second part by the Hyoglossus.

**Branches.**—The branches of the lingual artery are:

Hyoid.

Sublingual.

Dorsales linguae.

Profunda linguae.

The **Hyoid Branch** (*ramus hyoideus; suprahyoid branch*) runs along the upper border of the hyoid bone, supplying the muscles attached to it and anastomosing with its fellow of the opposite side.

The **Arteriae Dorsales Linguae** (*rami dorsales linguae*) consist usually of two or three small branches which *arise* beneath the Hyoglossus; they ascend to the back part of the dorsum of the tongue, and supply the mucous membrane in this situation, the glossopalatine arch, the tonsil, soft palate, and epiglottis; anastomosing with the vessels of the opposite side.

The **Sublingual Artery** (*a. sublingualis*) *arises* at the anterior margin of the Hyoglossus, and runs forward between the Genioglossus and Mylohyoideus to the sublingual gland. It supplies the gland and gives branches to the Mylohyoideus and neighboring muscles, and to the mucous membrane of the mouth and gums. One branch runs behind the alveolar process of the mandible in the substance of the gum to anastomose with a similar artery from the other side; another pierces the Mylohyoideus and anastomoses with the submental branch of the external maxillary artery.

The **Arteria Profunda Linguae** (*ranine artery; deep lingual artery*) is the terminal portion of the lingual artery; it pursues a tortuous course and runs along the under surface of the tongue, below the Longitudinalis inferior, and above the mucous membrane; it lies on the lateral side of the Genioglossus, accompanied by the lingual nerve. At the tip of the tongue, it is said to anastomose with the artery of the opposite side, but this is denied by Hyrtl. In the mouth, these vessels are placed one on either side of the frenulum linguae.

**Applied Anatomy.**—The lingual artery is not infrequently divided near its origin in cases of cut throat; while severe hemorrhage, which cannot be restrained by ordinary means, may ensue from a wound, or deep ulcer, of the tongue. In the former case, the primary wound may be enlarged if necessary, and the bleeding vessel secured; in the latter, it has been suggested that the lingual artery should be tied near its origin. Ligature of the lingual artery has been also occasionally practised, as a preliminary measure to removal of the tongue. The operation is a difficult one on account of the depth of the artery, the number of important parts by which it is surrounded, and its occasional irregularity of origin. An incision is to be made in a curved direction from a finger's breadth behind the symphysis menti downward to the cornu of the hyoid bone, and then upward to near the angle of the mandible. Care must be taken not to carry this incision too far backward, for fear of endangering the anterior facial vein. In the first incision the skin, superficial fascia, and Platysma will be divided, and the deep fascia displayed. This is then to be incised and the submaxillary gland exposed and pulled upward by retractors. A triangular space is now seen, bounded in front by the posterior border of the Mylohyoideus; below and behind, by the tendon of the Digastricus; and above, by the hypoglossal nerve. The floor of the space is formed by the Hyoglossus, beneath which the artery lies. The parts are to

be drawn forward by a blunt hook inserted beneath the tendon of the Digastricus, and the fibres of the Hyoglossus cut through horizontally just above the Digastricus. The artery will then be exposed; and in passing the aneurism needle, care must be taken not to open the pharynx. The hypoglossal nerve must also be avoided.

Troublesome hemorrhage may occur in the division of the frenulum linguae in children, if the aa. profundae linguae, which lie one on either side of it, be wounded. The operation should always be performed with a pair of blunt-pointed scissors, and the mucous membrane alone divided by a very superficial cut, which cannot endanger any vessel. Any further liberation of the tongue which may be necessary can be effected by tearing.




FIG. 586.—The arteries of the face and scalp.<sup>1</sup>

3. The **external maxillary artery** (*a. maxillaris externa; facial artery*) (Fig. 586), arises in the carotid triangle a little above the lingual artery and, sheltered by the ramus of the mandible, passes obliquely up beneath the Digastricus and Stylohyoideus, over which it arches to enter a groove on the posterior surface of the submaxillary gland. It then curves upward over the body of the mandible at the antero-inferior angle of the Masseter; passes forward and upward across the cheek to the angle of the mouth, then ascends along the side of the nose, and ends at the medial commissure of the eye, under the name of the **angular artery**. This vessel, both in the neck and on the face, is remarkably tortuous: in the former situation, to accommodate itself to the movements of the pharynx in deglutition; and in the latter, to the movements of the mandible, lips, and cheeks.

**Relations.**—In the neck, its origin is superficial, being covered by the integument, Platysma, and fascia; it then passes beneath the Digastricus and Stylohyoideus muscles and part of the

<sup>1</sup> The muscular tissue of the lips must be supposed to have been cut away, in order to show the course of the labial arteries.

submaxillary gland, and frequently beneath the hypoglossal nerve. It lies upon the Constrictores pharyngis medius and superior, the latter of which separates it, at the summit of its arch, from the lower and back part of the tonsil. *On the face*, where it passes over the body of the mandible, it is comparatively superficial, lying immediately beneath the Platysma. In its course over the face, it is covered by the integument, the fat of the cheek, and, near the angle of the mouth, by the Platysma, Risorius, and Zygomaticus. It rests on the Buccinator and Caninus, and passes either over or under the infraorbital head of the Quadratus labii superioris. The anterior facial vein lies lateral to the artery, and takes a more direct course across the face, where it is separated from the artery by a considerable interval. In the neck it lies superficial to the artery. The branches of the facial nerve cross the artery from behind forward.

**Branches.**—The branches of the artery may be divided into two sets: those given off in the neck (*cervical*), and those on the face (*facial*).

<i>Cervical Branches.</i>	<i>Facial Branches.</i>
Ascending Palatine.	Inferior Labial.
Tonsillar.	Superior Labial.
Glandular.	Lateral Nasal.
Submental.	Angular.
Muscular.	Muscular.

The **Ascending Palatine Artery** (*a. palatina ascendens*) (Fig. 590) arises close to the origin of the external maxillary artery and passes up between the Styloglossus and Stylopharyngeus to the side of the pharynx, along which it is continued between the Constrictor pharyngis superior and the Pterygoideus internus to near the base of the skull. It divides near the Levator veli palatini into two branches: one follows the course of this muscle, and, winding over the upper border of the Constrictor pharyngis superior, supplies the soft palate and the palatine glands, anastomosing with its fellow of the opposite side and with the descending palatine branch of the internal maxillary artery; the other pierces the Constrictor pharyngis superior and supplies the palatine tonsil and auditory tube, anastomosing with the tonsillar and ascending pharyngeal arteries.

The **Tonsillar Branch** (*ramus tonsillaris*) (Fig. 590) ascends between the Pterygoideus internus and Styloglossus, and then along the side of the pharynx, perforating the Constrictor pharyngis superior, to ramify in the substance of the palatine tonsil and root of the tongue.

The **Glandular Branches** (*rami glandulares; submaxillary branches*) consist of three or four large vessels, which supply the submaxillary gland, some being prolonged to the neighboring muscles, lymph glands, and integument.

The **Submental Artery** (*a. submentalis*) the largest of the cervical branches, is given off from the facial artery just as that vessel quits the submaxillary gland: it runs forward upon the Mylohyoideus, just below the body of the mandible, and beneath the Digastricus. It supplies the surrounding muscles, and anastomoses with the sublingual artery and with the mylohyoid branch of the inferior alveolar; at the symphysis menti it turns upward over the border of the mandible and divides into a superficial and a deep branch. The superficial branch passes between the integument and Quadratus labii inferioris, and anastomoses with the inferior labial artery; the deep branch runs between the muscle and the bone, supplies the lip, and anastomoses with the inferior labial and mental arteries.

The **Inferior Labial Artery** (*a. labialis inferior; inferior coronary artery*) arises near the angle of the mouth; it passes upward and forward beneath the Triangularis and, penetrating the Orbicularis oris, runs in a tortuous course along the edge of the lower lip between this muscle and the mucous membrane. It supplies the labial glands, the mucous membrane, and the muscles of the lower lip; and anastomoses with the artery of the opposite side, and with the mental branch of the inferior alveolar artery.

The **Superior Labial Artery** (*a. labialis superior; superior coronary artery*) is larger and more tortuous than the inferior. It follows a similar course along the edge

of the upper lip, lying between the mucous membrane and the Orbicularis oris, and anastomoses with the artery of the opposite side. It supplies the upper lip, and gives off in its course two or three vessels which ascend to the nose; a **septal branch** ramifies on the nasal septum as far as the point of the nose, and an **alar branch** supplies the ala of the nose.

The **Lateral Nasal branch** is derived from the external maxillary as that vessel ascends along the side of the nose. It supplies the ala and dorsum of the nose, anastomosing with its fellow, with the septal and alar branches, with the dorsal nasal branch of the ophthalmic, and with the infraorbital branch of the internal maxillary.

The **Angular Artery** (*a. angularis*) is the terminal part of the external maxillary; it ascends to the medial angle of the orbit, imbedded in the fibres of the angular head of the Quadratus labii superioris, and accompanied by the angular vein. On the cheek it distributes branches which anastomose with the infraorbital; after supplying the lacrimal sac and Orbicularis oculi, it ends by anastomosing with the dorsal nasal branch of the ophthalmic artery.

The **Muscular Branches** in the neck are distributed to the Pterygoideus internus and Stylohyoideus, and on the face to the Masseter and Buccinator. The anastomoses of the external maxillary artery are very numerous, not only with the vessel of the opposite side, but, *in the neck*, with the sublingual branch of the lingual, with the ascending pharyngeal, and by its ascending palatine and tonsillar branches with the palatine branch of the internal maxillary; *on the face*, with the mental branch of the inferior alveolar as it emerges from the mental foramen, with the transverse facial branch of the superficial temporal, with the infraorbital branch of the internal maxillary, and with the dorsal nasal branch of the ophthalmic.

**Peculiarities.**—The external maxillary artery not infrequently arises in common with the lingual. It varies in its size and in the extent to which it supplies the face; it occasionally ends as the submental, and not infrequently extends only as high as the angle of the mouth or nose. The deficiency is then compensated for by enlargement of one of the neighboring arteries.

**Applied Anatomy.**—The passage of the external maxillary artery over the body of the mandible would appear to afford a favorable position for the application of pressure in cases of hemorrhage from the lips, the result either of an accidental wound or during an operation; but its application is useless, except for a very short time, on account of the free communication of this vessel with its fellow, and with numerous branches from different sources. In a wound involving the lip, it is better to seize the part between the fingers, and evert it, when the bleeding vessel may be at once secured with pressure forceps. In order to prevent hemorrhage in cases of removal of growths from the lip, the latter should be compressed on either side between the fingers and thumb, or by a pair of specially devised clamp forceps, while the surgeon excises the diseased part. In order to stop hemorrhage when the lip has been divided in an operation, it is necessary, when closing the wound, to pass the sutures through the cut edges, almost as deep as its mucous surface; by these means, not only are the cut surfaces more neatly and securely adapted to each other, but the possibility of hemorrhage is prevented by including the divided artery in the suture. If, on the contrary, the suture be passed through merely the cutaneous portion of the wound, hemorrhage occurs into the cavity of the mouth. The student should observe the relation of the angular artery to the lacrimal sac; as the vessel passes up along the medial margin of the orbit, it ascends on the nasal side of the sac. In operating for fistula lacrimonalis, the sac should always be opened on its lateral side in order that this vessel may be avoided.

4. The **occipital artery** (*a. occipitalis*) (Fig. 586) arises from the posterior part of the external carotid, opposite the external maxillary, near the lower margin of the posterior belly of the Digastricus, and ends in the posterior part of the scalp.

**Course and Relations.**—At its origin, it is covered by the posterior belly of the Digastricus and the Stylohyoideus, and the hypoglossal nerve winds around it from behind forward; higher up, it crosses the internal carotid artery, the internal jugular vein, and the vagus and accessory nerves. It next ascends to the interval between the transverse process of the atlas and the mastoid process of the temporal bone, and passes horizontally backward, grooving the surface of the latter bone, being covered by the Sternocleidomastoideus, Splenius capitis, Longissimus capitis, and Digastricus, and resting upon the Rectus capitis lateralis, the Obliquus superior, and Semispinalis capitis. It then changes its course and runs vertically upward, pierces the fascia connecting the cranial attachment of the Trapezius with the Sternocleidomastoideus, and ascends



in a tortuous course in the superficial fascia of the scalp, where it divides into numerous branches, which reach as high as the vertex of the skull and anastomose with the posterior auricular and superficial temporal arteries. Its terminal portion is accompanied by the greater occipital nerve.

**Branches.**—The branches of the occipital artery are:

Muscular.	Sternocleidomastoid.	Auricular.
Meningeal.	Descending.	

The **Muscular Branches** (*rami musculares*) supply the Digastricus, Stylohyoideus, Splenius, and Longissimus capitis.

The **Sternocleidomastoid Artery** (*a. sternocleidomastoidea; sternomastoid artery*) generally arises from the occipital close to its commencement, but sometimes springs directly from the external carotid. It passes downward and backward over the hypoglossal nerve, and enters the substance of the muscle, in company with the accessory nerve.

The **Auricular Branch** (*ramus auricularis*) supplies the back of the concha and frequently gives off a branch, which enters the skull through the mastoid foramen and supplies the dura mater, the diploë, and the mastoid cells; this latter branch sometimes arises from the occipital artery, and is then known as the **mastoid branch**.

The **Meningeal Branch** (*ramus meningeus; dural branch*) ascends with the internal jugular vein, and enters the skull through the jugular foramen and condyloid canal, to supply the dura mater in the posterior fossa.

The **Descending Branch** (*ramus descendens; arteria princeps cervicis*) (Fig. 590), the largest branch of the occipital, descends on the back of the neck, and divides into a superficial and deep portion. The superficial portion runs beneath the Splenius, giving off branches which pierce that muscle to supply the Trapezius and anastomose with the ascending branch of the transverse cervical: the deep portion runs down between the Semispinales capitis and colli, and anastomoses with the vertebral and with the *a. profunda cervicalis*, a branch of the costocervical trunk. The anastomosis between these vessels assists in establishing the collateral circulation after ligature of the common carotid or subclavian artery.

The terminal branches of the occipital artery are distributed to the back of the head: they are very tortuous, and lie between the integument and Occipitalis, anastomosing with the artery of the opposite side and with the posterior auricular and temporal arteries, and supplying the Occipitalis, the integument, and pericranium. One of the terminal branches may give off a meningeal twig which passes through the parietal foramen.

5. The **posterior auricular artery** (*a. auricularis posterior*) (Fig. 586) is small and arises from the external carotid, above the Digastricus and Stylohyoideus, opposite the apex of the styloid process. It ascends, under cover of the parotid gland, on the styloid process of the temporal bone, to the groove between the cartilage of the ear and the mastoid process, immediately above which it divides into its auricular and occipital branches.

**Branches.**—Besides several small branches to the Digastricus, Stylohyoideus, and Sternocleidomastoideus, and to the parotid gland, this vessel gives off three branches:

Stylomastoid.	Auricular.	Occipital.
---------------	------------	------------

The **Stylomastoid Artery** (*a. stylomastoidea*) enters the stylomastoid foramen and supplies the tympanic cavity, the tympanic antrum and mastoid cells, and the semicircular canals. In the young subject a branch from this vessel forms, with the anterior tympanic artery from the internal maxillary, a vascular circle, which surrounds the tympanic membrane, and from which delicate vessels ramify on that membrane. It anastomoses with the superficial petrosal branch of the middle meningeal artery by a twig which enters the hiatus canalis facialis.

The **Auricular Branch** (*ramus auricularis*) ascends behind the ear, beneath the Auricularis posterior, and is distributed to the back of the auricula, upon which it ramifies minutely, some branches curving around the margin of the cartilage, others perforating it, to supply the anterior surface. It anastomoses with the parietal and anterior auricular branches of the superficial temporal.

The **Occipital Branch** (*ramus occipitalis*) passes backward, over the Sternocleidomastoideus, to the scalp above and behind the ear. It supplies the Occipitalis and the scalp in this situation and anastomoses with the occipital artery.

6. The **ascending pharyngeal artery** (*a. pharyngea ascendens*) (Fig. 590), the smallest branch of the external carotid, is a long, slender vessel, deeply seated in the neck, beneath the other branches of the external carotid and under the Stylopharyngeus. It arises from the back part of the external carotid, near the commencement of that vessel, and ascends vertically between the internal carotid and the side of the pharynx, to the under surface of the base of the skull, lying on the Longus capitis.

**Branches.**—Its branches are:

Pharyngeal.

Prevertebral.

Palatine.

Inferior Tympanic.

Posterior Meningeal.

The **Pharyngeal Branches** (*rami pharyngei*) are three or four in number. Two of these descend to supply the Constrictores pharyngis medius and inferior and the Stylopharyngeus, ramifying in their substance and in the mucous membrane lining them.

The **Palatine Branch** varies in size, and may take the place of the ascending palatine branch of the facial artery, when that vessel is small. It passes inward upon the Constrictor pharyngis superior, sends ramifications to the soft palate and tonsil, and supplies a branch to the auditory tube.

The **Prevertebral Branches** are numerous small vessels, which supply the Longi capitis and colli, the sympathetic trunk, the hypoglossal and vagus nerves, and the lymph glands; they anastomose with the ascending cervical artery.

The **Inferior Tympanic Artery** (*a. tympanica inferior*) is a small branch which passes through a minute foramen in the petrous portion of the temporal bone, in company with the tympanic branch of the glossopharyngeal nerve, to supply the medial wall of the tympanic cavity and anastomose with the other tympanic arteries.

The **Meningeal Branches** are several small vessels, which supply the dura mater. One, the **posterior meningeal**, enters the cranium through the jugular foramen; a second passes through the foramen lacerum; and occasionally a third through the canal for the hypoglossal nerve.

**Applied Anatomy.**—The ascending pharyngeal artery has been wounded from the throat; as in the case in which the stem of a tobacco pipe was driven into the vessel, causing fatal hemorrhage.

7. The **superficial temporal artery** (*a. temporalis superficialis*) (Fig. 586), the smaller of the two terminal branches of the external carotid, appears, from its direction, to be the continuation of that vessel. It begins in the substance of the parotid gland, behind the neck of the mandible, and crosses over the posterior root of the zygomatic process of the temporal bone; about 5 cm. above this process it divides into two branches, a frontal and a parietal.

**Relations.**—As it crosses the zygomatic process, it is covered by the Auricularis anterior muscle, and by a dense fascia; it is crossed by the temporal and zygomatic branches of the facial nerve and one or two veins, and is accompanied by the auriculotemporal nerve, which lies immediately behind it.

**Branches.**—Besides some twigs to the parotid gland, to the temporomandibular joint, and to the Masseter muscle, its branches are:

Transverse Facial.  
Middle Temporal.

Anterior Auricular.  
Frontal.

Parietal.

The **Transverse Facial Artery** (*a. transversa faciei*) is given off from the superficial temporal before that vessel quits the parotid gland; running forward through the substance of the gland, it passes transversely across the side of the face, between the parotid duct and the lower border of the zygomatic arch, and divides into numerous branches, which supply the parotid gland and duct, the Masseter, and the integument, and anastomose with the external maxillary, masseteric, buccinator, and infraorbital arteries. This vessel rests on the Masseter, and is accompanied by one or two branches of the facial nerve.

The **Middle Temporal Artery** (*a. temporalis media*) arises immediately above the zygomatic arch, and, perforating the temporal fascia, gives branches to the Temporalis, anastomosing with the deep temporal branches of the internal maxillary. It occasionally gives off a **zygomaticoörbital branch**, which runs along the upper border of the zygomatic arch, between the two layers of the temporal fascia, to the lateral angle of the orbit. This branch, which may arise directly from the superficial temporal artery, supplies the Orbicularis oculi, and anastomoses with the lacrimal and palpebral branches of the ophthalmic artery.

The **Anterior Auricular Branches** (*rami auriculares anteriores*) are distributed to the anterior portion of the auricle, the lobule, and part of the external meatus, anastomosing with the posterior auricular.

The **Frontal Branch** (*ramus frontalis; anterior temporal*) runs tortuously upward and forward to the forehead, supplying the muscles, integument, and pericranium in this region, and anastomosing with the supraorbital and frontal arteries.

The **Parietal Branch** (*ramus parietalis; posterior temporal*) larger than the frontal, curves upward and backward on the side of the head, lying superficial to the temporal fascia, and anastomosing with its fellow of the opposite side, and with the posterior auricular and occipital arteries.

**Applied Anatomy.**—The temporal artery, as it crosses the zygomatic process, lies immediately beneath the skin, and its pulsations may be readily felt during the administration of an anesthetic, or under circumstances where the radial pulse is not available; it may be easily compressed against the bone in order to check bleeding from the temporal region of the scalp. When a flap is raised from this part of the head, for trephining, the incision should be shaped like a horseshoe, with its convexity upward, so that the flap shall contain the temporal artery, which ensures a sufficient supply of blood. The same principle is applied, as far as possible, in making incisions to raise flaps in other parts of the scalp. Formerly the operation of arteriotomy was performed upon this vessel in cases of inflammation of the eye or brain, but this operation is now obsolete.

8. The **internal maxillary artery** (*a. maxillaris interna*) (Fig. 587), the larger of the two terminal branches of the external carotid, arises behind the neck of the mandible, and is at first imbedded in the substance of the parotid gland; it passes forward between the ramus of the mandible and the sphenomandibular ligament, and then runs, either superficial or deep to the Pterygoideus externus, to the pterygopalatine fossa. It supplies the deep structures of the face, and may be divided into **mandibular, pterygoid, and pterygopalatine portions**.

The **first or mandibular portion** passes horizontally forward, between the ramus of the mandible and the sphenomandibular ligament, where it lies parallel to and a little below the auriculotemporal nerve; it crosses the inferior alveolar nerve, and runs along the lower border of the Pterygoideus externus.

The **second or pterygoid portion** runs obliquely forward and upward under cover of the ramus of the mandible and insertion of the Temporalis, on the superficial (very frequently on the deep) surface of the Pterygoideus externus; it then passes between the two heads of origin of this muscle and enters the fossa.

The **third or pterygopalatine portion** lies in the pterygopalatine fossa in relation with the sphenopalatine ganglion.

The branches of this vessel may be divided into three groups (Fig. 588), corresponding with its three divisions.




FIG. 587.—The internal maxillary artery.




FIG. 588.—Plan of branches of internal maxillary artery.

**Branches of the First or Mandibular Portions.—**

Anterior Tympanic.  
Deep Auricular.

Middle Meningeal.  
Accessory Meningeal.  
Inferior Alveolar.

The **Anterior Tympanic Artery** (*a. tympanica anterior; tympanic artery*) passes upward behind the temporomandibular articulation, enters the tympanic cavity through the petrotympanic fissure, and ramifies upon the tympanic membrane, forming a vascular circle around the membrane with the stylomastoid branch of the posterior auricular, and anastomosing with the artery of the pterygoid canal and with the caroticotympanic branch from the internal carotid.

The **Deep Auricular Artery** (*a. auricularis profunda*) often arises in common with the preceding. It ascends in the substance of the parotid gland, behind the temporomandibular articulation, pierces the cartilaginous or bony wall of the external acoustic meatus, and supplies its cuticular lining and the outer surface of the tympanic membrane. It gives a branch to the temporomandibular joint.

- The **Middle Meningeal Artery** (*a. meningea media; medidural artery*) is the largest of the arteries which supply the dura mater. It ascends between the sphenomandibular ligament and the Pterygoideus externus, and between the two roots of the auriculotemporal nerve to the foramen spinosum of the sphenoid bone, through which it enters the cranium; it then runs forward in a groove on the great wing of the sphenoid bone, and divides into two branches, anterior and posterior. The **anterior branch**, the larger, crosses the great wing of the sphenoid, reaches the groove, or canal, in the sphenoidal angle of the parietal bone, and then divides into branches which spread out between the dura mater and internal surface of the cranium, some passing upward as far as the vertex, and others backward to the occipital region. The **posterior branch** curves backward on the squama of the temporal bone, and, reaching the parietal some distance in front of its mastoid angle, divides into branches which supply the posterior part of the dura mater and cranium. The branches of the middle meningeal artery are distributed partly to the dura mater, but chiefly to the bones; they anastomose with the arteries of the opposite side, and with the anterior and posterior meningeal.

The middle meningeal on entering the cranium gives off the following branches: (1) Numerous small vessels supply the semilunar ganglion and the dura mater in this situation. (2) A **superficial petrosal branch** enters the hiatus of the facial canal, supplies the facial nerve, and anastomoses with the stylomastoid branch of the posterior auricular artery. (3) A **superior tympanic artery** runs in the canal for the Tensor tympani, and supplies this muscle and the lining membrane of the canal. (4) **Orbital branches** pass through the superior orbital fissure or through separate canals in the great wing of the sphenoid, to anastomose with the lacrimal or other branches of the ophthalmic artery. (5) **Temporal branches** pass through foramina in the great wing of the sphenoid, and anastomose in the temporal fossa with the deep temporal arteries.

**Applied Anatomy.**—The middle meningeal is an artery of considerable surgical importance, as it may be torn in fractures of the temporal region of the skull, or, indeed, by injuries causing separation of the dura mater from the bone, without fracture. The injury may be followed by considerable hemorrhage between the bone and dura mater, which produces symptoms of compression of the brain, and requires trephining for its relief. As the compression implicates the motor region of the cortex, paralysis on the opposite side of the body forms the prominent symptom of the lesion. The anterior branch of this artery crosses the sphenoidal angle of the parietal bone at a point 4 cm. behind the zygomatic process of the frontal bone, and 4.5 cm. above the zygomatic arch. From this point it passes upward and slightly backward to the sagittal suture, lying about 1.25 to 2 cm. behind the coronal suture. The posterior branch runs backward over the squama of the temporal bone. In order to expose the anterior branch of the artery, a point is taken 4 cm. above the zygomatic arch and the same distance behind the zygomatic process of the frontal bone. Here the pin of the trephine is to be applied. A horseshoe-shaped flap, measuring 8 cm. in length and transversely, and consisting of all the structures of the scalp down to and including the pericranium, is first made, with its base just above the zygomatic arch. This flap is reflected and a 2.5 cm. trephine applied. After the crown of bone has been removed, the blood clot is exposed, and gently got rid of, and if possible the bleeding-point must be found and controlled.

The **Accessory Meningeal Branch** (*ramus meningeus accessorius; small meningeal or parridural branch*) is sometimes derived from the preceding. It enters the skull through the foramen ovale, and supplies the semilunar ganglion and dura mater.

The **Inferior Alveolar Artery** (*a. alveolaris inferior; inferior dental artery*) descends with the inferior alveolar nerve to the mandibular foramen on the medial surface of the ramus of the mandible. It runs along the mandibular canal in the substance of the bone, accompanied by the nerve, and opposite the first premolar tooth divides into two branches, incisor and mental. The **incisor branch** is continued forward beneath the incisor teeth as far as the middle line, where it anastomoses with the artery of the opposite side; the **mental branch** escapes with the nerve at the mental foramen, supplies the chin, and anastomoses with the submental and inferior labial arteries. Near its origin the inferior alveolar artery gives off a **lingual branch** which descends with the lingual nerve and supplies the mucous membrane of the mouth. As the inferior alveolar artery enters the foramen, it gives off a **mylohyoid branch** which runs in the mylohyoid groove, and ramifies on the under surface of the Mylohyoideus. The inferior alveolar artery and its incisor branch during their course through the substance of the bone give off a few twigs which are lost in the cancellous tissue, and a series of branches which correspond in number to the roots of the teeth: these enter the minute apertures at the extremities of the roots, and supply the pulp of the teeth.

**Branches of the Second or Pterygoid Portion.—**

Deep Temporal.

Masseteric.

Pterygoid.

Buccinator.

The **Deep Temporal Branches**, two in number, **anterior** and **posterior**, ascend between the Temporalis and the pericranium; they supply the muscle, and anastomose with the middle temporal artery; the anterior communicates with the lacrimal artery by means of small branches which perforate the zygomatic bone and great wing of the sphenoid.

The **Pterygoid Branches** (*rami pterygoidei*), irregular in their number and origin, supply the Pterygoidei.

The **Masseteric Artery** (*a. masseterica*) is small and passes lateralward through the mandibular notch to the deep surface of the Masseter. It supplies the muscle, and anastomoses with the masseteric branches of the external maxillary and with the transverse facial artery.

The **Buccinator Artery** (*a. buccinatoria; buccal artery*) is small and runs obliquely forward, between the Pterygoideus internus and the insertion of the Temporalis, to the outer surface of the Buccinator, to which it is distributed, anastomosing with branches of the external maxillary and with the infraorbital.

**Branches of the Third or Pterygopalatine Portion.—**

Posterior Superior Alveolar.

Artery of the Pterygoid Canal.

Infraorbital.

Pharyngeal.

Descending Palatine.

Sphenopalatine.

The **Posterior Superior Alveolar Artery** (*a. alveolaris superior posterior; alveolar or posterior dental artery*) is given off from the internal maxillary, frequently in conjunction with the infraorbital just as the trunk of the vessel is passing into the pterygopalatine fossa. Descending upon the tuberosity of the maxilla, it divides into numerous branches, some of which enter the alveolar canals, to supply the molar and premolar teeth and the lining of the maxillary sinus, while others are continued forward on the alveolar process to supply the gums.

The **Infraorbital Artery** (*a. infraorbitalis*) appears, from its direction, to be the continuation of the trunk of the internal maxillary, but often *arises* in conjunction with the posterior superior alveolar. It runs along the infraorbital groove and canal with the infraorbital nerve, and emerges on the face through the infraorbital foramen, beneath the infraorbital head of the Quadratus labii superioris. While in the canal, it gives off (*a*) **orbital branches** which assist in supplying the Rectus inferior and Obliquus inferior and the lacrimal sac, and (*b*) **anterior superior alveolar**



The **Anterior Tympanic Artery** (*a. tympanica anterior; tympanic artery*) passes upward behind the temporomandibular articulation, enters the tympanic cavity through the petrotympanic fissure, and ramifies upon the tympanic membrane, forming a vascular circle around the membrane with the stylomastoid branch of the posterior auricular, and anastomosing with the artery of the pterygoid canal and with the caroticotympanic branch from the internal carotid.

The **Deep Auricular Artery** (*a. auricularis profunda*) often arises in common with the preceding. It ascends in the substance of the parotid gland, behind the temporomandibular articulation, pierces the cartilaginous or bony wall of the external acoustic meatus, and supplies its cuticular lining and the outer surface of the tympanic membrane. It gives a branch to the temporomandibular joint.

- The **Middle Meningeal Artery** (*a. meningea media; medidural artery*) is the largest of the arteries which supply the dura mater. It ascends between the sphenomandibular ligament and the Pterygoideus externus, and between the two roots of the auriculotemporal nerve to the foramen spinosum of the sphenoid bone, through which it enters the cranium; it then runs forward in a groove on the great wing of the sphenoid bone, and divides into two branches, anterior and posterior. The **anterior branch**, the larger, crosses the great wing of the sphenoid, reaches the groove, or canal, in the sphenoidal angle of the parietal bone, and then divides into branches which spread out between the dura mater and internal surface of the cranium, some passing upward as far as the vertex, and others backward to the occipital region. The **posterior branch** curves backward on the squama of the temporal bone, and, reaching the parietal some distance in front of its mastoid angle, divides into branches which supply the posterior part of the dura mater and cranium. The branches of the middle meningeal artery are distributed partly to the dura mater, but chiefly to the bones; they anastomose with the arteries of the opposite side, and with the anterior and posterior meningeal.

The middle meningeal on entering the cranium gives off the following branches: (1) Numerous small vessels supply the semilunar ganglion and the dura mater in this situation. (2) A **superficial petrosal branch** enters the hiatus of the facial canal, supplies the facial nerve, and anastomoses with the stylomastoid branch of the posterior auricular artery. (3) A **superior tympanic artery** runs in the canal for the Tensor tympani, and supplies this muscle and the lining membrane of the canal. (4) **Orbital branches** pass through the superior orbital fissure or through separate canals in the great wing of the sphenoid, to anastomose with the lacrimal or other branches of the ophthalmic artery. (5) **Temporal branches** pass through foramina in the great wing of the sphenoid, and anastomose in the temporal fossa with the deep temporal arteries.

**Applied Anatomy.**—The middle meningeal is an artery of considerable surgical importance, as it may be torn in fractures of the temporal region of the skull, or, indeed, by injuries causing separation of the dura mater from the bone, without fracture. The injury may be followed by considerable hemorrhage between the bone and dura mater, which produces symptoms of compression of the brain, and requires trephining for its relief. As the compression implicates the motor region of the cortex, paralysis on the opposite side of the body forms the prominent symptom of the lesion. The anterior branch of this artery crosses the sphenoidal angle of the parietal bone at a point 4 cm. behind the zygomatic process of the frontal bone, and 4.5 cm. above the zygomatic arch. From this point it passes upward and slightly backward to the sagittal suture, lying about 1.25 to 2 cm. behind the coronal suture. The posterior branch runs backward over the squama of the temporal bone. In order to expose the anterior branch of the artery, a point is taken 4 cm. above the zygomatic arch and the same distance behind the zygomatic process of the frontal bone. Here the pin of the trephine is to be applied. A horseshoe-shaped flap, measuring 8 cm. in length and transversely, and consisting of all the structures of the scalp down to and including the pericranium, is first made, with its base just above the zygomatic arch. This flap is reflected and a 2.5 cm. trephine applied. After the crown of bone has been removed, the blood clot is exposed, and gently got rid of, and if possible the bleeding-point must be found and controlled.

The **Accessory Meningeal Branch** (*ramus meningeus accessorius; small meningeal or parvidural branch*) is sometimes derived from the preceding. It enters the skull through the foramen ovale, and supplies the semilunar ganglion and dura mater.

The **Inferior Alveolar Artery** (*a. alveolaris inferior*; *inferior dental artery*) descends with the inferior alveolar nerve to the mandibular foramen on the medial surface of the ramus of the mandible. It runs along the mandibular canal in the substance of the bone, accompanied by the nerve, and opposite the first premolar tooth divides into two branches, incisor and mental. The **incisor branch** is continued forward beneath the incisor teeth as far as the middle line, where it anastomoses with the artery of the opposite side; the **mental branch** escapes with the nerve at the mental foramen, supplies the chin, and anastomoses with the submental and inferior labial arteries. Near its origin the inferior alveolar artery gives off a **lingual branch** which descends with the lingual nerve and supplies the mucous membrane of the mouth. As the inferior alveolar artery enters the foramen, it gives off a **mylohyoid branch** which runs in the mylohyoid groove, and ramifies on the under surface of the Mylohyoideus. The inferior alveolar artery and its incisor branch during their course through the substance of the bone give off a few twigs which are lost in the cancellous tissue, and a series of branches which correspond in number to the roots of the teeth: these enter the minute apertures at the extremities of the roots, and supply the pulp of the teeth.

**Branches of the Second or Pterygoid Portion.—**

Deep Temporal.

Pterygoid.

Masseteric.

Buccinator.

The **Deep Temporal Branches**, two in number, **anterior** and **posterior**, ascend between the Temporalis and the pericranium; they supply the muscle, and anastomose with the middle temporal artery; the anterior communicates with the lacrimal artery by means of small branches which perforate the zygomatic bone and great wing of the sphenoid.

The **Pterygoid Branches** (*rami pterygoidei*), irregular in their number and origin, supply the Pterygoidei.

The **Masseteric Artery** (*a. masseterica*) is small and passes lateralward through the mandibular notch to the deep surface of the Masseter. It supplies the muscle, and anastomoses with the masseteric branches of the external maxillary and with the transverse facial artery.

The **Buccinator Artery** (*a. buccinatoria*; *buccal artery*) is small and runs obliquely forward, between the Pterygoideus internus and the insertion of the Temporalis, to the outer surface of the Buccinator, to which it is distributed, anastomosing with branches of the external maxillary and with the infraorbital.

**Branches of the Third or Pterygopalatine Portion.—**

Posterior Superior Alveolar.

Infraorbital.

Descending Palatine.

Artery of the Pterygoid Canal.

Pharyngeal.

Sphenopalatine.

The **Posterior Superior Alveolar Artery** (*a. alveolaris superior posterior*; *alveolar or posterior dental artery*) is given off from the internal maxillary, frequently in conjunction with the infraorbital just as the trunk of the vessel is passing into the pterygopalatine fossa. Descending upon the tuberosity of the maxilla, it divides into numerous branches, some of which enter the alveolar canals, to supply the molar and premolar teeth and the lining of the maxillary sinus, while others are continued forward on the alveolar process to supply the gums.

The **Infraorbital Artery** (*a. infraorbitalis*) appears, from its direction, to be the continuation of the trunk of the internal maxillary, but often *arises* in conjunction with the posterior superior alveolar. It runs along the infraorbital groove and canal with the infraorbital nerve, and emerges on the face through the infraorbital foramen, beneath the infraorbital head of the Quadratus labii superioris. While in the canal, it gives off (*a*) **orbital branches** which assist in supplying the Rectus inferior and Obliquus inferior and the lacrimal sac, and (*b*) **anterior superior alveolar**

**branches** which descend through the anterior alveolar canals to supply the upper incisor and canine teeth and the mucous membrane of the maxillary sinus. On the face, some branches pass upward to the medial angle of the orbit and the lacrimal sac, anastomosing with the angular branch of the external maxillary artery; others run toward the nose, anastomosing with the dorsal nasal branch of the ophthalmic; and others descend between the Quadratus labii superioris and the Caninus, and anastomose with the external maxillary, transverse facial, and buccinator arteries. The four remaining branches *arise* from that portion of the internal maxillary which is contained in the pterygopalatine fossa.

The **Descending Palatine Artery** (*a. palatina descendens*) descends through the pterygopalatine canal with the anterior palatine branch of the sphenopalatine ganglion, and, emerging from the greater palatine foramen, runs forward in a groove on the medial side of the alveolar border of the hard palate to the incisive canal; the terminal branch of the artery passes upward through this canal to anastomose with the sphenopalatine artery. Branches are distributed to the gums, the palatine glands, and the mucous membrane of the roof of the mouth; while in the pterygopalatine canal it gives off twigs which descend in the lesser palatine canals to supply the soft palate and palatine tonsil, anastomosing with the ascending palatine artery.

**Applied Anatomy.**—The position of the descending palatine artery on the hard palate should be borne in mind in performing an operation for the closure of a cleft in the hard palate, as it is in danger of being wounded, and may give rise to formidable hemorrhage; it has even been found necessary to plug the pterygopalatine canal in order to arrest the bleeding.

The **Artery of the Pterygoid Canal** (*a. canalis pterygoidei*; *Vidian artery*) passes backward along the pterygoid canal with the corresponding nerve. It is distributed to the upper part of the pharynx and to the auditory tube, sending into the tympanic cavity a small branch which anastomoses with the other tympanic arteries.

The **Pharyngeal Branch** is very small; it runs backward through the pharyngeal canal with the pharyngeal nerve, and is distributed to the upper part of the pharynx and to the auditory tube.

The **Sphenopalatine Artery** (*a. sphenopalatina*; *nasopalatine artery*) passes through the sphenopalatine foramen into the cavity of the nose, at the back part of the superior meatus. Here it gives off its **posterior lateral nasal branches** which spread forward over the conchæ and meatuses, anastomose with the ethmoidal arteries and the nasal branches of the descending palatine, and assist in supplying the frontal, maxillary, ethmoidal, and sphenoidal sinuses. Crossing the under surface of the sphenoid the sphenopalatine artery ends on the nasal septum as the **posterior septal branches**; these anastomose with the ethmoidal arteries and the septal branch of the superior labial; one branch descends in a groove on the vomer to the incisive canal and anastomoses with the descending palatine artery.

## THE TRIANGLES OF THE NECK (Fig. 589).

The side of the neck presents a somewhat quadrilateral outline, limited, *above*, by the lower border of the body of the mandible, and an imaginary line extending from the angle of the mandible to the mastoid process; *below*, by the upper border of the clavicle; in *front*, by the middle line of the neck; *behind*, by the anterior margin of the Trapezius. This space is subdivided into two large triangles by the Sternocleidomastoideus, which passes obliquely across the neck, from the sternum and clavicle below, to the mastoid process and occipital bone above. The triangular space in front of this muscle is called the **anterior triangle**; and that behind it, the **posterior triangle**.

**Anterior Triangle.**—The anterior triangle is bounded, in *front*, by the middle line of the neck; *behind*, by the anterior margin of the Sternocleidomastoideus; its *base*, directed upward, is formed by the lower border of the body of the mandible,

and a line extending from the angle of the mandible to the mastoid process; its apex is below, at the sternum. This space is subdivided into four smaller triangles by the Digastricus above, and the superior belly of the Omohyoideus below. These smaller triangles are named the **inferior carotid**, the **superior carotid**, the **submaxillary**, and the **suprahyoid**.




FIG. 589.—The triangles of the neck.

The **Inferior Carotid**, or **Muscular Triangle**, is bounded, in *front*, by the median line of the neck from the hyoid bone to the sternum; *behind*, by the anterior margin of the Sternocleidomastoideus; *above*, by the superior belly of the Omohyoideus. It is covered by the integument, superficial fascia, Platysma, and deep fascia, ramifying in which are some of the branches of the supraclavicular nerves. Beneath these superficial structures are the Sternohyoideus and Sternothyroideus, which, together with the anterior margin of the Sternocleidomastoideus, conceal the lower part of the common carotid artery.<sup>1</sup> This vessel is enclosed within its sheath, together with the internal jugular vein and vagus nerve; the vein lies lateral to the artery on the right side of the neck, but overlaps it below on the left side; the nerve lies between the artery and vein, on a plane posterior to both. In front of the sheath are a few descending filaments from the ansæ hypoglossi; behind the sheath are the inferior thyroid artery, the recurrent nerve, and the sympathetic trunk; and on its medial side, the œsophagus, the trachea, the thyroid gland, and the lower part of the larynx. By cutting into the upper part of this space, and slightly displacing the Sternocleidomastoideus, the common carotid artery may be tied below the Omohyoideus.

The **Superior Carotid**, or **Carotid Triangle**, is bounded, *behind* by the Sternocleidomastoideus; *below*, by the superior belly of the Omohyoideus; and *above*, by the Stylohyoideus and the posterior belly of the Digastricus. It is covered by the integument, superficial fascia, Platysma and deep fascia; ramifying in which are branches of the facial and cutaneous cervical nerves. Its floor is formed by parts of the Thyrohyoideus, Hyoglossus, and the Constrictores pharyngis medius and inferior. This

<sup>1</sup> Therefore the common carotid artery and internal jugular vein are not, strictly speaking, contained in this triangle, since they are covered by the Sternocleidomastoideus; that is to say, they lie under that muscle, which forms the posterior border of the triangle. But as they lie very close to the structures which are really contained in the triangle, and whose position it is essential to remember in operating on this part of the artery, it is expedient to study the relations of all these parts together.

space when dissected is seen to contain the upper part of the common carotid artery, which bifurcates opposite the upper border of the thyroid cartilage into the external and internal carotid. These vessels are somewhat concealed from view by the anterior margin of the Sternocleidomastoideus, which overlaps them. The external and internal carotids lie side by side, the external being the more anterior of the two. The following branches of the external carotid are also met with in this space: the superior thyroid, running forward and downward; the lingual, directly forward; the external maxillary, forward and upward; the occipital, backward; and the ascending pharyngeal, directly upward on the medial side of the internal carotid. The veins met with are: the internal jugular, which lies on the lateral side of the common and internal carotid arteries; and veins corresponding to the above-mentioned branches of the external carotid—viz., the superior thyroid, the lingual, common facial, ascending pharyngeal, and sometimes the occipital—all of which end in the internal jugular. The nerves in this space are the following. In front of the sheath of the common carotid is the ramus descendens hypoglossi. The hypoglossal nerve crosses both the internal and external carotids above, curving around the origin of the occipital artery. Within the sheath, between the artery and vein, and behind both, is the vagus nerve; behind the sheath, the sympathetic trunk. On the lateral side of the vessels, the accessory nerve runs for a short distance before it pierces the Sternocleidomastoideus; and on the medial side of the external carotid, just below the hyoid bone, may be seen the internal branch of the superior laryngeal nerve; and, still more inferiorly, the external branch of the same nerve. The upper portion of the larynx and lower portion of the pharynx are also found in the front part of this space.

The **Submaxillary or Digastric Triangle** corresponds to the region of the neck immediately beneath the body of the mandible. It is bounded, *above*, by the lower border of the body of the mandible, and a line drawn from its angle to the mastoid process; *below*, by the posterior belly of the Digastricus and the Stylohyoideus; *in front*, by the anterior belly of the Digastricus. It is covered by the integument, superficial fascia, Platysma, and deep fascia, ramifying in which are branches of the facial nerve and ascending filaments of the cutaneous cervical nerve. Its *floor* is formed by the Mylohyoideus, Hyoglossus, and Constrictor pharyngis superior. It is divided into an anterior and a posterior part by the stylomandibular ligament. The anterior part contains the submaxillary gland, superficial to which is the anterior facial vein, while imbedded in the gland is the external maxillary artery and its glandular branches; beneath the gland, on the surface of the Mylohyoideus, are the submental artery and the mylohyoid artery and nerve. The posterior part of this triangle contains the external carotid artery, ascending deeply in the substance of the parotid gland; this vessel lies here in front of, and superficial to, the internal carotid, being crossed by the facial nerve, and gives off in its course the posterior auricular, superficial temporal, and internal maxillary branches: more deeply are the internal carotid, the internal jugular vein, and the vagus nerve, separated from the external carotid by the Styloglossus and Stylopharyngeus, and the glossopharyngeal nerve.<sup>1</sup>

The **Suprahyoid Triangle** is limited *behind* by the anterior belly of the Digastricus, *in front* by the middle line of the neck between the mandible and the hyoid bone; *below*, by the body of the hyoid bone; its *floor* is formed by the Mylohyoideus. It contains one or two lymph glands and some small veins; the latter unite to form the anterior jugular vein.

**Posterior Triangle.**—The posterior triangle is bounded, *in front*, by the Sternocleidomastoideus; *behind*, by the anterior margin of the Trapezius; its *base* is formed

<sup>1</sup> The remark made about the inferior carotid triangle applies also to this one. The structures enumerated as contained in its posterior part lie, strictly speaking, beneath the muscles which form the posterior boundary of the triangle; but as it is very important to bear in mind their close relation to the parotid gland, all these parts are spoken of together.

by the middle third of the clavicle; its *apex*, by the occipital bone. The space is crossed, about 2.5 cm. above the clavicle, by the inferior belly of the Omohyoideus, which divides it into two triangles, an **upper or occipital**, and a **lower or subclavian**.

The **Occipital Triangle**, the larger division of the posterior triangle, is bounded, in *front*, by the Sternocleidomastoideus; *behind*, by the Trapezius; *below*, by the Omohyoideus. Its *floor* is formed from above downward by the Splenius capitis, Levator scapulae, and the Scaleri medius and posterior. It is covered by the skin, the superficial and deep fasciæ, and by the Platysma below. The accessory nerve is directed obliquely across the space from the Sternocleidomastoideus, which it pierces, to the under surface of the Trapezius; below, the supraclavicular nerves and the transverse cervical vessels and the upper part of the brachial plexus cross the space. A chain of lymph glands is also found running along the posterior border of the Sternocleidomastoideus, from the mastoid process to the root of the neck.

The **Subclavian Triangle**, the smaller division of the posterior triangle, is bounded, *above*, by the inferior belly of the Omohyoideus; *below*, by the clavicle; its *base* is formed by the posterior border of the Sternocleidomastoideus. Its *floor* is formed by the first rib with the first digitation of the Serratus anterior. The size of the subclavian triangle varies with the extent of attachment of the clavicular portions of the Sternocleidomastoideus and Trapezius, and also with the height at which the Omohyoideus crosses the neck. Its height also varies according to the position of the arm, being diminished by raising the limb, on account of the ascent of the clavicle, and increased by drawing the arm downward, when that bone is depressed. This space is covered by the integument, the superficial and deep fasciæ and the Platysma, and crossed by the supraclavicular nerves. Just above the level of the clavicle, the third portion of the subclavian artery curves lateralward and downward from the lateral margin of the Scaleri anterior, across the first rib, to the axilla, and this is the situation most commonly chosen for ligaturing the vessel. Sometimes this vessel rises as high as 4 cm. above the clavicle; occasionally, it passes in front of the Scaleri anterior, or pierces the fibres of that muscle. The subclavian vein lies behind the clavicle, and is not usually seen in this space; but in some cases it rises as high as the artery, and has even been seen to pass with that vessel behind the Scaleri anterior. The brachial plexus of nerves lies above the artery, and in close contact with it. Passing transversely behind the clavicle are the transverse scapular vessels; and traversing its upper angle in the same direction, the transverse cervical artery and vein. The external jugular vein runs vertically downward behind the posterior border of the Sternocleidomastoideus, to terminate in the subclavian vein; it receives the transverse cervical and transverse scapular veins, which form a plexus in front of the artery, and occasionally a small vein which crosses the clavicle from the cephalic. The small nerve to the Subclavius also crosses this triangle about its middle, and some lymph glands are usually found in the space.

### The Internal Carotid Artery (A. Carotis Interna) (Fig. 590).

The **internal carotid artery** supplies the anterior part of the brain, the eye and its appendages, and sends branches to the forehead and nose. Its size, in the adult, is equal to that of the external carotid, though, in the child, it is larger than that vessel. It is remarkable for the number of curvatures that it presents in different parts of its course. It occasionally has one or two flexures near the base of the skull, while in its passage through the carotid canal and along the side of the body of the sphenoid bone it describes a double curvature and resembles the italic letter S.

**Course and Relations.**—In considering the course and relations of this vessel it may be divided into four portions: **cervical**, **petrous**, **cavernous**, and **cerebral**.



**Cervical Portion.**—This portion of the internal carotid begins at the bifurcation of the common carotid, opposite the upper border of the thyroid cartilage, and runs perpendicularly upward, in front of the transverse processes of the upper three cervical vertebræ, to the carotid canal in the petrous portion of the temporal bone. It is comparatively superficial at its commencement, where it is contained




FIG. 590.—The internal carotid and vertebral arteries. Right side.

in the carotid triangle, and lies behind and lateral to the external carotid, overlapped by the Sternocleidomastoideus, and covered by the deep fascia, Platysma, and integument: it then passes beneath the parotid gland, being crossed by the hypoglossal nerve, the Digastricus and Stylohyoideus, and the occipital and posterior auricular arteries. Higher up, it is separated from the external carotid by the Styloglossus and Stylopharyngeus, the tip of the styloid process and the stylo-

hyoid ligament, the glossopharyngeal nerve and the pharyngeal branch of the vagus. It is in relation, *behind*, with the Longus capitis, the superior cervical ganglion of the sympathetic trunk, and the superior laryngeal nerve; *laterally*, with the internal jugular vein and vagus nerve, the nerve lying on a plane posterior to the artery; *medially*, with the pharynx, superior laryngeal nerve, and ascending pharyngeal artery. At the base of the skull the glossopharyngeal, vagus, accessory, and hypoglossal nerves lie between the artery and the internal jugular vein.

**Petrous Portion.**—When the internal carotid artery enters the canal in the petrous portion of the temporal bone, it first ascends a short distance, then curves forward and medialward, and again ascends as it leaves the canal to enter the cavity of the skull between the lingula and petrosal process of the sphenoid. The artery lies at first in front of the cochlea and tympanic cavity; from the latter cavity it is separated by a thin, bony lamella, which is cribriform in the young subject, and often partly absorbed in old age. Farther forward it is separated from the semilunar ganglion by a thin plate of bone, which forms the floor of the fossa for the ganglion and the roof of the horizontal portion of the canal. Frequently this bony plate is more or less deficient, and then the ganglion is separated from the artery by fibrous membrane. The artery is separated from the bony wall of the carotid canal by a prolongation of dura mater, and is surrounded by a number of small veins and by filaments of the carotid plexus, derived from the ascending branch of the superior cervical ganglion of the sympathetic trunk.

**Cavernous Portion.**—In this part of its course, the artery is situated between the layers of the dura mater forming the cavernous sinus, but covered by the lining membrane of the sinus. It at first ascends toward the posterior clinoid process, then passes forward by the side of the body of the sphenoid bone, and again curves upward on the medial side of the anterior clinoid process, and perforates the dura mater forming the roof of the sinus. This portion of the artery is surrounded by filaments of the sympathetic nerve, and on its lateral side is the abducent nerve.

**Cerebral Portion.**—Having perforated the dura mater on the medial side of the anterior clinoid process, the internal carotid passes between the optic and oculomotor nerves to the anterior perforated substance at the medial extremity of the lateral cerebral fissure, where it gives off its terminal or cerebral branches.

**Peculiarities.**—The length of the internal carotid varies according to the length of the neck, and also according to the point of bifurcation of the common carotid. It arises sometimes from the arch of the aorta; in such rare instances, this vessel has been found to be placed nearer the middle line of the neck than the external carotid, as far upward as the larynx, when the latter vessel crossed the internal carotid. The course of the artery, instead of being straight, may be very tortuous. A few instances are recorded in which this vessel was altogether absent; in one of these the common carotid passed up the neck, and gave off the usual branches of the external carotid; the cranial portion of the internal carotid was replaced by two branches of the internal maxillary, which entered the skull through the foramen rotundum and foramen ovale, and joined to form a single vessel.

**Applied Anatomy.**—The cervical part of the internal carotid is very rarely wounded. It is, however, sometimes injured by a stab or gunshot wound in the neck, or even occasionally by a stab from within the mouth, as when a person receives a thrust from the end of a parasol, or falls down with a tobacco pipe in his mouth. Although the internal carotid lies about 2 cm. behind and lateral to the tonsil, instances have occurred in which the artery has been wounded during the operation of excision of the tonsil, and fatal hemorrhage has supervened. The incision for ligature of the cervical portion of the internal carotid should be made along the anterior border of the Sternocleidomastoideus, from the angle of the mandible to the upper border of the thyroid cartilage. The superficial structures being divided, and the Sternocleidomastoideus defined and drawn lateralward, the areolar tissue must be carefully separated and the posterior belly of the Digastricus and the hypoglossal nerve sought for as guides to the vessel. When the artery is found, the external carotid should be drawn medialward and the Digastricus upward, and the aneurism needle passed from the lateral to the medial side.

Obstruction of the internal carotid by embolism or thrombosis may give rise to symptoms of cerebral anemia and softening if the collateral circulation is ill-developed. The patient suffers from giddiness, with failure of the mental powers; and convulsions, coma, or hemiplegia on the opposite side of the body, may be observed.

**Branches.**—The cervical portion of the internal carotid gives off no branches. Those from the other portions are:

<i>From the Petrous Portion</i>	{ Caroticotympanic. Artery of the Pterygoid Canal.
<i>From the Cavernous Portion</i>	{ Cavernous. Hypophyseal. Semilunar. Anterior Meningeal. Ophthalmic.
<i>From the Cerebral Portion</i>	{ Anterior Cerebral. Middle Cerebral. Posterior Communicating. Choroidal.

1. The **caroticotympanic branch** (*ramus caroticotympanicus*; *tympanic branch*) is small; it enters the tympanic cavity through a minute foramen in the carotid canal, and anastomoses with the anterior tympanic branch of the internal maxillary, and with the stylomastoid artery.

2. The **artery of the pterygoid canal** (*a. canalis pterygoidei* [Vidii]; *Vidian artery*) is a small, inconstant branch which passes into the pterygoid canal and anastomoses with a branch of the internal maxillary artery.

3. The **cavernous branches** are numerous small vessels which supply the hypophysis, the semilunar ganglion, and the walls of the cavernous and inferior petrosal sinuses. Some of them anastomose with branches of the middle meningeal.

4. The **hypophyseal branches** are one or two minute vessels supplying the hypophysis.

5. The **semilunar branches** are small vessels to the semilunar ganglion.

6. The **anterior meningeal branch** (*a. meningea anterior*) is a small branch which passes over the small wing of the sphenoid to supply the dura mater of the anterior cranial fossa; it anastomoses with the meningeal branch from the posterior ethmoidal artery.

7. The **ophthalmic artery** (*a. ophthalmica*) (Fig. 591) arises from the internal carotid, just as that vessel is emerging from the cavernous sinus, on the medial side of the anterior clinoid process, and enters the orbital cavity through the optic foramen, below and lateral to the optic nerve. It then passes over the nerve to reach the medial wall of the orbit, and thence horizontally forward, beneath the lower border of the Obliquus superior, and divides it into two terminal branches, the **frontal** and **dorsal nasal**. As the artery crosses the optic nerve it is accompanied by the nasociliary nerve, and is separated from the frontal nerve by the Rectus superior and Levator palpebrae superioris.

**Branches.**—The branches of the ophthalmic artery may be divided into an **orbital group**, distributed to the orbit and surrounding parts; and an **ocular group**, to the muscles and bulb of the eye.

#### *Orbital Group.*

Lacrimal.  
Supraorbital.  
Posterior Ethmoidal.  
Anterior Ethmoidal.  
Medial Palpebral.  
Frontal.  
Dorsal Nasal.

#### *Ocular Group.*

Central Artery of the Retina.  
Short Posterior Ciliary.  
Long Posterior Ciliary.  
Anterior Ciliary.  
Muscular.

The **Lacrimal Artery** (*a. lacrimalis*) arises close to the optic foramen, and is one of the largest branches derived from the ophthalmic: not infrequently it is given off before the artery enters the orbit. It accompanies the lacrimal nerve along the upper border of the Rectus lateralis, and supplies the lacrimal gland. Its terminal branches, escaping from the gland, are distributed to the eyelids and conjunctiva: of those supplying the eyelids, two are of considerable size and are named the **lateral palpebral arteries**; they run medialward in the upper and lower lids respectively and anastomose with the medial palpebral arteries, forming an arterial circle in this situation. The lacrimal artery give off one or two **zygomatic branches**, one of which passes through the zygomatico-temporal foramen, to reach the temporal fossa, and anastomoses with the deep temporal arteries; another appears on the cheek through the zygomatico-facial foramen, and anastomoses with the transverse facial. A **recurrent branch** passes backward through the lateral part of the superior orbital fissure to the dura mater, and anastomoses with a branch of the middle meningeal artery. The lacrimal artery is sometimes derived from one of the anterior branches of the middle meningeal artery.




FIG. 591.—The ophthalmic artery and its branches.

The **Supraorbital Artery** (*a. supraorbitalis*) springs from the ophthalmic as that vessel is crossing over the optic nerve. It passes upward on the medial borders of the Rectus superior and Levator palpebrae, and meeting the supraorbital nerve accompanies it between the periosteum and Levator palpebrae to the supraorbital foramen; passing through this it divides into a superficial and a deep branch, which supply the integument, the muscles, and the pericranium of the forehead, anastomosing with the frontal, the frontal branch of the superficial temporal, and the artery of the opposite side. This artery in the orbit supplies the Rectus superior and the Levator palpebrae, and sends a branch across the pulley of the Obliquus superior, to supply the parts at the medial palpebral commissure. At the supra-orbital foramen it frequently transmits a branch to the diploë.

The **Ethmoidal Arteries** are two in number: **posterior** and **anterior**. The **posterior ethmoidal artery**, the smaller, passes through the posterior ethmoidal canal, supplies the posterior ethmoidal cells, and, entering the cranium, gives off a meningeal branch to the dura mater, and nasal branches which descend into the nasal cavity through apertures in the cribriform plate, anastomosing with branches of the sphenopalatine. The **anterior ethmoidal artery** accompanies the nasociliary nerve through the anterior ethmoidal canal, supplies the anterior and middle ethmoidal cells and frontal sinus, and, entering the cranium, gives off a meningeal branch to the dura mater, and nasal branches; these latter descend into the nasal cavity through the slit by the side of the crista galli, and, running along the groove on the inner surface of the nasal bone, supply branches to the lateral wall and septum of the nose, and a terminal branch which appears on the dorsum of the nose between the nasal bone and the lateral cartilage.

The **Medial Palpebral Arteries** (*aa. palpebrales mediales; internal palpebral arteries*), two in number, **superior** and **inferior**, arise from the ophthalmic, opposite the pulley of the Obliquus superior; they leave the orbit to encircle the eyelids near their free margins, forming a superior and an inferior arch, which lie between the Orbicularis oculi and the tarsi. The **superior palpebral** anastomoses, at the lateral angle of the orbit, with the zygomaticoörbital branch of the temporal artery and with the upper of the two lateral palpebral branches from the lacrimal artery; the **inferior palpebral** anastomoses, at the lateral angle of the orbit, with the lower of the two lateral palpebral branches from the lacrimal and with the transverse facial artery, and, at the medial part of the lid, with a branch from the angular artery. From this last anastomoses a branch passes to the nasolacrimal duct, ramifying in its mucous membrane, as far as the inferior meatus of the nasal cavity.

The **Frontal Artery** (*a. frontalis*), one of the terminal branches of the ophthalmic, leaves the orbit at its medial angle with the supratrochlear nerve, and, ascending on the forehead, supplies the integument, muscles, and pericranium, anastomosing with the supraorbital artery, and with the artery of the opposite side.

The **Dorsal Nasal Artery** (*a. dorsalis nasi; nasal artery*), the other terminal branch of the ophthalmic, emerges from the orbit above the medial palpebral ligament, and, after giving a twig to the upper part of the lacrimal sac, divides into two branches, one of which crosses the root of the nosé, and anastomoses with the angular artery, the other runs along the dorsum of the nose, supplies its outer surface; and anastomoses with the artery of the opposite side, and with the lateral nasal branch of the external maxillary.

The **Central Artery of the Retina** (*a. centralis retinae*) is the first and one of the smallest branches of the ophthalmic artery. It runs for a short distance within the dural sheath of the optic nerve, but about 1.25 cm. behind the eyeball it pierces the nerve obliquely, and runs forward in the centre of its substance to the retina. Its mode of distribution will be described with the anatomy of the eye.

The **Ciliary Arteries** (*aa. ciliares*) are divisible into three groups, the long and short, posterior, and the anterior. The **short posterior ciliary arteries** from six to twelve in number, arise from the ophthalmic, or its branches; they pass forward around the optic nerve to the posterior part of the eyeball, pierce the sclera around the entrance of the nerve, and supply the choroid and ciliary processes. The **long posterior ciliary arteries**, two in number, pierce the posterior part of the sclera at some little distance from the optic nerve, and run forward, along either side of the eyeball, between the sclera and choroid, to the ciliary muscle, where they divide into two branches; these form an arterial circle, the **circulus arteriosus major**, around the circumference of the iris, from which numerous converging branches run, in the substance of the iris, to its pupillary margin, where they form a second arterial circle, the **circulus arteriosus minor**. The **anterior ciliary arteries** are derived from



the muscular branches; they run to the front of the eyeball in company with the tendons of the Recti, form a vascular zone beneath the conjunctiva, and then pierce the sclera a short distance from the cornea and end in the *circulus arteriosus major*.

The **Muscular Branches**, (*rami musculares*), two in number, **superior and inferior**, frequently spring from a common trunk. The **superior**, often wanting, supplies the Levator palpebrae superioris, Rectus superior, and Obliquus superior. The **inferior**, more constantly present, passes forward between the optic nerve and Rectus inferior, and is distributed to the Recti lateralis, medialis, and inferior, and the Obliquus inferior. This vessel gives off most of the anterior ciliary arteries. Additional muscular branches are given off from the lacrimal and supraorbital arteries, or from the trunk of the ophthalmic.




FIG. 592.—The arteries of the base of the brain. The temporal pole of the cerebrum and a portion of the cerebellar hemisphere have been removed on the right side.

8. The **anterior cerebral artery** (*a. cerebri anterior*) (Figs. 592, 593, 594) arises from the internal carotid, at the medial extremity of the lateral cerebral fissure. It passes forward and medialward across the anterior perforated substance, above the optic nerve, to the commencement of the longitudinal fissure. Here it comes into close relationship with the opposite artery, to which it is connected by a short trunk, the **anterior communicating artery**. From this point the two vessels run side by side in the longitudinal fissure, curve around the genu of the corpus callosum, and turning backward continue along the upper surface of the corpus callosum to its posterior part, where they end by anastomosing with the posterior cerebral arteries.



**Branches.**—In its course the anterior cerebral artery gives off the following branches:

Antero-medial Ganglionic.	Anterior.	Posterior.
Inferior.	Middle.	

The **Antero-medial Ganglionic Branches** are a group of small arteries which arise at the commencement of the anterior cerebral artery; they pierce the anterior perforated substance and lamina terminalis, and supply the rostrum of the corpus




FIG. 593.—Outer surface of cerebral hemisphere, showing areas supplied by cerebral arteries.

callosum, the septum pellucidum, and the head of the caudate nucleus. The **inferior branches**, two or three in number, are distributed to the orbital surface of the frontal lobe, where they supply the olfactory lobe, gyrus rectus, and internal orbital gyrus. The **anterior branches** supply a part of the superior frontal gyrus, and send twigs over the edge of the hemisphere to the superior and middle frontal gyri and upper part of the anterior central gyrus. The **middle branches** supply the corpus callosum, the cingulate gyrus, the medial surface of the superior frontal gyrus, and the upper part of the anterior central gyrus. The **posterior branches** supply the precuneus and adjacent lateral surface of the hemisphere.




FIG. 594.—Medial surface of cerebral hemisphere, showing areas supplied by cerebral arteries.

The **Anterior Communicating Artery** (*a. communicans anterior*) connects the two anterior cerebral arteries across the commencement of the longitudinal fissure. Sometimes this vessel is wanting, the two arteries joining together to form a single trunk, which afterward divides; or it may be wholly, or partially, divided into two. Its length averages about 4 mm., but varies greatly. It gives off some of the antero-medial ganglionic vessels, but these are principally derived from the anterior cerebral.

9. The **middle cerebral artery** (*a. cerebri media*) (Figs. 592, 593), the largest branch of the internal carotid, runs at first lateralward in the lateral cerebral or

Sylvian fissure and then backward and upward on the surface of the insula, where it divides into a number of branches which are distributed to the lateral surface of the cerebral hemisphere.

**Branches.**—The branches of this vessel are the:

Antero-lateral Ganglionic.	Ascending Parietal.
Inferior Lateral Frontal.	Parietotemporal.
Ascending Frontal.	Temporal.

The **Antero-lateral Ganglionic Branches**, a group of small arteries which *arise* at the commencement of the middle cerebral artery, are arranged in two sets: one, the **internal striate**, passes upward through the inner segments of the lentiform nucleus, and supplies it, the caudate nucleus, and the internal capsule; the other, the **external striate**, ascends through the outer segment of the lentiform nucleus, and supplies the caudate nucleus and the thalamus. One artery of this group is of larger size than the rest, and is of special importance, as being the artery in the brain most frequently ruptured; it has been termed by Charcot the **artery of cerebral hemorrhage**. It ascends between the lentiform nucleus and the external capsule, and ends in the caudate nucleus. The **inferior lateral frontal** supplies the inferior frontal gyrus (*Broca's convolution*) and the lateral part of the orbital surface of the frontal lobe. The **ascending frontal** supplies the anterior central gyrus. The **ascending parietal** is distributed to the posterior central gyrus and the lower part of the superior parietal lobule. The **parietotemporal** supplies the supra-marginal and angular gyri, and the posterior parts of the superior and middle temporal gyri. The **temporal branches**, two or three in number, are distributed to the lateral surface of the temporal lobe.

10. The **posterior communicating artery** (*a. communicans posterior*) (Fig. 592) runs backward from the internal carotid, and anastomoses with the posterior cerebral, a branch of the basilar. It varies in size, being sometimes small, and occasionally so large that the posterior cerebral may be considered as arising from the internal carotid rather than from the basilar. It is frequently larger on one side than on the other. From its posterior half are given off a number of small branches, the **postero-medial ganglionic branches**, which, with similar vessels from the posterior cerebral, pierce the posterior perforated substance and supply the medial surface of the thalami and the walls of the third ventricle.

11. The **anterior choroidal** (*a. chorioidea; choroid artery*) is a small but constant branch, which *arises* from the internal carotid, near the posterior communicating artery. Passing backward and lateralward between the temporal lobe and the cerebral peduncle, it enters the inferior horn of the lateral ventricle through the choroidal fissure and ends in the choroid plexus. It is distributed to the hippocampus, fimbria, tela chorioidea of the third ventricle, and choroid plexus.

## THE ARTERIES OF THE BRAIN.

Since the mode of distribution of the vessels of the brain has an important bearing upon a considerable number of the pathological lesions which may occur in this part of the nervous system, it is important to consider a little more in detail the manner in which the vessels are distributed.

The cerebral arteries are derived from the internal carotid and vertebral, which at the base of the brain form a remarkable anastomosis known as the **arterial circle of Willis**. It is formed in front by the anterior cerebral arteries, branches of the internal carotid, which are connected together by the anterior communicating; behind by the two posterior cerebral arteries, branches of the basilar, which are connected on either side with the internal carotid by the posterior communicating



frequently very difficult, and is only effected through vessels of small calibre. As a result of this, obstruction of one of the main branches, or its divisions, may have the effect of producing softening in a limited area of the cortex.

### THE ARTERIES OF THE UPPER EXTREMITY.

The artery which supplies the upper extremity continues as a single trunk from its commencement down to the elbow; but different portions of it have received different names, according to the regions through which they pass. That part of the vessel which extends from its origin to the outer border of the first rib is termed the **subclavian**; beyond this point to the lower border of the axilla it is named the **axillary**; and from the lower margin of the axillary space to the bend of the elbow it is termed **brachial**; here the trunk ends by dividing into two branches the **radial** and **ulnar**.

### THE SUBCLAVIAN ARTERY (A. SUBCLAVIA) (Fig. 596).

On the right side the **subclavian artery** *arises* from the innominate artery behind the right sternoclavicular articulation; on the left side it springs from the arch of the aorta. The two vessels, therefore, in the first part of their course, differ in length, direction, and relation with neighboring structures.

In order to facilitate the description, each subclavian artery is divided into three parts. The first portion extends from the origin of the vessel to the medial border of the *Scalenus anterior*; the second lies behind this muscle; and the third extends from the lateral margin of the muscle to the outer border of the first rib, where it becomes the axillary artery. The first portions of the two vessels require separate descriptions; the second and third parts of the two arteries are practically alike.

**First Part of the Right Subclavian Artery** (Figs. 583, 596).—The first part of the right subclavian artery *arises* from the innominate artery, behind the upper part of the right sternoclavicular articulation, and passes upward and lateralward to the medial margin of the *Scalenus anterior*. It ascends a little above the clavicle, the extent to which it does so varying in different cases.

**Relations.**—It is covered, *in front*, by the integument, superficial fascia, *Platysma*, deep fascia, the clavicular origin of the *Sternocleidomastoideus*, the *Sternohyoideus*, and *Sternothyroideus*, and another layer of the deep fascia. It is crossed by the internal jugular and vertebral veins, by the *vagus* nerve and the cardiac branches of the *vagus* and sympathetic, and by the subclavian loop of the sympathetic trunk which forms a ring around the vessel. The anterior jugular vein is directed lateralward in front of the artery, but is separated from it by the *Sternohyoideus* and *Sternothyroideus*. *Below and behind* the artery is the pleura, which separates it from the apex of the lung; *behind* is the sympathetic trunk, the *Longus colli* and the first thoracic vertebra. The right recurrent nerve winds around the lower and back part of the vessel.

**First Part of the Left Subclavian Artery** (Fig. 583).—The first part of the left subclavian artery *arises* from the arch of the aorta, behind the left common carotid, and at the level of the fourth thoracic vertebra; it ascends in the superior mediastinal cavity to the root of the neck and then arches lateralward to the medial border of the *Scalenus anterior*.

**Relations.**—It is in relation, *in front*, with the *vagus*, cardiac, and phrenic nerves, which lie parallel with it, the left common carotid artery, left internal jugular and vertebral veins, and the commencement of the left innominate vein, and is covered by the *Sternothyroideus*, *Sternohyoideus*, and *Sternocleidomastoideus*; *behind*, it is in relation with the *oesophagus*, thoracic duct, left recurrent nerve, inferior cervical ganglion of the sympathetic trunk, and *Longus colli*; higher up, however, the *oesophagus* and thoracic duct lie to its right side; the latter ultimately arching over the vessel to join the angle of union between the subclavian and internal jugular veins. *Medial* to it are the *oesophagus*, trachea, thoracic duct, and left recurrent nerve; *lateral* to it, the left pleura and lung.

**Second and Third Parts of the Subclavian Artery** (Fig. 596).—The second portion of the subclavian artery lies behind the Scalenus anterior; it is very short, and forms the highest part of the arch described by the vessel.




FIG. 596.—Superficial dissection of the right side of the neck, showing the carotid and subclavian arteries.

**Relations.**—It is covered, *in front*, by the skin, superficial fascia, Platysma, deep cervical fascia, Sternocleidomastoideus, and Scalenus anterior. On the right side of the neck the phrenic nerve is separated from the second part of the artery by the Scalenus anterior, while on the left side it crosses the first part of the artery close to the medial edge of the muscle. *Behind* the vessel are the pleura and the Scalenus medius; *above*, the brachial plexus of nerves; *below*, the pleura. The subclavian vein lies below and in front of the artery, separated from it by the Scalenus anterior.

The **third portion** of the subclavian artery runs downward and lateralward from the lateral margin of the Scalenus anterior to the outer border of the first rib, where it becomes the axillary artery. This is the most superficial portion of the vessel, and is contained in the subclavian triangle (see page 645).

**Relations.**—It is covered, *in front*, by the skin, the superficial fascia, the Platysma, the supraclavicular nerves, and the deep cervical fascia. The external jugular vein crosses its medial part and receives the transverse scapular, transverse cervical, and anterior jugular veins, which frequently form a plexus in front of the artery. Behind the veins, the nerve to the Subclavius descends in front of the artery. The terminal part of the artery lies behind the clavicle and the Subclavius and is crossed by the transverse scapular vessels. The subclavian vein is in front of and at a slightly lower level than the artery. *Behind*, it lies on the lowest trunk of the brachial plexus, which intervenes between it and the Scalenus medius. *Above* and to its *lateral* side are the upper trunks of the brachial plexus and the Omohyoideus. *Below*, it rests on the upper surface of the first rib.

**Peculiarities.**—The subclavian arteries vary in their origin, their course, and the height to which they rise in the neck.

The origin of the right subclavian from the innominate takes place, in some cases, above the sternoclavicular articulation, and occasionally, but less frequently, below that joint. The artery may arise as a separate trunk from the arch of the aorta, and in such cases it may be either the first, second, third, or even the last branch derived from that vessel; in the majority, however, it is the first or last, rarely the second or third. When it is the first branch, it occupies the ordinary position of the innominate artery; when the second or third, it gains its usual position by passing behind the right carotid; and when the last branch, it arises from the left extremity of the arch, and passes obliquely toward the right side, usually behind the trachea, œsophagus, and right carotid, sometimes between the œsophagus and trachea, to the upper border of the first rib, whence it follows its ordinary course. In very rare instances, this vessel arises from the thoracic aorta, as low down as the fourth thoracic vertebra. Occasionally, it perforates the Scalenus anterior; more rarely it passes in front of that muscle. Sometimes the subclavian vein passes with the artery behind the Scalenus anterior. The artery may ascend as high as 4 cm. above the clavicle, or any intermediate point between this and the upper border of the bone, the right subclavian usually ascending higher than the left.

The left subclavian is occasionally joined at its origin with the left carotid.

The left subclavian artery is more deeply placed than the right in the first part of its course, and, as a rule, does not reach quite as high a level in the neck. The posterior border of the Sternocleidomastoideus corresponds pretty closely to the lateral border of the Scalenus anterior, so that the third portion of the artery, the part most accessible for operation, lies immediately lateral to the posterior border of the Sternocleidomastoideus.

**Applied Anatomy.**—An aneurism may form on any part of the subclavian artery, except the intrathoracic portion of the left vessel, which is said never to be the seat of aneurism. The most common site is, however, the third portion, especially on the right side, on account of the greater exposure to injury and the greater amount of use of the right upper extremity. In this situation it may cause pressure on the brachial plexus, producing pain and numbness in the arm and fingers, with loss of power or paralysis of the muscles of these parts. Œdema of the arm may result from pressure on the subclavian vein. The external jugular vein may become distended and varicose. The treatment is unsatisfactory, since proximal ligature cannot be undertaken with much chance of success. If constitutional treatment and direct pressure on the aneurismal sac fail, the best treatment is excision of the sac, if it be small. In aneurisms of the first portion of this artery there is œdema of the head and face, with lividity, congestion of the brain, and semi-consciousness from pressure on the internal jugular vein; and spasmodic action of the Diaphragm from pressure on the phrenic nerve. The collateral circulation is so good that blocking of the subclavian artery by embolism or thrombosis often fails to give rise to any striking signs or symptoms, beyond occasional pains in the neck and shoulder and some degree of weakness and wasting in the muscles of the arm.

**Compression of the subclavian artery** may be required to control hemorrhage, and there is only one situation in which it can be effectually applied, viz., where the artery passes across the upper surface of the first rib. In order to compress the vessel in this situation, the shoulder should be depressed, and the surgeon grasping the side of the neck should press with his thumb in the angle formed by the posterior border of the Sternocleidomastoideus with the upper border of the clavicle, downward, backward, and inward against the rib; if from any cause the shoulder cannot be sufficiently depressed, pressure may be made from before backward, so as to compress the artery against the Scalenus medius and transverse process of the seventh cervical vertebra. In appropriate cases, a preliminary incision may be made through the cervical fascia, and the finger may be pressed down directly upon the artery.

**Ligature of the subclavian artery** may be required in cases of wounds, or of aneurism in the axilla, or in cases of aneurism on the cardiac side of the point of ligature; and the third part of the artery is that which is most favorable for an operation, on account of its being comparatively superficial, and most remote from the origin of the large branches. In those cases where the clavicle is not displaced, this operation may be performed with comparative facility; but where the clavicle is pushed up by a large aneurismal tumor in the axilla, the artery lies at a great depth from the surface, and this materially increases the difficulty of the operation. Under these



circumstances, it becomes a matter of importance to consider the height to which this vessel reaches above the bone. In ordinary cases, its arch is about 1.25 cm. above the clavicle, occasionally as high as 4 cm., and sometimes so low as to be on a level with its upper border. If the clavicle be displaced, these variations will necessarily make the operation more or less difficult, according as the vessel is less or more accessible. The vessel is also ligatured as a preliminary measure to the complete interscapulothoracic amputation of the upper extremity, in which case the transverse scapular and transverse cervical arteries may, if found, be ligatured at the same time, making the "fore-quarter" amputation an almost bloodless procedure.

The procedure in the operation of tying the third portion of the subclavian artery is as follows: The patient being placed on a table in the supine position, with the head drawn over to the opposite side, and the shoulder depressed as much as possible, the integument should be pulled downward over the clavicle, and an incision made through it, upon that bone, from the anterior border of the Trapezius to the posterior border of the Sternocleidomastoideus. The object in drawing the skin downward is to avoid any risk of wounding the external jugular vein, for as it perforates the deep fascia above the clavicle, it cannot be drawn downward with the skin. The soft parts should now be allowed to glide up, and the cervical fascia divided upon a director, and if the interval between the Trapezius and Sternocleidomastoideus be insufficient for the performance of the operation, a portion of one or both may be divided. The external jugular vein will now be seen toward the medial side of the wound; this and the transverse scapular and transverse cervical veins which end in it should be held aside. If the external jugular vein be at all in the way and exposed to injury, it should be tied in two places and divided. The transverse scapular artery should be avoided, and the Omohyoideus held aside if necessary. In the space beneath this muscle, careful search must be made for the vessel; a deep layer of fascia and some connective tissue having been divided carefully, the lateral margin of the Scalenus anterior muscle must be felt for, and the finger being guided by it to the first rib, the pulsation of the subclavian artery will be felt as it passes over the rib. The sheath of the vessels having been opened, the aneurism needle may then be passed around the artery from above downward and medialward so as to avoid including any of the branches of the brachial plexus. If the clavicle be so raised by the tumor that the application of the ligature cannot be effected in this situation, the artery may be tied above the first rib, or even behind the Scalenus anterior; the difficulties of the operation in such a case will be materially increased, on account of the greater depth of the artery, and the alteration in position of the surrounding parts.

The second part of the subclavian artery, the portion which rises highest in the neck, has been considered favorable for the application of the ligature when it is difficult to tie the artery in the third part of its course. There are, however, many objections to the operation in this situation. It is necessary to divide the Scalenus anterior, upon which lies the phrenic nerve, and at the medial side of which is situated the internal jugular vein; and a wound of either of these structures might lead to the most dangerous consequences. Again, the artery is in contact, below, with the pleura, which must also be avoided; and, lastly, the proximity of so many of its large branches arising medially to this point must be a still further objection to the operation. In cases, however, where the sac of an axillary aneurism encroaches on the neck, it may be necessary to divide the lateral half or two-thirds of the Scalenus anterior, so as to place the ligature on the vessel at a greater distance from the sac. The operation is performed exactly in the same way as ligature of the third portion, until the Scalenus anterior is exposed, when it is to be divided on a director (never to a greater extent than its lateral two-thirds), and it immediately retracts. The operation is therefore merely an extension of the operation for ligature of the third portion of the vessel.

In those cases of aneurism of the axillary or subclavian artery which encroach upon the lateral portion of the Scalenus anterior to such an extent that a ligature cannot be applied in that situation, it may be deemed advisable, as a last resource, to tie the first portion of the subclavian artery. On the left side, this operation is almost impracticable; the great depth of the artery from the surface, its intimate relation with the pleura, and its close proximity to the thoracic duct and to so many important veins and nerves, present a series of difficulties which it is next to impossible to overcome.<sup>1</sup> On the right side, the operation is practicable, and has been performed on several occasions. The main objection to the operation in this situation is the smallness of the interval which usually exists between the commencement of the vessel and the origin of the nearest branch. The operation may be performed in the following manner: The patient being placed on the table in the supine position, with the neck extended, an incision should be made along the upper border of the medial part of the clavicle, and a second along the medial border of the Sternocleidomastoideus, meeting the former at an angle. The attachments of both heads of the Sternocleidomastoideus must be divided on a director, and turned lateralward; a few small arteries and veins, and occasionally the anterior jugular, must be avoided, or, if necessary, ligatured in two places and divided, and the Sternohyoideus and Sternothyreoideus divided in the same manner as the preceding muscle. After tearing through the deep fascia, the

<sup>1</sup> The operation has, however, been performed by J. K. Rodgers, by Halsted, and by Schumpert.

internal jugular vein will be seen crossing the subclavian artery; this should be pressed aside, and the artery secured by passing the needle from below upward, by which the pleura is more effectually avoided. The exact position of the vagus, recurrent, and phrenic nerves and the sympathetic trunk should be borne in mind, and the ligature should be applied near the origin of the vertebral, in order to afford as much room as possible for the formation of a coagulum between the ligature and the origin of the vessel. It should be remembered that the right subclavian artery is occasionally deeply placed in the first part of its course, when it arises from the left side of the aortic arch, and passes in such cases behind the cesophagus, or between it and the trachea.

**Collateral Circulation.**—After ligature of the third part of the subclavian artery, the collateral circulation is established mainly by three sets of vessels, thus described in a dissection:

1. A posterior set, consisting of the transverse scapular and the descending ramus of the transverse cervical branches of the subclavian, anastomosing with the subscapular from the axillary.

2. A medial set, produced by the connection of the internal mammary on the one hand, with the highest intercostal and lateral thoracic arteries, and the branches from the subscapular on the other.

3. A middle or axillary set, consisting of a number of small vessels derived from branches of the subclavian, above, and, passing through the axilla, terminating either in the main trunk, or some of the branches of the axillary below. This last set presented most conspicuously the peculiar character of newly formed or, rather, dilated arteries, being excessively tortuous, and forming a complete plexus.

The chief agent in the restoration of the axillary artery below the tumor was the subscapular artery, which communicated most freely with the internal mammary, transverse scapular and descending ramus of the transverse cervical branches of the subclavian, from all of which it received so great an influx of blood as to dilate it to three times its natural size.<sup>1</sup>

When a ligature is applied to the first part of the subclavian artery, the collateral circulation is carried on by: (1) the anastomosis between the superior and inferior thyroids; (2) the anastomosis of the two vertebrales; (3) the anastomosis of the internal mammary with the inferior epigastric and the aortic intercostals; (4) the costocervical anastomosing with the aortic intercostals; (5) the profunda cervicis anastomosing with the descending branch of the occipital; (6) the scapular branches of the thyrocervical trunk anastomosing with the branches of the axillary, and (7) the thoracic branches of the axillary anastomosing with the aortic intercostals.

**Branches.**—The branches of the subclavian artery are:

Vertebral.

Internal mammary.

Thyrocervical.

Costocervical.

On the left side all four branches generally *arise* from the first portion of the vessel; but on the right side (Fig. 596) the costocervical trunk usually springs from the second portion of the vessel. On both sides of the neck, the first three branches arise close together at the medial border of the *Scalenus anterior*; in the majority of cases, a free interval of from 1.25 to 2.5 cm. exists between the commencement of the artery and the origin of the nearest branch.

1. The **vertebral artery** (*a. vertebralis*) (Fig. 590), is the first branch of the subclavian, and *arises* from the upper and back part of the first portion of the vessel. It is surrounded by a plexus of nerve fibres derived from the inferior cervical ganglion of the sympathetic trunk, and ascends through the foramina in the transverse processes of the upper six cervical vertebræ;<sup>2</sup> it then winds behind the superior articular process of the atlas and, entering the skull through the foramen magnum, unites, at the lower border of the pons, with the vessel of the opposite side to form the basilar artery.

**Relations.**—The vertebral artery may be divided into four parts: The **first part** runs upward and backward between the *Longus colli* and the *Scalenus anterior*. In front of it are the internal jugular and vertebral veins, and it is crossed by the inferior thyroid artery; the left vertebral is crossed by the thoracic duct also. Behind it are the transverse process of the seventh cervical vertebra, the sympathetic trunk and its inferior cervical ganglion. The **second part** runs upward through the foramina in the transverse processes of the upper six cervical vertebræ, and is surrounded by branches from the inferior cervical sympathetic ganglion and by a plexus of veins

<sup>1</sup> Guy's Hospital Reports, vol. i, 1836. Case of axillary aneurism, in which Aston Key had tied the subclavian artery on the lateral edge of the *Scalenus anterior*, twelve years previously.

<sup>2</sup> The vertebral artery sometimes enters the foramen in the transverse process of the fifth vertebra, and has been seen entering that of the seventh vertebra.

which unite to form the vertebral vein at the lower part of the neck. It is situated in front of the trunks of the cervical nerves, and pursues an almost vertical course as far as the transverse process of the atlas, above which it runs upward and lateralward to the foramen in the transverse process of the atlas. The **third part** issues from the latter foramen on the medial side of the Rectus capitis lateralis, and curves backward behind the superior articular process of the atlas, the anterior ramus of the first cervical nerve being on its medial side; it then lies in the groove on the upper surface of the posterior arch of the atlas, and enters the vertebral canal by passing beneath the posterior atlantoöccipital membrane. This part of the artery is covered by the Semispinalis capitis and is contained in the **suboccipital triangle**—a triangular space bounded by the Rectus capitis posterior major, the Obliquus superior, and the Obliquus inferior. The first cervical or suboccipital nerve lies between the artery and the posterior arch of the atlas. The **fourth part** pierces the dura mater and inclines medialward to the front of the medulla oblongata; it is placed between the hypoglossal nerve and the anterior root of the first cervical nerve and beneath the first digitation of the ligamentum denticulatum. At the lower border of the pons it unites with the vessel of the opposite side to form the basilar artery.

**Branches.**—The branches of the vertebral artery may be divided into two sets: those given off in the neck, and those within the cranium.

*Cervical Branches.*

Spinal.  
Muscular.

*Cranial Branches.*

Meningeal.  
Posterior Spinal.  
Anterior Spinal.  
Posterior Inferior Cerebellar.  
Medullary.

**Spinal Branches** (*rami spinales*) enter the vertebral canal through the intervertebral foramina, and each divides into two branches. Of these, one passes along the roots of the nerves to supply the medulla spinalis and its membranes, anastomosing with the other arteries of the medulla spinalis; the other divides into an ascending and a descending branch, which unite with similar branches from the arteries above and below, so that two lateral anastomotic chains are formed on the posterior surfaces of the bodies of the vertebræ, near the attachment of the pedicles. From these anastomotic chains branches are supplied to the periosteum and the bodies of the vertebræ, and others form communications with similar branches from the opposite side; from these communications small twigs arise which join similar branches above and below, to form a central anastomotic chain on the posterior surface of the bodies of the vertebræ.

**Muscular Branches** are given off to the deep muscles of the neck, where the vertebral artery curves around the articular process of the atlas. They anastomose with the occipital, and with the ascending and deep cervical arteries.

The **Meningeal Branch** (*ramus meningeus; posterior meningeal branch*) springs from the vertebral opposite the foramen magnum, ramifies between the bone and dura mater in the cerebellar fossa, and supplies the falx cerebelli. It is frequently represented by one or two small branches.

The **Posterior Spinal Artery** (*a. spinalis posterior; dorsal spinal artery*) arises from the vertebral, at the side of the medulla oblongata; passing backward, it descends on this structure, lying in front of the posterior roots of the spinal nerves, and is reinforced by a succession of small branches, which enter the vertebral canal through the intervertebral foramina; by means of these it is continued to the lower part of the medulla spinalis, and to the cauda equina. Branches from the posterior spinal arteries form a free anastomosis around the posterior roots of the spinal nerves, and communicate, by means of very tortuous transverse branches, with the vessels of the opposite side. Close to its origin each gives off an ascending branch, which ends at the side of the fourth ventricle.

The **Anterior Spinal Artery** (*a. spinalis anterior; ventral spinal artery*) is a small branch, which arises near the termination of the vertebral, and, descending in front of the medulla oblongata, unites with its fellow of the opposite side at the

level of the foramen magnum. One of these vessels is usually larger than the other, but occasionally they are about equal in size. The single trunk, thus formed, descends on the front of the medulla spinalis, and is reinforced by a succession of small branches which enter the vertebral canal through the intervertebral foramina; these branches are derived from the vertebral and the ascending cervical of the inferior thyroid in the neck; from the intercostals in the thorax; and from the lumbar, ilio-lumbar, and lateral sacral arteries in the abdomen and pelvis. They unite, by means of ascending and descending branches, to form a single anterior median artery, which extend as far as the lower part of the medulla spinalis, and is continued as a slender twig on the filum terminale. This vessel is placed in the pia mater along the anterior median fissure; it supplies that membrane, and the substance of the medulla spinalis, and sends off branches at its lower part to be distributed to the cauda equina.

**Applied Anatomy.**—Bleeding into the membranes or into the substance of the medulla spinalis itself is not common, but may occur from injuries received at birth when labor is unduly prolonged or instruments are used. It is also met with in chronic insanity, and in tetanus or strychnine poisoning.

The **Posterior Inferior Cerebellar Artery** (*a. cerebelli inferior posterior*) (Fig. 592), the largest branch of the vertebral, winds backward around the upper part of the medulla oblongata, passing between the origins of the vagus and accessory nerves, over the restiform body to the under surface of the cerebellum, where it divides into two branches. The **medial branch** is continued backward to the notch between the two hemispheres of the cerebellum; while the **lateral** supplies the under surface of the cerebellum, as far as its lateral border, where it anastomoses with the anterior inferior cerebellar and the superior cerebellar branches of the basilar artery. Branches from this artery supply the choroid plexus of the fourth ventricle.

The **Medullary Arteries** (*bulbar arteries*) are several minute vessels which spring from the vertebral and its branches and are distributed to the medulla oblongata.

The **Basilar Artery** (*a. basilaris*) (Fig. 592), so named from its position at the base of the skull, is a single trunk formed by the junction of the two vertebral arteries: it extends from the lower to the upper border of the pons, lying in its median groove, under cover of the arachnoid. It ends by dividing into the two posterior cerebral arteries.

Its **branches**, on either side, are the following:

Pontine.	Anterior Inferior Cerebellar.
Internal Auditory.	Superior Cerebellar.
	Posterior Cerebral.

The **pontine branches** (*rami ad pontem; transverse branches*) are a number of small vessels which come off at right angles from either side of the basilar artery and supply the pons and adjacent parts of the brain.

The **internal auditory artery** (*a. auditiva interna; auditory artery*), a long slender branch, *arises* from near the middle of the artery; it accompanies the acoustic nerve through the internal acoustic meatus, and is distributed to the internal ear.

The **anterior inferior cerebellar artery** (*a. cerebelli inferior anterior*) passes backward to be distributed to the anterior part of the under surface of the cerebellum, anastomosing with the posterior inferior cerebellar branch of the vertebral.

The **superior cerebellar artery** (*a. cerebelli superior*) *arises* near the termination of the basilar. It passes lateralward, immediately below the oculomotor nerve, which separates it from the posterior cerebral artery, winds around the cerebellar peduncle, close to the trochlear nerve, and, arriving at the upper surface of the cerebellum, divides into branches which ramify in the pia mater and anastomose with those of the inferior cerebellar arteries. Several branches are given to the

pineal body, the anterior medullary velum, and the tela chorioidea of the third ventricle.

The **posterior cerebral artery** (*a. cerebri posterior*) (Figs. 592, 593, 594) is larger than the preceding, from which it is separated near its origin by the oculomotor nerve. Passing lateralward, parallel to the superior cerebellar artery, and receiving the posterior communicating from the internal carotid, it winds around the cerebral peduncle, and reaches the tentorial surface of the occipital lobe of the cerebrum, where it breaks up into branches for the supply of the temporal and occipital lobes.

The **branches** of the posterior cerebral artery are divided into two sets, **ganglionic** and **cortical**:

Ganglionic	{	Posterior-medial.	Cortical	{	Anterior Temporal.
		Posterior Choroidal.			Posterior Temporal.
		Postero-lateral.			Calcarine.
					Parietooccipital.

**Ganglionic.**—The **postero-medial ganglionic branches** (Fig. 595) are a group of small arteries which *arise* at the commencement of the posterior cerebral artery; these, with similar branches from the posterior communicating, pierce the posterior perforated substance, and supply the medial surfaces of the thalami and the walls of the third ventricle. The **posterior choroidal branches** run forward beneath the splenium of the corpus callosum, and supply the tela chorioidea of the third ventricle and the choroid plexus. The **postero-lateral ganglionic branches** are small arteries which *arise* from the posterior cerebral artery after it has turned around the cerebral peduncle; they supply a considerable portion of the thalamus.

**Cortical.**—The cortical branches are: the **anterior temporal**, distributed to the uncus and the anterior part of the fusiform gyrus; the **posterior temporal**, to the fusiform and the inferior temporal gyri; the **calcarine**, to the cuneus and gyrus lingualis and the back part of the convex surface of the occipital lobe; and the **parietooccipital**, to the cuneus and the precuneus.

2. The **thyrocervical trunk** (*truncus thyrocervicalis*; *thyroid axis*) (Fig. 596) is a short thick trunk, which *arises* from the front of the first portion of the subclavian artery, close to the medial border of the Scalenus anterior, and divides almost immediately into three branches, the **inferior thyroid**, **transverse scapular**, and **transverse cervical**.

The **Inferior Thyroid Artery** (*a. thyreoidea inferior*) passes upward, in front of the vertebral artery and Longus colli; then turns medialward behind the carotid sheath and its contents, and also behind the sympathetic trunk, the middle cervical ganglion resting upon the vessel. Reaching the lower border of the thyroid gland it divides into two branches, which supply the postero-inferior parts of the gland, and anastomose with the superior thyroid, and with the corresponding artery of the opposite side. The recurrent nerve passes upward generally behind, but occasionally in front, of the artery.

The **branches** of the inferior thyroid are:

Inferior Laryngeal..	Esophageal.
Tracheal.	Ascending Cervical.
Muscular.	

The **inferior laryngeal artery** (*a. laryngea inferior*) ascends upon the trachea to the back part of the larynx under cover of the Constrictor pharyngis inferior, in company with the recurrent nerve, and supplies the muscles and mucous membrane of this part, anastomosing with the branch from the opposite side, and with the superior laryngeal branch of the superior thyroid artery.

The **tracheal branches** (*rami tracheales*) are distributed upon the trachea, and anastomose below with the bronchial arteries.

The **oesophageal branches** (*rami oesophagei*) supply the oesophagus, and anastomose with the oesophageal branches of the aorta.

The **ascending cervical artery** (*a. cervicalis ascendens*) is a small branch which *arises* from the inferior thyroid as that vessel is passing behind the carotid sheath; it runs up on the anterior tubercles of the transverse processes of the cervical vertebræ in the interval between the Scalenus anterior and Longus capitis. To the muscles of the neck it gives twigs which anastomose with branches of the vertebral, and it sends one or two spinal branches into the vertebral canal through the intervertebral foramina to be distributed to the medulla spinalis and its membranes, and to the bodies of the vertebræ, in the same manner as the spinal branches from the vertebral. It anastomoses with the ascending pharyngeal and occipital arteries.

The **muscular branches** supply the depressors of the hyoid bone, and the Longus colli, Scalenus anterior, and Constrictor pharyngis inferior.

The **Transverse Scapular Artery** (*a. transversa scapulae; suprascapular artery*) passes at first downward and lateralward across the Scalenus anterior and phrenic nerve, being covered by the Sternocleidomastoideus; it then crosses the subclavian artery and the brachial plexus, and runs behind and parallel with the clavicle and Subclavius, and beneath the inferior belly of the Omohyoideus, to the superior border of the scapula; it passes over the superior transverse ligament of the scapula which separates it from the suprascapular nerve, and enters the supraspinatus fossa (Fig. 597). In this situation it lies close to the bone, and ramifies between it and the Supraspinatus, to which it supplies branches. It then descends behind the neck of the scapula, through the great scapular notch and under cover of the inferior transverse ligament, to reach the infraspinatus fossa, where it anastomoses with the scapular circumflex and the descending branch of the transverse cervical. Besides distributing branches to the Sternocleidomastoideus, Subclavius, and neighboring muscles, it gives off a **suprasternal branch**, which crosses over the sternal end of the clavicle to the skin of the upper part of the chest; and an **acromial branch**, which pierces the Trapezius and supplies the skin over the acromion, anastomosing with the thoracoacromial artery. As the artery passes over the superior transverse ligament of the scapula, it sends a branch into the subscapular fossa, where it ramifies beneath the Subscapularis, and anastomoses with the subscapular artery and with the descending branch of the transverse cervical. It also sends articular branches to the acromioclavicular and shoulder-joints, and a nutrient artery to the clavicle.

The **Transverse Cervical Artery** (*a. transversa colli; transversalis colli artery*) lies at a higher level than the transverse scapular; it passes transversely above the inferior belly of the Omohyoideus to the anterior margin of the Trapezius, beneath which it divides into an **ascending** and a **descending branch**. It crosses in front of




FIG. 597.—The scapular and circumflex arteries.



the phrenic nerve and the Scaleni, and in front of or between the divisions of the brachial plexus, and is covered by the Platysma and Sternocleidomastoideus, and crossed by the Omohyoideus and Trapezius.

The **ascending branch** (*ramus ascendens; superficial cervical artery*) ascends beneath the anterior margin of the Trapezius, distributing branches to it, and to the neighboring muscles and lymph glands in the neck, and anastomosing with the superficial branch of the descending ramus of the occipital artery.

The **descending branch** (*ramus descendens; posterior scapular artery*) (Fig. 597) passes beneath the Levator scapulae to the medial angle of the scapula, and then descends under the Rhomboidei along the vertebral border of that bone as far as the inferior angle. It supplies the Rhomboidei, Latissimus dorsi and Trapezius, and anastomoses with the transverse scapular and subscapular arteries, and with the posterior branches of some of the intercostal arteries.

**Peculiarities.**—The ascending branch of the transverse cervical frequently arises directly from the thyrocervical trunk; and the descending branch from the third, more rarely from the second, part of the subclavian.

3. The **internal mammary artery** (*a. mammaria interna*) (Fig. 598) arises from the under surface of the first portion of the subclavian, opposite the thyrocervical trunk. It descends behind the cartilages of the upper six ribs at a distance of about 1.25 cm. from the margin of the sternum, and at the level of the sixth intercostal space divides into the **musculophrenic** and **superior epigastric arteries**.

**Relations.**—It is directed at first downward, forward, and medialward behind the sternal end of the clavicle, the subclavian and internal jugular veins, and the first costal cartilage, and passes forward close to the lateral side of the innominate vein. As it enters the thorax the phrenic nerve crosses from its lateral to its medial side. Below the first costal cartilage it descends almost vertically to its point of bifurcation. It is covered in front by the cartilages of the upper six ribs and the intervening Intercostales interni and anterior intercostal membranes, and is crossed by the terminal portions of the upper six intercostal nerves. It rests on the pleura, as far as the third costal cartilage; below this level, upon the Transversus thoracis. It is accompanied by a pair of veins; these unite above to form a single vessel, which runs medial to the artery and ends in the corresponding innominate vein.

**Branches.**—The branches of the internal mammary are:

Pericardiophrenic.	Intercostal.
Anterior Mediastinal.	Perforating.
Pericardial.	Musculophrenic.
Sternal.	Superior Epigastric.

The **Pericardiophrenic Artery** (*a. pericardiophrenica; a. comes nervi phrenici*) is a long slender branch, which accompanies the phrenic nerve, between the pleura and pericardium, to the Diaphragm, to which it is distributed; it anastomoses with the musculophrenic and inferior phrenic arteries.

The **Anterior Mediastinal Arteries** (*aa. mediastinales anteriores; mediastinal arteries*) are small vessels, distributed to the areolar tissue and lymph glands in the anterior mediastinal cavity, and to the remains of the thymus.

The **Pericardial Branches** supply the upper part of the anterior surface of the pericardium; the lower part receives branches from the musculophrenic artery.

The **Sternal Branches** (*rami sternales*) are distributed to the Transversus thoracis, and to the posterior surface of the sternum.

The anterior mediastinal, pericardial, and sternal branches, together with some twigs from the pericardiophrenic, anastomose with branches from the intercostal and bronchial arteries, and form a **subpleural mediastinal plexus**.

The **Intercostal Branches** (*rami intercostales; anterior intercostal arteries*) supply the upper five or six intercostal spaces. Two in number in each space, these small vessels pass lateralward, one lying near the lower margin of the rib above, and the

other near the upper margin of the rib below, and anastomose with the intercostal arteries from the aorta. They are at first situated between the pleura and the




FIG. 598.—The internal mammary artery and its branches.

Intercostales interni, and then between the Intercostales interni and externi. They supply the Intercostales and, by branches which perforate the Intercostales externi, the Pectorales and the mamma.

The **Perforating Branches** (*rami perforantes*) correspond to the five or six intercostal spaces. They pass forward through the intercostal spaces, and, curving lateralward, supply the Pectoralis major and the integument. Those which correspond to the second, third, and fourth spaces give branches to the mamma, and during lactation are of large size.

The **Musculophrenic Artery** (*a. musculophrenica*) is directed obliquely downward and lateralward, behind the cartilages of the false ribs; it perforates the Diaphragm at the eighth or ninth costal cartilage, and ends, considerably reduced in size, opposite the last intercostal space. It gives off intercostal branches to the seventh, eighth, and ninth intercostal spaces; these diminish in size as the spaces decrease in length, and are distributed in a manner precisely similar to the intercostals from the internal mammary. The musculophrenic also gives branches to the lower part of the pericardium, and others which run backward to the Diaphragm, and downward to the abdominal muscles.

The **Superior Epigastric Artery** (*a. epigastrica superior*) continues in the original direction of the internal mammary; it descends through the interval between the costal and sternal attachments of the Diaphragm, and enters the sheath of the Rectus abdominis, at first lying behind the muscle, and then perforating and supplying it, and anastomosing with the inferior epigastric artery from the external iliac. Branches perforate the anterior wall of the sheath of the Rectus, and supply the muscles of the abdomen and the integument, and a small branch passes in front of the xiphoid process and anastomoses with the artery of the opposite side. It also gives some twigs to the Diaphragm, while from the artery of the right side small branches extend into the falciform ligament of the liver and anastomose with the hepatic artery.

**Applied Anatomy.**—The internal mammary artery is liable to be wounded in stabs of the chest wall and in the operation of paracentesis pericardii (p. 603). It is most easily reached by a transverse incision in the second intercostal space.

4. The **costocervical trunk** (*truncus costocervicalis; superior intercostal artery*) (Fig. 590) arises from the upper and back part of the subclavian artery, behind the Scalenus anterior on the right side, and medial to that muscle on the left side. Passing backward, it gives off the **profunda cervicalis**, and, continuing as the **highest intercostal artery**, descends behind the pleura in front of the necks of the first and second ribs, and anastomoses with the first aortic intercostal. As it crosses the neck of the first rib it lies medial to the anterior division of the first thoracic nerve, and lateral to the first thoracic ganglion of the sympathetic trunk.

In the first intercostal space, it gives off a branch which is distributed in a manner similar to the distribution of the aortic intercostals. The branch for the second intercostal space usually joins with one from the highest aortic intercostal artery. This branch is not constant, but is more commonly found on the right side; when absent, its place is supplied by an intercostal branch from the aorta. Each intercostal gives off a posterior branch which goes to the posterior vertebral muscles, and sends a small spinal branch through the corresponding intervertebral foramen to the medulla spinalis and its membranes.

The **Profunda Cervicalis** (*a. cervicalis profunda; deep cervical branch*) arises, in most cases, from the costocervical trunk, and is analogous to the posterior branch of an aortic intercostal artery: occasionally it is a separate branch from the subclavian artery. Passing backward, above the eighth cervical nerve and between the transverse process of the seventh cervical vertebra and the neck of the first rib, it runs up the back of the neck, between the Semispinales capitis and colli, as high as the axis vertebra, supplying these and adjacent muscles, and anastomosing with the deep division of the descending branch of the occipital, and with branches of the vertebral. It gives off a spinal twig which enters the canal through the intervertebral foramen between the seventh cervical and first thoracic vertebrae.

## THE AXILLA.

The axilla is a pyramidal space, situated between the upper lateral part of the chest and the medial side of the arm.

**Boundaries.**—The *apex*, which is directed upward toward the root of the neck, corresponds to the interval between the outer border of the first rib, the superior border of the scapula, and the posterior surface of the clavicle, and through it the axillary vessels and nerves pass. The *base*, directed downward, is broad at the chest but narrow and pointed at the arm; it is formed by the integument and a thick layer of fascia, the **axillary fascia**, extending between the lower border of the Pectoralis major in front, and the lower border of the Latissimus dorsi behind. The *anterior wall* is formed by the Pectorales major and minor, the former covering the whole of this wall, the latter only its central part. The space between the upper border of the Pectoralis minor and the clavicle is occupied by the coracoclavicular fascia. The *posterior wall*, which extends somewhat lower than the anterior, is formed by the Subscapularis above, the Teres major and Latissimus dorsi below. On the *medial side* are the first four ribs with their corresponding Intercostales, and part of the Serratus anterior. On the *lateral side*, where the anterior and posterior walls converge, the space is narrow, and bounded by the humerus, the Coracobrachialis, and the Biceps brachii.

**Contents.**—It contains the axillary vessels, and the brachial plexus of nerves, with their branches, some branches of the intercostal nerves, and a large number of lymph glands, together with a quantity of fat and loose areolar tissue. The axillary artery and vein, with the brachial plexus of nerves, extend obliquely along the lateral boundary of the axilla, from its apex to its base, and are placed much nearer to the anterior than to the posterior wall, the vein lying to the thoracic side of the artery and partially concealing it. At the forepart of the axilla, in contact with the Pectorales, are the thoracic branches of the axillary artery, and along the lower margin of the Pectoralis minor the lateral thoracic artery extends to the side of the chest. At the back part, in contact with the lower margin of the Subscapularis, are the subscapular vessels and nerves; winding around the lateral border of this muscle are the scapular circumflex vessels; and, close to the neck of the humerus, the posterior humeral circumflex vessels and the axillary nerve curve backward to the shoulder. Along the medial or thoracic side no vessel of any importance exists, the upper part of the space being crossed merely by a few small branches from the highest thoracic artery. There are some important nerves, however, in this situation, viz., the long thoracic nerve, descending on the surface of the Serratus anterior, to which it is distributed; and the intercostobrachial nerve, perforating the upper and anterior part of this wall, and passing across the axilla to the medial side of the arm.

The position and arrangement of the lymph glands are described on pages 780 and 781.

**Applied Anatomy.**—The axilla is a space of considerable surgical importance. It transmits the large vessels and nerves to the upper extremity, and these may be the seat of injury or disease; it contains numerous lymph glands which may require removal; in it is a quantity of loose connective and adipose tissue which may be readily infiltrated with blood or inflammatory exudation; and it may be the seat of rapidly growing tumors. Moreover, it is covered at its base by thin skin, which is largely supplied with sebaceous and sweat glands, and is frequently the seat of small cutaneous abscesses and boils.

Penetrating wounds in the axilla are sometimes accompanied by extensive hemorrhage, either from wounds of the main vessels, or of one of the large branches of the axillary artery, *e. g.*, the lateral thoracic or the subscapular. Where the blood cannot find an easy exit externally, it collects in the axillary space and forms a large swelling which projects in the floor of the axilla and also bulges forward the Pectoralis major. The treatment consists in freely opening up the cavity and searching for and securing the bleeding vessel.

When suppuration occurs in the axilla, the arrangement of the fasciæ plays a very important part in the direction which the pus takes. As described on page 528, the coracoclavicular fascia, after covering in the space between the clavicle and the upper border of the Pectoralis minor splits to enclose this muscle, and, reblending at its lower border, becomes incorporated with the axillary fascia at the anterior fold of the axilla. Suppuration may take place either superficial to or beneath this layer of fascia; that is, either between the Pectorales or behind the Pectoralis minor; in the former case, the abscess would point either at the anterior border of the axillary fold, or in the groove between the Deltoideus and the Pectoralis major; in the latter, the pus would have a tendency to surround the vessels and nerves, and ascend into the neck, that being the direction in which there is least resistance. Its progress toward the surface is prevented by the axillary fascia; its progress backward, by the insertion of the Serratus anterior; forward, by the coracoclavicular fascia; medialward, by the wall of the thorax; and lateralward, by the upper limb. The pus in these cases, after extending into the neck, has been known to spread through the superior opening of the thorax into the mediastinal cavity. Instances have been recorded where the pus found its way along the course of the vessels into the upper arm.

When opening an axillary abscess, the knife should be entered in the floor of the axilla, midway between the anterior and posterior margins and near the thoracic side of the space. After an incision has been made through the skin and fascia it is well to use a director and dressing forceps in the manner directed by Hilton.

The relations of the vessels and nerves in the several parts of the axilla are important, for it is the almost universal plan, in the present day, to remove the glands from the axilla in operating for cancer of the breast. In performing such an operation, it is necessary to proceed with much caution in the direction of the lateral wall and apex of the space, as here the axillary vessels are in danger of being wounded. The subscapular, scapular circumflex, and posterior humeral circumflex vessels on the posterior wall and the thoracic branches along the anterior wall must be avoided. In clearing out the axilla, the axillary vein should be first defined and traced up to the apex of the space by means of a director. The Pectoralis major is retracted by an assistant; or, as is more commonly the practice in the present day, the sternocostal origin of this muscle is first removed. This proceeding not only lessens the chance of recurrence of the disease, but also enables the surgeon to clear out the axillary cavity more thoroughly. When the apex of the space is reached all fat and glands must be carefully removed and the whole axilla cleared by separating the tissues along the medial and posterior walls, so that when the proceeding is completed the axilla is emptied of all its contents except the main vessels and nerves.

### The Axillary Artery (A. Axillaris) (Fig. 599).

The **axillary artery**, the continuation of the subclavian, commences at the outer border of the first rib, and ends at the lower border of the tendon of the Teres major, where it takes the name of brachial. Its direction varies with the position of the limb; thus the vessel is nearly straight when the arm is directed at right angles with the trunk, concave upward when the arm is elevated above this, and convex upward and lateralward when the arm lies by the side. At its origin the artery is very deeply situated, but near its termination is superficial, being covered only by the skin and fascia. To facilitate the description of the vessel it is divided into three portions; the first part lies above, the second behind, and the third below the Pectoralis minor.

**Relations.**—The **first portion** of the axillary artery is covered *anteriorly* by the clavicular portion of the Pectoralis major and the coracoclavicular fascia, and is crossed by the lateral anterior thoracic nerve, and the thoracoacromial and cephalic veins; *posterior* to it are the first intercostal space, the corresponding Intercostalis externus, the first and second digitations of the Serratus anterior, and the long thoracic and medial anterior thoracic nerves, and the medial cord of the brachial plexus; on its *lateral side* is the brachial plexus, from which it is separated by a little areolar tissue; on its *medial*, or thoracic side, is the axillary vein which overlaps the artery. It is enclosed, together with the axillary vein and the brachial plexus, in a fibrous sheath—the **axillary sheath**—continuous above with the deep cervical fascia.

The **second portion** of the axillary artery is covered, *anteriorly*, by the Pectorales major and minor; posterior to it are the posterior cord of the brachial plexus, and some areolar tissue which intervenes between it and the Subscapularis; on the *medial side* is the axillary vein, separated from the artery by the medial cord of the brachial plexus and the medial anterior thoracic nerve; on the *lateral side* is the lateral cord of the brachial plexus. The brachial plexus thus surrounds the artery on three sides, and separates it from direct contact with the vein and adjacent muscles.

The **third portion** of the axillary artery extends from the lower border of the Pectoralis minor to the lower border of the tendon of the Teres major. *In front*, it is covered by the lower part



of the Pectoralis major above, but only by the integument and fascia below; *behind*, it is in relation with the lower part of the Subscapularis, and the tendons of the Latissimus dorsi and Teres major; on its *lateral side* is the Coracobrachialis, and on its *medial* or thoracic side, the axillary vein. The nerves of the brachial plexus bear the following relations to this part of the artery: on the *lateral side* are the lateral head and the trunk of the median, and the musculocutaneous for a short distance; on the *medial side* the ulnar (between the vein and artery) and medial brachial cutaneous (to the medial side of the vein); *in front* are the medial head of the median and the medial antibrachial cutaneous, and *behind*, the radial and axillary, the latter only as far as the lower border of the Subscapularis.




FIG. 599.—The axillary artery and its branches.

**Applied Anatomy.**—*Compression* of the vessel may be required in the removal of tumors, or in amputation of the upper part of the arm; and the only situation in which this can be effectually made is in the lower part of its course; by pressing it against the humerus in this situation, the circulation may be effectually arrested.

With the exception of the popliteal, the axillary artery is perhaps more frequently lacerated than any other artery in the body by violent movements, especially in those cases where its coats are diseased. It has occasionally been ruptured in attempts to reduce old dislocations of the shoulder-joint. This lesion is most likely to occur during the preliminary breaking down of adhesions, in cases where the artery has become fixed to the capsule of the joint. Aneurism of the axillary artery sometimes occurs; a large number of the cases are traumatic in their origin, due to the injuries to which the artery is exposed in the varied, extensive, and often violent movements of the limb.

The *application of a ligature to the axillary artery* may be required in cases of aneurism of the upper part of the brachial, or as a distal operation for aneurism of the subclavian; and there are only two situations in which it can be secured, viz., in the first and in the third parts of its course; for the second part of the artery is so deeply seated, and so closely surrounded with large nerve trunks, that the application of a ligature to it there would be almost impracticable.

In the *third part* of its course the operation is simple, and may be performed in the following manner. The arm is separated from the side, with the hand supinated, and an incision about 5 cm. in length is made through the integument forming the floor of the axilla, a little nearer to the anterior than to the posterior fold of the axilla. After carefully dissecting through the areolar tissue and fascia, the median nerve and axillary vein are exposed; the nerve is displaced to the



lateral, and the vein to the medial side of the arm, the elbow being at the same time bent so as to relax the structures and facilitate their separation; the ligature may be passed around the artery from the ulnar to the radial side. This portion of the artery is occasionally crossed by a muscular slip, the **axillary arch** (p. 524), derived from the *Latissimus dorsi*.

The *first portion* of the axillary artery may be tied in cases of aneurism encroaching so far upward that a ligature cannot be applied to the lower part of the artery. Notwithstanding that this operation has been performed in some few patients with success, its performance is attended with much difficulty and danger. The student will remark that, in this situation, it would be necessary to divide a thick muscle, and, after incising the coracoclavicular fascia, the artery would be exposed at the bottom of a more or less deep space, with the cephalic and axillary veins in such relation with it as must render the application of a ligature to it particularly hazardous. Under such circumstances, it is an easier and, at the same time, more advisable operation, to tie the third part of the subclavian artery. The first part of the axillary can be best secured by a curved incision with the convexity downward from a point 1.25 cm. lateral to the sternoclavicular joint to a point 1.25 cm. on the medial side of the coracoid process. The limb is to be well abducted and the head inclined to the opposite side, and the incision carried through the superficial structures, care being taken of the cephalic vein at the lateral angle of the incision. The clavicular origin of the *Pectoralis major* is then divided in the whole extent of the wound. The arm is now brought to the side, and the upper edge of the *Pectoralis minor* defined and drawn downward. The coracoclavicular fascia is carefully divided on a director, close to the coracoid process, and the axillary sheath exposed; this is to be opened with special care on account of the vein overlapping the artery. The needle should be passed from below, so as to avoid wounding the vein.

**Collateral Circulation after Ligature of the Axillary Artery.**—If the artery be tied above the origin of the thoracoacromial, the collateral circulation will be carried on by the same branches as after the ligature of the third part of the subclavian (p. 658); if at a lower point, between the thoracoacromial and the subscapular, the latter vessel, by its free anastomosis with the transverse scapular and transverse cervical branches of the subclavian, will become the chief agent in carrying on the circulation; the lateral thoracic, if it be below the ligature, will materially contribute by its anastomoses with the intercostal and internal mammary arteries. If the point included in the ligature is below the origin of the subscapular artery, it will most probably also be below the origins of the two humeral circumflex arteries. The chief agents in restoring the circulation will then be the subscapular and the two humeral circumflex arteries anastomosing with the *a. profunda brachii*.

**Branches.**—The branches of the axillary are:

<i>From first part,</i>	Highest Thoracic.	<i>From second part</i>	{Thoracoacromial. Lateral Thoracic.
<i>From third part</i>	{Subscapular. Posterior Humeral Circumflex. Anterior Humeral Circumflex.		

1. The **highest thoracic artery** (*a. thoracalis suprema; superior thoracic artery*) is a small vessel, which may arise from the thoracoacromial. Running forward and medialward along the upper border of the *Pectoralis minor*, it passes between it and the *Pectoralis major* to the side of the chest. It supplies branches to these muscles, and to the parietes of the thorax, and anastomoses with the internal mammary and intercostal arteries.

2. The **thoracoacromial artery** (*a. thoracoacromialis; acromiothoracic artery; thoracic axis*) is a short trunk, which arises from the forepart of the axillary artery, its origin being generally overlapped by the upper edge of the *Pectoralis minor*. Projecting forward to the upper border of this muscle, it pierces the coracoclavicular fascia and divides into four branches—pectoral, acromial, clavicular, and deltoid. The **pectoral branch** descends between the two *Pectorales*, and is distributed to them and to the mamma, anastomosing with the intercostal branches of the internal mammary and with the lateral thoracic. The **acromial branch** runs lateralward over the coracoid process and under the *Deltoideus*, to which it gives branches; it then pierces that muscle and ends on the acromion in an arterial network formed by branches from the transverse scapular, thoracoacromial, and posterior humeral circumflex arteries. The **clavicular branch** runs upward and medialward to the sternoclavicular joint, supplying this articulation, and the *Subclavius*. The

**deltoid (humeral) branch**, often arising with the acromial, crosses over the Pectoralis minor and passes in the same groove as the cephalic vein, between the Pectoralis major and Deltoideus, and gives branches to both muscles.

3. The **lateral thoracic artery** (*a. thoracalis lateralis*; *long thoracic artery*; *external mammary artery*) follows the lower border of the Pectoralis minor to the side of the chest, supplying the Serratus anterior and the Pectoralis, and sending branches across the axilla to the axillary glands and Subscapularis; it anastomoses with the internal mammary, subscapular, and intercostal arteries, and with the pectoral branch of the thoracoacromial. In the female it supplies an **external mammary branch** which turns round the free edge of the Pectoralis major and supplies the mamma.

4. The **subscapular artery** (*a. subscapularis*) the largest branch of the axillary artery, *arises* at the lower border of the Subscapularis, which it follows to the inferior angle of the scapula, where it anastomoses with the lateral thoracic and intercostal arteries and with the descending branch of the transverse cervical, and ends in the neighboring muscles. About 4 cm. from its origin it gives off a branch, the **scapular circumflex artery**.

The **Scapular Circumflex Artery** (*a. circumflexa scapulae*; *dorsalis scapulae artery*) is generally larger than the continuation of the subscapular. It curves around the axillary border of the scapula, traversing the space between the Subscapularis above, the Teres major below, and the long head of the Triceps laterally (Fig. 600); it enters the infraspinatus fossa under cover of the Teres minor, and anastomoses with the transverse scapular artery and the descending branch of the transverse cervical. In its course it gives off two branches: one (*infrascapular*) enters the subscapular fossa beneath the Subscapularis, which it supplies, anastomosing with the transverse scapular artery and the descending branch of the transverse cervical; the other is continued along the axillary border of the scapula, between the Teretes major and minor, and at the dorsal surface of the inferior angle anastomoses with the descending branch of the transverse cervical. In addition to these, small branches are distributed to the back part of the Deltoideus and the long head of the Triceps brachii, anastomosing with an ascending branch of the a. profunda brachii.

5. The **posterior humeral circumflex artery** (*a. circumflexa humeri posterior*; *posterior circumflex artery*) (Fig. 600) *arises* from the axillary artery at the lower border of the Subscapularis, and runs backward with the axillary nerve through the quadrangular space bounded by the Subscapularis and Teres minor above, the Teres major below, the long head of the Triceps brachii medially, and the surgical neck of the humerus laterally. It winds around the neck of the humerus and is distributed to the Deltoideus and shoulder-joint, anastomosing with the anterior humeral circumflex and profunda brachii.




FIG. 600.—The scapular and circumflex arteries.

6. The **anterior humeral circumflex artery** (*a. circumflexa humeri anterior; anterior circumflex artery*) (Fig. 600), considerably smaller than the posterior, *arises* nearly opposite it, from the lateral side of the axillary artery. It runs horizontally, beneath the Coracobrachialis and short head of the Biceps brachii, in front of the neck of the humerus. On reaching the intertubercular sulcus, it gives off a branch which ascends in the sulcus to supply the head of the humerus and the shoulder-joint. The trunk of the vessel is then continued onward beneath the long head of the Biceps brachii and the Deltoideus, and anastomoses with the posterior humeral circumflex artery.

**Peculiarities.**—The branches of the axillary artery vary considerably in different subjects. Occasionally the subscapular, humeral circumflex, and profunda arteries arise from a common trunk, and when this occurs the branches of the brachial plexus surround this trunk instead of the main vessel. Sometimes the axillary artery divides into the radial and ulnar arteries, and occasionally it gives origin to the volar interosseous artery of the forearm.

### The Brachial Artery (A. Brachialis) (Fig. 601).

The **brachial artery** commences at the lower margin of the tendon of the Teres major, and, passing down the arm, ends about 1 cm. below the bend of the elbow, where it divides into the **radial** and **ulnar arteries**. At first the brachial artery lies medial to the humerus; but as it runs down the arm it gradually gets in front of the bone, and at the bend of the elbow it lies midway between its two epicondyles.

**Relations.**—The artery is superficial throughout its entire extent, being covered, *in front*, by the integument and the superficial and deep fasciæ; the lacertus fibrosus (*bicipital fascia*) lies in front of it opposite the elbow and separates it from the vena mediana cubiti; the median nerve crosses from its lateral to its medial side opposite the insertion of the Coracobrachialis. *Behind*, it is separated from the long head of the Triceps brachii by the radial nerve and a. profunda brachii. It then lies upon the medial head of the Triceps brachii, next upon the insertion of the Coracobrachialis, and lastly on the Brachialis. *Laterally*, it is in relation above with the median nerve and the Coracobrachialis, below with the Biceps brachii, the two muscles overlapping the artery to a considerable extent. *Medially*, its upper half is in relation with the medial antibrachial cutaneous and ulnar nerves, its lower half with the median nerve. The basilic vein lies on its medial side, but is separated from it in the lower part of the arm by the deep fascia. The artery is accompanied by two venæ comitantes, which lie in close contact with it, and are connected together at intervals by short transverse branches.

The **Anticubital Fossa**.—At the bend of the elbow the brachial artery sinks deeply into a triangular interval, the **anticubital fossa**. The base of the triangle is directed upward, and is represented by a line connecting the two epicondyles of the humerus; the sides are formed by the medial edge of the Brachioradialis and the lateral margin of the Pronator teres; the floor is formed by the Brachialis and Supinator. This space contains the brachial artery, with its accompanying veins; the radial and ulnar arteries; the median and radial nerves; and the tendon of the Biceps brachii. The brachial artery occupies the middle of the space, and divides opposite the neck of the radius into the radial and ulnar arteries; it is covered, *in front*, by the integument, the superficial fascia, and the vena mediana cubiti, the last being separated from the artery by the lacertus fibrosus. *Behind* it is the Brachialis which separates it from the elbow-joint. The median nerve lies close to the medial side of the artery, above, but is separated from it below by the ulnar head of the Pronator teres. The tendon of the Biceps brachii lies to the lateral side of the artery; the radial nerve is situated upon the Supinator, and concealed by the Brachioradialis.

**Peculiarities of the Brachial Artery as Regards its Course.**—The brachial artery, accompanied by the median nerve, may leave the medial border of the Biceps brachii, and descend toward the medial epicondyle of the humerus; in such cases it usually passes behind the *supracondylar process* of the humerus, from which a fibrous arch is in most cases thrown over the artery; it then runs beneath or through the substance of the Pronator teres, to the bend of the elbow.

This variation bears considerable analogy with the normal condition of the artery in some of the carnivora; it has been referred to in the description of the humerus (p. 312).

**As Regards its Division.**—Occasionally, the artery is divided for a short distance at its upper part into two trunks, which are united below. Frequently the artery divides at a higher level than usual, and the vessels concerned in this high division are three, viz., radial, ulnar, and interosseous. Most frequently the radial is given off high up, the other limb of the bifurcation consisting of the ulnar and interosseous; in some instances the ulnar arises above the ordinary level, and the radial and interosseous form the other limb of the division; occasionally the interosseous arises high up.

Sometimes, long slender vessels, *vasa aberrantia*, connect the brachial or the axillary artery with one of the arteries of the forearm, or branches from them. These vessels usually join the radial.

**Varieties in Muscular Relations.**—The brachial artery is occasionally concealed, in some part of its course, by muscular or tendinous slips derived from the Coracobrachialis, Biceps brachii, Brachialis, or Pronator teres.

**Applied Anatomy.**—In spite of the fact that the brachial artery is very superficial and but little protected by surrounding tissues, it is seldom wounded. This, no doubt, is due to its situation on the medial side of the arm, which is little exposed to injury. Compression of the brachial artery is required in cases of amputation and some other operations in the arm and forearm, and may be effected in almost any part of the course of the artery. If pressure be made in the upper part of the limb, it should be directed lateralward; if in the lower part, backward, as the artery lies on the medial side of the humerus above, and in front of it below. The most favorable situation is about the middle of the arm, where the artery lies on the tendon of the Coracobrachialis on the medial surface of the humerus.

The application of a ligature to the brachial artery may be required in cases of wound of the vessel, and in some cases of wound of the volar arch. It is also sometimes necessary in cases of aneurism of the brachial, radial, ulnar, or interosseous arteries. The artery may be secured in any part of its course. The chief guides in determining its position are the surface markings produced by the medial margins of the Coracobrachialis and Biceps brachii, and the known course of the vessel; its pulsation should be carefully felt for before any operation is performed, as the vessel occasionally deviates from its usual position. It is essential in applying a ligature to this vessel that the arm should be held away from the side, and supported only from the elbow, for if the arm be allowed to rest on any firm structure the Triceps brachii is pressed forward and overlaps the vessel, thus making the operation much more difficult.

In the upper third of the arm the artery may be exposed in the following manner. The patient being placed supine upon a table, the affected limb should be raised from the side, and the hand supinated. An incision about 5 cm. in length is made on the medial side of the Coracobrachialis, and the subjacent fascia cautiously divided, so as to avoid wounding the medial antibrachial cutaneous nerve or basilic vein, as the latter sometimes runs on the surface of the artery as high as the axilla. The fascia having been divided, it should be remembered that the ulnar nerve and the medial antibrachial cutaneous nerve lie on the medial side of the artery, the median nerve




FIG. 601.—The brachial artery.

on the lateral side but occasionally superficial to the artery in this situation, and that the venae comitantes are also in relation with the vessel, one on either side. These being carefully separated, the aneurism needle should be passed around the artery from the medial side.

In the case of a high division, the two arteries are usually placed side by side; and if they are exposed in an operation, the surgeon should endeavor to ascertain, by alternately pressing on each vessel, which is connected with the wound or aneurism, when a ligature may be applied accordingly; if pulsation or hemorrhage ceases only when both vessels are compressed, both must be tied.

In the middle of the arm the brachial artery may be exposed by making an incision along the medial margin of the Biceps brachii. The forearm being bent so as to relax the muscle, it should be drawn slightly aside, and the fascia carefully divided, when the median nerve will be exposed lying upon (sometimes behind) the artery; the nerve being drawn medialward and the muscle lateralward, the artery should be separated from its accompanying veins and secured. In this situation the superior ulnar collateral (*inferior profunda*) may be mistaken for the main trunk, especially if enlarged from the collateral circulation having become established; this may be avoided by directing the incision toward the Biceps brachii, rather than toward the Triceps brachii.

The lower part of the brachial artery is of interest from a surgical point of view, on account of the relation which it bears to the veins most commonly opened in venesection. Of these vessels, the vena mediana cubiti (*median basilic vein*) is the largest and most prominent, and, consequently, the one usually selected for the operation. This vein runs parallel with the brachial artery, from which it is separated by the lacertus fibrosus (*bicipital fascia*), and care should be taken, in opening the vein, not to carry the incision too deep, so as to endanger the artery.

**Collateral Circulation.**—After the application of a ligature to the brachial artery in the upper third of the arm, the circulation is carried on by branches from the humeral circumflex and subscapular arteries anastomosing with ascending branches from the profunda brachii. If the artery be tied below the origin of the profunda brachii and superior ulnar collateral, the circulation is maintained by the branches of these two arteries anastomosing with the inferior ulnar collateral, the radial and ulnar recurrents, and the dorsal interosseous.

**Branches.**—The branches of the brachial artery are:

Profunda Brachii.	Superior Ulnar Collateral.
Nutrient.	Inferior Ulnar Collateral.
	Muscular.

1. The **arteria profunda brachii** (*superior profunda artery*) is a large vessel which arises from the medial and back part of the brachial, just below the lower border of the Teres major. It follows closely the radial nerve, running at first backward between the medial and lateral heads of the Triceps brachii, then along the groove for the radial nerve, where it is covered by the lateral head of the Triceps brachii, to the lateral side of the arm; there it pierces the lateral intermuscular septum, and, descending between the Brachioradialis and the Brachialis to the front of the lateral epicondyle of the humerus, ends by anastomosing with the radial recurrent artery. It gives branches to the Deltoideus and to the muscles between which it lies; it supplies an occasional **nutrient artery** which enters the humerus behind the deltoid tuberosity. A branch ascends between the long and lateral heads of the Triceps brachii to anastomose with the posterior humeral circumflex artery; a **middle collateral branch** descends in the middle head of the Triceps brachii and assists in forming the anastomosis above the olecranon; and, lastly, a **radial collateral branch** runs down behind the lateral intermuscular septum to the back of the lateral epicondyle of the humerus, where it anastomoses with the interosseous recurrent and the inferior ulnar collateral arteries.

2. The **nutrient artery** (*a. nutricia humeri*) of the body of the humerus arises about the middle of the arm and enters the nutrient canal near the insertion of the Coracobrachialis.

3. The **superior ulnar collateral artery** (*a. collateralis ulnaris superior; inferior profunda artery*), of small size, arises from the brachial a little below the middle of the arm; it frequently springs from the upper part of the a. profunda brachii. It pierces the medial intermuscular septum, and descends on the surface of the medial head of the Triceps brachii to the space between the medial epicondyle and



olecranon, accompanied by the ulnar nerve, and ends under the Flexor carpi ulnaris by anastomosing with the posterior ulnar recurrent, and inferior ulnar collateral. It sometimes sends a branch in front of the medial epicondyle, to anastomose with the anterior ulnar recurrent.

4. The **inferior ulnar collateral artery** (*a. collateralis ulnaris inferior; anastomotica magna artery*) arises about 5 cm. above the elbow. It passes medialward upon the Brachialis, and piercing the medial intermuscular septum, winds around the back of the humerus between the Triceps brachii and the bone, forming, by its junction with the profunda brachii, an arch above the olecranon fossa. As the vessel lies on the Brachialis, it gives off branches which ascend to join the superior ulnar collateral: others descend in front of the medial epicondyle, to anastomose with the anterior ulnar recurrent. Behind the medial epicondyle a branch anastomoses with the superior ulnar collateral and posterior ulnar recurrent arteries.

5. The **muscular branches** (*rami musculares*) three or four in number, are distributed to the Coracobrachialis, Biceps brachii, and Brachialis.




FIG. 602.—Diagram of the anastomosis around the elbow-joint.

**The Anastomosis Around the Elbow-joint** (Fig. 602).—The vessels engaged in this anastomosis may be conveniently divided into those situated *in front* of and those *behind* the medial and lateral epicondyles of the humerus. The branches anastomosing *in front* of the medial epicondyle are: the anterior branch of the inferior ulnar collateral, the anterior ulnar recurrent, and the anterior branch of the superior ulnar collateral. Those *behind* the medial epicondyle are: the inferior ulnar collateral, the posterior ulnar recurrent, and the posterior branch of the superior ulnar collateral. The branches anastomosing *in front* of the lateral epicondyle are: the radial recurrent and the terminal part of the profunda brachii. Those *behind* the lateral epicondyle (perhaps more properly described as being situated



between the lateral epicondyle and the olecranon) are: the inferior ulnar collateral, the interosseous recurrent, and the radial collateral branch of the profunda brachii. There is also an arch of anastomosis above the olecranon, formed by the interosseous recurrent joining with the inferior ulnar collateral and posterior ulnar recurrent (Fig. 605).

### The Radial Artery (*A. Radialis*) (Fig. 603).

The **radial artery** appears, from its direction, to be the continuation of the brachial, but it is smaller in calibre than the ulnar. It commences at the bifurcation of the brachial, just below the bend of the elbow, and passes along the radial side of the forearm to the wrist. It then winds backward, around the lateral side of the carpus, beneath the tendons of the *Abductor pollicis longus* and *Extensores pollicis longus* and *brevis* to the upper end of the space between the metacarpal bones of the thumb and index finger. Finally it passes forward between the two heads of the first *Interosseus dorsalis*, into the palm of the hand, where it crosses the metacarpal bones and at the ulnar side of the hand unites with the deep volar branch of the ulnar artery to form the deep volar arch. The radial artery therefore consists of three portions, one in the forearm, a second at the back of the wrist, and a third in the hand.

**Relations.**—(a) *In the forearm* the artery extends from the neck of the radius to the forepart of the styloid process, being placed to the medial side of the body of the bone above, and in front of it below. Its upper part is overlapped by the fleshy belly of the *Brachioradialis*; the rest of the artery is superficial, being covered by the integument and the superficial and deep fasciæ. In its course downward, it lies upon the tendon of the *Biceps brachii*, the *Supinator*, the *Pronator teres*, the radial origin of the *Flexor digitorum sublimis*, the *Flexor pollicis longus*, the *Pronator quadratus*, and the lower end of the radius. In the upper third of its course it lies between the *Brachioradialis* and the *Pronator teres*; in the lower two-thirds, between the tendons of the *Brachioradialis* and *Flexor carpi radialis*. The superficial branch of the radial nerve is close to the lateral side of the artery in the middle third of its course; and some filaments of the lateral antibrachial cutaneous nerve run along the lower part of the artery as it winds around the wrist. The vessel is accompanied by a pair of *venae comitantes* throughout its whole course.

(b) *At the wrist* the artery reaches the back of the carpus by passing between the radial collateral ligament of the wrist and the tendons of the *Abductor pollicis longus* and *Extensor pollicis brevis*. It then descends on the navicular and greater multangular bones, and before disappearing between the heads of the first *Interosseus dorsalis* is crossed by the tendon of the *Extensor pollicis longus*. In the interval between the two *Extensores pollicis* it is crossed by the digital rami of the superficial branch of the radial nerve which go to the thumb and index finger.

(c) *In the hand*, it passes from the upper end of the first interosseous space, between the heads of the first *Interosseus dorsalis*, transversely across the palm between the *Adductor pollicis obliquus* and *Adductor pollicis transversus*, but sometimes piercing the latter muscle, to the base of the metacarpal bone of the little finger, where it anastomoses with the deep volar branch from the ulnar artery, completing the **deep volar arch** (Fig. 604).

**Peculiarities.**—The origin of the radial artery is, in nearly one case in eight, higher than usual; more often it arises from the axillary or upper part of the brachial than from the lower part of the latter vessel. In the forearm it deviates less frequently from its normal position than the ulnar. It has been found lying on the deep fascia instead of beneath it. It has also been observed on the surface of the *Brachioradialis*, instead of under its medial border; and in turning around the wrist, it has been seen lying on, instead of beneath, the *Extensor* tendons of the thumb.

**Applied Anatomy.**—The radial artery is much exposed to injury in its lower third, and is frequently wounded by the hand being driven through a pane of glass, by the slipping of a knife or chisel held in the other hand, etc. The injury may be followed by a traumatic aneurism, for which the operation of laying open the sac and securing the vessel above and below is necessary.

The operation of tying the radial artery is required in cases of wounds either of its trunk, or of some of its branches, or for aneurism; and the vessel may be exposed in any part of its course through the forearm without the division of any muscular fibres. The operation in the middle or distal third of the forearm is easily performed; but in the proximal third, near the elbow, it is attended with some difficulty, from the greater depth of the vessel, and from its being overlapped by the *Brachioradialis*.

To tie the artery in the proximal third, an incision 7 or 8 cm. in length should be made through the integument, in a line drawn from the centre of the bend of the elbow to the front of the styloid process of the radius, avoiding the branches of the median vein; the fascia of the arm being divided,

and the Brachioradialis drawn aside, the artery will be exposed. The venae comitantes should be carefully separated from the vessel and the ligature passed from the radial to the ulnar side.




FIG. 603.—The radial and ulnar arteries.




FIG. 604.—Ulnar and radial arteries. Deep view.

In the middle third of the forearm the artery may be exposed by making an incision of similar length on the medial border of the Brachioradialis. In this situation, the superficial part of the

radial nerve lies in close relation with the lateral side of the artery, and should, as well as the veins, be carefully avoided.

In the distal third, the artery is easily secured by dividing the integument and fascia in the interval between the tendons of the Brachioradialis and Flexor carpi radialis.

**Branches.**—The branches of the radial artery may be divided into three groups, corresponding with the three regions in which the vessel is situated.

<i>In the Forearm.</i>	<i>At the Wrist.</i>	<i>In the Hand.</i>
Radial Recurrent.	Dorsal Carpal.	Princeps Pollicis.
Muscular.	First Dorsal Metacarpal.	Volaris Indicis Radialis.
Volar Carpal.		Volar Metacarpal.
Superficial Volar.		Perforating.
		Recurrent.

The **radial recurrent artery** (*a. recurrens radialis*) arises immediately below the elbow. It ascends between the branches of the radial nerve, lying on the Supinator and then between the Brachioradialis and Brachialis, supplying these muscles and the elbow-joint, and anastomosing with the terminal part of the profunda brachii.

The **muscular branches** (*rami musculares*) are distributed to the muscles on the radial side of the forearm.

The **volar carpal branch** (*ramus carpeus volaris; anterior radial carpal artery*) is a small vessel which arises near the lower border of the Pronator quadratus, and, running across the front of the carpus, anastomoses with the volar carpal branch of the ulnar artery. This anastomosis is joined by a branch from the volar interosseous above, and by recurrent branches from the deep volar arch below, thus forming a **volar carpal net-work** which supplies the articulations of the wrist and carpus.

The **superficial volar branch** (*ramus volaris superficialis; superficialis volae artery*) arises from the radial artery, just where this vessel is about to wind around the lateral side of the wrist. Running forward, it passes through, occasionally over, the muscles of the ball of the thumb, which it supplies, and sometimes anastomoses with the terminal portion of the ulnar artery, completing the **superficial volar arch**. This vessel varies considerably in size: usually it is very small, and ends in the muscles of the thumb; sometimes it is as large as the continuation of the radial.

The **dorsal carpal branch** (*ramus carpeus dorsalis; posterior radial carpal artery*) is a small vessel which arises beneath the Extensor tendons of the thumb; crossing the carpus transversely toward the medial border of the hand, it anastomoses with the dorsal carpal branch of the ulnar and with the volar and dorsal interosseous arteries to form a **dorsal carpal network**. From this network are given off three slender **dorsal metacarpal arteries**, which run downward on the second, third, and fourth Interossei dorsales and bifurcate into the dorsal digital branches for the supply of the adjacent sides of the middle, ring, and little fingers respectively, communicating with the proper volar digital branches of the superficial volar arch. Near their origins they anastomose with the deep volar arch by the **superior perforating arteries**, and near their points of bifurcation with the common volar digital vessels of the superficial volar arch by the **inferior perforating arteries**.

The **first dorsal metacarpal** arises just before the radial artery passes between the two heads of the first Interosseous dorsalis and divides almost immediately into two branches which supply the adjacent sides of the thumb and index finger; the radial side of the thumb receives a branch directly from the radial artery.

The **arteria princeps pollicis** arises from the radial just as it turns medialward to the deep part of the hand; it descends between the first Interosseus dorsalis and Adductor pollicis obliquus, along the ulnar side of the metacarpal bone of the thumb to the base of the first phalanx, where it lies beneath the tendon of the

Flexor pollicis longus and divides into two branches. These make their appearance between the medial and lateral insertions of the Adductor pollicis obliquus, and run along the sides of the thumb, forming on the volar surface of the last phalanx an arch, from which branches are distributed to the integument and subcutaneous tissue of the thumb.

The **arteria volaris indicis radialis** (*radialis indicis artery*) arises close to the preceding, descends between the first Interosseus dorsalis and Adductor pollicis transversus, and runs along the radial side of the index finger to its extremity, where it anastomoses with the proper digital artery, supplying the ulnar side of the finger. At the lower border of the Adductor pollicis transversus this vessel anastomoses with the princeps pollicis, and gives a communicating branch to the superficial volar arch. The a. princeps pollicis and a. volaris indicis radialis may spring from a common trunk termed the **first volar metacarpal artery**.

The **deep volar arch** (*arcus volaris profundus; deep palmar arch*) (Fig. 604) is formed by the anastomosis of the terminal part of the radial artery with the deep volar branch of the ulnar. It lies upon the carpal extremities of the metacarpal bones and on the Interossei, being covered by the Adductor pollicis obliquus, the Flexor tendons of the fingers, and the Lumbricales. Alongside of it, but running in the opposite direction—that is to say, toward the radial side of the hand—is the deep branch of the ulnar nerve.

The **volar metacarpal arteries** (*aa. metacarpeae volares; palmar interosseous arteries*), three or four in number, arise from the convexity of the deep volar arch; they run distally upon the Interossei, and anastomose at the clefts of the fingers with the common digital branches of the superficial volar arch.

The **perforating branches** (*rami perforantes*), three in number, pass backward from the deep volar arch, through the second, third, and fourth interosseous spaces and between the heads of the corresponding Interossei dorsalis, to anastomose with the dorsal metacarpal arteries.

The **recurrent branches** arise from the concavity of the deep volar arch. They ascend in front of the wrist, supply the intercarpal articulations, and end in the volar carpal network.

### The Ulnar Artery (A. Ulnaris) (Fig. 604).

The **ulnar artery**, the larger of the two terminal branches of the brachial, begins a little below the bend of the elbow, and, passing obliquely downward, reaches the ulnar side of the forearm at a point about midway between the elbow and the wrist. It then runs along the ulnar border to the wrist, crosses the transverse carpal ligament on the radial side of the pisiform bone, and immediately beyond this bone divides into two branches, which enter into the formation of the superficial and deep volar arches.

**Relations.**—(a) *In the forearm.*—In its *upper half*, it is deeply seated, being covered by the Pronator teres, Flexor carpi radialis, Palmaris longus, and Flexor digitorum sublimis; it lies upon the Brachialis and Flexor digitorum profundus. The median nerve is in relation with the medial side of the artery for about 2.5 cm. and then crosses the vessel, being separated from it by the ulnar head of the Pronator teres. In the *lower half* of the forearm it lies upon the Flexor digitorum profundus, being covered by the integument and the superficial and deep fasciæ, and placed between the Flexor carpi ulnaris and Flexor digitorum sublimis. It is accompanied by two venæ comitantes, and is overlapped in its middle third by the Flexor carpi ulnaris; the ulnar nerve lies on the medial side of the lower two-thirds of the artery, and the palmar cutaneous branch of the nerve descends on the lower part of the vessel to the palm of the hand.

(b) *At the wrist* (Fig. 603) the ulnar artery is covered by the integument and the volar carpal ligament, and lies upon the transverse carpal ligament. On its medial side is the pisiform bone, and, somewhat behind the artery, the ulnar nerve.

**Peculiarities.**—The ulnar artery varies in its origin in the proportion of about one in thirteen cases; it may arise about 5 to 7 cm. below the elbow, but more frequently higher, the brachial

being more often the source of origin than the axillary. Variations in the position of this vessel are more common than in the radial. When its origin is normal, the course of the vessel is rarely changed. When it arises high up, it is almost invariably superficial to the Flexor muscles in the forearm, lying commonly beneath the fascia, more rarely between the fascia and integument. In a few cases, its position was subcutaneous in the upper part of the forearm, and subaponeurotic in the lower part.

**Applied Anatomy.**—The application of a ligature to this vessel is required in cases of wound of the artery, or of its branches, or in consequence of aneurism. In the upper half of the forearm the artery is deeply seated beneath the superficial Flexor muscles, and the application of a ligature in this situation is attended with some difficulty. An incision is to be made in the course of a line drawn from the front of the medial epicondyle of the humerus to the lateral side of the pisiform bone, so that the centre of the incision is three fingers' breadth below the medial epicondyle. The skin and superficial fascia having been divided, and the deep fascia exposed, the white line which separates the Flexor carpi ulnaris from the other Flexor muscles is to be sought for, and the fascia incised in this line. The Flexor carpi ulnaris is now to be carefully separated from the other muscles, when the ulnar nerve will be exposed lying on the Flexor digitorum profundus, and must be drawn aside. The artery will be found accompanied by its venae comitantes, and may be ligatured as it lies to the lateral side of the nerve. In the middle and lower thirds of the forearm, this vessel may be easily secured by making an incision on the radial side of the tendon of the Flexor carpi ulnaris; when the deep fascia is divided, and the tendon separated from the Flexor sublimis, the vessel will be exposed, accompanied by its venae comitantes, the ulnar nerve lying on its medial side.

**Branches.**—The branches of the ulnar artery may be arranged in the following groups:

<i>In the Forearm</i>	{	Anterior Recurrent.	<i>At the Wrist</i>	{	Volar Carpal.	
		Posterior Recurrent.			Dorsal Carpal.	
		Common Interosseous.	<i>In the Hand</i>		{	Deep Volar.
		Muscular.				Superficial Volar Arch.

The **anterior ulnar recurrent artery** (*a. recurrentes ulnaris anterior*) arises immediately below the elbow-joint, runs upward between the Brachialis and Pronator teres, supplies twigs to those muscles, and, in front of the medial epicondyle, anastomoses with the superior and inferior ulnar collateral arteries.

The **posterior ulnar recurrent artery** (*a. recurrentes ulnaris posterior*) is much larger, and arises somewhat lower than the preceding. It passes backward and medialward on the Flexor digitorum profundus, behind the Flexor digitorum sublimis, and ascends behind the medial epicondyle of the humerus. In the interval between this process and the olecranon, it lies beneath the Flexor carpi ulnaris, and ascending between the heads of that muscle, in relation with the ulnar nerve, it supplies the neighboring muscles and the elbow-joint, and anastomoses with the superior and inferior ulnar collateral and the interosseous recurrent arteries (Fig. 605).

The **common interosseous artery** (*a. interossea communis*) (Fig. 604), about 1 cm. in length, arises immediately below the tuberosity of the radius, and, passing backward to the upper border of the interosseous membrane, divides into two branches, the **volar and dorsal interosseous arteries**.

The **Volar Interosseous Artery** (*a. interossea volaris; anterior interosseous artery*) (Fig. 604), passes down the forearm on the volar surface of the interosseous membrane. It is accompanied by the volar interosseous branch of the median nerve, and overlapped by the contiguous margins of the Flexor digitorum profundus and Flexor pollicis longus, giving off in this situation **muscular branches**, and the **nutrient arteries** of the radius and ulna. At the upper border of the Pronator quadratus it pierces the interosseous membrane and reaches the back of the forearm, where it anastomoses with the dorsal interosseous artery (Fig. 605). It then descends, in company with the terminal portion of the dorsal interosseous nerve, to the back of the wrist to join the dorsal carpal net-work. The volar interosseous artery gives off a slender branch, the **arteria mediana**, which accompanies the median nerve, and gives offsets to its substance; this artery is sometimes much enlarged, and runs

with the nerve into the palm of the hand. Before it pierces the interosseous membrane the volar interosseous sends a branch downward behind the Pronator quadratus to join the volar carpal network.




FIG. 605.—Arteries of the back of the forearm and hand.

The **Dorsal Interosseous Artery** (*a. interossea dorsalis*; *posterior interosseous artery*) (Fig. 605) passes backward between the oblique cord and the upper border of the interosseous membrane. It appears between the contiguous borders of the Supinator and the Abductor pollicis longus, and runs down the back of the forearm between



the superficial and deep layers of muscles, to both of which it distributes branches. Where it lies upon the Abductor pollicis longus and the Extensor pollicis brevis, it is accompanied by the dorsal interosseous nerve. At the lower part of the forearm it anastomoses with the termination of the volar interosseous artery, and with the dorsal carpal network. It gives off, near its origin, the **interosseous recurrent artery**, which ascends to the interval between the lateral epicondyle and olecranon, on or through the fibres of the Supinator, but beneath the Anconaeus, and anastomoses with the radial collateral branch of the profunda brachii, the posterior ulnar recurrent and the inferior ulnar collateral.

The **muscular branches** (*rami musculares*) are distributed to the muscles along the ulnar side of the forearm.

The **volar carpal branch** (*ramus carpeus volares; anterior ulnar carpal artery*) is a small vessel which crosses the front of the carpus beneath the tendons of the Flexor digitorum profundus, and anastomoses with the corresponding branch of the radial artery.

The **dorsal carpal branch** (*ramus carpeus dorsalis; posterior ulnar carpal artery*) arises immediately above the pisiform bone, and winds backward beneath the tendon of the Flexor carpi ulnaris; it passes across the dorsal surface of the carpus beneath the Extensor tendons, to anastomose with a corresponding branch of the radial artery. Immediately after its origin, it gives off a small branch, which runs along the ulnar side of the fifth metacarpal bone, and supplies the ulnar side of the dorsal surface of the little finger.

The **deep volar branch** (*ramus volaris profundus; profunda branch*) (Fig. 604) passes between the Abductor digiti quinti and Flexor digiti quinti brevis and through the origin of the Opponens digiti quinti; it anastomoses with the radial artery, and completes the deep volar arch.

The **superficial volar arch** (*arcus volaris superficialis; superficial palmar arch*) (Fig. 603) is formed by the ulnar artery, and is usually completed by a branch from the a. volaris indicis radialis, but sometimes by the superficial volar or by a branch from the a. princeps pollicis of the radial artery. The arch passes across the palm, describing a curve, with its convexity downward.

**Relations.**—The superficial volar arch is covered by the skin, the Palmaris brevis, and the palmar aponeurosis. It lies upon the transverse carpal ligament, the Flexor digiti quinti brevis and Opponens digiti quinti, the tendons of the Flexor digitorum sublimis, the Lumbricales, and the divisions of the median and ulnar nerves.

Three **Common Volar Digital Arteries** (*aa. digitales volares communes; palmar digital arteries*) (Fig. 603) arise from the convexity of the arch and proceed downward on the second, third, and fourth Lumbricales. Each receives the corresponding volar metacarpal artery and then divides into a pair of **proper volar digital arteries** (*aa. digitales volares propriae; collateral digital arteries*) which run along the contiguous sides of the index, middle, ring, and little fingers, behind the corresponding digital nerves; they anastomose freely in the subcutaneous tissue of the finger tips and by smaller branches near the interphalangeal joints. Each gives off a couple of dorsal branches which anastomose with the dorsal digital arteries, and supply the soft parts on the back of the second and third phalanges, including the matrix of the finger-nail. The proper volar digital artery for medial side of the little finger springs from the ulnar artery under cover of the Palmaris brevis.

**Applied Anatomy.**—Wounds of the volar arches are of special interest, and are always difficult to deal with. When the superficial arch is involved it is generally possible (enlarging the wound when necessary) to secure the vessel and tie it on both sides of the bleeding point; or in cases where it is found impossible to encircle the vessel with a ligature, a pair of hemostatic forceps may be applied and left on for twenty-four or forty-eight hours. Failing this, the wound may be plugged with gauze and an outside dressing carefully bandaged on. The plug should be allowed to remain untouched for three or four days. It is useless in these cases to ligature one of the arteries of the forearm alone, and indeed simultaneous ligature of both radial and ulnar arteries

above the wrist is often unsuccessful, on account of the anastomosis carried on by the carpal arches. Therefore, upon the failure of pressure to arrest hemorrhage, it is expedient to apply a ligature to the brachial artery. When an incision for deep-seated suppuration in the tendon sheath is required, the situation of the superficial arch must always be borne in mind, and the incisions placed either above or below it. The position of the common digital branches of the artery must also be remembered, and incisions must be made opposite the heads of the metacarpal bones and not between them.

## THE ARTERIES OF THE TRUNK.

### THE DESCENDING AORTA.

The descending aorta is divided into two portions, the **thoracic** and **abdominal**, in correspondence with the two great cavities of the trunk in which it is situated.

#### The Thoracic Aorta (*Aorta Thoracalis*) (Fig. 606).

The **thoracic aorta** is contained in the posterior mediastinal cavity. It begins at the lower border of the fourth thoracic vertebra where it is continuous with the aortic arch, and ends in front of the lower border of the twelfth at the aortic hiatus in the Diaphragma. At its commencement, it is situated on the left of the vertebral column; it approaches the median line as it descends; and, at its termination, lies directly in front of the column. The vessel describes a curve which is concave forward, and as the branches given off from it are small, its diminution in size is inconsiderable.

**Relations.**—It is in relation, *anteriorly*, from above downward, with the root of the left lung, the pericardium, the cesophagus, and the Diaphragma; *posteriorly*, with the vertebral column and the hemiazygos veins; on the *right side*, with the azygos vein and thoracic duct; on the *left side*, with the left pleura and lung. The cesophagus, with its accompanying plexus of nerves, lies on the right side of the aorta above; but at the lower part of the thorax it is placed in front of the aorta, and, close to the Diaphragma, is situated on its left side.

**Peculiarities.**—The aorta is occasionally found to be obliterated at the junction of the arch with the thoracic aorta, just below the ductus arteriosus. Whether this is the result of disease, or of congenital malformation, is immaterial to our present purpose; it affords an interesting opportunity of observing the resources of the collateral circulation. The course of the anastomosing vessels, by which the blood is brought from the upper to the lower part of the artery, will be found well described in an account of two cases in the *Pathological Transactions*, vols. viii and x. In the former, Sydney Jones thus sums up the detailed description of the anastomosing vessels: The principal communications by which the circulation was carried on were: (1) The internal mammary, anastomosing with the intercostal arteries, with the inferior phrenic of the abdominal aorta by means of the musculophrenic and pericardiophrenic, and largely with the inferior epigastric. (2) The costocervical trunk, anastomosing anteriorly by means of a large branch with the first aortic intercostal, and posteriorly with the posterior branch of the same artery. (3) The inferior thyroid, by means of a branch about the size of an ordinary radial, forming a communication with the first aortic intercostal. (4) The transverse cervical, by means of very large communications with the posterior branches of the intercostals. (5) The branches (of the subclavian and axillary) going to the side of the chest were large, and anastomosed freely with the lateral branches of the intercostals. In the second case Wood describes the anastomoses in a somewhat similar manner, adding the remark that "the blood which was brought into the aorta through the anastomosis of the intercostal arteries appeared to be expended principally in supplying the abdomen and pelvis; while the supply to the lower extremities had passed through the internal mammary and epigastrics."

In a few cases an apparently double descending thoracic aorta has been found, the two vessels lying side by side, and eventually fusing to form a single tube in the lower part of the thorax or in the abdomen. One of them is the aorta, the other represents a dissecting aortic aneurism which has become canalized; opening above and below into the true aorta, and at first sight presenting the appearances of a proper bloodvessel.

**Applied Anatomy.**—The effects likely to be produced by aneurism of the thoracic aorta, a disease of common occurrence, must now be considered. When the great depth of the vessel from the surface and the number of important structures which surround it are remembered, it may easily be conceived what a variety of obscure symptoms are likely to arise from disease

of this part of the arterial system, and how they may be mistaken for those of other affections. Aneurism of the thoracic aorta most usually extends backward, along the left side of the vertebral column, producing absorption of the bodies of the vertebræ, with curvature of the column; while the irritation or pressure on the medulla spinalis will give rise to pain, either in the chest, back, or loins, with radiating pain in the left upper intercostal spaces, from pressure on the intercostal nerves; at the same time the tumor may project backward on either side of the vertebral column, beneath the integument, as a pulsating swelling, simulating abscess connected with diseased




FIG. 606.—The thoracic aorta, viewed from the left side.

bone; or it may displace the œsophagus and compress the lungs on one or the other side. If the tumor extend forward, it may press upon and displace the heart, giving rise to palpitation and other symptoms of disease of that organ; it may displace or compress the œsophagus, causing pain and difficulty of swallowing; and ultimately even open into it by ulceration, producing fatal hemorrhage. If the disease extend to the right side, it may press upon the thoracic duct; or it may burst into the pleural cavity, or into the trachea or lung; and lastly, it may open into the posterior mediastinal cavity. Pressure on one of the bronchi, usually the left, will cause cough, and in time set up bronchiectasis; pressure on the left pulmonary plexus has been said

to give rise to asthmatic attacks. Of late years, the diagnosis of thoracic aneurism has been much facilitated by the employment of the x-rays, by means of which the outline of the sac may be demonstrated.

#### Branches of the Thoracic Aorta.—

<i>Visceral</i>	{	Pericardial.	<i>Parietal.</i>	{	Intercostal.
		Bronchial.			Subcostal.
		Œsophageal.			Superior Phrenic.
		Mediastinal.			

The **pericardial branches** (*rami pericardiaci*) consist of a few small vessels which are distributed to the posterior surface of the pericardium.

The **bronchial arteries** (*aa. bronchiales*) vary in number, size, and origin. There is as a rule only one **right bronchial artery**, which *arises* from the first aortic intercostal, or from the upper left bronchial artery. The **left bronchial arteries** are usually two in number, and *arise* from the thoracic aorta. The upper left bronchial arises opposite the fifth thoracic vertebra, the lower just below the level of the left bronchus. Each vessel runs on the back part of its bronchus, dividing and subdividing along the bronchial tubes, supplying them, the areolar tissue of the lungs, the bronchial lymph glands, and the œsophagus.

The **œsophageal arteries** (*aa. œsophageae*) four or five in number, *arise* from the front of the aorta, and pass obliquely downward to the œsophagus, forming a chain of anastomoses along that tube, anastomosing with the œsophageal branches of the inferior thyroid arteries above, and with ascending branches from the left inferior phrenic and left gastric arteries below.

The **mediastinal branches** (*rami mediastinales*) are numerous small vessels which supply the lymph glands and loose areolar tissue in the posterior mediastinal cavity.

**Intercostal Arteries** (*aa. intercostales*).—There are usually nine pairs of aortic intercostal arteries. They *arise* from the back of the aorta, and are redistributed to the lower nine intercostal spaces, the first two spaces being supplied by the highest intercostal artery, a branch of the costocervical trunk of the subclavian. The **right** aortic intercostals are longer than the left, on account of the position of the aorta on the left side of the vertebral column; they pass across the bodies of the vertebræ behind the œsophagus, thoracic duct, and vena azygos, and are covered by the right lung and pleura. The **left** aortic intercostals run backward on the sides of the vertebræ and are covered by the left lung and pleura; the upper two vessels are crossed by the highest left intercostal vein, the lower vessels by the hemiazygos veins. The further course of the intercostal arteries is practically the same on both sides. Opposite the heads of the ribs the sympathetic trunk passes downward in front of them, and the splanchnic nerves also descend in front by the lower arteries. Each artery then divides into an **anterior** and a **posterior ramus**.

The **Anterior Ramus** crosses the corresponding intercostal space obliquely toward the angle of the upper rib, and thence is continued forward in the costal groove. It is placed at first between the pleura and the posterior intercostal membrane, then it pierces this membrane, and lies between it and the *Intercostalis externus* as far as the angle of the rib; from this onward it runs between the *Intercostales externus* and *internus*, and anastomoses in front with the intercostal branch of the internal mammary or musculophrenic. Each artery is accompanied by a vein and a nerve, the former being above and the latter below the artery, except in the upper spaces, where the nerve is at first above the artery. The first aortic intercostal artery anastomoses with the intercostal branch of the costocervical trunk, and may form the chief supply of the second intercostal space. The lower two intercostal arteries

are continued anteriorly from the intercostal spaces into the abdominal wall, and anastomose with the subcostal, superior epigastric, and lumbar arteries.

**Branches.**—The anterior rami give off the following branches:

Collateral Intercostal.	Lateral Cutaneous.
Muscular.	Mammary.

The **collateral intercostal branch** comes off from the intercostal artery near the angle of the rib, and descends to the upper border of the rib below, along which it courses to anastomose with the intercostal branch of the internal mammary.

**Muscular branches** are given to the Intercostales and Pectorales and to the Serratus anterior; they anastomose with the highest and lateral thoracic branches of the axillary artery.

The **lateral cutaneous branches** accompany the lateral cutaneous branches of the thoracic nerves.

**Mammary branches** are given off by the vessels in the third, fourth, and fifth spaces. They supply the mamma, and increase considerably in size during the period of lactation.

The **Posterior Ramus** runs backward through a space which is bounded above and below by the necks of the ribs, medially by the body of a vertebra, and laterally by an anterior costotransverse ligament. It gives off a **spinal branch** which enters the vertebral canal through the intervertebral foramen and is distributed to the medulla spinalis and its membranes and the vertebræ. It then courses over the transverse process with the posterior division of the thoracic nerve, supplies branches to the muscles of the back and cutaneous branches which accompany the corresponding cutaneous branches of the posterior division of the nerve.

**Applied Anatomy.**—The position of the anterior rami of the intercostal vessels should be borne in mind in performing the operation of paracentesis thoracis. The puncture should never be made nearer the middle line posteriorly than the angle of the rib, as the artery crosses the space medial to this point. In the lateral portion of the chest, where the puncture is usually made, the artery lies at the upper part of the intercostal space, and therefore the puncture should be made just above the upper border of the rib forming the lower boundary of the space.

The **subcostal arteries**, so named because they lie below the last ribs, constitute the lowest pair of branches derived from the thoracic aorta, and are in series with the intercostal arteries. Each passes along the lower border of the twelfth rib behind the kidney and in front of the Quadratus lumborum muscle, and is accompanied by the twelfth thoracic nerve. It then pierces the posterior aponeurosis of the Transversus abdominis, and, passing forward between this muscle and the Obliquus internus, anastomoses with the superior epigastric, lower intercostal, and lumbar arteries. Each subcostal artery gives off a posterior branch which has a similar distribution to the posterior ramus of an intercostal artery.

The **superior phrenic branches** are small and arise from the lower part of the thoracic aorta; they are distributed to the posterior part of the upper surface of the Diaphragma, and anastomose with the musculophrenic and pericardiophrenic arteries.

A small **aberrant artery** is sometimes found arising from the right side of the thoracic aorta near the origin of the right bronchial. It passes upward and to the right behind the trachea and the œsophagus, and may anastomose with the highest right intercostal artery. It represents the remains of the right dorsal aorta, and in a small proportion of cases is enlarged to form the first part of the right subclavian artery.

#### **The Abdominal Aorta (Aorta Abdominalis) (Fig. 607).**

The **abdominal aorta** begins at the aortic hiatus of the Diaphragma, in front of the lower border of the body of the last thoracic vertebra, and, descending in



front of the vertebral column, ends on the body of the fourth lumbar vertebra, commonly a little to the left of the middle line,<sup>1</sup> by dividing into the two common iliac arteries. It diminishes rapidly in size, in consequence of the many large branches which it gives off. As it lies upon the bodies of the vertebræ, the curve which it describes is convex forward, the summit of the convexity corresponding to the third lumbar vertebra.




FIG. 607.—The abdominal aorta and its branches.

**Relations.**—The abdominal aorta is covered, *anteriorly*, by the lesser omentum and stomach, behind which are the branches of the celiac artery and the celiac plexus; below these, by the lienal vein, the pancreas, the left renal vein, the inferior part of the duodenum, the mesentery, and aortic plexus. *Posteriorly*, it is separated from the lumbar vertebræ and intervertebral fibrocartilages by the anterior longitudinal ligament and left lumbar veins. On the *right side* it is in relation above with the azygos vein, cisterna chyli, thoracic duct, and the right crus of the Diaphragma—the last separating it from the upper part of the inferior vena cava, and from the right celiac ganglion; the inferior vena cava is in contact with the aorta below. On the *left side* are the left crus of the Diaphragma, the left celiac ganglion, the ascending part of the duodenum, and some coils of the small intestine.

**Applied Anatomy.**—The abdominal aorta may be the seat of an aneurism either at its upper part, close to and often involving the celiac artery, or at its lower part, near the bifurcation.

<sup>1</sup> Lord Lister, having accurately examined 30 bodies in order to ascertain the exact point of termination of this vessel, found it "either absolutely, or almost absolutely, mesial in 15, while in 13 it deviated more or less to the left, and in 2 was slightly to the right." *System of Surgery*, edited by T. Holmes, 2d ed., v. 652.



Occasionally aneurisms are met with on some of the branches of the aorta, the mesenteric or lienal, quite independent of the main trunk.

When an aneurismal sac is connected with the posterior part of the abdominal aorta, it usually produces absorption of the bodies of the vertebræ. Pain is invariably present, and is usually of two kinds—a fixed and constant pain in the back, caused by the tumor pressing on or displacing the branches of the coeliac plexus and splanchnic nerves; and a sharp lancinating pain, radiating along those branches of the lumbar nerves which are pressed on by the tumor; hence the pain in the loins, the testes, the hypogastrium, and in the lower limb (generally of the left side). This form of aneurism usually bursts into or behind the peritoneal cavity.

When an aneurismal sac is connected with the front of the aorta near the coeliac artery, it forms a pulsating tumor in the left hypochondriac or epigastric regions, usually attended with symptoms of disturbance of the digestive tube, as sickness, dyspepsia, or constipation, and accompanied by pain, which is constant, but nearly always fixed, in the loins, epigastrium, or some part of the abdomen; the radiating pain being rare, as the lumbar nerves are seldom implicated. This form of aneurism may burst into the peritoneal cavity, behind the peritoneum, between the layers of the mesentery, or, more rarely, into the duodenum; it rarely extends backward so as to affect the vertebral column.

Occlusion of the abdominal aorta by thrombosis or embolism is rare, but produces very severe symptoms when it does occur. The patient complains of intense pain in the legs; pallor of the legs, followed by coldness, lividity, paresis, paralysis, and finally gangrene, are likely to succeed, death usually supervening within a fortnight.

The abdominal aorta has been tied in several cases, and although none of the patients permanently recovered, still, as one case lived forty-eight days, the possibility of the reestablishment of the circulation may be considered to be proved.

**Collateral Circulation.**—The collateral circulation would be carried on by the anastomoses between the internal mammary and the inferior epigastric; by the free communication between the superior and inferior mesenterics, if the ligature were placed between these vessels; or by the anastomosis between the inferior mesenteric and the internal pudendal, when (as is more common) the point of ligature is below the origin of the inferior mesenteric; and possibly by the anastomoses of the lumbar arteries with the branches of the hypogastric.

**Branches.**—The branches of the abdominal aorta may be divided into three sets: visceral, parietal, and terminal.

#### *Visceral Branches.*

Coeliac.  
Superior Mesenteric.  
Inferior Mesenteric.  
Middle Suprarenals.  
Renals.  
Internal Spermaties.  
Ovarian (in the female).

#### *Parietal Branches.*

Inferior Phrenics.  
Lumbars.  
Middle Sacral.

#### *Terminal Branches.*

Common Iliacs.

Of the visceral branches, the coeliac artery and the superior and inferior mesenteric arteries are unpaired, while the suprarenals, renals, internal spermaties, and ovarian are paired. Of the parietal branches the inferior phrenics and lumbars are paired; the middle sacral is unpaired. The terminal branches are paired.

The **coeliac artery** (*a. coeliaca; coeliac axis*) (Figs. 608, 609) is a short thick trunk, about 1.25 cm. in length, which *arises* from the front of the aorta, just below the aortic hiatus of the Diaphragma, and, passing nearly horizontally forward, divides into three large branches, the **left gastric**, the **hepatic**, and the **splenic**; it occasionally gives off one of the inferior phrenic arteries.

**Relations.**—The coeliac artery is covered by the lesser omentum. On the *right side* it is in relation with the right coeliac ganglion and the caudate process of the liver; on the *left side*, with the left coeliac ganglion and the cardiac end of the stomach. *Below*, it is in relation to the upper border of the pancreas, and the lienal vein.

1. The **Left Gastric Artery** (*a. gastrica sinistra; gastric or coronary artery*), the smallest of the three branches of the coeliac artery, passes upward and to the left, posterior to the omental bursa, to the cardiac orifice of the stomach. Here it distributes branches to the oesophagus, which anastomose with the aortic oesophageal

arteries; others supply the cardiac part of the stomach, anastomosing with branches of the lienal artery. It then runs from left to right, along the lesser curvature of the stomach to the pylorus, between the layers of the lesser omentum; it gives branches to both surfaces of the stomach and anastomoses with the right gastric artery.

2. The **Hepatic Artery** (*a. hepatica*) in the adult is intermediate in size between the left gastric and lienal; in the fetus, it is the largest of the three branches of the celiac artery. It is first directed forward and to the right, to the upper margin of the superior part of the duodenum, forming the lower boundary of the epiploic foramen (*foramen of Winslow*). It then crosses the portal vein anteriorly and ascends between the layers of the lesser omentum, and in front of the epiploic foramen, to the porta hepatis, where it divides into two branches, right and left, which




FIG. 608.—The celiac artery and its branches; the liver has been raised, and the lesser omentum and anterior layer of the greater omentum removed.

supply the corresponding lobes of the liver, accompanying the ramifications of the portal vein and hepatic ducts. The hepatic artery, in its course along the right border of the lesser omentum, is in relation with the common bile-duct and portal vein, the duct lying to the right of the artery, and the vein behind.

Its branches are:

Right Gastric.

Gastroduodenal { Right Gastroepiploic.  
Superior Pancreaticoduodenal.

Cystic.

The **right gastric artery** (*a. gastrica dextra; pyloric artery*) arises from the hepatic, above the pylorus, descends to the pyloric end of the stomach, and passes from

right to left along its lesser curvature, supplying it with branches, and anastomosing with the left gastric artery.

The **gastroduodenal artery** (*a. gastroduodenalis*) (Fig. 609) is a short but large branch, which descends, near the pylorus, between the superior part of the duodenum and the neck of the pancreas, and divides at the lower border of the duodenum into two branches, the **right gastroepiploic** and the **superior pancreaticoduodenal**. Previous to its division it gives off two or three small branches to the pyloric end of the stomach and to the pancreas.

*Branches to greater omentum*




FIG. 609.—The celiac artery and its branches; the stomach has been raised and the peritoneum removed.

The **right gastroepiploic artery** (*a. gastroepiploica dextra*) runs from right to left along the greater curvature of the stomach, between the layers of the greater omentum, anastomosing with the left gastroepiploic branch of the lienal artery. Except at the pylorus, where it is in contact with the stomach, it lies about a finger's breadth from the greater curvature. This vessel gives off numerous branches, some of which ascend to supply both surfaces of the stomach, while others descend to supply the greater omentum and anastomose with branches of the middle colic.

The **superior pancreaticoduodenal artery** (*a. pancreaticoduodenalis superior*) descends between the contiguous margins of the duodenum and pancreas. It supplies both these organs, and anastomoses with the inferior pancreaticoduodenal branch of the superior mesenteric artery, and with the pancreatic branches of the lienal artery.

The **cystic artery** (*a. cystica*) (Fig. 608), usually a branch of the right hepatic, passes downward and forward along the neck of the gall-bladder, and divides into two branches, one of which ramifies on the free surface, the other on the attached surface of the gall-bladder.

3. The **Lienal or Splenic Artery** (*a. lienalis*), the largest branch of the coeliac artery, is remarkable for the tortuosity of its course. It passes horizontally to the left side, behind the stomach and the omental bursa of the peritoneum, and along the upper border of the pancreas, accompanied by the lienal vein, which lies below it; it crosses in front of the upper part of the left kidney, and, on arriving near the spleen, divides into branches, some of which enter the hilus of that organ between the two layers of the phrenicolienal ligament to be distributed to the tissues of the spleen; some are given to the pancreas, while others pass to the greater curvature of the stomach between the layers of the gastrolienal ligament. Its branches are:

Pancreatic.

Left Gastroepiploic.

Short Gastric.

The **pancreatic branches** (*rami pancreatici*) are numerous small vessels derived from the lienal as it runs behind the upper border of the pancreas, supplying its body and tail. One of these, larger than the rest, is sometimes given off near the tail of the pancreas; it runs from left to right near the posterior surface of the gland, following the course of the pancreatic duct, and is called the **arteria pancreatica magna**. These vessels anastomose with the pancreatic branches of the pancreaticoduodenal and superior mesenteric arteries.

The **short gastric arteries** (*aa. gastricae breves; vasa brevia*) consist of from five to seven small branches, which arise from the end of the lienal artery, and from its terminal divisions. They pass from left to right, between the layers of the gastrolienal ligament, and are distributed to the greater curvature of the stomach, anastomosing with branches of the left gastric and left gastroepiploic arteries.

The **left gastroepiploic artery** (*a. gastroepiploica sinistra*) the largest branch of the lienal, runs from left to right about a finger's breadth or more from the greater curvature of the stomach, between the layers of the greater omentum, and anastomoses with the right gastroepiploic. In its course it distributes several ascending branches to both surfaces of the stomach; others descend to supply the greater omentum and anastomose with branches of the middle colic.

**Applied Anatomy.**—Embolism of branches of the lienal artery is tolerably common in heart disease, the embolus coming from the left side of the heart. It is characterized by the occurrence of a sudden sharp pain or "stitch" in the splenic region, with subsequent local enlargement of the spleen from the formation of an infarct in its substance.

The **superior mesenteric artery** (*a. mesenterica superior*) (Fig. 610) is a large vessel which supplies the whole length of the small intestine, except the superior part of the duodenum; it also supplies the cecum and the ascending part of the colon and about one-half of the transverse part of the colon. It arises from the front of the aorta, about 1.25 cm. below the coeliac artery, and is crossed at its origin by the lienal vein and the neck of the pancreas. It passes downward and forward, anterior to the processus uncinatus of the head of the pancreas and inferior part of the duodenum, and descends between the layers of the mesentery to the right iliac fossa, where, considerably diminished in size, it anastomoses with one of its own branches, viz., the ileocolic. In its course it crosses in front of the inferior vena cava, the right ureter and Psoas major, and forms an arch, the convexity of which is directed forward and downward to the left side, the concavity backward and upward to the right. It is accompanied by the superior mesenteric vein, which lies to its right side, and it is surrounded by the superior mesenteric plexus of nerves.



**Dissection.**—In order to expose the superior mesenteric artery raise the great omentum and transverse colon, draw down the small intestines, and cut through the peritoneum where the transverse mesocolon and mesentery join; the artery will then be exposed just as it issues from over the processus uncinatus of the head of the pancreas.




FIG. 610.—The superior mesenteric artery and its branches.

**Branches.**—Its branches are:

Inferior Pancreaticoduodenal.  
Intestinal.

Middle Colic.

Ileocolic.  
Right Colic.

The **Inferior Pancreaticoduodenal Artery** (*a. pancreaticoduodenalis inferior*) is given off from the superior mesenteric or from its first intestinal branch, opposite the upper border of the inferior part of the duodenum. It courses to the right between the head of the pancreas and duodenum, and then ascends to anastomose with the superior pancreaticoduodenal artery. It distributes branches to the head of the pancreas and to the descending and inferior parts of the duodenum.

The **Intestinal Arteries** (*aa. intestinales; vasa intestini tenuis*) arise from the convex side of the superior mesenteric artery. They are usually from twelve to fifteen in number, and are distributed to the jejunum and ileum. They run nearly parallel with one another between the layers of the mesentery, each vessel dividing into two branches, which unite with adjacent branches, forming a series of arches, the

convexities of which are directed toward the intestine (Fig. 611). From this first set of arches branches arise, which unite with similar branches from above and below and thus a second series of arches is formed; from the lower branches of the artery, a third, a fourth, or even a fifth series of arches may be formed, diminishing in size the nearer they approach the intestine. In the short, upper part of the mesentery only one set of arches exists, but as the depth of the mesentery increases, second, third, fourth, or even fifth groups are developed. From the terminal arches numerous small straight vessels arise which encircle the intestine, upon which they are distributed, ramifying between its coats. From the intestinal arteries small branches are given off to the lymph glands and other structures between the layers of the mesentery.




FIG. 611.—Loop of small intestine showing distribution of intestinal arteries. (From a preparation by Mr. Hamilton Drummond.) The vessels were injected while the gut was *in situ*; the gut was then removed, and an x-ray photograph taken.

The **Ileocolic Artery** (*a. ileocolica*) is the lowest branch arising from the concavity of the superior mesenteric artery. It passes downward and to the right behind the peritoneum toward the right iliac fossa, where it divides into a superior and an inferior branch; the inferior anastomoses with the end of the superior mesenteric artery, the superior with the right colic artery.

The inferior branch of the ileocolic runs toward the upper border of the ileocolic junction and supplies the following branches (Fig. 612):

(a) **colic**, which pass upward on the ascending colon; (b) **anterior and posterior cecal**, which are distributed to the front and back of the cecum; (c) an **appendicular artery**, which descends behind the termination of the ileum and enters the mesenteriole of the vermiform process; it runs near the free margin of this mesenteriole and ends in branches which supply the vermiform process; and (d) **ileal**, which run



upward and to the left on the lower part of the ileum, and anastomose with the termination of the superior mesenteric.

The **Right Colic Artery** (*a. colica dextra*) arises from about the middle of the concavity of the superior mesenteric artery, or from a stem common to it and the ileocolic. It passes to the right behind the peritoneum, and in front of the right internal spermatic or ovarian vessels, the right ureter and the Psoas major, toward the middle of the ascending colon; sometimes the vessel lies at a higher level, and crosses the descending part of the duodenum and the lower end of the right kidney. At the colon it divides into a descending branch, which anastomoses with the ileocolic, and an ascending branch, which anastomoses with the middle colic. These branches form arches, from the convexity of which vessels are distributed to the ascending colon.




FIG. 612.—Arteries of cecum and vermiform process.

The **Middle Colic Artery** (*a. colica media*) arises from the superior mesenteric just below the pancreas and, passing downward and forward between the layers of the transverse mesocolon, divides into two branches, right and left; the former anastomoses with the right colic; the latter with the left colic, a branch of the inferior mesenteric. The arches thus formed are placed about two fingers' breadth from the transverse colon, to which they distribute branches.

The **inferior mesenteric artery** (*a. mesenterica inferior*) (Fig. 613) supplies the left half of the transverse part of the colon, the whole of the descending and iliac parts of the colon, the sigmoid colon, and the greater part of the rectum. It is smaller than the superior mesenteric, and arises from the aorta, about 3 or 4 cm. above its division into the common iliacs and close to the lower border of the inferior part of the duodenum. It passes downward posterior to the peritoneum, lying at first anterior to and then on the left side of the aorta. It crosses the left common iliac artery and is continued into the lesser pelvis under the name of the **superior hemorrhoidal artery**, which descends between the two layers of the sigmoid mesocolon and ends on the upper part of the rectum.

**Dissection.**—In order to expose the inferior mesenteric artery draw the small intestines and mesentery over to the right side of the abdomen, raise the transverse colon toward the thorax, and divide the peritoneum covering the front of the aorta.




FIG. 613.—The inferior mesenteric artery and its branches.

**Branches.**—Its branches are:

Left Colic.

Sigmoid.

Superior Hemorrhoidal.

The **Left Colic Artery** (*a. colica sinistra*) runs to the left behind the peritoneum and in front of the Psoas major, and after a short, but variable, course divides into an ascending and a descending branch; the stem of the artery or its branches cross the left ureter and left internal spermatic vessels. The ascending branch crosses in front of the left kidney and ends, between the two layers of the transverse mesocolon, by anastomosing with the middle colic artery; the descending branch anastomoses with the highest sigmoid artery. From the arches formed by these anastomoses branches are distributed to the descending colon and the left part of the transverse colon.

The **Sigmoid Arteries** (*aa. sigmoideae*) (Fig. 614), two or three in number, run obliquely downward and to the left behind the peritoneum and in front of the Psoas major, ureter, and internal spermatic vessels. Their branches supply the lower part of the descending colon, the iliac colon, and the sigmoid or pelvic colon; anastomosing above with the left colic, and below with the superior hemorrhoidal artery.

The **Superior Hemorrhoidal Artery** (*a. haemorrhoidalis superior*) (Fig. 614), the continuation of the inferior mesenteric, descends into the pelvis between the layers of the mesentery of the sigmoid colon, crossing, in its course, the left common iliac vessels. It divides, opposite the third sacral vertebra, into two branches, which descend one on either side of the rectum, and about 10 or 12 cm. from the anus break up into several small branches. These pierce the muscular coat of the bowel and run downward, as straight vessels, placed at regular intervals from each other in the wall of the gut between its muscular and mucous coats, to the level of the Sphincter ani internus; here they form a series of loops around the lower end of the rectum, and communicate with the middle hemorrhoidal branches of the hypogastric, and with the inferior hemorrhoidal branches of the internal pudendal.




FIG. 614.—Sigmoid colon and rectum, showing distribution of branches of inferior mesenteric artery and their anastomoses. (From a preparation by Mr. Hamilton Drummond.) Prepared in same manner as Fig. 611.

**Applied Anatomy.**—Embolism of the mesenteric arteries produces acute and severe symptoms, of which the chief are abdominal pain and tenderness, nausea and vomiting, diarrhoea or constipation; blood is found in the stools of nearly half the patients. In many cases the symptoms closely resemble those of intestinal obstruction.

The **middle suprarenal arteries** (*aa. suprarenales mediae*; *middle capsular arteries*; *suprarenal arteries*) are two small vessels which arise, one from either side of the aorta, opposite the superior mesenteric artery. They pass lateralward and slightly upward, over the crura of the Diaphragma, to the suprarenal glands, where they anastomose with suprarenal branches of the inferior phrenic and renal arteries. In the fetus these arteries are of large size.

The **renal arteries** (*aa. renales*) (Fig. 607), are two large trunks, which arise from the side of the aorta, immediately below the superior mesenteric artery.

Each is directed across the crus of the Diaphragma, so as to form nearly a right angle with the aorta. The right is longer than the left, on account of the position of the aorta; it passes behind the inferior vena cava, the right renal vein, the head of the pancreas, and the descending part of the duodenum. The left is somewhat higher than the right; it lies behind the left renal vein, the body of the pancreas and the lienal vein, and is crossed by the inferior mesenteric vein. Before reaching the hilus of the kidney, each artery divides into four or five branches; the greater number of these lie between the renal vein and ureter, the vein being in front, the ureter behind, but one or more branches are usually situated behind the ureter. Each vessel gives off some small **inferior suprarenal branches** to the suprarenal gland, the ureter, and the surrounding cellular tissue and muscles. One or two accessory renal arteries are frequently found, more especially on the left side they usually arise from the aorta, and may come off above or below the main artery, the former being the more common position. Instead of entering the kidney at the hilus, they usually pierce the upper or lower part of the gland.

The **internal spermatic arteries** (*aa. spermaticae internae; spermatic arteries*) (Fig. 607) are distributed to the testes. They are two slender vessels of considerable length, and *arise* from the front of the aorta a little below the renal arteries. Each passes obliquely downward and lateralward behind the peritoneum, resting on the Psoas major, the right spermatic lying in front of the inferior vena cava and behind the middle colic and ileocolic arteries and the terminal part of the ileum, the left behind the left colic and sigmoid arteries and the iliac colon. Each crosses obliquely over the ureter and the lower part of the external iliac artery to reach the abdominal inguinal ring, through which it passes, and accompanies the other constituents of the spermatic cord along the inguinal canal to the scrotum, where it becomes tortuous, and divides into several branches. Two or three of these accompany the ductus deferens, and supply the epididymis, anastomosing with the artery of the ductus deferens; others pierce the back part of the tunica albuginea, and supply the substance of the testis. The internal spermatic artery supplies one or two small branches to the ureter, and in the inguinal canal gives one or two twigs to the Cremaster.

The **ovarian arteries** (*aa. ovaricae*) are the corresponding arteries in the female to the internal spermatic in the male. They supply the ovaries, are shorter than the internal spermatics, and do not pass out of the abdominal cavity. The origin and course of the first part of each artery are the same as those of the internal spermatic, but on arriving at the upper opening of the lesser pelvis the ovarian artery passes inward, between the two layers of the ovario pelvic ligament and of the broad ligament of the uterus, to be distributed to the ovary. Small branches are given to the ureter and the uterine tube, and one passes on to the side of the uterus, and unites with the uterine artery. Other offsets are continued on the round ligament of the uterus, through the inguinal canal, to the integument of the labium majus and groin.

At an early period of fetal life, when the testes or ovaries lie by the side of the vertebral column, below the kidneys, the internal spermatic or ovarian arteries are short; but with the descent of these organs into the scrotum or lesser pelvis, the arteries are gradually lengthened.

The **inferior phrenic arteries** (*aa. phrenicae inferiores*) (Fig. 607) are two small vessels, which supply the Diaphragma but present much variety in their origin. They may *arise* separately from the front of the aorta, immediately above the coeliac artery, or by a common trunk, which may spring either from the aorta or from the coeliac artery. Sometimes one is derived from the aorta, and the other from one of the renal arteries; they rarely arise as separate vessels from the aorta. They diverge from one another across the crura of the Diaphragma, and then run obliquely upward and lateralward upon its under surface. The left phrenic passes

behind the œsophagus, and runs forward on the left side of the œsophageal hiatus. The right phrenic passes behind the inferior vena cava, and along the right side of the foramen which transmits that vein. Near the back part of the central tendon each vessel divides into a medial and a lateral branch. The **medial branch** curves forward, and anastomoses with its fellow of the opposite side, and with the musculophrenic and pericardiophrenic arteries. The **lateral branch** passes toward the side of the thorax, and anastomoses with the lower intercostal arteries, and with the musculophrenic. The lateral branch of the right phrenic gives off a few vessels to the inferior vena cava; and the left one, some branches to the œsophagus. Each vessel gives off **superior suprarenal branches** to the suprarenal gland of its own side. The spleen and the liver also receive a few twigs from the left and right vessels respectively.

The **lumbar arteries** (*aa. lumbales*) are in series with the intercostals. They are usually four in number on either side, and *arise* from the back of the aorta, opposite the bodies of the upper four lumbar vertebræ. A fifth pair, small in size, is occasionally present: they *arise* from the middle sacral artery. They run lateralward and backward on the bodies of the lumbar vertebræ, behind the sympathetic trunk, to the intervals between the adjacent transverse processes, and are then continued into the abdominal wall. The arteries of the right side pass behind the inferior vena cava, and the upper two on each side run behind the corresponding crus of the Diaphragma. The arteries of both sides pass beneath the tendinous arches which give origin to the Psoas major, and are then continued behind this muscle and the lumbar plexus. They now cross the Quadratus lumborum, the upper three arteries running behind, the last usually in front of the muscle. At the lateral border of the Quadratus lumborum they pierce the posterior aponeurosis of the Transversus abdominis and are carried forward between this muscle and the Obliquus internus. They anastomose with the lower intercostal, the subcostal, the iliolumbar, the deep iliac circumflex, and the inferior epigastric arteries.

**Branches.**—In the interval between the adjacent transverse processes each lumbar artery gives off a **posterior ramus** which is continued backward between the transverse processes and is distributed to the muscles and skin of the back; it furnishes a **spinal branch** which enters the vertebral canal and is distributed in a manner similar to the spinal branches of the posterior rami of the intercostal arteries (page 686). **Muscular branches** are supplied from each lumbar artery and from its posterior ramus to the neighboring muscles.

The **middle sacral artery** (*a. sacralis media*) (Fig. 607) is a small vessel, which *arises* from the back of the aorta, a little above its bifurcation. It descends in the middle line in front of the fourth and fifth lumbar vertebræ, the sacrum and coccyx, and ends in the glomus coccygeum (*coccygeal gland*). From it, minute branches are said to pass to the posterior surface of the rectum. On the last lumbar vertebra it anastomoses with the lumbar branch of the iliolumbar artery; in front of the sacrum it anastomoses with the lateral sacral arteries, and sends offshoots into the anterior sacral foramina. It is crossed by the left common iliac vein, and is accompanied by a pair of venae comitantes; these unite to form a single vessel, which opens into the left common iliac vein.

#### THE COMMON ILIAC ARTERIES (AA. ILIACAE COMMUNES) (Figs. 607, 615).

The abdominal aorta divides, on the left side of the body of the fourth lumbar vertebra, into the two **common iliac arteries**. Each is about 5 cm. in length. They diverge from the termination of the aorta, pass downward and lateralward, and divide, opposite the intervertebral fibrocartilage between the last lumbar vertebra and the sacrum, into two branches, the **external iliac** and **hypogastric arteries**;



the former supplies the lower extremity; the latter, the viscera and parietes of the pelvis.

The **right common iliac artery** (Fig. 615) is somewhat longer than the left, and passes more obliquely across the body of the last lumbar vertebra. *In front* of it are the peritoneum, the small intestines, branches of the sympathetic nerves, and, at its point of division, the ureter. *Behind*, it is separated from the bodies of the fourth and fifth lumbar vertebræ, and the intervening fibrocartilage, by the terminations of the two common iliac veins and the commencement of the inferior vena cava. *Laterally*, it is in relation, above, with the inferior vena cava and the right common iliac vein; and, below, with the Psoas major. *Medial* to it, above, is the left common iliac vein.




FIG. 615.—The arteries of the pelvis.

The **left common iliac artery** is in relation, *in front*, with the peritoneum, the small intestines, branches of the sympathetic nerves, and the superior hemorrhoidal artery; and is crossed at its point of bifurcation by the ureter. It rests on the bodies of the fourth and fifth lumbar vertebræ, and the intervening fibrocartilage. The left common iliac vein lies partly *medial* to, and partly behind the artery; *laterally*, the artery is in relation with the Psoas major.

**Branches.**—The common iliac arteries give off small branches to the peritoneum, Psoas major, ureters, and the surrounding areolar tissue, and occasionally give origin to the iliolumbar, or accessory renal arteries.



**Peculiarities.**—The *point of origin* varies according to the bifurcation of the aorta. In three-fourths of a large number of cases, the aorta bifurcated either upon the fourth lumbar vertebra, or upon the fibrocartilage between it and the fifth; the bifurcation being, in one case out of nine, below, and in one out of eleven, above this point. In about 80 per cent. of the cases the aorta bifurcated within 1.25 cm. above or below the level of the crest of the ilium; more frequently below than above.

The *point of division* is subject to great variety. In two-thirds of a large number of cases it was between the last lumbar vertebra and the upper border of the sacrum; being above that point in one case out of eight, and below it in one case out of six. The left common iliac artery divides lower down more frequently than the right.

The *relative lengths*, also, of the two common iliac arteries vary. The right common iliac was the longer in sixty-three cases; the left in fifty-two; while they were equal in fifty-three. The length of the arteries varied, in five-sevenths of the cases examined, from 3.5 to 7.5 cm.; in about half of the remaining cases the artery was longer, and in the other half, shorter; the minimum length being less than 1.25 cm., the maximum, 11 cm. In rare instances, the right common iliac has been found wanting, the external iliac and hypogastric arising directly from the aorta.

**Applied Anatomy.**—The application of a ligature to the common iliac artery may be required on account of aneurism or hemorrhage, implicating the external iliac or hypogastric. The easiest and best method of tying the artery is by a transperitoneal route. The abdomen is opened, the intestines are drawn aside and the peritoneum covering the artery divided; the sheath is then opened and the needle passed from the medial to the lateral side. On the right side great care must be exercised in passing the needle, since both the common iliac veins lie behind the artery. After the vessel has been tied, the incision in the peritoneum over the artery should be sutured. Formerly there were different methods by which the common iliac artery was tied, without opening the peritoneal cavity, but these have now been discarded.

**Collateral Circulation.**—The principal agents in carrying on the collateral circulation after the application of a ligature to the common iliac are: the anastomoses of the hemorrhoidal branches of the hypogastric with the superior hemorrhoidal from the inferior mesenteric; of the uterine, ovarian, and vesical arteries of the opposite sides; of the lateral sacral with the middle sacral artery; of the inferior epigastric with the internal mammary, inferior intercostal, and lumbar arteries; of the deep iliac circumflex with the lumbar arteries; of the iliolumbar with the last lumbar artery; of the obturator artery, by means of its pubic branch, with the vessel of the opposite side and with the inferior epigastric.

### **The Hypogastric Artery (A. Hypogastrica; Internal Iliac Artery) (Fig. 615).**

The **hypogastric artery** supplies the walls and viscera of the pelvis, the buttock, the generative organs, and the medial side of the thigh. It is a short, thick vessel, smaller than the external iliac, and about 4 cm. in length. It *arises* at the bifurcation of the common iliac, opposite the lumbosacral articulation, and, passing downward to the upper margin of the greater sciatic foramen, divides into two large trunks, an **anterior** and a **posterior**.

**Relations.**—It is in relation *in front* with the ureter; *behind*, with the internal iliac vein, the lumbosacral trunk, and the Piriformis muscle; *laterally*, near its origin, with the external iliac vein, which lies between it and the Psoas major muscle; lower down, with the obturator nerve.

**In the fetus**, the hypogastric artery is twice as large as the external iliac, and is the direct continuation of the common iliac. It ascends along the side of the bladder, and runs upward on the back of the anterior wall of the abdomen to the umbilicus, converging toward its fellow of the opposite side. Having passed through the umbilical opening, the two arteries, now termed **umbilical**, enter the umbilical cord, where they are coiled around the umbilical vein, and ultimately ramify in the placenta.

At birth, when the placental circulation ceases, the pelvic portion only of the artery remains patent and constitutes the hypogastric and the first part of the superior vesical artery of the adult; the remainder of the vessel is converted into a solid fibrous cord, the **lateral umbilical ligament** (*obliterated hypogastric artery*) which extends from the pelvis to the umbilicus.

**Peculiarities as Regards Length.**—In two-thirds of a large number of cases, the length of the hypogastric varied between 2.25 and 3.4 cm.; in the remaining third it was more frequently longer than shorter, the maximum length being about 7 cm. the minimum about 1 cm.

The lengths of the common iliac and hypogastric arteries bear an inverse proportion to each other, the hypogastric artery being long when the common iliac is short, and *vice versa*.

**As Regards its Place of Division.**—The place of division of the hypogastric varies between the upper margin of the sacrum and the upper border of the greater sciatic foramen.

The right and left hypogastric arteries in a series of cases often differed in length, but neither seemed constantly to exceed the other.

**Applied Anatomy.**—The application of a ligature to the hypogastric artery may be required in cases of aneurism or hemorrhage affecting one of its branches. The vessel may be best secured by an abdominal section in the median line, and reaching the vessel through the peritoneal cavity. It should be remembered that the vein lies behind, and, on the right side, a little lateral to the artery, and in close contact with it; the ureter, which lies in front, must also be avoided. The degree of facility in applying a ligature to this vessel will mainly depend upon its length. It has been seen that, in the great majority of the cases examined, the artery was short, varying from 2 to 4 cm.; in these cases, the artery is deeply seated in the pelvis; when, on the contrary, the vessel is longer, it is found partly above that cavity. If the artery be very short, as occasionally happens, it would be preferable to apply a ligature to the common iliac.

**Collateral Circulation.**—The circulation after ligature of the hypogastric artery is carried on by the anastomoses of the uterine and ovarian arteries; of the vesical arteries of the two sides; of the hemorrhoidal branches of the hypogastric with those from the inferior mesenteric; of the obturator artery, by means of its pubic branch, with the vessel of the opposite side, and with the inferior epigastric and medial femoral circumflex; of the circumflex and perforating branches of the profunda femoris with the inferior gluteal; of the superior gluteal with the posterior branches of the lateral sacral arteries; of the iliolumbar with the last lumbar; of the lateral sacral with the middle sacral; and of the iliac circumflex with the iliolumbar and superior gluteal.<sup>1</sup>

**Branches.**—The branches of the hypogastric artery are:

*From the Anterior Trunk.*

*From the Posterior Trunk.*

Superior Vesical.

Iliolumbar.

Middle Vesical.

Lateral Sacral.

Inferior Vesical.

Superior Gluteal.

Middle Hemorrhoidal.

Obturator.

Internal Pudendal.

Inferior Gluteal.

Uterine } *In the Female.*  
Vaginal }

The **superior vesical artery** (*a. vesicalis superior*) supplies numerous branches to the upper part of the bladder. From one of these a slender vessel, the **artery to the ductus deferens**, takes origin and accompanies the duct in its course to the testis, where it anastomoses with the internal spermatic artery. Other branches supply the ureter. The first part of the superior vesical artery represents the terminal section of the pervious portion of the fetal hypogastric artery.

The **middle vesical artery** (*a. vesicalis medialis*), usually a branch of the superior, is distributed to the fundus of the bladder and the vesiculæ seminales.

The **inferior vesical artery** (*a. vesicalis inferior*) frequently arises in common with the middle hemorrhoidal, and is distributed to the fundus of the bladder, the prostate, and the vesiculæ seminales. The branches to the prostate communicate with the corresponding vessels of the opposite side.

The **middle hemorrhoidal artery** (*a. hæmorrhoidalis media*) usually arises with the preceding vessel. It is distributed to the rectum, anastomosing with the inferior vesical and with the superior and inferior hemorrhoidal arteries. It gives offshoots to the vesiculæ seminales and prostate.

The **uterine artery** (*a. uterina*) (Fig. 616) springs from the anterior division of the hypogastric and runs medialward on the Levator ani and toward the cervix uteri; about 2 cm. from the cervix it crosses above and in front of the ureter, to which it supplies a small branch. Reaching the side of the uterus it ascends in a tortuous manner between the two layers of the broad ligament to the junction

<sup>1</sup> For a description of a case in which Owen made a dissection ten years after ligature of the hypogastric artery, see *Med.-Chir. Trans.*, vol. xvi.

of the uterine tube and uterus. It then runs lateralward toward the hilus of the ovary, and ends by joining with the ovarian artery. It supplies branches to the cervix uteri and others which descend on the vagina; the latter anastomose with branches of the vaginal arteries and form with them two median longitudinal vessels—the **azygos arteries of the vagina**—one of which runs down one in front of and the other behind the vagina. It supplies numerous branches to the body of the uterus, and from its terminal portion twigs are distributed to the uterine tube and the round ligament of the uterus.

The **vaginal artery** (*a. vaginalis*) usually corresponds to the inferior vesical in the male; it descends upon the vagina, supplying its mucous membrane, and sends branches to the bulb of the vestibule, the fundus of the bladder, and the contiguous part of the rectum. It assists in forming the azygos arteries of the vagina, and is frequently represented by two or three branches.




FIG. 616.—The arteries of the internal organs of generation of the female, seen from behind. (After Hyrtl.)

The **obturator artery** (*a. obturatoria*) passes forward and downward on the lateral wall of the pelvis, to the upper part of the obturator foramen, and, escaping from the pelvic cavity through the obturator canal, it divides into an **anterior** and a **posterior branch**. In the pelvic cavity this vessel is in relation, laterally, with the obturator fascia; medially, with the ureter, ductus deferens, and peritoneum; while a little below it is the obturator nerve.

**Branches.**—*Inside the pelvis* the obturator artery gives off **iliac branches** to the iliac fossa, which supply the bone and the Iliacus, and anastomose with the ilio-lumbar artery; a **vesical branch**, which runs backward to supply the bladder; and a **pubic branch**, which is given off from the vessel just before it leaves the pelvic cavity. The pubic branch ascends upon the back of the pubis, communicating with the corresponding vessel of the opposite side, and with the inferior epigastric artery.

*Outside the pelvis*, the obturator artery divides at the upper margin of the obturator foramen, into an anterior and a posterior branch which encircle the foramen under cover of the Obturator externus.

The **anterior branch** runs forward on the outer surface of the obturator membrane and then curves downward along the anterior margin of the foramen. It distributes branches to the Obturator externus, Pectineus, Adductores, and Gracilis, and anastomoses with the posterior branch and with the medial femoral circumflex artery.

The **posterior branch** follows the posterior margin of the foramen and turns forward on the inferior ramus of the ischium, where it anastomoses with the anterior branch. It gives twigs to the muscles attached to the ischial tuberosity and anastomoses with the inferior gluteal. It also supplies an articular branch which enters the hip-joint through the acetabular notch, ramifies in the fat at the bottom of the acetabulum and sends a twig along the ligamentum teres to the head of the femur.

**Peculiarities.**—The obturator artery sometimes arises from the main stem or from the posterior trunk of the hypogastric, or it may spring from the superior gluteal artery; occasionally it arises from the external iliac. In about two out of every seven cases it springs from the inferior epigastric and descends almost vertically to the upper part of the obturator foramen. The artery in this course usually lies in contact with the external iliac vein, and on the lateral side of the femoral ring (Fig. 617 A); in such cases it would not be endangered in the operation for strangulated femoral hernia. Occasionally, however, it curves along the free margin of the lacunar ligament (Fig. 617 B), and if in such circumstances a femoral hernia occurred, the vessel would almost completely encircle the neck of the hernial sac, and would be in great danger of being wounded if an operation were performed for strangulation.




FIG. 617.—Variations in origin and course of obturator artery.

The **internal pudendal artery** (*a. pudenda interna; internal pudic artery*) is the smaller of the two terminal branches of the anterior trunk of the hypogastric, and supplies the external organs of generation. Though the course of the artery is the same in the two sexes, the vessel is smaller in the female than in the male, and the distribution of its branches somewhat different. The description of its arrangement in the male will first be given, and subsequently the differences which it presents in the female will be mentioned.

The **internal pudendal artery in the male** passes downward and outward to the lower border of the greater sciatic foramen, and emerges from the pelvis between the Piriformis and Coccygeus; it then crosses the ischial spine, and enters the perineum through the lesser sciatic foramen. The artery now crosses the Obturator internus, along the lateral wall of the ischiorectal fossa, being situated about 4 cm. above the lower margin of the ischial tuberosity. It gradually approaches the margin of the inferior ramus of the ischium and passes forward between the two layers of the fascia of the urogenital diaphragm; it then runs forward along the medial margin of the inferior ramus of the pubis, and about 1.25 cm. behind the pubic arcuate ligament it pierces the inferior fascia of the urogenital diaphragm and divides into the **dorsal and deep arteries of the penis**.

**Relations.**—Within the pelvis, it lies in front of the Piriformis muscle, the sacral plexus of nerves, and the inferior gluteal artery. As it crosses the ischial spine, it is covered by the Glutaeus maximus and overlapped by the sacrotuberous ligament. Here the pudendal nerve lies to the medial side and the nerve to the Obturator internus to the lateral side of the vessel. In the perineum it lies on the lateral wall of the ischiorectal fossa, in a canal (*Alcock's canal*) formed by the



splitting of the obturator fascia. It is accompanied by a pair of *venae comitantes* and the pudendal nerve.

**Peculiarities.**—The internal pudendal artery is sometimes smaller than usual, or fails to give off one or two of its usual branches; in such cases the deficiency is supplied by branches derived from an additional vessel, the **accessory pudendal**, which generally arises from the internal pudendal artery before its exit from the greater sciatic foramen. It passes forward along the lower part of the bladder and across the side of the prostate to the root of the penis, where it perforates the urogenital diaphragm, and gives off the branches usually derived from the internal pudendal artery. The deficiency most frequently met with is that in which the internal pudendal ends as the artery of the urethral bulb, the dorsal and deep arteries of the penis being derived from the accessory pudendal. The internal pudendal artery may also end as the perineal, the artery of the urethral bulb being derived, with the other two branches, from the accessory vessel. Occasionally the accessory pudendal artery is derived from one of the other branches of the hypogastric artery, most frequently the inferior vesical or the obturator.

**Branches.**—The branches of the internal pudendal artery (Figs. 618, 619) are:

Muscular.	Artery of the Urethral Bulb.
Inferior Hemorrhoidal.	Urethral.
Perineal.	Deep Artery of the Penis.
	Dorsal Artery of the Penis.




FIG. 618.—The superficial branches of the internal pudendal artery.

The **Muscular Branches** consist of two sets: one given off in the pelvis; the other, as the vessel crosses the ischial spine. The former consists of several small offsets which supply the Levator ani, the Obturator internus, the Piriformis, and the Coccygeus. The branches given off outside the pelvis are distributed to the adjacent parts of the Glutaeus maximus and external rotator muscles. They anastomose with branches of the inferior gluteal artery.

The **Inferior Hemorrhoidal Artery** (*a. haemorrhoidalis inferior*) arises from the internal pudendal as it passes above the ischial tuberosity. Piercing the wall of Alcock's canal it divides into two or three branches which cross the ischio-rectal fossa, and are distributed to the muscles and integument of the anal region, and

send offshoots around the lower edge of the *Glutaeus maximus* to the skin of the buttock. They anastomose with the corresponding vessels of the opposite side, with the superior and middle hemorrhoidal, and with the perineal artery.

The **Perineal Artery** (*a. perinei*; *superficial perineal artery*) arises from the internal pudendal, in front of the preceding branches, and turns upward, crossing either over or under the Transversus perinaei superficialis, and runs forward, parallel to the pubic arch, in the interspace between the Bulbocavernosus and Ischiocavernosus, both of which it supplies, and finally divides into several **posterior scrotal branches** which are distributed to the skin and dartos tunic of the scrotum. As it crosses the Transversus perinaei superficialis it gives off the **transverse perineal artery** which runs transversely on the cutaneous surface of the muscle, and anastomoses with the corresponding vessel of the opposite side and with the perineal and inferior hemorrhoidal arteries. It supplies the Transversus perinaei superficialis and the structures between the anus and the urethral bulb.




FIG. 619.—The deeper branches of the internal pudendal artery.

The **Artery of the Urethral Bulb** (*a. bulbi urethrae*) is a short vessel of large calibre which arises from the internal pudendal between the two layers of fascia of the urogenital diaphragm; it passes medialward, pierces the inferior fascia of the urogenital diaphragm, and gives off branches which ramify in the bulb of the urethra and in the posterior part of the corpus cavernosum urethrae. It gives off a small branch to the bulbo-urethral gland.

The **Urethral Artery** (*a. urethralis*) arises a short distance in front of the artery of the urethral bulb. It runs forward and medialward, pierces the inferior fascia of the urogenital diaphragm and enters the corpus cavernosum urethrae, in which it is continued forward to the glans penis.

The **Deep Artery of the Penis** (*a. profunda penis; artery to the corpus cavernosum*), one of the terminal branches of the internal pudendal, *arises* from that vessel while it is situated between the two fasciæ of the urogenital diaphragm; it pierces the inferior fascia, and, entering the crus penis obliquely, runs forward in the centre of the corpus cavernosum penis, to which its branches are distributed.



The **Dorsal Artery of the Penis** (*a. dorsalis penis*) ascends between the crus penis and the pubic symphysis, and, piercing the inferior fascia of the urogenital diaphragm, passes between the two layers of the suspensory ligament of the penis, and runs forward on the dorsum of the penis to the glans, where it divides into two branches, which supply the glans and prepuce. On the penis, it lies between the dorsal nerve and deep dorsal vein, the former being on its lateral side. It supplies the integument and fibrous sheath of the corpus cavernosum penis, sending branches through the sheath to anastomose with the preceding vessel.

The **internal pudendal artery in the female** is smaller than in the male. Its origin and course are similar, and there is considerable analogy in the distribution of its branches. The perineal artery supplies the labia pudendi; the artery of the bulb supplies the bulbus vestibuli and the erectile tissue of the vagina; the deep artery of the clitoris supplies the corpus cavernosum clitoridis; and the dorsal artery of the clitoris supplies the dorsum of that organ, and ends in the glans and prepuce of the clitoris.

The **inferior gluteal artery** (*a. glutea inferior; sciatic artery*) (Fig. 620), the larger of the two terminal branches of the anterior trunk of the hypogastric, is distributed chiefly to the buttock and back of the thigh. It passes down on the sacral plexus of nerves and the Piriformis, behind the internal pudendal artery, to the lower part of the greater sciatic foramen, through which it escapes from the pelvis between the Piriformis and Coccygeus. It then descends in the interval between the greater trochanter of the femur and tuberosity of the ischium, accompanied by the sciatic and posterior femoral cutaneous nerves, and covered by the Glutaeus maximus, and is continued down the back of the thigh, supplying the skin, and anastomosing with branches of the perforating arteries.

*Inside the pelvis* it distributes branches to the Piriformis, Coccygeus, and Levator ani; some branches which supply the fat around the rectum, and occasionally take the place of the middle hemorrhoidal artery; and vesical branches to the fundus of the bladder, vesiculae seminales, and prostate. *Outside the pelvis* it gives off the following branches:

Muscular.	Anastomotic.
Coccygeal.	Articular.
Comitans Nervi Ischiadici.	Cutaneous.

The **Muscular Branches** supply the Glutaeus maximus, anastomosing with the superior gluteal artery in the substance of the muscle; the external rotators, anastomosing with the internal pudendal artery; and the muscles attached to the tuberosity of the ischium, anastomosing with the posterior branch of the obturator and the medial femoral circumflex arteries.

The **Coccygeal Branches** run medialward, pierce the sacrotuberous ligament, and supply the Glutaeus maximus, the integument, and other structures on the back of the coccyx.

The **Arteria Comitans Nervi Ischiadici** is a long, slender vessel, which accompanies the sciatic nerve for a short distance; it then penetrates it, and runs in its substance to the lower part of the thigh.

The **Anastomotic** is directed downward across the external rotators, and assists in forming the so-called **crucial anastomosis** by joining with the first perforating and medial and lateral femoral circumflex arteries.

The **Articular Branch**, generally derived from the anastomotic, is distributed to the capsule of the hip-joint.

The **Cutaneous Branches** are distributed to the skin of the buttock and back of the thigh.

The **iliolumbar artery** (*a. iliolumbalis*) a branch of the posterior trunk of the hypogastric, turns upward behind the obturator nerve and the external iliac vessels

to the medial border of the Psoas major, behind which it divides into a lumbar and an iliac branch.

The **Lumbar Branch** (*ramus lumbalis*) supplies the Psoas major and Quadratus lumborum, anastomoses with the last lumbar artery, and sends a small **spinal branch** through the intervertebral foramen between the last lumbar vertebra and the sacrum, into the vertebral canal, to supply the cauda equina.

The **Iliac Branch** (*ramus iliacus*) descends to supply the Iliacus; some offsets, running between the muscle and the bone, anastomose with the iliac branches of the obturator; one of these enters an oblique canal to supply the bone, while others run along the crest of the ilium, distributing branches to the gluteal and abdominal muscles, and anastomosing in their course with the superior gluteal, iliac circumflex, and lateral femoral circumflex arteries.

The **lateral sacral arteries** (*aa. sacrales laterales*) (Fig. 615) arise from the posterior division of the hypogastric; there are usually two, a **superior** and an **inferior**.

The **superior**, of large size, passes medialward, and, after anastomosing with branches from the middle sacral, enters the first or second anterior sacral foramen, supplies branches to the contents of the sacral canal, and, escaping by the corresponding posterior sacral foramen, is distributed to the skin and muscles on the dorsum of the sacrum, anastomosing with the superior gluteal.

The **inferior** runs obliquely across the front of the Piriformis and the sacral nerves to the medial side of the anterior sacral foramina, descends on the front of the sacrum, and anastomoses over the coccyx with the middle sacral and opposite lateral sacral artery. In its course it gives off branches, which enter the anterior sacral foramina; these, after supplying the contents of the sacral canal, escapes by the posterior sacral foramina, and are distributed to the muscles and skin on the dorsal surface of the sacrum, anastomosing with the gluteal arteries.

The **superior gluteal artery** (*a. glutea superior*; *gluteal artery*) (Fig. 620) is the largest branch of the hypogastric, and appears to be the continuation of the posterior division of that vessel. It is a short artery which runs backward between




FIG. 620.—The arteries of the gluteal and posterior femoral regions.

the lumbosacral trunk and the first sacral nerve, and, passing out of the pelvis above the upper border of the Piriformis, immediately divides into a **superficial** and a **deep branch**. Within the pelvis it gives off a few branches to the Iliacus, Piriformis, and Obturator internus, and just previous to quitting that cavity, a nutrient artery which enters the ilium.

The **superficial branch** enters the deep surface of the Glutaeus maximus, and divides into numerous branches, some of which supply the muscle and anastomose with the inferior gluteal, while others perforate its tendinous origin, and supply the integument covering the posterior surface of the sacrum, anastomosing with the posterior branches of the lateral sacral arteries.

The **deep branch** lies under the Glutaeus medius and almost immediately subdivides into two. Of these, the **superior division**, continuing the original course of the vessel, passes along the upper border of the Glutaeus minimus to the anterior superior spine of the ilium, anastomosing with the deep iliac circumflex artery and the ascending branch of the lateral femoral circumflex artery. The **inferior division** crosses the Glutaeus minimus obliquely to the greater trochanter, distributing branches to the Glutaei and anastomoses with the lateral femoral circumflex artery. Some branches pierce the Glutaeus minimus and supply the hip-joint.

**Applied Anatomy.**—Any of these three vessels may require to be ligatured for a wound, or for aneurism which is generally traumatic. The *superior gluteal artery* is ligatured by turning the patient two-thirds over on to his face and making an incision from the posterior superior spine of the ilium to the upper and posterior angle of the greater trochanter. This must expose the Glutaeus maximus, and its fibres are to be separated through the whole thickness of the muscle and pulled apart with retractors. The contiguous margins of the Glutaeus medius and Piriformis are now to be separated from each other, and the artery will be exposed emerging from the greater sciatic foramen. In ligature of the *inferior gluteal artery*, the incision should be made parallel with that for ligature of the superior gluteal but 4 cm. lower down. After the fibres of the Glutaeus maximus have been separated, the vessel is to be sought for at the lower border of the Piriformis; the sciatic nerve, which lies just above it, forms the chief guide to the artery.

#### The External Iliac Artery (*A. Iliaca Externa*) (Fig. 615).

The **external iliac artery** is larger than the hypogastric, and passes obliquely downward and lateralward along the medial border of the Psoas major, from the bifurcation of the common iliac to a point beneath the inguinal ligament, midway between the anterior superior spine of the ilium and the symphysis pubis, where it enters the thigh and becomes the femoral artery.

**Relations.**—*In front and medially*, the artery is in relation with the peritoneum, subperitoneal areolar tissue, the termination of the ileum and frequently the vermiform process on the right side, and the sigmoid colon on the left, and a thin layer of fascia, derived from the iliac fascia, which surrounds the artery and vein. At its origin it is crossed by the ovarian vessels in the female, and occasionally by the ureter. The internal spermatic vessels lie for some distance upon it near its termination, and it is crossed in this situation by the external spermatic branch of the genitofemoral nerve and the deep iliac circumflex vein; the ductus deferens in the male, and the round ligament of the uterus in the female, curve down across its medial side. *Behind*, it is in relation with the medial border of the Psoas major, from which it is separated by the iliac fascia. At the upper part of its course, the external iliac vein lies partly behind it, but lower down lies entirely to its medial side. *Laterally*, it rests against the Psoas major, from which it is separated by the iliac fascia. Numerous lymphatic vessels and lymph glands lie on the front and on the medial side of the vessel.

**Applied Anatomy.**—The application of a ligature to the external iliac may be required in cases of aneurism of the femoral artery, iliofemoral aneurism, or for a wound of the artery. The vessel may be secured in any part of its course, excepting near its upper end, which is to be avoided on account of the proximity of the hypogastric, and near its lower end, which should also be avoided on account of the proximity of the inferior epigastric and deep iliac circumflex vessels. The operation may be performed by opening the abdomen and incising the peritoneum over the artery (*transperitoneal*); or by an incision in the iliac region, dividing all the structures down to the peritoneum, which is then reflected medialward unopened from the iliac fossa until the artery is reached (*retroperitoneal*).

The transperitoneal ligature requires an incision through the abdominal wall into the peritoneal cavity. The intestines are then pushed upward and held out of the way by a broad abdominal retractor, and an incision made through the peritoneum at the margin of the pelvis in the course of the artery; the vessel is secured in any part of its course which may seem desirable to the operator. The advantages of this operation appear to be, that if it is found necessary, the common iliac artery can be ligatured instead of the external iliac without extension or modification of the incision; and secondly, that the vessel can be ligatured without in any way interfering with the sac of an aneurism.

The retroperitoneal ligature may be performed by an incision above and parallel to the lateral half of the inguinal ligament. The abdominal muscles and transversalis fascia having been cautiously divided, the peritoneum should be separated from the iliac fossa and raised toward the pelvis; and on introducing the finger to the bottom of the wound, the artery may be felt pulsating along the medial border of the Psoas major. The external iliac vein is generally found on the medial side of the artery, and must be cautiously separated from it, and the aneurism needle should be introduced on the medial side, between the artery and vein.

**Collateral Circulation.**—The principal anastomoses in carrying on the collateral circulation, after the application of a ligature to the external iliac, are: the ilio-lumbar with the iliac circumflex; the superior gluteal with the lateral femoral circumflex; the obturator with the medial femoral circumflex; the inferior gluteal with the first perforating and circumflex branches of the profunda artery; and the internal pudendal with the external pudendal. When the obturator arises from the inferior epigastric, it is supplied with blood by branches, from either the hypogastric, the lateral sacral, or the internal pudendal. The inferior epigastric receives its supply from the internal mammary and lower intercostal arteries, and from the hypogastric by the anastomoses of its branches with the obturator.<sup>1</sup>

**Branches.**—Besides several small branches to the Psoas major and the neighboring lymph glands, the external iliac gives off two branches of considerable size:

#### Inferior Epigastric.

#### Deep Iliac Circumflex.

The **inferior epigastric artery** (*a. epigastrica inferior; deep epigastric artery*) (Fig. 623) arises from the external iliac, immediately above the inguinal ligament. It curves forward in the subperitoneal tissue, and then ascends obliquely along the medial margin of the abdominal inguinal ring; continuing its course upward, it pierces the transversalis fascia, and, passing in front of the linea semicircularis, ascends between the Rectus abdominis and the posterior lamella of its sheath. It finally divides into numerous branches, which anastomose, above the umbilicus, with the superior epigastric branch of the internal mammary and with the lower intercostal arteries (Fig. 598). As the inferior epigastric artery passes obliquely upward from its origin it lies along the lower and medial margins of the abdominal inguinal ring, and behind the commencement of the spermatic cord. The ductus deferens, as it leaves the spermatic cord in the male, and the round ligament of the uterus in the female, winds around the lateral and posterior aspects of the artery.

**Branches.**—The branches of the vessel are: the **external spermatic artery** (*cremasteric artery*), which accompanies the spermatic cord, and supplies the Cremaster and other coverings of the cord, anastomosing with the internal spermatic artery (in the female it is very small and accompanies the round ligament); a **pubic branch** which runs along the inguinal ligament, and then descends along the medial margin of the femoral ring to the back of the pubis, and there anastomoses with the pubic branch of the obturator artery; **muscular branches**, some of which are distributed to the abdominal muscles and peritoneum, anastomosing with the iliac circumflex and lumbar arteries; branches which perforate the tendon of the Obliquus externus, and supply the integument, anastomosing with branches of the superficial epigastric.

**Peculiarities.**—The origin of the inferior epigastric may take place from any part of the external iliac between the inguinal ligament and a point 6 cm. above it; or it may arise below this ligament, from the femoral. It frequently springs from the external iliac, by a common trunk with the obturator. Sometimes it arises from the obturator, the latter vessel being furnished by the

<sup>1</sup> Sir Astley Cooper describes in Guy's Hospital Reports, vol. i, the dissection of a limb eighteen years after successful ligature of the external iliac artery.

hypogastric, or it may be formed of two branches, one derived from the external iliac, the other from the hypogastric.

**Applied Anatomy.**—The inferior epigastric artery has important surgical relations, and is one of the principal means, through its anastomosis with the internal mammary, of establishing the collateral circulation after ligature of either the common or external iliac arteries. It lies close to the abdominal inguinal ring, and is therefore *medial* to an oblique inguinal hernia, but *lateral* to a direct inguinal hernia, as these emerge from the abdomen. It forms the lateral boundary of Hesselbach's triangle, and is in close relationship with the spermatic cord, which lies in front of it in the inguinal canal, separated only by the transversalis fascia. The ductus deferens hooks around its lateral side.

The **deep iliac circumflex artery** (*a. circumflexa ilium profunda*) arises from the lateral aspect of the external iliac nearly opposite the inferior epigastric artery. It ascends obliquely lateralward behind the inguinal ligament, contained in a fibrous sheath formed by the junction of the transversalis fascia and iliac fascia, to the anterior superior iliac spine, where it anastomoses with the ascending branch of the lateral femoral circumflex artery. It then pierces the transversalis fascia and passes along the inner lip of the crest of the ilium to about its middle, where it perforates the Transversus, and runs backward between that muscle and the Obliquus internus, to anastomose with the iliolumbar and superior gluteal arteries. Opposite the anterior superior spine of the ilium it gives off a large branch, which ascends between the Obliquus internus and Transversus muscles, supplying them, and anastomosing with the lumbar and inferior epigastric arteries.

### THE ARTERIES OF THE LOWER EXTREMITY.

The artery which supplies the greater part of the lower extremity is the direct continuation of the external iliac. It runs as a single trunk from the inguinal ligament to the lower border of the Popliteus, where it divides into two branches, the **anterior** and **posterior tibial**. The upper part of the main trunk is named the **femoral**, the lower part the **popliteal**.

#### THE FEMORAL ARTERY (A. FEMORALIS) (Figs. 624, 625).

The **femoral artery** begins immediately behind the inguinal ligament, midway between the anterior superior spine of the ilium and the symphysis pubis, and passes down the front and medial side of the thigh. It ends at the junction of the middle with the lower third of the thigh, where it passes through an opening in the Adductor magnus to become the popliteal artery. The vessel, at the upper part of the thigh, lies in front of the hip-joint; in the lower part of its course it lies to the medial side of the body of the femur, and between these two parts, where it crosses the angle between the head and body, the vessel is some distance from the bone. The first 4 cm. of the vessel is enclosed, together with the femoral vein, in a fibrous sheath—the **femoral sheath**. In the upper third of the thigh the femoral artery is contained in the **femoral triangle** (*Scarpa's triangle*), and in the middle third of the thigh, in the **adductor canal** (*Hunter's canal*).

The **femoral sheath** (*crural sheath*) (Figs. 621, 622) is formed by a prolongation downward, behind the inguinal ligament, of the fasciæ which line the abdomen, the transversalis fascia being continued down in front of the femoral vessels and the iliac fascia behind them. The sheath assumes the form of a short funnel, the wide end of which is directed upward, while the lower, narrow end fuses with the fascial investment of the vessels, about 4 cm. below the inguinal ligament. It is strengthened in front by a band termed the **deep crural arch** (page 509). The lateral wall of the sheath is vertical and is perforated by the lumboinguinal nerve; the medial wall is directed obliquely downward and lateralward, and is pierced by the






FIG. 621.—Femoral sheath laid open to show its three compartments.




FIG. 622.—Structures passing behind the inguinal ligament.



great saphenous vein and by some lymphatic vessels. The sheath is divided by two vertical partitions which stretch between its anterior and posterior walls. The lateral compartment contains the femoral artery, and the intermediate the femoral vein, while the medial and smallest compartment is named the **femoral canal**, and contains some lymphatic vessels and a lymph gland imbedded in a small amount of areolar tissue. The femoral canal is conical and measures about 1.25 cm. in length. Its base, directed upward and named the **femoral ring**, is oval in form, its long diameter being directed transversely and measuring about 1.25 cm. The femoral ring (Figs. 622, 623) is bounded in *front* by the inguinal ligament, *behind* by the Pectineus covered by the pectineal fascia, *medially* by the crescentic base of the lacunar ligament, and *laterally* by the fibrous septum on the medial side of the femoral vein. The spermatic cord in the male and the round ligament of the uterus in the female lie immediately above the anterior margin of the ring, while the inferior epigastric vessels are close to its upper and lateral angle. The femoral ring is closed by a somewhat condensed portion of the extraperitoneal fatty tissue, named the **septum femorale** (*crural septum*), the abdominal surface




FIG. 623.—The relations of the femoral and abdominal inguinal rings, seen from within the abdomen. Right side.

of which supports a small lymph gland and is covered by the parietal layer of the peritoneum. The septum femorale is pierced by numerous lymphatic vessels passing from the deep inguinal to the external iliac lymph glands, and the parietal peritoneum immediately above it presents a slight depression named the **femoral fossa**.

The **femoral triangle** (*trigonum femorale*; *Scarpa's triangle*) (Fig. 624) corresponds to the depression seen immediately below the fold of the groin. Its apex is directed downward, and the sides are formed laterally by the medial margin of the Sartorius, medially by the medial margin of the Adductor longus, and above by the inguinal ligament. The floor of the space is formed from its lateral to its medial side by the Iliacus, Psoas major, Pectineus, in some cases a small part of the Adductor brevis, and the Adductor longus; and it is divided into two nearly equal parts by the femoral vessels, which extend from near the middle of its base to its apex: the artery giving off in this situation its superficial and profunda branches, the vein receiving the deep femoral and great saphenous tributaries. On the lateral side of the femoral artery is the femoral nerve dividing into its

branches. Besides the vessels and nerves, this space contains some fat and lymphatics.

The **adductor canal** (*canalis adductorius*; *Hunter's canal*) is an aponeurotic tunnel in the middle third of the thigh, extending from the apex of the femoral triangle to the opening in the Adductor magnus. It is bounded, in front and laterally, by the Vastus medialis; behind by the Adductores longus and magnus; and is covered in by a strong aponeurosis which extends from the Vastus medialis, across the femoral vessels to the Adductores longus and magnus; lying on the aponeurosis is the Sartorius muscle. The canal contains the femoral artery and vein, the saphenous nerve, and the nerve to the Vastus medialis.




FIG. 624.—The left femoral triangle.

**Relations of the Femoral Artery.**—In the *femoral triangle* (Fig. 624) the artery is superficial. In front of it are the skin and superficial fascia, the superficial subinguinal lymph glands, the superficial iliac circumflex vein, the superficial layer of the fascia lata and the anterior part of the femoral sheath. The lumboinguinal nerve courses for a short distance within the lateral compartment of the femoral sheath, and lies at first in front and then lateral to the artery. Near the apex of the femoral triangle the medial branch of the anterior femoral cutaneous nerve crosses the artery from its lateral to its medial side.

Behind the artery are the posterior part of the femoral sheath, the pectineal fascia, the medial part of the tendon of the Psoas major, the Pectineus and the Adductor longus. The artery is separated from the capsule of the hip-joint by the tendon of the Psoas major, from the Pectineus by the femoral vein and profunda vessels, and from the Adductor longus by the femoral vein. The nerve to the Pectineus passes medialward behind the artery. On the lateral side of the artery, but separated from it by some fibres of the Psoas major, is the femoral nerve. The femora



vein is on the medial side of the upper part of the artery, but is behind the vessel in the lower part of the femoral triangle.

In the *adductor canal* (Fig. 625) the femoral artery is more deeply situated, being covered by the integument, the superficial and deep fasciæ, the Sartorius and the fibrous roof of the canal; the saphenous nerve crosses from its lateral to its medial side. Behind the artery are the Adductores longus and magnus; in front and lateral to it is the Vastus medialis. The femoral vein lies posterior to the upper part, and lateral to the lower part of the artery.




FIG. 625.—The femoral artery.

**Peculiarities.**—Several cases are recorded in which the femoral artery divided into two trunks below the origin of the profunda, and became reunited near the opening in the Adductor magnus, so as to form a single popliteal artery. One occurred in a patient who was operated upon for popliteal aneurism. A few cases have been recorded in which the femoral artery was absent, its place being supplied by the inferior gluteal artery which accompanied the sciatic nerve to the

popliteal fossa. The external iliac in these cases was small, and terminated in the profunda. The femoral vein is occasionally placed along the medial side of the artery throughout the entire extent of the femoral triangle; or it may be split so that a large vein is placed on either side of the artery for a greater or lesser distance.

**Applied Anatomy.**—Compression of the femoral artery, which is constantly requisite in amputations and other operations on the lower limb, is most effectually made immediately below the inguinal ligament. In this situation the artery is very superficial, and is merely separated from the superior ramus of the pubis by the Psoas major; here digital compression will effectually control the circulation through it. The vessel may also be controlled in the middle third of the thigh by a tourniquet, which presses the vessel against the medial side of the body of the femur.

The superficial position of the femoral artery in the femoral triangle renders it particularly liable to be injured in wounds, stabs, or gunshot injuries in the groin. On account of the close relationship between the artery and vein, the latter vessel is also liable to be wounded in these injuries. In such cases, the artery being compressed as it crosses the ramus of the pubis, the skin wound should be enlarged and the wound in the vessel sought for, and a ligature applied above and below the bleeding point.

The application of a ligature to the femoral artery may be required in cases of wound or aneurism of the popliteal, femoral, or arteries of the leg; and the vessel may be exposed and tied in any part of its course. The most favorable situation for the application of a ligature to the femoral is at the apex of the femoral triangle. In order to reach the artery in this situation, an incision 7 cm. long should be made in the course of the vessel, the patient lying in the recumbent position, with the limb slightly flexed and abducted, and rotated outward. A large vein is frequently met with, passing in the course of the artery to join the great saphenous vein; this must be avoided, and the fascia lata having been cautiously divided, and the Sartorius displayed, that muscle must be drawn lateralward, in order to expose fully the sheath of the vessels. The finger having been introduced into the wound, and the pulsation of the artery felt, the sheath is opened on the lateral side of the vessel to a sufficient extent to allow of the introduction of the aneurism needle. In this part of the operation the saphenous nerve and the nerve to the Vastus medialis, which are in close relation with the sheath, should be avoided. The aneurism needle must be carefully introduced and kept close to the artery, to avoid the femoral vein, which lies behind the vessel in this part of its course, and is very closely bound up with it.

To expose the artery in the adductor canal, an incision 7 cm. in length should be made through the integument, a finger's breadth medial to the line of the artery, the centre of the incision being in the middle of the thigh—i. e., midway between the groin and the knee. The fascia lata having been divided, and the lateral border of the Sartorius exposed, this muscle should be drawn medialward, when the strong fascia which is stretched across from the Adductors to the Vastus medialis will be observed, and must be freely divided; the sheath of the vessels is now seen, and must be opened, and the artery secured by passing the aneurism needle between it and the vein, from the lateral to the medial side of the artery. In this situation the femoral vein lies lateral to, and the saphenous nerve in front of the artery.

**Collateral Circulation.**—After ligature of the femoral artery, the main channels for carrying on the circulation are the anastomoses between—(1) the superior and inferior gluteal branches of the hypogastric with the medial and lateral femoral circumflex and first perforating branches of the profunda femoris; (2) the obturator branch of the hypogastric with the medial femoral circumflex of the profunda; (3) the internal pudendal of the hypogastric with the superficial and deep external pudendal of the femoral; (4) the deep iliac circumflex of the external iliac with the lateral femoral circumflex of the profunda and the superficial iliac circumflex of the femoral, and (5) the inferior gluteal of the hypogastric with the perforating branches of the profunda.

**Branches.**—The branches of the femoral artery are;

Superficial Epigastric.	Deep External Pudendal.
Superficial Iliac Circumflex.	Muscular.
Superficial External Pudendal.	Profunda Femoris.
Highest Genicular.	

The **superficial epigastric artery** (*a. epigastrica superficialis*) arises from the front of the femoral artery about 1 cm. below the inguinal ligament, and, passing through the femoral sheath and the fascia cribrosa, turns upward in front of the inguinal ligament, and ascends between the two layers of the superficial fascia of the abdominal wall nearly as far as the umbilicus. It distributes branches to the superficial subinguinal lymph glands, the superficial fascia, and the integument; it anastomoses with branches of the inferior epigastric, and with its fellow of the opposite side.

The **superficial iliac circumflex artery** (*a. circumflexa ilium superficialis*), the smallest of the cutaneous branches, *arises* close to the preceding, and, piercing the fascia lata, runs lateralward, parallel with the inguinal ligament, as far as the crest of the ilium; it divides into branches which supply the integument of the groin, the superficial fascia, and the superficial subinguinal lymph glands, anastomosing with the deep iliac circumflex, the superior gluteal and lateral femoral circumflex arteries.

The **superficial external pudendal artery** (*a. pudenda externa superficialis; superficial external pudic artery*) *arises* from the medial side of the femoral artery, close to the preceding vessels, and, after piercing the femoral sheath and fascia cribrosa, courses medialward, across the spermatic cord (or round ligament in the female), to be distributed to the integument on the lower part of the abdomen, the penis and scrotum in the male, and the labium majus in the female, anastomosing with branches of the internal pudendal.

The **deep external pudendal artery** (*a. pudenda externa profunda; deep external pudic artery*), more deeply seated than the preceding, passes medialward across the Pectineus and the Adductor longus muscles; it is covered by the fascia lata, which it pierces at the medial side of the thigh, and is distributed, in the male, to the integument of the scrotum and perineum, in the female to the labium majus; its branches anastomose with the scrotal (or labial) branches of the perineal artery.

**Muscular branches** (*rami musculares*) are supplied by the femoral artery to the Sartorius, Vastus medialis, and Adductores.

The **profunda femoris artery** (*a. profunda femoris; deep femoral artery*) (Fig. 625) is a large vessel *arising* from the lateral and back part of the femoral artery, from 2 to 5 cm. below the inguinal ligament. At first it lies lateral to the femoral artery; it then runs behind it and the femoral vein to the medial side of the femur, and, passing downward behind the Adductor longus, ends at the lower third of the thigh in a small branch, which pierces the Adductor magnus, and is distributed on the back of the thigh to the hamstring muscles. The terminal part of the profunda is sometimes named the **fourth perforating artery**.

**Relations.**—*Behind it*, from above downward, are the Iliacus, Pectineus, Adductor brevis, and Adductor magnus. *In front* it is separated from the femoral artery by the femoral and profunda veins above and by the Adductor longus below. *Laterally*, the origin of the Vastus medialis intervenes between it and the femur.

**Peculiarities.**—This vessel sometimes arises from the medial side, and, more rarely, from the back of the femoral artery; but a more important peculiarity, from a surgical point of view, is that relating to the height at which the vessel arises. In three-fourths of a large number of cases it arose from 2.25 to 5 cm. below the inguinal ligament; in a few cases the distance was less than 2.25 cm.; more rarely, opposite the ligament; and in one case above the inguinal ligament, from the external iliac. Occasionally the distance between the origin of the vessel and the inguinal ligament exceeds 5 cm.

**Branches.**—The profunda gives off the following branches:

Lateral Femoral Circumflex.	Perforating.
Medial Femoral Circumflex.	Muscular.

The **Lateral Femoral Circumflex Artery** (*a. circumflexa femoris lateralis; external circumflex artery*) *arises* from the lateral side of the profunda, passes horizontally between the divisions of the femoral nerve, and behind the Sartorius and Rectus femoris, and divides into ascending, transverse, and descending branches.

The **ascending branch** passes upward, beneath the Tensor fasciae latae, to the lateral aspect of the hip, and anastomoses with the terminal branches of the superior gluteal and deep iliac circumflex arteries.

The **descending branch** runs downward, behind the Rectus femoris, upon the Vastus lateralis, to which it gives offsets; one long branch descends in the muscle as far as the knee, and anastomoses with the superior lateral genicular branch of

the popliteal artery. It is accompanied by the branch of the femoral nerve to the Vastus lateralis.

The **transverse branch**, the smallest, passes lateralward over the Vastus intermedius, pierces the Vastus lateralis, and winds around the femur, just below the greater trochanter, anastomosing on the back of the thigh with the medial femoral circumflex, inferior gluteal, and first perforating arteries.

The **Medial Femoral Circumflex Artery** (*a. circumflexa femoris medialis; internal circumflex artery*) arises from the medial and posterior aspect of the profunda, and winds around the medial side of the femur, passing first between the Pectineus and Psoas major, and then between the Obturator externus and the Adductor brevis. At the upper border of the Adductor brevis it gives off two branches: one is distributed to the Adductores, the Gracilis, and Obturator externus, and anastomoses with the obturator artery; the other descends beneath the Adductor brevis, to supply it and the Adductor magnus; the continuation of the vessel passes backward and divides into superficial, deep, and acetabular branches. The **superficial branch** appears between the Quadratus femoris and upper border of the Adductor magnus, and anastomoses with the inferior gluteal, lateral femoral circumflex, and first perforating arteries (*crucial anastomosis*). The **deep branch** runs obliquely upward upon the tendon of the Obturator externus and in front of the Quadratus femoris toward the trochanteric fossa, where it anastomoses with twigs from the gluteal arteries. The **acetabular branch** arises opposite the acetabular notch and enters the hip-joint beneath the transverse ligament in company with an articular branch from the obturator artery; it supplies the fat in the bottom of the acetabulum, and is continued along the round ligament to the head of the femur.

The **Perforating Arteries** (Fig. 620), usually three in number, are so named because they perforate the tendon of the Adductor magnus to reach the back of the thigh. They pass backward close to the linea aspera of the femur under cover of small tendinous arches in the muscle. The first is given off above the Adductor brevis, the second in front of that muscle, and the third immediately below it.

The **first perforating artery** (*a. perforans prima*) passes backward between the Pectineus and Adductor brevis (sometimes it perforates the latter); it then pierces the Adductor magnus close to the linea aspera. It gives branches to the Adductores brevis and magnus, Biceps femoris, and Glutaeus maximus, and anastomoses with the inferior gluteal, medial and lateral femoral circumflex and second perforating arteries.

The **second perforating artery** (*a. perforans secunda*), larger than the first, pierces the tendons of the Adductores brevis and magnus, and divides into ascending and descending branches, which supply the posterior femoral muscles, anastomosing with the first and third perforating. The second artery frequently arises in common with the first. The **nutrient artery** of the femur is usually given off from the second perforating artery; when two nutrient arteries exist, they usually spring from the first and third perforating vessels.

The **third perforating artery** (*a. perforans tertia*) is given off below the Adductor brevis; it pierces the Adductor magnus, and divides into branches which supply the posterior femoral muscles; anastomosing above with the higher perforating arteries, and below with the terminal branches of the profunda and the muscular branches of the popliteal. The nutrient artery of the femur may arise from this branch. The termination of the profunda artery, already described, is sometimes termed the **fourth perforating artery**.

Numerous **muscular branches** arise from the profunda; some of these end in the Adductores, others pierce the Adductor magnus, give branches to the hamstrings, and anastomose with the medial femoral circumflex artery and with the superior muscular branches of the popliteal.



The **highest genicular artery** (*a. genu suprema; anastomotica magna artery*) (Fig. 625) arises from the femoral just before it passes through the opening in the tendon of the Adductor magnus, and immediately divides into a saphenous and a musculo-articular branch.

The **saphenous branch** pierces the aponeurotic covering of the adductor canal, and accompanies the saphenous nerve to the medial side of the knee. It passes between the Sartorius and Gracilis, and, piercing the fascia lata, is distributed to the integument of the upper and medial part of the leg, anastomosing with the medial inferior genicular artery.

The **musculoarticular branch** descends in the substance of the Vastus medialis, and in front of the tendon of the Adductor magnus, to the medial side of the knee, where it anastomoses with the medial superior genicular artery and anterior recurrent tibial artery. A branch from this vessel crosses above the patellar surface of the femur, forming an anastomotic arch with the lateral superior genicular artery, and supplying branches to the knee-joint.

### THE POPLITEAL FOSSA (Fig. 626).

**Dissection.**—A vertical incision about eight inches in length should be made along the back part of the knee-joint, connected above and below by a transverse incision from the inner to the outer side of the limb. The flaps of integument included between these incisions should be reflected in the direction shown in Fig. 570.

**Boundaries.**—The **popliteal fossa** or **space** is a lozenge-shaped space, at the back of the knee-joint. Laterally it is bounded by the Biceps femoris above, and by the Plantaris and the lateral head of the Gastrocnemius below; medially it is limited by the Semitendinosus and Semimembranosus above, and by the medial head of the Gastrocnemius below. The floor is formed by the popliteal surface of the femur, the oblique popliteal ligament of the knee-joint, the upper end of the tibia, and the fascia covering the Popliteus; the fossa is covered in by the fascia lata.

**Contents.**—The popliteal fossa contains the popliteal vessels, the tibial and the common peroneal nerves, the termination of the small saphenous vein, the lower part of the posterior femoral cutaneous nerve, the articular branch from the obturator nerve, a few small lymph glands, and a considerable quantity of fat. The tibial nerve descends through the middle of the fossa, lying under the deep fascia and crossing the vessels posteriorly from the lateral to the medial side. The common peroneal nerve descends on the lateral side of the upper part of the fossa, close to the tendon of the Biceps femoris. On the floor of the fossa are the popliteal vessels, the vein being superficial to the artery and united to it by dense areolar tissue; the vein is a thick-walled vessel, and lies at first lateral to the artery, and then crosses it posteriorly to gain its medial side below; sometimes it is double, the artery lying between the two veins, which are usually connected by short transverse branches. The articular branch from the obturator nerve descends upon the artery to the knee-joint. The popliteal lymph glands, six or seven in number, are imbedded in the fat; one lies beneath the popliteal fascia near the termination of the external saphenous vein, another between the popliteal artery and the back of the knee-joint, while the others are placed at the sides of the popliteal vessel. Arising from the artery, and passing off from it at right angles, are its genicular branches.

### The Popliteal Artery (A. Poplitea) (Fig. 626).

The **popliteal artery** is the continuation of the femoral, and courses through the popliteal fossa. It extends from the opening in the Adductor magnus, at the junction of the middle and lower thirds of the thigh, downward and lateralward to the intercondyloid fossa of the femur, and then vertically downward to the lower border of the Popliteus, where it divides into **anterior** and **posterior tibial arteries**.

**Relations.**—In front of the artery from above downward are the popliteal surface of the femur (which is separated from the vessel by some fat), the back of the knee-joint, and the fascia covering the Popliteus. Behind, it is overlapped by the Semimembranosus above, and is covered by the Gastrocnemius and Plantaris below. In the middle part of its course the artery is separated from the integument and fasciæ by a quantity of fat, and is crossed from the lateral to the medial side by the tibial nerve and the popliteal vein, the vein being between the nerve and the artery and closely adherent to the latter. On its lateral side, above, are the Biceps femoris, the tibial nerve, the popliteal vein, and the lateral condyle of the femur; below, the Plantaris and the lateral head of the Gastrocnemius. On its medial side, above, are the Semimembranosus and the medial condyle of the femur; below, the tibial nerve, the popliteal vein, and the medial head of the Gastrocnemius. The relations of the popliteal lymph glands to the artery are described above.

**Peculiarities in Point of Division.**—Occasionally the popliteal artery divides into its terminal branches opposite the knee-joint. The anterior tibial under these circumstances usually passes in front of the Popliteus.

**Unusual Branches.**—The artery sometimes divides into the anterior tibial and peroneal, the posterior tibial being wanting, or very small. Occasionally it divides into three branches, the anterior and posterior tibial, and peroneal.

**Applied Anatomy.**—The popliteal artery is not infrequently the seat of injury. It may be torn by direct violence, as by the passage of a cart wheel over the knee, or by hyperextension of the knee. It may also be lacerated by fracture of the lower part of the body of the femur, or by antero-posterior dislocation of the knee-joint. It has been torn in breaking down adhesions in cases of fibrous ankylosis of the knee, and is in danger of being wounded, and in fact has been wounded, in performing MacEwen's operation of osteotomy of the lower end of the femur for genu valgum. The popliteal artery is more frequently the seat of aneurism than any other artery in the body, with the exception of the thoracic aorta. No doubt this is due in a great measure to the amount of movement to which it is subjected, and to the fact that it is supported by loose and lax tissue only, and not by muscles as is the case with most arteries. When the knee is acutely flexed the popliteal artery becomes bent on itself to such an extent as to entirely arrest the circulation through it.

Ligature of the popliteal artery is required in cases of wound of the vessel, but for aneurism it is preferable to tie the femoral. The popliteal may be tied in the upper or lower part of its course; but in the middle of the fossa the operation is attended with considerable difficulty, from the great depth of the vessel, and from the extreme degree of tension of the lateral and medial boundaries of the fossa.

In order to expose the upper part of the vessel, the patient should be placed in the supine position, with the knee flexed and the thigh abducted and rotated outward, so that it rests on its lateral surface; an incision 7 or 8 cm. in length, beginning at the junction of the middle and lower thirds of the thigh, is to be made parallel




FIG. 626.—The popliteal, posterior tibial, and peroneal arteries.

to and immediately behind the tendon of the adductor magnus, and the skin, superficial and deep fasciæ divided. The tendon of the muscle is thus exposed, and is to be drawn forward, and the hamstring tendons backward. A quantity of fatty tissue will now be opened up, in which the artery will be felt pulsating. This is to be separated with the point of a director until the artery is exposed. The vein and nerve will not be seen, as they lie to the lateral side of the artery. The sheath is to be opened and the aneurism needle passed from before backward, keeping its point close to the artery for fear of injuring the vein. The only structure to avoid in the superficial incision is the great saphenous vein.

To expose the vessel in the lower part of its course, where the artery lies between the two heads of the Gastrocnemius, the patient should be placed in the prone position with the limb extended. An incision should then be made through the integument in the middle line, commencing opposite the bend of the knee-joint, care being taken to avoid the small saphenous vein and the medial sural cutaneous nerve. After dividing the deep fascia, and separating some dense cellular tissue, the artery, vein, and nerve will be exposed, between the two heads of the Gastrocnemius. Some muscular branches of the popliteal should be avoided if possible, or, if divided, tied immediately. The leg being now flexed, in order the more effectually to separate the two heads of the Gastrocnemius, the nerve should be drawn medialward and the vein lateralward, and the aneurism needle passed between the artery and vein from the lateral to the medial side.

**Branches.**—The branches of the popliteal artery are:

Muscular	{ Superior	Lateral Superior Genicular.
	{ Sural.	Middle Genicular.
Cutaneous.		Medial Inferior Genicular.
Medial Superior Genicular		Lateral Inferior Genicular.

The **superior muscular branches**, two or three in number, *arise* from the upper part of the artery, and are distributed to the lower parts of the Adductor magnus and hamstring muscles, anastomosing with the terminal part of the profunda femoris.

The **sural arteries** (*aa. surales; inferior muscular arteries*) are two large branches, which are distributed to the Gastrocnemius, Soleus, and Plantaris. They *arise* from the popliteal artery opposite the knee-joint.

The **cutaneous branches** *arise* either from the popliteal artery or from some of its branches; they descend between the two heads of the Gastrocnemius, and, piercing the deep fascia, are distributed to the skin of the back of the leg. One branch usually accompanies the small saphenous vein.

The **superior genicular arteries** (*aa. genu superiores; superior articular arteries*) (Figs. 625, 626), two in number, *arise* one on either side of the popliteal, and wind around the femur immediately above its condyles to the front of the knee-joint. The **medial superior genicular** runs in front of the Semimembranosus and Semitendinosus, above the medial head of the Gastrocnemius, and passes beneath the tendon of the Adductor magnus. It divides into two branches, one of which supplies the Vastus medialis, anastomosing with the highest genicular and medial inferior genicular arteries; the other ramifies close to the surface of the femur, supplying it and the knee-joint, and anastomosing with the lateral superior genicular artery. The medial superior genicular artery is frequently of small size, a condition, which is associated with an increase in the size of the highest genicular. The **lateral superior genicular** passes above the lateral condyle of the femur, beneath the tendon of the Biceps femoris, and divides into a superficial and a deep branch; the superficial branch supplies the Vastus lateralis, and anastomoses with the descending branch of the lateral femoral circumflex and the lateral inferior genicular arteries; the deep branch supplies the lower part of the femur and knee-joint, and forms an anastomotic arch across the front of the bone with the highest genicular and the medial inferior genicular arteries.

The **middle genicular artery** (*a. genu media; azygos articular artery*) is a small branch, *arising* opposite the back of the knee-joint. It pierces the oblique popliteal ligament, and supplies the ligaments and synovial membrane in the interior of the articulation.

The **inferior genicular arteries** (*aa. genu inferiores; inferior articular arteries*) (Figs. 625, 626), two in number, *arise* from the popliteal beneath the Gastrocnemius. The **medial inferior genicular** first descends along the upper margin of the Popliteus, to which it gives branches; it then passes below the medial condyle of the tibia, beneath the tibial collateral ligament, at the anterior border of which it ascends to the front and medial side of the joint, to supply the upper end of the tibia and the articulation of the knee, anastomosing with the lateral inferior and medial superior genicular arteries. The **lateral inferior genicular** runs lateralward above the head of the fibula to the front of the knee-joint, passing in its course beneath the lateral head of the Gastrocnemius, the fibular collateral ligament, and the tendon of the Biceps femoris. It ends by dividing into branches, which anastomose with the medial inferior and lateral superior genicular arteries, and with the anterior recurrent tibial artery.




FIG. 627.—Circumpatellar anastomosis.

**The Anastomosis Around the Knee-joint** (Fig. 627).—Around and above the patella, and on the contiguous ends of the femur and tibia, is an intricate net-work of vessels forming a superficial and a deep plexus. The **superficial plexus** is situated between the fascia and skin around about the patella, and forms three well-defined arches: one, above the upper border of the patella, in the loose connective tissue over the Quadriceps femoris; the other two, below the level of the patella, are situated in the fat behind the ligamentum patellae. The **deep plexus**, which forms a close net-work of vessels, lies on the lower end of the femur and upper end of the tibia around their articular surfaces, and sends numerous offsets into the interior of the joint. The arteries which form this plexus are the two medial and the two lateral genicular branches of the popliteal, the highest genicular, the descending branch of the lateral femoral circumflex, and the anterior recurrent tibial.

### The Anterior Tibial Artery (A. Tibialis Anterior) (Fig. 628).

The **anterior tibial artery** commences at the bifurcation of the popliteal, at the lower border of the Popliteus, passes forward between the two heads of the Tibialis posterior, and through the aperture above the upper border of the interosseous membrane, to the deep part of the front of the leg: it here lies close to the medial side of the neck of the fibula. It then descends on the anterior surface of the interosseous membrane, gradually approaching the tibia; at the lower part of the leg it lies on this bone, and then on the front of the ankle-joint, where it is more superficial, and becomes the **dorsalis pedis**.

**Relations.**—In the upper two-thirds of its extent, the anterior tibial artery rests upon the interosseous membrane; in the lower third, upon the front of the tibia, and the anterior ligament of the ankle-joint. In the upper third of its course, it lies between the Tibialis anterior and Extensor digitorum longus; in the middle third between the Tibialis anterior and Extensor hallucis longus. At the ankle it is crossed from the lateral to the medial side by the tendon of the Extensor hallucis longus, and lies between it and the first tendon of the Extensor digitorum longus. It is covered in the upper two-thirds of its course, by the muscles which lie on either side of it, and by the deep fascia; in the lower third, by the integument and fascia, and the transverse and cruciate crural ligaments.

The anterior tibial artery is accompanied by a pair of *venae comitantes* which lie one on either side of the artery; the deep peroneal nerve, coursing around the lateral side of the neck of the fibula, comes into relation with the lateral side of the artery shortly after it has reached the front of the leg; about the middle of the leg the nerve is in front of the artery; at the lower part it is generally again on the lateral side.

**Peculiarities in Size.**—This vessel may be diminished in size, may be deficient to a greater or less extent, or may be entirely wanting, its place being supplied by perforating branches from the posterior tibial, or by the perforating branch of the peroneal artery.

**Course.**—The artery occasionally deviates toward the fibular side of the leg, regaining its usual position at the front of the ankle. In rare instances the vessel has been found to approach the surface in the middle of the leg, being covered merely by the integument and fascia below that point.

**Applied Anatomy.**—The anterior tibial artery is liable to be injured in fractures of the lower third of the tibia, on account of its close proximity to the bone. The application of a ligature to the vessel is rarely required, except in cases of wound or for traumatic aneurism. The operation in the upper third of the leg is attended with great difficulty on account of the depth of the vessel from the surface. An incision about 10 cm. in length is made in the line of the artery to about a hand's breadth below the level of the knee-joint. The skin and superficial structures having been divided and the deep fascia exposed, the wound must be carefully dried, its edges retracted, and the white line separating the Tibialis anterior from the Extensor digitorum longus sought for. When this has been clearly defined, the deep fascia is to be divided in this line, and the Tibialis anterior separated from adjacent muscles until the interosseous membrane is reached. The foot is to be flexed in order to relax the muscles, and upon drawing them apart the artery will be found lying on the interosseous membrane with the nerve lateral or superficial to it. The nerve should be drawn lateralward, the *venae comitantes* separated from the artery and the needle passed around it.

To tie the vessel in the lower third of the leg above the ankle-joint, an incision about 7 cm. in length should be made through the integument between the tendons of the Tibialis anterior and Extensor hallucis longus, the deep fascia being divided to the same extent. The tendon on either side should be retracted, when the vessel, accompanied by the *venae comitantes*, will be seen lying upon the tibia, with the nerve on the lateral side.

**Branches.**—The branches of the anterior tibial artery are:

Posterior Tibial Recurrent.	Muscular.
Fibular.	Anterior Medial Malleolar.
Anterior Tibial Recurrent.	Anterior Lateral Malleolar.

The **posterior tibial recurrent artery** (*a. recurrens tibialis posterior*) an inconstant branch, is given off from the anterior tibial before that vessel passes through the interosseous space. It ascends in front of the Popliteus, which it supplies, and anastomoses with the inferior genicular branches of the popliteal artery, giving an offset to the tibiofibular joint.



The **fibular artery** is sometimes derived from the anterior tibial, sometimes from the posterior tibial. It passes lateralward, around the neck of the fibula, through the Soleus, which it supplies, and ends in the substance of the Peroneus longus.

The **anterior tibial recurrent artery** (*a. recurrens tibialis anterior*) arises from the anterior tibial, as soon as that vessel has passed through the interosseous space; it ascends in the Tibialis anterior, ramifies on the front and sides of the knee-joint, and assists in the formation of the patellar plexus by anastomosing with the genicular branches of the popliteal, and with the highest genicular artery.

The **muscular branches** (*rami musculares*) are numerous; they are distributed to the muscles which lie on either side of the vessel, some piercing the deep fascia to supply the integument, others passing through the interosseous membrane, and anastomosing with branches of the posterior tibial and peroneal arteries.

The **anterior medial malleolar artery** (*a. malleolaris anterior medialis; internal malleolar artery*) arises about 5 cm. above the ankle-joint, and passes behind the tendons of the Extensor hallucis longus and Tibialis anterior, to the medial side of the ankle, upon which it ramifies, anastomosing with branches of the posterior tibial and medial plantar arteries and with the medial calcaneal from the posterior tibial.

The **anterior lateral malleolar artery** (*a. malleolaris anterior lateralis; external malleolar artery*) passes beneath the tendons of the Extensor digitorum longus and Peroneus tertius and supplies the lateral side of the ankle, anastomosing with the perforating branch of the peroneal artery, and with ascending twigs from the lateral tarsal artery.

The arteries around the ankle-joint anastomose freely with one another and form net-works below the corresponding malleoli. The **medial malleolar net-work** is formed by the anterior medial malleolar branch of the anterior tibial, the medial tarsal branches of the dorsalis pedis, the posterior medial malleolar and medial calcaneal branches of the posterior tibial and branches




FIG. 628.—Anterior tibial and dorsalis pedis arteries.



from the medial plantar artery. The **lateral malleolar net-work** is formed by the anterior lateral malleolar branch of the anterior tibial, the lateral tarsal branch of the dorsalis pedis, the perforating and the lateral calcaneal branches of the peroneal, and twigs from the lateral plantar artery.

### The Arteria Dorsalis Pedis (Dorsalis Pedis Artery) (Fig. 628).

The *arteria dorsalis pedis*, the continuation of the anterior tibial, passes forward from the ankle-joint along the tibial side of the dorsum of the foot to the proximal part of the first intermetatarsal space, where it divides into two branches, the **first dorsal metatarsal** and the **deep plantar**.

**Relations.**—This vessel, in its course forward, rests upon the front of the articular capsule of the ankle-joint, the talus, navicular, and second cuneiform bones, and the ligaments connecting them, being covered by the integument, fascia and cruciate ligament, and crossed near its termination by the first tendon of the Extensor digitorum brevis. On its *tibial side* is the tendon of the Extensor hallucis longus; on its *fibular side*, the first tendon of the Extensor digitorum longus, and the termination of the deep peroneal nerve. It is accompanied by two veins.

**Peculiarities in Size.**—The dorsal artery of the foot may be larger than usual, to compensate for a deficient plantar artery; or its terminal branches to the toes may be absent, the toes then being supplied by the medial plantar; or its place may be taken altogether by a large perforating branch of the peroneal artery.

**Position.**—This artery frequently curves lateralward, lying lateral to the line between the middle of the ankle and the back part of the first interosseous space.

**Applied Anatomy.**—This artery may be tied, by making an incision 5 cm. in length, through the integument, on the fibular side of the tendon of the Extensor hallucis longus, in the interval between it and the medial border of the Extensor digitorum brevis. The incision should not extend farther forward than the proximal part of the first intermetatarsal space, as the artery divides in that situation. The deep fascia being divided to the same extent, the artery will be exposed, the deep peroneal nerve lying lateral to it.

**Branches.**—The branches of the *arteria dorsalis pedis* are:

Lateral Tarsal.  
Medial Tarsal.

Arcuate.  
First Dorsal Metatarsal.

Deep Plantar.

The **lateral tarsal artery** (*a. tarsea lateralis; tarsal artery*) arises from the dorsalis pedis, as that vessel crosses the navicular bone; it passes in an arched direction lateralward, lying upon the tarsal bones, and covered by the Extensor digitorum brevis; it supplies this muscle and the articulations of the tarsus, and anastomoses with branches of the arcuate, anterior lateral malleolar and lateral plantar arteries, and with the perforating branch of the peroneal artery.

The **medial tarsal arteries** (*aa. tarseae mediales*) are two or three small branches which ramify on the medial border of the foot and join the medial malleolar net-work.

The **arcuate artery** (*a. arcuata; metatarsal artery*) arises a little anterior to the lateral tarsal artery; it passes lateralward, over the bases of the metatarsal bones, beneath the tendons of the Extensor digitorum brevis, its direction being influenced by its point of origin; and it anastomoses with the lateral tarsal and lateral plantar arteries. This vessel gives off the **second, third, and fourth dorsal metatarsal arteries**, which run forward upon the corresponding Interossei dorsales; in the clefts between the toes, each divides into two dorsal digital branches for the adjoining toes. At the proximal parts of the interosseous spaces these vessels receive the posterior perforating branches from the plantar arch, and at the distal parts of the spaces they are joined by the anterior perforating branches, from the plantar metatarsal arteries. The fourth dorsal metatarsal artery gives off a branch which supplies the lateral side of the fifth toe.

The **first dorsal metatarsal artery** (*a. dorsalis hallucis*) runs forward on the first Interosseous dorsalis, and at the cleft between the first and second toes divides

into two branches, one of which passes beneath the tendon of the Extensor hallucis longus, and is distributed to the medial border of the great toe; the other bifurcates to supply the adjoining sides of the great and second toes.

The **deep plantar artery** (*ramus plantaris profundus; communicating artery*) descends into the sole of the foot, between the two heads of the first Interosseous dorsalis, and unites with the termination of the lateral plantar artery, to complete the plantar arch. It sends a branch along the medial side of the great toe, and is continued forward along the first interosseous space as the **first plantar metatarsal artery**, which bifurcates for the supply of the adjacent sides of the great and second toes.

### The Posterior Tibial Artery (A. Tibialis Posterior) (Fig. 626).

The **posterior tibial artery** begins at the lower border of the Popliteus, opposite the interval between the tibia and fibula; it extends obliquely downward, and, as it descends, it approaches the tibial side of the leg, lying behind the tibia, and in the lower part of its course is situated midway between the medial malleolus and the medial process of the calcaneal tuberosity. Here it divides beneath the origin of the Adductor hallucis into the **medial and lateral plantar arteries**.

**Relations.**—The posterior tibial artery lies successively upon the Tibialis posterior, the Flexor digitorum longus, the tibia, and the back of the ankle-joint. It is covered by the deep transverse fascia of the leg, which separates it above from the Gastrocnemius and Soleus; at its termination it is covered by the Abductor hallucis. In the lower third of the leg, where it is more superficial, it is covered only by the integument and fascia, and runs parallel with the medial border of the tendo calcaneus. It is accompanied by two veins, and by the tibial nerve, which lies at first to the medial side of the artery, but soon crosses it posteriorly, and is in the greater part of its course on its lateral side.

*Behind the medial malleolus*, the tendons, bloodvessels, and nerve are arranged, under cover of the lacinate ligament, in the following order from the medial to the lateral side: (1) the tendons of the Tibialis posterior and Flexor digitorum longus, lying in the same groove, behind the malleolus, the former being the more medial. Next is the posterior tibial artery, with a vein on either side of it; and lateral to the vessels is the tibial nerve; about 1.25 cm. nearer the heel is the tendon of the Flexor hallucis longus.

**Peculiarities in Size.**—The posterior tibial is not infrequently smaller than usual, or absent, its place being supplied by a large peroneal artery, which either joins the small posterior tibial artery, or continues alone to the sole of the foot.

**Applied Anatomy.**—The application of a ligature to the posterior tibial may be required in cases of wound of the sole of the foot, attended with great hemorrhage, when the vessel should be tied at the ankle. In cases of wound of the posterior tibial, it will be necessary to enlarge the opening so as to expose the vessel at the wounded point, excepting where the vessel is injured by a punctured wound from the front of the leg. In cases of aneurism from wound of the artery low down, the vessel should be tied in the middle of the leg.

To tie the posterior tibial artery at the ankle, a semilunar incision, about 6 cm. in length, convex backward, should be made through the integument, midway between the heel and the medial malleolus, or a little nearer the latter. The subcutaneous tissue having been divided, a strong and dense fascia, the lacinate (internal annular) ligament, is exposed. This ligament is continuous above with the deep fascia of the leg, covers the vessels and nerves, and is intimately adherent to the sheaths of the tendons. This having been cautiously divided upon a director, the sheath of the vessels is exposed, and, being opened, the artery is seen with one of the *venae comitantes* on either side. The aneurism needle should be passed around the vessel from the heel toward the ankle, in order to avoid the tibial nerve, care at the same time being taken not to include the *venae comitantes*.

The vessel may also be tied in the lower third of the leg by making an incision about 8 cm. in length, parallel with the medial border of the tendo calcaneus. The great saphenous vein being carefully avoided, the two layers of fascia must be divided upon a director, when the artery is exposed along the lateral margin of the Flexor digitorum longus, with one of its *venae comitantes* on either side, and the nerve lying lateral to it.

Ligature of the posterior tibial in the middle of the leg is a very difficult operation, on account of the great depth of the vessel from the surface. The patient being placed in the recumbent position, the injured limb should rest on its fibular side, the knee being partially bent, and the foot extended, so as to relax the muscles of the calf. An incision about 10 cm. in length should then be made through the integument, a finger's breadth behind the medial margin of the tibia, care being taken to avoid the great saphenous vein. The deep fascia having been divided, the

margin of the Gastrocnemius is exposed, and must be drawn aside, and the tibial attachment of the Soleus divided. The artery may now be felt pulsating beneath the deep transverse fascia, about 2.5 cm. from the margin of the tibia. This fascia having been divided, and the limb placed in such a position as to relax the muscles of the calf as much as possible, the veins should be separated from the artery and the aneurism needle passed around the vessel from the lateral to the medial side, so as to avoid wounding the tibial nerve.

**Branches.**—The branches of the posterior tibial artery are:

Peroneal.	Posterior Medial Malleolar.
Nutrient.	Communicating.
Muscular.	Medial Calcaneal.

The **peroneal artery** (*a. peronaea*) is deeply seated on the back of the fibular side of the leg. It *arises* from the posterior tibial, about 2.5 cm. below the lower border of the Popliteus, passes obliquely toward the fibula, and then descends along the medial side of that bone, contained in a fibrous canal between the Tibialis posterior and the Flexor hallucis longus, or in the substance of the latter muscle. It then runs behind the tibiofibular syndesmosis and divides into lateral calcaneal branches which ramify on the lateral and posterior surfaces of the calcaneus.

It is covered, in the *upper* part of its course, by the Soleus and deep transverse fascia of the leg; *below*, by the Flexor hallucis longus.

**Peculiarities in Origin.**—The peroneal artery may arise 7 or 8 cm. below the Popliteus, or from the posterior tibial high up, or even from the popliteal.

**Its size** is more frequently increased than diminished; and then it either reinforces the posterior tibial by its junction with it, or altogether takes the place of the posterior tibial in the lower part of the leg and foot, the latter vessel only existing as a short muscular branch. In those rare cases where the peroneal artery is smaller than usual, a branch from the posterior tibial supplies its place; and a branch from the anterior tibial compensates for the diminished anterior peroneal artery. In one case the peroneal artery was entirely wanting.

**Branches.**—The branches of the peroneal are:

Muscular.	Perforating.
Nutrient.	Communicating.
Lateral Calcaneal.	

**Muscular Branches.**—The peroneal artery, in its course, gives off branches to the Soleus, Tibialis posterior, Flexor hallucis longus, and Peronei.

The **Nutrient Artery** (*a. nutricia fibulae*) supplies the fibula, and is directed downward.

The **Perforating Branch** (*ramus perforans; anterior peroneal artery*) pierces the interosseous membrane, about 5 cm. above the lateral malleolus, to reach the front of the leg, where it anastomoses with the anterior lateral malleolar; it then passes down in front of the tibiofibular syndesmosis, gives branches to the tarsus, and anastomoses with the lateral tarsal. The perforating branch is sometimes enlarged, and takes the place of the dorsalis pedis artery.

The **Communicating Branch** (*ramus communicans*) is given off from the peroneal about 2.5 cm. from its lower end, and joins the communicating branch of the posterior tibial.

The **Lateral Calcaneal** (*ramus calcaneus lateralis; external calcaneal*) are the terminal branches of the peroneal artery; they pass to the lateral side of the heel, and communicate with the lateral malleolar and, on the back of the heel, with the medial calcaneal arteries.

The **nutrient artery** (*a. nutricia tibiae*) of the tibia *arises* from the posterior tibial, near its origin, and after supplying a few muscular branches enters the nutrient canal of the bone, which it traverses obliquely from above downward. This is the largest nutrient artery of bone in the body.

The **muscular branches** of the posterior tibial are distributed to the Soleus and deep muscles along the back of the leg.

The **posterior medial malleolar artery** (*a. malleolaris posterior medialis; internal malleolar artery*) is a small branch which winds around the tibial malleolus and ends in the medial malleolar net-work.

The **communicating branch** (*ramus communicans*) runs transversely across the back of the tibia, about 5 cm. above its lower end, beneath the Flexor hallucis longus, and joins the communicating branch of the peroneal.

The **medial calcaneal** (*rami calcanei mediales; internal calcaneal*) are several large arteries which arise from the posterior tibial just before its division; they pierce the laciniated ligament and are distributed to the fat and integument behind the tendo calcaneus and about the heel, and to the muscles on the tibial side of the sole, anastomosing with the peroneal and medial malleolar and, on the back of the heel, with the lateral calcaneal arteries.




FIG. 629.—The plantar arteries. Superficial view.




FIG. 630.—The plantar arteries. Deep view.

The **medial plantar artery** (*a. plantaris medialis; internal plantar artery*) (Figs. 629 and 630), much smaller than the lateral, passes forward along the medial side of the foot. It is at first situated above the Abductor hallucis, and then between it and the Flexor digitorum brevis, both of which it supplies. At the base of the first metatarsal bone, where it is much diminished in size, it passes along the medial border of the first toe, anastomosing with the first dorsal metatarsal artery. Small superficial digital branches accompany the digital branches of the medial plantar nerve and join the plantar metatarsal arteries of the first three spaces.

The **lateral plantar artery** (*a. plantaris lateralis; external plantar artery*), much larger than the medial, passes obliquely lateralward and forward to the base of the fifth metatarsal bone. It then turns medialward to the interval between the bases of the first and second metatarsal bones, where it unites with the deep plantar branch of the dorsalis pedis artery, thus completing the **plantar arch**. As this artery passes lateralward, it is first placed between the calcaneus and Abductor hallucis,

and then between the *Flexor digitorum brevis* and *Quadratus plantae*; as it runs forward to the base of the little toe it lies more superficially between the *Flexor digitorum brevis* and *Abductor digiti quinti*, covered by the plantar aponeurosis and integument. The remaining portion of the vessel is deeply situated; it extends from the base of the fifth metatarsal bone to the proximal part of the first interosseous space, and forms the plantar arch; it is convex forward, lies below the bases of the second, third, and fourth metatarsal bones and the corresponding *Interossei*, and upon the oblique part of the *Adductor hallucis*.

**Applied Anatomy.**—Wounds of the plantar arch are always serious, on account of the depth of the vessel and the important structures which must be interfered with in an attempt to ligature it. They must be treated on similar lines to those of wounds of the volar arches (see p. 682). Pressure locally, combined with elevation of the limb, may in some cases be sufficient to arrest the bleeding, but this failing, an attempt should be made to find the bleeding point and ligature it. Should this prove unsuccessful, it may be necessary to ligature the femoral below the origin of the *profunda femoris*, as ligature of the anterior and posterior tibial arteries may not be sufficient to control the hemorrhage, and it is safer and quicker to tie the femoral under the circumstances.

**Branches.**—The plantar arch, besides distributing numerous branches to the muscles, integument, and fasciæ in the sole, gives off the following branches:

Perforating.

Plantar Metatarsal.

The **Perforating Branches** (*rami perforantes*) are *three* in number; they ascend through the proximal parts of the second, third, and fourth interosseous spaces, between the heads of the *Interossei dorsales*, and anastomose with the dorsal metatarsal arteries.

The **Plantar Metatarsal Arteries** (*aa. metatarsae plantares; digital branches*) are *four* in number, and run forward between the metatarsal bones and in contact with the *Interossei*. Each divides into a pair of plantar digital arteries which supply the adjacent sides of the toes. Near their points of division each sends upward an **anterior perforating branch** to join the corresponding dorsal metatarsal artery. The **first plantar metatarsal artery** (*arteria princeps hallucis*) springs from the junction between the lateral plantar and deep plantar arteries and sends a digital branch to the medial side of the first toe. The digital branch for the lateral side of the fifth toe arise from the lateral plantar artery near the base of the fifth metatarsal bone.

## THE VEINS.

**THE Veins** convey the blood from the capillaries of the different parts of the body to the heart. They consist of two distinct sets of vessels, the **pulmonary** and **systemic**.

The **Pulmonary Veins**, unlike other veins, contain arterial blood, which they return from the lungs to the left atrium of the heart.

The **Systemic Veins** return the venous blood from the body generally, to the right atrium of the heart.

The **Portal Vein**, an appendage to the systemic venous system, is confined to the abdominal cavity, and returns the venous blood from the spleen and the viscera of digestion to the liver. This vessel ramifies in the substance of the liver and there breaks up into a minute network of capillary-like vessels, from which the blood is conveyed by the hepatic veins to the inferior vena cava.

The veins commence by minute plexuses which receive the blood from the capillaries. The branches arising from these plexuses unite together into trunks, and these, in their passage toward the heart, constantly increase in size as they receive tributaries, or join other veins. The veins are larger and altogether more numerous than the arteries; hence, the entire capacity of the venous system is much greater than that of the arterial; the capacity of the pulmonary veins, however, only slightly exceeds that of the pulmonary arteries. The veins are cylindrical like the arteries; their walls, however, are thin and they collapse when the vessels are empty, and the uniformity of their surfaces is interrupted at intervals by slight constrictions, which indicate the existence of valves in their interior. They communicate very freely with one another, especially in certain regions of the body; and these communications exist between the larger trunks as well as between the smaller branches. Thus, between the venous sinuses of the cranium, and between the veins of the neck, where obstruction would be attended with imminent danger to the cerebral venous system, large and frequent anastomoses are found. The same free communication exists between the veins throughout the whole extent of the vertebral canal, and between the veins composing the various venous plexuses in the abdomen and pelvis, *e. g.*, the spermatic, uterine, vesical, and pudendal.

The systemic venous channels are subdivided into three sets, viz., **superficial** and **deep veins**, and **venous sinuses**.

The **Superficial Veins** (*cutaneous veins*) are found between the layers of the superficial fascia immediately beneath the skin; they return the blood from these structures, and communicate with the deep veins by perforating the deep fascia.

The **Deep Veins** accompany the arteries, and are usually enclosed in the same sheaths with those vessels. With the smaller arteries—as the radial, ulnar, brachial, tibial, peroneal—they exist generally in pairs, one lying on each side of the vessel, and are called *venae comitantes*. The larger arteries—such as the axillary, subclavian, popliteal, and femoral—have usually only one accompanying vein. In certain organs of the body, however, the deep veins do not accompany the arteries; for instance, the veins in the skull and vertebral canal, the hepatic veins in the liver, and the larger veins returning blood from the bones.

**Venous Sinuses** are found only in the interior of the skull, and consist of canals formed by a separation of the two layers of the dura mater; their outer coat consists of fibrous tissue, their inner of an endothelial layer continuous with the lining membrane of the veins.



### THE PULMONARY VEINS (VENAE PULMONALES).

The **pulmonary veins** return the arterialized blood from the lungs to the left atrium of the heart. They are four in number, two from each lung, and are destitute of valves. They commence in a capillary net-work upon the walls of the air sacs, where they are continuous with the capillary ramifications of the pulmonary artery, and, joining together, form one vessel for each lobule. These vessels uniting successively, form a single trunk for each lobe, three for the right, and two for the left lung. The vein from the middle lobe of the right lung generally unites with that from the upper lobe, so that ultimately two trunks from each lung are formed; they perforate the fibrous layer of the pericardium and open separately into the upper and back part of the left atrium. Occasionally the three veins on the right side remain separate. Not infrequently the two left pulmonary veins end by a common opening.

*At the root of the lung*, the superior pulmonary vein lies in front of and a little below the pulmonary artery; the inferior is situated at the lowest part of the hilus of the lung and on a plane posterior to the upper vein. Behind the pulmonary artery is the bronchus.

*Within the pericardium*, their anterior surfaces are invested by the serous layer of this membrane.

The right pulmonary veins pass behind the right atrium and superior vena cava; the left in front of the descending thoracic aorta.

### THE SYSTEMIC VEINS.

The **systemic veins** may be arranged into three groups: (1) The **veins of the heart**. (2) The veins of the **upper extremities, head, neck, and thorax**, which end in the superior vena cava. (3) The veins of the **lower extremities, abdomen, and pelvis**, which end in the inferior vena cava.

#### THE VEINS OF THE HEART (VV. Cordis) (Fig. 631).

**Coronary Sinus** (*sinus coronarius*).—Most of the veins of the heart open into the coronary sinus. This is a wide venous channel about 2.25 cm. in length situated in the posterior part of the coronary sulcus, and covered by muscular fibres from the left atrium. It ends in the right atrium between the opening of the inferior vena cava and the atrioventricular aperture, its orifice being guarded by a semilunar valve, the **valve of the coronary sinus** (*valve of Thebesius*).

**Tributaries.**—Its tributaries are the great, small, and middle cardiac veins, the posterior vein of the left ventricle, and the oblique vein of the left atrium, all of which, except the last, are provided with valves at their orifices.

1. The **Great Cardiac Vein** (*v. cordis magna; left coronary vein*) begins at the apex of the heart and ascends along the anterior longitudinal sulcus to the base of the ventricles. It then curves to the left in the coronary sulcus, and reaching the back of the heart, opens into the left extremity of the coronary sinus. It receives tributaries from the left atrium and from both ventricles: one, the **left marginal vein**, is of considerable size, and ascends along the left margin of the heart.

2. The **Small Cardiac Vein** (*v. cordis parva; right coronary vein*) runs in the coronary sulcus between the right atrium and ventricle, and opens into the right extremity of the coronary sinus. It receives blood from the back of the right atrium and ventricle; the **right marginal vein** ascends along the right margin of the heart and joins it in the coronary sulcus, or opens directly into the right atrium.

3. The **Middle Cardiac Vein** (*v. cordis media*) commences at the apex of the heart, ascends in the posterior longitudinal sulcus, and ends in the coronary sinus near its right extremity.

4. The **Posterior Vein of the Left Ventricle** (*v. posterior ventriculi sinistri*) runs on the diaphragmatic surface of the left ventricle to the coronary sinus, but may end in the great cardiac vein.

5. The **Oblique Vein of the Left Atrium** (*v. obliqua atrii sinistri* [Marshalli]; *oblique vein of Marshall*) is a small vessel which descends obliquely on the back of the left atrium and ends in the coronary sinus near its left extremity; it is continuous above with the **ligament of the left vena cava** (*lig. venae cavae sinistrae*; *vestigial fold of Marshall*), and the two structures form the remnant of the left Cuvierian duct.




FIG. 631.—Base and diaphragmatic surface of heart.

The following cardiac veins do not end in the coronary sinus: (1) the **anterior cardiac veins**, comprising three or four small vessels which collect blood from the front of the right ventricle and open into the right atrium; the right marginal vein frequently opens into the right atrium, and is therefore sometimes regarded as belonging to this group; (2) the **smallest cardiac veins** (*veins of Thebesius*), consisting of a number of minute veins which arise in the muscular wall of the heart; the majority open into the atria, but a few end in the ventricles.

### THE VEINS OF THE HEAD AND NECK.

The veins of the head and neck may be subdivided into three groups: (1) The **veins of the exterior of the head and face**. (2) The **veins of the neck**. (3) The **diploic veins**, the **veins of the brain**, and the **venous sinuses of the dura mater**.

**The Veins of the Exterior of the Head and Face (Fig. 632).**

The veins of the exterior of the head and face are:

Frontal.	Superficial Temporal
Supraorbital.	Internal Maxillary.
Angular.	Posterior Facial.
Anterior Facial.	Posterior Auricular.
Occipital.	




FIG. 632.—Veins of the head and neck.

The **frontal vein** (*v. frontalis*) begins on the forehead in a venous plexus which communicates with the frontal branches of the superficial temporal vein. The veins converge to form a single trunk, which runs downward near the middle line of the forehead parallel with the vein of the opposite side. The two veins are joined, at the root of the nose, by a transverse branch, called the **nasal arch**, which receives some small veins from the dorsum of the nose. At the root of the nose the veins diverge, and, each at the medial angle of the orbit, joins the **supraorbital vein**, to

form the **angular vein**. Occasionally the frontal veins join to form a single trunk, which bifurcates at the root of the nose into the two angular veins.

The **supraorbital vein** (*v. supraorbitalis*) begins on the forehead where it communicates with the frontal branch of the superficial temporal vein. It runs downward superficial to the Frontalis muscle, and joins the frontal vein at the medial angle of the orbit to form the **angular vein**. Previous to its junction with the frontal vein, it sends through the supraorbital notch into the orbit a branch which communicates with the ophthalmic vein; as this vessel passes through the notch, it receives the frontal diploic vein through a foramen at the bottom of the notch.

The **angular vein** (*v. angularis*) formed by the junction of the frontal and supra-orbital veins, runs obliquely downward, on the side of the root of the nose, to the level of the lower margin of the orbit, where it becomes the anterior facial vein. It receives the veins of the ala nasi, and communicates with the superior ophthalmic vein through the nasofrontal vein, thus establishing an important anastomosis between the anterior facial vein and the cavernous sinus.

The **anterior facial vein** (*v. facialis anterior; facial vein*) commences at the side of the root of the nose, and is a direct continuation of the angular vein. It lies behind the external maxillary (facial) artery and follows a less tortuous course. It runs obliquely downward and backward, beneath the zygomaticus and zygomatic head of the Quadratus labii superioris, descends along the anterior border and then on the superficial surface of the Masseter, crosses over the body of the mandible, and passes obliquely backward, beneath the Platysma and cervical fascia, superficial to the submaxillary gland, the Digastricus and Stylohyoideus. It unites with the posterior facial vein to form the **common facial vein**, which crosses the external carotid artery and enters the internal jugular vein at a variable point below the hyoid bone. From near its termination a communicating branch often runs down the anterior border of the Sternocleidomastoideus to join the lower part of the anterior jugular vein.

**Tributaries.**—The anterior facial vein receives a branch of considerable size, the **deep facial vein**, from the pterygoid venous plexus. It is also joined by the superior and inferior palpebral, the superior and inferior labial, the buccinator and the masseteric veins. Below the mandible it receives the submental, palatine, and submaxillary veins, and, generally, the vena comitans of the hypoglossal nerve.

**Applied Anatomy.**—There are some points about the anterior facial vein which render it of great importance in surgery. It is not so flaccid as are most superficial veins, and, in consequence of this, remains more patent when divided. It has, moreover, no valves. It communicates freely with the intracranial circulation, not only at its commencement by the angular and supra-orbital veins which communicate with the ophthalmic vein, a tributary of the cavernous sinus, but also by the deep facial vein, which communicates through the pterygoid plexus with the cavernous sinus by branches which pass through the foramen ovale and foramen lacerum (see p. 746). These facts have an important bearing upon the surgery of some diseases; any phlegmonous inflammation of the face following a poisoned wound is liable to set up thrombosis in the anterior facial vein, and detached portions of the clot may give rise to purulent foci in other parts of the body. On account of its communications with the cerebral sinuses, these thrombi are apt to extend upward into them, and so induce a fatal issue; this has been known to follow in cases of ordinary carbuncle of the face. The position of the vein should always be borne in mind when incisions are made for the relief of suppuration about the mandible.

The **superficial temporal vein** (*v. temporalis superficialis*) begins on the side and vertex of the skull in a plexus which communicates with the frontal and supra-orbital veins, with the corresponding vein of the opposite side, and with the posterior auricular and occipital veins. From this net-work frontal and parietal branches arise, and unite above the zygomatic arch to form the trunk of the vein, which is joined in this situation by the **middle temporal vein**, from the substance of the Temporalis. It then crosses the posterior root of the zygomatic arch, enters the substance of the parotid gland, and unites with the internal maxillary vein to form the **posterior facial vein**.

**Tributaries.**—The superficial temporal vein receives in its course some parotid veins, articular veins from the temporomandibular joint, anterior auricular veins from the auricula, and the **transverse facial** from the side of the face. The middle temporal vein receives the **orbital vein**, which is formed by some lateral palpebral branches, and passes backward between the layers of the temporal fascia to join the superficial temporal vein.

The **pterygoid plexus** (*plexus pterygoideus*) is of considerable size, and is situated between the Temporalis and Pterygoideus externus, and partly between the two Pterygoidei. It receives tributaries corresponding with the branches of the internal maxillary artery. Thus it receives the sphenopalatine, the middle meningeal, the deep temporal, the pterygoid, masseteric, buccinator, alveolar, and some palatine veins, and a branch which communicates with the ophthalmic vein through the inferior orbital fissure. This plexus communicates freely with the anterior facial vein; it also communicates with the cavernous sinus, by branches through the foramen Vesalii, foramen ovale, and foramen lacerum.

The **internal maxillary vein** (*v. maxillaris interna*) is a short trunk which accompanies the first part of the internal maxillary artery. It is formed by a confluence of the veins of the pterygoid plexus, and passes backward between the sphenomandibular ligament and the neck of the mandible, and unites with the temporal vein to form the posterior facial vein.

The **posterior facial vein** (*v. facialis posterior; temporomaxillary vein*), formed by the union of the superficial temporal and internal maxillary veins, descends in the substance of the parotid gland, superficial to the external carotid artery but beneath the facial nerve, between the ramus of the mandible and the Sternocleidomastoideus muscle. It divides into two branches, an **anterior**, which passes forward and unites with the anterior facial vein to form the common facial vein and a **posterior**, which is joined by the posterior auricular vein and becomes the external jugular vein.

The **posterior auricular vein** (*v. auricularis posterior*) begins upon the side of the head, in a plexus which communicates with the tributaries of the occipital, and superficial temporal veins. It descends behind the auricula, and joins the posterior division of the posterior facial vein to form the external jugular. It receives the stylomastoid vein, and some tributaries from the cranial surface of the auricula.

The **occipital vein** (*v. occipitalis*) begins in a plexus at the back part of the vertex of the skull. From the plexus emerges a single vessel, which pierces the cranial attachment of the Trapezius and, dipping into the suboccipital triangle, joins the deep cervical and vertebral veins. Occasionally it follows the course of the occipital artery and ends in the internal jugular; in other instances, it joins the posterior auricular and through it opens into the external jugular. The parietal emissary vein connects it with the superior sagittal sinus; and as it passes across the mastoid portion of the temporal bone, it receives the mastoid emissary vein which connects it with the transverse sinus. The occipital diploic vein sometimes joins it.

### The Veins of the Neck (Fig. 633).

The veins of the neck, which return the blood from the head and face, are:

External Jugular.	Anterior Jugular.
Posterior External Jugular.	Internal Jugular.
Vertebral.	

The **external jugular vein** (*v. jugularis externa*) receives the greater part of the blood from the exterior of the cranium and the deep parts of the face, being formed by the junction of the posterior division of the posterior facial with the posterior

auricular vein. It commences in the substance of the parotid gland, on a level with the angle of the mandible, and runs perpendicularly down the neck, in the direction of a line drawn from the angle of the mandible to the middle of the clavicle at the posterior border of the Sternocleidomastoideus. In its course it crosses the Sternocleidomastoideus obliquely, and in the subclavian triangle perforates the deep fascia, and ends in the subclavian vein, lateral to or in front of the Scalenus anterior. It is separated from the Sternocleidomastoideus by the investing layer of the deep cervical fascia, and is covered by the Platysma, the superficial fascia, and the integument; it crosses the cutaneous cervical nerve, and its upper half runs parallel with the great auricular nerve. The external jugular vein varies in




FIG. 633.—The veins of the neck, viewed from in front. (After Spalteholz.)

size, bearing an inverse proportion to the other veins of the neck, it is occasionally double. It is provided with two pairs of valves, the lower pair being placed at its entrance into the subclavian vein, the upper in most cases about 4 cm. above the clavicle. The portion of vein between the two sets of valves is often dilated, and is termed the *sinus*. These valves do not prevent the regurgitation of the blood, or the passage of injection from below upward.

**Tributaries.**—This vein receives the occipital occasionally, the posterior external jugular, and, near its termination, the transverse cervical, transverse scapular, and anterior jugular veins; in the substance of the parotid, a large branch of communication from the internal jugular joins it.



**Applied Anatomy.**—Venesection used formerly to be performed on the external jugular vein, but is now probably never resorted to. The anatomical point to be remembered in performing this operation is to cut across the fibres of the Platysma in opening the vein, so that by their contraction they will expose the orifice in the vein and so allow the flow of blood.

The **posterior external jugular vein** (*v. jugularis posterior*) begins in the occipital region and returns the blood from the skin and superficial muscles in the upper and back part of the neck, lying between the Splenius and Trapezius. It runs down the back part of the neck; and opens into the external jugular vein just below the middle of its course.

The **anterior jugular vein** (*v. jugularis anterior*) begins near the hyoid bone by the confluence of several superficial veins from the submaxillary region. It descends between the median line and the anterior border of the Sternocleidomastoideus, and, at the lower part of the neck, passes beneath that muscle to open into the termination of the external jugular, or, in some instances, into the subclavian vein (Figs. 632, 633). It varies considerably in size, bearing usually an inverse proportion to the external jugular; most frequently there are two anterior jugulars, a right and left; but sometimes only one. Its tributaries are some laryngeal veins, and occasionally a small thyroid vein. Just above the sternum the two anterior jugular veins communicate by a transverse trunk, the **venous jugular arch**, which receive tributaries from the inferior thyroid veins; each also communicates with the internal jugular. There are no valves in this vein.

The **internal jugular vein** (*v. jugularis interna*) collects the blood from the brain, from the superficial parts of the face, and from the neck. It is directly continuous with the transverse sinus, and begins in the posterior compartment of the jugular foramen, at the base of the skull. At its origin it is somewhat dilated, and this dilatation is called the **superior bulb**. It runs down the side of the neck in a vertical direction, lying at first lateral to the internal carotid artery, and then lateral to the common carotid, and at the root of the neck unites with the subclavian vein to form the innominate vein; a little above its termination is a second dilatation, the **inferior bulb**. Above, it lies upon the Rectus capitis lateralis, behind the internal carotid artery and the nerves passing through the jugular foramen; lower down, the vein and artery lie upon the same plane, the glossopharyngeal and hypoglossal nerves passing forward between them; the vagus descends between and behind the vein and the artery in the same sheath, and the accessory runs obliquely backward, superficial or deep to the vein. At the root of the neck the right internal jugular vein is placed at a little distance from the common carotid artery, and crosses the first part of the subclavian artery, while the left internal jugular vein usually overlaps the common carotid artery. The left vein is generally smaller than the right, and each contains a pair of valves, which are placed about 2.5 cm. above the termination of the vessel.

**Tributaries.**—This vein receives in its course the inferior petrosal sinus, the common facial, lingual, pharyngeal, superior and middle thyroid veins, and sometimes the occipital. The thoracic duct on the left side and the right lymphatic duct on the right side open into the angle of union of the internal jugular and subclavian veins.

The **Inferior Petrosal Sinus** (*sinus petrosus inferior*) leaves the skull through the anterior part of the jugular foramen, and joins the superior bulb of the internal jugular vein.

The **Lingual Veins** (*vv. linguales*) begin on the dorsum, sides, and under surface of the tongue, and, passing backward along the course of the lingual artery, end in the internal jugular vein. The vena comitans of the hypoglossal nerve (**ranine vein**), a branch of considerable size, begins below the tip of the tongue, and may join the lingual; generally, however, it passes backward on the Hyoglossus, and joins the common facial.

The **Pharyngeal Veins** (*vv. pharyngeae*) begin in the **pharyngeal plexus** on the outer surface of the pharynx, and, after receiving some posterior meningeal veins and the vein of the pterygoid canal, end in the internal jugular. They occasionally open into the facial, lingual, or superior thyroid vein.

The **Superior Thyroid Vein** (*v. thyroidea superioris*) (Fig. 634) begins in the substance and on the surface of the thyroid gland, by tributaries corresponding with the branches of the superior thyroid artery, and ends in the upper part of the internal jugular vein. It receives the superior laryngeal and cricothyroid veins.

The **Middle Thyroid Vein** (Fig. 634) collects the blood from the lower part of the thyroid gland, and after being joined by some veins from the larynx and trachea, ends in the lower part of the internal jugular vein.

The common facial and occipital veins have been described.




FIG. 634.—The veins of the thyroid gland.

**Applied Anatomy.**—The internal jugular vein requires ligature in cases of septic thrombosis of the transverse sinus, in order to prevent septic emboli being carried into the general circulation. This operation has been performed in many cases, with the most satisfactory results. The cases are generally those of chronic disease of the middle ear, with discharge of pus which perhaps has existed for many years. The patient is seized with acute septic inflammation, spreading to the mastoid cells, and setting up septic thrombosis of the transverse sinus and extending downward into the internal jugular vein. Such cases are always extremely grave, for there is danger of portions of the septic clot being detached and causing septic embolism in the lungs, the portions of clot having passed through the right side of the heart. If the condition be suspected, the diseased bone should be removed at once from the mastoid process. The sinus is then investigated, and if it be found thrombosed, the surgeon should proceed to ligature the internal jugular vein, by an incision along the anterior border of the Sternocleidomastoideus, the centre of which is on a level with the greater cornu of the hyoid bone. The vein should be ligatured in two places and divided between. After the vessel has been secured and divided, the transverse sinus is to be thoroughly cleared out, and, by removing the ligature from the upper end of the divided vein, all septic clots removed by syringing from the sinus through the vein. If hemorrhage occur from the distal end of the sinus, it can be arrested by careful plugging with antiseptic gauze.

The internal jugular vein is also surgically important, because it is surrounded by a large number of deep cervical lymph glands; and when these are enlarged in tuberculous or malignant disease, they are apt to become adherent to the vessel, rendering their removal difficult and often dangerous. The proper course to pursue in these cases is to ligature the vessel above and below the glandular mass, and resect the included portion together with the glands.

Cardiac pulsation is often demonstrable in the internal jugular vein at the root of the neck. There are no valves in the innominate veins or superior vena cava; in consequence, the systole of the right atrium causes a wave to pass up these vessels, and when the conditions are favorable this wave appears as a somewhat feeble flicker over the internal jugular vein at the root of the neck, quite distinct from, and just preceding, the more forcible impulse transmitted from the underlying common carotid artery and due to the ventricular systole. This atrial systolic venous impulse is much increased in conditions in which the right atrium is abnormally distended with blood or is hypertrophied, as is often the case in disease of the bicuspid valve. In Stokes-Adams disease (p. 614) it is this pulsation which gives evidence of the fact that the atria are beating faster—often two or three times faster—than the ventricles.

The **vertebral vein** (*a. vertebralis*) is formed in the suboccipital triangle, from numerous small tributaries which spring from the internal vertebral venous plexuses and issue from the vertebral canal above the posterior arch of the atlas. They unite with small veins from the deep muscles at the upper part of the back of the neck, and form a vessel which enters the foramen in the transverse process of the atlas, and descends, forming a dense plexus around the vertebral artery, in the canal formed by the foramina transversaria of the cervical vertebræ. This plexus ends in a single trunk, which emerges from the foramen transversarium of the sixth cervical vertebra, and opens at the root of the neck into the back part of the innominate vein near its origin, its mouth being guarded by a pair of valves. On the right side, it crosses the first part of the subclavian artery.

**Tributaries.**—The vertebral vein communicates with the transverse sinus by a vein which passes through the condyloid canal, when that canal exists. It receives branches from the occipital vein and from the prevertebral muscles, from the internal and external vertebral venous plexuses, from the anterior vertebral and the deep cervical veins; close to its termination it is sometimes joined by the first intercostal vein.

The **Anterior Vertebral Vein** commences in a plexus around the transverse processes of the upper cervical vertebræ, descends in company with the ascending cervical artery between the Scalenus anterior and Longus capitis muscles, and opens into the terminal part of the vertebral vein.

The **Deep Cervical Vein** (*v. cervicalis profunda*; *posterior vertebral* or *posterior deep cervical vein*) accompanies its artery between the Semispinales capitis and colli. It begins in the suboccipital region by communicating branches from the occipital vein and by small veins from the deep muscles at the back of the neck. It receives tributaries from the plexuses around the spinous processes of the cervical vertebræ, and terminates in the lower part of the vertebral vein.

### The Diploic Veins (*Venae Diploicae*) (Fig. 635).

The **diploic veins** occupy channels in the diploë of the cranial bones. They are large and exhibit at irregular intervals pouch-like dilatations; their walls are thin, and formed of endothelium resting upon a layer of elastic tissue.

So long as the cranial bones are separable from one another, these veins are confined to the particular bones; but when the sutures are obliterated, they unite with each other, and increase in size. They communicate with the meningeal veins and the sinuses of the dura mater, and with the veins of the pericranium. They consist of (1) the **frontal**, which opens into the supraorbital vein and the superior sagittal sinus; (2) the **anterior temporal**, which is confined chiefly to the frontal bone, and opens into the sphenoparietal sinus and into one of the deep temporal veins, through an aperture in the great wing of the sphenoid; (3) the

**posterior temporal**, which is situated in the parietal bone, and ends in the transverse sinus, through an aperture at the mastoid angle of the parietal bone or through the mastoid foramen; and (4) the **occipital**, the largest of the four, which is confined to the occipital bone, and opens either externally into the occipital vein, or internally into the transverse sinus or into the confluence of the sinuses (*torcular Herophili*).



FIG. 635.—Veins of the diploë as displayed by the removal of the outer table of the skull.

### The Veins of the Brain.

The veins of the brain possess no valves, and their walls, owing to the absence of muscular tissue, are extremely thin. They pierce the arachnoid membrane and the inner or meningeal layer of the dura mater, and open into the cranial venous sinuses. They may be divided into two sets, **cerebral** and **cerebellar**.

The **cerebral veins** (*vv. cerebri*) are divisible into external and internal groups according as they drain the outer surfaces or the inner parts of the hemispheres.

The **external veins** are the superior, inferior, and middle cerebral.

The **Superior Cerebral Veins** (*vv. cerebri superiores*), eight to twelve in number, drain the superior, lateral, and medial surfaces of the hemispheres, and are mainly lodged in the sulci between the gyri, but some run across the gyri. They open into the superior sagittal sinus; the anterior veins runs nearly at right angles to the sinus; the posterior and larger veins are directed obliquely forward and open into the sinus in a direction more or less opposed to the current of the blood contained within it.

The **Middle Cerebral Vein** (*v. cerebri media*; *superficial Sylvian vein*) begins on the lateral surface of the hemisphere, and, running along the lateral cerebral fissure, ends in the cavernous or the sphenoparietal sinus. It is connected (a) with the superior sagittal sinus by the **great anastomotic vein of Trolard**, which opens into one of the superior cerebral veins; (b) with the transverse sinus by the **posterior anastomotic vein of Labbé**, which courses over the temporal lobe.

The **Inferior Cerebral Veins** (*vv. cerebri inferiores*), of small size, drain the under surfaces of the hemispheres. Those on the orbital surface of the frontal lobe join the superior cerebral veins, and through these open into the superior sagittal sinus; those of the temporal lobe anastomose with the middle cerebral and basal veins, and join the cavernous, sphenoparietal, and superior petrosal sinuses.

The **basal vein** is formed at the anterior perforated substance by the union of (a) a small **anterior cerebral vein** which accompanies the anterior cerebral artery, (b) the **deep middle cerebral vein** (*deep Sylvian vein*), which receives tributaries from the insula and neighboring gyri, and runs in the lower part of the lateral cerebral fissure, and (c) the **inferior striate veins**, which leave the corpus striatum through the anterior perforated substance. The basal vein passes backward around the cerebral peduncle, and ends in the internal cerebral vein (*vein of Galen*); it receives tributaries from the interpeduncular fossa, the inferior horn of the lateral ventricle, the hippocampal gyrus, and the mid-brain.

The **Internal Cerebral Veins** (*vv. cerebri internae; veins of Galen; deep cerebral veins*) drain the deep parts of the hemisphere and are two in number; each is formed near the interventricular foramen by the union of the **terminal** and **choroid veins**. They ran backward parallel with one another, between the layers of the tela chorioidea of the third ventricle, and beneath the splenium of the corpus callosum, where they unite to form a short trunk, the **great cerebral vein**; just before their union each receives the corresponding basal vein.

The **terminal vein** (*v. terminalis; vena corporis striati*) commences in the groove between the corpus striatum and thalamus, receives numerous veins from both of these parts, and unites behind the crus fornicis with the choroid vein, to form one of the internal cerebral veins. The **choroid vein** runs along the whole length of the choroid plexus, and receives veins from the hippocampus, the fornix, and the corpus callosum.

The **Great Cerebral Vein** (*v. cerebri magna [Galen]; great vein of Galen*), formed by the union of the two internal cerebral veins, is a short median trunk which curves backward and upward around the splenium of the corpus callosum and ends in the anterior extremity of the straight sinus.

The **cerebellar veins** are placed on the surface of the cerebellum, and are disposed in two sets, superior and inferior. The **superior cerebellar veins** (*vv. cerebelli superiores*) pass partly forward and medialward, across the superior vermis, to end in the straight sinus and the internal cerebral veins, partly lateralward to the transverse and superior petrosal sinuses. The **inferior cerebellar veins** (*vv. cerebelli inferiores*) of large size, end in the transverse, superior petrosal, and occipital sinuses.

### **The Sinuses of the Dura Mater (Sinus Durae Matris). Ophthalmic Veins and Emissary Veins.**

The **sinuses of the dura mater** are venous channels which drain the blood from the brain; they are devoid of valves, and are situated between the two layers of the dura mater and lined by endothelium continuous with that which lines the veins. They may be divided into two groups: (1) a **postero-superior**, at the upper and back part of the skull, and (2) an **antero-inferior**, at the base of the skull.

The postero-superior group comprises the

Superior Sagittal.

Inferior Sagittal.

Straight.

Two Transverse.

Occipital.

The **superior sagittal sinus** (*sinus sagittalis superior; superior longitudinal sinus*) (Figs. 636, 637) occupies the attached or convex margin of the falx cerebri. Commencing at the foramen cecum, through which it receives a vein from the nasal cavity, it runs from before backward, grooving the inner surface of the frontal, the adjacent margins of the two parietals, and the superior division of the cruciate eminence of the occipital; near the internal occipital protuberance it deviates to one or other side (usually the right), and is continued as the corresponding transverse sinus. It is triangular in section, narrow in front, and gradually increases in



size as it passes backward. Its inner surface presents the openings of the superior cerebral veins, which run, for the most part, obliquely forward, and open chiefly at the back part of the sinus, their orifices being concealed by fibrous folds; numerous fibrous bands (*chordae Willisii*) extend transversely across the inferior angle of the sinus; and, lastly, small openings communicate with irregularly shaped venous spaces (*venous lacunæ*) in the dura mater near the sinus. There are usually three lacunæ on either side of the sinus: a small frontal, a large parietal, and an occipital, intermediate in size between the other two (Sargent<sup>1</sup>). Most of the cerebral veins from the outer surface of the hemisphere open into these lacunæ, and numerous **arachnoid granulations** (*Pacchionian bodies*) project into them from below. The superior sagittal sinus receives the superior cerebral veins, veins from the diploë and dura mater, and, near the posterior extremity of the sagittal suture, veins from the pericranium, which pass through the parietal foramina.




FIG. 636.—Superior sagittal sinus laid open after removal of the skull cap. The chordae Willisii are clearly seen. The venous lacunæ are also well shown; from two of them probes are passed into the superior sagittal sinus. (Poirier and Charpy.)

**Applied Anatomy.**—The numerous communications which take place between this sinus and the veins of the nose, scalp, and diploë, cause it to be at times the seat of infective thrombosis from suppurative processes in these parts.

The **inferior sagittal sinus** (*sinus sagittalis inferior; inferior longitudinal sinus*) (Fig. 637) is contained in the posterior half or two-thirds of the free margin of the falx cerebri. It is of a cylindrical form, increases in size as it passes backward, and ends in the straight sinus. It receives several veins from the falx cerebri, and occasionally a few from the medial surfaces of the hemispheres.

The **straight sinus** (*sinus rectus; tentorial sinus*) (Figs. 637, 638) is situated at the line of junction of the falx cerebri with the tentorium cerebelli. It is triangular

<sup>1</sup> Journal of Anatomy and Physiology, vol. xlv.



in section, increases in size as it proceeds backward, and runs downward and backward from the end of the inferior sagittal sinus to the transverse sinus of the opposite side to that into which the superior sagittal sinus is prolonged. Its terminal part communicates by a cross branch with the confluence of the sinuses. Besides the inferior sagittal sinus, it receives the great cerebral vein (*great vein of Galen*) and the superior cerebellar veins. A few transverse bands cross its interior.




FIG. 637.—Dura mater and its processes exposed by removing part of the right half of the skull, and the brain.

The **transverse sinuses** (*sinus transversus*; *lateral sinuses*) (Figs. 638, 639) are of large size and begin at the internal occipital protuberance; one, generally the right, being the direct continuation of the superior sagittal sinus, the other of the straight sinus. Each transverse sinus passes lateralward and forward, describing a slight curve with its convexity upward, to the base of the petrous portion of the temporal bone, and lies, in this part of its course, in the attached margin of the tentorium cerebelli; it then leaves the tentorium and curves downward and medialward to reach the jugular foramen, where it ends in the internal jugular vein. In its course it rests upon the squama of the occipital, the mastoid angle of the parietal, the mastoid part of the temporal, and, just before its termination, the jugular process of the occipital; the portion which occupies the groove on the mastoid part of the temporal is sometimes termed the **sigmoid sinus**. The transverse sinuses are frequently of unequal size, that formed by the superior sagittal sinus being the larger; they increase in size as they proceed from behind forward. On transverse section the horizontal portion exhibits a prismatic, the curved

portion a semicylindrical form. They receive the blood from the superior petrosal sinuses at the base of the petrous portion of the temporal bone; they communicate with the veins of the pericranium by means of the mastoid and condyloid emissary veins; and they receive some of the inferior cerebral and inferior cerebellar veins, and some veins from the diploë. The **petrosquamous sinus**, when present, runs backward along the junction of the squama and petrous portion of the temporal, and opens into the transverse sinus.




FIG. 638.—Tentorium cerebelli from above.

The **occipital sinus** (*sinus occipitalis*) (Fig. 639) is the smallest of the cranial sinuses. It is situated in the attached margin of the falx cerebelli, and is generally single, but occasionally there are two. It commences around the margin of the foramen magnum by several small venous channels, one of which joins the terminal part of the transverse sinus; it communicates with the posterior internal vertebral venous plexuses and ends in the confluence of the sinuses.

The **Confluence of the Sinuses** (*confluens sinuum*; *torcular Herophili*) is the term applied to the dilated extremity of the superior sagittal sinus. It is of irregular form, and is lodged on one side (generally the right) of the internal occipital protuberance. From it the transverse sinus of the same side is derived. It receives also the blood from the occipital sinus, and is connected across the middle line with the commencement of the transverse sinus of the opposite side.

The antero-inferior group of sinuses comprises the

Two Cavernous.

Two Superior Petrosal.

Two Intercavernous.

Two Inferior Petrosal.

Basilar Plexus.



The **cavernous sinuses** (*sinus cavernosus*) (Fig. 639) are so named because they present a reticulated structure, due to their being traversed by numerous interlacing filaments. They are of irregular form, larger behind than in front, and are placed one on either side of the body of the sphenoid bone, extending from the superior orbital fissure to the apex of the petrous portion of the temporal bone. Each opens behind into the petrosal sinuses. On the medial wall of each sinus is the internal carotid artery, accompanied by filaments of the carotid plexus; near the artery is the abducent nerve; on the lateral wall are the oculomotor and trochlear nerves, and the ophthalmic and maxillary divisions of the trigeminal nerve




FIG. 639.—The sinuses at the base of the skull.

(Fig. 640). These structures are separated from the blood flowing along the sinus by the lining membrane of the sinus. The cavernous sinus receives the superior ophthalmic vein through the superior orbital fissure, some of the cerebral veins, and also the small **sphenoparietal sinus**, which courses along the under surface of the small wing of the sphenoid. It communicates with the transverse sinus by means of the superior petrosal sinus; with the internal jugular vein through the inferior petrosal sinus and a plexus of veins on the internal carotid artery; with the pterygoid venous plexus through the foramen Vesalii, foramen ovale, and foramen lacerum, and with the angular vein through the ophthalmic vein. The two sinuses

also communicate with each other by means of the anterior and posterior intercavernous sinuses.

**Applied Anatomy.**—An arteriovenous communication may be established between the cavernous sinus and the internal carotid artery, giving rise to a pulsating tumor in the orbit. These communications may be the result of injury, such as a bullet wound, a stab, or a blow, or fall sufficiently severe to cause a fracture of the base of the skull in this situation. The symptoms are sudden noise and pain in the head, followed by exophthalmos, swelling and congestion of the lids and conjunctivæ, and development of a pulsating tumor at the margin of the orbit, with thrill and the characteristic bruit; accompanying these symptoms there may be impairment of sight, paralysis of the iris and orbital muscles, and pain of varying intensity. In some cases the opposite orbit becomes affected by the passage of the arterial blood into the opposite sinus by means of the intercavernous sinuses; or the arterial blood may find its way through the emissary veins (see p. 747) into the pterygoid plexus, and thence into the veins of the face. Pulsating tumors of the orbit may also be due to traumatic aneurism of one of the orbital arteries, and symptoms resembling those of pulsating tumor may be produced by pressure on the ophthalmic vein, as it enters the sinus, by an aneurism of the internal carotid artery. Ligature of the internal or common carotid artery has been performed in these cases with considerable success.

Of recent years more attention has been paid to thrombosis of the cavernous sinus than formerly, and it is now well established that caries in the upper parts of the nasal cavities and suppuration in certain of the accessory sinuses of the nose are frequently responsible for septic thrombosis of the cavernous sinuses, in exactly the same way as transverse sinus thrombosis is due to septic disease in the mastoid process. Many deaths from meningitis, hitherto unaccounted for, are in reality due to the spread of an infection from an ethmoidal or sphenoidal air cell to the cavernous sinus, and thence to the meninges. It is obvious, therefore, that no case of chronic nasal suppuration should be left untreated.




FIG. 640.—Oblique section through the cavernous sinus.




FIG. 641.—Veins of orbit. (Poirier and Charpy.)

The **ophthalmic veins** (Fig. 641), two in number, **superior** and **inferior**, are devoid of valves.

The **Superior Ophthalmic Vein** (*v. ophthalmica superior*) begins at the inner angle of the orbit in a vein named the **nasofrontal** which communicates anteriorly with the angular vein; it pursues the same course as the ophthalmic artery, and receives

tributaries corresponding to the branches of that vessel. Forming a short single trunk, it passes between the two heads of the Rectus lateralis and through the medial part of the superior orbital fissure, and ends in the cavernous sinus.

The **Inferior Ophthalmic Vein** (*v. ophthalmica inferior*) begins in a venous net-work at the forepart of the floor and medial wall of the orbit; it receives some veins from the Rectus inferior, Obliquus inferior, lacrimal sac and eyelids, runs backward in the lower part of the orbit and divides into two branches. One of these passes through the inferior orbital fissure and joins the pterygoid venous plexus, while the other enters the cranium through the superior orbital fissure and ends in the cavernous sinus, either by a separate opening, or more frequently in common with the superior ophthalmic vein.

The **intercavernous sinuses** (*sini intercavernosi*) (Fig. 639) are two in number, an anterior and a posterior, and connect the two cavernous sinuses across the middle line. The **anterior** passes in front of the hypophysis cerebri, the **posterior** behind it, and they form with the cavernous sinuses a venous circle (**circular sinus**) around the hypophysis. The anterior one is usually the larger of the two, and one or other is occasionally absent.

The **superior petrosal sinus** (*sinus petrosus superior*) (Fig. 639) small and narrow, connects the cavernous with the transverse sinus. It runs lateralward and backward, from the posterior end of the cavernous sinus, over the trigeminal nerve, and lies in the attached margin of the tentorium cerebelli and in the superior petrosal sulcus of the temporal bone; it joins the transverse sinus where the latter curves downward on the inner surface of the mastoid part of the temporal. It receives some cerebellar and inferior cerebral veins, and veins from the tympanic cavity.

The **inferior petrosal sinus** (*sinus petrosus inferior*) (Fig. 639) is situated in the inferior petrosal sulcus formed by the junction of the petrous part of the temporal with the basilar part of the occipital. It begins in the postero-inferior part of the cavernous sinus, and, passing through the anterior part of the jugular foramen, ends in the superior bulb of the internal jugular vein. The inferior petrosal sinus receives the internal auditory veins and also veins from the medulla oblongata, pons, and under surface of the cerebellum.

The exact relation of the parts to one another in the jugular foramen is as follows: the inferior petrosal sinus lies medially and anteriorly with the meningeal branch of the ascending pharyngeal artery, and is directed obliquely downward and backward; the transverse sinus is situated at the lateral and back part of the foramen with a meningeal branch of the occipital artery, and between the two sinuses are the glossopharyngeal, vagus, and accessory nerves. These three sets of structures are divided from each other by two processes of fibrous tissue. The junction of the inferior petrosal sinus with the internal jugular vein takes place on the lateral aspect of the nerves.

The **basilar plexus** (*plexus basilaris; transverse or basilar sinus*) (Fig. 640) consists of several interlacing venous channels between the layers of the dura mater over the basilar part of the occipital bone, and serves to connect the two inferior petrosal sinuses. It communicates with the anterior vertebral venous plexus.

**Emissary Veins** (*emissaria*).—The emissary veins pass through apertures in the cranial wall and establish communication between the sinuses inside the skull and the veins external to it. Some are always present, others only occasionally so. The principal emissary veins are the following: (1) A mastoid emissary vein, usually present, runs through the mastoid foramen and unites the transverse sinus with the posterior auricular or with the occipital vein. (2) A parietal emissary vein passes through the parietal foramen and connects the superior sagittal sinus with the veins of the scalp. (3) A net-work of minute veins (*rete canalis hypoglossi*) traverses the hypoglossal canal and joins the transverse sinus with the vertebral

vein and deep veins of the neck. (4) An inconstant condyloid emissary vein passes through the condyloid canal and connects the transverse sinus with the deep veins of the neck. (5) A net-work of veins (*rete foraminis ovalis*) unites the cavernous sinus with the pterygoid plexus through the foramen ovale. (6) Two or three small veins run through the foramen lacerum and connect the cavernous sinus with the pterygoid plexus. (7) The emissary vein of the foramen of Vesalius connects the same parts. (8) An internal carotid plexus of veins traverses the carotid canal and unites the cavernous sinus with the internal jugular vein. (9) A vein is transmitted through the foramen caecum and connects the superior sagittal sinus with the veins of the nasal cavity.

**Applied Anatomy.**—These emissary veins together with the other communications between the intra- and extracranial circulation are of great importance in surgery. Inflammatory processes commencing on the outside of the skull may travel inward through them, and lead to osteophlebitis of the diploë and inflammation of the membranes of the brain. To this in former days was to be attributed one of the principal dangers of wounds of the scalp.

By means of these emissary veins blood may be abstracted from the intracranial circulation—*e. g.*, leeches applied behind the ear drain blood almost directly from the transverse sinus, through the mastoid vein. Again, epistaxis in children will frequently relieve severe headache, the blood which flows from the nose being partly derived from the superior sagittal sinus by means of the vein passing through the foramen caecum.

## THE VEINS OF THE UPPER EXTREMITY AND THORAX.

The veins of the upper extremity are divided into two sets, **superficial** and **deep**; the two sets anastomose frequently with each other. The superficial veins are placed immediately beneath the integument between the two layers of superficial fascia. The deep veins accompany the arteries, and constitute the *venae comitantes* of those vessels. Both sets are provided with valves, which are more numerous in the deep than in the superficial veins.

### The Superficial Veins of the Upper Extremity.

The superficial veins of the upper extremity are the **digital**, **metacarpal**, **cephalic**, **basilic**, **median**.

**Digital Veins.**—The dorsal digital veins pass along the sides of the fingers and are joined to one another by oblique communicating branches. Those from the adjacent sides of the fingers unite to form three **dorsal metacarpal veins** (Fig. 642), which end in a dorsal venous net-work opposite the middle of the metacarpus. The radial part of the net-work is joined by the dorsal digital vein from the radial side of the index finger and by the dorsal digital veins of the thumb, and is prolonged upward as the cephalic vein. The ulnar part of the net-work receives the dorsal digital vein of the ulnar side of the little finger and is continued upward as the basilic vein. A communicating branch frequently connects the dorsal venous network with the cephalic vein about the middle of the forearm.

The **volar digital veins** on each finger are connected to the dorsal digital veins by oblique **intercapitular veins**. They drain into a venous plexus which is situated over the thenar and hypothenar eminences and across the front of the wrist.

The **cephalic vein** (Fig. 643) begins in the radial part of the dorsal venous network and winds upward around the radial border of the forearm, receiving tributaries from both surfaces. Below the front of the elbow it gives off the **vena mediana cubiti** (*median basilic vein*), which receives a communicating branch from the deep veins of the forearm and passes across to join the basilic vein. The cephalic vein then ascends in front of the elbow in the groove between the Brachioradialis and the Biceps brachii. It crosses superficial to the musculocutaneous nerve and ascends in the groove along the lateral border of the Biceps brachii. In the upper third



of the arm it passes between the Pectoralis major and Deltoideus, where it is accompanied by the deltoid branch of the thoracoacromial artery. It pierces the coracoclavicular fascia and, crossing the axillary artery, ends in the axillary vein just below the clavicle. Sometimes it communicates with the external jugular vein by a branch which ascends in front of the clavicle.




FIG. 612.—The veins on the dorsum of the hand. (Bourguery.)

The **accessory cephalic vein** (*v. cephalica accessoria*) arises either from a small tributary plexus on the back of the forearm or from the ulnar side of the dorsal venous net-work; it joins the cephalic below the elbow. In some cases the accessory cephalic springs from the cephalic above the wrist and joins it again higher up. A large oblique branch frequently connects the basilic and cephalic veins on the back of the forearm.

The **basilic vein** (*v. basilica*) (Fig. 643) begins in the ulnar part of the dorsal venous network. It runs up the posterior surface of the ulnar side of the forearm and inclines forward to the anterior surface below the elbow, where it is joined by the vena mediana cubiti. It ascends obliquely in the groove between the Biceps brachii and Pronator teres and crosses the brachial artery, from which it is separated

by the *lacertus fibrosus*; filaments of the medial antibrachial cutaneous nerve pass both in front of and behind this portion of the vein. It then runs upward along the medial border of the arm, and, ascending on the medial side of the brachial artery to the lower border of the *Teres major*, is continued onward as the axillary vein.

The **median antibrachial vein** (*v. mediana antibrachii*) drains the venous plexus on the volar surface of the hand. It ascends on the ulnar side of the front of the forearm and ends in the basilic vein or in the *vena mediana cubiti*; in a small proportion of cases it divides into two branches, one of which joins the basilic, the other the cephalic, below the elbow.

**Applied Anatomy.**—*Venesection* is generally performed at the bend of the elbow, and as a matter of practice the largest vein in this situation is commonly selected. This is usually the *vena mediana cubiti* (*median basilic*), and there are anatomical advantages and disadvantages in selecting this vein. The advantages are, that in addition to its being the largest vessel, and therefore yielding a greater supply of blood, it is the least movable and can be easily steadied on the *lacertus fibrosus* (*bicipital fascia*), on which it rests. The disadvantages are, that it is in close relationship with the brachial artery, separated only by the *lacertus fibrosus*; and formerly, when venesection was frequently practised, arteriovenous aneurism was no uncommon result of this practice.

*Intravenous infusion* of normal saline solution is very frequently required in modern surgery for all conditions of severe shock and after profuse hemorrhages, the older method of transfusion of blood having quite sunk into oblivion. The patient's arm is surrounded by a tight bandage so as to impede the venous return, and a small incision is made over the largest vein visible in front of the elbow; a double ligature is now passed around the vein, and the lower one is tied; the vein is then opened and a cannula connected with a funnel by tubing and filled with hot saline solution is inserted. The bandage is next removed from the arm, and two, three, or more pints of fluid are allowed to flow into the vein; when a sufficient quantity has gone in, the upper ligature around the vein is tied and a stitch put in the skin wound.




FIG. 643.—The superficial veins of the upper extremity.

### The Deep Veins of the Upper Extremity.

The **deep veins** follow the course of the arteries, forming their *venae comitantes*. They are generally arranged in pairs, and are situated one on either side of the corresponding artery, and connected at intervals by short transverse branches.

**Deep Veins of the Hand.**—The superficial and deep volar arterial arches are each accompanied by a pair of *venae comitantes* which constitute respectively the **superficial and deep volar venous arches**, and receive the veins corresponding to the branches of the arterial arches; thus the **common volar digital veins**, formed by the union of the **proper volar digital veins**, open into the superficial, and the **volar metacarpal veins** into the deep volar venous arches. The **dorsal metacarpal veins** receive perforating branches from the volar metacarpal veins and end in the radial veins and in the superficial veins on the dorsum of the wrist.

The **deep veins of the forearm** are the *venae comitantes* of the radial and ulnar veins and constitute respectively the upward continuations of the deep and superficial volar venous arches; they unite in front of the elbow to form the brachial veins. The radial veins are smaller than the ulnar and receive the dorsal metacarpal veins. The ulnar veins receive tributaries from the deep volar venous arches and communicate with the superficial veins at the wrist; near the elbow they receive the volar and dorsal interosseous veins and send a large communicating branch (*profunda vein*) to the *vena mediana cubiti*.

The **brachial veins** (*vv. brachiales*) are placed one on either side of the brachial artery, receiving tributaries corresponding with the branches given off from that vessel; near the lower margin of the Subscapularis, they join the axillary vein; the medial one frequently joins the basilic vein.

These deep veins have numerous anastomoses, not only with each other, but also with the superficial veins.

The **axillary vein** (*v. axillaris*) begins at the lower border of the *Teres major*, as the continuation of the basilic vein, increases in size as it ascends, and ends at the outer border of the first rib as the subclavian vein. Near the lower border of the Subscapularis it receives the brachial veins and, close to its termination, the cephalic vein; its other tributaries correspond with the branches of the axillary artery. It lies on the medial side of the artery, which it partly overlaps; between the two vessels are the medial cord of the brachial plexus, the median, the ulnar, and the medial anterior thoracic nerves. It is provided with a pair of valves opposite the lower border of the Subscapularis; valves are also found at the ends of the cephalic and subscapular veins.

**Applied Anatomy.**—Since the axillary vein is superficial to and larger than the axillary artery, which it overlaps, it is more liable to be wounded than the artery in the operation of extirpation of the axillary glands, especially as these glands, when diseased, are apt to become adherent to it. When it is wounded, there is always a danger of air being drawn into it, and death resulting. To avoid wounding the axillary vein in the extirpation of glands from the axilla, it is advisable to expose the vein as soon as possible; no sharp cutting instruments should be used after the axillary cavity has been freely exposed; and care should be taken to use no undue force in isolating the glands (see p. 781). Should the vein be so imbedded in a malignant deposit that the latter cannot be removed without taking away a part of the vein, this must be done after the vessel has been ligatured above and below.

The **subclavian vein** (*v. subclavia*), the continuation of the axillary, extends from the outer border of the first rib to the sternal end of the clavicle, where it unites with the internal jugular to form the innominate vein. It is in relation, in *front*, with the clavicle and Subclavius; *behind* and *above*, with the subclavian artery, from which it is separated medially by the *Scalenus anterior* and the phrenic nerve. *Below*, it rests in a depression on the first rib and upon the pleura. It is usually provided with a pair of valves, which are situated about 2.5 cm. from its termination.

The subclavian vein occasionally rises in the neck to a level with the third part of the subclavian artery, and occasionally passes with this vessel behind the *Scalenus anterior*.

**Tributaries.**—This vein receives the external jugular vein, sometimes the anterior jugular vein, and occasionally a small branch, which ascends in front of the clavicle, from the cephalic. At its angle of junction with the internal jugular, the left subclavian vein receives the thoracic duct, and the right subclavian vein the right lymphatic duct.

#### The Veins of the Thorax (Fig. 644)

The **innominate veins** (*vv. anonymae; brachiocephalic veins*) are two large trunks, placed one on either side of the root of the neck, and formed by the union of the internal jugular and subclavian veins of the corresponding side; they are devoid of valves.

The **Right Innominate Vein** (*v. anonyma dextra*) is a short vessel, about 2.5 cm. in length, which begins behind the sternal end of the clavicle, and, passing almost vertically downward, joins with the left innominate vein just below the cartilage of the first rib, close to the right border of the sternum, to form the superior vena cava. It lies in front and to the right of the innominate artery; on its right side are the phrenic nerve and the pleura, which are interposed between it and the apex of the lung. This vein, at its commencement, receives the right vertebral vein; and, lower down, the right internal mammary and right inferior thyroid veins, and sometimes the vein from the first intercostal space.

The **Left Innominate Vein** (*v. anonyma sinistra*), about 6 cm. in length, begins behind the sternal end of the clavicle and runs obliquely downward and to the right behind the upper half of the manubrium sterni to the sternal end of the first right costal cartilage, where it unites with the right innominate vein to form the **superior vena cava**. It is separated from the manubrium sterni by the *Sternohyoideus* and *Sternothyroideus*, the thymus or its remains, and some loose areolar tissue. Behind it are the three large arteries, innominate, left common carotid, and left subclavian, arising from the aortic arch, together with the vagus and phrenic nerves. The left innominate vein may occupy a higher level, crossing the jugular notch and lying directly in front of the trachea.

**Tributaries.**—Its tributaries are the left vertebral, left internal mammary, left inferior thyroid, and the left highest intercostal veins, and occasionally some thymic and pericardiac veins.

**Peculiarities.**—Sometimes the innominate veins open separately into the right atrium; in such cases the right vein takes the ordinary course of the superior vena cava; the left vein—*left superior vena cava*, as it is then termed—which may communicate by a small branch with the right one, passes in front of the root of the left lung, and, turning to the back of the heart, ends in the right atrium. This occasional condition in the adult is due to the persistence of the early fetal condition, and is the normal state of things in birds and some mammalia.

The **internal mammary veins** (*vv. mammae internae*) are *venae comitantes* to the lower half of the internal mammary artery, and receive tributaries corresponding to the branches of the artery. They then unite to form a single trunk, which runs up on the medial side of the artery and ends in the corresponding innominate vein. The **superior phrenic vein**, *i. e.*, the vein accompanying the pericardiacophrenic artery, usually opens into the internal mammary vein.

The **inferior thyroid veins** (*vv. thyroideae inferiores*) two, frequently three or four, in number, arise in the venous plexus on the thyroid gland, communicating with the middle and superior thyroid veins. They form a plexus in front of the trachea, behind the *Sternothyroidei*. From this plexus, a left vein descends and joins the left innominate trunk, and a right vein passes obliquely downward and to the right across the innominate artery to open into the right innominate vein,



just at its junction with the superior vena cava; sometimes the right and left veins open by a common trunk in the latter situation. These veins receive œsophageal,




FIG. 644.—The venae cavae and azygos veins, with their tributaries.

tracheal, and inferior laryngeal veins, and are provided with valves at their terminations in the innominate veins.



The **highest intercostal vein** (*v. intercostalis suprema; superior intercostal veins*) (right and left) drain the blood from the upper three or four intercostal spaces. The **right vein** (*v. intercostalis suprema dextra*) passes downward and opens into the vena azygos; the **left vein** (*v. intercostalis suprema sinistra*) runs across the arch of the aorta and the origins of the left subclavian and left common carotid arteries and opens into the left innominate vein. It usually receives the left bronchial vein, and sometimes the left superior phrenic vein, and communicates below with the accessory hemiazygos vein.

The **superior vena cava** (*v. cava superior*) drains the blood from the upper half of the body. It measures about 7 cm. in length, and is formed by the junction of the two innominate veins. It begins immediately below the cartilage of the right first rib close to the sternum, and, descending vertically behind the first and second intercostal spaces, ends in the upper part of the right atrium opposite the upper border of the third right costal cartilage: the lower half of the vessel is within the pericardium. In its course it describes a slight curve, the convexity of which is to the right side.

**Relations.**—In front are the anterior margins of the right lung and pleura with the pericardium intervening below; these separate it from the first and second intercostal spaces and from the second and third right costal cartilages; behind it are the root of the right lung and the right vagus nerve. On its *right side* are the phrenic nerve and right pleura; on its *left side*, the commencement of the innominate artery and the ascending aorta, the latter overlapping it. Just before it pierces the pericardium, it receives the azygos vein and several small veins from the pericardium and other contents of the mediastinal cavity. The portion contained within the pericardium is covered, in front and laterally, by the serous layer of the membrane. The superior vena cava has no valves.

The **azygos vein** (*v. azygos; vena azygos major*) begins opposite the first or second lumbar vertebra, by a branch, the **ascending lumbar vein** (page 763); sometimes by a branch from the right renal vein, or from the inferior vena cava. It enters the thorax through the aortic hiatus in the Diaphragma, and passes along the right side of the vertebral column to the fourth thoracic vertebra, where it arches forward over the root of the right lung, and ends in the superior vena cava, just before that vessel pierces the pericardium. In the aortic hiatus, it lies with the thoracic duct on the right side of the aorta; in the thorax it lies upon the intercostal arteries, on the right side of the aorta and thoracic duct, and is partly covered by pleura.

**Tributaries.**—It receives the right subcostal and intercostal veins, the upper three or four of these latter opening by a common stem, the highest superior intercostal vein. It receives the hemiazygos veins, several œsophageal, mediastinal, and pericardial veins, and, near its termination, the right bronchial vein. A few imperfect valves are found in the azygos vein; but its tributaries are provided with complete valves.

The intercostal veins on the left side, below the upper three intercostal spaces, usually form two trunks, named the **hemiazygos** and **accessory hemiazygos veins**.

The **Hemiazygos Veins** (*v. hemiazygos; vena azygos minor inferior*) begins in the left ascending lumbar or renal vein, It enters the thorax, through the left crus of the Diaphragma, and, ascending on the left side of the vertebral column, as high as the ninth thoracic vertebra, passes across the column, behind the aorta, œsophagus, and thoracic duct, to end in the azygos vein. It receives the lower four or five intercostal veins and the subcostal vein of the left side, and some œsophageal and mediastinal veins.

The **Accessory Hemiazygos Vein** (*v. hemiazygos accessoria; vena azygos minor superior*) descends on the left side of the vertebral column, and varies inversely in size with the highest left intercostal vein. It receives veins from the three or four intercostal spaces between the highest left intercostal vein and highest tributary of the hemiazygos; the left bronchial vein sometimes opens into it. It either crosses

the body of the eighth thoracic vertebra to join the azygos vein or ends in the hemiazygos. When this vein is small, or altogether wanting, the left highest intercostal vein may extend as low as the fifth or sixth intercostal space.

**Applied Anatomy.**—In obstruction of the superior vena cava, the azygos and hemiazygos veins are one of the principal means by which the venous circulation is carried on, connecting as they do the superior and inferior venæ cavæ, and communicating with the common iliac veins by the ascending lumbar veins and with many of the tributaries of the inferior vena cava.

Thrombosis of the superior vena cava is oftenest due to pressure exerted on the vessel by an aneurism or a tumor; it may also occur by propagation of clotting from a tributary peripheral vein. If occlusion of the vessel take place slowly, a collateral venous circulation may be established; the patient will have some œdema with dilatation and congestion of the veins about the head and neck, and may also suffer from attacks of dyspnoea and recurrent pleural effusion. In most cases, however, the blockage of the superior cava takes place rapidly, and is rapidly fatal.

The **Bronchial Veins** (*vv. bronchiales*) return the blood from the larger bronchi, and from the structures at the roots of the lungs; that of the right side opens into the azygos vein, near its termination; that of the left side, into the highest left intercostal or the accessory hemiazygos vein. A considerable quantity of the blood which is carried to the lungs through the bronchial arteries is returned to the left side of the heart through the pulmonary veins.




FIG. 645.—Transverse section of a thoracic vertebra, showing the vertebral venous plexuses.




FIG. 646.—Median sagittal section of two thoracic vertebrae, showing the vertebral venous plexuses.

### The Veins of the Vertebral Column (Figs. 645, 646).

The veins which drain the blood from the vertebral column, the neighboring muscles, and the meninges of the medulla spinalis form intricate plexuses extending along the entire length of the column; these plexuses may be divided into two groups, external and internal, according to their positions inside or outside the vertebral canal. The plexuses of the two groups anastomose freely with each other and end in the intervertebral veins.

The **external vertebral venous plexuses** (*plexus venosi vertebrales externi; extra-spinal veins*) best marked in the cervical region, consist of anterior and posterior plexuses which anastomose freely with each other. The **anterior external plexuses** lie in front of the bodies of the vertebrae, communicate with the basivertebral and intervertebral veins, and receive tributaries from the vertebral bodies. The **posterior external plexuses** are placed partly on the posterior surfaces of the vertebral

arches and their processes, and partly between the deep dorsal muscles. They are best developed in the cervical region, and there anastomose with the vertebral, occipital, and deep cervical veins.

The **internal vertebral venous plexuses** (*plexus venosi vertebrales interni; intra-spinal veins*) lie within the vertebral canal between the dura mater and the vertebræ, and receive tributaries from the bones and from the medulla spinalis. They form a closer net-work than the external plexuses, and, running mainly in a vertical direction, form four longitudinal veins, two in front and two behind; they therefore may be divided into anterior and posterior groups. The **anterior internal plexuses** consist of large veins which lie on the posterior surfaces of the vertebral bodies and intervertebral fibrocartilages on either side of the posterior longitudinal ligament; under cover of this ligament they are connected by transverse branches into which the basivertebral veins open. The **posterior internal plexuses** are placed, one on either side of the middle line in front of the vertebral arches and ligamenta flava, and anastomose by veins passing through those ligaments with the posterior external plexuses. The anterior and posterior plexuses communicate freely with one another by a series of **venous rings** (*retia venosa vertebrarum*), one opposite each vertebra. Around the foramen magnum they form an intricate net-work which opens into the vertebral veins and is connected above with the occipital sinus, the basilar plexus, the condyloid emissary vein, and the rete canalis hypoglossi.

The **basivertebral veins** (*vv. basivertebrales*) emerge from the foramina on the posterior surfaces of the vertebral bodies. They are contained in large, tortuous channels in the substance of the bones, similar in every respect to those found in the diploë of the cranial bones. They communicate through small openings on the front and sides of the bodies of the vertebræ with the anterior external vertebral plexuses, and converge behind to the principal canal, which is sometimes double toward its posterior part, and open by valved orifices into the transverse branches which unite the anterior internal vertebral plexuses. They become greatly enlarged in advanced age.

The **intervertebral veins** (*vv. intervertebrales*) accompany the spinal nerves through the intervertebral foramina; they receive the veins from the medulla spinalis, drain the internal and external vertebral plexuses and end in the vertebral, intercostal, lumbar, and lateral sacral veins, their orifices being provided with valves.

The **veins of the medulla spinalis** (*vv. spinales; veins of the spinal cord*) are situated in the pia mater and form a minute, tortuous, venous plexus. They emerge chiefly from the median fissures of the medulla spinalis and are largest in the lumbar region. In this plexus there are (1) two median longitudinal veins, one in front of the anterior fissure, and the other behind the posterior sulcus of the cord, and (2) four lateral longitudinal veins which run behind the nerve roots. They end in the intervertebral veins. Near the base of the skull they unite, and form two or three small trunks, which communicate with the vertebral veins, and then end in the inferior cerebellar veins, or in the inferior petrosal sinuses.

## THE VEINS OF THE LOWER EXTREMITY, ABDOMEN, AND PELVIS.

The veins of the lower extremity are subdivided, like those of the upper, into two sets, **superficial** and **deep**; the superficial veins are placed beneath the integument between the two layers of superficial fascia; the deep veins accompany the arteries. Both sets of veins are provided with valves, which are more numerous in the deep than in the superficial set. Valves are also more numerous in the veins of the lower than in those of the upper limb.

### The Superficial Veins of the Lower Extremity.

The **superficial veins** of the lower extremity are the **great and small saphenous veins** and their tributaries.

On the **dorsum of the foot** the **dorsal digital veins** receive, in the clefts between the toes, the **intercapitular veins** from the plantar cutaneous venous arch and join to form short **common digital veins** which unite across the distal ends of the metatarsal bones in a **dorsal venous arch**. Proximal to this arch is an irregular venous net-work which receives tributaries from the deep veins and is joined at the sides of the foot by a **medial** and a **lateral marginal vein**, formed mainly by the union of branches from the superficial parts of the sole of the foot.

On the **sole of the foot** the superficial veins form a **plantar cutaneous venous arch** which extends across the roots of the toes and opens at the sides of the foot into the medial and lateral marginal veins. Proximal to this arch is a **plantar cutaneous venous net-work** which is especially dense in the fat beneath the heel; this net-work communicates with the cutaneous venous arch and with the deep veins, but is chiefly drained into the medial and lateral marginal veins.

The **great saphenous vein** (*v. saphena magna*; *internal or long saphenous vein*) (Fig. 647), the longest vein in the body, *begins* in the medial marginal vein of the dorsum of the foot and ends in the femoral vein about 3 cm. below the inguinal ligament. It ascends in front of the tibial malleolus and along the medial side of the leg in relation with the saphenous nerve. It runs upward behind the medial condyles of the tibia and femur and along the medial side of the thigh and, passing through the fossa ovalis, ends in the femoral vein.


**Tributaries.**—At the ankle it receives branches from the sole of the foot through the medial marginal vein; in the leg it anastomoses freely with the small saphenous vein, communicates with the anterior and posterior tibial veins and receives many cutaneous veins; in the thigh it communicates with the femoral vein and receives numerous tributaries; those from the medial and posterior parts of the thigh frequently unite to form a large **accessory saphenous vein** which joins the main vein at a variable level. Near the fossa ovalis (Fig. 648) it is joined by the superficial epigastric, superficial iliac circumflex, and superficial external pudendal veins. A vein, named the **thoracoepigastric**, runs along the lateral aspect of the trunk between the superficial epigastric vein below and the lateral thoracic vein above and establishes an important communication between the femoral and axillary veins.



Fig. 647.—The great saphenous vein and its tributaries.

The valves in the great saphenous vein vary from ten to twenty in number; they are more numerous in the leg than in the thigh.

The **small saphenous vein** (*v. saphena parva*; *external or short saphenous vein*) (Fig. 649) begins behind the lateral malleolus as a continuation of the lateral marginal vein; it first ascends along the lateral margin of the tendocalcaneus, and then crosses it to reach the middle of the back of the leg. Running directly upward, it perforates the deep fascia in the lower part of the popliteal fossa, and ends in the popliteal vein, between the heads of the Gastrocnemius. It communicates with the deep veins on the dorsum of the foot, and receives numerous large tributaries from the back of the leg. Before it pierces the deep fascia, it gives off a branch which runs upward and forward to join the great saphenous vein. The small saphenous vein possesses from nine to twelve valves, one of which is always found near its termination in the popliteal vein. In the lower third of the leg the small saphenous vein is in close relation with the sural nerve, in the upper two-thirds with the medial sural cutaneous nerve.



• FIG. 648.—The great saphenous vein and its tributaries at the fossa ovalis.

**Applied Anatomy.**—A varicose condition of the saphenous veins is more frequently met with than in the other veins of the body, except perhaps the spermatic and hemorrhoidal veins. The main cause of this is the high blood pressure, determined chiefly by the erect position, and the length of the column of blood, which has to be propelled in an uphill direction. In normal vessels there is only just sufficient force to perform this task; and in those cases where there is diminished resistance of the walls of the veins, these vessels are liable to dilate and a varicose condition is set up. This diminished resistance may be due to heredity, the vein walls being congenitally weak, or it may follow inflammatory conditions of the vessels. Increased blood pressure in the veins, caused by any obstacle to the return of the venous blood, such as the pressure of a tumor,



or the gravid uterus, or tight gartering, may also produce varix. In the normal condition of the veins, the valves in their interior break up the column of blood into a number of smaller columns, and so to a considerable extent mitigate the ill effects of the erect position; but when the dilatation of the veins has reached a certain limit, the valves become incapable of supporting the overlying column of blood, and the pressure is increased, tending to emphasize also the varicose condition. Both the saphenous veins in the leg are accompanied by nerves, the great saphenous being joined by its companion nerve just below the level of the knee-joint. No doubt much of the pain of varicose veins in the leg is due to this fact.




FIG. 649.—The small saphenous vein.

Operations for the relief of varicose veins are frequently required, portions of the veins being removed after having been ligatured above and below. It is important to note whether the main varicose area drains into the great or the small saphenous vein—the former condition being much the more common—and to control the venous return by removing a small portion of the main trunk just before it opens into the deep vein by passing through the deep fascia; thus in most cases a piece should be removed from the great saphenous just before it passes through the fossa ovalis (*saphenous opening*), and in addition the affected veins should be excised just above and just below the level of the knee-joint. In other cases the small saphenous will have to be dealt with immediately below the point where it pierces the fascial roof of the popliteal fossa.

### The Deep Veins of the Lower Extremity.

The **deep veins** of the lower extremity accompany the arteries and their branches; they possess numerous valves.

The **plantar digital veins** (*vv. digitales plantares*) arise from plexuses on the plantar surfaces of the digits, and, after sending **intercapitular veins** to join the dorsal digital veins, unite to form four **metatarsal veins**; these run backward in the metatarsal spaces, communicate, by means of perforating veins, with the veins on the dorsum of the foot, and unite to form the **deep plantar venous arch** which lies alongside the plantar arterial arch. From the deep plantar venous arch the **medial** and **lateral plantar veins** run backward close to the corresponding arteries and, after communicating with the great and small saphenous veins, unite behind the medial malleolus to form the posterior tibial veins.

The **posterior tibial veins** (*vv. tibiales posteriores*) accompany the posterior tibial artery, and are joined by the **peroneal veins**.

The **anterior tibial veins** (*vv. tibiales anteriores*) are the upward continuation of the *venae comitantes* of the *dorsalis pedis* artery. They leave the front of the leg by passing between the tibia and fibula, over the interosseous membrane, and unite with the posterior tibial, to form the **popliteal vein**.

The **Popliteal Vein** (*v. poplitea*) is formed by the junction of the anterior and posterior tibial veins at the lower border of the Popliteus; it ascends through the popliteal fossa to the aperture in the Adductor magnus, where it becomes the femoral vein. In the lower part of its course it is placed medial to the artery; between the heads of the Gastrocnemius it is superficial to that vessel; but above the knee-joint, it is close to its lateral side. It receives tributaries corresponding to the branches of the popliteal artery, and it also receives the small saphenous vein. The valves in the popliteal vein are usually four in number.

The **femoral vein** (*v. femoralis*) accompanies the femoral artery through the upper two-thirds of the thigh. In the lower part of its course it lies lateral to the

artery; higher up, it is behind it; and at the inguinal ligament, it lies on its medial side, and on the same plane. It receives numerous muscular tributaries, and about 4 cm. below the inguinal ligament is joined by the *v. profunda femoris*; near its termination it is joined by the great saphenous vein. The valves in the femoral vein are three in number.

The **Deep Femoral Vein** (*v. profunda femoris*) receives tributaries corresponding to the perforating branches of the profunda artery, and through these establishes communications with the popliteal vein below and the inferior gluteal vein above. It also receives the medial and lateral femoral circumflex veins.




FIG. 650.—The veins of the right half of the male pelvis. (Spalteholz.)

### The Veins of the Abdomen and Pelvis (Fig. 650).

The **external iliac vein** (*v. iliaca externa*), the upward continuation of the femoral vein, begins behind the inguinal ligament, and, passing upward along the brim of the lesser pelvis, ends opposite the sacroiliac articulation, by uniting with the hypogastric vein to form the common iliac vein. On the right side, it lies at first medial to the artery: but, as it passes upward, gradually inclines behind it. On

the left side, it lies altogether on the medial side of the artery. It frequently contains one, sometimes two, valves.

**Tributaries.**—The external iliac vein receives the inferior epigastric, deep iliac circumflex, and pubic veins.

The **Inferior Epigastric Vein** (*v. epigastrica inferior; deep epigastric vein*) is formed by the union of the venae comitantes of the inferior epigastric artery, which communicate above with the superior epigastric vein; it joins the external iliac about 1.25 cm. above the inguinal ligament.

The **Deep Iliac Circumflex Vein** (*v. circumflexa ilium profunda*) is formed by the union of the venae comitantes of the deep iliac circumflex artery, and joins the external iliac vein about 2 cm. above the inguinal ligament.

The **Pubic Vein** communicates with the obturator vein in the obturator foramen, and ascends on the back of the pubis to the external iliac vein.

The **hypogastric vein** (*v. hypogastrica; internal iliac vein*) begins near the upper part of the greater sciatic foramen, passes upward behind and slightly medial to the hypogastric artery and, at the brim of the pelvis, joins with the external iliac to form the common iliac vein.

**Tributaries.**—With the exception of the fetal umbilical vein which passes upward and backward from the umbilicus to the liver, and the iliolumbar vein which usually joins the common iliac vein, the tributaries of the hypogastric vein correspond with the branches of the hypogastric artery. It receives (a) the **gluteal, internal pudendal, and obturator veins**, which have their origins outside the pelvis; (b) the **lateral sacral veins**, which lie in front of the sacrum; and (c) the **middle hemorrhoidal, vesical, uterine, and vaginal veins**, which originate in venous plexuses connected with the pelvic viscera.

1. The **Superior Gluteal Veins** (*vv. glutaeae superiores; gluteal veins*) are venae comitantes of the superior gluteal artery; they receive tributaries from the buttock corresponding with the branches of the artery, and enter the pelvis through the greater sciatic foramen, above the Piriformis, and frequently unite before ending in the hypogastric vein.

2. The **Inferior Gluteal Veins** (*vv. glutaeae inferiores; sciatic veins*), or venae comitantes of the inferior gluteal artery, begin on the upper part of the back of the thigh, where they anastomose with the medial femoral circumflex and first perforating veins. They enter the pelvis through the lower part of the greater sciatic foramen and join to form a single stem which opens into the lower part of the hypogastric vein.

3. The **Internal Pudendal Veins** (*internal pudic veins*) are the venae comitantes of the internal pudendal artery. They begin in the deep veins of the penis which issue from the corpus cavernosum penis, accompany the internal pudendal artery, and unite to form a single vessel, which ends in the hypogastric vein. They receive the veins from the urethral bulb, and the perineal and inferior hemorrhoidal veins. The deep dorsal vein of the penis communicates with the internal pudendal veins, but ends mainly in the pudendal plexus.

4. The **Obturator Vein** (*v. obturatoria*) begins in the upper portion of the adductor region of the thigh and enters the pelvis through the upper part of the obturator foramen. It runs backward and upward on the lateral wall of the pelvis below the obturator artery, and then passes between the ureter and the hypogastric artery, to end in the hypogastric vein.

5. The **Lateral Sacral Veins** (*vv. sacrales laterales*) accompany the lateral sacral arteries on the anterior surface of the sacrum and end in the hypogastric vein.

6. The **Middle Hemorrhoidal Vein** (*v. haemorrhoidalis media*) takes origin in the hemorrhoidal plexus and receives tributaries from the bladder, prostate, and seminal vesicle; it runs lateralward on the pelvic surface of the Levator ani to end in the hypogastric vein.

The **hemorrhoidal plexus** (*plexus haemorrhoidalis*) surrounds the rectum, and communicates in front with the vesical plexus in the male, and the uterovaginal plexus in the female. It consists of two parts, an **internal** in the submucosa, and an **external** outside the muscular coat. The internal plexus presents a series of dilated pouches which are arranged in a circle around the tube, immediately above the anal orifice, and are connected by transverse branches.

The lower part of the external plexus is drained by the inferior hemorrhoidal veins into the internal pudendal vein; the middle part by the middle hemorrhoidal vein which joins the hypogastric vein; and the upper part by the superior hemorrhoidal vein which forms the commencement of the inferior mesenteric vein, a tributary of the portal vein. A free communication between the portal and systemic venous systems is established through the hemorrhoidal plexus.

The **pudendal plexus** (*plexus pudendalis*; *vesicoprostatic plexus*) lies behind the arcuate pubic ligament and the lower part of the symphysis pubis, and in front of the bladder and prostate. Its chief tributary is the deep dorsal vein of the penis, but it also receives branches from the front of the bladder and prostate. It communicates with the vesical plexus and with the internal pudendal vein and drains into the vesical and hypogastric veins. The **prostatic veins** form a well-marked **prostatic plexus** which lies partly in the fascial sheath of the prostate and partly between the sheath and the prostatic capsule. It communicates with the pudendal and vesical plexuses.

The **vesical plexus** (*plexus vesicalis*) envelops the lower part of the bladder and the base of the prostate and communicates with the pudendal and prostatic plexuses. It is drained, by means of several vesical veins, into the hypogastric veins.

**Applied Anatomy.**—The veins of the hemorrhoidal plexus are apt to become dilated and varicose, and form piles. This is due to several anatomical reasons: the vessels are contained in very loose, connective tissue, so that they get less support from surrounding structures than most other veins, and are less capable of resisting increased blood pressure; the condition is favored by gravitation, being influenced by the erect posture, either sitting or standing, and by the fact that the superior hemorrhoidal and portal veins have no valves; the veins pass through muscular tissue and are liable to be compressed by its contraction, especially during the act of defecation; they are affected by every form of portal obstruction.

The prostatic plexus of veins is apt to become congested in many inflammatory conditions in the neighborhood, such as acute gonorrheal prostatitis. It is owing to the free communication which exists between this and the middle hemorrhoidal plexus that great relief can be given by free saline purgation.

Hemorrhage may be very free from the prostatic plexus after operations on that gland, but can usually be checked by hot fluid irrigation. Septic thrombosis sometimes occurs after operations, and infected emboli may find their way into the general circulation.

The **Dorsal Veins of the Penis** (*vv. dorsales penis*) are two in number, a superficial and a deep. The **superficial vein** drains the prepuce and skin of the penis, and, running backward in the subcutaneous tissue, inclines to the right or left, and opens into the corresponding superficial external pudendal vein, a tributary of the great saphenous vein. The **deep vein** lies beneath the deep fascia of the penis; it receives the blood from the glans penis and corpora cavernosa penis and courses backward in the middle line between the dorsal arteries; near the root of the penis it passes between the two parts of the suspensory ligament and then through an aperture between the arcuate pubic ligament and the transverse ligament of the pelvis, and divides into two branches, which enter the pudendal plexus. The deep vein also communicates below the symphysis pubis with the internal pudendal vein.

The **uterine plexuses** lie along the sides and superior angles of the uterus between the two layers of the broad ligament, and communicate with the ovarian and vaginal plexuses. They are drained by a pair of uterine veins on either side: these *arise* from the lower part of the plexuses, opposite the external orifice of the uterus, and open into the corresponding hypogastric vein.



The **vaginal plexuses** are placed at the sides of the vagina; they communicate with the uterine, vesical, and hemorrhoidal plexuses, and are drained by the vaginal veins, one on either side, into the hypogastric veins.

The **common iliac veins** (*vv. iliacae communes*) are formed by the union of the external iliac and hypogastric veins, in front of the sacroiliac articulation; passing obliquely upward toward the right side, they end upon the fifth lumbar vertebra, by uniting with each other at an acute angle to form the inferior vena cava. The **right common iliac** is shorter than the left, nearly vertical in its direction, and ascends behind and then lateral to its corresponding artery. The **left common iliac**, longer than the right and more oblique in its course, is at first situated on the medial side of the corresponding artery, and then behind the right common iliac. Each common iliac receives the ilio-lumbar, and sometimes the lateral sacral veins. The left receives, in addition, the middle sacral vein. No valves are found in these veins.

The **Middle Sacral Veins** (*vv. sacrales mediales*) accompany the corresponding artery along the front of the sacrum, and join to form a single vein, which ends in the left common iliac vein; sometimes in the angle of junction of the two iliac veins.

**Peculiarities.**—The left common iliac vein, instead of joining with the right in its usual position, occasionally ascends on the left side of the aorta as high as the kidney, where, after receiving the left renal vein, it crosses over the aorta, and then joins with the right vein to form the vena cava. In these cases, the two common iliacs are connected by a small communicating branch at the spot where they are usually united.

The **inferior vena cava** (*v. cava inferior*) (Fig. 644), returns to the heart the blood from the parts below the Diaphragma. It is formed by the junction of the two common iliac veins, on the right side of the fifth lumbar vertebra. It ascends along the front of the vertebral column, on the right side of the aorta, and, having reached the liver, is continued in a groove on its posterior surface. It then perforates the Diaphragma between the median and right portions of its central tendon; it subsequently inclines forward and medialward for about 2.5 cm., and, piercing the fibrous pericardium, passes behind the serous pericardium to open into the lower and back part of the right atrium. In front of its atrial orifice is a semilunar valve, termed the **valve of the inferior vena cava**: this is rudimentary in the adult, but is of large size and exercises an important function in the fetus (see page 618).

**Relations.**—The *abdominal portion* of the inferior vena cava is in relation *in front*, from below upward, with the right common iliac artery, the mesentery, the right internal spermatic artery, the inferior part of the duodenum, the pancreas, the common bile duct, the portal vein, and the posterior surface of the liver; the last partly overlaps and occasionally completely surrounds it; *behind*, with the vertebral column, the right Psoas major, the right crus of the Diaphragma, the right inferior phrenic, suprarenal, renal and lumbar arteries, right sympathetic trunk and right coeliac ganglion, and the medial part of the right suprarenal gland; on the *right side*, with the right kidney and ureter; on the *left side*, with the aorta, right crus of the Diaphragma, and the caudate lobe of the liver.

The *thoracic portion* is only about 2.5 cm. in length, and is situated partly inside and partly outside the pericardial sac. The *extrapericardial part* is separated from the right pleura and lung by a fibrous band, named the **right phrenicopericardiac ligament**. This ligament, often feebly marked, is attached below to the margin of the vena-caval opening in the Diaphragma, and above to the pericardium in front of and behind the root of the right lung. The *intrapericardiac part* is very short, and is covered antero-laterally by the serous layer of the pericardium.

**Peculiarities.**—*In Position.*—This vessel is sometimes placed on the left side of the aorta, as high as the left renal vein, and, after receiving this vein, crosses over to its usual position on the right side; or it may be placed altogether on the left side of the aorta, and in such a case the abdominal and thoracic viscera, together with the great vessels, are all transposed.

*Point of Termination.*—Occasionally the inferior vena cava joins the azygos vein, which is then of large size. In such cases, the superior vena cava receives the whole of the blood from the body before transmitting it to the right atrium, except the blood from the hepatic veins, which passes directly into the right atrium.

**Applied Anatomy.**—Thrombosis of the inferior vena cava is due to much the same causes as that of the superior (see p. 754). It usually causes œdema of the legs and back, without ascites;



if the renal veins are involved, blood and albumin will often appear in the urine. An extensive collateral venous circulation is soon established by enlargement either of the superficial or of the deep veins, or of both. In the first case the epigastric, the iliac circumflex, the lateral thoracic, the internal mammary, the intercostals, the external pudendal, and the lumbovertebral anastomatic veins of Braune effect the communication with the superior cava; in the second, the deep anastomosis is made by the azygos and hemiazygos and the lumbar veins.<sup>1</sup>

**Tributaries.**—The inferior vena cava receives the following veins:

Lumbar.	Renal.	Inferior Phrenic.
Right Spermatic or Ovarian.	Suprarenal.	Hepatic.

The **Lumbar Veins** (*vv. lumbales*) four in number on each side, collect the blood by dorsal tributaries from the muscles and integument of the loins, and by abdominal tributaries from the walls of the abdomen, where they communicate with the epigastric veins. At the vertebral column, they receive veins from the vertebral plexuses, and then pass forward, around the sides of the bodies of the vertebræ, beneath the Psoas major, and end in the back part of the inferior cava. The left lumbar veins are longer than the right, and pass behind the aorta. The lumbar veins are connected together by a longitudinal vein which passes in front of the transverse processes of the lumbar vertebræ, and is called the **ascending lumbar**; it forms the most frequent origin of the corresponding azygos or hemiazygos vein, and serves to connect the common iliac, iliolumbar, and azygos or hemiazygos veins of its own side of the body.

The **Spermatic Veins** (*vv. spermaticæ*) emerge from the back of the testis, and receive tributaries from the epididymis; they unite and form a convoluted plexus, called the **pampiniform plexus**, which constitutes the greater mass of the spermatic cord; the vessels composing this plexus are very numerous, and ascend along the cord, in front of the ductus deferens. Below the subcutaneous inguinal ring they unite to form three or four veins, which pass along the inguinal canal, and, entering the abdomen through the abdominal inguinal ring, coalesce to form two veins, which ascend on the Psoas major, behind the peritoneum, lying one on either side of the internal spermatic artery. These unite to form a single vein, which opens on the right side into the inferior vena cava, at an acute angle; on the left side into the left renal vein, at a right angle. The spermatic veins are provided with valves.<sup>2</sup> The left spermatic vein passes behind the iliac colon, and is thus exposed to pressure from the contents of that part of the bowel.

**Applied Anatomy.**—The spermatic veins are very frequently varicose, constituting the condition known as **varicocele**. Though it is quite possible that the originating cause of this affection may be a congenital weakness of the walls of the veins of the pampiniform plexus, still it must be admitted that there are many anatomical reasons why these veins should become varicose, viz.: the imperfect support afforded to them by the loose tissue of the scrotum; their great length; their vertical course; their dependent position; their plexiform arrangement in the scrotum, with their termination in one small vein in the abdomen; their few and imperfect valves; and the fact that they may be subjected to pressure in their passage through the abdominal wall. Varicocele almost invariably occurs on the left side, and this has been accounted for by the facts that the left spermatic vein joins the left renal at a right angle; that it is overlaid by the iliac colon, and that when this portion of the gut is full of fecal matter, in cases of constipation, its weight impedes the return of the venous blood; and that the left spermatic veins are somewhat longer than the right.

The operation for the removal of a varicocele consists in making a small incision just over the subcutaneous inguinal ring and passing an aneurism needle around the mass of veins, taking care that the ductus deferens is not included. The veins are isolated from the ductus and ligatured above and below, as high and as low as possible, and the intermediate portion cut away; the divided ends are fixed together with a suture, and the skin wound closed.

<sup>1</sup> G. Blumer, in Osler and McCrae's *Modern Medicine*, Philadelphia, 1908, vol. iv.

<sup>2</sup> Rivington has pointed out that valves are usually found at the orifices of both the right and left spermatic veins. When no valves exist at the opening of the left spermatic vein into the left renal vein, valves are generally present in the left renal vein within 6 mm. from the orifice of the spermatic vein.—*Journal of Anatomy and Physiology*, vii, 163.

The **Ovarian Veins** (*vv. ovaricae*) correspond with the spermatic in the male; they form a plexus in the broad ligament near the ovary and uterine tube, and communicate with the uterine plexus. They end in the same way as the spermatic veins in the male. Valves are occasionally found in these veins. Like the uterine veins, they become much enlarged during pregnancy.

The **Renal Veins** (*vv. renales*) are of large size, and placed in front of the renal arteries. The left is longer than the right, and passes in front of the aorta, just below the origin of the superior mesenteric artery. It receives the left spermatic and left inferior phrenic veins, and, generally, the left suprarenal vein. It opens into the inferior vena cava at a slightly higher level than the right.

The **Suprarenal Veins** (*vv. suprarenales*) are two in number: the right ends in the inferior vena cava; the left, in the left renal or left inferior phrenic vein.

The **Inferior Phrenic Veins** (*vv. phrenicae inferiores*) follow the course of the inferior phrenic arteries; the right ends in the inferior vena cava; the left is often represented by two branches, one of which ends in the left renal or suprarenal vein, while the other passes in front of the oesophageal hiatus in the Diaphragma and opens into the inferior vena cava.

The **Hepatic Veins** (*vv. hepaticae*) commence in the substance of the liver, in the terminations of the portal vein and hepatic artery, and are arranged in two groups, upper and lower. The **upper group** usually consists of three large veins, which converge toward the posterior surface of the liver, and open into the inferior vena cava, while that vessel is situated in the groove on the back part of the liver. The veins of the **lower group** vary in number, and are of small size; they come from the right and caudate lobes. The hepatic veins run singly, and are in direct contact with the hepatic tissue. They are destitute of valves.

### THE PORTAL SYSTEM OF VEINS (Fig. 651).

The **portal system** includes all the veins which drain the blood from the abdominal part of the digestive tube (with the exception of the lower part of the rectum) and from the spleen, pancreas, and gall-bladder. From these viscera the blood is conveyed to the liver by the **portal vein**. In the liver this vein ramifies like an artery and ends in capillary-like vessels termed **sinusoids**, from which the blood is conveyed to the inferior vena cava by the hepatic veins. From this it will be seen that the blood of the portal system passes through two sets of minute vessels, viz., (a) the capillaries of the digestive tube, spleen, pancreas, and gall-bladder; and (b) the sinusoids of the liver. In the adult the portal vein and its tributaries are destitute of valves; in the fetus and for a short time after birth valves can be demonstrated in the tributaries of the portal vein; as a rule they soon atrophy and disappear, but in some subjects they persist in a degenerate form.

The **portal vein** (*vena portae*) is about 8 cm. in length, and is formed at the level of the second lumbar vertebra by the junction of the superior mesenteric and lienal veins, the union of these veins taking place in front of the inferior vena cava and behind the neck of the pancreas. It passes upward behind the superior part of the duodenum and then ascends in the right border of the lesser omentum to the right extremity of the porta hepatis, where it divides into a right and a left branch, which accompany the corresponding branches of the hepatic artery into the substance of the liver. In the lesser omentum it is placed behind and between the common bile duct and the hepatic artery, the former lying to the right of the latter. It is surrounded by the hepatic plexus of nerves, and is accompanied by numerous lymphatic vessels and some lymph glands. The **right branch** of the portal vein enters the right lobe of the liver, but before doing so generally receives the cystic vein. The **left branch**, longer but of smaller calibre than the right, crosses the left

sagittal fossa, gives branches to the caudate lobe, and then enters the left lobe of the liver. As it crosses the left sagittal fossa it is joined in front by a fibrous cord, the **ligamentum teres** (*obliterated umbilical vein*), and is united to the inferior vena cava by a second fibrous cord, the **ligamentum venosum** (*obliterated ductus venosus*).




FIG. 651.—The portal vein and its tributaries.

**Tributaries.**—The tributaries of the portal vein are:

Lienal.	Pyloric.
Superior Mesenteric.	Cystic.
Coronary.	Parumbilical.

The **Lienal Vein** (*v. lienalis; splenic vein*) commences by five or six large branches which return the blood from the spleen. These unite to form a single vessel, which passes from left to right, grooving the upper and back part of the pancreas, below the lineal artery, and ends behind the neck of the pancreas by uniting at a right angle with the superior mesenteric to form the portal vein. The lienal vein is of large size, but is not tortuous like the artery.

**Tributaries.**—The lienal vein receives the short gastric veins, the left gastroepiploic vein, the pancreatic veins, and the inferior mesenteric veins.

The **short gastric veins** (*vv. gastricae breves*), four or five in number, drain the fundus and left part of the greater curvature of the stomach, and pass between the two layers of the gastrolial ligament to end in the lienal vein or in one of its large tributaries.

The **left gastroepiploic vein** (*v. gastroepiploica sinistra*) receives branches from the antero-superior and postero-inferior surfaces of the stomach and from the greater omentum; it runs from right to left along the greater curvature of the stomach and ends in the commencement of the lienal vein.

The **pancreatic veins** (*vv. pancreaticae*) consist of several small vessels which drain the body and tail of the pancreas, and open into the trunk of the lienal vein.

The **inferior mesenteric vein** (*v. mesenterica inferior*) returns blood from the rectum and the sigmoid, and descending parts of the colon. It begins in the rectum as the **superior hemorrhoidal vein**, which has its origin in the hemorrhoidal plexus, and through this plexus communicates with the middle and inferior hemorrhoidal veins. The superior hemorrhoidal vein leaves the lesser pelvis and crosses the left common iliac vessels with the superior hemorrhoidal artery, and is continued upward as the inferior mesenteric vein. This vein lies to the left of its artery, and ascends behind the peritoneum and in front of the left Psoas major; it then passes behind the body of the pancreas and opens into the lienal vein; sometimes it ends in the angle of union of the lienal and superior mesenteric veins.

**Tributaries.**—The inferior mesenteric vein receives the **sigmoid veins** from the sigmoid colon and iliac colon, and the **left colic vein** from the descending colon and left colic flexure.

The **Superior Mesenteric Vein** (*v. mesenterica superior*) returns the blood from the small intestine, from the cecum, and from the ascending and transverse portions of the colon. It begins in the right iliac fossa by the union of the veins which drain the terminal part of the ileum, the cecum, and vermiform process, and ascends between the two layers of the mesentery on the right side of the superior mesenteric artery. In its upward course it passes in front of the right ureter, the inferior vena cava, the inferior part of the duodenum, and the lower portion of the head of the pancreas. Behind the neck of the pancreas it unites with the lienal vein to form the portal vein.

**Tributaries.**—Besides the tributaries which correspond with the branches of the superior mesenteric artery, viz., the **intestinal, ileocolic, right colic, and middle colic veins**, the superior mesenteric vein is joined by the right gastroepiploic and pancreaticoduodenal veins.

The **right gastroepiploic vein** (*v. gastroepiploica dextra*) receives branches from the greater omentum and from the lower parts of the antero-superior and postero-inferior surfaces of the stomach; it runs from left to right along the greater curvature of the stomach between the two layers of the greater omentum.

The **pancreaticoduodenal veins** (*vv. pancreaticoduodenales*) accompany their corresponding arteries; the lower of the two frequently joins the right gastroepiploic vein.

The **Coronary Vein** (*v. coronaria ventriculi; gastric vein*) derives tributaries from both surfaces of the stomach; it runs from right to left along the lesser curvature of the stomach, between the two layers of the lesser omentum, to the oesophageal opening of the stomach, where it receives some oesophageal veins. It then turns backward and passes from left to right behind the omental bursa and ends in the portal vein.

The **Pyloric Vein** is of small size, and runs from left to right along the pyloric portion of the lesser curvature of the stomach, between the two layers of the lesser omentum, to end in the portal vein.

The **Cystic Vein** (*v. cystica*) drains the blood from the gall-bladder, and, accompanying the cystic duct, usually ends in the right branch of the portal vein.

**Parumbilical Veins** (*vv. parumbilicales*).—In the course of the ligamentum teres of the liver and of the middle umbilical ligament, small veins (*parumbilical*) are found which establish an anastomosis between the veins of the anterior abdominal wall and the portal, hypogastric, and iliac veins. The best marked of these small veins is one which commences at the umbilicus and runs backward and upward in, or on the surface of, the ligamentum teres between the layers of the falciform ligament to end in the left portal vein.

**Applied Anatomy.**—Obstruction to the portal vein may produce ascites, and this may arise from many causes: as (1) the pressure of a tumor on the portal vein, such as cancer or hydatid cyst in the liver, enlarged lymph glands in the lesser omentum, or cancer of the head of the pancreas; (2) from cirrhosis of the liver, when the radicles of the portal vein are pressed upon by the contracting fibrous tissue in the portal canals; (3) from valvular disease of the heart, and back pressure on the hepatic veins, and so on the whole of the circulation through the liver. In this condition the prognosis as regards life and freedom from ascites may be much improved by the establishment of a good collateral venous circulation to relieve the portal obstruction in the liver. This is effected by communications between (*a*) the gastric veins and the œsophageal veins which often project as a varicose bunch into the stomach, emptying themselves into the hemiazygos vein; (*b*) the veins of the colon and duodenum and the left renal vein; (*c*) the accessory portal system of Sappey, branches of which pass in the round and falciform ligaments (particularly the latter) to unite with the epigastric and internal mammary veins, and through the diaphragmatic veins with the azygos; a single large vein, shown to be a parumbilical vein, may pass from the hilus of the liver by the round ligament to the umbilicus, producing there a bunch of prominent varicose veins known as the *caput medusae*; (*d*) the veins of Retzius, which connect the intestinal veins with the inferior vena cava and its retroperitoneal branches; (*e*) the inferior mesenteric veins, and the hemorrhoidal veins that open into the hypogastriacs; (*f*) very rarely the ductus venosus remains patent, affording a direct connection between the portal vein and the inferior vena cava.

An operation for the relief of portal obstruction on these lines has been advocated by Rutherford Morison and by Talma. It consists in curetting the opposed surfaces of the liver and Diaphragma and stitching them together, so as to secure vascular inflammatory adhesions between the two. The greater omentum may with advantage be interposed between them, so as to increase the amount of the adhesions, and the spleen has been similarly scraped and sutured to or into the abdominal wall. The operation should not be deferred until the patient is moribund.

Thrombosis of the portal vein, or pylethrombosis, is a very serious event, and is oftenest due to pathological processes causing compression of the vessel or injury to its wall, such as tumors or inflammation about the pylorus, head of the pancreas, or vermiform process, or to gall-stones, or cirrhosis of the liver. If the thrombus is infected with bacteria, as is often the case when it is due to appendicitis, septic or suppurative pylephlebitis results; this condition is known also as *portal pyemia*. Fragments of the infected clot break off and are carried away to lodge in the smaller veins in the liver, with the development of multiple abscesses in its substance and a rapidly fatal result. When the thrombus is sterile, the chief signs produced are enlargement of the spleen, recurrent ascites, and the establishment of a collateral venous circulation, the case clinically resembling one of atrophic cirrhosis of the liver.

The symptoms of thrombosis of the mesenteric veins are very much the same as those of embolism of the mesenteric arteries (see p. 696).



## THE LYMPHATIC SYSTEM.

---

**T**HE lymphatic system includes the lymphatic vessels and lymph glands. The lymphatic vessels of the small intestine receive the special designation of **lacteals** or **chyliferous vessels**; they differ in no respect from the lymphatic vessels generally excepting that during the process of digestion they contain a milk-white fluid, the **chyle**.

The lymphatic vessels are exceedingly delicate, and their coats are so transparent that the fluid they contain is readily seen through them. They are interrupted at intervals by constrictions, which give them a knotted or beaded appearance; these constrictions correspond to the situations of valves in their interior. Lymphatic vessels have been found in nearly every texture and organ of the body which contains bloodvessels. Such non-vascular structures as cartilage, the nails, cuticle, and hair have none, but these with exceptions it is probable that eventually all parts will be found to be permeated by these vessels.

**Structure of Lymphatic Vessels.**—The larger lymphatic vessels are each composed of three coats. The *internal* coat is thin, transparent, slightly elastic, and consists of a layer of elongated endothelial cells with wavy margins by which the contiguous cells are dovetailed into one another; the cells are supported on an elastic membrane. The *middle* coat is composed of smooth muscular and fine elastic fibres, disposed in a transverse direction. The *external* coat consists of connective tissue, intermixed with smooth muscular fibres longitudinally or obliquely disposed; it forms a protective covering to the other coats, and serves to connect the vessel with the neighboring structures. In the smaller vessels there are no muscular or elastic fibres, and the wall consists only of a connective-tissue coat, lined by endothelium. The thoracic duct has a more complex structure than the other lymphatic vessels; it presents a distinct subendothelial layer of branched corpuscles, similar to that found in the arteries; in the middle coat there is, in addition to the muscular and elastic fibres, a layer of connective tissue with its fibres arranged longitudinally. The lymphatic vessels are supplied by nutrient vessels, which are distributed to their outer and middle coats; and here also have been traced many non-medullated nerves in the form of a fine plexus of fibrils.

The valves of the lymphatic vessels are formed of thin layers of fibrous tissue covered on both surfaces by endothelium which presents the same arrangement as on the valves of veins (p. 599). In form the valves are semilunar; they are attached by their convex edges to the wall of the vessel, the concave edges being free and directed along the course of the contained current. Usually two such valves, of equal size, are found opposite one another; but occasionally exceptions occur, especially at or near the anastomoses of lymphatic vessels. Thus, one valve may be of small size and the other increased in proportion.

In the lymphatic vessels the valves are placed at much shorter intervals than in the veins. They are most numerous near the lymph glands, and are found more frequently in the lymphatic vessels of the neck and upper extremity than in those of the lower extremity. The wall of the lymphatic vessel immediately above the point of attachment of each segment of a valve is expanded into a pouch or sinus which gives to these vessels, when distended, the knotted or beaded appearance already referred to. Valves are wanting in the vessels composing the plexiform net-work in which the lymphatic vessels usually originate on the surface of the body.

The **lymph glands** (*lymphoglandulae*) are small oval or bean-shaped bodies, situated in the course of lymphatic and lacteal vessels so that the lymph and chyle pass through them on their way to the blood. Each generally presents on one side a slight depression—the **hilus**—through which the bloodvessels enter and leave the interior. The efferent lymphatic vessel also emerges from the gland at this spot, while the afferent vessels enter the organ at different parts of the periphery. On section (Fig. 652) a lymph gland displays two different structures: an external,

of lighter color—the **cortical**; and an internal, darker—the **medullary**. The cortical structure does not form a complete investment, but is deficient at the hilum, where the medullary portion reaches the surface of the gland; so that the efferent vessel is derived directly from the medullary structures, while the afferent vessels empty themselves into the cortical substance.




FIG. 652.—Section of small lymph gland of rabbit.  $\times 100$ .

**Structure of Lymph Glands.**—A lymph gland consists of (1) a fibrous envelope, or **capsule**, from which a frame-work of processes (*trabeculae*) proceeds inward, imperfectly dividing the gland into open spaces freely communicating with each other; (2) a quantity of lymphoid tissue occupying these spaces without completely filling them; (3) a free supply of bloodvessels, which




FIG. 653.—Lymph gland tissue. Highly magnified. *a*, Trabeculae. *b*, Small artery in substance of same. *c*, Lymph paths. *d*, Lymph corpuscles. *e*, Capillary plexus.

are supported in the trabeculae; and (4) the **afferent** and **efferent vessels** communicating through the lymph paths in the substance of the gland. The nerves passing into the hilus are few in number and are chiefly distributed to the bloodvessels supplying the gland.

The **capsule** is composed of connective tissue with some plain muscle fibres, and from its internal surface are given off a number of membranous processes or trabeculae, consisting, in man, of connective tissue, with a small admixture of plain muscle fibres; but in many of the lower animals composed almost entirely of involuntary muscle. They pass inward, radiating toward the centre

of the gland, for a certain distance—that is to say, for about one-third or one-fourth of the space between the circumference and the centre of the gland. In some animals they are sufficiently well-marked to divide the peripheral or cortical portion of the gland into a number of compartments (so-called follicles), but in man this arrangement is not obvious. The larger trabeculae springing from the capsule break up into finer bands, and these interlace to form a mesh-work in the central or medullary portion of the gland. In these spaces formed by the interlacing trabeculae is contained the proper gland substance or lymphoid tissue. The gland pulp does not, however, completely fill the spaces, but leaves, between its outer margin and the enclosing trabeculae, a channel or space of uniform width throughout. This is termed the **lymph path** or **lymph sinus** (Fig. 652). Running across it are a number of finer trabeculae of retiform connective tissue, the fibres of which are, for the most part, covered by ramifying cells.

On account of the peculiar arrangement of the frame-work of the organ, the gland pulp in the cortical portion is disposed in the form of nodules, and in the medullary part in the form of rounded cords. It consists of ordinary lymphoid tissue (Fig. 653), being made up of a delicate net-work of retiform tissue, which is continuous with that in the lymph paths, but marked off from it by a closer reticulation; it is probable, moreover, that the reticular tissue of the gland pulp and the lymph paths is continuous with that of the trabeculae, and ultimately with that of the capsule of the gland. In its meshes, in the nodules and cords of lymphoid tissue, are closely packed lymph corpuscles. The gland pulp is traversed by a dense plexus of capillary bloodvessels. The nodules or follicles in the cortical portion of the gland frequently show, in their centres, areas where karyokinetic figures indicate a division of the lymph corpuscles. These areas are termed **germ centres**. The cells composing them have more abundant protoplasm than the peripheral cells.

The **afferent vessels**, as stated above, enter at all parts of the periphery of the gland, and after branching and forming a dense plexus in the substance of the capsule, open into the lymph sinuses of the cortical part. In doing this they lose all their coats except their endothelial lining, which is continuous with a layer of similar cells lining the lymph paths. In like manner the **efferent vessel** commences from the lymph sinuses of the medullary portion. The stream of lymph carried to the gland by the afferent vessels thus passes through the plexus in the capsule to the lymph paths of the cortical portion, where it is exposed to the action of the gland pulp; flowing through these it enters the paths or sinuses of the medullary portion, and finally emerges from the hilus by means of the efferent vessel. The stream of lymph in its passage through the lymph sinuses is much retarded by the presence of the reticulum, hence morphological elements, either normal or morbid, are easily arrested and deposited in the sinuses. Many lymph corpuscles pass with the efferent lymph stream to join the general blood stream. The arteries of the gland enter at the hilus, and either go at once to the gland pulp, to break up into a capillary plexus, or else run along the trabeculae, partly to supply them and partly running across the lymph paths, to assist in forming the capillary plexus of the gland pulp. This plexus traverses the lymphoid tissue, but does not enter into the lymph sinuses. From it the veins commence and emerge from the organ at the same place as that at which the arteries enter.

The lymphatic vessels are arranged into a **superficial** and a **deep set**. On the surface of the body the **superficial** lymphatic vessels are placed immediately beneath the integument, accompanying the superficial veins; they join the deep lymphatic vessels in certain situations by perforating the deep fascia. In the interior of the body they lie in the submucous areolar tissue, throughout the whole length of the digestive, respiratory, and genito-urinary tracts; and in the subserous tissue of the thoracic and abdominal walls. Plexiform networks of minute lymphatic vessels are found interspersed among the proper elements and bloodvessels of the several tissues; the vessels composing the net-work, as well as the meshes between them, are much larger than those of the capillary plexus. From these net-works small vessels emerge, which pass, either to a neighboring gland, or to join some larger lymphatic trunk. The **deep** lymphatic vessels, fewer in number, but larger than the superficial, accompany the deep bloodvessels. Their mode of origin is probably similar to that of the superficial vessels. The lymphatic vessels of any part or organ exceed the veins in number, but in size they are much smaller. Their anastomoses also, especially those of the large trunks, are more frequent, and are effected by vessels equal in diameter to those which they connect, the continuous trunks retaining the same diameter.

**Applied Anatomy.**—The lymphatic channels and lymph glands draining any infected area of the body are very liable to become infected, resulting in acute or chronic lymphangitis and lymphadenitis. In acute cases the paths of the superficial lymphatic vessels are often marked

out on the skin by pain, redness, heat, and swelling, while the glands swell and may suppurate. Chronic inflammation leads to growth and fibrosis of the lymphatic vessels and the connective tissue around them; obstruction to the passage of the lymph results, as the fibrous tissue contracts and causes stenosis or obliteration of the lymphatic channels, and hard oedema of the involved skin and subcutaneous tissues follows (*pachydermia lymphangiectatica*). Chronic lymphangitis, together with the blocking of numerous lymphatic vessels by the escaped ova of the minute parasitic worm *Microfilaria nocturna*, is the cause of elephantiasis, a condition common in the tropics and subtropics, and characterized by enormous enlargement and thickening of the integuments of some part of the body, most frequently of the leg. Tubercular and syphilitic enlargements of the lymphatic vessels and glands are both very commonly met with. Primary tumors of the lymphatic vessels are lymphangioma and endothelioma; the so-called "congenital cystic hygroma" of the neck, arm, trunk, or thigh, is a cystic lymphangioma. Primary tumors of the lymph glands may be innocent (lymphadenoma, myxoma, chondroma) or malignant (lymphosarcoma); cancer is never met with as a primary affection, but is extremely common secondarily to cancer of some other part of the body.

The appearance of secondary malignant deposits or of secondary infection in parts of the body that seem not to be directly associated by any lymphatic connection with the seat of the primary growth or infection has often been observed, and explained as due to "retrograde transport" of cancer cells or bacteria by a reversed flow of lymph. Weleminsky,<sup>1</sup> however, believes that the explanation is to be found in the fact that when the infected glands have grown to a certain size they no longer permit the normal flow of lymph through them, and that under these circumstances very delicate lymphatic connections, whose existence normally remains unsuspected, develop to a surprising extent between groups of lymph glands that at first sight appear to be unconnected with one another.

### THE THORACIC DUCT.

The **thoracic duct** (*ductus thoracicus*) (Fig. 654) conveys the greater part of the lymph and chyle into the blood. It is the common trunk of all the lymphatic vessels of the body, excepting those on the right side of the head, neck, and thorax, and right upper extremity, the right lung, right side of the heart, and the convex surface of the liver. In the adult it varies in length from 38 to 45 cm. and extends from the second lumbar vertebra to the root of the neck. It begins in the abdomen by a triangular dilatation, the **cisterna chyli**, which is situated on the front of the body of the second lumbar vertebra, to the right side of and behind the aorta, by the side of the right crus of the Diaphragma. It enters the thorax through the aortic hiatus of the Diaphragma, and ascends through the posterior mediastinal cavity between the aorta and azygos vein. Behind it in this region are the vertebral column, the right intercostal arteries, and the hemiazygos veins as they cross to open into the azygos vein; in front of it are the Diaphragma, oesophagus, and pericardium, the last being separated from it by a recess of the right pleural cavity. Opposite the fifth thoracic vertebra, it inclines toward the left side, enters the superior mediastinal cavity, and ascends behind the aortic arch and the thoracic part of the left subclavian artery and between the left side of the oesophagus and the left pleura, to the upper orifice of the thorax. Passing into the neck it forms an arch which rises about 3 or 4 cm. above the clavicle and crosses anterior to the subclavian artery, the vertebral artery and vein, and the thyrocervical trunk or its branches. It also passes in front of the phrenic nerve and the medial border of the Scalenus anterior, but is separated from these two structures by the pre-vertebral fascia. In front of it are the left common carotid artery, vagus nerve, and internal jugular vein; it ends by opening into the angle of junction of the left subclavian vein with the left internal jugular vein. The thoracic duct, at its commencement, is about equal in diameter to a goose-quill, but it diminishes considerably in calibre in the middle of the thorax, and is again dilated just before its termination. It is generally flexuous, and constricted at intervals so as to present a varicose appearance. Not infrequently it divides in the middle of its course into two vessels of unequal size which soon reunite, or into several branches which form

<sup>1</sup> Berliner klin. Woch., 1905, No. 24, p. 743.

a plexiform interlacement. It occasionally divides at its upper part into two branches, right and left; the left ending in the usual manner, while the right opens into the right subclavian vein, in connection with the right lymphatic duct. The thoracic duct has several valves; at its termination it is provided with a pair, the free borders of which are turned toward the vein, so as to prevent the passage of venous blood into the duct.

The **cisterna chyli** (*receptaculum chyli*) (Fig. 655) receives the two lumbar lymphatic trunks, right and left, and the intestinal lymphatic trunk. The **lumbar trunks** are formed by the union of the efferent vessels from the lateral aortic lymph glands. They receive the lymph from the lower limbs, from the walls and viscera of the pelvis, from the kidneys and suprarenal glands and the deep lymphatics of the greater part of the abdominal wall. The **intestinal trunk** receives the lymph from the stomach and intestine, from the pancreas and spleen, and from the lower and front part of the liver.

**Tributaries.**—Opening into the commencement of the thoracic duct, on either side, is a descending trunk from the posterior intercostal lymph glands of the lower six or seven intercostal spaces. In the thorax the duct is joined, on either side, by a trunk which drains the upper lumbar lymph glands and pierces the crus of the Diaphragm. It also receives the efferents from the posterior mediastinal lymph glands and from the posterior intercostal lymph glands of the upper six left spaces. In the neck it is joined by the **left jugular** and **left subclavian trunks**, and sometimes by the **left broncho-mediastinal trunk**; the last-named, however, usually opens independently into the junction of the left subclavian and internal jugular veins.




FIG. 654.—The thoracic and right lymphatic ducts.

The **right lymphatic duct** (*ductus lymphaticus dexter*) (Fig. 656), about 1.25 cm. in length, courses along the medial border of the Scalenus anterior at the root of the neck and ends in the right subclavian vein, at its angle of junction with the right internal jugular vein. Its orifice is guarded by two semilunar valves, which prevent the passage of venous blood into the duct.



**Tributaries.**—The right lymphatic duct receives the lymph from the right side of the head and neck through the **right jugular trunk**; from the right upper extremity through the **right subclavian trunk**; from the right side of the thorax, right lung, right side of the heart, and part of the convex surface of the liver, through the **right bronchomediastinal trunk**. These three collecting trunks frequently open separately in the angle of union of the two veins.




FIG. 655.—Modes of origin of thoracic duct. (Poirier and Charpy.) a. Thoracic duct. a'. Cisterna chyli. Effluent trunks from lateral aortic glands. d. An efferent vessel which pierces the left crus of the diaphragm. Lateral aortic glands. h. Retroaortic glands. i. Intestinal trunk. f. Descending branch from intercostal lymphatics.

**Applied Anatomy.**—Blockage of the thoracic duct by mature specimens of the minute parasite *Microfilaria nocturna* gives rise to stasis of the chyle, and to its passage in various abnormal directions on its course past the obstruction. The neighboring abdominal, renal, and pelvic lymphatics become enlarged, varicose, and tortuous, and chyle may make its way into the urine (*chyluria*), the tunica vaginalis (*chylocele*), the abdominal cavity (*chylous ascites*), or the pleural cavity (*chylous pleural effusion*), in consequence of rupture of some of these distended lymphatic vessels.




FIG. 656.—Termination of the collecting trunks of the thoracic duct. (Poirier and Charpy.) a. Jugular trunk. b. Subclavian trunk. c. Bronchomediastinal trunk. d. Right lymphatic trunk. e. Trunk of internal mammary chain. f. Junction of thoracic duct with venous system.

The thoracic duct may be secondarily infected in interstitial or pulmonary tuberculosis, may contain caseating tubercles, caseating tuberculous masses, or even tuberculous concretions. It is often the seat of secondary carcinomatous deposits in cases of cancer of some abdominal viscus, becoming infiltrated throughout until it becomes a stiff, moniliform rod as thick as a pin, with multiple stenoses and dilatations of its lumen; in such cases the left supraclavicular gland often becomes infected and enlarged, while the lungs remain entirely free from secondary growths.

substitutions in the course of the lymphatic vessels of the thorax. The lymphatic vessels of the plexus are much

## THE LYMPHATICS OF THE HEAD, FACE, AND NECK.

### The Lymph Glands of the Head (Fig. 657).

The lymph glands of the head are arranged in the following groups:

Occipital.  
Posterior Auricular.  
Anterior Auricular.  
Parotid.

Facial.  
Deep Facial.  
Lingual.  
Retropharyngeal.




FIG. 657.—Superficial lymph glands and lymphatic vessels of head and neck.

The occipital glands (*lymphoglandulae occipitales*), one to three in number, are situated on the back of the head close to the margin of the Trapezius and resting on the insertion of the Semispinalis capitis. Their afferent vessels drain the occipital region of the scalp, while their efferents pass to the superior deep cervical glands.

The posterior auricular glands (*lymphoglandulae auriculares; mastoid glands*), only two in number, are situated on the mastoid insertion of the Sternocleidomastoid muscle, the Auricularis posterior. Their afferent vessels drain the posterior auricular region, the superficial blood into the duct.



of the auricula or pinna, and the back of the external acoustic meatus; their efferents pass to the superior deep cervical glands.

The **anterior auricular glands** (*lymphoglandulae auriculares anteriores*; superficial parotid or preauricular glands), from one to three in number, lie immediately in front of the tragus. Their afferents drain the lateral surface of the auricula and the skin of the adjacent part of the temporal region; their efferents pass to the superior deep cervical glands.

The **parotid glands** (*lymphoglandulae parotideae*), form two groups in relation with the parotid salivary gland, viz., a group imbedded in the substance of the gland and a group of subparotid glands lying on the lateral wall of the pharynx. Occasionally small glands are found in the subcutaneous tissue over the parotid gland. Their afferent vessels drain the root of the nose, the eyelids, the frontotemporal region, the external acoustic meatus and the tympanic cavity, possibly also the posterior parts of the palate and the floor of the nasal cavity. The efferents of these glands pass to the superior deep cervical glands. The afferents of the subparotid glands drain the nasal part of the pharynx and the posterior parts of the nasal cavities; their efferents pass to the superior deep cervical glands.




FIG. 658.—Lymphatics of pharynx. (Poirier and Charpy.)

The **facial glands** comprise three groups: (a) **infraorbital** or **maxillary**, scattered over the infraorbital region from the groove between the nose and cheek to the zygomatic arch; (b) **buccinator**, one or more placed on the Buccinator opposite the angle of the mouth; (c) **supramandibular**, on the outer surface of the mandible, in front of the Masseter and in contact with the external maxillary artery and anterior facial vein. Their efferent vessels drain the eyelids, the conjunctiva, and the skin and mucous membrane of the nose and cheek; their efferents pass to the submaxillary glands.

The **deep facial glands** (*lymphoglandulae faciales profunda*; internal maxillary glands) are placed beneath the ramus of the mandible, on the outer surface of the Pterygoideus externus, in relation to the internal maxillary artery. Their afferent vessels drain the temporal and infratemporal fossæ and the nasal part of the pharynx; their efferents pass to the superior deep cervical glands.

The **lingual glands** (*lymphoglandulae linguales*) are two or three small nodules lying on the Hyoglossus and under the Genioglossus. They form merely glandular substations in the course of the lymphatic vessels of the tongue.

The **retropharyngeal glands** (Fig. 658), from one to three in number, lie in the buccopharyngeal fascia, behind the upper part of the pharynx and in front of the arch of the atlas, being separated, however, from the latter by the Longus capitis. Their afferents drain the nasal cavities, the nasal part of the pharynx, and the auditory tubes; their efferents pass to the superior deep cervical glands.

**T** The **lymphatic vessels of the scalp** are divisible into (a) those of the frontal region, which terminate in the anterior auricular and parotid glands; (b) those of the temporoparietal region, which end in the parotid and posterior auricular glands; and (c) those of the occipital region, which terminate partly in the occipital glands and partly in a trunk which runs down along the posterior border of the Sternocleidomastoideus to end in the inferior deep cervical glands.

The **lymphatic vessels of the auricle and external acoustic meatus** are also divisible into three groups: (a) an anterior, from the lateral surface of the auricle and anterior wall of the meatus to the anterior auricular glands; (b) a posterior, from the margin of the auricle, the upper part of its cranial surface, the internal surface and posterior wall of the meatus to the posterior auricular and superior deep cervical glands; (c) an inferior, from the floor of the meatus and from the lobule of the auricle to the superficial and superior deep cervical glands.




FIG. 659.—The lymphatics of the face. (After Küttner.)

The **lymphatic vessels of the face** (Fig. 659) are more numerous than those of the scalp. Those from the eyelids and conjunctiva terminate partly in the submaxillary but mainly in the parotid glands. The vessels from the posterior part of the cheek also pass to the parotid glands, while those from the anterior portion of the cheek, the side of the nose, the upper lip, and the lateral portions of the lower lip end in the submaxillary glands. The deeper vessels from the temporal and infratemporal fossæ pass to the deep facial and superior deep cervical glands. The deeper vessels of the cheek and lips end, like the superficial, in the submaxillary glands. Both isuperficial and deep vessels of the central part of the lower lip run to the submental glands.

**int** The **lymphatic vessels of the nasal cavities** can be injected from the subdural the subar cavities. Those from the anterior parts of the nasal cavities

communicate with the vessels of the integument of the nose and end in the submaxillary glands; those from the posterior two-thirds of the nasal cavities and from the accessory air sinuses pass partly to the retropharyngeal and partly to the superior deep cervical glands.

**Lymphatic Vessels of the Mouth.**—The vessels of the gums pass to the submaxillary glands; those of the hard plate are continuous in front with those of the upper gum, but pass backward to pierce the Constrictor pharyngis superior and end in the superior deep cervical and subparotid glands; those of the soft palate pass backward and lateralward and end partly in the retropharyngeal and subparotid, and partly in the superior deep cervical glands. The vessels of the anterior part of the floor of the mouth pass either directly to the inferior glands of the superior deep cervical group, or indirectly through the submental glands; from the rest of the floor of the mouth the vessels pass to the submaxillary and superior deep cervical glands.




FIG. 660.—Lymphatics of the tongue. (Poirier.)

The **lymphatic vessels of the palatine tonsil**, usually three to five in number, pierce the buccopharyngeal fascia and constrictor pharyngis superior and pass between the Stylohyoideus and internal jugular vein to the uppermost of the superior deep cervical glands. They end in a gland which lies at the side of the posterior belly of the Digastricus, on the internal jugular vein; occasionally one or two additional vessels run to small glands on the lateral side of the cover of the Sternocleidomastoideus.



The **lymphatic vessels of the tongue** (Fig. 660) are drained chiefly into the deep cervical glands lying between the posterior belly of the Digastricus and the superior belly of the Omohyoideus; one gland situated at the bifurcation of the common carotid artery is so intimately associated with these vessels that it is known as the **principal gland of the tongue**. The lymphatic vessels of the tongue may be divided into four groups: (1) apical, from the tip of the tongue to the suprahyoid glands and principal gland of the tongue; (2) lateral, from the margin of the tongue—some of these pierce the Mylohyoideus to end in the submaxillary glands, others pass down on the Hyoglossus to the superior deep cervical glands; (3) basal, from the region of the papillae vallatae to the superior deep cervical glands; and (4) median, a few of which perforate the Mylohyoideus to reach the submaxillary glands, while the majority turn around the posterior border of the muscle to enter the superior deep cervical glands.

### The Lymph Glands of the Neck.

The lymph glands of the neck include the following groups:

Submaxillary.  
Submental.

Superficial Cervical.  
Anterior Cervical.

Deep Cervical.

The **submaxillary glands** (*lymphoglandulae submaxillares*) (Fig. 659), three to six in number, are placed beneath the body of the mandible in the submaxillary triangle, and rest on the superficial surface of the submaxillary salivary gland. One gland, the **middle gland of Stahr**, which lies on the external maxillary artery as it turns over the mandible, is the most constant of the series; small lymph glands are sometimes found on the deep surface of the submaxillary salivary glands. The afferents of the submaxillary glands drain the medial palpebral commissure, the cheek, the side of the nose, the upper lip, the lateral part of the lower lip, the gums, and the anterior part of the margin of the tongue; efferent vessels from the facial and submental glands also enter the submaxillary glands. Their efferent vessels pass to the superior deep cervical glands.

The **submental or suprahyoid glands** are situated between the anterior bellies of the Digastrici. Their afferents drain the central portions of the lower lip and floor of the mouth and the apex of the tongue; their efferents pass partly to the submaxillary glands and partly to a gland of the deep cervical group situated on the internal jugular vein at the level of the cricoid cartilage.

The **superficial cervical glands** (*lymphoglandulae cervicales superficiales*) lie in close relationship with the external jugular vein as it emerges from the parotid gland, and, therefore, superficial to the Sternocleidomastoideus. Their afferents drain the lower parts of the auricula and parotid region, while their efferents pass around the anterior margin of the Sternocleidomastoideus to join the superior deep cervical glands.

The **anterior cervical glands** form an irregular and inconstant group on the front of the larynx and trachea. They may be divided into (a) a **superficial set**, placed on the anterior jugular vein; (b) a **deeper set**, which is further subdivided into prelaryngeal, on the middle cricothyroid ligament, and pretracheal, on the front of the trachea. This deeper set drains the lower part of the larynx, the thyroid gland, and the upper part of the trachea; its efferents pass to the lowest of the superior deep cervical glands.

The **deep cervical glands** (*lymphoglandulae cervicales profundae*) (Figs. 657, 658) are numerous and of large size: they form a chain along the carotid sheath, lying by the side of the larynx, oesophagus, and trachea, and extending from the base of the skull to the upper part of the neck. They are usually described in two groups: the **superior deep cervical glands**, which receive the lymph from the superficial and anterior cervical glands, and the **inferior deep cervical glands**, which receive the lymph from the superior deep cervical glands and the lymphatic vessels of the thorax.

(1) the **superior deep cervical glands** lying under the Sternocleidomastoideus in close relation with the accessory nerve and the internal jugular vein, some of the glands lying in front of and others behind the vessel; (2) the **inferior deep cervical glands** extending beyond the posterior margin of the Sternocleidomastoideus into the supraclavicular triangle, where they are closely related to the brachial plexus and subclavian vein. A few minute **paratracheal glands** are situated alongside the recurrent nerves on the lateral aspects of the trachea and œsophagus. The superior deep cervical glands drain the occipital portion of the scalp, the auricula, the back of the neck, a considerable part of the tongue, the larynx, thyroid gland, trachea, nasal part of the pharynx, nasal cavities, palate, and œsophagus. They receive also the efferent vessels from all the other glands of the head and neck, except those from the inferior deep cervical glands. The inferior deep cervical glands drain the back of the scalp and neck, the superficial pectoral region, part of the arm (see page 782), and, occasionally, part of the superior surface of the liver. In addition, they receive vessels from the superior deep cervical glands. The efferents of the superior deep cervical glands pass partly to the inferior deep cervical glands and partly to a trunk which unites with the efferent vessel of the inferior deep cervical glands and forms the **jugular trunk**. On the right side, this trunk ends in the junction of the internal jugular and subclavian veins; on the left side it joins the thoracic duct.

The **lymphatic vessels of the skin and muscles of the neck** pass to the deep cervical glands. From the upper part of the *pharynx* the lymphatic vessels pass to the retropharyngeal, from the lower part to the deep cervical glands. From the *larynx* two sets of vessels arise, an upper and a lower. The vessels of the upper set pierce the hyothyroid membrane and join the superior deep cervical glands. Of the lower set, some pierce the conus elasticus and join the pretracheal and prelaryngeal glands; others run between the cricoid and first tracheal ring and enter the inferior deep cervical glands. The lymphatic vessels of the *thyroid gland* consist of two sets, an upper, which accompanies the superior thyroid artery and joins the superior deep cervical glands, and a lower, which runs partly to the pretracheal glands and partly to the small paratracheal glands which accompany the recurrent nerves. These latter glands receive also the lymphatic vessels from the cervical portion of the trachea.

**Applied Anatomy.**—The cervical glands are very frequently the seat of tuberculous disease. This condition is most usually set up by some lesion in those parts from which they receive their lymph. It is very desirable therefore for the surgeon, in dealing with these cases, to possess a knowledge of the relation of the respective groups of glands to the periphery, while in order to eradicate them by operation a long and difficult dissection may be required.

## THE LYMPHATICS OF THE UPPER EXTREMITY.

### The Lymph Glands of the Upper Extremity (Fig. 661).

The lymph glands of the upper extremity are divided into two sets, **superficial** and **deep**.

The **superficial lymph glands** are few and of small size. One or two **supra-trochlear glands** are placed above the medial epicondyle of the humerus, medial to the basilic vein. Their afferents drain the middle, ring, and little fingers, the medial portion of the hand, and the superficial area over the ulnar side of the forearm; these vessels are, however, in free communication with the other lymphatic vessels of the forearm. Their efferents accompany the basilic vein to the deeper vessels. One or two **deltoideopectoral glands** are found between the Pectoralis major and Deltoideus, immediately lateral to the axilla, which everywhere pervades the skin; the meshes of the plexus

## ANGIOLOGY

**deep lymph glands** are chiefly grouped in the axilla, although a few may be found in the forearm, in the course of the radial, ulnar, and interosseous vessels, and in the arm along the medial side of the brachial artery.




FIG. 661.—The superficial lymph glands and lymphatic vessels of the upper extremity.

The **Axillary Glands** (*lymphoglandulae axillares*) (Fig. 662) are of large size, vary from twenty to thirty in number, and may be arranged in the following groups:

1. A **lateral group** of from four to six glands lies in relation to the medial and posterior aspects of the axillary vein; the afferents of these glands drain the whole arm with the exception of that portion whose vessels accompany the cephalic vein. The efferent vessels pass partly to the central and subclavicular groups of axillary glands and partly to the inferior deep cervical glands.

2. An **anterior or pectoral group** consists of four or five glands situated beneath the Pectoralis minor, in relation with the lateral thoracic vein. Their afferents drain the skin and muscles of the anterior thoracic wall, and the venous blood into the duct.

3. A **posterior or subscapular group** of six or seven glands is placed along the lower margin of the posterior wall of the axilla in the course of the subscapular artery. The afferents of this group drain the skin and muscles of the lower part of the back of the neck and of the posterior thoracic wall; their efferents pass to the central group of axillary glands.

4. A **central or intermediate group** of three or four large glands is imbedded in the adipose tissue near the base of the axilla. Its afferents are the efferent vessels of all the preceding groups of axillary glands; its efferents pass to the subclavicular group.




FIG. 662.—Lymphatics of the mamma, and the axillary glands (semidiagrammatic). (Poirier and Charpy.)

5. A **medial or subclavicular group** of six to twelve glands is situated partly posterior to the upper portion of the Pectoralis minor and partly above the upper border of this muscle. Its only direct territorial afferents are those which accompany the cephalic vein and one which drains the upper peripheral part of the mamma, but it receives the efferents of all the other axillary glands. The efferent vessels of the subclavicular group unite to form the **subclavian trunk**, which opens either directly into the junction of the internal jugular and subclavian veins or into the jugular lymphatic trunk; on the left side it may end in the thoracic duct. A few efferents from the subclavicular glands usually pass to the inferior deep cervical glands.

**Applied Anatomy.**—In malignant disease or infectious processes implicating the upper part of the back and shoulder, the front of the chest and mamma, the upper part of the front and side of the abdomen, or the hand, forearm, and arm, enlargement of the axillary glands is very often found.

### The Lymphatic Vessels of the Upper Extremity.

The lymphatic vessels of the upper extremity are divided into two sets, superficial and deep.

The **superficial lymphatic vessels** commence (Fig. 663) in the lymphatic plexus which everywhere pervades the skin; the meshes of the plexus are much finer in the

palm and on the flexor aspect of the digits than elsewhere. The digital plexuses are drained by a pair of vessels which run on the sides of each digit, and incline




FIG. 663.—Lymphatic vessels of the dorsal surface of the hand. (Sappey.)

backward to reach the dorsum of the hand. From the dense plexus of the palm, vessels pass in different directions, viz., upward toward the wrist, downward to join the digital vessels, medialward to join the vessels on the ulnar border of the hand, and lateralward to those on the thumb. Several vessels from the central part of the plexus unite to form a trunk, which passes around the metacarpal bone of the index finger to join the vessels on the back of that digit and on the back of the thumb. Running upward in front of and behind the wrist, the lymphatic vessels are collected into radial, median, and ulnar groups, which accompany respectively the cephalic, median, and basilic veins in the forearm. A few of the ulnar lymphatics end in the supratrochlear glands, but the majority pass directly to the lateral group of axillary glands. Some of the radial vessels are collected into a trunk which ascends with the cephalic vein to the deltoideopectoral glands; the efferents from this group pass either to the subclavicular axillary glands or to the inferior cervical glands.

The **deep lymphatic vessels** accompany the deep bloodvessels. In the forearm, they consist of four sets, corresponding with the radial, ulnar, volar, and dorsal interosseous arteries; they communicate at intervals with the superficial lymphatics, and some of them end in the glands which are occasionally found beside the arteries. In their course upward, a few end in the glands which lie upon the brachial artery; but most of them pass to the lateral group of axillary glands.

## THE LYMPHATICS OF THE LOWER EXTREMITY.

### The Lymph Glands of the Lower Extremity.

The lymph glands of the lower extremity consist of the **anterior tibial gland** and the **popliteal** and **inguinal glands**.

The **anterior tibial gland** (*lymphoglandula tibialis anterior*) is small and inconstant. It lies on the interosseous membrane in relation to the upper part of the anterior tibial vessels, and constitutes a substation in the course of the anterior tibial lymphatic trunks.

The **popliteal glands** (*lymphoglandulae popliteae*) (Fig. 664), small in size and some six or seven in number, are imbedded in the fat contained in the popliteal fossa. One lies immediately beneath the popliteal fascia, near the terminal part of the small saphenous vein, and drains the region from which this vein derives



its tributaries. Another is placed between the popliteal artery and the posterior surface of the knee-joint; it receives the lymphatic vessels from the knee-joint together with those which accompany the genicular arteries. The others lie at the sides of the popliteal vessels, and receive as efferents the trunks which accompany the anterior and posterior tibial vessels. The efferents of the popliteal glands pass almost entirely alongside the femoral vessels to the deep inguinal glands, but a few may accompany the great saphenous vein, and end in the glands of the superficial subinguinal group.

The **inguinal glands** (*lymphoglandulae inguinales*) (Fig. 665), from twelve to twenty in number, are situated at the upper part of the femoral triangle. They may be divided into two groups by a horizontal line at the level of the termination of the great saphenous vein; those lying above this line are termed the **superficial inguinal glands**, and those below it the **subinguinal glands**, the latter group consisting of a *superficial* and a *deep* set.




FIG. 664.—Lymph glands of popliteal fossa. (Poirier and Charpy.)

The **Superficial Inguinal Glands** form a chain immediately below the inguinal ligament. They receive as afferents lymphatic vessels from the integument of the penis, scrotum, perineum, buttock, and abdominal wall below the level of the umbilicus.

The **Superficial Subinguinal Glands** (*lymphoglandulae subinguinales superficiales*) are placed on either side of the upper part of the great saphenous vein; their efferents consist chiefly of the superficial lymphatic vessels of the lower extremity; but they also receive some of the vessels which drain the integument of the penis, scrotum, perineum, and buttock.

The **Deep Subinguinal Glands** (*lymphoglandulae subinguinales profundae*) vary from one to three in number, and are placed under the fascia lata, on the medial side of the femoral vein. When three are present, the lowest is situated just below the junction of the great saphenous and femoral veins, the middle in the femoral canal, and the highest in the lateral part of the femoral ring. The middle one is the most inconstant of the three, but the highest, the **gland of Cloquet** or **Rosenmüller**,




FIG. 665.—The superficial lymph glands and lymphatic vessels of the lower extremity.

is also frequently absent. They receive as afferents the deep lymphatic trunks which accompany the femoral vessels, the lymphatics from the glans penis vel clitoridis, and also some of the efferents from the superficial subinguinal glands.

**Applied Anatomy.**—Inflammation and supuration of the popliteal glands are most commonly due to a sore on the lateral side of the heel.

The inguinal and subinguinal glands frequently become enlarged in diseases implicating the parts from which their lymphatic vessels originate. Thus in malignant or syphilitic affections of the prepuce and penis, or labia majora, in cancer of the scrotum, in abscess in the perineum, or in similar diseases affecting the integument and superficial structures in those parts, or the subumbilical part of the abdominal wall, or the gluteal region, the upper group of glands is almost invariably enlarged, the lower groups being implicated in diseases affecting the lower limb.

### The Lymphatic Vessels of the Lower Extremity.

The lymphatic vessels of the lower extremity consist of two sets, superficial and deep, and in their distribution correspond closely with the veins.

The **superficial lymphatic vessels** lie in the superficial fascia, and are divisible into two groups: a medial, which follows the course of the great saphenous vein, and a lateral, which accompanies the small saphenous vein. The vessels of the **medial group** (Fig. 665) are larger and more numerous than those of the lateral group, and commence on the tibial side and dorsum of the foot; they ascend both in front of and behind the medial malleolus, run up the leg with the great saphenous vein, pass with it behind the medial condyle of the femur, and accompany it to the groin, where they end in the subinguinal group of superficial glands. The vessels of the **lateral group** arise from the fibular side of the foot; some ascend in front of the leg, and, just below the knee, cross the tibia to join the lymphatics on the medial side of the thigh; others pass behind the lateral malleolus, and, accompanying the small saphenous vein, enter the popliteal glands.

The **deep lymphatic vessels** are few in number, and accompany the deep bloodvessels. In the leg, they consist of three sets, the anterior tibial, posterior tibial, and peroneal, which accompany the corresponding bloodvessels, two or three with each artery; they enter the popliteal lymph glands.

The deep lymphatic vessels of the gluteal and ischial regions follow the course of the corresponding bloodvessels. Those accompanying the superior gluteal vessels end in a gland which lies on the intrapelvic portion of the superior gluteal artery near the upper border of the greater sciatic foramen. Those following the inferior gluteal vessels traverse one or two small glands which lie below the Piriformis muscle, and end in the hypogastric glands.




FIG. 666.—The parietal lymph glands of the pelvis. (Cunéo and Marcille.)

## THE LYMPHATICS OF THE ABDOMEN AND PELVIS.

### The Lymph Glands of the Abdomen and Pelvis.

The lymph glands of the abdomen and pelvis may be divided, from their situations, into (a) **parietal**, lying behind the peritoneum and in close association with the larger bloodvessels; and (b) **visceral**, which are found in relation to the visceral arteries.



The **parietal glands** (Figs. 666, 667) include the following groups:

External Iliac.	Iliac Circumflex.	Lumbar {	Lateral Aortic. Preaortic. Retroaortic.
Common Iliac.	Hypogastric.		
Epigastric.	Sacral.		

The **External Iliac Glands**, from eight to ten in number, lie along the external iliac vessels. They are arranged in three groups, one on the lateral, another on the medial, and a third on the anterior aspect of the vessels; the third group is, however, sometimes absent. Their principal afferents are derived from the inguinal and subinguinal glands, the deep lymphatics of the abdominal wall below the umbilicus and of the adductor region of the thigh, and the lymphatics from the glans penis vel clitoridis, the membranous urethra, the prostate, the fundus of the bladder, the cervix uteri, and upper part of the vagina.




FIG. 667.—Iliopelvic glands (lateral view). (Cunéo and Marcille.)

The **Common Iliac Glands**, four to six in number, are grouped behind and on the sides of the common iliac artery, one or two being placed below the bifurcation of the aorta, in front of the fifth lumbar vertebra. They drain chiefly the hypogastric and external iliac glands, and their efferents pass to the lateral aortic glands.

The **Epigastric Glands** (*lymphoglandulae epigastricae*), three or four in number, are placed alongside the lower portion of the inferior epigastric vessels.

The **Iliac Circumflex Glands**, two to four in number, are situated along the course of the deep iliac circumflex vessels; they are sometimes absent.

The **Hypogastric Glands** (*lymphoglandulae hypogastricae*; *internal iliac gland*) (Fig. 667) surround the hypogastric vessels, and receive the lymphatics corresponding to the distribution of the branches of the hypogastric artery, *i. e.*, they receive lymphatics from all the pelvic viscera, from the deeper parts of the perineum,

including the membranous and cavernous portions of the urethra, and from the buttock and back of the thigh. An **obturator gland** is sometimes seen in the upper part of the obturator foramen.

The **Sacral Glands** are placed in the concavity of the sacrum, in relation to the middle and lateral sacral arteries; they receive lymphatics from the rectum and posterior wall of the pelvis.

The efferents of the hypogastric group end in the common iliac glands.

The **Lumbar Glands** (*lymphoglandulae lumbales*) are very numerous, and consist of right and left lateral aortic, preaortic, and retroaortic groups.

The **right lateral aortic glands** are situated partly in front of the inferior vena cava, near the termination of the renal vein, and partly behind it on the origin of the Psoas major, and on the right crus of the Diaphragma. The **left lateral aortic glands** form a chain on the left side of the abdominal aorta in front of the origin of the Psoas major and left crus of the Diaphragma. The glands on either side receive (a) the efferents of the common iliac glands, (b) the lymphatics from the testis in the male and from the ovary, uterine tube, and body of the uterus in the female; (c) the lymphatics from the kidney and suprarenal gland; and (d) the lymphatics draining the lateral abdominal muscles and accompanying the lumbar veins. Most of the efferent vessels of the lateral aortic glands converge to form the **right and left lumbar trunks** which join the cisterna chyli, but some enter the pre- and retroaortic glands, and others pierce the crura of the Diaphragma to join the lower end of the thoracic duct. The **preaortic glands** lie in front of the aorta, and may be divided into **coeliac**, **superior mesenteric**, and **inferior mesenteric** groups, arranged around the origins of the corresponding arteries. They receive a few vessels from the lateral aortic glands, but their principal afferents are derived from the viscera supplied by the three arteries with which they are associated. Some of their efferents pass to the retroaortic glands, but the majority unite to form the **intestinal trunk**, which enters the cisterna chyli. The **retroaortic glands** are placed below the cisterna chyli, on the bodies of the third and fourth lumbar vertebræ. They receive lymphatic trunks from the lateral and preaortic glands, while their efferents end in the cisterna chyli.

### The Lymphatic Vessels of the Abdomen and Pelvis.

The lymphatic vessels of the walls of the abdomen and pelvis may be divided into two sets, superficial and deep.

The **superficial vessels** follow the course of the superficial bloodvessels and converge to the superficial inguinal glands; those derived from the integument of the front of the abdomen below the umbilicus follow the course of the superficial epigastric vessels, and those from the sides of the lumbar part of the abdominal wall pass along the crest of the ilium, with the superficial iliac circumflex vessels. The superficial lymphatic vessels of the gluteal region turn horizontally around the buttock, and join the superficial inguinal and subinguinal glands.

The **deep vessels** run alongside the principal bloodvessels. Those of the parietes of the pelvis, which accompany the superior and inferior gluteal, and obturator vessels, follow the course of the hypogastric artery, and ultimately join the lateral aortic glands.

**Lymphatic Vessels of the Perineum and External Genitals.**—The lymphatic vessels of the perineum, of the integument of the penis, and of the scrotum (or vulva), follow the course of the external pudendal vessels, and end in the superficial inguinal and subinguinal glands. Those of the glans penis vel clitoridis terminate partly in the deep subinguinal glands and partly in the external iliac glands.

The **visceral glands** are associated with the branches of the coeliac, superior



and inferior mesenteric arteries. Those related to the branches of the cœliac artery form three sets, gastric, hepatic, and pancreaticolienal.

The **Gastric Glands** (Figs. 668, 669) consist of two sets, superior and inferior.

The **Superior Gastric Glands** (*lymphoglandulae gastricae superiores*) accompany the left gastric artery and are divisible into three groups, viz.: (a) **upper**, on the stem of the artery; (b) **lower**, accompanying the descending branches of the artery along the cardiac half of the lesser curvature of the stomach, between the two layers of the lesser omentum; and (c) **paracardial** outlying members of the gastric glands, disposed in a manner comparable to a chain of beads around the neck of the stomach (Jamieson and Dobson<sup>1</sup>). They receive their afferents from the stomach; their efferents pass to the cœliac group of preaortic glands.




FIG. 668.—Lymphatics of stomach, etc. (Jamieson and Dobson.)

The **Inferior Gastric Glands** (*lymphoglandulae gastricae inferiores*; *right gastroepiploic gland*), four to seven in number, lie between the two layers of the greater omentum along the pyloric half of the greater curvature of the stomach, and may be regarded as an outlying group of the hepatic glands.

The **Hepatic Glands** (*lymphoglandulae hepaticae*) (Fig. 668), consist of the following groups: (a) **hepatic**, on the stem of the hepatic artery, and extending upward along the common bile duct, between the two layers of the lesser omentum, as far as the porta hepatis; the **cystic gland**, a member of this group, is placed near the neck of the gall-bladder; (b) **subpyloric**, four or five in number, in close relation to the bifurcation of the gastroduodenal artery, in the angle between the superior and descending parts of the duodenum; an outlying member of this group is sometimes found above the duodenum on the right gastric (pyloric) artery. The glands of the hepatic chain receive afferents from the stomach, duodenum, liver, gall-bladder, and pancreas; their efferents join the cœliac group of preaortic glands.

The **Pancreaticolienal Glands** (*lymphoglandulae pancreaticolienales*; *splenic glands*) (Fig. 669) accompany the lienal (splenic) artery, and are situated in relation to the posterior surface and upper border of the pancreas; one or two members

<sup>1</sup> Lancet, April 20 and 27, 1907.

of this group are found in the gastrolial ligament (Jamieson and Dobson, *op. cit.*). Their afferents are derived from the stomach, spleen, and pancreas, their efferents join the celiac group of preaortic glands.

The **superior mesenteric glands** may be divided into three principal groups: **mesenteric**, **ileocolic**, and **mesocolic**.

The **Mesenteric Glands** (*lymphoglandulae mesentericae*) lie between the layers of the mesentery. They vary from one hundred to one hundred and fifty in number, and may be grouped into three sets, viz.: one lying close to the wall of the small intestine, among the terminal twigs of the superior mesenteric artery; a second, in relation to the loops and primary branches of the vessels; and a third along the trunk of the artery.




FIG. 669.—Lymphatics of stomach, etc. The stomach has been turned upward. (Jamieson and Dobson.)

**Applied Anatomy.**—Enlargement of the mesenteric lymphatic glands is seen in most diseased conditions of the intestinal tract, and is well-marked in enteric fever, tuberculous ulceration or malignant growths of the bowel. The enlarged glands can often be palpated through the wall of the abdomen.

The **Ileocolic glands** (Figs. 670, 671), from ten to twenty in number, form a chain around the ileocolic artery, but show a tendency to subdivision into two groups, one near the duodenum and another on the lower part of the trunk of the artery. Where the vessel divides into its terminal branches the chain is broken up into several groups, viz.: (a) **ileal**, in relation to the ileal branch of the artery; (b) **anterior ileocolic**, usually of three glands, in the ileocolic fold, near the wall of the cecum; (c) **posterior ileocolic**, mostly placed in the angle between the ileum and the colon, but partly lying behind the cecum at its junction with the ascending colon; (d)

a single gland, between the layers of the mesenteriole of the vermiform process;  
 (e) **right colic**, along the medial side of the ascending colon.




FIG. 670.—The lymphatics of cecum and vermiform process from the front. (Jamieson and Dobson.)




FIG. 671.—The lymphatics of cecum and vermiform process from behind. (Jamieson and Dobson.)



The **Mesocolic Glands** (*lymphoglandulae mesocolicae*) are numerous, and lie between the layers of the transverse mesocolon, in close relation to the transverse colon; they are best developed in the neighborhood of the right and left colic flexures. One or two small glands are occasionally seen along the trunk of the right colic artery and others are found in relation to the trunk and branches of the middle colic artery.

The superior mesenteric glands receive afferents from the jejunum, ileum, cecum, vermiform process, and the ascending and transverse parts of the colon; their efferents pass to the preaortic glands.




FIG. 672.—Lymphatics of colon. (Jamieson and Dobson.)

The **inferior mesenteric glands** (Fig. 672) consist of: (a) small glands on the branches of the left colic and sigmoid arteries; (b) a group in the sigmoid mesocolon, around the superior hemorrhoidal artery; and (c) a **pararectal** group in contact with the muscular coat of the rectum. They drain the descending iliac and sigmoid parts of the colon and the upper part of the rectum; their efferents pass to the preaortic glands.

#### The Lymphatic Vessels of the Abdominal and Pelvic Viscera.

The lymphatic vessels of the abdominal and pelvic viscera consist of (1) those of the subdiaphragmatic portion of the digestive tube and its associated glands, the liver and pancreas; (2) those of the spleen and suprarenal glands; (3) those of the urinary organs; (4) those of the reproductive organs.

1. The **lymphatic vessels of the subdiaphragmatic portion of the digestive tube** are situated partly in the mucous membrane and partly in the seromuscular coats, but as the former system drains into the latter, the two may be considered as one.

The **Lymphatic Vessels of the Stomach** (Figs. 668, 669) are continuous at the cardiac orifice with those of the œsophagus, and at the pylorus with those of the duodenum. They mainly follow the bloodvessels, and may be arranged in four sets. Those of the first set accompany the branches of the left gastric artery, receiving tributaries from a large area on either surface of the stomach, and terminate in the superior gastric glands. Those of the second set drain the fundus and body of the stomach on the left of a line drawn vertically from the œsophagus; they accompany, more or less closely, the short gastric and left gastroepiploic arteries, and end in the pancreaticocolic glands. The vessels of the third set drain the right portion of the greater curvature as far as the pyloric portion, and end in the inferior gastric glands, the efferents of which pass to the subpyloric group. Those of the fourth set drain the pyloric portion and pass to the hepatic and subpyloric glands, and to the superior gastric glands.

The **Lymphatic Vessels of the Duodenum** consist of an anterior and a posterior set, which open into a series of small **pancreaticoduodenal glands** on the anterior and posterior aspects of the groove between the head of the pancreas and the duodenum. The efferents of these glands run in two directions, upward to the hepatic glands and downward to the preaortic glands around the origin of the superior mesenteric artery.

The **Lymphatic Vessels of the Jejunum and Ileum** are termed **lacteals**, from the milk-white fluid they contain during intestinal digestion. They run between the layers of the mesentery and enter the mesenteric glands, the efferents of which end in the preaortic glands.

The **Lymphatic Vessels of the Vermiform Process and Cecum** (Figs. 670, 671) are numerous, since in the wall of this process there is a large amount of adenoid tissue. From the body and tail of the vermiform process eight to fifteen vessels ascend between the layers of the mesenteriole, one or two being interrupted in the gland which lies between the layers of this peritoneal fold. They unite to form three or four vessels, which end partly in the lower and partly in the upper glands of the ileocolic chain. The vessels from the root of the vermiform process and from the cecum consist of an anterior and a posterior group. The anterior vessels pass in front of the cecum, and end in the anterior ileocolic glands and in the upper and lower glands of the ileocolic chain; the posterior vessels ascend over the back of the cecum and terminate in the posterior ileocolic glands and in the lower glands of the ileocolic chain.

**Lymphatic Vessels of the Colon** (Fig. 672).—The lymphatic vessels of the ascending and transverse parts of the colon finally end in the mesenteric glands, after traversing the right colic and mesocolic glands. Those of the descending and iliac sigmoid parts of the colon are interrupted by the small glands on the branches of the left colic and sigmoid arteries, and ultimately end in the preaortic glands around the origin of the inferior mesenteric artery.

**Lymphatic Vessels of the Anus, Anal Canal, and Rectum.**—The lymphatics from the **anus** pass forward and end with those of the integument of the perineum and scrotum in the superficial inguinal glands; those from the **anal canal** accompany the middle and inferior hemorrhoidal arteries, and end in the hypogastric glands; while the vessels from the **rectum** traverse the pararectal glands and pass to those in the sigmoid mesocolon; the efferents of the latter terminate in the preaortic glands around the origin of the inferior mesenteric artery.

The **Lymphatic Vessels of the Liver** are divisible into two sets, superficial and deep. The former arise in the subperitoneal areolar tissue over the entire surface of the organ, and may be grouped into (a) those on the convex surface, (b) those on the inferior surface.

(a) On the **convex surface**: The vessels from the back part of this surface reach



their terminal glands by three different routes; the vessels of the middle set, five or six in number, pass through the vena-caval foramen in the Diaphragma and end in one or two glands which are situated around the terminal part of the inferior vena cava; a few vessels from the left side pass backward toward the œsophageal hiatus, and terminate in the paracardial group of superior gastric glands; the vessels from the right side, one or two in number, run on the abdominal surface of the Diaphragma, and, after crossing its right crus, end in the preaortic glands which surround the origin of the cœliac artery. From the portions of the right and left lobes adjacent to the falciform ligament, the lymphatic vessels converge to form two trunks, one of which accompanies the inferior vena cava through the Diaphragma, and ends in the glands around the terminal part of this vessel; the other runs downward and forward, and, turning around the anterior sharp margin of the liver, accompanies the upper part of the ligamentum teres, and ends in the upper hepatic glands. From the anterior surface a few additional vessels turn around the anterior sharp margin to reach the upper hepatic glands.

(b) On the **inferior surface**: The vessels from this surface mostly converge to the porta hepatis, and accompany the deep lymphatics, emerging from the porta to the hepatic glands; one or two from the posterior parts of the right and caudate lobes accompany the inferior vena cava through the Diaphragma, and end in the glands around the terminal part of this vein.

The deep lymphatics converge to ascending and descending trunks. The ascending trunks accompany the hepatic veins and pass through the Diaphragma to end in the glands around the terminal part of the inferior vena cava. The descending trunks emerge from the porta hepatis, and end in the hepatic glands.

The **Lymphatic Vessels of the Gall-bladder** pass to the hepatic glands in the porta hepatis; those of the **common bile duct** to the hepatic glands alongside the duct and to the upper pancreaticoduodenal glands.

The **Lymphatic Vessels of the Pancreas** follow the course of its bloodvessels. Most of them enter the pancreaticolienal glands, but some end in the pancreaticoduodenal glands, and others in the preaortic glands near the origin of the superior mesenteric artery.

## 2. The lymphatic vessels of the spleen and suprarenal glands.

The **Lymphatic Vessels of the Spleen**, both superficial and deep, pass to the pancreaticolienal glands.

The **Lymphatic Vessels of the Suprarenal Glands** usually accompany the suprarenal veins, and end in the lateral aortic glands; occasionally some of them pierce the crura of the Diaphragma and end in the glands of the posterior mediastinal cavity.

## 3. The lymphatic vessels of the urinary organs.

The **Lymphatic Vessels of the Kidney** form three plexuses: one in the substance of the kidney, a second beneath its fibrous capsule, and a third in the perinephric fat; the second and third communicate freely with each other. The vessels from the plexus in the kidney substance converge to form four or five trunks which issue at the hilus. Here they are joined by vessels from the plexus under the capsule, and, following the course of the renal vein, end in the lateral aortic glands. The perinephric plexus is drained directly into the upper lateral aortic glands.

The **Lymphatic Vessels of the Ureter** run in different directions. Those from its upper portion end partly in the efferent vessels of the kidney and partly in the lateral aortic glands; those from the portion immediately above the brim of the lesser pelvis are drained into the common iliac glands; while the vessels from the intrapelvic portion of the tube either join the efferents from the bladder, or end in the hypogastric glands.

The **Lymphatic Vessels of the Bladder** (Fig. 673) originate in two plexuses, an intra- and an extramuscular, it being generally admitted that the mucous mem-

brane is devoid of lymphatic.<sup>1</sup> The efferent vessels are arranged in two groups, one from the anterior and another from the posterior surface of the bladder. The vessels from the *anterior* surface pass to the external iliac glands, but in their course minute glands are situated. These minute glands are arranged in two groups, an *anterior vesical*, in front of the bladder, and a *lateral vesical*, in relation to the lateral umbilical ligament. The vessels from the *posterior* surface pass to the hypogastric, external, and common iliac glands; those draining the upper part of this surface traverse the lateral vesical glands.

The **Lymphatic Vessels of the Prostate** (Fig. 674) terminate chiefly in the hypogastric and sacral glands, but one trunk from the posterior surface ends in the external iliac glands, and another from the anterior surface joins the vessels which drain the membranous part of the urethra.




FIG. 673.—Lymphatics of the bladder. (Cunéo and Marcille.)

**Lymphatic Vessels of the Urethra.**—The lymphatics of the cavernous portion of the urethra accompany those of the glans penis, and terminate with them in the deep subinguinal and external iliac glands. Those of the *membranous and prostatic* portions, and those of the whole urethra in the female, pass to the hypogastric glands.

(4) The **lymphatic vessels of the reproductive organs.**

The **Lymphatic Vessels of the Testes** consist of two sets, superficial and deep, the former commencing on the surface of the tunica vaginalis, the latter in the epididymis and body of the testis. They form from four to eight collecting trunks which ascend with the spermatic veins in the spermatic cord and along the front of the Psoas major to the level where the spermatic vessels cross the ureter and end in the lateral and preaortic groups of lumbar glands.<sup>2</sup>

The **Lymphatic Vessels of the Ductus Deferens** pass to the external iliac glands; those of the *vesiculæ seminales* partly to the hypogastric and partly to the external glands.

<sup>1</sup> Some authorities maintain that a plexus of lymphatic vessels does exist in the mucous membrane of the bladder (consult *Médecine opératoire des Voies urinaires*, par J. Albarran, Paris, 1909).

<sup>2</sup> "The Lymphatics of the Testicle," by Jamieson and Dobson, *Lancet*, February 19, 1900.

The **Lymphatic Vessels of the Ovary** are similar to those of the testis, and ascend with the ovarian artery to the lateral and preaortic glands.

The **Lymphatic Vessels of the Uterine Tube** pass partly with those of the ovary and partly with those of the uterus.




FIG. 674.—Lymphatics of the prostate. (Cunéo and Marcille.) *a, b.* External iliac glands. *c.* Vessel draining into external iliac glands. *d.* Retroprostatic lymph nodes. *e.* Vessels draining into gland on sacral promontory. *f.* Gland in front of sacral promontory. *g.* Lateral sacral glands. *h.* Middle hemorrhoidal gland. *i.* Middle hemorrhoidal lymphatic vessels.

The **Lymphatic Vessels of the Uterus** (Fig. 675) consist of two sets, superficial and deep, the former being placed beneath the peritoneum, the latter in the substance of the organ. The lymphatics of the cervix uteri run in three directions: transversely to the external iliac glands, postero-laterally to the hypogastric glands, and posteriorly to the common iliac glands. The majority of the vessels of the body and fundus of the uterus pass lateralward in the broad ligaments, and are continued up with the ovarian vessels to the lateral and preaortic glands; a few, however, run to the external iliac glands, and one or two to the superficial inguinal glands. In the unimpregnated uterus the lymphatic vessels are very small, but during gestation they are greatly enlarged.

The **Lymphatic Vessels of the Vagina** are carried in three directions: those of the upper part of the vagina to the external iliac glands, those of the middle part to the hypogastric glands, and those of the lower part to the common iliac glands.



On the course of the vessels from the middle and lower parts small glands are situated. Some lymphatic vessels from the lower part of the vagina join those of the vulva and pass to the superficial inguinal glands. The lymphatics of the vagina anastomose with those of the cervix uteri, vulva, and rectum, but not with those of the bladder.




FIG. 675.—Lymphatics of the uterus. (Cunéo and Marcille.) *a*. Efferents to lateral aortic glands. *b, c, d*. Efferents to external iliac glands. *e*. Net-work on lateral aspect of cervix uteri. *f*. Glands in front of sacral promontory. *g*. Efferents to glands in front of sacral promontory. *h*. Hypogastric glands. *i*. Lateral sacral glands. *j*. Vessels draining into hypogastric glands. *k*. Vessels passing to lateral sacral glands.

### THE LYMPHATICS OF THE THORAX.

The lymph glands of the thorax may be divided into parietal and visceral—the former being situated in the thoracic wall, the latter in relation to the viscera.

The parietal lymph glands include the sternal, intercostal, and diaphragmatic glands.

1. The **Sternal Glands** (*lymphoglandulae sternales*; *internal mammary glands*) are placed at the anterior ends of the intercostal spaces, by the side of the internal mammary artery. They derive afferents from the mamma, from the deeper structures of the anterior abdominal wall above the level of the umbilicus, from the upper surface of the liver through a small group of glands which lie behind the xiphoid process, and from the deeper parts of the anterior portion of the thoracic wall. Their efferents usually unite to form a single trunk on either side; this may open directly into the junction of the internal jugular and subclavian veins, or

that of the right side may join the right subclavian trunk, and that of the left the thoracic duct.

2. The **Intercostal Glands** (*lymphoglandulae intercostales*) occupy the posterior parts of the intercostal spaces, in relation to the intercostal vessels. They receive the deep lymphatics from the postero-lateral aspect of the chest; some of these vessels are interrupted by small lateral intercostal glands. The efferents of the glands in the lower four or five spaces unite to form a trunk, which descends and opens either into the cisterna chyli or into the commencement of the thoracic duct. The efferents of the glands in the upper spaces of the left side end in the thoracic duct; those of the corresponding right spaces, in the right lymphatic duct.

3. The **Diaphragmatic Glands** lie on the thoracic aspect of the Diaphragm, and consist of three sets, anterior, middle, and posterior.

The **anterior set** comprises (a) two or three small glands behind the base of the xiphoid process, which receive afferents from the convex surface of the liver, and (b) one or two glands on either side near the junction of the seventh rib with its cartilage, which receive lymphatic vessels from the front part of the Diaphragm. The efferent vessels of the anterior set pass to the sternal glands.

The **middle set** consists of two or three glands on either side close to where the phrenic nerves enter the Diaphragm. On the right side some of the glands of this group lie within the fibrous sac of the pericardium, on the front of the termination of the inferior vena cava. The afferents of this set are derived from the middle part of the Diaphragm, those on the right side also receiving afferents from the convex surface of the liver. Their efferents pass to the posterior mediastinal glands.

The **posterior set** consists of a few glands situated on the back of the crura of the Diaphragm, and connected on the one hand with the lumbar glands and on the other with the posterior mediastinal glands.

The **superficial lymphatic vessels of the thoracic wall** ramify beneath the skin and converge to the axillary glands. Those over the Trapezius and Latissimus dorsi run forward and unite to form about ten or twelve trunks which end in the subscapular group. Those over the pectoral region, including the vessels from the skin covering the peripheral part of the mamma, run backward, and those over the Serratus anterior upward, to the pectoral group. Others near the lateral margin of the sternum pass inward between the rib cartilages and end in the sternal glands, while the vessels of opposite sides anastomose across the front of the sternum. A few vessels from the upper part of the pectoral region ascend over the clavicle to the supraclavicular group of cervical glands.

The **Lymphatic Vessels of the Mamma** originate in a plexus in the interlobular spaces and on the walls of the galactophorous ducts. Those from the central part of the gland pass to an intricate plexus situated beneath the areola, a plexus which receives also the lymphatics from the skin over the central part of the gland and those from the areola and nipple. Its efferents are collected into two trunks which pass to the pectoral group of axillary glands. The vessels which drain the medial part of the mamma pierce the thoracic wall and end in the sternal glands, while a vessel has occasionally been seen to emerge from the upper part of the mamma and, piercing the Pectoralis major, terminate in the subclavicular glands (Fig. 662).

The **deep lymphatic vessels of the thoracic wall** consist of:

1. The lymphatics of the muscles which lie on the ribs: most of these end in the axillary glands, but some from the Pectoralis major pass to the sternal glands.
2. The intercostal vessels which drain the Intercostales and parietal pleura. Those draining the Intercostales externi run backward and, after receiving the vessels which accompany the posterior branches of the intercostal arteries, end in the intercostal glands. Those of the Intercostales interni and parietal pleura consist of a single trunk in each space. These trunks run forward in the subpleural tissue and the upper six open separately into the sternal glands or into the vessels which



unite them; those of the lower spaces unite to form a single trunk which terminates in the lowest of the sternal glands. 3. The **lymphatic vessels of the Diaphragma**, which form two plexuses, one on its thoracic and another on its abdominal surface. These plexuses anastomose freely with each other, and are best marked on the parts covered respectively by the pleuræ and peritoneum. That on the thoracic surface communicates with the lymphatics of the costal and mediastinal parts of the pleura, and its efferents consist of three groups: (a) anterior, passing to the gland which lie near the junction of the seventh rib with its cartilage; (b) middle, to the glands on the œsophagus and to those around the termination of the inferior vena cava; and (c) posterior, to the glands which surround the aorta at the point where this vessel leaves the thoracic cavity.

The plexus on the abdominal surface is composed of fine vessels, and anastomoses with the lymphatics of the liver and, at the periphery of the Diaphragma, with those of the subperitoneal tissue. The efferents from the right half of this plexus terminate partly in a group of glands on the trunk of the corresponding inferior phrenic artery, while others end in the right lateral aortic glands. Those from the left half of the plexus pass to the pre- and lateral aortic glands and to the glands on the terminal portion of the œsophagus.

The **visceral lymph glands** consist of three groups, viz.: **anterior mediastinal**, **posterior mediastinal**, and **tracheobronchial**.

The **Anterior Mediastinal Glands** (*lymphoglandulae mediastinales anteriores*) are placed in the anterior part of the superior mediastinal cavity, in front of the aortic arch and in relation to the innominate veins and the large arterial trunks which arise from the aortic arch. They receive afferents from the thymus and pericardium, and from the sternal glands; their efferents unite with those of the tracheobronchial glands, to form the right and left bronchomediastinal trunks.

The **Posterior Mediastinal Glands** (*lymphoglandulae mediastinales posteriores*) lie behind the pericardium in relation to the œsophagus and descending thoracic aorta. Their afferents are derived from the œsophagus, the posterior part of the pericardium, the Diaphragma, and the convex surface of the liver. Their efferents mostly end in the thoracic duct, but some join the tracheobronchial glands.

The **Tracheobronchial Glands** (Fig. 676) form four main groups: (a) **tracheal**, on either side of the trachea; (b) **bronchial**, in the angles between the lower part of the trachea and bronchi and in the angle between the two bronchi; (c) **bronchopulmonary**, in the hilus of each lung; and (d) **pulmonary**, in the lung substance, on the larger branches of the bronchi. The afferents of the tracheobronchial glands drain the lungs and bronchi, the thoracic part of the trachea and the heart; some of the efferents of the posterior mediastinal glands also end in this group. Their efferent vessels ascend upon the trachea and unite with efferents of the internal mammary and anterior mediastinal glands to form the **right and left bronchomediastinal trunks**. The right bronchomediastinal trunk may join the right lymphatic duct, and the left the thoracic duct, but more frequently they open independently of these ducts into the junction of the internal jugular and subclavian veins of their own side.

**Applied Anatomy.**—In all town dwellers there are continually being swept into these glands from the bronchi and alveoli large quantities of the dust and black carbonaceous pigment that are so freely inhaled in cities. At first the glands are moderately enlarged, firm, inky black, and gritty on section; later they enlarge still further, often becoming fibrous from the irritation set up by the minute foreign bodies with which they are crammed, and may break down into a soft slimy mass or may calcify. In tuberculosis of the lungs these glands are practically always infected; they enlarge, being filled with tuberculous deposits that may soften, or become fibrous, or calcify. Not infrequently an enlarged tuberculous gland perforates into a bronchus, discharging its contents into the tube. When this happens there is great danger of acute pulmonary tuberculosis, the infecting gland substance being rapidly spread throughout the bronchial system by the coughing its presence in the air passages excites.

The **lymphatic vessels of the thoracic viscera** comprise those of the heart and pericardium, lungs and pleura, thymus, and œsophagus.

The **Lymphatic Vessels of the Heart** consist of two plexuses: (a) deep, immediately under the endocardium; and (b) superficial, subjacent to the visceral pericardium. The deep plexus opens into the superficial, the efferents of which form right and left collecting trunks. The **left trunks**, two or three in number, ascend in the anterior longitudinal sulcus, receiving, in their course, vessels from both ventricles. On reaching the coronary sulcus they are joined by a large trunk from the diaphragmatic surface of the heart, and then unite to form a single vessel which ascends between the pulmonary artery and the left atrium and ends in one of the tracheobronchial




FIG. 676.—The tracheobronchial lymph glands. (From a figure designed by M. Hallé.)

glands. The **right trunk** receives its afferents from the right atrium and from the right border and diaphragmatic surface of the right ventricle. It ascends in the posterior longitudinal sulcus and then runs forward in the coronary sulcus, and passes up behind the pulmonary artery, to end in one of the tracheobronchial glands.

The **Lymphatic Vessels of the Lungs** originate in two plexuses, a superficial and a deep. The superficial plexus is placed beneath the pulmonary pleura. The deep accompanies the branches of the pulmonary vessels and the ramifications of the bronchi. In the case of the larger bronchi the deep plexus consists of two net-works—one, submucous, beneath the mucous membrane, and another, peribronchial, outside the walls of the bronchi. In the smaller bronchi there is but a single plexus, which extends as far as the bronchioles, but fails to reach the alveoli, in the walls

of which there are no traces of lymphatic vessels. The superficial efferents turn around the borders of the lungs and the margins of their fissures, and converge to end in some glands situated at the hilus; the deep efferents are conducted to the hilus along the pulmonary vessels and bronchi, and end in the tracheobronchial glands. Little or no anastomosis occurs between the superficial and deep lymphatics of the lungs, except in the region of the hilus.

The **Lymphatic Vessels of the Pleura** consist of two sets—one in the visceral and another in the parietal part of the membrane. Those of the visceral pleura drain into the superficial efferents of the lung, while the lymphatics of the parietal pleura have three modes of ending, viz.: (a) those of the costal portion join the lymphatics of the *Intercostales interni* and so reach the sternal glands; (b) those of the diaphragmatic part are drained by the efferents of the *Diaphragma*; while (c) those of the mediastinal portion terminate in the posterior mediastinal glands.

The **Lymphatic Vessels of the Thymus** end in the anterior mediastinal, tracheobronchial, and sternal glands.

The **Lymphatic Vessels of the Œsophagus** form a plexus around that tube, and the collecting vessels from the plexus drain into the posterior mediastinal glands.

# NEUROLOGY.

---

**THE Nervous System** is the most complicated and highly organized of the various systems which make up the human body. It may be divided into two parts, **central** and **peripheral**.

The **central nervous system** consists of (*a*) an upper expanded portion, the **encephalon** or **brain**, contained within the cranium, and (*b*) a lower, elongated, nearly cylindrical portion, the **medulla spinalis** or **spinal cord**, lodged in the vertebral canal; the two portions are continuous with one another at the level of the upper border of the atlas vertebra.

The **peripheral nervous system** consists of a series of nerves by which the central nervous system is connected with the various tissues of the body. For descriptive purposes these nerves may be arranged in two groups, **cerebrospinal** and **sympathetic**, the arrangement, however, being an arbitrary one, since the two groups are intimately connected and closely intermingled. The cerebrospinal nerves are forty-three in number on either side—twelve **cerebral**, attached to the brain, and thirty-one **spinal**, to the medulla spinalis. They are associated with the functions of the special and general senses and with the voluntary movements of the body. The sympathetic nerves transmit the impulses which regulate the movements of the viscera, determine the calibre of the bloodvessels, and control the phenomena of secretion. In relation with them are two rows of **central ganglia**, situated one on either side of the middle line in front of the vertebral column; these ganglia are intimately connected with the medulla spinalis and the spinal nerves, and are also joined to each other by vertical strands of nerve fibres so as to constitute a pair of knotted cords, the **sympathetic trunks**, which reach from the base of the skull to the coccyx. The sympathetic nerves issuing from the ganglia form three great prevertebral plexuses which supply the thoracic, abdominal, and pelvic viscera; in relation to the walls of these viscera intricate nerve plexuses and numerous **peripheral ganglia** are found.

The nervous system is built up of nervous and non-nervous tissues—the former consisting of nerve cells and nerve fibres; the latter, of neuroglia and bloodvessels, together with certain enveloping membranes.

The minute structure of the nervous elements, and of the neuroglia, has been described in the chapter on Histology (pp. 69 to 76); and an outline of the development of the nervous system furnished in that on Embryology (pp. 117 to 133). The structure of the individual parts of the brain is given under their specific descriptions.

**Structure of the Peripheral Nerves and Ganglia.**—The **cerebrospinal nerves** consist of numerous nerve fibres collected together and enclosed in membranous sheaths (Fig. 677). A small bundle of fibres, enclosed in a tubular sheath, is called a **funiculus**; if the nerve is of small size, it may consist only of a single funiculus; but if large, the funiculi are collected together into larger bundles or **fasciculi**, which are bound together in a common membranous investment. In structure, the common membranous investment, or sheath of the whole nerve (**epineurium**), as well as the septa given off from it to separate the fasciculi, consist of connective tissue, composed of white and yellow elastic fibres, the latter existing in great abundance. The tubular sheath of the funiculi (**perineurium**) is a fine, smooth, transparent membrane, which may be easily separated, in the form of a tube, from the fibres it encloses; in structure it is made up of connective tissue, which has a distinctly lamellar arrangement. The nerve fibres are held together and supported within

the funiculus by delicate connective tissue, called the **endoneurium**. It is continuous with septa which pass inward from the innermost layer of the perineurium, and shows a ground substance in which are imbedded fine bundles of fibrous connective tissue running for the most part longitudinally. It serves to support capillary vessels, arranged so as to form a net-work with elongated meshes. The cerebrospinal nerves consist almost exclusively of medullated nerve fibres, only a very small proportion of non-medullated being present.

The bloodvessels supplying a nerve end in a minute capillary plexus, the vessels composing which pierce the perineurium, and run, for the most part, parallel with the fibres; they are connected together by short, transverse vessels, forming narrow, oblong meshes, similar to the capillary system of muscle. Fine non-medullated nerve fibres, **vasomotor fibres**, accompany these capillary vessels, and break up into elementary fibrils, which form a network around the vessels. Horsley has demonstrated certain medullated fibres running in the epineurium and terminating in small **spheroidal tactile corpuscles** or **end bulbs of Krause**. These nerve fibres, which Marshall believes to be sensory, and which he has termed **nervi nervorum**, are considered by him to have an important bearing upon certain neuralgic pains.




FIG. 677.—Transverse section of human tibial nerve.

The nerve fibres, so far as is at present known, do not coalesce, but pursue an uninterrupted course from the centre to the periphery. In separating a nerve, however, into its component funiculi, it may be seen that these do not pursue a perfectly insulated course, but occasionally join at a very acute angle with other funiculi proceeding in the same direction; from this, branches are given off, to join again in like manner with other funiculi. It must be distinctly understood, however, that in these communications the individual nerve fibres do not coalesce, but merely pass into the sheath of the adjacent nerve, become intermixed with its nerve fibres, and again pass on to intermingle with the nerve fibres in some adjoining funiculus.

Nerves, in their course, subdivide into branches, and these frequently communicate with branches of a neighboring nerve. The communications which thus take place form what is called a **plexus**. Sometimes a plexus is formed by the primary branches of the trunks of the nerves—as the cervical, brachial, lumbar, and sacral plexuses—and occasionally by the terminal funiculi, as in the plexuses formed at the periphery of the body. In the formation of a plexus, the component nerves divide, then join, and again subdivide in such a complex manner that the individual funiculi become interlaced most intricately; so that each branch leaving a plexus may contain filaments from all the primary nervous trunks which form the plexus. In the formation also of smaller plexuses at the periphery of the body there is a free interchange of the funiculi and primitive fibres. In each case, however, the individual fibres remain separate and distinct.

It is probable that through this interchange of fibres, every branch passing off from a plexus has a more extensive connection with the spinal cord than if it had proceeded to its distribution without forming connections with other nerves. Consequently the parts supplied by these nerves have more extended relations with the nervous centres; by this means, also, groups of muscles may be associated for combined action.



The **sympathetic nerves** are constructed in the same manner as the cerebrospinal nerves, but consist mainly of non-medullated fibres, collected in funiculi and enclosed in sheaths of connective tissue. There is, however, in these nerves a certain admixture of medullated fibres. The number of the latter varies in different nerves, and may be estimated by the color of the nerve. Those branches of the sympathetic which present a well-marked gray color are composed chiefly of non-medullated nerve fibres, intermixed with a few medullated fibres; while those of a white color contain many of the latter fibres, and few of the former.

The cerebrospinal and sympathetic nerve fibres convey various impressions. The **sensory nerves**, called also **centripetal** or **afferent nerves**, transmit to the nervous centres impressions made upon the peripheral extremities of the nerves, and in this way the mind, through the medium of the brain, becomes conscious of external objects. The **centrifugal** or **efferent nerves** transmit impressions from the nervous centres to the parts to which the nerves are distributed, these impressions either exciting muscular contraction, or influencing the processes of nutrition, growth, and secretion.

**Origins and Terminations of Nerves.**—By the expression “the terminations of nerve fibres” is signified their connections with the nerve centres and with the parts they supply. The former are sometimes called their **origins** or **central terminations**; the latter their **peripheral terminations**.

**Origins of Nerves.**—The origin in some cases is single—that is to say, the whole nerve emerges from the nervous centre by a single root; in other instances the nerve arises by two or more roots which come off from different parts of the nerve centre, sometimes widely apart from each other, and it often happens, when a nerve arises in this way by two roots, that the functions of these two roots are different; as, for example, in the spinal nerves, each of which arises by two roots, the anterior of which is motor, and the posterior sensory. The point where the nerve root or roots emerge from the surface of the nervous centre is named the **superficial** or **apparent origin**, but the fibres of the nerve can be traced for a certain distance into the substance of the nervous centre to some portion of the gray matter, which constitutes the **deep** or **real origin** of the nerve. The centrifugal or efferent nerve fibres originate in the nerve cells of the gray substance, the axis-cylinder processes of these cells being prolonged to form the fibres. In the case of the centripetal or afferent nerves the fibres grow inward either from nerve cells in the organs of special sense, *e. g.*, the retina, or from nerve cells in the ganglia. Having entered the nerve centre they branch and send their ultimate twigs among the cells, without, however, uniting with them.

**Peripheral Terminations of Nerves.**—Nerve fibres terminate peripherally in various ways, and these may be conveniently studied in the sensory and motor nerves respectively. The terminations of the sensory nerves are dealt with in the section on Sense Organs.

**Motor nerves** can be traced into either unstripped or striped muscular fibres. In the *unstripped* or *involuntary muscles* the nerves are derived from the sympathetic, and are composed mainly of non-medullated fibres. Near their terminations they divide into numerous branches, which communicate and form intimate plexuses. At the junctions of the branches small triangular nuclear bodies (ganglion cells) are situated. From these plexuses minute branches are given off which divide and break up into the ultimate fibrillæ of which the nerves are composed. These fibrillæ course between the involuntary muscle cells, and, according to Elischer, terminate on the surfaces of the cells, opposite the nuclei, in minute swellings.

In the *striped* or *voluntary muscle*, the nerves supplying the muscular fibres are derived from the cerebrospinal nerves, and are composed mainly of medullated fibres. The nerve, after entering the sheath of the muscle, breaks up into fibres or bundles of fibres, which form plexuses, and gradually divide until, as a rule, a single nerve fibre enters a single muscular fibre. Sometimes, however, if the muscular fibre be long, more than one nerve fibre enters it. Within the muscular fibre the nerve terminates in a special expansion, called by Kühne, who first accurately described it, a **motor end plate** (Fig. 678). The nerve fibre, on approaching the muscular fibre, suddenly loses its medullary sheath, the neurolemma becomes continuous with the sarcolemma of the muscle, and only the axis-cylinder enters the muscular fibre. There it at once spreads out, ramifying like the roots of a tree, immediately beneath the sarcolemma, and becomes imbedded in a layer of granular matter, containing a number of clear, oblong nuclei, the whole constituting an end-plate from which the contractile wave of the muscular fibre is said to start.

**Ganglia** are small aggregations of nerve cells. They are found on the posterior roots of the spinal nerves; on the sensory roots of the trigeminal, facial, glossopharyngeal, and vagus nerves, and on the acoustic nerves. They are also found in connection with the sympathetic nerves. On section they are seen to consist of a reddish-gray substance, traversed by numerous white nerve fibres; they vary considerably in form and size; the largest are found in the cavity of the abdomen; the smallest, not visible to the naked eye, exist in considerable numbers upon the nerves distributed to the different viscera. Each ganglion is invested by a smooth and firm, closely adhering, membranous envelope, consisting of dense areolar tissue; this sheath is continuous with the perineurium of the nerves, and sends numerous processes into the interior to support the bloodvessels supplying the substance of the ganglion.

In structure all ganglia are essentially similar, consisting of the same structural elements—*viz.*, nerve cells and nerve fibres. Each nerve cell has a nucleated sheath which is continuous

with the neurolemma of the nerve fibre with which the cell is connected. The nerve cells in the ganglia of the spinal nerves (Fig. 679) are pyriform in shape, and have each a single process. A short distance from the cell and while still within the ganglion this process divides in a T-shaped manner, one limb of the cross-bar turning into the medulla spinalis, the other limb passing outward to the periphery. In the sympathetic ganglia (Fig. 680) the nerve cells are multipolar and each has one axis-cylinder process and several dendrons; the axon emerges from the ganglion




FIG. 678.—Muscular fibres of *Lacerta viridis* with the terminations of nerves. *a.* Seen in profile. *P P.* The nerve end-plates. *S S.* The base of the plate, consisting of a granular mass with nuclei. *b.* The same as seen in looking at a perfectly fresh fibre, the nervous ends being probably still excitable. (The forms of the variously divided plate can hardly be represented in a woodcut by sufficiently delicate and pale contours to reproduce correctly what is seen in nature.) *c.* The same as seen two hours after death from poisoning by curare.

as a non-medullated nerve fibre. Similar cells are found in the ganglia connected with the trigeminal nerve, and these ganglia are therefore regarded as the cerebral portions of the "autonomic" system. The autonomic nervous system includes those portions of the nervous mechanism in which a medullated nerve fibre from the central system passes to a ganglion, sympathetic or peripheral, from which fibres, usually non-medullated, are distributed to such structures, *e. g.*, bloodvessels, as are not under voluntary control. The spinal and sympathetic ganglia differ somewhat in the size and disposition of the cells and in the number of nerve fibres entering and




FIG. 679.—Transverse section of spinal ganglion of rabbit. *A.* Ganglion.  $\times 30$ . *a.* Large clear nerve cell. *b.* Small deeply staining nerve cell. *c.* Nuclei of capsule.  $\times 250$ . The lines in the centre point to the corresponding cells in the ganglion.

leaving them. In the spinal ganglia (Fig. 679) the nerve cells are much larger and for the most part collected in groups near the periphery, while the fibres, which are mostly medullated, traverse the central portion of the ganglion; whereas in the sympathetic ganglia (Fig. 680) the cells are smaller and distributed in irregular groups throughout the whole ganglion; the fibres also are irregularly scattered; some of the entering ones are medullated, while many of those leaving the ganglion are non-medullated.

**Neuron Theory.**—The nerve cell and its processes collectively constitute what is termed a **neuron**, and Waldeyer formulated the theory that the nervous system is built up of numerous neurons, "anatomically and genetically independent of one another." According to this theory (*neuron theory*) the processes of one neuron only come into contact, and are never in direct continuity, with those of other neurons; while impulses are transmitted from one nerve cell to another through these points of contact. This theory is based on the following facts, viz.: (1) embryonic nerve cells or neuroblasts are entirely distinct from one another; (2) when nervous tissues are stained by the Golgi method no continuity is seen even between neighboring neurons; and (3) when degenerative changes occur in nervous tissue, either as the result of disease or experiment, they never spread from one neuron to another, but are limited to the individual neurons, or groups of neurons, primarily affected. It must, however, be




FIG. 680.—Transverse section of sympathetic ganglion of cat. A. Ganglion.  $\times 50$ . a. A nerve cell.  $\times 250$ .




FIG. 681.—Sagittal section of vertebral canal to show the lower end of the medulla spinalis and the filum terminale. (Testut.) *L1*, *L5*. First and fifth lumbar vertebrae. *S2*. Second sacral vertebra. 1. Dura mater. 2. Lower part of tube of dura mater. 3. Lower extremity of medulla spinalis. 4. Intradural, and 5, Extradural portions of filum terminale. 6. Attachment of filum terminale to first segment of coccyx.

added that within the past few years the validity of the neuron theory has been called in question by certain eminent histologists, who maintain that by the employment of more delicate histological methods, minute fibrils can be followed from one nerve cell into another.

## THE MEDULLA SPINALIS OR SPINAL CORD.

**Dissection.**—To dissect the medulla spinalis and its membranes it will be necessary to lay open the whole length of the vertebral canal. For this purpose the muscles must be separated from the vertebral grooves, so as to expose the spinous processes and laminae of the vertebrae; and the latter must be sawn through on each side, close to the roots of the transverse processes, from the third or fourth cervical vertebra above to the sacrum below. The vertebral arches having been displaced by means of a chisel and the separate fragments removed, the dura will be exposed, covered by a plexus of veins and a quantity of loose areolar tissue, often infiltrated with serous fluid. The arches of the upper vertebrae are best divided by means of a strong pair of cutting bone forceps or by a rachitome.

The **medulla spinalis** or **spinal cord** forms the elongated, nearly cylindrical, part of the central nervous system which occupies the upper two-thirds of the vertebral canal. Its average length in the male is about 45 cm., in the female from 42 to 43 cm., while its weight amounts to about 30 gms. It extends from the level of the upper border of the atlas to that of the lower border of the first, or upper border

of the second, lumbar vertebra. Above, it is continuous with the brain; below, it ends in a conical extremity, the *conus medullaris*, from the apex of which a delicate filament, the *filum terminale*, descends as far as the first segment of the coccyx (Fig. 681).

The position of the medulla spinalis varies with the movements of the vertebral column, its lower extremity being drawn slightly upward when the column is flexed. It also varies at different periods of life; up to the third month of fetal life the medulla spinalis is as long as the vertebral canal, but from this stage onward the vertebral column elongates more rapidly than the medulla spinalis, so that by the end of the fifth month the medulla spinalis terminates at the base of the sacrum, and at birth about the third lumbar vertebra.

The medulla spinalis does not fill the part of the vertebral canal in which it lies; it is ensheathed by three protective membranes, separated from each other by two concentric spaces. The three membranes are named from without inward, the *dura mater*, the *arachnoid*, and the *pia mater*. The *dura mater* is a strong, fibrous membrane which forms a wide, tubular sheath; this sheath extends below the termination of the medulla spinalis and ends in a pointed cul-de-sac at the level of the lower border of the second sacral vertebra. The *dura mater* is separated from the wall of the vertebral canal by the *epidural cavity*, which contains a quantity of loose areolar tissue and a plexus of veins; between the *dura mater* and the subjacent *arachnoid* is a capillary interval, the *subdural cavity*, which contains a small quantity of fluid, probably of the nature of lymph. The *arachnoid* is a thin, transparent sheath, separated from the *pia mater* by a comparatively wide interval, the *subarachnoid cavity*, which is filled with cerebrospinal fluid. The *pia mater* closely invests the medulla spinalis and sends delicate septa into its substance; a narrow band, the *ligamentum denticulatum*, extends along each of its lateral surfaces and is attached by a series of pointed processes to the inner surface of the *dura mater*.

Thirty-one pairs of spinal nerves spring from the medulla spinalis, each nerve having an anterior or ventral, and a posterior or dorsal root, the latter being distinguished by the presence of an oval swelling, the *spinal ganglion*, which contains numerous nerve cells. Each root consists of several bundles of nerve fibres, and at its attachment extends for some distance along the side of the medulla spinalis. The pairs of spinal nerves are grouped as follows: cervical 8, thoracic 12, lumbar 5, sacral 5, coccygeal 1, and, for convenience of description, the medulla spinalis is divided into cervical, thoracic, lumbar and sacral regions, corresponding with the attachments of the different groups of nerves.

Although no trace of transverse segmentation is visible on the surface of the medulla spinalis, it is convenient to regard it as being built up of a series of superimposed *spinal segments* or *neuromeres*, each of which has a length equivalent to the extent of attachment of a pair of spinal nerves. Since the extent of attachment of the successive pairs of nerves varies in different parts, it follows that the spinal segments are of varying lengths; thus, in the cervical region they average about 13 mm., in the mid-thoracic region about 26 mm., while in the lumbar and sacral regions they diminish rapidly from about 15 mm. at the level of the first pair of lumbar nerves to about 4 mm. opposite the attachments of the lower sacral nerves.

As a consequence of the relative inequality in the rates of growth of the medulla spinalis and vertebral column, the nerve roots, which in the early embryo passed transversely outward to reach their respective intervertebral foramina, become more and more oblique in direction from above downward, so that the lumbar and sacral nerves descend almost vertically to reach their points of exit. From the appearance these nerves present at their attachment to the medulla spinalis and from their great length they are collectively termed the *cauda equina* (Fig. 682).

The **filum terminale** is a delicate filament, about 20 cm. in length, prolonged downward from the apex of the conus medullaris. It consists of two parts, an upper and a lower. The upper part, or **filum terminale internum**, measures about 15 cm. in length and reaches as far as the lower border of the second sacral vertebra. It is contained within the tubular sheath of dura mater, and is surrounded by the nerves forming the cauda equina, from which it can be readily recognized by its bluish-white color. The lower part, or **filum terminale externum**, is closely invested by, and is adherent to, the dura mater; it extends downward from the apex of the tubular sheath





FIG. 682.—Cauda equina and filum terminale seen from behind. The dura mater has been opened and spread out, and the arachnoid has been removed.



Ventral aspect      Dorsal aspect

FIG. 683.—Diagrams of the medulla spinalis.



and is attached to the back of the first segment of the coccyx. The *filum terminale* consists mainly of fibrous tissue, continuous above with that of the pia mater. Adhering to its outer surface, however, are a few strands of nerve fibres which probably represent rudimentary second and third coccygeal nerves; further, the central canal of the medulla spinalis extends downward into it for 5 or 6 cm.

**Enlargements.**—The medulla spinalis is not quite cylindrical, being slightly flattened from before backward; it also presents two swellings or enlargements, an upper or cervical, and a lower or lumbar (Fig. 683).

The **cervical enlargement** is the more pronounced, and corresponds with the attachments of the large nerves which supply the upper limbs. It extends from about the third cervical to the second thoracic vertebra, its maximum circumference (about 38 mm.) being on a level with the attachment of the sixth pair of cervical nerves.

The **lumbar enlargement** gives attachment to the nerves which supply the lower limbs. It commences about the level of the ninth thoracic vertebra, and reaches its maximum circumference, of about 33 mm., opposite the last thoracic vertebra, below which it tapers rapidly into the *conus medullaris*.

**Fissures and Sulci** (Fig. 684).—An anterior median fissure and a posterior median sulcus incompletely divide the medulla spinalis into two symmetrical parts, which are joined across the middle line by a commissural band of nervous matter.

The **Anterior Median Fissure** (*fissura mediana anterior*) has an average depth of about 3 mm., but this is increased in the lower part of the medulla spinalis. It contains a double fold of pia mater, and its floor is formed by a transverse band of white substance, the **anterior white commissure**, which is perforated by blood-vessels on their way to or from the central part of the medulla spinalis.

The **Posterior Median Sulcus** (*sulcus medianus posterior*) is very shallow; from it a septum of neuroglia reaches rather more than half-way into the substance of the medulla spinalis; this septum varies in depth from 4 to 6 mm., but diminishes considerably in the lower part of the medulla spinalis.

On either side of the posterior median sulcus, and at a short distance from it, the posterior nerve roots are attached along a vertical furrow named the **postero-lateral sulcus**. The portion of the medulla spinalis which lies between this and the posterior median sulcus is named the **posterior funiculus**. In the cervical and upper thoracic regions this funiculus presents a longitudinal furrow, the **postero-intermediate sulcus**; this marks the position of a septum which extends into the posterior funiculus and subdivides it into two fasciculi—a medial, named the **fasciculus gracilis** (*tract of Goll*); and a lateral, the **fasciculus cuneatus** (*tract of Burdach*) (Fig. 690). The portion of the medulla spinalis which lies in front of the postero-lateral sulcus is termed the **antero-lateral region**. The anterior nerve roots, unlike the posterior, are not attached in linear series, and their position of exit is not marked by a sulcus. They arise by separate bundles which spring from the anterior column of gray substance and, passing forward through the white substance, emerge over an area of some slight width. The most lateral of these bundles is generally taken as a dividing line which separates the antero-lateral region into two parts, viz., an **anterior funiculus**, between the anterior median fissure and the most lateral of the anterior nerve roots; and a **lateral funiculus**, between the exit of these roots and the postero-lateral sulcus. In the upper part of the cervical region a series of nerve roots passes outward through the lateral funiculus of the medulla spinalis; these unite to form the spinal portion of the accessory nerve, which runs upward and enters the cranial cavity through the foramen magnum.

**The Internal Structure of the Medulla Spinalis.**—On examining a transverse section of the medulla spinalis (Fig. 684) it is seen to consist of gray and white nervous substance, the former being enclosed within the latter.

**Gray Substance** (*substantia grisea centralis*).—The gray substance consists of two symmetrical portions, one in each half of the medulla spinalis: these are joined across the middle line by a transverse commissure of gray substance, through which runs a minute canal, the **central canal**, just visible to the naked eye. In a transverse section each half of the gray substance is shaped like a comma or crescent, the concavity of which is directed laterally; and these, together with the intervening gray commissure, present the appearance of the letter H. An imaginary coronal plane through the central canal serves to divide each crescent into an **anterior** or **ventral**, and a **posterior** or **dorsal column**.

The **Anterior Column** (*columna anterior; anterior cornu*), directed forward, is broad and of a rounded or quadrangular shape. Its posterior part is termed the **base**, and its anterior part the **head**, but these are not differentiated from each other by any well-defined constriction. It is separated from the surface of the medulla spinalis by a layer of white substance which is traversed by the bundles of the anterior nerve roots. In the thoracic region, the postero-lateral part of the anterior column projects lateralward as a triangular field, which is named the **lateral column** (*columna lateralis; lateral cornu*).




FIG. 684.—Transverse section of the medulla spinalis in the mid-thoracic region.

The **Posterior Column** (*columna posterior; posterior cornu*) is long and slender, and is directed backward and lateralward: it reaches almost as far as the postero-lateral sulcus, from which it is separated by a thin layer of white substance, the **tract of Lissauer**. It consists of a **base**, directly continuous with the base of the anterior horn, and a **neck** or slightly constricted portion, which is succeeded by an oval or fusiform area, termed the **head**, of which the **apex** approaches the postero-lateral sulcus. The apex is capped by a V-shaped or crescentic mass of translucent, gelatinous neuroglia, termed the **substantia gelatinosa of Rolando**, which contains both neuroglia cells, and small nerve cells. Between the anterior and posterior columns the gray substance extends as a series of processes into the lateral funiculus, to form a net-work called the **formatio reticularis**.

The quantity of gray substance, as well as the form which it presents on transverse section, varies markedly at different levels. In the thoracic region it is small, not only in amount but relatively to the surrounding white substance. In the

cervical and lumbar enlargements it is greatly increased: in the latter, and especially in the conus medullaris, its proportion to the white substance is greatest (Fig. 685).



C.1.

C.2.

C.5.

C.8.

Th.2.

Th.8.

Th.12.

L.3.

S.2.

Coc.

In the cervical region its posterior column is comparatively narrow, while its anterior is broad and expanded; in the thoracic region, both columns are attenuated, and the lateral column is evident; in the lumbar enlargement, both are expanded; while in the conus medullaris the gray substance assumes the form of two oval masses, one in each half of the cord, connected together by a broad gray commissure.

The **Central Canal** (*canalis centralis*) runs throughout the entire length of the medulla spinalis. The portion of gray substance in front of the canal is named the **anterior gray commissure**; that behind it, the **posterior gray commissure**. The former is thin, and is in contact anteriorly with the anterior white commissure: it contains a couple of longitudinal veins, one on either side of the middle line. The posterior gray commissure reaches from the central canal to the posterior median septum, and is thinnest in the thoracic region, and thickest in the conus medullaris. The central canal is continued upward through the lower part of the medulla oblongata, and opens into the fourth ventricle of the brain; below, it reaches for a short distance into the filum terminale. In the lower part of the conus medullaris it exhibits a fusiform dilatation, the **terminal ventricle**; this has a vertical measurement of from 8 to 10 mm., is triangular on cross-section with its base directed forward, and tends to undergo obliteration after the age of forty years.

Throughout the cervical and thoracic regions the central canal is situated in the anterior third of the medulla spinalis; in the lumbar enlargement it is near the middle, and in the conus medullaris it approaches the posterior surface. It is filled with cerebrospinal fluid, and lined by ciliated, columnar epithelium, outside of which is an encircling band of gelatinous substance, the **substantia gelatinosa centralis**. This gelatinous substance consists mainly of neuroglia, but contains a few nerve cells and fibres; it is traversed by processes from the deep ends of the columnar ciliated cells which line the central canal (Fig. 686).

**Structure of the Gray Substance.**—The gray substance consists of numerous nerve cells and nerve fibres held together by neuroglia. Throughout the greater part of the gray substance the neuroglia presents the appearance of a sponge-like net-work, but around the central canal and on the apices of the posterior columns it consists of the gelatinous substance already referred to. The nerve cells are multipolar, and vary greatly in size and shape. They consist of (1) motor cells of large size, which are

FIG. 685.—Transverse sections of the medulla spinalis at different levels.

situated in the anterior horn, and are especially numerous in the cervical and lumbar enlargements; the axons of most of these cells pass out to form the anterior nerve roots, but before leaving the white substance they frequently give off collaterals, which reënter and ramify in the gray substance.<sup>1</sup> (2) Cells of small or medium size, whose axons pass into the white matter, where some pursue an ascending, and others a descending course, but most of them divide in a T-shape manner into descending and ascending processes. They give off collaterals which enter and ramify in the gray substance, and the terminations of the axons behave in a similar manner. The lengths of these axons vary greatly: some are short and pass only between adjoining spinal segments, while others are longer and connect more distant segments. These cells and their processes constitute a series of **association** or **intersegmental neurons** (Fig. 687), which link together the different parts of the medulla spinalis. The axons of most of these cells are confined to that side of the medulla spinalis in which the nerve cells are situated, but some cross to the opposite side through the anterior commissure, and are termed **crossed commissural fibres**. Some of these latter end directly in the gray substance, while others enter the white




FIG. 686.—Section of central canal of medulla spinalis, showing ependymal and neuroglial cells. (v. Lenhossek.)




FIG. 687.—Cells of medulla spinalis. (Poirier.) Diagram showing in longitudinal section the intersegmental neurons of the medulla spinalis. The gray and white parts correspond respectively to the gray and white substance of the medulla spinalis.

substance, and ascend or descend in it for varying distances, before finally terminating in the gray substance. (3) Cells of the type II of Golgi, limited to the posterior column, are found in the substantia gelatinosa of Rolando; their axons are short and entirely confined to the gray substance, in which they break up into numerous fine filaments. Most of the nerve cells are arranged in longitudinal column, and appear as groups on transverse section (Figs. 688, 689).

**Nerve Cells in the Anterior Column.**—The nerve cells in the anterior column are arranged in columns of varying length. The longest occupies the medial part of

<sup>1</sup> Lenhossek and Cajal found that in the chick embryo the axons of a few of these nerve cells passed backward through the posterior column, and emerged as the *motor fibres* of the *posterior nerve roots*. These fibres are said to control the peristaltic movements of the intestine. Their presence, in man, has not yet been determined.



the anterior column, and is named the **antero-medial column**: it is absent only in the fifth lumbar, the first sacral and the upper part of the second sacral segments (Bruce).<sup>1</sup> Behind it is a **dorso-medial column** of small cells, which extends from the second thoracic to the first lumbar segment, and is also present in the first, sixth, and seventh cervical segments.




FIG. 688.—Mode of distribution of the nerve cells in the gray substance. (Schematic.) (Testut.) 1, 2. Medial and lateral groups of nerve cells in anterior column. 3. Nerve cells in lateral column. 4, 4'. Dorsal nucleus. 5. Group of nerve cells in substantia gelatinosa of Rolando. 6. Nerve cell of anterior column, the axon of which is passing into the posterior nerve root. 7. Cells of substantia gelatinosa centralis. 8, 8'. Solitary cells. 9. Cells of Golgi. 10. Cells of origin of the superficial antero-lateral fasciculus. 11. Anterior root. 12. Posterior root. 13. Spinal ganglion.

In the cervical and lumbar enlargements, where the anterior column is expanded in a lateral direction, the following additional columns are present, viz.: (a) **antero-lateral**, in the fourth, fifth, and sixth cervical and the second thoracic segments, and in the lower four lumbar and upper two sacral segments; (b) **postero-lateral**, in the lower five cervical, lower four lumbar, and upper three sacral segments; (c) **post-postero-lateral**, in the last cervical, first thoracic, and upper three sacral segments; and (d) a **central**, in the lower four lumbar and upper two sacral segments. Throughout the base of the anterior column are scattered solitary cells, the axons of some of which form crossed commissural fibres, while others constitute the motor fibres of the posterior nerve roots. (See footnote, page 811.)

**Nerve Cells in the Lateral Column.**—These form a column which is best marked where the lateral gray column is differentiated, viz., in the thoracic region;<sup>2</sup> but it can be traced throughout the entire length of the medulla spinalis in the form of groups of small cells which are situated in the anterior part of the formatio reticularis. The cells of this column are fusiform or star-shaped, and of a medium size: the axons of some of them pass into the anterior nerve roots, by which they are carried to the sympathetic nerves; while the axons of others pass into the anterior and lateral funiculi, where they become longitudinal.

<sup>1</sup> Topographical Atlas of the Spinal Cord, 1901.

<sup>2</sup> According to Bruce and Pirie (B. M. J., November 17, 1906) this column extends from the middle of the eighth cervical segment to the lower part of the second lumbar or the upper part of the third lumbar segment.



**Nerve Cells in the Posterior Column.**—1. The **dorsal nucleus** (*nucleus dorsalis*; *column of Clarke*) occupies the medial part of the base of the posterior column, and appears on the transverse section as a well-defined oval area. It begins below at the level of the second or third lumbar nerve, and reaches its maximum size opposite the twelfth thoracic nerve. Above the level of the ninth thoracic nerve its size diminishes, and the column ends opposite the last cervical or first thoracic nerve. It is represented, however, in the other regions by scattered cells, which become aggregated to form a **cervical nucleus** opposite the third cervical nerve, and a **sacral nucleus** in the middle and lower part of the sacral region. Its cells are of medium size, and of an oval or pyriform shape; their axons pass into the peripheral part of the lateral funiculus of the same side, and there ascend, under the name of the **cerebellospinal** (*direct cerebellar*) **fasciculus**. 2. The **nerve cells in the substantia gelatinosa of Rolando** are arranged in three zones: a posterior or marginal, of large angular or fusiform cells; an intermediate, of small fusiform cells; and an anterior, of star-shaped cells. The axons of these cells pass into the lateral and posterior funiculi, and there assume a vertical course. In the anterior zone some Golgi cells are found whose short axons ramify in the gray substance. 3. **Solitary cells** of varying form and size are scattered throughout the posterior column. Some of these are grouped to form the **posterior basal column** in the base of the posterior column, lateral to the dorsal nucleus; the posterior basal column is well-marked in the gorilla (Waldeyer), but is ill-defined in man. The axons of its cells pass partly to the posterior and lateral funiculi of the same side, and partly through the anterior white commissure to the lateral funiculus of the opposite side. Before leaving the gray substance, a considerable number run longitudinally for a varying distance in the head of the posterior column, forming what is termed the **longitudinal fasciculus** of the posterior column.




FIG. 689.—Transverse sections of the medulla spinalis at different levels to show the arrangement of the principal cell columns.

A few star-shaped or fusiform nerve cells of varying size are found in the *substantia gelatinosa centralis*. Their axons pass into the lateral funiculus of the same, or of the opposite side.

The nerve fibres in the gray substance form a dense interlacement of minute fibrils among the nerve cells. This interlacement is formed partly of axons which pass from the cells in the gray substance to enter the white funiculi or nerve roots; partly of the axons of Golgi's cells which ramify only in the gray substance; and partly of collaterals from the nerve fibres in the white funiculi which, as already stated, enter the gray substance and ramify within it.




FIG. 690.—Diagram of the principal fasciculi in the medulla spinalis.

**White Substance (*substantia alba*).**—The white substance of the medulla spinalis consists of medullated nerve fibres imbedded in a sponge-like net-work of neuroglia, and is arranged in three funiculi: anterior, lateral, and posterior. The anterior funiculus lies between the anterior median fissure and the most lateral of the anterior nerve roots; the lateral funiculus between these nerve roots and the posterolateral sulcus; and the posterior funiculus between the posterolateral and the posterior median sulci (Fig. 690). The fibres vary greatly in thickness, the smallest being found in the fasciculus gracilis, the tract of Lissauer, and inner part of the lateral funiculus; while the largest are situated in the anterior funiculus, and in the peripheral part of the lateral funiculus. Some of the nerve fibres assume a more or less transverse direction, as for example those which cross from side to side in the anterior white commissure, but the majority pursue a longitudinal course and are divisible into (1) those connecting the medulla spinalis with the brain and conveying impulses to or from the latter, and (2) those which are confined to the medulla spinalis and link together its different segments, *i. e.*, intersegmental or association fibres.

**Nerve Fasciculi.**—The longitudinal fibres are grouped into more or less definite bundles or fasciculi. These are not recognizable from each other in the normal

state, and their existence has been determined by the following methods: (1) A. Waller discovered that if a bundle of nerve fibres be cut, the portions of the fibres which are separated from their cells rapidly degenerate and become atrophied, while the cells and the parts of the fibres connected with them undergo little alteration.<sup>1</sup> This is known as **Wallerian degeneration**. Similarly, if a group of nerve cells be destroyed, the fibres arising from them undergo degeneration. Thus, if the motor cells of the cerebral cortex be destroyed, or if the fibres arising from these cells be severed, a **descending degeneration** from the seat of injury takes place in the fibres. In the same manner, if a spinal ganglion be destroyed, or the fibres which pass from it into the medulla spinalis be cut, an **ascending degeneration** will extend along these fibres. (2) By tracing the development of the nervous system, it has been observed that at first the nerve fibres are merely naked axis-cylinders, and that they do not all acquire their medullary sheaths at the same time; hence the fibres can be grouped into different bundles according to the dates at which they receive their medullary sheaths. (3) Various methods of staining nervous tissue are of great value in tracing the course and mode of termination of the axis-cylinder processes.

**Fasciculi in the Anterior Funiculus.**—The principal fasciculus is the **anterior cerebrospinal** (*fasciculus cerebrospinalis anterior; direct pyramidal tract*), which is usually small, but varies inversely in size with the lateral cerebrospinal fasciculus. It lies close to the anterior median fissure, and is present only in the upper part of the medulla spinalis; gradually diminishing in size as it descends, it ends about the middle of the thoracic region. It consists of descending fibres which arise from cells in the motor area of the cerebral hemisphere of the same side, and which, as they run downward in the medulla spinalis, cross in succession through the anterior white commissure to the opposite side, where they end by arborizing around the motor cells in the anterior column.

In addition to the anterior cerebrospinal fasciculus there are strands of fibres in the anterior funiculus connecting certain ganglia in the brain with the gray substance of the medulla spinalis. The most important of these is the **vestibulospinal**, situated chiefly in the marginal part of the funiculus and mainly derived from the cells of Deiters' nucleus, *i. e.*, the chief terminal nucleus of the vestibular division of the acoustic nerve. Of the other descending fibres some pass downward from the corpora quadrigemina (**tectospinal**) and others are continuous with the medial longitudinal fasciculus.

The remaining fibres of the anterior funiculus constitute what is termed the **anterior proper fasciculus** (*fasciculus anterior proprius; anterior basis bundle*). It consists of (a) longitudinal intersegmental fibres which arise from cells in the gray substance, more especially from those of the medial group of the anterior column, and, after a longer or shorter course, reënter the gray substance; (b) fibres which cross in the anterior white commissure from the gray substance of the opposite side; (c) fibres arising from cells of the cerebellum and extending down the medulla spinalis to end around the cells of the anterior column—these fibres constitute an irregular tract, **cerebellospinal tract of Lowenthal**, disposed in the peripheral portions of the anterior and lateral proper fasciculi; and (d) fibres of the anterior nerve roots, which run obliquely forward to reach the surface of the medulla spinalis.

**Fasciculi in the Lateral Funiculus.**—1. **Descending Fasciculi.**—(a) The **lateral cerebrospinal fasciculus** (*fasciculus cerebrospinalis lateralis; crossed pyramidal tract*) extends throughout the entire length of the medulla spinalis, and on transverse section appears as an oval area in front of the posterior column and medial

<sup>1</sup> Somewhat later a change, termed *chromatolysis*, takes place in the nerve cells, and consists of a breaking down and an ultimate disappearance of the Nissl bodies. Further, the body of the cell is swollen, the nucleus displaced toward the periphery, and the part of the axon still attached to the altered cell is diminished in size and somewhat atrophied. Under favorable conditions the cell is capable of reassuming its normal appearance, and its axon may grow again.

to the cerebellospinal. Its fibres arise from cells in the motor area of the cerebral hemisphere of the opposite side. They pass downward in company with those of the anterior cerebrospinal fasciculus through the same side of the brain as that from which they originate, but they cross to the opposite side in the medulla oblongata and descend in the lateral funiculus of the medulla spinalis; they end by arborizing around the motor cells in the anterior column.<sup>1</sup>

The anterior and lateral cerebrospinal fasciculi constitute the motor fasciculi of the medulla spinalis and have their origins in the motor cells of the cerebral cortex. They descend through the internal capsule of the cerebrum, traverse the cerebral peduncles and pons and enter the pyramid of the medulla oblongata. In the lower part of the latter about two-thirds of them cross the middle line and run downward in the lateral funiculus as the lateral cerebrospinal fasciculus, while the remaining fibres do not cross the middle line, but are continued into the same side of the medulla spinalis, where they form the anterior cerebrospinal fasciculus. The fibres of the latter, however, cross the middle line in the anterior white commissure, and thus all the motor fibres from one side of the brain ultimately reach the opposite side of the medulla spinalis. The proportion of fibres which cross in the medulla oblongata is not a constant one, and thus the anterior and lateral cerebrospinal fasciculi vary inversely in size. Sometimes the former is absent, and in such cases it may be presumed that the decussation of the motor fibres in the medulla oblongata has been complete. The fibres of these two fasciculi do not acquire their medullary sheaths until after birth. In some animals the motor fibres are situated in the posterior funiculus.

(b) The **rubrospinal fasciculus** (Monakow) (*prepyramidal tract*), lies on the ventral aspect of the lateral cerebrospinal fasciculus and on transverse section appears as a somewhat triangular area. Its fibres descend from the mid-brain, where they have their origin in the red nucleus of the tegmentum of the opposite side.

(c) The **tectospinal fasciculus** originates in the superior colliculus (upper quadrigeminal body) of the opposite side, and its fibres are partly intermingled with those of the rubrospinal fasciculus, and are partly contained in the anterior funiculus.

(d) The **olivospinal fasciculus** (Helweg) arises in the vicinity of the inferior olivary nucleus in the medulla oblongata, and is seen only in the cervical region of the medulla spinalis, where it forms a small triangular area at the periphery, close to the most lateral of the anterior nerve roots. Its exact origin and its mode of ending have not yet been definitely made out.

2. **Ascending Fasciculi.**—(a) The **cerebellospinal fasciculus** (*fasciculus cerebellospinalis*; *direct cerebellar tract of Flechsig*) is situated at the periphery of the posterior part of the lateral funiculus, and on transverse section appears as a flattened band reaching as far forward as a line drawn transversely through the central canal. Medially, it is in contact with the lateral cerebrospinal fasciculus, behind, with the fasciculus of Lissauer. It begins about the level of the second or third lumbar nerve and, increasing in size as it ascends, passes to the cerebellum through the restiform body. Its fibres are generally regarded as being formed by the axons of the cells of the dorsal nucleus (Clarke's column); they receive their medullary sheaths about the sixth or seventh month of fetal life.

(b) The **superficial antero-lateral fasciculus** (*fasciculus anterolateralis superficialis*; *tract of Gowers*) skirts the periphery of the lateral funiculus in front of the cerebellospinal fasciculus. In transverse section it is shaped somewhat like a comma, the expanded end of which lies in front of the lateral cerebrospinal fasciculus while the tail reaches forward into the anterior funiculus. Its fibres come from the oppo-

<sup>1</sup> It is probable (Schäfer, Proc. Physiolog. Soc., 1899) that the fibres of the anterior and lateral cerebrospinal fasciculi are not related in this direct manner with the cells of the anterior column, but terminate by arborizing around the cells at the base of the posterior column and the cells of Clarke's column, which in turn link them to the motor cells in the anterior column, usually of several segments of the cord. In consequence of these interposed neurons the fibres of the cerebrospinal fasciculi correspond not to individual muscles, but to associated groups of muscles.

site side of the medulla spinalis and cross in the anterior white commissure; they are derived from the cells of the dorsal nucleus and from other cells of the posterior column. The superficial antero-lateral fasciculus begins about the level of the third pair of lumbar nerves, and, increasing in size as it ascends, can be followed into the medulla oblongata and pons. It consists of three fasciculi: (1) the **ventral spino-cerebellar**, the largest of the three, passes to the cerebellum by way of the brachia conjunctiva; (2) the **spinothalamic** ends in the thalamus, and is sometimes termed the **secondary sensory fasciculus**; and (3) the **spinotectal** passes to the corpora quadrigemina.

(c) The **fasciculus of Lissauer** is a small strand situated in relation to the tip of the posterior column close to the entrance of the posterior nerve roots. It consists of fine fibres which do not receive their medullary sheaths until toward the close of fetal life. It is usually regarded as being formed by some of the fibres of the posterior nerve roots, which ascend for a short distance in the tract and then enter the posterior column, but since its fibres are myelinated later than those of the posterior nerve roots, and do not undergo degeneration in locomotor ataxia, they are probably intersegmental in character.

(d) The **lateral proper fasciculus** (*fasciculus lateralis proprius*; *lateral basis bundle*) constitutes the remainder of the lateral column, and is continuous in front with the anterior proper fasciculus. It consists chiefly of intersegmental fibres which arise from cells in the gray substance, and, after a longer or shorter course, reënter the gray substance and ramify in it. Some of its fibres are, however, continued upward into the brain under the name of the **medial longitudinal fasciculus**.

**Fasciculi in the Posterior Funiculus.**—This funiculus comprises two main fasciculi, viz., the **fasciculus gracilis**, and the **fasciculus cuneatus**. These are separated from each other in the cervical and upper thoracic regions by the postero-intermediate septum, and consist mainly of ascending fibres derived from the posterior nerve roots.

The **fasciculus gracilis** (*tract of Goll*) is wedge-shaped on transverse section, and lies next the posterior median septum, its base being at the surface of the medulla spinalis, and its apex directed toward the posterior gray commissure. It increases in size from below upward, and consists of long thin fibres which are derived from the posterior nerve roots, and ascend as far as the medulla oblongata, where they end in the nucleus gracilis.

The **fasciculus cuneatus** (*tract of Burdach*) is triangular on transverse section, and lies between the fasciculus gracilis and the posterior column, its base corresponding with the surface of the medulla spinalis. Its fibres, larger than those of the fasciculus gracilis, are mostly derived from the same source, viz., the posterior nerve roots. Some ascend for only a short distance in the tract, and, entering the gray matter, come into close relationship with the cells of the dorsal nucleus; while others can be traced as far as the medulla oblongata, where they end in the gracile and cuneate nuclei.

Occupying the ventral part of the posterior funiculus is a strand of fibres termed the **cornu-commissural fasciculus**. It is somewhat triangular on transverse section, and occupies the angle between the posterior gray commissure and the posterior column. It is best marked in the lumbar region, but can be traced into the thoracic and cervical regions. Its fibres, derived from the cells of the posterior column, divide into ascending and descending branches which reënter and ramify in the gray substance. It has been found to preserve its integrity in certain cases of locomotor ataxia.

**Descending Fibres in the Posterior Funiculus** (Fig. 692).—The posterior funiculus contains some descending fibres which occupy different parts at different levels. In the cervical and upper thoracic regions, they appear as a **comma-shaped fasciculus** in the lateral part of the fasciculus cuneatus, the blunt end of the comma being



directed toward the posterior gray commissure; in the lower thoracic region they form a **dorsal peripheral band** on the posterior surface of the funiculus; in the lumbar region, they are situated by the side of the posterior median septum, and appear on section as a semi-elliptical bundle, which, together with the corresponding bundle of the opposite side, forms the **oval area of Flechsig**; while in the conus medullaris they assume the form of a **triangular strand** in the postero-medial part




FIG. 691.—Formation of the fasciculus gracilis. (Poirier.) Medulla spinalis viewed from behind. To the left, the fasciculus gracilis is shaded. To the right, the drawing shows that the fasciculus gracilis is formed by the long fibres of the posterior roots, and that in this tract the sacral nerves lie next the median plane, the lumbar to their lateral side, and the thoracic still more laterally.




FIG. 692.—Descending fibres in the posterior funiculi, shown at different levels. (After Testut.) A. In the conus medullaris. B. In the lumbar region. C. In the lower thoracic region. D. In the upper thoracic region.

of the fasciculus gracilis. These descending fibres are mainly intersegmental in character and derived from cells in the posterior column, but some consist of the descending branches of the posterior nerve roots. The comma-shaped fasciculus was supposed to belong to the second category, but against this view is the fact that it does not undergo descending degeneration when the posterior nerve roots are destroyed.

**Roots of the Spinal Nerves.**—As already stated, each spinal nerve possesses two roots, an **anterior** and a **posterior**, which are attached to the surface of the

medulla spinalis opposite the corresponding column of gray substance (Fig. 693); their fibres become medullated about the fifth month of fetal life.

The **Anterior Nerve Root** (*radix anterior*) consists of efferent fibres, which are the axons of the nerve cells in the ventral part of the anterior column. A short distance from their origins, these axons are invested by medullary sheaths and, passing forward, emerge in two or three irregular rows over an area which measures about 3 mm. in width.

The **Posterior Root** (*radix posterior*) comprises some six or eight fasciculi, attached in linear series along the postero-lateral sulcus. It consists of afferent fibres which arise from the nerve cells in a spinal ganglion. Each ganglion cell gives off a single fibre which divides in a T-shaped manner into two processes, medial and lateral. The medial processes of the ganglion cells grow into the medulla spinalis as the posterior roots of the spinal nerves, while the lateral are directed toward the periphery.




FIG. 693.—A spinal nerve with its anterior and posterior roots. (Testut.) 1. A portion of the medulla spinalis, viewed from the left side. 2. Anterior median fissure. 3. Anterior column. 4. Posterior column. 5. Lateral column. 6. Formatio reticularis. 7. Anterior root. 8. Posterior root, with 8', its ganglion. 9. Spinal nerve; 9', its posterior division.




FIG. 694.—Posterior roots entering medulla spinalis and dividing into ascending and descending branches. (Van Gehuchten.) a. Stem fibre. b, b. Ascending and descending limbs of bifurcation. c. Collateral arising from stem fibre.

The posterior nerve root enters the medulla spinalis in three chief bundles, medial, intermediate, and lateral. The **medial** strand passes directly into the fasciculus cuneatus: it consists of coarse fibres, which acquire their medullary sheaths about the fifth month of intrauterine life; the **intermediate** strand consists of coarse fibres, which enter the gelatinous substance of Rolando; the **lateral** is composed of fine fibres, which assume a longitudinal direction in the tract of Lissauer, and do not acquire their medullary sheaths until after birth.

Having entered the medulla spinalis, all the fibres of the posterior nerve roots divide into ascending and descending branches, and these in their turn give off collaterals which enter the gray substance (Fig. 694). The descending fibres are short, and soon enter the gray substance. The ascending fibres are grouped into long, short, and intermediate: the long fibres ascend in the fasciculus cuneatus and fasciculus gracilis as far as the medulla oblongata, where they end by arborizing around the cells of the cuneate and gracile nuclei; the short fibres run upward for a distance of only 5 or 6 mm. and enter the gray substance; while the inter-

mediate fibres, after a somewhat longer course, have a similar destination. All fibres entering the gray substance end by arborizing around its nerve cells, those of intermediate length being especially associated with the cells of the dorsal nucleus.

The fibres of the posterior nerve roots pursue an oblique course upward, being situated at first in the lateral part of the fasciculus cuneatus: higher up, they occupy the middle of this fasciculus, having been displaced by the accession of other entering fibres; while still higher, they ascend in the fasciculus gracilis. The upper cervical fibres do not reach this fasciculus, but are entirely confined to the fasciculus cuneatus. The localization of these fibres is very precise: the sacral nerves lie in the medial part of the fasciculus gracilis and near its periphery, the lumbar nerves lateral to them, the thoracic nerves still more laterally; while the cervical nerves are confined to the fasciculus cuneatus (Fig. 691).

The development of the medulla spinalis is described in the section on Embryology (pages 117 to 120).

**Applied Anatomy.**—Several cases have been recorded<sup>1</sup> in which a local doubling of the medulla spinalis has taken place. The condition is probably due to some interference with the development of the neural tube in the embryo; in a few it was associated with spina bifida, while in one recent case<sup>2</sup> the two parts were separated by a dermoid tumor. Other *congenital abnormalities* of the medulla spinalis occur in connection with spina bifida (see p. 214), and also in *syringomyelia*. In this latter chronic condition an abnormal proliferation of the neuroglia takes place, generally near the central canal and in the cervical enlargement, and later this mass becomes absorbed, leaving an irregular cavity in its place. This gives rise to a number of interesting signs and symptoms, such as analgesia (or insensitiveness to pain), inability to distinguish between cold and heat, progressive atrophy in the muscles of the hands and arms, trophic changes in the bones and joints, and painless whitlows. Severe *injuries* to the medulla spinalis may occur in fractures or fracture-dislocations of the vertebral column anywhere above the second lumbar vertebra. If the medulla spinalis is completely crushed or torn across, total paralysis and anesthesia of all parts of the body drawing their nerve supply from below the injured spot will follow, with loss of control over the actions of the bladder and rectum. The higher up such a lesion occurs, the worse the prognosis. Thus, when the medulla spinalis is crushed by fracture of the atlas or axis, the vital centres in the medulla oblongata are injured, and death occurs at once. If the origin of the phrenic nerve—mainly the fourth cervical—just escape in a case where the neck is broken, respiration will have to be carried on by the Diaphragm alone, and death is likely to ensue before long from pulmonary complications. When the back is broken in the lower thoracic region, life is not immediately threatened; but unless the patient is carefully nursed, death may follow at any time from the development of bed-sores in the anesthetic area, or from septic infection spreading up the ureters into the kidneys and secondary to the cystitis that is so prone to occur in patients who have no control over the bladder. *Inflammation* of the medulla spinalis, or *spinal myelitis*, sometimes follows influenza or one of the acute specific fevers. A transverse patch of such myelitis extending completely across the medulla spinalis produces more or less complete interruption of the passage of nervous impulses through it. Hence it will occasion more or less complete paralysis and anesthesia of the parts of the body obtaining their nerve supply from below it, and, in addition, a zone of cutaneous hyperesthesia at its level, in consequence of the irritation of the sensory fibres entering the inflamed region of the medulla spinalis. The disease mainly attacking children, and known as *infantile spinal paralysis*, or *acute anterior poliomyelitis*, is a bacterial infection of the pia mater that spreads into the medulla spinalis along the bloodvessels, and destroys groups of the motor neurons aggregated in the anterior column. Destruction of the cells causes rapid and permanent paralysis of the muscles innervated, and groups of muscles in one or more of the limbs are commonly picked out for attack. The affected limbs are thus partially paralyzed, and their subsequent growth and nutrition both suffer. Further, the muscles that normally antagonize the affected groups of muscles, finding their actions unopposed, tend to assume a state of spastic contraction. In consequence, much dwarfing and deformity follow later, and may demand for their relief such operations as tenotomy, the transplantation of tendons, or even amputation.

Inflammation of the ganglia on one or more of any of the posterior nerve roots is the cause of *shingles*<sup>3</sup> or herpes zoster, in which there is a painful eruption of groups of cutaneous vesicles corresponding to the distribution of the nerves derived from the affected ganglia. It is com-

<sup>1</sup> For an analysis of these cases consult paper by Bruce, Stuart McDonald, and Pirie, *Review of Neurology and Psychiatry*, January, 1906.

<sup>2</sup> Harriehausen, *D. Ztschrift. f. Nervenheilk.*, Band xxxvi, Heft 3 and 4, S. 268.

<sup>3</sup> From Lat. *cingulum*, a belt.

monest along the course of the intercostal nerves; the eruption is often preceded and followed, as well as accompanied, by girdle pains, and in old people these may be prolonged and serious in character. Herpes is the analogue on the sensory side to anterior poliomyelitis on the motor side of the nervous system.

### THE ENCEPHALON OR BRAIN.

**Dissection.**—To examine the brain with its membranes, the skull-cap must be removed. In order to effect this, saw through the external table, the section commencing, in front, about 2 cm. ( $\frac{1}{2}$  inch) above the margin of the orbits, and extending, behind, to a little above the level of the occipital protuberance. Then break the internal table with the chisel and hammer, to avoid injuring the investing membranes or brain; loosen and forcibly detach the skull-cap, and the dura will be exposed. The adhesion between the bone and the dura often is very intimate, particularly along the sutures.

**General Considerations and Divisions.**—The encephalon, or brain, is contained within the cranium, and constitutes the upper, greatly expanded part of the central nervous system. In its early embryonic condition it consists of three hollow vesicles, termed the **rhombencephalon** or **hind-brain**, the **mesencephalon** or **mid-brain**, and the **prosencephalon** or **fore-brain**; and the parts derived from each of these can be recognized in the adult (Fig. 695). Thus in the process of development the wall of the rhombencephalon undergoes modification to form the medulla oblongata, the pons, and cerebellum, while its cavity is expanded to form the fourth ventricle. The mesencephalon forms only a small part of the adult brain; its cavity becomes the **cerebral aqueduct** (*aqueduct of Sylvius*), which serves as a tubular communication between the third and fourth ventricles; while its walls are thickened to form the corpora quadrigemina and cerebral peduncles. The prosencephalon undergoes great modification: its anterior part or **telencephalon** expands laterally in the form of two hollow vesicles, the cavities of which become the lateral ventricles, while the surrounding walls form the cerebral hemispheres and their commissures; the cavity of the posterior part or **diencephalon** forms the greater part of the third ventricle, and from its walls are developed most of the structures which bound that cavity. Further details regarding these important changes are given in the section on Embryology (pages 120 to 132).




FIG. 695.—Scheme showing the connections of the several parts of the brain. (After Schwalbe.)

### THE RHOMBENCEPHALON OR HIND-BRAIN.

The **rhombencephalon** or **hind-brain** occupies the posterior fossa of the cranial cavity and lies below a fold of dura mater, the **tentorium cerebelli**. It consists of (a) the **myelencephalon**, comprising the medulla oblongata and the lower part of the fourth ventricle; (b) the **metencephalon**, consisting of the pons, cerebellum, and the intermediate part of the fourth ventricle; and (c) the **isthmus rhombencephali**, a constricted portion immediately adjoining the mesencephalon and includ-

ing the brachia, conjunctiva of the cerebellum, the anterior medullary velum, and the upper part of the fourth ventricle.

**The Medulla Oblongata** (*spinal bulb*).—The medulla oblongata is the lowest and smallest division of the brain; its structure, however, is extremely complex, since it gives attachment to many of the cerebral nerves, and forms the connecting link between the medulla spinalis below and the cerebrum and cerebellum above.

It extends from the lower margin of the pons to a plane passing transversely below the pyramidal decussation and above the first pair of cervical nerves; this plane corresponds with the upper border of the atlas behind, and the middle of the odontoid process of the epistropheus or axis in front; at this level the medulla oblongata is continuous with the medulla spinalis. Its anterior surface is separated from the basilar part of the occipital bone and the upper part of the odontoid process by the membranes of the brain and the occipitoaxial ligaments. Its posterior surface is received into the fossa between the hemispheres of the cerebellum, and the upper portion of it forms the lower part of the floor of the fourth ventricle. The vertebral arteries pass upward and forward in relation to its lateral surfaces; they then curve forward on to its anterior surface and unite at the lower border of the pons to form the basilar artery.

The medulla oblongata is pyramidal in shape, its broad extremity being directed upward toward the pons, while its narrow, lower end is continuous with the medulla spinalis. It measures about 3 cm. in length, about 2 cm. in breadth at its widest part, and about 1.25 cm. in thickness. The central canal of the medulla spinalis is prolonged into its lower half, and then opens into the cavity of the fourth ventricle; the medulla oblongata may therefore be divided into a lower *closed part* containing the central canal, and an upper *open part* corresponding with the lower portion of the fourth ventricle. Its anterior and posterior surfaces are marked by median fissures.

The **Anterior Median Fissure** (*fissura mediana anterior; ventral or ventromedian fissure*) contains a fold of pia mater, and extends along the entire length of the medulla oblongata: it ends at the lower border of the pons in a small triangular expansion, termed the **foramen caecum**. Its lower part is interrupted by bundles of fibres which cross obliquely from one side to the other, and constitute the **pyramidal decussation**. Some fibres, termed the **anterior external arcuate fibres**, emerge from the fissure above this decussation and curve lateralward and upward over the surface of the medulla oblongata.

The **Posterior Median Fissure** (*fissura mediana posterior; dorsal or dorsomedian fissure*) is a narrow groove; and exists only in the closed part of the medulla oblongata; it becomes gradually shallower from below upward, and finally ends about the middle of the medulla oblongata, where the central canal expands into the cavity of the fourth ventricle.

These two fissures divide the closed part of the medulla oblongata into symmetrical halves, each presenting elongated eminences which, on surface view, are continuous with the funiculi of the medulla spinalis. In the open part the halves are separated by the anterior median fissure, and by a median **raphe** which extends from the bottom of the fissure to the floor of the fourth ventricle. Further, certain of the cerebral nerves pass through the substance of the medulla oblongata, and are attached to its surface in series with the roots of the spinal nerves; thus, the fibres of the hypoglossal nerve represent the upward continuation of the anterior nerve roots, and emerge in linear series from a furrow termed the **antero-lateral sulcus**. Similarly, the accessory, vagus, and glossopharyngeal nerves correspond with the posterior nerve roots, and are attached to the bottom of a sulcus named the **postero-lateral sulcus**. Advantage is taken of this arrangement to subdivide each half of the medulla oblongata into three districts, **anterior, middle, and posterior**. Although these three districts appear to be directly continuous



with the corresponding funiculi of the medulla spinalis, they do not necessarily contain the same fibres, since some of the fasciculi of the medulla spinalis end in the medulla oblongata, while others alter their course in passing through it.

The **anterior district** (Fig. 696) is named the **pyramid** (*pyramis medullae oblongatae*) and lies between the anterior median fissure and the antero-lateral sulcus. Its upper end is slightly constricted, and between it and the pons the fibres of the abducent nerve emerge; a little below the pons it becomes enlarged and prominent, and finally tapers into the anterior funiculus of the medulla spinalis, with which, at first sight, it appears to be directly continuous.

The two pyramids contain the motor fibres which pass from the brain to the medulla spinalis. When these pyramidal fibres are traced downward it is found that some two-thirds or more of them




FIG. 696.—Medulla oblongata and pons. Anterior surface.




FIG. 697.—Decussation of pyramids. Scheme showing passage of various fasciculi from medulla spinalis to medulla oblongata. (Testut.) a. Pons. b. Medulla oblongata. c. Decussation of the pyramids. d. Section of cervical part of medulla spinalis. 1. Anterior cerebrospinal fasciculus (in red). 2. Lateral cerebrospinal fasciculus (in red). 3. Sensory tract (fasciculi gracilis et cuneatus) (in blue). 3'. Gracile and cuneate nuclei. 4. Antero-lateral proper fasciculus (in dotted line). 5. Pyramid. 6. Lemniscus. 7. Medial longitudinal fasciculus. 8. Superficial antero-lateral fasciculus (in blue). 9. Cerebellospinal fasciculus (in yellow).

leave the pyramids in successive bundles, and decussate in the anterior median fissure, forming what is termed the **pyramidal decussation**. Having crossed the middle line, they pass down in the posterior part of the lateral funiculus as the lateral cerebrospinal fasciculus. The remaining fibres—i. e., those which occupy the lateral part of the pyramid—do not cross the middle line, but are carried downward as the anterior cerebrospinal fasciculus (Fig. 697) into the anterior funiculus of the same side.

The greater part of the anterior proper fasciculus of the medulla spinalis is continued upward through the medulla oblongata under the name of the **medial longitudinal fasciculus**.

The **lateral district** (Fig. 698) is limited in front by the antero-lateral sulcus and the roots of the hypoglossal nerve, and behind by the postero-lateral sulcus and the roots of the accessory, vagus, and glossopharyngeal nerves. Its upper part consists of a prominent oval mass which is named the **olive**, while its lower part

is of the same width as the lateral funiculus of the medulla spinalis, and appears on the surface to be a direct continuation of it. As a matter of fact, only a portion of the lateral funiculus is continued upward into this district, for the lateral cerebro-spinal fasciculus passes into the pyramid of the opposite side, and the cerebello-spinal fasciculus is carried into the restiform body in the posterior district. The remainder of the lateral funiculus, which consists chiefly of the lateral proper fasciculus and the superficial antero-lateral fasciculus can be traced into the lateral district. Most of these fibres dip beneath the olive and disappear from the surface; but a small strand remains superficial, and ascends between the olive and the postero-lateral sulcus. In a depression at the upper end of this strand is the acoustic nerve.




FIG. 698.—Hind- and mid-brains; postero-lateral view.

The **olive** (*oliva*; *olivary body*) is situated lateral to the pyramid, from which it is separated by the antero-lateral sulcus, and the fibres of the hypoglossal nerve. Behind, it is separated from the postero-lateral sulcus by the small superficial strand of the lateral funiculus already referred to. It measures about 1.25 cm. in length, and between its upper end and the pons there is a slight depression to which the roots of the facial nerve are attached. The external arcuate fibres wind across the lower part of the pyramid and olive and enter the restiform body.

The **posterior district** (Fig. 699) lies behind the postero-lateral sulcus and the roots of the accessory, vagus, and the glossopharyngeal nerves, and, like the lateral district, is divisible into a lower and an upper portion.

The **lower part** is limited behind by the posterior median fissure, and consists of the **fasciculus gracilis** and the **fasciculus cuneatus**. The fasciculus gracilis is placed parallel to and along the side of the posterior median fissure, and separated from the fasciculus cuneatus by the postero-intermediate sulcus and septum. The gracile and cuneate fasciculi are at first vertical in direction; but at the lower part of the rhomboid fossa they diverge from the middle line in a V-shaped manner, and each presents an elongated swelling. That on the fasciculus gracilis is named the **clava**, and is produced by a subjacent nucleus of gray matter, the **nucleus**

**gracilis**; that on the fasciculus cuneatus is termed the **cuneate tubercle**, and is likewise caused by a gray nucleus, named the **nucleus cuneatus**. The fibres of these fasciculi terminate by arborizing around the cells in their respective nuclei. A third elevation, produced by the substantia gelatinosa of Rolando, is present in the lower part of the posterior district of the medulla oblongata. It lies on the lateral aspect of the fasciculus cuneatus, and is separated from the surface of the medulla oblongata by a band of nerve fibres which form the spinal tract (spinal root) of the trigeminal nerve. Narrow below, this elevation gradually expands above, and ends, about 1.25 cm. below the pons, in a tubercle, the **tubercle of Rolando** (*tuber cinereum*).




FIG. 699.—Upper part of medulla spinalis and hind- and mid-brains; posterior aspect, exposed *in situ*.

The upper part of the posterior district of the medulla oblongata is occupied by the **restiform body**, a thick rope-like strand situated between the lower part of the fourth ventricle and the roots of the glossopharyngeal and vagus nerves. The restiform bodies connect the medulla spinalis and medulla oblongata with the cerebellum, and are sometimes named the **inferior peduncles of the cerebellum**. As they pass upward, they diverge from each other, and assist in forming the lower part of the lateral boundaries of the fourth ventricle; higher up, they are directed backward, each passing to the corresponding cerebellar hemisphere. Near their entrance into the cerebellum they are crossed by several strands of fibres, which run to the median sulcus of the rhomboid fossa, and are named the **striae medullares**.



The restiform body appears to be the upward continuation of the fasciculus gracilis and fasciculus cuneatus; this, however, is not so, as the fibres of these fasciculi end in the gracile and cuneate nuclei. The constitution of the restiform body will be subsequently discussed.

**Internal Structure of the Medulla Oblongata.**—Although the external form of the medulla oblongata bears a certain resemblance to that of the upper part of the medulla spinalis, its internal structure differs widely from that of the latter, and this for the following principal reasons: (1) certain fasciculi which extend from the medulla spinalis to the brain, and *vice versa*, undergo a rearrangement in their passage through the medulla oblongata; (2) others which exist in the medulla spinalis end in the medulla oblongata; (3) new fasciculi originate in the gray substance of the medulla oblongata and pass to different parts of the brain; (4) the gray substance, which in the medulla spinalis forms a continuous H-shaped column, becomes greatly modified and subdivided in the medulla oblongata, where also new masses of gray substance are added; (5) on account of the opening out of the central canal




FIG. 700.—Section of the medulla oblongata through the lower part of the decussation of the pyramids. (Testut.) 1. Anterior median fissure. 2. Posterior median sulcus. 3. Anterior column (in red), with 3', anterior root. 4. Posterior column (in blue), with 4', posterior root. 5. Lateral cerebrospinal fasciculus. 6. Posterior funiculus. The red arrow, *a, a'*, indicates the course the lateral cerebrospinal fasciculus takes at the level of the decussation of the pyramids; the blue arrow, *b, b'*, indicates the course which the sensory fibres take.




FIG. 701.—Section of the medulla oblongata at the level of the decussation of the pyramids. (Testut.) 1. Anterior median fissure. 2. Posterior median sulcus. 3. Motor roots. 4. Sensory roots. 5. Base of the anterior column, from which the head (5') has been detached by the lateral cerebrospinal fasciculus. 6. Decussation of the lateral cerebrospinal fasciculus. 7. Posterior columns (in blue). 8. Gracile nucleus.

of the medulla spinalis, certain parts of the gray substance, which in the medulla spinalis were more or less centrally situated, are displayed in the rhomboid fossa; (6) the medulla oblongata is intimately associated with many of the cerebral nerves, some arising from, and others ending in, nuclei within its substance.

The internal structure of the medulla oblongata is best studied in series of transverse (Figs. 704, 705) and of longitudinal sections. A short description of the course taken by the principal fasciculi, and of the arrangement of the gray substance, will now be given.

**The Cerebrospinal Fasciculi.**—The downward course of these fasciculi from the pyramids of the medulla oblongata and their partial decussation have already been described (page 816). In crossing to reach the lateral funiculus of the opposite side, the fibres of the lateral cerebrospinal fasciculi extend backward through the anterior columns, and separates the head of each of these columns from its base (Figs. 700, 701). The base retains its position in relation to the ventral aspect of the central canal, and, when the latter opens into the fourth ventricle, appears in the rhomboid fossa close to the middle line, where it forms the nuclei of the hypoglossal and abducent nerves; while above the level of the ventricle it exists as the nuclei of the trochlear and oculomotor nerves in relation to the floor of the cerebral aqueduct. The head of the column is pushed lateralward and forms the **nucleus ambiguus**, which gives origin from below upward to the cerebral part

of the accessory and the motor fibres of the vagus and glossopharyngeal, and still higher to the motor fibres of the facial and trigeminal nerves.

The *fasciculus gracilis* and *fasciculus cuneatus* constitute the posterior sensory fasciculi of the medulla spinalis; they are prolonged upward into the lower part of the medulla oblongata, where they end respectively in the nucleus gracilis and nucleus cuneatus. These two nuclei are continuous with the central gray substance of the medulla spinalis, and may be regarded as dorsal projections of this, each being covered superficially by the fibres of the corresponding fasciculus. On

transverse section (Fig. 704) the nucleus gracilis appears as a single, more or less quadrangular mass, while the nucleus cuneatus consists of two parts: a larger, somewhat triangular, **medial nucleus**, composed of small or medium-sized cells, and a smaller **lateral nucleus** containing large cells.

The fibres of the *fasciculus gracilis* and *fasciculus cuneatus* end by arborizing




FIG. 702.—Superior terminations of the posterior fasciculi of the medulla spinalis. (Testut.) 1. Posterior median sulcus. 2. Fasciculus gracilis. 3. Fasciculus cuneatus. 4. Gracile nucleus. 5. Cuneate nucleus. 6, 6', 6''. Sensory fibres forming the lemniscus. 7. Sensory decussation. 8. Cerebellar fibres uncrossed (in black). 9. Cerebellar fibres crossed (in black).




FIG. 703.—Transverse section passing through the sensory decussation. (Schematic.) (Testut.) 1. Anterior median fissure. 2. Posterior median sulcus. 3, 3. Head and base of anterior column (in red). 4. Hypoglossal nerve. 5. Bases of posterior columns. 6. Gracile nucleus. 7. Cuneate nucleus. 8, 8. Lemniscus. 9. Sensory decussation. 10. Cerebrospinal fasciculus.

around the cells of these nuclei (Fig. 702). From the cells of the nuclei new fibres arise; some of these are continued as the posterior external arcuate fibres into the restiform body, and through it to the cerebellum, but most of them pass forward through the neck of the posterior column, thus cutting off its head from its base (Fig. 703). Curving forward, they decussate in the middle line with the corresponding fibres of the opposite side, and run upward immediately behind the cerebrospinal fibres, as a flattened band, named the **lemniscus** or **fillet**. The decussation of these sensory fibres is situated above that of the motor fibres, and is named the **decussation of the lemniscus** or **sensory decussation**. The **lemniscus** is joined by the spinothalamic fasciculus (page 817), the fibres of which are derived from the cells of the gray substance of the opposite side of the medulla spinalis.

The base of the posterior column at first lies on the dorsal aspect of the central canal, but when the latter opens into the fourth ventricle, it appears in the lateral part of the rhomboid fossa. It forms the terminal nuclei of the sensory fibres of the vagus and glossopharyngeal nerves, and is associated with the vestibular part of the acoustic nerve and the sensory root of the facial nerve. Still higher, it forms a mass of pigmented cells—the **locus coeruleus**—in which some of the sensory fibres



of the trigeminal nerve appear to end. The head of the posterior column forms a long nucleus, in which the fibres of the spinal tract of the trigeminal nerve largely end.




FIG. 704.—Section of the medulla oblongata at about the middle of the olive. (Schwalbe.)




FIG. 705.—Transverse section of medulla oblongata below the middle of the olive.

The **cerebellospinal fasciculus** (*fasciculus cerebellospinalis*; *direct cerebellar tract*) leaves the lateral district of the medulla oblongata; most of its fibres are carried backward into the restiform body of the same side, and through it are conveyed

to the cerebellum; but some run upward with the fibres of the lemniscus, and, reaching the inferior colliculus, undergo decussation, and are carried to the cerebellum through the brachium conjunctivum.

The **proper fasciculi** (*basis bundles*) of the anterior and lateral funiculi largely consist of intersegmental fibres, which link together the different segments of the medulla spinalis; they assist in the production of the formatio reticularis of the medulla oblongata, and many of them are accumulated into a fasciculus which runs up close to the median raphe between the lemniscus and the rhomboid fossa; this strand is named the **medial longitudinal fasciculus**, and will be again referred to.

**Gray Substance of the Medulla Oblongata** (Figs. 704, 705).—In addition to the gracile and cuneate nuclei, there are several other nuclei to be considered. Some of these are traceable from the gray substance of the medulla spinalis, while others are unrepresented in it.

1. The **hypoglossal nucleus** is derived from the base of the anterior column; in the lower closed part of the medulla oblongata it is situated on the ventrolateral aspect of the central canal; but in the upper part it approaches the rhomboid fossa, where it lies close to the middle line, under an eminence named the **trigonum hypoglossi** (Fig. 719). The nucleus measures about 2 cm. in length, and consists of large multipolar nerve cells, whose axons constitute the roots of the hypoglossal nerve. These nerve roots pass forward between the anterior and lateral districts of the medulla oblongata, and emerge from the antero-lateral sulcus.

2. The **motor nucleus** (Figs. 706, 707), common to the *glossopharyngeal*, *vagus*, and cerebral part of the *accessory nerves*, is named the **nucleus ambiguus**. It represents the head of the anterior column, lies deeply in the formatio reticularis grisea, and extends throughout nearly the whole length of the medulla oblongata.

3. The **sensory nucleus** (Figs. 706, 708), or terminal nucleus of the sensory fibres of the *glossopharyngeal* and *vagus*, represents the base of the posterior column. It measures about 2 cm. in length, and in the lower, closed part of the medulla oblongata is situated behind the hypoglossal nucleus; whereas in the upper, open part it lies lateral to that nucleus, and corresponds to an eminence, named the **ala cinerea** (*trigonum vagi*), in the rhomboid fossa.




FIG. 706.—The cerebral nerve nuclei schematically represented; dorsal view. Motor nuclei in red; sensory in blue. (The olfactory and optic centres are not represented.)

4. The **nuclei of the acoustic nerve** are described on page 836.

5. The **olivary nuclei** (Fig. 704) are three in number on either side of the middle line, viz., the inferior olivary nucleus, and the medial and dorsal accessory olivary nuclei; they consist of small, round, yellowish cells and numerous fine nerve fibres. (a) The **inferior olivary nucleus** is the largest, and is situated within the olive. It consists of a gray folded lamina arranged in the form of an incomplete capsule, opening medially by an aperture called the **hilus**; emerging from the hilus are numerous fibres which collectively constitute the **peduncle of the olive**. (b) The **medial accessory olivary nucleus** lies between the inferior olivary nucleus and the pyramid, and forms a curved lamina, the concavity of which is directed laterally. The fibres of the hypoglossal nerve, as they traverse the medulla, pass between the medial accessory and the inferior olivary nuclei. (c) The **dorsal accessory olivary nucleus** is the smallest, and appears on transverse section as a curved lamina behind the inferior olivary nucleus.




FIG. 707.—Nuclei of origin of cerebral motor nerves schematically represented; lateral view.

The inferior olivary nucleus is connected (1) with that of the opposite side by fibres which cross through the raphé; (2) with the anterior column of the same side of the medulla spinalis by the **spinoölivary fasciculus**; (3) with the thalamus of the cerebrum by the **cerebroölivary fasciculus** which passes through the pons and tegmentum; (4) with the opposite cerebellar hemisphere by the **cerebello-olivary fasciculus**, the fibres of which cross the raphé and turn backward to enter the deep part of the restiform body. Removal of one cerebellar hemisphere is followed by atrophy of the opposite olivary nucleus.

6. The **nucleus arcuatus** is described below with the anterior external arcuate fibres.

**Restiform Bodies** (*corpus restiformes*).—The position of the restiform bodies has already been described (page 825). Each comprises: (1) the cerebellospinal

fasciculus, which ascends from the lateral funiculus of the medulla spinalis; (2) descending cerebellar fibres, many of which are disseminated throughout the peripheral part of the anterior and lateral funiculi of the medulla spinalis, while others are conducted to the motor nuclei of the cerebral nerves; and (3) the arcuate fibres, which are arranged in three sets, viz., internal, and anterior and posterior external.

The **internal arcuate fibres** form the deeper and larger part of the restiform body. They decussate in the middle line of the medulla oblongata, and having reached the opposite side, terminate partly in the gracile and cuneate nuclei, while many of them enter the hilus of the inferior olivary nucleus, and constitute the cerebelloolivary tract already described (Fig. 709).




FIG. 708.—Primary terminal nuclei of the afferent (sensory) cerebral nerves schematically represented; lateral view. The olfactory and optic centres are not represented.

The **anterior external arcuate fibres** vary as to their prominence in different cases: in some they form an almost continuous layer covering the pyramid and olive, while in others they are barely visible on the surface. They arise from the cells of the gracile and cuneate nuclei, and passing forward through the formatio reticularis, decussate in the middle line. Most of them reach the surface by way of the anterior median fissure, and arch backward over the pyramid. Reinforced by others which emerge between the pyramid and olive, they pass backward over the olive and lateral district of the medulla oblongata, and enter the restiform body. They thus connect the cerebellum with the gracile and cuneate nuclei of the opposite side. As the fibres arch across the pyramid, they enclose a small nucleus which lies in front of and medial to the pyramid. This is named the **nucleus arcuatus**, and is serially continuous above with the nuclei pontis in the pons; it contains small fusiform cells, around which some of the arcuate fibres end, and from which others arise.

The **posterior external arcuate fibres** also take origin in the gracile and cuneate nuclei; they pass to the restiform body of the same side.




FIG. 709.—Diagram showing the course of the arcuate fibres. (Testut.) 1. Medulla oblongata anterior surface. 2. Anterior median fissure. 3. Fourth ventricle. 4. Inferior olivary nucleus, with the accessory olivary nuclei. 5. Gracile nucleus. 6. Cuneate nucleus. 7. Trigeminal. 8. Restiform bodies, seen from in front. 9. Posterior external arcuate fibres. 10. Anterior external arcuate fibres. 11. Internal arcuate fibres. 12. Peduncle of inferior olivary nucleus. 13. Nucleus arcuatus. 14. Vagus. 15. Hypoglossal.




FIG. 710.—The formatio reticularis of the medulla oblongata, shown by a transverse section passing through the middle of the olive. (Testut.) 1. Anterior median fissure. 2. Fourth ventricle. 3. Formatio reticularis, with 3', its internal part (reticularis alba), and 3'', its external part (reticularis grisea). 4. Raphé. 5. Pyramid. 6. Lemniscus. 7. Inferior olivary nucleus with the two accessory olivary nuclei. 8. Hypoglossal nerve, with 8', its nucleus of origin. 9. Vagus nerve, with 9', its nucleus of termination. 10. Lateral dorsal acoustic nucleus. 11. Nucleus ambiguus (nucleus of origin of motor fibres of glossopharyngeal, vagus, and cerebral portion of spinal accessory). 12. Gracile nucleus. 13. Cuneate nucleus. 14. Head of posterior column, with 14', the lower sensory root of trigeminal nerve. 15. Fasciculus solitarius. 16. Anterior external arcuate fibres, with 16', the nucleus arcuatus. 17. Nucleus lateralis. 18. Nucleus of fasciculus teres. 19. Ligula.

**Formatio Reticularis** (Fig. 710).—This term is applied to the coarse reticulum which occupies the anterior and lateral districts of the medulla oblongata. It



is situated behind the pyramid and olive, extending laterally as far as the restiform bodies, and dorsally to within a short distance of the rhomboid fossa. The reticulum is caused by the intersection of bundles of fibres running at right angles to each other, some being longitudinal, others more or less transverse in direction. The *formatio reticularis* presents a different appearance in the anterior district from what it does in the lateral; in the former, there is an almost entire absence of nerve cells, and hence this part is known as the **reticularis alba**; whereas in the lateral district nerve cells are numerous, and as a consequence it presents a gray appearance, and is termed the **reticularis grisea**.

In the substance of the *formatio reticularis* are two small nuclei of gray matter: one, the **inferior central nucleus** (*nucleus of Roller*), near the dorsal aspect of the hilus of the inferior olivary nucleus; the other, the **nucleus lateralis**, between the olive and the spinal tract of the trigeminal nerve.

In the *reticularis alba* the longitudinal fibres form two well-defined fasciculi, viz.: (1) the **lemniscus**, which lies close to the raphé, immediately behind the fibres of the pyramid; and (2) the **medial longitudinal fasciculus**, which is continued upward from the anterior and lateral proper fasciculi of the medulla spinalis, and, in the upper part of the medulla oblongata, lies between the lemniscus and the gray substance of the rhomboid fossa. The longitudinal fibres in the *reticularis grisea* are derived from the lateral funiculus of the medulla spinalis after the lateral cerebrospinal fasciculus has passed over to the opposite side, and the cerebello-spinal fasciculus has entered the restiform body. They form indeterminate fibres, with the exception of a bundle named the **fasciculus solitarius**, which is made up of descending fibres of the vagus and glossopharyngeal nerves. The transverse fibres of the *formatio reticularis* are the arcuate fibres already described (page 831).

**Applied Anatomy.**—In *bulbar paralysis*, i. e., paralysis of the medulla oblongata, which is really a special form of a progressive degeneration affecting the whole efferent or motor tract, the disease begins with impairment of the movements of the lips, tongue, pharynx, and larynx, due to degeneration of the motor cells in the nuclei of the medulla oblongata. Speech and swallowing become difficult, and the saliva dribbles from the open mouth. Other groups of muscles soon become involved, and death often occurs from “aspiration pneumonia,” set up by food that has accidentally passed down the trachea.

**The Pons** (*pons Varoli*). — The pons or forepart of the rhombencephalon is situated in front of the cerebellum. From its superior surface the cerebral peduncles emerge, one on either side of the middle line. Curving around each peduncle, close to the upper surface of the pons, a thin white band, the **taenia pontis**, is frequently seen; it enters the cerebellum between the brachium pontis and brachium conjunctivum. Behind and below, the pons is continuous with the medulla oblongata, but is separated from it in front by a furrow in which the abducent, facial, and acoustic nerves appear.

Its **ventral or anterior surface** (*pars basilaris pontis*) is very prominent, markedly convex from side to side, less so from above downward. It consists of transverse fibres arched like a bridge across the middle line, and gathered on either side into a compact mass which forms the **brachium pontis**. It rests upon the clivus of the sphenoidal bone, and is limited above and below by well-defined borders. In the middle line is the **sulcus basilaris** for the lodgement of the basilar artery; this sulcus is bounded on either side by an eminence caused by the descent of the cerebrospinal fibres through the substance of the pons. Outside these eminences, near the upper border of the pons, the trigeminal nerves make their exit, each consisting of a smaller, medial, motor root, and a larger, lateral, sensory root; vertical lines drawn immediately beyond the trigeminal nerves, may be taken as the boundaries between the ventral surface of the pons and the brachia pontis.

Its **dorsal or posterior surface** (*pars dorsalis pontis*), triangular in shape, is hidden by the cerebellum, and is bounded laterally by the brachia conjunctiva; it forms the upper part of the rhomboid fossa, with which it will be described.

**Structure** (Fig. 711).—Transverse sections of the pons show it to be composed of two parts which differ in appearance and structure: thus, the basilar or ventral portion consists for the most part of fibres arranged in transverse and longitudinal bundles, together with a small amount of gray substance; while the dorsal tegmental portion is a continuation of the reticular formation of the medulla oblongata, and most of its constituents are continued into the tegmenta of the cerebral peduncles.




FIG. 711.—Coronal section of the pons, at its upper part. (Testut.) 1. Fourth ventricle; its ependyma in yellow. 2. Anterior medullary velum, with 2', its white stratum, and 2'', its gray stratum. 3. Mesencephalic root of trigeminal. 4. Nerve cells associated with this root. 5. Medial longitudinal fasciculus. 6. Formatio reticularis. 7. Lateral sulcus. 8. Section of brachium conjunctivum. 9. Medial lemniscus. 9'. Lateral lemniscus. 10, 10. Transverse fibres of pons. 11, 11. Cerebrospinal fasciculi. 12. Raphé. V. Trigeminal.

The **basilar part** of the pons consists of—(a) superficial and deep transverse fibres, (b) longitudinal fasciculi, and (c) some small nuclei of gray substance, termed the nuclei pontis.

The **superficial transverse fibres** (*fibrae pontis superficiales*) constitute a rather thick layer on the ventral surface of the pons, and are collected into a large rounded bundle on either side of the middle line. This bundle, with the addition of some transverse fibres from the deeper part of the pons, forms the greater part of the brachium pontis.

The **deep transverse fibres** (*fibrae pontis profundae*) partly intersect and partly lie on the dorsal aspect of the cerebrospinal fibres. They course to the lateral border of the pons, and form part of the brachium pontis; the further connections of this brachium will be discussed with the anatomy of the cerebellum.

The **longitudinal fasciculi** (*fasciculi longitudinales*) are derived from the cerebral peduncles, and enter the upper surface of the pons. They stream downward on either side of the middle line in larger or smaller bundles, separated from each other by the deep transverse fibres; these longitudinal bundles cause a forward projection of the superficial transverse fibres, and thus give rise to the eminences on the anterior surface. Some of these fibres end in the nuclei pontis, and others,

after decussating, in the motor nuclei of the trigeminal, abducent, facial, and hypoglossal nerves; but most of them are carried through the pons, and at its lower surface are collected into the pyramids of the medulla. The fibres which end in the motor nuclei of the cerebral nerves are derived from the cells of the cerebral cortex, and bear the same relation to the motor cells of the cerebral nerves that the cerebro-spinal fibres bear to the motor cells in the anterior column of the medulla spinalis.

The **nuclei pontis** are serially continuous with the arcuate nuclei in the medulla, and consist of small groups of multipolar nerve cells which are scattered between the bundles of transverse fibres.

The **dorsal or tegmental part** of the pons is chiefly composed of an upward continuation of the reticular formation and gray substance of the medulla oblongata. It consists of transverse and longitudinal fibres and also contains important gray nuclei, and is subdivided by a median raphé, which, however, does not extend into the basilar part, being obliterated by the transverse fibres. The transverse fibres in the lower part of the pons are collected into a distinct strand, named the **trapezoid body**. This consists of fibres which arise from the cells of the ventral or accessory acoustic nucleus, and will be referred to in connection with the cochlear division of the acoustic nerve. In the substance of the trapezoid body is a collection of nerve cells, which constitutes the **trapezoid nucleus**. The longitudinal fibres, which are continuous with those of the medulla oblongata, are mostly collected into two fasciculi on either side. One of these lies between the trapezoid body and the reticular formation, and forms the upward prolongation of the lemniscus; the second is situated near the floor of the fourth ventricle, and is the **medial longitudinal fasciculus**. Other longitudinal fibres, more diffusely distributed, arise from the cells of the gray substance of the pons.

The rest of the dorsal part of the pons is a continuation upward of the formation reticularis of the medulla oblongata, and, like it, presents the appearance of a network, in the meshes of which are numerous nerve cells. Besides these scattered nerve cells, there are some larger masses of gray substance, viz., the superior olivary nucleus and the nuclei of the trigeminal, abducent, facial, and acoustic nerves (Fig. 706).

1. The **superior olivary nucleus** (*nucleus olivaris superior*) is a small mass of gray substance situated on the dorsal surface of the lateral part of the trapezoid body. Rudimentary in man, but well developed in certain animals, it exhibits the same structure as the inferior olivary nucleus, and is situated immediately above it. Some of the fibres of the trapezoid body end by arborizing around the cells of this nucleus, while others arise from these cells.

2. The **nuclei of the trigeminal nerve** (*nuclei n. trigemini*) in the pons are two in number: a motor and a sensory. The **motor nucleus** is situated in the upper part of the pons, close to its posterior surface and along the line of the lateral margin of the fourth ventricle. The axis-cylinder processes of its cells form a portion of the motor root of the trigeminal nerve: the remaining fibres of the motor root of this nerve consist of a fasciculus which arises from the gray substance of the floor of the cerebral aqueduct, and hence is named the **mesencephalic root**. The **sensory nucleus** is lateral to the motor one, and beneath the brachium conjunctivum. Some of the sensory fibres of the trigeminal nerve end in this nucleus; but the greater number descend, under the name of the spinal tract of the trigeminal nerve, to end in the substantia gelatinosa of Rolando. The roots, motor and sensory, of the trigeminal nerve pass through the substance of the pons and emerge near the upper margin of its anterior surface.

3. The **nucleus of the abducent nerve** (*nucleus n. abducentis*) is a circular mass of gray substance situated close to the floor of the fourth ventricle, above the striae medullares and subjacent to the medial eminence: it lies a little lateral to the ascending part of the facial nerve. The fibres of the abducent nerve pass forward

through the entire thickness of the pons on the medial side of the superior olivary nucleus, and between the lateral fasciculi of the cerebrospinal fibres, and emerge in the furrow between the lower border of the pons and the pyramid of the medulla oblongata.

4. The **nucleus of the facial nerve** (*nucleus n. fascialis*) is situated deeply in the reticular formation of the pons, on the dorsal aspect of the superior olivary nucleus, and the roots of the nerve derived from it pursue a remarkably tortuous course in the substance of the pons. At first they pass backward and medialward until they reach the rhomboid fossa, close to the median sulcus, where they are collected into a round bundle; this passes upward and forward, producing an elevation, the **colliculus facialis**, in the rhomboid fossa, and then takes a sharp bend, and arches lateralward through the substance of the pons to emerge at its lower border in the interval between the olive and the restiform body of the medulla oblongata.

5. The **nuclei of the acoustic nerve** (*nuclei n. acustici*) consists of a cochlear and a vestibular division. The fibres of the cochlear division end in two nuclei: (a) the **lateral cochlear nucleus**, corresponding to the tuberculum acusticum on the dorso-lateral surface of the restiform body; and (b) the **ventral or accessory cochlear nucleus**, placed between the two divisions of the nerve, on the ventral aspect of the restiform body. The nuclei in which the vestibular division ends are (a) the **dorsal or chief vestibular nucleus**, corresponding to the lower part of the area acustica in the rhomboid fossa; the caudal end of this nucleus is sometimes termed the **descending or spinal vestibular nucleus**; (b) the **nucleus of Deiters**, consisting of large cells and situated in the lateral angle of the rhomboid fossa; the dorso-lateral part of this nucleus is sometimes termed the **nucleus of Bechterew**.

**Applied Anatomy.**—Injury to the pons, such as may occur on the occlusion or rupture of one of its bloodvessels, often gives rise to a special train of symptoms that is almost diagnostic. Pontine lesions are characterized mainly by "alternate paralyses;" that is to say, by paralysis of one of the motor cerebral nerves on one side, and of the limbs on the other side of the body. Thus a hemorrhage into the lower part of the pons might cause paralysis of the face, *lower segment paralysis*, on the same side, from destruction of the facial nucleus or nerve root, and paralysis of the arm and leg on the opposite side from injury to the adjacent cerebrospinal tract. In the same way, paralysis of the Rectus lateralis of one eye and of the Rectus medialis of the other, *conjugate paralysis*, of the muscles turning the two eyes in one direction, and often paralysis of one side of the face as well, together with palsy of the limbs on the opposite side of the body, may be found when the lesion occurs about the nucleus of the abducent nerve. Hearing is often unaffected in pontine lesions, possibly because the central acoustic tract occupies a ventral and lateral position in the pons.

**The Cerebellum.**—The cerebellum constitutes the largest part of the hind-brain. It lies behind the pons and medulla oblongata; between its central portion and these structures is the cavity of the fourth ventricle. It rests on the inferior occipital fossæ, while above it is the tentorium cerebelli, a fold of dura mater which separates it from the tentorial surface of the cerebrum. It is somewhat oval in form, but constricted medially and flattened from above downward, its greatest diameter being from side to side. Its surface is not convoluted like that of the cerebrum, but is traversed by numerous curved furrows or sulci, which vary in depth at different parts, and separate the laminae of which it is composed. Its average weight in the male is about 150 gms. In the adult the proportion between the cerebellum and cerebrum is about 1 to 8, in the infant about 1 to 20.

**Lobes of the Cerebellum.**—The cerebellum consists of three parts, a median and two lateral, which are continuous with each other, and are substantially the same in structure. The median portion is constricted, and is called the **vermis**, from its annulated appearance which it owes to the transverse ridges and furrows upon it; the lateral expanded portions are named the **hemispheres**. On the upper surface of the cerebellum the vermis is elevated above the level of the hemispheres, but on the under surface it is sunk almost out of sight in the bottom of a deep depres-

sion between them; this depression is called the **vallecula cerebelli**, and lodges the posterior part of the medulla oblongata. The part of the vermis on the upper surface of the cerebellum is named the **superior vermis**; that on the lower surface, the **inferior vermis**. The hemispheres are separated below and behind by a deep notch, the **posterior cerebellar notch**, and in front by a broader shallower notch, the **anterior cerebellar notch**. The anterior notch lies close to the pons and upper part of the medulla, and its superior edge encircles the inferior colliculi and the brachia conjunctiva cerebelli. The posterior notch contains the upper part of the falx cerebelli, a fold of dura mater.

The cerebellum is characterized by its laminated or foliated appearance; it is marked by deep, somewhat curved fissures, which extend for a considerable distance into its substance, and divide it into a series of layers or leaves. The largest and deepest fissure is named the **horizontal sulcus**. It commences in front of the pons, and passes horizontally around the free margin of the hemisphere to the middle line behind, and divides the cerebellum into an upper and a lower portion. Several secondary but deep fissures separate the cerebellum into lobes, and these are further subdivided by shallower sulci, which separate the individual folia or laminæ from each other. Sections across the laminæ show that the folia, though differing in appearance from the convolutions of the cerebrum, are analogous to them, inasmuch as they consist of central white substance covered by gray substance.




FIG. 712.—Upper surface of the cerebellum. (Schäfer.)

The cerebellum is connected to the cerebrum, pons, and medulla oblongata; to the cerebrum by the brachia conjunctiva, to the pons by the brachia pontis, and to the medulla oblongata by the restiform bodies.

The **upper surface of the cerebellum** (Fig. 712) is elevated in the middle and sloped toward the circumference, the hemispheres being connected together by the superior vermis, which assumes the form of a raised median ridge, most prominent in front, but not sharply defined from the hemispheres. The superior vermis is subdivided from before backward into the lingula, the lobulus centralis, the monticulus and the folium vermis, and each of these, with the exception of the lingula, is continuous with the corresponding parts of the hemispheres—the lobulus centralis with the alae, the monticulus with the quadrangular lobules, and the folium vermis with the superior semilunar lobules.

The **lingula** (*lingula cerebelli*) is a small tongue-shaped process, consisting of four or five folia; it lies in front of the lobulus centralis, and is concealed by it. Anteriorly, it rests on the dorsal surface of the anterior medullary velum, and its white substance is continuous with that of the velum.



The **Lobulus Centralis and Alae**.—The **lobulus centralis** is a small square lobule, situated in the anterior cerebellar notch. It overlaps the **lingula**, from which it is separated by the **precentral fissure**; laterally, it extends along the upper and anterior part of each hemisphere, where it forms a wing-like prolongation, the **ala lobuli centralis**.

The **Monticulus and Quadrangular Lobules**.—The **monticulus** is the largest part of the superior vermis. Anteriorly, it overlaps the **lobulus centralis**, from which it is separated by the **postcentral fissure**; laterally, it is continuous with the **quadrangular lobule** in the hemispheres. It is divided by the **preclival fissure** into an anterior, raised part, the **culmen** or summit, and a posterior sloped part, the **clivus**; the quadrangular lobule is similarly divided. The **culmen** and the anterior parts of the quadrangular lobules form the **lobus culminis**; the **clivus** and the posterior parts, the **lobus clivi**.

The **Folium Vermis and Superior Semilunar Lobule**.—The **folium vermis** (*folium cacuminis*; *cacuminal lobe*) is a short, narrow, concealed band at the posterior extremity of the vermis, consisting apparently of a single folium, but in reality marked on its upper and under surfaces by secondary fissures. Laterally, it expands in either hemisphere into a considerable lobule, the **superior semilunar lobule** (*lobulus semilunaris superior*; *postero-superior lobules*), which occupies the posterior third of the upper surface of the hemisphere, and is bounded below by the **horizontal sulcus**. The superior semilunar lobules and the **folium vermis** form the **lobus semilunaris**.




FIG. 713.—Under surface of the cerebellum. (Schäfer.)

The **under surface of the cerebellum** (Fig. 713) presents, in the middle line, the **inferior vermis**, buried in the **vallecula**, and separated from the hemisphere on either side by a deep groove, the **sulcus vallecule**. Here, as on the upper surface, there are deep fissures, dividing it into separate segments or lobules; but the arrangement is more complicated, and the relation of the segments of the vermis to those of the hemispheres is less clearly marked. The inferior vermis is subdivided from before backward, into (1) the **nodulus**, (2) the **uvula**, (3) the **pyramid**, and (4) the **tuber vermis**; the corresponding parts on the hemispheres are (1) the **flocculus**, (2) the **tonsilla cerebelli**, (3) the **biventral lobule**, and (4) the **inferior semilunar lobule**. The three main fissures are (1) the **postnodular fissure**, which runs transversely across the vermis, between the nodulus and the uvula. In the hemispheres this fissure passes in front of the tonsil, crosses between the flocculus in front and the biventral lobule behind, and joins the anterior end of the horizontal sulcus. (2) The **pre-**

**pyramidal fissure** crosses the vermis between the uvula in front and the pyramid behind, then curves forward between the tonsil and the biventral lobe, to join the postnodular fissure. (3) The **postpyramidal fissure** passes across the vermis between the pyramid and the tuber vermis, and, in the hemispheres, courses behind the tonsil and biventral lobules, and then along the lateral border of the biventral lobule to the postnodular sulcus; in the hemisphere it forms the anterior boundary of the inferior semilunar lobule.

**The Nodule and Flocculus.**—The **nodule** (*nodulus vermis*; *nodular lobe*), or anterior end of the inferior vermis, abuts against the roof of the fourth ventricle, and can only be distinctly seen after the cerebellum has been separated from the medulla oblongata and pons. On either side of the nodule is a thin layer of white substance, named the **posterior medullary velum**. It is semilunar in form, its convex border being continuous with the white substance of the cerebellum; it extends on either side as far as the flocculus. The **flocculus** is a prominent, irregular lobule, situated in front of the biventral lobule, between it and the brachium pontis cerebelli. It is subdivided into a few small laminae, and is connected to the inferior medullary velum by its central white core. The flocculi, together with the posterior medullary velum and nodule, constitute the **lobus noduli**.

**The Uvula and Tonsilla.**—The **uvula** (*uvula vermis*; *uvular lobe*) forms a considerable portion of the inferior vermis; it is separated on either side from the tonsil by the **sulcus valleculae**, at the bottom of which it is connected to the tonsil by a ridge of gray matter, indented on its surface by shallow furrows, and hence called the **furrowed band**. The **tonsilla** (*tonsilla cerebelli*; *amygdaline nucleus*) is a rounded mass, situated in the hemispheres. Each lies in a deep fossa, termed the **bird's nest** (*nidus avis*), between the uvula and the biventral lobule. The uvula and tonsillae form the **lobus uvulae**.

**The Pyramid and Biventral lobules** constitute the **lobus pyramidis**. The **pyramid** is a conical projection, forming the largest prominence of the inferior vermis. It is separated from the hemispheres by the sulcus valleculae, across which it is connected to the biventral lobule by an indistinct gray band, analogous to the furrowed band already described. The **biventral lobule** is triangular in shape; its apex points backward, and is joined by the gray band to the pyramid. The lateral border is separated from the inferior semilunar lobule by the postpyramidal fissure. The base is directed forward, and is on a line with the anterior border of the tonsil, and is separated from the flocculus by the postnodular fissure.

**The Tuber Vermis** (*tuber valvulae*) and the **Inferior Semilunar Lobule** (*lobulus semilunaris inferior*; *postero-superior lobule*) collectively form the **lobus tuberis** (*tuberae lobe*). The **tuber vermis**, the most posterior division of the inferior vermis, is of small size, and laterally spreads out into the large inferior semilunar lobules, which comprise at least two-thirds of the inferior surface of the hemisphere.

**Internal Structure of the Cerebellum.**—The cerebellum consists of white and gray substance.

**White Substance.**—If a sagittal section (Fig. 714) be made through either hemisphere, the interior will be found to consist of a central stem of white substance, in the middle of which is a gray mass, the **dentate nucleus**. From the surface of this central white stem a series of plates are prolonged; these are covered with gray substance and form the laminae. In consequence of the main branches from the central stem dividing and subdividing, a characteristic appearance, named the **arbor vitae**, is presented. If the sagittal section be made through the middle of the vermis, it will be found that the central stem divides into a vertical and a horizontal branch. The **vertical** branch passes upward to the culmen monticuli, where it subdivides freely, one of its ramifications passing forward and upward to the central lobule. The **horizontal** branch passes backward to the folium vermis, greatly diminished in size in consequence of having given off large secondary

branches; one, from its upper surface, ascends to the clivus monticuli; the others descend, and enter the lobes in the inferior vermis, viz., the tuber vermis, the pyramid, the uvula, and the nodule.




FIG. 714.—Sagittal section of the cerebellum, near the junction of the vermis with the hemisphere. (Schäfer.)




FIG. 715.—Dissection showing the projection fibres of the cerebellum. (After E. B. Jamieson.)

The white substance of the cerebellum includes two sets of nerve fibres: (1) **projection fibres**, (2) **fibræ propriae**.

**Projection Fibres.**—The cerebellum is connected to the other parts of the brain by three large bundles of projection fibres, viz., to the cerebrum by the brachia conjunctiva, to the pons by the brachia pontis, and to the medulla oblongata by the restiform bodies (Fig. 715).

The **brachia conjunctiva** (*superior cerebellar peduncles*), two in number, emerge from the upper and medial part of the white substance of the hemispheres and are placed under cover of the upper part of the cerebellum. They are joined to each other across the middle line by the anterior medullary velum, and can be followed upward as far as the inferior colliculi, under which they disappear. Below, they form the upper lateral boundaries of the fourth ventricle, but as they ascend they converge on the dorsal aspect of the ventricle and thus assist in roofing it in.

The fibres of the *brachium conjunctivum* are mainly derived from the cells of the dentate nucleus of the cerebellum and emerge from the hilus of this nucleus; a few arise from the cells of the smaller gray nuclei in the cerebellar white substance, and others from the cells of the cerebellar cortex. They are continued upward beneath the corpora quadrigemina, and the fibres of the two brachia undergo a complete decussation ventral to the Sylvian aqueduct. Having crossed the middle line they divide into ascending and descending groups of fibres, the former ending in the red nucleus, the thalamus, and the nucleus of the oculomotor nerve, while the descending fibres can be traced as far as the dorsal part of the pons; Cajal believes them to be continued into the anterior funiculus of the medulla spinalis.

As already stated (page 816), the majority of the fibres of the superficial antero-lateral fasciculi of the medulla spinalis pass to the cerebellum, which they reach by way of the brachia conjunctiva.

The **brachia pontis** (*middle cerebellar peduncles*) (Fig. 715) are composed entirely of centripetal fibres, which arise from the cells of the nuclei pontis of the opposite side and end in the cerebellar cortex; the fibres are arranged in three fasciculi, superior, inferior, and deep. The **superior fasciculus**, the most superficial, is derived from the upper transverse fibres of the pons; it is directed backward and lateralward superficial to the other two fasciculi, and is distributed mainly to the lobules on the inferior surface of the cerebellar hemisphere and to the parts of the superior surface adjoining the posterior and lateral margins. The **inferior fasciculus** is formed by the lowest transverse fibres of the pons; it passes under cover of the superior fasciculus and is continued downward and backward more or less parallel with it, to be distributed to the folia on the under surface close to the vermis.

The **deep fasciculus** comprises most of the deep transverse fibres of the pons. It is at first covered by the superior and inferior fasciculi, but crosses obliquely and appears on the medial side of the superior, from which it receives a bundle; its fibres spread out and pass to the upper anterior cerebellar folia. The fibres of this fasciculus cover those of the restiform body.<sup>1</sup>

The **restiform bodies** (*corpus restiformes; inferior cerebellar peduncles*) pass at first upward and lateralward, forming part of the lateral walls of the fourth ventricle, and then bend abruptly backward to enter the cerebellum between the brachia conjunctiva and brachia pontis. Each contains the following fasciculi: (1) the cerebellospinal fasciculus of the medulla spinalis, which ends mainly in the superior vermis; (2) fibres from the gracile and cuneate nuclei of the same and of the opposite sides; (3) fibres from the opposite olivary nuclei; (4) crossed and uncrossed fibres from the reticular formation of the medulla oblongata; (5) vestibular fibres, derived partly from the vestibular division of the acoustic nerve and partly from the nuclei in which this division ends—these fibres occupy the medial segment of the restiform body and divide into ascending and descending groups of fibres; the ascending fibres partly end in the roof nucleus of the opposite side of the cerebellum; (6) cerebellobulbar fibres which come from the opposite roof nucleus and probably from the dentate nucleus, and are said to end in the nucleus of Deiters and in the *formatio reticularis* of the medulla oblongata.

<sup>1</sup> See article by E. B. Jamieson, *Journal of Anatomy and Physiology*, vol. xlv.

The **anterior medullary velum** (*velum medullare anterius; valve of Vieussens; superior medullary velum*) is a thin, transparent lamina of white substance, which stretches between the brachial conjunctiva; on the dorsal surface of its lower half the folia and lingula are prolonged. It forms, together with the brachia conjunctiva, the roof of the upper part of the fourth ventricle; it is narrow above, where it passes beneath the inferior colliculi, and broader below, where it is continuous with the white substance of the superior vermis. A slightly elevated ridge, the **fraenulum veli**, descends upon its upper part from between the inferior colliculi, and on either side of this the trochlear nerve emerges.

The **posterior medullary velum** (*velum medullare posterius; inferior medullary velum*) is a thin layer of white substance, prolonged from the white centre of the cerebellum, above and on either side of the nodule; it forms a part of the roof of the fourth ventricle. Somewhat semilunar in shape, its convex edge is continuous with the white substance of the cerebellum, while its thin concave margin is apparently free; in reality, however, it is continuous with the epithelium of the ventricle, which is prolonged downward from the posterior medullary velum to the ligula.

The two medullary vela are in contact with each other along their line of emergence from the white substance of the cerebellum; and this line of contact forms the summit of the roof of the fourth ventricle, which, in a vertical section through the cavity, appears as a pointed angle.

The **Fibrae Propriae** of the cerebellum are of two kinds: (1) **commissural fibres**, which cross the middle line at the anterior and posterior parts of the vermis and connect the opposite halves of the cerebellum; (2) **arcuate or association fibres**, which connect adjacent laminae with each other.

**Gray Substance.**—The gray substance of the cerebellum is found in two situations: (1) on the surface, forming the cortex; (2) as independent masses in the anterior.

(1) The **gray substance of the cortex** presents a characteristic foliated appearance, due to the series of laminae which are given off from the central white substance; these in their turn give off secondary laminae, which are covered by gray substance. Externally, the cortex is covered by pia mater; internally is the medullary centre, consisting mainly of nerve fibres.

**Microscopic Appearance of the Cortex** (Fig. 716).—The cortex consists of two layers, viz., an external gray molecular layer, and an internal rust-colored nuclear layer; between these is an incomplete stratum of cells which are characteristic of the cerebellum, viz., the **cells of Purkinje**.

The **external gray or molecular layer** consists of fibres and cells. The nerve fibres are delicate fibrillae, and are derived from the following sources: (a) the dendrites and axon collaterals of Purkinje's cells; (b) fibres from cells in the nuclear layer; (c) fibres from the central white substance of the cerebellum; (d) fibres derived from cells in the molecular layer itself. In addition to these are other fibres, which have a vertical direction, and are the processes of large neuroglia cells, situated in the nuclear layer. They pass outward to the periphery of the gray matter, where they expand into little conical enlargements which form a sort of limiting membrane beneath the pia mater, analogous to the *membrana limitans interna* in the retina, formed by the sustentacular fibres of Müller.

The **cells of the molecular layer** are small, and are arranged in two strata, an outer and an inner. They all possess branched axons; those of the inner layer are termed **basket cells**; they run for some distance parallel with the surface of the folium—giving off collaterals which pass in a vertical direction toward the bodies of Purkinje's cells, around which they become enlarged, and form basket-like net-works.

The **cells of Purkinje** form a single stratum of large, flask-shaped cells at the junction of the molecular and nuclear layers, their bases resting against the latter; in fishes and reptiles they are arranged in several layers. The cells are flattened



in a direction transverse to the long axis of the folium, and thus appear broad in sections carried across the folium, and fusiform in sections parallel to the long axis of the folium. From the neck of the flask one or more dendrites arise and pass into the molecular layer, where they subdivide and form an extremely rich arborescence, the various subdivisions of the dendrites being covered by lateral spine-like processes. This arborescence is not circular, but, like the cell, is flattened at right angles to the long axis of the folium; in other words, it does not resemble a round bush, but has been aptly compared by Obersteiner to the branches of a fruit tree trained against a trellis or a wall. Hence, in sections carried across the folium the arborescence is broad and expanded; whereas in those which are parallel to the long axis of the folium, the arborescence, like the cell itself, is seen in profile, and is limited to a narrow area.




FIG. 716.—Transverse section of a cerebellar folium. (Diagrammatic, after Cajal and Kölliker.)

From the bottom of the flask-shaped cell the axon arises; this passes through the nuclear layer, and, becoming medullated, is continued as a nerve fibre in the subjacent white substance. As this axon traverses the granular layer it gives off fine collaterals, some of which run back into the molecular layer.

The **internal rust-colored** or **nuclear layer** (Fig. 716) is characterized by containing numerous small nerve cells of a reddish-brown color, together with many nerve

fibrils. Most of the cells are nearly spherical and provided with short dendrites which spread out in a spider-like manner in the nuclear layer. Their axons pass outward into the molecular layer, and, bifurcating at right angles, run for some distance parallel with the surface. In the outer part of the nuclear layer are some larger cells, of the type II of Golgi. Their axons undergo frequent division as soon as they leave the nerve cells, and pass into the nuclear layer; while their dendrites ramify chiefly in the molecular layer.

Finally, in the gray substance of the cerebellar cortex there are fibres which come from the white centre and penetrate the cortex. The cell-origin of these fibres is unknown, though it is believed that it is probably in the gray substance of the medulla spinalis. Some of these fibres end in the nuclear layer by dividing into numerous branches, on which are to be seen peculiar moss-like appendages; hence they have been termed by Ramón y Cajal the **moss fibres**; they form an arborescence around the cells of the nuclear layer. Other fibres, the **clinging** or **tendrill fibres**, derived from the medullary centre can be traced into the molecular layer, where their branches cling around the dendrites of Purkinje's cells.

(2) The **independent centres of gray substance** in the cerebellum are four in number on either side: one is of large size, and is known as the **nucleus dentatus**; the other three, much smaller, are situated near the middle of the cerebellum, and are known as the **nucleus emboliformis**, **nucleus globosus**, and **nucleus fastigii**.




FIG. 717.—Sagittal section through right cerebellar hemisphere. The right olive has also been cut sagittally.

The **nucleus dentatus** (Fig. 717) is situated a little to the medial side of the centre of the stem of the white substance of the hemisphere. It consists of an irregularly folded lamina, of a grayish-yellow color, containing white fibres, and presenting on its antero-medial aspect an opening, the **hilus**, from which most of the fibres of the brachium conjunctiva emerge (page 841).

The **nucleus emboliformis** lies immediately to the medial side of the nucleus dentatus, and partly covering its hilus. The **nucleus globosus** is an elongated mass, directed antero-posteriorly, and placed medial to preceding. The **nucleus fastigii** is somewhat larger than the other two, and is situated close to the middle line at the anterior end of the superior vermis, and immediately over the roof of the fourth ventricle, from which it is separated by a thin layer of white substance.

**Applied Anatomy.**—The general functions of the cerebellum in the human economy appear to be the coördination of movements and equilibration. The exact functions of its different parts are still quite uncertain, owing to the contradictory nature of the evidence furnished by

(1) ablation experiments upon animals, and (2) clinical observations in man of the effects produced by abscesses or tumors affecting different portions of the organ. According to W. Aldren Turner, "The following localizing symptoms would therefore indicate the presence of a tumor implicating the right cerebellar hemisphere and middle peduncle; deafness in the right ear, unassociated with middle-ear complications; an unsteady and uncertain gait, with a tendency to fall more particularly to the right side; coarse nystagmoid oscillations on looking to the right; movements resembling those of disseminated sclerosis on volitional effort of the right arm; an awkward uncertain action of the right leg; a slight increase of the right knee-jerk; and, perhaps, slight blunting of sensibility over the right cornea and side of the face."

**The Fourth Ventricle** (*ventriculus quartus*).—The fourth ventricle, or cavity of the rhombencephalon, is situated in front of the cerebellum and behind the pons and upper half of the medulla oblongata. Developmentally considered, the fourth ventricle consists of three parts: a **superior** belonging to the isthmus rhombencephali, an **intermediate**, to the metencephalon, and an **inferior**, to the myelencephalon. It is lined by ciliated epithelium, and is continuous below with the central canal of the medulla oblongata;<sup>1</sup> above, it communicates, by means of a passage termed the cerebral aqueduct, with the cavity of the third ventricle. It presents four angles, and possesses a **roof** or dorsal wall, a **floor** or ventral wall, and **lateral boundaries**.

**Angles.**—The **superior angle** is on a level with the upper border of the pons, and is continuous with the lower end of the cerebral aqueduct. The **inferior angle** is on a level with the lower end of the olive, and opens into the central canal of the medulla oblongata. Each **lateral angle** corresponds with the point of meeting of the brachia and restiform body. A little below the lateral angles, on a level with the striae medullares, the ventricular cavity is prolonged outward in the form of two narrow **lateral recesses**, one on either side; these are situated between the restiform bodies and the flocculi, and reach as far as the attachments of the glossopharyngeal and vagus nerves.

**Lateral Boundaries.**—The lower part of each lateral boundary is constituted by the clava, the fasciculus cuneatus, and the restiform body; the upper part by the brachium pontis and the brachium conjunctivum.

**Roof or Dorsal Wall** (Fig. 718).—The upper portion of the roof is formed by the brachia conjunctiva and the anterior medullary velum; the lower portion, by the posterior medullary velum, the epithelial lining of the ventricle covered by the tela chorioidea inferior, the tæniæ of the fourth ventricle, and the obex.

The **brachia conjunctiva** (page 841), on emerging from the central white substance of the cerebellum, pass upward and forward, forming at first the lateral boundaries of the upper part of the cavity; on approaching the inferior colliculi, they converge, and their medial portions overlap the cavity and form part of its roof.

The **anterior medullary velum** (page 842) fills in the angular interval between the brachia conjunctiva, and is continuous behind with the central white substance of the cerebellum; it is covered on its dorsal surface by the lingula of the superior vermis.

The **posterior medullary velum** (page 842) is continued downward and forward from the central white substance of the cerebellum in front of the nodule and tonsils, and ends inferiorly in a thin, concave, somewhat ragged margin. Below this margin the roof is devoid of nervous matter except in the immediate vicinity of the lower lateral boundaries of the ventricle, where two narrow white bands, the **tæniæ of the fourth ventricle** (*ligulae*), appear; these bands meet over the inferior angle of the ventricle in a thin triangular lamina, the **obex**. The non-nervous part of the roof is formed by the **epithelial lining of the ventricle**, which is prolonged downward as a thin membrane, from the deep surface of the posterior medullary

<sup>1</sup> J. T. Wilson (Journal of Anatomy and Physiology, vol. xl) has pointed out that the central canal of the medulla oblongata, immediately below its entrance into the fourth ventricle, retains the cleft-like form presented by the fetal medulla spinalis, and that it is marked by dorso- and ventro-lateral sulci.

velum to the corresponding surface of the obex and taeniae, and thence on to the floor of the ventricular cavity; it is covered and strengthened by a portion of the pia mater, which is named the **tela chorioidea of the fourth ventricle**.

The **taeniae of the fourth ventricle** (*taenia ventriculi quarti; ligula*) are two narrow bands of white matter, one on either side, which complete the lower part of the roof of the cavity. Each consists of a vertical and a horizontal part. The vertical part is continuous below the obex with the clava, to which it is adherent by its lateral border. The horizontal portion extends transversely across the restiform body, below the striae medullares, and roofs in the lower and posterior part of the lateral recess; it is attached by its lower margin to the restiform body, and partly encloses the choroid plexus, which, however, projects beyond it like a cluster of grapes; and hence this part of the taenia has been termed the **cornucopia** (Bochdalek). The **obex** is a thin, triangular, gray lamina, which roofs in the lower angle of the ventricle and is attached by its lateral margins to the clavae.<sup>1</sup> The **tela chorioidea of the fourth ventricle** is the name applied to the triangular fold of pia mater which is carried upward between the cerebellum and the medulla oblongata. It consists of two




FIG. 718.—Scheme of roof of fourth ventricle. The arrow is in the foramen of Majendie.

layers, which are continuous with each other in front, and are more or less adherent throughout. The posterior layer covers the antero-inferior surface of the cerebellum, while the anterior is applied to the structures which form the lower part of the roof of the ventricle, and is continuous inferiorly with the pia mater on the restiform bodies and closed part of the medulla.

**Choroid Plexuses.**—These consist of two highly vascular inflexions of the tela chorioidea, which invaginate the lower part of the roof of the ventricle and are everywhere covered by the epithelial lining of the cavity. Each consists of a vertical and a horizontal portion: the former lies close to the middle line, and the latter passes into the lateral recess and projects beyond its apex. The vertical parts of the plexuses are distinct from each other, but the horizontal portions are joined in the middle line; and hence the entire structure presents the form of the letter T, the vertical limb of which, however, is double.

<sup>1</sup> J. T. Wilson, op. cit., recognizes two forms of obex: (a) the *true obex*, constituted by a medullary thickening of the roof plate, and (b) a *false or membranous obex*, where the medullary thickening fails to take place, and where the roof plate is represented only by the ependymal layer clothing the ventral surface of a pial reduplication which forms the main substance of the membranous fold in question.

**Openings in the Roof.**—In the roof of the fourth ventricle there are three openings, a medial and two lateral: the **medial aperture** (*foramen Majendii*), is situated immediately above the inferior angle of the ventricle; the **lateral apertures** are found at the extremities of the lateral recesses. By means of these three openings the ventricle communicates with the subarachnoid cavity, and the cerebrospinal fluid can circulate from the one to the other.

**Rhomboid Fossa** (*fossa rhomboidea*; “floor” of the fourth ventricle) (Fig. 719).—The anterior part of the fourth ventricle is named, from its shape, the **rhomboid fossa**, and its anterior wall, formed by the back of the pons and medulla oblongata, constitutes the floor of the fourth ventricle. It is covered by a thin layer of gray substance continuous with that of the medulla spinalis; superficial to this is a thin lamina of neuroglia which constitutes the ependyma of the ventricle and supports a layer of ciliated epithelium. The fossa consists of three parts, superior, inter-




FIG. 719.—Rhomboid fossa.

mediate, and inferior. The **superior part** is triangular in shape and limited laterally by the brachia conjunctiva cerebelli; its apex, directed upward, is continuous with the cerebral aqueduct; its base is represented by an imaginary line at the level of the upper ends of the superior foveæ. The **intermediate part** extends from this level to that of the horizontal portions of the tæniæ of the ventricle; it is narrow above where it is limited laterally by the brachia pontis, but widens below and is prolonged into the lateral recesses of the ventricle. The **inferior part** is triangular, and its downwardly directed apex, named the **calamus scriptorius**, is continuous with the central canal of the closed part of the medulla oblongata.

The rhomboid fossa is divided into symmetrical halves by a **median sulcus** which reaches from the upper to the lower angles of the fossa and is deeper below than above. On either side of this sulcus is an elevation, the **medial eminence**, bounded laterally by a sulcus, the **sulcus limitans**. In the superior part of the fossa the medial eminence has a width equal to that of the corresponding half of the



fossa, but opposite the superior fovea it forms an elongated swelling, the **colliculus facialis**, which overlies the nucleus of the abducent nerve, and is, in part at least, produced by the ascending portion of the root of the facial nerve. In the inferior part of the fossa the medial eminence assumes the form of a triangular area, the **trigonum hypoglossi**. When examined under water with a lens this trigone is seen to consist of a medial and a lateral area separated by a series of oblique furrows; the medial area corresponds with the upper part of the nucleus of the hypoglossal nerve, the lateral with a small nucleus, the **nucleus intercalatus**.

The **sulcus limitans** forms the lateral boundary of the medial eminence. In the superior part of the rhomboid fossa it corresponds with the lateral limit of the fossa and presents a bluish-gray area, the **locus coeruleus**, which owes its color to an underlying patch of deeply pigmented nerve cells, termed the **substantia ferruginea**. At the level of the colliculus facialis the sulcus limitans widens into a flattened depression, the **superior fovea**, and in the inferior part of the fossa appears as a distinct dimple, the **inferior fovea**. Lateral to the foveæ is a rounded elevation named the **area acustica**, which extends into the lateral recess and there forms a feebly marked swelling, the **tuberculum acusticum**. Winding around the restiform body and crossing the area acustica and the medial eminence are a number of white strands, the **striae medullares**, which form a portion of the cochlear division of the acoustic nerve and disappear into the median sulcus. Below the inferior fovea, and between the trigonum hypoglossi and the lower part of the area acustica is a triangular dark field, the **ala cinerea**, which corresponds to the sensory nucleus of the vagus and glossopharyngeal nerves. The lower end of the ala cinerea is crossed by a narrow translucent ridge, the **funiculus separans**, and between this funiculus and the clava, is a small tongue-shaped area, the **area postrema**. On section it is seen that the funiculus separans is formed by a strip of thickened ependyma, and the area postrema by loose, highly vascular, neuroglial tissue containing nerve cells of moderate size.

### THE MESENCEPHALON OR MID-BRAIN.

The **mesencephalon** or **mid-brain** (Fig. 725) is the short, constricted portion which connects the pons and cerebellum with the thalamencephalon and cerebral hemispheres. It is directed upward and forward, and consists of (1) a ventro-lateral portion, composed of a pair of cylindrical bodies, named the **cerebral peduncles**; (2) a dorsal portion, consisting of four rounded eminences, named the **corpora quadrigemina**; and (3) an intervening passage or tunnel, the **cerebral aqueduct**, which represents the original cavity of the mid-brain and connects the third with the fourth ventricle (Fig. 720).

The **cerebral peduncles** (*pedunculus cerebri*; *crus cerebri*) are two cylindrical masses situated at the base of the brain, and largely hidden by the temporal lobes of the cerebrum, which must be drawn aside or removed in order to expose them. They emerge from the upper surface of the pons, one on either side of the middle line, and, diverging as they pass upward and forward, disappear into the substance of the cerebral hemispheres. The depressed area between the crura is termed the **interpeduncular fossa**, and consists of a layer of grayish substance, the **posterior perforated substance**, which is pierced by small apertures for the transmission of bloodvessels; its lower part lies on the ventral aspect of the medial portions of the tegmenta, and contains a nucleus named the **interpeduncular ganglion** (page 850); its upper part assists in forming the floor of the third ventricle. The ventral surface of each peduncle is crossed from the medial to the lateral side by the superior cerebellar and posterior cerebral arteries; its lateral surface is in relation to the gyrus hippocampi of the cerebral hemisphere and is crossed from behind forward

by the trochlear nerve. Close to the point of disappearance of the peduncle into the cerebral hemisphere, the optic tract winds forward around its ventro-lateral surface. The medial surface of the of the interpeduncular fossa, and is marked by a longitudinal furrow, the **oculomotor sulcus**, from which the roots of the oculomotor nerve emerge. On the lateral surface of each peduncle there is a second longitudinal furrow, termed the **lateral sulcus**; the fibres of the lateral lemniscus come to the surface in this sulcus, and pass backward and upward, to disappear under the inferior colliculus.

**Structure of the Cerebral Peduncles** (Figs. 721, 722).—On transverse section, each peduncle is seen to consist of a dorsal and a ventral part, separated by a deeply pigmented lamina of gray substance, termed the **substantia nigra**. The dorsal part is named the **tegmentum**; the ventral, the **base** or **crusta**; the two bases are separated from each other, but the tegmenta are joined in the median plane by a forward prolongation of the raphé of the pons. Laterally, the tegmenta are free; dorsally, they blend with the corpora quadrigemina.




FIG. 720.—Coronal section through mid-brain. (Schematic.) (Testut.) 1. Corpora quadrigemina. 2. Cerebral aqueduct. 3. Central gray stratum. 4. Interpeduncular space. 5. Sulcus lateralis. 6. Substantia nigra. 7. Red nucleus of tegmentum. 8. Oculomotor nerve, with 8', its nucleus of origin. a. Lemniscus (in blue) with a' the medial lemniscus and a'' the lateral lemniscus. b. Medial longitudinal fasciculus. c. Raphé. d. Temporo-pontine fibres. e. Portion of medial lemniscus, which runs to the lentiform nucleus and insula. f. Cerebropontine fibres. g. Frontopontine fibres.




FIG. 721.—Transverse section of mid-brain at level of inferior colliculi.

The **base** (*basis pedunculi*; *crusta* or *pes*) is semilunar on transverse section, and consists almost entirely of longitudinal bundles of efferent fibres, which arise from the cells of the cerebral cortex and are grouped into three principal sets, viz., cerebropontine, frontopontine, and temporo-pontine (Fig. 720). The **cerebropontine**

**fibres**, derived from the cells of the motor area of the cerebral cortex, occupy the middle three-fifths of the base; they are continued partly to the nuclei of the motor cerebral nerves, but mainly into the pyramids of the medulla oblongata. The **frontopontine fibres** are situated in the medial fifth of the base; they arise from the cells of the frontal lobe and end in the nuclei of the pons. The **temporopontine fibres** are lateral to the cerebrospinal fibres; they originate in the temporal lobe and end in the nuclei pontis.<sup>1</sup>




FIG. 722.—Transverse section of mid-brain at level of superior colliculi.

The **substantia nigra** (*intercalatum*) is a layer of gray substance containing numerous deeply pigmented, multipolar nerve cells. It is semilunar on transverse section, its concavity being directed toward the tegmentum; from its convexity, prolongations extend between the fibres of the base of the peduncle. Thicker medially than laterally, it reaches from the oculomotor sulcus to the lateral sulcus, and extends from the upper surface of the pons to the subthalamic region; its medial part is traversed by the fibres of the oculomotor nerve as these stream forward to reach the oculomotor sulcus. The connections of the cells of the substantia nigra have not been definitely established.

The **tegmentum** is continuous below with the reticular formation of the pons, and, like it, consists of longitudinal and transverse fibres, together with a considerable amount of gray substance. The principal gray masses of the tegmentum are the red nucleus and the interpeduncular ganglion; of its fibres the chief longitudinal tracts are the brachium conjunctivum, the medial longitudinal fasciculus, and the lemniscus.

**GRAY SUBSTANCE.**—The **red nucleus** is situated in the anterior part of the tegmentum, and is continued upward into the posterior part of the subthalamic region. In sections at the level of the superior colliculus it appears as a circular mass which is traversed by the fibres of the oculomotor nerve. Most of the fibres of the brachium conjunctivum end in it (page 847). The axons of its larger cells cross the middle line and are continued downward into the lateral funiculus of the medulla spinalis as the rubrospinal tract (page 816); those of its smaller cells end mainly in the thalamus.

The **interpeduncular ganglion** is a median collection of nerve cells situated in the ventral part of the tegmentum. The fibres of the fasciculus retroflexus of

<sup>1</sup> A band of fibres, the *tractus peduncularis transversus*, is sometimes seen emerging from in front of the superior colliculus; it passes around the ventral aspect of the peduncle about midway between the pons and the optic tract, and dips into the oculomotor sulcus. This band is a constant structure in many mammals, but is only present in about 30 per cent. of human brains. Since it undergoes atrophy after enucleation of the eyeballs, it may be considered as forming a path for visual sensations.

Meynert, which have their origin in the cells of the ganglion habenulæ (page 859), end in it.

Besides the two nuclei mentioned, there are small collections of cells which form the dorsal and ventral nuclei and the central nucleus or nucleus of the raphé.

WHITE SUBSTANCE.—(1) The origin and course of the *brachium conjunctivum* have already been described (page 841).

(2) The **medial (posterior) longitudinal fasciculus** (Fig. 723) is continuous below with the proper fasciculi of the anterior and lateral funiculi of the medulla spinalis, and has been traced by Edinger as far as a nucleus, the **nucleus of the medial longitudinal fasciculus**, situated in the hypothalamus, immediately in front of the cerebral aqueduct. In the medulla oblongata and pons it runs close to the middle line, near the floor of the fourth ventricle; in the mesencephalon it is situated on the




FIG. 723.—Scheme of the medial longitudinal fasciculus; motor fibres in red, sensory in blue.

ventral aspect of the cerebral aqueduct, below the nuclei of the oculomotor and trochlear nerves. Its connections are imperfectly known, but it consists largely of ascending and descending intersegmental or association fibres, which connect the nuclei of the rhombencephalon and mesencephalon to each other. Many of the descending fibres arise in the superior colliculus, and, after decussating in the middle line, end in the motor nuclei of the pons and medulla oblongata. The ascending fibres arise from the cells of the gray substance of the upper part of the medulla spinalis, and from the nuclei in the medulla oblongata and pons, and pass

without undergoing decussation to the higher nuclei. Fibres are also carried through the medial longitudinal fasciculus from the nucleus of the abducent nerve into the oculomotor nerve of the opposite side, and through this nerve to the Rectus medialis oculi. Again, fibres are said to be prolonged through this fasciculus from the nucleus of the oculomotor nerve into the facial nerve, and are distributed to the Orbicularis oculi, the Corrugator, and the Frontalis.<sup>1</sup>




FIG. 724.—Scheme showing the course of the fibres of the lemniscus; medial lemniscus in blue, lateral in red.

(3) The **lemniscus** or **fillet** (Fig. 724).—The fibres of the lemniscus take origin in the gracile and cuneate nuclei of the medulla oblongata, and cross to the opposite side in the sensory decussation (page 827). They then pass upward through the medulla oblongata, in which they are situated behind the cerebrospinal fibres and between the olives. Here they are joined by the fibres of the superficial antero-lateral fasciculus, these having already undergone decussation in the medulla spinalis. As the lemniscus ascends, it receives additional fibres from the terminal nuclei of the sensory cerebral nerves of the opposite side. In the pons, it assumes a flattened, ribbon-like appearance, and is placed dorsal to the trapezium. In

<sup>1</sup> A. Bruce and J. H. Harvey Pirrie, "On the Origin of the Facial Nerve," *Review of Neurology and Psychiatry*, December, 1908, No. 12, vol. vi, produce weighty evidence against the view that the facial nerve derives fibres from the nucleus of the oculomotor nerve.



the mesencephalon, its lateral part is folded backward and forms nearly a right angle with its medial portion; and hence it is customary to speak of the lemniscus as consisting of lateral and medial parts.

The **lateral lemniscus** (*lemniscus lateralis*) comes to the surface of the mesencephalon along its lateral sulcus, and disappears under the inferior colliculus. It consists of fibres from the terminal nuclei of the cochlear division of the acoustic nerve, together with others from the superior olivary and trapezoid nuclei. Most of these fibres are crossed, but some are uncrossed. Many of them pass to the inferior colliculus of the same or opposite side, but others are prolonged to the thalamus, and thence through the occipital part of the internal capsule to the middle and superior temporal gyri.

The **medial lemniscus** (*lemniscus medialis*) begins in the gracile and cuneate nuclei of the opposite side, and is joined by the superficial antero-lateral fasciculus of the medulla spinalis and by fibres from the terminal nuclei of the sensory cerebral nerves of the opposite side, excepting the cochlear division of the acoustic. In the cerebral peduncle, a few of its fibres pass upward in the lateral part of the base of the peduncle, on the dorsal aspect of the temporopontine fibres, and reach the lentiform nucleus and the insula. The greater part of the medial lemniscus, on the other hand, is prolonged through the tegmentum, and most of its fibres end in the thalamus; probably some are continued directly through the occipital part of the internal capsule to the cerebral cortex. From the cells of the thalamus a relay of fibres is prolonged to the cerebral cortex.

In the tegmentum there are, besides these three tracts, the **tectospinal fasciculus** from the superior colliculus and the **rubrospinal fasciculus** from the red nucleus; these cross the middle line and are continued downward into the medulla spinalis.

The **corpora quadrigemina** (Fig. 729) are four rounded eminences which form the dorsal part of the mesencephalon. They are situated above and in front of the anterior medullary velum and brachia conjunctiva, and below and behind the third ventricle and posterior commissure. They are covered by the splenium of the corpus callosum, and are partly overlapped on either side by the medial angle, or **pulvinar**, of the posterior end of the thalamus; on the lateral aspect, under cover of the pulvinar, is an oval eminence, named the **medial geniculate body**. The corpora quadrigemina are arranged in pairs (**superior and inferior colliculi**), and are separated from one another by a crucial sulcus. The longitudinal part of this sulcus expands superiorly to form a slight depression which supports the **pineal body**, a cone-like structure which projects backward from the thalamencephalon and partly obscures the superior colliculi. From the inferior end of the longitudinal sulcus, a white band, termed the **frinulum veli**, is prolonged downward to the anterior medullary velum; on either side of this band the trochlear nerve emerges, and passes forward on the lateral aspect of the cerebral peduncle to reach the base of the brain. The **superior colliculi** are larger and darker in color than the inferior, and are oval in shape. The **inferior colliculi** are hemispherical, and somewhat more prominent than the superior. The superior colliculi are associated with the sense of sight, the inferior with that of hearing.

From the lateral aspect of each colliculus a white band, termed the **brachium**,




FIG. 725.—Transverse section passing through the sensory decussation. Schematic. (Testut.) 1. Anterior median fissure. 2. Posterior median sulcus. 3, 3'. Head and base of anterior column sulcus. 4. Hypoglossal nerve. 5. Bases of posterior column. 6. Gracile nucleus. 7. Cuneate nucleus. 8, 8'. Lemniscus. 9. Sensory decussation. 10. Cerebrospinal fasciculus.

is prolonged upward and forward. The **superior brachium** extends lateralward from the superior colliculus, and, passing between the pulvinar and medial geniculate body, is partly continued into an eminence called the **lateral geniculate body**, and partly into the optic tract. The **inferior brachium** passes forward and upward from the inferior colliculus and disappears under cover of the **medial geniculate body**.

In close relationship with the corpora quadrigemina are the brachia conjunctiva, which emerge from the upper and medial parts of the cerebellar hemispheres. They run upward and forward, and, passing under the inferior colliculi, enter the tegmenta as already described (page 841).

**Structure of the Corpora Quadrigemina.**—The **inferior colliculus** (*colliculus inferior; inferior quadrigeminal body; postgemina*) consists of a compact nucleus of gray substance containing large and small multipolar nerve cells, and more or less completely surrounded by white fibres derived from the lateral lemniscus. Most of these fibres end in the gray nucleus of the same side, but some cross the middle line and end in that of the opposite side. From the cells of the gray nucleus, fibres are prolonged through the inferior brachium into the tegmentum of the cerebral peduncle, and are carried to the thalamus and the cortex of the temporal lobe; other fibres cross the middle line and end in the opposite colliculus.

The **superior colliculus** (*colliculus superior; superior quadrigeminal body; pregemina*) is covered by a thin stratum (**stratum zonale**) of white fibres, the majority of which are derived from the optic tract. Beneath this is the **stratum cinereum**, a cap-like layer of gray substance, thicker in the centre than at the circumference, and consisting of numerous small multipolar nerve cells, imbedded in a fine network of nerve fibres. Still deeper is the **stratum opticum**, containing large multipolar nerve cells, separated by numerous fine nerve fibres. Finally, there is the **stratum lemnisci**, consisting of fibres derived partly from the lemniscus and partly from the cells of the stratum opticum; interspersed among these fibres are many large multipolar nerve cells. The two last-named strata are sometimes termed the **gray-white layers**, from the fact that they consist of both gray and white substance. Of the afferent fibres which reach the superior colliculus, some are derived from the lemniscus, but the majority have their origins in the retina and are conveyed to it through the superior brachium; all of them end by arborizing around the cells of the gray substance. Of the efferent fibres, some cross the middle line to the opposite colliculus; many ascend through the superior brachium, and finally reach the cortex of the occipital lobe of the cerebrum; while others, after undergoing decussation (**fountain decussation of Meynert**) form the tectospinal fasciculus which descends through the formatio reticularis of the mesencephalon, pons, and medulla oblongata into the medulla spinalis, where it is found partly in the anterior funiculus and partly intermingled with the fibres of the rubrospinal tract.

The corpora quadrigemina are larger in the lower animals than in man. In fishes, reptiles, and birds they are hollow, and only two in number (*corpora bigemina*); they represent the superior colliculi of mammals, and are frequently termed the optic lobes, because of their intimate connection with the optic tracts.

The **cerebral aqueduct** (*aqueductus cerebri; aqueduct of Sylvius*) is a narrow canal, about 15 mm. long, situated between the corpora quadrigemina and tegmenta, and connecting the third with the fourth ventricle. Its shape, as seen in transverse section, varies at different levels, being T-shaped, triangular above, and oval in the middle; the central part is slightly dilated, and was named by Retzius the **ventricle of the mid-brain**. It is lined by ciliated columnar epithelium, and is surrounded by a layer of gray substance named the **central gray stratum**: this is continuous below with the gray substance in the rhomboid fossa, and above with that of the third ventricle. Dorsally, it is partly separated from the gray

substance of the quadrigeminal bodies by the fibres of the lemniscus; ventral to it are the medial longitudinal fasciculus, and the *formatio reticularis* of the tegmentum. Scattered throughout the central gray stratum are numerous nerve cells of various sizes, interlaced, by a net-work of fine fibres. Besides these scattered cells it contains three groups which constitute the nuclei of the oculomotor and trochlear nerves, and the nucleus of the mesencephalic root of the trigeminal nerve. The **nucleus of the trigeminal nerve** extends along the entire length of the aqueduct, and occupies the lateral part of the gray stratum, while the nuclei of the oculomotor and trochlear nerves are situated in its ventral part. The **nucleus of the oculomotor nerve** is about 10 cm. long, and lies under the superior colliculus, beyond which, however, it extends for a short distance into the gray substance of the third ventricle. The **nucleus of the trochlear nerve** is small and nearly circular, and is on a level with a plane carried transversely through the upper part of the inferior colliculus.

### THE PROSENCEPHALON OR FORE-BRAIN.

The **prosencephalon** or **fore-brain** consists of: (1) the **diencephalon**, corresponding in a large measure to the third ventricle and the structures which bound it; and (2) the **telencephalon**, comprising the largest part of the brain, viz., the cerebral hemispheres; these hemispheres are intimately connected with each other across the middle line, and each contains a large cavity, named the lateral ventricle. The lateral ventricles communicate through the interventricular foramen with the third ventricle, but are separated from each other by a medial septum, the *septum pellucidum*; this contains a slit-like cavity, which does not communicate with the ventricles.

**The Diencephalon.**—The diencephalon is connected above and in front with the cerebral hemispheres; behind with the mesencephalon. Its upper surface is concealed by the corpus callosum, and is covered by a fold of pia mater, named the *tela chorioidea* of the third ventricle; inferiorly it reaches to the base of the brain.

The diencephalon comprises: (1) the **thalamencephalon**; (2) the **pars mamillaria hypothalami**; and (3) the **posterior part of the third ventricle**. For descriptive purposes, however, it is more convenient to consider the whole of the third ventricle and its boundaries together; this necessitates the inclusion, under this heading, of the *pars optica hypothalami* and the corresponding part of the third ventricle—structures which properly belong to the telencephalon.

**The Thalamencephalon.**—The thalamencephalon comprises: (1) the **thalamus**; (2) the **metathalamus** or **corpora geniculata**; and (3) the **epithalamus**, consisting of the *trigonum habenulae*, the pineal body, and the posterior commissure.

The **Thalami** (*optic thalamus*) (Figs. 726, 727) are two large ovoid masses, situated one on either side of the third ventricle and reaching for some distance behind that cavity. Each measures about 4 cm. in length, and presents two extremities, an anterior and a posterior, and four surfaces, superior, inferior, medial, and lateral.

The **anterior extremity** is narrow; it lies close to the middle line and forms the posterior boundary of the interventricular foramen.

The **posterior extremity** is expanded, directed backward and lateralward, and overlaps the superior colliculus. Medially it presents an angular prominence, the **pulvinar**, which is continued laterally into an oval swelling, the **lateral geniculate body**, while beneath the pulvinar, but separated from it by the superior brachium, is a second oval swelling, the **medial geniculate body**.

The **superior surface** is free, slightly convex, and covered by a layer of white substance, termed the **stratum zonale**. It is separated laterally from the caudate nucleus by a white band, the **stria terminalis**, and by the terminal vein. It is divided into a medial and a lateral portion by an oblique shallow furrow which runs from

behind forward and medialward and corresponds with the lateral margin of the fornix; the lateral part forms a portion of the floor of the lateral ventricle, and is covered by the epithelial lining of this cavity; the medial part is covered by the tela chorioidea of the third ventricle, and is destitute of an epithelial covering. In front, the superior is separated from the medial surface by a salient margin, the *taenia thalami*, along which the epithelial lining of the third ventricle is reflected on to the under surface of the tela chorioidea. Behind, it is limited medially by a groove, the *sulcus habenulae*, which intervenes between it and a small triangular area, termed the *trigonum habenulae*.

The *inferior surface* rests upon and is continuous with the upward prolongation of the tegmentum (*subthalamie tegmental region*), in front of which it is related to the *substantia innominata* of Meynert.




FIG. 726.—Dissection showing the ventricles of the brain.

The *medial surface* constitutes the upper part of the lateral wall of the third ventricle, and is connected to the corresponding surface of the opposite thalamus by a flattened gray band, the *massa intermedia* (*middle or gray commissure*). This mass averages about 1 cm. in its antero-posterior diameter: it sometimes consists of two parts and occasionally is absent. It contains nerve cells and nerve fibres; a few of the latter may cross the middle line, but most of them pass toward the middle line and then curve lateralward on the same side.

The *lateral surface* is in contact with a thick band of white substance which forms the occipital part of the internal capsule and separates the thalamus from the lentiform nucleus of the corpus striatum.

**Structure.**—The thalamus consists chiefly of gray substance, but its upper surface is covered by a layer of white substance, named the *stratum zonale*, and its lateral surface by a similar layer termed the *lateral medullary lamina*. Its gray

substance is incompletely subdivided into three parts—**anterior**, **medial**, and **lateral**—by a white layer, the **medial medullary lamina**. The anterior part comprises the anterior tubercle, the medial part lies next the lateral wall of the third ventricle while the lateral and largest part is interposed between the medullary laminae and includes the pulvinar. The lateral part is traversed by numerous fibres which radiate from the thalamus into the internal capsule, and pass through the latter to the cerebral cortex. These three parts are built up of numerous nuclei, the connections of many of which are imperfectly known.




FIG. 727.—Coronal section of brain immediately in front of pons.

**Connections.**—The thalamus may be regarded as a large ganglionic mass in which the ascending tracts of the tegmentum and a considerable proportion of the fibres of the optic tract end, and from the cells of which numerous fibres (thalamocortical) take origin, and radiate to almost every part of the cerebral cortex. The lemniscus, together with the other longitudinal strands of the tegmentum, enters its ventral part: the **thalamomamillary fasciculus** (*bundle of Vicq d'Azyr*), from the corpus mamillare, enters in its anterior tubercle, while many of the fibres of the optic tract terminate in its posterior end. The thalamus also receives numerous fibres (corticothalamic) from the cells of the cerebral cortex. The fibres that arise from the cells of the thalamus form four principal groups or stalks: (a) those of the **anterior stalk** pass through the frontal part of the internal capsule to the frontal lobe; (b) the fibres of the **posterior stalk** (*optic radiations*) arise in the pulvinar and are



conveyed through the occipital part of the internal capsule to the occipital lobe: the fibres of the **inferior stalk** leave the under and medial surfaces of the thalamus, and pass beneath the lentiform nucleus to the temporal lobe and insula: those of the **parietal stalk** pass from the lateral nucleus of the thalamus to the parietal lobe. Fibres also extend from the thalamus into the corpus striatum—those destined for the caudate nucleus leave the lateral surface, and those for the lentiform nucleus, the inferior surface of the thalamus.




FIG. 728.—Coronal section of brain through intermediate mass of third ventricle.

The **Metathalamus** (Fig. 729) comprises the **geniculate bodies**, which are two in number—a **medial** and a **lateral**—on each side.

The **medial geniculate body** (*corpus geniculatum mediale*; *internal geniculate body*; *postgeniculatum*) lies under cover of the pulvinar of the thalamus and on the lateral aspect of the corpora quadrigemina. Oval in shape, with its long axis directed forward and lateralward, it is lighter in color and smaller in size than the lateral. The inferior brachium from the inferior colliculus disappears under cover of it while from its lateral extremity a strand of fibres passes to join the optic tract. Entering it are many acoustic fibres from the lateral lemniscus. The medial geniculate bodies are connected with one another by the commissure of Gudden, which passes through the posterior part of the optic chiasma.

The **lateral geniculate body** (*corpus geniculatum laterale*; *external geniculate body*; *pregeniculatum*) is an oval elevation on the lateral part of the posterior end of the

thalamus, and is connected with the superior colliculus by the superior brachium. It is of a dark color, and presents a laminated arrangement consisting of alternate layers of gray and white substance. It receives numerous fibres from the optic tract, while other fibres of this tract pass over or through it into the pulvinar. Its cells are large and pigmented; their axons pass to the visual area in the occipital part of the cerebral cortex.

The superior colliculus, the pulvinar, and the lateral geniculate body receive many fibres from the optic tracts, and are therefore intimately connected with sight, constituting what are termed the **lower visual centres**. Extirpation of the eyes in a newly born animal entails an arrest of the development of these centres, but has no effect on the medial geniculate bodies or on the inferior colliculi. Moreover, the latter are well-developed in the mole, an animal in which the superior colliculi are rudimentary.




FIG. 729.—Hind- and mid-brains; postero-lateral view.

The **Epithalamus** comprises the **trigonum habenulae**, the **pineal body**, and the **posterior commissure**.

The **trigonum habenulae** is a small depressed triangular area situated in front of the superior colliculus and on the lateral aspect of the posterior part of the taenia thalami. It contains a group of nerve cells termed the **ganglion habenulae**. Fibres enter it from the stalk of the pineal body, and others, forming what is termed the **habenular commissure**, pass across the middle line to the corresponding ganglion of the opposite side. Most of its fibres are, however, directed downward and form a bundle, the **fasciculus retroflexus** of Meynert, which passes medial to the red nucleus, and, after decussating with the corresponding fasciculus of the opposite side, ends in the interpeduncular ganglion.

The **pineal body** (*corpus pineale*; *epiphysis*) is a small, conical, reddish-gray body which lies in the depression between the superior colliculi. It is placed beneath the splenium of the corpus callosum, but is separated from this by the tela chorioidea of the third ventricle, the lower layer of which envelops it. It measures about 8 cm. in length, and its base, directed forward, is attached by a stalk or peduncle

of white substance. The **stalk** of the pineal body divides anteriorly into two laminae, a dorsal and a ventral, separated from one another by the pineal recess of the third ventricle. The ventral lamina is continuous with the posterior commissure; the dorsal lamina is continuous with the habenular commissure and divides into two strands the medullary striæ, which run forward, one on either side, along the junction of the medial and upper surfaces of the thalamus to blend in front with the columns of the fornix.

**Structure.**—The pineal body is destitute of nervous substance, and consists of follicles lined by epithelium and enveloped by connective tissue. These follicles contain a variable quantity of gritty material, composed of phosphate and carbonate of calcium, phosphate of magnesium and ammonia, and a little animal matter.

The pineal body is generally believed to be the homologue of the pineal eye of lizards. In these animals it is attached by an elongated stalk and projects through an aperture in the roof of the cranium. Its extremity lies immediately under the epidermis, and, on microscopic examination, presents in a rudimentary fashion structures similar to those found in the eyeball. Recent observations tend to the conclusion that the pineal body arises as a paired structure, probably serially homologous with the paired eyes.

The **posterior commissure** is a rounded band of white fibres crossing the middle line on the dorsal aspect of the upper end of the cerebral aqueduct. Its fibres acquire their medullary sheaths early, but their connections have not been definitely determined. Most of them have their origin in a nucleus, the **nucleus of the posterior commissure** (*nucleus of Darkschewitsch*), which lies in the central gray substance of the upper end of the cerebral aqueduct, in front of the nucleus of the oculomotor nerve. Some are probably derived from the posterior part of the thalamus and from the superior colliculus, while others are believed to be continued downward into the medial longitudinal fasciculus.

The **Hypothalamus** (Fig. 730) includes the **subthalamie tegmental region** and the structures forming the greater part of the floor of the third ventricle, viz., the **corpora mamillaria**, **tuber cinereum**, **infundibulum**, **hypophysis**, and **optic chiasma**.

The **subthalamie tegmental region** consists of the upward continuation of the tegmentum; it lies on the ventro-lateral aspect of the thalamus and separates it from the fibres of the internal capsule. The red nucleus and the substantia nigra are prolonged into its lower part; in front it is continuous with the substantia innominata of Meynert, medially with the gray substance of the floor of the third ventricle.

It consists from above downward of three strata: (1) **stratum dorsale**, directly applied to the under surface of the thalamus and consisting of fine longitudinal fibres; (2) **zona incerta**, a continuation forward of the formatio reticularis of the tegmentum; and (3) the **corpus subthalamieum** (*nucleus of Luys*), a brownish mass presenting a lenticular shape on transverse section, and situated on the dorsal aspect of the fibres of the base of the cerebral peduncle; it is encapsuled by a lamina of nerve fibres and contains numerous medium-sized nerve cells, the connections of which are as yet not fully determined.

The **corpora mamillaria** (*corpus albicans*) are two round white masses, each about the size of a small pea, placed side by side below the gray substance of the floor of the third ventricle in front of the posterior perforated substance. They consist of white substance externally and of gray substance internally, the cells of the latter forming two nuclei, a **medial** of smaller and a **lateral** of larger cells. The white substance is mainly formed by the fibres of the columns of the fornix, which descend to the base of the brain and end partly in the corpora mamillaria. From the cells of the gray substance of each mamillary body two fasciculi arise: one, the **thalamomamillary fasciculus** (*bundle of Vicq d'Azyr*), passes upward into the anterior nucleus of the thalamus; the other is directed downward into the tegmentum. Afferent fibres are believed to reach the corpus mamillare from the medial lemniscus and from the tegmentum.

The **tuber cinereum** is a hollow eminence of gray substance situated between the corpora mamillaria behind, and the optic chiasma in front. Laterally it is




FIG. 730.—Median sagittal section of brain. The relations of the pia mater are indicated by the red color.

continuous with the anterior perforated substances and anteriorly with a thin lamina, the **lamina terminalis**. From the under surface of the tuber cinereum a hollow conical process, the **infundibulum**, projects downward and forward and is attached to the posterior lobe of the hypophysis.

In the lateral part of the tuber cinereum is a nucleus of nerve cells, the **basal optic nucleus of Meynert**, while close to the cavity of the third ventricle are three additional nuclei. Between the tuber cinereum and the corpora mamillaria a small elevation, with a corresponding depression in the third ventricle, is sometimes seen. Retzius has named it the **eminencia saccularis**, and regards it as a representative of the saccus vasculosus found in this situation in some of the lower vertebrates.




FIG. 731.—The hypophysis cerebri, in position. Shown in sagittal section. (Testut.) 1, 1'. Anterior and posterior lobes of hypophysis. 2. Infundibulum. 3. Optic chiasma. 4. Lamina terminalis. 5. Optic recess. 6. Anterior commissure. 7, 7'. Circular sinus. 8. Anterior cerebral artery. 9. Basilar artery. 10. Posterior cerebral artery. 11. Corpus mamillare. 12. Cerebral peduncle. 13. Pons.

The **hypophysis** (*pituitary body*) (Fig. 731) is a reddish-gray, somewhat oval mass, measuring about 1.25 cm. in its transverse, and about 8 cm. in its antero-



posterior diameter. It is attached to the end of the infundibulum, and is situated in the fossa hypophyseos of the sphenoidal bone, where it is retained by a circular fold of dura mater, the **diaphragma sellæ**; this fold almost completely roofs in the fossa, leaving only a small central aperture through which the infundibulum passes.

The hypophysis consists of an anterior and a posterior lobe, which differ from one another in their mode of development and in their structure (Fig. 732). The **anterior lobe** is the larger, and is somewhat kidney-shaped, the concavity being directed backward and embracing the posterior lobe. It is developed from a diverticulum of the ectoderm of the primitive buccal cavity or stomodeum (see page 166) and consists of a pars anterior and a pars intermedia, separated from each other by a narrow cleft, the remnant of the pouch or diverticulum. The pars anterior is extremely vascular and consists of epithelial cells of varying size and shape, arranged in cord-like trabeculæ or alveoli and separated by large, thin-walled bloodvessels. The pars intermedia is a thin lamina closely applied to the body and neck of the posterior lobe and extending on to the neighboring parts of the brain; it contains few bloodvessels and consists of finely granular cells between which are small masses of colloid material. The **posterior lobe** is developed as a downgrowth from the floor of the embryonic brain, and during early fetal life contains a cavity continuous with that of the third ventricle. In some animals, *e. g.*,




FIG. 732.—Median sagittal section through the hypophysis of an adult monkey. Semidiagrammatic. (Herring.)

cat, this cavity persists throughout life. Although of nervous origin the posterior lobe contains no nerve cells or fibres. It consists of neuroglia cells and fibres and is invaded by columns which grow into it from the pars intermedia; imbedded in it are large quantities of a colloid substance histologically similar to that found in the thyroid gland. In certain of the lower vertebrates, *e. g.*, fishes, nervous structures are present, and the lobe is of large size.

**Applied Anatomy.**—Prof. Schäfer has isolated from the pars intermedia a substance, no doubt an internal secretion, that causes constriction of the bloodvessels, rise of arterial blood pressure, and increased secretion of urine, when injected subcutaneously. Enlargement of the hypophysis and of the cavity of the sella turcica are found in the rare disease *acromegaly*, which is characterized by gradual enlargement of the face, hands, and feet, with headache and often a peculiar type of blindness. This blindness is due to the pressure of the enlarging hypophysis on the optic chiasma (Fig. 731). The pressure causes atrophy, for the most part of the nerve fibres coming from the nasal sides of the retina; with the result that the patient loses his two temporal fields of vision while retaining his nasal fields (bitemporal hemianopsy).

**Optic Chiasma** (*chiasma opticum*; *optic commissure*).—The optic chiasma is a flattened, somewhat quadrilateral band of fibres, situated at the junction of the floor and anterior wall of the third ventricle. Most of its fibres have their origins



in the retina, and reach the chiasma through the optic nerves, which are continuous with its antero-lateral angles. In the chiasma, they undergo a partial decussation (Fig. 733); the fibres from the nasal half of the retina decussate and enter the optic tract of the opposite side, while the fibres from the temporal half of the retina do not undergo decussation, but pass back into the optic tract of the same side. Occupying the posterior part of the commissure, however, is a strand of fibres, the **commissure of Gudden**, which is not derived from the optic nerves; it forms a connecting link between the medial geniculate bodies.




FIG. 733.—Scheme showing central connections of the optic nerves and optic tracts.

**Optic Tracts.**—The optic tracts are continued backward and lateralward from the postero-lateral angles of the optic chiasma. Each passes between the anterior perforated substance and the tuber cinereum, and, winding around the ventro-lateral aspect of the cerebral peduncle, divides into a medial and a lateral root. The former comprises the fibres of Gudden's commissure. The lateral root consists mainly of afferent fibres which arise in the retina and undergo partial decussation in the optic chiasma, as described; but it also contains a few fine efferent fibres which have their origins in the brain and their terminations in the retina. When traced backward, the afferent fibres of the lateral root are found to end in the lateral geniculate body and pulvinar of the thalamus, and in the superior colliculus; and

these three structures constitute the **lower visual centres**. Fibres arise from the nerve cells in these centres and pass through the occipital part of the internal capsule, under the name of the **optic radiations**, to the cortex of the occipital lobe of the cerebrum, where the **higher or cortical visual centre** is situated. Some of the fibres of the optic radiations take an opposite course, arising from the cells of the occipital cortex and passing to the lower visual centres. Some fibres are detached from the optic tract, and pass through the cerebral peduncle to the nucleus of the oculomotor nerve. These may be regarded as the afferent branches for the Sphincter pupillae and Ciliaris muscles. Other fibres have been described as reaching the cerebellum through the brachia conjunctiva; while others, again, are lost in the pons.

**The Third Ventricle** (*ventriculus tertius*) (Figs. 726, 730).—The third ventricle is a median cleft between the two thalami. Behind, it communicates with the fourth ventricle through the cerebral aqueduct, and in front with the lateral ventricles through the interventricular foramen. Somewhat triangular in shape, with the apex directed backward, it has a **roof**, a **floor**, an **anterior** and a **posterior** boundary and a pair of **lateral walls**.




FIG. 734.—Coronal section of lateral and third ventricles. (Diagrammatic.)

The **roof** (Fig. 734) is formed by a layer of epithelium, which stretches between the upper edges of the lateral walls of the cavity and is continuous with the epithelial lining of the ventricle. It is covered by and adherent to a fold of pia mater, named the **tela chorioidea** of the third ventricle, from the under surface of which a pair of vascular fringed processes, the **choroid plexuses of the third ventricle**, project downward, one on either side of the middle line, and invaginate the epithelial roof into the ventricular cavity.

The **floor** slopes downward and forward and is formed mainly by the structures which constitute the hypothalamus: from before backward these are: the optic chiasma, the tuber cinereum and infundibulum, and the corpora mamillaria. Behind the last, the floor is formed by the interpeduncular fossa and the tegmenta of the cerebral peduncles. The ventricle is prolonged downward as a funnel-shaped recess, the **recessus infundibuli**, into the infundibulum, and to the apex of the latter the hypophysis is attached.

The **anterior boundary** is constituted below by the **lamina terminalis**, a thin layer of gray substance stretching from the upper surface of the optic chiasma to the rostrum of the corpus callosum; above by the columns of the fornix and the anterior commissure. At the junction of the floor and anterior wall, immediately above the optic chiasma, the ventricle presents a small angular recess or diverticulum,

the optic recess. Between the columns of the fornix, and above the anterior commissure, is a second recess termed the *vulva*. At the junction of the roof and anterior wall of the ventricle, and situated between the thalami behind and the columns of the fornix in front, is the *interventricular foramen* (*foramen of Monro*) through which the third communicates with the lateral ventricles.

The *posterior boundary* is constituted by the pineal body, the posterior commissure and the cerebral aqueduct. A small recess, the *recessus pinealis*, projects into the stalk of the pineal body, while in front of and above the pineal body is a second recess, the *recessus suprapinealis*, consisting of a diverticulum of the epithelium which forms the ventricular roof.

Each *lateral wall* consists of an upper portion formed by the medial surface of the anterior two-thirds of the thalamus, and a lower consisting of an upward continuation of the gray substance of the ventricular floor. These two parts correspond to the alar and basal laminae respectively of the lateral wall of the fore-brain vesicle and are separated from each other by a furrow, the *sulcus of Monro*, which extends from the interventricular foramen to the cerebral aqueduct (pages 125 and 126). The lateral wall is limited above by the *taenia thalami*. The columns of the fornix curve downward in front of the interventricular foramen, and then run in the lateral walls of the ventricle, where, at first, they form distinct prominences, but subsequently are lost to sight. The lateral walls are joined to each other across the cavity of the ventricle by a band of gray matter, the *massa intermedia* (page 856).

**Interpeduncular Fossa** (Fig. 735).—This is a somewhat lozenge-shaped area of the base of the brain, limited in front by the optic chiasma, behind by the antero-superior surface of the pons, antero-laterally by the converging optic tracts, and postero-laterally by the diverging cerebral peduncles. The structures contained in it have already been described; from behind forward, they are the posterior perforated substance, corpora mamillaria, tuber cinereum, infundibulum, and hypophysis.

**The Telencephalon.**—The telencephalon includes: (1) the cerebral hemispheres with their cavities, the lateral ventricles; and (2) the *pars optica hypothalami* and the anterior portion of the third ventricle (already described under the diencephalon). As stated in the chapter on Embryology (page 128), each cerebral hemisphere may be divided into three fundamental parts, viz., the rhinencephalon, the corpus striatum, and the neopallium. The rhinencephalon, associated with the sense of smell, is the oldest part of the telencephalon, and forms almost the whole of the hemisphere in some of the lower animals, *e. g.*, fishes, amphibians, and reptiles. In man it is rudimentary, whereas the neopallium undergoes great development and forms the chief part of the hemisphere.

**The Cerebral Hemispheres.**—The cerebral hemispheres constitute the largest part of the encephalon, and, when viewed together from above, assume the form of an ovoid mass broader behind than in front, the greatest transverse diameter corresponding with a line connecting the two parietal eminences. The hemispheres are separated medially by a deep cleft, named the *longitudinal cerebral fissure*, and each possesses a central cavity, the lateral ventricle.

**The Longitudinal Cerebral Fissure** (*fissura cerebri longitudinalis*; *great longitudinal fissure*) contains a sickle-shaped process of dura mater, the *falx cerebri*. It front and behind, the fissure extends from the upper to the under surfaces of the hemispheres and completely separates them, but its middle portion only separates them for about one-half of their vertical extent; for at this part they are connected across the middle line by a great central white commissure, the *corpus callosum*.

In a median sagittal section (Fig. 730) the cut corpus callosum presents the appearance of a broad, arched band. Its *thick posterior end*, termed the *splenium*, overlaps the mid-brain, but is separated from it by the tela chorioidea of the third

ventricle and the pineal body. Its anterior curved end, termed the **genu**, gradually tapers into a thinner portion, the **rostrum**, which is continued downward and backward in front of the anterior commissure to join the lamina terminalis. Arching backward from immediately behind the anterior commissure to the under surface of the splenium is a second white band named the **fornix**: between this and the corpus callosum are the laminae and cavity of the septum pellucidum.




FIG. 735.—Base of brain.

**Surfaces of the Cerebral Hemispheres.**—Each hemisphere presents three surfaces: **lateral**, **medial**, and **inferior**.

The **lateral surface** is convex in adaptation to the concavity of the corresponding half of the vault of the cranium. The **medial surface** is flat and vertical, and is separated from that of the opposite hemisphere by the great longitudinal fissure and the falx cerebri. The **inferior surface** is of an irregular form, and may be divided into three areas: anterior, middle, and posterior. The anterior area, formed by the orbital surface of the frontal lobe, is concave, and rests on the roof of the orbit and nose; the middle area is convex, and consists of the under surface of the temporal lobe: it is adapted to the corresponding half of the middle cranial fossa. The posterior area is concave, directed medialward as well as downward, and is named the **tentorial surface**, since it rests upon the tentorium cerebelli, which intervenes between it and the upper surface of the cerebellum.

These three surfaces are separated from each other by the following **borders**:

(a) **supero-medial**, between the lateral and medial surfaces; (b) **infero-lateral**, between the lateral and inferior surfaces; the anterior part of this border separating the lateral from the orbital surface, is known as the **superciliary border**; (c) **medial occipital**, separating the medial and tentorial surfaces; and (d) **medial orbital**, separating the orbital from the medial surface. The anterior end of the hemisphere is named the **frontal pole**; the posterior, the **occipital pole**; and the anterior end of the temporal lobe, the **temporal pole**. About 5 cm. in front of the occipital pole on the infero-lateral border is an indentation or notch, named the **preoccipital notch**.

The surfaces of the hemispheres are moulded into a number of irregular eminences, named **gyri** or **convolutions**, and separated by furrows termed **fissures** and **sulci**. The furrows are of two kinds, *complete* and *incomplete*. The former appear early in fetal life, are few in number, and are produced by infoldings of the entire thickness of the brain wall, and give rise to corresponding elevations in the interior of the ventricle. They comprise the hippocampal fissure, and parts of the calcarine and collateral fissures. The incomplete furrows are very numerous, and only indent the subjacent white substance, without producing any corresponding elevations in the ventricular cavity.

The gyri and their intervening fissures and the sulci are fairly constant in their arrangement; at the same time they vary within certain limits, not only in different individuals, but on the two hemispheres of the same brain. The convoluted condition of the surface permits of a great increase of the gray matter without the sacrifice of much additional space. The number and extent of the gyri, as well as the depth of the intervening furrows, appear to bear a direct relation to the intellectual powers of the individual.

Certain of the fissures and sulci are utilized for the purpose of dividing the hemisphere into lobes, and are therefore termed **interlobular**; included under this category are the lateral cerebral, parietooccipital, calcarine, and collateral fissures, the central and cingulate sulci, and the sulcus circularis.

The **Lateral Cerebral Fissure** (*fissura cerebri lateralis* [Sylvii]; *fissure of Sylvius*) (Fig. 737) is a well-marked cleft on the inferior and lateral surfaces of the hemisphere, and consists of a short stem which divides into three rami. The **stem** is situated on the base of the brain, and commences in a depression at the lateral angle of the anterior perforated substance. From this point it extends between the anterior part of the temporal lobe and the orbital surface of the frontal lobe, and reaches the lateral surface of the hemisphere. Here it divides into three rami: an anterior horizontal, an anterior ascending, and a posterior. The **anterior horizontal ramus** passes forward for about 2.5 cm. into the inferior frontal gyrus, while the **anterior ascending ramus** extends upward into the same convolution for about an equal distance. The **posterior ramus** is the longest; it runs backward and slightly upward for about 7 cm., and ends by an upward inflexion in the parietal lobe.




FIG. 736.—Lateral surface of left cerebral hemisphere, viewed from above.



The **Central Sulcus** (*sulcus centralis* [Rolandi]; *fissure of Rolando*; *central fissure*) (Figs. 736, 737) is situated about the middle of the lateral surface of the hemisphere, and begins in or near the longitudinal cerebral fissure, a little behind its mid-point. It runs sinuously downward and forward, and ends a little above the posterior




FIG. 737.—Lateral surface of left cerebral hemisphere, viewed from the side.

ramus of the lateral fissure, and about 2.5 cm. behind the anterior ascending ramus of the same fissure. It described two chief curves: a **superior genu** with its concavity directed forward, and an **inferior genu** with its concavity directed backward. The central sulcus forms an angle opening forward of about 70° with the median plane.




FIG. 738.—Medial surface of left cerebral hemisphere.

**The Parietooccipital Fissure** (*fissura parietooccipitalis*).—Only a small part of this fissure is seen on the lateral surface of the hemisphere, its chief part being on the medial surface.

The **lateral part** of the parietooccipital fissure (Fig. 737) is situated about 5 cm. in front of the occipital pole of the hemisphere, and measures about 1.25 cm. in length.

The **medial part** of the parietooccipital fissure (Fig. 738) runs downward and forward as a deep cleft on the medial surface of the hemisphere, and joins the calcarine fissure below and behind the posterior end of the corpus callosum. In most cases it contains a submerged gyrus.

The **Calcarine Fissure** (*fissura calcarina*) (Fig. 738) is on the medial surface of the hemisphere. It begins near the occipital pole in two converging rami, and runs forward to a point a little below the splenium of the corpus callosum, where it is joined at an acute angle by the medial part of the parietooccipital fissure. The anterior part of this fissure gives rise to the prominence of the *calcar avis* in the posterior cornu of the lateral ventricle.

The **Cingulate Sulcus** (*sulcus cinguli*; *callosomarginal fissure*) (Fig. 738) is on the medial surface of the hemisphere; it begins below the anterior end of the corpus callosum and runs upward and forward nearly parallel to the rostrum of this body and, curving in front of the genu, is continued backward above the corpus callosum, and finally ascends to the supero-medial border of the hemisphere a short distance behind the upper end of the central sulcus. It separates the superior frontal from the cingulate gyrus.

The **Collateral Fissure** (*fissura collateralis*) (Fig. 738) is on the tentorial surface of the hemisphere and extends from near the occipital pole to within a short distance of the temporal pole. Behind, it lies below and lateral to the calcarine fissure, from which it is separated by the lingual gyrus; in front, it is situated between the hippocampal gyrus and the anterior part of the fusiform gyrus.

The **Sulcus Circularis** (*circuminsular fissure*) (Fig. 741) is on the lower and lateral surfaces of the hemisphere: it surrounds the insula and separates it from the frontal, parietal, and temporal lobes.

**Lobes of the Hemispheres.**—By means of these fissures and sulci, assisted by certain arbitrary lines, each hemisphere is divided into the following lobes: the **frontal**, the **parietal**, the **temporal**, the **occipital**, the **limbic**, and the **insula**.

**Frontal Lobe** (*lobus frontalis*).—On the lateral surface of the hemisphere this lobe extends from the frontal pole to the central sulcus, the latter separating it from the parietal lobe. Below, it is limited by the posterior ramus of the lateral fissure, which intervenes between it and the central lobe. On the medial surface, it is separated from the cingulate gyrus by the cingulate sulcus; and on the inferior surface, it is bounded behind by the stem of the lateral fissure.

The **lateral surface** of the frontal lobe (Fig. 737) is traversed by three sulci which divide it into four gyri: the sulci are named the precentral, and the superior and inferior frontal; the gyri are the anterior central, and the superior, middle, and inferior frontal. The **precentral sulcus** runs parallel to the central sulcus, and is usually divided into an upper and a lower part; between it and the central sulcus is the **anterior central gyrus**. From the precentral sulcus, the **superior and inferior frontal sulci** run forward and downward, and divide the remainder of the lateral surface of the lobe into three parallel gyri, named, respectively the **superior, middle, and inferior frontal gyri**.

The **anterior central gyrus** (*gyrus centralis anterior*; *ascending frontal convolution*; *precentral gyre*) is bounded in front by the precentral sulcus, behind by the central sulcus; it extends from the supero-medial border of the hemisphere to the posterior ramus of the lateral fissure.

The **superior frontal gyrus** (*gyrus frontalis superior*; *superfrontal gyre*) is situated above the superior frontal sulcus and is continued on to the medial surface of the hemisphere. The portion on the lateral surface of the hemisphere is usually more or less completely subdivided into an upper and a lower part by an antero-

posterior sulcus, the **paramedial sulcus**, which, however, is frequently interrupted by bridging gyri.

The **middle frontal gyrus** (*gyrus frontalis medius; medifrontal gyre*), between the superior and inferior frontal sulci, is continuous with the anterior orbital gyrus on the inferior surface of the hemisphere; it is frequently subdivided into two by a horizontal sulcus, the **medial frontal sulcus** of Eberstaller, which ends anteriorly in a wide bifurcation.

The **inferior frontal gyrus** (*gyrus frontalis inferior; subfrontal gyre*) lies below the inferior frontal sulcus, and extends forward from the lower part of the precentral sulcus; it is continuous with the lateral and posterior orbital gyri on the under surface of the lobe. It is subdivided by the anterior horizontal and ascending rami of the lateral fissure into three parts, viz., (1) the **orbital part**, below the anterior horizontal ramus of the fissure; (2) the **triangular part** (*cap of Broca*), between the ascending and horizontal rami; and (3) the **basilar part**, behind the anterior ascending ramus. The left inferior frontal gyrus is, as a rule, more highly developed than the right, and is named the **gyrus of Broca**, from the fact that Broca described it as the centre for articulate speech.

The **inferior or orbital surface** of the frontal lobe is concave, and rests on the orbital plate of the frontal bone (Fig. 739). It is divided into four orbital gyri by a well-marked H-shaped **orbital sulcus**. These are named, from their position, the **medial, anterior, lateral, and posterior orbital gyri**. The medial orbital gyrus presents a well-marked antero-posterior sulcus, the **olfactory sulcus**, for the olfactory tract; the portion medial to this is named the **straight gyrus**, and is continuous with the superior frontal gyrus on the medial surface.




FIG. 739.—Orbital surface of left frontal lobe.

The **medial surface** of the frontal lobe is occupied by the medial part of the superior frontal gyrus (*marginal gyrus*) (Fig. 738). It lies between the cingulate sulcus and the supero-medial margin of the hemisphere. The posterior part of this gyrus is sometimes marked off by a vertical sulcus, and is distinguished as the **paracentral lobule**, because it is continuous with the anterior and posterior central gyri.

**Parietal Lobe** (*lobus parietalis*).—The parietal lobe is separated from the frontal lobe by the central sulcus, but its boundaries below and behind are not so definite. Posteriorly, it is limited by the parietooccipital fissure, and by a line carried across the hemisphere from the end of this fissure toward the preoccipital notch. Below, it is separated from the temporal lobe by the posterior ramus of the lateral fissure, and by a line carried backward from it to meet the line passing downward to the preoccipital notch.

The **lateral surface** of the parietal lobe (Fig. 737) is cleft by a well-marked furrow, the **intraparietal sulcus** of Turner, which consists of an oblique and a horizontal portion. The oblique part is named the **postcentral sulcus**, and commences below, about midway between the lower end of the central sulcus and the upturned end of the lateral fissure. It runs upward and backward, parallel to the central sulcus, and is sometimes divided into an *upper* and a *lower* ramus. It forms the hinder limit of the posterior central gyrus.

From about the middle of the postcentral sulcus, or from the upper end of its inferior ramus, the **horizontal portion** of the intraparietal sulcus is carried backward and slightly upward on the parietal lobe, and is prolonged, under the name of the

**occipital ramus**, on to the occipital lobe, where it divides into two parts, which form nearly a right angle with the main stem and constitute the **transverse occipital sulcus**. The part of the parietal lobe above the horizontal portion of the intraparietal sulcus is named the **superior parietal lobule**; the part below, the **inferior parietal lobule**.

The **posterior central gyrus** (*gyrus centralis posterior; ascending parietal convolution; postcentral gyre*) extends from the longitudinal fissure above to the posterior ramus of the lateral fissure below. It lies parallel with the anterior central gyrus, with which it is connected below, and also, sometimes, above, the central sulcus.

The **superior parietal lobule** (*lobulus parietalis superior*) is bounded in front by the upper part of the postcentral sulcus, but is usually connected with the posterior central gyrus above the end of the sulcus; behind it is the lateral part of the parietooccipital fissure, around the end of which it is joined to the occipital lobe by a curved gyrus, the **arcus parietooccipitalis**; below, it is separated from the inferior parietal lobule by the horizontal portion of the intraparietal sulcus.

The **inferior parietal lobule** (*lobulus parietalis inferior; subparietal district or lobule*) lies below the horizontal portion of the intraparietal sulcus, and behind the lower part of the postcentral sulcus. It is divided from before backward into two gyri. One, the **supramarginal**, arches over the upturned end of the lateral fissure; it is continuous in front with the postcentral gyrus, and behind with the superior temporal gyrus. The second, the **angular**, arches over the posterior end of the superior temporal sulcus, behind which it is continuous with the middle temporal gyrus.

The **medial surface** of the parietal lobe (Fig. 738) is bounded behind by the medial part of the parietooccipital fissure; in front, by the posterior end of the cingulate sulcus; and below, it is separated from the cingulate gyrus by the **subparietal sulcus**. It is of small size, and consists of a square-shaped convolution, which is termed the **precuneus** or **quadrate lobe**.

**Occipital Lobe** (*lobus occipitalis*).—The occipital lobe is small and pyramidal in shape; it presents three surfaces: **lateral**, **medial**, and **tentorial**.

The **lateral surface** is limited in front by the lateral part of the parietooccipital fissure, and by a line carried from the end of this fissure to the preoccipital notch; it is traversed by the transverse occipital and the lateral occipital sulci. The **transverse occipital sulcus** is continuous with the posterior end of the occipital ramus of the intraparietal sulcus, and runs across the upper part of the lobe, a short distance behind the parietooccipital fissure. The **lateral occipital sulcus** extends from behind forward, and divides the lateral surface of the occipital lobe into a **superior** and an **inferior gyrus**, which are continuous in front with the parietal and temporal lobes.<sup>1</sup>

The **medial surface** of the occipital lobe is bounded in front by the medial part of the parietooccipital fissure, and is traversed by the calcarine fissure, which subdivides it into the cuneus and the lingual gyrus. The cuneus is a wedge-shaped area between the calcarine fissure and the medial part of the parietooccipital fissure. The **lingual gyrus** lies between the calcarine fissure and the posterior part of the collateral fissure; behind, it reaches the occipital pole; in front, it is continued on to the tentorial surface of the temporal lobe, and joins the hippocampal gyrus.

The **tentorial surface** of the occipital lobe is limited in front by an imaginary transverse line through the preoccipital notch, and consists of the posterior part of the **fusiform gyrus** (*occipitotemporal convolution*) and the lower part of the lingual gyrus, which are separated from each other by the posterior segment of the collateral fissure.

**Temporal Lobe** (*lobus temporalis*).—The temporal lobe presents **superior**, **lateral**, and **inferior surfaces**.

<sup>1</sup> Elliot Smith has named the lateral occipital sulcus the *sulcus lunatus*; he regards it as the representative, in the human brain, of the "Affenspalte" of the brain of the ape.

The **superior surface** forms the lower limit of the lateral fissure and overlaps the insula. On opening out the lateral fissure, three or four gyri will be seen springing from the depth of the hinder end of the fissure, and running obliquely forward and outward on the posterior part of the upper surface of the superior temporal gyrus; these are named the **transverse temporal gyri** (Heschl) (Fig. 740).

The **lateral surface** (Fig. 737) is bounded above by the posterior ramus of the lateral fissure, and by the imaginary line continued backward from it; below, it is limited by the infero-lateral border of the hemisphere. It is divided into superior, middle, and inferior gyri by the superior and middle temporal sulci. The **superior temporal sulcus** runs from before backward across the temporal lobe, some little distance below, but parallel with, the posterior ramus of the lateral fissure; and hence it is often termed the **parallel sulcus**. The **middle temporal sulcus** takes the same direction as the superior, but is situated at a lower level, and is usually subdivided into two or more parts. The **superior temporal gyrus** lies between




FIG. 740.—Section of brain showing upper surface of temporal lobe.

the posterior ramus of the lateral fissure and the superior temporal sulcus, and is continuous behind with the supramarginal and angular gyri. The **middle temporal gyrus** is placed between the superior and middle temporal sulci, and is joined posteriorly with the angular gyrus. The **inferior temporal gyrus** is placed below the middle temporal sulcus, and is connected behind with the inferior occipital gyrus; it also extends around the infero-lateral border on to the inferior surface of the temporal lobe, where it is limited by the inferior sulcus.

The **inferior surface** is concave, and is continuous posteriorly with the tentorial surface of the occipital lobe. It is traversed by the **inferior temporal sulcus**, which extends from near the occipital pole behind, to within a short distance of the temporal pole in front, but is frequently subdivided by bridging gyri. Lateral to this fissure is the narrow tentorial part of the inferior temporal gyrus, and medial to it the **fusiform gyrus**, which extends from the occipital to the temporal pole; this gyrus is limited medially by the collateral fissure, which separates it from the lingual gyrus behind and from the hippocampal gyrus in front.



The **Insula** (*island of Reil; central lobe*) (Fig. 741) lies deeply in the lateral or Sylvian fissure, and can only be seen when the lips of that fissure are widely separated, since it is overlapped and hidden by the gyri which bound the fissure. These gyri are termed the **opercula of the insula**; they are separated from each other by the three rami of the lateral fissure, and are named the orbital, frontal, frontoparietal, and temporal opercula. The **orbital operculum** lies below the anterior horizontal ramus of the fissure, the **frontal** between this and the anterior ascending ramus, the **parietal** between the anterior ascending ramus and the upturned end of the posterior ramus, and the **temporal** below the posterior ramus. The frontal operculum is of small size in those cases where the anterior horizontal and ascending rami of the lateral fissure arise from a common stem. The insula is surrounded by a deep **circular sulcus** which separates it from the frontal, parietal, and temporal lobes. When the opercula have been removed, the insula is seen as a triangular eminence, the apex of which is directed toward the anterior perforated substance. It is divided into a larger anterior and a smaller posterior part by a deep sulcus, which runs backward and upward from the apex of the insula. The anterior part is subdivided by shallow sulci into three or four **short gyri**, while the posterior part is formed by one **long gyrus**, which is often bifurcated at its upper end. The cortical gray substance of the insula is continuous with that of the different opercula, while its deep surface corresponds with the lentiform nucleus of the corpus striatum.



FIG. 741.—The insula of the left side, exposed by removing the opercula.

**Limbic Lobe** (Fig. 738).—The term limbic lobe was introduced by Broca, and under it he included the cingulate and hippocampal gyri, which together arch around the corpus callosum and the hippocampal fissure. These he separated on the morphological ground that they are well-developed in animals possessing a keen sense of smell (osmatic animals), such as the dog and fox. They were thus regarded as a part of the rhinencephalon, but it is now recognized that they belong to the neopallium; the cingulate gyrus is therefore sometimes described as a part of the frontal lobe, and the hippocampal as a part of the temporal lobe.

The **cingulate gyrus** (*gyrus cinguli*; *callosal convolution*) is an arch-shaped convolution, lying in close relation to the superficial surface of the corpus callosum, from which it is separated by a slit-like fissure, the **callosal fissure**. It commences below the rostrum of the corpus callosum, curves around in front of the genu, extends along the upper surface of the body, and finally turns downward behind the splenium, where it is connected by a narrow **isthmus** with the hippocampal

gyrus. It is separated from the medial part of the superior frontal gyrus by the cingulate sulcus, and from the precuneus by the subparietal sulcus.

The **hippocampal gyrus** (*gyrus hippocampi*) is bounded above by the hippocampal fissure, and below by the anterior part of the collateral fissure. Behind, it is continuous superiorly, through the isthmus, with the cingulate gyrus and inferiorly with the lingual gyrus. Running in the substance of the cingulate and hippocampal gyri, and connecting them together, is a tract of arched fibres, named the **cingulum** (page 890). The anterior extremity of the hippocampal gyrus is recurved in the form of a hook (**uncus**), which is separated from the apex of the temporal lobe by a slight fissure, the **incisura temporalis**. Although superficially continuous with the hippocampal gyrus, the uncus forms morphologically a part of the rhinencephalon.

The **Hippocampal Fissure** (*fissura hippocampi; dentate fissure*) begins immediately behind the splenium of the corpus callosum, and runs forward between the hippocampal and dentate gyri to end in the uncus. It is a complete fissure (page 867), and gives rise to the prominence of the hippocampus in the inferior cornu of the lateral ventricle.




FIG. 742.—Scheme of rhinencephalon.

**Rhinencephalon** (Fig. 742).—The rhinencephalon comprises the **olfactory lobe**, the **uncus**, the **subcallosal** and **supracallosal gyri**, the **fascia dentata hippocampi**, the **septum pellucidum**, the **fornix**, and the **hippocampus**.

1. The **Olfactory Lobe** (*lobus olfactorius*) is situated under the inferior or orbital surface of the frontal lobe. In many vertebrates it constitutes a well-marked portion of the hemisphere and contains an extension of the lateral ventricle; but in man and some other mammals it is rudimentary. It consists of the **olfactory bulb** and **tract**, the **olfactory trigone**, the **parolfactory area of Broca**, and the **anterior perforated substance**.

(a) The **olfactory bulb** (*bulbus olfactorius*) is an oval, reddish-gray mass which rests on the cribriform plate of the ethmoid and forms the anterior expanded extremity of the olfactory tract. Its under surface receives the olfactory nerves, which pass upward through the cribriform plate from the olfactory region of the nasal cavity. Its minute structure is described on page 893.

(b) The **olfactory tract** (*tractus olfactorius*) is a narrow white band, triangular on coronal section, the apex being directed upward. It lies in the olfactory sulcus on the inferior surface of the frontal lobe, and divides posteriorly into two striae, a medial and a lateral. The **lateral stria** is directed across the lateral part of the

anterior perforated substance and then bends abruptly medialward toward the uncus of the hippocampal gyrus. The **medial stria** turns medialward behind the parolfactory area and ends in the subcallosal gyrus; in some cases a small **intermediate stria** is seen running backward to the anterior perforated substance.

(c) The **olfactory trigone** (*trigonum olfactorium*) is a small triangular area in front of the anterior perforated substance. Its apex, directed forward, occupies the posterior part of the olfactory sulcus, and is brought into view by throwing back the olfactory tract.

(d) The **parolfactory area of Broca** (*area parolfactoria*) is a small triangular field on the medial surface of the hemisphere in front of the subcallosal gyrus, from which it is separated by the posterior parolfactory sulcus; it is continuous below with the olfactory trigone, and above and in front with the cingulate gyrus; it is limited anteriorly by the anterior parolfactory sulcus.

(e) The **anterior perforated substance** (*substantia perforata anterior*) is an irregularly quadrilateral area in front of the optic tract and behind the olfactory trigone, from which it is separated by the **fissure prima**; medially and in front it is continuous with the subcallosal gyrus; laterally it is bounded by the lateral stria of the olfactory tract and is continued into the uncus. Its gray substance is confluent above with that of the corpus striatum, and is perforated anteriorly by numerous small bloodvessels.

2. The **Uncus** has already been described (page 874) as the recurved, hook-like portion of the hippocampal gyrus.

3. The **Subcallosal**, **Supracallosal**, and **Dentate Gyri** form a rudimentary arch-shaped lamina of gray substance extending over the corpus callosum and above the hippocampal gyrus from the anterior perforated substance to the uncus.

(a) The **subcallosal gyrus** (*gyrus subcallosus*; *peduncle of the corpus callosum*) is a narrow lamina on the medial surface of the hemisphere in front of the lamina terminalis, behind the parolfactory area, and below the rostrum of the corpus callosum. It is continuous around the genu of the corpus callosum with the supracallosal gyrus.

(b) The **supracallosal gyrus** (*indusium griseum*; *gyrus epiccallosus*) consists of a thin layer of gray substance in contact with the upper surface of the corpus callosum and continuous laterally with the gray substance of the cingulate gyrus. It contains two longitudinally directed strands of fibres termed respectively the **medial** and **lateral longitudinal striæ**. The supracallosal gyrus is prolonged around the splenium of the corpus callosum as a delicate lamina, the **fasciola cinerea**, which is continuous below with the fascia dentata hippocampi.

(c) The **fascia dentata hippocampi** (*gyrus dentatus*) is a narrow band extending downward and forward above the hippocampal gyrus but separated from it by the hippocampal fissure; its free margin is notched and overlapped by the fimbria—the **fimbriodentate fissure** intervening. Anteriorly it is continued into the notch of the uncus, where it forms a sharp bend and is then prolonged as a delicate band, the **band of Giacomini**, over the incus, on the lateral surface of which it is lost.

The remaining parts of the rhinencephalon, viz., the septum pellucidum, fornix, and hippocampus, will be described in connection with the lateral ventricle.

**Interior of the Cerebral Hemispheres.**—If the upper part of either hemisphere be removed, at a level about 1.25 cm. above the corpus callosum, the central white substance will be exposed as an oval-shaped area, the **centrum ovale minus**, surrounded by a narrow convoluted margin of gray substance, and studded with numerous minute red dots (**puncta vasculosa**), produced by the escape of blood from divided bloodvessels. If the remaining portions of the hemispheres be slightly drawn apart a broad band of white substance, the **corpus callosum**, will be observed, connecting them at the bottom of the longitudinal fissure; the margins of the hemispheres which overlap the corpus callosum are called the **labia cerebri**. Each labium is

part of the cingulate gyrus already described; and the slit-like interval between it and the upper surface of the corpus callosum is termed the **callosal fissure** (Fig. 738). If the hemispheres be sliced off to a level with the upper surface of the corpus callosum, the white substance of that structure will be seen connecting the two hemispheres. The large expanse of medullary matter now exposed, surrounded by the convoluted margin of gray substance, is called the **centrum ovale majus**.

The **Corpus Callosum** (Fig. 743) is the great transverse commissure which unites the cerebral hemispheres and roofs in the lateral ventricles. A good conception of its position and size is obtained by examining a median sagittal section of the brain (Fig. 730), when it is seen to form an arched structure about 10 cm. long. Its anterior end is about 4 cm. from the frontal pole, and its posterior end about 6 cm. from the occipital pole of the hemisphere.




FIG. 743.—Corpus callosum from above.

The **anterior end** is named the **genu**, and is bent downward and backward in front of the septum pellucidum; diminishing rapidly in thickness, it is prolonged backward under the name of the **rostrum**, which is connected below with the lamina terminalis. The anterior cerebral arteries are in contact with the under surface of the rostrum; they then arch over the front of the genu, and are carried backward above the body of the corpus callosum.

The **posterior end** is termed the **splenium** and constitutes the thickest part of the corpus callosum. It overlaps the tela chorioidea of the third ventricle and the mesencephalon, and ends in a thick, convex, free border. A sagittal section of

the splenium shows that the posterior end of the corpus callosum is acutely bent forward, the upper and lower parts being applied to each other.

The **superior surface** is convex from before backward, and is about 2.5 cm. wide. Its medial part forms the bottom of the longitudinal fissure, and is in contact posteriorly with the lower border of the falx cerebri. Laterally it is overlapped by the cingulate gyrus, but is separated from it by the slit-like callosal fissure. It is traversed by numerous transverse ridges and furrows, and is covered by a thin layer of gray matter, the **supracallosal gyrus**, which exhibits on either side of the middle line the medial and lateral longitudinal striæ, already described (page 875).

The **inferior surface** is concave, and forms on either side of the middle line the roof of the lateral ventricle. Medially, this surface is attached in front to the septum pellucidum; behind this it is fused with the upper surface of the body of the fornix, while the splenium is in contact with the tela chorioidea.

On either side, the fibres of the corpus callosum radiate in the white substance and pass to the various parts of the cerebral cortex; those curving forward from the genu into the frontal lobe constitute the **forceps anterior**, and those curving backward into the occipital lobe, the **forceps posterior**. Between these two parts is the main body of the fibres which constitute the **tapetum** and extend laterally on either side into the temporal lobe, and cover in the central part of the lateral ventricle.




FIG. 744.—Scheme showing relations of the ventricles to the surface of the brain.

**The Lateral Ventricles** (*ventriculus lateralis*) (Fig. 744).—The two lateral ventricles are irregular cavities situated in the lower and medial parts of the cerebral hemispheres, one on either side of the middle line. They are separated from each other by a median vertical partition, the **septum pellucidum**, but communicate with the third ventricle and indirectly with each other through the **interventricular foramen**. They are lined by a thin, diaphanous membrane, the **ependyma**, covered by ciliated epithelium, and contain cerebrospinal fluid, which, even in health, may be secreted in considerable amount. Each lateral ventricle consists of a **central part** or **body**, and three prolongations from it, termed **cornua** (Figs. 745, 746).

The **central part** (*pars centralis ventriculi lateralis; cella*) (Fig. 747) of the lateral ventricle extends from the interventricular foramen to the splenium of the corpus



callosum. It is an irregularly curved cavity, triangular on transverse section, with a roof, a floor, and a medial wall. The roof is formed by the under surface of the corpus callosum; the floor by the following parts, enumerated in their order of position, from before backward: the caudate nucleus of the corpus striatum, the




FIG. 745.—Drawing of a cast of the ventricular cavities, viewed from above. (Retsius.)

stria terminalis and the terminal vein, the lateral portion of the upper surface of the thalamus, the choroid plexus, and the lateral part of the fornix; the medial wall is the posterior part of the septum pellucidum, which separates it from the opposite ventricle.




FIG. 746.—Drawing of a cast of the ventricular cavities, viewed from the side. (Retsius.)

The **anterior cornu** (*cornu anterius*; *anterior horn*; *precornu*) (Fig. 746) passes forward and lateralward, with a slight inclination downward, from the interventricular foramen into the frontal lobe, curving around the anterior end of the caudate nucleus. Its floor is formed by the upper surface of the reflected portion of the

corpus callosum, the **rostrum**. It is bounded medially by the anterior portion of the septum pellucidum, and laterally by the head of the caudate nucleus. Its apex reaches the posterior surface of the genu of the corpus callosum.

The **posterior cornu** (*cornu posterius*; *postcornu*) (Figs. 747, 748) passes into the occipital lobe, its direction being backward and lateralward, and then medialward. Its roof is formed by the fibres of the corpus callosum passing to the temporal and occipital lobes. On its medial wall is a longitudinal eminence, the **calcar avis** (*hippocampus minor*), which is an involution of the ventricular wall produced by the calcarine fissure. Above this the forceps posterior of the corpus callosum, sweeping around to enter the occipital lobe, causes another projection, termed the **bulb of the posterior cornu**. The calcar avis and bulb of the posterior cornu are extremely variable in their degree of development; in some cases they are ill-defined, in others prominent.




FIG. 747.—Central part and anterior and posterior cornua of lateral ventricles exposed from above.

The **inferior cornu** (*cornu inferior*; *descending horn*; *middle horn*; *medicornu*) (Fig. 749), the largest of the three, traverses the temporal lobe of the brain, forming in its course a curve around the posterior end of the thalamus. It passes at first backward, lateralward, and downward, and then curves forward to within 2.5 cm. of the apex of the temporal lobe, its direction being fairly well indicated on the surface of the brain by that of the superior temporal sulcus. Its roof is formed chiefly by the inferior surface of the tapetum of the corpus callosum, but the tail of the caudate nucleus and the stria terminalis also extend forward in the roof of the inferior cornu to its extremity, where they end in a mass of gray substance,

the **nucleus amygdalae**. Its floor presents the following parts: the hippocampus, the fimbria hippocampi, the collateral eminence, and the choroid plexus. When the




FIG. 748.—Coronal section through posterior cornu of lateral ventricle.

choroid plexus is removed, a cleft-like opening is left along the medial wall of the inferior cornu; this cleft constitutes the lower part of the choroidal fissure.




FIG. 749.—Posterior and inferior cornua of left lateral ventricle exposed from the side.

The **hippocampus** (*hippocampus major*) (Figs. 749, 750) is a curved eminence, about 5 cm. long, which extends throughout the entire length of the floor of the



inferior cornu. Its lower end is enlarged, and presents two or three rounded elevations or digitations which give it a paw-like appearance, and hence it is named the *pes hippocampi*. If a transverse section be made through the hippocampus, it will be seen that this eminence is produced by the folding of the wall of the hemisphere to form the hippocampal fissure. The main mass of the hippocampus consists of gray substance, but on its ventricular surface is a thin white layer, the *alveus*, which is continuous with the *fimbria hippocampi*.

The *collateral eminence* (*eminencia collateralis*) (Fig. 750) is an elongated swelling lying lateral to and parallel with the hippocampus. It corresponds with the middle part of the collateral fissure, and its size depends on the depth and direction of this fissure. It is continuous behind with a flattened triangular area, the *trigonum collaterale*, situated between the posterior and inferior cornua.

The *fimbria hippocampi* is a continuation of the crus of the fornix, and will be discussed with that body; a description of the choroid plexus will be found on page 887.

The *corpus striatum* has received its name from the striped appearance which a section of its anterior part presents, in consequence of diverging white fibres being mixed with the gray substance which forms its chief mass. A part of the corpus striatum is imbedded in the white substance of the hemisphere, and is therefore external to the ventricle; it is termed the *extraventricular portion*, or the *lentiform nucleus*; the remainder, however, projects into the ventricle, and is named the *intraventricular portion*, or the *caudate nucleus* (Fig. 747).

The *caudate nucleus* (*nucleus caudatus; caudatum*) (Fig. 751) is a pear-shaped, highly arched gray mass; its broad extremity, or *head*, is directed forward into the anterior cornu of the lateral ventricle, and is continuous with the anterior perforated substance and with the anterior end of the lentiform nucleus; its narrow end, or *tail*, is directed backward on the lateral side of the thalamus, from which it is separated by the *stria terminalis* and the terminal vein. It is then continued downward into the roof of the inferior cornu, and ends in the *nucleus amygdalæ*, at the apex of the temporal lobe. It is covered by the lining of the ventricle, and crossed by some veins of considerable size. It is separated from the lentiform nucleus, in the greater part of its extent, by a thick lamina of white substance, called the *internal capsule*, but the two portions of the corpus striatum are united in front (Figs. 752, 753).

The *lentiform nucleus* (*nucleus lentiformis; lenticular nucleus; lenticula*) is lateral to the caudate nucleus and thalamus, and is seen only in sections of the hemisphere. When divided horizontally, it exhibits, to some extent, the appearance of a biconvex lens (Fig. 751), while a coronal section of its central part presents a somewhat triangular outline. It is shorter than the caudate nucleus and does not extend as far forward. It is bounded laterally by a lamina of white substance called the *external capsule*, and lateral to this is a thin layer of gray substance termed the *claustrum*. Its anterior end is continuous with the lower part of the head of the caudate nucleus and with the anterior perforated substance.

In a coronal section through the middle of the lentiform nucleus, two *medullary laminae* are seen dividing it into three parts. The lateral and largest part is of a




FIG. 750.—Inferior and posterior cornua, viewed from above.

reddish color, and is known as the **putamen**, while the medial and intermediate are of a yellowish tint, and together constitute the **globus pallidus**; all three are marked by fine radiating white fibres, which are most distinct in the putamen (Fig. 753).

The gray substance of the corpus striatum is traversed by nerve fibres, some of which originate in it. The cells are multipolar, both large and small; those of the lentiform nucleus contain yellow pigment. The caudate and lentiform nuclei are not only directly continuous with each other anteriorly, but are connected to each other by numerous fibres. The corpus striatum is also connected: (1) to the




FIG. 751.—Horizontal section of right cerebral hemisphere.

cerebral cortex, by what are termed the **corticostriate fibres**; (2) to the thalamus, by fibres which pass through the internal capsule, and by a strand named the **ansa lentiformis**; (3) to the cerebral peduncle, by fibres which leave the lower aspect of the caudate and lentiform nuclei.

The **claustrum** (Figs. 751, 753) is a thin layer of gray substance, situated on the lateral surface of the external capsule. Its transverse section is triangular, with the apex directed upward. Its medial surface, contiguous to the external capsule, is smooth, but its lateral surface presents ridges and furrows corresponding with the gyri and sulci of the insula, with which it is in close relationship. The claustrum is regarded as a detached portion of the gray substance of the insula, from which



it is separated by a layer of white fibres, the **capsula extrema** (*band of Baillarger*). Its cells are small and spindle-shaped, and contain yellow pigment; they are similar to those of the deepest layer of the cortex.

The **nucleus amygdalæ** (*amygdala*) is an ovoid gray mass, situated at the lower end of the roof of the inferior cornu. It is merely a localized thickening of the gray cortex, continuous with that of the uncus; in front it is continuous with the putamen, behind with the stria terminalis and the tail of the caudate nucleus.




FIG. 752.—Coronal section through anterior cornua of lateral ventricles.

The **internal capsule** (*capsula interna*) (Fig. 754) is a flattened band of white fibres, between the lentiform nucleus on the lateral side and the caudate nucleus and thalamus on the medial side. In horizontal section (Figs. 751) it is seen to be somewhat abruptly curved, with its convexity inward; the prominence of the curve is called the **genu**, and projects between the caudate nucleus and the thalamus. The portion in front of the genu is termed the frontal part, and separates the lentiform from the caudate nucleus; the portion behind the genu is the occipital part, and separates the lentiform nucleus from the thalamus.

The **frontal part** of the internal capsule contains: (1) fibres running from the thalamus to the frontal lobe; (2) fibres connecting the lentiform and caudate nuclei; (3) fibres connecting the cortex with the corpus striatum; and (4) fibres passing from the frontal lobe through the medial fifth of the base of the cerebral peduncle to the nuclei pontis. The fibres in the region of the genu are named the **geniculate fibres**; they originate in the motor part of the cerebral cortex, and, after passing downward through the base of the cerebral peduncle with the cerebro-

spinal fibres, undergo decussation and end in the motor nuclei of the cerebral nerves of the opposite side. The anterior two-thirds of the occipital part of the internal capsule contains the **cerebrospinal fibres**, which arise in the motor area of the cerebral cortex and, passing downward through the middle three-fifths of the base of the cerebral peduncle, are continued into the pyramids of the medulla oblongata. The posterior third of the occipital part contains: (1) sensory fibres, largely derived from the thalamus, though some may be continued upward from the medial lemniscus; (2) the fibres of optic radiation, from the lower visual centres to the cortex of the occipital lobe; (3) acoustic fibres, from the lateral lemniscus to the temporal lobe; and (4) fibres which pass from the occipital and temporal lobes to the nuclei pontis.




FIG. 753.—Coronal section of brain through anterior commissure.

The fibres of the internal capsule radiate widely as they pass to and from the various parts of the cerebral cortex, forming the **corona radiata** (Fig. 754) and intermingling with the fibres of the corpus callosum.

The **external capsule** (*capsula externa*) (Fig. 751) is a lamina of white substance, situated lateral to the lentiform nucleus, between it and the claustrum, and continuous with the internal capsule below and behind the lentiform nucleus. It probably contains fibres derived from the thalamus, the anterior commissure, and the subthalamic region.

The **substantia innominata of Meynert** is a stratum consisting partly of gray and partly of white substance, which lies below the anterior part of the thalamus and lentiform nucleus. It consists of three layers, superior, middle, and inferior. The *superior* layer is named the **ansa lentiformis**, and its fibres, derived from the medullary lamina of the lentiform nucleus, pass medially to end in the thalamus

and subthalamie region, while others are said to end in the tegmentum and red nucleus. The *middle* layer consists of nerve cells and nerve fibres; fibres enter it from the parietal lobe through the external capsule, while others are said to connect it with the medial longitudinal fasciculus. The *inferior* layer forms the main part of the inferior stalk of the thalamus, and connects this body with the temporal lobe and the insula.

The **stria terminalis** (*taenia semicircularis*) is a narrow band of white substance situated in the depression between the caudate nucleus and the thalamus. Anteriorly, its fibres are partly continued into the column of the fornix; some, however, pass over the anterior commissure to the gray substance between the caudate nucleus and septum pellucidum, while others are said to enter the caudate nucleus. Posteriorly, it is continued into the roof of the inferior cornu of the lateral ventricle, at the extremity of which it enters the nucleus amygdalæ. Superficial to it is a




FIG. 754.—Dissection showing the course of the cerebrospinal fibres. (E. B. Jamieson.)

large vein, the **terminal vein** (*vein of the corpus striatum*), which receives numerous tributaries from the corpus striatum and thalamus; it runs forward to the interventricular foramen and there joins with the vein of the choroid plexus to form the corresponding internal cerebral vein. On the surface of the terminal vein is a narrow white band, named the **lamina affixa**.

The **Fornix** (Figs. 730, 755) is a longitudinal, arch-shaped lamella of white substance, situated below the corpus callosum, and continuous with it behind, but separated from it in front by the septum pellucidum. It may be described as consisting of two symmetrical bands, one for either hemisphere. The two portions are not united to each other in front and behind, but their central parts are joined together in the middle line. The anterior parts are called the **columns** of the fornix; the intermediate united portions, the **body**; and the posterior parts, the **crura**.

The **body** (*corpus fornicis*) of the fornix is triangular, narrow in front, and broad behind. The medial part of its upper surface is connected to the septum pellucidum in front and to the corpus callosum behind. The lateral portion of this surface forms part of the floor of the lateral ventricle, and is covered by the ventricular epithelium. Its lateral edge overlaps the choroid plexus, and is continuous with the epithelial covering of this structure. The under surface rests upon the tela chorioidea of the third ventricle, which separates it from the epithelial roof of that cavity, and from the medial portions of the upper surfaces of the thalami. Below, the lateral portions of the body of the fornix are joined by a thin triangular lamina, named the **psalterium** (*lyra*). This lamina contains some transverse fibres which connect the two hippocampi across the middle line and constitute the **hippocampal commissure**. Between the psalterium and the corpus callosum a horizontal cleft, the so-called **ventricle of the fornix** (*ventricle of Verga*), is sometimes found.




FIG. 755.—The fornix and corpus callosum from below. (From a specimen in the Department of Human Anatomy of the University of Oxford.)

The **columns** (*columna fornicis*; *anterior pillars*; *fornicolumns*) of the fornix arch downward in front of the interventricular foramen and behind the anterior commissure, and each descends through the gray substance in the lateral wall of the third ventricle to the base of the brain, where it ends in the corpus mamillare. From the cells of the corpus mamillare the **thalamomamillary fasciculus** (*bundle of Vicq d'Azyr*) takes origin and is prolonged into the anterior nucleus of the thalamus. The column of the fornix and the thalamomamillary fasciculus together form a loop resembling the figure 8, but the continuity of the loop is broken in the corpus

mamillare. The column of the fornix is joined by the stria medullaris of the pineal body and by the superficial fibres of the stria terminalis, and is said to receive also fibres from the septum pellucidum. Zuckerkandl describes an **olfactory fasciculus** which becomes detached from the main portion of the column of the fornix, and passes downward in front of the anterior commissure to the base of the brain, where it divides into two bundles, one joining the medial stria of the olfactory tract; the other joins the subcallosal gyrus, and through it reaches the hippocampal gyrus.

The **crura** (*crus fornicis*; *posterior pillars*) of the fornix are prolonged backward from the body. They are flattened bands, and at their commencement are intimately connected with the under surface of the corpus callosum. Diverging from one another, each curves around the posterior end of the thalamus, and passes downward and forward into the inferior cornu of the lateral ventricle (Fig. 757). Here it lies along the concavity of the hippocampus, on the surface of which some of its fibres are spread out to form the **alveus**, while the remainder are continued as a narrow white band, the **fimbria hippocampi**, which is prolonged into the uncus of the hippocampal gyrus. The inner edge of the fimbria overlaps the **fascia dentata hippocampi** (*dentate gyrus*) (page 875), from which it is separated by the **fimbriodentate fissure**; from its lateral margin, which is thin and ragged, the ventricular epithelium is reflected over the choroid plexus as the latter projects into the chorioidial fissure.

**Interventricular Foramen** (*foramen of Monro*).—Between the columns of the fornix and the anterior ends of the thalami, an oval aperture is present on either side: this is the interventricular foramen, and through it the lateral ventricles communicate with the third ventricle. Behind the epithelial lining of the foramen the choroid plexuses of the lateral ventricles are joined across the middle line.

The **Anterior Commissure** (*precommissure*) is a bundle of white fibres, connecting the two cerebral hemispheres across the middle line, and placed in front of the columns of the fornix. On sagittal section it is oval in shape, its long diameter being vertical and measuring about 5 mm. Its fibres can be traced lateralward and backward on either side beneath the corpus striatum into the substance of the temporal lobe. It serves in this way to connect the two temporal lobes, but it also contains decussating fibres from the olfactory tracts.

The **Septum Pellucidum** (*septum lucidum*) (Fig. 730) is a thin, vertically placed partition consisting of two laminæ, separated in the greater part of their extent by a narrow chink or interval, the **cavity of the septum pellucidum**. It is attached, above, to the under surface of the corpus callosum; below, to the anterior part of the fornix behind, and the reflected portion of the corpus callosum in front. It is triangular in form, broad in front and narrow behind; its inferior angle corresponds with the upper part of the anterior commissure. The lateral surface of each lamina is directed toward the body and anterior cornu of the lateral ventricle, and is covered by the ependyma of that cavity.

The **cavity of the septum pellucidum** (*cavum septi pellucidi*; *pseudocoele*; *fifth ventricle*) is generally regarded as part of the longitudinal cerebral fissure, which has become shut off by the union of the hemispheres in the formation of the corpus callosum above and the fornix below. Each half of the septum therefore forms part of the medial wall of the hemisphere, and consists of a medial layer of gray substance, derived from that of the cortex, and a lateral layer of white substance continuous with that of the cerebral hemispheres. This cavity is not developed from the cavity of the cerebral vesicles, and never communicates with the ventricles of the brain.

The **Choroid Plexus of the Lateral Ventricle** (*plexus chorioideus ventriculus lateralis*; *paraplexus*) (Fig. 757) is a highly vascular, fringe-like process of pia mater, which projects into the ventricular cavity. The plexus, however, is everywhere



covered by a layer of epithelium continuous with the epithelial lining of the ventricle. It extends from the interventricular foramen, where it is joined with the plexus of the opposite ventricle, to the end of the inferior cornu. The part in relation to the body of the ventricle forms the vascular fringed margin of a triangular process of pia mater, named the **tela chorioidea of the third ventricle**, and projects from under cover of the lateral edge of the fornix. It lies upon the upper surface of the thalamus, from which the epithelium is reflected over the plexus on to the edge of the fornix (Fig. 734). The portion in relation to the inferior cornu lies in the concavity of the hippocampus and overlaps the fimbria hippocampi: from the lateral edge of the fimbria the epithelium is reflected over the plexus on to the roof of the cornu (Fig. 756). It consists of minute and highly vascular villous processes, each with an afferent and an efferent vessel. The *arteries* of the plexus are: (a) the anterior choroidal, a branch of the internal carotid, which enters the plexus at the end of the inferior cornu; and (b) the posterior choroidal, one or two small branches of the posterior cerebral, which pass forward under the splenium. The *veins* of the choroid plexus unite to form a tortuous vein, which courses from behind forward to the interventricular foramen and there joins with the terminal vein to form the corresponding internal cerebral vein.




FIG. 756.—Coronal section of inferior horn of lateral ventricle. (Diagrammatic.)

When the choroid plexus is pulled away, the continuity between its epithelial covering and the epithelial lining of the ventricle is severed, and a cleft-like space is produced. This is named the **choroidal fissure**; like the plexus, it extends from the interventricular foramen to the end of the inferior cornu. The upper part of the fissure, *i. e.*, the part nearest the interventricular foramen is situated between the lateral edge of the fornix and the upper surface of the thalamus; farther back at the beginning of the inferior cornu it is between the commencement of the fimbria hippocampi and the posterior end of the thalamus, while in the inferior cornu it lies between the fimbria in the floor and the stria terminalis in the roof of the cornu.

The **tela chorioidea of the third ventricle** (*tela chorioidea ventriculi tertii; velum interpositum*) (Fig. 757) is a double fold of pia mater, triangular in shape, which lies beneath the fornix. The lateral portions of its lower surface rest upon the thalami, while its medial portion is in contact with the epithelial roof of the third ventricle. Its apex is situated at the interventricular foramen; its base corresponds with the splenium of the corpus callosum, and occupies the interval between that structure above and the corpora quadrigemina and pineal body below. This

interval, together with the lower portions of the choroidal fissures, is sometimes spoken of as the **transverse fissure of the brain**. At its base the two layers of the velum separate from each other, and are continuous with the pia mater investing the brain in this region. Its lateral margins are modified to form the highly vascular choroid plexuses of the lateral ventricles. It is supplied by the anterior and posterior choroidal arteries already described. The veins of the tela chorioidea are named the **internal cerebral veins** (*venae Galeni*); they are two in number, and run backward between its layers, each being formed at the interventricular foramen by the union of the terminal vein with the choroidal vein. The internal cerebral veins unite posteriorly in a single trunk, the **great cerebral vein** (*vena magna Galeni*), which passes backward beneath the splenium and ends in the straight sinus.




FIG. 757.—Tela chorioidea of the third ventricle, and the choroid plexus of the left lateral ventricle, exposed from above.

**Structure of the Cerebral Hemispheres.**—The cerebral hemispheres are composed of gray and white substance: the former covers their surface, and is termed the **cortex**; the latter occupies the interior of the hemispheres.

The **white substance** consists of medullated fibres, varying in size, and arranged in bundles separated by neuroglia. They may be divided, according to their course and connections, into three distinct systems. (1) **Projection fibres** connect the hemisphere with the lower parts of the brain and with the medulla spinalis. (2) **Transverse or commissural fibres** unite the two hemispheres. (3) **Association fibres** connect different structures in the same hemisphere; these are, in many

instances, collateral branches of the projection fibres, but others are the axons of independent cells.

1. The **projection fibres** consist of efferent and afferent fibres uniting the cortex with the lower parts of the brain and with the medulla spinalis. The principal efferent strands are: (1) the *motor tract*, occupying the genu and anterior two-thirds of the occipital part of the internal capsule, and consisting of (a) the geniculate fibres, which decussate and end in the motor nuclei of the cerebral nerves of the opposite side; and (b) the cerebrospinal fibres, which are prolonged through the pyramid of the medulla oblongata into the medulla spinalis: (2) the *corticopontine fibres*, ending in the nuclei pontis. The chief afferent fibres are: (1) those of the lemniscus which are not interrupted in the thalamus; (2) those of the brachia conjunctiva cerebelli which are not interrupted in the red nucleus and thalamus; (3) numerous fibres arising within the thalamus, and passing through its stalks to the different parts of the cortex (page 857); (4) optic and acoustic fibres, the former passing to the occipital, the latter to the temporal lobe.

2. The **transverse or commissural fibres** connect the two hemispheres. They include: (a) the *transverse fibres* of the corpus callosum, (b) the anterior commissure, (c) the posterior commissure, and (d) the lyra or hippocampal commissure; they have already been described.




FIG. 758.—Diagram showing principal systems of association fibres in the cerebrum.

3. The **association fibres** (Fig. 758) unite different parts of the same hemisphere, and are of two kinds: (1) those connecting adjacent gyri, **short association fibres**; (2) those passing between more distant parts, **long association fibres**.

The *short association fibres* lie immediately beneath the gray substance of the cortex of the hemispheres, and connect together adjacent gyri.

The *long association fibres* include the following: (a) the uncinat fasciculus; (b) the cingulum; (c) the superior longitudinal fasciculus; (d) the inferior longitudinal fasciculus; (e) the perpendicular fasciculus; (f) the occipitofrontal fasciculus; and (g) the fornix.

(a) The *uncinate fasciculus* passes across the bottom of the lateral fissure, and unites the gyri of the frontal lobe with the anterior end of the temporal lobe.

(b) The *cingulum* is a band of white matter contained within the cingulate gyrus. Beginning in front at the anterior perforated substance, it passes forward and upward parallel with the rostrum, winds around the genu, runs backward above the corpus callosum, turns around the splenium, and ends in the hippocampal gyrus.

(c) The *superior longitudinal fasciculus* passes backward from the frontal lobe above the lentiform nucleus and insula; some of its fibres end in the occipital lobe, and others curve downward and forward into the temporal lobe.

(d) The *inferior longitudinal fasciculus* connects the temporal and occipital lobes, running along the lateral walls of the inferior and posterior cornua of the lateral ventricle.

(e) The *perpendicular fasciculus* runs vertically through the front part of the occipital lobe, and connects the inferior parietal lobule with the fusiform gyrus.

(f) The *occipitofrontal fasciculus* passes backward from the frontal lobe, along the lateral border of the caudate nucleus, and on the mesial aspect of the corona radiata; its fibres radiate in a fan-like manner and pass into the occipital and temporal lobes lateral to the posterior and inferior cornua. Déjerine regards the fibres of the tapetum as being derived from this fasciculus, and not from the corpus callosum.

(g) The *fornix* connects the hippocampal gyrus with the corpus mamillare and, by means of the thalamomamillary fasciculus, with the thalamus (see page 886). Through the fibres of the hippocampal commissure it probably also unites the opposite hippocampal gyri.

The **gray substance of the hemisphere** is divided into: (1) that of the cerebral cortex, and (2) that of the caudate nucleus, the lentiform nucleus, the claustrum, and the nucleus amygdalæ.

**Structure of the Cerebral Cortex** (Fig. 759).—The cerebral cortex differs in thickness and structure in different parts of the hemisphere. It is thinner in the occipital region than in the anterior and posterior central gyri, and it is also much thinner at the bottom of the sulci than on the top of the gyri. Again, the minute structure of the anterior central differs from that of the posterior central gyrus, and areas possessing a specialized type of cortex can be mapped out in the occipital lobe.

On examining a section of the cortex with a lens, it is seen to consist of alternating white and gray layers thus disposed from the surface inward: (1) a thin layer of white substance; (2) a layer of gray substance; (3) a second white layer (*outer band of Baillarger* or *band of Gennari*); (4) a second gray layer; (5) a third white layer (*inner band of Baillarger*); (6) a third gray layer, which rests on the medullary substance of the gyrus.

The cortex is made up of nerve cells of varying size and shape, and of nerve fibres which are either medullated or naked axis-cylinders, imbedded in a matrix of neuroglia.

**Nerve Cells.**—According to Cajal, the nerve cells are arranged in four layers, named from the surface inward as follows: (1) the molecular layer, (2) the layer of small pyramidal cells, (3) the layer of large pyramidal cells, (4) the layer of polymorphous cells.

**The Molecular Layer.**—In this layer the cells are polygonal, triangular, or fusiform in shape. Each polygonal cell gives off some four or five dendrites, while its axon may arise directly from the cell or from one of its dendrites. Each triangular cell gives off two or three dendrites, from one of which the axon arises. The fusiform cells are placed with their long axes parallel to the surface and are mostly bipolar, each pole being prolonged into a dendrite, which runs horizontally for some distance and furnishes ascending branches. Their axons, two or three in number, arise from the dendrites, and, like them, take a horizontal course, giving off numerous ascending collaterals. The distribution of the axons and dendrites of all three sets of cells is limited to the molecular layer.

**The Layer of Small and the Layer of Large Pyramidal Cells.**—The cells in these two layers may be studied together, since, with the exception of the difference in size and the more superficial position of the smaller cells, they resemble each other. The average length of the small cells is from 10 to 15 $\mu$ ; that of the large cells from 20 to 30 $\mu$ . The body of each cell is pyramidal in shape, its base being directed to the deeper parts and its apex toward the surface. It contains granular pigment, and stains deeply with ordinary reagents. The nucleus is of large size, and round or oval in shape. The base of the cell gives off the axis cylinder, and this runs into the central white substance, giving off collaterals in its course, and is distributed as a projection, commissural, or association fibre. The apical and basal parts of the cell give off dendrites; the apical dendrite is directed toward the surface, and ends in the molecular layer by dividing into numerous branches, all of which may be seen, when prepared by the silver or methylene-blue method, to be studded with projecting bristle-like processes. The largest pyramidal cells are found in the upper part of the anterior central gyrus and in the paracentral lobule; they are often arranged in groups or nests of from three to five, and are named the *giant cells of Betz*.



In the former situation they may exceed  $50\mu$  in length and  $40\mu$  in breadth, while in the paracentral lobule they may attain a length of  $65\mu$ .

**Layer of Polymorphous Cells.**—The cells in this layer, as their name implies, are very irregular in contour; they may be fusiform, oval, triangular, or star-shaped. Their dendrites are directed outward, but do not reach so far as the molecular layer; their axons pass into the subjacent white matter.




FIG. 759.—Cerebral cortex. (Poirier.) To the left, the groups of cells; to the right, the systems of fibres. Quite to the left of the figure a sensory nerve fibre is shown.

There are two other kinds of cells in the cerebral cortex. They are: (a) the *cells of Golgi*, the axons of which divide immediately after their origins into a large number of branches, which are directed toward the surface of the cortex; (b) the *cells of Martinotti*, which are chiefly found in the polymorphous layer; their dendrites are short, and may have an ascending or descending course, while their axons pass out into the molecular layer and form an extensive horizontal arborization.

**Nerve Fibres.**—These fill up a large part of the intervals between the cells, and may be medullated or non-medullated—the latter comprising the axons of the smallest pyramidal cells and the cells of Golgi. In their direction the fibres may be either tangential or radial. The *tangential fibres* run parallel to the surface of the hemisphere, intersecting the radial fibres at a right angle.



They constitute several strata, of which the following are the more important: (1) a stratum of white fibres covering the superficial aspect of the molecular layer (*plexus of Ezner*); (2) the band of Bechterew, in the outer part of the layer of small pyramidal cells; (3) the band of Gennari or external band of Baillarger, running through the layer of large pyramidal cells; (4) the internal band of Baillarger, between the layer of large pyramidal cells and the polymorphous layer; (5) the deep tangential fibres, in the lower part of the polymorphous layer. The tangential fibres consist of (a) the collaterals of the pyramidal and polymorphous cells and of the cells of Martinotti; (b) the branching axons of Golgi's cells; (c) the collaterals and terminal arborizations of the projection, commissural, or association fibres. *The radial fibres.*—Some of these, viz., the axons of the pyramidal and polymorphous cells, descend into the central white matter, while others, the terminations of the projection, commissural, or association fibres, ascend to end in the cortex. The axons of the cells of Martinotti are also ascending fibres.

**Special Types of Cerebral Cortex.**—It has been already pointed out that the minute structure of the cortex differs in different regions of the hemisphere; and A. W. Campbell<sup>1</sup> has endeavored to prove, as the result of an exhaustive examination of a series of human and anthropoid brains, "that there exists a direct correlation between physiological function and histological structure." The principal regions where the "typical" structure is departed from will now be referred to.

1. In the calcarine fissure and the gyri bounding it, the internal band of Baillarger is absent, while the band of Gennari is of considerable thickness, and forms a characteristic feature of this region of the cortex. If a section be examined microscopically, an additional layer of cells is seen to be interpolated between the molecular layer and the layer of small pyramidal cells. This extra layer consists of two or three strata of fusiform cells, the long axes of which are at right angles to the surface; each cell gives off two dendrites, external and internal, from the latter of which the axon arises and passes into the white central substance. In the layer of small pyramidal cells, fusiform cells, identical with the above, are seen, as well as ovoid or star-like cells with ascending axons (*cells of Martinotti*). This is the *visual area* of the cortex, and it has been shown by J. S. Bolton<sup>2</sup> that in old-standing cases of optic atrophy the thickness of Gennari's band is reduced by nearly 50 per cent.

A. W. Campbell says: "Histologically, two distinct types of cortex can be made out in the occipital lobe. The first of these coats the walls and bounding convolutions of the calcarine fissure, and is distinguished by the well-known line of Gennari or Vicq d'Azyr; the second area forms an investing zone a centimetre or more broad around the first, and is characterized by a remarkable wealth of fibres, as well as by curious pyriform cells of large size richly stocked with chromophilic elements—cells which seem to have escaped the observation of Ramón y Cajal, Bolton, and others who have worked at this region. As to the functions of these two regions there is abundant evidence, anatomical, embryological, and pathological, to show that the first or calcarine area is that to which visual sensations primarily pass, and we are gradually obtaining proof to the effect that the second investing area is constituted for the interpretation and further elaboration of these sensations. These areas therefore deserve the names *visuo-sensory* and *visuo-psychic*."

2. The anterior central gyrus is characterized by the presence of the giant cells of Betz and by "a wealth of nerve fibres immeasurably superior to that of any other part" (Campbell), and in these respects differs from the posterior central gyrus. These two gyri, together with the paracentral lobule, were long regarded as constituting the "motor areas" of the hemisphere; but Sherrington and Grunbaum have shown<sup>3</sup> that in the chimpanzee the motor area never extends on to the free face of the posterior central gyrus, but occupies the entire length of the anterior central gyrus, and in most cases the greater part or the whole of its width. It extends into the depth of the central sulcus, occupying the anterior wall, and in some places the floor, and in some extending even into the deeper part of the posterior wall of the sulcus.

3. In the hippocampus the molecular layer is very thick and contains a large number of Golgi cells. It has been divided into three strata: (a) *s. convolutum* or *s. granulosum*, containing many tangential fibres; (b) *s. lacunosum*, presenting numerous vascular spaces; (c) *s. radiatum*, exhibiting a rich plexus of fibrils. The two layers of pyramidal cells are condensed into one, and the cells are mostly of large size. The axons of the cells in the polymorphous layer may run in an ascending, a descending, or a horizontal direction. Between the polymorphous layer and the ventricular ependyma is the white substance of the alveus.

4. In the fascia dentata hippocampi or dentate gyrus the molecular layer contains some pyramidal cells, while the layer of pyramidal cells is almost entirely represented by small ovoid cells.

5. *The Olfactory Bulb.*—In many of the lower animals this contains a cavity which communicates through the olfactory tract with the lateral ventricle. In man the original cavity is filled up by neuroglia and its wall becomes thickened, but much more so on its ventral than on its dorsal aspect. Its dorsal part contains a small amount of gray and white substance, but it is scanty and ill-defined. A section through the ventral part (Fig. 760) shows it to consist of the following layers from without inward:

<sup>1</sup> Histological Studies on the Localization of Cerebral Function, Cambridge University Press

<sup>2</sup> Philosophical Transactions of Royal Society, Series B, cxliii, 165.

<sup>3</sup> Transactions of the Pathological Society of London, vol. liii.

1. A layer of olfactory nerve fibres, which are the non-medullated axons prolonged from the olfactory cells of the nasal cavity, and reach the bulb by passing through the cribriform plate of the ethmoid bone. At first they cover the bulb, and then penetrate it to end by forming synapses with the dendrites of the mitral cells, presently to be described.

2. *Glomerular Layer*.—This contains numerous spheroidal reticulated enlargements, termed **glomeruli**, produced by the branching and arborization of the processes of the olfactory nerve fibres with the descending dendrites of the mitral cells.

3. *Molecular Layer*.—This is formed of a matrix of neuroglia, imbedded in which are the *mitral cells*. These cells are pyramidal in shape, and the basal part of each gives off a thick dendrite which descends into the glomerular layer, where it arborizes as indicated above, and others which interlace with similar dendrites of neighboring mitral cells. The axons pass through the next layer into the white matter of the bulb, and after becoming bent on themselves at a right angle, are continued into the olfactory tract.

4. *Nerve Fibre Layer*.—This lies next the central core of neuroglia, and its fibres consist of the axons or afferent processes of the mitral cells passing to the brain; some efferent fibres are, however, also present, and end in the molecular layer, but nothing is known as to their exact origin.




FIG. 760.—Coronal section of olfactory bulb. (Schwalbe.)

**Weight of the Encephalon.**—The average weight of the brain, in the adult male, is about 1380 gms.; that of the female, about 1250 gms. In the male, the maximum weight out of 278 cases was 1840 gms. and the minimum weight 964 gms. The maximum weight of the adult female brain, out of 191 cases, was 1585 gms. and the minimum weight 879 gms. The brain increases rapidly during the first four years of life, and reaches its maximum weight by about the twentieth year. As age advances, the brain decreases slowly in weight; in old age the decrease takes place more rapidly, to the extent of about 28 gms.

The human brain is heavier than that of any of the lower animals, except the elephant and whale. The brain of the former weighs from 3.5 to 4.5 kilogram., and that of a whale, in a specimen 22.8 metres long, weighed rather more than 225 kilogram.

**Cerebral Localization.**—Physiological and pathological research have now gone far to prove that a considerable part of the surface of the brain may be mapped out into a series of more or less definite areas, each of which is intimately connected with some well-defined function.

The chief areas are indicated in Figs. 761 and 762.

**Motor Areas.**—The motor area occupies the anterior central and frontal gyri and the paracentral lobule. The centres for the lower limb are located on the uppermost part of the anterior central gyrus and its continuation on to the paracentral lobule; those for the trunk are on the upper portion, and those for the upper limb on the middle portion of the anterior central gyrus. The facial centres are situated on the lower part of the anterior central gyrus, those for the tongue, larynx, muscles of mastication, and pharynx on the frontal operculum, while those for the head and neck occupy the posterior end of the middle frontal gyrus.

**Sensory Areas.**—Tactile and temperature senses are located on the posterior central gyrus, while the sense of form and solidity is on the superior parietal lobule and precuneus. With regard to the special senses, the area for the sense of taste is probably related to the uncus and

hippocampal gyrus. The auditory area occupies the middle third of the superior temporal gyrus and the adjacent gyri in the lateral fissure; the visual area, the calcarine fissure and cuneus; the olfactory area, the rhinencephalon. As special centres of much importance may be noted: the emissive centre for speech on the left inferior frontal and anterior central gyri (Broca); the auditory receptive centre on the transverse and superior temporal gyri, and the visual receptive centre on the lingual gyrus and cuneus.




FIG. 761.—Areas of localization on lateral surface of hemisphere. Motor area in red. Area of general sensations in blue. Auditory area in green. Visual area in yellow. The psychic portions are in lighter tints.

**Applied Anatomy.**—The *internal capsule* is of great interest to the clinician because it is so often the seat of hemorrhage (from the lenticulo-striate and lenticulo-optic arteries, Charcot's "arteries of cerebral hemorrhage"), or of thrombosis, in patients whose vessels are weakened by old age




FIG. 762.—Areas of localization on medial surface of hemisphere. Motor area in red. Area of general sensations in blue. Visual area in yellow. Olfactory area in purple. The psychic portions are in lighter tints.

or disease. A *stroke* or *apoplexy* is the result; blood is effused from the ruptured vessel and tears up the surrounding brain tissue, and also interferes with the neighboring fibres by the compression set up by its mass. If the hemorrhage is sudden and at all large, rapid and complete loss of consciousness follows, with paralysis of the opposite side of the body and loss of control over

the sphincters. If it is the occipital part of the internal capsule that is involved, the paralysis will be more marked in the leg than in the arm, and will be associated with hemianesthesia, and also with homonymous hemianopsia or blindness of the corresponding halves of the two retinae, the patient being unable to see objects on the opposite side of the body. If the hemorrhage is very extensive blood often makes its way into the ventricles, and death may follow in a few hours or days without recovery of consciousness, and with hyperpyrexia. If the hemorrhage is small, consciousness is soon regained, and a fair degree of recovery from the paralysis follows, particularly in the leg. If the hemorrhage takes place very slowly, the hemiplegia sets in gradually (*ingravescent apoplexy*), with headache and gradual clouding of the faculties. It is the upper motor neuron (see below) that is injured in cerebral hemorrhage; hence the muscles on the affected side of the body become spastic, with increased reflexes, while such muscular atrophy as follows is mainly due to disuse.

### THE MOTOR AND SENSORY TRACTS.

The anatomy of the various parts of the central nervous system having been described, a short account will now be given of the motor and sensory nerve tracts connecting the brain and the medulla spinalis. The methods employed in elucidating this complex subject have already been referred to (page 815).

**The Motor Tract** (Fig. 763).—The constituent fibres of this tract are the axis-cylinder processes of cells situated in the motor area of the cortex. The fibres are at first somewhat widely diffused, but as they descend through the corona radiata they gradually approach each other, and pass between the lentiform nucleus and thalamus, in the genu and anterior two-thirds of the occipital part of the internal capsule; those in the genu are named the **geniculate fibres**, while the remainder constitute the **cerebrospinal fibres**; proceeding downward they enter the middle three-fifths of the base of the cerebral peduncle. The geniculate fibres cross the middle line, and end by arborizing around the cells of the motor nuclei of the cerebral nerves. The cerebrospinal fibres are continued downward into the pyramids of the medulla oblongata, and the transit of the fibres from the medulla oblongata is effected by two paths. The fibres nearest to the anterior median fissure cross the middle line, forming the **decussation of the pyramids**, and descend in the opposite side of the medulla spinalis, as the **lateral cerebrospinal fasciculus** (*crossed pyramidal tract*). Throughout the length of the medulla spinalis fibres from this column pass into the gray substance, to terminate by ramifying around the motor cells of the anterior column. The more laterally placed portion of the tract does not decussate in the medulla oblongata, but descends as the **anterior cerebrospinal fasciculus** (*direct pyramidal tract*); these fibres, however, end in the anterior gray column of the opposite side of the medulla spinalis by passing across in the anterior white commissure. There is considerable variation in the extent to which decussation takes place in the medulla oblongata; about two-thirds or three-fourths of the fibres usually decussate in the medulla oblongata and the remainder in the medulla spinalis.

The axons of the motor cells in the anterior column pass out as the fibres of the anterior roots of the spinal nerves, along which the impulses are conducted to the muscles of the trunk and limbs.

From this it will be seen that all the fibres of the motor tract pass to the nuclei of the motor nerves on the opposite side of the brain or medulla spinalis, a fact which explains why a lesion involving the motor area of one side causes paralysis of the muscles of the opposite side of the body. Further, it will be seen that there is a break in the continuity of the motor chain; in the case of the cerebral nerves this break occurs in the nuclei of these nerves; and in the case of the spinal nerves, in the anterior gray column of the medulla spinalis. For clinical purposes it is convenient to emphasize this break and divide the motor tract into two portions: (1) a series of **upper motor neurons** which comprises the motor cells in the cortex

and their descending fibres down to the nuclei of the motor nerves; (2) a series of **lower motor neurons** which includes the cells of the nuclei of the motor cerebral nerves or the cells of the anterior columns of the medulla spinalis and their axis-cylinder processes to the periphery.<sup>1</sup>




FIG. 763.—The motor tract. (Modified from Poirier.)

**The Sensory Tract** (Fig. 764).—Sensory impulses are conveyed to the medulla spinalis through the posterior roots of the spinal nerves. On entering the medulla spinalis these root fibres divide into descending and ascending branches; the former soon enter the gray substance: some of the latter end in the gray substance after a longer or shorter course, while others are continued directly into the posterior

<sup>1</sup> As already mentioned (footnote, p. 816), a neuron in the posterior column of the medulla spinalis is probably interposed between each upper and lower motor neuron.



funiculi, where they form the fasciculus gracilis and fasciculus cuneatus. From the cells of the posterior column, fibres arise which cross the middle line and ascend in the superficial antero-lateral fasciculus. The fibres of the fasciculus gracilis and fasciculus cuneatus end by arborizing around the cells of the gracile and cuneate nuclei in the medulla oblongata, and from these cells the fibres of the medial




FIG. 764 —The sensory tract. (Modified from Poirier.)

lemniscus take origin and cross to the opposite side in the **sensory decussation**. The medial lemniscus is then joined by the fibres of the superficial antero-lateral fasciculus, which have already crossed in the medulla spinalis, and in its further course receives fibres from the cerebral sensory nuclei of the opposite side, with the exception of the cochlear division of the acoustic nerve. Ascending through the cerebral peduncle, the lemniscus gives off some fibres to the lentiform nucleus

and insula, but the greater part of it is carried into the thalamus, where most of its fibres end—only a small proportion being continued directly into the cerebral cortex. From the gray substance of the thalamus the fibres of the third link in the chain arise and pass to the cerebral cortex. The fibres from the terminal nuclei of the cochlear nerve pass upward in the lateral lemniscus, and are carried through the occipital part of the internal capsule to the temporal lobe. Further, the superficial antero-lateral fasciculus gives off fibres which reach the cerebellum through the brachia conjunctiva. It will be evident, therefore, that in most cases there are three cell-stations interposed in the course of the sensory impulses. For clinical purposes, therefore, three neurons are described: (1) the **lowest sensory neurons** comprise the cells of the posterior root ganglia and their peripheral and central processes; (2) the **intermediate sensory neurons** are the cells of the nuclei cuneati and gracilis and their processes, while (3) the **highest sensory neurons** are the cells of the thalami and the fibres passing from these to the cerebral cortex.

**Applied Anatomy.**—The chief symptoms of diseases of the brain and medulla spinalis depend upon the particular systems of neurons picked out for attack, and some of them may be briefly summarized as follows: *Motor paralysis* of the *spastic* type, with rigidity of the muscles and increased reflexes, follows destruction of the upper motor neurons; *flaccid paralysis*, with loss of the reflexes and rapid muscular atrophy, follows destruction of the lower motor neurons. *Sensory paralysis* follows injury to any part of the sensory path; in tabes it is due to injury of the lowest sensory neurons, in hemiplegia to destruction of the highest sensory axon as it traverses the occipital part of the internal capsule. *Dissociation of sensations*, or the loss of some forms of sensation while others remain unimpaired, is seen in a number of conditions such as tabes or syringomyelia; it shows that the paths through which various forms of sensation travel to the brain are different. *Abnormalities of reflex actions* are of very great help in the diagnosis of nervous complaints. The numerous *superficial* or *skin reflexes*, *e. g.*, the scapular, irritation of the skin over the scapula produces contraction of the scapular muscles; the abdominal, stroking the abdomen causes its retraction; the cremasteric, stroking the inner side of the thigh causes retraction of the testis on that side; the plantar, tickling the sole of the foot brings on plantar flexion of the toes, if present, show that the reflex arcs on whose integrity their existence depends are intact; but they are often absent in health, and so cannot be trusted to indicate disease. The *deep reflexes* or *tendon reactions*, such as the knee-jerk or the tendo-calcaneus jerk, are increased in chronic degeneration of, or gradually increasing pressure on, the cerebrospinal fibres (upper motor neuron), in nervous or hysterical patients, and when the irritability of the cells of the anterior column (lower motor neuron) is increased, as happens in tetanus or in poisoning by strychnine. They are lost when the lower motor or lower sensory neurons are diseased, and in a few other conditions; absence of the knee-jerk is very rare in health, and suggests disease in some part of its reflex arc, in the third and fourth lumbar segments of the cord, or else, more rarely, grave intracranial or spinal disease cutting off the lower from the higher nervous centres. The *organic reflexes* of the pupil, bladder, and rectum are of the greatest practical importance. The commonest defect in the reflexes of the pupil is reflex iridoplegia, or failure to contract on exposure to light, without failure to contract on convergence or accommodation (*Argyll-Robertson pupil*). The pupil is also contracted (*miosis*), and may or may not dilate when the skin of the neck is pinched (the cilio-spinal reflex). Micturition is a spinal reflex much under the control of the brain; if the centre for micturition in the second sacral segment is destroyed the sphincter and the walls of the bladder are paralyzed, the bladder becomes distended with urine, and incontinence from overflow results. If this centre escapes injury but is cut off more or less completely from impulses descending to it from above, there will be more or less interference with micturition. This varies in degree from the "precipitate micturition" of tabetic patients, who must perforce hurry to pass water the moment the impulse seizes them, to the state of "reflex incontinence," when the bladder automatically empties itself from time to time, almost without the patient's knowledge. Defecation is a very similar spinal reflex, and is liable to very similar disorders of function.

The *upper motor neuron* (p. 896) is affected in hemiplegia, the *lower motor neuron* (p. 897) in infantile spinal paralysis; both these systems of neurons are diseased together in the somewhat rare disorders known as *amyotrophic lateral sclerosis* and *progressive muscular atrophy*. The chief symptom here is wasting and weakness in certain groups of muscles; the palsy will be flaccid, with loss of the reflexes, or spastic, with increased reflexes, according as the degeneration mainly involves the lower or the upper motor neuron. The sphincters are affected only in the later stages of these diseases.

Pathological changes in the *lowest sensory neuron* are the cause of *tabes dorsalis* or *locomotor ataxy*, which occurs almost entirely in adults who have had syphilis. In the early or preataxic

stage the patient may exhibit the Argyll-Robertson pupil (page 899), and loss of the knee-jerks, and complain of sharp, stabbing pains ("lightning pains") in the limbs, difficult or precipitate micturition, and sometimes of severe and painful attacks of indigestion (gastric crises). In the second or ataxic stage, coming on perhaps years later, he will complain, in addition, of interference with his powers of getting about and turning, although his muscular strength is well preserved. He is unable to stand steady with his eyes shut or in the dark, his gait becomes exaggerated and stamping in character, he has to use a stout stick to walk with, and he may suffer from painful crises in various parts of the body. Control over the sphincters is further weakened, and on examination there will be found marked incoördination of the limbs, zones of anesthesia about the trunk or down the limbs, and marked analgesia (or insensitiveness to pain) when pressure is applied to the bones, tendons, trachea, tongue, eyeballs, mammæ, and testes.<sup>1</sup> The ataxy progresses until the third or bedridden stage is reached; control over the sphincters is still further lost, and the patient is likely to die of intercurrent disease or of general paralysis of the insane.

No nervous disease is recognized as dependent upon degeneration of either the *intermediate* or *highest sensory neuron*.

### MENINGES OF THE BRAIN AND MEDULLA SPINALIS.

The brain and medulla spinalis are enclosed within three membranes. These are named from without inward: the *dura mater*, the *arachnoid*, and the *pia mater*.

#### The Dura Mater.

The *dura mater* is a thick and dense inelastic membrane. The portion which encloses the brain differs in several essential particulars from that which surrounds the medulla spinalis, and therefore it is necessary to describe them separately; but at the same time it must be distinctly understood that the two form one complete membrane, and are continuous with each other at the foramen magnum.

The *cerebral dura mater* (*dura mater encephali*; *dura of the brain*) lines the interior of the skull, and serves the two-fold purpose of an internal periosteum to the bones, and a membrane for the protection of the brain. It is composed of two layers, an inner or meningeal and an outer or endosteal, closely connected together, except in certain situations, where, as already described (page 729), they separate to form sinuses for the passage of venous blood. Its outer surface is rough and fibrillated, and adheres closely to the inner surfaces of the bones, the adhesions being most marked opposite the sutures and at the base of the skull its inner surface is smooth and lined by a layer of endothelium. It sends inward four processes which divide the cavity of the skull into a series of freely communicating compartments, for the lodgement and protection of the different parts of the brain; and it is prolonged to the outer surface of the skull, through the various foramina which exist at the base, and thus becomes continuous with the pericranium; its fibrous layer forms sheaths for the nerves which pass through these apertures. Around the margin of the foramen magnum it is closely adherent to the bone, and is continuous with the spinal dura mater.

**Processes.**—The processes of the cerebral dura mater, which projects into the cavity of the skull, are formed by reduplications of the inner or meningeal layer of the membrane, and are four in number: the *falx cerebri*, the *tentorium cerebelli*, the *falx cerebelli*, and the *diaphragma sellæ*.

The *falx cerebri* (Fig. 765), so named from its sickle-like form, is a strong, arched process which descends vertically in the longitudinal fissure between the cerebral hemispheres. It is narrow in front, where it is attached to the crista galli of the ethmoid; and broad behind, where it is connected with the upper surface of the tentorium cerebelli. Its upper margin is convex, and attached to the inner surface of the skull in the middle line, as far back as the internal occipital protuberance; it contains the superior sagittal sinus. Its lower margin is free and concave, and contains the inferior sagittal sinus.

<sup>1</sup> J. Grasset, *Le Tabes, Maladie de la Sensibilité profonde*, Montpellier, 1906.

The **tentorium cerebelli** (Fig. 766) is an arched lamina, elevated in the middle, and inclining downward toward the circumference. It covers the superior surface of the cerebellum, and supports the occipital lobes of the brain. Its anterior border is free and concave, and bounds a large oval opening, the **incisura tentorii**, for the transmission of the cerebral peduncles. It is attached, behind, by its convex border, to the transverse ridges upon the inner surface of the occipital bone, and there encloses the transverse sinuses; in front, to the superior angle of the petrous part of the temporal bone on either side, enclosing the superior petrosal sinuses. At the apex of the petrous part of the temporal bone the free and attached borders meet, and, crossing one another, are continued forward to be fixed to the anterior and posterior clinoid processes respectively. To the middle line of its upper surface the posterior border of the falx cerebri is attached, the straight sinus being placed at their line of junction.




FIG. 765.—Dura mater and its processes exposed by removing part of the right half of the skull and the brain.

The **falx cerebelli** is a small triangular process of dura mater, received into the posterior cerebellar notch. Its base is attached, above, to the under and back part of the tentorium; its posterior margin, to the lower division of the vertical crest on the inner surface of the occipital bone. As it descends, it sometimes divides into two smaller folds, which are lost on the sides of the foramen magnum.

The **diaphragma sellae** is a small circular horizontal fold, which roofs in the sella turcica and almost completely covers the hypophysis; a small central opening transmits the infundibulum.

**Structure.**—The cranial dura mater consists of white fibrous tissue and elastic fibres arranged in flattened laminæ which are imperfectly separated by lacunar spaces and bloodvessels into two layers, **endosteal** and **meningeal**. The **endosteal layer** is the internal periosteum for the cranial bones, and contains the bloodvessels for their supply. At the margin of the foramen magnum it is continuous with the periosteum lining the vertebral canal. The **meningeal** or **supporting layer** is lined on its inner surface by a layer of nucleated endothelium, similar to that found on serous membranes.




FIG. 766.—Tentorium cerebelli seen from above.

The **arteries** of the dura mater are very numerous. Those in the anterior fossa are the anterior meningeal branches of the anterior and posterior ethmoidal and internal carotid, and a branch from the middle meningeal. Those in the middle fossa are the middle and accessory meningeal of the internal maxillary; a branch from the ascending pharyngeal, which enters the skull through the foramen lacerum; branches from the internal carotid, and a recurrent branch from the lacrimal. Those in the posterior fossa are meningeal branches from the occipital, one entering the skull through the jugular foramen, and another through the mastoid foramen; the posterior meningeal from the vertebral; occasional meningeal branches from the ascending pharyngeal, entering the skull through the jugular foramen and hypoglossal canal; and a branch from the middle meningeal.

The **veins** returning the blood from the cranial dura mater anastomose with the diploic veins and end in the various sinuses. Many of the meningeal veins do not open directly into the sinuses, but indirectly through a series of ampullæ, termed **venous lacunæ**. These are found on either side of the superior sagittal sinus, especially near its middle portion, and are often invaginated by arachnoid granulations; they also exist near the transverse and straight sinuses. They communicate with the underlying cerebral veins, and also with the diploic and emissary veins.

The **nerves** of the cerebral dura mater are filaments from the semilunar ganglion, from the ophthalmic, maxillary, mandibular, vagus, and hypoglossal nerves, and from the sympathetic.

The **spinal dura mater** (*dura mater spinalis*; *spinal dura*) (Fig. 767) forms a loose sheath around the medulla spinalis, and represents only the inner or meningeal layer of the cerebral dura mater; the outer or endosteal layer ceases at the foramen magnum, its place being taken by the periosteum lining the vertebral canal. The



spinal dura mater is separated from the arachnoid by a potential cavity, the **subdural cavity**; the two membranes are, in fact, in contact with each other, except where they are separated by a minute quantity of fluid, which serves to moisten the apposed surfaces. It is separated from the wall of the vertebral canal by a space, the **epidural space**, which contains a quantity of loose areolar tissue and a plexus of veins; the situation of these veins between the dura mater and the periosteum of the vertebræ corresponds therefore to that of the cranial sinuses between the meningeal and endosteal layers of the cerebral dura mater. The spinal dura mater is attached to the circumference of the foramen magnum, and to the second and third cervical vertebræ; it is also connected to the posterior longitudinal ligament, especially near the lower end of the vertebral canal, by fibrous slips. The subdural cavity ends at the lower border of the second sacral vertebra; below this level the dura mater closely invests the filum terminale and descends to the back of the coccyx, where it blends with the periosteum. The sheath of dura mater is much larger than is necessary for the accommodation of its contents, and its size is greater in the cervical and lumbar regions than in the thoracic. On each side may be seen the double openings which transmit the two roots of the corresponding spinal nerve, the dura mater being continued in the form of tubular prolongations on them as they pass through the intervertebral foramina. These prolongations are short in the upper part of the vertebral column, but gradually become longer below, forming a number of tubes of fibrous membrane, which enclose the lower spinal nerves and are contained in the vertebral canal.




FIG. 767.—The medulla spinalis and its membranes.

**Structure.**—The spinal dura mater resembles in structure the meningeal or supporting layer of the cranial dura mater, consisting of white fibrous and elastic tissue arranged in bands or lamellæ which, for the most part, are parallel with one another and have a longitudinal arrangement. Its internal surface is smooth and covered by a layer of endothelium. It is sparingly supplied with bloodvessels, and a few nerves have been traced into it.

### The Arachnoid.

The **arachnoid** is a delicate membrane enveloping the brain and medulla spinalis and lying between the pia mater internally and the dura mater externally; it is separated from the pia mater by the subarachnoid cavity, which is filled with cerebrospinal fluid.

The **cerebral part** (*arachnoidea encephali*) of the arachnoid invests the brain loosely, and does not dip into the sulci between the gyri, nor into the fissures, with the exception of the longitudinal. On the upper surface of the brain the arachnoid is thin and transparent; at the base it is thicker, and slightly opaque toward the central part, where it extends across between the two temporal lobes in front of the pons, so as to leave a considerable interval between it and the brain.

The **spinal part** (*arachnoidea spinalis*) of the arachnoid is a thin, delicate, tubular membrane loosely investing the medulla spinalis. *Above*, it is continuous with the cerebral arachnoid; *below*, it widens out and invests the cauda equina and the nerves proceeding from it. It is separated from the dura mater by the **subdural space**, but here and there this space is traversed by isolated connective-tissue trabeculæ, which are most numerous on the posterior surface of the medulla spinalis.

The arachnoid surrounds the cerebral and spinal nerves, and encloses them in loose sheaths as far as their points of exit from the skull and vertebral canal.

**Structure.**—The arachnoid consists of bundles of white fibrous and elastic tissue intimately blended together. Its outer surface is covered with a layer of endothelium. Vessels of considerable size, but few in number, and, according to Bochdalek, a rich plexus of nerves derived from the motor root of the trigeminal, the facial, and the accessory nerves, are found in the arachnoid.

The **subarachnoid cavity** (*cavum subarachnoideale*; *subarachnoid space*) is the interval between the arachnoid and pia mater. It is occupied by a spongy tissue consisting of trabeculæ of delicate connective tissue, and intercommunicating channels in which the subarachnoid fluid is contained. This cavity is small on the surface of the hemispheres of the brain; on the summit of each gyrus the pia mater and the arachnoid are in close contact; but in the sulci between the gyri, triangular spaces are left, in which the subarachnoid trabecular tissue is found, for the pia mater dips into the sulci, whereas the arachnoid bridges across them from gyrus to gyrus. At certain parts of the base of the brain, the arachnoid is separated from the pia mater by wide intervals, which communicate freely with each other and are named **subarachnoid cisternæ**; in these the subarachnoid tissue is less abundant.




FIG. 768.—Diagram showing the positions of the three principal subarachnoid cisternæ.

**Subarachnoid Cisternæ** (*cisternæ subarachnoidales*) (Fig. 768).—The **cisterna cerebellomedullaris** (*cisterna magna*) is triangular on sagittal section, and results from the arachnoid bridging over the interval between the medulla oblongata and the under surfaces of the hemispheres of the cerebellum; it is continuous with the subarachnoid cavity of the medulla spinalis at the level of the foramen magnum. The **cisterna pontis** is a considerable space on the ventral aspect of the pons. It contains the basilar artery, and is continuous behind with the subarachnoid cavity of the medulla spinalis, and with the cisterna cerebellomedullaris; and in front of the pons with the cisterna interpeduncularis. The **cisterna interpeduncularis** (*cisterna basalis*) is a wide cavity where the arachnoid extends across between the two temporal lobes. It encloses the cerebral peduncles and the structures contained in the interpeduncular fossa, and contains the arterial circle of Willis. In front, the cisterna interpeduncularis extends forward across the optic chiasma, forming the **cisterna chiasmatis**, and on to the upper surface of the corpus callosum, for the arachnoid stretches across from one cerebral hemisphere to the other immediately beneath the free border of the falx cerebri, and thus leaves a space in which

the anterior cerebral arteries are contained. The **cisterna fossae cerebri lateralis** is formed in front of either temporal lobe by the arachnoid bridging across the lateral fissure. This cavity contains the middle cerebral artery. The **cisterna venae magnae cerebri** occupies the interval between the splenium of the corpus callosum and the superior surface of the cerebellum; it extends between the layers of the tela chorioidea of the third ventricle and contains the great cerebral vein.

The subarachnoid cavity communicates with the general ventricular cavity of the brain by three openings; one, the **foramen of Majendie**, is in the middle line at the inferior part of the roof of the fourth ventricle; the other two are at the extremities of the lateral recesses of that ventricle, behind the upper roots of the glossopharyngeal nerves. It is stated by Meckel that the lateral ventricles also communicate with the subarachnoid cavity at the apices of their inferior cornua. There is no direct communication between the subdural and subarachnoid cavities.




FIG. 769.—Diagrammatic representation of a section across the top of the skull, showing the membranes of the brain, etc. (Modified from Testut.)

The spinal part of the subarachnoid cavity is a very wide interval, and is the largest at the lower part of the vertebral canal, where the arachnoid encloses the nerves which form the cauda equina. Above, it is continuous with the cranial subarachnoid cavity; below, it ends at the level of the lower border of the second sacral vertebra. It is partially divided by a longitudinal septum, the **subarachnoid septum**, which connects the arachnoid with the pia mater opposite the posterior median sulcus of the medulla spinalis, and forms a partition, incomplete and cribriform above, but more perfect in the thoracic region. The spinal subarachnoid cavity is further subdivided by the **ligamentum denticulatum**, which will be described with the pia mater.

The cerebrospinal fluid is a clear limpid fluid, having a saltish taste, and a slightly alkaline reaction. According to Lassaigne, it consists of 98.5 parts of water, the remaining 1.5 per cent. being solid matters, animal and saline. It varies in quantity, being most abundant in old persons, and is quickly secreted.

The **arachnoid granulations** (*granulationes arachnoideales*; *glandulae Pacchioni*; *arachnoid villi*; *Pacchionian bodies*) (Fig. 769) are small, fleshy-looking eleva-

tions, usually collected into clusters of variable size, which are present upon the outer surface of the dura mater, in the vicinity of the superior sagittal sinus, and in some other situations. Upon laying open the sagittal sinus and the venous lacunæ on either side of it granulations will be found protruding into its interior. They are not seen in infancy, and very rarely until the third year. They are usually found after the seventh year; and from this period they increase in number and size as age advances. They are not glandular in structure, but are enlarged normal villi of the arachnoid. As they grow they push the thinned dura mater before them, and cause absorption of the bone from pressure, and so produce the pits or depressions on the inner wall of the calvarium.

**Structure.**—An arachnoidal granulation consists of the following parts: (1) In the interior is a core of subarachnoid tissue, continuous with the mesh-work of the general subarachnoid tissue through a narrow pedicle, by which the granulation is attached to the arachnoid. (2) Around this tissue is a layer of arachnoid membrane, limiting and enclosing the subarachnoid tissue. (3) Outside this is the thinned wall of the lacuna, which is separated from the arachnoid by a space which corresponds to and is continuous with the subdural cavity. (4) And finally, if the granulation projects into the sagittal sinus, it will be covered by the greatly thinned upper walls of the sinus. It will be seen, therefore, that fluid injected into the subarachnoid cavity will find its way into these granulations, and it has been found experimentally that it passes by osmosis from the granulations into the venous sinuses into which they project.

### The Pia Mater.

The **pia mater** is a vascular membrane, consisting of a minute plexus of blood-vessels, held together by an extremely fine areolar tissue.

The **cerebral pia mater** (*pia mater encephali*; *pia of the brain*) invests the entire surface of the brain, dips between the cerebral gyri and cerebellar laminæ, and is invaginated to form the tela chorioidea of the third ventricle, and the choroid plexuses of the lateral and third ventricles (pages 887 and 888); as it passes over the roof of the fourth ventricle, it forms the tela chorioidea and the choroid plexuses of this ventricle. Upon the surfaces of the hemispheres, where it covers the gray substance, it gives off from its deep surface a multitude of sheaths, around the minute vessels, that extend perpendicularly for some distance into the cerebral substance. On the cerebellum the membrane is more delicate; the vessels from its deep surface are shorter, and its relations to the cortex are not so intimate.




FIG. 770.—Diagrammatic transverse section of the medulla spinalis and its membranes.

The **spinal pia mater** (*pia mater spinalis*; *pia of the cord*) (Figs. 767, 770) is thicker, firmer, and less vascular than the cerebral pia mater: this is due to the fact that it consists of two layers, the outer or additional one being composed of bundles of connective-tissue fibres, arranged for the most part longitudinally. Between the layers are cleft-like spaces which communicate with the subarachnoid cavity, and a number of bloodvessels which are enclosed in perivascular lymphatic sheaths.



The spinal pia mater covers the entire surface of the medulla spinalis, and is very intimately adherent to it; in front it sends a process backward into the anterior fissure. A longitudinal fibrous band, called the *linea splendens*, extends along the middle line of the anterior surface; and a somewhat similar band, the *ligamentum denticulatum*, is situated on either side. Below the conus medullaris, the pia mater is continued as a long, slender filament (*filum terminale*), which descends through the centre of the mass of nerves forming the cauda equina. It blends with the dura mater at the level of the lower border of the second sacral vertebra, and extends downward as far as the base of the coccyx, where it fuses with the periosteum. It assists in maintaining the medulla spinalis in its position during the movements of the trunk, and is, from this circumstance, called the *central ligament* of the medulla spinalis.

The pia mater forms sheaths for the cerebral and spinal nerves; these sheaths are closely connected with the nerves, and blend with their common membranous investments.

The *ligamentum denticulatum* (*dentate ligament*) (Fig. 767) is a narrow fibrous band situated on either side of the medulla spinalis throughout its entire length, and separating the anterior from the posterior nerve roots. Its medial border is continuous with the pia mater at the side of the medulla spinalis. Its lateral border presents a series of triangular tooth-like processes, the points of which are fixed at intervals to the dura mater. These processes are twenty-one in number, on either side, the first being attached to the dura mater, opposite the margin of the foramen magnum, between the vertebral artery and the hypoglossal nerve; and the last near the lower end of the medulla spinalis.

**Applied Anatomy.**—Evidence of great value in the diagnosis of meningitis may sometimes be obtained by puncturing the spinal membranes and withdrawing some of the cerebrospinal fluid; moreover, the operation of lumbar puncture is in many cases curative, under the supposition that the draining of some of the cerebrospinal fluid relieves the patient by diminishing the intracranial pressure. The operation is performed by inserting a trocar, of the smallest size, between the laminae of the third and fourth, or of the fourth and fifth lumbar vertebrae, through the ligamentum flavum. The medulla spinalis, even of a child at birth, does not reach below the third lumbar vertebra, and therefore the canal may be punctured between the third and fourth lumbar vertebrae without any risk of injuring this structure. The point of puncture is indicated by laying the patient on the side and dropping a perpendicular line from the highest point of the iliac crest; this will cross the upper border of the spinous process of the fourth lumbar vertebra, and will indicate the level at which the trocar should be inserted a little to one side of the middle line. The puncture may require to be repeated more than once, and the greatest precaution must be taken not to allow septic infection of the meninges. If there be any appreciable increase of pressure, the fluid will flow through the trocar with the greatest freedom.

In addition to the constitutional signs and symptoms of fever, *acute spinal meningitis* exhibits certain characteristic features. Pain and tenderness to pressure along the vertebral column are common, and so are pains in the limbs or around the trunk from irritation of the posterior nerve roots by the inflammatory products. Irritation of the anterior nerve roots is shown by the increased tone of the muscles, which may go on to the point where they pass into a state of spasm with much increased reflexes; this is often seen in the retraction of the head and neck. Later in the disease the reflexes are often lost, when, also, the urine and feces may be passed involuntarily.

## THE CEREBRAL NERVES (NERVI CEREBRALES; CRANIAL NERVES).

There are twelve pairs of cerebral nerves; they are attached to the brain and are transmitted through foramina in the base of the cranium. The different pairs are named from before backward as follows:

- |                  |                        |
|------------------|------------------------|
| 1st. Olfactory.  | 7th. Facial.           |
| 2d. Optic.       | 8th. Acoustic.         |
| 3rd. Oculomotor. | 9th. Glossopharyngeal. |
| 4th. Trochlear.  | 10th. Vagus.           |
| 5th. Trigeminal. | 11th. Accessory.       |
| 6th. Abducent.   | 12th. Hypoglossal.     |



tions, usually collected into clusters of variable size, which are present upon the outer surface of the dura mater, in the vicinity of the superior sagittal sinus, and in some other situations. Upon laying open the sagittal sinus and the venous lacunæ on either side of it granulations will be found protruding into its interior. They are not seen in infancy, and very rarely until the third year. They are usually found after the seventh year; and from this period they increase in number and size as age advances. They are not glandular in structure, but are enlarged normal villi of the arachnoid. As they grow they push the thinned dura mater before them, and cause absorption of the bone from pressure, and so produce the pits or depressions on the inner wall of the calvarium.

**Structure.**—An arachnoidal granulation consists of the following parts: (1) In the interior is a core of subarachnoid tissue, continuous with the mesh-work of the general subarachnoid tissue through a narrow pedicle, by which the granulation is attached to the arachnoid. (2) Around this tissue is a layer of arachnoid membrane, limiting and enclosing the subarachnoid tissue. (3) Outside this is the thinned wall of the lacuna, which is separated from the arachnoid by a space which corresponds to and is continuous with the subdural cavity. (4) And finally, if the granulation projects into the sagittal sinus, it will be covered by the greatly thinned upper walls of the sinus. It will be seen, therefore, that fluid injected into the subarachnoid cavity will find its way into these granulations, and it has been found experimentally that it passes by osmosis from the granulations into the venous sinuses into which they project.

### The Pia Mater.

The **pia mater** is a vascular membrane, consisting of a minute plexus of blood-vessels, held together by an extremely fine areolar tissue.

The **cerebral pia mater** (*pia mater encephali*; *pia of the brain*) invests the entire surface of the brain, dips between the cerebral gyri and cerebellar laminæ, and is invaginated to form the tela chorioidea of the third ventricle, and the choroid plexuses of the lateral and third ventricles (pages 887 and 888); as it passes over the roof of the fourth ventricle, it forms the tela chorioidea and the choroid plexuses of this ventricle. Upon the surfaces of the hemispheres, where it covers the gray substance, it gives off from its deep surface a multitude of sheaths, around the minute vessels, that extend perpendicularly for some distance into the cerebral substance. On the cerebellum the membrane is more delicate; the vessels from its deep surface are shorter, and its relations to the cortex are not so intimate.




FIG. 770.—Diagrammatic transverse section of the medulla spinalis and its membranes.

The **spinal pia mater** (*pia mater spinalis*; *pia of the cord*) (Figs. 767, 770) is thicker, firmer, and less vascular than the cerebral pia mater: this is due to the fact that it consists of two layers, the outer or additional one being composed of bundles of connective-tissue fibres, arranged for the most part longitudinally. Between the layers are cleft-like spaces which communicate with the subarachnoid cavity, and a number of bloodvessels which are enclosed in perivascular lymphatic sheaths.

The spinal pia mater covers the entire surface of the medulla spinalis, and is very intimately adherent to it; in front it sends a process backward into the anterior fissure. A longitudinal fibrous band, called the *linea splendens*, extends along the middle line of the anterior surface; and a somewhat similar band, the *ligamentum denticulatum*, is situated on either side. Below the conus medullaris, the pia mater is continued as a long, slender filament (*filum terminale*), which descends through the centre of the mass of nerves forming the cauda equina. It blends with the dura mater at the level of the lower border of the second sacral vertebra, and extends downward as far as the base of the coccyx, where it fuses with the periosteum. It assists in maintaining the medulla spinalis in its position during the movements of the trunk, and is, from this circumstance, called the *central ligament* of the medulla spinalis.

The pia mater forms sheaths for the cerebral and spinal nerves; these sheaths are closely connected with the nerves, and blend with their common membranous investments.

The *ligamentum denticulatum* (*dentate ligament*) (Fig. 767) is a narrow fibrous band situated on either side of the medulla spinalis throughout its entire length, and separating the anterior from the posterior nerve roots. Its medial border is continuous with the pia mater at the side of the medulla spinalis. Its lateral border presents a series of triangular tooth-like processes, the points of which are fixed at intervals to the dura mater. These processes are twenty-one in number, on either side, the first being attached to the dura mater, opposite the margin of the foramen magnum, between the vertebral artery and the hypoglossal nerve; and the last near the lower end of the medulla spinalis.

**Applied Anatomy.**—Evidence of great value in the diagnosis of meningitis may sometimes be obtained by puncturing the spinal membranes and withdrawing some of the cerebrospinal fluid; moreover, the operation of lumbar puncture is in many cases curative, under the supposition that the draining of some of the cerebrospinal fluid relieves the patient by diminishing the intracranial pressure. The operation is performed by inserting a trocar, of the smallest size, between the laminae of the third and fourth, or of the fourth and fifth lumbar vertebrae, through the ligamentum flavum. The medulla spinalis, even of a child at birth, does not reach below the third lumbar vertebra, and therefore the canal may be punctured between the third and fourth lumbar vertebrae without any risk of injuring this structure. The point of puncture is indicated by laying the patient on the side and dropping a perpendicular line from the highest point of the iliac crest; this will cross the upper border of the spinous process of the fourth lumbar vertebra, and will indicate the level at which the trocar should be inserted a little to one side of the middle line. The puncture may require to be repeated more than once, and the greatest precaution must be taken not to allow septic infection of the meninges. If there be any appreciable increase of pressure, the fluid will flow through the trocar with the greatest freedom.

In addition to the constitutional signs and symptoms of fever, *acute spinal meningitis* exhibits certain characteristic features. Pain and tenderness to pressure along the vertebral column are common, and so are pains in the limbs or around the trunk from irritation of the posterior nerve roots by the inflammatory products. Irritation of the anterior nerve roots is shown by the increased tone of the muscles, which may go on to the point where they pass into a state of spasm with much increased reflexes; this is often seen in the retraction of the head and neck. Later in the disease the reflexes are often lost, when, also, the urine and feces may be passed involuntarily.

## THE CEREBRAL NERVES (NERVI CEREBRALES; CRANIAL NERVES).

There are twelve pairs of cerebral nerves; they are attached to the brain and are transmitted through foramina in the base of the cranium. The different pairs are named from before backward as follows:

- |                  |                        |
|------------------|------------------------|
| 1st. Olfactory.  | 7th. Facial.           |
| 2d. Optic.       | 8th. Acoustic.         |
| 3rd. Oculomotor. | 9th. Glossopharyngeal. |
| 4th. Trochlear.  | 10th. Vagus.           |
| 5th. Trigeminal. | 11th. Accessory.       |
| 6th. Abducent.   | 12th. Hypoglossal.     |

The area of attachment of a cerebral nerve to the surface of the brain is termed its **superficial or apparent origin**. The fibres of the nerve can be traced into the substance of the brain to a special *nucleus* of gray substance. The motor or efferent cerebral nerves arise within the brain from groups of nerve cells which constitute their **nuclei of origin**. The sensory or afferent cerebral nerves arise from groups of nerve cells outside the brain; these nerve cells may be grouped to form ganglia on the trunks of the nerves or may be situated in peripheral sensory organs such as the nose and eye. The central processes of these cells run into the brain, and there end by arborizing around nerve cells, which are grouped to form **nuclei of termination**. The nuclei of origin of the motor nerves and the nuclei of termination of the sensory nerves are brought into relationship with the cerebral cortex, the former through the geniculate fibres of the internal capsule, the latter through the lemniscus. The geniculate fibres arise from the cells of the motor area of the cortex, and, after crossing the middle line, end by arborizing around the cells of the nuclei of origin of the motor cerebral nerves. On the other hand, fibres arise from the cells of the nuclei of termination of the sensory nerves, and after crossing to the opposite side, join the lemniscus, and thus connect these nuclei, directly or indirectly, with the cerebral cortex.

#### THE OLFACTORY NERVES (NN. OLFACTORII; FIRST NERVE) (Fig. 771).

The **olfactory nerves** or nerves of smell are distributed to the mucous membrane of the olfactory region of the nasal cavity: this region comprises the superior nasal concha, and the corresponding part of the nasal septum. The nerves originate from the central or deep processes of the olfactory cells of the nasal mucous membrane. They form a plexiform net-work in the mucous membrane, and are then collected into about twenty branches, which pierce the cribriform plate of the ethmoid bone in two groups, a **lateral** and a **medial group**, and end in the glomeruli




FIG. 771.—Nerves of septum of nose. Right side.




FIG. 772.—Plan of olfactory neurons

of the olfactory bulb (Fig. 772). Each branch receives tubular sheaths from the dura mater and pia mater, the former being lost in the periosteum of the nose, the latter in the neurolemma of the nerve.

The olfactory nerves are non-medullated, and consist of axis-cylinders surrounded by nucleated sheaths, in which, however, there are fewer nuclei than are found in the sheaths of ordinary non-medullated nerve fibres.

The olfactory centre in the cortex is generally associated with the rhinencephalon (page 874).

**Applied Anatomy.**—In severe injuries to the head involving the anterior fossa of the base of the skull, the olfactory bulb may become separated from the olfactory nerves, or the nerves may be torn, thus producing loss of smell (*anosmia*), and with this there is a considerable loss in the sense of taste, since much of the perfection of the sense of taste is due to the substances being also odorous, and simultaneously exciting the sense of smell.

Anosmia often occurs after influenza or other acute infection of the nose. Parosmia, or a perversion of the sense of smell, may occur in lesions of the cortical olfactory centres, or in insanity.

### THE OPTIC NERVE (N. OPTICUS; SECOND NERVE) (Fig. 773).

The **optic nerve**, or nerve of sight, is distributed exclusively to the bulb of the eye. The nerves of opposite sides are connected together at the optic chiasma, and from the back of the chiasma the nerve fibres may be traced to the brain, in the **optic tracts**.

The **optic tract**, at its connection with the brain, is divided into two bands, lateral and medial. The **lateral band** is larger; it is connected with the lateral geniculate body, the pulvinar of the thalamus and the superior colliculus. The **medial band** ends in the medial geniculate body; its fibres are merely commissural, forming Gudden's commissure. From these attachments the tract winds obliquely across the under surface of the cerebral peduncle in the form of a flattened band, and is attached to the peduncle by its anterior margin. It then assumes a cylindrical form, and, as it passes forward, is connected with the tuber cinereum and lamina terminalis. It finally joins with the tract of the opposite side to form the optic chiasma.




FIG. 773.—The left optic nerve and the optic tracts.

The **optic chiasma** (*chiasma opticum*), somewhat quadrilateral in form, rests upon the tuberculum sellae and on the anterior part of the diaphragma sellae. It is in relation, *above*, with the lamina terminalis; *behind*, with the tuber cinereum; on *either side*, with the anterior perforated substance. Within the chiasma, the optic nerves undergo a partial decussation. The fibres forming the medial part of each tract and posterior part of the chiasma have no connection with the optic nerves. They simply cross in the chiasma, and connect the medial geniculate bodies of the two sides; they form the **commissure of Gudden**. The remaining and principal part of the chiasma consists of two sets of fibres, crossed and uncrossed. The **crossed fibres** which are the more numerous, occupy the central part of the chiasma, and pass from the optic nerve of one side to the optic tract of the other. decussating in the chiasma with similar fibres of the opposite optic nerve. The **uncrossed fibres** occupy the lateral part of the chiasma, and pass from the nerve of one side into the tract of the same side.<sup>1</sup>

The great majority of the fibres of the optic nerve (Fig. 774) consist of the afferent fibres of nerve cells in the retina; a few, however, are efferent fibres, and grow out from cells in the brain. They become medullated about the tenth week after birth. The afferent fibres end in arborizations around the cells in the lateral geniculate body, pulvinar, and superior colliculus, which constitute the **lower visual centres**. From the cells of these centres fibres are prolonged to the **cortical visual centre**, situated in the cuneus and in the neighborhood of the calcarine fissure.

<sup>1</sup> A specimen of congenital absence of the optic chiasma is to be found in the Museum of the Westminster Hospital. See also Henle, *Nervenlehre*, p. 393, ed. 2.

Some fibres are detached from the optic tract, and pass through the cerebral peduncle to the nucleus of the oculomotor nerve. These fibres are small, and may be regarded as afferent branches for the Sphincter pupillae and Ciliaris muscles. Other fibres pass to the cerebellum through the brachia conjunctiva, while others end in the nuclei in the pons.

The **optic nerves** arise from the forepart of the chiasma, and, diverging from one another, each becomes rounded in form and firm in texture, and is enclosed in a sheath derived from the pia mater and arachnoid. The nerve passes beneath the anterior cerebral artery, and enters the optic foramen, receiving as it does so




FIG. 774.—Scheme showing central connections of the optic nerves and optic tracts.

a sheath from the dura mater. When the nerve reaches the orbit this sheath divides into two layers, one of which becomes continuous with the periosteum of the orbit; the other forms the proper sheath of the nerve, and surrounds it as far as the bulb of the eye. The nerve runs forward and lateralward through the cavity of the orbit, pierces the sclera and choroid at the back part of the bulb of the eye, about 3 to 4 mm. to the nasal side of its centre, and expands to form the **stratum opticum of the retina**. A little behind the bulb of the eye the arteria centralis retinae perforates the optic nerve, and runs along its interior in a tubular canal of fibrous tissue. It supplies the retina, and is accompanied by corresponding veins. The retina is described with the anatomy of the eyeball.



**Applied Anatomy.**—The optic nerve is peculiarly liable to become the seat of neuritis or undergo atrophy in affection of the central nervous system, and as a rule the pathological relationship between the two affections is exceedingly difficult to trace. There are, however, certain points in connection with the anatomy of this nerve which tend to throw light upon the frequent association of these affections with intracranial disease. (1) From its mode of development, and from its structure, the optic nerve must be regarded as a prolongation of the brain substance, rather than as an ordinary cerebrospinal nerve. (2) As it passes from the brain it receives sheaths from the three cerebral membranes, a perineural sheath from the pia mater, an intermediate sheath from the arachnoid, and an outer sheath from the dura mater, which is also connected with the periosteum as it passes through the optic foramen. These sheaths are separated from each other by cavities which communicate with the subdural and subarachnoid cavities respectively. The innermost or perineural sheath sends a process around the arteria centralis retinae into the interior of the nerve, and enters intimately into its structure. Thus inflammatory affections of the meninges or of the brain may readily extend along these spaces, or along the interstitial connective tissue in the nerve.

The course of the fibres in the optic chiasma has an important pathological bearing, and has been the subject of much controversy. Microscopic examination, experiments, and pathology all seem to point to the fact that there is a partial decussation of the fibres, each optic tract supplying the corresponding half of each eye, so that the right tract supplies the right half of each eye, and the left tract the left half of each eye. At the same time Charcot believes, and his view has met with general acceptance, that the fibres which do not decussate at the optic chiasma undergo decussation in the corpora quadrigemina, so that the lesion of the cerebral centre of one side causes complete blindness of the opposite eye, because both sets of decussating fibres are destroyed; whereas if one tract, say the right, be destroyed by disease, there will be blindness of the right half of both retinae.

An antero-posterior section through the chiasma would divide the decussating fibres, and would therefore produce blindness of the medial half of each eye; while a section at the margin of the side of the optic chiasma would produce blindness of the lateral half of the retina of the same side. An early symptom of tumor growth in the hypophysis is pressure on the chiasma.

The optic nerve may also be affected in injuries or diseases involving the orbit; in fractures of the anterior fossa of the base of the skull; in tumors of the orbit itself, or those invading this cavity from neighboring parts.

### THE OCULOMOTOR NERVE (N. OCULOMOTORIUS; THIRD NERVE)

(Figs. 776, 777, 778).

The oculomotor nerve supplies all the ocular muscles, except the Obliquus superior and Rectus lateralis; it also supplies through its connections with the ciliary ganglion, the Sphincter pupillae and the Ciliaris muscles.

The fibres of the oculomotor nerve arise from a nucleus which lies in the gray substance of the floor of the cerebral aqueduct and extends in front of the aqueduct for a short distance into the floor of the third ventricle. From this nucleus the fibres pass forward through the tegmentum, the red nucleus, and the medial part of the substantia nigra, forming a series of curves with a lateral convexity, and emerge from the oculomotor sulcus on the medial side of the cerebral peduncle.

The nucleus of the oculomotor nerve does not consist of a continuous column of cells, but is broken up into a number of smaller nuclei, which are arranged in two groups, anterior and posterior. Those of the posterior group are six in number, five of which are symmetrical on the two sides of the middle line, while the sixth, centrally placed and is common to the nerves of both sides. The anterior group consists of two nuclei, an antero-medial and an antero-lateral (Fig. 775).

The nucleus of the third nerve is said to give fibres to the facial nerve, which probably supply the Orbicularis oculi, Corrugator, and Frontalis muscles.<sup>1</sup> It is also connected with the nuclei of the trochlear and abducent nerves, with the cerebellum, the superior colliculus, and the cortex of the occipital lobe of the cerebrum.

The nucleus of the oculomotor nerve, considered from a physiological standpoint, can be subdivided into several smaller groups of cells, each group controlling a

<sup>1</sup> See footnote, p. 852.

particular muscle. The nerves to the different muscles appear to take their origin from behind forward, as follows: Obliquus inferior, Rectus inferior, Rectus superior, Levator palpebrae superioris, and Rectus medialis; while from the anterior end of the nucleus the fibres for the Ciliaris and the Sphincter pupillae take their origin.




FIG. 775.—Figure showing the different groups of cells, which constitute, according to Perlia, the nucleus of origin of the oculomotor nerve. (Testut.) 1. Posterior dorsal nucleus. 1'. Posterior ventral nucleus. 2. Anterior dorsal nucleus. 2'. Anterior ventral nucleus. 3. Central nucleus. 4. Nucleus of Edinger and Westphal. 5. Antero-internal nucleus. 6. Antero-external nucleus. 8. Crossed fibres. 9. Trochlear nerve, with 9', its nucleus of origin, and 9'', its decussation. 10. Third ventricle. M, M. Median line.

On emerging from the brain, the nerve is invested with a sheath of pia mater, and enclosed in a prolongation from the arachnoid. It passes between the superior cerebellar and posterior cerebral arteries, and then pierces the dura mater in front of and lateral to the posterior clinoid process, passing between the free and attached borders of the tentorium cerebelli. It runs along the lateral wall of the cavernous sinus, above the other orbital nerves, receiving in its course one or two filaments from the cavernous plexus of the sympathetic, and a communicating branch from the ophthalmic division of the trigeminal. It then divides into two branches, which enter the orbit through the superior orbital fissure, between the two heads of the Rectus lateralis. Here the nerve is placed below the trochlear nerve and the frontal and lacrimal branches of the ophthalmic nerve, while the nasociliary nerve is placed between its two rami.

The **superior ramus**, the smaller, passes medialward over the optic nerve, and supplies the Rectus superior and Levator palpebrae superioris. The **inferior ramus**, the larger, divides into three branches. One passes beneath the optic nerve to the Rectus medialis; another, to the Rectus inferior; the third and longest runs forward between the Recti inferior and lateralis to the Obliquus inferior. From the last a short thick branch is given off to the lower part of the




FIG. 776.—Plan of oculomotor nerve.

ciliary ganglion, and forms its **short root**. All these branches enter the muscles on their ocular surfaces, with the exception of the nerve to the Obliquus inferior, which enters the muscle at its posterior border.

**Applied Anatomy.**—Paralysis of the oculomotor nerve may be the result of many causes, such as cerebral disease; or conditions causing pressure on the cavernous sinus; or periostitis of the bones entering into the formation of the superior orbital fissure. It results, when complete, in (1) ptosis, or drooping of the upper eyelid, in consequence of the Levator palpebrae superioris being paralyzed; (2) external strabismus, on account of the unopposed action of the Rectus lateralis and Obliquus superior, which are not supplied by the oculomotor nerve and are therefore not paralyzed; (3) dilatation of the pupil, because the Sphincter pupillae is paralyzed; (4) loss of power of accommodation and of contraction on exposure to light, as the Sphincter pupillae and the Ciliaris are paralyzed; (5) slight prominence of the eyeball, owing to most of its muscles being relaxed; and (6) the patient will complain of the resulting diplopia, or double vision, the false image being higher than the true, and the separation of the two images increasing with medial movements. Occasionally paralysis may affect only a part of the nerve—that is to say, there may be, for example, a dilated and fixed pupil, with ptosis, but no other signs. Irritation of the nerve causes spasm of one or other of the muscles supplied by it; thus, there may be internal strabismus from spasm of the Rectus medialis; accommodation for near objects only, from spasm of the Ciliaris; or miosis (contraction of the pupil) from irritation of the Sphincter pupillae.

The oculomotor nerve is particularly liable to become involved in a syphilitic periarteritis as it leaves the base of the brain, when passing between the posterior cerebral and superior cerebellar arteries; associated with locomotor ataxia various partial or complete paralyses of the nerve are often seen.

### THE TROCHLEAR NERVE (N. TROCHLEARIS; FOURTH NERVE) (Fig. 777).

The **trochlear nerve**, the smallest of the cerebral nerves, supplies the Obliquus superior oculi.

It *arises* from a nucleus situated in the floor of the cerebral aqueduct, opposite the upper part of the inferior colliculus. From its origin it runs downward through the tegmentum, and then turns backward into the upper part of the anterior medullary velum. Here it decussates with its fellow of the opposite side and emerges from the surface of the velum at the side of the frenulum veli, immediately behind the inferior colliculus.

The nerve is directed across the brachium conjunctiva cerebelli, and then winds forward around the cerebral peduncle, immediately above the pons, pierces the dura mater in the free border of the tentorium cerebelli, just behind, and lateral to, the posterior clinoid process, and passes forward in the lateral wall of the cavernous sinus, between the oculomotor nerve and the ophthalmic division of the trigeminal. It crosses the oculomotor nerve, and enters the orbit through the superior orbital fissure. It now becomes the highest of all the nerves, and lies medial to the frontal nerve. In the orbit it passes medialward, above the origin of the Levator palpebrae superioris, and finally enters the orbital surface of the Obliquus superior.

In the lateral wall of the cavernous sinus the trochlear nerve forms communications with the ophthalmic division of the trigeminal and with the cavernous plexus




FIG. 777.—Nerves of the orbit. Seen from above.

of the sympathetic. In the superior orbital fissure it occasionally gives off a branch to the lacrimal nerve. It gives off a recurrent branch which passes backward between the layers of the tentorium cerebelli and divides into two or three filaments which may be traced as far as the wall of the transverse sinus.

**Applied Anatomy.**—When the trochlear nerve is paralyzed there is loss of function in the Obliquus superior, so that the patient is unable to turn his eye downward and outward. Should the patient attempt to do this, the eye of the affected side is rotated inward, producing diplopia or double vision. Single vision exists in the whole of the field so long as the eyes look above the horizontal plane, but diplopia occurs on looking downward. To counteract this the patient holds his head forward, and also inclines it to the sound side.

### THE TRIGEMINAL NERVE (N. TRIGEMINUS; FIFTH OR TRIFACIAL NERVE).

The **trigeminal nerve** is the largest cerebral nerve and is the great sensory nerve of the head and face, and the motor nerve of the muscles of mastication.

It emerges from the side of the pons, near its upper border, by a small *motor* and a large *sensory root*—the former being situated in front of and medial to the latter.

**Motor Root.**—The fibres of the motor root *arise* from two nuclei, a superior and an inferior. The **superior nucleus** consists of a strand of cells occupying the whole length of the lateral portion of the gray substance of the cerebral aqueduct. The **inferior or chief nucleus** is situated in the upper part of the pons, close to its dorsal surface, and along the line of the lateral margin of the rhomboid fossa. The fibres from the superior nucleus constitute the **mesencephalic root**: they descend through the mesencephalon, and, entering the pons, join with the fibres from the lower nucleus, and the motor root, thus formed, passes forward through the pons to its point of emergence.

**Sensory Root.**—The fibres of the sensory root *arise* from the cells of the semilunar ganglion which lies in a cavity of the dura mater near the apex of the petrous part of the temporal bone. They pass backward below the superior petrosal sinus and tentorium cerebelli, and, entering the pons, divide into upper and lower roots. The upper root ends partly in a nucleus which is situated in the pons lateral to the lower motor nucleus, and partly in the locus caeruleus; the lower root descends through the pons and medulla oblongata, and ends in the upper part of the substantia gelatinosa of Rolando. This lower root is sometimes named the **spinal root** of the nerve. Medullation of the fibres of the sensory root begins about the fifth month of fetal life, but the whole of its fibres are not medullated until the third month after birth.

The **semilunar ganglion** (*ganglion semilunare* [Gasseri]; *Gasserian ganglion*) occupies a cavity (*cavum Meckelii*) in the dura mater covering the trigeminal impression near the apex of the petrous part of the temporal bone. It is somewhat crescentic in shape, with its convexity directed forward: medially, it is in relation with the internal carotid artery and the posterior part of the cavernous sinus. The motor root runs in front of and medial to the sensory root, and passes beneath the ganglion; it leaves the skull through the foramen ovale, and, immediately below this foramen, joins the mandibular nerve. The greater superficial petrosal nerve lies also underneath the ganglion.

The ganglion receives, on its medial side, filaments from the carotid plexus of the sympathetic. It gives off minute branches to the tentorium cerebelli, and to the dura mater in the middle fossa of the cranium. From its convex border, which is directed forward and lateralward, three large nerves proceed, viz., the **ophthalmic**, **maxillary**, and **mandibular**. The ophthalmic and maxillary consist exclusively of sensory fibres; the mandibular is joined outside the cranium by the motor root.



Associated with the three divisions of the trigeminal nerve are four small ganglia. The **ciliary ganglion** is connected with the ophthalmic nerve; the **sphenopalatine ganglion** with the maxillary nerve; and the **otic** and **submaxillary ganglia** with the mandibular nerve. All four receive sensory filaments from the trigeminal, and motor and sympathetic filaments from various sources; these filaments are called the **roots of the ganglia**.

The **ophthalmic nerve** (*n. ophthalmicus*) (Figs. 777, 778), or **first division** of the trigeminal, is a sensory nerve. It supplies branches to the cornea, ciliary body, and iris; to the lacrimal gland and conjunctiva; to the part of the mucous membrane of the nasal cavity; and to the skin of the eyelids, eyebrow, forehead, and nose. It is the smallest of the three divisions of the trigeminal, and *arises* from the upper part of the semilunar ganglion as a short, flattened band, about 2.5 cm. long, which passes forward along the lateral wall of the cavernous sinus, below the oculomotor and trochlear nerves; just before entering the orbit, through the superior orbital fissure, it divides into three branches, **lacrimal**, **frontal**, and **nasociliary**.




FIG. 778.—Nerves of the orbit, and the ciliary ganglion. Side view.

The ophthalmic nerve is joined by filaments from the cavernous plexus of the sympathetic, and communicates with the oculomotor, trochlear, and abducent nerves; it gives off a recurrent filament which passes between the layers of the tentorium.

The **Lacrimal Nerve** (*n. lacrimalis*) is the smallest of the three branches of the ophthalmic. It sometimes receives a filament from the trochlear nerve, but this is possibly derived from the branch which goes from the ophthalmic to the trochlear nerve. It passes forward in a separate tube of dura mater, and enters the orbit through the narrowest part of the superior orbital fissure. In the orbit it runs along the upper border of the Rectus lateralis, with the lacrimal artery, and communicates with the zygomatic branch of the maxillary nerve. It enters the lacrimal gland and gives off several filaments, which supply the gland and the conjunctiva. Finally it pierces the orbital septum, and ends in the skin of the upper eyelid, joining with filaments of the facial nerve. The lacrimal nerve is occasionally absent, and its place is then taken by the zygomaticotemporal branch of the maxillary. Sometimes the latter branch is absent, and a continuation of the lacrimal is substituted for it.



The **Frontal Nerve** (*n. frontalis*) is the largest branch of the ophthalmic, and may be regarded, both from its size and direction, as the continuation of the nerve. It enters the orbit through the superior orbital fissure, and runs forward between the Levator palpebrae superioris and the periosteum. Midway between the apex and base of the orbit it divides into two branches, **supratrochlear** and **supraorbital**.

The **supratrochlear nerve** (*n. supratrochlearis*), the smaller of the two, passes above the pulley of the Obliquus superior, and gives off a descending filament, to join the infratrochlear branch of the nasociliary nerve. It then escapes from the orbit between the pulley of the Obliquus superior and the supraorbital foramen, curves up on to the forehead close to the bone, ascends beneath the Corrugator and Frontalis, and dividing into branches which pierce these muscles, it supplies the skin of the lower part of the forehead close to the middle line and sends filaments to the conjunctiva and skin of the upper eyelid.

The **supraorbital nerve** (*n. supraorbitalis*) passes through the supraorbital foramen, and gives off, in this situation, palpebral filaments to the upper eyelid. It then ascends upon the forehead, and ends in two branches, a medial and a lateral, which supply the integument of the scalp, reaching nearly as far back as the lambdoidal suture; they are at first situated beneath the Frontalis, the medial branch perforating the muscle, the lateral branch the galea aponeurotica. Both branches supply small twigs to the pericranium.

The **Nasociliary Nerve** (*n. nasociliaris; nasal nerve*) is intermediate in size between the frontal and lacrimal, and is more deeply placed. It enters the orbit between the two heads of the Rectus lateralis, and between the superior and inferior rami of the oculomotor nerve. It passes across the optic nerve and runs obliquely beneath the Rectus superior and Obliquus superior, to the medial wall of the orbital cavity. Here it passes through the anterior ethmoidal foramen, and, entering the cavity of the cranium, traverses a shallow groove on the lateral margin of the front part of the cribriform plate of the ethmoid bone, and runs down, through a slit at the side of the crista galli, into the nasal cavity. It supplies **internal nasal branches** to the mucous membrane of the front part of the septum and lateral wall of the nasal cavity. Finally, it emerges, as the **external nasal branch**, between the lower border of the nasal bone and the lateral nasal cartilage, and, passing down beneath the Nasalis muscle, supplies the skin of the ala and apex of the nose.

The nasociliary nerve gives off the following branches, viz.: the **long root of the ciliary ganglion**, the **long ciliary**, and the **ethmoidal nerves**.

The **long root of the ciliary ganglion** (*radix longa ganglii ciliaris*) usually arises from the nasociliary between the two heads of the Rectus lateralis. It passes forward on the lateral side of the optic nerve, and enters the postero-superior angle of the ciliary ganglion; it is sometimes joined by a filament from the cavernous plexus of the sympathetic, or from the superior ramus of the trochlear nerve.

The **long ciliary nerves** (*nn. ciliares longi*), two or three in number, are given off from the nasociliary, as it crosses the optic nerve. They accompany the short ciliary nerves from the ciliary ganglion, pierce the posterior part of the sclera, and running forward between it and the choroid, are distributed to the Ciliaris muscle, iris, and cornea.

The **infratrochlear nerve** (*n. infratrochlearis*) is given off from the nasociliary just before it enters the anterior ethmoidal foramen. It runs forward along the upper border of the Rectus medialis, and is joined, near the pulley of the Obliquus superior, by a filament from the supratrochlear nerve. It then passes to the medial angle of the eye, and supplies the skin of the eyelids and side of the nose, the conjunctiva, lacrimal sac, and caruncula lacrimalis.

The **ethmoidal branches** (*nn. ethmoidales*) supply the ethmoidal cells; the posterior branch leaves the orbital cavity through the posterior ethmoidal foramen and gives some filaments to the sphenoidal sinus.

**The Ciliary Ganglion** (*ganglion ciliare; ophthalmic or lenticular ganglion*) (Figs. 776, 778).—The ciliary ganglion is a small, quadrangular, flattened ganglion, of a reddish-gray color, and about the size of a pin's head; it is situated at the back part of the orbit, in some loose fat between the optic nerve and the Rectus lateralis muscle, lying generally on the lateral side of the ophthalmic artery.

Its **roots** are three in number, and enter its posterior border. One, the long or sensory root, is derived from the nasociliary nerve, and joins its postero-superior angle. The second, the short or motor root, is a thick nerve (occasionally divided into two parts) derived from the branch of the oculomotor nerve to the Obliquus inferior, and connected with the postero-inferior angle of the ganglion. The third, the sympathetic root, is a slender filament from the cavernous plexus of the sympathetic; it is frequently blended with the long root. According to Tiedemann, the ciliary ganglion receives a twig of communication from the sphenopalatine ganglion.

Its **branches** are the **short ciliary nerves**. These are delicate filaments, from six to ten in number, which *arise* from the forepart of the ganglion in two bundles connected with its superior and inferior angles; the lower bundle is the larger. They run forward with the ciliary arteries in a wavy course, one set above and the other below the optic nerve, and are accompanied by the long ciliary nerves from the nasociliary. They pierce the sclera at the back part of the bulb of the eye, pass forward in delicate grooves on the inner surface of the sclera, and are distributed to the Ciliaris muscle, iris, and cornea. Tiedemann has described a small branch as penetrating the optic nerve with the arteria centralis retinae.

The **maxillary nerve** (*n. maxillaris; superior maxillary nerve*) (Fig. 779), or **second division** of the trigeminal, is a sensory nerve. It is intermediate, both in position and size, between the ophthalmic and mandibular. It begins at the middle of the semilunar ganglion as a flattened plexiform band, and, passing horizontally forward, it leaves the skull through the foramen rotundum, where it becomes more cylindrical in form, and firmer in texture. It then crosses the pterygopalatine fossa, inclines lateralward on the back of the maxilla, and enters the orbit through the inferior orbital fissure; it traverses the infraorbital groove and canal in the floor of the orbit, and appears upon the face at the infraorbital foramen.<sup>1</sup> At its termination, the nerve lies beneath the Quadratus labii superioris, and divides into a leash of branches which spread out upon the side of the nose, the lower eyelid, and the upper lip, joining with filaments of the facial nerve.

**Branches.**—Its branches may be divided into four groups, according as they are given off in the **cranium**, in the **pterygopalatine fossa**, in the **infraorbital canal**, or on the **face**.

In the Cranium . . . . .	Middle meningeal.
In the Pterygopalatine Fossa . . . . .	{ Zygomatic.
	{ Sphenopalatine.
	{ Posterior superior alveolar.
In the Infraorbital Canal . . . . .	{ Anterior superior alveolar.
	{ Middle superior alveolar.
	{ Inferior palpebral.
On the Face . . . . .	{ External nasal.
	{ Superior labial.

**The Middle Meningeal Nerve** (*n. meningeus medius; meningeal or dural branch*) is given off from the maxillary nerve directly after its origin from the semilunar ganglion; it accompanies the middle meningeal artery and supplies the dura mater.

**The Zygomatic Nerve** (*n. zygomaticus; temporomalar nerve; orbital nerve*) arises in the pterygopalatine fossa, enters the orbit by the inferior orbital fissure,

<sup>1</sup> After it enters the infraorbital canal, the nerve is frequently called the *infraorbital*.

and divides at the back of that cavity into two branches, **zygomaticotemporal** and **zygomaticofacial**.

The **zygomaticotemporal branch** (*ramus zygomaticotemporalis*; *temporal branch*) runs along the lateral wall of the orbit in a groove in the zygomatic bone, receives a branch of communication from the lacrimal, and, passing through a foramen in the zygomatic bone, enters the temporal fossa. It ascends between the bone, and substance of the Temporalis muscle, pierces the temporal fascia about 2.5 cm. above the zygomatic arch, and is distributed to the skin of the side of the forehead, and communicates with the facial nerve and with the auriculotemporal branch of the mandibular nerve. As it pierces the temporal fascia, it gives off a slender twig, which runs between the two layers of the fascia to the lateral angle of the orbit.




FIG. 779.—Distribution of the maxillary and mandibular nerves, and the submaxillary ganglion.

The **zygomaticofacial branch** (*ramus zygomaticofacialis*; *malar branch*) passes along the infero-lateral angle of the orbit, emerges upon the face through a foramen in the zygomatic bone, and, perforating the Orbicularis oculi, supplies the skin on the prominence of the cheek. It joins with the facial nerve and with the inferior palpebral branches of the maxillary.

The **Sphenopalatine Branches** (*nn. sphenopalatini*), two in number, descend to the sphenopalatine ganglion.

The **Posterior Superior Alveolar Branches** (*rami alveolares superiores posteriores*; *posterior superior dental branches*) arise from the trunk of the nerve just before it enters the infraorbital groove; they are generally two in number, but sometimes arise by a single trunk. They descend on the tuberosity of the maxilla and give off

several twigs to the gums and neighboring parts of the mucous membrane of the cheek. They then enter the posterior alveolar canals on the infratemporal surface of the maxilla, and, passing from behind forward in the substance of the bone, communicate with the middle superior alveolar nerve, and give off branches to the lining membrane of the maxillary sinus and three twigs to each molar tooth; these twigs enter the foramina at the apices of the roots of the teeth.

The **Middle Superior Alveolar Branch** (*ramus alveolaris superior medius; middle superior dental branch*), is given off from the nerve in the posterior part of the infra-orbital canal, and runs downward and forward in a canal in the lateral wall of the maxillary sinus to supply the two premolar teeth. It forms a superior dental plexus with the anterior and posterior superior alveolar branches.

The **Anterior Superior Alveolar Branch** (*ramus alveolaris superior anteriores; anterior superior dental branch*), of considerable size, is given off from the nerve just before its exit from the infraorbital foramen; it descends in a canal in the anterior wall of the maxillary sinus, and divides into branches which supply the incisor and canine teeth. It communicates with the middle superior alveolar branch, and gives off a **nasal branch**, which passes through a minute canal in the lateral wall of the inferior meatus, and supplies the mucous membrane of the anterior part of the inferior meatus and the floor of the nasal cavity, communicating with the nasal branches from the sphenopalatine ganglion.

The **Inferior Palpebral Branches** (*rami palpebrales; inferiores palpebral branches*) ascend behind the Orbicularis oculi. They supply the skin and conjunctiva of the lower eyelid, joining at the lateral angle of the orbit with the facial and zygomatico-facial nerves.

The **External Nasal Branches** (*rami nasales externi*) supply the skin of the side of the nose and of the septum mobile nasi, and join with the terminal twigs of the nasociliary nerve.

The **Superior Labial Branches** (*rami labiales superiores; labial branches*), the largest and most numerous, descend behind the Quadratus labii superioris, and are distributed to the skin of the upper lip, the mucous membrane of the mouth, and labial glands. They are joined, immediately beneath the orbit, by filaments from the facial nerve, forming with them the **infraorbital plexus**.

**Sphenopalatine Ganglion** (*ganglion sphenopalatinum; ganglion of Meckel*) (Fig. 780).—The sphenopalatine ganglion, the largest of the ganglia associated with the branches of the trigeminal nerve, is deeply placed in the pterygopalatine fossa, close to the sphenopalatine foramen. It is triangular or heart-shaped, of a reddish-gray color, and is situated just below the maxillary nerve as it crosses the fossa. It receives a sensory, a motor, and a sympathetic root.

Its **sensory root** is derived from two sphenopalatine branches of the maxillary nerve; their fibres, for the most part, pass directly into the palatine nerves; a few, however, enter the ganglion, constituting its sensory root. Its **motor root** is probably derived from the facial nerve through the greater superficial petrosal nerve and its **sympathetic root** from the carotid plexus through the deep petrosal nerve. These two nerves join to form the nerve of the pterygoid canal, before their entrance into the ganglion.

The **greater superficial petrosal nerve** (*n. petrosus superficialis major; large superficial petrosal nerve*) is given off from the genicular ganglion of the facial nerve; it passes through the hiatus of the facial canal, enters the cranial cavity, and runs forward beneath the dura mater in a groove on the anterior surface of the petrous portion of the temporal bone. It then enters the cartilaginous substance which fills the foramen lacerum, and joining with the deep petrosal branch forms the nerve of the pterygoid canal.

The **deep petrosal nerve** (*n. petrosus profundus; large deep petrosal nerve*) is given off from the carotid plexus, and runs through the carotid canal lateral to the internal

carotid artery. It then enters the cartilaginous substance which fills the foramen lacerum, and joins with the greater superficial petrosal nerve to form the nerve of the pterygoid canal.

The **nerve of the pterygoid canal** (*n. canalis pterygoidei* [Vidii]; *Vidian nerve*), formed by the junction of the two preceding nerves in the cartilaginous substance which fills the foramen lacerum, passes forward, through the pterygoid canal, with the corresponding artery, and is joined by a small ascending **sphenoidal branch** from the otic ganglion. Finally, it enters the pterygopalatine fossa, and joins the posterior angle of the pterygopalatine ganglion.




FIG. 780.—The sphenopalatine ganglion and its branches.

**Branches of Distribution.**—These are divisible into four groups, viz., **orbital**, **palatine**, **posterior**, **superior nasal**, and **pharyngeal**.

The **orbital branches** (*rami orbitales*; *ascending branches*) are two or three delicate filaments, which enter the orbit by the inferior orbital fissure, and supply the periosteum. According to Luschka, some filaments pass through foramina in the fronto-ethmoidal suture to supply the mucous membrane of the posterior ethmoidal and sphenoidal sinuses.

The **palatine nerves** (*nn. palatini*; *descending branches*) are distributed to the roof of the mouth, soft palate, tonsil, and lining membrane of the nasal cavity. Most of their fibres are derived from the sphenopalatine branches of the maxillary nerve. They are three in number: **anterior**, **middle**, and **posterior**.

The **anterior palatine nerve** (*n. palatinus anterior*) descends through the pterygopalatine canal, emerges upon the hard palate through the greater palatine foramen, and passes forward in a groove in the hard palate, nearly as far as the incisor teeth. It supplies the gums, the mucous membrane and glands of the hard palate, and communicates in front with the terminal filaments of the nasopalatine nerve. While in the pterygopalatine canal, it gives off **posterior inferior nasal branches**, which enter the nasal cavity through openings in the palatine bone, and ramify



over the inferior nasal concha and middle and inferior meatuses; at its exit from the canal, a palatine branch is distributed to both surfaces of the soft palate.

The **middle palatine nerve** (*n. palatinus medius*) emerges through one of the minor palatine canals and distributes branches to the uvula, tonsil, and soft palate. It is occasionally wanting.

The **posterior palatine nerve** (*n. palatinus posterior*) descends through the pterygo-palatine canal, and emerges by a separate opening behind the greater palatine foramen; it supplies the soft palate, tonsil, and uvula. The middle and posterior palatine join with the tonsillar branches of the glossopharyngeal to form a plexus (*circulus tonsillaris*) around the tonsil.

The **posterior superior nasal branches** (*rami nasales posteriores superiores*) are distributed to the septum and lateral wall of the nasal fossa. They enter the posterior part of the nasal cavity by the sphenopalatine foramen and supply the mucous membrane covering the superior and middle nasal conchæ, the lining of the posterior ethmoidal cells, and the posterior part of the septum. One branch, longer and larger than the others, is named the **nasopalatine nerve**. It enters the nasal cavity through the sphenopalatine foramen, passes across the roof of the nasal cavity below the orifice of the sphenoidal sinus to reach the septum, and then runs obliquely downward and forward between the periosteum and mucous membrane of the lower part of the septum. It descends to the roof of the mouth through the incisive canal and communicates with the corresponding nerve of the opposite side and with the anterior palatine nerve. It furnishes a few filaments to the mucous membrane of the nasal septum.

The **pharyngeal nerve** (*pterygopalatine nerve*) is a small branch arising from the posterior part of the ganglion. It passes through the pharyngeal canal with the pharyngeal branch of the internal maxillary artery, and is distributed to the mucous membrane of the nasal part of the pharynx, behind the auditory tube.

The **mandibular nerve** (*n. mandibularis; inferior maxillary nerve*) (Figs. 779, 781) supplies the teeth and gums of the mandible, the skin of the temporal region, the auricula, the lower lip, the lower part of the face, and the muscles of mastication; it also supplies the mucous membrane of the anterior two-thirds of the tongue. It is the largest of the three divisions of the fifth, and is made up of two roots: a large, **sensory root** proceeding from the inferior angle of the semilunar ganglion, and a small **motor root** (the motor part of the trigeminal), which passes beneath the ganglion, and unites with the sensory root, just after its exit through the foramen ovale. Immediately beneath the base of the skull, the nerve gives off from its medial side a recurrent branch (*nervus spinosus*) and the nerve to the Pterygoideus internus, and then divides into two trunks, an anterior and a posterior.

The **Nervus Spinosus** (*recurrent or meningeal branch*) enters the skull through the foramen spinosum with the middle meningeal artery. It divides into two branches, anterior and posterior, which accompany the main divisions of the artery and supply the dura mater; the posterior branch also supplies the mucous lining of the mastoid cells; the anterior communicates with the meningeal branch of the maxillary nerve.

The **Internal Pterygoid Nerve** (*n. pterygoideus internus*).—The nerve to the Pterygoideus internus is a slender branch, which enters the deep surface of the muscle; it gives off one or two filaments to the otic ganglion.

The anterior and smaller division of the mandibular nerve receives nearly the whole of the fibres of the motor root of the nerve, and supplies the muscles of mastication and the skin and mucous membrane of the cheek. Its branches are the **masseteric**, **deep temporal**, **buccinator**, and **external pterygoid**.

The **Masseteric Nerve** (*n. massetericus*) passes lateralward, above the Pterygoideus externus, in front of the temporomandibular articulation, and behind the tendon of the Temporalis; it crosses the mandibular notch with the masseteric artery,

to the deep surface of the Masseter, in which it ramifies nearly as far as its anterior border. It gives a filament to the temporomandibular joint.

The **Deep Temporal Nerves** (*nn. temporales profundi*) are two in number, anterior and posterior. They pass above the upper border of the Pterygoideus externus and enter the deep surface of the Temporalis. The **posterior branch**, of small size, is placed at the back of the temporal fossa, and sometimes arises in common with the masseteric nerve. The **anterior branch** is frequently given off from the buccinator nerve, and then turns upward over the upper head of the Pterygoideus externus. Frequently a third or intermediate branch is present.




FIG. 781.—The Pterygoideus externus and the branches of the mandibular nerve in relation to it.

The **Buccinator Nerve** (*n. buccinatorius*; *long buccal nerve*) passes forward between the two heads of the Pterygoideus externus, and downward beneath or through the lower part of the Temporalis; it emerges from under the anterior border of the Masseter, ramifies on the surface of the Buccinator, and unites with the buccal branches of the facial nerve. It supplies a branch to the Pterygoideus externus during its passage through that muscle, and may give off the anterior deep temporal nerve. The buccinator nerve supplies the skin over the Buccinator, and the mucous membrane lining its inner surface.

**External Pterygoid Nerve** (*n. pterygoideus externus*).—The nerve to the Pterygoideus externus frequently arises in conjunction with the buccinator nerve, but it may be given off separately from the anterior division of the mandibular nerve. It enters the deep surface of the muscle.

The posterior and larger division of the mandibular nerve is for the most part sensory, but receives a few filaments from the motor root. It divides into **auriculotemporal**, **lingual**, and **inferior alveolar nerves**.

The **Auriculotemporal Nerve** (*n. auriculotemporalis*) generally arises by two roots, between which the middle meningeal artery ascends. It runs backward beneath the Pterygoideus externus to the medial side of the neck of the mandible. It then turns upward with the superficial temporal artery, between the auricula and condyle of the mandible, under cover of the parotid gland; escaping from beneath the gland, it ascends over the zygomatic arch, and divides into superficial temporal branches.

The **branches of communication** of the auriculotemporal nerve are with the facial nerve and with the otic ganglion. The branches to the facial, usually two in number, pass forward from behind the neck of the mandible and join the facial nerve at the posterior border of the Masseter. The filaments to the otic ganglion are derived from the roots of the auriculotemporal nerve close to their origin.

Its **branches of distribution** are:

Anterior auricular.	Articular.
Branches to the external acoustic meatus.	Parotid.
Superficial temporal.	

The **anterior auricular branches** (*nn. auriculares anteriores*) are usually two in number; they supply the front of the upper part of the auricula, being distributed principally to the skin covering the front of the helix and tragus.

The **branches to the external acoustic meatus** (*n. meatus auditorii externi*), two in number, enter the meatus between its bony and cartilaginous portions and supply the skin lining it; the upper one sends a filament to the tympanic membrane.

The **articular branches** consist of one or two twigs which enter the posterior part of the temporomandibular joint.

The **parotid branches** (*rami parotidei*) supply the parotid gland.

The **superficial temporal branches** (*rami temporales superficiales*) accompany the superficial temporal artery to the vertex of the skull; they supply the skin of the temporal region and communicate with the facial and zygomaticotemporal nerves.

The **Lingual Nerve** (*n. lingualis*) supplies the mucous membrane of the anterior two-thirds of the tongue. It lies at first beneath the Pterygoideus externus, medial to and in front of the inferior alveolar nerve, and is occasionally joined to this nerve by a branch which may cross the internal maxillary artery. The chorda tympani also joins it at an acute angle in this situation. The nerve then passes between the Pterygoideus internus and the ramus of the mandible, and crosses obliquely to the side of the tongue over the Constrictor pharyngis superior and Styloglossus, and then between the Hyoglossus and deep part of the submaxillary gland; it finally runs across the duct of the submaxillary gland, and along the tongue to its tip, lying immediately beneath the mucous membrane.

Its **branches of communication** are with the facial (through the chorda tympani), the inferior alveolar and hypoglossal nerves, and the submaxillary ganglion. The branches to the submaxillary ganglion are two or three in number; those connected with the hypoglossal nerve form a plexus at the anterior margin of the Hyoglossus.

Its **branches of distribution** supply the sublingual gland, the mucous membrane of the mouth, the gums, and the mucous membrane of the anterior two-thirds of the tongue; the terminal filaments communicate, at the tip of the tongue, with the hypoglossal nerve.

The **Inferior Alveolar Nerve** (*n. alveolaris inferior; inferior dental nerve*) is the largest branch of the mandibular nerve. It descends with the inferior alveolar artery, at first beneath the Pterygoideus externus, and then between the sphenomandibular ligament and the ramus of the mandible to the mandibular foramen. It then passes forward in the mandibular canal, beneath the teeth, as far as the mental foramen, where it divides into two terminal branches, incisive and mental.

The branches of the inferior alveolar nerve are the **mylohyoid**, **dental**, **incisive**, and **mental**.

The **mylohyoid nerve** (*n. mylohyoideus*) is derived from the inferior alveolar just before it enters the mandibular foramen. It descends in a groove on the deep surface of the ramus of the mandible, and reaching the under surface of the Mylohyoideus supplies this muscle and the anterior belly of the Digastricus.

The **dental branches** supply the molar and premolar teeth. They correspond in number to the roots of those teeth; each nerve entering the orifice at the point of the root, and supplying the pulp of the tooth; above the alveolar nerve they form an **inferior dental plexus**.

The **incisive branch** is continued onward within the bone, and supplies the canine and incisor teeth.

The **mental nerve** (*n. mentalis*) emerges at the mental foramen, and divides beneath the Triangularis muscle into three branches; one descends to the skin of the chin, and two ascend to the skin and mucous membrane of the lower lip; these branches communicate freely with the facial nerve.

Two small ganglia, the **otic** and the **submaxillary**, are connected with the mandibular nerve.




FIG. 782.—The otic ganglion and its branches.

**Otic Ganglion** (*ganglion oticum*) (Fig. 782).—The otic ganglion is a small, oval-shaped, flattened ganglion of a reddish-gray color, situated immediately below the foramen ovale; it lies on the medial surface of the mandibular nerve, and surrounds the origin of the nerve to the Pterygoideus internus. It is in relation, *laterally*, with the trunk of the mandibular nerve at the point where the motor and sensory roots join; *medially*, with the cartilaginous part of the auditory tube, and the origin of the Tensor veli palatini; *posteriorly*, with the middle meningeal artery.

**Branches of Communication.**—It is connected by two or three short filaments with the nerve to the Pterygoideus internus, from which it may obtain a motor, and possibly a sensory root. It communicates with the glossopharyngeal and facial nerves, through the lesser superficial petrosal nerve continued from the tympanic plexus, and through this nerve it probably receives a sensory root from the glossopharyngeal and a motor root from the facial; its sympathetic root consists of a filament from the plexus surrounding the middle meningeal artery. The ganglion

also communicates with the auriculotemporal nerve by a branch which is probably derived from the glossopharyngeal, and which passes to the ganglion, and then through it and auriculotemporal nerve to the parotid gland. A slender filament (*sphenoidal*) ascends from it to the nerve of the Pterygoid canal, and a small branch connects it with the chorda tympani.

Its **branches of distribution** are: a filament to the Tensor tympani, and one to the Tensor veli palatini. The former passes backward, lateral to the auditory tube; the latter arises from the ganglion, near the origin of the nerve to the Pterygoideus internus, and is directed forward. The fibres of these nerves are, however, mainly derived from the nerve to the Pterygoideus internus.

**Submaxillary Ganglion** (*ganglion submaxillare*) (Fig. 779).—The submaxillary ganglion is of small size and is fusiform in shape. It is situated above the deep portion of the submaxillary gland, on the hyoglossus, near the posterior border of the Mylohyoideus, and is connected by filaments with the lower border of the lingual nerve. It is suspended from the lingual nerve by two filaments which join the anterior and posterior parts of the ganglion. Through the posterior of these it receives a branch from the chorda tympani nerve which runs in the sheath of the lingual; it communicates with the sympathetic by filaments from the sympathetic plexus around the external maxillary artery.

Its **branches of distribution** are five or six in number; they *arise* from the lower part of the ganglion, and supply the mucous membrane of the mouth and the duct of the submaxillary gland, some being lost in the submaxillary gland. The branch of communication from the lingual to the forepart of the ganglion is by some regarded as a branch of distribution, through which filaments pass from the ganglion to the lingual nerve, and by it are conveyed to the sublingual gland and the tongue.

**Applied Anatomy.**—Paralysis of the trigeminal nerve causes anesthesia of the corresponding anterior half of the scalp, and of the face, excepting over a small area near the angle of the mandible supplied by the cervical nerves, and of the cornea and conjunctiva, and of the mucous membrane of the nose, mouth, and tongue. Taste is lost (*ageusia*) on the affected side. Paralysis and atrophy follow in the Temporalis, Masseter, and Pterygoidei, possibly also in the Tensor tympani; when the mouth is opened the mandible is thrust over toward the paralyzed side. Interference with the secretion of the tears, the nasal mucus, and the saliva, causes dryness of the corresponding mucous membranes. The sense of smell is gradually lost on the affected side from the trophic changes that follow in the nasal mucous membrane. Inflammation of the eyeball, under these circumstances known as neuroparalytic ophthalmia, is not rare, and is due to the dryness and insensitiveness of the conjunctiva; it is not a "trophic" phenomenon, but depends on the occurrence and neglect of traumatic inflammation in the anesthetic eye.

**Trigeminal Nerve Reflexes.**—Pains referred to various branches of the trigeminal nerve are of very frequent occurrence, and should always lead to a careful examination in order to discover a local cause. As a general rule the diffusion of pain over the various branches of the nerve is at first confined to one only of the main divisions, and the search for the causative lesion should always commence with a thorough examination of all those parts which are supplied by that division; although in severe cases pain may radiate over the branches of the other main divisions. The commonest example of this condition is the neuralgia which is so often associated with dental caries—here, although the tooth itself may not appear to be painful, the most distressing referred pains may be experienced, and these are at once relieved by treatment directed to the affected tooth.

Many other examples of trigeminal reflexes could be quoted, but it will be sufficient to mention the more common ones. Dealing with the ophthalmic nerve, severe supraorbital pain is commonly associated with acute glaucoma or with disease of the frontal or ethmoidal air cells. Malignant growths or empyema of the maxillary antrum, or unhealthy conditions about the inferior conchæ or the septum of the nose, are often found giving rise to "second division" neuralgia, and should be always looked for in the absence of dental disease in the maxilla.

It is on the mandibular nerve, however, that some of the most striking reflexes are seen. It is quite common to meet with patients who complain of pain in the ear, in whom there is no sign of aural disease, and the cause is usually to be found in a carious tooth in the mandible. Moreover, with an ulcer or cancer of the tongue, often the first pain to be experienced is one which radiates to the ear and temporal fossa, over the distribution of the auriculotemporal nerve.



The trigeminal nerve is often the seat of severe neuralgia for which no local cause can be discovered; each of the three divisions has been divided, or a portion of the nerve excised, for this affection, usually, however, with only temporary relief. The supraorbital nerve may be exposed by making an incision 4 cm. in length along the supraorbital margin, below the eyebrow which is to be drawn upward, the centre of the incision corresponding to the supraorbital notch. The skin and Orbicularis oculi having been divided, the nerve can be easily found emerging from the notch, and lying in some loose cellular tissue. It should be drawn up by a blunt hook and 1.25 cm. of it resected, or the nerve can be injected with absolute alcohol.

The infraorbital nerve has been divided at its exit by an incision on the cheek; or the floor of the orbit has been exposed, the infraorbital canal opened up, and the anterior part of the nerve resected; or the whole nerve, together with sphenopalatine ganglion as far back as the foramen rotundum may be removed, but even then a return of the neuralgia in some other branches of the trigeminal nerve is the rule rather than the exception. The operation is performed as follows: the maxilla is first exposed by a T-shaped incision, one limb passing along the lower margin of the orbit, the other from the centre of this vertically down the cheek to the angle of the mouth. The nerve is to be found, divided, and a piece of silk tied to it as a guide. A small trephine (half-inch) is applied to the bone, below, but including the infraorbital foramen, and the maxillary sinus opened. The trephine is then applied to the posterior wall of the sinus, and the pterygo-palatine fossa exposed. The infraorbital canal is opened up from below, and the nerve drawn down into the trephine hole, and held on the stretch by means of the piece of silk; it is severed with fine curved scissors as near the foramen rotundum as possible, any branches coming off from the ganglion being also divided.




FIG. 783.—Diagram showing cutaneous areas of face and scalp.

The inferior alveolar nerve can be reached by a transverse incision over the ramus of the mandible placed so as to avoid injury to the facial nerve; the Masseter having been divided, a small trephine is applied to the ramus immediately beneath the mandibular notch, and, when the bone has been removed, the nerve is found lying on the Pterygoideus internus just as it enters the mandibular foramen, and it can here be resected. The lingual nerve is occasionally divided with the view of relieving the pain in cancerous disease of the tongue. This may be done in that part of its course where it lies below and behind the last molar tooth. If a line be drawn from the middle of the crown of the last molar tooth to the angle of the mandible it will cross the nerve, which lies about 1.25 cm. behind the tooth, parallel to the bulging alveolar ridge on the inner side of the body of the bone. The tongue should be pulled forward and over to the opposite side, when the nerve can be seen standing out as a firm cord under the mucous membrane by the side of the tongue, and after division of the mucous membrane can be easily seized with a hook and a portion excised. This is a simple enough operation on the cadaver, but when the disease is extensive and has extended to the floor of the mouth, as is generally the case when the division is required, the operation is not practicable.

In severe cases of neuralgia of the trigeminal nerve, the semilunar ganglion has been removed in whole or in part with a considerable measure of success. Rose was the first to perform this operation; and he reached the ganglion by trephining the base of the skull in the position of the foramen ovale, after dividing the zygomatic arch, in front and behind, and turning it and the Masseter downward, and cutting through the coronoid process of the mandible, and turning it and the Temporalis upward. A more efficient method appears to be that known as the Krause-Hartley method. The bone forming the temporal fossa having been removed to a sufficient extent, the dura mater beneath the temporal lobe of the brain is gradually raised from the middle fossa, until the foramen spinosum, with the middle meningeal artery passing through it, is exposed. This vessel is to be ligatured in two places, and divided between the ligatures; and then by further raising the dura mater, the foramina ovale and rotundum will be exposed, with the mandibular and maxillary nerves passing through them. These nerves are to be clearly defined and divided. The dura mater is then to be raised from the ganglion, when the ophthalmic nerve will be exposed and must be divided, and the ganglion, by means of a little careful dissection, raised from its bed and removed. In some cases where the neuralgia has been limited to the maxillary nerve an intracranial resection of that nerve alone has been performed with great success. In other cases where the disease has not affected the ophthalmic division, resection of the lateral half of the ganglion only, with the maxillary and mandibular nerves, has been performed, thus leaving the sensory nerve supply to the cornea intact. The motor root is usually resected with the mandibular nerve, leading to complete paralysis of the muscles of mastication on that side.

### THE ABDUCENT NERVE (N. ABDUCENS; SIXTH NERVE) (Fig. 778).

The abducent nerve supplies the Rectus lateralis oculi.

Its fibres arise from a small nucleus situated in the upper part of the rhomboid fossa, close to the middle line and beneath the colliculus facialis. They pass downward and forward through the pons, and emerge in the furrow between the lower border of the pons and the upper end of the pyramid of the medulla oblongata.

From the nucleus of the sixth nerve, fibres pass through the medial longitudinal fasciculus to the oculomotor nerve of the opposite side, along which they are carried to the Rectus medialis. The Rectus lateralis of one eye and the Rectus medialis of the other may therefore be said to receive their nerves from the same nucleus (Fig. 784).

The nerve pierces the dura mater on the dorsum sellae of the sphenoid, runs through a notch in the bone below the posterior clinoid process, and passes forward through the cavernous sinus, on the lateral side of the internal carotid artery. It enters the orbit through the superior orbital fissure, above the ophthalmic vein, from which it is separated by a lamina of dura mater. It then passes between the two heads of the Rectus lateralis, and enters the ocular surface of that muscle. The abducent nerve is joined by several filaments from the carotid and cavernous plexuses, and by one from the ophthalmic nerve. The oculomotor, trochlear, ophthalmic, and abducent nerves bear certain relations to each other in the cavernous sinus, at the superior orbital fissure, and in the cavity of the orbit, as follows:




FIG. 784.—Figure showing the mode of innervation of the Recti medialis and lateralis of the eye (after Duval and Laborde). (Testut.) a. Left eyeball. b. Right eyeball. 1. Rectus lateralis. 2. Rectus medialis. 3. Rhomboid fossa. 4. Nucleus of abducent nerve. 5. Nucleus of oculomotor nerve. 6. Abducent nerve. 7. Nerve to Rectus medialis arising from the nucleus of the oculomotor of the same side. 7'. Nerve to Rectus medialis arising from the nucleus of the abducent of the opposite side. 8. Decussation of the fibres of the abducent nerve to the Rectus medialis.

In the **cavernous sinus** (Fig. 785), the oculomotor, trochlear, and ophthalmic nerves are placed in the lateral wall of the sinus, in the order given, from above downward. The abducent nerve lies at the lateral side of the internal carotid artery. As these nerves pass forward to the superior orbital fissure, the oculo-




FIG. 785.—Oblique section through the right cavernous sinus.

motor and ophthalmic divide into branches, and the abducent nerve approaches the others; so that their relative positions are considerably changed.

In the **superior orbital fissure** (Fig. 786), the trochlear nerve and the frontal and lacrimal divisions of the ophthalmic lie in this order from the medial to the lateral side upon the same plane; they enter the cavity of the orbit above the muscles. The remaining nerves enter the orbit between the two heads of the Rectus lateralis. The superior division of

the oculomotor is the highest of these; beneath this lies the nasociliary branch of the ophthalmic; then the inferior division of the oculomotor; and the abducent lowest of all.




FIG. 786.—Dissection showing origins of right ocular muscles, and nerves entering by the superior orbital fissure.

In the **orbit**, the trochlear, frontal, and lacrimal nerves lie immediately beneath the periosteum, the trochlear nerve resting on the Obliquus superior, the frontal on the Levator palpebrae superioris, and the lacrimal on the Rectus lateralis. The superior division of the oculomotor nerve lies immediately beneath the Rectus superior, while the nasociliary nerve crosses the optic nerve to reach the medial wall of the orbit. Beneath these is the optic nerve, surrounded in front by the ciliary nerves, and having the ciliary ganglion on its lateral side, between it and the Rectus lateralis. Below the optic nerve are the inferior division of the oculomotor, and the abducent, the latter lying on the medial surface of the Rectus lateralis.

**Applied Anatomy.**—The abducent nerve is frequently involved in fractures of the base of the skull. The result of paralysis of this nerve is medial or convergent squint. Diplopia is also present. When injured so that its function is destroyed there is, in addition to the paralysis of the Rectus lateralis oculi, often a certain amount of contraction of the pupil, because some of the sympathetic fibres to the Dilator pupillae muscle are conveyed through this nerve.

### THE FACIAL NERVE (N. FACIALIS; SEVENTH NERVE) (Figs. 787, 789).

The facial nerve consists of a motor and a sensory part, the latter being frequently described under the name of the *nervus intermedius (pars intermedii of Wrisberg)* (Fig. 787). The two parts emerge at the lower border of the pons in the recess between the olive and the restiform body, the motor part being the more medial; immediately to the lateral side of the sensory part is the acoustic nerve.




FIG. 787.—Plan of the facial nerve. The course of the sensory fibres is represented by the blue lines.

The motor part supplies the muscles of the face, scalp, and auricular, the Buccinator and Platysma, the Stapedius, the Stylohyoideus, and posterior belly of the Digastricus; it also contains some fibres which constitute the vasodilator nerves of the submaxillary and sublingual glands, and are conveyed to these glands through the chorda tympani nerve. The sensory part contains the fibres of taste for the anterior two-thirds of the tongue.

The motor root arises from a nucleus which lies deeply in the reticular formation of the lower part of the pons. This nucleus is situated above the nucleus ambiguus, behind the superior olivary nucleus, and medial to the spinal tract of the trigeminal nerve. From this origin the fibres pursue a curved course in the substance

of the pons. They first pass backward and medialward toward the rhomboid fossa, and, reaching the posterior end of the nucleus of the abducent nerve, run upward close to the middle line beneath the colliculus fascialis. At the anterior end of the nucleus of the abducent nerve they make a second bend, and run downward and forward through the pons to their point of emergence between the olive and the restiform body.

Some fibres from the nucleus of the oculomotor nerve are said to descend in the medial longitudinal fasciculus and join the motor root of the facial nerve before it leaves the pons. These fibres are believed to supply the *Orbicularis oculi*, *Corrugator*, and *Frontalis*, since these muscles have been observed to escape paralysis in lesions of the motor nucleus of the facial nerve.<sup>1</sup>

The **sensory root** arises from the genicular ganglion, which is situated on the geniculum of the facial nerve in the facial canal, behind the hiatus of the canal. The cells of this ganglion are unipolar, and the single process divides in a T-shaped manner into central and peripheral branches. The central branches leave the trunk of the facial nerve in the internal acoustic meatus, and form the sensory root; the peripheral branches are continued into the chorda tympani and greater superficial petrosal nerves. Entering the brain at the lower border of the pons between the motor root and the acoustic nerve, the fibres of the sensory root pass into the substance of the medulla oblongata and end in the upper part of the terminal nucleus of the glossopharyngeal nerve and in the fasciculus solitarius.

From their superficial attachments to the brain, the two roots of the facial nerve pass lateralward and forward with the acoustic nerve to the internal acoustic meatus. In the meatus the motor root lies in a groove on the upper and anterior surface of the acoustic nerve, the sensory root being placed between them.

At the bottom of the meatus, the facial nerve enters the facial canal, which it traverses to its termination at the stylomastoid foramen. It is at first directed lateralward between the cochlea and vestibule toward the medial wall of the tympanic cavity; it then bends suddenly backward and arches downward behind the tympanic cavity to the stylomastoid foramen. The point where it changes its direction is named the **geniculum**; it presents a reddish gangliform swelling, the **genicular ganglion** (*ganglion geniculi*; *geniculate ganglion*; *nucleus of the sensory root*




FIG. 788.—The course and connections of the facial nerve in the temporal bone.

of the nerve) (Fig. 788). On emerging from the stylomastoid foramen, the facial nerve runs forward in the substance of the parotid gland, crosses the external carotid artery, and divides behind the ramus of the mandible into branches, from which numerous offsets are distributed over the side of the head, face, and upper part of the neck, supplying the superficial muscles in these regions. The branches and their offsets unite to form the **parotid plexus**.

**Branches of Communication.**—The branches of communication of the facial nerve may be arranged as follows:

<sup>1</sup> See footnote, p. 852.



In the internal acoustic meatus . . . . .	With the acoustic nerve.
At the genicular ganglion . . . . .	{ With the sphenopalatine ganglion by the greater superficial petrosal nerve. { With the otic ganglion by a branch which joins the lesser superficial petrosal nerve. { With the sympathetic on the middle meningeal artery.
In the facial canal . . . . .	With the auricular branch of the vagus.
At its exit from the stylo-mastoid foramen . . . . .	{ With the glossopharyngeal. { With the vagus. { With the great auricular. { With the auriculotemporal.
Behind the ear . . . . .	With the lesser occipital.
On the face . . . . .	With the trigeminal.
In the neck . . . . .	With the cutaneous cervical.

In the internal acoustic meatus some minute filaments pass from the facial to the acoustic nerve.

The **greater superficial petrosal nerve** (*large superficial petrosal nerve*) arises from the genicular ganglion, and consists chiefly of sensory branches which are distributed to the mucous membrane of the soft palate; but it probably contains a few motor fibres which form the motor root of the sphenopalatine ganglion. It passes forward through the hiatus of the facial canal, and runs in a sulcus on the anterior surface of the petrous portion of the temporal bone beneath the semilunar ganglion, to the foramen lacerum. It receives a twig from the tympanic plexus, and in the foramen is joined by the deep petrosal, from the sympathetic plexus on the internal carotid artery, to form the nerve of the pterygoid canal which passes forward through the pterygoid canal and ends in the sphenopalatine ganglion. The genicular ganglion is connected with the otic ganglion by a branch which joins the lesser superficial petrosal nerve, and also with the sympathetic filaments accompanying the middle meningeal artery. According to Arnold, a twig passes back from the ganglion to the acoustic nerve. Just before the facial nerve emerges from the stylomastoid foramen, it generally receives a twig from the auricular branch of the vagus.

After its exit from the stylomastoid foramen, the facial nerve sends a twig to the glossopharyngeal, and communicates with the auricular branch of the vagus, with the great auricular nerve of the cervical plexus, with the auriculotemporal nerve in the parotid gland, and with the lesser occipital behind the ear; on the face with the terminal branches of the trigeminal, and in the neck with the cutaneous cervical nerve.

**Branches of Distribution.**—The branches of distribution (Fig. 787) of the facial nerve may be thus arranged:

With the facial canal . . . . .	{ Nerve to the Stapedius muscle. { Chorda tympani.
At its exit from the stylo-mastoid foramen . . . . .	{ Posterior auricular. { Digastric. { Stylohyoid. { Temporal. { Zygomatic. { Buccal. { Mandibular. { Cervical.
On the face . . . . .	

The **Nerve to the Stapedius** (*n. stapedius*; *tympanic branch*) arises opposite the pyramidal eminence (page 1052); it passes through a small canal in this eminence to reach the muscle.

The **Chorda Tympani Nerve** is given off from the facial as it passes downward behind the tympanic cavity, about 6 mm. from the stylomastoid foramen. It runs upward and forward in a canal, and enters the tympanic cavity, through an aperture (*iter chordae posterius*) on its posterior wall, close to the medial surface of the posterior border of the tympanic membrane and on a level with the upper




FIG. 789.—The nerves of the scalp, face, and side of neck.

end of the manubrium of the malleus. It traverses the tympanic cavity, between the fibrous and mucous layers of the tympanic membrane, crosses the manubrium of the malleus, and emerges from the cavity through a foramen situated at the inner end of the petrotympanic fissure, and named the *iter chordae anterius* (*canal of Huguier*). It then descends between the Pterygoideus externus and internus on the medial surface of the spina angularis of the sphenoid, which it sometimes grooves, and joins, at an acute angle, the posterior border of the lingual nerve. It receives a few efferent fibres from the motor root; these enter the submaxillary ganglion, and through it are distributed to the submaxillary and sublingual glands;

the majority of its fibres are efferent, and are continued onward through the muscular substance of the tongue to the mucous membrane covering its anterior two-thirds; they constitute the nerve of taste for this portion of the tongue. Before uniting with the lingual nerve the chorda tympani is joined by a small branch from the otic ganglion.

The **Posterior Auricular Nerve** (*n. auricularis posterior*) arises close to the stylo-mastoid foramen, and runs upward in front of the mastoid process; here it is joined by a filament from the auricular branch of the vagus, and communicates with the posterior branch of the great auricular, and with the lesser occipital. As it ascends between the external acoustic meatus and mastoid process it divides into auricular and occipital branches. The **auricular branch** supplies the Auricularis posterior and the intrinsic muscles on the cranial surface of the auricula. The **occipital branch**, the larger, passes backward along the superior nuchal line of the occipital bone, and supplies the Occipitalis.

The **Digastric Branch** (*ramus digastricus*) arises close to the stylo-mastoid foramen, and divides into several filaments, which supply the posterior belly of the Digastricus; one of these filaments joins the glossopharyngeal nerve.

The **Stylohyoid Branch** (*ramus stylohyoideus*) frequently arises in conjunction with the digastric branch; it is long and slender, and enters the Stylohyoideus about its middle.

The **Temporal Branches** (*rami temporales*) cross the zygomatic arch to the temporal region, supplying the Auriculares anterior and superior, and joining with the zygomaticotemporal branch of the maxillary, and with the auriculotemporal branch of the mandibular. The more anterior branches supply the Frontalis, the Orbicularis oculi, and the Corrugator, and join the supraorbital and lacrimal branches of the ophthalmic.

The **Zygomatic Branches** (*rami zygomatici; malar branches*) run across the zygomatic bone to the lateral angle of the orbit, where they supply the Orbicularis oculi, and join with filaments from the lacrimal nerve and the zygomaticofacial branch of the maxillary nerve.

The **Buccal Branches** (*rami buccales; infraorbital branches*), of larger size than the rest, pass horizontally forward to be distributed below the orbit and around the mouth. The **superficial branches** run beneath the skin and above the superficial muscles of the face, which they supply: some are distributed to the Procerus, joining at the medial angle of the orbit with the infratrochlear and nasociliary branches of the ophthalmic. The **deep branches** pass beneath the Zygomaticus and the Quadratus labii superioris, supplying them and forming an **infraorbital plexus** with the infraorbital branch of the maxillary nerve. These branches also supply the small muscles of the nose. The lower deep branches supply the Buccinator and Orbicularis oris, and join with filaments of the buccinator branch of the mandibular nerve.

The **Mandibular Branch** (*ramus marginalis mandibulae*) passes forward beneath the Platysma and Triangularis, supplying the muscles of the lower lip and chin, and communicating with the mental branch of the inferior alveolar nerve.

The **Cervical Branch** (*ramus colli*) runs forward beneath the Platysma, and forms a series of arches across the side of the neck over the suprahyoid region. One branch descends to join the cervical cutaneous nerve from the cervical plexus; others supply the Platysma.

**Applied Anatomy.**—Facial palsy is commonly unilateral, and may be either: (1) *peripheral*, from lesion of the facial nerve; (2) *nuclear*, from destruction of the facial nucleus; or (3) *central, cerebral, or supranuclear*, from injury in the brain to the fibres passing from the cortex through the internal capsule to the facial nucleus, or from injury to the face area of the motor cortex itself. In supranuclear facial paralysis, which is usually part of a hemiplegia, it is the lower part of the face that is chiefly affected, while the forehead can be freely wrinkled on the palsied side, the eye can be closed fairly well, and the eyeball is not rolled up under the upper lid; emotional

movements of the face are much better executed than voluntary; and the electrical reactions of the muscles on the affected side are not altered. If the paralysis is due to lesion of the facial nucleus, the Orbicularis oris escapes, as the nuclear origin of the nerve to this muscle seems to be connected with that of the tongue nerves; otherwise the symptoms are identical with those of the common peripheral facial palsy, of which several types may be distinguished according to the point in its course at which the facial nerve is injured. If the lesion occurs (a) in the pons, facial paralysis is produced as in (d) below; taste and hearing are not affected, but the abducent nerve also will be paralyzed because the fibres of the facial nerve loop around its nucleus in the pons. When the nerve is paralyzed (b) in the petrous bone, in addition to the paralysis of the muscles of expression, there is loss of taste in the anterior part of the tongue, and the patient is unable to recognize the difference between bitters and sweets, acids and salines, from involvement of the chorda tympani. The mouth is dry, because the salivary glands are not secreting; and the sense of hearing is affected from paralysis of the Stapedius. When the cause of the paralysis is (c) fracture of the base of the skull, the acoustic and petrosal nerves are usually involved. But by far the commonest cause of facial palsy is (d) exposure of the nerve to cold or injury at or after its exit from the stylomastoid foramen (*Bell's paralysis*). In these cases the face looks asymmetrical even when at rest, and more so in the old than in the young. The affected side of the face and forehead remains motionless when voluntary or emotional movement is attempted. The lines on the forehead are smoothed out, the eye can be shut only by hand, tears fail to enter the lacrimal puncta because they are no longer in contact with the conjunctiva, the conjunctival reflex is absent, and efforts to close the eye merely cause the eyeball to roll upward until the cornea lies under the upper lid. The tip of the nose is drawn over toward the sound side; the nasolabial fold is partially obliterated on the affected side, and the ala nasi does not move properly on respiration. The lips remain in contact on the paralyzed side, and cannot be put together for whistling; when a smile is attempted the angle of the mouth is drawn up on the unaffected side; on the affected side the lips remain nearly closed, and the mouth assumes a characteristic triangular form. During mastication food accumulates in the cheek, from paralysis of the Buccinator, and dribbles or is pushed out from between the paralyzed lips. On protrusion the tongue seems to be thrust over toward the palsied side, but verification of its position by reference to the incisor teeth will show that this is not really so. The Platysma and the muscles of the auricula are paralyzed; in severe cases the articulation of labials is impaired. The electrical reactions of the affected muscles are altered (reaction of degeneration), and the degree to which this alteration has taken place after a week or ten days gives a valuable guide to the prognosis. Most cases of Bell's palsy recover completely.

The facial nerve is at fault in cases of so-called *histrionic spasm*, which consists in an almost constant and uncontrollable twitching of some or all of the muscles of the face. This twitching is sometimes so severe as to cause great discomfort and annoyance to the patient, and to interfere with sleep, and for its relief the facial nerve has been stretched. The operation is performed by making an incision behind the ear, from the root of the mastoid process to the angle of the mandible. The parotid is turned forward and the dissection carried along the anterior border of the Sternocleidomastoideus and mastoid process, until the upper border of the posterior belly of the Digastricus is found. The nerve is parallel to this on about the level of the middle of the mastoid process. When found, the nerve must be stretched by passing a blunt hook beneath it and pulling it forward and outward. Too great force must not be used, for fear of permanent injury to the nerve.

#### THE ACOUSTIC NERVE (N. ACUSTICUS; EIGHTH OR AUDITORY NERVE).

The **acoustic nerve**, or **nerve of hearing**, is distributed exclusively to the internal ear. It consists of two sets of fibres, which, although differing in their central connections, are both concerned in the transmission of afferent impulses from the internal ear to the medulla oblongata and pons, and from there, by means of fibres which arise from collections of gray substance in these structures, to the cerebrum and cerebellum. One set of fibres forms the vestibular root of the nerve, and *arises* from the cells in the vestibular ganglion situated in the internal acoustic meatus; the other set constitutes the cochlear root, and takes *origin* from the cells in the ganglion spirale, which occupies the spiral canal of the cochlea. Both of these ganglia consist of bipolar nerve cells; from each of the cells a central fibre passes to the brain, a peripheral fibre to the internal ear. At its connection with the brain the eighth nerve occupies the groove between the pons and medulla, lying behind the facial nerve and in front of the restiform body.

**Vestibular Root** (*radix vestibularis; vestibular nerve*) (Fig. 790).—The fibres of this root enter the medulla oblongata on the medial side of those of the cochlear root, and pass between the restiform body and the spinal tract of the trigeminal. They then divide into ascending and descending fibres. The latter end by arborizing around the cells of the **medial nucleus**, which is situated in the **area acustica** of the rhomboid fossa. The ascending fibres either end in the same manner or in the **lateral nucleus**, which is situated lateral to the area acustica and farther from the ventricular floor; the lateral nucleus consists of two parts, a medial, the **nucleus of Deiters**, and a lateral, the **nucleus of Bechterew**. Some of the axons of the cells of the lateral nucleus, and possibly also of the medial nucleus, are continued upward through the restiform body to the roof nuclei of the opposite side of the cerebellum, to which also other fibres of the vestibular root are prolonged without interruption in the nuclei of the medulla oblongata. A second set of fibres from the medial and lateral nuclei end partly in the tegmentum, while the remainder ascend in the medial longitudinal fasciculus to arborize around the cells of the nuclei of the oculomotor nerve.

**Cochlear Root** (*radix cochlearis; cochlear nerve*) (Fig. 791).—The cochlear root is placed lateral to the vestibular root. Its fibres end in two nuclei: one, the **accessory nucleus**, lies immediately in front of the restiform body; the other, the **tuberculum acusticum**, somewhat lateral to it.

The **striae medullares** (*striae acusticae*) are the axons of the cells of the tuberculum acusticum. They pass over the restiform body, and across the rhomboid fossa to the median sulcus. Here they dip into the substance of the pons, to end around the cells of the superior olivary nuclei of both sides. There are, however, other fibres, and these are both direct and crossed, which pass into the lateral lemniscus. The cells of the accessory nucleus give origin to fibres which run transversely in the pons and constitute the trapezium. Of the trapezoid fibres some end around the cells of the superior olivary nucleus or of the trapezoid nucleus of the same or opposite side, while others, crossed or uncrossed, pass directly into the lateral lemniscus.

If the further connections of the cochlear nerve of one side, say the left, be considered, it is found that they lie lateral to the main sensory tract, the lemniscus, and are therefore termed the **lateral lemniscus**. The fibres comprising the left lateral lemniscus arise in the superior olivary and trapezoid nuclei of the same or opposite side, while others are the uninterrupted fibres already alluded to, and these are either crossed or uncrossed, the former being the axons of the cells of the right accessory nucleus or of the cells of the right tuberculum acusticum, while the latter are derived from the cells of the left nuclei. In the upper part of the lateral lemniscus there is a collection of nerve cells, the **nucleus of the lateral lemniscus**, around the cells of which some of the fibres arborize and from the cells of which axons originate to continue upward the tract of the lateral lemniscus. The ultimate




FIG. 790.—Terminal nuclei of the vestibular root of the acoustic nerve, with their upper connections. (Schematic.) (Testut.) 1. Posterior or cochlear root, with its two nuclei. 2. Accessory nucleus. 3. Tuberculum acusticum. 4. Anterior or vestibular root. 5. Internal nucleus. 6. Nucleus of Deiters. 7. Nucleus of Bechterew. 8. Inferior or descending root of acoustic. 9. Ascending cerebellar fibres. 10. Fibres going to raphé. 11. Fibres taking an oblique course. 12. Lemniscus. 13. Inferior sensory root of trigeminal. 14. Cerebrospinal fasciculus. 15. Raphé. 16. Fourth ventricle. 17. Restiform body. 18. Origin of striae medullares.



ending of the left lateral lemniscus is partly in the opposite medial geniculate body, and partly in the inferior colliculi. From the cells of these bodies new fibres arise and ascend in the occipital part of the internal capsule to reach the posterior three-fifths of the left superior temporal gyrus and the transverse temporal gyri.

The acoustic nerve contains a few efferent fibres which *arise* in the quadrigeminal bodies, the nucleus of the lateral lemniscus, the superior olivary and trapezoid nuclei.




FIG. 791.—Terminal nuclei of the cochlear root of the acoustic nerve, with their upper connections. (Schematic.) (Testut.) The vestibular root with its terminal nuclei and their efferent fibres have been suppressed. On the other hand, in order not to obscure the trapezoid body, the efferent fibres of the terminal nuclei on the right side have been resected in a considerable portion of their extent. The trapezoid body, therefore, shows only one-half of its fibres, viz., those which come from the left. 1. Vestibular root of the acoustic, divided at its entrance into the medulla oblongata. 2. Cochlear root. 3. Accessory nucleus of acoustic nerve. 4. Tuberculum acusticum. 5. Efferent fibres of accessory nucleus. 6. Efferent fibres of tuberculum acusticum, forming the striae medullares, with 6', their direct bundle going to the superior olivary nucleus of the same side; 6'', their decussating bundles going to the superior olivary nucleus of the opposite side. 7. Superior olivary nucleus. 8. Trapezoid body. 9. Trapezoid nucleus. 10. Central acoustic tract (lateral lemniscus). 11. Raphe. 12. Cerebrosplinal fasciculus. 13. Fourth ventricle. 14. Restiform body.

The acoustic nerve is soft in texture, and destitute of neurilemma. After leaving the medulla oblongata it passes forward across the posterior border of the brachium pontis, in company with the facial nerve, from which it is partially separated by the internal auditory artery. It then enters the internal acoustic meatus with the facial nerve. At the bottom of the meatus it receives one or two filaments from the facial nerve, and then divides into its two branches, *cochlear* and *vestibular*, the distribution of which will be described with the anatomy of the internal ear.

**Applied Anatomy.**—The acoustic nerve is frequently injured, together with the facial nerve, in fracture of the middle fossa of the base of the skull implicating the internal acoustic meatus. The nerve may be either torn across, producing permanent deafness, or it may be bruised or pressed upon by extravasated blood or inflammatory exudation, when the deafness will in all probability be temporary. The nerve may also be injured by violent blows on the head without any fracture of the bones of the skull taking place, and deafness may arise from loud explosions from dynamite, etc., probably from some lesion of this nerve, which is more liable to be injured than the other cerebral nerves on account of its structure. "Nerve deafness" as contrasted with deafness due to changes in the middle ear or meatus, is suggested if (1) a sounding tuning fork placed on the middle line of the head is heard better (Weber's test) by the unaffected ear; or if (2) the sounding tuning fork is heard longer when held before the affected ear (= air conduction) than when it is stood on the corresponding mastoid (= bone conduction, Rinné's test); or if (3) the sounding tuning fork applied to the vertex or mastoid is heard less well when the air in the meatus is compressed by the use of a Siegle's speculum (Gellé's test); or if (4) the tuning fork placed on the mastoid is heard for a shorter time than its sound is perceptible to a normal individual (=evidence that bone conduction is diminished, Schwabach's test). It must be

remembered that all these tests are liable to anomalies and exceptions, and are not applicable to old people. If, however, concordant results are yielded by the tests of Weber, Rin  , and Gell  , Bezold's "triad of symptoms," nerve deafness rather than deafness due to disease of the conducting structures is rendered highly probable.

*Tinnitus aurium*, or the hearing of sounds in the ear that have no objective cause outside the body, is said to be present in as many as 60 per cent. of cases of ear disease of all sorts, and is commonest in disease of the labyrinth or of the nerve. It is very variable in intensity; the worst forms are purely subjective and due to irritation of the nerve itself. The sounds heard are of the most varied nature—buzzing, hissing, whistling, rushing, bell ringing, and so forth—and may occupy the patient's attention so completely that he is no longer able to attend to his business; he may even commit suicide in order to escape from them. In the insane, tinnitus is associated with delusions and hallucinations of hearing; cases of insanity have even been recorded in which cure was effected by the removal of cerumen impacted in the meatus and giving rise to persistent tinnitus.

### THE GLOSSOPHARYNGEAL NERVE (N. GLOSSOPHARYNGEUS; NINTH NERVE) (Figs. 792, 793, 794).

The **glossopharyngeal nerve** contains both motor and sensory fibres, and is distributed, as its name implies, to the tongue and pharynx. It is the nerve of ordinary sensation to the mucous membrane of the pharynx, fauces, and palatine tonsil, and the nerve of taste to the posterior part of the tongue. It is attached by three or four filaments to the upper part of the medulla oblongata, in the groove between the olive and the restiform body.

The **sensory fibres** arise from the cells of the superior and petrous ganglia, which are situated on the trunk of the nerve, and will be presently described. When traced into the medulla, some of the sensory fibres end by arborizing around the cells of the upper part of a nucleus which lies beneath the ala cinera in the lower part of the rhomboid fossa. Many of the fibres, however, contribute to form a strand, named the **fasciculus solitarius**, which descends in the medulla oblongata. Associated with this strand are numerous nerve cells, and around these the fibres of the fasciculus end.

The **motor fibres** spring from the cells of the **nucleus ambiguus**, which lies some distance from the surface of the rhomboid fossa in the lateral part of the medulla and is continuous below with the anterior gray column of the medulla spinalis. From this nucleus the fibres are first directed backward, and then they bend forward and lateralward to join the fibres of the sensory root. The nucleus ambiguus gives origin to the motor branches of the glossopharyngeal and vagus nerves, and to the cerebral part of the accessory nerve.




FIG. 792.—Plan of upper portions of glossopharyngeal, vagus, and accessory nerves.

From the medulla oblongata, the glossopharyngeal nerve passes lateralward across the flocculus, and leaves the skull through the central part of the jugular foramen, in a separate sheath of the dura mater, lateral to and in front of the vagus and accessory nerves (Fig. 793). In its passage through the jugular foramen, it grooves the lower border of the petrous part of the temporal bone; and, at its exit from the skull, passes forward between the internal jugular vein and internal carotid artery; it descends in front of the latter vessel, and beneath the styloid process and the muscles connected with it, to the lower border of the Stylopharyngeus. It then curves forward, forming an arch on the side of the neck and lying upon the Stylopharyngeus and Constrictor pharyngis medius. Thence it passes under cover of the Hyoglossus, and is finally distributed to the palatine tonsil, the mucous membrane of the fauces and base of the tongue, and the mucous glands of the mouth.




FIG. 793.—Upper part of medulla spinalis and hind- and mid-brains; posterior aspect, exposed in situ.

In passing through the jugular foramen, the nerve presents two ganglia, the **superior** and the **petrous** (Fig. 792).

The **superior ganglion** (*ganglion superius*; *jugular ganglion*) is situated in the upper part of the groove in which the nerve is lodged during its passage through the jugular foramen. It is very small, and is usually regarded as a detached portion of the petrous ganglion.

The **petrous ganglion** (*ganglion petrosum; inferior ganglion*) is larger than the superior and is situated in a depression in the lower border of the petrous portion of the temporal bone.

**Branches of Communication.**—

The glossopharyngeal nerve communicates with the **vagus**, **sympathetic**, and **facial**.

The branches to the vagus are two filaments which *arise* from the petrous ganglion, one passing to the auricular branch, and the other to the jugular ganglion, of the vagus. The petrous ganglion is connected by a filament with the superior cervical ganglion of the sympathetic. The branch of communication with the facial perforates the posterior belly of the Digastricus. It *arises* from the trunk of the glossopharyngeal below the petrous ganglion, and joins the facial just after the exit of that nerve from the stylomastoid foramen.

**Branches of Distribution.**—The branches of distribution of the glossopharyngeal are: the **tympanic**, **carotid**, **pharyngeal**, **muscular**, **tonsillar**, and **lingual**.

The **Tympanic Nerve** (*n. tympanicus; nerve of Jacobson*) arises from the petrous ganglion, and ascends to the tympanic cavity through a small canal on the under surface of the petrous portion of the temporal bone on the ridge which separates the carotid canal from the jugular fossa. In the tympanic cavity it divides into branches which form the **tympanic plexus** and are contained in grooves upon the surface of the promontory. This plexus gives off: (1) the lesser superficial petrosal nerve; (2) a branch to join the greater superficial petrosal nerve; and (3) branches to the tympanic cavity, all of which will be described in connection with the anatomy of the middle ear.

The **Carotid Branches** (*n. caroticotympanicus superior* and *n. caroticotympanicus inferior*) descend along the trunk of the internal carotid artery as far as its origin, communicating with the pharyngeal branch of the vagus, and with branches of the sympathetic.




FIG. 794.—Course and distribution of the glossopharyngeal, vagus, and accessory nerves.

The **Pharyngeal Branches** (*rami pharyngei*) are three or four filaments which unite, opposite the Constrictor pharyngis medius, with the pharyngeal branches of the vagus and sympathetic, to form the **pharyngeal plexus**; branches from this plexus perforate the muscular coat of the pharynx and supply its muscles and mucous membrane.

The **Muscular Branch** (*ramus stylopharyngeus*) is distributed to the Stylopharyngeus.

The **Tonsillar Branches** (*rami tonsillares*) supply the palatine tonsil, forming around it a plexus from which filaments are distributed to the soft palate and fauces, where they communicate with the palatine nerves.

The **Lingual Branches** (*rami linguales*) are two in number; one supplies the papillae vallatae and the mucous membrane covering the base of the tongue; the other supplies the mucous membrane and follicular glands of the posterior part of the tongue, and communicates with the lingual nerve.

### THE VAGUS NERVE (N. VAGUS; TENTH NERVE; PNEUMOGASTRIC NERVE) (Figs. 792, 793, 794).

The **vagus nerve** is composed of both motor and sensory fibres, and has a more extensive course and distribution than any of the other cerebral nerves, since it passes through the neck and thorax to the abdomen.

The vagus is attached by eight or ten filaments to the medulla oblongata in the groove between the olive and the restiform body, below the glossopharyngeal. The **sensory fibres** arise from the cells of the jugular ganglion and ganglion nodosum of the nerve, and, when traced into the medulla oblongata mostly end by arborizing around the cells of the inferior part of a nucleus which lie beneath the ala cinerea in the lower part of the rhomboid fossa. Some of the sensory fibres of the glossopharyngeal nerve have been seen to end in the upper part of this nucleus. A few of the sensory fibres of the vagus descend in the fasciculus solitarius and end around its cells. The **motor fibres** arise from the cells of the nucleus ambiguus, already referred to in connection with the motor root of the glossopharyngeal nerve (page 937).

The filaments of the nerve unite, and form a flat cord, which passes beneath the flocculus to the jugular foramen, through which it leaves the cranium. In emerging through this opening, the vagus is accompanied by and contained in the same sheath of dura mater with the accessory nerve, a septum separating them from the glossopharyngeal which lies in front (Fig. 793). In this situation the vagus presents a well-marked ganglionic enlargement, which is called the **jugular ganglion** (*ganglion of the root*); to it the accessory nerve is connected by one or two filaments. After its exit from the jugular foramen the vagus is joined by the cerebral portion of the accessory nerve, and enlarges into a second gangliiform swelling, called the **ganglion nodosum** (*ganglion of the trunk*); through this the fibres of the cerebral portion of the accessory pass without interruption, being principally distributed to the pharyngeal and superior laryngeal branches of the vagus, but some of its fibres descend in the trunk of the vagus, to be distributed with the recurrent nerve and probably also with the cardiac nerves.

The vagus nerve passes vertically down the neck within the carotid sheath, lying between the internal jugular vein and internal carotid artery as far as the upper border of the thyroid cartilage, and then between the same vein and the common carotid artery to the root of the neck. The further course of the nerve differs on the two sides of the body.

On the *right side*, the nerve passes across the subclavian artery between it and the right innominate vein, and descends by the side of the trachea to the back of



the root of the lung, where it spreads out in the **posterior pulmonary plexus**. From the lower part of this plexus two cords descend on the œsophagus, and divide to form, with branches from the opposite nerve, the **œsophageal plexus**. Below, these branches are collected into a single cord, which runs along the back of the œsophagus enters the abdomen, and is distributed to the postero-inferior surface of the stomach, joining the left side of the cœliac plexus, and sending filaments to the lienal plexus.

On the *left side*, the vagus enters the thorax between the left carotid and subclavian arteries, behind the left innominate vein. It crosses the left side of the arch of the aorta, and descends behind the root of the left lung, forming there the **posterior pulmonary plexus**. From this it runs along the anterior surface of the œsophagus, where it unites with the nerve of the right side in the **œsophageal plexus**, and is continued to the stomach, distributing branches over its antero-superior surface; some of these extend over the fundus, and others along the lesser curvature. Filaments from these branches enter the lesser omentum, and join the hepatic plexus.

The **jugular ganglion** (*ganglion jugulare; ganglion of the root*) is of a grayish color, spherical in form, about 4 mm. in diameter.

**Branches of Communication.**—This ganglion is connected by several delicate filaments to the cerebral portion of the accessory nerve; it also communicates by a twig with the petrous ganglion of the glossopharyngeal, with the facial nerve by means of its auricular branch, and with the sympathetic by means of an ascending filament from the superior cervical ganglion.

The **ganglion nodosum** (*ganglion of the trunk; inferior ganglion*) is cylindrical in form, of a reddish color, and 2.5 cm. in length. Passing through it is the cerebral portion of the accessory nerve, which blends with the vagus below the ganglion.

**Branches of Communication.**—This ganglion is connected with the hypoglossal, the superior cervical ganglion of the sympathetic, and the loop between the first and second cervical nerves.

**Branches of Distribution.**—The branches of distribution of the vagus are:

In the Jugular Fossa . . . . .	{ Meningeal. Auricular. Pharyngeal.
In the Neck . . . . .	{ Superior laryngeal. Recurrent. Superior cardiac.
In the Thorax . . . . .	{ Inferior cardiac. Anterior bronchial. Posterior bronchial. œsophageal.
In the Abdomen . . . . .	{ Gastric. Cœliac. Hepatic.

The **Meningeal Branch** (*ramus meningeus; dural branch*) is a recurrent filament given off from the jugular ganglion; it is distributed to the dura mater in the posterior fossa of the base of the skull.

The **Auricular Branch** (*ramus auricularis; nerve of Arnold*) arises from the jugular ganglion, and is joined soon after its origin by a filament from the petrous ganglion of the glossopharyngeal; it passes behind the internal jugular vein, and enters the mastoid canaliculus on the lateral wall of the jugular fossa. Traversing the substance of the temporal bone, it crosses the facial canal about 4 mm. above the stylo-mastoid foramen, and here it gives off an ascending branch which joins the facial nerve. The nerve reaches the surface by passing through the tympanomastoid fissure between the mastoid process and the tympanic part of the temporal bone,

and divides into two branches: one joins the posterior auricular nerve, the other is distributed to the skin of the back of the auricula and to the posterior part of the external acoustic meatus.

The **Pharyngeal Branch** (*ramus pharyngeus*), the principal motor nerve of the pharynx, *arises* from the upper part of the ganglion nodosum, and consists principally of filaments from the cerebral portion of the accessory nerve. It passes across the internal carotid artery to the upper border of the Constrictor pharyngis medius, where it divides into numerous filaments, which join with branches from the glossopharyngeal, sympathetic, and external laryngeal to form the **pharyngeal plexus**. From the plexus, branches are distributed to the muscles and mucous membrane of the pharynx and the muscles of the soft palate, except the Tensor veli palatini. A minute filament descends and joins the hypoglossal nerve as it winds around the occipital artery.

The **Superior Laryngeal Nerve** (*n. laryngeus superior*) larger than the preceding, *arises* from the middle of the ganglion nodosum and in its course receives a branch from the superior cervical ganglion of the sympathetic. It descends, by the side of the pharynx, behind the internal carotid artery, and divides into two branches, **external** and **internal**.

The **external branch** (*ramus externus*), the smaller, descends on the larynx, beneath the Sternothyreoideus, to supply the Cricothyreoideus. It gives branches to the pharyngeal plexus and the Constrictor pharyngis inferior, and communicates with the superior cardiac nerve, behind the common carotid artery.

The **internal branch** (*ramus internus*) descends to the hyothyroid membrane, pierces it in company with the superior laryngeal artery, and is distributed to the mucous membrane of the larynx. Of these branches some are distributed to the epiglottis, the base of the tongue, and the epiglottic glands; others pass backward, in the aryepiglottic fold, to supply the mucous membrane surrounding the entrance of the larynx, and that lining the cavity of the larynx as low down as the vocal folds. A filament descends beneath the mucous membrane on the inner surface of the thyroid cartilage and joins the recurrent nerve.

The **Recurrent Nerve** (*n. recurrens; inferior or recurrent laryngeal nerve*) *arises*, on the *right side*, in front of the subclavian artery; winds from before backward around that vessel, and ascends obliquely to the side of the trachea behind the common carotid artery, and either in front of or behind the inferior thyroid artery. On the *left side*, it *arises* on the left of the arch of the aorta, and winds below the aorta at the point where the ligamentum arteriosum is attached, and then ascends to the side of the trachea. The nerve on either side ascends in the groove between the trachea and œsophagus, passes under the lower border of the Constrictor pharyngis inferior, and enters the larynx behind the articulation of the inferior cornu of the thyroid cartilage with the cricoid; it is distributed to all the muscles of the larynx, excepting the Cricothyreoideus. It communicates with the internal branch of the superior laryngeal nerve, and gives off a few filaments to the mucous membrane of the lower part of the larynx.

As the recurrent nerve hooks around the subclavian artery or aorta, it gives off several cardiac filaments to the deep part of the cardiac plexus. As it ascends in the neck it gives off branches, more numerous on the left than on the right side, to the mucous membrane and muscular coat of the œsophagus; branches to the mucous membrane and muscular fibres of the trachea; and some pharyngeal filaments to the Constrictor pharyngis inferior.

The **Superior Cardiac Branches** (*rami cardiaci superiores; cervical cardiac branches*), two or three in number, *arise* from the vagus, at the upper and lower parts of the neck.

The **upper branches** are small, and communicate with the cardiac branches of the sympathetic. They can be traced to the deep part of the cardiac plexus.

The **lower branch** arises at the root of the neck, just above the first rib. That from the right vagus passes in front or by the side of the innominate artery, and proceeds to the deep part of the cardiac plexus; that from the left runs down across the left side of the arch of the aorta, and joins the superficial part of the cardiac plexus.

The **Inferior Cardiac Branches** (*rami cardiaci inferiores; thoracic cardiac branches*), on the right side, arise from the trunk of the vagus as it lies by the side of the trachea, and from its recurrent nerve; on the left side from the recurrent nerve only; passing inward, they end in the deep part of the cardiac plexus.

The **Anterior Bronchial Branches** (*rami bronchiales anteriores; anterior or ventral pulmonary branches*), two or three in number, and of small size, are distributed on the anterior surface of the root of the lung. They join with filaments from the sympathetic, and form the **anterior pulmonary plexus**.

The **Posterior Bronchial Branches** (*rami bronchiales posteriores; posterior or dorsal pulmonary branches*), more numerous and larger than the anterior, are distributed on the posterior surface of the root of the lung; they are joined by filaments from the third and fourth (sometimes also from the first and second) thoracic ganglia of the sympathetic trunk, and form the **posterior pulmonary plexus**. Branches from this plexus accompany the ramifications of the bronchi through the substance of the lung.

The **Œsophageal Branches** (*rami oesophagei*) are given off both above and below the bronchial branches; the lower are numerous and larger than the upper. They form, together with the branches from the opposite nerve, the **œsophageal plexus**. From this plexus filaments are distributed to the back of the pericardium.

The **Gastric Branches** (*rami gastrici*) are distributed to the stomach. The right vagus forms the **posterior gastric plexus** on the postero-inferior surface of the stomach and the left the **anterior gastric plexus** on the antero-superior surface.

The **Celiac Branches** (*rami coeliaci*) are mainly derived from the right vagus: they join the celiac plexus and through it supply branches to the pancreas, spleen, kidneys, suprarenal bodies, and intestine.

The **Hepatic Branches** (*rami hepatici*) arise from the left vagus: they join the hepatic plexus and through it are conveyed to the liver.

**Applied Anatomy.**—The trunk of the vagus is rarely injured, but the functions of the nerve may be interfered with by damage to its nucleus of origin in the medulla; by thickening or growth from the meninges or bones, or aneurism of the basilar artery, before its exit from the skull; injuries such as gunshot or punctured wounds in the neck, or injuries during such operations as ligature of the carotid artery, removal of tuberculous glands or other deep-seated tumors. The vagus may also be compressed by aneurisms of the carotid artery, and its deep origin becomes affected in bulbar paralysis. The symptoms produced by paralysis of the nerve are palpitation, with increased frequency of the pulse, constant vomiting, slowing of the respiration, and a sensation of suffocation.

"Reflexes" on the branches of the vagus are not at all uncommonly met with. The "ear cough" is perhaps one of the commonest, where a plug of wax in the acoustic meatus may by irritating the filaments of the auricular (Arnold's) nerve be responsible for a persistent cough. Syringing the external acoustic meatus frequently produces cough, and, in children, vomiting is not uncommon as the result of such a procedure; moreover, in people with weak hearts, syringing the ear has been responsible for a sudden fatal syncope, by reflex irritation of the cardiac branches. Another very common example is the persistent cough which is frequently due to enlarged bronchial glands in children, the irritation of which is referred to the superior laryngeal filaments.

The anatomy of the laryngeal nerves is of importance in considering some of the morbid conditions of the larynx. When the peripheral terminations of the superior laryngeal nerve are irritated by some foreign body passing over them, reflex spasm of the glottis is the result. When its trunk is pressed upon by, for instance, a goitre or an aneurism of the upper part of the carotid, there is a peculiar dry, brassy cough. When the nerve is paralyzed, there is anesthesia of the mucous membrane of the larynx, so that foreign bodies can readily enter the cavity, and, as the nerve also supplies the Cricothyreoideus muscle, the vocal folds cannot be made tense, and the voice is deep and hoarse. Paralysis may be the result of bulbar paralysis; may be a sequel to diphtheria, when both nerves are usually involved; or it may, though less commonly, be caused

by the pressure of tumors or aneurisms, when the paralysis is generally unilateral. Irritation of the recurrent nerves produces spasm of the muscles of the larynx. When both recurrent nerves are paralyzed, the vocal folds are motionless, in the so-called "cadaveric position"—that is to say, in the position in which they are found in ordinary tranquil respiration; neither closed as in phonation, nor open as in deep inspiratory efforts. When one recurrent nerve is paralyzed, the vocal fold of the same side is motionless, while the opposite one crosses the middle line to accommodate itself to the affected one; hence phonation is possible, but the voice is altered and weak in timbre. The nerves may be paralyzed in bulbar paralysis or after diphtheria, when the paralysis usually affects both sides; or they may be affected by the pressure of aneurisms of the aorta, innominate, or subclavian arteries; by mediastinal tumors; by gummata; or by cancer of the upper part of the œsophagus, when the paralysis is often unilateral. Paralysis of the adductor muscles of the larynx on both sides is quite common, and is usually functional in nature. The voice is reduced to a whisper, but the power of coughing is preserved.




FIG. 795.—Hypoglossal nerve, cervical plexus, and their branches.

**THE ACCESSORY NERVE (N. ACCESSORIUS; ELEVENTH NERVE; SPINAL ACCESSORY NERVE) (Figs. 793, 794, 795).**

The **accessory nerve** consists of two parts: a **cerebral** and a **spinal**.

The **cerebral part** (*ramus internus; accessory portion*) is the smaller of the two. Its fibres *arise* from the cells of the **nucleus ambiguus** and emerge as four or five delicate rootlets from the side of the medulla oblongata, below the roots of the vagus. It runs lateralward to the jugular foramen, where it interchanges fibres with the spinal portion or becomes united to it for a short distance; here it is also connected by one or two filaments with the jugular ganglion of the vagus. It

then passes through the jugular foramen, separates from the spinal portion and is continued over the surface of the ganglion nodosum of the vagus, to the surface of which it is adherent, and is distributed principally to the pharyngeal and superior laryngeal branches of the vagus. Through the pharyngeal branch it probably supplies the *Musculus uvulae* and *Levator veli palatini*. Some few filaments from it are continued into the trunk of the vagus below the ganglion, to be distributed with the recurrent nerve and probably also with the cardiac nerves.

The **spinal part** (*ramus externus; spinal portion*) is firm in texture, and its fibres arise from the motor cells in the lateral part of the anterior column of the gray substance of the medulla spinalis as low as the fifth cervical nerve. Passing through the lateral funiculus of the medulla spinalis, they emerge on its surface and unite to form a single trunk, which ascends between the *ligamentum denticulatum* and the posterior roots of the spinal nerves, enters the skull through the foramen magnum, and is then directed to the jugular foramen, through which it passes, lying in the same sheath of *dura mater* as the vagus, but separated from it by a fold of the arachnoid. In the jugular foramen, it receives one or two filaments from the cerebral part of the nerve, or else joins it for a short distance and then separates from it again. At its exit from the jugular foramen, it runs backward in front of the internal jugular vein in 66.6 per cent. of cases, and behind in it 33.3 per cent. (Tandler). The nerve then descends obliquely behind the *Digastricus* and *Stylohyoideus* to the upper part of the *Sternocleidomastoideus*; it pierces this muscle, and courses obliquely across the posterior triangle of the neck, to end in the deep surface of the *Trapezius*. As it traverses the *Sternocleidomastoideus* it gives several filaments to the muscle, and joins with branches from the second cervical nerve. In the posterior triangle it unites with the second and third cervical nerves, while beneath the *Trapezius* it forms a plexus with the third and fourth cervical nerves, and from this plexus fibres are distributed to the muscle.

**Applied Anatomy.**—The functions of the accessory nerve may be interfered with either by central changes; or at its exit from the skull, by fractures running across the jugular foramen; or in the neck, by inflamed lymph glands, etc. The acute wry-neck in children is most commonly due to inflamed or suppurating glands, and rapidly subsides with appropriate treatment. Central irritation causes clonic spasm of the *Sternocleidomastoideus* and *Trapezius* muscles, or, as it is termed, spasmodic torticollis. In cases of this affection in which all previous palliative treatment has failed, and the spasms are so severe as to undermine the patient's health, division or excision of a portion of the accessory nerve has been resorted to. This must be done from the anterior border of the *Sternocleidomastoideus*. The operation consists in making an incision, 8 cm. in length, from the apex of the mastoid process along the anterior border of the muscle, which is defined and pulled backward, so as to stretch the nerve, which is then to be sought for beneath the *Digastricus*, about 5 cm. below the apex of the mastoid process. Unfortunately, the operation does not yield a satisfactory or permanent cure, as the spasms tend to recur after an interval, either in the same muscles or in other groups of neck muscles.

In cases where extensive dissections are undertaken for enlarged glands in the neck, it is essential that this nerve should be at once sought for and isolated from the mass of inflamed glands so as to maintain its continuity.

### THE HYPOGLOSSAL NERVE (N. HYPOGLOSSUS; TWELFTH NERVE) (Figs. 795, 796).

The **hypoglossal nerve** is the motor nerve of the tongue.

Its fibres arise from the cells of the **hypoglossal nucleus**, which is an upward prolongation of the base of the anterior column of gray substance of the medulla spinalis. This nucleus is about 2 cm. in length, and its upper part corresponds with the **trigonum hypoglossi**, or lower portion of the medial eminence of the rhomboid fossa (page 848). The lower part of the nucleus extends downward into the closed part of the medulla oblongata, and there lies in relation to the ventro-lateral aspect of the central canal. The fibres run forward through the medulla oblongata, and emerge in the antero-lateral sulcus between the pyramid and the olive.



The rootlets of this nerve are collected into two bundles, which perforate the dura mater separately, opposite the hypoglossal canal in the occipital bone, and unite together after their passage through it; in some cases the canal is divided into two by a small bony spicule. The nerve descends almost vertically to a point corresponding with the angle of the mandible. It is at first deeply seated beneath the internal carotid artery and internal jugular vein, and intimately connected with the vagus nerve; it then passes forward between the vein and artery, and lower down in the neck becomes superficial below the Digastricus. The nerve then loops




FIG. 796.—Plan of hypoglossal nerve.

around the occipital artery, and crosses the external carotid and lingual arteries below the tendon of the Digastricus. It passes beneath the tendon of the Digastricus, the Stylohyoideus, and the Mylohyoideus, lying between the last-named muscle and the Hyoglossus, and communicates at the anterior border of the Hyoglossus with the lingual nerve; it is then continued forward in the fibres of the Genioglossus as far as the tip of the tongue, distributing branches to its muscular substance.

**Branches of Communication.**—Its branches of communication are, with the

Vagus.

First and second cervical nerves.

Sympathetic.

Lingual.

The communications with the vagus take place close to the skull, numerous filaments passing between the hypoglossal and the ganglion nodosum of the vagus

through the mass of connective tissue which unites the two nerves. As the nerve winds around the occipital artery it gives off a filament to the pharyngeal plexus.

The communication with the sympathetic takes place opposite the atlas by branches derived from the superior cervical ganglion, and in the same situation the nerve is joined by a filament derived from the loop connecting the first and second cervical nerves.

The communications with the lingual take place near the anterior border of the Hyoglossus by numerous filaments which ascend upon the muscle.

**Branches of Distribution.**—The branches of distribution of the hypoglossal nerve are.

Meningeal.  
Descending.

Thyrothyroid.  
Muscular.

Of these branches, the meningeal, descending, thyrothyroid, and the muscular twig to the Geniohyoideus, are probably derived mainly from the branch which passes from the loop between the first and second cervical to join the hypoglossal (Fig. 726).

**Meningeal Branches** *dural branches*.—As the hypoglossal nerve passes through the hypoglossal canal it gives off, according to Luschka, several filaments to the dura mater in the posterior fossa of the skull.

The **Descending Ramus** *ramus descendens; descendens hypoglossi*, long and slender, quits the hypoglossal where it turns around the occipital artery and descends in front of or in the sheath of the carotid vessels; it gives a branch to the superior belly of the Omohyoideus, and then joins the communicantes cervicales from the second and third cervical nerves; just below the middle of the neck, to form a loop, the **ansa hypoglossi**. From the convexity of this loop branches pass to supply the Sternohyoideus, the Sternothyreoideus, and the inferior belly of the Omohyoideus. According to Arnold, another filament descends in front of the vessels into the thorax, and joins the cardiac and phrenic nerves.

The **Thyrothyroid Branch** (*ramus thyreochoideus*) arises from the hypoglossal near the posterior border of the hyoglossus; it runs obliquely across the greater cornu of the hyoid bone, and supplies the Thyreochoideus muscle.

The **Muscular Branches** are distributed to the Styloglossus, Hyoglossus, Geniohyoideus, and Genioglossus. At the under surface of the tongue numerous slender branches pass upward into the substance of the organ to supply its intrinsic muscles.

**Applied Anatomy.**—The hypoglossal nerve is an important guide in the operation of ligature of the lingual artery (see p. 632). It runs forward on the Hyoglossus just above the greater cornu of the hyoid bone, and forms the upper boundary of the triangular space in which the artery is to be sought for by cutting through the fibres of the Hyoglossus. In cases where the nerve is involved by gumma or new growth of the base of the skull, or where it has been injured on one side of the neck, or in some cases of bulbar paralysis, unilateral paralysis, together with hemiatrophy of the tongue, results; the tongue, when protruded, being directed to the paralyzed side owing to the unopposed action of the Genioglossus of the opposite side. On retraction, the wasted and paralyzed side of the tongue rises up higher than the other. The larynx may deviate toward the sound side on swallowing, from the unilateral paralysis of the depressors of the hyoid bone. If the paralysis is bilateral, the tongue lies motionless in the mouth, while articulation and mastication are much interfered with.

## THE SPINAL NERVES (NERVI SPINALES).

The **spinal nerves** spring from the medulla spinalis, and are transmitted through the intervertebral foramina. They number thirty-one pairs, which are grouped as follows: Cervical, 8; Thoracic, 12; Lumbar, 5; Sacral, 5; Coccygeal, 1.

The **first cervical nerve** emerges from the vertebral canal between the occipital bone and the atlas, and is therefore called the **suboccipital nerve**; the eighth issues between the seventh cervical and first thoracic vertebrae.

**Nerve Roots.**—Each nerve is attached to the medulla spinalis by two roots, an **anterior** or **ventral**, and a **posterior** or **dorsal**, the latter being characterized by the presence of a ganglion, the **spinal ganglion**.

The **Anterior Root** (*radix anterior; ventral root*) emerges from the anterior surface of the medulla spinalis as a number of rootlets or filaments (*fila radicularia*), which coalesce to form two bundles near the intervertebral foramen.

The **Posterior Root** (*radix posterior; dorsal root*) is larger than the anterior owing to the greater size and number of its rootlets; these are attached along the posterolateral furrow of the medulla spinalis and unite to form two bundles which join the spinal ganglion. The posterior root of the first cervical nerve is exceptional in that it is smaller than the anterior; it is occasionally wanting.




FIG. 797.—Distribution of cutaneous nerves.

The **Spinal Ganglia** (*ganglion spinale*) are collections of nerve cells on the posterior roots of the spinal nerves. Each ganglion is oval in shape, reddish in color, and its size bears a proportion to that of the nerve root on which it is situated; it is bifid medially where it is joined by the two bundles of the posterior nerve root.

The ganglia are usually placed in the intervertebral foramina, immediately outside the points where the nerve roots perforate the dura mater, but there are exceptions to this rule; thus the ganglia of the first and second cervical nerves lie on the vertebral arches of the atlas and axis respectively, those of the sacral nerves are inside the vertebral canal, while that on the posterior root of the coccygeal nerve is placed within the sheath of dura mater.

**Structure** (Fig. 679).—The ganglia consist chiefly of unipolar nerve cells, and from these the fibres of the posterior root take origin—the single process of each cell dividing after a short course into a central fibre which enters the medulla spinalis and a peripheral fibre which runs into the spinal nerve. Two other forms of cells are, however, present, viz.: (a) the cells of Dogiel, whose axons ramify close to the cell (type II, of Golgi), and are distributed entirely within the ganglion; and (b) multipolar cells similar to those found in the sympathetic ganglia.

The ganglia of the first cervical nerve may be absent, while small *aberrant ganglia* consisting of groups of nerve cells are sometimes found on the posterior roots between the spinal ganglia and the medulla spinalis.

Each nerve root receives a covering from the pia mater, and is loosely invested by the arachnoid, the latter being prolonged as far as the points where the roots pierce the dura mater. The two roots pierce the dura mater separately, each receiving a sheath from this membrane; where the roots join to form the spinal nerve this sheath is continuous with the epineurium of the nerve.

**Size and Direction.**—The roots of the upper four *cervical* nerves are small, those of the lower four are large. The posterior roots of the cervical nerves bear a proportion to the anterior of three to one, which is greater than in the other regions; their individual filaments are also larger than those of the anterior roots. The posterior root of the first cervical is an exception to this rule, being smaller than the anterior root; in eight per cent. of cases it is wanting. The roots of the first and second cervical nerves are short, and run nearly horizontally to their points of exit from the vertebral canal. From the second to the eighth cervical they are directed obliquely downward, the obliquity and length of the roots successively increasing; the distance, however, between the level of attachment of any of these roots to the medulla spinalis and the points of exit of the corresponding nerves never exceeds the depth of one vertebra.

The roots of the *thoracic* nerves, with the exception of the first, are of small size, and the posterior only slightly exceed the anterior in thickness. They increase successively in length, from above downward, and in the lower part of the thoracic region descend in contact with the medulla spinalis for a distance equal to the height of at least two vertebræ before they emerge from the vertebral canal.

The roots of the lower *lumbar* and upper *sacral* nerves are the largest, and their individual filaments the most numerous of all the spinal nerves, while the roots of the *coccygeal* nerve are the smallest.

The roots of the lumbar, sacral, and coccygeal nerves run vertically downward to their respective exits, and as the medulla spinalis ends near the lower border of the first lumbar vertebra it follows that the length of the successive roots must rapidly increase. As already mentioned (page 806), the term *cauda equina* is applied to this collection of nerve roots.

From the description given it will be seen that the largest nerve roots, and consequently the largest spinal nerves, are attached to the cervical and lumbar swellings of the medulla spinalis; these nerves are distributed to the upper and lower limbs.

**Connections with Sympathetic.**—Immediately beyond the spinal ganglion, the anterior and posterior nerve roots unite to form the **spinal nerve** which emerges through the intervertebral foramen. Each spinal nerve receives a branch (**gray ramus communicans**) from the adjacent ganglion of the sympathetic trunk, while the thoracic, and the first and second lumbar nerves each contribute a branch

(white ramus communicans) to the adjoining sympathetic ganglion. The second, third, and fourth sacral nerves also supply white rami; these, however, are not connected with the ganglia of the sympathetic trunk, but run directly into the pelvic plexuses of the sympathetic.

**Structure.**—Each typical spinal nerve contains fibres belonging to two systems, viz., the **somatic**, and the **sympathetic** or **splanchnic**, as well as fibres connecting these systems with each other (Fig. 798).

1. The **somatic fibres** are efferent and afferent. The *efferent fibres* originate in the cells of the anterior column of the medulla spinalis, and run outward through the anterior nerve roots to the spinal nerve. They convey impulses to the voluntary muscles, and are continuous from their origin to their peripheral distribution. The *afferent fibres* convey impressions inward from the skin, etc., and originate in the unipolar nerve cells of the spinal ganglia. The single processes of these cells divide into peripheral and central fibres, and the latter enter the medulla spinalis through the posterior nerve roots.




FIG. 798.—Scheme showing structure of a typical spinal nerve. 1. Somatic efferent. 2. Somatic afferent. 3, 4, 5. Splanchnic efferent. 6, 7. Splanchnic afferent.

2. The **sympathetic fibres** are also efferent and afferent. The *efferent fibres* originate in the lateral column of the medulla spinalis, and are conveyed through the anterior nerve root and the white ramus communicans to the corresponding ganglion of the sympathetic trunk; here they may end by forming synapses around its cells, or may run through the ganglion to end in another of the ganglia of the sympathetic trunk, or in a more distally placed ganglion in one of the sympathetic plexuses. In all cases they end by forming synapses around other nerve cells. From the cells of the ganglia of the sympathetic trunk other fibres take origin; some of these run through the gray rami communicantes to join the spinal nerves, along which they are carried to the blood-vessels of the trunk and limbs, while others pass to the viscera, either directly or after interruption in one of the distal ganglia. The *afferent fibres* are derived partly from the unipolar cells and partly from the multipolar cells of the spinal ganglia. Their peripheral processes are carried through the white rami communicantes, and after passing through one or more sympathetic ganglia (but always without interruption in them) finally end in the tissues of the viscera. The central processes of the unipolar cells enter the medulla spinalis through the posterior nerve root and form synapses around either somatic or sympathetic efferent neurons, thus completing reflex arcs. The dendrites of the multipolar nerve cells form synapses around the cells of type II (cells of Dogiel) in the spinal ganglia, and by this path the original impulse is transferred from the sympathetic to the somatic system, through which it is conveyed to the sensorium.



**Divisions.**—After emerging from the intervertebral foramen, each spinal nerve gives off a small **meningeal branch** which reënters the vertebral canal through the intervertebral foramen and supplies the vertebræ and their ligaments, and the bloodvessels of the medulla spinalis and its membranes. The spinal nerve then splits into a **posterior** or **dorsal**, and an **anterior** or **ventral division**, each receiving fibres from both nerve roots.

#### POSTERIOR DIVISIONS OF THE SPINAL NERVES (RAMI POSTERIORES).

The **posterior divisions** are as a rule smaller than the anterior. They are directed backward, and, with the exceptions of those of the first cervical, the fourth and fifth sacral, and the coccygeal, divide into medial and lateral branches for the supply of the muscles and skin (Figs. 799, 800) of the posterior part of the trunk.

#### The Cervical Nerves (Nn. Cervicales).

The **posterior division of the first cervical or suboccipital nerve** is larger than the anterior division, and emerges above the posterior arch of the atlas and beneath the vertebral artery. It enters the suboccipital triangle and supplies the muscles which bound this triangle, viz., the Rectus capitis posterior major, and the Obliqui superior and inferior; it gives branches also to the Rectus capitis posterior minor and the Semispinalis capitis. A filament from the branch to the Obliquus inferior joins the posterior division of the second cervical nerve.

The nerve occasionally gives off a cutaneous branch which accompanies the occipital artery to the scalp, and communicates with the greater and lesser occipital nerves.

The **posterior division of the second cervical nerve** is much larger than the anterior division, and is the greatest of all the cervical posterior divisions. It emerges between the posterior arch of the atlas and the lamina of the axis, below the Obliquus inferior. It supplies a twig to this muscle, receives a communicating filament from the posterior division of the first cervical, and then divides into a large medial and a small lateral branch.

The **medial branch** (*ramus medialis; internal branch*), called from its size and distribution the **greater occipital nerve** (*n. occipitalis major; great occipital nerve*), ascends obliquely between the Obliquus inferior and the Semispinalis capitis, and pierces the latter muscle and the Trapezius near their attachments to the occipital bone (Fig. 799). It is then joined by a filament from the medial branch of the posterior division of the third cervical, and, ascending on the back of the head with the occipital artery, divides into branches which communicate with the lesser occipital nerve and supply the skin of the scalp as far forward as the vertex of the skull. It gives off muscular branches to the Semispinalis capitis, and occasionally a twig to the back of the auricula. The **lateral branch** (*ramus lateralis; external branch*) supplies filaments to the Splenius, Longus capitis, and Semispinalis capitis, and is often joined by the corresponding branch of the third cervical.

The **posterior division of the third cervical** is intermediate in size between those of the second and fourth. Its **medial branch** runs between the Semispinalis capitis and cervicis, and, piercing the Splenius and Trapezius, ends in the skin. While under the Trapezius it gives off a branch called the **third occipital nerve**, which pierces the Trapezius and ends in the skin of the lower part of the back of the head (Fig. 799). It lies medial to the greater occipital and communicates with it. The **lateral branch** often joins that of the second cervical.

The posterior division of the suboccipital, and the medial branches of the posterior division of the second and third cervical nerves are sometimes joined by communicating loops to form the **posterior cervical plexus** (Cruveilhier).

The **posterior divisions of the lower five cervical nerves** divide into medial and lateral branches. The **medial branches** of the fourth and fifth run between the

Semispinales cervicis and capitis, and, having reached the spinous processes, pierce the Splenius and Trapezius to end in the skin (Fig. 799). Sometimes the branch of the fifth fails to reach the skin. Those of the lower three nerves are small, and end in the Semispinales cervicis and capitis, Multifidus, and Inter-spinales. The **lateral branches** of the lower five nerves supply the Iliocostalis cervicis, Longissimus cervicis, and Longissimus capitis.




FIG. 799.—Diagram of the distribution of the cutaneous branches of the posterior divisions of the spinal nerves.




FIG. 800.—Areas of distribution of the cutaneous branches of the posterior divisions of the spinal nerves. (H. M. Johnston.) The areas of the medial branches are in black, those of the lateral in red.

### The Thoracic Nerves (Nn. Thoracales).

The **medial branches** (*ramus medialis; internal branch*) of the **posterior divisions of the upper six thoracic nerves** run between the Semispinalis dorsi and Multifidus, which they supply; they then pierce the Rhomboidei and Trapezius, and reach the skin by the sides of the spinous processes (Fig. 799). The medial branches



The rootlets of this nerve are collected into two bundles, which perforate the dura mater separately, opposite the hypoglossal canal in the occipital bone, and unite together after their passage through it; in some cases the canal is divided into two by a small bony spicule. The nerve descends almost vertically to a point corresponding with the angle of the mandible. It is at first deeply seated beneath the internal carotid artery and internal jugular vein, and intimately connected with the vagus nerve; it then passes forward between the vein and artery, and lower down in the neck becomes superficial below the Digastricus. The nerve then loops




FIG. 796.—Plan of hypoglossal nerve.

around the occipital artery, and crosses the external carotid and lingual arteries below the tendon of the Digastricus. It passes beneath the tendon of the Digastricus, the Stylohyoideus, and the Mylohyoideus, lying between the last-named muscle and the Hyoglossus, and communicates at the anterior border of the Hyoglossus with the lingual nerve; it is then continued forward in the fibres of the Genioglossus as far as the tip of the tongue, distributing branches to its muscular substance.

**Branches of Communication.**—Its branches of communication are, with the

Vagus.

Sympathetic.

First and second cervical nerves.

Lingual.

The communications with the vagus take place close to the skull, numerous filaments passing between the hypoglossal and the ganglion nodosum of the vagus

through the mass of connective tissue which unites the two nerves. As the nerve winds around the occipital artery it gives off a filament to the pharyngeal plexus.

The communication with the sympathetic takes place opposite the atlas by branches derived from the superior cervical ganglion, and in the same situation the nerve is joined by a filament derived from the loop connecting the first and second cervical nerves.

The communications with the lingual take place near the anterior border of the Hyoglossus by numerous filaments which ascend upon the muscle.

**Branches of Distribution.**—The branches of distribution of the hypoglossal nerve are:

Meningeal.  
Descending.

Thyrohyoid.  
Muscular.

Of these branches, the meningeal, descending, thyrohyoid, and the muscular twig to the Geniohyoideus, are probably derived mainly from the branch which passes from the loop between the first and second cervical to join the hypoglossal (Fig. 796).

**Meningeal Branches** (*dural branches*).—As the hypoglossal nerve passes through the hypoglossal canal it gives off, according to Luschka, several filaments to the dura mater in the posterior fossa of the skull.

The **Descending Ramus** (*ramus descendens; descendens hypoglossi*), long and slender, quits the hypoglossal where it turns around the occipital artery and descends in front of or in the sheath of the carotid vessels; it gives a branch to the superior belly of the Omohyoideus, and then joins the communicantes cervicales from the second and third cervical nerves; just below the middle of the neck, to form a loop, the *ansa hypoglossi*. From the convexity of this loop branches pass to supply the Sternohyoideus, the Sternothyreoideus, and the inferior belly of the Omohyoideus. According to Arnold, another filament descends in front of the vessels into the thorax, and joins the cardiac and phrenic nerves.

The **Thyrohyoid Branch** (*ramus thyrohyoideus*) arises from the hypoglossal near the posterior border of the hyoglossus; it runs obliquely across the greater cornu of the hyoid bone, and supplies the Thyrohyoideus muscle.

The **Muscular Branches** are distributed to the Styloglossus, Hyoglossus, Geniohyoideus, and Genioglossus. At the under surface of the tongue numerous slender branches pass upward into the substance of the organ to supply its intrinsic muscles.

**Applied Anatomy.**—The hypoglossal nerve is an important guide in the operation of ligature of the lingual artery (see p. 632). It runs forward on the Hyoglossus just above the greater cornu of the hyoid bone, and forms the upper boundary of the triangular space in which the artery is to be sought for by cutting through the fibres of the Hyoglossus. In cases where the nerve is involved by gumma or new growth of the base of the skull, or where it has been injured on one side of the neck, or in some cases of bulbar paralysis, unilateral paralysis, together with hemiatrophy of the tongue, results; the tongue, when protruded, being directed to the paralyzed side owing to the unopposed action of the Genioglossus of the opposite side. On retraction, the wasted and paralyzed side of the tongue rises up higher than the other. The larynx may deviate toward the sound side on swallowing, from the unilateral paralysis of the depressors of the hyoid bone. If the paralysis is bilateral, the tongue lies motionless in the mouth, while articulation and mastication are much interfered with.

## THE SPINAL NERVES (NERVI SPINALES).

The **spinal nerves** spring from the medulla spinalis, and are transmitted through the intervertebral foramina. They number thirty-one pairs, which are grouped as follows: Cervical, 8; Thoracic, 12; Lumbar, 5; Sacral, 5; Coccygeal, 1.

The **first cervical nerve** emerges from the vertebral canal between the occipital bone and the atlas, and is therefore called the **suboccipital nerve**; the eighth issues between the seventh cervical and first thoracic vertebræ.



**Nerve Roots.**—Each nerve is attached to the medulla spinalis by two roots, an **anterior** or **ventral**, and a **posterior** or **dorsal**, the latter being characterized by the presence of a ganglion, the **spinal ganglion**.

The **Anterior Root** (*radix anterior; ventral root*) emerges from the anterior surface of the medulla spinalis as a number of rootlets or filaments (*fila radicularia*), which coalesce to form two bundles near the intervertebral foramen.

The **Posterior Root** (*radix posterior; dorsal root*) is larger than the anterior owing to the greater size and number of its rootlets; these are attached along the posterolateral furrow of the medulla spinalis and unite to form two bundles which join the spinal ganglion. The posterior root of the first cervical nerve is exceptional in that it is smaller than the anterior; it is occasionally wanting.




FIG. 797.—Distribution of cutaneous nerves.

The **Spinal Ganglia** (*ganglion spinale*) are collections of nerve cells on the posterior roots of the spinal nerves. Each ganglion is oval in shape, reddish in color, and its size bears a proportion to that of the nerve root on which it is situated; it is bifid medially where it is joined by the two bundles of the posterior nerve root.

The ganglia are usually placed in the intervertebral foramina, immediately outside the points where the nerve roots perforate the dura mater, but there are exceptions to this rule; thus the ganglia of the first and second cervical nerves lie on the vertebral arches of the atlas and axis respectively, those of the sacral nerves are inside the vertebral canal, while that on the posterior root of the coccygeal nerve is placed within the sheath of dura mater.

**Structure** (Fig. 679).—The ganglia consist chiefly of unipolar nerve cells, and from these the fibres of the posterior root take origin—the single process of each cell dividing after a short course into a central fibre which enters the medulla spinalis and a peripheral fibre which runs into the spinal nerve. Two other forms of cells are, however, present, viz.: (a) the cells of Dogiel, whose axons ramify close to the cell (type II, of Golgi), and are distributed entirely within the ganglion; and (b) multipolar cells similar to those found in the sympathetic ganglia.

The ganglia of the first cervical nerve may be absent, while small *aberrant ganglia* consisting of groups of nerve cells are sometimes found on the posterior roots between the spinal ganglia and the medulla spinalis.

Each nerve root receives a covering from the pia mater, and is loosely invested by the arachnoid, the latter being prolonged as far as the points where the roots pierce the dura mater. The two roots pierce the dura mater separately, each receiving a sheath from this membrane; where the roots join to form the spinal nerve this sheath is continuous with the epineurium of the nerve.

**Size and Direction.**—The roots of the upper four *cervical* nerves are small, those of the lower four are large. The posterior roots of the cervical nerves bear a proportion to the anterior of three to one, which is greater than in the other regions; their individual filaments are also larger than those of the anterior roots. The posterior root of the first cervical is an exception to this rule, being smaller than the anterior root; in eight per cent. of cases it is wanting. The roots of the first and second cervical nerves are short, and run nearly horizontally to their points of exit from the vertebral canal. From the second to the eighth cervical they are directed obliquely downward, the obliquity and length of the roots successively increasing; the distance, however, between the level of attachment of any of these roots to the medulla spinalis and the points of exit of the corresponding nerves never exceeds the depth of one vertebra.

The roots of the *thoracic* nerves, with the exception of the first, are of small size, and the posterior only slightly exceed the anterior in thickness. They increase successively in length, from above downward, and in the lower part of the thoracic region descend in contact with the medulla spinalis for a distance equal to the height of at least two vertebræ before they emerge from the vertebral canal.

The roots of the lower *lumbar* and upper *sacral* nerves are the largest, and their individual filaments the most numerous of all the spinal nerves, while the roots of the *coccygeal* nerve are the smallest.

The roots of the lumbar, sacral, and coccygeal nerves run vertically downward to their respective exits, and as the medulla spinalis ends near the lower border of the first lumbar vertebra it follows that the length of the successive roots must rapidly increase. As already mentioned (page 806), the term *cauda equina* is applied to this collection of nerve roots.

From the description given it will be seen that the largest nerve roots, and consequently the largest spinal nerves, are attached to the cervical and lumbar swellings of the medulla spinalis; these nerves are distributed to the upper and lower limbs.

**Connections with Sympathetic.**—Immediately beyond the spinal ganglion, the anterior and posterior nerve roots unite to form the **spinal nerve** which emerges through the intervertebral foramen. Each spinal nerve receives a branch (**gray ramus communicans**) from the adjacent ganglion of the sympathetic trunk, while the thoracic, and the first and second lumbar nerves each contribute a branch

(white ramus communicans) to the adjoining sympathetic ganglion. The second, third, and fourth sacral nerves also supply white rami; these, however, are not connected with the ganglia of the sympathetic trunk, but run directly into the pelvic plexuses of the sympathetic.

**Structure.**—Each typical spinal nerve contains fibres belonging to two systems, viz., the **somatic**, and the **sympathetic** or **splanchnic**, as well as fibres connecting these systems with each other (Fig. 798).

1. The **somatic fibres** are efferent and afferent. The *efferent fibres* originate in the cells of the anterior column of the medulla spinalis, and run outward through the anterior nerve roots to the spinal nerve. They convey impulses to the voluntary muscles, and are continuous from their origin to their peripheral distribution. The *afferent fibres* convey impressions inward from the skin, etc., and originate in the unipolar nerve cells of the spinal ganglia. The single processes of these cells divide into peripheral and central fibres, and the latter enter the medulla spinalis through the posterior nerve roots.




FIG. 798.—Scheme showing structure of a typical spinal nerve. 1. Somatic efferent. 2. Somatic afferent. 3, 4, 5. Splanchnic efferent. 6, 7. Splanchnic afferent.

2. The **sympathetic fibres** are also efferent and afferent. The *efferent fibres* originate in the lateral column of the medulla spinalis, and are conveyed through the anterior nerve root and the white ramus communicans to the corresponding ganglion of the sympathetic trunk; here they may end by forming synapses around its cells, or may run through the ganglion to end in another of the ganglia of the sympathetic trunk, or in a more distally placed ganglion in one of the sympathetic plexuses. In all cases they end by forming synapses around other nerve cells. From the cells of the ganglia of the sympathetic trunk other fibres take origin; some of these run through the gray rami communicantes to join the spinal nerves, along which they are carried to the blood-vessels of the trunk and limbs, while others pass to the viscera, either directly or after interruption in one of the distal ganglia. The *afferent fibres* are derived partly from the unipolar cells and partly from the multipolar cells of the spinal ganglia. Their peripheral processes are carried through the white rami communicantes, and after passing through one or more sympathetic ganglia (but always without interruption in them) finally end in the tissues of the viscera. The central processes of the unipolar cells enter the medulla spinalis through the posterior nerve root and form synapses around either somatic or sympathetic efferent neurons, thus completing reflex arcs. The dendrites of the multipolar nerve cells form synapses around the cells of type II (cells of Dogiel) in the spinal ganglia, and by this path the original impulse is transferred from the sympathetic to the somatic system, through which it is conveyed to the sensorium.

**Divisions.**—After emerging from the intervertebral foramen, each spinal nerve gives off a small **meningeal branch** which reënters the vertebral canal through the intervertebral foramen and supplies the vertebræ and their ligaments, and the bloodvessels of the medulla spinalis and its membranes. The spinal nerve then splits into a **posterior or dorsal**, and an **anterior or ventral division**, each receiving fibres from both nerve roots.

#### POSTERIOR DIVISIONS OF THE SPINAL NERVES (RAMI POSTERIORES).

The **posterior divisions** are as a rule smaller than the anterior. They are directed backward, and, with the exceptions of those of the first cervical, the fourth and fifth sacral, and the coccygeal, divide into medial and lateral branches for the supply of the muscles and skin (Figs. 799, 800) of the posterior part of the trunk.

#### The Cervical Nerves (Nn. Cervicales).

The **posterior division of the first cervical or suboccipital nerve** is larger than the anterior division, and emerges above the posterior arch of the atlas and beneath the vertebral artery. It enters the suboccipital triangle and supplies the muscles which bound this triangle, viz., the Rectus capitis posterior major, and the Obliqui superior and inferior; it gives branches also to the Rectus capitis posterior minor and the Semispinalis capitis. A filament from the branch to the Obliquus inferior joins the posterior division of the second cervical nerve.

The nerve occasionally gives off a cutaneous branch which accompanies the occipital artery to the scalp, and communicates with the greater and lesser occipital nerves.

The **posterior division of the second cervical nerve** is much larger than the anterior division, and is the greatest of all the cervical posterior divisions. It emerges between the posterior arch of the atlas and the lamina of the axis, below the Obliquus inferior. It supplies a twig to this muscle, receives a communicating filament from the posterior division of the first cervical, and then divides into a large medial and a small lateral branch.

The **medial branch** (*ramus medialis; internal branch*), called from its size and distribution the **greater occipital nerve** (*n. occipitalis major; great occipital nerve*), ascends obliquely between the Obliquus inferior and the Semispinalis capitis, and pierces the latter muscle and the Trapezius near their attachments to the occipital bone (Fig. 799). It is then joined by a filament from the medial branch of the posterior division of the third cervical, and, ascending on the back of the head with the occipital artery, divides into branches which communicate with the lesser occipital nerve and supply the skin of the scalp as far forward as the vertex of the skull. It gives off muscular branches to the Semispinalis capitis, and occasionally a twig to the back of the auricula. The **lateral branch** (*ramus lateralis; external branch*) supplies filaments to the Splenius, Longus capitis, and Semispinalis capitis, and is often joined by the corresponding branch of the third cervical.

The **posterior division of the third cervical** is intermediate in size between those of the second and fourth. Its **medial branch** runs between the Semispinalis capitis and cervicis, and, piercing the Splenius and Trapezius, ends in the skin. While under the Trapezius it gives off a branch called the **third occipital nerve**, which pierces the Trapezius and ends in the skin of the lower part of the back of the head (Fig. 799). It lies medial to the greater occipital and communicates with it. The **lateral branch** often joins that of the second cervical.

The posterior division of the suboccipital, and the medial branches of the posterior division of the second and third cervical nerves are sometimes joined by communicating loops to form the **posterior cervical plexus** (Cruveilhier).

The **posterior divisions of the lower five cervical nerves** divide into medial and lateral branches. The **medial branches** of the fourth and fifth run between the

Semispinales cervicis and capitis, and, having reached the spinous processes, pierce the Splenius and Trapezius to end in the skin (Fig. 799). Sometimes the branch of the fifth fails to reach the skin. Those of the lower three nerves are small, and end in the Semispinales cervicis and capitis, Multifidus, and Interspinales. The **lateral branches** of the lower five nerves supply the Iliocostalis cervicis, Longissimus cervicis, and Longissimus capitis.




FIG. 799.—Diagram of the distribution of the cutaneous branches of the posterior divisions of the spinal nerves.




FIG. 800.—Areas of distribution of the cutaneous branches of the posterior divisions of the spinal nerves. (H. M. Johnston.) The areas of the medial branches are in black, those of the lateral in red.

### The Thoracic Nerves (Nn. Thoracales).

The **medial branches** (*ramus medialis; internal branch*) of the **posterior divisions of the upper six thoracic nerves** run between the Semispinalis dorsi and Multifidus, which they supply; they then pierce the Rhomboidei and Trapezius, and reach the skin by the sides of the spinous processes (Fig. 799). The medial branches



of the **lower six** are distributed chiefly to the Multifidus and Longissimus dorsi; occasionally they give off filaments to the skin near the middle line.

The **lateral branches** (*ramus lateralis; external branch*) increase in size from above downward. They run through or beneath the Longissimus dorsi to the interval between it and the Iliocostales, and supply these muscles; the lower five or six also give off cutaneous branches which pierce the Serratus posterior inferior and Latissimus dorsi in a line with the angles of the ribs (Fig. 799). The lateral branches of a variable number of the upper thoracic nerves also give filaments to the skin. The lateral branch of the twelfth thoracic, after sending a filament medialward along the iliac crest, passes downward to the skin of the buttock.

The medial cutaneous branches of the posterior divisions of the thoracic nerves descend for some distance close to the spinous processes before reaching the skin, while the lateral branches travel downward for a considerable distance—it may be as much as the breadth of four ribs—before they become superficial; the branch from the twelfth thoracic, for instance, reaches the skin only a little way above the iliac crest.<sup>1</sup>

### The Lumbar Nerves (Nn. Lumbales).

The **medial branches** of the posterior divisions of the lumbar nerves run close to the articular processes of the vertebræ and end in the Multifidus.

The **lateral branches** supply the Sacrospinalis. The upper three give off cutaneous nerves which pierce the aponeurosis of the Latissimus dorsi at the lateral border of the Sacrospinalis and descend across the posterior part of the iliac crest to the skin of the buttock (Fig. 799), some of their twigs running as far as the level of the greater trochanter.




FIG. 801.—The posterior divisions of the sacral nerves.

### The Sacral Nerves (Nn. Sacrales).

The **posterior divisions of the sacral nerves** (*rami posteriores*) (Fig. 801) are small, and diminish in size from above downward; they emerge, except the last,

<sup>1</sup> See article by H. M. Johnston, *Journal of Anatomy and Physiology*, vol. xliii.

through the posterior sacral foramina. The *upper three* are covered at their points of exit by the Multifidus, and divide into medial and lateral branches.

The **medial branches** are small, and end in the Multifidus.

The **lateral branches** join with one another and with the lateral branches of the posterior divisions of the last lumbar and fourth sacral to form loops on the dorsal surface of the sacrum. From these loops branches run to the dorsal surface of the sacrotuberous ligament and form a second series of loops under the Glutaeus maximus. From this second series cutaneous branches, two or three in number, pierce the Glutaeus maximus along a line drawn from the posterior superior iliac spine to the tip of the coccyx; they supply the skin over the posterior part of the buttock.

The posterior divisions of the *lower two* sacral nerves are small and lie below the Multifidus. They do not divide into medial and lateral branches, but unite with each other and with the posterior division of the coccygeal nerve to form loops on the back of the sacrum; filaments from these loops supply the skin over the coccyx.

#### **The Coccygeal Nerve (N. Coccygeus).**

The **posterior division of the coccygeal nerve** (*ramus posterior*) does not divide into a medial and a lateral branch, but receives, as already stated, a communicating branch from the last sacral; it is distributed to the skin over the back of the coccyx.

#### **ANTERIOR DIVISIONS OF THE SPINAL NERVES (RAMI ANTERIORES).**

The **anterior divisions of the spinal nerves** supply the antero-lateral parts of the trunk, and the limbs; they are for the most part larger than the posterior divisions. In the thoracic region they run independently of one another, but in the cervical, lumbar, and sacral regions they unite near their origins to form plexuses.

#### **The Cervical Nerves (Nn. Cervicales).**

The anterior divisions of the cervical nerves (*rami anteriores*), with the exception of the first, pass outward between the Intertransversarii anterior and posterior, lying on the grooved upper surfaces of the transverse processes of the vertebræ. The **anterior division of the first or suboccipital nerve** issues from the vertebral canal above the posterior arch of the atlas and runs forward around the lateral aspect of its superior articular process, medial to the vertebral artery. In most cases it descends medial to and in front of the Rectus capitis lateralis, but occasionally it pierces the muscle.

The anterior divisions of the **upper four cervical nerves** unite to form the **cervical plexus**, and each receives a gray ramus communicans from the superior cervical ganglion of the sympathetic trunk. Those of the **lower four cervical**, together with the greater part of the first thoracic, form the **brachial plexus**. They each receive a gray ramus communicans, those for the fifth and sixth being derived from the middle, and those for the seventh and eighth from the lowest, cervical ganglion of the sympathetic trunk.

**The Cervical Plexus** (*plexus cervicalis*) (Fig. 802).—The cervical plexus is formed by the anterior divisions of the upper four cervical nerves; each nerve, except the first, divides into an upper and a lower branch, and the branches unite to form three loops. The plexus is situated opposite the upper four cervical vertebræ, in front of the Levator scapulae and Scalenus medius, and covered by the Sternocleidomastoideus.

Its branches are divided into two groups, **superficial and deep**, and are here given in tabular form; the figures following the names indicate the nerves from which the different branches take origin:

<i>Superficial</i>	{	Smaller occipital . . . . .	2, C.				
		Great auricular . . . . .	2, 3, C.				
		Cutaneous cervical . . . . .	2, 3, C.				
		Supraclavicular . . . . .	3, 4, C.				
<i>Deep</i>	{	Internal	{	Communicating	{	With hypoglossal . . . . .	1, 2, C.
					" vagus . . . . .	1, 2, C.	
					" sympathetic . . . . .	1, 2, 3, 4, C.	
		Muscular . . . . .		Rectus capitis lateralis . . . . .	1, C.		
				Rectus capitis anterior . . . . .	1, 2, C.		
				Longus capitis . . . . .	1, 2, 3, C.		
	{	Communicating with	{	Communicantes cervi- cales . . . . .	2, 3, C.		
					Phrenic . . . . .	3, 4, 5, C.	
					accessory . . . . .	2, 3, 4, C.	
		External	{	Sternocleidomastoideus . . . . .	2, C.		
				Trapezius . . . . .	3, 4, C.		
				Levator scapulæ . . . . .	3, 4, C.		
				Scalenus medius . . . . .	3, 4, C.		




FIG. 802.—Plan of cervical plexus.

**Superficial Branches of the Cervical Plexus** (Fig. 803).—The **Smaller Occipital Nerve** (*n. occipitalis minor*; *small occipital nerve*) arises from the second cervical nerve, sometimes also from the third; it curves around and ascends along the posterior border of the Sternocleidomastoideus. Near the cranium it perforates the deep fascia, and is continued upward along the side of the head behind the auricula, supplying the skin and communicating with the greater occipital, the great auricular, and the posterior auricular branch of the facial. The smaller occipital varies in size, and is sometimes duplicated.




FIG. 803.—The nerves of the scalp, face, and side of neck.

It gives off an **auricular branch**, which supplies the skin of the upper and back part of the auricula, communicating with the mastoid branch of the great auricular. This branch is occasionally derived from the greater occipital nerve.

The **Great Auricular Nerve** (*n. auricularis magnus*) is the largest of the ascending branches. It arises from the second and third cervical nerves, winds around the posterior border of the Sternocleidomastoideus, and, after perforating the deep fascia, ascends upon that muscle beneath the Platysma to the parotid gland, where it divides into an anterior and a posterior branch.

The **anterior branch** (*ramus anterior*; *facial branch*) is distributed to the skin of the face over the parotid gland, and communicates in the substance of the gland with the facial nerve.

The **posterior branch** (*ramus posterior; mastoid branch*) supplies the skin over the mastoid process and on the back of the auricula, except at its upper part; a filament pierces the auricula to reach its lateral surface, where it is distributed to the lobule and lower part of the concha. The posterior branch communicates with the smaller occipital, the auricular branch of the vagus, and the posterior auricular branch of the facial.

The **Cutaneous Cervical** (*n. cutaneus colli; superficial or transverse cervical nerve*) arises from the second and third cervical nerves, turns around the posterior border of the Sternocleidomastoideus about its middle, and, passing obliquely forward beneath the external jugular vein to the anterior border of the muscle, it perforates the deep cervical fascia, and divides beneath the Platysma into ascending and descending branches, which are distributed to the antero-lateral parts of the neck.

The **ascending branches** (*rami superiores*) pass upward to the submaxillary region, and form a plexus with the cervical branch of the facial nerve beneath the Platysma; others pierce that muscle, and are distributed to the skin of the upper and front part of the neck.

The **descending branches** (*rami inferiores*) pierce the Platysma, and are distributed to the skin of the side and front of the neck, as low as the sternum.

The **Supraclavicular Nerves** (*nn. supraclaviculares; descending branches*) arise from the third and fourth cervical nerves; they emerge beneath the posterior border of the Sternocleidomastoideus, and descend in the posterior triangle of the neck beneath the Platysma and deep cervical fascia. Near the clavicle they perforate the fascia and Platysma to become cutaneous, and are arranged, according to their position, into three groups—**anterior, middle and posterior**.

The **anterior supraclavicular nerves** (*nn. supraclaviculares anteriores; suprasternal nerves*) cross obliquely over the external jugular vein and the clavicular and sternal heads of the Sternocleidomastoideus, and supply the skin as far as the middle line. They furnish one or two filaments to the sternoclavicular joint.

The **middle supraclavicular nerves** (*nn. supraclaviculares medii; supraclavicular nerves*) cross the clavicle, and supply the skin over the Pectoralis major and Deltoideus, communicating with the cutaneous branches of the upper intercostal nerves.

The **posterior supraclavicular nerves** (*nn. supraclaviculares posteriores; supra-acromial nerves*) pass obliquely across the outer surface of the Trapezius and the acromion, and supply the skin of the upper and posterior parts of the shoulder.

**Deep Branches of the Cervicle Plexus.** INTERNAL SERIES.—The **Communicating Branches** consist of several filaments, which pass from the loop between the first and second cervical nerves to the vagus, hypoglossal, and sympathetic. The branch to the hypoglossal ultimately leaves that nerve as a series of branches, viz., the descending ramus, the nerve to the Thyreo-hyoideus and the nerve, to the Genio-hyoideus (see page 947). A communicating branch also passes from the fourth to the fifth cervical, while each of the first four cervical nerves receives a gray ramus communicans from the superior cervical ganglion of the sympathetic.

**Muscular Branches** supply the Longus capitis, Rectus capitis anterior, and Rectus capitis lateralis.

The **Communicantes Cervicales** (*communicantes hypoglossi*) (Fig. 802) consist usually of two filaments, one derived from the second, and the other from the third cervical. These filaments join to form the **descendens cervicalis**, which passes downward on the lateral side of the internal jugular vein, crosses in front of the vein a little below the middle of the neck, and forms a loop (**ansa hypoglossi**) with the descending ramus of the hypoglossal in front of the sheath of the carotid vessels (see page 947). Occasionally, the loop is formed within the sheath.

The **Phrenic Nerve** (*n. phrenicus; internal respiratory nerve of Bell*) contains motor and sensory fibres in the proportion of about two to one. It arises chiefly from the



fourth cervical nerve, but receives a branch from the third and another from the fifth; the fibres from the fifth occasionally come through the nerve to the Subclavius. It descends to the root of the neck, running obliquely across the front of the Scalenus anterior, and beneath the Sternocleidomastoideus, the inferior belly of the Omohyoideus, and the transverse cervical and transverse scapular vessels. It next passes in front of the first part of the subclavian artery, between it and the subclavian vein, and, as it enters the thorax, crosses the internal mammary artery near its origin. Within the thorax, it descends nearly vertically in front of the root of the lung, and then between the pericardium and the mediastinal pleura, to the Diaphragma, where it divides into branches, which pierce that muscle, and are distributed to its under surface. In the thorax it is accompanied by the pericardiophrenic branch of the internal mammary artery.

The two phrenic nerves differ in their length, and also in their relations at the upper part of the thorax.

The **right nerve** is situated more deeply, and is shorter and more vertical in direction than the left; it lies lateral to the right innominate vein and superior vena cava.

The **left nerve** is rather longer than the right, from the inclination of the heart to the left side, and from the Diaphragma being lower on this than on the right side. At the root of the neck it is crossed by the thoracic duct; in the superior mediastinal cavity it lies between the left common carotid and left subclavian arteries, and crosses superficial to the vagus on the left side of the arch of the aorta.

Each nerve supplies filaments to the pericardium and pleura, and at the root of the neck is joined by a filament from the sympathetic, and, occasionally, by one from the ansa hypoglossi. Branches have been described as passing to the peritoneum.

From the *right nerve*, one or two filaments pass to join in a small **phrenic ganglion** with phrenic branches of the celiac plexus; and branches from this ganglion are distributed to the falciform and coronary ligaments of the liver, the suprarenal gland, inferior vena cava, and right atrium. From the *left nerve*, filaments pass to join the phrenic branches of the celiac plexus, but without any ganglionic enlargement; and a twig is distributed to the left suprarenal gland.

**Deep Branches of the Cervical Plexus.** **EXTERNAL SERIES.**—**Communicating Branches.**—The external series of deep branches of the cervical plexus communicates with the accessory nerve, in the substance of the Sternocleidomastoideus, in the posterior triangle, and beneath the Trapezius.

**Muscular Branches** are distributed to the Sternocleidomastoideus, Trapezius, Levator scapulae, and Scalenus medius.

The branch for the Sternocleidomastoideus is derived from the second cervical; the Trapezius and Levator scapulae receive branches from the third and fourth. The Scalenus medius receives twigs either from the third or fourth, or occasionally from both.

**Applied Anatomy.**—Pains referred to the terminal branches of the cervical plexus are not uncommon in caries of the cervical vertebræ, where pain may be felt radiating over the occipital bone, if the disease is situated high up in the vertebral column.

**The Brachial Plexus** (*plexus brachialis*) (Fig. 804).—The brachial plexus is formed by the union of the anterior divisions of the lower four cervical nerves and the greater part of the anterior division of the first thoracic nerve; the fourth cervical usually gives a branch to the fifth cervical, and the first thoracic frequently receives one from the second thoracic. The plexus extends from the lower part of the side of the neck to the axilla. The nerves which form it are nearly equal in size, but their mode of communication is subject to some variation. The following

is, however, the most constant arrangement. The fifth and sixth cervical unite soon after their exit from the intervertebral foramina to form a trunk. The eighth cervical and first thoracic also unite to form one trunk, while the seventh cervical runs out alone. Three trunks—upper, middle, and lower—are thus formed, and, as they pass beneath the clavicle, each splits into an **anterior** and a **posterior division**.<sup>1</sup> The anterior divisions of the upper and middle trunks unite to form a cord, which is situated on the lateral side of the second part of the axillary artery, and is called the **lateral cord or fasciculus of the plexus**. The anterior division of the lower trunk passes down on the medial side of the axillary artery, and forms the **medial cord or fasciculus of the brachial plexus**. The posterior divisions of all three trunks unite to form the **posterior cord or fasciculus of the plexus**, which is situated behind the second portion of the axillary artery.




FIG. 804.—Plan of brachial plexus.

**Relations.**—*In the neck*, the brachial plexus lies in the posterior triangle, being covered by the skin, Platysma, and deep fascia; it is crossed by the supraclavicular nerves, the inferior belly of the Omohyoideus, the external jugular vein, and the transverse cervical artery. It emerges between the Scaleni anterior and medius; its upper part lies above the third part of the subclavian artery, while the trunk formed by the union of the eighth cervical and first thoracic is placed behind the artery; the plexus next passes behind the clavicle, the Subclavius, and the transverse scapular vessels, and lies upon the first digitation of the Serratus anterior, and the Subscapularis. *In the axilla* it is placed lateral to the first portion of the axillary artery; it surrounds the second part of the artery, one cord lying medial to it, one lateral to it, and one behind it; at the lower part of the axilla it gives off its terminal branches to the upper limb.

<sup>1</sup> The posterior division of the lower trunk is very much smaller than the others, and is frequently derived entirely from the eighth cervical nerve.

**Branches of Communication.**—Close to their exit from the intervertebral foramina the fifth and sixth cervical nerves each receive a gray ramus communicans from the middle cervical ganglion of the sympathetic trunk, and the seventh and eighth cervical similar twigs from the inferior ganglion. The first thoracic nerve receives a gray ramus from, and contributes a white ramus to, the first thoracic ganglion. On the Scalenus anterior the phrenic nerve is joined by a branch from the fifth cervical.

**Branches of Distribution.**—The branches of distribution of the brachial plexus may be arranged into two groups, viz., those given off above and those below the clavicle.

#### SUPRACLAVICULAR BRANCHES.

Dorsal scapular . . . . .	5 C.
Suprascapular . . . . .	5, 6 C.
Nerve to Subclavius . . . . .	5, 6 C.
Long thoracic . . . . .	5, 6, 7 C.
To Longus colli and Scaleni . . . . .	5, 6, 7, 8 C.

The **Dorsal Scapular Nerve** (*n. dorsalis scapulae*; *nerve to the Rhomboidei*; *posterior scapular nerve*) arises from the fifth cervical, pierces the Scalenus medius, passes beneath the Levator scapulae, to which it occasionally gives a twig, and ends in the Rhomboidei.

The **Suprascapular** (*n. suprascapularis*) (Fig. 810) arises from the trunk formed by the union of the fifth and sixth cervical nerves. It runs lateralward beneath the Trapezius and the Omohyoideus, and enters the supraspinatous fossa through the suprascapular notch, below, the superior transverse scapular ligament; it then passes beneath the Supraspinatus, and curves around the lateral border of the spine of the scapula to the infraspinatous fossa. In the supraspinatous fossa it gives off two branches to the Supraspinatus muscle, and an articular filament to the shoulder-joint; and in the infraspinatous fossa it gives off two branches to the Infraspinatus muscle, besides some filaments to the shoulder-joint and scapula.

The **Nerve to the Subclavius** (*n. subclavius*) is a small filament, which arises from the point of junction of the fifth and sixth cervical nerves; it descends to the muscle in front of the third part of the subclavian artery and the lower trunk of the plexus, and is usually connected by a filament with the phrenic nerve.

The **Long Thoracic Nerve** (*n. thoracalis longus*; *external respiratory nerve of Bell*; *posterior thoracic nerve*) (Fig. 809) supplies the Serratus anterior. It usually arises by three roots from the fifth, sixth, and seventh cervical nerves; but the root from the seventh nerve may be absent. The roots from the fifth and sixth nerves pierce the Scalenus medius, while that from the seventh passes in front of the muscle. The nerve descends behind the brachial plexus and the axillary vessels, resting on the outer surface of the Serratus anterior. It extends along the side of the thorax to the lower border of that muscle, supplying filaments to each of its digitations.

The branches for the Longus colli and Scaleni arise from the lower four cervical nerves at their exit from the intervertebral foramina.

#### INFRACLAVICULAR BRANCHES.

The infraclavicular branches are derived from the three cords of the brachial plexus, but the fasciculi of the nerves may be traced through the plexus to the spinal nerves from which they originate. They are as follows:

Lateral cord .	{	Musculocutaneous . . . . .	5, 6, 7 C.
		Lateral anterior thoracic . . . . .	5, 6, 7 C.
		Lateral head of median . . . . .	6, 7 C.
Medial cord .	{	Medial anterior thoracic . . . . .	} 8 C, 1 T.
		Medial antibrachial cutaneous . . . . .	
		Medial brachial cutaneous . . . . .	
		Ulnar . . . . .	
Posterior cord .	{	Medial head of median . . . . .	} 8 C, 1 T.
		Upper subscapular . . . . .	5, 6 C.
		Lower subscapular . . . . .	5, 6 C.
		Thoracodorsal . . . . .	5, 6, 7 C.
		Axillary . . . . .	5, 6 C.
		Radial . . . . .	6, 7, 8 C, 1 T.

The **Anterior Thoracic Nerves** (*nn. thoracales anteriores*) (Fig. 809) supply the Pectorales major and minor.

The **lateral anterior thoracic** (*fasciculus lateralis*) the larger of the two, *arises* from the lateral cord of the brachial plexus, and through it from the fifth, sixth, and seventh cervical nerves. It passes across the axillary artery and vein, pierces the coracoclavicular fascia, and is distributed to the deep surface of the Pectoralis major. It sends a filament to join the medial anterior thoracic and form with it a loop in front of the first part of the axillary artery.

The **medial anterior thoracic** (*fasciculus medialis*) *arises* from the medial cord of the plexus and through it from the eighth cervical and first thoracic. It passes behind the first part of the axillary artery, curves forward between the axillary artery and vein, and unites in front of the artery with a filament from the lateral nerve. It then enters the deep surface of the Pectoralis minor, where it divides into a number of branches, which supply the muscle. Two or three branches pierce the muscle and end in the Pectoralis major.

The **Subscapular Nerves** (*nn. subscapulares*), two in number, spring from the posterior cord of the plexus and through it from the fifth and sixth cervical nerves.

The **upper subscapular** (*short subscapular*), the smaller enters the upper part of the Subscapularis, and is frequently represented by two branches.

The **lower subscapular** supplies the lower part of the Subscapularis, and ends in the Teres major; the latter muscle is sometimes supplied by a separate branch.

The **Thoracodorsal Nerve** (*n. thoracodorsalis; middle or long subscapular nerve*), a branch of the posterior cord of the plexus, derives its fibres from the fifth, sixth, and seventh cervical nerves; it follows the course of the subscapular artery, along the posterior wall of the axilla to the Latissimus dorsi, in which it may be traced as far as the lower border of the muscle.

The **Axillary Nerve** (*n. axillaris; circumflex nerve*) (Fig. 810) *arises* from the posterior cord of the brachial plexus, and its fibres are derived from the fifth and sixth cervical nerves. It lies at first behind the axillary artery, and in front of the Subscapularis, and passes downward to the lower border of that muscle. It then winds backward, in company with the posterior humeral circumflex artery, through a quadrilateral space bounded above by the Subscapularis, below by the Teres major, medially by the long head of the Triceps brachii, and laterally by the surgical neck of the humerus, and divides into an anterior and a posterior branch.

The **anterior branch** (*upper branch*) winds around the surgical neck of the humerus, beneath the Deltoideus, with the posterior humeral circumflex vessels, as far as the anterior border of that muscle, supplying it, and giving off a few small cutaneous branches, which pierce the muscle and ramify in the skin covering its lower part.

The **posterior branch** (*lower branch*) supplies the Teres minor and the posterior part of the Deltoideus; upon the branch to the Teres minor an oval enlargement

(pseudoganglion) usually exists. The posterior branch then pierces the deep fascia and is continued as the **lateral brachial cutaneous nerve**, which sweeps around the posterior border of the Deltoideus and supplies the skin over the lower two-thirds of the posterior part of this muscle, as well as that covering the long head of the Triceps brachii (Figs 805, 807).




FIG. 805.—Cutaneous nerves of right upper extremity. Anterior view.




FIG. 806.—Diagram of segmental distribution of the cutaneous nerves of the right upper extremity. Anterior view.

The trunk of the axillary nerve gives off an articular filament which enters the shoulder-joint below the Subscapularis.

The **Musculocutaneous Nerve** (*n. musculocutaneus*) (Fig. 809) arises from the lateral cord of the brachial plexus, opposite the lower border of the Pectoralis minor, its fibres being derived from the fifth, sixth, and seventh cervical nerves.



It pierces the Coracobrachialis muscle and passes obliquely between the Biceps brachii and the Brachialis, to the lateral side of the arm; a little above the elbow it pierces the deep fascia lateral to the tendon of the Biceps brachii and is continued into the forearm as the **lateral antibrachial cutaneous nerve**. In its course through the arm it supplies the Coracobrachialis, Biceps brachii, and the greater part of the




FIG. 807.—Cutaneous nerves of right upper extremity. Posterior view.




FIG. 808.—Diagram of segmental distribution of the cutaneous nerves of the right upper extremity. Posterior view

Brachialis. The branch to the Coracobrachialis is given off from the nerve close to its origin, and in some instances as a separate filament from the lateral cord of the plexus; it is derived from the seventh cervical nerve. The branches to the Biceps brachii and Brachialis are given off after the musculocutaneous has pierced the Coracobrachialis; that supplying the Brachialis gives a filament to the elbow-

joint. The nerve also sends a small branch to the bone, which enters the nutrient foramen with the accompanying artery.

The **lateral antibrachial cutaneous nerve** (*n. cutaneus antibrachii cutaneus lateralis; branch of musculocutaneous nerve*) passes behind the cephalic vein, and divides, opposite the elbow-joint, into a volar and a dorsal branch (Figs. 805, 807).

The **volar branch** (*ramus volaris; anterior branch*) descends along the radial border of the forearm to the wrist, and supplies the skin over the lateral half of its volar surface. At the wrist-joint it is placed in front of the radial artery, and some filaments, piercing the deep fascia, accompany that vessel to the dorsal surface of the carpus. The nerve then passes downward to the ball of the thumb, where it ends in cutaneous filaments. It communicates with the superficial branch of the radial nerve, and with the palmar cutaneous branch of the median nerve.

The **dorsal branch** (*ramus dorsalis; posterior branch*) descends, along the dorsal surface of the radial side of the forearm to the wrist. It supplies the skin of the lower two-thirds of the dorso-lateral surface of the forearm, communicating with the superficial branch of the radial nerve and the dorsal antibrachial cutaneous branch of the radial.

The musculocutaneous nerve presents frequent irregularities. It may adhere for some distance to the median and then pass outward, beneath the Biceps brachii, instead of through the Coracobrachialis. Some of the fibres of the median may run for some distance in the musculo-cutaneous and then leave it to join their proper trunk; less frequently the reverse is the case, and the median sends a branch to join the musculocutaneous. The nerve may pass under the Coracobrachialis or through the Biceps brachii. Occasionally it gives a filament to the Pronator teres, and it supplies the dorsal surface of the thumb when the superficial branch of the radial nerve is absent.

The **Medial Antibrachial Cutaneous Nerve** (*n. cutaneus antibrachii medialis; internal cutaneous nerve*) (Fig. 809) arises from the medial cord of the brachial plexus. It derives its fibres from the eighth cervical and first thoracic nerves, and at its commencement is placed medial to the axillary artery. It gives off, near the axilla, a filament, which pierces the fascia and supplies the integument covering the Biceps brachii, nearly as far as the elbow. The nerve then runs down the ulnar side of the arm medial to the brachial artery, pierces the deep fascia with the basilic vein, about the middle of the arm, and divides into a volar and an ulnar branch.

The **volar branch** (*ramus volaris; anterior branch*), the larger, passes usually in front of, but occasionally behind, the vena mediana cubiti (*median basilic vein*). It then descends on the front of the ulnar side of the forearm, distributing filaments to the skin as far as the wrist, and communicating with the palmar cutaneous branch of the ulnar nerve (Fig. 805).

The **ulnar branch** (*ramus ulnaris; posterior branch*) passes obliquely downward on the medial side of the basilic vein, in front of the medial epicondyle of the humerus, to the back of the forearm, and descends on its ulnar side as far as the wrist, distributing filaments to the skin. It communicates with the medial brachial cutaneous, the dorsal antibrachial cutaneous branch of the radial, and the dorsal branch of the ulnar (Fig. 807).

The **Medial Brachial Cutaneous Nerve** (*n. cutaneus brachii medialis; lesser internal cutaneous nerve; nerve of Wrisberg*) is distributed to the skin on the ulnar side of the arm (Figs. 805, 807). It is the smallest branch of the brachial plexus, and arising from the medial cord receives its fibres from the eighth cervical and first thoracic nerves. It passes through the axilla, at first lying behind, and then medial to the axillary vein, and communicates with the intercostobrachial nerve. It descends along the medial side of the brachial artery to the middle of the arm, where it pierces the deep fascia, and is distributed to the skin of the back of the lower third of the arm, extending as far as the elbow, where some filaments are lost in the skin in

front of the medial epicondyle, and others over the olecranon. It communicates with the ulnar branch of the medial antibrachial cutaneous nerve.

In some cases the medial brachial cutaneous and intercostobrachial are connected by two or three filaments, which form a plexus in the axilla. In other cases the intercostobrachial is of large size, and takes the place of the medial brachial cutaneous, receiving merely a filament of communication from the brachial plexus, which represents the latter nerve; in a few cases, this filament is wanting.

The **Median Nerve** (*n. medianus*) (Fig. 809) extends along the middle of the arm and forearm to the hand. It *arises* by two roots, one from the lateral and one from the medial cord of the brachial plexus; these embrace the lower part of the axillary artery, uniting either in front of or lateral to that vessel. Its fibres are derived from the sixth, seventh, and eighth cervical and first thoracic nerves. As it descends through the arm, it lies at first lateral to the brachial artery; about the level of the insertion of the Coracobrachialis it crosses the artery, usually in front of, but occasionally behind it, and lies on its medial side at the bend of the elbow, where it is situated behind the lacertus fibrosus (*bicipital fascia*), and is separated from the elbow-joint by the Brachialis. In the forearm it passes between the two heads of the Pronator teres and crosses the ulnar artery, but is separated from this vessel by the deep head of the Pronator teres. It descends beneath the Flexor digitorum sublimis, lying on the Flexor digitorum profundus, to within 5 cm. of the transverse carpal ligament; here it becomes more superficial, and is situated between the tendons of the Flexor digitorum sublimis and Flexor carpi radialis. In this situation it lies behind, and rather to the radial side of, the tendon of the Palmaris longus, and is covered by the skin and fascia. It then passes behind the transverse carpal ligament into the palm of the hand. In its course through the forearm it is accompanied by the median artery, a branch of the volar interosseous artery.

**Branches.**—With the exception of the nerve to the Pronator teres, which sometimes arises above the elbow-joint, the median nerve gives off no branches in the arm. As it passes in front of the elbow, it supplies one or two twigs to the joint.

In the forearm its branches are: **muscular**, **volar interosseous**, and **palmar**.

The **muscular branches** (*rami musculares*) are derived from the nerve near the elbow and supply all the superficial muscles on the front of the forearm, except the Flexor carpi ulnaris.

The **volar interosseous nerve** (*n. interosseus [antibrachii] volaris; anterior interosseous nerve*) supplies the deep muscles on the front of the forearm, except the ulnar half of the Flexor digitorum profundus. It accompanies the volar interosseous artery along the front of the interosseous membrane, in the interval between the Flexor pollicis longus and Flexor digitorum profundus, supplying the whole of the former and the radial half of the latter, and ending below in the Pronator quadratus and wrist-joint.

The **palmar branch** (*ramus cutaneus palmaris n. mediani*) of the median nerve *arises* at the lower part of the forearm. It pierces the volar carpal ligament, and divides into a lateral and a medial branch; the lateral branch supplies the skin over the ball of the thumb, and communicates with the volar branch of the lateral antibrachial cutaneous nerve; the medial branch supplies the skin of the palm and communicates with the palmar cutaneous branch of the ulnar.

In the palm of the hand the median nerve is covered by the skin and the palmar aponeurosis, and rests on the tendons of the Flexor muscles. Immediately after emerging from under the transverse carpal ligament the nerve becomes enlarged and flattened and splits into a smaller, lateral, and a larger, medial portion. The **lateral portion** supplies a short, stout branch to certain of the muscles of the ball of the thumb, viz., the Abductor brevis, the Opponens, and the superficial head of the Flexor brevis, and then divides into three **proper volar digital nerves**; two of these supply the sides of the thumb, while the third gives a twig to the first Lumbricalis

and is distributed to the radial side of the index finger. The **medial portion** of the nerve divides into two **common volar digital nerves**. The first of these gives a twig




FIG. 809.—Nerves of the left upper extremity.

to the second Lumbricalis and runs toward the cleft between the index and middle fingers, where it divides into two proper digital nerves for the adjoining sides of these digits; the second runs toward the cleft between the middle and ring fingers, and splits into two proper digital nerves for the adjoining sides of these digits; it communicates with a branch from the ulnar nerve and sometimes sends a twig to the third Lumbricalis.

Each proper digital nerve, opposite the base of the first phalanx, gives off a dorsal branch which joins the dorsal digital nerve from the superficial branch of the radial nerve, and supplies the integument on the dorsal aspect of the last phalanx. At the end of the digit, the proper digital nerve divides into two branches, one of which supplies the pulp of the finger, the other ramifies around and beneath the nail. The proper digital nerves, as they run along the fingers, are placed superficial to the corresponding arteries.

The **Ulnar Nerve** (*n. ulnaris*) (Fig. 809) is placed along the medial side of the limb, and is distributed to the muscles and skin of the forearm and hand. It *arises* from the medial cord of the brachial plexus, and derives its fibres from the eighth cervical and first thoracic nerves. It is smaller than the median, and lies at first behind it, but diverges from it in its course down the arm. At its origin it lies medial to the axillary artery, and bears the same relation to the brachial artery as far as the middle of the arm. Here it pierces the medial intermuscular septum, runs obliquely across the medial head of the Triceps brachii, and descends to the groove between the medial epicondyle and the olecranon, accompanied by the superior ulnar collateral artery. **At the elbow**, it rests upon the back of the medial epicondyle, and enters the forearm between the two heads of the Flexor carpi ulnaris. **In the forearm**, it descends along the ulnar side, lying upon the Flexor digitorum profundus; its upper half is covered by the Flexor carpi ulnaris, its lower half lies on the lateral side of the muscle, covered by the integument and fascia. In the upper third of the forearm, it is separated from the ulnar artery by a considerable interval, but in the rest of its extent lies close to the medial side of the artery. About 5 cm. above the wrist it ends by dividing into a dorsal and a volar branch.

The branches of the ulnar nerve are: **articular** to the elbow-joint, **muscular**, **palmar cutaneous**, **dorsal**, and **volar**.

The **articular branches** to the elbow-joint are several small filaments which *arise* from the nerve as it lies in the groove between the medial epicondyle and olecranon.

The **muscular branches** (*rami musculares*) two in number, *arise* near the elbow: one supplies the Flexor carpi ulnaris; the other, the ulnar half of the Flexor digitorum profundus.

The **palmar cutaneous branch** (*ramus cutaneus palmaris*) *arises* about the middle of the forearm, and descends on the ulnar artery, giving off some filaments to the vessel. It perforates the volar carpal ligament and ends in the skin of the palm, communicating with the palmar branch of the median nerve.

The **dorsal branch** (*ramus dorsalis manus*) *arises* about 5 cm. above the wrist; it passes backward beneath the Flexor carpi ulnaris, perforates the deep fascia, and, running along the ulnar side of the back of the wrist and hand, divides into two dorsal digital branches; one supplies the ulnar side of the little finger; the other, the adjacent sides of the little and ring fingers. It also sends a twig to join that given by the superficial branch of the radial nerve for the adjoining sides of the middle and ring fingers, and assists in supplying them. A branch is distributed to the metacarpal region of the hand, communicating with a twig of the superficial branch of the radial nerve (Fig. 807).

On the little finger the dorsal digital branches extend only as far as the base of the terminal phalanx, and on the ring finger as far as the base of the second phalanx; the more distal parts of these digits are supplied by dorsal branches derived from the proper volar digital branches of the ulnar nerve.



The **volar branch** (*ramus volaris manus*) crosses the transverse carpal ligament on the lateral side of the pisiform bone, medial to and a little behind the ulnar artery. It ends by dividing into a superficial and a deep branch.

The **superficial branch** (*ramus superficialis [n. ulnaris]*) supplies the Palmaris brevis, and the skin on the ulnar side of the hand, and divides into a proper volar digital branch for the ulnar side of the little finger, and a common volar digital branch which gives a communicating twig to the median nerve and divides into two proper digital nerves for the adjoining sides of the little and ring fingers (Fig. 805). The proper digital branches are distributed to the fingers in the same manner as those of the median.

The **deep branch** (*ramus profundus*) accompanied by the deep branch of the ulnar artery, passes between the Abductor digiti quinti and Flexor digiti quinti brevis; it then perforates the Opponens digiti quinti and follows the course of the deep volar arch beneath the Flexor tendons. At its origin it supplies the three short muscles of the little finger. As it crosses the deep part of the hand, it supplies all the Interossei and the third and fourth Lumbricalis; it ends by supplying the Adductores pollicis and the medial head of the Flexor pollicis brevis. It also sends articular filaments to the wrist-joint.

It has been pointed out that the ulnar part of the Flexor digitorum profundus is supplied by the ulnar nerve; the third and fourth Lumbricales, which are connected with the tendons




FIG. 810.—The suprascapular, axillary, and radial nerves.

of this part of the muscle, are supplied by the same nerve. In like manner the lateral part of the Flexor digitorum profundus and the first and second Lumbricales are supplied by the median nerve; the third Lumbricalis frequently receives an additional twig from the median nerve.

The **Radial Nerve** (*n. radialis; musculospiral nerve*) (Fig. 810), the largest branch of the brachial plexus, is the continuation of the posterior cord of the plexus. Its fibres are derived from the fifth, sixth, seventh, and eighth cervical and first thoracic

nerves. It descends behind the first part of the axillary artery and the upper part of the brachial artery, and in front of the tendons of the Latissimus dorsi and Teres major. It then winds around from the medial to the lateral side of the humerus in a groove with the a. profunda brachii, between the medial and lateral heads of the Triceps brachii. It pierces the lateral intermuscular septum, and passes between the Brachialis and Brachioradialis to the front of the lateral epicondyle, where it divides into a superficial and a deep branch.

The **branches** of the musculospiral nerve are:

Muscular.  
Cutaneous.

Superficial.  
Deep.

The **muscular branches** (*rami musculares*) supply the Triceps brachii, Anconaeus, Brachioradialis, Extensor carpi radialis longus, and Brachialis, and are grouped as medial, posterior, and lateral.

The medial muscular branches supply the medial and long heads of the Triceps brachii. That to the medial head is a long, slender filament, which lies close to the ulnar nerve as far as the lower third of the arm, and is therefore frequently spoken of as the **ulnar collateral nerve**.

The posterior muscular branch, of large size, *arises* from the nerve in the groove between the Triceps brachii and the humerus. It divides into filaments, which supply the medial and lateral heads of the Triceps brachii and the Anconaeus muscles. The branch for the latter muscle is a long, slender filament, which descends in the substance of the medial head of the Triceps brachii.

The lateral muscular branches supply the Brachioradialis, Extensor carpi radialis longus, and the lateral part of the Brachialis.

The **cutaneous branches** are two in number, the posterior brachial cutaneous and the dorsal antibrachial cutaneous.

The **posterior brachial cutaneous nerve** (*n. cutaneus brachii posterior; internal cutaneous branch of musculospiral*) *arises* in the axilla, with the medial muscular branch. It is of small size, and passes through the axilla to the medial side of the area supplying the skin on its dorsal surface nearly as far as the olecranon. In its course it crosses behind, and communicates with, the intercostobrachial.

The **dorsal antibrachial cutaneous nerve** (*n. cutaneus antibrachii dorsalis; external cutaneous branch of musculospiral*) *perforates* the lateral head of the Triceps brachii at its attachment to the humerus. The **upper** and smaller branch of the nerve passes to the front of the elbow, lying close to the cephalic vein, and supplies the skin of the lower half of the arm (Fig. 805). The **lower** branch pierces the deep fascia below the insertion of the Deltoideus, and descends along the lateral side of the arm and elbow, and then along the back of the forearm to the wrist, supplying the skin in its course, and joining, near its termination, with the dorsal branch of the lateral antibrachial cutaneous nerve (Fig. 807).

The **Superficial Branch of the Radial Nerve** (*ramus superficialis radial nerve*) passes along the front of the radial side of the forearm to the commencement of its lower third. It lies at first slightly lateral to the radial artery, concealed beneath the Brachioradialis. In the middle third of the forearm, it lies behind the same muscle, close to the lateral side of the artery. It quits the artery about 7 cm. above the wrist, passes beneath the tendon of the Brachioradialis, and, piercing the deep fascia, divides into two branches (Fig. 807).

The lateral branch, the smaller, supplies the skin of the radial side and ball of the thumb, joining with the volar branch of the lateral antibrachial cutaneous nerve.

The medial branch communicates, above the wrist, with the dorsal branch of the lateral antibrachial cutaneous, and, on the back of the hand, with the dorsal branch of the ulnar nerve. It then divides into four digital nerves, which are

distributed as follows: the first supplies the ulnar side of the thumb; the second, the radial side of the index finger; the third, the adjoining sides of the index and middle fingers; the fourth communicates with a filament from the dorsal branch of the ulnar nerve, and supplies the adjacent sides of the middle and ring fingers.<sup>1</sup>

The **Deep Branch of the Radial Nerve** (*n. interosseus dorsalis; dorsal or posterior interosseous nerve*) winds to the back of the forearm around the lateral side of the radius between the two planes of fibres of the Supinator, and is prolonged downward between the superficial and deep layers of muscles, to the middle of the forearm. Considerably diminished in size, it descends, as the **dorsal interosseous nerve**, on the interosseous membrane, in front of the Extensor pollicis longus, to the back of the carpus, where it presents a gangliform enlargement from which filaments are distributed to the ligaments and articulations of the carpus. It supplies all the muscles on the radial side and dorsal surface of the forearm, excepting the Anconaeus, Brachioradialis, and Extensor carpi radialis longus.

**Applied Anatomy.**—The brachial plexus may be injured by falls from a height on to the side of the head and shoulder, whereby the nerves of the plexus are violently stretched; the fifth cervical nerve sustains the greatest amount of injury, and the subsequent paralysis may be confined to the muscles supplied by this nerve, viz., the Deltoides, Biceps brachii, Brachialis, and Brachioradialis, with sometimes the Supra- and Infraspinatus and the Supinator. The position of the limb, under such conditions, is characteristic; the arm hangs by the side and is rotated inward; the forearm is extended and pronated. The arm cannot be raised from the side; all power of flexion of the elbow is lost, as is also supination of the forearm. This is known as *Erb's paralysis*, and a very similar condition is occasionally met with in newborn children, either from injury to the fifth nerve from the pressure of forceps used in affecting delivery, or from traction of the head in breech presentations. A second variety of partial palsy of the brachial plexus is known as *Klumpke's paralysis*. In this it is the eighth cervical and first thoracic nerves that are injured, either before or after they have joined to form the lower trunk. Atrophy follows in the intrinsic muscles of the hand, and in the Flexors of the fingers and wrist; the thenar and hypothenar eminences waste and flatten; the fingers cannot be spread out or approximated, on account of the paralysis of the Interossei, and become clawed. The injury to the nerves may follow direct violence or a gunshot wound.

The brachial plexus may also be injured by violent traction on the arm, or by efforts at reducing a dislocation of the shoulder-joint; and the amount of paralysis will depend upon the amount of injury to the constituent nerves. When the entire plexus is involved, the whole of the upper extremity will be paralyzed and anesthetic. In these cases the injury appears to be rather a tearing away of the roots of the nerves from the medulla spinalis, than a rupture of the nerves themselves. The brachial plexus in the axilla is often damaged from the pressure of a crutch, producing the condition known as *crutch paralysis*. In these cases the radial seems most frequently to be the nerve implicated; the ulnar nerve suffers next in frequency. The median and radial nerves often suffer from "sleep palsies," paralysis from pressure coming on while the patient is profoundly asleep under the influence of alcohol or some narcotic.

Paralysis of the *long thoracic nerve* throws the Serratus anterior out of action, and may occur in porters in whom the nerve is exposed to injury as it crosses the posterior triangle of the neck. The inferior angle of the scapula is drawn toward the middle line, by the unopposed action of the Rhomboidei and Levator scapulae, and tends to project backward when the arm is held horizontally forward. The arm cannot be raised above the horizontal unless the inferior angle of the scapula is pushed lateralward for the patient.

The *axillary (circumflex) nerve*, on account of its course around the surgical neck of the humerus, is liable to be torn in fractures of this part of the bone, and in dislocations of the shoulder-joint; paralysis of the Deltoides, and anesthesia of the skin over the lower part of that muscle, result. According to Erb, inflammation of the shoulder-joint is liable to be followed by a neuritis of this nerve from extension of the inflammation to it. Paralysis of the Deltoides renders abduction of the arm to the horizontal level impossible. The associated paralysis of the *Teres minor* is not easily demonstrated.

Hilton gave the axillary nerve as an illustration of a law which he laid down, that "the same trunks of nerves whose branches supply the groups of muscles moving a joint, furnish also a

<sup>1</sup> According to Hutchison, the digital nerve to the thumb reaches only as high as the root of the nail; the one to the forefinger as high as the middle of the second phalanx; and the one to the middle and ring fingers not higher than the first phalangeal joint.—London Hosp. Gaz., iii, 319.

distribution of nerves to the skin over the insertions of the same muscles, and the interior of the joint receives its nerves from the same source." In this way he explains the fact that an inflamed joint becomes rigid.

The *median nerve* is liable to injury in wounds of the forearm. In such cases there is loss of flexion of the second phalanges of all the fingers, and of the terminal phalanges of the index and middle fingers. Flexion of the terminal phalanges of the ring and little fingers is effected by that portion of the *Flexor digitorum profundus* which is supplied by the ulnar nerve. There is power to flex the proximal phalanges through the *Interossei*. The thumb cannot be flexed or opposed, and is maintained in a position of extension and adduction. There is loss in the power of pronating the forearm; the *Brachioradialis* has the power of bringing the forearm into a position of mid-pronation, but beyond this no further pronation can be effected. The wrist can be flexed, if the hand is first adducted by the action of the *Flexor carpi ulnaris*. There is loss or impairment of sensation on the volar surfaces of the thumb, index, middle, and radial half of ring fingers, and on the dorsal surfaces of the same fingers over the last two phalanges; except in the thumb, where the loss of sensation would be limited to the back of the last phalanx. In old cases the unopposed action of the *Interossei* produces backward dislocation of the interphalangeal joints. The thumb is extended and adducted to the index finger, cannot be flexed or abducted, and cannot be apposed to any one of the fingers; in consequence an "ape-like" hand is produced. More commonly, however, the nerve is injured just above the annular ligament when the power of flexion of the fingers and pronation of the forearm remain intact unless the *Flexor tendons* are also divided. This injury seriously interferes with the use of the hand, as, besides the wasting of the muscles of the thenar eminence, great trouble is experienced from the trophic changes which result about the skin and nails of the fingers which are anesthetic. In order to expose the median nerve, for the purpose of uniting the divided ends, supposing the injury to be just above the wrist, and incision should be made along the radial side of the tendon of the *palmaris longus*, which serves as a guide to the nerve.

The *ulnar nerve* is also liable to be injured in wounds of the forearm, such injury leading to impaired power of ulnar flexion, and upon an attempt being made to flex the wrist, the hand is drawn to the radial side from paralysis of the *Flexor carpi ulnaris*; there is inability to spread out the fingers from paralysis of the *Interossei*, and for the same reason the fingers, especially the ring and little fingers, cannot be flexed at the metacarpophalangeal joints or extended at the interphalangeal joints, and the hand assumes a claw shape from the action of the opposing muscles; there is loss of power of flexion in the little and ring fingers; and there is inability to adduct the thumb. The muscles of the hypothenar eminence become wasted. Sensation is lost, or impaired, in the skin supplied by the nerve. In order to expose the nerve in the lower part of the forearm, an incision should be made along the radial border of the tendon of the *Flexor carpi ulnaris*, and the nerve will be found lying on the ulnar side of the ulnar artery. This nerve may be also affected in cases of dislocation of the shoulder or fracture of the surgical neck of the humerus. Wasting of the muscles which it supplies is not uncommonly seen where a "cervical rib" is present, the lower end of the plexus passing between this and the first thoracic rib.

The *radial (musculospiral) nerve* is also frequently injured. In consequence of its close relationship to the humerus, it is often torn or injured in fractures of this bone, or subsequently involved in the callus that may be thrown out around a fracture, and thus pressed upon and its functions interfered with. It is also liable to be contused against the bone by kicks or blows, or to be divided in wounds of the arm. When paralyzed, the hand is flexed at the wrist and lies flaccid. This is known as *wrist drop*. The fingers are also flexed, and on an attempt being made to extend them, the last two phalanges only will be extended, through the action of the *Interossei*; the first phalanges remaining flexed. There is no power of extending the wrist. Supination is completely lost when the forearm is extended on the arm, but is possible to a certain extent if the forearm be flexed so as to allow of the action of the *Biceps brachii*. The power of extension of the forearm is lost on account of paralysis of the *Triceps brachii*, if the injury to the nerve has taken place near its origin. In cases due to pressure, sensation is hardly affected; severe injury to the nerve occasions anesthesia over the area supplied by the superficial branch of the radial nerve, and, if the lesion be high up, on the lateral side of the upper arm and the back of the forearm (posterior brachial and dorsal antibrachial cutaneous branches) as well.

The nerve is best exposed by making an incision along the medial border of the *Brachioradialis*, just above the level of the elbow-joint. The skin and superficial structures are to be divided and the deep fascia exposed. The white line in the fascia indicating the border of the muscle is to be defined, and the deep fascia divided in this line. On raising the *Brachioradialis*, the nerve will be found lying between it and the *Brachialis*. The muscles supplied by the deep branch of the radial nerve are also particularly liable to be affected in chronic lead poisoning; here the affection is probably in the cells of the anterior column of the medulla spinalis. Incisions down to the neck of the radius posteriorly or on the lateral side should never be made, as the deep branch of the radial nerve would be severed.

### The Thoracic Nerves (Nn. Thoracales).

The **anterior divisions of the thoracic nerves** (*rami anteriores; ventral divisions*) are twelve in number on either side. Eleven of them are situated between the ribs, and are therefore termed **intercostal**; the twelfth lies below the last rib. Each nerve is connected with the adjoining ganglion of the sympathetic trunk by a gray and a white *ramus communicans*. The intercostal nerves are distributed chiefly to the parietes of the thorax and abdomen, and differ from the anterior divisions of the other spinal nerves, in that each pursues an independent course, *i. e.*, there is no plexus formation. The first two nerves supply fibres to the upper limb in addition to their thoracic branches; the next four are limited in their distribution to the parietes of the thorax; the lower five supply the parietes of the thorax and abdomen. The twelfth thoracic is distributed to the abdominal wall and the skin of the buttock.

**The First Thoracic Nerve.**—The anterior division of the first thoracic nerve divides into two branches: one, the larger, leaves the thorax in front of the neck of the first rib, and enters the brachial plexus; the other and smaller branch, the **first intercostal nerve**, runs along the first intercostal space, and ends on the front of the chest as the first anterior cutaneous branch of the thorax. Occasionally this anterior cutaneous branch is wanting. The first intercostal nerve as a rule gives off no lateral cutaneous branch; but sometimes it sends a small branch to communicate with the intercostobrachial. From the second thoracic nerve it frequently receives a connecting twig, which ascends over the neck of the second rib.




FIG. 811.—Diagram of the course and branches of a typical intercostal nerve.

**The Upper Thoracic Nerves** (*nn. intercostales*).—The anterior divisions of the second, third, fourth, fifth, and sixth thoracic nerves, and the small branch from the first thoracic, are confined to the parietes of the thorax, and are named **thoracic intercostal nerves**. They pass forward (Fig. 811) in the intercostal spaces below the intercostal vessels. At the back of the chest they lie between the pleura and the posterior intercostal membranes, but soon pierce the latter and run between the two planes of Intercostal muscles as far as the middle of the rib. They then enter the substance of the *Intercostales interni*, and, running amidst their fibres as far as



the costal cartilages, they gain the inner surfaces of the muscles and lie between them and the pleura. Near the sternum, they cross in front of the internal mammary artery and Transversus thoracis muscle, pierce the Intercostales interni, the anterior intercostal membranes, and Pectoralis major, and supply the integument of the front of the thorax and over the mamma, forming the anterior cutaneous branches of the thorax; the branch from the second nerve unites with the anterior supraclavicular nerves of the cervical plexus.

**Branches.**—Numerous slender muscular filaments supply the Intercostales, the Subcostales, the Levatores costarum, the Serratus posterior superior, and the Transversus thoracis. At the front of the thorax some of these branches cross the costal cartilages from one intercostal space to another.

**Lateral cutaneous branches** (*rami cutanei laterales*) are derived from the intercostal nerves, about midway between the vertebræ and sternum; they pierce the Intercostales externi and Serratus anterior, and divide into anterior and posterior branches. The **anterior branches** run forward to the side and the forepart of the chest, supplying the skin and the mamma; those of the fifth and sixth nerves supply the upper digitations of the Obliquus externus abdominis. The **posterior branches** run backward, and supply the skin over the scapula and Latissimus dorsi.

The lateral cutaneous branch of the second intercostal nerve does not divide, like the others, into an anterior and a posterior branch; it is named the **intercostobrachial nerve** (Fig. 809). It pierces the Intercostalis externus and the Serratus anterior, crosses the axilla to the medial side of the arm, and joins with a filament from the medial brachial cutaneous nerve. It then pierces the fascia, and supplies the skin of the upper half of the medial and posterior part of the arm, communicating with the posterior brachial cutaneous branch of the radial nerve. The size of the intercostobrachial nerve is in inverse proportion to that of the medial brachial cutaneous nerve. A second intercostobrachial nerve is frequently given off from the lateral cutaneous branch of the third intercostal; it supplies filaments to the axilla and medial side of the arm.

**The Lower Thoracic Nerves.**—The anterior divisions of the seventh, eighth, ninth, tenth, and eleventh thoracic nerves are continued anteriorly from the intercostal spaces into the abdominal wall; hence they are named **thoracicoabdominal intercostal nerves**. They have the same arrangement as the upper ones as far as the anterior ends of the intercostal spaces, where they pass behind the costal cartilages, and between the Obliquus internus and Transversus abdominis, to the sheath of the Rectus abdominis, which they perforate. They supply the Rectus abdominis and end as the **anterior cutaneous branches** of the abdomen; they supply the skin of the front of the abdomen. The lower intercostal nerves supply the Intercostales and abdominal muscles; the last three send branches to the Serratus posterior inferior. About the middle of their course they give off **lateral cutaneous branches**. These pierce the Intercostales externi and the Obliquus externus abdominis, in the same line as the lateral cutaneous branches of the upper thoracic nerves, and divide into anterior and posterior branches, which are distributed to the skin of the abdomen and back; the anterior branches supply the digitations of the Obliquus externus abdominis, and extend downward and forward nearly as far as the margin of the Rectus abdominis; the posterior branches pass backward to supply the skin over the Latissimus dorsi.

The anterior division of the **twelfth thoracic nerve** is larger than the others; it runs along the lower border of the twelfth rib, often gives a communicating branch to the first lumbar nerve, and passes under the lateral lumbocostal arch. It then runs in front of the Quadratus lumborum, perforates the Transversus, and passes forward between it and the Obliquus internus to be distributed in the same manner as the lower intercostal nerves. It communicates with the iliohypogastric nerve of the lumbar plexus, and gives a branch to the Pyramidalis. The **lateral cutaneous**

branch of the last thoracic nerve is large, and does not divide into an anterior and a posterior branch. It perforates the Obliqui internus and externus, descends over the iliac crest in front of the lateral cutaneous branch of the iliohypogastric (Fig. 819), and is distributed to the skin of the front part of the gluteal region, some of its filaments extending as low as the greater trochanter.

**Applied Anatomy.**—The lower seven thoracic nerves and the iliohypogastric from the first lumbar nerve supply the skin of the abdominal wall. They run downward and forward fairly equidistant from each other. The sixth and seventh supply the skin over the "pit of the stomach;" the eighth corresponds to about the position of the middle tendinous inscription of the Rectus abdominis; the tenth to the umbilicus; and the iliohypogastric supplies the skin over the pubis and subcutaneous inguinal ring. In many diseases affecting the nerve trunks at or near their origins, the pain is referred to their peripheral terminations. Thus, in Pott's disease of the vertebrae, children often suffer from pain in the abdomen. When the irritation is confined to a single pair of nerves, the sensation complained of is often a feeling of constriction, as if a cord were tied around the abdomen, and in these cases the situation of the sense of constriction may serve to localize the disease in the vertebral column. In other cases where the bone disease is more extensive, and two or more nerves are involved, a more general, diffused pain in the abdomen is felt.

Again, it must be borne in mind that the nerves which supply the skin of the abdomen supply also the planes of muscle which constitute the greater part of the abdominal wall. Hence, any irritation applied to the peripheral ends of the cutaneous branches in the skin of the abdomen is immediately followed by reflex contraction of the abdominal muscles. The supply of both muscles and skin from the same source is of importance in protecting the abdominal viscera from injury. A blow on the abdomen, even of a severe character, will do no injury to the viscera if the muscles are in a condition of firm contraction; whereas in cases where the muscles have been taken unawares, and the blow has been struck while they were in a state of rest, an injury insufficient to produce any lesion of the abdominal wall has been attended with rupture of some of the abdominal contents. The importance, therefore, of immediate reflex contraction upon the receipt of an injury cannot be overestimated, and the intimate association of the cutaneous and muscular fibres in the same nerve produces a much more rapid response on the part of the muscles to any peripheral stimulation of the cutaneous filaments than would be the case if the two sets of fibres were derived from independent sources.

The nerves supplying the abdominal muscles and skin, derived from the lower intercostal nerves, are intimately connected with the sympathetic supplying the abdominal viscera through the lower thoracic ganglia from which the splanchnic nerves are derived. In consequence of this, in laceration of the abdominal viscera and in acute peritonitis, the muscles of the belly wall become firmly contracted, and thus as far as possible preserve the abdominal contents in a condition of rest.

### **The Lumbosacral Plexus (Plexus Lumbosacralis).**

The anterior divisions of the lumbar, sacral, and coccygeal nerves form the lumbosacral plexus, the first lumbar nerve being frequently joined by a branch from the twelfth thoracic. For descriptive purposes this plexus is usually divided into three parts—the lumbar, sacral, and pudendal plexuses.

### **The Lumbar Nerves (Nn. Lumbales).**

The anterior divisions of the lumbar nerves (*rami anteriores*) increase in size from above downward. They are joined, near their origins, by *gray rami communicantes* from the lumbar ganglia of the sympathetic trunk. These rami consist of long, slender branches which accompany the lumbar arteries around the sides of the vertebral bodies, beneath the Psoas major. Their arrangement is somewhat irregular: one ganglion may give rami to two lumbar nerves, or one lumbar nerve may receive rami from two ganglia. The first and second, and sometimes the third and fourth lumbar nerves are each connected with the lumbar part of the sympathetic trunk by a *white ramus communicans*.

The nerves pass obliquely outward behind the Psoas major, or between its fasciculi, distributing filaments to it and the Quadratus lumborum. The first three and the greater part of the fourth are connected together in this situation by anastomotic loops, and form the **lumbar plexus**. The smaller part of the fourth

joins with the fifth to form the **lumbosacral trunk**, which assists in the formation of the sacral plexus. The fourth nerve is named the **nervus furcalis**, from the fact that it is subdivided between the two plexuses.<sup>1</sup>

**The Lumbar Plexus** (*plexus lumbalis*) (Figs. 812, 813).—The lumbar plexus is formed by the loops of communication between the anterior divisions of the first three and the greater part of the fourth lumbar nerves; the first lumbar often receives a branch from the last thoracic nerve. It is situated in the posterior part of the Psoas major, in front of the transverse processes of the lumbar vertebræ.




FIG. 812.—Plan of lumbar plexus.

The mode in which the plexus is arranged varies in different subjects. It differs from the brachial plexus in not forming an intricate interlacement, but the several nerves of distribution *arise* from one or more of the spinal nerves, in the following manner: the first lumbar nerve, frequently supplemented by a twig from the last thoracic, splits into an upper and lower branch; the upper and larger branch divides into the iliohypogastric and ilioinguinal nerves; the lower and smaller branch unites with a branch of the second lumbar to form the genitofemoral nerve. The remainder of the second nerve, and the third and fourth nerves, divide into ventral and dorsal divisions. The ventral division of the second unites with the ventral divisions of the third and fourth nerves to form the obturator nerve. The dorsal divisions of the second and third nerves divide into two branches, a smaller branch from each uniting to form the lateral femoral cutaneous nerve, and a larger branch

<sup>1</sup> In most cases the fourth lumbar is the *nervus furcalis*; but this arrangement is frequently departed from. The third is occasionally the lowest nerve which enters the lumbar plexus, giving at the same time some fibres to the sacral plexus, and thus forming the *nervus furcalis*; or both the third and fourth may be furcal nerves. When this occurs, the plexus is termed *high* or *prefixed*. More frequently the fifth nerve is divided between the lumbar and sacral plexuses, and constitutes the *nervus furcalis*; and when this takes place, the plexus is distinguished as a *low* or *postfixed* plexus. These variations necessarily produce corresponding modifications in the sacral plexus.

from each joining with the dorsal division of the fourth nerve to form the femoral nerve. The accessory obturator, when it exists, is formed by the union of two small branches given off from the third and fourth nerves.




FIG. 813.—The lumbar plexus and its branches.

The **branches** of the lumbar plexus may therefore be arranged as follows:

Iliohypogastric	1 L.
Ilioinguinal	1 L.
Genitofemoral	1, 2 L.
	Dorsal divisions.
Lateral femoral cutaneous	2, 3 L.
Femoral.	2, 3, 4 L.
	Ventral divisions.
Obturator	2, 3, 4 L.
Accessory obturator	3, 4 L.

The **Iliohypogastric Nerve** (*n. iliohypogastricus*) arises from the first lumbar nerve. It emerges from the upper part of the lateral border of the Psoas major, and crosses obliquely in front of the Quadratus lumborum to the iliac crest. It then perforates the posterior part of the Transversus abdominis, near the crest of the ilium, and

divides between that muscle and the Obliquus internus abdominis into a **lateral** and an **anterior cutaneous branch**.

The **lateral cutaneous branch** (*ramus cutaneus lateralis; iliac branch*) pierces the Obliqui internus and externus immediately above the iliac crest, and is distributed to the skin of the gluteal region, behind the lateral cutaneous branch of the last thoracic nerve (Fig. 819); the size of this branch bears an inverse proportion to that of the lateral cutaneous branch of the last thoracic nerve.

The **anterior cutaneous branch** (*ramus cutaneus anterior; hypogastric branch*) (Fig. 814) continues onward between the Obliquus internus and Transversus. It then pierces the Obliquus internus, becomes cutaneous by perforating the aponeurosis of the Obliquus externus about 2.5 cm. above the subcutaneous inguinal ring, and is distributed to the skin of the hypogastric region.

The iliohypogastric nerve communicates with the last thoracic and ilioinguinal nerves.

The **Ilioinguinal Nerve** (*n. ilioinguinalis*), smaller than the preceding, *arises* with it from the first lumbar nerve. It emerges from the lateral border of the Psoas major just below the iliohypogastric, and, passing obliquely across the Quadratus lumborum and Iliacus, perforates the Transversus abdominis, near the anterior part of the iliac crest, and communicates with the iliohypogastric nerve between the Transversus and the Obliquus internus. The nerve then pierces the Obliquus internus, distributing filaments to it, and, accompanying the spermatic cord through the subcutaneous inguinal ring, is distributed to the skin of the upper and medial part of the thigh, to the skin over the root of the penis and upper part of the scrotum in the male, and to the skin covering the mons pubis and labium majus in the female. The size of this nerve is in inverse proportion to that of the iliohypogastric. Occasionally it is very small, and ends by joining the iliohypogastric; in such cases, a branch from the iliohypogastric takes the place of the ilioinguinal, or the latter nerve may be altogether absent.

The **Genitofemoral Nerve** (*n. genitofemoralis; genitocrural nerve*) *arises* from the first and second lumbar nerves. It passes obliquely through the substance of the Psoas major, and emerges from its medial border, close to the vertebral column, opposite the fibrocartilage between the third and fourth lumbar vertebræ; it then descends on the surface of the Psoas major, under cover of the peritoneum, and divides into the external spermatic and lumboinguinal nerves. Occasionally these two nerves emerge separately through the substance of the Psoas.

The **external spermatic nerve** (*n. spermaticus externus; genital branch of genitofemoral*) passes outward on the Psoas major, and pierces the fascia transversalis, or passes through the abdominal inguinal ring; it then descends behind the spermatic cord to the scrotum, supplies the Cremaster, and gives a few filaments to the skin of the scrotum. In the female, it accompanies the round ligament of the uterus, and is lost upon it.

The **lumboinguinal nerve** (*n. lumboinguinalis; femoral or crural branch of genitofemoral*) descends on the external iliac artery, sending a few filaments around it, and, passing beneath the inguinal ligament, enters the sheath of the femoral vessels, lying superficial and lateral to the femoral artery. It pierces the anterior layer of the sheath of the vessels and the fascia lata, and supplies the skin of the anterior surface of the upper part of the thigh (Fig. 814). On the front of the thigh it communicates with the anterior cutaneous branches of the femoral nerve. A few filaments from the lumboinguinal nerve may be traced to the femoral artery.

The **Lateral Femoral Cutaneous Nerve** (*n. cutaneus femoralis lateralis; external cutaneous nerve*) *arises* from the dorsal divisions of the second and third lumbar nerves. It emerges from the lateral border of the Psoas major about its middle, and crosses the Iliacus obliquely, toward the anterior superior iliac spine. It then






FIG. 814 - Cutaneous nerves of right lower extremity.  
Distal view.




FIG. 815 - Diagram of segmental distribution of  
the cutaneous nerves of the right lower extremity.  
Front view.

The **anterior branch** becomes superficial about 10 cm. below the inguinal ligament, and divides into branches which are distributed to the skin of the anterior and lateral parts of the thigh, as far as the knee. The terminal filaments of this nerve frequently communicate with the anterior cutaneous branches of the femoral nerve, and with the infrapatellar branch of the saphenous nerve, forming with them the **patellar plexus**.

The **posterior branch** pierces the fascia lata, and subdivides into filaments which pass backward across the lateral and posterior surfaces of the thigh, supplying the skin from the level of the greater trochanter to the middle of the thigh.

The **Obturator Nerve** (*n. obturatorius*) arises from the ventral divisions of the second, third, and fourth lumbar nerves; the branch from the third is the largest, while that from the second is often very small. It descends through the fibres of the Psoas major, and emerges from its medial border near the brim of the pelvis; it then passes behind the common iliac vessels, and on the lateral side of the hypogastric vessels and ureter, which separate it from the ureter, and runs along the lateral wall of the lesser pelvis, above and in front of the obturator vessels, to the upper part of the obturator foramen. Here it enters the thigh, and divides into an anterior and a posterior branch, which are separated at first by some of the fibres of the Obturator externus, and lower down by the Adductor brevis.

The **anterior branch** (*ramus anterior*) (Fig. 816) leaves the pelvis in front of the Obturator externus and descends in front of the Adductor brevis, and behind the Pectineus and Adductor longus; at the lower border of the latter muscle it communicates with the anterior cutaneous




FIG. 816.—Nerves of the right lower extremity. Front view.

and saphenous branches of the femoral nerve, forming a kind of plexus. It then descends upon the femoral artery, to which it is finally distributed. Near the obturator foramen the nerve gives off an articular branch to the hip-joint. Behind the Pectineus, it distributes branches to the Adductor longus and Gracilis, and usually to the Adductor brevis, and in rare cases to the Pectineus; it receives a communicating branch from the accessory obturator nerve when that nerve is present.

Occasionally the communicating branch to the anterior cutaneous and saphenous branches of the femoral is continued down, as a cutaneous branch, to the thigh and leg. When this is so, it emerges from beneath the lower border of the Adductor longus, descends along the posterior margin of the Sartorius to the medial side of the knee, where it pierces the deep fascia, communicates with the saphenous nerve, and is distributed to the skin of the tibial side of the leg as low down as its middle.

The **posterior branch** (*ramus posterior*) pierces the anterior part of the Obturator externus, and supplies this muscle; it then passes behind the Adductor brevis on the front of the Adductor magnus, where it divides into numerous muscular branches which are distributed to the Adductor magnus and the Adductor brevis when the latter does not receive a branch from the anterior division of the nerve. It usually gives off an articular filament to the knee-joint.

The **articular branch for the knee-joint** is sometimes absent; it either perforates the lower part of the Adductor magnus, or passes through the opening which transmits the femoral artery, and enters the popliteal fossa; it then descends upon the popliteal artery, as far as the back part of the knee-joint, where it perforates the oblique popliteal ligament, and is distributed to the synovial membrane. It gives filaments to the popliteal artery.

The **Accessory Obturator Nerve** (*n. obturatorius accessorius*) (Fig. 813) is present in about 29 per cent. of cases. It is of small size, and *arises* from the ventral divisions of the third and fourth lumbar nerves. It descends along the medial border of the Psoas major, crosses the superior ramus of the pubis, and passes under the Pectineus, where it divides into numerous branches. One of these supplies the Pectineus, penetrating its deep surface, another is distributed to the hip-joint; while a third communicates with the anterior branch of the obturator nerve. Occasionally the accessory obturator nerve is very small and is lost in the capsule of the hip-joint. When it is absent, the hip-joint receives two branches from the obturator nerve.

The **Femoral Nerve** (*n. femoralis; anterior crural nerve*) (Fig. 816), the largest branch of the lumbar plexus, *arises* from the dorsal divisions of the second, third, and fourth lumbar nerves. It descends through the fibres of the Psoas major, emerging from the muscle at the lower part of its lateral border, and passes down between it and the Iliacus, behind the iliac fascia; it then runs beneath the inguinal ligament, into the thigh, and splits into an anterior and a posterior division. Under the inguinal ligament, it is separated from the femoral artery by a portion of the Psoas major.

Within the abdomen the femoral nerve gives off small branches to the Iliacus, and a branch which is distributed upon the upper part of the femoral artery; the latter branch may arise in the thigh.

In the thigh the anterior division of the femoral nerve gives off anterior cutaneous and muscular branches. The anterior cutaneous branches comprise the intermediate and medial cutaneous nerves (Fig. 814).

The **intermediate cutaneous nerve** (*ramus cutaneus anterior; middle cutaneous nerve*) pierces the fascia lata (and generally the Sartorius) about 7.5 cm. below the inguinal ligament, and divides into two branches which descend in immediate proximity along the forepart of the thigh, to supply the skin as low as the front of the knee. Here they communicate with the medial cutaneous nerve and the

infrapatellar branch of the saphenous, to form the patellar plexus. In the upper part of the thigh the lateral branch of the intermediate cutaneous communicates with the lumboinguinal branch of the genitofemoral nerve.

The **medial cutaneous nerve** (*ramus cutaneus anterior; internal cutaneous nerve*) passes obliquely across the upper part of the sheath of the femoral artery, and divides in front, or at the medial side of that vessel, into two branches, an anterior and a posterior. The **anterior branch** runs downward on the Sartorius, perforates the fascia lata at the lower third of the thigh, and divides into two branches: one supplies the integument as low down as the medial side of the knee; the other crosses to the lateral side of the patella, communicating in its course with the infrapatellar branch of the saphenous nerve. The **posterior branch** descends along the medial border of the Sartorius muscle to the knee, where it pierces the fascia lata, communicates with the saphenous nerve, and gives off several cutaneous branches. It then passes down to supply the integument of the medial side of the leg. Beneath the fascia lata, at the lower border of the Adductor longus, it joins to form a plexiform net-work (**subsartorial plexus**) with branches of the saphenous and obturator nerves. When the communicating branch from the obturator nerve is large and continued to the integument of the leg, the posterior branch of the medial cutaneous is small, and terminates in the plexus, occasionally giving off a few cutaneous filaments. The medial cutaneous nerve, before dividing, gives off a few filaments, which pierce the fascia lata, to supply the integument of the medial side of the thigh, accompanying the long saphenous vein. One of these filaments passes through the saphenous opening; a second becomes subcutaneous about the middle of the thigh; a third pierces the fascia at its lower third.

**MUSCULAR BRANCHES** (*rami musculares*).—The **nerve to the Pectineus arises** immediately below the inguinal ligament, and passes behind the femoral sheath to enter the anterior surface of the muscle; it is often duplicated. The **nerve to the Sartorius arises** in common with the intermediate cutaneous.

The posterior division of the femoral nerve gives off the saphenous nerve, and muscular and articular branches.

The **Saphenous Nerve** (*n. saphenus; long or internal saphenous nerve*) (Fig. 816) is the largest cutaneous branch of the femoral nerve. It approaches the femoral artery where this vessel passes beneath the Sartorius, and lies in front of it, behind the aponeurotic covering of the adductor canal, as far as the opening in the lower part of the Adductor magnus. Here it quits the artery, and emerges from behind the lower edge of the aponeurotic covering of the canal; it descends vertically along the medial side of the knee behind the Sartorius, pierces the fascia lata, between the tendons of the Sartorius and Gracilis, and becomes subcutaneous. The nerve then passes along the tibial side of the leg, accompanied by the great saphenous vein, descends behind the medial border of the tibia, and, at the lower third of the leg, divides into two branches: one continues its course along the margin of the tibia, and ends at the ankle; the other passes in front of the ankle, and is distributed to the skin on the medial side of the foot, as far as the ball of the great toe, communicating with the medial branch of the superficial peroneal nerve.

**BRANCHES.**—The saphenous nerve, about the middle of the thigh, gives off a branch which joins the subsartorial plexus.

At the medial side of the knee it gives off a large **infrapatellar branch**, which pierces the Sartorius and fascia lata, and is distributed to the skin in front of the patella. This nerve communicates above the knee with the anterior cutaneous branches of the femoral nerve; below the knee, with other branches of the saphenous; and, on the lateral side of the joint, with branches of the lateral femoral cutaneous nerve, forming a plexiform net-work, the **plexus patellae**. The infrapatellar branch is occasionally small, and ends by joining the anterior cutaneous branches of the femoral, which supply its place in front of the knee.

Below the knee, the branches of the saphenous nerve are distributed to the skin of the front and medial side of the leg, communicating with the cutaneous branches of the femoral, or with filaments from the obturator nerve.

The **muscular branches** supply the four parts of the Quadriceps femoris. The branch to the Rectus femoris enters the upper part of the deep surface of the muscle, and supplies a filament to the hip-joint. The branch to the Vastus lateralis, of large size, accompanies the descending branch of the lateral femoral circumflex artery to the lower part of the muscle. It gives off an articular filament to the knee-joint. The branch to the Vastus medialis descends lateral to the femoral vessels in company with the saphenous nerve. It enters the muscle about its middle, and gives off a filament, which can usually be traced downward, on the surface of the muscle, to the knee-joint. The branches to the Vastus intermedius, two or three in number, enter the anterior surface of the muscle about the middle of the thigh; a filament from one of these descends through the muscle to the Articularis genu and the knee-joint. The **articular branch to the hip-joint** is derived from the nerve to the Rectus femoris.

The **articular branches to the knee-joint** are three in number. One, a long slender filament, is derived from the nerve to the Vastus lateralis; it penetrates the capsule of the joint on its anterior aspect. Another, derived from the nerve to the Vastus medialis, can usually be traced downward on the surface of this muscle to near the joint; it then penetrates the muscular fibres, and accompanies the articular branch of the highest genicular artery, pierces the medial side of the articular capsule, and supplies the synovial membrane. The third branch is derived from the nerve to the Vastus intermedius.

#### **The Sacral and Coccygeal Nerves (Nn. Sacrales et Coccygeus).**

The **anterior divisions of the sacral and coccygeal nerves** (*rami anteriores*) form the sacral and pudendal plexuses. The anterior divisions of the upper four sacral nerves enter the pelvis through the anterior sacral foramina, that of the fifth between the sacrum and coccyx, while that of the coccygeal nerve curves forward below the rudimentary transverse process of the first piece of the coccyx. The first and second sacral nerves are large; the third, fourth, and fifth diminish progressively from above downward. Each receives a gray ramus communicans from the corresponding ganglion of the sympathetic trunk, while from the third, and frequently from the second and the fourth sacral nerves, a white ramus communicans is given to the pelvic plexuses of the sympathetic.

**The Sacral Plexus** (*plexus sacralis*) (Fig. 817).—The sacral plexus is formed by the lumbosacral trunk, the anterior division of the first, and portions of the anterior divisions of the second and third sacral nerves.

The lumbosacral trunk comprises the whole of the anterior division of the fifth and a part of that of the fourth lumbar nerve; it appears at the medial margin of the Psoas major and runs downward over the pelvic brim to join the first sacral nerve. The anterior division of the third sacral nerve divides into an upper and a lower branch, the former entering the sacral and the latter the pudendal plexus.

The nerves forming the sacral plexus converge toward the lower part of the greater sciatic foramen, and unite to form a flattened band, from the anterior and posterior surfaces of which several branches arise. The band itself is continued as the **sciatic nerve**, which splits on the back of the thigh into the **tibial** and **common peroneal nerves**; these two nerves sometimes arise separately from the plexus, and in all cases their independence can be shown by dissection.

**Relations.**—The sacral plexus lies on the back of the pelvis between the Piriformis and the pelvic fascia (Fig. 818); in front of it are the hypogastric vessels, the ureter and the sigmoid colon. The superior gluteal vessels run between the lumbosacral trunk and the first sacral nerve, and the inferior gluteal vessels between the second and third sacral nerves.

All the nerves entering the plexus, with the exception of the third sacral, split into ventral and dorsal divisions, and the nerves arising from these are as follows:



	Ventral divisions.	Dorsal divisions.
Nerve to Quadratus femoris and Gemellus inferior	} 4, 5 L, 1 S.	
Nerve to Obturator internus and Gemellus superior		
Nerve to Piriformis	} 5 L, 1, 2 S.	(1) 2 S.
Superior gluteal		4, 5 L, 1 S.
Inferior gluteal		5 L, 1, 2 S.
Posterior femoral cutaneous	2, 3 S.	1, 2 S.
Sciatic	Tibial	4, 5 L, 1, 2 S.
	Common peroneal	




FIG. 817.—Plan of sacral and pudendal plexuses.

The **Nerve to the Quadratus Femoris and Gemellus Inferior** arises from the ventral divisions of the fourth and fifth lumbar and first sacral nerves: it leaves the pelvis through the greater sciatic foramen, below the Piriformis, and runs down in front of the sciatic nerve, the Gemelli, and the tendon of the Obturator internus, and enters the anterior surfaces of the muscles; it gives an articular branch to the hip-joint.

The **Nerve to the Obturator Internus and Gemellus Superior** arises from the ventral divisions of the fifth lumbar and first and second sacral nerves. It leaves the pelvis through the greater sciatic foramen below the Piriformis, and gives off the branch to the Gemellus superior, which enters the upper part of the posterior surface of the muscle. It then crosses the ischial spine, reënters the pelvis through the lesser sciatic foramen, and pierces the pelvic surface of the Obturator internus.




FIG. 818.—Dissection of side wall of pelvis showing sacral and pudendal plexuses.

The **Nerve to the Piriformis** arises from the dorsal division of the second sacral nerve, or the dorsal divisions of the first and second sacral nerves, and enters the anterior surface of the muscle; this nerve may be double.

The **Superior Gluteal Nerve** (*n. gluteus superior*) arises from the dorsal divisions of the fourth and fifth lumbar and first sacral nerves: it leaves the pelvis through the greater sciatic foramen above the Piriformis, accompanied by the superior gluteal vessels, and divides into a superior and an inferior branch. The **superior branch** accompanies the upper branch of the deep division of the superior gluteal artery and ends in the Gluteus minimus. The **inferior branch** runs with the lower branch of the deep division of the superior gluteal artery across the Gluteus

minimus; it gives filaments to the Glutaei medius and minimus, and ends in the Tensor fasciae latae.

The **Inferior Gluteal Nerve** (*n. glutaeus inferior*) arises from the dorsal divisions of the fifth lumbar and first and second sacral nerves: it leaves the pelvis through the greater sciatic foramen, below the Piriformis, and divides into branches which enter the deep surface of the Glutaeus maximus.

The **Posterior Femoral Cutaneous Nerve** (*n. cutaneus femoralis posterior; small sciatic nerve*) is distributed to the skin of the perineum and posterior surface of the thigh and leg. It arises partly from the dorsal divisions of the first and second, and from the ventral divisions of the second and third sacral nerves, and issues from the pelvis through the greater sciatic foramen below the Piriformis. It then descends beneath the Glutaeus maximus with the inferior gluteal artery, and runs down the back of the thigh beneath the fascia lata, and over the long head of the Biceps femoris to the back of the knee; here it pierces the deep fascia and accompanies the small saphenous vein to about the middle of the back of the leg, its terminal twigs communicating with the sural nerve.

Its branches are all cutaneous, and are distributed to the gluteal region, the perineum, and the back of the thigh and leg.

The **gluteal branches** (*nn. clunium inferiores*), three or four in number, turn upward around the lower border of the Glutaeus maximus, and supply the skin covering the lower and lateral part of that muscle.

The **perineal branches** (*rami perineales*) are distributed to the skin at the upper and medial side of the thigh. One long perineal branch, **inferior pudendal** (*long scrotal nerve*), curves forward below and in front of the ischial tuberosity, pierces the fascia lata, and runs forward beneath the superficial fascia of the perineum to the skin of the scrotum in the male, and of the labium majus in the female. It communicates with the inferior hemorrhoidal and posterior scrotal nerves.

The **branches to the back of the thigh and leg** consist of numerous filaments derived from both sides of the nerve, and distributed to the skin covering the back and medial side of the thigh, the popliteal fossa, and the upper part of the back of the leg (Fig. 819).

The **Sciatic** (*n. ischiadicus; great sciatic nerve*) (Fig. 821) supplies nearly the whole of the skin of the leg, the muscles of the back of the thigh, and those of the leg and foot. It is the largest nerve in the body, measuring 2 cm. in breadth, and is the continuation of the flattened band of the sacral plexus. It passes out of the pelvis through the greater sciatic foramen, below the Piriformis muscle. It descends between the greater trochanter of the femur and the tuberosity of the ischium, and along the back of the thigh to about its lower third, where it divides into two large branches, the tibial and common peroneal nerves. This division may take place at any point between the sacral plexus and the lower third of the thigh. When it occurs at the plexus, the common peroneal nerve usually pierces the Piriformis.

In the upper part of its course the nerve rests upon the posterior surface of the ischium, the nerve to the Quadratus femoris, the Obturator internus and Gemelli, and the Quadratus femoris; it is accompanied by the posterior femoral cutaneous nerve and the inferior gluteal artery, and is covered by the Glutaeus maximus. Lower down, it lies upon the Adductor magnus, and is crossed obliquely by the long head of the Biceps femoris.

The nerve gives off articular and muscular branches.

The **articular branches** (*rami articulares*) arise from the upper part of the nerve and supply the hip-joint, perforating the posterior part of its capsule; they are sometimes derived from the sacral plexus.

The **muscular branches** (*rami musculares*) are distributed to the Biceps femoris, Semitendinosus, Semimembranosus, and Adductor magnus. The nerve to the short head of the Biceps femoris comes from the common peroneal part of the sciatic,

while the other muscular branches *arise* from the tibial portion, as may be seen in those cases where there is a high division of the sciatic nerve.




FIG. 819.—Cutaneous nerves of right lower extremity. Posterior view.




FIG. 820.—Diagram of the segmental distribution of the cutaneous nerves of the right lower extremity. Posterior view.

The **Tibial Nerve** (*n. tibialis*; *internal popliteal nerve*) (Fig. 821) the larger of the two terminal branches of the sciatic, *arises* from the anterior branches of the fourth and fifth lumbar and first, second, and third sacral nerves. It descends along the back of the thigh and through the middle of the popliteal fossa, to the lower part of the Popliteus muscle, where it passes with the popliteal artery beneath the arch of the Soleus. It then runs along the back of the leg with the posterior tibial vessels to the interval between the medial malleolus and the heel, where it divides beneath the lacinate ligament into the medial and lateral plantar nerves. In the thigh it is overlapped by the hamstring muscles above, and then becomes more superficial, and lies lateral to, and some distance from, the popliteal vessels; opposite the knee-joint, it is in close relation with these vessels, and crosses to the medial side of the artery. In the leg it is covered in the upper part of its course by the muscles of the calf; lower down by the skin, the superficial and deep fasciæ. It is placed on the medial side of the posterior tibial artery, but soon crosses that vessel and descends on its lateral side as far as the ankle. In the lower third of the leg it runs parallel with the medial margin of the tendo calcaneus.

The **branches** of this nerve are: **articular**, **muscular**, **medial sural cutaneous**, **medial calcaneal**, **medial and lateral plantar**.

**Articular branches** (*rami articulares*), usually three in number, supply the knee-joint; two of these accompany the superior and inferior medial genicular arteries; and a third, the middle genicular artery. Just above the bifurcation of the nerve an articular branch is given off to the ankle-joint.

**Muscular branches** (*rami musculares*), four or five in number, *arise* from the nerve as it lies between the two heads of the Gastrocnemius muscle; they




FIG. 821.—Nerves of the right lower extremity.<sup>1</sup> Posterior view.

<sup>1</sup> N. B.—In this diagram the medial sural cutaneous and peroneal anastomotic are not in their normal position. They have been displaced by the removal of the superficial muscles.



supply that muscle, and the Plantaris, Soleus, and Popliteus. The branch for the Popliteus turns around the lower border and is distributed to the deep surface of the muscle. Lower down, muscular branches *arise* separately or by a common trunk and supply the Soleus, Tibialis posterior, Flexor digitorum longus, and Flexor hallucis longus; the branch to the last muscle accompanies the peroneal artery; that to the Soleus enters the deep surface of the muscle.

The **medial sural cutaneous nerve** (*n. cutaneus surae medialis; n. communicans tibialis*) descends between the two heads of the Gastrocnemius, and, about the middle of the back of the leg, pierces the deep fascia, and unites with the anastomotic ramus of the common peroneal to form the sural nerve (Fig. 819).

The **sural nerve** (*n. suralis; short saphenous nerve*), formed by the junction of the medial sural cutaneous with the peroneal anastomotic branch, passes downward near the lateral margin of the tendo calcaneus, lying close to the small saphenous vein, to the interval between the lateral malleolus and the calcaneus. It runs forward below the lateral malleolus, and is continued as the **lateral dorsal cutaneous nerve** along the lateral side of the foot and little toe, communicating on the dorsum of the foot with the intermediate dorsal cutaneous nerve, a branch of the superficial peroneal. In the leg, its branches communicate with those of the posterior femoral cutaneous.

The **medial calcaneal branches** (*rami calcanei mediales; internal calcaneal branches*) perforate the lacinate ligament, and supply the skin of the heel and medial side of the sole of the foot.

The **medial plantar nerve** (*n. plantaris medialis; internal plantar nerve*) (Fig. 822), the larger of the two terminal divisions of the tibial nerve, accompanies the medial plantar artery. From its origin under the lacinate ligament it passes under cover of the Abductor hallucis, and, appearing between this muscle and the Flexor digitorum brevis, gives off a proper digital plantar nerve and finally divides opposite the bases of the metatarsal bones into three common digital plantar nerves.

**BRANCHES.**—The branches of the medial plantar nerve are: (1) **cutaneous**, (2) **muscular**, (3) **articular**, (4) a **proper digital nerve** to the medial side of the great toe, and (5) three **common digital nerves**.

The **cutaneous branches** pierce the plantar aponeurosis between the Abductor hallucis and the Flexor digitorum brevis and are distributed to the skin of the sole of the foot.

The **muscular branches** supply the Abductor hallucis, the Flexor digitorum brevis, the Flexor hallucis brevis, and the first Lumbricalis; these for the Abductor hallucis and Flexor digitorum brevis arise from the trunk of the nerve near its origin and enter the deep surfaces of the muscles; the branch of the Flexor hallucis brevis springs from the proper digital nerve to the medial side of the great toe, and that for the first Lumbricalis from the first common digital nerve.

The **articular branches** supply the articulations of the tarsus and metatarsus.

The **proper digital nerve of the great toe** (*nn. digitales plantares proprii; plantar digital branches*) supplies the Flexor hallucis brevis and the skin on the medial side of the great toe.

The **three common digital nerves** (*nn. digitales plantares communes*) pass between the divisions of the plantar aponeurosis, and each splits into two proper digital nerves—those of the first common digital nerve supply the adjacent sides of the great and second toes; those of the second, the adjacent sides of the second and third toes; and those of the third, the adjacent sides of the third and fourth toes. The third common digital nerve receives a communicating branch from the lateral plantar nerve; the first gives a twig to the first Lumbricalis. Each proper digital nerve gives off cutaneous and articular filaments; and opposite the last phalanx sends upward a dorsal branch, which supplies the structures around the nail, the continuation of the nerve being distributed to the ball of the toe. It will be

observed that these digital nerves are similar in their distribution to those of the median nerve in the hand.

The **Lateral Plantar Nerve** (*n. plantaris lateralis*; *external plantar nerve*) (Fig. 822) supplies the skin of the fifth toe and lateral half of the fourth, as well as most of the deep muscles, its distribution being similar to that of the ulnar nerve in the hand. It passes obliquely forward with the lateral plantar artery to the lateral side of the foot, lying between the Flexor digitorum brevis and Quadratus plantae; and, in the interval between the former muscle and the abductor digiti quinti, divides into a superficial and a deep branch. Before its division, it supplies the Quadratus plantae and Abductor digiti quinti.

The **superficial branch** (*ramus superficialis*) splits into a proper and a common digital nerve; the proper digital nerve supplies the lateral side of the little toe, the Flexor digiti quinti brevis, and the two Interossei of the fourth intermetatarsal space; the common digital nerve communicates with the third common digital branch of the medial plantar nerve and divides into two proper digital nerves which supply the adjoining sides of the fourth and fifth toes.




FIG. 822.—The plantar nerves.




FIG. 823.—Diagram of the segmental distribution of the cutaneous nerves of the sole of the foot.

The **deep branch** (*ramus profundus*; *muscular branch*) accompanies the lateral plantar artery on the deep surface of the tendons of the Flexor muscles and the Adductor hallucis, and supplies all the Interossei (except those in the fourth metatarsal space), the second, third, and fourth Lumbricales, and the Adductor hallucis.

The **Common Peroneal Nerve** (*n. peronaeus communis*; *external popliteal nerve*; *peroneal nerve*) (Fig. 821), about one-half the size of the tibial, is derived from the dorsal branches of the fourth and fifth lumbar and the first and second sacral nerves. It descends obliquely along the lateral side of the popliteal fossa to the head of the fibula, close to the medial margin of the Biceps femoris muscle. It lies between the tendon of the Biceps femoris and lateral head of the Gastrocnemius muscle, winds around the neck of the fibula, between the Peronaeus longus and the bone, and divides beneath the muscle into the superficial and deep peroneal nerves. Previous to its division it gives off articular and lateral sural cutaneous nerves.

The **articular branches** (*rami articulares*) are three in number; two of these accompany the superior and inferior lateral genicular arteries to the knee; the upper one occasionally *arises* from the trunk of the sciatic nerve. The third (*recurrent*) articular nerve is given off at the point of division of the common peroneal nerve; it ascends with the anterior recurrent tibial artery through the Tibialis anterior to the front of the knee.

The **lateral sural cutaneous nerve** (*n. cutaneus surae lateralis; lateral cutaneous branch*) supplies the skin on the posterior and lateral surfaces of the leg; one branch, the **peroneal anastomotic** (*n. communicans fibularis*), *arises* near the head of the fibula, crosses the lateral head of the Gastrocnemius to the middle of the leg, and joins with the medial sural cutaneous to form the sural nerve. The peroneal anastomotic is occasionally continued down as a separate branch as far as the heel.

The **Deep Peroneal Nerve** (*n. peronaeus profundus; anterior tibial nerve*) (Fig. 816) begins at the bifurcation of the common peroneal nerve, between the fibula and upper part of the Peronaeus longus, passes obliquely forward beneath the Extensor digitorum longus to the front of the interosseous membrane, and comes into relation with the anterior tibial artery above the middle of the leg; it then descends with the artery to the front of the ankle-joint, where it divides into a lateral and a medial terminal branch. It lies at first on the lateral side of the anterior tibial artery, then in front of it, and again on its lateral side at the ankle-joint.

In the leg, the deep peroneal nerve supplies **muscular branches** to the Tibialis anterior, Extensor digitorum longus, Peronaeus tertius, and Extensor hallucis proprius, and an **articular branch** to the ankle-joint.

The **lateral terminal branch** (*external or tarsal branch*) passes across the tarsus, beneath the Extensor digitorum brevis, and, having become enlarged like the dorsal interosseous nerve at the wrist, supplies the Extensor digitorum brevis. From the enlargement three minute **interosseous branches** are given off, which supply the tarsal joints and the metatarsophalangeal joints of the second, third, and fourth toes. The first of these sends a filament to the second Interosseus dorsalis muscle.

The **medial terminal branch** (*internal branch*) accompanies the dorsalis pedis artery along the dorsum of the foot, and, at the first interosseous space, divides into two **dorsal digital nerves** (*nn. digitales dorsales hallucis lateralis et digiti secundi medialis*) which supply the adjacent sides of the great and second toes, communicating with the medial dorsal cutaneous branch of the superficial peroneal nerve. Before it divides it gives off to the first space an **interosseous branch** which supplies the metatarsophalangeal joint of the great toe and sends a filament to the first Interosseus dorsalis muscle.

The **Superficial Peroneal Nerve** (*n. peronaeus superficialis; musculocutaneous nerve*) (Fig. 816) supplies the Peronei longus and brevis and the skin over the greater part of the dorsum of the foot. It passes forward between the Peronaei and the Extensor digitorum longus, pierces the deep fascia at the lower third of the leg, and divides into a medial and an intermediate dorsal cutaneous nerve. In its course between the muscles, the nerve gives off muscular branches to the Peronaei longus and brevis, and cutaneous filaments to the integument of the lower part of the leg.

The **medial dorsal cutaneous nerve** (*n. cutaneus dorsalis medialis; internal dorsal cutaneous branch*) passes in front of the ankle-joint, and divides into two **dorsal digital branches**, one of which supplies the medial side of the great toe, the other, the adjacent side of the second and third toes. It also supplies the integument of the medial side of the foot and ankle, and communicates with the saphenous nerve, and with the deep peroneal nerve (Fig. 814).

The **intermediate dorsal cutaneous nerve** (*n. cutaneus dorsalis intermedius; external dorsal cutaneous branch*), the smaller, passes along the lateral part of the dorsum of the foot, and divides into **dorsal digital branches**, which supply the contiguous

sides of the third and fourth, and of the fourth and fifth toes. It also supplies the skin of the lateral side of the foot and ankle, and communicates with the sural nerve (Fig. 814).

The branches of the superficial peroneal nerve supply the skin of the dorsal surfaces of all the toes excepting the lateral side of the little toe, and the adjoining sides of the great and second toes, the former being supplied by the lateral dorsal cutaneous nerve from the sural nerve, and the latter by the medial branch of the deep peroneal nerve. Frequently some of the lateral branches of the superficial peroneal are absent, and their places are then taken by branches of the sural nerve.

**The Pudendal Plexus** (*plexus pudendus*) (Fig. 817).—The pudendal plexus is not sharply marked off from the sacral plexus, and as a consequence some of the branches which spring from it may *arise* in conjunction with those of the sacral plexus. It lies on the posterior wall of the pelvis, and is usually formed by branches from the anterior divisions of the second and third sacral nerves, the whole of the anterior divisions of the fourth and fifth sacral nerves, and the coccygeal nerve.

It gives off the following branches:

Perforating cutaneous . . . . .	2, 3 S.
Pudendal . . . . .	2, 3, 4 S.
Visceral . . . . .	3, 4 S.
Muscular . . . . .	4 S.
Anococcygeal . . . . .	4, 5 S. and Cocc.

**The Perforating Cutaneous Nerve** (*n. clunium inferior medialis*) usually *arises* from the posterior surface of the second and third sacral nerves. It pierces the lower part of the sacrotuberous ligament, and winding around the inferior border of the Glutæus maximus supplies the skin covering the medial and lower parts of that muscle.

The perforating cutaneous nerve may arise from the pudendal or it may be absent; in the latter case its place may be taken by a branch from the posterior femoral cutaneous nerve or by a branch from the third and fourth, or fourth and fifth, sacral nerves.

**The Pudendal Nerve** (*n. pudendus; internal pudic nerve*) derives its fibres from the ventral branches of the second, third, and fourth sacral nerves. It passes between the Piriformis and Coccygeus muscles and leaves the pelvis through the lower part of the greater sciatic foramen. It then crosses the spine of the ischium, and reënters the pelvis through the lesser sciatic foramen. It accompanies the internal pudendal vessels upward and forward along the lateral wall of the ischiorectal fossa, being contained in a sheath of the obturator fascia termed **Alcock's canal**, and divides into two terminal branches, viz., the **perineal nerve**, and the **dorsal nerve of the penis or clitoris**. Before its division it gives off the **inferior hemorrhoidal nerve**.

The **inferior hemorrhoidal nerve** (*n. hæmorrhoidalis inferior*) occasionally *arises* directly from the sacral plexus; it crosses the ischiorectal fossa, with the inferior hemorrhoidal vessels, toward the anal canal and the lower end of the rectum, and is distributed to the Sphincter ani externus and to the integument around the anus. Branches of this nerve communicate with the perineal branch of the posterior femoral cutaneous and with the posterior scrotal nerves at the forepart of the perineum.

The **perineal nerve** (*n. perinei*), the inferior and larger of the two terminal branches of the pudendal, is situated below the internal pudendal artery. It accompanies the perineal artery and divides into **posterior scrotal** (or **labial**) and **muscular branches**.

The **posterior scrotal** (or **labial**) branches (*nn. scrotales* (or *labiales*) *posteriores; superficial peroneal nerves*) are two in number, medial and lateral. They pierce the fascia of the urogenital diaphragm, and run forward along the lateral part of the urethral triangle in company with the posterior scrotal branches of the perineal

artery; they are distributed to the skin of the scrotum and communicate with the perineal branch of the posterior femoral cutaneous nerve. These nerves supply the labium majus in the female.

The **muscular branches** are distributed to the Transversus perinaei superficialis, Bulbocavernosus, Ischiocavernosus, and Constrictor urethrae. A branch, the **nerve to the bulb**, given off from the nerve to the Bulbocavernosus, pierces this muscle, and supplies the corpus cavernosum urethrae, ending in the mucous membrane of the urethra.

The **dorsal nerve of the penis** (*n. dorsalis penis*) is the deepest division of the pudendal nerve; it accompanies the internal pudendal artery along the ramus of the ischium; it then runs forward along the margin of the inferior ramus of the pubis, between the superior and inferior layers of the fascia of the urogenital diaphragm. Piercing the inferior layer it gives a branch to the corpus cavernosum penis, and passes forward, in company with the dorsal artery of the penis, between the layers of the suspensory ligament, on to the dorsum of the penis, and ends on the glans penis. In the female this nerve is very small, and supplies the **clitoris** (*n. dorsalis clitoridis*).

The **Visceral Branches** arise from the third and fourth, and sometimes from the second, sacral nerves, and are distributed to the bladder and rectum and, in the female, to the vagina; they communicate with the pelvic plexuses of the sympathetic.

The **Muscular Branches** are derived from the fourth sacral, and supply the Levator ani, Coccygeus, and Sphincter ani externus. The branches to the Levator ani and Coccygeus enter their pelvic surfaces; that to the Sphincter ani externus (perineal branch) reaches the ischiorectal fossa by piercing the Coccygeus or by passing between it and the Levator ani. Cutaneous filaments from this branch supply the skin between the anus and the coccyx.

**Anococcygeal Nerves** (*nn. anococcygei*).—The fifth sacral nerve receives a communicating filament from the fourth, and unites with the coccygeal nerve to form the **coccygeal plexus**. From this plexus the anococcygeal nerves take origin; they consist of a few fine filaments which pierce the sacrotuberous ligament to supply the skin in the region of the coccyx.

**Applied Anatomy**.—The lumbar plexus passes through the Psoas major, and therefore in psoas abscess any or all of its branches may be irritated, causing severe pain in the part to which the irritated nerves are distributed. The genitofemoral nerve is the one which is most frequently implicated. This nerve is also of importance as it is concerned in one of the principal superficial reflexes employed in the investigation of diseases of the medulla spinalis. If the skin over the medial side of the thigh just below the inguinal ligament (the part supplied by the lumboinguinal nerve) be gently tickled in a male child, the testes will be drawn upward, through the action of the Cremaster muscle, supplied by the lumboinguinal nerve. The same result may sometimes be noticed in adults, and can almost always be produced by severe stimulation. This reflex, when present, shows that the portion of the cord from which the first and second lumbar nerves are derived is in a normal condition.

The femoral nerve is in danger of being injured in fractures of the lesser pelvis, since the fracture most commonly takes place through the superior ramus of the pubis, at or near the point where this nerve crosses the bone. It is also liable to be pressed upon, and its functions impaired, by some tumors growing in the pelvis. Moreover, on account of its superficial position, it is exposed to injury in wounds and stabs in the groin. Its central origin is often affected in cases of infantile paralysis. When this nerve is paralyzed, the patient is unable to flex his hip completely, on account of the paralysis of the Iliacus; or to extend the knee on the thigh, on account of paralysis of the Quadriceps femoris; there is complete paralysis of the Sartorius, and partial paralysis of the Pectineus. There is loss of sensation down the front and medial side of the thigh, except in that part supplied by the lumboinguinal and ilioinguinal nerves. There is also loss of sensation down the medial side of the leg and foot as far as the ball of the great toe.

The obturator nerve is rarely paralyzed alone, but occasionally in association with the femoral. The principal interest attached to it is in connection with its supply to the knee; pain in the knee being symptomatic of many diseases in which the trunk of this nerve, or one of its branches, is irritated. Thus it is well known that in the earlier stages of hip-joint disease the patient does not always complain of pain in that articulation, but on the medial side of the knee, or in the knee-joint itself, both of these articulations being supplied by the obturator nerve, the final



distribution of the nerve being to the knee-joint. Again, the same thing occurs in sacroiliac disease; pain is complained of in the knee-joint, or on its medial side. The obturator nerve is in close relationship with the sacroiliac articulation, passing over it, and, according to some anatomists, distributing filaments to it. Further, in cancer of the sigmoid colon, and even in cases where masses of hardened feces are impacted in this portion of the gut, pain is complained of in the knee. The left obturator nerve lies beneath the sigmoid colon, and is readily pressed upon and irritated when disease exists in this part of the intestine. Finally, pain in the knee forms an important diagnostic sign in obturator hernia. The hernial protrusion as it passes out through the opening in the obturator membrane presses upon the nerve and causes pain in the parts supplied by its peripheral filaments. When the obturator nerve is paralyzed, the patient is unable to press his knees together or to cross one leg over the other, on account of paralysis of the Adductor muscles. Rotation outward of the thigh is impaired from paralysis of the Obturator externus. Sometimes there is loss of sensation in the upper half of the medial side of the thigh.

The sciatic nerve is liable to be pressed upon by various forms of pelvic tumor, giving rise to pain along its trunk, to which the term *sciatica* is applied. Tumors growing from the pelvic viscera, especially advanced cancer of the rectum, aneurisms of some of the branches of the hypogastric artery, calculus in the bladder when of large size, accumulation of feces in the rectum, may all cause pressure on the nerve inside the pelvis, and give rise to *sciatica*. Outside the pelvis violent movements of the hip-joint, exostoses or other tumors growing from the margin of the greater sciatic foramen, may also give rise to the same condition. Most cases of *sciatica*, however, are due to neuritis of the sciatic nerve from exposure to cold, and it occurs more often in men than in women, in the latter half of life, and often in association with rheumatism, gout, or diabetes mellitus. The inflamed nerve is often sensitive to pressure, particularly in certain "tender spots," e. g., near the posterior iliac spine, at the sciatic notch, about the middle of the back of the thigh, in the popliteal fossa, below the head of the fibula, behind the malleoli, on the dorsum of the foot, and pain is felt whenever extension of the leg is attempted, and the nerve is stretched. Paralysis of the sciatic nerve is rarely complete; when the lesion occurs high up there is palsy of the Biceps femoris, Semimembranosus, and Semitendinosus, and of the muscles below the knee. If the lesion be lower down, there is loss of motion in all the muscles below the knee, and loss of sensation in the same situation, except the upper half of the back of the leg, which is supplied by the posterior femoral cutaneous, and in the upper half of the medial side of the leg, when the communicating branch of the obturator is large (see p. 980). Lesions of the common peroneal nerve cause paralysis of the Tibialis anterior, the Peronei, the long Extensors of the toes, and the short Extensor on the dorsum of the foot. "Foot drop" follows, dorsal flexion of the toes and abduction of the foot becoming impossible. Later on talipes results, largely by the action of gravity or by the weight of the superincumbent bedclothes when the patient lies in bed, aided by the contracture of the unopposed posterior crural group of muscles.

The sciatic nerve has been frequently cut down upon and stretched, or has been acupunctured, for the relief of *sciatica*. In order to define it on the surface, a point is taken at the junction of the middle and lower thirds of a line stretching from the posterior superior spine of the ilium to the lateral part of the ischial tuberosity, and a line drawn from this to the middle of the upper part of the popliteal fossa. The line must be slightly curved with its convexity outward, and as it passes downward to the lower border of the Gluteus maximus is slightly nearer to the ischial tuberosity than to the greater trochanter, as it crosses a line drawn between these two points. The operation of stretching the sciatic nerve is performed by making an incision over the course of the nerve beneath the fold of the buttock. The skin, superficial structures, and deep fascia having been divided, the hamstrings are defined, and pulled apart with retractors. The nerve will be found lying on the Adductor magnus and covered by the Biceps femoris. It is to be separated from the surrounding structures, hooked up with the finger, and stretched by steady and continuous traction for two or three minutes. The sciatic nerve may also be stretched by what is known as the "dry" plan. The patient is laid on his back, the foot is extended, the leg flexed on the thigh, and the thigh strongly flexed on the abdomen. While the thigh is maintained in this position, the leg is forcibly extended to its full extent, and the foot as fully flexed on the leg.

The position of the common peroneal nerve, close behind the tendon of the Biceps femoris, on the lateral side of the popliteal fossa, should be remembered in subcutaneous division of the tendon. After the tendon is divided, the common peroneal nerve rises up as a cord and might be mistaken for a small undivided portion of the tendon. Where this nerve winds around the neck of the fibula, it is also liable to be severed accidentally if its exact situation is not kept in mind, and especial care must be used when dealing with sinuses leading down to carious bone in this situation. Section of the nerve results in complete "foot drop" from paralysis of the anterior tibial group of muscles and inversion of the foot from the unopposed action of the Tibialis posterior, the Peronei being paralyzed, together with anesthesia of the parts supplied by the nerve, and, owing to loss of nutrition, the limb frequently becomes blue and cold, and may develop "trophic" sores.

two branches, which lie one on the lateral and the other on the medial side of that vessel.

The **lateral branch**, the larger of the two, distributes filaments to the internal carotid artery, and forms the **internal carotid plexus**.

The **medial branch** also distributes filaments to the internal carotid artery, and, continuing onward, forms the **cavernous plexus**.

The **internal carotid plexus** (*plexus caroticus internus; carotid plexus*) is situated on the lateral side of the internal carotid artery, and in the plexus there occasionally exists a small gangliform swelling, the **carotid ganglion**, on the under surface of the artery. The internal carotid plexus communicates with the semilunar ganglion, the abducent nerve, and the sphenopalatine ganglion; it distributes filaments to the wall of the carotid artery, and also communicates with the tympanic branch of the glossopharyngeal nerve.

The communicating branches with the abducent nerve consist of one or two filaments which join that nerve as it lies upon the lateral side of the internal carotid artery. The communication with the sphenopalatine ganglion is effected by a branch, the **deep petrosal**, given off from the plexus on the lateral side of the artery; this branch passes through the cartilage filling up the foramen lacerum, and joins the greater superficial petrosal to form the nerve of the pterygoid canal (*Vidian nerve*), which passes through the pterygoid canal to the sphenopalatine ganglion. The communication with the tympanic branch of the glossopharyngeal nerve is effected by the **caroticotympanic**, which may consist of two or three delicate filaments.

The **cavernous plexus** (*plexus cavernosus*) is situated below and medial to that part of the internal carotid artery which is placed by the side of the sella turcica in the cavernous sinus, and is formed chiefly by the medial division of the internal carotid nerve. It communicates with the oculomotor, the trochlear, the ophthalmic and the abducent nerves, and with the ciliary ganglion, and distributes filaments to the wall of the internal carotid artery. The branch of communication with the oculomotor nerve joins that nerve at its point of division; the branch to the trochlear nerve joins it as it lies on the lateral wall of the cavernous sinus; other filaments are connected with the under surface of the ophthalmic nerve; and a second filament joins the abducent nerve.

The **filaments of connection** with the ciliary ganglion *arise* from the anterior part of the cavernous plexus and enter the orbit through the superior orbital fissure; they may join the nasociliary branch of the ophthalmic nerve, or be continued forward as a separate branch.

The **terminal filaments** from the internal carotid and cavernous plexuses are prolonged as plexuses around the anterior and middle cerebral arteries and the ophthalmic artery; along the former vessels, they may be traced to the pia mater; along the latter, into the orbit, where they accompany each of the branches of the vessel. The filaments prolonged on to the anterior communicating artery connect the sympathetic nerves of the right and left sides.

#### THE CERVICAL PORTION OF THE SYMPATHETIC SYSTEM (PARS CERVICALIS S. SYMPATHICI).

The **cervical portion** of the sympathetic trunk consists of three ganglia, distinguished, according to their positions, as the **superior, middle, and inferior ganglia**, connected by intervening cords. This portion receives no white rami communicantes from the cervical spinal nerves; its spinal fibres are derived from the white rami of the upper thoracic nerves, and enter the corresponding thoracic ganglia of the sympathetic trunk, through which they ascend into the neck.

The **superior cervical ganglion** (*ganglion cervicale superius*), the largest of the three, is placed opposite the second and third cervical vertebræ. It is of a reddish-gray color, and usually fusiform in shape; sometimes broad and flattened, and occasionally constricted at intervals; it is believed to be formed by the coalescence of four ganglia, corresponding to the upper four cervical nerves. It is in relation, in *front*, with the sheath of the internal carotid artery and internal jugular vein; in *behind*, with the Longus capitis muscle. (*Rectus Cap. Ant.*)

Its branches may be divided into **inferior, lateral, medial, and anterior**.

The **Inferior Branch** communicates with the middle cervical ganglion.

The **Lateral Branches** (*external branches*) consist of gray rami communicantes to the upper four cervical nerves and to certain of the cerebral nerves. Sometimes the branch to the fourth cervical nerve may come from the trunk connecting the upper and middle cervical ganglia. The branches to the cerebral nerves consist of delicate filaments, which run to the ganglion nodosum of the vagus, and to the hypoglossal nerve. A filament, the **jugular nerve**, passes upward to the base of the skull, and divides to join the petrous ganglion of the glossopharyngeal, and the jugular ganglion of the vagus.

The **Medial Branches** (*internal branches*) are peripheral, and are the **laryngopharyngeal branches** and the **superior cardiac nerve**.

The **laryngopharyngeal branches** (*rami laryngopharyngei*) pass to the side of the pharynx, where they join with branches from the glossopharyngeal, vagus, and external laryngeal nerves to form the **pharyngeal plexus**.

The **superior cardiac nerve** (*n. cardiacus superior*) arises by two or more branches from the superior cervical ganglion, and occasionally receives a filament from the trunk between the first and second cervical ganglia. It runs down the neck behind the common carotid artery, and in front of the Longus colli muscle; and crosses in front of the inferior thyroid artery, and recurrent nerve. The course of the nerves on the two sides then differ. The **right nerve**, at the root of the neck, passes either in front of or behind the subclavian artery, and along the innominate artery to the back of the arch of the aorta, where it joins the deep part of the cardiac plexus. It is connected with other branches of the sympathetic; about the middle of the neck it receives filaments from the external laryngeal nerve; lower down, one or two twigs from the vagus; and as it enters the thorax it is joined by a filament from the recurrent nerve. Filaments from the nerve communicate with the thyroid branches from the middle cervical ganglion. The **left nerve**, in the thorax, runs in front of the left common carotid artery and across the left side of the arch of the aorta, to the superficial part of the cardiac plexus.

The **Anterior Branches** (*nn. carotici externi*) ramify upon the common carotid artery and upon the external carotid artery and its branches, forming around each a delicate plexus, on the nerves composing which small ganglia are occasionally found. The plexuses accompanying some of these arteries have important communications with other nerves. That surrounding the external maxillary artery communicates with the submaxillary ganglion by a filament; and that accompanying the middle meningeal artery sends an offset to the otic ganglion, and a second, the **external petrosal nerve**, to the genicular ganglion of the facial nerve.

The **middle cervical ganglion** (*ganglion cervicale medium*) is the smallest of the three cervical ganglia, and is occasionally wanting. It is placed opposite the sixth cervical vertebra, usually in front of, or close to, the inferior thyroid artery. It is probably formed by the coalescence of two ganglia corresponding to the fifth and sixth cervical nerves.

It sends gray rami communicantes to the fifth and sixth cervical nerves, and gives off the middle cardiac nerve.

The **Middle Cardiac Nerve** (*n. cardiacus medius; great cardiac nerve*), the largest of the three cardiac nerves, arises from the middle cervical ganglion, or from the

trunk between the middle and inferior ganglia. On the right side it descends behind the common carotid artery, and at the root of the neck runs either in front of or behind the subclavian artery; it then descends on the trachea, receives a few filaments from the recurrent nerve, and joins the right half of the deep part of the cardiac plexus. In the neck, it communicates with the superior cardiac and recurrent nerves. On the left side, the middle cardiac nerve enters the chest between the left carotid and subclavian arteries, and joins the left half of the deep part of the cardiac plexus.

The **inferior cervical ganglion** (*ganglion cervicale inferius*) is situated between the base of the transverse process of the last cervical vertebra and the neck of the first rib, on the medial side of the costocervical artery. Its form is irregular; it is larger in size than the preceding, and is frequently fused with the first thoracic ganglion. It is probably formed by the coalescence of two ganglia which correspond to the seventh and eighth cervical nerves. It is connected to the middle cervical ganglion by two or more cords, one of which forms a loop around the subclavian artery and supplies offsets to it. This loop is named the **ansa subclavia** (*Vieussenii*).

The ganglion sends gray rami communicantes to the seventh and eighth cervical nerves.

It gives off the inferior cardiac nerve, and offsets to bloodvessels.

The **inferior cardiac nerve** (*n. cardiacus inferior*) arises from either the inferior cervical or the first thoracic ganglion. It descends behind the subclavian artery and along the front of the trachea, to join the deep part of the cardiac plexus. It communicates freely behind the subclavian artery with the recurrent nerve and the middle cardiac nerve.

The **offsets to bloodvessels** form plexuses on the subclavian artery and its branches. The plexus on the vertebral artery is continued on to the basilar, posterior cerebral, and cerebellar arteries. The plexus on the inferior thyroid artery accompanies the artery to the thyroid gland, and communicates with the recurrent and external laryngeal nerves, with the superior cardiac nerve, and with the plexus on the common carotid artery.

#### THE THORACIC PORTION OF THE SYMPATHETIC SYSTEM (PARS THORACALIS S. SYMPATHICI) (Fig. 825).

The thoracic portion of the sympathetic trunk consists of a series of ganglia, which usually correspond in number to that of the vertebræ; but, on account of the occasional coalescence of two ganglia, their number is uncertain. The thoracic ganglia rest against the heads of the ribs, and are covered by the costal pleura; the last two, however, are more anterior than the rest, and are placed on the sides of the bodies of the eleventh and twelfth thoracic vertebræ. The ganglia are small in size, and of a grayish color. The first, larger than the others, is of an elongated form, and frequently blended with the inferior cervical ganglion. They are connected together by the intervening portions of the trunk.

Two rami communicantes, a white and a gray, connect each ganglion with its corresponding spinal nerve.

The *branches from the upper five ganglia* are very small; they supply filaments to the thoracic aorta and its branches. Twigs from the second, third, and fourth ganglia enter the posterior pulmonary plexus.

The *branches from the lower seven ganglia* are large, and white in color; they distribute filaments to the aorta, and unite to form the greater, the lesser, and the lowest splanchnic nerves.

The **greater splanchnic nerve** (*n. splanchnicus major; great splanchnic nerve*) is white in color, firm in texture, and of a considerable size; it is formed by branches

from the fifth to the ninth or tenth thoracic ganglia, but the fibres in the higher roots may be traced upward in the sympathetic trunk as far as the first or second thoracic ganglion. It descends obliquely on the bodies of the vertebræ, perforates the crus of the Diaphragma, and ends in the cœliac ganglion. A ganglion (**ganglion splanchnicum**) exists on this nerve opposite the eleventh or twelfth thoracic vertebra.




FIG. 825.—Thoracic portion of the sympathetic trunk.

The **lesser splanchnic nerve** (*n. splanchnicus minor*) is formed by filaments from the ninth and tenth, and sometimes the eleventh thoracic ganglia, and from the cord between them. It pierces the Diaphragma with the preceding nerve, and joins the aorticorenal ganglion.

The **lowest splanchnic nerve** (*n. splanchnicus imus*; *least splanchnic nerve*) arises from the last thoracic ganglion, and, piercing the Diaphragma, ends in the renal plexus.



A striking analogy exists between the splanchnic and the cardiac nerves. The cardiac nerves are three in number; they arise from all three cervical ganglia,




FIG. 826.—Abdominal portion of the sympathetic trunk, with the celiac and hypogastric plexuses. (After Hanle.)

and are distributed to a large and important organ in the thoracic cavity. The splanchnic nerves, also three in number, are connected probably with all the thoracic ganglia, and are distributed to important organs in the abdominal cavity.

**THE ABDOMINAL PORTION OF THE SYMPATHETIC SYSTEM (PARS ABDOMINALIS S. SYMPATHICI; LUMBAR PORTION OF GANGLIATED CORD) (Fig. 826).**

The abdominal portion of the sympathetic trunk is situated in front of the vertebral column, along the medial margin of the Psoas major. It consists usually of four lumbar ganglia, connected together by interganglionic cords. It is continuous above with the thoracic portion beneath the medial lumbocostal arch, and below with the pelvic portion behind the common iliac artery. The ganglia are of small size, and placed much nearer the median line than are the thoracic ganglia.

Gray rami communicantes pass from all the ganglia to the lumbar spinal nerves. The first and second, and sometimes the third, lumbar nerves send white rami communicantes to the corresponding ganglia. The rami communicantes are of considerable length, and accompany the lumbar arteries around the sides of the bodies of the vertebræ, passing beneath the fibrous arches from which some of the fibres of the Psoas major arise.

Of the **branches of distribution**, some pass in front of the aorta, and join the aortic plexus; others descend in front of the common iliac arteries, and assist in forming the hypogastric plexus.

**THE PELVIC PORTION OF THE SYMPATHETIC SYSTEM (PARS PELVINA S. SYMPATHICI).**

The pelvic portion of each sympathetic trunk is situated in front of the sacrum, medial to the anterior sacral foramina. It consists of four or five small sacral ganglia, connected together by interganglionic cords, and continuous above with the abdominal portion. Below, the two pelvic sympathetic trunks converge, and end on the front of the coccyx in a small ganglion, the **ganglion impar**.

Gray rami communicantes pass from the ganglia to the sacral and coccygeal nerves. No white rami communicantes are given to this part of the gangliated cord, but the visceral branches which arise from the third and fourth, and sometimes from the second, sacral, and run directly to the pelvic plexuses, are regarded as white rami communicantes.

The **branches of distribution** communicate on the front of the sacrum with the corresponding branches from the opposite side; some, from the first two ganglia, pass to join the pelvic plexus, and others form a plexus, which accompanies the middle sacral artery and sends filaments to the **glomus coccygeum** (*coccygeal body*).

**THE GREAT PLEXUSES OF THE SYMPATHETIC SYSTEM.**

The great plexuses of the sympathetic are aggregations of nerves and ganglia, situated in the thoracic, abdominal, and pelvic cavities, and named the **cardiac**, **cœliac**, and **hypogastric plexuses**. They consist not only of sympathetic fibres derived from the ganglia, but of fibres from the medulla spinalis, which are conveyed through the white rami communicantes. From the plexuses branches are given to the thoracic, abdominal, and pelvic viscera.

**The Cardiac Plexus (Plexus Cardiacus) (Fig. 824).**

The **cardiac plexus** is situated at the base of the heart, and is divided into a **superficial part**, which lies in the concavity of the aortic arch, and a **deep part**, between the aortic arch and the trachea. The two parts are, however, closely connected.

The **superficial part of the cardiac plexus** lies beneath the arch of the aorta, in front of the right pulmonary artery. It is formed by the superior cardiac branch of the left sympathetic and the lower superior cervical cardiac branch of the left vagus. A small ganglion, the **cardiac ganglion of Wrisberg**, is occasionally found connected with these nerves at their point of junction. This ganglion, when present, is situated immediately beneath the arch of the aorta, on the right side of the ligamentum arteriosum. The superficial part of the cardiac plexus gives branches (*a*) to the deep part of the plexus; (*b*) to the anterior coronary plexus; and (*c*) to the left anterior pulmonary plexus.

The **deep part of the cardiac plexus** is situated in front of the bifurcation of the trachea, above the point of division of the pulmonary artery, and behind the aortic arch. It is formed by the cardiac nerves derived from the cervical ganglia of the sympathetic, and the cardiac branches of the vagus and recurrent nerves. The only cardiac nerves which do not enter into the formation of the deep part of the cardiac plexus are the superior cardiac nerve of the left sympathetic, and the lower of the two superior cervical cardiac branches from the left vagus, which pass to the superficial part of the plexus.

The branches from the **right half** of the deep part of the cardiac plexus pass, some in front of, and others behind, the right pulmonary artery; the former, the more numerous, transmit a few filaments to the anterior pulmonary plexus, and are then continued onward to form part of the anterior coronary plexus; those behind the pulmonary artery distribute a few filaments to the right atrium, and are then continued onward to form part of the posterior coronary plexus.

The **left half** of the deep part of the plexus is connected with the superficial part of the cardiac plexus, and gives filaments to the left atrium, and to the anterior pulmonary plexus, and is then continued to form the greater part of the posterior coronary plexus.

The **Posterior Coronary Plexus** (*plexus coronarius posterior; left coronary plexus*) is larger than the anterior, and accompanies the left coronary artery; it is chiefly formed by filaments prolonged from the left half of the deep part of the cardiac plexus, and by a few from the right half. It gives branches to the left atrium and ventricle.

The **Anterior Coronary Plexus** (*plexus coronarius anterior; right coronary plexus*) is formed partly from the superficial and partly from the deep parts of the cardiac plexus. It accompanies the right coronary artery, and gives branches to the right atrium and ventricle.

### **The Coeliac Plexus (Plexus Coeliacus; Solar Plexus) (Figs. 824, 827).**

The **coeliac plexus**, the largest of the three sympathetic plexuses, is situated at the level of the upper part of the first lumbar vertebra and is composed of two large ganglia, the **coeliac ganglia**, and a dense net-work of nerve fibres uniting them together. It surrounds the coeliac artery and the root of the superior mesenteric artery. It lies behind the stomach and the omental bursa, in front of the crura of the Diaphragma and the commencement of the abdominal aorta, and between the suprarenal glands. The plexus and the ganglia receive the greater and lesser splanchnic nerves of both sides and some filaments from the right vagus, and give off numerous secondary plexuses along the neighboring arteries.

The **Coeliac Ganglia** (*ganglia coeliaca; semilunar ganglia*) are two large irregularly-shaped masses having the appearance of lymph glands and placed one on either side of the middle line in front of the crura of the Diaphragma close to the suprarenal glands, that on the right side being placed behind the inferior vena cava. The upper part of each ganglion is joined by the greater splanchnic nerve, while the

lower part, which is segmented off and named the **aorticorenal ganglion**, receives the lesser splanchnic nerve and gives off the greater part of the renal plexus.




FIG. 827.—The celiac ganglia with the sympathetic plexuses of the abdominal viscera radiating from the ganglia. (Toldt.)

The secondary plexuses springing from or connected with the cœliac plexus are the

- |                   |                      |
|-------------------|----------------------|
| Phrenic.          | Renal.               |
| Hepatic.          | Spermatic.           |
| Lienal.           | Superior mesenteric. |
| Superior gastric. | Abdominal aortic.    |
| Suprarenal.       | Inferior mesenteric. |

The **phrenic plexus** (*plexus phrenicus*) accompanies the inferior phrenic artery to the Diaphragma, some filaments passing to the suprarenal gland. It arises from the upper part of the cœliac ganglion, and is larger on the right than on the left side. It receives one or two branches from the phrenic nerve. At the point



of junction of the right phrenic plexus with the phrenic nerve is a small ganglion (**ganglion phrenicum**). This plexus distributes branches to the inferior vena cava, and to the suprarenal and hepatic plexuses.

The **hepatic plexus** (*plexus hepaticus*), the largest offset from the cœliac plexus, receives filaments from the left vagus and right phrenic nerves. It accompanies the hepatic artery, ramifying upon its branches, and upon those of the portal vein in the substance of the liver. Branches from this plexus accompany all the divisions of the hepatic artery. A considerable plexus accompanies the gastroduodenal artery and is continued as the **inferior gastric plexus** on the right gastroepiploic artery along the greater curvature of the stomach, where it unites with offshoots from the lienal plexus.

The **lienal plexus** (*plexus lienalis*; *splenic plexus*) is formed by branches from the cœliac plexus, the left cœliac ganglion, and from the right vagus nerve. It accompanies the lienal artery to the spleen, giving off, in its course, subsidiary plexuses along the various branches of the artery.

The **superior gastric plexus** (*plexus gastricus superior*; *gastric or coronary plexus*) accompanies the left gastric artery along the lesser curvature of the stomach, and joins with branches from the left vagus.

The **suprarenal plexus** (*plexus suprarenalis*) is formed by branches from the cœliac plexus, from the cœliac ganglion, and from the phrenic and greater splanchnic nerves, a ganglion being formed at the point of junction with the latter nerve. The plexus supplies the suprarenal gland, being distributed chiefly to its medullary portion; its branches are remarkable for their large size in comparison with that of the organ they supply.

The **renal plexus** (*plexus renalis*) is formed by filaments from the cœliac plexus, the aorticorenal ganglion, and the aortic plexus. It is joined also by the smallest splanchnic nerve. The nerves from these sources, fifteen or twenty in number, have a few ganglia developed upon them. They accompany the branches of the renal artery into the kidney; some filaments are distributed to the spermatic plexus and, on the right side, to the inferior vena cava.

The **spermatic plexus** (*plexus spermaticus*) is derived from the renal plexus, receiving branches from the aortic plexus. It accompanies the internal spermatic artery to the testis. In the female, the **ovarian plexus** (*plexus arteriae ovaricae*) arises from the renal plexus, and is distributed to the ovary, and fundus of the uterus.

**Applied Anatomy.**—The intimate connection which exists between the renal and spermatic plexuses serves to explain the very frequent symptom in renal calculus, of pain which is referred to the body of the testis.

The **superior mesenteric plexus** (*plexus mesentericus superior*) is a continuation of the lower part of the cœliac plexus, receiving a branch from the junction of the right vagus nerve with the plexus. It surrounds the superior mesenteric artery, accompanies it into the mesentery, and divides into a number of secondary plexuses, which are distributed to all the parts supplied by the artery, viz., pancreatic branches to the pancreas; intestinal branches to the small intestine; and ileocolic, right colic, and middle colic branches, which supply the corresponding parts of the great intestine. The nerves composing this plexus are white in color and firm in texture; in the upper part of the plexus close to the origin of the superior mesenteric artery is a ganglion (**ganglion mesentericum superius**).

The **abdominal aortic plexus** (*plexus aorticus abdominalis*; *aortic plexus*) is formed by branches derived, on either side, from the cœliac plexus and ganglia, and receives filaments from some of the lumbar ganglia. It is situated upon the sides and front of the aorta, between the origins of the superior and inferior mesenteric arteries. From this plexus arise part of the spermatic, the inferior mesenteric, and the hypogastric plexuses; it also distributes filaments to the inferior vena cava.



The **inferior mesenteric plexus** (*plexus mesentericus inferior*) is derived chiefly from the aortic plexus. It surrounds the inferior mesenteric artery, and divides into a number of secondary plexuses, which are distributed to all the parts supplied by the artery, viz., the **left colic** and **sigmoid plexuses**, which supply the descending and sigmoid parts of the colon; and the **superior hemorrhoidal plexus**, which supplies the rectum and joins in the pelvis with branches from the pelvic plexuses.

### The Hypogastric Plexus (*Plexus Hypogastricus*) (Fig. 824).

The **hypogastric plexus** is situated in front of the last lumbar vertebra and the promontory of the sacrum, between the two common iliac arteries, and is formed by the union of numerous filaments, which descend on either side from the aortic plexus, and from the lumbar ganglia; it divides, below, into two lateral portions which are named the **pelvic plexuses**.

**The Pelvic Plexuses** (Fig. 824).—The pelvic plexuses supply the viscera of the pelvic cavity, and are situated at the sides of the rectum in the male, and at the sides of the rectum and vagina in the female. They are formed on either side by a continuation of the hypogastric plexus, by the visceral branches from the second, third, and fourth sacral nerves, and by a few filaments from the first two sacral ganglia. At the points of junction of these nerves small ganglia are found. From these plexuses numerous branches are distributed to the viscera of the pelvis. They accompany the branches of the hypogastric artery.

The **Middle Hemorrhoidal Plexus** (*plexus haemorrhoidalis medius*) arises from the upper part of the pelvic plexus. It supplies the rectum, and joins with branches of the superior hemorrhoidal plexus.

The **Vesical Plexus** (*plexus vesicalis*) arises from the forepart of the pelvic plexus. The nerves composing it are numerous, and contain a large proportion of spinal nerve fibres. They accompany the vesical arteries, and are distributed to the sides and fundus of the bladder. Numerous filaments also pass to the vesiculae seminales and ductus deferentes; those accompanying the ductus deferens join, on the spermatic cord, with branches from the spermatic plexus.

The **Prostatic Plexus** (*plexus prostaticus*) is continued from the lower part of the pelvic plexus. The nerves composing it are of large size. They are distributed to the prostate vesiculae seminales and the corpora cavernosa of the penis and urethra. The nerves supplying the corpora cavernosa consist of two sets, the lesser and greater cavernous nerves, which arise from the forepart of the prostatic plexus, and, after joining with branches from the pudendal nerve, pass forward beneath the pubic arch.

The **lesser cavernous nerves** (*nn. cavernosi penis minores; small cavernous nerves*) perforate the fibrous covering of the penis, near its root.

The **greater cavernous nerve** (*n. cavernosus penis major; large cavernous plexus*) passes forward along the dorsum of the penis, joins with the dorsal nerve of the penis, and is distributed to the corpora cavernosa.

The **Vaginal Plexus** arises from the lower part of the pelvic plexus. It is distributed to the walls of the vagina, to the erectile tissue of the vestibule, and to the clitoris. The nerves composing this plexus contain, like the vesical, a large proportion of spinal nerve fibres.

The **Uterine Plexus** accompanies the uterine artery to the side of the uterus, between the layers of the broad ligament; it communicates with the ovarian plexus.

**Applied Anatomy.**—Little is known as to the connection between the numerous microscopic alterations (pigmentation, atrophy, hemorrhage, fibrosis) that have been described in the sympathetic nervous system, and the functional changes that ensue therefrom. Grosser lesions due to stabs, bullet wounds, or the pressure of new growths, may cause either irritative or paralytic

of junction of the right phrenic plexus with the phrenic nerve is a small ganglion (**ganglion phrenicum**). This plexus distributes branches to the inferior vena cava, and to the suprarenal and hepatic plexuses.

The **hepatic plexus** (*plexus hepaticus*), the largest offset from the celiac plexus, receives filaments from the left vagus and right phrenic nerves. It accompanies the hepatic artery, ramifying upon its branches, and upon those of the portal vein in the substance of the liver. Branches from this plexus accompany all the divisions of the hepatic artery. A considerable plexus accompanies the gastroduodenal artery and is continued as the **inferior gastric plexus** on the right gastroepiploic artery along the greater curvature of the stomach, where it unites with offshoots from the lienal plexus.

The **lienal plexus** (*plexus lienalis*; *splenic plexus*) is formed by branches from the celiac plexus, the left **coeliac ganglion**, and from the right vagus nerve. It accompanies the lienal artery to the spleen, giving off, in its course, subsidiary plexuses along the various branches of the artery.

The **superior gastric plexus** (*plexus gastricus superior*; *gastric or coronary plexus*) accompanies the left gastric artery along the lesser curvature of the stomach, and joins with branches from the left vagus.

The **suprarenal plexus** (*plexus suprarenalis*) is formed by branches from the celiac plexus, from the celiac ganglion, and from the phrenic and greater splanchnic nerves, a ganglion being formed at the point of junction with the latter nerve. The plexus supplies the suprarenal gland, being distributed chiefly to its medullary portion; its branches are remarkable for their large size in comparison with that of the organ they supply.

The **renal plexus** (*plexus renalis*) is formed by filaments from the celiac plexus, the aorticorenal ganglion, and the aortic plexus. It is joined also by the smallest splanchnic nerve. The nerves from these sources, fifteen or twenty in number, have a few ganglia developed upon them. They accompany the branches of the renal artery into the kidney; some filaments are distributed to the spermatic plexus and, on the right side, to the inferior vena cava.

The **spermatic plexus** (*plexus spermaticus*) is derived from the renal plexus, receiving branches from the aortic plexus. It accompanies the internal spermatic artery to the testis. In the female, the **ovarian plexus** (*plexus arteriae ovaricae*) arises from the renal plexus, and is distributed to the ovary, and fundus of the uterus.

**Applied Anatomy.**—The intimate connection which exists between the renal and spermatic plexuses serves to explain the very frequent symptom in renal calculus, of pain which is referred to the body of the testis.

The **superior mesenteric plexus** (*plexus mesentericus superior*) is a continuation of the lower part of the celiac plexus, receiving a branch from the junction of the right vagus nerve with the plexus. It surrounds the superior mesenteric artery, accompanies it into the mesentery, and divides into a number of secondary plexuses, which are distributed to all the parts supplied by the artery, viz., pancreatic branches to the pancreas; intestinal branches to the small intestine; and ileocolic, right colic, and middle colic branches, which supply the corresponding parts of the great intestine. The nerves composing this plexus are white in color and firm in texture; in the upper part of the plexus close to the origin of the superior mesenteric artery is a ganglion (**ganglion mesentericum superius**).

The **abdominal aortic plexus** (*plexus aorticus abdominalis*; *aortic plexus*) is formed by branches derived, on either side, from the celiac plexus and ganglia, and receives filaments from some of the lumbar ganglia. It is situated upon the sides and front of the aorta, between the origins of the superior and inferior mesenteric arteries. From this plexus arise part of the spermatic, the inferior mesenteric, and the hypogastric plexuses; it also distributes filaments to the inferior vena cava.

The **inferior mesenteric plexus** (*plexus mesentericus inferior*) is derived chiefly from the aortic plexus. It surrounds the inferior mesenteric artery, and divides into a number of secondary plexuses, which are distributed to all the parts supplied by the artery, viz., the **left colic** and **sigmoid plexuses**, which supply the descending and sigmoid parts of the colon; and the **superior hemorrhoidal plexus**, which supplies the rectum and joins in the pelvis with branches from the pelvic plexuses.

### The Hypogastric Plexus (*Plexus Hypogastricus*) (Fig. 824).

The **hypogastric plexus** is situated in front of the last lumbar vertebra and the promontory of the sacrum, between the two common iliac arteries, and is formed by the union of numerous filaments, which descend on either side from the aortic plexus, and from the lumbar ganglia; it divides, below, into two lateral portions which are named the **pelvic plexuses**.

**The Pelvic Plexuses** (Fig. 824).—The pelvic plexuses supply the viscera of the pelvic cavity, and are situated at the sides of the rectum in the male, and at the sides of the rectum and vagina in the female. They are formed on either side by a continuation of the hypogastric plexus, by the visceral branches from the second, third, and fourth sacral nerves, and by a few filaments from the first two sacral ganglia. At the points of junction of these nerves small ganglia are found. From these plexuses numerous branches are distributed to the viscera of the pelvis. They accompany the branches of the hypogastric artery.

The **Middle Hemorrhoidal Plexus** (*plexus haemorrhoidalis medius*) arises from the upper part of the pelvic plexus. It supplies the rectum, and joins with branches of the superior hemorrhoidal plexus.

The **Vesical Plexus** (*plexus vesicalis*) arises from the forepart of the pelvic plexus. The nerves composing it are numerous, and contain a large proportion of spinal nerve fibres. They accompany the vesical arteries, and are distributed to the sides and fundus of the bladder. Numerous filaments also pass to the vesiculae seminales and ductus deferentes; those accompanying the ductus deferens join, on the spermatic cord, with branches from the spermatic plexus.

The **Prostatic Plexus** (*plexus prostaticus*) is continued from the lower part of the pelvic plexus. The nerves composing it are of large size. They are distributed to the prostate vesiculae seminales and the corpora cavernosa of the penis and urethra. The nerves supplying the corpora cavernosa consist of two sets, the lesser and greater cavernous nerves, which arise from the forepart of the prostatic plexus, and, after joining with branches from the pudendal nerve, pass forward beneath the pubic arch.

The **lesser cavernous nerves** (*nn. cavernosi penis minores; small cavernous nerves*) perforate the fibrous covering of the penis, near its root.

The **greater cavernous nerve** (*n. cavernosus penis major; large cavernous plexus*) passes forward along the dorsum of the penis, joins with the dorsal nerve of the penis, and is distributed to the corpora cavernosa.

The **Vaginal Plexus** arises from the lower part of the pelvic plexus. It is distributed to the walls of the vagina, to the erectile tissue of the vestibule, and to the clitoris. The nerves composing this plexus contain, like the vesical, a large proportion of spinal nerve fibres.

The **Uterine Plexus** accompanies the uterine artery to the side of the uterus, between the layers of the broad ligament; it communicates with the ovarian plexus.

**Applied Anatomy.**—Little is known as to the connection between the numerous microscopic alterations (pigmentation, atrophy, hemorrhage, fibrosis) that have been described in the sympathetic nervous system, and the functional changes that ensue therefrom. Grosser lesions due to stabs, bullet wounds, or the pressure of new growths, may cause either irritative or paralytic

symptoms. In *paralysis* of the cervical sympathetic on one side, the pupil is small and does not dilate when shaded or on the instillation of cocaine, although it contracts still farther when brightly illuminated; it also loses the ciliospinal reflex, failing to dilate when the skin of the neck is pinched. The palpebral fissure narrows from paralysis of the involuntary muscle of the eyelid, and the eyeball sinks backward into the orbit—enophthalmos—either from paralysis of Müller's orbital muscle which closes the inferior orbital fissure, or from wasting of the intraorbital fat. The superficial vessels of the face and scalp are at first dilated, but later they contract. Anidrosis, or absence of sweating, is often noted on the affected side. *Irritation* of the cervical sympathetic produces signs mainly the converse of those described above. We have no definite knowledge of the signs and symptoms that follow lesions of the thoracic or abdominal sympathetic systems. It is likely, however, that a number of nervous disorders characterized by persistent vascular disturbances, such as dilatation of the vessels with throbbing, flushing, sweating, and localized oedema, or contraction of the vessels with pallor, chilliness, pain, and malnutrition of the affected parts, are due to implication of the sympathetic nervous system. It is possible, too, that the rare condition of *progressive facial hemiatrophy*, coming on between the ages of ten and twenty, and producing marked unilateral shrinkage of all the tissues of the face, is primarily an affection of the sympathetic.

# THE ORGANS OF THE SENSES AND THE COMMON INTEGUMENT.

**THE organs of the senses** may be divided into (a) those of the special senses of taste, smell, sight, and hearing, and (b) those associated with the general sensations of heat, cold, pain, pressure, etc.

## THE PERIPHERAL ORGANS OF THE SPECIAL SENSES.

### THE ORGAN OF TASTE (ORGANON GUSTUS).

The **periphery gustatory** or **taste organs** consist of certain modified epithelial cells arranged in flask-shaped groups termed **gustatory calyculi** (*taste-buds*), which are found on the tongue and adjacent parts. They occupy nests in the stratified epithelium, and are present in large numbers on the sides of the papillae vallatae (Fig. 828), and to a less extent on their opposed walls. They are also found on the




FIG. 828.—Vertical section of papilla foliata of the rabbit, crossing the folia. (Ranvier.) *a*. Serous gland. *g*. Gustatory calyculus. *n*. Nerve bundles. *p*. Central lamina of the corium. *p'*. Lateral lamina in which the nerve fibres run. *z*. Sinus-like vein which traverses the whole length of the folium.

fungiform papillae over the back part and sides of the tongue, and in the general epithelial covering of the same areas. They are very plentiful over the fimbriae linguae, and are also present on the under surface of the soft palate, and on the posterior surface of the epiglottis.

**Structure.**—Each taste bud is flask-like in shape (Fig. 829), its broad base resting on the corium, and its neck opening by an orifice, the **gustatory pore**, between the cells of the epithelium. The bud is formed by two kinds of cells: supporting cells and gustatory cells. The **supporting cells** are mostly arranged like the staves of a cask, and form an outer envelope for the bud. Some, however, are found in the interior of the bud between the gustatory cells. The **gustatory cells**



occupy the central portion of the bud; they are spindle-shaped, and each possesses a large spherical nucleus near the middle of the cell. The peripheral end of the cell terminates at the gustatory pore in a fine hair-like filament, the **gustatory hair**. The central process passes toward the deep extremity of the bud, and there ends in single or bifurcated varicosities. The nerve fibrils after losing their medullary sheaths enter the taste bud, and end in fine extremities between the gustatory cells; other nerve fibrils ramify between the supporting cells and terminate in fine extremities; these, however, are believed to be nerves of ordinary sensation and not gustatory.




FIG. 829.—Taste-bud, highly magnified.

**Nerves of Taste.**—The chorda tympani nerve, derived from the sensory root of the facial, is the nerve of taste for the anterior two-thirds of the tongue; the nerve for the posterior third is the glossopharyngeal.

### THE ORGAN OF SMELL (ORGANON OLFACTORIUS; THE NOSE).

The **peripheral olfactory organ** or **organ of smell** consists of two parts: an outer, the **external nose**, which projects from the centre of the face; and an internal, the **nasal cavity**, which is divided by a septum into **right** and **left nasal chambers**.

#### The External Nose (*Nasus Externus*; Outer Nose).

The **external nose** is pyramidal in form, and its upper angle or **root** is connected directly with the forehead; its free angle is termed the **apex**. Its **base** is perforated by two elliptical orifices, the **nares**, separated from each other by an antero-posterior septum, the **columna**. The margins of the nares are provided with a number of stiff hairs, or **vibrissæ**, which arrest the passage of foreign substances carried with the current of air intended for respiration. The lateral surfaces of the nose form, by their union in the middle line, the **dorsum nasi**, the direction of which varies considerably in different individuals; the upper part of the dorsum is supported by the nasal bones, and is named the **bridge**. The lateral surface ends below in a rounded eminence, the **ala nasi**.

**Structure.**—The frame-work of the external nose is composed of bones and cartilages; it is covered by the integument, and lined by mucous membrane.

The **bony frame-work** occupies the upper part of the organ; it consists of the nasal bones, and the frontal processes of the maxillæ.

The **cartilaginous frame-work** (*cartilagine nati*) consists of five large pieces, viz., the **cartilage of the septum**, the **two lateral** and the **two greater alar cartilages**, and several smaller pieces, the **lesser alar cartilages** (Figs. 830, 831, 832). The various cartilages are connected to each other and to the bones by a tough fibrous membrane.

The **cartilage of the septum** (*cartilago septi nasi*) is somewhat quadrilateral in form, thicker at its margins than at its centre, and completes the separation between the nasal cavities in front. Its anterior margin, thickest above, is connected with the nasal bones, and is continuous with the anterior margins of the lateral cartilages; below, it is connected to the medial crura of the greater alar cartilages by fibrous tissue. Its posterior margin is connected with the perpendicular plate of the ethmoid; its inferior margin with the vomer and the palatine processes of the maxillæ.

It may be prolonged backward (especially in children) as a narrow process, the **sphenoidal process**, for some distance between the vomer and perpendicular plate of the ethmoid. The septal cartilage does not reach as far as the lowest part of the nasal septum. This is formed by the medial crura of the greater alar cartilages and by the skin; it is freely movable, and hence is termed the **septum mobile nasi**.

The **lateral cartilage** (*cartilago nasi lateralis*; *upper lateral cartilage*) is situated below the inferior margin of the nasal bone, and is flattened, and triangular in shape. Its anterior margin is thicker than the posterior, and is continuous above with the cartilage of the septum, but separated from it below by a narrow fissure; its superior margin is attached to the nasal bone and the frontal process of the maxilla; its inferior margin is connected by fibrous tissue with the greater alar cartilage.

The **greater alar cartilage** (*cartilago alaris major*; *lower lateral cartilage*) is a thin, flexible plate, situated immediately below the preceding, and bent upon itself in such a manner as to form the medial and lateral walls of the naris of its own side. The portion which forms the **medial wall** (*crus mediale*) is loosely connected with the corresponding portion of the opposite cartilage, the two forming, together with the thickened integument and subjacent tissue, the **septum mobile nasi**. The part which forms the **lateral wall** (*crus laterale*) is curved to correspond with the ala of the nose; it is oval and flattened, narrow behind, where it is connected with the frontal process of the maxilla by a tough fibrous membrane, in which are found three or four small cartilaginous plates, the **lesser alar cartilages** (*cartilagines alares minores*; *sesamoid cartilages*). Above, it is connected by fibrous tissue to the lateral cartilage and front part of the cartilage of the septum; below, it falls short of the margin of the naris, the ala being completed by fatty and fibrous tissue covered by skin. In front, the greater alar cartilages are separated by a notch which corresponds with the apex of the nose.




FIG. 830.—Cartilages of the nose. Side view.




FIG. 831.—Cartilages of the nose, seen from below.



FIG. 832.—Bones and cartilages of septum of nose. Right side.

The **muscles** acting on the external nose have been described in the section on Myology.

The **integument** of the dorsum and sides of the nose is thin, and loosely connected with the subjacent parts; but over the tip and alæ it is thicker and more firmly adherent, and is furnished with a large number of sebaceous follicles, the orifices of which are usually very distinct.

The **arteries** of the external nose are the alar and septal branches of the external maxillary, which supply the alæ and septum; the dorsum and sides being supplied from the dorsal nasal branch of the ophthalmic and the infraorbital branch of the internal maxillary. The **veins** end in the anterior facial and ophthalmic veins.

The **nerves** for the muscles of the nose are derived from the facial, while the skin receives branches from the infratrochlear and nasociliary branches of the ophthalmic, and from the infra-orbital of the maxillary.

### **The Nasal Cavity (*Cavum Nasi*; *Nasal Fossa*).**

The nasal chambers are situated one on either side of the median plane. They open in front through the nares, and communicate behind through the choanæ with the nasal part of the pharynx. The **nares** are somewhat pear-shaped apertures, each measuring about 2.5 cm. antero-posteriorly and 1.25 cm. transversely at its widest part. The **choanæ** are two oval openings each measuring 2.5 cm. in the vertical, and 1.25 cm. in the transverse direction in a well-developed adult skull.

For the description of the bony boundaries of the nasal cavities, see pages 292 to 294.

Inside the aperture of the nostril is a slight dilatation, the **vestibule**, bounded laterally by the ala and lateral crus of the greater alar cartilage, and medially by the medial crus of the same cartilage. It is lined by skin containing hairs and sebaceous glands, and extends as a small recess toward the apex of the nose. Each nasal cavity, above and behind the vestibule, is divided into two parts: an **olfactory region**, consisting of the superior nasal concha and the opposed part of the septum, and a **respiratory region**, which comprises the rest of the cavity.




FIG. 833.—Lateral wall of nasal cavity.

**Lateral Wall** (Figs. 833, 834).—On the lateral wall are the **superior, middle, and inferior nasal conchæ**, and below and lateral to each concha is the corresponding nasal passage or meatus. Above the superior concha is a narrow recess, the **sphenoethmoidal recess**, into which the sphenoidal sinus opens. The **superior meatus** is a short oblique passage extending about half-way along the upper border of the middle concha; the posterior ethmoidal cells open into the front part of this meatus. The **middle meatus** is below and lateral to the middle concha, and is

continued anteriorly into a shallow depression, situated above the vestibule and named the **atrium** of the middle meatus. On raising or removing the middle concha the lateral wall of this meatus is fully displayed. On it is a rounded elevation, the **bullæ ethmoidalis**, and below and in front of this is a curved cleft, the **hiatus semilunaris**.

The **bullæ ethmoidalis** is caused by the bulging of the middle ethmoidal cells which open on or immediately above it, and the size of the bulla varies with that of its contained cells.




FIG. 834.—Lateral wall of nasal cavity; the three nasal conchæ have been removed.

The **hiatus semilunaris** is bounded inferiorly by the sharp concave margin of the uncinæ process of the ethmoid bone, and leads into a curved channel, the **infundibulum**, bounded above by the bullæ ethmoidalis and below by the lateral surface of the uncinæ process of the ethmoid. The anterior ethmoidal cells open into the front part of the infundibulum, and this in slightly over 50 per cent. of subjects is directly continuous with the frontonasal duct or passage leading from the frontal air sinus; but when the anterior end of the uncinæ process fuses with the front part of the bulla, this continuity is interrupted and the frontonasal duct then opens directly into the anterior end of the middle meatus.

Below the bullæ ethmoidalis, and partly hidden by the inferior end of the uncinæ process, is the **ostium maxillare**, or opening from the maxillary sinus; in a frontal section this opening is seen to be placed near the roof of the sinus. An accessory opening from the sinus is frequently present below the posterior end of the middle nasal concha. The **inferior meatus** is below and lateral to the inferior nasal concha; the nasolacrimal duct opens into this meatus under cover of the anterior part of the inferior concha.

**Medial Wall** (Fig. 832).—The medial wall or septum is frequently more or less deflected from the median plane, thus lessening the size of one nasal cavity and increasing that of the other; ridges or spurs of bone growing into one or other cavity from the septum are also sometimes present. Immediately over the incisive canal at the lower edge of the cartilage of the septum a depression, the **nasopalatine recess**, is seen. In the septum close to this recess a minute orifice may be discerned; it leads backward into a blind pouch, the rudimentary **vomeronasal organ of Jacobson**, which is supported by a strip of cartilage, the **vomeronasal cartilage**. This organ is well-developed in many of the lower animals, where it apparently plays a part in the sense of smell, since it is supplied by twigs of the olfactory nerve and lined by epithelium similar to that in the olfactory region of the nose.

The **roof** of the nasal cavity is narrow from side to side, except at its posterior part, and may be divided, from behind forward, into sphenoidal, ethmoidal, and frontonasal parts, after the bones which form it.

The **floor** is concave from side to side and almost horizontal antero-posteriorly; its anterior three-fourths are formed by the palatine process of the maxilla, its posterior fourth by the horizontal process of the palatine bone. In its antero-medial part, directly over the incisive foramen, a small depression, the **nasopalatine recess**, is sometimes seen; it points downward and forward and occupies the position of a canal which connected the nasal with the buccal cavity in early fetal life.

**The Mucous Membrane** (*membrana mucosa nasi*).—The nasal mucous membrane lines the nasal cavities, and is intimately adherent to the periosteum or perichondrium. It is continuous with the skin through the nares, and with the mucous membrane of the nasal part of the pharynx through the choanæ. From the nasal cavity its continuity with the conjunctiva may be traced, through the nasolacrimal and lacrimal ducts; and with the frontal, ethmoidal, sphenoidal, and maxillary sinuses, through the several openings in the meatuses. The mucous membrane is thickest, and most vascular, over the nasal conchæ. It is also thick over the septum; but it is very thin in the meatuses on the floor of the nasal cavities, and in the various sinuses.

Owing to the thickness of the greater part of this membrane, the nasal cavities are much narrower, and the middle and inferior nasal conchæ appear larger and more prominent than in the skeleton; also the various apertures communicating with the meatuses are considerably narrowed.

**Structure of the Mucous Membrane** (Fig. 835).—The epithelium covering the mucous membrane differs in its character according to the functions of the part of the nose in which it is found. In the **respiratory region** it is columnar and ciliated. Interspersed among the columnar cells are goblet or mucin cells, while between their bases are found smaller pyramidal cells. Beneath the epithelium and its basement membrane is a fibrous layer infiltrated with lymph corpuscles, so as to form in many parts a diffuse adenoid tissue, and under this a nearly continuous layer of small and larger glands, some mucous and some serous, the ducts of which open upon the surface. In the **olfactory region** the mucous membrane is yellowish in color and the epithelial cells are columnar and non-ciliated; they are of two kinds, supporting cells and olfactory cells. The **supporting cells** contain oval nuclei, which are situated in the deeper parts of the cells and constitute the zone of oval nuclei; the superficial part of each cell is columnar, and contains granules of yellow pigment, while its deep part is prolonged as a delicate process which ramifies and communicates with similar processes from neighboring cells, so as to form a net-work in the mucous membrane. Lying between the deep processes of the supporting cells are a number of bipolar nerve cells, the **olfactory cells**, each consisting of a small amount of granular protoplasm with a large spherical nucleus, and possessing two processes—a superficial one which runs between the columnar epithelial cells, and projects on the surface of the mucous membrane as a fine, hair-like process, the **olfactory hair**; the other or deep process runs inward, is frequently beaded, and is continued as the axon of an olfactory nerve fibre. Beneath the epithelium, and extending through the thickness of the mucous membrane, is a layer of tubular, often branched, glands, the **glands of Bowman**, identical in structure with serous glands.



**Vessels and Nerves.**—The **arteries** of the nasal cavities are the anterior and posterior ethmoidal branches of the ophthalmic, which supply the ethmoidal cells, frontal sinuses, and roof of the nose; the sphenopalatine branch of the internal maxillary, which supplies the mucous membrane covering the conchæ, the meatuses and septum; the septal branch of the superior labial of the external maxillary; the infraorbital and alveolar branches of the internal maxillary, which supply the lining membrane of the maxillary sinus; and the pharyngeal branch of the same artery, distributed to the sphenoidal sinus. The ramifications of these vessels form a close plexiform net-work, beneath and in the substance of the mucous membrane.




FIG. 835.—Section of the olfactory mucous membrane. (Cadiat.) *a.* Epithelium. *b.* Glands of Bowman. *c.* Nerve bundles.

The **veins** form a close cavernous plexus beneath the mucous membrane. This plexus is especially well-marked over the lower part of the septum and over the middle and inferior conchæ. Some of the veins open into the sphenopalatine vein; others join the anterior facial vein; some accompany the ethmoidal arteries, and end in the ophthalmic veins; and, lastly, a few communicate with the veins on the orbital surface of the frontal lobe of the brain, through the foramina in the cribriform plate of the ethmoid bone; when the foramen caecum is patent it transmits a vein to the superior sagittal sinus.

The **lymphatics** have already been described (p. 776).

The **nerves** of ordinary sensation are: the nasociliary branch of the ophthalmic, filaments from the anterior alveolar branch of the maxillary, the nerve of the pterygoid canal, the nasopalatine, the anterior palatine, and nasal branches of the sphenopalatine ganglion.

The nasociliary branch of the ophthalmic distributes filaments to the forepart of the septum and lateral wall of the nasal cavity. Filaments from the anterior alveolar nerve supply the inferior meatus and inferior concha. The nerve of the pterygoid canal supplies the upper and back part of the septum, and superior concha; and the upper nasal branches from the sphenopalatine ganglion have a similar distribution. The nasopalatine nerve supplies the middle of the septum. The anterior palatine nerve supplies the lower nasal branches to the middle and inferior conchæ.

The **olfactory**, the special nerve of the sense of smell, is distributed to the olfactory region. Its fibres arise from the bipolar olfactory cells and are destitute of medullary sheaths. They unite in fasciculi which form a plexus beneath the mucous membrane and then ascend in grooves or canals in the ethmoid bone; they pass into the skull through the foramina in the cribriform plate of the ethmoid and enter the under surface of the olfactory bulb, in which they ramify and form synapses with the dendrites of the mitral cells (Fig. 772).




FIG. 836.—Nerves of septum of nose. Right side.

**The Accessory Sinuses of the Nose (Sinus Paranasales)** (Figs. 833, 834, 837).

The **accessory sinuses** or **air cells of the nose** are the **frontal**, **ethmoidal**, **sphenoidal**, and **maxillary**; they vary in size and form in different individuals, and are lined by mucous membrane directly continuous with that of the nasal cavities.

The **frontal sinuses** (*sinus frontales*), situated behind the superciliary arches, are rarely symmetrical, and the septum between them frequently deviates to one or other side of the middle line. Their average measurements are as follows: height, 3 cm.; breadth, 2.5 cm.; depth from before backward, 2.5 cm. Each opens into the anterior part of the corresponding middle meatus of the nose through the frontonasal duct which traverses the anterior part of the labyrinth of the ethmoid. Absent at birth, they are generally fairly well developed between the seventh and eighth years, but only reach their full size after puberty.




FIG. 837.—Coronal section of nasal cavities.

The **ethmoidal air cells** (*cellulae ethmoidales*) consist of numerous thin-walled cavities situated in the ethmoidal labyrinth and completed by the frontal, maxilla, lacrimal, sphenoidal, and palatine. They lie between the upper parts of the nasal cavities and the orbits, and are separated from these cavities by thin bony laminae. On either side they are arranged in three groups, **anterior**, **middle**, and **posterior**. The anterior and middle groups open into the middle meatus of the nose, the former by way of the infundibulum, the latter on or above the bulla ethmoidalis. The posterior cells open into the superior meatus under cover of the superior nasal concha; sometimes one or more opens into the sphenoidal sinus. The ethmoidal cells begin to develop during fetal life.

The **sphenoidal sinuses** (*sinus sphenoidales*) contained within the body of the sphenoid vary in size and shape; owing to the lateral displacement of the intervening septum they are rarely symmetrical. The following are their average measurements: vertical height, 2.2 cm.; transverse breadth, 2 cm.; antero-posterior

depth, 2.2 cm. When exceptionally large they may extend into the roots of the pterygoid processes or great wings, and may invade the basilar part of the occipital bone. Each sinus communicates with the sphenoethmoidal recess by means of an aperture in the upper part of its anterior wall. They are present as minute cavities at birth, but their main development takes place after puberty.

The **maxillary sinus** (*sinus maxillaris; antrum of Highmore*), the largest of the accessory sinuses of the nose, is a pyramidal cavity in the body of the maxilla. Its base is formed by the lateral wall of the nasal cavity, and its apex extends into the zygomatic process. Its roof or orbital wall is frequently ridged by the infra-orbital canal, while its floor is formed by the alveolar process and is usually on a level with the floor of the nose; projecting into the floor are several conical elevations corresponding with the roots of the first and second molar teeth, and in some cases the floor is perforated by one or more of these roots. The size of the sinus varies in different skulls, and even on the two sides of the same skull. The following measurements are those of an average-sized sinus: vertical height opposite the first molar tooth, 3.75 cm.; transverse breadth, 2.5 cm.; antero-posterior depth, 3 cm. In the antero-superior part of its base is an opening through which it communicates with the lower part of the hiatus semilunaris; a second orifice is frequently seen in, or immediately behind, the hiatus. The maxillary sinus appears as a shallow groove on the medial surface of the bone about the fourth month of fetal life, but does not reach its full size until after the second dentition.<sup>1</sup>

**Applied Anatomy.**—Instances of congenital deformity of the nose are occasionally met with, such as complete absence of the external nose, an aperture only being present; or perfect development on one side, and suppression or malformation on the other. Deformities which have been acquired are much more common, such as flattening of the nose, the result of syphilitic necrosis; or imperfect development of the nasal bones in cases of congenital syphilis; or a lateral deviation of the nose may result from fracture.

The skin over the alæ and apex of the nose is thick and closely adherent to subjacent parts; inflammation of this part is therefore very painful, on account of the tension. It is richly supplied with blood, and, the circulation here being terminal, vascular engorgement is liable to occur especially in women at the menopause, and in both sexes from disorders of digestion, exposure to cold, etc. The skin of the nose also contains a large number of sebaceous follicles, and these, as the result of intemperance, are apt to become affected and the nose reddened, congested, and irregularly swollen. To this the term "grog blossom" is popularly applied. In some of these cases there is enormous hypertrophy of the skin and subcutaneous tissues. Epithelioma and rodent ulcer may attack the nose, the latter being the more common of the two. Lupus and syphilitic ulceration frequently affect the nose, and may destroy the whole of the cartilaginous portion. In fact, lupus vulgaris begins more frequently on the alæ of the nose than in any other situation.

To examine the nasal cavities, the head should be thrown back and the nose drawn upward, the parts being dilated by some form of speculum. The choanæ can be explored by reflected light from the mouth, through which they can be illuminated. The examination is very difficult to carry out, and, as a rule, sufficient information regarding the presence of foreign bodies or tumors in the nasopharynx can be obtained by the introduction of the finger behind the soft palate through the mouth. The septum of the nose may be displaced or may deviate from the middle line; this may be the result of an injury or of some congenital defect. Sometimes the deviation may be so great that the septum may come into contact with the lateral wall of the nasal cavity, and may even become adherent to it, thus producing complete obstruction. Perforation of the septum is not an uncommon affection, and may arise from several causes: syphilitic or tuberculous ulceration, blood tumor or abscess of the septum. When small, the perforation may cause a peculiar whistling sound during respiration. When large, it may lead to the falling in of the bridge of the nose.

**Epistaxis** is a very common affection in children. It is rarely of much consequence, and will almost always subside without treatment; but in the more violent hemorrhages of later life it may be necessary to plug the choanæ. A ready method of regulating the bulk of the plug to fit the opening is to make it of the same size as the terminal phalanx of the thumb of the patient to be operated on.

<sup>1</sup> The various measurements of the accessory sinuses of the nose are based on those given by Aldren Turner in his *Accessory Sinuses of the Nose*.

*Foreign bodies*, such as buttons, are frequently inserted into the nostrils by children, and require some care in removal, as unskilled attempts only result in pushing the foreign body farther into the nasal cavity. Bodies which remain in the nose for any length of time set up ulceration of the mucous membrane, sometimes spreading to the bone, and a profuse purulent discharge results. A condition of unilateral nasal discharge in a child is always suggestive of the presence of a foreign body. The removal of such objects is best effected by giving the child an anesthetic, opening the mouth with a gag, and placing the left forefinger in the nasopharynx, so as to prevent the escape of the body into the air passages; the foreign body is then removed through the anterior naris by a suitable scoop or forceps manipulated by the right hand.

*Enlargement of the mucous membrane* covering the inferior or middle nasal conchæ is a very frequent accompaniment of chronic nasal catarrh. In old-standing cases the bones themselves may become enlarged, constituting the "hypertrophied turbinals" which are so often the cause of nasal obstruction. In the case of the inferior concha either the anterior or posterior end is usually more especially affected, giving rise to a reddened mass of tissue often confused with a nasal polypus; the appearances, however, are totally different, as the true nasal polypi appear as glistening grayish-white bodies between the conchæ. Hypertrophy of the conchæ can be temporarily reduced to a great extent by the local application of cocaine, and if the reduction by this means is to practically the normal condition, then treatment by application of the galvano-cautery will be sufficient; otherwise the enlarged portion of the bone or bones will require removal by a wire snare after the attachment to the lateral wall of the nasal cavity has been freed, by special nasal scissors, in the case of enlargement of the anterior end, and by the spokeshave when the posterior end is enlarged. It is highly inadvisable to remove more than is necessary, as too free removal results in a dry condition of the air passages, which conduces to a chronic dry pharyngitis and laryngitis.

*Nasal polypi* are of frequent occurrence; in the common gelatinous form they spring from the lateral wall of the nasal cavity and project down between the conchæ, giving rise to obstructed nasal respiration. They are always accompanied by purulent discharge, and are due in all instances to small areas of carious bone in the region of the *bullæ ethmoidalis*, or about the ethmoidal or sphenoidal air cells. They appear as glistening grayish-white bodies swinging on a pedicle, and the larger ones can be encircled with a cold wire snare and thus removed; usually, however, after the extirpation of the larger ones has been carried out, numerous small polypi can be seen springing from the region of their bases, and cauterization of such affected areas must be thoroughly carried out if a recurrence of the trouble is to be avoided. In bad cases a free curetting of the ethmoidal air cells may be called for after removal of the middle concha. Fibrous polypi are also more rarely met with, and these are of the nature of new growths; they most frequently spring from the base of the skull behind the choanæ and form pedunculated tumors occupying the nasopharynx. Malignant polypi also occur, most commonly originating in the maxillary sinus and projecting through its medial wall into the nasal cavity; for such cases removal of the maxilla offers the only hope of cure.

*Suppuration in the accessory nasal sinuses* is of frequent occurrence, and in connection with this the situations at which the various sinuses normally communicate with the nasal cavities, are important; thus one finds they fall into two main groups: the anterior, opening into the middle meatus, and draining the maxillary sinus, the frontal sinus, and the anterior ethmoidal air cells; and the posterior group, opening into the superior meatus and sphenothmoidal recess, and draining the posterior ethmoidal and sphenoidal air cells. Suppuration in the anterior group is the more common, and the pus can be seen running down over the anterior end of the inferior concha, whereas in the case of the posterior group the pus does not come forward, but runs back into the nasopharynx over the posterior end of the middle concha. Again, it is of importance to notice that the middle meatus is of such a form that pus running down from the frontal sinus is directed by the groove beneath the *bullæ ethmoidalis* into the ostium of the maxillary sinus, so that the latter sinus may, in some cases, act as a secondary reservoir for pus discharged from the frontal sinus. All the accessory sinuses can be and are infected from the nasal cavity, but it should be noted that in the case of the maxillary sinus, the infection is frequently conveyed in another way, and that is from the teeth. This sinus is the one most frequently the seat of chronic suppuration and it often requires drainage; this can be carried out by drilling a hole through the alveolus after removal of a tooth, preferably the first molar, or by gouging away the anterior surface of the maxilla, after having reflected the gum, or by removing bone from the lateral wall of the inferior meatus of the nose. Simple drainage, however, is not usually sufficient, and more extensive operations have often to be performed. Distension of the walls of the maxillary antrum occurs as the result of new-growth or cyst formation within its cavity. Thus the facial surface may be prominently bulged outward, upward extension may displace the eyeball outward, or the nasal cavity on that side may be occluded, giving rise to unilateral obstruction. In some cases the disease will perforate the palatine process of the maxilla and a soft spot will be found under the mucoperiosteum. If the disease be malignant in nature, nothing short of excision of the maxilla is of any avail (see p. 300).

**THE ORGAN OF SIGHT (ORGANON VISUS; THE EYE).**

The **bulb of the eye** (*bulbus oculi*; *eyeball*), or **organ of sight**, is contained in the cavity of the orbit, where it is protected from injury and moved by the ocular muscles. Associated with it are certain accessory structures, viz., the muscles, fasciæ, eyebrows, eyelids, conjunctiva, and lacrimal apparatus.

The bulb of the eye is imbedded in the fat of the orbit, but is separated from it by a thin membranous sac, the *fascia bulbi* (page 1037). It is composed of segments of two spheres of different sizes. The anterior segment is one of a small sphere; it is transparent, and forms about one-sixth of the bulb. It is more prominent than the posterior segment, which is one of a larger sphere, and is opaque, and forms about five-sixths of the bulb. The term **anterior pole** is applied to the central point of the anterior curvature of the bulb, and that of **posterior pole** to the central point of its posterior curvature; a line joining the two poles forms the **optic axis**. The axes of the two bulbs are nearly parallel, and therefore do not correspond to the axes of the orbits, which are directed forward and lateralward. The optic nerves follow the direction of the axes of the orbits, and are therefore not parallel; each enters its eyeball 3 mm. to the nasal side and a little below the level of the posterior pole. The bulb measures rather more in its transverse and antero-posterior diameters than in its vertical diameter, the former amounting to about 24 mm., the latter to about 23.5 mm.; in the female all three diameters are rather less than in the male; its antero-posterior diameter at birth is about 17.5 mm., and at puberty from 20 to 21 mm.

The bulb of the eye is composed of three **tunics**, and of three **refracting media**.

**The Tunics of the Eye (Fig. 838).**

From without inward the three tunics are: (1) A fibrous tunic, consisting of the **sclera** behind and the **cornea** in front; (2) a vascular pigmented tunic, comprising, from behind forward, the **choroid**, **ciliary body**, and **iris**; and (3) a nervous tunic, the **retina**.

**The Fibrous Tunic** (*tunica fibrosa oculi*).—The sclera and cornea (Fig. 838) form the fibrous tunic of the bulb of the eye; the sclera is opaque, and constitutes the posterior five-sixths of the tunic; the cornea is transparent, and forms the anterior sixth.

**The Sclera.**—The sclera has received its name from its extreme density and hardness; it is a firm, unyielding membrane, serving to maintain the form of the bulb. It is much thicker behind than in front; the thickness of its posterior part is 1 mm. Its **external surface** is of white color, and is in contact with the inner surface of the *fascia* of the bulb; it is quite smooth, except at the points where the Recti and Obliqui are inserted into it; its anterior part is covered by the conjunctival membrane. Its **inner surface** is brown in color and marked by grooves, in which the ciliary nerves and vessels are lodged; it is separated from the outer surface of the choroid by an extensive lymph space (*spatium perichorioideale*) which is traversed by an exceedingly fine cellular tissue, the *lamina suprachorioidea*. Behind it is pierced by the optic nerve, and is continuous through the fibrous sheath of this nerve with the dura mater. Where the optic nerve passes through the sclera, the latter forms a thin cribriform lamina, the *lamina cribrosa sclerae*; the minute orifices in this lamina serve for the transmission of the nervous filaments, and the fibrous *septa* dividing them from one another are continuous with the membranous processes which separate the bundles of nerve fibres. One of these openings, larger than the rest, occupies the centre of the lamina; it transmits the central artery and vein of the retina. Around the entrance of the optic nerve are numerous



small apertures for the transmission of the ciliary vessels and nerves, and about midway between this entrance and the sclerocorneal junction are four or five large apertures for the transmission of veins (*venae vorticosae*). In front, the sclera is directly continuous with the cornea, the line of union being termed the **sclerocorneal junction**. In the inner part of the sclera close to this junction is a circular canal, the **sinus venosus sclerae** (*canal of Schlemm*). In a meridional section of this region this sinus presents the appearance of a cleft, the outer wall of which consists of the firm tissue of the sclera, while its inner wall is formed by a triangular mass of trabecular tissue (Fig. 839); the apex of the mass is directed forward and is continuous with the posterior elastic lamina of the cornea. The sinus is lined by endothelium and communicates internally with the anterior chamber of the eye and externally with the anterior ciliary veins.




FIG. 838.—Horizontal section of the eyeball.

**Structure.**—The sclera is formed of white fibrous tissue intermixed with fine elastic fibres; flattened connective-tissue corpuscles, some of which are pigmented, are contained in cell spaces between the fibres. The fibres are aggregated into bundles, which are arranged chiefly in a longitudinal direction. Its *vessels* are not numerous, the capillaries being of small size, uniting at long and wide intervals. Its *nerves* are derived from the ciliary nerves, but their exact mode of ending is not known.

**The Cornea.**—The cornea is the projecting transparent part of the external tunic, and forms the anterior sixth of the surface of the bulb. It is almost circular in outline, occasionally a little broader in the transverse than in the vertical direction. It is convex anteriorly and projects like a dome in front of the sclera. Its degree of curvature varies in different individuals, and in the same individual at different periods of life, being more pronounced in youth than in advanced life. The cornea is dense and of uniform thickness throughout; its posterior surface is perfectly circular in outline, and exceeds the anterior surface slightly in diameter. Immediately in front of the sclerocorneal junction the cornea bulges inward as a thickened

rim, and behind this there is a distinct furrow between the attachment of the iris and the sclerocorneal junction. This furrow has been named by Arthur Thomson<sup>1</sup> the **sulcus circularis corneae**; it is bounded externally by the trabecular tissue already described as forming the inner wall of the sinus venosus sclerae. Between this tissue and the anterior surface of the attached margin of the iris is an angular recess, named the **iridial angle** or **filtration angle** of the eye (Fig. 839). Immediately outside the filtration angle is a projecting rim of scleral tissue which appears in a meridional section as a small triangular area, termed the **scleral spur**. Its base is continuous with the inner surface of the sclera immediately to the outer side of the filtration angle and its apex is directed forward and inward. To the anterior sloping margin of this spur are attached the bundles of trabecular tissue just referred to; from its posterior margin the meridional fibres of the Ciliaris muscle arise.




FIG. 839.—Enlarged general view of the iridial angle. (Arthur Thomson.)

**Structure** (Fig. 840).—The cornea consists from before backward of four layers, viz.: (1) the **corneal epithelium**, continuous with that of the conjunctiva; (2) the **substantia propria**; (3) the **posterior elastic lamina**; and (4) the **endothelium** of the anterior chamber.

The **corneal epithelium** (*epithelium corneae*; *anterior layer*) covers the front of the cornea and consists of several layers of cells. The cells of the deepest layer are columnar; then follow two or three layers of polyhedral cells, the majority of which are prickle cells similar to those found in the stratum mucosum of the cuticle. Lastly, there are three or four layers of squamous cells, with flattened nuclei.

The **substantia propria** is fibrous, tough, unyielding, and perfectly transparent. It is composed of about sixty flattened lamellæ, superimposed one on another. These lamellæ are made up of bundles of modified connective tissue, the fibres of which are directly continuous with those

<sup>1</sup> Atlas of the Eye, Clarendon Press, Oxford, 1912.

of the sclera. The fibres of each lamella are for the most part parallel with one another, but at right angles to those of adjacent lamellæ. Fibres, however, frequently pass from one lamella to the next.

The lamellæ are connected with each other by an interstitial cement substance, in which are spaces, the **corneal spaces**. These are stellate in shape and communicate with one another by numerous offsets. Each contains a cell, the **corneal corpuscle**, resembling in form the space in which it is lodged, but not entirely filling it.




FIG. 840.—Vertical section of human cornea from near the margin. (Waldeyer.) Magnified. 1. Epithelium. 2. Anterior elastic lamina. 3. substantia propria. 4. Posterior elastic lamina. 5. Endothelium of the anterior chamber. a. Oblique fibres in the anterior layer of the substantia propria. b. Lamellæ the fibres of which are cut across, producing a dotted appearance. c. Corneal corpuscles appearing fusiform in section. d. Lamellæ the fibres of which are cut longitudinally. e. Transition to the sclera, with more distinct fibrillation, and surmounted by a thicker epithelium. f. Small bloodvessels cut across near the margin of the cornea.

The layer immediately beneath the corneal epithelium presents certain characteristics which have led some anatomists to regard it as a distinct membrane, and it has been named the **anterior elastic lamina** (*lamina elastica anterior*; *anterior limiting layer*; *Bowman's membrane*). It differs, however, from the posterior elastic lamina, in presenting evidence of fibrillar structure, and in not having the same tendency to curl inward, or to undergo fracture, when detached from the other layers of the cornea. It consists of extremely closely interwoven fibrils, similar to those found in the substantia propria, but contains no corneal corpuscles. It may be regarded as a condensed part of the substantia propria.

The **posterior elastic lamina** (*lamina elastica posterior*; *membrane of Descemet*; *membrane of Demours*) covers the posterior surface of the substantia propria, and is an elastic, transparent homogeneous membrane, of extreme thinness, which is not rendered opaque by either water,



alcohol, or acids. When stripped from the substantia propria it curls up, or rolls upon itself with the attached surface innermost.

At the margin of the cornea the posterior elastic lamina breaks up into fibres which form the trabecular tissue already described (p. 1008); the spaces between the trabeculae are termed the **spaces of the angle of the iris** (*spaces of Fontana*); they communicate with the sinus venosus sclerae and with the anterior chamber at the filtration angle. Some of the fibres of this trabecular tissue are continued into the substance of the iris, forming the **pectinate ligament of the iris**; while others are connected with the forepart of the sclera and choroid.

The **endothelium of the anterior chamber** (*endothelium camerae anterioris*; *posterior layer*; *corneal endothelium*) covers the posterior surface of the elastic lamina, is reflected on to the front of the iris, and also lines the spaces of the angle of the iris; it consists of a single stratum of polygonal, flattened, nucleated cells.

**Vessels and Nerves.**—The cornea is a non-vascular structure, the capillary vessels ending in loops at its circumference. Lymphatic vessels have not yet been demonstrated in it, but are represented by the channels in which the bundles of nerves run; these channels are lined by an endothelium. The **nerves** are numerous and are derived from the ciliary nerves. Around the periphery of the cornea they form an *annular plexus*, from which fibres enter the substantia propria. They lose their medullary sheaths and ramify throughout its substance in a delicate net-work, and their terminal filaments form a firm and closer plexus on the surface of the cornea proper, beneath the epithelium. This is termed the *subepithelial plexus*, and from it fibrils are given off which ramify between the epithelial cells, forming an *intraepithelial plexus*.

**Dissection.**—In order to separate the sclera and cornea, so as to expose the second tunic, the eyeball should be immersed in a small vessel of water and held between the finger and thumb. The sclera is then carefully incised, in the equator of the globe, until the choroid is exposed. One blade of a pair of probe-pointed scissors is now introduced through the opening thus made, and the sclera divided around its entire circumference, and removed in separate portions. The front segment being then drawn forward, the handle of the scalpel should be pressed gently against it at its connection with the iris, and, these being separated, a quantity of perfectly transparent fluid will escape; this is the aqueous humor. In the course of the dissection the ciliary nerves (Fig. 841) may be seen lying in the loose cellular tissue between the choroid and sclera or continued in delicate grooves on the inner surface of the latter membrane.

**The Vascular Tunic** (*tunica vasculosa oculi*) (Figs. 841, 842, 843).—The vascular tunic of the eye is formed from behind forward by the choroid, the ciliary body, and the iris.

The choroid invests the posterior five-sixths of the bulb, and extends as far forward as the ora serrata of the retina. The ciliary body connects the choroid to the circumference of the iris. The iris is a circular diaphragm behind the cornea, and presents near its centre a rounded aperture, the **pupil**.

**The Choroid** (*chorioidea*).—The choroid is a thin, highly vascular membrane, of a dark brown or chocolate color, investing the posterior five-sixths of the globe; it is pierced behind by the optic nerve, and in this situation is firmly adherent to the sclera. It is thicker behind than in front. Its outer surface is loosely connected by the lamina suprachorioidea with the sclera; its inner surface is attached to the pigmented layer of the retina.

**Structure.**—The choroid consists mainly of a dense capillary plexus, and of small arteries and veins carrying blood to and returning it from this plexus. On its external surface is a thin




FIG. 841.—The choroid and iris. (Enlarged.)

membrane, the **lamina suprachoriodea**, composed of delicate non-vascular lamellæ—each lamella consisting of a net-work of fine elastic fibres among which are branched pigment cells. The spaces between the lamellæ are lined by endothelium, and open freely into the perichoroidal lymph space, which, in its turn, communicates with the periscleral space by the perforations in the sclera through which the vessels and nerves are transmitted.




FIG. 842.—The arteries of the choroid and iris. The greater part of the sclera has been removed. (Enlarged.)

Internal to this lamina is the **choroid proper**, consisting of two layers: an outer, composed of small arteries and veins, with pigment cells interspersed between them; and an inner, consisting of a capillary plexus. The **outer layer** (*lamina vasculosa*) consists, in part, of the larger branches of the short ciliary arteries which run forward between the veins, before they bend inward to end in the capillaries, but is formed principally of veins, named, from their arrangement, the **venae**

**vorticossae**. They converge to four or five equidistant trunks, which pierce the sclera about midway between the sclero-corneal junction and the entrance of the optic nerve. Interspersed between the vessels are dark star-shaped pigment cells, the processes of which, communicating with those of neighboring cells, form a delicate net-work or stroma, which toward the inner surface of the choroid loses its pigmentary character. The **inner layer** (*lamina choriocapillaris*) consists of an exceedingly fine capillary plexus, formed by the short ciliary vessels; the net-work is closer and finer in the posterior than in the anterior part of the choroid. About 1.25 cm. behind the cornea its meshes become larger, and are continuous with those of the ciliary processes. These two laminae are connected by a **stratum intermedium** consisting of fine elastic fibres. On the inner surface of the lamina choriocapillaris is a very thin, structureless, or faintly




FIG. 843.—The veins of the choroid. (Enlarged.)

fibrous membrane, called the **lamina basalis**; it is closely connected with the stroma of the choroid, and separates it from the pigmentary layer of the retina.

**Tapetum**.—This name is applied to the outer and posterior part of the choroid, which in many animals presents an iridescent appearance.

**Dissection**.—The ciliary body should now be examined. It may be exposed, either by detaching the iris from its connection with the Ciliaris muscle, or by making a transverse section of the globe, and examining it from behind.



**The Ciliary Body** (*corpus ciliare*).—The ciliary body comprises the **orbiculus ciliaris**, the **ciliary processes**, and the **Ciliaris muscle**.

The **orbiculus ciliaris** is a zone of about 4 mm. in width, directly continuous with the anterior part of the choroid; it presents numerous ridges arranged in a radial manner (Fig. 844).




FIG. 844.—Interior of anterior half of bulb of eye.

The **ciliary processes** (*processus ciliares*) are formed by the inward folding of the various layers of the choroid, *i. e.*, the choroid proper and the lamina basalis, and are received between corresponding foldings of the suspensory ligament of the lens. They are arranged in a circle, and form a sort of frill behind the iris, around the margin of the lens (Fig. 844). They vary from sixty to eighty in number, lie side by side, and may be divided into large and small; the former are about 2.5 mm. in length, and the latter, consisting of about one-third of the entire number, are situated in spaces between them, but without regular arrangement. They are attached by their periphery to three or four of the ridges of the orbiculus ciliaris, and are continuous with the layers of the choroid: their opposite extremities are free and rounded, and are directed toward the posterior chamber of the eyeball and circumference of the lens. In front, they are continuous with the periphery of the iris. Their posterior surfaces are connected with the suspensory ligament of the lens.

**Structure.**—The ciliary processes (Figs. 845, 846) are similar in structure to the choroid, but the vessels are larger, and have chiefly a longitudinal direction. Their posterior surfaces are covered by a bilaminar layer of black pigment cells, which is continued forward from the retina, and is named the **pars ciliaris retinae**. In the stroma of the ciliary processes there are also stellate pigment cells, but these are not so numerous as in the choroid itself.

The **Ciliaris muscle** (*m. ciliaris*; *Bowman's muscle*) consists of unstriated fibres: it forms a grayish, semitransparent, circular band, about 3 mm. broad, on the outer surface of the forepart of the choroid. It is thickest in front, and consists of two sets of fibres, **meridional** and **circular**. The meridional fibres, much the more numerous, arise from the posterior margin of the scleral spur (page 1019); they run backward, and are attached to the ciliary processes and orbiculus ciliaris. One bundle, according to Waldeyer, is inserted into the sclera. The circular fibres are internal to the meridional ones, and in a meridional section appear as a triangular zone

behind the filtration angle and close to the circumference of the iris. They are well-developed in hypermetropic, but are rudimentary or absent in myopic eyes. The Ciliaris muscle is the chief agent in accommodation, *i. e.*, in adjusting the eye to the vision of near objects. When it contracts it draws forward the ciliary processes, relaxes the suspensory ligament of the lens, and thus allows the lens to become more convex.

**The Iris.**—The iris has received its name from its various colors in different individuals. It is a thin, circular, contractile disk, suspended in the aqueous humor between the cornea and lens, and perforated a little to the nasal side of its centre by a circular aperture, the **pupil**. By its periphery it is continuous with the ciliary body, and is also connected with the posterior elastic lamina of the cornea by means of the pectinate ligament; its surfaces are flattened, and look forward and backward, the ante-



FIG. 845.—Vessels of the choroid, ciliary processes, and iris of a child. (Arnold.) Magnified 10 times. *a*. Capillary net-work of the posterior part of the choroid, ending at *b*, the ora serrata. *c*. Arteries of the corona ciliaris, supplying the ciliary processes, *d*, and passing into the iris *e*. *f*. The capillary net-work close to the pupillary margin of the iris.




FIG. 846.—Diagrammatic representation of the course of the vessels in the eye. Horizontal section. (Leber.) Arteries and capillaries red; veins blue. *O*. Entrance of optic nerve. *a*. Short posterior ciliary arteries. *b*. Long posterior ciliary arteries. *c*. Anterior ciliary vessels. *d*. Posterior conjunctival vessels. *d'*. Anterior conjunctival vessels. *e*. Central vessels of the retina. *f*. Vessels of the inner sheath of the optic nerve. *g*. Vessels of the outer sheath. *h*. Vorticose vein. *i*. Short posterior ciliary vein. *k*. Branches of the short posterior ciliary arteries to the optic nerve. *l*. Anastomosis of choroidal vessels with those of optic nerve. *m*. Choriocapillaris. *n*. Episcleral vessels. *o*. Recurrent artery of the choroid. *p*. Circulus iridis major (in section). *q*. Vessels of iris. *r*. Vessels of ciliary process. *s*. Branch from ciliary muscle to vorticose vein. *t*. Branch from ciliary muscle to anterior ciliary vein. *u*. Sinus venosus sclerae. *v*. Capillary loop at margin of cornea.

rior toward the cornea, the posterior toward the ciliary processes and lens. The iris divides the space between the lens and the cornea into an anterior and a posterior chamber. The **anterior chamber** of the eye is bounded in front by the posterior surface of the cornea; behind by the front of the iris and the central part of the lens. The **posterior chamber** is a narrow chink behind the peripheral part of the iris, and in front of the suspensory ligament of the lens and the ciliary processes. In the adult the two chambers communicate through the pupil, but in the fetus up to the seventh month they are separated by the *membrana pupillaris*.

**Structure.**—The iris is composed of the following structures:

1. In front is a layer of flattened endothelial cells placed on a delicate hyaline basement membrane. This layer is continuous with the endothelium covering the posterior elastic lamina of the cornea, and in individuals with dark-colored irides the cells contain pigment granules.

2. The **stroma** (*stroma iridis*) of the iris consists of fibres and cells. The former are made up of delicate bundles of fibrous tissue; a few fibres at the circumference of the iris have a circular direction; but the majority radiate toward the pupil, forming by their interlacement, delicate meshes, in which the vessels and nerves are contained. Interspersed between the bundles of connective tissue are numerous branched cells with fine processes. In dark eyes many of them contain pigment granules, but in blue eyes and the eyes of albinos they are unpigmented.

3. The **muscular fibres** are involuntary, and consist of circular and radiating fibres. The **circular fibres** form the Sphincter pupillae; they are arranged in a narrow band about 1 mm. in width which surrounds the margin of the pupil toward the posterior surface of the iris; those near the free margin are closely aggregated; those near the periphery of the band are somewhat separated and form incomplete circles. The **radiating fibres** form the Dilator pupillae; they converge from the circumference toward the centre, and blend with the circular fibres near the margin of the pupil.

4. The posterior surface of the iris is of a deep purple tint, being covered by two layers of pigmented columnar epithelium, continuous at the periphery of the iris with the pars ciliaris retinae. This pigmented epithelium is named the **pars iridica retinae**, or, from the resemblance of its color to that of a ripe grape, the **uvea**.

The color of the iris is produced by the reflection of light from dark pigment cells underlying a translucent tissue, and is therefore determined by the amount of the pigment and its distribution throughout the texture of the iris. The number and the situation of the pigment cells differ in different irides. In the albino pigment is absent; in the various shades of blue eyes the pigment cells are confined to the posterior surface of the iris, whereas in gray, brown, and black eyes pigment is found also in the cells of the stroma and in those of the endothelium on the front of the iris.




FIG. 847.—The iris, viewed from in front, with its greater and smaller arterial circles. (Testut.) *a*. Choroid. *b*. Ciliaris muscle. *c*. Iris. *d*. Pupil. 1 and 1'. The two long ciliary arteries, with 2, their ascending branch of bifurcation; 3, their descending branch of bifurcation. 4. The anterior ciliary arteries. 5. Circulus major; 6, its branches radiating through the iris. 7. Circulus minor around the pupil.

**Vessels and Nerves.**—The **arteries of the iris** are derived from the long and anterior ciliary arteries, and from the vessels of the ciliary processes (see p. 650). Each of the two long ciliary arteries, having reached the attached margin of the iris, divides into an upper and lower branch; these anastomose with corresponding branches from the opposite side and thus encircle the iris; into this vascular circle (*circulus arteriosus major*) the anterior ciliary arteries pour their blood, and from it vessels converge to the free margin of the iris, and there communicate and form a second circle (*circulus arteriosus minor*) (Figs. 846 and 847).

The **nerves of the choroid and iris** are the long and short ciliary; the former being branches of the nasociliary nerve, the latter of the ciliary ganglion. They pierce the sclera around the entrance of the optic nerve, run forward in the perichoroidal space, and supply the bloodvessels of the choroid. After reaching the iris they form a plexus around its attached margin; from this are derived non-medullated fibres which end in the Sphincter and Dilatator pupillae; their exact mode of termination has not been ascertained. Other fibres from the plexus end in a net-work on the anterior surface of the iris. The fibres derived through the motor root of the ciliary ganglion from the oculomotor nerve, supply the Sphincter, while those derived from the sympathetic supply the Dilatator.

**Membrana Pupillaris.**—In the fetus, the pupil is closed by a delicate vascular membrane, the **membrana pupillaris**, which divides the space in which the iris is suspended into two distinct chambers. The vessels of this membrane are partly derived from those of the margin of the iris and partly from those of the capsule of the lens; they have a looped arrangement, and converge toward each other without anastomosing. About the sixth month the membrane begins to disappear by absorption from the centre toward the circumference, and at birth only a few fragments are present; in exceptional cases it persists.




FIG. 848.—Interior of posterior half of bulb of left eye. The veins are darker in appearance than the arteries.

**The Retina** (*tunica interna*).—The retina is a delicate nervous membrane, upon which the images of external objects are received. Its outer surface is in contact with the choroid; its inner with the hyaloid membrane of the vitreous body. Behind, it is continuous with the optic nerve; it gradually diminishes in thickness from behind forward, and extends nearly as far as the ciliary body, where it appears to end in a jagged margin, the **ora serrata**. Here the nervous tissues of the retina end, but a thin prolongation of the membrane extends forward over the back of the ciliary processes and iris, forming the **pars ciliaris retinae** and **pars iridica retinae** already referred to. This forward prolongation consists of the pigmentary layer of the retina together with a stratum of columnar epithelium. The retina is soft, semitransparent, and of a purple tint in the fresh state, owing to the presence of a coloring material named **rhodopsin** or **visual purple**; but it soon becomes clouded, opaque, and bleached when exposed to sunlight. Exactly in the centre of the posterior part of the retina, corresponding to the axis of the eye, and at a point in which the sense of vision is most perfect, is an oval yellowish area, the **macula lutea**; in the macula is a central depression, the **fovae centralis** (Fig. 848). At the fovea centralis the retina is exceedingly thin, and the dark color of the choroid is



distinctly seen through it. About 3 mm. to the nasal side of the macula lutea is the entrance of the optic nerve (*optic disk*), the circumference of which is slightly raised to form an eminence (*colliculus nervi optici*) (Fig. 849); the *arteria centralis retinae* pierces the centre of the disk. This is the only part of the surface of the retina which is insensitive to light, and it is termed the **blind spot**.




FIG. 849.—The terminal portion of the optic nerve and its entrance into the eyeball, in horizontal section. (Toldt.)

**Structure** (Figs. 850, 851).—The retina consists of an outer pigmented layer and an inner nervous stratum or retina proper.

The **pigmented layer** consists of a single stratum of cells. When viewed from the outer surface these cells are smooth and hexagonal in shape; when seen in section each cell consists of an outer non-pigmented part containing a large oval nucleus and an inner pigmented portion which extends as a series of straight thread-like processes between the rods, this being especially the case when the eye is exposed to light. In the eyes of albinos the cells of this layer are destitute of pigment.

**Retina Proper.**—The nervous structures of the retina proper are supported by a series of non-nervous or sustentacular fibres, and, when examined microscopically by means of sections made perpendicularly to the surface of the retina, are found to consist of seven layers, named from within outward as follows:

1. Stratum opticum.
2. Ganglionic layer.
3. Inner plexiform layer.
4. Inner nuclear layer, or layer of inner granules.
5. Outer plexiform layer.
6. Outer nuclear layer, or layer of outer granules.
7. Layer of rods and cones.

1. The **stratum opticum** or **layer of nerve fibres** is formed by the expansion of the fibres of the optic nerve; it is thickest near the *porus opticus*, gradually diminishing toward the *ora serrata*. As the nerve fibres pass through the *lamina cribrosa sclerae*, they lose their medullary sheaths and are continued onward through the choroid and retina as simple axis-cylinders. When they reach the internal surface of the retina they radiate from their point of entrance over this surface grouped in bundles, and in many places arranged in plexuses. Most of the fibres are centripetal, and are the direct continuations of the axis-cylinder processes of the cells of the ganglionic layer, but a few of them are centrifugal and ramify in the inner plexiform and inner nuclear layers, where they end in enlarged extremities.




FIG. 850. — Section of retina. (Magnified.) a. Membrana limitans interna. b. Stratum opticum. c. Ganglionic layer. d. Inner plexiform layer. e. Inner nuclear layer. f. Outer plexiform layer. g. Outer nuclear layer. h. Membrana limitans externa. i. Layer of rods and cones. k. Pigmented layer. m. Fibres of Müller.



2. The **ganglionic layer** consists of a single layer of large ganglion cells, except in the macula lutea, where there are several strata. The cells are somewhat flask-shaped; the rounded internal surface of each resting on the stratum opticum, and sending off an axon which is prolonged into it. From the opposite end numerous dendrites extend into the inner plexiform layer, where they branch and form flattened arborizations at different levels. The ganglion cells vary much in size, and the dendrites of the smaller ones as a rule arborize in the inner plexiform layer as soon as they enter it; while those of the larger cells ramify close to the inner nuclear layer.

3. The **inner plexiform layer** is made up of a dense reticulum of minute fibrils formed by the interlacement of the dendrites of the ganglion cells with those of the cells of the inner nuclear layer; within this reticulum a few branched spongioblasts are sometimes imbedded.

4. The **inner nuclear layer or layer of inner granules** is made up of a number of closely packed cells, of which there are three varieties, viz.: bipolar cells, horizontal cells, and amacrine cells.




FIG. 851.—Plan of retinal neurons. (After Cajal.)

The **bipolar cells**, by far the most numerous, are round or oval in shape, and each is prolonged into an inner and an outer process. They are divisible into rod bipolars and cone bipolars. The inner processes of the **rod bipolars** run through the inner plexiform layer and arborize around the bodies of the cells of the ganglionic layer; their outer processes end in the outer plexiform layer in tufts of fibrils around the button-like ends of the inner processes of the rod granules. The inner processes of the **cone bipolars** ramify in the inner plexiform layer in contact with the dendrites of the ganglionic cells.

The **horizontal cells** lie in the outer part of the inner nuclear layer and possess somewhat flattened cell bodies. Their dendrites divide into numerous branches in the outer plexiform layer, while their axons run horizontally for some distance and finally ramify in the same layer.

The **amacrine cells** are placed in the inner part of the inner nuclear layer, and are so named because they have not yet been shown to possess axis-cylinder processes. Their dendrites undergo extensive ramification in the inner plexiform layer.

5. The **outer plexiform layer** is much thinner than the inner; but, like it, consists of a dense net-work of minute fibrils derived from the processes of the horizontal cells of the preceding layer, and the outer processes of the rod and cone bipolar granules, which ramify in it, forming arborizations around the enlarged ends of the rod fibres and with the branched foot plates of the cone fibres.

6. The **outer nuclear layer or layer of outer granules**, like the inner nuclear layer, contains several strata of oval nuclear bodies; they are of two kinds, viz.: rod and cone granules, so

named on account of their being respectively connected with the rods and cones of the next layer. The **rod granules** are much the more numerous, and are placed at different levels throughout the layer. Their nuclei present a peculiar cross-striated appearance, and prolonged from either extremity of each cell is a fine process; the outer process is continuous with a single rod of the layer of rods and cones; the inner ends in the outer plexiform layer in an enlarged extremity, and is imbedded in the tuft into which the outer processes of the rod bipolar cells break up. In its course it presents numerous varicosities. The **cone granules**, fewer in number than the rod granules, are placed close to the *membrana limitans externa*, through which they are continuous with the cones of the layer of rods and cones. They do not present any cross-striation, but contain a pyriform nucleus, which almost completely fills the cell. From the inner extremity of the granule a thick process passes into the outer plexiform layer, and there expands into a pyramidal enlargement or foot plate, from which are given off numerous fine fibrils, that come in contact with the outer processes of the cone bipolars.

**7. The Layer of Rods and Cones (*Jacob's membrane*).**—The elements composing this layer are of two kinds, **rods** and **cones**, the former being much more numerous than the latter except in the macula lutea. The **rods** are cylindrical, of nearly uniform thickness, and are arranged perpendicularly to the surface. Each rod consists of two segments, an outer and inner, of about equal lengths. The segments differ from each other as regards refraction and in their behavior toward coloring reagents; the inner segment is stained by carmine, iodine, etc.; the outer segment is not stained by these reagents, but is colored yellowish brown by osmic acid. The outer segment is marked by transverse striæ, and tends to break up into a number of thin disks superimposed on one another; it also exhibits faint longitudinal markings. The deeper part of the inner segment is indistinctly granular; its more superficial part presents a longitudinal striation, being composed of fine, bright, highly refracting fibrils. The visual purple or rhodopsin is found only in the outer segments.

The **cones** are conical or flask-shaped, their broad ends resting upon the *membrana limitans externa*, the narrow-pointed extremity being turned to the choroid. Like the rods, each is made up of two segments, outer and inner; the outer segment is a short conical process, which, like the outer segment of the rod, exhibits transverse striæ. The inner segment resembles the inner segment of the rods in structure, presenting a superficial striated and deep granular part, but differs from it in size and shape, being bulged out laterally and flask-shaped. The chemical and optical characters of the two portions are identical with those of the rods.

**Supporting Frame-work of the Retina.**—The nervous layers of the retina are connected together by a supporting frame-work, formed by the **sustentacular fibres of Müller**; these fibres pass through all the nervous layers, except that of the rods and cones. Each begins on the inner surface of the retina by an expanded, often forked base, which sometimes contains a spheroidal body staining deeply with hematoxylin, the edges of the bases of adjoining fibres being united to form the *membrana limitans interna*. As the fibres pass through the nerve fibre and ganglionic layers they give off a few lateral branches; in the inner nuclear layer they give off numerous lateral processes for the support of the bipolar cells, while in the outer nuclear layer they form a network around the rod- and cone-fibrils, and unite to form the **external limiting membrane** at the bases of the rods and cones. At the level of the inner nuclear layer each sustentacular fibre contains a clear oval nucleus.

**Macula Lutea and Fovea Centralis.**—In the macula lutea the nerve fibres are wanting as a continuous layer, the ganglionic layer consists of several strata of cells, there are no rods, but only cones, which are longer and narrower than in other parts, and in the outer nuclear layer there are only cone-granules, the processes of which are very long and arranged in curved lines. In the fovea centralis the only parts present are (1) the cones; (2) the outer nuclear layer, the cone-fibres of which are almost horizontal in direction; (3) an exceedingly thin inner plexiform layer. The pigmented layer is thicker and its pigment more pronounced than elsewhere. The color of the macula seems to imbue all the layers except that of the rods and cones; it is of a rich yellow, deepest toward the centre of the macula, and does not appear to be due to pigment cells, but simply to a staining of the constituent parts.

At the *ora serrata* the nervous layers of the retina end abruptly, and the retina is continued onward as a single layer of columnar cells covered by the pigmented layer. This double layer is known as the *pars ciliaris retinae*, and can be traced forward from the ciliary processes on to the back of the iris, where it is termed the *pars iridica retinae* or *uvea*.

The *arteria centralis retinae* (Fig. 848) and its accompanying vein pierce the optic nerve, and enter the bulb of the eye through the porus opticus. The artery immediately bifurcates into an upper and a lower branch, and each of these again divides into a medial or nasal and a lateral or temporal branch, which at first run between the hyaloid membrane and the nervous layer; but they soon enter the latter, and pass forward, dividing dichotomously. From these branches a minute capillary plexus is given off, which does not extend beyond the inner nuclear layer. The macula receives two small branches (superior and inferior macular arteries) from the temporal branches and small twigs directly from the central artery; these do not, however, reach as far as the fovea centralis, which has no bloodvessels. The branches of the *arteria centralis*

retinae do not anastomose with each other—in other words they are terminal arteries. In the fetus, a small vessel, the *arteria hyaloidea*, passes forward as a continuation of the *arteria centralis* retinae through the vitreous humor to the posterior surface of the capsule of the lens.

### The Refracting Media.

The refracting media are three, viz.:

Aqueous humor.

Vitreous body.

Crystalline lens.

**The Aqueous Humor** (*humor aqueus*).—The aqueous humor fills the anterior and posterior chambers of the eyeball. It is small in quantity, has an alkaline reaction, and consists mainly of water, less than one-fiftieth of its weight being solid matter, chiefly chloride of sodium.

**The Vitreous Body** (*corpus vitreum*).—The vitreous body forms about four-fifths of the bulb of the eye. It fills the concavity of the retina, and is hollowed in front, forming a deep concavity, the *hyaloid fossa*, for the reception of the lens. It is transparent, of the consistence of thin jelly, and is composed of an albuminous fluid enclosed in a delicate transparent membrane, the *hyaloid membrane*. It has been supposed, by Hannover, that from its surface numerous thin lamellæ are prolonged inward in a radiating manner, forming spaces in which the fluid is contained. In the adult, these lamellæ cannot be detected even after careful microscopic examination in the fresh state, but in preparations hardened in weak chromic acid it is possible to make out a distinct lamellation at the periphery of the body. In the centre of the vitreous body, running from the entrance of the optic nerve to the posterior surface of the lens, is a canal, the *hyaloid canal*, filled with lymph and lined by a prolongation of the hyaloid membrane. This canal, in the embryonic vitreous body, conveyed the *arteria hyaloidea* from the central artery of the retina to the back of the lens. The fluid from the vitreous body is nearly pure water; it contains, however, some salts, and a little albumin.

The *hyaloid membrane* envelopes the vitreous body. The portion in front of the *ora serrata* is thickened by the accession of radial fibres and is termed the *zonula ciliaris* (*zonule of Zinn*). Here it presents a series of radially arranged furrows, in which the ciliary processes are accommodated and to which they adhere, as is shown by the fact that when they are removed some of their pigment remains attached to the zonula. The *zonula ciliaris* splits into two layers, one of which is thin and lines the *hyaloid fossa*; the other is named the **suspensory ligament of the lens**: it is thicker, and passes over the ciliary body to be attached to the capsule of the lens a short distance in front of its equator. Scattered and delicate fibres are also attached to the region of the equator itself. This ligament retains the lens in position, and is relaxed by the contraction of the meridional fibres of the *Ciliaris* muscle, so that the lens is allowed to become more convex. Behind the suspensory ligament there is a sacculated canal, the *spatia zonularis* (*canal of Petit*), which encircles the equator of the lens; it can be easily inflated through a fine blowpipe inserted under the suspensory ligament.

No bloodvessels penetrate the vitreous body, so that its nutrition must be carried on by vessels of the retina and ciliary processes, situated upon its exterior.

**The Crystalline Lens** (*lens crystallina*).—The crystalline lens, enclosed in its capsule, is situated immediately behind the iris, in front of the vitreous body, and encircled by the ciliary processes, which slightly overlap its margin.

The **capsule of the lens** (*capsula lentis*) is a transparent, structureless membrane which closely surrounds the lens, and is thicker in front than behind. It is brittle but highly elastic, and when ruptured the edges roll up with the outer surface innermost. It rests, behind, in the *hyaloid fossa* in the forepart of the vitreous body; in front, it is in contact with the free border of the iris, but recedes from it

at the circumference, thus forming the posterior chamber of the eye; it is retained in its position chiefly by the suspensory ligament of the lens, already described.

The **lens** is a transparent, biconvex body, the convexity of its anterior being less than that of its posterior surface. The central points of these surfaces are termed respectively the **anterior** and **posterior poles**; a line connecting the poles constitutes the **axis** of the lens, while the marginal circumference is termed the **equator**.

**Structure.**—The lens is made up of soft cortical substance and a firm, central part, the **nucleus** (Fig. 852). Faint lines (*radii lentis*) radiate from the poles to the equator. In the adult there may be six or more of these lines, but in the fetus they are only three in number and diverge from each other at angles of  $120^\circ$  (Fig. 853); on the anterior surface one line ascends vertically and the other two diverge downward; on the posterior surface one ray descends vertically and the other two diverge upward. They correspond with the free edges of an equal number of septa composed of an amorphous substance, which dip into the substance of the lens. When the lens has been hardened it is seen to consist of a series of concentrically arranged laminae, each of which is interrupted at the septa referred to. Each lamina is built up of a number of hexagonal, ribbon-like lens fibres, the edges of which are more or less serrated—the serrations fitting between those of neighboring fibres, while the ends of the fibres come into apposition at the septa. The fibres run in a curved manner from the septa on the anterior surface to those on the posterior surface. No fibres pass from pole to pole; they are arranged in such a way that those which begin near the pole on one surface of the lens end near the peripheral extremity of the plane on the other, and *vice versa*. The fibres of the outer layers of the lens are nucleated, and together form a nuclear layer, most distinct toward the equator. The anterior surface of the lens is covered by a layer of transparent, columnar, nucleated epithelium. At the equator the cells become elongated, and their gradual transition into lens fibres can be traced (Fig. 855).



FIG. 852.—The crystalline lens, hardened and divided. (Enlarged.)



FIG. 853.—Diagram to show the direction and arrangement of the radiating lines on the front and back of the fetal lens. A. From the front. B. From the back.

**In the fetus**, the lens is nearly spherical, and has a slightly reddish tint; it is soft and breaks down readily on the slightest pressure. A small branch from the *arteria centralis retinae* runs forward, as already mentioned, through the vitreous body to the posterior part of the capsule of the lens, where its branches radiate and form a plexiform network, which covers the posterior surface of the capsule, and they are continuous around the margin of the capsule with the vessels of the pupillary membrane, and with those of the iris. **In the adult**, the lens is colorless, transparent, firm in texture, and devoid of vessels. **In old age** it becomes flattened on both surfaces, slightly opaque, of an amber tint, and increased in density (Fig. 854).

**Vessels and Nerves.**—The **arteries** of the bulb of the eye are the long, short, and anterior ciliary arteries, and the *arteria centralis retinae*. They have already been described (see p. 650).

The **ciliary veins** are seen on the outer surface of the choroid, and are named, from their arrangement, the *venae vorticosae*; they converge to four or five equidistant trunks which pierce the sclera midway between the sclerocorneal junction and the porus opticus. Another set of veins accompanies the anterior ciliary arteries. All of these veins open into the ophthalmic veins.

The **ciliary nerves** are derived from the nasociliary nerve and from the ciliary ganglion.

**Applied Anatomy.**—From a surgical point of view the cornea may be regarded as consisting of three layers: (1) an external epithelial layer, developed from the ectoderm, and continuous with the epithelial covering of the rest of the body, so that its lesions resemble those of the epidermis; (2) the cornea proper, derived from the mesoderm, and associated in its diseases with

the fibrovascular structures of the body; and (3) the posterior elastic lamina with its endothelium, also derived from the mesoderm and having the characters of a serous membrane, so that inflammation of it resembles inflammation of the serous and synovial membranes of the body.

The cornea contains no bloodvessels except at its periphery, where numerous delicate loops, derived from the anterior ciliary arteries, may be demonstrated on its anterior surface. The rest of the cornea is nourished by lymph, which gains access to the proper substance of the cornea and the posterior layer through the spaces of the angle of the iris. This lack of a direct blood supply renders the cornea very apt to inflame in the cachectic and ill-nourished. In cases of *granular lids*, there is a peculiar affection of the cornea, called *pannus*, in which the anterior layers of the cornea become vascularized, and a rich net-work of bloodvessels may be seen upon it; and in interstitial keratitis new vessels extend into the cornea, giving it a pinkish hue to which the term "salmon patch" is applied. In cases of glaucoma the ciliary nerves may be pressed upon as they course between the choroid and sclera, and the cornea becomes anesthetic.

The sclera has very few bloodvessels and nerves. As the bloodvessels approach the corneal margin the arrangement is peculiar. Some branches pass through the sclera to the ciliary body; others become superficial and lie in the episcleral tissue, and form arches, by anastomosing with each other some little distance behind the corneal margin. From these arches numerous straight vessels are given off, which run forward to the cornea, forming its marginal plexus. In inflammation of the sclera and episcleral tissue these vessels become conspicuous, and form a pinkish zone of straight vessels radiating from the corneal margin, commonly known as the *zone of ciliary injection*. In inflammation of the iris and ciliary body this zone is present, since the sclera speedily becomes involved when these structures are inflamed. But in inflammation of the cornea the sclera is seldom much affected, though the two are structurally continuous. This would appear to be due to the fact, that the nutrition of the cornea is derived from a different source than that of the sclera. The sclera may be ruptured without any laceration of the conjunctiva, and the rupture usually occurs near the corneal margin. It may be complicated with lesions of adjacent parts—laceration of the choroid, retina, iris, or suspensory ligament of the lens—and is then often attended with hemorrhage into the anterior chamber, which masks the nature of the injury. In some cases the lens has escaped through the rent in the sclera and has been found under the conjunctiva. Wounds of the sclera are always dangerous, and are often followed by inflammation, suppuration, and by sympathetic ophthalmia.




FIG. 854.—Profile views of the lens at different periods of life.  
1. In the fetus. 2. In adult life. 3. In old age.




FIG. 855.—Section through the margin of the lens, showing the transition of the epithelium into the lens fibres. (Babuchin.)

One of the functions of the choroid is to provide nutrition for the retina, and to convey vessels and nerves to the ciliary body and iris. Inflammation of the choroid is therefore followed by grave disturbances in the nutrition of the retina, and is attended with early interference with



vision. Its diseases bear a considerable analogy to those which affect the skin, and it is one of the places from which melanotic sarcomata may grow. These tumors contain a large amount of pigment in their cells, and originate only in those parts where pigment is naturally present.

The iris may be absent, either in part or altogether as a congenital condition, and in some instances the pupillary membrane may remain persistent, though it is rarely complete. Again, the iris may be the seat of a malformation, termed *coloboma*, which consists in a deficiency or cleft, clearly due in a great number of cases to an arrest in development. In these cases the cleft is found at the lower aspect, extending directly downward from the pupil, and the gap frequently extends through the choroid to the porus opticus. In some rarer cases the gap is found in other parts of the iris, and is not then associated with any deficiency of the choroid. Wounds of the iris, especially if complicated with injury to the ciliary body, may be followed by serious consequences. If septic matter is introduced, and a suppurative inflammation is set up, complete loss of vision may result; and, what is perhaps of greater consequence, similar inflammatory changes may be set up in the sound eye, from spreading of the infective process through the connective tissue surrounding the optic nerve to the chiasma, and thence along the opposite nerve to the sound eye. The iris is abundantly supplied with bloodvessels and nerves, and is very prone to become inflamed, and when inflamed, in consequence of the intimate relationship which exists between the vessels of the iris and choroid, this latter tunic is very liable to participate in the inflammation. The iris is covered with epithelium, and partakes of the character of a serous membrane, and, like these structures, is apt to pour out a plastic exudation, when inflamed, and contract adhesions, either to the cornea in front (*synechia anterior*), or to the capsule of the lens behind (*synechia posterior*). In iritis the lens may become involved, and the condition known as *secondary cataract* may be set up. Tumors occasionally commence in the iris; of these, cysts, which are usually congenital, and sarcomatous tumors, are the most common. Gummata are not infrequently found in this situation. In some forms of injury of the eyeball, as from the impact of a spent shot, the rebound of a twig, or a blow with a whip, the iris may be detached from the Ciliaris muscle.

The retina, with the exception of its pigment layer and its vessels, is perfectly transparent when examined by the ophthalmoscope, so that its diseased conditions are recognized by its loss of transparency. In retinitis, for instance, there is more or less dense and extensive opacity of its structure, and not infrequently extravasations of blood into its substance. Hemorrhages may also take place into the retina, from rupture of a bloodvessel without inflammation. The retina may become displaced from effusion of serum between it and the choroid, or by blows on the eyeball, or may occur without apparent cause in progressive myopia, and in this case the ophthalmoscope shows an opaque, tremulous cloud. Glioma, a form of sarcoma, is occasionally met with in connection with the retina.

The lens has no bloodvessels, nerves, or connective tissue in its structure, and therefore is not subject to those morbid changes to which tissues containing these structures are liable. It does, however, present certain morbid or abnormal conditions of various kinds. Thus, variations in shape, and displacements, are among its congenital defects. Opacities may occur from injury, senile changes, or malnutrition. These opacities give rise to *cataract*, of which the senile variety, is the most common. They vary as to the part of the lens in which the opacity commences and are classified accordingly, as nuclear, cortical, lamellar, anterior, and posterior polar. Senile changes may take place in the lens, impairing its elasticity and rendering it harder than in youth, so that it loses its power of altering its curvature to suit the requirements of near vision. This condition is known as *presbyopia*. And, finally, the lens may be dislocated or displaced by blows upon the eyeball; and its relations to surrounding structures altered by adhesions or the pressure of new growths.

There are two particular regions of the eye which require special notice: one of these is known as the "filtration angle," and the other as the "dangerous area." The *filtration angle* is the circumcorneal zone immediately in front of the iris. Here are situated the spaces of the angle of the iris, which communicate with the sinus venosus sclerae through which the chief transudation of fluid from the eye is believed to take place. If any obstruction to this transudation occur, increased intra-ocular tension is set up, and the disease known as *glaucoma* results. The *dangerous area of the eye* is the region in the neighborhood of the ciliary body, and wounds or injuries in this situation are peculiarly dangerous; for inflammation of the ciliary body is apt to spread to many of the other structures of the eye, especially to the iris and choroid, which are intimately connected with it by nervous and vascular supplies.

**The Accessory Organs of the Eye (*Organa Oculi Accessoria*).**

The accessory organs of the eye include the **ocular muscles**, the **fasciæ**, the **eyebrows**, the **eyelids**, the **conjunctiva**, and the **lacrimal apparatus**.

**The Ocular Muscles (*musculi oculi*).**—The ocular muscles are the:

Levator palpebrae superioris.	Rectus medialis.
Rectus superior.	Rectus lateralis.
Rectus inferior.	Obliquus superior.
	Obliquus inferior.

**Dissection.**—To open the cavity of the orbit, remove the skull-cap and brain; then saw through the frontal bone at the inner extremity of the supraorbital ridge, and externally at its junction with the zygomatic bone. Break in pieces the thin roof of the orbit by a few slight blows of the hammer, and take it away; drive forward the superciliary portion of the frontal bone by a smart stroke, but do not remove it, as that would destroy the pulley of the Obliquus superior. When the fragments are cleared away, the periosteum of the orbit will be exposed; this being removed, together with the fat which fills the cavity of the orbit, the several muscles of this region can be examined. The dissection will be facilitated by distending the globe of the eye. In order to effect this, puncture the optic nerve near the eyeball with a curved needle, and push the needle onward into the globe; insert the point of a blowpipe through this aperture, and force a little air into the cavity of the eyeball; then apply a ligature around the nerve so as to prevent the air escaping. The globe being now drawn forward, the muscles will be put upon the stretch.




FIG. 856.—Sagittal section of right orbital cavity.

The **Levator palpebrae superioris** (Fig. 856) is thin, flat, and triangular in shape. It *arises* from the under surface of the small wing of the sphenoid, above and in front of the optic foramen, from which it is separated by the origin of the Rectus superior. At its origin, it is narrow and tendinous, but soon becomes broad and fleshy, and ends anteriorly in a wide aponeurosis which splits into three lamellæ. The superficial lamella blends with the upper part of the orbital septum, and is prolonged forward above the superior tarsus to the palpebral part of the Orbicularis oculi, and to the deep surface of the skin of the upper eyelid. The middle lamella, largely made up of non-striped muscular fibres, is inserted into the upper margin of the superior tarsus, while the deepest lamella blends with an expansion from the sheath of the Rectus superior and with it is attached to the superior fornix of the conjunctiva.

Whitnall<sup>1</sup> has pointed out that the upper part of the sheath of the Levator palpebrae becomes thickened in front and forms, above the anterior part of the muscle, a transverse ligamentous band which is attached to the sides of the orbital cavity. On the medial side it is mainly fixed to the pulley of the Obliquus superior, but some fibres are attached to the bone behind the pulley and a slip passes forward and bridges over the supraorbital notch; on the lateral side it is fixed to the capsule of the lacrimal gland and to the frontal bone. In front of the transverse ligamentous band the sheath is continued over the aponeurosis of the Levator palpebrae, as a thin connective-tissue layer which is fixed to the upper orbital margin immediately behind the attachment of the orbital septum. When the Levator palpebrae contracts, the lateral and medial parts of the ligamentous band are stretched and check the action of the muscle; the retraction of the upper eyelid is checked also by the orbital septum coming into contact with the transverse part of the ligamentous band.




FIG. 857.—Muscles of the right orbit.

The **four Recti** (Fig. 857) arise from a fibrous ring (*annulus tendineus communis*) which surrounds the upper, medial, and lower margins of the optic foramen and encircles the optic nerve (Fig. 858). The ring is completed by a tendinous bridge prolonged over the lower and medial part of the superior orbital fissure and attached to a tubercle on the margin of the great wing of the sphenoid, bounding the fissure. Two specialized parts of this fibrous ring may be made out: a lower, the **ligament or tendon of Zinn**, which gives origin to the Rectus inferior, part of the Rectus internus, and the lower head of origin of the Rectus lateralis; and an upper, which gives origin to the Rectus superior, the rest of the Rectus medialis, and the upper head of the Rectus lateralis. This upper band is sometimes termed the **superior tendon of Lockwood**. Each muscle passes forward in the position implied by its name, to be inserted by a tendinous expansion into the sclera, about 6 mm. from the margin of the cornea. Between the two heads of the Rectus lateralis is a narrow interval, through which pass the two divisions of the oculomotor nerve, the nasociliary nerve, the abducent nerve, and the ophthalmic vein. Although these muscles present a common origin and are inserted in a similar manner into the sclera, there are certain differences to be observed in them as regards their length and breadth. The Rectus medialis is the broadest, the Rectus lateralis the longest, and the Rectus superior the thinnest and narrowest.

The **Obliquus oculi superior** (*superior oblique*) is a fusiform muscle, placed at the upper and medial side of the orbit. It arises immediately above the margin of the optic foramen, above and medial to the origin of the Rectus superior, and, passing forward, ends in a rounded tendon, which plays in a fibrocartilaginous ring or pulley attached to the trochlear fovea of the frontal bone. The contiguous surfaces of the tendon and ring are lined by a delicate mucous sheath, and enclosed in a thin

<sup>1</sup> Journal of Anatomy and Physiology, vol. xlv.

fibrous investment. The tendon is reflected backward, lateralward, and downward beneath the Rectus superior to the lateral part of the bulb of the eye, and is inserted into the sclera, behind the equator of the eyeball, the insertion of the muscle lying between the Rectus superior and Rectus lateralis.

The **Obliquus oculi inferior** (*inferior oblique*) is a thin, narrow muscle, placed near the anterior margin of the floor of the orbit. It arises from the orbital surface of the maxilla, lateral to the lacrimal groove. Passing lateralward, backward, and upward, at first between the Rectus inferior and the floor of the orbit, and then between the bulb of the eye and the Rectus lateralis, it is inserted into the lateral part of the sclera between the Rectus superior and Rectus lateralis, near to, but somewhat behind the insertion of the Obliquus superior.




FIG. 858.—Dissection showing origins of right ocular muscles, and nerves entering by the superior orbital fissure.

**Nerves.**—The Levator palpebrae superioris, Obliquus inferior, and the Recti superior, inferior, and medialis are supplied by the oculomotor nerve; the Obliquus superior, by the trochlear nerve; the Rectus lateralis, by the abducent nerve.

**Actions.**—The Levator palpebrae raises the upper eyelid, and is the direct antagonist of the Orbicularis oculi. The four Recti are attached to the bulb of the eye in such a manner that, acting singly, they will turn its corneal surface either upward, downward, medialward, or lateralward, as expressed by their names. The movement produced by the Rectus superior or Rectus inferior is not quite a simple one, for inasmuch as each passes obliquely lateralward and forward to the bulb of the eye, the elevation or depression of the cornea is accompanied by a certain deviation medialward, with a slight amount of rotation. These latter movements are corrected by the Obliqui, the Obliquus inferior correcting the medial deviation caused by the Rectus superior and the Obliquus superior that caused by the Rectus inferior. The contraction of the Rectus lateralis or Rectus medialis, on the other hand, produces a purely horizontal movement. If any two neighboring Recti of one eye act together they carry the globe of the eye in the diagonal of these directions, viz., upward and medialward, upward and lateralward, downward and medialward, or downward and lateralward. Sometimes the corresponding Recti of the two eyes act in unison, and at other times the opposite Recti act together. Thus, in turning the eyes to the right, the Rectus lateralis of the right eye will act in unison with the Rectus medialis of the left eye; but if both eyes are directed to an object in the middle line at a short distance, the two Recti mediales will act in unison. The movement of circumduction, as in looking around a room, is performed by the successive actions of the four Recti. The Obliqui rotate the eyeball on its

antero-posterior axis, the superior directing the cornea downward and lateralward, and the inferior directing it upward and lateralward; these movements are required for the correct viewing of an object when the head is moved laterally, as from shoulder to shoulder, in order that the picture may fall in all respects on the same part of the retina of either eye.

A layer of non-striped muscle, the **Orbitalis muscle** of H. Müller, may be seen bridging across the inferior orbital fissure.




FIG. 859.—The right eye in sagittal section, showing the fascia bulbi (semidiagrammatic). (Testut.)

The **fascia bulb** (*capsule of Ténon*) (Fig. 859) is a thin membrane which envelops the bulb of the eye from the ciliary region, separating it from the orbital fat and forming a socket in which it plays. Its inner surface is smooth, and is separated from the outer surface of the sclera by the **periscleral lymph space**. This lymph space is continuous with the subdural and subarachnoid cavities, and is traversed by delicate bands of connective tissue which extend between the fascia and the sclera. The fascia is perforated behind by the ciliary vessels and nerves, and fuses with the sheath of the optic nerve and with the sclera around the entrance of the optic nerve. In front it blends with the ocular conjunctiva, and with it is attached to the ciliary region of the eyeball. It is perforated by the tendons of the ocular muscles, and is reflected backward on each as a tubular sheath. The sheath of the Obliquus superior is carried as far as the fibrous pulley of that muscle; that on the Obliquus inferior reaches as far as the floor of the orbit, to which it gives off a slip. The sheaths on the Recti are gradually lost in the perimysium, but they give off important expansions. The expansion from the Rectus superior blends with the tendon of the Levator palpebrae; that of the Rectus inferior is attached to the inferior tarsus. The expansions from the sheaths of the Recti lateralis and medialis are strong, especially that from the latter muscle, and are attached to the lacrimal and zygomatic bones respectively. As they prob-



ably check the actions of these two Recti they have been named the **medial** and **lateral check ligaments**. Lockwood has described a thickening of the lower part of the *facia bulbi*, which he has named the **suspensory ligament of the eye**. It is slung like a hammock below the eyeball, being expanded in the centre, and narrow at its extremities which are attached to the zygomatic and lacrimal bones respectively.<sup>1</sup>

The **orbital fascia** forms the periosteum of the orbit. It is loosely connected to the bones and can be readily separated from them. Behind, it is united with the *dura mater* by processes which pass through the optic foramen and superior orbital fissure, and with the sheath of the optic nerve. In front, it is connected with the periosteum at the margin of the orbit, and sends off a process which assists in forming the orbital septum. From it two processes are given off; one to enclose the lacrimal gland, the other to hold the pulley of the *Obliquus superior* in position.

**Applied Anatomy.**—The positions and exact areas of insertion of the tendons of the *Recti medialis* and *lateralis* into the bulb of the eye should be carefully examined from the front, as the surgeon is often required to divide one or other of the muscles for the cure of strabismus. In convergent strabismus, which is the more common form of the disease, the eye is turned medialward, requiring the division of the *Rectus medialis*. In the divergent form, which is more rare, the eye is turned lateralward, the *Rectus lateralis* being especially implicated. The deformity produced in either case may be remedied by division of one or the other muscle. The operation is thus performed: the lids are to be well separated; the eyeball is rotated lateralward or medialward, and the conjunctiva raised by a pair of forceps, and incised immediately beneath the lower border of the tendon of the muscle to be divided, a little behind its insertion into the sclera; the submucous areolar tissue is then divided, and into the small aperture thus made, a blunt hook is passed upward between the muscle and the bulb, and the tendon of the muscle divided by a pair of blunt-pointed scissors passed between the hook and the bulb.

A more recent operation is that of *advancement* in which either the *Rectus medialis* or *Rectus lateralis* (depending on the form of strabismus) is shortened. The muscle is exposed in the same manner; a portion is then cut out of it and the cut ends are sew together.

The **eyebrows** (*supercilia*) are two arched eminences of integument, which surmount the upper circumference of the orbits, and support numerous short, thick hairs, directed obliquely on the surface. The eyebrows consist of thickened integument, connected beneath with the *Orbicularis oculi*, *Corrugator*, and *Frontalis* muscles.

The **eyelids** (*palpebrae*) are two thin, movable folds, placed in front of the eye, protecting it from injury by their closure. The upper eyelid is the larger, and the more movable of the two, and is furnished with an elevator muscle, the *Levator palpebrae superioris*. When the eyelids are open, an elliptical space, the **palpebral fissure** (*rima palpebrarum*), is left between their margins, the angles of which correspond to the junctions of the upper and lower eyelids, and are called the **palpebral commissures** or **canthi**.

The **lateral palpebral commissure** (*commissura palpebrarum lateralis*; *external canthus*) is more acute than the medial, and the eyelids here lie in close contact with the bulb of the eye: but the **medial palpebral commissure** (*commissura palpebrarum medialis*; *internal canthus*) is prolonged for a short distance toward the nose, and the two eyelids are separated by a triangular space, the **lacus lacrimalis** (Fig. 860). At the basal angles of the *lacus lacrimalis*, on the margin of each eyelid, is a small conical elevation, the **lacrimal papilla**, the apex of which is pierced by a small orifice, the **punctum lacrimale**, the commencement of the lacrimal duct.

The **eyelashes** (*cilia*) are attached to the free edges of the eyelids; they are short, thick, curved hairs, arranged in a double or triple row: those of the upper eyelid, more numerous and longer than those of the lower, curve upward; those of the lower

<sup>1</sup> C. B. Lockwood, *Journal of Anatomy and Physiology*, vol. xx.

eyelid curve downward, so that they do not interlace in closing the lids. Near the attachment of the eyelashes are the openings of a number of glands, the **ciliary glands**, arranged in several rows close to the free margin of the lid; they are regarded as enlarged and modified sudoriferous glands.

**Structure of the Eyelids.**—The eyelids are composed of the following structures taken in their order from without inward: integument, areolar tissue, fibres of the *Orbicularis oculi*, tarsus, orbital septum, tarsal glands and conjunctiva. The upper eyelid has, in addition, the aponeurosis of the *Levator palpebrae superioris* (Fig. 861).




FIG. 860.—Front of left eye with eyelids separated to show medial canthus.

The **integument** is extremely thin, and continuous at the margins of the eyelids with the conjunctiva.

The **subcutaneous areolar tissue** is very lax and delicate, and seldom contains any fat.

The **palpebral fibres of the *Orbicularis oculi*** are thin, pale in color, and possess an involuntary action.

The **tarsi (tarsal plates)** (Fig. 862) are two thin elongated plates of dense connective tissue, about 2.5 cm. in length; one is placed in each eyelid, and contributes to its form and support. The **superior tarsus (tarsus superior; superior tarsal plate)**, the larger, is of a semilunar form, about 10 mm. in breadth at the centre, and gradually narrowing toward its extremities. To the anterior surface of this plate the aponeurosis of the *Levator palpebrae superioris* is attached. The **inferior tarsus (tarsus inferior; inferior tarsal plate)**, the smaller, is thin, elliptical in form, and has a vertical diameter of about 5 mm. The free or ciliary margins of these plates are thick and straight. The attached or orbital margins are connected to the circumference of the orbit by the orbital septum. The lateral angles are attached to the zygomatic bone by the lateral palpebral raphé. The medial angles of the two plates end at the lacus lacrimalis, and are attached to the frontal process of the maxilla by the medial palpebral ligament (page 468).

The **orbital septum (septum orbitale; palpebral ligament)** is a membranous sheet, attached to the edge of the orbit, where it is continuous with the periosteum. In the upper eyelid it blends by its peripheral circumference with the tendon of the *Levator palpebrae superioris* and the superior tarsus, in the lower eyelid with the inferior tarsus. Medially it is thin, and, becoming separated from the medial palpebral ligament, is fixed to the lacrimal bone immediately behind the lacrimal sac. The septum is perforated by the vessels and nerves which pass from the orbital cavity to the face and scalp.




FIG. 861.—Sagittal section through the upper eyelid. (After Waldeyer.) a. Skin. b. *Orbicularis oculi*. b'. Marginal fasciculus of *Orbicularis* (ciliary bundle). c. *Levator palpebrae*. d. Conjunctiva. e. Tarsus. f. Tarsal gland. g. Sebaceous gland. h. Eyelashes. i. Small hairs of skin. j. Sweat glands. k. Posterior tarsal glands.

**The Tarsal Glands** (*glandulae tarsales* [Meibomi]; *Meibomian glands*) (Fig. 863).—The tarsal glands are situated upon the inner surfaces of the eyelids, between the tarsi and conjunctiva, and may be distinctly seen through the latter on everting the eyelids, presenting an appearance like parallel strings of pearls. There are about thirty in the upper eyelid, and somewhat fewer in the lower. They are imbedded in grooves in the inner surfaces of the tarsi, and correspond in length with the breadth of these plates; they are, consequently, longer in the upper than in the lower eyelid. Their ducts open on the free margins of the lids by minute foramina.




FIG. 862.—The tarsi and their ligaments. Right eye; front view. (Testut.)

**Structure.**—The tarsal glands are modified sebaceous glands, each consisting of a single straight tube or follicle, with numerous small lateral diverticula. The tubes are supported by a basement membrane, and are lined at their mouths by stratified epithelium; the deeper parts of the tubes and the lateral offshoots are lined by a layer of polyhedral cells.




FIG. 863.—The tarsal glands, etc., seen from the inner surface of the eyelids.

The **conjunctiva** is the mucous membrane of the eye. It lines the inner surfaces of the eyelids or palpebræ, and is reflected over the forepart of the sclera and cornea.

The **Palpebral Portion** (*tunica conjunctiva palpebrarum*) is thick, opaque, highly vascular, and covered with numerous papillæ, its deeper part presenting a considerable amount of lymphoid tissue. At the margins of the lids it becomes

continuous with the lining membrane of the ducts of the tarsal glands, and, through the lacrimal ducts, with the lining membrane of the lacrimal sac and nasolacrimal duct. At the lateral angle of the upper eyelid the ducts of the lacrimal gland open on its free surface; and at the medial angle it forms a semilunar fold, the **plica semilunaris**. The line of reflection of the conjunctiva from the upper eyelid on to the bulb of the eye is named the **superior fornix**, and that from the lower lid the **inferior fornix**.

The **Bulbar Portion** (*tunica conjunctiva bulbi*).—Upon the *sclera* the conjunctiva is loosely connected to the bulb of the eye; it is thin, transparent, destitute of papillæ, and only slightly vascular. Upon the *cornea*, the conjunctiva consists only of epithelium, constituting the epithelium of the cornea, already described (see page 1019). *Lymphatics* arise in the conjunctiva in a delicate zone around the cornea, and run to the ocular conjunctiva.

In and near the fornices, but more plentiful in the upper than in the lower eyelid, a number of convoluted tubular glands open on the surface of the conjunctiva. Other glands, analogous to lymphoid follicles, and called by Henle **trachoma glands**, are found in the conjunctiva, and, according to Strohmeyer, are chiefly situated near the medial palpebral commissure. They were first described by Brush, in his description of Peyer's patches of the small intestine, as "identical structures existing in the under eyelid of the ox."

The **caruncula lacrimalis** is a small, reddish, conical-shaped body, situated at the medial palpebral commissure, and filling up the **lacus lacrimalis**. It consists of a small island of skin containing sebaceous and sudoriferous glands, and is the source of the whitish secretion which constantly collects in this region. A few slender hairs are attached to its surface. Lateral to the caruncula is a slight semilunar fold of conjunctiva, the concavity of which is directed toward the cornea; it is called the **plica semilunaris**. Müller found smooth muscular fibres in this fold; in some of the domesticated animals it contains a thin plate of cartilage.

The nerves in the conjunctiva are numerous and form rich plexuses. According to Krause they terminate in a peculiar form of tactile corpuscle, which he terms "terminal bulb."

The **Lacrimal Apparatus** (*apparatus lacrimalis*) (Fig. 864) consists of (a) the **lacrimal gland**, which secretes the tears, and its excretory ducts, which convey the fluid to the surface of the eye; (b) the **lacrimal ducts**, the **lacrimal sac**, and the **nasolacrimal duct**, by which the fluid is conveyed into the cavity of the nose.

The **Lacrimal Gland** (*glandula lacrimalis*).—The lacrimal gland is lodged in the lacrimal fossa, on the medial side of the zygomatic process of the frontal bone. It is of an oval form, about the size and shape of an almond, and consists of two portions, described as the superior and inferior lacrimal glands. The **superior lacrimal gland** is connected to the periosteum of the orbit by a few fibrous bands, and rests upon the tendons of the Recti superior and lateralis, which separate it from the bulb of the eye. The **inferior lacrimal gland** is separated from the superior by a fibrous septum, and projects into the back part of the upper eyelid, where its deep surface is related to the conjunctiva. The ducts of the glands, from six to twelve in number, run obliquely beneath the conjunctiva for a short distance, and open along the upper and lateral half of the superior conjunctival fornix.

**Structures of the Lacrimal Gland** (Fig. 865).—In structure and general appearance the lacrimal resembles the serous salivary glands (p. 1137). In the recent state the cells are so crowded with granules that their limits can hardly be defined. They contain oval nuclei, and the cell protoplasm is finely fibrillated.

The **Lacrimal Ducts** (*ductus lacrimalis; lacrimal canals*).—The lacrimal ducts, one in each eyelid, commence at minute orifices, termed **puncta lacrimalia**, on the summits of the **papillæ lacrimales**, seen on the margins of the lids at the lateral extremity of the lacus lacrimalis. The **superior duct**, the smaller and shorter of the

two, at first ascends, and then bends at an acute angle, and passes medialward and downward to the lacrimal sac. The **inferior duct** at first descends, and then

runs almost horizontally to the lacrimal sac. At the angles they are dilated into **ampullæ**; their walls are dense in structure and their mucous lining is covered by stratified squamous epithelium, placed on a basement membrane. Outside the latter is a layer




FIG. 864.—The lacrimal apparatus. Right side.




FIG. 865.—Alveoli of lacrimal gland.

of striped muscle, continuous with the lacrimal part of the *Orbicularis oculi*; at the base of each lacrimal papilla the muscular fibres are circularly arranged and form a kind of sphincter.

**The Lacrimal Sac** (*saccus lacrimalis*).—The lacrimal sac is the upper dilated end of the nasolacrimal duct, and is lodged in a deep groove formed by the lacrimal bone and frontal process of the maxilla. It is oval in form and measures from 12 to 15 mm. in length; its upper end is closed and rounded; its lower is continued into the nasolacrimal duct. Its superficial surface is covered by a fibrous expansion derived from the medial palpebral ligament, and its deep surface is crossed by the lacrimal part of the *Orbicularis oculi* (page 467), which is attached to the crest on the lacrimal bone.

**Structure.**—The lacrimal sac consists of a fibrous elastic coat, lined internally by mucous membrane: the latter is continuous, through the lacrimal ducts, with the conjunctiva, and through the nasolacrimal duct with the mucous membrane of the nasal cavity.

**The Nasolacrimal Duct** (*ductus nasolacrimalis*; *nasal duct*).—The nasolacrimal duct is a membranous canal, about 18 mm. in length, which extends from the lower part of the lacrimal sac to the inferior meatus of the nose, where it ends by a somewhat expanded orifice, provided with an imperfect valve, the **plica lacrimalis** (*Hasneri*), formed by a fold of the mucous membrane. It is contained in an osseous canal, formed by the maxilla, the lacrimal bone, and the inferior nasal concha; it is narrower in the middle than at either end, and is directed downward, backward, and a little lateralward. The mucous lining of the lacrimal sac and nasolacrimal duct is covered with columnar epithelium, which in places is ciliated.

**Applied Anatomy.**—The eyelids are composed of various tissues, and consequently are liable to a variety of diseases. The skin covering them is thin and delicate, and is supported on a quantity of loose areolar subcutaneous tissue, devoid of fat. In consequence of this it is very freely movable, and is liable to be drawn down by the contraction of neighboring cicatrices, and thus produce an eversion of the lid, known as *ectropion*. Inversion of the lids (*entropion*) from spasm of the *Orbicularis oculi* or from chronic inflammation of the palpebral conjunctiva may also occur. The eyelids are richly supplied with blood, and are often the seat of vascular growths, such as *navi*. Rodent ulcer frequently commences about the medial palpebral commissure. The loose cellular tissue beneath the skin is liable to become extensively infiltrated either with blood or inflammatory products, producing very great swelling. Even from very slight injuries to this tissue, the extravasation of blood may be so great as to produce considerable swelling of the eyelids and complete closure of the eye, and the same is the case when



inflammatory products are poured out. The follicles of the eyelashes, or the sebaceous glands associated with these follicles, may be the seat of inflammation, constituting the ordinary *stye*. The tarsal glands are affected in the so-called *tarsal tumor*, which, according to some, is caused by the retained secretion of these glands; by others it is believed to be a neoplasm connected with the gland. The ciliary follicles are liable to become inflamed, constituting the disease known as *blepharitis ciliaris*. Irregular or disorderly growth of the eyelashes not infrequently occurs, some of them being turned toward the eyeball and producing inflammation and ulceration of the cornea, and possibly eventually complete destruction of the eye. The *Orbicularis oculi* may be the seat of spasm, either in the form of slight quivering of the lids; or repeated twitchings, most commonly due to errors of refraction in children; or more continuous spasms, due to some irritation of the trigeminal or facial nerve. The *Orbicularis oculi* may be paralyzed with the other facial muscles. Under these circumstances the patient is unable to close the lids, and, if he attempts to do so, rolls the eyeball upward under the upper eyelid. The tears overflow from displacement of the lower eyelid, and the conjunctiva and cornea, being constantly exposed and the patient being unable to wink, become irritated from dust and foreign bodies. *Ptosis*, or dropping of the upper eyelid, may be congenital, or may be due to paralysis of the *Levator palpebrae superioris*, in which case there will probably be other symptoms of implication of the oculomotor nerve. The eyelids may be the seat of bruises, wounds, or burns. Following *burns*, adhesion of the margins of the lids to each other, or adhesion of the lids to the bulb, may take place. They are sometimes the seat of emphysema, after fracture of some of the thin bones forming the medial wall of the orbit. If shortly after such an injury the patient blows his nose, air is forced from the nostril through the lacerated structures into the connective tissue of the eyelids, which suddenly swell up and present the peculiar crackling characteristic of this affection.

*Foreign bodies* frequently get into the conjunctival sac and cause great pain, especially if they come in contact with the corneal surface, during the movements of the eyelids and the eye on each other. The conjunctiva is often involved in severe injuries of the eyeball, but is seldom ruptured alone; the most common form of injury to the conjunctiva alone is from a burn, either from fire, strong acids, or lime. In these cases union is liable to take place between the eyelid and the eyeball. The conjunctiva is often the seat of inflammation arising from many different causes, and the arrangement of the conjunctival vessels should be remembered as affording a means of diagnosis between this condition and injection of the sclera, which is present in inflammation of the deeper structures of the bulb of the eye. The inflamed conjunctiva is bright red; the vessels are large and tortuous, and greatest at the circumference, shading off toward the corneal margin; they anastomose freely and form a dense net-work, and they can be emptied or displaced by gentle pressure. Inflammation of the underlying sclera, ciliary body, or iris is a far more serious condition; the injection is in the deeper vessels of the eye, and as seen through the sclera presents a diffuse and dull purplish or violet zone of circumcorneal discoloration.

The *lacrimal gland* is occasionally, though rarely, the seat of inflammation, either acute or chronic; it is also sometimes the seat of tumors, benign or malignant, and for these may require removal. This may be done by an incision through the skin, just below the eyebrow; and the gland, being invested with a special capsule, may be isolated and removed, without opening the general cavity of the orbit. The lacrimal ducts may be obstructed, either as a congenital defect or by some foreign body, as an eyelash or a dacryolith, causing the tears to run over the cheek. The lacrimal ducts may also become occluded as a result of burns or injury; overflow of the tears may in addition result from deviation of the puncta, or from chronic inflammation of the lacrimal sac. This latter condition is set up by some obstruction to the nasolacrimal duct, frequently occurring in tuberculous subjects. In consequence of this the tears and mucus accumulate in the lacrimal sac and distend it. Suppuration in the lacrimal sac is sometimes met with; this may be the sequel of a chronic inflammation; or may occur after some of the eruptive fevers, in cases where the lacrimal passages were previously quite healthy. It may lead to lacrimal fistula from an abscess forming in the sac, which bursts or is opened on the surface; the condition is often seen in badly nourished, tuberculous children.

## THE ORGAN OF HEARING (ORGANON AUDITUS; THE EAR).

The ear, or organ of hearing, is divisible into three parts: the external ear, the middle ear or tympanic cavity, and the internal ear or labyrinth.

### The External Ear.

The external ear consists of the expanded portion named the *auricula* or *pinna*, and the external acoustic meatus. The former projects from the side of the head

and serves to collect the vibrations of the air by which sound is produced; the latter leads inward from the bottom of the auricula and conducts the vibrations to the tympanic cavity.

The **Auricula** or **Pinna** (Fig. 866) is of an ovoid form, with its larger end directed upward. Its lateral surface is irregularly concave, directed slightly forward, and presents numerous eminences and depressions to which names have been assigned.



FIG. 866.—The auricula. Lateral surface.

The prominent rim of the auricula is called the **helix**; where the helix turns downward behind, a small tubercle, the **auricular tubercle of Darwin**, is frequently seen; this tubercle is very evident about the sixth month of fetal life when the whole auricula has a close resemblance to that of some of the adult monkeys. Another curved prominence, parallel with and in front of the helix, is called the **antihelix**; this divides above into two crura, between which is a triangular depression, the **fossa triangularis**. The narrow-curved depression between the helix and the antihelix is called the **scapha**; the antihelix describes a curve around a deep, capacious cavity, the **concha**, which is partially divided into two parts by the **crus** or commencement of the helix; the upper part is termed the **cymba conchae**, the lower part the **cavum conchae**. In front of the concha, and projecting backward over the meatus, is a small pointed eminence, the **tragus**, so called from its being generally covered on its under surface with a tuft of hair, resembling a goat's beard.

Opposite the tragus, and separated from it by the **intertragic notch**, is a small tubercle, the **antitragus**. Below this is the **lobule**, composed of tough areolar and adipose tissues, and wanting the firmness and elasticity of the rest of the auricula.

The cranial surface of the auricula presents elevations which correspond to the depressions on its lateral surface and after which they are named, *e. g.*, eminentia conchae, eminentia triangularis, etc.

**Structure.**—The auricula is composed of a thin plate of yellow fibrocartilage, covered with integument, and connected to the surrounding parts by ligaments and muscles; and to the commencement of the external acoustic meatus by fibrous tissue.

The **skin** is thin, closely adherent to the cartilage, and covered with fine hairs furnished with sebaceous glands, which are most numerous in the concha and scaphoid fossa. On the tragus and antitragus the hairs are strong and numerous. The skin of the auricula is continuous with that lining the external acoustic meatus.

The **cartilage of the auricula** (*cartilago auriculæ*; *cartilage of the pinna*) (Figs. 867, 868) consists of a single piece; it gives form to this part of the ear, and upon its surface are found the eminences and depressions above described. It is absent from the lobule; it is deficient, also, between the tragus and beginning of the helix, the gap being filled up by dense fibrous tissue. At the front part of the auricula, where the helix bends upward, is a small projection of cartilage, called the *spina helices*, while in the lower part of the helix the cartilage is prolonged downward as a tail-like process, the *cauda helices*; this is separated from the antihelix by a fissure, the *fissura antitragohelicina*. The cranial aspect of the cartilage exhibits a transverse furrow, the *sulcus antihelices transversus*, which corresponds with the inferior crus of the antihelix and separates the eminentia conchae from the eminentia triangularis. The eminentia conchae is crossed by a vertical ridge (*ponticulus*), which gives attachment to the Auricularis posterior muscle. In the cartilage of the auricula are two fissures, one behind the crus helices and another in the tragus.

The **ligaments of the auricula** (*ligamenti auricularia* [Valsalva]; *ligaments of the pinna*) consist of two sets: (1) **extrinsic**, connecting it to the side of the head; (2) **intrinsic**, connecting various parts of its cartilage together.

The **extrinsic ligaments** are two in number, anterior and posterior. The *anterior ligament* extends from the tragus and spina helices to the root of the zygomatic process of the temporal bone. The *posterior ligament* passes from the posterior surface of the concha to the outer surface of the mastoid process.

The chief **intrinsic ligaments** are: (a) a strong fibrous band, stretching from the tragus to the commencement of the helix, completing the meatus in front, and partly encircling the boundary of the concha; and (b) a band between the antihelix and the cauda helix. Other less important bands are found on the cranial surface of the pinna.




FIG. 867.—Cranial surface of cartilage of right auricle.

The **muscles of the auricle** (Fig. 868) consist of two sets: (1) the **extrinsic**, which connect it with the skull and scalp and move the auricle as a whole; and (2) the **intrinsic**, which extend from one part of the auricle to another.

The **extrinsic muscles** are the Auriculares anterior, superior, and posterior.

The *Auricularis anterior* (*Altrahens aurem*), the smallest of the three, is thin, fan-shaped, and its fibers are pale and indistinct. It arises from the lateral edge of the galea aponeurotica, and its fibres converge to be inserted into a projection on the front of the helix.

The *Auricularis superior* (*Attolens aurem*), the largest of the three, is thin and fan-shaped. Its fibres arise from the galea aponeurotica, and converge to be inserted by a thin, flattened tendon into the upper part of the cranial surface of the auricle.

The *Auricularis posterior* (*Retrahens aurem*) consists of two or three fleshy fasciculi, which arise from the mastoid portion of the temporal bone by short aponeurotic fibres. They are inserted into the lower part of the cranial surface of the concha.

**Actions.**—In man, these muscles possess very little action: the Auricularis anterior draws the auricle forward and upward; the Auricularis superior slightly raises it; and the Auricularis posterior draws it backward.

The **intrinsic muscles** are the:

Helicis major.	Antitragicus.
Helicis minor.	Transversus auriculæ.
Tragicus.	Obliquus auriculæ.




FIG. 868.—The muscles of the auricle.

The *Helicis major* is a narrow vertical band situated upon the anterior margin of the helix. It arises below, from the spina helix, and is inserted into the anterior border of the helix, just where it is about to curve backward.

The *Helicis minor* is an oblique fasciculus, covering the crus helix.

The *Tragicus* is a short, flattened vertical band on the lateral surface of the tragus.

The *Antitragicus* arises from the outer part of the antitragus, and is inserted into the caudal helix and antihelix.

The *Transversus auriculæ* is placed on the cranial surface of the pinna. It consists of scattered fibres, partly tendinous and partly muscular, extending from the eminentia conchæ to the prominence corresponding with the scapha.

The *Obliquus auriculæ*, also on the cranial surface, consists of a few fibres extending from the upper and back part of the concha to the convexity immediately above it.

**Nerves.**—The Auriculares anterior and superior and the intrinsic muscles on the lateral surface are supplied by the temporal branch of the facial nerve, the Auricularis posterior and the intrinsic muscles on the cranial surface by the posterior auricular branch of the same nerve.

The **arteries of the auricle** are the posterior auricular from the external carotid, the anterior auricular from the superficial temporal, and a branch from the occipital artery.

The **veins** accompany the corresponding arteries.

The **sensory nerves** are: the great auricular, from the cervical plexus; the auricular branch of the vagus; the auriculotemporal branch of the mandibular nerve; and the lesser occipital from the cervical plexus.




FIG. 869.—External and middle ear, opened from the front. Right side.

The **External Acoustic Meatus** (*meatus acusticus externus*; *external auditory canal* or *meatus*) extends from the bottom of the concha to the tympanic membrane (F 869, 870). It is about 4 cm. in length if measured from the tragus; from the bottom of the concha its length is about 2.5 cm. It forms an S-shaped curve, and is directed at first inward, forward, and slightly upward (*pars externa*); it then passes inward and backward (*pars media*), and lastly is carried inward, forward, and slightly downward (*pars interna*). It is an oval cylindrical canal, the greatest diameter being directed downward and backward at the external orifice, but nearly horizontal at the inner end. It presents two constrictions, one near the inner end of the cartilaginous portion, and another, the **isthmus**, in the osseous portion, about 2 cm. from the bottom of the concha. The tympanic membrane, which closes the inner end of the meatus, is obliquely directed; in consequence of this the floor and anterior wall of the meatus are longer than the roof and posterior wall.

The external acoustic meatus is formed partly by cartilage and membrane, and partly by bone, and is lined by skin.

The **cartilaginous portion** (*meatus acusticus externus cartilagineus*) is about 8 mm. in length; it is continuous with the cartilage of the auricula, and firmly attached to the circumference of the auditory process of the temporal bone. The cartilage is deficient at the upper and back part of the meatus, its place being supplied by fibrous membrane; two or three deep fissures are present in the anterior part of the cartilage.

The **osseous portion** (*meatus acusticus externus osseus*) is about 16 mm. in length, and is narrower than the cartilaginous portion. It is directed inward and a little forward, forming in its course a slight curve the convexity of which is upward and backward. Its inner end is smaller than the outer, and sloped, the anterior wall




FIG. 870.—Horizontal section through left ear; upper half of section.

projecting beyond the posterior for about 4 mm.; it is marked, except at its upper part, by a narrow groove, the **tympanic sulcus**, in which the circumference of the tympanic membrane is attached. Its outer end is dilated and rough in the greater part of its circumference, for the attachment of the cartilage of the auricula. The front and lower parts of the osseous portion are formed by a curved plate of bone, the tympanic part of the temporal, which, in the fetus, exists as a separate ring (**annulus tympanicus**,) incomplete at its upper part (page 245).

The **skin** lining the meatus is very thin; adheres closely to the cartilaginous and osseous portions of the tube, and covers the outer surface of the tympanic membrane. After maceration, the thin pouch of epidermis, when withdrawn, preserves the form of the meatus. In the thick subcutaneous tissue of the cartilaginous part of the meatus are numerous ceruminous glands, which secrete the ear-wax; their structure resembles that of the sudoriferous glands.

**Relations of the Meatus.**—In front of the osseous part is the condyle of the mandible, which however, is frequently separated from the cartilaginous part by a portion of the parotid gland. The movements of the jaw influence to some extent the lumen of this latter portion. Behind the osseous part are the mastoid air cells, separated from the meatus by a thin layer of bone.

The **arteries** supplying the meatus are branches from the posterior auricular, internal maxillary, and temporal.

The **nerves** are chiefly derived from the auriculotemporal branch of the mandibular nerve and the auricular branch of the vagus.



The *Tragicus* is a short, flattened vertical band on the lateral surface of the tragus.

The *Antitragicus aris*es from the outer part of the antitragus, and is inserted into the cauda helix and antihelix.

The *Transversus auriculæ* is placed on the cranial surface of the pinna. It consists of scattered fibres, partly tendinous and partly muscular, extending from the eminentia conchæ to the prominence corresponding with the scapha.

The *Obliquus auriculæ*, also on the cranial surface, consists of a few fibres extending from the upper and back part of the concha to the convexity immediately above it.

*Nerves*.—The Auriculares anterior and superior and the intrinsic muscles on the lateral surface are supplied by the temporal branch of the facial nerve, the Auricularis posterior and the intrinsic muscles on the cranial surface by the posterior auricular branch of the same nerve.

The **arteries of the auricula** are the posterior auricular from the external carotid, the anterior auricular from the superficial temporal, and a branch from the occipital artery.

The **veins** accompany the corresponding arteries.

The **sensory nerves** are: the great auricular, from the cervical plexus; the auricular branch of the vagus; the auriculotemporal branch of the mandibular nerve; and the lesser occipital from the cervical plexus.




FIG. 869.—External and middle ear, opened from the front. Right side.

The **External Acoustic Meatus** (*meatus acusticus externus*; *external auditory canal* or *meatus*) extends from the bottom of the concha to the tympanic membrane (Figs. 869, 870). It is about 4 cm. in length if measured from the tragus; from the bottom of the concha its length is about 2.5 cm. It forms an S-shaped curve, and is directed at first inward, forward, and slightly upward (*pars externa*); it then passes inward and backward (*pars media*), and lastly is carried inward, forward, and slightly downward (*pars interna*). It is an oval cylindrical canal, the greatest diameter being directed downward and backward at the external orifice, but nearly horizontally at the inner end. It presents two constrictions, one near the inner end of the cartilaginous portion, and another, the **isthmus**, in the osseous portion, about 2 cm. from the bottom of the concha. The tympanic membrane, which closes the inner end of the meatus, is obliquely directed; in consequence of this the floor and anterior wall of the meatus are longer than the roof and posterior wall.

The external acoustic meatus is formed partly by cartilage and membrane, and partly by bone, and is lined by skin.

The **cartilaginous portion** (*meatus acusticus externus cartilagineus*) is about 8 mm. in length; it is continuous with the cartilage of the auricula, and firmly attached to the circumference of the auditory process of the temporal bone. The cartilage is deficient at the upper and back part of the meatus, its place being supplied by fibrous membrane; two or three deep fissures are present in the anterior part of the cartilage.

The **osseous portion** (*meatus acusticus externus osseus*) is about 16 mm. in length, and is narrower than the cartilaginous portion. It is directed inward and a little forward, forming in its course a slight curve the convexity of which is upward and backward. Its inner end is smaller than the outer, and sloped, the anterior wall




FIG. 870.—Horizontal section through left ear; upper half of section.

projecting beyond the posterior for about 4 mm.; it is marked, except at its upper part, by a narrow groove, the **tympanic sulcus**, in which the circumference of the tympanic membrane is attached. Its outer end is dilated and rough in the greater part of its circumference, for the attachment of the cartilage of the auricula. The front and lower parts of the osseous portion are formed by a curved plate of bone, the tympanic part of the temporal, which, in the fetus, exists as a separate ring (**annulus tympanicus**), incomplete at its upper part (page 245).

The **skin** lining the meatus is very thin; adheres closely to the cartilaginous and osseous portions of the tube, and covers the outer surface of the tympanic membrane. After maceration, the thin pouch of epidermis, when withdrawn, preserves the form of the meatus. In the thick subcutaneous tissue of the cartilaginous part of the meatus are numerous ceruminous glands, which secrete the ear-wax; their structure resembles that of the sudoriferous glands.

**Relations of the Meatus.**—In front of the osseous part is the condyle of the mandible, which however, is frequently separated from the cartilaginous part by a portion of the parotid gland. The movements of the jaw influence to some extent the lumen of this latter portion. Behind the osseous part are the mastoid air cells, separated from the meatus by a thin layer of bone.

The **arteries** supplying the meatus are branches from the posterior auricular, internal maxillary, and temporal.

The **nerves** are chiefly derived from the auriculotemporal branch of the mandibular nerve and the auricular branch of the vagus.

**Applied Anatomy.**—Malformations, such as imperfect development of the external parts, supernumerary auricles, or absence of the meatus, are occasionally met with. The skin of the auricula is thin and richly supplied with blood, but in spite of this it is often the seat of frost-bite, due to the fact that it is much exposed to cold, and lacks the usual underlying subcutaneous fat found in most other parts of the body. A collection of blood is sometimes found between the cartilage and perichondrium (*hematoma auris*), usually the result of traumatism, but not necessarily due to this cause; it is said to occur most frequently in the ears of the insane. Keloid sometimes grows in the auricula around the puncture made for earrings, and epithelioma occasionally affects this part. Deposits of urate of soda are often met with in the auricula in gouty subjects.

The external acoustic meatus can be most satisfactorily examined by light reflected down a funnel-shaped speculum; by gently moving the latter in different directions the greater part of the canal and tympanic membrane can be brought into view. In using this instrument, it is advisable that the auricula should be drawn upward, backward, and a little outward, so as to render the meatus as straight as possible. The points to be noted are: the presence of wax or foreign bodies; the size of the meatus; and the condition of the tympanic membrane. Accumulation of wax is often a cause of deafness, and may give rise to very serious consequences, such as ulceration of the membrane; it is best removed by syringing. Foreign bodies are not infrequently introduced into the ear by children, and, when situated in the first portion of the meatus may be removed with tolerable facility by means of a minute hook or loop of fine wire, aided by reflected light; but when they have slipped beyond the narrow middle part of the meatus their removal is in no wise easy, and attempts to effect it, in inexperienced hands, may be followed by destruction of the tympanic membrane and possibly the contents of the tympanic cavity. The calibre of the external acoustic meatus may be narrowed by inflammation of its lining membrane; by periostitis; by polypi; or by exostoses.




FIG. 871.—Right tympanic membrane as seen through a speculum.

At the point of junction of the osseous and cartilaginous portions an obtuse angle, which projects into the tube at its antero-inferior wall, is formed; this produces a sort of constriction and renders it a narrow portion of the meatus—an important point to be remembered in connection with the presence of foreign bodies in the meatus. The shortness of the meatus in children should be borne in mind in introducing the aural speculum, so that it be not pushed in too far, at the risk of injuring the tympanic membrane; indeed, even in the adult the speculum should never be introduced beyond the constriction which marks the junction of the osseous and cartilaginous portions. Just in front of the membrane is a well-marked depression, situated on the floor of the meatus, and bounded by a somewhat prominent ridge; in this foreign bodies may become lodged. By aid of the speculum, combined with traction of the auricle upward and backward, the greater part of the tympanic membrane is rendered visible (Fig. 871). It is a pearly-gray membrane, slightly glistening in the adult, placed obliquely, so as to form with the floor of the meatus a very acute angle (about fifty-five degrees), while with the roof it forms an obtuse angle. At birth it is more horizontal, situated in almost the same plane as the base of the skull. About midway between the anterior and posterior margins of the membrane, extending from the centre obliquely upward, is a reddish-yellow streak; this is the handle of the malleus, which is inserted into the membrane. At the upper part of this streak, close to the roof of the meatus, a little white, rounded prominence is plainly to be seen; this is the lateral or short process of the malleus, projecting against the membrane. The tympanic membrane

does not present a plane surface; on the contrary, its centre is drawn inward, on account of its connection with the manubrium of the malleus, and thus the external surface is rendered concave.

The connections of the nerves of the meatus explain the fact of the occurrence, in cases of irritation of the meatus, of constant coughing and sneezing, from implication of the vagus, and the vomiting which may follow syringing the ears of children, and the occasional heart failure similarly induced in elderly people. No doubt also the association of earache with toothache or with cancer of the tongue is due to implication of the mandibular branch of the trigeminal nerve, which supplies also the teeth and the tongue. The upper half of the tympanic membrane is much more vascular than the lower half; for this reason, and also to avoid the chorda tympani nerve and ossicles, incisions through the membrane should be made at the lower and posterior part.

### **The Middle Ear or Tympanic Cavity (Cavum Tympani; Drum; Tympanum).**

The **middle ear or tympanic cavity** is an irregular, laterally compressed space within the temporal bone. It is filled with air, which is conveyed to it from the nasal part of the pharynx through the auditory tube. It contains a chain of movable bones, which connect its lateral to its medial wall, and serve to convey the vibrations communicated to the tympanic membrane across the cavity to the internal ear.

The tympanic cavity consists of two parts: the **tympanic cavity proper**, opposite the tympanic membrane, and the **attic or epitympanic recess**, above the level of the membrane; the latter contains the upper half of the malleus and the greater part of the incus. Including the attic, the vertical and antero-posterior diameters of the cavity are each about 15 mm. The transverse diameter measures about 6 mm. above and 4 mm. below; opposite the centre of the tympanic membrane it is only about 2 mm. The tympanic cavity is bounded laterally by the tympanic membrane; medially, by the lateral wall of the internal ear; it communicates, behind, with the tympanic antrum and through it with the mastoid air cells, and in front with the auditory tube (Fig. 869).

The **Tegmental Wall or Roof** (*paries tegmentalis*) is formed by a thin plate of bone, the **tegmen tympani**, which separates the cranial and tympanic cavities. It is situated on the anterior surface of the petrous portion of the temporal bone close to its angle of junction with the squama temporalis; it is prolonged backward so as to roof in the tympanic antrum, and forward to cover in the semicanal for the Tensor tympani muscle. Its lateral edge corresponds with the remains of the petrosquamous suture.

The **Jugular Wall or Floor** (*paries jugularis*) is narrow, and consists of a thin plate of bone (**fundus tympani**) which separates the tympanic cavity from the jugular fossa. It presents, near the labyrinthine wall, a small aperture for the passage of the tympanic branch of the glossopharyngeal nerve.

The **Membranous or Lateral Wall** (*paries membranacea; outer wall*) is formed mainly by the tympanic membrane, partly by the ring of bone into which this membrane is inserted. This ring of bone is incomplete at its upper part, forming a notch (**notch of Rivinus**), close to which are three small apertures: the **iter chordae posterius**, the **petrotympanic fissure**, and the **iter chordae anteriorius**.

The **iter chordae posterius** (*apertura tympanica canaliculi chordae*) is situated in the angle of junction between the mastoid and membranous wall of the tympanic cavity immediately behind the tympanic membrane and on a level with the upper end of the manubrium of the malleus; it leads into a minute canal, which descends in front of the canal for the facial nerve, and ends in that canal near the stylo-mastoid foramen. Through it the chorda tympani nerve enters the tympanic cavity.

The **petrotympanic fissure** (*fissura petrotympanica; Glaserian fissure*) opens just above and in front of the ring of bone into which the tympanic membrane is

inserted; in this situation it is a mere slit about 2 mm. in length. It lodges the anterior process and anterior ligament of the malleus, and gives passage to the anterior tympanic branch of the internal maxillary artery.

The *iter chordae anteriorius* (*canal of Huguier*) is placed at the medial end of the petrotympanic fissure; through it the chorda tympani nerve leaves the tympanic cavity.

The **Tympanic Membrane** (*membrana tympani*) (Figs. 871, 872) separates the tympanic cavity from the bottom of the external acoustic meatus. It is a thin




FIG. 872.—The tympanic membrane viewed from within. (Testut.) The malleus has been resected immediately beyond its lateral process, in order to show the tympanomalleolar folds and the membrana flaccida. 1. Tympanic membrane. 2. Umbo. 3. Handle of the malleus. 4. Lateral process. 5. Anterior tympanomalleolar fold. 6. Posterior tympanomalleolar fold. 7. Pars flaccida. 8. Anterior pouch of Tröltsch. 9. Posterior pouch of Tröltsch. 10. Fibrocartilaginous ring. 11. Petrotympanic fissure. 12. Auditory tube. 13. Iter chordae posteriorius. 14. Iter chordae anteriorius. 15. Fossa incudis for short crus of the incus. 16. Prominentia styloidea.

semitransparent membrane, nearly oval in form, somewhat broader above than below, and directed very obliquely downward and inward so as to form an angle of about fifty-five degrees with the floor of the meatus. Its longest diameter is downward and forward, and measures from 9 to 10 mm.; its shortest diameter measures from 8 to 9 mm. The greater part of its circumference is thickened and forms a **fibrocartilaginous ring** which is fixed in the **tympanic sulcus** at the inner end of the meatus. This sulcus is deficient superiorly at the notch of Rivinus and from the ends of this notch two bands, the **anterior** and **posterior malleolar fold**, are prolonged to the lateral process of the malleus. The small, somewhat triangular part of the membrane situated above the folds is lax and thin, and is named the **pars flaccida**; in it a small orifice is sometimes seen. The manubrium of the malleus is firmly attached to the medial surface of the membrane as far as its centre, where it draws toward the tympanic cavity; the lateral surface of the membrane is thin and concave, and the most depressed part of this concavity is named the **umbo**.

**Structure.**—The tympanic membrane is composed of three strata: a **lateral** (*cutaneous*), an **intermediate** (*fibrous*), and a **medial** (*mucous*). The **cutaneous stratum** is derived from the integument lining the meatus. The **fibrous stratum** consists of two layers: a radiate stratum, the fibres of which diverge from the manubrium of the malleus, and a circular stratum, the fibres of which are plentiful around the circumference but sparse and scattered near the center of the membrane. Branched or dendritic fibres, as pointed out by Grüber, are also present especially in the posterior half of the membrane.

**Vessels and Nerves.**—The **arteries** of the tympanic membrane are derived from the auricular branch of the internal maxillary, which ramifies beneath the cutaneous stratum; from the stylomastoid branch of the posterior auricular, and tympanic branch of the internal maxillary, which are distributed on the mucous surface. The superficial **veins** open into the external jugular; those on the deep surface drain partly into the transverse sinus and vein of the dura mater, and partly into a plexus on the auditory tube. The membrane receives its **nerve supply** from the auriculotemporal branch of the mandibular, the auricular branch of the vagus, and the tympanic branch of the glossopharyngeal.

The **Labyrinthine or Medial Wall** (*paries labyrinthica*; *inner wall*) (Fig. 873) is vertical in direction, and presents for examination the **fenestrae vestibuli**, the **cochleae**, the **promontory**, and the **prominence of the facial canal**.



The **fenestra vestibuli** (*fenestra ovalis*) is a reniform opening leading from the tympanic cavity into the vestibule of the internal ear; its long diameter is horizontal, and its convex border is upward. In the recent state it is occupied by the base of the stapes, the circumference of which is fixed by the annular ligament to the margin of the foramen.

The **fenestra cochleæ** (*fenestra rotunda*) is situated below and a little behind the fenestra vestibuli, from which it is separated by a rounded elevation, the **promontory**. It is placed at the bottom of a funnel-shaped depression and, in the macerated bone, leads into the cochlea of the internal ear; in the recent state it is closed by a membrane, the **secondary tympanic membrane**, which is concave toward the tympanic cavity, convex toward the cochlea. This membrane consists of three layers: an external, or mucous, derived from the mucous lining of the tympanic cavity; an internal, from the lining membrane of the cochlea; and an intermediate, or fibrous layer.




FIG. 873.—Coronal section of right temporal bone.

The **promontory** (*promontorium*) is a rounded hollow prominence, formed by the projection outward of the first turn of the cochlea; it is placed between the fenestrae, and is furrowed on its surface by small grooves, for the lodgement of branches of the tympanic plexus. A minute spicule of bone frequently connects the promontory to the pyramidal eminence.

The **prominence of the facial canal** (*prominentia canalis facialis*; *prominence of aqueduct of Fallopius*) indicates the position of the bony canal in which the facial nerve is contained; this canal traverses the labyrinthine wall of the tympanic cavity above the fenestra vestibuli, and behind that opening curves nearly vertically downward along the mastoid wall.

The **mastoid** or **posterior wall** (*paries mastoidea*) is wider above than below, and presents for examination the **entrance to the tympanic antrum**, the **pyramidal eminence**, and the **fossa incudis**.

The **entrance to the antrum** is a large irregular aperture, which leads backward from the epitympanic recess into a considerable air space, named the **tympanic** or **mastoid antrum** (see page 240). The antrum communicates behind and below with the **mastoid air cells**, which vary considerably in number, size, and form; the antrum and mastoid air cells are lined by mucous membrane, continuous with that lining the tympanic cavity. On the medial wall of the entrance to the antrum is a rounded eminence, situated above and behind the prominence of the facial canal; it corresponds with the position of the ampullated ends of the superior and lateral semicircular canals.

The **pyramidal eminence** (*eminencia pyramidalis; pyramid*) is situated immediately behind the fenestra vestibuli, and in front of the vertical portion of the facial canal; it is hollow, and contains the Stapedius muscle; its summit projects forward toward the fenestra vestibuli, and is pierced by a small aperture which transmits the tendon of the muscle. The cavity in the pyramidal eminence is prolonged downward and backward in front of the facial canal, and communicates with it by a minute aperture which transmits a twig from the facial nerve to the Stapedius muscle.

The **fossa incudis** is a small depression in the lower and back part of the epitympanic recess; it lodges the short crus of the incus.

The **Carotid** or **Anterior Wall** (*paries carotica*) is wider above than below; it corresponds with the carotid canal, from which it is separated by a thin plate of bone perforated by the tympanic branch of the internal carotid artery, and by the deep petrosal nerve which connects the sympathetic plexus on the internal carotid artery with the tympanic plexus on the promontory. At the upper part of the anterior wall are the orifice of the semicanal for the Tensor tympani muscle and the tympanic orifice of the auditory tube, separated from each other by a thin horizontal plate of bone, the **septum canalis musculotubarii**. These canals run from the tympanic cavity forward and downward to the retiring angle between the squama and the petrous portion of the temporal bone.

The **semicanal for the Tensor tympani** (*semicanalis m. tensoris tympani*) is the superior and the smaller of the two; it is cylindrical and lies beneath the tegmen tympani. It extends on to the labyrinthine wall of the tympanic cavity and ends immediately above the fenestra vestibuli.

The **septum canalis musculotubarii** (*processus cochleariformis*) passes backward below this semicanal, forming its lateral wall and floor; it expands above the anterior end of the fenestra vestibuli and terminates there by curving laterally so as to form a pulley over which the tendon of the muscle passes.

The **auditory tube** (*tuba auditiva; Eustachian tube*) is the channel through which the tympanic cavity communicates with the nasal part of the pharynx. Its length is about 36 mm., and its direction is downward, forward, and medialward, forming an angle of about 45 degrees with the sagittal plane and one of from 30 to 40 degrees with the horizontal plane. It is formed partly of bone, partly of cartilage and fibrous tissue (Fig. 869).

The **osseous portion** (*pars osseo tubae auditivae*) is about 12 mm. in length. It begins in the carotid wall of the tympanic cavity, below the septum canalis musculotubarii, and, gradually narrowing, ends at the angle of junction of the squama and the petrous portion of the temporal bone, its extremity presenting a jagged margin which serves for the attachment of the cartilaginous portion.

The **cartilaginous portion** (*pars cartilaginea tubae auditivae*), about 24 mm. in length, is formed of a triangular plate of elastic fibrocartilage, the apex of which is attached to the margin of the medial end of the osseous portion of the tube, while its base lies directly under the mucous membrane of the nasal part of the pharynx, where it forms an elevation, the **torus tubarius** or **cushion**, behind the pharyngeal orifice of the tube. The upper edge of the cartilage is curled upon itself, being bent later

so as to present on transverse section the appearance of a hook; a groove or furrow is thus produced, which is open below and laterally, and this part of the canal is completed by fibrous membrane. The cartilage lies in a groove between the petrous part of the temporal and the great wing of the sphenoid; this groove ends opposite the middle of the medial pterygoid plate. The cartilaginous and bony portions of the tube are not in the same plane, the former inclining downward a little more than the latter. The diameter of the tube is not uniform throughout, being greatest at the pharyngeal orifice, least at the junction of the bony and cartilaginous portions, and again increased toward the tympanic cavity; the narrowest part of the tube is termed the *isthmus*. The position and relations of the pharyngeal orifice are described with the nasal part of the pharynx. The mucous membrane of the tube is continuous in front with that of the nasal part of the pharynx, and behind with that of the tympanic cavity; it is covered with ciliated epithelium and is thin in the osseous portion, while in the cartilaginous portion it contains many mucous glands and near the pharyngeal orifice a considerable amount of adenoid tissue, which has been named by Gerlach the *tube tonsil*. The tube is opened during deglutition by the Salpingopharyngeus and Dilator tubae. The latter arises from the hook of the cartilage and from the membranous part of the tube, and blends below with the Tensor veli palatini.

### The Auditory Ossicles (*Ossicula Auditus*).

The tympanic cavity contains a chain of three movable ossicles, the **malleus**, **incus**, and **stapes**. The first is attached to the tympanic membrane, the last to the circumference of the fenestra vestibuli, the incus being placed between and connected to both by delicate articulations.

The **Malleus** (Fig. 874), so named from its fancied resemblance to a hammer, consists of a **head**, **neck**, and three processes, viz., the **manubrium**, the **anterior** and **lateral processes**.

The **head** (*capitulum mallei*) is the large upper extremity of the bone; it is oval in shape, and articulates posteriorly with the incus, being free in the rest of its extent. The facet for articulation with the incus is constricted near the middle, and consists of an upper larger and lower smaller part, which form nearly a right angle with each other. Opposite the constriction the lower margin of the facet projects in the form of a process, the **cog-tooth** or **spur of the malleus**.

The **neck** (*collum mallei*) is the narrow contracted part just beneath the head; below it, is a prominence, to which the various processes are attached.

The **manubrium mallei** (*handle*) is connected by its lateral margin with the tympanic membrane. It is directed downward, medialward, and backward; it decreases in size toward its free end, which is curved slightly forward, and flattened transversely. On its medial side, near its upper end, is a slight projection, into which the tendon of the Tensor tympani is inserted.

The **anterior process** (*processus anterior* [Folii]; *processus gracilis*) is a delicate spicule, which springs from the eminence below the neck and is directed forward




FIG. 874.—Left malleus. A. From behind. B. From within.

The *Tragicus* is a short, flattened vertical band on the lateral surface of the tragus.

The *Antitragicus* arises from the outer part of the antitragus, and is inserted into the cauda helix and antihelix.

The *Transversus auriculæ* is placed on the cranial surface of the pinna. It consists of scattered fibres, partly tendinous and partly muscular, extending from the eminentia conchæ to the prominence corresponding with the scapha.

The *Obliquus auriculæ*, also on the cranial surface, consists of a few fibres extending from the upper and back part of the concha to the convexity immediately above it.

*Nerves*.—The Auriculares anterior and superior and the intrinsic muscles on the lateral surface are supplied by the temporal branch of the facial nerve, the Auricularis posterior and the intrinsic muscles on the cranial surface by the posterior auricular branch of the same nerve.

The *arteries of the auricle* are the posterior auricular from the external carotid, the anterior auricular from the superficial temporal, and a branch from the occipital artery.

The *veins* accompany the corresponding arteries.

The *sensory nerves* are: the great auricular, from the cervical plexus; the auricular branch of the vagus; the auriculotemporal branch of the mandibular nerve; and the lesser occipital from the cervical plexus.




FIG. 869.—External and middle ear, opened from the front. Right side.

The **External Acoustic Meatus** (*meatus acusticus externus*; *external auditory canal or meatus*) extends from the bottom of the concha to the tympanic membrane (Figs. 869, 870). It is about 4 cm. in length if measured from the tragus; from the bottom of the concha its length is about 2.5 cm. It forms an S-shaped curve, and is directed at first inward, forward, and slightly upward (*pars externa*); it then passes inward and backward (*pars media*), and lastly is carried inward, forward, and slightly downward (*pars interna*). It is an oval cylindrical canal, the greatest diameter being directed downward and backward at the external orifice, but nearly horizontally at the inner end. It presents two constrictions, one near the inner end of the cartilaginous portion, and another, the **isthmus**, in the osseous portion, about 2 cm. from the bottom of the concha. The tympanic membrane, which closes the inner end of the meatus, is obliquely directed; in consequence of this the floor and anterior wall of the meatus are longer than the roof and posterior wall.

The external acoustic meatus is formed partly by cartilage and membrane, and partly by bone, and is lined by skin.

The **cartilaginous portion** (*meatus acusticus externus cartilagineus*) is about 8 mm. in length; it is continuous with the cartilage of the auricula, and firmly attached to the circumference of the auditory process of the temporal bone. The cartilage is deficient at the upper and back part of the meatus, its place being supplied by fibrous membrane; two or three deep fissures are present in the anterior part of the cartilage.

The **osseous portion** (*meatus acusticus externus osseus*) is about 16 mm. in length, and is narrower than the cartilaginous portion. It is directed inward and a little forward, forming in its course a slight curve the convexity of which is upward and backward. Its inner end is smaller than the outer, and sloped, the anterior wall




FIG. 870.—Horizontal section through left ear; upper half of section.

projecting beyond the posterior for about 4 mm.; it is marked, except at its upper part, by a narrow groove, the **tympanic sulcus**, in which the circumference of the tympanic membrane is attached. Its outer end is dilated and rough in the greater part of its circumference, for the attachment of the cartilage of the auricula. The front and lower parts of the osseous portion are formed by a curved plate of bone, the tympanic part of the temporal, which, in the fetus, exists as a separate ring (**annulus tympanicus**), incomplete at its upper part (page 245).

The **skin** lining the meatus is very thin; adheres closely to the cartilaginous and osseous portions of the tube, and covers the outer surface of the tympanic membrane. After maceration, the thin pouch of epidermis, when withdrawn, preserves the form of the meatus. In the thick subcutaneous tissue of the cartilaginous part of the meatus are numerous ceruminous glands, which secrete the ear-wax; their structure resembles that of the sudoriferous glands.

**Relations of the Meatus.**—In front of the osseous part is the condyle of the mandible, which however, is frequently separated from the cartilaginous part by a portion of the parotid gland. The movements of the jaw influence to some extent the lumen of this latter portion. Behind the osseous part are the mastoid air cells, separated from the meatus by a thin layer of bone.

The **arteries** supplying the meatus are branches from the posterior auricular, internal maxillary, and temporal.

The **nerves** are chiefly derived from the auriculotemporal branch of the mandibular nerve and the auricular branch of the vagus.



The *Tragicus* is a short, flattened vertical band on the lateral surface of the tragus.

The *Antitragicus* arises from the outer part of the antitragus, and is inserted into the cauda helix and antihelix.

The *Transversus auriculæ* is placed on the cranial surface of the pinna. It consists of scattered fibres, partly tendinous and partly muscular, extending from the eminentia conchæ to the prominence corresponding with the scapha.

The *Obliquus auriculæ*, also on the cranial surface, consists of a few fibres extending from the upper and back part of the concha to the convexity immediately above it.

*Nerves.*—The Auriculares anterior and superior and the intrinsic muscles on the lateral surface are supplied by the temporal branch of the facial nerve, the Auricularis posterior and the intrinsic muscles on the cranial surface by the posterior auricular branch of the same nerve.

The **arteries of the auricula** are the posterior auricular from the external carotid, the anterior auricular from the superficial temporal, and a branch from the occipital artery.

The **veins** accompany the corresponding arteries.

The **sensory nerves** are: the great auricular, from the cervical plexus; the auricular branch of the vagus; the auriculotemporal branch of the mandibular nerve; and the lesser occipital from the cervical plexus.




FIG. 869.—External and middle ear, opened from the front. Right side.

The **External Acoustic Meatus** (*meatus acusticus externus*; *external auditory canal or meatus*) extends from the bottom of the concha to the tympanic membrane (Figs. 869, 870). It is about 4 cm. in length if measured from the tragus; from the bottom of the concha its length is about 2.5 cm. It forms an S-shaped curve, and is directed at first inward, forward, and slightly upward (*pars externa*); it then passes inward and backward (*pars media*), and lastly is carried inward, forward, and slightly downward (*pars interna*). It is an oval cylindrical canal, the greatest diameter being directed downward and backward at the external orifice, but nearly horizontally at the inner end. It presents two constrictions, one near the inner end of the cartilaginous portion, and another, the **isthmus**, in the osseous portion, about 2 cm. from the bottom of the concha. The tympanic membrane, which closes the inner end of the meatus, is obliquely directed; in consequence of this the floor and anterior wall of the meatus are longer than the roof and posterior wall.

The external acoustic meatus is formed partly by cartilage and membrane, and partly by bone, and is lined by skin.

The **cartilaginous portion** (*meatus acusticus externus cartilagineus*) is about 8 mm. in length; it is continuous with the cartilage of the auricula, and firmly attached to the circumference of the auditory process of the temporal bone. The cartilage is deficient at the upper and back part of the meatus, its place being supplied by fibrous membrane; two or three deep fissures are present in the anterior part of the cartilage.

The **osseous portion** (*meatus acusticus externus osseus*) is about 16 mm. in length, and is narrower than the cartilaginous portion. It is directed inward and a little forward, forming in its course a slight curve the convexity of which is upward and backward. Its inner end is smaller than the outer, and sloped, the anterior wall




FIG. 870.—Horizontal section through left ear; upper half of section.

projecting beyond the posterior for about 4 mm.; it is marked, except at its upper part, by a narrow groove, the **tympanic sulcus**, in which the circumference of the tympanic membrane is attached. Its outer end is dilated and rough in the greater part of its circumference, for the attachment of the cartilage of the auricula. The front and lower parts of the osseous portion are formed by a curved plate of bone, the tympanic part of the temporal, which, in the fetus, exists as a separate ring (**annulus tympanicus**,) incomplete at its upper part (page 245).

The **skin** lining the meatus is very thin; adheres closely to the cartilaginous and osseous portions of the tube, and covers the outer surface of the tympanic membrane. After maceration, the thin pouch of epidermis, when withdrawn, preserves the form of the meatus. In the thick subcutaneous tissue of the cartilaginous part of the meatus are numerous ceruminous glands, which secrete the ear-wax; their structure resembles that of the sudoriferous glands.

**Relations of the Meatus.**—In front of the osseous part is the condyle of the mandible, which however, is frequently separated from the cartilaginous part by a portion of the parotid gland. The movements of the jaw influence to some extent the lumen of this latter portion. Behind the osseous part are the mastoid air cells, separated from the meatus by a thin layer of bone.

The **arteries** supplying the meatus are branches from the posterior auricular, internal maxillary, and temporal.

The **nerves** are chiefly derived from the auriculotemporal branch of the mandibular nerve and the auricular branch of the vagus.

These are cavities hollowed out of the substance of the bone, and lined by periosteum; they contain a clear fluid, the perilymph, in which the membranous labyrinth is situated.

**The Vestibule** (*vestibulum*).—The vestibule is the central part of the osseous labyrinth, and is situated medial to the tympanic cavity, behind the cochlea, and in front of the semicircular canals. It is somewhat ovoid in shape, but flattened transversely; it measures about 5 mm. from before backward, the same from above downward, and about 3 mm. across. In its *lateral* or *tympanic wall* is the **fenestra vestibuli**, closed, in the recent state, by the base of the stapes and annular ligament. On its *medial wall*, at the forepart, is a small circular depression, the **recessus sphaericus**, which is perforated, at its anterior and inferior part, by several minute holes (**macula cribrosa media**) for the passage of filaments of the acoustic nerve to the sacculæ; and behind this depression is an oblique ridge, the **crista vestibuli**, the anterior end of which is named the **pyramid of the vestibule**. This ridge bifurcates below to enclose a small depression, the **fossa cochlearis**, which is perforated by a number of holes for the passage of filaments of the acoustic nerve which supply the vestibular end of the ductus cochlearis. As the hinder part of the medial wall




FIG. 878.—Interior of right osseous labyrinth.

is the orifice of the **aquaeductus vestibuli**, which extends to the posterior surface of the petrous portion of the temporal bone. It transmits a small vein, and contains a tubular prolongation of the membranous labyrinth, the **ductus endolymphaticus**, which ends in a cul-de-sac between the layers of the dura mater within the cranial cavity. On the *upper wall* or *roof* is a transversely oval depression, the **recessus ellipticus**, separated from the recessus sphaericus by the crista vestibuli already mentioned. The pyramid and adjoining part of the recessus ellipticus are perforated by a number of holes (**macula cribrosa superior**). The apertures in the pyramid transmit the nerves to the utricle; those in the recessus ellipticus the nerves to the ampullæ of the superior and lateral semicircular ducts. *Behind* are the five orifices of the semicircular canals. In *front* is an elliptical opening, which communicates with the scala vestibuli of the cochlea.

**The Bony Semicircular Canals** (*canales semicirculares ossei*).—The bony semicircular canals are three in number, **superior**, **posterior**, and **lateral**, and are situated above and behind the vestibule. They are unequal in length, compressed from side to side, and each describes the greater part of a circle. Each measures about 0.8 mm. in diameter, and presents a dilatation at one end, called the **ampulla**, which

measures more than twice the diameter of the tube. They open into the vestibule by five orifices, one of the apertures being common to two of the canals.

The **superior semicircular canal** (*canalis semicircularis superior*), 15 to 20 mm. in length, is vertical in direction, and is placed transversely to the long axis of the petrous portion of the temporal bone, on the anterior surface of which its arch forms a round projection. It describes about two-thirds of a circle. Its lateral extremity is ampullated, and opens into the upper part of the vestibule; the opposite end joins with the upper part of the posterior canal to form the **crus commune**, which opens into the upper and medial part of the vestibule.

The **posterior semicircular canal** (*canalis semicircularis posterior*), also vertical, is directed backward, nearly parallel to the posterior surface of the petrous bone; it is the longest of the three, measuring from 18 to 22 mm.; its lower or ampullated end opens into the lower and back part of the vestibule, its upper into the crus commune already mentioned.




FIG. 879.—The cochlea and vestibule, viewed from above. (Testut.) All the hard parts which form the roof of the internal ear have been removed with the saw. A. Cochlea. B. Vestibule. C. Internal acoustic meatus. D. Tympanic cavity. 1. Lower border of vestibular fenestra. 2. Fissura vestibuli. 3. Recessus sphaericus. 4. Recessus ellipticus. 5. Fossa cochlearis. 6. Orifice of the aqueductus vestibuli. 7. Inferior opening of the posterior semicircular canal. 8. Non-ampullated end of lateral semicircular canal. 9. Scala tympani of the cochlea. 10. Scala vestibuli. 11. Cupula. 12. Lamina spiralis ossea, with 12', its vestibular origin; 12'', its external border. 13. Helicotrema. 14. Bony wall of cochlea.

The **lateral or horizontal canal** (*canalis semicircularis lateralis; external semicircular canal*) is the shortest of the three. It measures from 12 to 15 mm., and its arch is directed horizontally backward and lateralward; thus each semicircular canal stands at right angles to the other two. Its ampullated end corresponds to the upper and lateral angle of the vestibule, just above the fenestra vestibuli, where it opens close to the ampullated end of the superior canal; its opposite end opens at the upper and back part of the vestibule. The lateral canal of one ear is very nearly in the same plane as that of the other; while the superior canal of one ear is nearly parallel to the posterior canal of the other.

The **Cochlea** (Figs. 878, 879).—The cochlea bears some resemblance to a common snail-shell; it forms the anterior part of the labyrinth, is conical in form, and placed almost horizontally in front of the vestibule; its **apex** (*cupula*) is directed forward and lateralward, with a slight inclination downward, toward the upper and front

part of the labyrinthic wall of the tympanic cavity; its **base** corresponds with the bottom of the internal acoustic meatus, and is perforated by numerous apertures for the passage of the cochlear division of the acoustic nerve. It measures about 5 mm. from base to apex, and its breadth across the base is about 9 mm. It consists of a conical shaped central axis, the **modiolus**; of a canal, the inner wall of which is formed by the central axis, wound spirally around it for two turns and three-quarters, from the base to the apex; and of a delicate lamina, the **osseous spiral lamina**, which projects from the modiolus, and, following the windings of the canal, partially subdivides it into two. In the recent state a membrane, the **basilar membrane**, stretches from the free border of this lamina to the outer wall of the bony cochlea and completely separates the canal into two passages, which, however, communicate with each other at the apex of the modiolus by a small opening, named the **helicotrema**.

The **modiolus** is the conical central axis or pillar of the cochlea. Its base is broad, and appears at the bottom of the internal acoustic meatus, where it corresponds with the area cochleae; it is perforated by numerous orifices, which transmit filaments of the cochlear division of the acoustic nerve; the nerves for the first turn and a half pass through the foramina of the tractus spiralis foraminosus; those for the apical turn, through the foramen centrale. The canals of the tractus spiralis foraminosus pass up through the modiolus and successively bend outward to reach the attached margin of the lamina spiralis ossea. Here they become enlarged, and by their apposition form the **spiral canal of the modiolus**, which follows the course of the attached margin of the osseous spiral lamina and lodges the **spiral ganglion** (*ganglion of Corti*). The foramen centrale is continued into a canal which runs up the middle of the modiolus to its apex. The modiolus diminishes rapidly in size in the second and succeeding coil.

The bony canal of the cochlea takes two turns and three-quarters around the modiolus. It is about 30 mm. in length, and diminishes gradually in diameter from the base to the summit, where it terminates in the **cupula**, which forms the apex of the cochlea. The beginning of this canal is about 3 mm. in diameter; it diverges from the modiolus toward the tympanic cavity and vestibule, and presents three openings. One, the **fenestra cochleae**, communicates with the tympanic cavity—in the recent state this aperture is closed by the **secondary tympanic membrane**; another, of an elliptical form, opens into the vestibule. The third is the aperture of the aquaeductus cochleae, leading to a minute funnel-shaped canal, which opens on the inferior surface of the petrous part of the temporal bone and transmits a small vein, and also forms a communication between the subarachnoid cavity and the scala tympani.

The **osseous spiral lamina** (*lamina spiralis ossea*) is a bony shelf or ledge which projects from the modiolus into the interior of the canal, and, like the canal, takes two and three-quarter turns around the modiolus. It reaches about half-way toward the outer wall of the tube, and partially divides its cavity into two passages or *scalæ*, of which the upper is named the **scala vestibuli**, while the lower is termed the **scala tympani**. Near the summit of the cochlea the lamina ends in a hook-shaped process, the **hamulus laminae spiralis**; this assists in forming the boundary of a small opening, the **helicotrema**, through which the two *scalæ* communicate with each other. From the spiral canal of the modiolus numerous canals pass outward through the osseous spiral lamina as far as its free edge. In the lower part of the first turn a second bony lamina, the **secondary spiral lamina**, projects inward from the outer wall of the bony tube; it does not, however, reach the primary osseous spiral lamina, so that if viewed from the vestibule a narrow fissure, the **vestibule fissure**, is seen between them.

The *osseous labyrinth* is lined by an exceedingly thin fibro-serous membrane; its attached surface is rough and fibrous, and closely adherent to the bone; its



free surface is smooth and pale, covered with a layer of epithelium, and secretes a thin, limpid fluid, the **perilymph**. A delicate tubular process of this membrane is prolonged along the aqueduct of the vestibule to the inner surface of the dura mater.




FIG. 880.—The membranous labyrinth. (Enlarged.)

**The Membranous Labyrinth** (*labyrinthus membranaceus*) (Figs. 880, 881, 882).—The membranous labyrinth is lodged within the bony cavities just described, and has the same general form as these; it is, however, considerably smaller, and




FIG. 881.—Right human membranous labyrinth, removed from its bony enclosure and viewed from the antero-lateral aspect. (G. Retzius.)

is partly separated from the bony walls by a quantity of fluid, the **perilymph**. In certain places it is fixed to the walls of the cavity. The membranous labyrinth contains fluid, the **endolymph**, and on its walls the ramifications of the acoustic nerve are distributed.

Within the osseous vestibule the membranous labyrinth does not quite preserve the form of the bony cavity, but consists of two membranous sacs, the **utricle**, and the **sacculus**.

**The Utricle (*utriculus*).**—The utricle, the larger of the two, is of an oblong form, compressed transversely, and occupies the upper and back part of the vestibule, lying in contact with the recessus ellipticus and the part below it. That portion which is lodged in the recess forms a sort of pouch or cul-de-sac, the floor and anterior wall of which are thickened, and form the **macula acustica utriculi**, which receives the utricular filaments of the acoustic nerve. The cavity of the utricle communicates behind with the semicircular ducts by five orifices. From its anterior wall is given off the **ductus utriculosaccularis**, which opens into the ductus endolymphaticus.




FIG. 882.—The same from the postero-medial aspect. (G. Retzius.) 1. Lateral semicircular canal; 1', its ampulla. 2. Posterior canal; 2', its ampulla. 3. Superior canal; 3', its ampulla. 4. Conjoined limb of superior and posterior canals (*sinus utriculi superior*). 5. Utricle. 5'. Recessus utriculi. 5". Sinus utriculi posterior. 6. Ductus endolymphaticus. 7. Canalis utriculosaccularis. 8. Nerve to ampulla of superior canal. 9. Nerve to ampulla of lateral canal. 10. Nerve to recessus utriculi (in Fig. 881, the three branches appear conjoined). 10'. Ending of nerve in recessus utriculi. 11. Facial nerve. 12. Lagena cochleae. 13. Nerve of cochlea within spiral lamina. 14. Basilar membrane. 15. Nerve fibres to macula of sacculus. 16. Nerve to ampulla of posterior canal. 17. Sacculus. 18. Secondary membrane of tympanum. 19. Canalis reuniens. 20. Vestibular end of ductus cochlearis. 23. Section of the facial and acoustic nerves within internal acoustic meatus (the separation between them is not apparent in the section).

**The Sacculus (*sacculus*).**—The sacculus is the smaller of the two vestibular sacs; it is globular in form, and lies in the recessus sphaericus near the opening of the scala vestibuli of the cochlea. Its anterior part exhibits an oval thickening, the **macula acustica sacculi**, to which are distributed the saccular filaments of the acoustic nerve. Its cavity does not directly communicate with that of the utricle. From the posterior wall a canal, the **ductus endolymphaticus**, is given off; this duct is joined by the ductus utriculosaccularis, and then passes along the aquaeductus vestibuli and ends in a blind pouch (**saccus endolymphaticus**) on the posterior surface of the petrous portion of the temporal bone, where it is in contact with the dura mater. From the lower part of the sacculus a short tube, the **canalis reuniens of Hensen**, passes downward and opens into the ductus cochlearis near its vestibular extremity (Fig. 880).

**The Semicircular Ducts (*ductus semicirculares*; membranous semicircular canals),** (Figs. 881, 882).—The semicircular ducts are about one-fourth of the diameter

of the osseous canals, but in number, shape, and general form they are precisely similar, and each presents at one end an ampulla. They open by five orifices into the utricle, one opening being common to the medial end of the superior and the upper end of the posterior duct. In the ampullæ the wall is thickened, and projects into the cavity as a fiddle-shaped, transversely placed elevation, the **septum transversum**, in which the nerves end.

The utricle, saccule, and semicircular ducts are held in position by numerous fibrous bands which stretch across the space between them and the bony walls.

**Structure** (Fig. 883).—The walls of the utricle, saccule, and semicircular ducts consist of three layers. The *outer layer* is a loose and flocculent structure, apparently composed of ordinary fibrous tissue containing bloodvessels and some pigment-cells. The *middle layer*, thicker and more transparent, forms a homogeneous *membrana propria*, and presents on its internal surface, especially in the semicircular ducts, numerous papilliform projections, which, on the addition of acetic acid, exhibit an appearance of longitudinal fibrillation. The *inner layer* is formed of polygonal nucleated epithelial cells. In the maculæ of the utricle and saccule, and in the transverse septa of the ampullæ of the semicircular ducts, the middle coat is thickened and the epithelium is columnar, and consists of **supporting cells** and **hair cells**. The former are fusiform, and their deep ends are attached to the *membrana propria*, while their free extremities are united to form a thin cuticle. The hair cells are flask-shaped, and their deep, rounded ends do not reach the *membrana propria*, but lie between the supporting cells. The deep part of each contains a large nucleus, while its more superficial part is granular and pigmented. The free end is surmounted by a long, tapering, hair-like filament, which projects into the cavity. The filaments of the acoustic nerve enter these parts, and having pierced the outer and middle layers, they lose their medullary sheaths, and their axis-cylinders ramify between the hair cells.

Two small rounded bodies termed **otoconia**, and consisting of a mass of minute crystalline grains of carbonate of lime, held together in a mesh of gelatinous tissue, are suspended in the endolymph in contact with the free ends of the hairs projecting from the maculæ. According to Bowman, a calcareous material is also sparingly scattered in the cells lining the ampullæ of the semicircular ducts.

**The Ductus Cochlearis** (*membranous cochlea; scala media*).—The ductus cochlearis consists of a spirally arranged tube enclosed in the bony canal of the cochlea and lying along its outer wall.

As already stated, the osseous spiral lamina extends only part of the distance between the modiolus and the outer wall of the cochlea, while the **basilar membrane** stretches from its free edge to the outer wall of the cochlea, and completes the roof of the scala tympani. A second and more delicate membrane, the **vestibular membrane** (*Reissneri*) extends from the thickened periosteum covering the osseous spiral lamina to the outer wall of the cochlea, where it is attached at some little distance above the outer edge of the basilar membrane. A canal is thus shut off between the scala tympani below and the scala vestibuli above; this is the **ductus**




FIG. 883.—Transverse section of a human semicircular canal and duct (after Rüdinger). (Testut.) 1. Semicircular canal. 2. Periosteum. 3. Semicircular duct, with 4. papilliform processes on its internal surface. 5. Connective tissue binding the duct to the periosteum. 6, 6. Fibrous bands uniting the free surface of the duct to the periosteum. 7. Vessels. 8. Endolymphatic space. 9, 9. Perilymphatic space.



**cochlearis** or **scala media** (Fig. 884). It is triangular on transverse section, its roof being formed by the vestibular membrane, its outer wall by the periosteum lining the bony canal, and its floor by the membrana basilaris and the outer part of the lamina spiralis ossea. Its extremities are closed; the upper is termed the **lagena** and is attached to the cupula at the upper part of the helicotrema; the lower is lodged in the recessus cochlearis of the vestibule. Near the lower end the ductus




FIG. 884.—Diagrammatic longitudinal section of the cochlea.

cochlearis is brought into continuity with the saccule by a narrow, short canal, the **canalis reuniens of Hensen** (Fig. 880). On the membrana basilaris is situated the spiral organ of Corti. The vestibular membrane is thin and homogeneous, and is covered on its upper and under surfaces by a layer of epithelium. The periosteum, forming the outer wall of the ductus cochlearis, is greatly thickened and altered in character, and is called the **spiral ligament**. It projects inward below as a triangular prominence, the **basilar crest**, which gives attachment to the outer




FIG. 885.—Floor of ductus cochlearis.

edge of the basilar membrane; immediately above the crest is a concavity, the **sulcus spiralis externus**. The upper portion of the spiral ligament contains numerous capillary loops and small bloodvessels, and is termed the **stria vascularis**.

The osseous spiral lamina consists of two plates of bone, and between these are the canals for the transmission of the filaments of the acoustic nerve. On the upper plate of that part of the lamina which is outside the vestibular membrane, the perios-

teum is thickened to form the **limbus laminae spiralis** (Fig. 885), this ends externally in a concavity, the **sulcus spiralis internus**, which represents, on section, the form of the letter C; the upper part, formed by the overhanging extremity of the limbus, is named the **vestibular lip**; the lower part, prolonged and tapering, is called the **tympanic lip**, and is perforated by numerous foramina for the passage of the cochlear nerves. The upper surface of the vestibular lip is intersected at right angles by a number of furrows, between which are numerous elevations; these present the appearance of teeth along the free surface and margin of the lip, and have been named by Huschke the **auditory teeth** (Fig. 886). The limbus is covered by a layer of what appears to be squamous epithelium, but the deeper parts of the cells with their contained nuclei occupy the intervals between the elevations and between the auditory teeth. This layer of epithelium is continuous on the one hand with that lining the sulcus spiralis internus, and on the other with that covering the under surface of the vestibular membrane.




FIG. 886.—Limbus laminae spiralis and membrana basilaris. (Schematic.) (Testut.) 1, 1'. Upper and lower lamellae of the lamina spiralis ossea. 2. Limbus laminae spiralis, with *a*, the teeth of the first row; *b*, *b'*, the auditory teeth of the other rows; *c*, *c'*, the interdental grooves and the cells which are lodged in them. 3. Sulcus spiralis internus, with 3', its labium vestibulare, and 3'', its labium tympanicum. 4. Foramina nervosa, giving passage to the nerves from the ganglion spirale or ganglion of Corti. 5. Vas spirale. 6. Zona arcuata, and 6', zona pectinata of the basilar membrane, with *a*, its hyaline layer, *β*, its connective-tissue layer. 7. Arch of spiral organ, with 7', its inner rod, and 7'', its outer rod. 8. Feet of the internal rods, from which the cells are removed. 9. Feet of the external rods. 10. Vestibular membrane, at its origin.

**Basilar Membrane.**—The basilar membrane stretches from the tympanic lip of the osseous spiral lamina to the basilar crest and consists of two parts, an inner and an outer. The inner is thin, and is named the **zona arcuata**: it supports the spiral organ of Corti. The outer is thicker and striated, and is termed the **zona pectinata**. The under surface of the membrane is covered by a layer of vascular connective tissue; one of the vessels in this tissue is somewhat larger than the rest, and is named the **vas spirale**; it lies below Corti's tunnel.

The **spiral organ of Corti** (*organon spirale* [Corti]; *organ of Corti*) (Figs. 887, 888) is composed of a series of epithelial structures placed upon the inner part of the basilar membrane. The more central of these structures are two rows of rod-like bodies, the **inner and outer rods** or **pillars of Corti**. The bases of the rods are supported on the basilar membrane, those of the inner row at some distance from those of the outer; the two rows incline toward each other and, coming into contact above, enclose between them and the basilar membrane a triangular tunnel, the **tunnel of Corti**. On the inner side of the inner rods is a single row of hair cells, and on the outer side of the outer rods three or four rows of similar cells, together with certain



supporting cells termed the cells of Deiters and Hensen. The free ends of the outer hair cells occupy a series of apertures in a net-like membrane, the **reticular membrane**, and the entire organ is covered by the tectorial membrane.




FIG. 887.—Section through the spiral organ of Corti. Magnified. (G. Retzius.)

**RODS OF CORTI.**—Each of these consists of a base or foot-plate, and elongated part or body, and an upper end or head; the body of each rod is finely striated, but in the head there is an oval non-striated portion which stains deeply with carmine.




FIG. 888.—The lamina reticularis and subjacent structures. (Schematic) (Testut.) A. Internal rod of Corti, with *a*, its plate. B. External rod (in yellow). C. Tunnel of Corti. D. Membrana basilaris. E. Inner hair cells. 1, 1' Internal and external borders of the membrana reticularis. 2, 2', 2'' The three rows of circular holes (in blue). 3. First row of phalanges (in yellow). 4, 4', 4'' Second, third, and fourth rows of phalanges (in red). 6, 6', 6'' The three rows of outer hair cells (in blue). 7, 7', 7'' Cells of Deiters. 8. Cells of Hensen and Claudius.

Occupying the angles between the rods and the basilar membrane are nucleated cells which partly envelop the rods and extend on to the floor of Corti's tunnel; these may be looked upon as the undifferentiated parts of the cells from which the rods have been formed.

The **inner rods** number nearly 6000, and their bases rest on the basilar membrane close to the tympanic lip of the sulcus spiralis internus. The shaft or body of each is sinuously curved and forms an angle of about 60 degrees with the basilar membrane. The head resembles the proximal end of the ulna and presents a deep concavity which accommodates a convexity on the head of the outer rod. The head-plate, or portion overhanging the concavity, overlaps the head-plate of the outer rod.

The **outer rods**, nearly 4000 in number, are longer and more obliquely set than the inner, forming with the basilar membrane an angle of about 40 degrees. Their heads are convex internally; they fit into the concavities on the heads of the inner rods and are continued outward as thin flattened plates, termed **phalangeal processes**, which unite with the phalangeal processes of Deiters' cells to form the reticular membrane.

**Hair Cells.**—The hair cells are short columnar cells; their free ends are on a level with the heads of Corti's rods, and each is surmounted by about twenty hair-like processes arranged in the form of a crescent with its concavity directed inward. The deep ends of the cells reach about half-way along Corti's rods, and each contains a large nucleus; in contact with the deep ends of the hair cells are the terminal filaments of the cochlear division of the acoustic nerve. The *inner* hair cells are arranged in a single row on the medial side of the inner rods, and their diameters being greater than those of the rods it follows that each hair cell is supported by more than one rod. The free ends of the inner hair cells are encircled by a cuticular membrane which is fixed to the heads of the inner rods. Adjoining the inner hair cells are one or two rows of columnar supporting cells, which, in turn, are continuous with the cubical cells lining the sulcus spiralis internus. The *outer* hair cells number about 12,000, and are nearly twice as long as the inner. In the basal coil of the cochlea they are arranged in three regular rows; in the apical coil, in four, somewhat irregular, rows.

Between the rows of the outer hair cells are rows of supporting cells, called the **cells of Deiters**; their expanded bases are planted on the basilar membrane, while the opposite end of each presents a clubbed extremity or **phalangeal process**. Immediately to the outer side of Deiters' cells are five or six rows of columnar cells, the **supporting cells of Hensen**. Their bases are narrow, while their upper parts are expanded and form a rounded elevation on the floor of the ductus cochlearis. The columnar cells lying outside Hensen's cells are termed the **cells of Claudius**. A space exists between the outer rods of Corti and the adjacent hair cells; this is called the **space of Nuel**.

The **reticular lamina** (Fig. 888) is a delicate frame-work perforated by rounded holes which are occupied by the free ends of the outer hair cells. It extends from the heads of the outer rods of Corti to the external row of the outer hair cells, and is formed by several rows of "minute fiddle-shaped cuticular structures," called **phalanges**, between which are circular apertures containing the free ends of the hair cells. The inner most row of phalanges consists of the phalangeal processes of the outer rods of Corti; the outer rows are formed by the modified free ends of Deiters' cells.

Covering the sulcus spiralis internus and the spiral organ of Corti is the **tectorial membrane**, which is attached to the limbus laminae spiralis close to the inner edge of the vestibular membrane. Its inner part is thin and overlies the auditory teeth of Huschke; its outer part is thick, and along its lower edge, opposite the inner hair cells, is a clear band, named **Hensen's stripe**. The lateral margin of the membrane is much thinner, and is attached to the outer row of Deiters' cells (Retzius).

The **acoustic nerve** (*n. acusticus*; *auditory nerve* or *nerve of hearing*) divides near the bottom of the internal acoustic meatus into an anterior or cochlear and a posterior or vestibular branch.

The **vestibular nerve** (*n. vestibularis*) supplies the utricle, the saccule, and the ampullæ of the semicircular ducts. On the trunk of the nerve, within the internal acoustic meatus, is a ganglion, the **vestibular ganglion** (*ganglion of Scarpa*); the fibres of the nerve arise from the cells of this ganglion. On the distal side of the ganglion the nerve splits into a superior, an inferior, and a posterior branch.<sup>1</sup> The filaments of the *superior branch* are transmitted through the foramina in the area vestibularis superior, and end in the macula of the utricle and in the ampullæ of the superior and lateral semicircular ducts; those of the *inferior branch* traverse the foramina in the area vestibularis inferior, and end in the macula of the saccule. The *posterior branch* runs through the foramen singulare at the postero-inferior part of the bottom of the meatus and divides into filaments for the supply of the ampulla of the posterior semicircular duct.

The **cochlear nerve** (*n. cochlearis*) divides into numerous filaments at the base of the modiolus; those for the basal and middle coils pass through the foramina in the tractus spiralis foraminosus, those for the apical coil through the canalis centralis, and the nerves bend outward to pass between the lamellæ of the osseous spiral lamina. Occupying the spiral canal of the modiolus is the **spiral ganglion of the cochlea** (*ganglion of Corti*) (Fig. 889), consisting of bipolar nerve cells, which constitute the cells of origin of this nerve. Reaching the outer edge of the osseous spiral lamina, the fibres of the nerve pass through the foramina in the tympanic lip; some end by arborizing around the bases of the inner hair cells, while others pass




FIG. 889.—Part of the cochlear division of the acoustic nerve, highly magnified. (Henle.)

between Corti's rods and across the tunnel, to end in a similar manner in relation to the outer hair cells. The cochlear nerve gives off a vestibular branch to supply the vestibular end of the ductus cochlearis; the filaments of this branch pass through the foramina in the fossa cochlearis (page 1058).

**Vessels.**—The **arteries of the labyrinth** are the internal auditory, from the basilar, and the stylomastoid, from the posterior auricular. The internal auditory artery divides at the bottom of the internal acoustic meatus into two branches: cochlear and vestibular. The cochlear branch subdivides into twelve or fourteen twigs, which traverse the canals in the modiolus, and are distributed, in the form of a capillary net-work, in the lamina spiralis and basilar membrane. The vestibular branches are distributed to the utricle, saccule, and semicircular ducts.

The **veins** of the vestibule and semicircular canals accompany the arteries, and, receiving those of the cochlea at the base of the modiolus, unite to form the internal auditory veins which end in the posterior part of the superior petrosal sinus or in the transverse sinus.

**Applied Anatomy.**—The diseased conditions which may be found in the internal ear usually result from the spread of a suppurative process from the middle ear—thus in chronic suppuration of the latter, destruction of the internal ear may take place, with necrosis of parts of the cochlea or vestibule. Such cases will be associated with “nerve deafness,” and the disease may spread by means of the sheaths of the facial and acoustic nerves into the posterior fossa of the skull.

Hemorrhage occasionally occurs into the labyrinth in certain blood disorders, resulting in complete nerve deafness, and such conditions may be associated with symptoms known as *Ménière's disease*, vertigo, giddiness, and tinnitus. Nerve deafness is diagnosticated when all “bone-conduction” of sound is lost, and is most commonly seen in patients suffering from congenital syphilis, many deaf-mutes being the subjects of this condition.

<sup>1</sup> The nerve sometimes splits on the proximal side of the ganglion, and the latter is then divided into three parts, one on each branch of the nerve.

## PERIPHERAL TERMINATIONS OF NERVES OF GENERAL SENSATIONS.

The peripheral terminations of the nerves associated with general sensations, *i. e.*, the muscular sense and the senses of heat, cold, pain, and pressure, are widely distributed throughout the body. These nerves may end *free* among the tissue elements, or in *special end-organs* where the terminal nerve filaments are enclosed in capsules.

**Free nerve-endings** occur chiefly in the epidermis and in the epithelium covering certain mucous membranes; they are well seen also in the stratified squamous epithelium of the cornea, and are also found in the root-sheaths and papillæ of the hairs, and around the bodies of the sudoriferous glands. When the nerve fibre approaches its termination, the medullary sheath suddenly disappears, leaving only the axis-cylinder surrounded by the neurolemma. After a time the fibre loses its neurolemma, and consists only of an axis-cylinder, which can be seen, in preparations stained with chloride of gold, to be made up of fine varicose fibrillæ. Finally, the axis-cylinder breaks up into its constituent fibrillæ which often present regular varicosities and anastomose with one another, and end in small knobs or disks between the epithelial cells.

Under this heading may be classed the **tactile disks** described by Merkel as occurring in the epidermis of the pig's snout, where the fibrillæ of the axis-cylinder end in cup-shaped disks in apposition with large epithelial cells.

The **special end-organs** exhibit great variety in size and shape, but have one feature in common—*viz.*, the terminal nerve fibrillæ are enveloped by a capsule. Included in this group are the end-bulbs of Krause, the corpuscles of Grandry, of Pacini, of Golgi and Mazzoni, of Wagner and Meissner, and the neurotendinous and neuromuscular spindles.

The **end-bulbs of Krause** (Fig. 890) are minute cylindrical or oval bodies, consisting of a capsule formed by the expansion of the connective-tissue sheath of a medullated fibre, and containing a soft semifluid core in which the axis-cylinder terminates either in a bulbous extremity or in a coiled-up plexiform mass. End-bulbs are found in the conjunctiva of the eye (where they are spheroidal in shape in man, but cylindrical in most other animals), in the mucous membrane of the lips and tongue, and in the epineurium of nerve trunks. They are also found in the penis and the clitoris, and have received the name of **genital corpuscles**; in these situations they have a mulberry-like appearance, being constricted by connective-tissue septa into from two to six knob-like masses. In the synovial membranes of certain joints, *e. g.*, those of the fingers, rounded or oval end-bulbs occur, and are designated **articular end-bulbs**.

The **tactile corpuscles of Grandry** occur in the papillæ of the beak and tongue of birds. Each consists of a capsule composed of a very delicate, nucleated membrane, and contains two or more granular, somewhat flattened cells; between these cells the axis-cylinder ends in flattened disks.

The **Pacinian corpuscles** (Fig. 891) are found in the subcutaneous tissue on the nerves of the palm of the hand and sole of the foot and in the genital organs of both sexes; they also occur in connection with the nerves of the joints, and in some other situations, as in the mesentery and pancreas of the cat and along the tibia of the rabbit. Each of these corpuscles is attached to and encloses the termination of a single nerve fibre. The corpuscle, which is perfectly visible to the naked eye (and which can be most easily demonstrated in the mesentery of a cat), consists of a number of lamellæ or capsules arranged more or less concentrically around a central clear space, in which the nerve-fibre is contained. Each lamella is composed of bundles of fine connective-tissue fibres, and is lined on its inner surface by a single layer of flattened epithelioid cells. The central clear space, which is elongated or cylindrical in shape, is filled with a transparent core, in the middle of which the axis-cylinder traverses the space to near its distal extremity, where it ends in one or more small knobs. Todd and Bowman have described minute arteries as entering by the sides of the nerves and forming capillary loops in the intercapsular spaces, and even penetrating into the central space.

Herbst has described a nerve-ending somewhat similar to the Pacinian corpuscle, in the mucous membrane of the tongue of the duck, and in some other situations. It differs, however, from the Pacinian corpuscle, in being smaller, in its capsules being more closely approximated, and especially in the fact that the axis cylinder in the central clear space is coated with a continuous row of nuclei. These bodies are known as the **corpuscles of Herbst**.

The **corpuscles of Golgi and Mazzoni** are found in the subcutaneous tissue of the pulp of the fingers. They differ from Pacinian corpuscles in that their capsules are thinner, their contained cores thicker, and in the latter the axis-cylinders ramify more extensively and end in flat expansions.




FIG. 890. — End-bulb of Krause. *a.* Medullated nerve fibre. *b.* Capsule of corpuscle. (Klein.)

The **tactile corpuscles of Wagner and Meissner** (Fig. 892) are oval-shaped bodies. Each is enveloped by a connective-tissue capsule, and imperfect membranous septa derived from this penetrate the interior. The axis-cylinder passes through the capsule, and after making several spiral turns around the body of the corpuscle ends in small globular or pyriform enlargements. These tactile corpuscles occur in the papillæ of the corium of the hand and foot, the front of the forearm, the skin of the lips, the mucous membrane of the tip of the tongue, the palpebral conjunctiva, and the skin of the mammary papilla.

**Corpuscles of Ruffini.**—Ruffini described a special variety of nerve-ending in the subcuta-




FIG. 891.—Pacinian corpuscle, with its system of capsules and central cavity. *a*. Arterial twig, ending in capillaries, which form loops in some of the intercapsular spaces, and one penetrates to the central capsule. *b*. The fibrous tissue of the stalk. *n*. Nerve tube advancing to the central capsule, there losing its white matter, and stretching along the axis to the opposite end, where it ends by a tuberculated enlargement.




FIG. 892.—Papilla of the hand, treated with acetic acid. Magnified 350 times. *A*. Side view of a papilla of the hand. *a*. Cortical layer. *b*. Tactile corpuscle. *c*. Small nerve of the papilla, with neurolemma. *d*. Its two nervous fibres running with spiral coils around the tactile corpuscle. *e*. Apparent termination of one of these fibres. *B*. A tactile papilla seen from above so as to show its transverse section. *a*. Cortical layer. *b*. Nerve fibres. *c*. Outer layer of the tactile body, with nuclei. *d*. Clear interior substance.

neous tissue of the human finger (Fig. 893); they are principally situated at the junction of the corium with the subcutaneous tissue. They are oval in shape, and consist of strong connective-tissue sheaths, inside which the nerve-fibres divide into numerous branches, which show vari-  
cosities and end in small free knobs.




FIG. 893.—Nerve ending of Ruffini. (After A. Ruffini.)

The **neurotendinous spindles** (*organs of Golgi*) are chiefly found near the junctions of tendons and muscles. Each is enclosed in a capsule which contains a number of enlarged tendon fasciculi (*intrafusal fasciculi*). One or more nerve fibres perforate the side of the capsule and lose their medullary sheaths; the axis-cylinders subdivide and end between the tendon fibres in irregular disks or varicosities (Fig. 894).



The **neuromuscular spindles** are present in the majority of voluntary muscles, and consist of small bundles of peculiar muscular fibres (*intrafusal fibres*), embryonic in type, invested by capsules, within which nerve fibres, experimentally shown to be sensory in origin, terminate.




FIG. 894.—Organ of Golgi (neurotendinous spindle) from the human tendo calcaneus. (After Ciaccio.)

These neuromuscular spindles vary in length from 0.8 mm. to 5 mm., and have a distinctly fusiform appearance. The large medullated nerve fibres passing to the end-organ are from one to three or four in number; entering the fibrous capsule, they divide several times, and,




FIG. 895.—Middle third of a terminal plaque in the muscle spindle of an adult cat. (After Ruffini.)

losing their medullary sheaths, ultimately end in naked axis-cylinders encircling the intrafusal fibres by flattened expansions, or irregular ovoid or rounded disks (Fig. 895). Neuromuscular spindles have not yet been demonstrated in the tongue muscles, and only a few exist in the ocular muscles.

## THE COMMON INTEGUMENT (INTEGUMENTUM COMMUNE; SKIN).

The **integument** (Fig. 896) covers the body and protects the deeper tissues; it contains the peripheral endings of many of the sensory nerves; it plays an important part in the regulation of the body temperature, and has also limited excretory and absorbing powers. It consists principally of a layer of vascular connective tissue, named the **corium** or **cutis vera**, and an external covering of epithelium, termed the **epidermis** or **cuticle**. On the surface of the former layer are sensitive and **vascular papillæ** within, or beneath it, are certain organs with special functions: namely, the **sudoriferous** and **sebaceous glands**, and the **hair follicles**.

The **epidermis**, **cuticle**, or **scarf skin** is non-vascular, and consists of stratified epithelium (Fig. 897), and is accurately moulded on the papillary layer of the corium. It varies in thickness in different parts. In some situations, as in the palms of the hands and soles of the feet, it is thick, hard, and horny in texture. This may be in

a measure due to the fact that these parts are exposed to intermittent pressure, but that this is not the only cause is proved by the fact that the condition exists to a very considerable extent at birth. The more superficial layers of cells, called the **horny layer** (*stratum corneum*), may be separated by maceration from a deeper stratum, which is called the **stratum mucosum**, and which consists of several layers of differently shaped cells. The free surface of the epidermis is marked by a net-work of linear furrows of variable size, dividing the surface into a number of polygonal or lozenge-shaped areas. Some of these furrows are large, as opposite the flexures of the joints, and correspond to the folds in the corium produced by move-




FIG. 896.—A diagrammatic sectional view of the skin (magnified).

ments. In other situations, as upon the back of the hand, they are exceedingly fine, and intersect one another at various angles. Upon the palmar surfaces of the hands and fingers, and upon the soles of the feet, these lines are very distinct, and are disposed in curves; they depend upon the large size and peculiar arrangements of the papillæ upon which the epidermis is placed. In each individual the lines on the tips of the fingers and thumbs form distinct patterns unlike those of any other person. A method of determining the identity of a criminal is based on this fact, impressions "finger-prints" of these lines being made on paper covered with soot, or on white paper after first covering the fingers with ink. The deep

surface of the epidermis is accurately moulded upon the papillary layer of the corium, the papillæ being covered by a basement membrane; so that when the epidermis is removed by maceration, it presents on its under surface a number of pits or depressions corresponding to the papillæ, and ridges corresponding to the intervals between them. Fine tubular prolongations are continued from this layer into the ducts of the sudoriferous and sebaceous glands.




FIG. 897.—Section of epidermis. (Ranvier.)

The epidermis consists of stratified epithelium which is arranged in four layers from within outward as follows: (a) **stratum mucosum**, (b) **stratum granulosum**, (c) **stratum lucidum**, and (d) **stratum corneum**.

The **stratum mucosum** (*mucous layer*) is composed of several layers of cells; those of the deepest layer are columnar in shape and placed perpendicularly on the surface of the basement membrane, to which they are attached by toothed extremities; this deepest layer is sometimes termed the **stratum germinativum**; the succeeding strata consist of cells of a more rounded or polyhedral form, the contents of which are soft, opaque, granular, and soluble in acetic acid. These are known as prickly cells, because of the bridges by which they are connected to one another (see page 38). They contain fine fibrils which are continuous across the connecting processes with corresponding fibrils in adjacent cells. Between the bridges are fine intercellular clefts serving for the passage of lymph, and in these, lymph corpuscles or pigment granules may be found.

The **stratum granulosum** comprises two or three layers of flattened cells which contain granules of *eleidin*, a substance readily stained by hematoxylin or carmine, and probably an intermediate substance in the formation of keratin. They are supposed to be cells in a transitional stage between the protoplasmic cells of the **stratum mucosum** and the horny cells of the superficial layers.

The **stratum lucidum** appears in section as a homogeneous or dimly striated membrane, composed of closely packed cells in which traces of flattened nuclei may be found, and in which minute granules of a substance named *keratohyalin* are present.

The **stratum corneum** (*horny layer*) consists of several layers of horny epithelial



scales in which no nuclei are discernible, and which are unaffected by acetic acid, the protoplasm having become changed into horny material or *keratin*. According to Ranvier they contain granules of a material which has the characteristics of beeswax.

The black color of the skin in the negro, and the tawny color among some of the white races, is due to the presence of pigment in the cells of the epidermis. This pigment is more especially distinct in the cells of the *stratum mucosum*, and is similar to that found in the cells of the pigmentary layer of the retina. As the cells approach the surface and desiccate, the color becomes partially lost; the disappearance of the pigment from the superficial layers of the epidermis is, however, difficult to explain.

The **Corium, Cutis Vera, Dermis, or True Skin** is tough, flexible, and highly elastic. It varies in thickness in different parts of the body. Thus it is very thick in the palms of the hands and soles of the feet; thicker on the posterior aspect of the body than on the front, and on the lateral than on the medial sides of the limbs. In the eyelids, scrotum, and penis it is exceedingly thin and delicate.

It consists of felted connective tissue, with a varying amount of elastic fibres and numerous bloodvessels, lymphatics, and nerves. The connective tissue is arranged in two layers: a deeper or **reticular**, and a superficial or **papillary**. Unstriped muscular fibres are found in the superficial layers of the corium, wherever hairs are present, and in the subcutaneous areolar tissue of the scrotum, penis, labia majora, and nipples. In the nipples the fibres are disposed in bands, closely reticulated and arranged in superimposed laminæ.

The **reticular layer** (*stratum reticulare; deep layer*) consists of strong interlacing bands, composed chiefly of white fibrous tissue, but containing some fibres of yellow elastic tissue, which vary in number in different parts; and connective-tissue corpuscles, which are often to be found flattened against the white fibrous tissue bundles. Toward the attached surface the fasciculi are large and coarse, and the areolæ left by their interlacement are large, and occupied by adipose tissue and sweat glands. Below the reticular layer is the subcutaneous areolar tissue, which, except in a few situations, contains fat.

The **papillary layer** (*stratum papillare; superficial layer; corpus papillare of the corium*) consists of numerous small, highly sensitive, and vascular eminences, the **papillæ**, which rise perpendicularly from its surface. The papillæ are minute conical eminences, having rounded or blunted extremities, occasionally divided into two or more parts, and are received into corresponding pits on the under surface of the cuticle. On the general surface of the body, more especially in parts endowed with slight sensibility, they are few in number, and exceedingly minute; but in some situations, as upon the palmar surfaces of the hands and fingers, and upon the plantar surfaces of the feet and toes, they are long, of large size, closely aggregated together, and arranged in parallel curved lines, forming the elevated ridges seen on the free surface of the epidermis. Each ridge contains two rows of papillæ, between which the ducts of the sudoriferous glands pass outward to open on the summit of the ridge. Each papilla consists of very small and closely interlacing bundles of finely fibrillated tissue, with a few elastic fibres; within this tissue is a capillary loop, and in some papillæ, especially in the palms of the hands and the fingers, there are tactile corpuscles.

The **arteries** supplying the skin form a net-work in the subcutaneous tissue, and from this net-work branches are given off to supply the sudoriferous glands, the hair follicles, and the fat. Other branches unite in a plexus immediately beneath the corium; from this plexus, fine capillary vessels pass into the papillæ, forming, in the smaller ones, a single capillary loop, but in the larger, a more or less convoluted vessel. The **lymphatic vessels** of the skin form two net-works, superficial and deep, which communicate with each other and with those of the subcutaneous tissue by oblique branches.

The **nerves** of the skin terminate partly in the epidermis and partly in the corium; their different modes of ending are described on pages 1069 to 1071.

## THE APPENDAGES OF THE SKIN.

The appendages of the skin are the **nails**, the **hairs**, and the **sudoriferous** and **sebaceous glands** with their ducts.

The **Nails** (*ungues*) (Fig. 898) are flattened, elastic structures of a horny texture, placed upon the dorsal surfaces of the terminal phalanges of the fingers and toes. Each nail is convex on its outer surface, concave within, and is implanted by a portion, called the **root**, into a groove in the skin; the exposed portion is called the **body**, and the distal extremity the **free edge**. The nail is firmly adherent to the corium, being accurately moulded upon its surface; the part beneath the body and root of the nail is called the **nail matrix**, because from it the nail is produced. Under the greater part of the body of the nail, the matrix is thick, and raised into a series of longitudinal ridges which are very vascular, and the color is seen through the transparent tissue. Near the root of the nail, the papillæ are smaller, less vascular, and have no regular arrangement, and here the tissue of the nail is more opaque; hence this portion is of a whiter color, and is called the **lunula** on account of its shape.




FIG. 898.—Longitudinal section through nail and its nail groove (sulcus).

The cuticle as it passes forward on the dorsal surface of the finger or toe is attached to the surface of the nail a little in advance of its root; at the extremity of the finger it is connected with the under surface of the nail a little behind its free edge. The cuticle and horny substance of the nail (both epidermic structures) are thus directly continuous with each other. The superficial, horny part of the nail consists of a greatly thickened stratum lucidum, the stratum corneum forming merely the thin cuticular fold (**eponychium**) which overlaps the lunula; the deeper part consists of the stratum mucosum. The cells in contact with the papillæ of the matrix are columnar in form and arranged perpendicularly to the surface; those which succeed them are of a rounded or polygonal form, the more superficial ones becoming broad, thin, and flattened, and so closely packed as to make the limits of the cells very indistinct. The nails grow in length by the proliferation of the cells of the stratum mucosum at the root of the nail, and in thickness from that part of the stratum mucosum which underlies the lunula.

**Hairs** (*pili*) are found on nearly every part of the surface of the body, but are absent from the palms of the hands, the soles of the feet, the dorsal surfaces of the terminal phalanges, the glans penis, the inner surface of the prepuce, and the inner surfaces of the labia. They vary much in length, thickness, and color in different parts of the body and in different races of mankind. In some parts, as in the skin of the eyelids, they are so short as not to project beyond the follicles containing them; in others, as upon the scalp, they are of considerable length; again, in other parts, as the eyelashes, the hairs of the pubic region, and the whiskers and beard, they are remarkable for their thickness. Straight hairs are stronger than curly hairs, and present on transverse section a cylindrical or oval outline; curly hairs, on the other hand, are flattened. A hair consists of a **root**, the part implanted in the skin; and a **shaft** or **scapus**, the portion projecting from the surface.

The **root of the hair** (*radix pili*) ends in an enlargement, the **hair bulb**, which is



whiter in color and softer in texture than the shaft, and is lodged in a follicular involution of the epidermis called the **hair follicle** (Fig. 899). When the hair is of considerable length the follicle extends into the subcutaneous cellular tissue. The hair follicle commences on the surface of the skin with a funnel-shaped opening, and passes inward in an oblique or curved direction—the latter in curly hairs—to become dilated at its deep extremity, where it corresponds with the hair bulb. Opening into the follicle, near its free extremity, are the ducts of one or more sebaceous glands. At the bottom of each hair follicle is a small conical, vascular eminence or papilla, similar in every respect to those found upon the surface of the skin; it is continuous with the dermic layer of the follicle, and is supplied with nerve fibrils. The hair follicle consists of two coats—an **outer** or **dermic**, and an **inner** or **epidermic**.




FIG. 899.—Section of skin, showing the epidermis and dermis; a hair in its follicle; the Arrector pili muscle; sebaceous glands.

The **outer** or **dermic coat** is formed mainly of fibrous tissue; it is continuous with the corium, is highly vascular, and supplied by numerous minute nervous filaments. It consists of three layers (Fig. 900). The most internal is a hyaline basement membrane, which is well-marked in the larger hair follicles, but is not very distinct in the follicles of minute hairs; it is limited to the deeper part of the follicle. Outside this is a compact layer of fibres and spindle-shaped cells arranged circularly around the follicle; this layer extends from the bottom of the follicle as high as the entrance of the ducts of the sebaceous glands. Externally is a thick layer of connective tissue, arranged in longitudinal bundles, forming a more open texture and corresponding to the reticular part of the corium; in this are contained the bloodvessels and nerves.

The **inner** or **epidermic coat** is closely adherent to the root of the hair, and consists of two strata named respectively the **outer** and **inner root sheaths**; the former of these corresponds with the stratum mucosum of the epidermis, and resembles it in the rounded form and soft character of its cells; at the bottom of the hair follicle these cells become continuous with those of the root of the hair. The inner root sheath consists of (1) a delicate cuticle next the hair, composed of a single layer of imbricated scales with atrophied nuclei; (2) one or two layers of horny, flattened, nucleated cells, known as **Huxley's layer**; and (3) a single layer of cubical cells with clear flattened nuclei, called **Henle's layer**.

The hair bulb is moulded over the papilla and composed of polyhedral epithelial cells, which as they pass upward into the root of the hair become elongated and spindle-shaped, except some in the centre which remain polyhedral. Some of these latter cells contain pigment granules which give rise to the color of the hair. It occasionally happens that these pigment granules completely fill the cells in the centre of the bulb; this gives rise to the dark tract of pigment often found, of greater or less length, in the axis of the hair.

The **shaft of the hair** (*scapus pili*) consists, from within outward, of three parts, the medulla, the cortex, and the cuticle. The **medulla** is usually wanting in the fine hairs covering the surface of the body, and commonly in those of the head. It is more opaque and deeper colored than the cortex when viewed by transmitted light; but when viewed by reflected light it is white. It is composed of rows of polyhedral cells, containing granules of eleidin and frequently air spaces. The **cortex** constitutes the chief part of the shaft; its cells are elongated and united to form flattened fusiform fibres which contain pigment granules in dark hair, and air in white hair. The **cuticle** consists of a single layer of flat scales which overlap one another from below upward.

Connected with the hair follicles are minute bundles of involuntary muscular fibres, termed the **Arrectores pilorum**. They arise from the superficial layer of the corium, and are inserted into the hair follicle, below the entrance of the duct of the sebaceous gland. They are placed on the side toward which the hair slopes, and by their action diminish the obliquity of the follicle and elevate the hair (Fig. 899).<sup>1</sup> The sebaceous gland is situated in the angle which the Arrector muscle forms with the superficial portion of the hair follicle, and contraction of the muscle thus tends to squeeze the sebaceous secretion out from the duct of the gland.

The **Sebaceous Glands** (*glandulae sebaceae*) are small, sacculated, glandular




FIG. 900.—Transverse section of hair follicle.

<sup>1</sup> Professor Arthur Thomson of Oxford suggests that the contraction of these muscles on follicles which contain weak, flat hairs will tend to produce a permanent curve in the follicle, and this curve will be impressed on the hair which is moulded within it, so that the hair, on emerging through the skin, will be curled. Curved hair follicles are characteristic of the scalp of the Bushman.

organs, lodged in the substance of the corium. They are found in most parts of the skin, but are especially abundant in the scalp and face; they are also very numerous around the apertures of the anus, nose, mouth, and external ear, but are wanting in the palms of the hands and soles of the feet. Each gland consists of a single duct, more or less capacious, which emerges from a cluster of oval or flask-shaped alveoli which vary from two to five in number, but in some instances there may be as many as twenty. Each alveolus is composed of a transparent basement membrane, enclosing a number of epithelial cells. The outer or marginal cells are small and polyhedral, and are continuous with the cells lining the duct. The remainder of the alveolus is filled with larger cells, containing fat, except in the centre, where the cells have become broken up, leaving a cavity filled with their debris and a mass of fatty matter, which constitutes the *sebum cutaneum*. The ducts open most frequently into the hair follicles, but occasionally upon the general surface, as in the labia minora and the free margin of the lips. On the nose and face the glands are of large size, distinctly lobulated, and often become much enlarged from the accumulation of pent-up secretion. The tarsal glands of the eyelids are elongated sebaceous glands with numerous lateral diverticula.

The **Sudoriferous** or **Sweat Glands** (*glandulae sudoriferae*) are found in almost every part of the skin, and are situated in small pits on the under surface of the corium, or, more frequently, in the subcutaneous areolar tissue, surrounded by a quantity of adipose tissue. Each consists of a single tube, the deep part of which is rolled into an oval or spherical ball, named the **body** of the gland, while the super-

ficial part, or **duct**, traverses the corium and cuticle and opens on the surface of the skin by a funnel-shaped aperture. In the superficial layers of the corium the duct is straight, but in the deeper layers it is convoluted or even twisted; where the epidermis is thick, as in the palms of the hands and soles of the feet, the part of the duct which passes through it is spirally coiled. The size of the glands varies. They are especially large in those regions where the amount of perspiration is great, as in the axillæ, where they form a thin, mammillated layer of a reddish color, which corresponds exactly to the situation of the hair in this region; they are large also in the groin. Their number varies.

They are very plentiful on the palms




FIG. 901.—Body of a sudoriferous-gland cut in various directions. *a*. Longitudinal section of the proximal part of the coiled tube. *b*. Transverse section of the same. *c*. Longitudinal section of the distal part of the coiled tube. *d*. Transverse section of the same. (Klein and Noble Smith.)

of the hands, and on the soles of the feet, where the orifices of the ducts are exceedingly regular, and open on the curved ridges; they are least numerous in the neck and back. The tube, both in the body of the gland and in the duct, consists of two layers—an outer, of fine **areolar tissue**, and an inner of **epithelium** (Fig. 901). The outer layer is thin and is continuous with the superficial stratum of the corium. In the body of the gland the epithelium consists of a single layer of cubical cells, between the deep ends of which and the basement membrane is a layer of longitudinally or obliquely arranged non-striped muscular fibres. The ducts are destitute of muscular fibres and are composed of a basement membrane lined by two or three layers of polyhedral cells; the lumen of the duct is coated by a thin cuticle. When the cuticle is carefully removed from the surface of the corium, the ducts may be drawn out in the form of short, thread-like processes on its under surface. The ceruminous glands of the external acoustic meatus, and the ciliary glands at the margins of the eyelids, are modified sudoriferous glands.

# SPLANCHNOLOGY.

**U**NDER this heading are included the respiratory, digestive, and urogenital organs, and the ductless glands.

## THE RESPIRATORY APPARATUS (APPARATUS RESPIRATORIUS; RESPIRATORY SYSTEM).

The respiratory apparatus consists of the larynx, trachea, bronchi, lungs, and pleura.

### THE LARYNX.

The larynx or organ of voice is placed at the upper part of the air passage. It is situated between the trachea and the root of the tongue, at the upper and forepart of the neck, where it presents a considerable projection in the middle line. It forms the lower part of the anterior wall of the pharynx, and is covered behind by the mucous lining of that cavity; on either side of it lie the great vessels of the neck. Its vertical extent corresponds to the fourth, fifth, and sixth cervical vertebræ, but it is placed somewhat higher in the female and also during childhood. Symington found that in infants between six and twelve months of age the tip of the epiglottis was a little above the level of the fibrocartilage between the odontoid process and body of the axis, and that between infancy and adult life the larynx descends for a distance equal to two vertebral bodies and two intervertebral fibrocartilages. According to Sappey the average measurements of the adult larynx are as follows:

	In males.	In females.
Length . . . . .	44 mm.	36 mm.
Transverse diameter . . . . .	43 "	41 "
Antero-posterior diameter . . . . .	36 "	26 "
Circumference . . . . .	136 "	112 "

Until puberty the larynx of the male differs little in size from that of the female. In the female its increase after puberty is only slight; in the male it undergoes considerable increase; all the cartilages are enlarged and the thyroid cartilage becomes prominent in the middle line of the neck, while the length of the rima glottidis is nearly doubled.

The larynx is broad above, where it presents the form of a triangular box flattened behind and at the sides, and bounded in front by a prominent vertical ridge. Below, it is narrow and cylindrical. It is composed of cartilages, which are connected together by ligaments and moved by numerous muscles. It is lined by mucous membrane continuous above with that of the pharynx and below with that of the trachea.

The **Cartilages of the Larynx** (*cartilagines laryngis*) (Fig. 902) are nine in number, three single and three paired, as follows:

Thyroid.	Two Corniculate.
Cricoid.	Two Cuneiform.
Two Arytenoid.	Epiglottis.

and medialward. They are situated in the posterior parts of the aryepiglottic folds of mucous membrane, and are sometimes fused with the arytenoid cartilages.

The **Cuneiform Cartilages** (*cartilaginee cuneiformes*; *cartilages of Wrisberg*) are two small, elongated pieces of yellow elastic cartilage, placed one on either side, in the aryepiglottic fold, where they give rise to small whitish elevations on the surface of the mucous membrane, just in front of the arytenoid cartilages.

The **Epiglottis** (*cartilago epiglottica*) is a thin lamella of fibrocartilage of a yellowish color, shaped like a leaf, and projecting obliquely upward behind the root of the tongue, in front of the entrance to the larynx. The free extremity is broad and rounded; the attached part or stem is long, narrow, and connected by the **thyroepiglottic ligament** to the angle formed by the two laminae of the thyroid cartilage, a short distance below the superior thyroid notch. The lower part of its anterior surface is connected to the upper border of the body of the hyoid bone by an elastic ligamentous band, the **hyoepiglottic ligament**.

The **anterior or lingual surface** is curved forward, and covered on its upper, free part by mucous membrane which is reflected on to the sides and root of the tongue, forming a median and two lateral **glossoepiglottic folds**; the lateral folds are partly attached to the wall of the pharynx. The depressions between the epiglottis and the root of the tongue, on either side of the median fold, are named the **valleculae**. The lower part of the anterior surface lies behind the hyoid bone, the hyothyroid membrane, and upper part of the thyroid cartilage, but is separated from these structures by a mass of fatty tissue.

The **posterior or laryngeal surface** is smooth, concave from side to side, concavo-convex from above downward; its lower part projects backward as an elevation, the **tubercle** or **cushion**. When the mucous membrane is removed, the surface of the cartilage is seen to be indented by a number of small pits, in which mucous glands are lodged. To its sides the aryepiglottic folds are attached.

**Structure.**—The corniculate and cuneiform cartilages, the epiglottis, and the apices of the arytenoids at first consist of hyaline cartilage, but later elastic fibres are deposited in the matrix, converting them into yellow fibrocartilage, which shows little tendency to calcification. The thyroid, cricoid, and the greater part of the arytenoids consist of hyaline cartilage, and become more or less ossified as age advances. Ossification commences about the twenty-fifth year in the thyroid cartilage, and somewhat later in the cricoid and arytenoids; by the sixty-fifth year these cartilages may be completely converted into bone.

**Ligaments.**—The ligaments of the larynx (Figs. 903, 904) are **extrinsic**, *i. e.*, those connecting the thyroid cartilage and epiglottis with the hyoid bone, and the cricoid cartilage with the trachea; and **intrinsic**, those which connect the several cartilages of the larynx to each other.

**Extrinsic Ligaments.**—The ligaments connecting the thyroid cartilage with the hyoid bone are the hyothyroid membrane, and a middle and two lateral hyothyroid ligaments.

The **Hyothyroid Membrane** (*membrana hyothyreoidea*; *thyrohyoid membrane*) is a broad, fibro-elastic layer, attached below to the upper border of the thyroid cartilage and to the front of its superior cornu, and above to the upper margin of the posterior surface of the body and greater cornua of the hyoid bone, thus passing behind the posterior surface of the body of the hyoid, and being separated from it by a mucous bursa, which facilitates the upward movement of the larynx during deglutition. Its middle thicker part is termed the **middle hyothyroid ligament** (*ligamentum hyothyroideum medium*; *middle thyrohyoid ligament*), its lateral thinner portions are pierced by the superior laryngeal vessels and the internal branch of the superior laryngeal nerve. Its anterior surface is in relation with the Thyrohyoideus, Sternohyoideus, and Omohyoideus, and with the body of the hyoid bone.



The **Lateral Hyothyroid Ligament** (*ligamentum hyothyreoideum laterale*; *lateral thyrohyoid ligament*) is a round elastic cord, which forms the posterior border of the hyothyroid membrane and passes between the tip of the superior cornu of the thyroid cartilage and the extremity of the greater cornu of the hyoid bone. A small cartilaginous nodule (*cartilago triticea*), sometimes bony, is frequently found in it.

The **Epiglottis** is connected with the hyoid bone by an elastic band, the **hyoepiglottic ligament** (*ligamentum hyoepiglotticum*), which extends from the anterior surface of the epiglottis to the upper border of the body of the hyoid bone. The glossoepiglottic folds of mucous membrane (page 1082) may also be considered as extrinsic ligaments of the epiglottis.




FIG. 903.—The ligaments of the larynx. Antero-lateral view.

The **Cricotracheal Ligament** (*ligamentum cricotracheale*) connects the cricoid cartilage with the first ring of the trachea. It resembles the fibrous membrane which connects the cartilaginous rings of the trachea to each other.

**Intrinsic Ligaments.**—Beneath the mucous membrane of the larynx is a broad sheet of fibrous tissue containing many elastic fibres, and termed the **elastic membrane of the larynx**. It is subdivided on either side by the interval between the ventricular and vocal ligaments, the upper portion extends between the arytenoid cartilage and the epiglottis and is often poorly defined; the lower part is a well-marked membrane forming, with its fellow of the opposite side, the conus elasticus which connects the thyroid, cricoid, and arytenoid cartilages to one another. In addition the joints between the individual cartilages are provided with ligaments.

The **Conus Elasticus** (*cricothyroid membrane*) is composed mainly of yellow elastic tissue. It consists of an anterior and two lateral portions. The **anterior part** or **middle cricothyroid ligament** (*ligamentum cricothyreoideum medium*; *central part* of

*thyroepiglottic membrane*) is thick and strong, narrow above and broad below. It connects together the front parts of the contiguous margins of the thyroid and cricoid cartilages. It is overlapped on either side by the Cricothyroideus, but between these is subcutaneous; it is crossed horizontally by a small anastomotic arterial arch, formed by the junction of the two cricothyroid arteries, branches of which pierce it. The lateral portions are thinner and lie close under the mucous membrane of the larynx; they extend from the superior border of the cricoid cartilage to the inferior margin of the vocal ligaments, with which they are continuous. These ligaments may therefore be regarded as the free borders of the lateral portions of the conus elasticus, and extend from the vocal processes of the arytenoid cartilages to the angle of the thyroid cartilage about midway between its upper and lower borders. The lateral portions are lined medially by mucous membrane, and covered by the Cricoarytaenoideus lateralis and Thyreoarytaenoideus.




FIG. 904.—Ligaments of the larynx. Posterior view.

An **articular capsule**, strengthened posteriorly by a well-marked fibrous band, encloses the articulation of the inferior cornu of the thyroid with the cricoid cartilage on either side.

Each arytenoid cartilage is connected to the cricoid by a capsule and a posterior cricoarytenoid ligament. The **capsule** (*capsula articularis cricoarytenoidea*) is thin and loose, and is attached to the margins of the articular surfaces. The **posterior cricoarytenoid ligament** (*ligamentum cricoarytenoideum posterius*) extends from the cricoid to the medial and back part of the base of the arytenoid.

The **thyroepiglottic ligament** (*ligamentum thyroepiglotticum*) is a long, slender, elastic cord which connects the stem of the epiglottis with the angle of the thyroid

cartilage, immediately beneath the superior thyroid notch, above the attachment of the ventricular ligaments.

**Movements.**—The articulation between the inferior cornu of the thyroid cartilage and the cricoid cartilage on either side is a diarthrodial one, and permits of rotatory and gliding movements. The rotatory movement is one in which the cricoid cartilage rotates upon the inferior cornua of the thyroid cartilage around an axis passing transversely through both joints. The gliding movement consists in a limited shifting of the cricoid on the thyroid in different directions.

The articulation between the arytenoid cartilages and the cricoid is also a diarthrodial one, and permits of two varieties of movement: one is a rotation of the arytenoid on a vertical axis, whereby the vocal process is moved lateralward or medialward, and the rima glottidis increased or diminished; the other is a gliding movement, and allows the arytenoid cartilages to approach or recede from each other; from the direction and slope of the articular surfaces lateral gliding is accompanied by a forward and downward movement. The two movements of gliding and rotation are associated, the medial gliding being connected with medialward rotation, and the lateral gliding with lateralward rotation. The posterior cricoarytenoid ligaments limit the forward movement of the arytenoid cartilages on the cricoid.

**Interior of the Larynx** (Figs. 905, 907).—The **cavity of the larynx** (*cavum laryngis*) extends from the laryngeal entrance to the lower border of the cricoid cartilage where it is continuous with that of the trachea. It is divided into two parts by the projection of the vocal folds, between which is a narrow triangular fissure or chink, the **rima glottidis**. The portion of the cavity of the larynx above the vocal folds is called the **vestibule**; it is wide and triangular in shape, its base or anterior wall presenting, however, about its centre the backward projection of the tubercle of the epiglottis. It contains the ventricular folds, and between these and the vocal folds are the **ventricles of the larynx**. The portion below the vocal folds is at first of an elliptical form, but lower down it widens out, assumes a circular form, and is continuous with the tube of the trachea.

The **entrance of the larynx** (Fig. 906) is a triangular opening, wide in front, narrow behind, and sloping obliquely downward and backward. It is bounded, in front, by the epiglottis; behind, by the apices of the arytenoid cartilages, the corniculate cartilages, and the interarytenoid notch; and on either side, by a fold of mucous membrane, enclosing ligamentous and muscular fibres, stretched between the side of the epiglottis and the apex of the arytenoid cartilage; this is the **aryepiglottic fold**, on the posterior part of the margin of which the cuneiform cartilage forms a more or less distinct whitish prominence, the **cuneiform tubercle**.

The **Ventricular Folds** (*plicae ventriculares*; *superior or false vocal cords*) are two thick folds of mucous membrane, each enclosing a narrow band of fibrous tissue, the **ventricular ligament** which is attached in front to the angle of the thyroid cartilage immediately below the attachment of the epiglottis, and behind to the antero-




FIG. 905.—Sagittal section of the larynx and upper part of the trachea.

*cricothyroid membrane*) is thick and strong, narrow above and broad below. It connects together the front parts of the contiguous margins of the thyroid and cricoid cartilages. It is overlapped on either side by the Cricothyreoides, but between these is subcutaneous; it is crossed horizontally by a small anastomotic arterial arch, formed by the junction of the two cricothyroid arteries, branches of which pierce it. The **lateral portions** are thinner and lie close under the mucous membrane of the larynx; they extend from the superior border of the cricoid cartilage to the inferior margin of the vocal ligaments, with which they are continuous. These ligaments may therefore be regarded as the free borders of the lateral portions of the conus elasticus, and extend from the vocal processes of the arytenoid cartilages to the angle of the thyroid cartilage about midway between its upper and lower borders. The lateral portions are lined medially by mucous membrane, and covered by the Cricoarytaenoideus lateralis and Thyreoarytaenoideus.




FIG. 904.—Ligaments of the larynx. Posterior view.

An **articular capsule**, strengthened posteriorly by a well-marked fibrous band, encloses the articulation of the inferior cornu of the thyroid with the cricoid cartilage on either side.

Each arytenoid cartilage is connected to the cricoid by a capsule and a posterior cricoarytenoid ligament. The **capsule** (*capsula articularis cricoarytenoidea*) is thin and loose, and is attached to the margins of the articular surfaces. The **posterior cricoarytenoid ligament** (*ligamentum cricoarytenoideum posterius*) extends from the cricoid to the medial and back part of the base of the arytenoid.

The **thyroepiglottic ligament** (*ligamentum thyroepiglotticum*) is a long, slender, elastic cord which connects the stem of the epiglottis with the angle of the thyroid



cartilage, immediately beneath the superior thyroid notch, above the attachment of the ventricular ligaments.

**Movements.**—The articulation between the inferior cornu of the thyroid cartilage and the cricoid cartilage on either side is a diarthrodial one, and permits of rotatory and gliding movements. The rotatory movement is one in which the cricoid cartilage rotates upon the inferior cornua of the thyroid cartilage around an axis passing transversely through both joints. The gliding movement consists in a limited shifting of the cricoid on the thyroid in different directions.

The articulation between the arytenoid cartilages and the cricoid is also a diarthrodial one, and permits of two varieties of movement: one is a rotation of the arytenoid on a vertical axis, whereby the vocal process is moved lateralward or medialward, and the rima glottidis increased or diminished; the other is a gliding movement, and allows the arytenoid cartilages to approach or recede from each other; from the direction and slope of the articular surfaces lateral gliding is accompanied by a forward and downward movement. The two movements of gliding and rotation are associated, the medial gliding being connected with medialward rotation, and the lateral gliding with lateralward rotation. The posterior cricoarytenoid ligaments limit the forward movement of the arytenoid cartilages on the cricoid.

**Interior of the Larynx** (Figs. 905, 907).—The **cavity of the larynx** (*cavum laryngis*) extends from the laryngeal entrance to the lower border of the cricoid cartilage where it is continuous with that of the trachea. It is divided into two parts by the projection of the vocal folds, between which is a narrow triangular fissure or chink, the **rima glottidis**. The portion of the cavity of the larynx above the vocal folds is called the **vestibule**; it is wide and triangular in shape, its base or anterior wall presenting, however, about its centre the backward projection of the tubercle of the epiglottis. It contains the ventricular folds, and between these and the vocal folds are the **ventricles of the larynx**. The portion below the vocal folds is at first of an elliptical form, but lower down it widens out, assumes a circular form, and is continuous with the tube of the trachea.

The **entrance of the larynx** (Fig. 906) is a triangular opening, wide in front, narrow behind, and sloping obliquely downward and backward. It is bounded, in front, by the epiglottis; behind, by the apices of the arytenoid cartilages, the corniculate

cartilages, and the interarytenoid notch; and on either side, by a fold of mucous membrane, enclosing ligamentous and muscular fibres, stretched between the side of the epiglottis and the apex of the arytenoid cartilage; this is the **aryepiglottic fold**, on the posterior part of the margin of which the cuneiform cartilage forms a more or less distinct whitish prominence, the **cuneiform tubercle**.

The **Ventricular Folds** (*plicae ventriculares*; *superior or false vocal cords*) are two thick folds of mucous membrane, each enclosing a narrow band of fibrous tissue, the **ventricular ligament** which is attached in front to the angle of the thyroid cartilage immediately below the attachment of the epiglottis, and behind to the antero-




FIG. 905.—Sagittal section of the larynx and upper part of the trachea.



lateral surface of the arytenoid cartilage, a short distance above the vocal process. The lower border of this ligament, enclosed in mucous membrane, forms a free crescentic margin, which constitutes the upper boundary of the ventricle of the larynx.




FIG. 906.—The entrance to the larynx, viewed from behind.

The **Vocal Folds** (*plicae vocales*; *inferior or true vocal cords*) are concerned in the production of sound, and enclose two strong bands, named the **vocal ligaments** (*ligamenta vocales*; *inferior thyroarytenoid*). Each ligament consists of a band of yellow elastic tissue, attached in front to the angle of the thyroid cartilage, and behind to the vocal process of the arytenoid. Its lower border is continuous with the thin lateral part of the conus elasticus. Its upper border forms the lower boundary of the ventricle of the larynx. Laterally, the Vocalis muscle lies parallel with it. It is covered medially by mucous membrane, which is extremely thin and closely adherent to its surface.

The **Ventricle of the Larynx** (*ventriculus laryngis* [Morgagni]; *laryngeal sinus*) is a fusiform fossa, situated between the ventricular and vocal folds on either side, and extending nearly their entire length. The fossa is bounded, *above*, by the free crescentic edge of the ventricular fold; *below*, by the straight margin of the vocal fold; *laterally*, by the mucous membrane covering the corresponding Thyroarytaenoides. The anterior part of the ventricle leads up by a narrow opening into a cecal pouch of mucous membrane of variable size called the **appendix**.

The **appendix of the laryngeal ventricle** (*appendix ventriculi laryngis*; *laryngeal sacculle*) is a membranous sac, placed between the ventricular fold and the inner surface of the thyroid cartilage, occasionally extending as far as its upper border or even higher; it is conical in form, and curved slightly backward. On the surface

of its mucous membrane are the openings of sixty or seventy mucous glands, which are lodged in the submucous areolar tissue. This sac is enclosed in a fibrous capsule, continuous below with the ventricular ligament. Its medial surface is covered by a few delicate muscular fasciculi, which arise from the apex of the arytenoid cartilage and become lost in the aryepiglottic fold of mucous membrane; laterally it is separated from the thyroid cartilage by the Thyreoepiglotticus. These muscles compress the sac, and express the secretion it contains upon the vocal folds to lubricate their surfaces.

The **Rima Glottidis** (Fig. 908) is the elongated fissure or chink between the vocal folds in front, and the bases and vocal processes of the arytenoid cartilages behind. It is therefore subdivided into a larger anterior intramembranous part (*glottis vocalis*), which measures about three-fifths of the length of the entire aperture, and a posterior intercartilaginous part (*glottis respiratoria*). Posteriorly it is limited by the mucous membrane passing between the arytenoid cartilages. The rima glottidis is the narrowest part of the cavity of the larynx, and its level corresponds with the bases of the arytenoid cartilages. Its length, in the male, is about 23 mm.; in the female from 17 to 18 mm.

The width and shape of the rima glottidis vary with the movements of the vocal folds and arytenoid cartilages during respiration and phonation. In the condition of rest, *i. e.*, when these structures are uninfluenced by muscular action, as in




FIG. 907.—Coronal section of larynx and upper part of trachea.




FIG. 908.—Laryngoscopic view of interior of larynx.

quiet respiration, the intramembranous part is triangular, with its apex in front and its base behind—the latter being represented by a line, about 8 mm. long, connecting the anterior ends of the vocal processes, while the medial surfaces of

the arytenoids are parallel to each other, and hence the intercartilaginous part is rectangular. During extreme adduction of the vocal folds, as in the emission of a high note, the intramembranous part is reduced to a linear slit by the apposition of the vocal folds, while the intercartilaginous part is triangular, its apex corresponding to the anterior ends of the vocal processes of the arytenoids, which are approximated by the medial rotation of the cartilages. Conversely in extreme abduction of the vocal folds, as in forced inspiration, the arytenoids and their vocal processes are rotated lateralward, and the intercartilaginous part is triangular in shape but with its apex directed backward. In this condition the entire glottis is somewhat lozenge-shaped, the sides of the intramembranous part diverging from before backward, those of the intercartilaginous part diverging from behind forward—the widest part of the aperture corresponding with the attachments of the vocal folds to the vocal processes.

**Muscles.**—The muscles of the larynx are *extrinsic*, passing between the larynx and parts around—these have been described in the section on Myology; and *intrinsic*, confined entirely to the larynx.

The intrinsic muscles are:

Cricothyroideus.

Cricoarytaenoideus posterior.

Cricoarytaenoideus lateralis.

Arytaenoideus.

Thyroarytaenoideus.

The **Cricothyroideus** (*Cricothyroid*) (Fig. 909), triangular in form, *arises* from the front and lateral part of the cricoid cartilage; its fibres diverge, and are arranged in two groups. The lower fibres constitute a **pars obliqua** and slant backward and lateralward to the anterior border of the inferior cornu; the anterior fibres, forming a **pars recta**, run upward, backward, and lateralward to the posterior part of the lower border of the lamina of the thyroid cartilage.




FIG. 909.—Side view of the larynx, showing muscular attachments.

The medial borders of the two muscles are separated by a triangular interval, occupied by the middle cricothyroid ligament.

The **Cricoarytaenoideus posterior** (*posterior cricoarytenoid*) (Fig. 910) *arises* from the broad depression on the corresponding half of the posterior surface of the lamina of the cricoid cartilage; its fibres run upward and lateralward, and converge to be *inserted* into the back of the muscular process of the arytenoid cartilage. The uppermost fibres are nearly horizontal, the middle oblique, and the lowest almost vertical.

The **Cricoarytaenoideus lateralis** (*lateral cricoarytenoid*) (Fig. 911) is smaller than the preceding, and of an oblong form. It *arises* from the upper border of the arch of the cricoid cartilage, and, passing obliquely up-

ward and backward, is inserted into the front of the muscular process of the arytenoid cartilage.

The **Arytaenoideus** (Fig. 910) is a single muscle, filling up the posterior concave surfaces of the arytenoid cartilages. It *arises* from the posterior surface and lateral border of one arytenoid cartilage, and is inserted into the corresponding parts of the opposite cartilage. It consists of oblique and transverse parts. The **Arytae-**



**noideus obliquus**, the more superficial, forms two fasciculi, which pass from the base of one cartilage to the apex of the opposite one, and therefore cross each other




FIG. 910.—Muscles of larynx. Posterior view.

FIG. 911.—Muscles of larynx. Side view. Right lamina of thyroid cartilage removed.

like the limbs of the letter X; a few fibres are continued around the lateral margin of the cartilage, and are prolonged into the aryepiglottic fold; they are sometimes described as a separate muscle, the **Aryepiglotticus**. The **Arytaenoides transversus** crosses transversely between the two cartilages.

The **Thyroarytaenoides** (*Thyroarytenoid*) (Figs. 911, 912) is a broad, thin, muscle which lies parallel with and lateral to the vocal fold, and supports the wall of the ventricle and its appendix. It arises in front from the lower half of the angle of the thyroid cartilage, and from the middle-cricothyroid ligament. Its fibres pass backward and lateralward, to be inserted into the base and anterior surface of the arytenoid cartilage. The lower and deeper fibres of the muscle can be differentiated as a triangular band which is inserted into the vocal process of the arytenoid cartilage, and into the adjacent portion of its anterior surface; it is termed the **Vocalis**, and lies parallel with the vocal ligament, to which it is adherent.




FIG. 912.—Muscles of the larynx, seen from above. (Enlarged.)

A considerable number of the fibres of the *Thyreothyrotaenoideus* are prolonged into the aryepiglottic fold, where some of them become lost, while others are continued to the margin of the epiglottis. They have received a distinctive name, *Thyreopiglotticus*, and are sometimes described as a separate muscle.

**Actions.**—In considering the actions of the muscles of the larynx, they may be conveniently divided into two groups, viz.: 1. Those which open and close the glottis. 2. Those which regulate the degree of tension of the vocal folds.

1. The muscles which open the glottis are the *Cricothyrotaenoidei posteriores*; and those which close it are the *Cricothyrotaenoidei laterales* and the *Arytaenoideus*. 2. The muscles which regulate the tension of the vocal folds are the *Cricothyrotaenoidei*, which elongate and render them tense; and the *Thyreothyrotaenoidei*, which relax and shorten them.

The *Cricothyrotaenoidei posteriores* separate the vocal folds, and, consequently, open the glottis, by rotating the arytenoid cartilages outward around a vertical axis passing through the cricoarytenoid joints; so that their vocal processes and the vocal folds attached to them become widely separated.

The *Cricothyrotaenoidei laterales* close the glottis by rotating the arytenoid cartilages inward, so as to approximate their vocal processes.

The *Arytaenoideus* approximates the arytenoid cartilages, and thus closes the opening of the glottis, especially at its back part.

The *Cricothyrotaenoidei* produce tension and elongation of the vocal folds by drawing up the arch of the cricoid cartilage and tilting back the upper border of its lamina; the distance between the vocal processes and the angle of the thyroid is thus increased, and the folds are consequently elongated.

The *Thyreothyrotaenoidei*, consisting of two parts having different attachments and different directions, are rather complicated as regards their action. Their main use is to draw the arytenoid cartilages forward toward the thyroid, and thus shorten and relax the vocal folds. But, owing to the connection of the deeper portion with the vocal fold, this part, if acting separately, is supposed to modify its elasticity and tension, while the lateral portion rotates the arytenoid cartilage inward, and thus narrows the rima glottidis by bringing the two vocal folds together.

The manner in which the entrance of the larynx is closed during deglutition is referred to on page 1114.

**Mucous Membrane.**—The mucous membrane of the larynx is continuous above with that lining the mouth and pharynx, and is prolonged through the trachea and bronchi into the lungs. It lines the posterior surface and the upper part of the anterior surface of the epiglottis, to which it is closely adherent, and forms the aryepiglottic folds which bound the entrance of the larynx. It lines the whole of the cavity of the larynx; forms, by its reduplication, the chief part of the ventricular fold, and, from the ventricle, is continued into the ventricular appendix. It is then reflected over the vocal ligament, where it is thin, and very intimately adherent; covers the inner surface of the conus elasticus and cricoid cartilage; and is ultimately continuous with the lining membrane of the trachea. The anterior surface and the upper half of the posterior surface of the epiglottis, the upper part of the aryepiglottic folds and the vocal folds are covered by stratified squamous epithelium; all the rest of the laryngeal mucous membrane is covered by columnar ciliated cells, but patches of stratified squamous epithelium are found in the mucous membrane above the glottis.

**Glands.**—The mucous membrane of the larynx is furnished with numerous mucous secreting glands, the orifices of which are found in nearly every part; they are very plentiful upon the epiglottis, being lodged in little pits in its substance; they are also found in large numbers along the margin of the aryepiglottic fold, in front of the arytenoid cartilages, where they are termed the *arytenoid glands*. They exist also in large numbers in the ventricular appendages. None are found on the free edges of the vocal folds.

**Vessels and Nerves.**—The chief arteries of the larynx are the laryngeal branches derived from the superior and inferior thyroid. The veins accompany the arteries; those accompanying the superior laryngeal artery join the superior thyroid vein which opens into the internal jugular vein; while those accompanying the inferior laryngeal artery join the inferior thyroid vein which opens into the innominate vein. The lymphatic vessels consist of two sets, superior and inferior. The former accompany the superior laryngeal artery and pierce the hyothyroid membrane, to end in the glands situated near the bifurcation of the common carotid artery. Of the latter, some pass through the middle cricothyroid ligament and open into a gland lying in front of that ligament or in front of the upper part of the trachea, while others pass to the deep cervical glands and to the glands accompanying the inferior thyroid artery. The nerves are derived from the internal and external branches of the superior laryngeal nerve, from the recurrent nerve, and from the sympathetic. The internal laryngeal branch is almost entirely sensory, but some motor filaments are said to be carried by it to the *Arytaenoideus*. It enters the larynx by piercing the posterior part of the hyothyroid membrane above the superior



laryngeal vessels, and divides into a branch which is distributed to both surfaces of the epiglottis, a second to the aryepiglottic fold, and a third, the largest, which supplies the mucous membrane over the back of the larynx and communicates with the recurrent nerve. The external laryngeal branch supplies the Cricothyroideus. The recurrent nerve passes upward beneath the lower border of the Constrictor pharyngis inferior immediately behind the cricothyroid joint. It supplies all the muscles of the larynx except the Cricothyroideus, and perhaps a part of the Arytaenoideus. The sensory branches of the laryngeal nerves form subepithelial plexuses, from which fibres pass to end between the cells covering the mucous membrane.

Over the posterior surface of the epiglottis, in the aryepiglottic folds, and less regularly in some other parts, taste-buds, similar to those in the tongue, are found.

### THE TRACHEA AND BRONCHI (Fig. 913).

The **trachea** or **windpipe** is a cartilaginous and membranous tube, extending from the lower part of the larynx, on a level with the sixth cervical vertebra, to the




FIG. 913.—Front view of cartilages of larynx, trachea, and bronchi.

upper border of the fifth thoracic vertebra, where it divides into the two bronchi, one for each lung. The trachea is nearly but not quite cylindrical, being flattened posteriorly; it measures about 11 cm. in length; its diameter, from side to side,

is from 2 to 2.5 cm., being always greater in the male than in the female. In the child the trachea is smaller, more deeply placed, and more movable than in the adult.

**Relations.**—The *anterior surface* of the trachea is convex, and covered, in the **neck**, from above downward, by the isthmus of the thyroid gland, the inferior thyroid veins, the *arteria thyroidea ima* (when that vessel exists), the *Sternothyroideus* and *Sternohyoideus* muscles, the cervical fascia, and, more superficially, by the anastomosing branches between the anterior jugular veins; in the **thorax**, it is covered from before backward by the manubrium sterni, the remains of the thymus, the left innominate vein, the aortic arch, the innominate and left common carotid arteries, and the deep cardiac plexus. Posteriorly it is in contact with the oesophagus. *Laterally, in the neck*, it is in relation with the common carotid arteries, the right and left lobes of the thyroid gland, the inferior thyroid arteries, and the recurrent nerves; in the **thorax**, it lies in the superior mediastinal cavity, and is in relation on the right side with the pleura and right vagus, and near the root of the neck with the innominate artery; on its left side are the left recurrent nerve, the aortic arch, and the left common carotid and subclavian arteries.

The **right bronchus** (*bronchus dexter*), wider, shorter, and more vertical in direction than the left, is about 2.5 cm. long, and enters the right lung nearly opposite the fifth thoracic vertebra. The azygos vein arches over it from behind; and the right pulmonary artery lies at first below and then in front of it. About 2 cm. from its commencement it gives off a branch to the upper lobe of the right lung. This is termed the **eparterial branch** of the bronchus, because it arises above the right pulmonary artery. The bronchus now passes below the artery, and is known as the **hyparterial branch**; it divides into two branches for the middle and lower lobes.

The **left bronchus** (*bronchus sinister*) is smaller in calibre but longer than the right, being nearly 5 cm. long. It enters the root of the left lung opposite the sixth thoracic vertebra. It passes beneath the aortic arch, crosses in front of the oesophagus, the thoracic duct, and the descending aorta, and has the left pulmonary artery lying at first above, and then in front of it. The left bronchus has no eparterial branch, and therefore it has been supposed by some that there is no upper lobe to the left lung, but that the so-called upper lobe corresponds to the middle lobe of the right lung.

The further subdivisions of the bronchi will be considered with the anatomy of the lung.

If a transverse section be made across the trachea a short distance above its point of bifurcation, and a bird's-eye view taken of its interior (Fig. 914), the septum placed at the bottom of the trachea and separating the two bronchi will be seen




FIG. 914.—Transverse section of the trachea, just above its bifurcation, with a bird's-eye view of the interior.

to occupy the left of the median line, and the right bronchus appears to be a more direct continuation of the trachea than the left, so that any solid body dropping into the trachea would naturally be directed toward the right bronchus. This tendency is aided by the larger diameter of the right tube as compared with its fellow. This fact serves to explain why a foreign body in the trachea more frequently falls into the right bronchus.<sup>1</sup>

**Structure** (Fig. 915).—The trachea and extrapulmonary bronchi are composed of imperfect rings of hyaline cartilage, fibrous tissue, muscular fibres, mucous membrane, and glands.

The **cartilages** of the trachea vary from sixteen to twenty in number: each forms an imperfect ring, which occupies the anterior two-thirds or so of the circumference of the trachea, being deficient behind, where the tube is completed by fibrous tissue and unstriped muscular fibres. The cartilages are placed horizontally above each other, separated by narrow intervals. They measure about 4 mm. in depth and 1 mm. in thickness. Their outer surfaces are flattened in a vertical direction, but the internal are convex, the cartilages being thicker in the middle than

<sup>1</sup> Reigel asserts that the entry of a foreign body into the *left* bronchus is by no means so infrequent as is generally supposed. See also *Med.-Chi. Trans.*, lxxi, 121.

at the margins. Two or more of the cartilages often unite, partially or completely, and they are sometimes bifurcated at their extremities. They are highly elastic, but may become calcified in advanced life. In the right bronchus the cartilages vary in number from six to eight; in the left, from nine to twelve. They are shorter and narrower than those of the trachea, but have the same shape and arrangement. The peculiar tracheal cartilages are the first and the last (Fig. 913).

The *first cartilage* is broader than the rest, and often divided at one end; it is connected by the cricotracheal ligament with the lower border of the cricoid cartilage, with which, or with the succeeding cartilage, it is sometimes blended.

The *last cartilage* is thick and broad in the middle, in consequence of its lower border being prolonged into a triangular hook-shaped process, which curves downward and backward between the two bronchi. It ends on each side in an imperfect ring, which encloses the commencement of the bronchus. The cartilage above the last is somewhat broader than the others at its centre.

**The Fibrous Membrane.**—The cartilages are enclosed in an elastic fibrous membrane, which consists of two layers; one, the thicker, passing over the outer surface of the ring, the other over the inner surface: at the upper and lower margins of the cartilages the two layers blend together to form a single membrane, which connects the rings one with another. They are thus invested by the membrane. In the space behind, between the ends of the rings, the membrane forms a single layer.

The **muscular tissue** consists of two layers of non-striated muscle, longitudinal and transverse. The **longitudinal fibers** are external, and consist of a few scattered bundles. The **transverse fibres** (*Trachealis muscle*) are internal, and form a thin layer which extends transversely between the ends of the cartilages.

**Mucous Membrane.**—The mucous membrane is continuous above with that of the larynx, and below with that of the bronchi. It consists of areolar and lymphoid tissue, and presents a well-marked basement membrane, supporting a stratified epithelium, the surface layer of which is columnar and ciliated, while the deeper layers are composed of oval or rounded cells. Beneath the basement membrane there is a distinct layer of longitudinal elastic fibres with a small amount of intervening areolar tissue. The submucous layer is composed of a loose mesh-work of connective tissue, containing large bloodvessels, nerves, and mucous glands; the ducts of the latter pierce the overlying layers and open on the surface (Fig. 915).

**Vessels and Nerves.**—The trachea is supplied with blood by the inferior thyroid arteries. The **veins** end in the thyroid venous plexus. The **nerves** are derived from the vagus and the recurrent nerves, and from the sympathetic; they are distributed to the *Trachealis* muscles and between the epithelial cells.

**Applied Anatomy.**—*Foreign bodies* often find their way into the air passages. These may consist of large soft substances, as pieces of meat, which may become lodged in the entrance of the larynx, or in the rima glottidis, and cause speedy suffocation unless rapidly got rid of, or unless an opening is made into the air passages below, so as to enable the patient to breathe. Smaller bodies, frequently of a hard nature, such as cherry or plum stones, small pieces of bone, buttons, etc., may find their way through the rima glottidis into the trachea or bronchus, or may become lodged in the ventricle of the larynx. The dangers then depend not so much upon the mechanical obstruction as upon the spasm of the glottis which they excite from reflex irritation. When lodged in the ventricle of the larynx, they may produce very few symptoms, beyond sudden loss of voice or alteration in the voice sounds immediately after the inhalation of the foreign body. When, however, they are situated in the trachea, they are constantly striking against




FIG. 915.—Transverse section of trachea.

the vocal folds during expiratory efforts, and produce attacks of dyspnoea from spasm of the glottis. When lodged in the bronchus, they usually become fixed there, and, occluding the lumen of the tube, cause a loss of the respiratory murmur on the affected side, and may subsequently lead to purulent bronchitis and gangrene of the lung. Foreign bodies in the air passages should always be removed as soon as possible.

Beneath the mucous membrane of the upper part of the air passages there is a considerable amount of submucous tissue, which is liable to become much swollen from effusion in inflammatory affections, constituting the condition known as *œdema of the glottis*. This effusion does not extend below the level of the vocal folds, on account of the fact that the mucous membrane is closely adherent to these structures without the intervention of any submucous tissue. So that, in cases of œdema of the glottis, in which it is necessary to open the air passages to prevent suffocation, the operation of laryngotomy is sufficient. Laryngeal or glottidean œdema may be secondary to some local inflammatory affection, such as acute septic laryngitis, syphilitic laryngeal perichondritis, or to malignant disease. Or the œdema may be passive (non-inflammatory), consequent upon renal or cardiac mischief, angioneurotic œdema; or, in unusually susceptible persons, the administration of potassium iodide.

*Chronic laryngitis* is an inflammation of the mucous glands of the larynx, which occurs in those who speak much in public, and is known as *clergyman's sore throat*. It is due to the dryness induced by the large amount of cold air drawn into the air passages during prolonged speaking, which excites increased activity of the mucous glands to keep the parts moist, and this eventually terminates in inflammation of these structures.

*Ulceration of the larynx* may occur from syphilis, either as a superficial ulceration, or from the softening of a gumma; from tuberculous disease (laryngeal phthisis), or from malignant disease (epithelioma).

The air passages may be opened in three different situations: by a vertical incision through the centre of the thyroid cartilage (*thyrotomy*); through the middle cricothyroid ligament (*laryngotomy*), or in some part of the trachea (*tracheotomy*).

*Thyrotomy* is usually performed for the purpose of removing growths from the vocal folds or for extracting foreign bodies from the ventricle of the larynx. A median incision is made from the upper border of the body of the hyoid bone to the lower border of the cricoid cartilage, and is carried through the subcutaneous tissues and deep fascia between the margins of the Sternohyoidei. An incision is then made in the middle cricothyroid ligament, and one blade of a stout, sharp-pointed pair of scissors is introduced beneath the lower border of the thyroid cartilage, and this structure is divided from below upward. Great care must be taken to cut exactly in the middle line to avoid wounding the vocal folds. If the two halves of the cartilage are now drawn apart, a very good view of the interior of the larynx will be obtained.

*Laryngotomy* is anatomically a simple operation: it can readily be performed, and should be employed in those cases where the air passages require opening in an emergency for the relief of some sudden obstruction to respiration. The middle cricothyroid membrane is very superficial, being covered only in the middle line by the skin, superficial fascia, and the deep fascia. On either side of the middle line it is also covered by the Sternohyoideus and Sternothyreoideus, which diverge from each other at their upper parts, leaving a slight interval between them. On these muscles rest the anterior jugular veins. The only vessel of any importance in connection with this operation is the cricothyroid artery, which crosses the middle cricothyroid ligament, and may be wounded, but rarely gives rise to any trouble. The operation is performed thus: the head being thrown back and steadied by an assistant, the finger is passed over the front of the neck, and the cricothyroid depression felt for. A vertical incision is then made through the skin in the middle line over this spot, and carried down through the fascia until the middle cricothyroid ligament is exposed. A cross-cut is then made through the ligament close to the upper border of the cricoid cartilage, so as to avoid, if possible, the cricothyroid artery, and a laryngotomy tube inserted. It has been recommended, as a more rapid way of performing the operation, to make a transverse instead of a longitudinal cut through the superficial structures, and thus to open at once the air passages. It will be seen, however, that in operating in this way the anterior jugular veins are in danger of being wounded.

*Tracheotomy* may be performed either above or below the isthmus of the thyroid gland, or this structure may be divided and the trachea opened behind it.

From the relations already described, it must be evident that the trachea can be more readily opened above than below the isthmus of the thyroid gland.

Tracheotomy above the isthmus is performed thus: the patient should, if possible, be laid on his back on a table in a good light. A pillow is to be placed under the shoulders and the head thrown back and steadied by an assistant. The surgeon standing on the right side of his patient makes an incision from 4 to 5 cm. long in the median line of the neck from the top of the cricoid cartilage. The incision must be made exactly in the middle line so as to avoid the anterior jugular veins, and after the superficial structures have been divided, the interval between the Sternohyoidei must be found, the raphé divided, and the muscles drawn apart. The lower border of the cricoid cartilage must now be felt for, and the upper part of the trachea exposed

from this point downward in the middle line. Bose has recommended that the layer of fascia in front of the trachea should be divided transversely at the level of the lower border of the cricoid cartilage, and, having been seized with a pair of forceps, pressed downward with the handle of the scalpel. By this means the isthmus of the thyroid gland is depressed and is saved from all danger of being wounded, and the trachea cleanly exposed. The trachea is now trans-fixed with a sharp hook and drawn forward in order to steady it, and is then opened by inserting the knife into it and dividing the upper two or three rings by cutting upward. If the trachea is to be opened beneath the isthmus, the incision must be made from a little below the cricoid cartilage to the top of the sternum.

A portion of the larynx or the whole of it may be removed for malignant disease. The results which have been obtained from the removal of the whole of it have not been very satisfactory, and the cases in which the operation is justifiable are very few. It may be removed by a median incision through the soft parts, freeing the cartilages from the muscles and other structures in front, separating the larynx from the trachea below, and dissecting off the deeper structure from below upward.

### THE PLEURÆ.

Each lung is invested by an exceedingly delicate serous membrane, the **pleura**, which is arranged in the form of a closed invaginated sac. A portion of the serous membrane covers the surface of the lung and dips into the fissures between its lobes; it is called the **pulmonary pleura**. The rest of the membrane lines the inner surface of the chest wall, covers the Diaphragma, and is reflected over the structures occupying the middle of the thorax; this portion is termed the **parietal pleura**. The two layers are continuous with one another around and below the root of the lung; in health they are in actual contact with one another, but the potential space between them is known as the **pleural cavity**. When the lung collapses or when air or fluid collects between the two layers the cavity becomes apparent. The right and left pleural sacs are entirely separate from one another; between them are all the thoracic viscera except the lungs, and they only touch each other for a short distance in front; opposite the second and third pieces of the sternum the interval between the two sacs is termed the mediastinal cavity.

Different portions of the parietal pleura have received special names which indicate their position: thus, that portion which lines the inner surfaces of the ribs and Intercostales is the **costal pleura**; that clothing the convex surface of the Diaphragma is the **diaphragmatic pleura**; that which rises into the neck, over the summit of the lung, is the **cupula of the pleura** (*cervical pleura*); and that which is applied to the other thoracic viscera is the **mediastinal pleura**.

**Reflections of the Pleura** (Figs. 916, 917).—Commencing at the sternum, the pleura passes lateralward, lines the inner surfaces of the costal cartilages, ribs, and Intercostales, and at the back part of the thorax passes over the sympathetic trunk and its branches, and is reflected upon the sides of the bodies of the vertebræ, where it is separated by a narrow interval, the **posterior mediastinal cavity**, from the opposite pleura. From the vertebral column the pleura passes to the side of the pericardium, which it covers to a slight extent; it then covers the back part of the root of the lung, from the lower border of which a triangular sheet descends vertically toward the Diaphragma. This sheet is the posterior layer of a wide fold, known as the **pulmonary ligament**. From the back of the lung root, the pleura may be traced over the costal surface of the lung, the apex and base, and also over the sides of the fissures between the lobes, on to its mediastinal surface and the front part of its root. It is continued from the lower margin of the root as the anterior layer of the pulmonary ligament, and from this it is reflected on to the pericardium (**pericardial pleura**), and from it to the back of the sternum. Above the level of the root of the lung, however, the mediastinal pleura passes uninterruptedly from the vertebral column to the sternum over the structures in the superior mediastinal cavity. *Below*, it covers the upper surface of the Diaphragma and extends, in front, as low as the costal cartilage of the seventh rib; at the side of the chest,



to the lower border of the tenth rib on the left side and to the upper border of the same rib on the right side; and *behind*, it reaches as low as the twelfth rib, and sometimes even to the transverse process of the first lumbar vertebra. *Above*, its cupula projects through the superior opening of the thorax into the neck, extending from 2.5 to 5 cm. above the sternal end of the first rib; this portion of the sac is strengthened by a dome-like expansion of fascia (*Sibson's fascia*), attached in front to the inner border of the first rib, and behind to the anterior border of the transverse process of the seventh cervical vertebra. This is covered and strengthened by a few spreading muscular fibres derived from the Scaleni.




FIG. 916.—Front view of thorax, showing the relations of the pleurae and lungs to the chest wall. Pleura in blue; lungs in purple.

In the front of the chest, where the parietal pleura is reflected backward to the pericardium, the two pleural sacs are in contact for a short distance. At the upper part of the chest, behind the manubrium, they are separated by an angular interval; the line of reflection being represented by a line drawn from the sternoclavicular articulation to the mid-point of the junction of the manubrium with the body of the sternum. From this point the two pleurae descend in close contact to the level of the fourth costal cartilages, and the line of reflection on the right side is continued downward in nearly a straight line to the xiphoid process, and then turns lateralward, while on the left side the line of reflection diverges lateralward and is continued downward, close to the left border of the sternum, as far as the sixth costal cartilage. The inferior limit of the pleura is on a considerably lower level than the corresponding limit of the lung, but does not extend to the attachment of the Diaphragma, so that below the line of reflection of the pleura from the chest wall on to the Diaphragma the latter is in direct contact with the rib cartilages

and the *Intercostales interni*. Moreover, in ordinary inspiration the thin inferior margin of the lung does not extend as low as the line of the pleural reflection, with the result that the costal and diaphragmatic pleuræ are here in contact, the intervening narrow slit being termed the **phrenicocostal sinus**. A similar condition exists behind the sternum and rib cartilages, where the anterior thin margin of the lung falls short of the line of pleural reflection, and where the slit-like cavity between the two layers of pleura forms what is called the **costomediastinal sinus**.

The line along which the right pleura is reflected from the chest-wall to the Diaphragma starts in front, immediately below the seventh sternocostal joint, and runs downward and backward behind the seventh costal cartilage so as to cross the tenth rib in the mid-axillary line, from which it is prolonged to the spinous process of the twelfth thoracic vertebra. The reflection of the left pleura follows at first the ascending part of the sixth costal cartilage, and in the rest of its course is slightly lower than that of the right side.

The free surface of the pleura is smooth, polished, and moistened by a serous fluid; its attached surface is intimately adherent to the lung, and to the pulmonary vessels as they emerge from the pericardium; it is also adherent to the upper surface of the Diaphragma: throughout the rest of its extent it is easily separable from the adjacent parts.

The right pleural sac is shorter, wider, and reaches higher in the neck than the left.

**Pulmonary Ligament** (*ligamentum pulmonale; ligamentum latum pulmonis*).—From the above description it will be seen that the root of the lung is covered in front, above, and behind by pleura, and that at its lower border the investing layers come into contact. Here they form a sort of mesenteric fold, the pulmonary ligament, which extends between the lower part of the mediastinal surface of the lung and the pericardium. Just above the Diaphragma the ligament ends in a free falciform border. It serves to retain the lower part of the lung in position.

**Structure of Pleura.**—Like other serous membranes, the pleura is covered by a single layer of flattened, nucleated cells, united at their edges by cement substance. These cells are modified connective-tissue corpuscles, and rest on a basement membrane. Beneath the basement membrane there are net-works of yellow elastic and white fibres, imbedded in ground substance which also contains connective-tissue cells. Bloodvessels, lymphatics, and nerves are distributed in the substance of the pleura, and the lymphatics communicate with the pleural cavity by means of stomata or openings between the cells of the superficial layer.

**Vessels and Nerves.**—The **arteries of the pleura** are derived from the intercostal, internal mammary, musculophrenic, thymic, pericardiac, and bronchial vessels. The **veins** correspond




FIG. 917.—Lateral view of thorax, showing the relations of the pleuræ and lungs to the chest wall. Pleura in blue; lungs in purple.

to the arteries. The **lymphatics** are described on page 800. The **nerves** are derived from the phrenic and sympathetic (Luschka). Kölliker states that nerves accompany the ramifications of the bronchial arteries in the pulmonary pleura.

**Applied Anatomy.**—Acute inflammation of the pleura or *pleurisy* may be either dry or wet, and, if wet, either serous or purulent. *Dry pleurisy* is common in pneumonia, and is often an early manifestation of tuberculosis. It gives rise to much pain, and to friction sounds due to the scraping to and fro over one another of the inflamed and roughened parietal and pulmonary pleuræ. *Wet pleurisy* occurs if the inflammation causes the effusion of serum into the pleural cavity. The two pleural layers are now separated by the fluid effusion, so the friction sounds are no longer produced. Room is found for the fluid by shrinkage of the supernatant lung due to the retraction of its elastic tissue, and later, when the quantity of serum exceeds about 1.5 litre, by shifting over of the heart and unaffected lung toward the sound side. This shifting may be so extensive that the apex beat of the heart comes to lie under the right mammary papilla. Any pleural effusion that is large enough to embarrass respiration seriously, or has remained unabsorbed for two or three weeks, should be removed by tapping (*paracentesis thoracis*). The trocar is pushed through the chest wall into the fluid, in the sixth or seventh intercostal space in the mid-axillary line, or in the eighth or ninth space just outside the angle of the scapula. Aspiration is then performed, and as much fluid as possible drawn off; it must be stopped, however, if the patient shows signs of collapse, or if fits of coughing occur and threaten to wound the expanding lung against the sharp end of the trocar. Non-inflammatory or passive effusion into the pleura, called *hydrothorax*, is often seen in the later stages of chronic renal or cardiac disease, and demands treatment on lines similar to the above.

Purulent pleural effusion, or *empyema*, often occurs after such diseases as pneumonia or measles. This condition requires drainage of the cavity, which usually necessitates excision of a portion of the rib. An incision is made down to the seventh or eighth rib in the mid- or posterior axillary line and the periosteum is incised, and separated from the shaft of the rib, carrying with it the structures in the costal groove. With bone-cutting forceps about 4 or 5 cm. of the rib are separated and removed, and the underlying pleura is incised. The pus having been evacuated, a large drainage-tube is inserted into the cavity. The pleura should never be irrigated, as sudden death has followed this proceeding, and great care should be taken to prevent the tube from slipping into the cavity, an occurrence which is far from uncommon.

*Pneumothorax*, or the presence of gas in the pleural cavity, is a common terminal event in tuberculosis of the lungs; less often it is due to trauma—rupture of the lung, for example, when the chest is crushed; or tearing of the lung tissue by the sharp projecting end of a broken rib. Air escapes from the lung into the pleural cavity; the elastic tissue of the lung at once contracts, and finally that organ shrinks away to a dark rounded mass the size of a fist, lying close against the vertebral column. The symptoms of pneumothorax are often very severe; cyanosis, intense dyspnoea, great pain on the affected side, and cardiac failure. Their severity is increased by the fact that the bloodvessels of the collapsed lung offer less resistance to the circulation of the blood than do those of the other lung. Not only, therefore, does the sound lung suddenly have to take over the work—the aëration of the blood—normally performed by both lungs, but it has to do so at the moment when the circulation of blood through it is partially short-circuited by the collapsed lung. If the patient survives for a few days, empyema often complicates the pneumothorax, setting up the condition called *pyopneumothorax*.

In operations upon the kidney, it must be borne in mind that the pleura usually extends below the level of the medial portion of the last rib, and may therefore be opened in these operations, especially when the last rib is removed in order to give more room.

### THE MEDIASTINAL CAVITY (INTERPLEURAL SPACE).

The **mediastinal cavity** is the space between the right and left pleuræ in and near the median sagittal plane of the chest. It extends from the sternum in front to the vertebral column behind, and contains all the thoracic viscera excepting the lungs. The cavity may be divided for purposes of description into two parts: an upper portion, above the upper level of the pericardium, which is named the **superior mediastinal cavity**; and a lower portion, below the upper level of the pericardium. This lower portion is again subdivided into three parts, viz., that in front of the pericardium, the **anterior mediastinal cavity**; that containing the pericardium and its contents, the **middle mediastinal cavity**; and that behind the pericardium, the **posterior mediastinal cavity**.

The **superior mediastinal cavity** (Fig. 918) is that portion of the interpleural space which lies between the manubrium sterni in front, and the upper thoracic

vertebræ behind. It is bounded below by a slightly oblique plane passing backward from the junction of the manubrium and body of the sternum to the lower part




FIG. 918.—Transverse section through the upper margin of the second thoracic vertebra. (Braune.)




FIG. 919.—A transverse section of the thorax, showing the contents of the middle and posterior mediastinal cavities.



of the body of the fourth thoracic vertebra, and laterally by the pleuræ. It contains the origins of the Sternohyoidei and Sternothyroidei and the lower ends of the Longi colli; the aortic arch; the innominate artery and the thoracic portions of the left common carotid and the left subclavian arteries; the innominate veins and the upper half of the superior vena cava; the left highest intercostal vein; the vagus, cardiac, phrenic, and left recurrent nerves; the trachea, œsophagus, and thoracic duct; the remains of the thymus, and some lymph glands. .




FIG. 920.—The middle and posterior mediastina. Left side.

The **anterior mediastinal cavity** (Fig. 919) exists only on the left side where the left pleura diverges from the mid-sternal line. It is bounded in front by the sternum, laterally by the pleuræ, and behind by the pericardium. It is narrow, above, but widens out a little below. Its anterior wall is formed by the left Transversus thoracis and the fifth, sixth, and seventh left costal cartilages. It contains



a quantity of loose areolar tissue, some lymphatic vessels which ascend from the convex surface of the liver, two or three anterior mediastinal lymph glands, and the small mediastinal branches of the internal mammary artery.

The **middle mediastinal cavity** (Fig. 919) is the broadest part of the interpleural space. It contains the heart enclosed in the pericardium, the ascending aorta, the lower half of the superior vena cava with the azygos vein opening into it, the bifurcation of the trachea and the two bronchi, the pulmonary artery dividing into its two branches, the right and left pulmonary veins, the phrenic nerves, and some bronchial lymph glands.

The **posterior mediastinal cavity** (Figs. 919, 920) is an irregular triangular space running parallel with the vertebral column; it is bounded in front by the pericardium above, and by the posterior surface of the Diaphragma below, behind by the vertebral column from the lower border of the fourth to the twelfth thoracic vertebra, and on either side by the mediastinal pleura. It contains the thoracic part of the descending aorta, the azygos and the two hemiazygos veins, the vagus and splanchnic nerves, the œsophagus, the thoracic duct, and some lymph glands.

**Applied Anatomy.**—*Primary tumors* of the mediastinum are usually lymphoma or lymphosarcoma arising from the thymus or from the bronchial or posterior mediastinal lymph glands. *sarcomata*, dermoid cysts, and *embryomata* occur more rarely. These tumors give rise to pain, deformity of the chest, and symptoms of pressure on the various nerves, bloodvessels, air passages, lymphatics, and on the œsophagus, as these various structures pass through the thorax. They may produce physical signs very much like those of an aortic aneurism, so that diagnosis between the two is often difficult. The prognosis is bad, the condition usually proving fatal within a few months or a year of the onset of the symptoms.

*Inflammation* of the mediastinum due to wounds, or to the spread of inflammation from adjacent parts, *e. g.*, the œsophagus, the pericardium, is sometimes acute, leading to abscess formation. A more chronic form associated with adhesions and inflammation of the pericardium—the so-called chronic adhesive mediastinopericarditis—gives rise to obscure symptoms suggesting gradual heart-failure, and leads to death slowly but surely.

## THE LUNGS (PULMONES).

The **lungs** are the essential organs of respiration; they are two in number, placed one on either side within the thorax, and separated from each other by the heart and other contents of the mediastinal cavity (Fig. 921). The substance of the lung is of a light, porous, spongy texture; it floats in water, and crepitates when handled, owing to the presence of air in the alveoli; it is also highly elastic; hence the retracted state of these organs when they are removed from the closed cavity of the thorax. The surface is smooth, shining, and marked out into numerous polyhedral areas, indicating the lobules of the organ: each of these areas is crossed by numerous lighter lines.

At birth the lungs are pinkish white in color; in adult life the color is a dark slaty gray, mottled in patches; and as age advances, this mottling assumes a black color. The coloring matter consists of granules of a carbonaceous substance deposited in the areolar tissue near the surface of the organ. It increases in quantity as age advances, and is more abundant in males than in females. As a rule, the posterior border of the lung is darker than the anterior.

The right lung usually weighs about 625 gm., the left 567 gm., but much variation is met with according to the amount of blood or serous fluid they may contain. The lungs are heavier in the male than in the female, their proportion to the body being, in the former, as 1 to 37, in the latter as 1 to 43.

Each lung is conical in shape, and presents for examination an **apex**, a **base**, three **borders**, and two **surfaces**.

The **apex** (*apex pulmonis*) is rounded, and extends into the root of the neck, reaching from 2.5 to 4 cm. above the level of the sternal end of the first rib. A

sulcus produced by the subclavian artery as it curves in front of the pleura runs upward and lateralward immediately below the apex.

The **base** (*basis pulmonis*) is broad, concave, and rests upon the convex surface of the Diaphragma, which separates the right lung from the right lobe of the liver, and the left lung from the left lobe of the liver, the stomach, and the spleen. Since the Diaphragma extends higher on the right than on the left side, the concavity on the base of the right lung is deeper than that on the left. Laterally and behind, the base is bounded by a thin, sharp margin which projects for some distance into the phrenicocostal sinus of the pleura, between the lower ribs and the costal attachment of the Diaphragma. The base of the lung descends during inspiration and ascends during expiration.




FIG. 921.—Front view of heart and lungs.

**Surfaces.**—The **costal surface** (*facies costalis*; *external or thoracic surface*) is smooth, convex, of considerable extent, and corresponds to the form of the cavity of the chest, being deeper behind than in front. It is in contact with the costal pleura, and presents, in specimens which have been hardened *in situ*, slight grooves corresponding with the overlying ribs.

The **mediastinal surface** (*facies mediastinalis*; *inner surface*) is in contact with the mediastinal pleura. It presents a deep concavity, the **cardiac impression**, which accommodates the pericardium; this is larger and deeper on the left than on the right lung, on account of the heart projecting farther to the left than to the right side of the median plane. Above and behind this concavity is a triangular depression named the **hilus**, where the structures which form the root of the lung enter and leave the viscus. These structures are invested by pleura, which, below

the hilus and behind the pericardial impression, forms the pulmonary ligament. On the *right lung* (Fig. 922), immediately above the hilus, is an arched furrow which accommodates the azygos vein; while running upward, and then arching lateralward some little distance below the apex, is a wide groove for the superior vena cava and right innominate vein; behind this, and nearer the apex, is a furrow for the innominate artery. Behind the hilus and the attachment of the pulmonary ligament is a vertical groove for the œsophagus; this groove becomes less distinct below, owing to the inclination of the lower part of the œsophagus to the left of the middle line. In front and to the right of the lower part of the œsophageal groove is a deep concavity for the extrapericardiac portion of the thoracic part of the inferior vena cava. On the *left lung* (Fig. 923), immediately above the hilus, is a well-marked curved furrow produced by the aortic arch, and running upward




FIG. 922.—Mediastinal surface of right lung.

from this toward the apex is a groove accommodating the left subclavian artery; a slight impression in front of the latter and close to the margin of the lung lodges the left innominate vein. Behind the hilus and pulmonary ligament is a vertical furrow produced by the descending aorta, and in front of this, near the base of the lung, the lower part of the œsophagus causes a shallow impression.

**Borders.**—The **inferior border** (*margo inferior*) is thin and sharp where it separates the base from the costal surface and extends into the phrenicocostal sinus; medially where it divides the base from the mediastinal surface it is blunt and rounded.

The **posterior border** (*margo posterior*) is broad and rounded, and is received into the deep concavity on either side of the vertebral column. It is much longer than the anterior border, and projects, below, into the phrenicocostal sinus.

The **anterior border** (*margo anterior*) is thin and sharp, and overlaps the front of the pericardium. The anterior border of the *right* lung is almost vertical, and projects into the costomediastinal sinus; that of the *left* presents, below, an angular notch, the **cardiac notch**, in which the pericardium is exposed. Opposite this notch the anterior margin of the left lung is situated some little distance lateral to the line of reflection of the corresponding part of the pleura.




FIG. 923.—Mediastinal surface of left lung.

**Fissures and Lobes of the Lungs.**—The **left lung** is divided into two lobes, an upper and a lower, by an interlobular fissure, which extends from the costal to the mediastinal surface of the lung both above and below the hilus. As seen on the surface, this fissure begins on the mediastinal surface of the lung at the upper and posterior part of the hilus, and runs backward and upward to the posterior border, which it crosses at a point about 6 cm. below the apex. It then extends downward and forward over the costal surface, and reaches the lower border a little behind its anterior extremity, and its further course can be followed upward and backward across the mediastinal surface as far as the lower part of the hilus. The **superior lobe** lies above and in front of this fissure, and includes the apex, the anterior border, and a considerable part of the costal surface and the greater part of the mediastinal surface of the lung. The **inferior lobe**, the larger of the two, is situated below and behind the fissure, and comprises almost the whole of the base, a large portion of the costal surface, and the greater part of the posterior border.

The **right lung** is divided into three lobes, superior, middle, and inferior, by two interlobular fissures. One of these separates the inferior from the middle and superior lobes, and corresponds closely with the fissure in the left lung. Its



direction is, however, more vertical, and it cuts the lower border about 7.5 cm. behind its anterior extremity. The other fissure separates the superior from the middle lobe. It begins in the previous fissure near the posterior border of the lung, and, running horizontally forward, cuts the anterior border on a level with the sternal end of the fourth costal cartilage; on the mediastinal surface it may be traced backward to the hilus. The **middle lobe**, the smallest lobe of the right lung, is wedge-shaped, and includes the lower part of the anterior border and the anterior part of the base of the lung.

The right lung, although shorter by 2.5 cm. than the left, in consequence of the Diaphragm rising higher on the right side to accommodate the liver, is broader, owing to the inclination of the heart to the left side; its total capacity is greater and it weighs more than the left lung.

**The Root of the Lung** (*radix pulmonis*).—A little above the middle of the mediastinal surface of each lung, and nearer its posterior than its anterior border, is its root, by which the lung is connected to the heart and the trachea. The root is formed by the bronchus, the pulmonary artery, the pulmonary veins, the bronchial arteries and veins, the pulmonary plexuses of nerves, lymphatic vessels, bronchial lymph glands, and areolar tissue, all of which are enclosed by a reflection of the pleura. The root of the right lung lies behind the superior vena cava and part of the right atrium, and below the azygos vein. That of the left lung passes beneath the aortic arch and in front of the descending aorta; the phrenic nerve, the pericardiophrenic artery and vein, and the anterior pulmonary plexus, lie in front of each, and the vagus and posterior pulmonary plexus behind each; below each is the pulmonary ligament.

The chief structures composing the root of each lung are arranged in a similar manner from before backward on both sides, viz., the upper of the two pulmonary veins in front; the pulmonary artery in the middle; and the bronchus, together with the bronchial vessels, behind. From above downward, on the two sides, their arrangement differs, thus:

On the right side their position is—**eparterial** bronchus, pulmonary artery, **hyarterial** bronchus, pulmonary veins, but on the left side their position is—pulmonary artery, bronchus, pulmonary veins. The lower of the two pulmonary veins, is situated below the bronchus, at the apex or lowest part of the hilus (Figs. 922, 923).

**Divisions of the Bronchi.**—Just as the lungs differ from each other in the number of their lobes, so the bronchi differ in their mode of subdivision.

The **right bronchus** gives off, about 2.5 cm. from the bifurcation of the trachea, a branch for the superior lobe. This branch arises above the level of the pulmonary artery, and is therefore named the **eparterial bronchus**. All the other divisions of the main stem come off below the pulmonary artery, and consequently are termed **hyarterial bronchi**. The first of these is distributed to the middle lobe, and the main tube then passes downward and backward into the inferior lobe, giving off in its course a series of large ventral and small dorsal branches. The ventral and dorsal branches arise alternately, and are usually eight in number—four of each kind. The branch to the middle lobe is regarded as the first of the ventral series.

The **left bronchus** passes below the level of the pulmonary artery before it divides, and hence all its branches are **hyarterial**; it may therefore be looked upon as equivalent to that portion of the right bronchus which lies on the distal side of its **eparterial** branch. The first branch of the left bronchus arises about 5 cm. from the bifurcation of the trachea, and is distributed to the superior lobe. The main stem then enters the inferior lobe, where it divides into ventral and dorsal branches similar to those in the right lung. The branch to the superior lobe of the left lung is regarded as the first of the ventral series.



**Structure.**—The lungs are composed of an external serous coat, a subserous areolar tissue, and the pulmonary substance or parenchyma.

The **serous coat** is the pulmonary pleura (page 1097); it is thin, transparent, and invests the entire organ as far as the root.

The **subserous areolar tissue** contains a large proportion of elastic fibres; it invests the entire surface of the lung, and extends inward between the lobules.

The **parenchyma** is composed of lobules which, although closely connected together by an interlobular areolar tissue, are quite distinct from one another, and may be teased asunder without much difficulty in the fetus. The lobules vary in size; those on the surface are large, of pyramidal form, the base turned toward the surface; those in the interior smaller, and of various forms. Each lobule is composed of a lobular bronchiole and its terminal air cells, and of the ramifications of the pulmonary and bronchial vessels, lymphatics, and nerves; all of these structures being connected together by areolar tissue.

The **intrapulmonary bronchi** divide and subdivide throughout the entire organ, the smallest subdivisions constituting the lobular bronchioles. The *larger divisions* consist of: (1) an outer coat of fibrous tissue in which are found at intervals irregular plates of hyaline cartilage, most developed at the points of division; (2) internal to the fibrous coat, a layer of circularly disposed smooth muscle fibres, the bronchial muscle; and (3) most internally, the mucous membrane, lined by columnar ciliated epithelium resting on a basement membrane. The corium of the mucous membrane contains numerous elastic fibres running longitudinally, and a certain amount of lymphoid tissue; it also contains the ducts of mucous glands, the acini of which lie in the fibrous coat. The **lobular bronchioles** differ from the larger tubes in containing no cartilage and in the fact that the ciliated epithelial cells are cubical in shape. The lobular bronchioles are about 0.2 mm. in diameter.




FIG. 924.—Section of lung of cat, showing termination of bronchus.  $\times 50$ .

Each bronchiole terminates at a point called the **vestibule** by dividing into from three to six wider irregular passages called **atria**. These are lined by flattened non-ciliated epithelium; at the vestibule the bronchial muscle forms a definite circular band. From each atrium arise two or more **infundibula**, elongated, blind passages, lined by simple squamous epithelium, and beset on all sides by hemispherical alveoli or air cells (Fig. 924).

The **alveoli** are lined by a delicate layer of simple squamous epithelium, the cells of which are united at their edges by cement substance. Between the squames are here and there smaller, polygonal, nucleated cells. Outside the epithelial lining is a little delicate connective tissue, containing numerous elastic fibres and a close net-work of blood capillaries, and forming a common wall to adjacent alveoli (Fig. 925).

The fetal lung resembles a gland in that the alveoli have a small lumen and are lined by cubical epithelium (Fig. 926). After the first respiration the alveoli become distended, and the epithelium takes on the characters described above.

**Vessels and Nerves.**—The **pulmonary artery** conveys the venous blood to the lungs; it divides into branches which accompany the bronchial tubes and end in a dense capillary net-work in




FIG. 925.—Section of lung tissue.

the walls of the alveoli. In the lung the branches of the pulmonary artery are usually above and in front of a bronchial tube, the vein below.




FIG. 926.—Section of lung of pig embryo, 13 cm. long, showing the glandular character of the developing alveoli. (J. M. Flint.)  $\times 70$ . a. Interstitial connective tissue. b. A bronchial tube. c. An Alveolus. l. lymphatic clefts. p. Pleura.

The **pulmonary capillaries** form plexuses which lie immediately beneath the lining epithelium, in the walls and septa of the alveoli and of the infundibula. In the septa between the

alveoli the capillary net-work forms a single layer. The capillaries form a very minute net-work, the meshes of which are smaller than the vessels themselves; their walls are also exceedingly thin. The arteries of neighboring lobules are independent of each other, but the veins freely anastomose.

The **pulmonary veins** commence in the pulmonary capillaries, the radicles coalescing into larger branches which run through the substance of the lung, independently of the pulmonary arteries and bronchi. After freely communicating with other branches they form large vessels, which ultimately come into relation with the arteries and bronchial tubes, and accompany them to the hilus of the organ. Finally they open into the left atrium of the heart, conveying oxygenated blood to be distributed to all parts of the body by the aorta.

The **bronchial arteries** supply blood for the nutrition of the lung; they are derived from the thoracic aorta or from the upper aortic intercostal arteries, and, accompanying the bronchial tubes, are distributed to the bronchial glands and upon the walls of the larger bronchial tubes and pulmonary vessels. Those supplying the bronchial tubes form a capillary plexus in the muscular coat, from which branches are given off to form a second plexus in the mucous coat; this plexus communicates with branches of the pulmonary artery, and empties itself into the pulmonary veins. Others are distributed in the interlobular areolar tissue, and end partly in the deep, partly in the superficial, bronchial veins. Lastly, some ramify upon the surface of the lung, beneath the pleura, where they form a capillary network.

The **bronchial vein** is formed at the root of the lung, receiving superficial and deep veins corresponding to branches of the bronchial artery. It does not, however, receive all the blood supplied by the artery, as some of it passes into the pulmonary veins. It ends on the right side in the azygos vein, and on the left side in the highest intercostal or in the accessory hemiazygos vein.

The **lymphatics** are described on page 799.

**Nerves.**—The lungs are supplied from the anterior and posterior pulmonary plexuses, formed chiefly by branches from the sympathetic and vagus. The filaments from these plexuses accompany the bronchial tubes, supplying efferent fibres to the bronchial muscle and afferent fibres to the bronchial mucous membrane and to the alveoli of the lung. Small ganglia are found upon these nerves.

**Applied Anatomy.**—The lungs may be wounded or torn in three ways: (1) by compression of the chest, without any injury to the ribs; (2) by a fractured rib penetrating the lung; (3) by stabs, gunshot wounds, etc.

The first form, where the lung is ruptured by external compression without any fracture of the ribs, is very rare, and usually occurs in young children, and affects the root of the lung, *i. e.*, the most fixed part, and thus, implicating the great vessels, is frequently fatal. It would seem *a priori* a most unusual injury, and its exact mode of causation is difficult to interpret.

In the second variety, when the wound in the lung is produced by the penetration of a broken rib, both the costal pleura and pulmonary pleura must necessarily be injured, and consequently the air taken into the wounded alveoli may find its way through these wounds into the cellular tissue of the parietes of the chest, producing *surgical emphysema*. This it may do without collecting in the pleural cavity; the two layers of the pleura are so intimately in contact that the air passes straight through from the wounded lung into the subcutaneous tissue. Emphysema constitutes therefore the most important sign of injury to the lung in cases of fracture of the ribs. Pneumothorax, or air in the pleural cavity, is much more likely to occur in injuries of the third variety—that is to say, from external wounds, from stabs, gunshot injuries, and such like—in which case air passes either from the wound of the lung or from the external wound into the cavity of the pleura during the respiratory movements. In these cases there is generally no emphysema of the subcutaneous tissue unless the external wound is small and valvular, so that the air is drawn into the wound during inspiration, and then forced into the cellular tissue around during expiration because it cannot escape from the external wound. Occasionally in wounds of the parietes of the chest no air finds its way into the cavity of the pleura, because the lung at the time of the accident protrudes through the wound and blocks the opening. This takes place where the wound is large, and constitutes one form of *hernia* of the lung. Another form of *hernia* of the lung occurs, though very rarely, after wounds of the chest wall, when the wound has healed and the cicatrix subsequently yields from the pressure of the viscus behind. It forms a globular, elastic, crepitating swelling, which enlarges during expiratory efforts, falls in during inspiration, and disappears on holding the breath.

An incision into the lung is occasionally required in cases of abscess the result of pneumonia or the presence of a foreign body, and from an abscess in the liver which has made its way through the Diaphragma into the lung substance, and also in cases of hydatid disease. In these cases there is always risk of hemorrhage, and it has been recommended that the lung tissue should be penetrated by the actual cautery, rather than with the knife. Unless adhesions have formed between the two layers of the pleura, the pleural cavity must necessarily be opened, and there is the further risk of pneumothorax, and possibly of septic infection. It is therefore advisable to suture the lung to the opening in the thoracic wall, and wait for adhesions to form before perforating the lung.

The routine methods of physical examination—inspection, palpation, percussion, and auscultation—are nowhere more important than they are in the diagnosis of diseases of the lungs. It is essential, too, that in every case the two sides of the chest should be compared with one another, and that the wide variations that may be met with under normal conditions in different persons and at different ages should be kept in mind when the chest is being examined. On *inspection* the thorax will be seen to be enlarged and barrel-shaped in emphysema, in which the volume of the lungs is increased by dilatation of their alveoli, or in an acute attack of asthma, or when a large pleural effusion or mediastinal tumor is present. The chest wall will be flattened or sunken, on the other hand, over an area of lung that has collapsed or become fibrosed, as often happens in chronic pulmonary tuberculosis. The respiratory movements of the chest wall will be lessened, or even absent, over a part of the whole of the affected side in such acute disorders as pleurisy, pneumonia, or pleural effusion, or in more chronic diseases where the underlying lung is fibrosed, or is crushed to one side by a mediastinal tumor; and by the use of the *x*-rays a corresponding loss of movement or displacement of the Diaphragm on the affected side can often be observed. Under normal conditions the intercostal spaces are a little depressed; but they may be obliterated or even bulging on that side when a large effusion or new growth fills up one of the pleural cavities.

On *palpation* the hand can be used to verify the eye's impressions as to the degree of movement on respiration of any part of the chest wall. The facility with which the vibrations produced by the voice are conducted from the larynx by the underlying lung to the hand (in the form of *vocal fremitus*) can also be tested. The vocal fremitus is commonly much increased over the consolidated area in pneumonia or in fibrosis of the lung, and much diminished over a pleural effusion when the lung is pushed up by the fluid toward the top of the pleural cavity. It is also diminished, but to a less extent, in emphysema, and in bronchitis when the bronchi are blocked by secretion. In bronchitis the bubbling of the secretion in the tubes can often be felt by a hand placed on the chest wall as the patient breathes; and in chronic pleurisy the friction of the two roughened pleural surfaces against one another can sometimes be felt in the same way.

On *percussion*, the normal resonance of the pulmonary tissue is found to be increased in emphysema, and in pneumothorax (page 1098) this hyperresonance may be still further increased. The resonance is lessened in any condition causing collapse or solidification of the lung tissue, or when its place is taken by fluid (pleural effusion) or some solid growth (mediastinal tumor). Thus dullness on percussion at the bases of the lungs is common in the hypostatic congestion of the bases seen in heart failure; dullness at the right base is often due to compression of the lung by enlargement of the liver; some dullness at the apex of a lung is frequently met with in tuberculosis of the part, before the disease has progressed very far. Complete dullness over one side of the chest, back and front alike, except at the apex, is common when a large pleural effusion has taken the lung's place. Von Korányi, Grocco, and others have drawn attention to a triangular patch of dullness along the vertebral column (the paravertebral triangle of dullness) on the unaffected side in pleural effusion; this triangle of dullness is said to be absent in other conditions, causing loss of pulmonary resonance on percussion, and is due to shifting over of the contents of the posterior mediastinal cavity toward the sound side. The apex of this triangle is in the middle line at the upper level of the fluid effusion; its base, some 5 to 10 cm. in length, runs horizontally outward from the middle line at the level where the pulmonary resonance normally comes to an end.

On *auscultation* of the lungs, both in health and disease, the variety of sounds to be heard is very great. It is impossible to give adequate consideration to them here, and for further information reference should be made to text-books dealing with the subject.<sup>1</sup>

## THE DIGESTIVE APPARATUS (APPARATUS DIGESTORIUS; ORGANS OF DIGESTION).

The apparatus for the digestion of the food consists of the **digestive tube** and of certain **accessory organs**.

The **Digestive Tube** (*alimentary canal*) is a musculomembranous tube, about 9 metres long, extending from the mouth to the anus, and lined throughout its entire extent by mucous membrane. It has received different names in the various parts of its course: at its commencement is the **mouth**, where provision is made for the mechanical division of the food (*mastication*), and for its admixture with a fluid secreted by the salivary glands (*insalivation*); beyond this are the organs of deglutition, the **pharynx** and the **oesophagus**, which convey the food into the **stomach**, in which it is stored for a time and in which also the first stages of the

<sup>1</sup> See especially *Auscultation and Percussion*, by Austin Flint, M.D., 6th ed., 1912.

digestive process take place; the stomach is followed by the **small intestine**, which is divided for purposes of description into three parts, the **duodenum**, the **jejunum**, and **ileum**. In the small intestine the process of digestion is completed and the resulting products are absorbed into the blood and lacteal vessels. Finally the small intestine ends in the **large intestine**, which is made up of **cecum**, **colon**, **rectum**, and **anal canal**, the last terminating on the surface of the body at the **anus**.

The accessory organs are the **teeth**, for purposes of mastication; the three pairs of **salivary glands**—the **parotid**, **submaxillary**, and **sublingual**—the secretion from which mixes with the food in the mouth and converts it into a bolus and acts chemically on one of its constituents; the **liver** and **pancreas**, two large glands in the abdomen, the secretions of which, in addition to that of numerous minute glands in the walls of the alimentary canal, assist in the process of digestion.

### THE MOUTH (CAVUM ORIS; ORAL OR BUCCAL CAVITY).

The **cavity of the mouth** is placed at the commencement of the digestive tube (Fig. 927); it is a nearly oval-shaped cavity which consists of two parts: an outer, smaller portion, the **vestibule**, and an inner, larger part, the **mouth cavity proper**.

The **Vestibule** (*vestibulum oris*) is a slit-like space, bounded externally by the lips and cheeks; internally by the gums and teeth. It communicates with the surface of the body by the **rima** or **orifice of the mouth**. Above and below, it is limited by the reflection of the mucous membrane from the lips and cheeks to the gum covering the upper and lower alveolar arch respectively. It receives the secretion from the parotid salivary glands, and communicates, when the jaws are closed, with the mouth cavity proper by an aperture on either side behind the wisdom teeth, and by narrow clefts between opposing teeth.

The **Mouth Cavity Proper** (*cavum oris proprium*) (Fig. 943) is bounded laterally and in front by the alveolar arches with their contained teeth; behind, it communicates with the pharynx by a constricted aperture termed the **isthmus faucium**. It is roofed in by the hard and soft plates, while the greater part of the floor is formed by the tongue, the remainder by the reflection of the mucous membrane from the sides and under surface of the tongue to the gum lining the inner aspect of the mandible. It receives the secretion from the submaxillary and sublingual salivary glands.

**Structure.**—The **mucous membrane** lining the mouth is continuous with the integument at the free margin of the lips, and with the mucous lining of the pharynx behind; it is of a rose-pink tinge during life, and very thick where it overlies the hard parts bounding the cavity. It is covered by stratified squamous epithelium.

The **Lips** (*labia oris*), the two fleshy folds which surround the rima or orifice of the mouth, are formed externally of integument and internally of mucous membrane, between which are found the Orbicularis oris muscle, the labial vessels, some nerves, areolar tissue, and fat, and numerous small labial glands. The inner surface of each lip is connected in the middle line to the corresponding gum by a fold of mucous membrane, the **frenulum**—the upper being the larger.

The **Labial Glands** (*glandulae labiales*) are situated between the mucous membrane and the Orbicularis oris, around the orifice of the mouth. They are circular in form, and about the size of small peas; their ducts open by minute orifices upon the mucous membrane. In structure they resemble the salivary glands.

The **Cheeks** (*buccae*) form the sides of the face, and are continuous in front with the lips. They are composed externally of integument; internally of mucous membrane; and between the two of a muscular stratum, besides a large quantity of fat, areolar tissue, vessels, nerves, and buccal glands.

**Structure.**—The **mucous membrane** lining the cheek is reflected above and below upon the gums, and is continuous behind with the lining membrane of the soft palate. Opposite the



second molar tooth of the maxilla is a papilla, on the summit of which is the aperture of the parotid duct. The principal muscle of the cheek is the Buccinator; but other muscles enter into its formation, viz., the Zygomaticus, Risorius, and Platysma.

The *buccal glands* are placed between the mucous membrane and Buccinator muscle: they are similar in structure to the labial glands, but smaller. About five, of a larger size than the rest, are placed between the Masseter and Buccinator muscles around the distal extremity of the parotid duct; their ducts open in the mouth opposite the last molar tooth. They are called **molar glands**.




FIG. 927.—Sagittal section of nose, mouth, pharynx, and larynx.

The **Gums** (*gingivæ*) are composed of dense fibrous tissue, closely connected to the periosteum of the alveolar processes, and surrounding the necks of the teeth. They are covered by smooth and vascular mucous membrane, which is remarkable for its limited sensibility. Around the necks of the teeth this membrane

presents numerous fine papillæ, and is reflected into the alveoli, where it is continuous with the periosteal membrane lining these cavities.

**Applied Anatomy.**—The gums are occasionally the seat of considerable hypertrophy, forming a lobulated vascular fold growing up in front of and behind the teeth, so as almost to bury them. They may also become swollen and congested, bleeding freely, and often becoming ulcerated. The condition is known as *spongy gums*, and may occur in scurvy, in stomatitis and dyspepsia, in ill-fed tuberculous children, and from the administration of mercury; the gums are very tender, mastication is painful, and there is often considerable fetor. The margin of the gum presents an interrupted blue line in cases of lead poisoning. The collection of tartar, which consists of the secretion from the gums, mixed with fragments of food and salivary salts, may give rise to a condition known as *pyorrhæa alveolaris*, which is an inflammatory condition of the gums, followed by the gradual absorption of the alveolus and the falling out of the teeth. Fibrous tumors (*epulis*), myeloid growths, and epitheliomata are met with in the gums.

The **Palate** (*palatum*) forms the roof of the mouth; it consists of two portions, the **hard palate** in front, the **soft palate** behind.

The **Hard Palate** (*palatum durum*) (Fig. 943) is bounded in front and at the sides by the alveolar arches and gums; behind, it is continuous with the soft palate: It is covered by a dense structure, formed by the periosteum and mucous membrane of the mouth, which are intimately adherent. Along the middle line is a linear raphé, which ends anteriorly in a small papilla corresponding with the incisive canal. On either side and in front of the raphé the mucous membrane is thick, pale in color, and corrugated; behind, it is thin, smooth, and of a deeper color; it is covered with stratified squamous epithelium, and furnished with numerous palatal glands, which lie between the mucous membrane and the surface of the bone.

The **Soft Palate** (*palatum molle*) (Fig. 943) is a movable fold, suspended from the posterior border of the hard palate, and forming an incomplete septum between the mouth and pharynx. It consists of a fold of mucous membrane enclosing muscular fibres, an aponeurosis, vessels, nerves, adenoid tissue, and mucous glands. When occupying its usual position, *i. e.*, relaxed and pendent, its anterior surface is concave, continuous with the roof of the mouth, and marked by a median raphé. Its posterior surface is convex, and continuous with the mucous membrane covering the floor of the nasal cavities. Its upper border is attached to the posterior margin of the hard palate, and its sides are blended with the pharynx. Its lower border is free. Its lower portion, which hangs like a curtain between the mouth and pharynx is termed the **palatine velum**.

Hanging from the middle of its lower border is a small, conical, pendulous process, the **palatine uvula**; and arching lateralward and downward from the base of the uvula on either side are two curved folds of mucous membrane, containing muscular fibres, called the **arches or pillars of the fauces**.

The **glossopalatine arch** (*arcus glossopalatinus*; *anterior pillar of fauces*) on either side runs downward, lateralward, and forward to the side of the base of the tongue, and is formed by the projection of the Glossopalatinus with its covering mucous membrane.

The **pharyngopalatine arch** (*arcus pharyngopalatinus*; *posterior pillar of fauces*) is larger and projects farther toward the middle line than the anterior; it runs downward, lateralward, and backward to the side of the pharynx, and is formed by the projection of the Pharyngopalatinus, covered by mucous membrane. On either side the two arches are separated below by a triangular interval, in which the palatine tonsil is lodged.

The aperture by which the mouth communicates with the pharynx is called the **isthmus faucium**. It is bounded, above, by the soft palate; below, by the dorsum of the tongue; and on either side, by the glossopalatine arch.

**Palatine Aponeurosis.**—Attached to the posterior border of the hard palate is a thin, firm fibrous lamella which supports the muscles and gives strength to the

soft palate. It is thicker above than below, where it becomes very thin and difficult to define. Laterally it is continuous with the pharyngeal aponeurosis.

**Muscles of the Palate.**—The muscles of the palate (Fig. 928) are:

Levator veli palatini.

Glossopalatinus.

Tensor veli palatini.

Pharyngopalatinus.

Musculus uvulae.




FIG. 928.—Dissection of the muscles of the palate from behind.

The **Levator veli palatini** (*Levator palati*) is a thick, rounded muscle situated lateral to the choanæ. It *arises* from the under surface of the apex of the petrous part of the temporal bone and from the medial lamina of the cartilage of the auditory tube. After passing above the upper concave margin of the Constrictor pharyngis superior it spreads out in the palatine velum, its fibres extending obliquely downward and medialward to the middle line, where they blend with those of the opposite side.

The **Tensor veli palatini** (*Tensor palati*) is a broad, thin, ribband-like muscle placed lateral to the Levator veli palatini. It *arises* by a flat lamella from the scaphoid fossa at the base of the medial pterygoid plate, from the spina angularis of the sphenoid and from the lateral wall of the cartilage of the auditory tube. Descending vertically between the medial pterygoid plate and the Pterygoideus internus it ends in a tendon which winds around the pterygoid hamulus, being retained in this situation by some of the fibres of origin of the Pterygoideus internus.

Between the tendon and the hamulus is a small bursa. The tendon then passes medialward and is *inserted* into the palatine aponeurosis and into the surface behind the transverse ridge on the horizontal part of the palatine bone.

The **Musculus uvulae** (*Azygos uvulae*) *arises* from the posterior nasal spine of the palatine bones and from the palatine aponeurosis; it descends to be inserted into the uvula.

The **Glossopalatinus** (*Palatoglossus*) is a small fleshy fasciculus, narrower in the middle than at either end, forming, with the mucous membrane covering its surface, the glossopalatine arch. It *arises* from the anterior surface of the soft palate, where it is continuous with the muscle of the opposite side, and passing downward, forward, and lateralward in front of the palatine tonsil, is inserted into the side of the tongue, some of its fibres spreading over the dorsum, and others passing deeply into the substance of the organ to intermingle with the Transversus linguae.

The **Pharyngopalatinus** (*Palatopharyngeus*) is a long, fleshy fasciculus narrower in the middle than at either end, forming, with the mucous membrane covering its surface, the pharyngopalatine arch. It is separated from the Glossopalatinus by an angular interval, in which the palatine tonsil is lodged. It *arises* from the soft palate, where it is divided into two fasciculi by the Levator veli palatini and Musculus uvulae. The **posterior fasciculus** lies in contact with the mucous membrane, and joins with that of the opposite muscle in the middle line; the **anterior fasciculus**, the thicker, lies in the soft palate between the Levator and Tensor, and joins in the middle line the corresponding part of the opposite muscle. Passing lateralward and downward behind the palatine tonsil, the Pharyngopalatinus joins the Stylopharyngeus, and is inserted with that muscle into the posterior border of the thyroid cartilage, some of its fibres being lost on the side of the pharynx and others passing across the middle line posteriorly, to decussate with the muscle of the opposite side.

**Dissection.**—In a dissection of the soft palate from its posterior or pharyngeal surface to its anterior or oral surface, the muscles would be exposed in the following order: viz., the posterior fasciculus of the Pharyngopalatinus, covered by a continuation of the mucous membrane of the floor of the nasal cavities; the Musculus uvulae; the Levator veli palatini; the anterior fasciculus of the Pharyngopalatinus; the aponeurosis of the Tensor veli palatini, and the Glossopalatinus covered by a continuation of the oral mucous membrane.

**Nerves.**—The Tensor veli palatini is supplied by a branch from the otic ganglion; the remaining muscles of this group are in all probability supplied by the accessory nerve through the pharyngeal plexus.<sup>1</sup>

**Actions.**—During the *first stage* of deglutition, the bolus of food is driven back into the fauces by the pressure of the tongue against the hard palate, the base of the tongue being, at the same time, retracted, and the larynx raised with the pharynx. During the second stage the entrance to the larynx is closed by the drawing forward of the arytenoid cartilages toward the cushion of the epiglottis—a movement produced by the contraction of the Thyreoarytaenoidei, the Arytaenoidei, and the Arytaenoepiglottidei.

After leaving the tongue the bolus passes on to the posterior or laryngeal surface of the epiglottis, and glides along this for a certain distance; then the Glossopalatini, the constrictors of the fauces, contract behind it; the palatine velum is slightly raised by the Levator veli palatini, and made tense by the Tensor veli palatini; and the Pharyngopalatini, by their contraction, pull the pharynx upward over the bolus, and come nearly together, the uvula filling up the slight interval between them. By these means the food is prevented from passing into the nasal part of the pharynx; at the same time, the Pharyngopalatini form an inclined plane, directed obliquely downward and backward along the under surface of which the bolus descends into, the lower part of the pharynx. The Salpingopharyngei raise the upper and lateral parts of the pharynx—i. e., those parts which are above the points where the Stylopharyngei are attached to the pharynx.

**Mucous Membrane.**—The *mucous membrane of the soft palate* is thin, and covered with stratified squamous epithelium on both surfaces, excepting near the pharyngeal ostium of the auditory tube, where it is columnar and ciliated. According to Klein, the mucous membrane on the

<sup>1</sup> "The Innervation of the Soft Palate," by Aldren Turner, *Journal of Anatomy and Physiology*, xxiii, 523.



nasal surface of the soft palate in the fetus is covered throughout by columnar ciliated epithelium, which subsequently becomes squamous; some anatomists state that it is covered with columnar ciliated epithelium, except at its free margin, throughout life. Beneath the mucous membrane on the oral surface of the soft plate is a considerable amount of adenoid tissue. The palatine glands form a continuous layer on its posterior surface and around the uvula.

**Vessels and Nerves.**—The **arteries** supplying the palate are the descending palatine branch of the internal maxillary, the ascending palatine branch of the external maxillary, and the palatine branch of the ascending pharyngeal. The **veins** end chiefly in the pterygoid and tonsillar plexuses. The **lymphatic vessels** pass to the deep cervical glands. The **sensory nerves** are derived from the palatine and nasopalatine nerves and from the glossopharyngeal.

**Applied Anatomy.**—The occurrence of a congenital cleft in the palate has been already referred to as a defect in development (page 299). After the operation for the closure of a cleft in the palate, the palatine muscles, especially the Tensor and Levator veli palatini, have a tendency to retard the healing process by active traction upon the line of suture. To obviate this, it is necessary to divide them. This is best done by making longitudinal incisions, on either side, parallel to the cleft and just medial to the pterygoid hamulus, in such a position as to avoid the descending palatine artery. Acquired perforations of the palate are almost invariably the result of the breaking down of syphilitic gummata. The ensuing ulceration may continue until practically the whole palate, both hard and soft, has been destroyed. Tumors of the palate, both innocent and malignant, are occasionally seen.

Paralysis of the soft palate often occurs after diphtheria. It gives rise to a change in the voice, which becomes nasal, and to the regurgitation of fluids down the nose when their swallowing is attempted. On inspection, the palate is seen to hang flaccid and motionless when phonation or deglutition are attempted; it is also anesthetic.




FIG. 929.—Side view of the teeth and jaws.

**The Teeth (*dentes*)** (Figs. 929 to 931).—Man is provided with two sets of teeth, which make their appearance at different periods of life. Those of the first set appear in childhood, and are called the **deciduous** or **milk teeth**. Those of the second set, which also appear at an early period, may continue until old age, and are named **permanent**.

The **deciduous teeth** are twenty in number: four incisors, two canines, and four molars, in each jaw.

The **permanent teeth** are thirty-two in number: four incisors, two canines, four premolars, and six molars, in each jaw.



The dental formulæ may be represented as follows:

<i>Deciduous Teeth.</i>										
	mol.	can.	in.	in.	can.	mol.				
Upper jaw	2	1	2	2	1	2	}	Total	20	
Lower jaw	2	1	2	2	1	2				
<i>Permanent Teeth.</i>										
	mol.	pr. mol.	can.	in.	in.	can.	pr. mol.	mol.		
Upper jaw	3	2	1	2	2	1	2	3	}	
Lower jaw	3	2	1	2	2	1	2	3		
								}		Total 32

**General Characteristics.**—Each tooth consists of three portions: the **crown**, projecting above the gum; the **root**, imbedded in the alveolus; and the **neck**, the constricted portion between the crown and root.




FIG. 930.—Permanent teeth of upper dental arch, seen from below.




FIG. 931.—Permanent teeth of right half of lower dental arch, seen from above.

The roots of the teeth are firmly implanted in depressions within the alveoli; these depressions are lined with periosteum which invests the tooth as far as the neck. At the margins of the alveoli, the periosteum is continuous with the fibrous structure of the gums.

In consequence of the curve of the dental arch, terms such as anterior and posterior, as applied to the teeth, are misleading and confusing. Special terms are therefore used to indicate the different surfaces of a tooth: the surface directed toward the lips or cheek is known as the **labial** or **buccal surface**; that directed toward the tongue is described as the **lingual surface**; those surfaces which touch

neighboring teeth are termed **surfaces of contact**. In the case of the incisor and canine teeth the surfaces of contact are medial and lateral; in the premolar and molar teeth they are anterior and posterior.

The superior dental arch is larger than the inferior, so that in the normal condition the teeth in the maxillæ slightly overlap those of the mandible both in front and at the sides. Since the upper central incisors are wider than the lower, the other teeth in the upper arch are thrown somewhat distally, and the two sets do not quite correspond to each other when the mouth is closed: thus the upper canine tooth rests partly on the lower canine and partly on the first premolar, and the cusps of the upper molar teeth lie behind the corresponding cusps of the lower molar teeth. The two series, however, end at nearly the same point behind; this is mainly because the molars in the upper arch are the smaller.

**The Permanent Teeth** (*dentes permanentes*) (Fig. 932).—The **Incisors** (*dentes incisivi*; *incisive* or *cutting teeth*) are so named from their presenting a sharp cutting edge, adapted for biting the food. They are eight in number, and form the four front teeth in each dental arch.




FIG. 932.—Permanent teeth. Right side. (Burchard.)

The **crown** is directed vertically, and is chisel-shaped, being bevelled at the expense of its lingual surface, so as to present a sharp horizontal cutting edge, which, before being subjected to attrition, presents three small prominent points separated by two slight notches. It is convex, smooth, and highly polished on its labial surface; concave on its lingual surface, where, in the teeth of the upper arch, it is frequently marked by an inverted V-shaped eminence, situated near the gum. This is known as the **basal ridge** or **cingulum**. The **neck** is constricted. The **root** is long, single, conical, transversely flattened, thicker in front than behind, and slightly grooved on either side in the longitudinal direction.

The **upper incisors** are larger and stronger than the lower, and are directed obliquely downward and forward. The central ones are larger than the lateral, and their roots are more rounded.

The **lower incisors** are smaller than the upper: the central ones are smaller than the lateral, and are the smallest of all the incisors. They are placed vertically and are somewhat bevelled in front, where they have been worn down by contact with the overlapping edge of the upper teeth. The cingulum is absent.

The **Canine Teeth** (*dentes canini*) are four in number, two in the upper, and two in the lower arch, one being placed laterally to each lateral incisor. They are larger and stronger than the incisors, and their roots sink deeply into the bones, and cause well-marked prominences upon the surface.

The **crown** is large and conical, very convex on its labial surface, a little hollowed and uneven on its lingual surface, and tapering to a blunted point or cusp, which projects beyond the level of the other teeth. The **root** is single, but longer and thicker than that of the incisors, conical in form, compressed laterally, and marked by a slight groove on each side.

The **upper canine teeth** (popularly called *eye teeth*) are larger and longer than the lower, and usually present a distinct basal ridge.

The **lower canine teeth** (popularly called *stomach teeth*) are placed nearer the middle line than the upper, so that their summits correspond to the intervals between the upper canines and the lateral incisors.

The **Premolars** or **Bicuspid teeth** (*dentes praemolares*) are eight in number, four in each arch. They are situated lateral to and behind the canine teeth, and are smaller and shorter than them.

The **crown** is compressed antero-posteriorly, and surmounted by two pyramidal eminences or cusps, a labial and a lingual, separated by a groove; hence their name **bicuspid**. Of the two cusps the labial is the larger and more prominent. The **neck** is oval. The **root** is generally single, compressed, and presents in front and behind a deep groove, which indicates a tendency in the root to become double. The apex is generally bifid.

The **upper premolars** are larger, and present a greater tendency to the division of their roots than the lower; this is especially the case in the first upper premolar.

The **Molar Teeth** (*dentes molares*) are the largest of the permanent set, and their broad crowns are adapted for grinding and pounding the food. They are twelve in number; six in each arch, three being placed posterior to each of the second premolars.

The **crown** of each is nearly cubical in form, convex on its buccal and lingual surfaces, flattened on its surfaces of contact; it is surmounted by four or five tubercles, or cusps, separated from each other by a crucial depression; hence the molars are sometimes termed **multicuspids**. The **neck** is distinct, large, and rounded.

**Upper Molars.**—As a rule the first is the largest, and the third the smallest of the upper molars. The crown of the first has usually four tubercles; that of the second, three or four; that of the third, three. Each upper molar has three roots, and of these two are buccal and nearly parallel to one another; the third is lingual and diverges from the others as it runs upward. The roots of the third molar (*dens serotinus* or *wisdom-tooth*) are more or less fused together.

**Lower Molars.**—The lower molars are larger than the upper. On the crown of the first there are usually five tubercles; on those of the second and third, four or five. Each lower molar has two roots, an anterior, nearly vertical, and a posterior, directed obliquely backward; both roots are grooved longitudinally, indicating a tendency to division. The two roots of the third molar (*dens serotinus* or *wisdom tooth*) are more or less united.




FIG. 933.—Deciduous teeth. Left side.

**The Deciduous Teeth** (*dentes decidui*; *temporary* or *milk teeth*) (Fig. 933).—The deciduous are smaller than, but, generally speaking, resemble in form, the teeth which bear the same names in the permanent set. The hinder of the two molars is the largest of all the deciduous teeth, and is succeeded by the

second premolar. The first upper molar has only three cusps—two labial, one lingual; the second upper molar has four cusps. The first lower molar has four cusps; the second lower molar has five. The roots of the deciduous molars are

smaller and more divergent than those of the permanent molars, but in other respects bear a strong resemblance to them.

**Structure of the Teeth.**—On making a vertical section of a tooth (Fig. 934), a cavity will be found in the interior of the crown and the centre of each root; it opens by a minute orifice at the extremity of the latter. This is called the **pulp cavity**, and contains the **dental pulp**, a loose connective tissue richly supplied with vessels and nerves, which enter the cavity through the small aperture at the point of each root. Some of the cells of the pulp are arranged as a layer on the wall of the pulp cavity; they are named the **odontoblasts of Waldeyer**, and during the development of the tooth, are columnar in shape, but later on, after the dentin is fully formed, they become flattened and resemble osteoblasts. Each has two fine processes, the outer one passing into a dental canaliculus, the inner being continuous with the processes of the connective-tissue cells of the pulp matrix.




FIG. 934.—Vertical section of a tooth *in situ*.  $\times 15$ . *c* is placed in the pulp cavity, opposite the neck of the tooth; the part above it is the crown, that below is the root. 1. Enamel with radial and concentric markings. 2. Dentin with tubules and incremental lines. 3. Cement or crusta petrosa, with bone corpuscles. 4. Dental periosteum. 5. Mandible.



FIG. 935.—Vertical section of a molar tooth.




FIG. 936.—Vertical section of a premolar tooth. (Magnified.)

The solid portion of the tooth consists of (1) the **ivory** or **dentin**, which forms the bulk of the tooth; (2) the **enamel**, which covers the exposed part of the crown; and (3) a thin layer of bone, the **cement** or **crusta petrosa**, which is disposed on the surface of the root.

The **dentin** (*substantia eburnea*; *ivory*) (Fig. 936) forms the principal mass of a tooth. It is a modification of osseous tissue, from which it differs, however, in structure. On microscopic examination it is seen to consist of a number of minute wavy and branching tubes, the **dental canaliculi**, imbedded in a dense homogeneous substance, the **matrix**.

The **dental canaliculi** (*dental tubules*) (Fig. 937) are placed parallel with one another, and open at their inner ends into the pulp cavity. In their course to the periphery they present two or three curves, and are twisted on themselves in a spiral direction. These canaliculi vary in direction: thus in a tooth of the mandible they are vertical in the upper portion of the crown, becoming oblique and then horizontal in the neck and upper part of the root, while toward the lower part of the root they are inclined downward. In their course they divide and subdivide dichotomously, and, especially in the root, give off minute branches, which join together in loops in the matrix, or end blindly. Near the periphery of the dentin, the finer ramifications of the canaliculi terminate imperceptibly by free ends. The dental canaliculi have definite walls, consisting of an elastic homogeneous membrane, the **dental sheath of Neumann**, which resists the action of acids; they contain slender cylindrical prolongations of the odontoblasts, first described by Tomes, and named **Tomes' fibres** or **dental fibres**.

The **matrix** (*intertubular dentin*) is translucent, and contains the chief part of the earthy matter of the dentin. In it are a number of fine fibrils, which are continuous with the fibrils




FIG. 937.—Transverse section of a portion of the root of a canine tooth.  $\times 300$ .

of the dental pulp. After the earthy matter has been removed by steeping a tooth in weak acid, the animal basis remaining may be torn into laminae which run parallel with the pulp cavity, across the direction of the tubes. A section of dry dentin often displays a series of somewhat parallel lines—the **incremental lines of Salter**. These lines are composed of imperfectly calcified dentin arranged in layers. In consequence of the imperfection in the calcifying process, little irregular cavities are left, termed **interglobular spaces** (Fig. 937). Normally a series of these spaces is found toward the outer surface of the dentin, where they form a layer which is sometimes known as the **granular layer**. They have received their name from the fact that they are surrounded by minute nodules or globules of dentin. Other curved lines may be seen parallel to the surface. These are the **lines of Schreger**, and are due to the optical effect of simultaneous curvature of the dental fibres.

**Chemical Composition.**—According to Berzelius and von Bibra, dentin consists of 28 parts of animal and 72 parts of earthy matter. The animal matter is converted by boiling into gelatin. The earthy matter consists of phosphate of lime, carbonate of lime, a trace of fluoride of calcium, phosphate of magnesium, and other salts.

The **enamel** (*substantia adamantina*) is the hardest and most compact part of the tooth, and forms a thin crust over the exposed part of the crown, as far as the commencement of the root. It is thickest on the grinding surface of the crown, until worn away by attrition, and becomes thinner toward the neck. It consists of minute hexagonal rods or columns

termed **enamel fibres** or **enamel prisms** (*prismata adamantina*). They lie parallel with one another, resting by one extremity upon the dentin, which presents a number of minute depressions for their reception; and forming the free surface of the crown by the other extremity. The columns are directed vertically on the summit of the crown, horizontally at the sides; they are about  $4\mu$  in diameter, and pursue a more or less wavy course. Each column is a six-sided prism and presents numerous dark transverse shadings; these shadings are probably due to the manner in which the columns are developed in successive stages, producing shallow constrictions, as will be subsequently explained. Another series of lines, having a brown appearance, the **parallel striæ** or **colored lines of Retzius**, is seen on section. According to Ebner, they are produced by air in the interprismatic spaces; others believe that they are the result of true pigmentation.

Numerous minute interstices intervene between the enamel fibres near their dentinal ends, a provision calculated to allow of the permeation of fluids from the dental canaliculi into the substance of the enamel.

**Chemical Composition.**—According to von Bibra, enamel consists of 96.5 per cent. of earthy matter, and 3.5 per cent. of animal matter. The earthy matter consists of phosphate of lime, with traces of fluoride of calcium, carbonate of lime, phosphate of magnesium, and other salts. According to Tomes, the enamel contains the merest trace of organic matter.



The **crusta petrosa** or **cement** (*substantia ossea*) is disposed as a thin layer on the roots of the teeth, from the termination of the enamel to the apex of each root, where it is usually very thick. In structure and chemical composition it resembles bone. It contains, sparingly, the lacunæ and canaliculi which characterize true bone; the lacunæ placed near the surface receive the canaliculi radiating from the side of the lacunæ toward the periodontal membrane; and those more deeply placed join with the adjacent dental canaliculi. In the thicker portions of the crusta petrosa, the lamellæ and Haversian canals peculiar to bone are also found.




FIG. 938.—Sagittal section through the first lower deciduous molar of a human embryo 30 mm. long. (Röse.)  $\times 100$ . *L.E.L.* Labiodental lamina, here separated from the dental lamina. *Z.L.* Placed over the shallow dental furrow, points to the dental lamina, which is spread out below to form the enamel germ of the future tooth. *P.p.* Bicuspidate papilla, capped by the enamel germ. *Z.S.* Condensed tissue forming dental sac. *M.E.* Mouth epithelium.

As age advances, the cement increases in thickness, and gives rise to those bony growths or exostoses so common in the teeth of the aged; the pulp cavity also becomes partially filled up by a hard substance, intermediate in structure between dentin and bone (*osteodentin*, Owen; *secondary dentin*, Tomes). It appears to be formed by a slow conversion of the dental pulp, which shrinks, or even disappears.

**Development of the Teeth** (Figs. 938 to 941).—In describing the development of the teeth, the mode of formation of the deciduous teeth must first be considered, and then that of the permanent series.




FIG. 939.—Similar section through the canine tooth of an embryo 40 mm. long. (Röse.)  $\times 100$ . *L.F.* Labiodental furrow. The other lettering as in Fig. 938.

**Development of the Deciduous Teeth.**—The development of the deciduous teeth begins about the sixth week of fetal life as a thickening of the epithelium along the line of the future jaw, the thickening being due to a rapid multiplication of the more deeply situated epithelial cells. As the cells multiply they extend into the subjacent mesoderm, and thus form a ridge or strand of cells imbedded in mesoderm. About the seventh week a longitudinal splitting or cleavage of this strand of cells takes place, and it becomes divided into two strands; the separation begins in front and extends laterally, the process occupying four or five weeks. Of the two strands thus formed, the **labial** forms the **labiodental lamina**; while the other, the **lingual**, is the ridge of cells in connection with which the teeth, both deciduous and permanent, are developed. Hence it is known as the **dental lamina** or **common dental germ**. It forms a flat

band of cells, which grows into the substance of the embryonic jaw, at first horizontally inward, and then, as the teeth develop, vertically, *i. e.*, upward in the upper jaw, and downward in the lower jaw. While still maintaining a horizontal direction it has two edges




FIG. 940.—Vertical section of the mandible of an early human fetus.  $\times 25$ .

—an *attached edge*, continuous with the epithelium lining the mouth, and a *free edge*, projecting inward, and imbedded in the mesodermal tissue of the embryonic jaw. Along its line of attachment to the buccal epithelium is a shallow groove, the **dental furrow**.




FIG. 941.—Longitudinal section of the lower part of a growing tooth, showing the extension of the layer of adamantoblasts beyond the crown to mark off the limit of formation of the dentin of the root. (Röse.) *ad.* Adamantoblasts, continuous below with *ep.sch.*, the epithelial sheath of Hertwig. *d.* Dentin. *en.* Enamel. *od.* Odontoblasts. *p.* Pulp.

About the ninth week the dental lamina begins to develop enlargements along its free border. These are ten in number in each jaw, and each corresponds to a future deciduous tooth. They consist of masses of epithelial cells; and the cells of the deeper part—that is, the part farthest from the margin of the jaw—increase rapidly and spread out in all directions. Each mass thus comes to assume a club shape, connected with the general epithelial lining of the mouth by a narrow neck, embraced by mesoderm. They are now known as **special dental germs**. After a time the lower expanded portion inclines outward, so as to form an angle with the superficial constricted portion, which is sometimes known as the neck of the special dental germ. About the tenth week the mesodermal tissue beneath these special dental germs becomes differentiated into papillæ; these grow upward, and come in contact with the epithelial cells of the special dental germs, which become folded over them like a hood or cap. There is, then, at this stage a papilla (or papillæ) which has already begun to assume somewhat the shape of the crown of the future tooth, and from which the dentin and pulp of the tooth are formed, surmounted by a dome or cap of epithelial cells from which the enamel is derived.

In the meantime, while these changes have been going on, the dental lamina has been extending backward behind the special dental germ corresponding to the second deciduous molar tooth, and at about the seventeenth week it presents an enlargement, the special dental germ, for the first permanent molar, soon followed by the formation of a papilla in the mesodermal tissue for the same tooth. This is followed, about the sixth month after birth, by a further extension backward of the dental lamina, with the formation

of another enlargement and its corresponding papilla for the second molar. And finally the process is repeated for the third molar, its papilla appearing about the fifth year of life.

After the formation of the special dental germs, the dental lamina undergoes atrophic changes and becomes cribriform, except on the lingual and lateral aspects of each of the special germs of the temporary teeth, where it undergoes a local thickening forming the special dental germ of each of the successional permanent teeth—i. e., the ten anterior ones in each jaw. Here the same process goes on as has been described in connection with those of the deciduous teeth: that is, they recede into the substance of the gum behind the germs of the deciduous teeth. As they recede they become club-shaped, form expansions at their distal extremities, and finally meet papillæ, which have been formed in the mesoderm, just in the same manner as was the case in the deciduous teeth. The apex of each papilla indents the dental germ, which encloses it, and, forming a cap for it, becomes converted into the enamel, while the papilla forms the dentin and pulp of the permanent tooth.

The special dental germs consist at first of rounded or polyhedral epithelial cells; after the formation of the papillæ, these cells undergo a differentiation into three layers. Those which are in immediate contact with the papilla become elongated, and form a layer of well-marked columnar epithelium coating the papilla. They are the cells which form the enamel fibres, and are therefore termed **enamel cells** or **adamantoblasts**. The cells of the outer layer of the special dental germ, which are in contact with the inner surface of the dental sac, presently to be described, are much shorter, cubical in form, and are named the **external enamel epithelium**. All the intermediate round cells of the dental germ between these two layers undergo a peculiar change. They become stellate in shape and develop processes, which unite to form a net-work into which fluid is secreted; this has the appearance of a jelly, and to it the name of **enamel pulp** is given. This transformed special dental germ is now known under the name of **enamel organ** (Fig. 940).

While these changes are going on, a sac is formed around each enamel organ from the surrounding mesodermal tissue. This is known as the **dental sac**, and is a vascular membrane of connective tissue. It grows up from below, and thus encloses the whole tooth germ; as it grows it causes the neck of the enamel organ to atrophy and disappear; so that all communication between the enamel organ and the superficial epithelium is cut off. At this stage there are vascular papillæ surmounted by caps of epithelial cells, the whole being surrounded by by membranous sacs.

*Formation of the Enamel.*—The enamel is formed exclusively from the enamel cells or adamantoblasts of the special dental germ, either by direct calcification of the columnar cells, which become elongated into the hexagonal rods of the enamel; or, as is more generally believed, as a secretion from the adamantoblasts, within which calcareous matter is subsequently deposited.

The process begins at the apex of each cusp, at the ends of the enamel cells in contact with the dental papilla. Here a fine globular deposit takes place, being apparently shed from the end of the adamantoblasts. It is known by the name of the **enamel droplet**, and resembles keratin in its resistance to the action of mineral acids. This droplet then becomes fibrous and calcifies and forms the first layer of the enamel; a second droplet now appears and calcifies, and so on; successive droplets of keratin-like material are shed from the adamantoblasts and form successive layers of enamel, the adamantoblasts gradually receding as each layer is produced, until at the termination of the process they have almost disappeared. The intermediate cells of the enamel pulp atrophy and disappear, so that the newly formed calcified material and the external enamel epithelium come into apposition. This latter layer, however, soon disappears on the emergence of the tooth beyond the gum. After its disappearance the crown of the tooth is still covered by a distinct membrane, which persists for some time. This is known as the **cuticula dentis**, or **Nasmyth's membrane**, and is believed to be the last-formed layer of enamel derived from the adamantoblasts, which has not become calcified. It forms a horny layer, which may be separated from the subjacent calcified mass by the action of strong acids. It is marked by the hexagonal impressions of the enamel prisms, and, when stained by nitrate of silver, shows the characteristic appearance of epithelium.

*Formation of the Dentin.*—While these changes are taking place in the epithelium to form the enamel, contemporaneous changes occurring in the differentiated mesoderm of the dental papillæ result in the formation of the dentin. As before stated, the first germs of the dentin are the papillæ, corresponding in number to the teeth, formed from the soft mesodermal tissue which bounds the depressions containing the special enamel germs. The papillæ grow upward into the enamel germs and become covered by them, both being enclosed in a vascular connective tissue, the **dental sac**, in the manner above described. Each papilla then constitutes the formative pulp from which the dentin and permanent pulp are developed; it consists of rounded cells and is very vascular, and soon begins to assume the shape of the future tooth. The next step is the appearance of the **odontoblasts**, which have a relation to the development of the teeth similar to that of the osteoblasts to the formation of bone. They are formed from the cells of the periphery of the papilla—that is to say, from the cells in immediate contact with the adamantoblasts of the special dental germ. These cells become elongated, one end of the

elongated cell resting against the epithelium of the special dental germs, the other being tapered and often branched. By the direct transformation of the peripheral ends of these cells, or by a secretion from them, a layer of uncalcified matrix (**pro-dentin**) is formed which caps the cusp or cusps, if there are more than one, of the papillæ. This matrix becomes fibrillated, and in its islets of calcification make their appearance, and coalescing give rise to a continuous layer of calcified material which covers each cusp and constitutes the first layer of dentin. The odontoblasts, having thus formed the first layer, retire toward the centre of the papilla, and, as they do so, produce successive layers of dentin from their peripheral extremities—that is to say, they form the dentinal matrix in which calcification subsequently takes place. As they thus recede from the periphery of the papilla, they leave behind them filamentous processes of cell protoplasm, provided with finer side processes; these are surrounded by calcified material, and thus form the dental canaliculi, and, by their side branches, the anastomosing canaliculi: the processes of protoplasm contained within them constitute the **dentinal fibres** (*Tomes' fibres*). In this way the entire thickness of the dentin is developed, each canaliculus being completed throughout its whole length by a single odontoblast. The central part of the papilla does not undergo calcification, but persists as the pulp of the tooth. In this process of formation of dentin it has been shown that an uncalcified matrix is first developed, and that in this matrix islets of calcification appear which subsequently blend together to form a cap to each cusp: in like manner successive layers are produced, which ultimately become blended with each other. In certain places this blending is not complete, portions of the matrix remaining uncalcified between the successive layers; this gives rise to little spaces, which are the interglobular spaces alluded to above.

*Formation of the Cement.*—The root of the tooth begins to be formed shortly before the crown emerges through the gum, but is not completed until some time afterward. It is produced by a downgrowth of the epithelium of the dental germ, which extends almost as far as the situation of the apex of the future root, and determines the form of this portion of the tooth. This fold of epithelium is known as the **epithelial sheath**, and on its papillary surface odontoblasts appear, which in turn form dentin, so that the dentin formation is identical in the crown and root of the tooth. After the dentin of the root has been developed, the vascular tissues of the dental sac begin to break through the epithelial sheath, and spread over the surface of the root as a layer of bone-forming material. In this osteoblasts make their appearance, and the process of ossification goes on in identically the same manner as in the ordinary intramembranous ossification of bone. In this way the cement is formed, and consists of ordinary bone containing canaliculi and lacunæ.

*Formation of the Alveoli.*—About the fourteenth week of embryonic life the dental lamina becomes enclosed in a trough or groove of mesodermal tissue, which at first is common to all the dental germs, but subsequently becomes divided by bony septa into loculi, each loculus containing the special dental germ of a deciduous tooth and its corresponding permanent tooth. After birth each cavity becomes subdivided, so as to form separate loculi (the future alveoli) for the deciduous tooth and its corresponding permanent tooth. Although at one time the whole of the growing tooth is contained in the cavity of the alveolus, the latter never completely encloses it, since there is always an aperture over the top of the crown filled by soft tissue, by which the dental sac is connected with the surface of the gum, and which in the permanent teeth is called the **gubernaculum dentis**.

*Development of the Permanent Teeth.*—The permanent teeth as regards their development may be divided into two sets: (1) those which replace the deciduous teeth, and which, like them, are ten in number in each jaw: these are the **successional permanent teeth**; and (2) those which have no deciduous predecessors, but are superadded distal to the temporary dental series. These are three in number on either side in each jaw, and are termed **superadded permanent teeth**. They are the three molars of the permanent set, the molars of the deciduous set being replaced by the premolars of the permanent set. The development of the successional permanent teeth—the ten anterior ones in either jaw—has already been indicated. During their development the permanent teeth, enclosed in their sacs, come to be placed on the lingual side of the deciduous teeth and more distant from the margin of the future gum, and, as already stated, are separated from them by bony partitions. As the crown of the permanent tooth grows, absorption of these bony partitions and of the root of the deciduous tooth takes place, through the agency of **osteoclasts**, which appear at this time, and finally nothing but the crown of the deciduous tooth remains. This is shed or removed, and the permanent tooth takes its place.

The superadded permanent teeth are developed in the manner already described, by extensions backward of the posterior part of the dental lamina in each jaw.

*Eruption of the Teeth.*—When the calcification of the different tissues of the tooth is sufficiently advanced to enable it to bear the pressure to which it will be afterward subjected, eruption takes place, the tooth making its way through the gum. The gum is absorbed by the pressure of the crown of the tooth against it, which is

itself pressed up by the increasing size of the root. At the same time the septa between the dental sacs ossify, and constitute the alveoli; these firmly embrace the necks of the teeth, and afford them a solid basis of support.

The eruption of the deciduous teeth commences about the seventh month after birth, and is completed about the end of the second year, the teeth of the lower jaw preceding those of the upper.

The following, according to C. S. Tomes, are the most usual times of eruption:

Lower central incisors . . . . .	6 to 9 months.
Upper incisors . . . . .	8 to 10 months.
Lower lateral incisors and first molars . . . . .	15 to 21 months.
Canines . . . . .	16 to 20 months.
Second molars . . . . .	20 to 24 months.

There are, however, considerable variations in these times; thus, according to Holt:

At the age of 1 year a child should have	6 teeth.
" " $1\frac{1}{2}$ years " "	12 "
" " 2 " " "	16 "
" " $2\frac{1}{2}$ " " "	20 "

Calcification of the permanent teeth proceeds in the following order in the lower jaw (in the upper jaw it takes place a little later): the first molar, soon after birth; the central and lateral incisors, and the canine, about six months after birth; the premolars, at the second year, or a little later; the second molar, about the end of the second year; the third molar, about the twelfth year.

The eruption of the permanent teeth takes place at the following periods, the teeth of the lower jaw preceding those of the upper by short intervals:

First molars . . . . .	6th year.
Two central incisors . . . . .	7th year.
Two lateral incisors . . . . .	8th year.
First premolars . . . . .	9th year.
Second premolars . . . . .	10th year.
Canines . . . . .	11th to 12th year.
Second molars . . . . .	12th to 13th year.
Third molars . . . . .	17th to 25th year.

Toward the sixth year, before the shedding of the deciduous teeth begins, there are twenty-four teeth in each jaw, viz., the ten deciduous teeth and the crowns of all the permanent teeth except the third molars.

**Applied Anatomy.**—As a consequence of local irritation or of chronic digestive disturbances occurring during their eruption, both the deciduous and the permanent teeth may show defective development or irregular transverse furrowing and erosions; this is particularly the case with the incisors. Quite distinct from and much less common than this is a characteristic malformation of the two upper central permanent incisors seen in patients with inherited syphilis, and first described by Hutchinson. Here there is a crescentic notch in the anterior surface and at the cutting edge of the tooth, which is peg-shaped, stunted, and often also set obliquely in the gum, pointing either inward or outward. Numerous forms of innocent *tumor* arising from the teeth, or from their constituent layers, have been described under the general name of *odontoma*. Infection of the pulp of a tooth by bacteria gaining access thereto in consequence of dental caries gives rise to the common and very painful *alveolar abscess*; starting in the apical space between the root of the tooth and its alveolar socket, the pus from such an abscess may make its way into the maxillary antrum, or burst through the hard palate or cheek. A more superficial abscess forming between the root of a tooth and the gum is known as a *gum-boil*.

**The Tongue** (*lingua*).—The tongue is the principal organ of the sense of taste, and an important organ of speech; it also assists in the mastication and deglutition



of the food. It is situated in the floor of the mouth, within the curve of the body of the mandible.

Its **Root** (*radix linguae; base*) (Fig. 906) is directed backward, and connected with the hyoid bone by the Hyoglossi and Genioglossi muscles and the hyoglossal membrane; with the epiglottis by three folds (*glossoepiglottic*) of mucous membrane; with the soft palate by the glossopalatine arches; and with the pharynx by the Constrictores pharyngis superiores and the mucous membrane.

Its **Apex** (*apex linguae; tip*), thin and narrow, is directed forward against the lingual surfaces of the lower incisor teeth.




FIG. 942.—The mouth cavity. The apex of the tongue is turned upward, and on the right side a superficial dissection of its under surface has been made.

Its **Inferior Surface** (*facies inferior linguae; under surface*) (Fig. 942) is connected with the mandible by the Genioglossi; the mucous membrane is reflected from it to the lingual surface of the gum and on to the floor of the mouth, where, in the middle line, it is elevated into a distinct vertical fold, the **frenulum linguae**. On either side lateral to the frenulum is a slight fold of the mucous membrane, the **plica fimbriata**, the free edge of which occasionally exhibits a series of fringe-like processes.

The apex of the tongue, part of the inferior surface, the sides, and dorsum are free.

The **Dorsum of the Tongue** (*dorsum linguae*) (Fig. 943) is convex and marked by a **median sulcus**, which divides it into symmetrical halves; this sulcus ends behind, about 2.5 cm. from the root of the organ, in a depression, the **foramen cecum**, from which a shallow groove, the **sulcus terminalis**, runs lateralward and forward on either side to the margin of the tongue. The part of the dorsum of the tongue

in front of this groove, forming about two-thirds of its surface, looks upward, and is rough and covered with papillæ; the posterior third looks backward, and is smoother, and contains numerous muciparous glands and lymph follicles (*lingual tonsil*). The foramen cecum is the remains of the upper part of the **thyroglossal duct** or diverticulum from which the thyroid gland is developed; the pyramidal lobe of the thyroid gland indicates the position of the lower part of the duct.




FIG. 943.—The mouth cavity. The cheeks have been slit transversely and the tongue pulled forward.

The **Papillæ of the Tongue** (Fig. 943) are projections of the corium. They are thickly distributed over the anterior two-thirds of its dorsum, giving to this surface its characteristic roughness. The varieties of papillæ met with are the **papillæ vallatae**, **papillæ fungiformes**, **papillæ filiformes**, and **papillæ simplices**.

The **papillæ vallatae** (*circumvallate papillae*) (Fig. 944) are of large size, and vary from eight to twelve in number. They are situated on the dorsum of the tongue immediately in front of the foramen cecum and sulcus terminalis, forming a row on either side; the two rows run backward and medialward, and meet in the middle line, like the limbs of the letter V inverted. Each papilla consists of a projection of mucous membrane from 1 to 2 mm. wide, attached to the bottom of a circular depression of the mucous membrane; the margin of the depression is elevated to form a wall (*vallum*), and between this and the papilla is a circular sulcus termed

of the food. It is situated in the floor of the mouth, within the curve of the body of the mandible.

Its **Root** (*radix linguae; base*) (Fig. 906) is directed backward, and connected with the hyoid bone by the Hyoglossi and Genioglossi muscles and the hyoglossal membrane; with the epiglottis by three folds (*glossoepiglottic*) of mucous membrane; with the soft palate by the glossopalatine arches; and with the pharynx by the Constrictores pharyngis superiores and the mucous membrane.

Its **Apex** (*apex linguae; tip*), thin and narrow, is directed forward against the lingual surfaces of the lower incisor teeth.




FIG. 942.—The mouth cavity. The apex of the tongue is turned upward, and on the right side a superficial dissection of its under surface has been made.

Its **Inferior Surface** (*facies inferior linguae; under surface*) (Fig. 942) is connected with the mandible by the Genioglossi; the mucous membrane is reflected from it to the lingual surface of the gum and on to the floor of the mouth, where, in the middle line, it is elevated into a distinct vertical fold, the **frenulum linguae**. On either side lateral to the frenulum is a slight fold of the mucous membrane, the **plica fimbriata**, the free edge of which occasionally exhibits a series of fringe-like processes.

The apex of the tongue, part of the inferior surface, the sides, and dorsum are free.

The **Dorsum of the Tongue** (*dorsum linguae*) (Fig. 943) is convex and marked by a **median sulcus**, which divides it into symmetrical halves; this sulcus ends behind, about 2.5 cm. from the root of the organ, in a depression, the **foramen cecum**, from which a shallow groove, the **sulcus terminalis**, runs lateralward and forward on either side to the margin of the tongue. The part of the dorsum of the tongue



in front of this groove, forming about two-thirds of its surface, looks upward, and is rough and covered with papillæ; the posterior third looks backward, and is smoother, and contains numerous muciparous glands and lymph follicles (*lingual tonsil*). The foramen cecum is the remains of the upper part of the **thyroglossal duct** or diverticulum from which the thyroid gland is developed; the pyramidal lobe of the thyroid gland indicates the position of the lower part of the duct.




FIG. 943.—The mouth cavity. The cheeks have been slit transversely and the tongue pulled forward.

The **Papillæ of the Tongue** (Fig. 943) are projections of the corium. They are thickly distributed over the anterior two-thirds of its dorsum, giving to this surface its characteristic roughness. The varieties of papillæ met with are the **papillæ vallatæ**, **papillæ fungiformes**, **papillæ filiformes**, and **papillæ simplices**.

The **papillæ vallatæ** (*circumvallate papillæ*) (Fig. 944) are of large size, and vary from eight to twelve in number. They are situated on the dorsum of the tongue immediately in front of the foramen cecum and sulcus terminalis, forming a row on either side; the two rows run backward and medialward, and meet in the middle line, like the limbs of the letter V inverted. Each papilla consists of a projection of mucous membrane from 1 to 2 mm. wide, attached to the bottom of a circular depression of the mucous membrane; the margin of the depression is elevated to form a wall (*vallum*), and between this and the papilla is a circular sulcus termed

the fossa. The papilla is shaped like a truncated cone, the smaller end being directed downward and attached to the tongue, the broader part or base projecting a little above the surface of the tongue and being studded with numerous small secondary papillæ and covered by stratified squamous epithelium.




FIG. 944.—Vertical section of vallate papilla from the calf. (Engelmann.) A. The papilla. B. The surrounding wall. n. Nerves. d. Duct of a lingual gland.



FIG. 945.—A filiform papilla. Magnified

The **papillæ fungiformes** (*fungiform papillæ*) (Fig. 946), more numerous than the preceding, are found chiefly at the sides and apex, but are scattered irregularly and sparingly over the dorsum. They are easily recognized, among the other papillæ, by their large size, rounded eminences, and deep red color. They are narrow at their attachment to the tongue, but broad and rounded at their free extremities, and covered with secondary papillæ.



FIG. 946.—Section of a fungiform papilla. Magnified.

The **papillæ filiformes** (*filiform or conical papillæ*) (Fig. 945) cover the anterior two-thirds of the dorsum. They are very minute, filiform in shape, and arranged in lines parallel with the two rows of the papillæ vallatæ, excepting at the apex of the organ, where their direction is transverse. Projecting from their apices are numerous filamentous processes, or secondary papillæ; these are of a whitish tint, owing to the thickness and density of the epithelium of which they are composed, and which has here undergone a peculiar modification, the cells having become cornified and elongated into dense, imbricated, brush-like processes. They contain also a number of elastic fibres, which render them firmer and more elastic than the papillæ of mucous membrane generally. The larger and longer papillæ of this group are sometimes termed **papillæ conicæ**.

The **papillæ simplices** are similar to those of the skin, and cover the whole of the mucous membrane of the tongue, as well as the larger papillæ. They consist of closely set microscopic elevations of the corium, each containing a capillary loop, covered by a layer of epithelium.

**Muscles of the Tongue.**—The tongue is divided into lateral halves by a median fibrous septum which extends throughout its entire length and is fixed below to the hyoid bone. In either half there are two sets of muscles, extrinsic and intrinsic; the former have their origins outside the tongue, the latter are contained entirely within it.



The **extrinsic muscles** (Fig. 947) are:

Genioglossus.

Hyoglossus.

Glossopalatinus.<sup>1</sup>

Chondroglossus.

Styloglossus.




FIG. 947.—Extrinsic muscles of the tongue. Left side.

The **Genioglossus** (*Geniohyoglossus*) is a flat triangular muscle close to and parallel with the median plane, its apex corresponding with its point of origin from the mandible, its base with its insertion into the tongue and hyoid bone. It *arises* by a short tendon from the superior mental spine on the inner surface of the symphysis menti, immediately above the Geniohyoideus, and from this point spreads out in a fan-like form. The inferior fibres extend downward, to be attached by a thin aponeurosis to the upper part of the body of the hyoid bone, a few passing between the Hyoglossus and Chondroglossus to blend with the Constrictores pharyngis; the middle fibres pass backward, and the superior ones upward and forward, to enter the whole length of the under surface of the tongue, from the root to the apex. The muscles of opposite sides are separated at their insertions by the median fibrous septum of the tongue; in front, they are more or less blended owing to the decussation of fasciculi in the median plane.

The **Hyoglossus**, thin and quadrilateral, *arises* from the side of the body and from the whole length of the greater cornu of the hyoid bone, and passes almost vertically upward to enter the side of the tongue, between the Styloglossus and Longitudinalis inferior. The fibres arising from the body of the hyoid bone overlap those from the greater cornu.

**Relations.**—The Hyoglossus is in relation by its *superficial surface* with the Digastricus, the Stylohyoideus, Styloglossus, and Mylohyoideus, the submaxillary ganglion, the lingual and

<sup>1</sup> The *Glossopalatinus* (*Palatoglossus*), although one of the muscles of the tongue, is more closely associated with the soft palate both in situation and function; it has consequently been described with the muscles of that structure (p. 1114).

hypoglossal nerves, the ranine vein, the sublingual gland, the deep portion of the submaxillary gland, and the submaxillary duct. By its *deep surface* it is in relation with the stylohyoid ligament, the Genioglossus, Longitudinalis inferior, and Constrictor pharyngis medius, the lingual vessels, and the glossopharyngeal nerve.

The **Chondroglossus** is sometimes described as a part of the Hyoglossus, but is separated from it by fibres of the Genioglossus, which pass to the side of the pharynx. It is about 2 cm. long, and *arises* from the medial side and base of the lesser cornu and contiguous portion of the body of the hyoid bone, and passes directly upward to blend with the intrinsic muscular fibres of the tongue, between the Hyoglossus and Genioglossus.

A small slip of muscular fibres is occasionally found, arising from the cartilago triticea in the lateral hyothyroid ligament and entering the tongue with the hindmost fibres of the Hyoglossus.

The **Styloglossus**, the shortest and smallest of the three styloid muscles, *arises* from the anterior and lateral surfaces of the styloid process, near its apex, and from the stylomandibular ligament. Passing downward and forward between the internal and external carotid arteries, it divides upon the side of the tongue into two portions: one, longitudinal, enters the side of the tongue near its dorsal surface, blending with the fibres of the Longitudinalis inferior in front of the Hyoglossus; the other, oblique, overlaps the Hyoglossus and decussates with its fibres.

The **intrinsic muscles** (Fig. 948) are:

Longitudinalis superior.  
Longitudinalis inferior.

Transversus.  
Verticalis.

The **Longitudinalis linguae superior** (*Superior lingualis*) is a thin stratum of oblique and longitudinal fibres immediately underlying the mucous membrane on the dorsum of the tongue. It *arises* from the submucous fibrous layer close to the epiglottis and from the median fibrous septum, and runs forward to the edges of the tongue.

The **Longitudinalis linguae inferior** (*Inferior lingualis*) is a narrow band situated on the under surface of the tongue between the Genioglossus and Hyoglossus. It extends from the root to the apex of the tongue: behind, some of its fibres are connected with the body of the hyoid bone; in front it blends with the fibres of the Styloglossus.

The **Transversus linguae** (*Transverse lingualis*) consists of fibres which *arise* from the median fibrous septum and pass lateralward to be inserted into the submucous fibrous tissue at the sides of the tongue.

The **Verticalis linguae** (*Vertical lingualis*) is found only at the borders of

the forepart of the tongue. Its fibres extend from the upper to the under surface of the organ.

**Applied Anatomy.**—The median fibrous septum of the tongue is very complete, so that the anastomosis between the two lingual arteries is not very free. This is a point of considerable




FIG. 948.—Coronal section of tongue, showing intrinsic muscles. (Altered from Krause.) a. Lingual artery. b. Longitudinalis inferior. c. Hyoglossus. d. Styloglossus. e. Insertion of Transversus. f. Longitudinalis superior. g. Papillae of tongue. h. Vertical fibres of Genioglossus intersecting Transversus. i. Septum.

importance in connection with removal of one-half of the tongue for cancer, an operation frequently resorted to when the disease is strictly confined to one side of the organ. If the mucous membrane be divided exactly in the middle line, the tongue can be split into halves, without any appreciable hemorrhage, and the diseased half can then be removed.

**Nerves.**—The muscles of the tongue described above are supplied by the hypoglossal nerve.

**Actions.**—The movements of the tongue, although numerous and complicated, may be understood by carefully considering the direction of the fibres of its muscles. The Genioglossi, by means of their posterior fibres, draw the root of the tongue forward, and protrude the apex from the mouth. The anterior fibres draw the tongue back into the mouth. The two muscles acting in their entirety draw the tongue downward, so as to make its superior surface concave from side to side, forming a channel along which fluids may pass toward the pharynx, as in sucking. The Hyoglossi depress the tongue, and draw down its sides. The Styloglossi draw the tongue upward and backward. The Glossopalatini draw the root of the tongue upward. The intrinsic muscles are mainly concerned in altering the shape of the tongue, whereby it becomes shortened, narrowed, or curved in different directions; thus, the Longitudinalis superior and inferior tend to shorten the tongue, but the former, in addition, turn the tip and sides upward so as to render the dorsum concave, while the latter pull the tip downward and render the dorsum convex. The Transversus narrows and elongates the tongue, and the Verticalis flattens and broadens it. The complex arrangement of the muscular fibres of the tongue, and the various directions in which they run, give to this organ the power of assuming the forms necessary for the enunciation of the different consonantal sounds; and Macalister states "there is reason to believe that the musculature of the tongue varies in different races owing to the hereditary practice and habitual use of certain motions required for enunciating the several vernacular languages."

**Structure of the Tongue.**—The tongue is partly invested by mucous membrane and a sub-mucous fibrous layer.

The **mucous membrane** (*tunica mucosa linguae*) differs in different parts. That covering the under surface of the organ is thin, smooth, and identical in structure with that lining the rest of the oral cavity. The mucous membrane of the dorsum of the tongue behind the foramen cecum and sulcus terminalis is thick and freely movable over the subjacent parts. It contains a large number of lymphoid follicles, which together constitute what is sometimes termed the **lingual tonsil**. Each follicle forms a rounded eminence, the centre of which is perforated by a minute orifice leading into a funnel-shaped cavity or recess; around this recess are grouped numerous oval or rounded nodules of lymphoid tissue, each enveloped by a capsule derived from the submucosa, while opening into the bottom of the recesses are also seen the ducts of mucous glands. The mucous membrane on the anterior part of the dorsum of the tongue is thin, intimately adherent to the muscular tissue, and presents numerous minute surface eminences, the **papillae** of the tongue. It consists of a layer of connective tissue, the **corium** or **mucosa**, covered with epithelium.

The epithelium is of the stratified squamous variety, similar to but much thinner than that of the skin; and each papilla has a separate investment from root to summit. The deepest cells may sometimes be detached as a separate layer, corresponding to the rete mucosum, but they never contain coloring matter.

The **corium** consists of a dense felt-work of fibrous connective tissue, with numerous elastic fibres, firmly connected with the fibrous tissue forming the septa between the muscular bundles of the tongue. It contains the ramifications of the numerous vessels and nerves from which the papillae are supplied, large plexuses of lymphatic vessels, and the glands of the tongue.

**Structure of the Papillae.**—The papillae apparently resemble in structure those of the cutis, consisting of cone-shaped projections of connective tissue, covered with a thick layer of stratified squamous epithelium, and containing one or more capillary loops among which nerves are distributed in great abundance. If the epithelium be removed, it will be found that they are not simple elevations like the papillae of the skin, for the surface of each is studded with minute conical processes which form secondary papillae. In the papillae vallatae, the nerves are numerous and of large size; in the papillae fungiformes they are also numerous, and end in a plexiform net-work, from which brush-like branches proceed; in the papillae filiformes, their mode of termination is uncertain.

**Glands of the Tongue.**—The tongue is provided with mucous and serous glands.

The **mucous glands** are similar in structure to the labial and buccal glands. They are found especially at the back part behind the vallate papillae, but are also present at the apex and marginal parts. In this connection the anterior lingual glands (Blandin or Nuhn) require special notice. They are situated on the under surface of the apex of the tongue (Fig. 942), one on either side of the frenulum, where they are covered by a fasciculus of muscular fibres derived from the Styloglossus and Longitudinalis inferior. They are from 12 to 25 mm. long, and about 8 mm. broad, and each opens by three or four ducts on the under surface of the apex.

The **serous glands** occur only at the back of the tongue in the neighborhood of the taste-buds, their ducts opening for the most part into the fossae of the vallate papillae. These glands are racemose, the duct of each branching into several minute ducts, which end in alveoli, lined by

a single layer of more or less columnar epithelium. Their secretion is of a watery nature, and probably assists in the distribution of the substance to be tasted over the taste area. (Ebner.)

The **septum** consists of a vertical layer of fibrous tissue, extending throughout the entire length of the median plane of the tongue, though not quite reaching the dorsum. It is thicker behind than in front, and occasionally contains a small fibrocartilage, about 6 mm. in length. It is well displayed by making a vertical section across the organ.

The **hyoglossal membrane** is a strong fibrous lamina, which connects the under surface of the root of the tongue to the body of the hyoid bone. This membrane receives, in front, some of the fibres of the Genioglossi.

**Taste-buds**, the end-organs of the gustatory sense, are scattered over the mucous membrane of the mouth and tongue at irregular intervals. They occur especially in the sides of the vallate papillæ. In the rabbit there is a localized area at the side of the base of the tongue, the **papilla foliata**, in which they are especially abundant (Fig. 949). They are described under the organs of the senses (page 1007).



FIG. 949.—Vertical section of papilla foliata of the rabbit, passing across the folia. (Ranvier.) *a*. Serous gland. *g*. Gustatory calyculus. *n*. Nerve bundles. *p*. Central lamina of corium. *p'*. Lateral lamina. *z*. Section across a sinus-like vein, which traverses the whole length of the folium.

**Vessels and Nerves.**—The main **artery** of the tongue is the lingual branch of the external carotid, but the external maxillary and ascending pharyngeal also give branches to it. The **veins** open into the internal jugular.

The **lymphatics of the tongue** have been described on page 778.

The **sensory nerves of the tongue** are: (1) the lingual branch of the mandibular, which is distributed to the papillæ at the forepart and sides of the tongue, and forms the nerve of ordinary sensibility for its anterior two-thirds; (2) the chorda tympani branch of the facial, which runs in the sheath of the lingual, and is generally regarded as the nerve of taste for the anterior two-thirds; this nerve is a continuation of the sensory root of the facial (*nervus intermedius*); (3) the lingual branch of the glossopharyngeal, which is distributed to the mucous membrane at the base and sides of the tongue, and to the papillæ vallatæ, and which supplies both gustatory filaments and fibres of general sensation to this region; (4) the superior laryngeal, which sends some fine branches to the root near the epiglottis.

**Applied Anatomy.**—The diseases to which the tongue is liable are numerous, and any or all of the structures of which it is composed—muscles, connective tissue, mucous membrane, glands, vessels, nerves, and lymphatics—may be the seat of morbid changes. It is not often the seat of congenital defects, though a few cases of vertical cleft have been recorded, and it is occasionally, though much more rarely than is commonly supposed, the seat of “tongue-tie,” from shortness of the frenulum.

There is one condition which may be regarded as congenital, the so-called macroglossia, though sometimes it does not evidence itself until a year or two after birth. This is an enlargement of the tongue which is due primarily to a dilatation of the lymph channels and a greatly increased development of the lymphatic tissue throughout the organ. This is often aggravated by inflammatory changes induced by injury or exposure, and the tongue may assume enormous dimensions and hang out of the mouth, giving the child an imbecile expression. The treatment consists in excising a V-shaped portion and bringing the cut surfaces together with deeply placed sutures.

Acute inflammation of the tongue, which may be caused by injury and the introduction of some septic or irritating matter, is attended by great swelling from infiltration of its connective

tissue, which is in considerable quantity. This renders the patient incapable of swallowing or speaking, and may seriously impede respiration. It may run on to suppuration, and the formation of an acute abscess.

In all ages the mucous membrane of the tongue has received much sedulous consideration in disease, and it is certain that the amount and the distribution of the "fur" with which it may be covered often give valuable help in diagnosis. The fur consists of proliferating or desquamated epithelium, bound up with inspissated mucus, the debris of food, and bacteria of all sorts. The mucous membrane of the tongue may become chronically inflamed, and presents different appearances in the various stages of the disease, to which the terms leucoplakia and psoriasis linguae have been given. They are usually the result of syphilis.

The tongue is frequently the seat of ulceration, which may arise from many causes, as from the irritation of jagged teeth, dyspepsia, tuberculosis, syphilis, and cancer. Of these the cancerous ulcer is the most important and also the most common. The variety is the squamous epithelioma, which soon develops into an ulcer with an indurated edge. It causes great pain, which speedily extends to all parts supplied with sensation by the trigeminal nerve, especially to the region of the ear (auriculotemporal nerve).

Cancer of the tongue may necessitate removal of a part or the whole of the organ, and many different methods have been adopted for its excision. It may be removed from the mouth by the scissors; this is usually known as Whitehead's method. The mouth is widely opened with a gag, the tongue transfixed with a stout silk ligature, by which to hold and make traction on it; the reflection of mucous membrane from the tongue to the jaw, and the insertion of the Genioglossus, are first divided with a pair of curved, blunt-pointed scissors. The Glossopalatinus is also divided. The tongue can now be pulled well out of the mouth. The base of the tongue is cut through by a series of short snips, each bleeding vessel being dealt with as soon as divided, until the situation of the main artery is reached. The remaining undivided portion of tissue is to be seized with a pair of Wells' forceps, the tongue removed, and the vessel secured. In the event of the artery being accidentally injured, hemorrhage can be at once controlled by passing the forefinger over the tongue till it touches the epiglottis, and then turning it toward the side on which the artery is to be compressed, and pushing it forcibly against the jaw (Heath). In cases where the disease is confined to one side of the tongue, this operation may be modified by splitting the tongue down the centre and removing only the affected half.

In cases where the submaxillary lymph glands are involved, Kocher's operation should be resorted to. Having performed a preliminary tracheotomy, Kocher removes the tongue from the neck by an incision from near the lobule of the auricula, down the anterior border of the Sternocleidomastoideus to the level of the greater cornu of the hyoid bone, then forward to the body of the hyoid bone, and upward to near the symphysis menti. The lingual artery is now secured, and by a careful dissection the submaxillary lymph glands and the tongue are removed. If the lymph glands in the submaxillary region are in any way affected, an extensive dissection of these will be required if there is any chance of eradicating the disease, and for this purpose it will be found necessary to remove the submaxillary salivary gland.

The more recent operations aim at, first, clearing the neck thoroughly of affected glands, both in the submaxillary region and along the carotid sheath, and secondly, removal of the tongue from within the mouth, leaving if possible the mucous membrane of the floor of the mouth intact, so as to avoid soiling the large wound in the neck by discharges from the mouth.

**The Salivary Glands** (Fig. 952).—Three large pairs of salivary glands communicate with the mouth, and pour their secretion into its cavity; they are the **parotid**, **submaxillary**, and **sublingual**.

**Parotid Gland** (*glandulae parotis*).—The parotid gland (Figs. 950, 951), the largest of the three, varies in weight from 14 to 28 gm. It lies upon the side of the face, immediately below and in front of the external ear. The main portion of the gland is superficial, somewhat flattened and quadrilateral in form, and is placed between the ramus of the mandible in front and the mastoid process and Sternocleidomastoideus behind, overlapping, however, both boundaries. Above, it is broad and reaches nearly to the zygomatic arch; below, it tapers somewhat to about the level of a line joining the tip of the mastoid process to the angle of the mandible. The remainder of the gland is irregularly wedge-shaped, and extends deeply inward toward the pharyngeal wall.

The gland is enclosed within a capsule continuous with the deep cervical fascia; the layer covering the superficial surface is dense and closely adherent to the gland; a portion of the fascia, attached to the styloid process and the angle of the mandible, is thickened to form the stylomandibular ligament which intervenes between the parotid and submaxillary glands.



The **anterior surface** of the gland is moulded on the posterior border of the ramus of the mandible, clothed by the Pterygoideus internus and Masseter. The inner lip of the groove dips, for a short distance, between the two Pterygoid muscles,




FIG. 950.—Right parotid gland. Posterior and deep aspects.

while the outer lip extends for some distance over the superficial surface of the Masseter; a small portion of this lip immediately below the zygomatic arch is usually detached, and is named the **accessory part** (*socia parotidis*) of the gland.




FIG. 951.—Right parotid gland. Deep and anterior aspects.

The **posterior surface** is grooved longitudinally and abuts against the external acoustic meatus, the mastoid process, and the anterior border of the Sternocleidomastoideus.

The **superficial surface**, slightly lobulated, is covered by the integument, the superficial fascia containing the facial branches of the great auricular nerve and some small lymph glands, and the fascia which forms the capsule of the gland.

The **deep surface** extends inward by means of two processes, one of which lies on the Digastricus, styloid process, and the styloid group of muscles, and projects under the mastoid process and Sternocleidomastoideus; the other is situated in front of the styloid process, and sometimes passes into the posterior part of the mandibular fossa behind the temporomandibular joint. The deep surface is in contact with the internal and external carotid arteries, the internal jugular vein, and the vagus and glossopharyngeal nerves.

The gland is separated from the pharyngeal wall by some loose connective tissue.

**Structures within the Gland.**—The *external carotid artery* lies at first on the deep surface, and then in the substance of the gland. The artery gives off its *posterior auricular* branch which emerges from the gland behind; it then divides into its terminal branches, the *internal maxillary* and *superficial temporal*; the former runs forward deep to the neck of the mandible; the latter runs upward across the zygomatic arch and gives off its *transverse facial* branch which emerges from the front of the gland. Superficial to the arteries are the *superficial temporal* and *internal maxillary veins*, uniting to form the *posterior facial vein*; in the lower part of the gland this vein splits into anterior and posterior divisions. The anterior division emerges from the gland and unites with the anterior facial to form the *common facial vein*; the posterior unites in the gland with the posterior auricular to form the *external jugular vein*. On a still more superficial plane is the facial nerve, the branches of which emerge from the borders of the gland. Branches of the *great auricular nerve* pierce the gland to join the facial, while the *auriculotemporal nerve* issues from the upper part of the gland.

The **parotid duct** (*ductus parotideus*; *Stensen's duct*) is about 7 cm. long. It begins by numerous branches from the anterior part of the gland, crosses the Masseter, and at the anterior border of this muscle turns inward nearly at a right angle, passes through the corpus adiposum of the cheek and pierces the Buccinator; it then runs for a short distance obliquely forward between the Buccinator and mucous membrane of the mouth, and opens upon the oral surface of the cheek by a small orifice, opposite the second upper molar tooth. While crossing the Masseter, it receives the duct of the accessory portion; in this position it lies between the branches of the facial nerve; the accessory part of the gland and the transverse facial artery are above it.

**Structure.**—The parotid duct is dense, its wall being of considerable thickness; its canal is about the size of a crow-quill, but at its orifice on the oral surface of the cheek its lumen is greatly reduced in size. It consists of a thick external fibrous coat which contains contractile fibres, and of an internal or mucous coat lined with short columnar epithelium.

**Vessels and Nerves.**—The **arteries** supplying the parotid gland are derived from the external carotid, and from the branches given off by that vessel in or near its substance. The **veins** empty themselves into the external jugular, through some of its tributaries. The **lymphatic** end in the superficial and deep cervical lymph glands, passing in their course through two of three glands, placed on the surface and in the substance of the parotid. The **nerves** are derived from the plexus of the sympathetic on the external carotid artery, the facial, the auriculotemporal, and the great auricular nerves. It is probable that the branch from the auriculotemporal nerve is derived from the glossopharyngeal through the otic ganglion. At all events, in some of the lower animals this has been proved experimentally to be the case.

**Submaxillary Gland** (*glandula submaxillaris*).—The submaxillary gland (Fig. 952) is irregular in form and about the size of a walnut. A considerable part of it is situated in the submaxillary triangle, reaching forward to the anterior belly of the Digastricus and backward to the stylomandibular ligament, which intervenes between it and the parotid gland. Above, it extends under cover of the

body of the mandible; below, it usually overlaps the intermediate tendon of the Digastricus and the insertion of the Stylohyoideus, while from its deep surface a tongue-like *deep process* extends forward above the Mylohyoideus muscle.

Its **superficial surface** consists of an upper and a lower part. The **upper part** is directed outward, and lies partly against the submaxillary depression on the inner surface of the body of the mandible, and partly on the Pterygoideus internus. The **lower part** is directed downward and outward, and is covered by the skin, superficial fascia, Platysma, and deep cervical fascia; it is crossed by the anterior facial vein and by filaments of the facial nerve; in contact with it, near the mandible, are the submaxillary lymph glands.




FIG. 952.—Dissection, showing salivary glands of right side.

The **deep surface** is in relation with the Mylohyoideus, Hyoglossus, Styloglossus, Stylohyoideus, and posterior belly of the Digastricus; in contact with it are the mylohyoid nerve and the mylohyoid and submental vessels.

The external maxillary artery is imbedded in a groove in the posterior border of the gland.

The **deep process** of the gland extends forward between the Mylohyoideus below and externally, and the Hyoglossus and Styloglossus internally; above it, is the lingual nerve and submaxillary ganglion; below it, the hypoglossal nerve and its accompanying vein.

The **submaxillary duct** (*ductus submaxillaris*; *Wharton's duct*) is about 5 cm. long, and its wall is much thinner than that of the parotid duct. It begins by numerous branches from the deep surface of the gland, and runs forward between the Mylohyoideus and the Hyoglossus and Genioglossus, then between the sublingual gland and the Genioglossus, and opens by a narrow orifice on the summit of a small papilla, at the side of the frenulum linguae. On the Hyoglossus it lies between the

lingual and hypoglossal nerves, but at the anterior border of the muscle it is crossed laterally by the lingual nerve; the terminal branches of the lingual nerve ascend on its medial side.

**Vessels and Nerves.**—The arteries supplying the submaxillary gland are branches of the external maxillary and lingual. Its veins follow the course of the arteries. The nerves are derived from the submaxillary ganglion, through which it receives filaments from the chorda tympani of the facial nerve and the lingual branch of the mandibular, sometimes from the mylohyoid branch of the inferior alveolar, and from the sympathetic.

**Sublingual Gland (*glandula sublingualis*).**—The sublingual gland (Fig. 952) is the smallest of the three glands. It is situated beneath the mucous membrane of the floor of the mouth, at the side of the frenulum linguae, in contact with the sublingual depression on the inner surface of the mandible, close to the symphysis. It is narrow, flattened, shaped somewhat like an almond, and weighs nearly 2 gm. It is in relation, *above*, with the mucous membrane; *below*, with the Mylohyoideus; *in front*, with its fellow of the opposite side; *behind*, with the deep part of the submaxillary gland; *laterally*, with the mandible; and *medially*, with the Genioglossus, from which it is separated by the lingual nerve and the submaxillary duct. Its excretory ducts are from eight to twenty in number. Of the **smaller sublingual ducts** (*ducts of Rivinus*), some join the submaxillary duct; others open separately into the mouth, on the elevated crest of mucous membrane (*plica sublingualis*), caused by the projection of the gland, on either side of the frenulum linguae. One or more join to form the **larger sublingual duct** (*duct of Bartholin*), which opens into the submaxillary duct.

**Vessels and Nerves.**—The sublingual gland is supplied with blood from the sublingual and submental arteries. Its nerves are derived from the lingual, the chorda tympani, and the sympathetic.

**Structure of the Salivary Glands.**—The salivary glands are compound racemose glands, consisting of numerous lobes, which are made up of smaller lobules, connected together by dense areolar tissue, vessels, and ducts. Each lobule consists of the ramifications of a single duct, the branches ending in dilated ends or alveoli on which the capillaries are distributed. The alveoli are enclosed by a basement-membrane, which is continuous with the membrana propria of the duct and consists of a net-work of branched and flattened nucleated cells.

The alveoli of the salivary glands are of two kinds, which differ in the appearance of their secreting cells, in their size, and in the nature of their secretion. (1) The mucous variety secretes a viscid fluid, which contains mucin; (2) the serous variety secretes a thinner and more watery fluid. The sublingual gland consists of mucous, the parotid of serous alveoli. The submaxillary contains both mucous and serous alveoli, the latter, however, preponderating.

The cells in the **mucous alveoli** are columnar in shape. In the fresh condition they contain large granules of mucinogen. In hardened preparations a delicate protoplasmic net-work is seen, and the cells are clear and transparent. The nucleus is usually situated near the basement-membrane, and is flattened.

In some alveoli are seen peculiar crescentic bodies, lying between the cells and the membrana propria. They are termed the **crescents of Gianuzzi**, or the **demilunes of Heidenhain** (Fig. 953), and are composed of polyhedral granular cells, which Heidenhain regards as young epithelial cells destined to supply the place of those salivary cells which have undergone disintegration. This view, however, is not accepted by Klein. Fine canaliculi pass between the mucus-secreting cells to reach the demilunes and even penetrate the cells forming these structures.

In the **serous alveoli** the cells almost completely fill the cavity, so that there is hardly any lumen perceptible; they contain secretory granules imbedded in a closely reticulated protoplasm (Fig. 954). The cells are more cubical than those of the mucous type; the nucleus of each is spherical and placed near the centre of the cell, and the granules are smaller.

Both mucous and serous cells vary in appearance according to whether the gland is in a resting condition or has been recently active. In the former case the cells are large and contain many secretory granules; in the latter case they are shrunken and contain few granules, chiefly collected at the inner ends of the cells. The granules are best seen in fresh preparations.

The ducts are lined at their origins by epithelium which differs little from the pavement form. As the ducts enlarge, the epithelial cells change to the columnar type, and the part of the cell next the basement-membrane is finely striated.

The lobules of the salivary glands are richly supplied with bloodvessels which form a dense net-work in the intervalveolar spaces. Fine plexuses of nerves are also found in the interlobular tissue. The nerve fibrils pierce the basement-membrane of the alveoli, and end in branched varicose filaments between the secreting cells. In the hilus of the submaxillary gland there is a collection of nerve cells termed **Langley's ganglion**.




FIG. 953.—Section of submaxillary gland of kitten. Duct semidiagrammatic. X 200.




FIG. 954.—Human submaxillary gland. (R. Heidenhain.) To the right of the figure is a group of mucous alveoli, to the left a group of serous alveoli.

**Accessory Glands.**—Besides the salivary glands proper, numerous other glands are found in the mouth. Many of these glands are found at the posterior part of the dorsum of the tongue behind the vallate papillæ, and also along its margins as far forward as the apex. Others lie around and in the palatine tonsil between its crypts, and large numbers are present in the soft palate, the lips, and cheeks. These glands are of the same structure as the larger salivary glands, and are of the mucous or mixed type.

**Applied Anatomy.**—The parotid glands, and much less often the other salivary glands, are liable to an acute infectious inflammation, known in the case of the parotid as *mumps*. The affected glands swell up, becoming tense, tender, and painful; much pain is felt when swallowing or mastication is attempted, and salivation may or may not occur. The inflammation goes down after a few days; suppuration in the affected glands is very rare.

## THE PHARYNX.

The **pharynx** is that part of the digestive tube which is placed behind the nasal cavities, mouth, and larynx. It is a musculomembranous tube, somewhat conical in form, with the base upward, and the apex downward, extending from the under surface of the skull to the level of the cricoid cartilage in front, and that of the sixth cervical vertebra behind.

The cavity of the pharynx is about 12.5 cm. long, and broader in the transverse than in the antero-posterior diameter. Its greatest breadth is immediately below the base of the skull, where it projects on either side, behind the pharyngeal ostium of the auditory tube, as the **pharyngeal recess** (*fossa of Rosenmüller*); its narrowest point is at its termination in the œsophagus. It is limited, *above*, by the body of the sphenoid and basilar part of the occipital bone; *below*, it is continuous with the œsophagus; *posteriorly*, it is connected by loose areolar tissue with the cervical portion of the vertebral column, and the prevertebral fascia covering the Longus colli and Longus capitis muscles; *anteriorly*, it is incomplete, and is attached in



succession to the medial pterygoid plate, pterygomandibular raphé, mandible, tongue, hyoid bone, and thyroid and cricoid cartilages; *laterally*, it is connected to the styloid processes and their muscles, and is in contact with the common and internal carotid arteries, the internal jugular veins, the glossopharyngeal, vagus, and hypoglossal nerves, and the sympathetics trunks, and above with small parts of the Pterygoidei interni. Seven cavities communicate with it, viz., the two nasal cavities, the two tympanic cavities, the mouth, the larynx, and the oesophagus. The cavity of the pharynx may be subdivided from above downward into three parts: **nasal**, **oral**, and **laryngeal** (Fig. 927).




FIG. 955.—Front of nasal part of pharynx, as seen with the laryngoscope.

The **Nasal Part of the Pharynx** (*pars nasalis pharyngis*; *nasopharynx*) lies behind the nose and above the level of the soft palate: it differs from the oral and laryngeal parts of the pharynx in that its cavity always remains patent. In front (Fig. 955) it communicates through the choanæ with the nasal cavities. On its lateral wall is the **pharyngeal ostium of the auditory tube**, somewhat triangular in shape, and bounded behind by a firm prominence, the **torus** or **cushion**, caused by the medial end of the cartilage of the tube which elevates the mucous membrane. A vertical fold of mucous membrane, the **salpingopharyngeal fold**, stretches from the lower part of the torus; it contains the Salpingopharyngeus muscle. A second and smaller fold, the **salpingopalatine fold**, stretches from the upper part of the torus to the palate. Behind the ostium of the auditory tube is a deep recess, the **pharyngeal recess** (*fossa of Rosenmüller*). On the posterior wall is a prominence, best marked in childhood, produced by a mass of lymphoid tissue, which is known as the **pharyngeal tonsil**. Above the pharyngeal tonsil, in the middle line, an irregular flask-shaped depression of the mucous membrane sometimes extends up as far as the basilar process of the occipital bone; it is known as the **pharyngeal bursa**.

The **oral part of the pharynx** (*pars oralis pharyngis*) reaches from the soft palate to the level of the hyoid bone. It opens anteriorly, through the isthmus faucium, into the mouth, while in its lateral wall, between the two palatine arches, is the **palatine tonsil**.

The **Palatine Tonsils** (*tonsillae palatinae*; *tonsil*) are two prominent masses situated one on either side between the glossopalatine and pharyngopalatine arches. Each tonsil consists fundamentally of an aggregation of lymphoid tissue underlying the mucous membrane between the palatine arches. The lymphoid mass, however, does not completely fill the interval between the two arches, so that a small depression, the **supratonsillar fossa**, exists at the upper part of the interval. Further,

the tonsil extends for a variable distance under cover of the glossopalatine arch, and is here covered by a reduplication of mucous membrane; the upper part of this fold reaches across the supratonsillar fossa, between the two arches, as a thin fold sometimes termed the **plica semilunaris**; the remainder of the fold is called the **plica triangularis**. Between the plica triangularis and the surface of the tonsil is a space known as the **tonsillar sinus**; in many cases, however, this sinus is obliterated by its walls becoming adherent. From this description it will be apparent that a portion of the tonsil is below the level of the surrounding mucous membrane, *i. e.*, is imbedded, while the remainder projects as the visible tonsil. In the child the tonsils are relatively (and frequently absolutely) larger than in the adult, and about one-third of the tonsil is imbedded. After puberty the imbedded portion diminishes considerably in size and the tonsil assumes a disk-like form, flattened from side to side; the shape and size of the tonsil, however, vary considerably in different individuals.




FIG. 956.—Section through one of the crypts of the tonsil. (Stöhr.) Magnified. *e*, Stratified epithelium of general surface, continued into crypt. *f*, *f*, Nodules of lymphoid tissue—opposite each nodule numbers of lymph cells are passing into or through the epithelium. *s*, *s*, Cells which have thus escaped to mix with the saliva as salivary corpuscles.

The **medial surface** of the tonsil is free except anteriorly, where it is covered by the plica triangularis; it presents from twelve to fifteen orifices leading into small crypts or recesses from which numerous follicles branch out into the tonsillar substance.

The **lateral or deep surface** is adherent to a fibrous capsule which is continued into the plica triangularis. It is separated from the inner surface of the Constrictor pharyngis superior usually by some loose connective tissue; this muscle intervenes between the tonsil and the external maxillary artery with its tonsillar and ascending palatine branches. The internal carotid artery lies behind and lateral to the tonsil at a distance of 20 to 25 mm. from it.

The tonsils form part of a circular band of adenoid tissue which guards the opening into the digestive and respiratory tubes. The anterior part of the ring is formed by the submucous adenoid collections (**lingual tonsil**) on the posterior part of the tongue; the lateral portions consist of the palatine tonsils and the adenoid collections in the vicinity of the auditory tubes, while the ring is completed

behind by the pharyngeal tonsil on the posterior wall of the pharynx. In the intervals between these main masses are smaller collections of adenoid tissue.

**Structure** (Fig. 956).—The follicles of the tonsil are lined by a continuation of the mucous membrane of the pharynx, covered with stratified squamous epithelium; around each follicle is a layer of closed capsules consisting of lymphoid tissue imbedded in the submucous tissue. Lymph corpuscles are found in large numbers invading the stratified epithelium. It is probable that they pass into the mouth and form the so-called *salivary corpuscles*. Surrounding each follicle is a close plexus of lymphatics, from which the lymphatic vessels pass to the deep cervical glands in the neighborhood of the greater cornu of the hyoid bone, behind and below the angle of the mandible.

**Vessels and Nerves**.—The arteries supplying the tonsil are the *dorsalis linguae* from the lingual, the ascending palatine and tonsillar from the external maxillary, the ascending pharyngeal from the external carotid, the descending palatine branch of the internal maxillary, and a twig from the small meningeal.

The veins end in the tonsillar plexus, on the lateral side of the tonsil.

The nerves are derived from the sphenopalatine ganglion, and from the glossopharyngeal.

**Applied Anatomy**.—The palatine tonsils can be easily inspected by instructing the patient to throw the head back and open his mouth widely; the tongue at the same time being depressed by a spatula or tongue-depressor. The normal tonsil should not project beyond the plane of the glossopalatine arch. They are prone to become enlarged, especially in tuberculous children; and when much increased in size they cause great trouble, owing to obstruction to respiration and deglutition. The tonsils may be the seat of acute inflammation, which may run on to supuration, requiring evacuation of the pus. The incision into the tonsil should always be made from in front backward and medialward. Another form of acute inflammation of the tonsil is follicular tonsillitis, due to the lodgement of microorganisms in the crypts of the tonsil. The removal of an enlarged tonsil is, as a rule, a very simple operation, and is not usually attended with much hemorrhage, unless the patient is suffering from hemophilia. The tonsil may be the seat of malignant growth, either an epithelioma or a lymphosarcoma.

The **Laryngeal Part of the Pharynx** (*pars laryngea pharyngis*) reaches from the hyoid bone to the lower border of the cricoid cartilage, where it is continuous with the œsophagus. In front it presents the triangular entrance of the larynx, the base of which is directed forward and is formed by the epiglottis, while its lateral boundaries are constituted by the aryepiglottic folds. On either side of the laryngeal orifice is a recess, termed the *sinus piriformis*, which is bounded medially by the aryepiglottic fold, laterally by the thyroid cartilage and hyothyroid membrane.

**Muscles of the Pharynx**.—The muscles of the pharynx (Fig. 957) are:

Constrictor inferior.	Stylopharyngeus.
Constrictor medius.	Salpingopharyngeus.
Constrictor superior.	Pharyngopalatinus. <sup>1</sup>

**Dissection**.—In order to examine the muscles of the pharynx, cut through the trachea and œsophagus just above the sternum, and draw them upward by dividing the loose areolar tissue connecting the pharynx with the front of the vertebral column. The parts being drawn well forward, apply the edge of the saw immediately behind the styloid processes, and saw the base of the skull through from below upward. The pharynx and mouth should then be stuffed with tow, in order to distend its cavity and render the muscles tense and easier of dissection.

The **Constrictor pharyngis inferior** (*Inferior constrictor*), the thickest of the three constrictors, arises from the sides of the cricoid and thyroid cartilage. From the cricoid cartilage it arises in the interval between the Cricothyroideus in front, and the articular facet for the inferior cornu of the thyroid cartilage behind. On the thyroid cartilage it arises from the oblique line on the side of the lamina, from the surface behind this nearly as far as the posterior border and from the inferior cornu. From these origins the fibres spread backward and medialward to be inserted with the muscle of the opposite side into the fibrous raphe in the posterior median line of the pharynx. The inferior fibres are horizontal and continuous with the circular fibres of the œsophagus; the rest ascend, increasing in obliquity, and overlap the Constrictor medius.

<sup>1</sup> The Pharyngopalatinus is described with the muscles of the palate (p. 1114).

**Relations.**—The Constrictor inferior is covered by the thin membrane which surrounds the entire pharynx (*buccopharyngeal fascia*). *Behind*, it is in relation with the vertebral column and the prevertebral fascia and muscles; *laterally*, with the thyroid gland, the common carotid artery, and the Sternothyroideus; by its *internal surface*, with the Constrictor medius, the Stylopharyngeus, the Pharyngopalatinus, the pharyngeal aponeurosis and the mucous membrane of the pharynx. The internal branch of the superior laryngeal nerve and the laryngeal branch of the superior thyroid artery run near the upper border, and the recurrent nerve and the laryngeal branch of the inferior thyroid artery pass beneath the lower border of this muscle, before they enter the larynx.




FIG. 957.—Muscles of the pharynx and cheek.

some lymph glands. Near its origin it is covered by the Hyoglossus, from which it is separated by the lingual vessels. It lies upon the Constrictor superior, the Stylopharyngeus, the Pharyngopalatinus, the pharyngeal aponeurosis, and the mucous membrane of the pharynx.

The **Constrictor pharyngis superior** (*Superior constrictor*) is a quadrilateral muscle, thinner and paler than the other two. It *arises* from the lower third of the posterior margin of the medial pterygoid plate and its hamulus, from the pterygomandibular raphe, from the alveolar process of the mandible above the posterior end of the mylohyoid line, and by a few fibres from the side of the tongue. The fibres curve backward to be inserted into the median raphe, being also prolonged by means of an aponeurosis to the pharyngeal spine on the basilar part of the occipital bone. The superior fibres arch beneath the Levator veli palatini and the auditory tube. The interval between the upper border of the muscle and the base of the skull is closed by the pharyngeal aponeurosis, and is known as the **sinus of Morgagni**.

**Relations.**—The Constrictor superior is in relation by its *outer surface* with the prevertebral fascia and muscles, the vertebral column, the internal carotid and ascending pharyngeal arteries, the internal jugular vein and pharyngeal venous plexus, and the glossopharyngeal, vagus, hypoglossal, and lingual nerves, the sympathetic trunks, the Constrictor medius and Pterygoideus internus, the styloid process, the stylohyoid ligament, and the Stylopharyngeus. By its *internal surface* it is in relation with the Pharyngopalatinus, the capsule of the palatine tonsil, the pharyngeal aponeurosis, and the mucous membrane of the pharynx. Its *lower border* is separated from the Constrictor medius by the Stylopharyngeus and the glossopharyngeal nerve.

The **Stylopharyngeus** (Fig. 947) is a long, slender muscle, cylindrical above, flattened below. It *arises* from the medial side of the base of the styloid process,

passes downward along the side of the pharynx between the Constrictores superior and medius, and spreads out beneath the mucous membrane. Some of its fibres are lost in the Constrictor muscles, while others, joining with the Pharyngopalatinus, are inserted into the posterior border of the thyroid cartilage. The glossopharyngeal nerve runs on the lateral side of this muscle, and crosses over it to reach the tongue.

The **Salpingopharyngeus** (Fig. 928) arises from the inferior part of the auditory tube near its orifice; it passes downward and blends with the posterior fasciculus of the Pharyngopalatinus.

**Nerves.**—The Constrictores and Salpingopharyngeus are supplied by branches from the pharyngeal plexus, the Constrictor inferior by additional branches from the external laryngeal and recurrent nerves, and the Stylopharyngeus by the glossopharyngeal nerve.

**Actions.**—When deglutition is about to be performed, the pharynx is drawn upward and dilated in different directions, to receive the food propelled into it from the mouth. The Stylopharyngei, which are much farther removed from one another at their origin than at their insertion, draw the sides of the pharynx upward and lateralward, and so increase its transverse diameter; its breadth in the antero-posterior direction is increased by the larynx and tongue being carried forward in their ascent. As soon as the bolus of food is received in the pharynx, the elevator muscles relax, the pharynx descends, and the Constrictores contract upon the bolus, and convey it downward into the œsophagus.

**Structure.**—The pharynx is composed of three coats: **mucous, fibrous, and muscular.**

The **pharyngeal aponeurosis, or fibrous coat**, is situated between the mucous and muscular layers. It is thick above where the muscular fibres are wanting, and is firmly connected to the basilar portion of the occipital and the petrous portions of the temporal bones. As it descends it diminishes in thickness, and is gradually lost. It is strengthened posteriorly by a strong fibrous band, which is attached above to the pharyngeal spine on the under surface of the basilar portion of the occipital bone, and passes downward, forming a median raphé, which gives attachment to the Constrictores pharyngis.

The **mucous coat** is continuous with that lining the auditory tubes, the nasal cavities, the mouth, and the larynx. In the nasal part of the pharynx it is covered by columnar ciliated epithelium; in the oral and laryngeal portions the epithelium is stratified squamous. Beneath the mucous membrane are found racemose mucous glands; they are especially numerous at the upper part of the pharynx around the orifices of the auditory tubes.

**Applied Anatomy.**—Hypertrophy of the lymphatic tissue in the nasal part of the pharynx commonly known as “adenoids,” is a frequent cause of mouth-breathing and all its attendant disadvantages and dangers in children. It entails a proneness to inflammation of all parts of the air passages and the auditory tubes, and leads to deformed development of the palate and dental arch. In many cases adenoids tend to atrophy about the age of puberty, by which time their presence is likely to have caused permanent injury to the health and development of the patient.

The pharynx is sometimes the seat of a pouch-like dilatation of its walls, in which the food collects when the patient swallows. A cure is effected by removing the diverticulum and accurately suturing the opening which has been made in the pharynx. The internal carotid artery is in close relation with the pharynx, so that its pulsations can be felt through the mouth. It has been occasionally wounded by sharp-pointed instruments, introduced into the mouth and thrust through the wall of the pharynx. In aneurism of this vessel in the neck, the tumor necessarily bulges into the pharynx, as this is the direction in which it meets with the least resistance, nothing lying between the vessel and the mucous membrane except the thin Constrictor muscles, whereas on the lateral side there are the dense cervical fascia, the muscles descending from the styloid process, and the margin of the Sternocleidomastoideus.

The mucous membrane of the pharynx is very vascular, and is often the seat of inflammation, frequently of a septic character, since the numerous recesses are prone to lodge microorganisms. And, in addition, owing to its exposed situation, the mucous membrane is liable to be irritated by agents introduced during inspiration. The inflammation may be attended with serious consequences: it may extend up the auditory tube and involve the middle ear; it may spread to the entrance of the larynx, causing œdema and seriously interfering with respiration; or, invading the lymphatics, it may spread to the loose areolar tissue surrounding the pharyngeal wall, and may extend far and wide, sometimes into the posterior mediastinal cavity along the œsophagus. Abscess may form in the connective tissue behind the pharynx, between it and the vertebral column, constituting what is known as *retropharyngeal abscess*. This may lead to caries of the cervical vertebrae or may be caused by suppuration of the lymph glands which are situated in this position opposite the axis, and which receive the lymphatics from the cavities. In these cases the pus may be easily evacuated by incision with a guarded blade.



through the mouth, but, for aseptic reasons, it is desirable that the abscess should be opened from the neck. In some instances this is perfectly easy: the abscess can be felt bulging at the side of the neck, and merely requires an incision for its relief; but this is not always so, and then an incision should be made along the posterior border of the Sternocleidomastoideus and the deep fascia divided. A director is now to be inserted into the wound, the forefinger of the left hand being introduced into the mouth and pressure made upon the swelling. This acts as a guide, and the director is to be pushed onward until pus appears in the groove. A pair of sinus forceps is now inserted along the director and the opening into the cavity dilated.

Abscess also occurs in children, underneath the mucous membrane, between it and the pharyngeal aponeurosis. The condition usually arises from a peritonsillar inflammation, which spreads backward. In some cases an enormous swelling may form, which pushes forward the soft palate and gives rise to respiratory obstruction. In such the abscess should be opened through the mouth with the child in the inverted positions, so as to prevent the first gush of pus from entering the superior opening of the larynx.

*Foreign bodies* not infrequently become lodged in the pharynx, and most usually at its termination at about the level of the cricoid cartilage, just beyond the reach of the finger, as the distance from the arch of the teeth to the commencement of the œsophagus is about 15 cm.

### THE ŒSOPHAGUS (Fig. 958).

The **œsophagus** or **gullet** is a muscular canal, about 23 to 25 cm. long, extending from the pharynx to the stomach. It begins in the neck at the lower border of the cricoid cartilage, opposite the sixth cervical vertebra, descends along the front of the vertebral column, through the superior and posterior mediastinal cavities, passes through the Diaphragma, and, entering the abdomen, ends at the cardiac orifice of the stomach, opposite the eleventh thoracic vertebra. The general direction of the œsophagus is vertical; but it presents two slight curves in its course. At its commencement it is placed in the middle line; but it inclines to the left side as far as the root of the neck, gradually passes to the middle line again at the level of the fifth thoracic vertebra, and finally deviates to the left as it passes forward to the œsophageal hiatus in the Diaphragma. The œsophagus also presents antero-posterior flexures corresponding to the curvatures of the cervical and thoracic portions of the vertebral column. It is the narrowest part of the digestive tube, and is most contracted at its commencement, and at the point where it passes through the Diaphragma.

**Relations.**—The **cervical portion** of the œsophagus is in relation, *in front*, with the trachea; and at the lower part of the neck, where it projects to the left side, with the thyroid gland; *behind*, it rests upon the vertebral column and Longus colli muscles; *on either side* it is in relation with the common carotid artery (especially the left, as it inclines to that side), and parts of the lobes of the thyroid gland; the recurrent nerves ascend between it and the trachea; to its left side is the thoracic duct.

The **thoracic portion** of the œsophagus is at first situated in the superior mediastinal cavity between the trachea and the vertebral column, a little to the left of the median line. It then passes behind and to the right of the aortic arch, and descends in the posterior mediastinal cavity, along the right side of the descending aorta, then runs in front and a little to the left of the aorta, and enters the abdomen through the Diaphragma at the level of the tenth thoracic vertebra. Just before it perforates the Diaphragma it presents a distinct dilatation. It is in relation, *in front*, with the trachea, the left bronchus, the pericardium, and the Diaphragma; *behind*, it rests upon the vertebral column, the Longus colli muscles, the right aortic intercostal arteries, the thoracic duct, and the hemiazygos veins; and below, near the Diaphragma, upon the front of the aorta. On its *left* side, in the superior mediastinal cavity, are the terminal part of the aortic arch, the left subclavian artery, the thoracic duct, and left pleura, while running upward in the angle between it and the trachea is the left recurrent nerve; below, it is in relation with the descending thoracic aorta. On its *right* side are the right pleura, and the azygos vein which it overlaps. Below the roots of the lungs the vagi descend in close contact with it, the right nerve passing down behind, and the left nerve in front of it; the two nerves uniting to form a plexus around the tube.

In the lower part of the posterior mediastinal cavity the thoracic duct lies to the right side of the œsophagus; higher up, it is placed behind it, and, crossing about the level of the fourth thoracic vertebra, is continued upward on its left side.

The **abdominal portion** of the œsophagus lies in the œsophageal groove on the posterior surface of the left lobe of the liver. It measures about 1.25 cm. in length, and only its front and left aspects are covered by peritoneum. It is somewhat conical with its base applied to the upper orifice of the stomach, and is known as the **antrum cardiacum**.

**Structure** (Fig. 959).—The œsophagus has four coats: an **external** or **fibrous**, a **muscular**, a **submucous** or **areolar**, and an **internal** or **mucous** coat.

The **muscular coat** (*tunica muscularis*) is composed of two planes of considerable thickness: an external of longitudinal and an internal of circular fibres.

The **longitudinal fibres** are arranged, at the commencement of the tube, in three fasciculi: one in front, which is attached to the vertical ridge on the posterior surface of the lamina of the cricoid cartilage; and one at either side, which is continuous with the muscular fibres of the pharynx: as they descend they blend together, and form a uniform layer, which covers the outer surface of the tube.

**Accessory slips** of muscular fibres pass between the œsophagus and the




FIG. 958.—The œsophagus.




FIG. 959.—Section of the human œsophagus. (From a drawing by V. Horsley.) Moderately magnified. The section is transverse and from near the middle of the gullet. *a*. Fibrous covering. *b*. Divided fibres of longitudinal muscular coat. *c*. Transverse muscular fibres. *d*. Submucous or areolar layer. *e*. Muscularis mucosae. *f*. Mucous membrane, with vessels and part of a lymphoid nodule. *g*. Stratified epithelial lining. *h*. Mucous gland. *i*. Gland duct. *m'*. Striated muscular fibres cut across.

left pleura, where the latter covers the thoracic aorta, or the root of the left bronchus, or the back of the pericardium.

The **circular fibres** are continuous above with the Constrictor pharyngis inferior; their direction is transverse at the upper and lower parts of the tube, but oblique in the intermediate part.

The muscular fibres in the upper part of the œsophagus are of a red color, and consist chiefly of the striped variety; but below, they consist of the most part of involuntary fibres.

The **areolar** or **submucous coat** (*tela submucosa*) connects loosely the mucous and muscular coats. It contains bloodvessels, nerves, and mucous glands.

The **mucous coat** (*tunica mucosa*) is thick, of a reddish color above, and pale below. It is disposed in longitudinal folds, which disappear on distension of the tube. Its surface is studded with minute papillæ, and it is covered throughout with a thick layer of stratified squamous epithelium. Beneath the mucous membrane, between it and the areolar coat, is a layer of longitudinally arranged non-striped muscular fibres. This is the **muscularis mucosæ**. At the commencement of the œsophagus it is absent, or only represented by a few scattered bundles; lower down it forms a considerable stratum.

The **œsophageal glands** (*glandulæ œsophageæ*) are small compound racemose glands of the mucous type: they are lodged in the submucous tissue, and each opens upon the surface by a long excretory duct.

**Vessels and Nerves.**—The **arteries** supplying the œsophagus are derived from the inferior thyroid branch of the thyrocervical trunk, from the descending thoracic aorta, from the left gastric branch of the cœliac artery, and from the left inferior phrenic of the abdominal aorta. They have for the most part a longitudinal direction.

The **nerves** are derived from the vagi and from the sympathetic trunks; they form a plexus, in which are groups of ganglion cells, between the two layers of the muscular coats, and also a second plexus in the submucous tissue.

**Applied Anatomy.**—The œsophagus may be obstructed by foreign bodies, and also by changes in its coats producing stricture, or by pressure on it from without of new growths or aneurism, etc. The different forms of stricture are: (1) the fibrous, due to cicatrization following destruction of tissue, the result of swallowing boiling or corrosive fluids—here dilatation of the stricture may be carried out; and (2) malignant, usually epitheliomatous in its nature. This may be situated either at the upper end of the tube, opposite the cricoid cartilage, or at its lower end at the cardiac orifice, but is most commonly found in that part of the tube which is crossed by the left bronchus. In these cases, if the patient is losing weight from insufficient nourishment, the operation of gastrostomy may be performed in order to avoid death from starvation; death, however, most commonly occurs from ulceration of the growth into the mediastinal cavity or air passages. In cases of stricture of the œsophagus it may be necessary to dilate the canal by a bougie, when it is of importance that the direction of the œsophagus and its relations to surrounding parts should be remembered. In cases of malignant disease of the œsophagus, where its tissues have become softened from infiltration of the growth, the greatest care is requisite in directing the bougie through the strictured part, as a false passage may easily be made, and the instrument may pass into the mediastinal cavity or into one or other pleural cavity, or even into the pericardium.

In cases of obstruction of the œsophagus, and consequent symptoms of stricture, produced by an aneurism of some part of the aorta pressing upon this tube, the passage of a bougie will only hasten the fatal issue.

In passing a bougie, the left forefinger should be introduced into the mouth, and the epiglottis felt for, care being taken not to throw the head too far backward. The bougie is then to be passed beyond the finger until it touches the posterior wall of the pharynx. The patient is now asked to swallow, and at the moment of swallowing the bougie is passed gently onward, all violence being carefully avoided.

It occasionally happens that a foreign body becomes impacted in the œsophagus, and can neither be brought upward nor moved downward. When all ordinary means for its removal have failed, excision is the only resource. This, of course, can only be performed when it is not very low down. If the foreign body is allowed to remain, extensive inflammation and ulceration of the œsophagus may ensue. In one case the foreign body ultimately penetrated the intervertebral fibrocartilage, and destroyed life by inflammation of the membranes and substance of the medulla spinalis.

## THE ABDOMEN.

The **abdomen** is the largest cavity in the body. It is of an oval shape, the extremities of the oval being directed upward and downward. The upper extremity is formed by the Diaphragma which extends as a dome over the abdomen, so that the cavity extends high into the bony thorax, reaching on the right side, in the mammary line, to the upper border of the fifth rib; on the left side it falls below this level by about 2.5 cm. The lower extremity is formed by the structures which clothe the inner surface of the bony pelvis, principally the Levator ani and Coccygeus on either side. These muscles are sometimes termed the **diaphragm of the pelvis**. The cavity is wider above than below, and measures more in the vertical than in the transverse diameter. In order to facilitate description, it is artificially divided into two parts: an upper and larger part, the **abdomen proper**; and a lower and smaller

part, the **pelvis**. These two cavities are not separated from each other, but the limit between them is marked by the superior aperture of the lesser pelvis.

The **abdomen proper** differs from the other great cavities of the body in being bounded for the most part by muscles and fasciæ, so that it can vary in capacity and shape according to the condition of the viscera which it contains; but, in addition to this, the abdomen varies in form and extent with age and sex. In the adult male, with moderate distension of the viscera, it is oval in shape, but at the same time flattened from before backward. In the adult female, with a fully developed pelvis, it is ovoid with the narrower pole upward, and in young children it is also ovoid but with the narrower pole downward.

**Boundaries.**—It is bounded *in front* and *at the sides* by the abdominal muscles and the Iliacus muscles; *behind* by the vertebral column and the Psoas and Quadratus lumborum muscles; *above* by the Diaphragma; *below* by the plane of the superior aperture of the lesser pelvis. The muscles forming the boundaries of the cavity are lined upon their inner surfaces by a layer of fascia.

The abdomen contains the greater part of the digestive tube; some of the accessory organs to digestion, viz., the liver and pancreas; the spleen, the kidneys, and the suprarenal glands. Most of these structures, as well as the wall of the cavity in which they are contained, are more or less covered by an extensive and complicated serous membrane, the **peritoneum**.

**The Apertures in the Walls of the Abdomen.**—The apertures in the walls of the abdomen, for the transmission of structures to or from it, are, *in front*, the **umbilical** (in the fetus), for the transmission of the umbilical vessels, the allantois, and vitelline duct; *above*, the **vena caval opening**, for the transmission of the inferior vena cava, the **aortic hiatus**, for the passage of the aorta, azygos vein, and thoracic duct, and the **oesophageal hiatus**, for the oesophagus and vagi. *Below*, there are two apertures on either side: one for the passage of the femoral vessels and lumbo-inguinal nerve, and the other for the transmission of the spermatic cord in the male, and the round ligament of the uterus in the female.

**Regions.**—For convenience of description of the viscera, as well as of reference to the morbid conditions of the contained parts, the abdomen is artificially divided into nine regions by imaginary planes, two horizontal and two sagittal, passing through the cavity, the edges of the planes being indicated by lines drawn on the surface of the body. Of the horizontal planes the upper or **transpyloric** is indicated by a line encircling the body at the level of a point midway between the jugular notch and the symphysis pubis, the lower by a line carried around the trunk at the level of a point midway between the transpyloric and the symphysis pubis. The latter is practically the **intertubercular plane** of Cunningham, who pointed out<sup>1</sup> that its level corresponds with the prominent and easily defined tubercle on the iliac crest about 5 cm. behind the anterior superior iliac spine. By means of these imaginary planes the abdomen is divided into three zones, which are named from above downward the **subcostal**, **umbilical**, and **hypogastric zones**. Each of these is further subdivided into three regions by the two sagittal planes, which are indicated on the surface by lines drawn vertically through points half-way between the anterior superior iliac spines and the symphysis pubis.<sup>2</sup>

The middle region of the upper zone is called the **epigastric**; and the two lateral regions, the **right** and **left hypochondriac**. The central region of the middle zone is the **umbilical**; and the two lateral regions, the **right** and **left lumbar**. The middle region of the lower zone is the **hypogastric** or **pubic region**; and the lateral regions are the **right** and **left iliac** or **inguinal** (Fig. 960).

The **pelvis** is that portion of the abdominal cavity which lies below and behind a plane passing through the promontory of the sacrum, lineæ terminales of the hip bones, and the pubic crests. It is bounded behind by the sacrum, coccyx,

<sup>1</sup> Journal of Anatomy and Physiology, vol. xxvii.

<sup>2</sup> Ibid., vols. xxxiii, xxxiv, xxxv.



Piriformes, and the sacrospinous and sacrotuberous ligaments; in front and laterally by the pubes and ischia and Obturatores interni; above it communicates




FIG. 900.—Front view of the thoracic and abdominal viscera. *a*. Median plane. *b b*. Lateral planes. *c c*. Trans-tubercular plane. *d d*. Subcostal plane. *e e*. Transpyloric plane.



with the abdomen proper; below it is closed by the Levatores ani and Coccygei and the urogenital diaphragm. The pelvis contains the urinary bladder, the sigmoid colon and rectum, a few coils of the small intestine, and some of the generative organs.

When the anterior abdominal wall is removed, the viscera are partly exposed as follows: above and to the right side is the liver, situated chiefly under the shelter of the right ribs and their cartilages, but extending across the middle line and reaching for some distance below the level of the xiphoid process. To the left of the liver is the stomach, from the lower border of which an apron-like fold of peritoneum, the **greater omentum**, descends for a varying distance, and obscures, to a greater or lesser extent, the other viscera. Below it, however, some of the coils of the small intestine can generally be seen, while in the right and left iliac regions respectively the cecum and the iliac colon are partly exposed. The bladder occupies the anterior part of the pelvis, and, if distended, will project above the symphysis pubis; the rectum lies in the concavity of the sacrum, but is usually obscured by the coils of the small intestine. The sigmoid colon lies between the rectum and the bladder.

When the stomach is followed from left to right it is seen to be continuous with the first part of the small intestine, or duodenum, the point of continuity being marked by a thickened ring which indicates the position of the pyloric valve. The duodenum passes toward the under surface of the liver, and then, curving downward, is lost to sight. If, however, the greater omentum be thrown upward over the chest, the inferior part of the duodenum will be observed passing across the vertebral column toward the left side, where it becomes continuous with the coils of the jejunum and ileum. These measure some 6 metres in length, and if followed downward the ileum will be seen to end in the right iliac fossa by opening into the cecum, the commencement of the large intestine. From the cecum the large intestine takes an arched course, passing at first upward on the right side, then across the middle line and downward on the left side, and forming respectively the ascending transverse, and descending parts of the colon. In the pelvis it assumes the form of a loop, the sigmoid colon, and ends in the rectum.

The spleen lies behind the stomach in the left hypochondriac region, and may be in part exposed by pulling the stomach over toward the right side.

The glistening appearance of the deep surface of the abdominal wall and of the surfaces of the exposed viscera is due to the fact that the former is lined, and the latter are more or less completely covered, by a serous membrane, the **peritoneum**.

### The Peritoneum (Tunica Serosa).

The peritoneum is the largest serous membrane in the body, and consists, in the male, of a closed sac, a part of which is applied against the abdominal parietes, while the remainder is reflected over the contained viscera. In the female the peritoneum is not a closed sac, since the free ends of the uterine tubes open directly into the peritoneal cavity. The part which lines the parietes is named the **parietal portion** of the peritoneum; that which is reflected over the contained viscera constitutes the **visceral portion** of the peritoneum. The free surface of the membrane is smooth, covered by a layer of flattened endothelium, and lubricated by a small quantity of serous fluid. Hence the viscera can glide freely against the wall of the cavity or upon one another with the least possible amount of friction. The attached surface is rough, being connected to the viscera and inner surface of the parietes by means of areolar tissue, termed the **subserous areolar tissue**. The parietal portion is loosely connected with the fascial lining of the abdomen and pelvis, but is more closely adherent to the under surface of the Diaphragma, and also in the middle line of the abdomen.

The space between the parietal and visceral layers of the peritoneum is named the **peritoneal cavity**; but under normal conditions this cavity is merely a potential

one, since the parietal and visceral layers are in contact. The peritoneal cavity gives off a large diverticulum, the omental bursa, which is situated behind the stomach and adjoining structures; the neck of communication between the cavity and the bursa is termed the epiploic foramen (*foramen of Winslow*). Formerly the main portion of the cavity was described as the greater, and the omental bursa as the lesser sac.

The peritoneum differs from the other serous membranes of the body in presenting a much more complex arrangement, and one that can only be clearly understood by following the changes which take place in the digestive tube during its development; the student therefore is advised to preface his study of the peritoneum by reviewing the chapter dealing with this subject in the section on Embryology (page 162).

To trace the membrane from one viscus to another, and from the viscera to the parietes, it is necessary to follow its continuity in the vertical and horizontal directions, and it will be found simpler to describe the main portion of the cavity and the omental bursa separately.




FIG. 961.—Vertical disposition of the peritoneum. Main cavity, red; omental bursa, blue.

**Vertical Disposition of the Main Peritoneal Cavity** (*greater sac*) (Fig. 961).—It is convenient to trace this from the back of the abdominal wall at the level of the umbilicus. On following the peritoneum upward from this level it is seen to be reflected around a fibrous cord, the ligamentum teres (*obliterated umbilical vein*), which reaches from the umbilicus to the under surface of the liver. This reflection forms a somewhat triangular fold, the falciform ligament of the liver, attaching the upper and anterior surfaces of the liver to the Diaphragm and abdominal wall. With the exception of the line of attachment of this ligament the peritoneum covers the whole of the under surface of the anterior part of the Diaphragm, and is continued from it on to the upper surface of the right lobe of the liver as

the **superior layer of the coronary ligament**, and on to the upper surface of the left lobe as the **superior layer of the left triangular ligament** of the liver. Covering the upper and anterior surfaces of the liver, it is continued around its sharp margin on to the under surface, where it presents the following relations: (a) It covers the under surface of the right lobe and is reflected from the back part of this on to the right suprarenal gland and upper extremity of the right kidney, forming in this situation the **inferior layer of the coronary ligament**; a special fold, the **hepatorenal ligament**, is frequently present between the inferior surface of the liver and the front of the kidney. From the kidney it is carried downward to the duodenum and right colic flexure and medialward in front of the inferior vena cava, where it is continuous with the posterior wall of the omental bursa. Between the two layers of the coronary ligament there is a large triangular surface of the liver devoid of peritoneal covering; this is named the **bare area** of the liver, and is attached to the Diaphragma by areolar tissue. Toward the right margin of the liver the two layers of the coronary ligament gradually approach each other, and ultimately fuse to form a small triangular fold connecting the right lobe of the liver to the Diaphragma, and named the **right triangular ligament** of the liver. The apex of the triangular bare area corresponds with the point of meeting of the two layers of the coronary ligament, its base with the fossa for the inferior vena cava. (b) It covers the lower surface of the quadrate lobe, the under and lateral surfaces of the gall-bladder, and the under surface and posterior border of the left lobe; it is then reflected from the upper surface of the left lobe to the Diaphragma as the **inferior layer of the left triangular ligament**, and from the porta of the liver and the fossa for the ductus venosus to the lesser curvature of the stomach and the first 2.5 cm. of the duodenum as the anterior layer of the **hepatogastric** and **hepatoduodenal ligaments**, which together constitute the **lesser omentum**. If this layer of the lesser omentum be followed to the right it will be found to turn around the hepatic artery, bile duct, and portal vein, and become continuous with the anterior wall of the omental bursa, forming a free folded edge of peritoneum. Traced downward, it covers the antero-superior surface of the stomach and the commencement of the duodenum, and is carried down into a large free fold, known as the **gastrocolic ligament** or **greater omentum**. Reaching the free margin of this fold, it is reflected upward to cover the under and posterior surfaces of the transverse colon, and thence to the posterior abdominal wall as the inferior layer of the **transverse mesocolon**. It reaches the abdominal wall at the head and anterior border of the pancreas, is then carried down over the lower part of the head and over the inferior surface of the pancreas on the superior mesenteric vessels, and thence to the small intestine as the anterior layer of the **mesentery**. It encircles the intestine, and subsequently may be traced, as the posterior layer of the mesentery, upward and backward to the abdominal wall. From this it sweeps down over the aorta into the pelvis, where it invests the sigmoid colon, its reduplication forming the **sigmoid mesocolon**. Leaving first the sides and then the front of the rectum, it is reflected on to the seminal vesicles and fundus of the urinary bladder and, after covering the upper surface of that viscus, is carried along the medial and lateral umbilical ligaments (Fig. 962) on to the back of the abdominal wall to the level from which a start was made.

Between the rectum and the bladder it forms, in the male, a pouch, the **rectovesical excavation**, the bottom of which is slightly below the level of the upper ends of the vesiculæ seminales—i. e., about 7.5 cm. from the orifice of the anus. When the bladder is distended, the peritoneum is carried up with the expanded viscus so that a considerable part of the anterior surface of the latter lies directly against the abdominal wall without the intervention of peritoneal membrane. In the female the peritoneum is reflected from the rectum over the posterior vaginal fornix to the cervix and body of the uterus, forming the **rectouterine excavation** (*pouch of Douglas*). It is continued over the intestinal surface and fundus of the

uterus on to its vesical surface, which it covers as far as the junction of the body and cervix uteri, and then to the bladder, forming here a second, but shallower, pouch, the **vesicouterine excavation**. It is also reflected from the sides of the uterus to the lateral walls of the pelvis as two expanded folds, the **broad ligaments of the uterus**, in the free margin of each of which is the uterine tube.




FIG. 962.—Posterior view of the anterior abdominal wall in its lower half. The peritoneum is in place, and the various cords are shining through. (After Joessel.)

**Vertical Disposition of the Omental Bursa (lesser peritoneal sac)** (Fig. 961).—A start may be made in this case on the posterior abdominal wall at the anterior border of the pancreas. From this region the peritoneum may be followed upward over the pancreas on to the inferior surface of the Diaphragma, and thence on to the caudate lobe and caudate process of the liver to the fossa from the ductus venosus and the porta of the liver. Traced to the right, it is continuous over the inferior vena cava with the posterior wall of the main cavity. From the liver it is carried downward to the lesser curvature of the stomach and the commencement of the duodenum as the posterior layer of the lesser omentum, and is continuous on the right, around the hepatic artery, bile duct, and portal vein, with the anterior layer of this omentum. The posterior layer of the lesser omentum is carried down as a covering for the postero-inferior surfaces of the stomach and commencement of the duodenum, and is continued downward as the deep layer of the **gastrocolic ligament** or **greater omentum**. From the free margin of this fold it is reflected upward on itself to the anterior and superior surfaces of the transverse colon, and thence as the superior layer of the transverse mesocolon to the anterior border of the pancreas, the level from which a start was made. It will be seen that the loop formed by



the wall of the omental bursa below the transverse colon follows, and is closely applied to, the deep surface of that formed by the peritoneum of the main cavity, and that the greater omentum or large fold of peritoneum which hangs in front of the small intestine therefore consists of four layers, two anterior and two posterior separated by the potential cavity of the omental bursa.

**Horizontal Disposition of the Peritoneum.**—Below the transverse colon the arrangement is simple, as it includes only the main cavity; above the level of the transverse colon it is more complicated on account of the existence of the omental bursa. Below the transverse colon it may be considered in the two regions, viz., in the pelvis and in the abdomen proper.




FIG. 963.—The peritoneum of the male pelvis. (Dixon and Birmingham.)

(1) **In the Pelvis.**—The peritoneum here follows closely the surfaces of the pelvic viscera and the inequalities of the pelvic walls, and presents important differences in the two sexes. (a) **In the male** (Fig. 963) it encircles the sigmoid colon, from which it is reflected to the posterior wall of the pelvis as a fold, the sigmoid mesocolon. It then leaves the sides and, finally, the front of the rectum, and is continued on to the upper ends of the seminal vesicles and the bladder; on either side of the rectum it forms a fossa, the pararectal fossa, which varies in size with the distension of the rectum. In front of the rectum the peritoneum forms a rectovesical excavation, which is limited laterally by peritoneal folds extending from the sides of the bladder to the rectum and sacrum. These folds are known from their position as the rectovesical or sacrogenital folds. The peritoneum of the anterior pelvic wall covers the superior surface of the bladder, and on either side of this viscus forms a depression, termed the paravesical fossa, which is limited laterally by the fold of peritoneum covering the ductus deferens. The size of this fossa is dependent on the state of distension of the bladder; when the bladder is empty, a variable fold of peritoneum, the plica vesicalis transversa, divides the fossa into two portions. On the peritoneum between the paravesical and pararectal fossæ the only elevations are those produced by the ureters and the hypogastric vessels. (b) **In the female**, pararectal and paravesical fossæ similar to those in the



male are present: the lateral limit of the paravesical fossa is the peritoneum investing the round ligament of the uterus. The rectovesical excavation is, however, divided by the uterus and vagina into a small anterior vesicouterine and a large, deep, posterior rectouterine excavation. The sacrogenital folds form the margins of the latter, and are continued on to the back of the uterus to form a transverse fold, the **torus uterinus**. The broad ligaments extend from the sides of the uterus to the lateral walls of the pelvis; they contain in their free margins the uterine tubes, and in their posterior layers the ovaries. Below, the broad ligaments are continuous with the peritoneum on the lateral walls of the pelvis. On the lateral pelvic wall behind the attachment of the broad ligament, in the angle between the elevations produced by the diverging hypogastric and external iliac vessels is a slight fossa, the **ovarian fossa**, in which the ovary normally lies.




Fig. 964.—Horizontal disposition of the peritoneum in the lower part of the abdomen.

(2) **In the Lower Abdomen** (Fig. 964).—Starting from the linea alba, below the level of the transverse colon, and tracing the continuity of the peritoneum in a horizontal direction to the right, the membrane covers the inner surface of the abdominal wall almost as far as the lateral border of the Quadratus lumborum; it encloses the cecum and vermiform process, and is reflected over the sides and front of the ascending colon; it may then be traced over the duodenum, Psoas major, and inferior vena cava toward the middle line, whence it passes along the mesenteric vessels to invest the small intestine, and back again to the large vessels in front of the vertebral column, forming the **mesentery**, between the layers of which are contained the mesenteric bloodvessels, lacteals, and glands. It is then continued over the left Psoas; it covers the sides and front of the descending colon, and, reaching the abdominal wall, is carried on it to the middle line.

(3) **In the Upper Abdomen** (Fig. 965).—Above the transverse colon the omental bursa is superadded to the general sac, and the communication of the two cavities with one another through the epiploic foramen can be demonstrated.

(a) **Main Cavity**.—Commencing on the posterior abdominal wall at the inferior vena cava, the peritoneum may be followed to the right over the front of the suprarenal gland and upper part of the right kidney on to the antero-lateral

abdominal wall. From the middle line of the anterior wall a backwardly directed fold encircles the obliterated umbilical vein and forms the falciform ligament of the liver. Continuing to the left, the peritoneum lines the antero-lateral abdominal wall and covers the lateral part of the front of the left kidney, and is reflected to the posterior border of the hilus of the spleen as the posterior layer of the **phrenicolienal ligament**. It can then be traced around the surface of the spleen to the front of the hilus, and thence to the cardiac end of the greater curvature of the stomach as the anterior layer of the **gastrolial ligament**. It covers the antero-superior surfaces of the stomach and commencement of the duodenum, and extends up from the lesser curvature of the stomach to the liver as the anterior layer of the lesser omentum.




FIG. 965.—Horizontal disposition of the peritoneum in the upper part of the abdomen.

(b) **Omental Bursa** (*bursa omentalis*; *lesser peritoneal sac*).—On the posterior abdominal wall the peritoneum of the general cavity is continuous with that of the omental bursa in front of the inferior vena cava. Starting from here, the bursa may be traced across the aorta and over the medial part of the front of the left kidney and Diaphragma to the hilus of the spleen as the anterior layer of the phrenicolienal ligament. From the spleen it is reflected to the stomach as the posterior layer of the gastrosplenic ligament. It covers the postero-inferior surfaces of the stomach and commencement of the duodenum, and extends upward to the liver as the posterior layer of the lesser omentum; the right margin of this layer is continuous around the hepatic artery, bile duct, and portal vein, with the wall of the general cavity.

The **epiploic foramen** (*foramen epiploicum*; *foramen of Winslow*) is the passage of communication between the general cavity and the omental bursa. It is bounded *in front* by the free border of the lesser omentum, with the common bile duct, hepatic artery, and portal vein between its two layers; *behind* by the peritoneum covering the inferior vena cava; *above* by the peritoneum on the caudate process of the liver, and *below* by the peritoneum covering the commencement of the duodenum and the hepatic artery, the latter passing forward below the foramen before ascending between the two layers of the lesser omentum.

The boundaries of the *omental bursa* will now be evident. It is bounded *in front*

from above downward, by the caudate lobe of the liver, the lesser omentum, the stomach, and the anterior two layers of the greater omentum. *Behind*, it is limited, from below upward, by the two posterior layers of the greater omentum, the transverse colon, and the ascending layer of the transverse mesocolon, the upper surface of the pancreas, the left suprarenal gland, and the upper end of the left kidney. To the right of the oesophageal opening of the stomach it is formed by that part of the Diaphragma which supports the caudate lobe of the liver. *Laterally*, the bursa extends from the epiploic foramen to the spleen, where it is limited by the phrenicolienal and gastrolienal ligaments.

The omental bursa, therefore, consists of a series of pouches or recesses to which the following terms are applied: (1) the **vestibule**, a narrow channel continued from the epiploic foramen, over the head of the pancreas to the **gastropancreatic fold**; this fold extends from the omental tuberosity of the pancreas to the right side of the fundus of the stomach, and contains the left gastric artery and coronary vein; (2) the **superior omental recess**, between the caudate lobe of the liver and the Diaphragma; (3) the **lienal recess**, between the spleen and the stomach; (4) the **inferior omental recess**, which comprises the remainder of the bursa.

In the fetus the bursa reaches as low as the free margin of the greater omentum, but in the adult its vertical extent is usually more limited owing to adhesions between the layers of the omentum. During a considerable part of fetal life the transverse colon is suspended from the posterior abdominal wall by a mesentery of its own, the two posterior layers of the greater omentum passing at this stage in front of the colon. This condition occasionally persists throughout life, but as a rule adhesion occurs between the mesentery of the transverse colon and the posterior layer of the greater omentum, with the result that the colon appears to receive its peritoneal covering by the splitting of the two posterior layers of the latter fold. In the adult the omental bursa intervenes between the stomach and the structures on which that viscus lies, and performs therefore the functions of a serous bursa for the stomach.

Numerous peritoneal folds extend between the various organs or connect them to the parietes; they serve to hold the viscera in position, and, at the same time, enclose the vessels and nerves proceeding to them. They are grouped under the three headings of **ligaments**, **omenta**, and **mesenteries**.

The **ligaments** will be described with their respective organs.

There are two **omenta**, the lesser and the greater.

The **lesser omentum** (*omentum minus*; *small omentum*; *gastrohepatic omentum*) is the duplicature which extends to the liver from the lesser curvature of the stomach and the commencement of the duodenum. It is extremely thin, and is continuous with the two layers of peritoneum which cover respectively the antero-superior and postero-inferior surfaces of the stomach and first part of the duodenum. When these two layers reach the lesser curvature of the stomach and the upper border of the duodenum, they join together and ascend as a double fold to the porta of the liver; to the left of the porta the fold is attached to the bottom of the fossa for the ductus venosus, along which it is carried to the Diaphragma, where the two layers separate to embrace the end of the oesophagus. At the right border of the omentum the two layers are continuous, and form a free margin which constitutes the anterior boundary of the epiploic foramen. The portion of the lesser omentum extending between the liver and stomach is termed the **hepatogastric ligament**, while that between the liver and duodenum is the **hepatoduodenal ligament**. Between the two layers of the lesser omentum, close to the right free margin, are the hepatic artery, the common bile duct, the portal vein, lymphatics, and the hepatic plexus of nerves—all these structures being enclosed in a **fibrous capsule** (*Glisson's capsule*). Between the layers of the lesser omentum, where they are attached to the stomach, run the right and left gastric vessels.

The **greater omentum** (*omentum majus*; *great omentum*; *gastrocolic omentum*) is the largest peritoneal fold. It consists of a double sheet of peritoneum, folded on itself so that it is made up of four layers. The two layers which descend from the stomach and commencement of the duodenum pass in front of the small intestines, sometimes as low down as the pelvis; they then turn upon themselves, and ascend again as far as the transverse colon, where they separate and enclose that part of the intestine. These individual layers may be easily demonstrated in the young subject, but in the adult they are more or less inseparably blended. The left border of the greater omentum is continuous with the gastrolial ligament; its right border extends as far as the commencement of the duodenum. The greater omentum is usually thin, presents a cribriform appearance, and always contains some adipose tissue, which in fat people accumulates in considerable quantity. Between its two anterior layers, a short distance from the greater curvature of the stomach, is the anastomosis between the right and left gastroepiploic vessels.

The **mesenteries** are: the **mesentery proper**, the **transverse mesocolon**, and the **sigmoid mesocolon**. In addition to these there are sometimes present an ascending and a descending mesocolon.

The **mesentery proper** (*mesenterium*) is the broad, fan-shaped fold of peritoneum which connects the convolutions of the jejunum and ileum with the posterior wall of the abdomen. Its **root**—the part connected with the structures in front of the vertebral column—is narrow, about 15 cm. long, and is directed obliquely from the duodenojejunal flexure at the left side of the second lumbar vertebra to the right sacroiliac articulation (Fig. 966). Its **intestinal border** is about 6 metres long; and here the two layers separate to enclose the intestine, and form its peritoneal coat. It is narrow above, but widens rapidly to about 20 cm., and is thrown into numerous plaits or folds. It suspends the small intestine, and contains between its layers the intestinal branches of the superior mesenteric artery, with their accompanying veins and plexuses of nerves, the lacteal vessels, and mesenteric lymph glands.

The **transverse mesocolon** (*mesocolon transversum*) is a broad fold, which connects the transverse colon to the posterior wall of the abdomen. It is continuous with the two posterior layers of the greater omentum, which, after separating to surround the transverse colon, join behind it, and are continued backward to the vertebral column, where they diverge in front of the anterior border of the pancreas. This fold contains between its layers the vessels which supply the transverse colon.

The **sigmoid mesocolon** (*mesocolon sigmoideum*) is the fold of peritoneum which retains the sigmoid colon in connection with the pelvic wall. Its line of attachment forms a V-shaped curve, the apex of the curve being placed about the point of division of the left common iliac artery. The curve begins on the medial side of the left Psoas major, and runs upward and backward to the apex, from which it bends sharply downward, and ends in the median plane at the level of the third sacral vertebra. The sigmoid and superior hemorrhoidal vessels run between the two layers of this fold.

In most cases the peritoneum covers only the front and sides of the ascending and descending parts of the colon. Sometimes, however, these are surrounded by the serous membrane and attached to the posterior abdominal wall by an ascending and a descending mesocolon respectively. A fold of peritoneum, the **phrenicocolic ligament**, is continued from the left colic flexure to the Diaphragma opposite the tenth and eleventh ribs; it passes below and serves to support the spleen, and therefore has received the name of **sustentaculum lienis**.

The **appendices epiploicae** are small pouches of the peritoneum filled with fat and situated along the colon and upper part of the rectum. They are chiefly appended to the transverse and sigmoid parts of the colon.

**Peritoneal Recesses or Fossae** (*retroperitoneal fossae*).—In certain parts of the abdominal cavity there are recesses of peritoneum forming culs-de-sac or pouches,



which are of surgical interest in connection with the possibility of the occurrence of "retroperitoneal" herniæ. The largest of these is the omental bursa (already described), but several others, of smaller size, require mention, and may be divided into three groups, viz.: **duodenal**, **cecal**, and **intersigmoid**.




FIG. 966.—Diagram devised by Delépine to show the lines along which the peritoneum leaves the wall of the abdomen to invest the viscera.

1. **Duodenal Fossæ** (Figs. 967, 968).—Three are fairly constant, viz.: (a) The **inferior duodenal fossa**, present in from 70 to 75 per cent. of cases, is situated opposite the third lumbar vertebra on the left side of the ascending portion of the duodenum. Its opening is directed upward, and is bounded by a thin sharp fold of peritoneum with a concave margin, called the **duodenomesocolic fold**. The tip of the index finger introduced into the fossa under the fold passes some little distance behind the ascending portion of the duodenum. (b) The **superior duodenal fossa**, present in from 40 to 50 per cent. of cases, often coexists with the inferior one, and its orifice looks downward. It lies on the left of the ascending portion of the duodenum, in front of the second lumbar vertebra, and behind a



sickle-shaped fold of peritoneum, the **duodenojejunal fold**, and has a depth of about 2 cm. (c) The **duodenojejunal fossa** exists in from 15 to 20 per cent. of cases, but has never yet been found in conjunction with the other forms of duodenal fossæ; it can be seen by pulling the jejunum downward and to the right, after the




FIG. 967.—Superior and inferior duodenal fossæ. (Poirier and Charpy.)

transverse colon has been pulled upward. It is bounded above by the pancreas, to the right by the aorta, and to the left by the kidney; beneath is the left renal vein. It has a depth of from 2 to 3 cm., and its orifice, directed downward and to the right, is nearly circular and will admit the tip of the little finger.




FIG. 968.—Duodenojejunal fossa. (Poirier and Charpy.)

**2. Cecal Fossæ (pericecal folds or fossæ).**—There are three principal pouches or recesses in the neighborhood of the cecum (Figs. 969 to 971): (a) The **superior ileocecal fossa** is formed by a fold of peritoneum, arching over the branch of the

ileocolic artery which supplies the ileocolic junction. The fossa is a narrow chink situated between the mesentery of the small intestine, the ileum, and the small portion of the cecum behind. (b) The **inferior ileocecal fossa** is situated behind the angle of junction of the ileum and cecum. It is formed by the **ileocecal fold** of peritoneum (*bloodless fold of Treves*), the upper border of which is fixed to the ileum,




FIG. 969.—Superior ileocecal fossa. (Poirier and Charpy.)

opposite its mesenteric attachment, while the lower border, passing over the ileocecal junction, joins the mesenteriole of the vermiform process, and sometimes the process itself. Between this fold and the mesenteriole of the vermiform process is the inferior ileocecal fossa. It is bounded above by the posterior surface of the ileum and the mesentery; in front and below by the ileocecal fold, and behind by the upper part of the mesenteriole of the vermiform process. (c) The **cecal fossa** is situated immediately behind the cecum, which has to be raised to bring it into view. It varies much in size and extent. In some cases

it is sufficiently large to admit the index finger, and extends upward behind the ascending colon in the direction of the kidney; in others it is merely a shallow depression. It is bounded on the right by the cecal fold, which is attached by one edge to the abdominal wall from the lower border of the kidney to the iliac fossa and by the other to the postero-lateral aspect of the colon. In some instances additional fossæ, the **retrocæcal fossæ**, are present.




FIG. 970.—Inferior ileocecal fossa. The cecum and ascending colon have been drawn lateralward and downward, the ileum upward and backward, and the vermiform process downward. (Poirier and Charpy.)

3. The **intersigmoid fossa** (*recessus intersigmoideus*) is constant in the fetus and during infancy, but disappears in a certain percentage of cases as age advances. Upon drawing the sigmoid colon upward, the left surface of the sigmoid mesocolon is exposed, and on it will be seen a funnel-shaped recess of the peritoneum, lying on the external iliac vessels, in the interspace between the Psoas and Iliacus muscles. This is the orifice leading to the intersigmoid fossa, which lies behind the sigmoid

mesocolon, and in front of the parietal peritoneum. The fossa varies in size; in some instances it is a mere dimple, whereas in others it will admit the whole of the index finger.




FIG. 971.—The cecal fossa. The ileum and cecum are drawn backward and upward. (Souligoux.)

**Applied Anatomy.**—Any of these fossæ may be the site of a “retroperitoneal” hernia. The cecal fossæ are of special interest, because hernia of the vermiform process frequently takes place into one of them, and it may there become strangulated. The presence of these pouches also explains the course which pus has been known to take in cases of perforation of the vermiform process, where it travels upward behind the ascending colon as far as the Diaphragma.<sup>1</sup>

### The Stomach (Ventriculus; Gaster).

The **stomach** is the most dilated part of the digestive tube, and is situated between the end of the œsophagus and the beginning of the small intestine. It lies in the epigastric, umbilical, and left hypochondriac regions of the abdomen, and occupies a recess bounded by the upper abdominal viscera, and completed in front and on the left side by the anterior abdominal wall and the Diaphragma.

The **shape and position** of the stomach are so greatly modified by changes within itself and in the surrounding viscera that no one form can be described as typical. The chief modifications are determined by (1) the amount of the stomach contents, (2) the stage which the digestive process has reached, (3) the degree of development of the gastric musculature, and (4) the condition of the adjacent intestines. It is, however, possible by comparing a series of stomachs to determine certain markings more or less common to all (Figs. 972, 973).

The stomach presents two **openings**, two **borders or curvatures**, and two **surfaces**.

**Openings.**—The opening by which the œsophagus communicates with the stomach is known as the **cardiac orifice**, and is situated on the left of the middle line at the level of the tenth thoracic vertebra. The short abdominal portion of the œsophagus (*antrum cardiacum*) is conical in shape and curved sharply to the left, the base of the cone being continuous with the cardiac orifice of the stomach. The right margin of the œsophagus is continuous with the lesser curvature of the

<sup>1</sup> On the anatomy of these fossæ, see the Arris and Gale Lectures by Moynihan, 1899.

stomach, while the left margin joins the greater curvature at an acute angle, termed the **incisura cardiaca**.

The **pyloric orifice** communicates with the duodenum, and its position is usually indicated on the surface of the stomach by a circular groove, the **duodenopyloric constriction**. This orifice lies to the right of the middle line at the level of the upper border of the first lumbar vertebra.

**Curvatures.**—The **lesser curvature** (*curvatura ventriculi minor*), extending between the cardiac and pyloric orifices, forms the right or posterior border of the stomach. It descends as a continuation of the right margin of the oesophagus in front of the fibres of the right crus of the Diaphragma, and then, turning to the right, it crosses the first lumbar vertebra and ends at the pylorus. Nearer its pyloric than its cardiac end is a well-marked notch, the **incisura angularis**, which varies somewhat in position with the state of distension of the viscus; it serves to separate the stomach into a right and a left portion. The lesser curvature gives attachment to the two layers of the hepatogastric ligament, and between these two layers are the left gastric artery and the right gastric branch of the hepatic artery.




FIG. 972.—Outline of stomach, showing its anatomical landmarks.




FIG. 973.—Outline of stomach at an early stage of gastric digestion.

The **greater curvature** (*curvatura ventriculi major*) is directed mainly forward, and is four or five times as long as the lesser curvature. Starting from the cardiac orifice at the incisura cardiaca, it forms an arch backward, upward, and to the left; the highest point of the convexity is on a level with the sixth left costal cartilage. From this level it may be followed downward and forward, with a slight convexity to the left as low as the cartilage of the ninth rib; it then turns to the right, to the end of the pylorus. Directly opposite the incisura angularis or the lesser curvature the greater curvature presents a dilatation, which is the left extremity of the **pyloric part**; this dilatation is limited on the right by a slight groove, the **sulcus intermedius**, which is about 2.5 cm, from the duodenopyloric constriction. The portion between the sulcus intermedius and the duodenopyloric constriction is termed the **pyloric antrum**. At its commencement the greater curvature is covered by peritoneum continuous with that covering the front of the organ. The left part of the curvature gives attachment to the gastrolial ligament, while to its anterior portion are attached the two layers of the greater omentum, separated from each other by the gastroepiploic vessels.

**Surfaces.**—When the stomach is in the contracted condition, its surfaces are directed upward and downward respectively, but when the viscus is distended they are directed forward, and backward. They may therefore be described as antero-superior and postero-inferior.

**Antero-superior Surface.**—The left half of this surface is in contact with the Diaphragma, which separates it from the base of the left lung, the pericardium,

and the seventh, eighth, and ninth ribs, and intercostal spaces of the left side. The right half is in relation with the left and quadrate lobes of the liver and with the anterior abdominal wall. When the stomach is empty, the transverse colon may lie on the front part of this surface. The whole surface is covered by peritoneum.

The **Postero-inferior Surface** is in relation with the Diaphragma, the spleen, the left suprarenal gland, the upper part of the front of the left kidney, the anterior surface of the pancreas, the left colic flexure, and the upper layer of the transverse mesocolon. These structures form a shallow bed, the **stomach bed**, on which the viscus rests. The transverse mesocolon separates the stomach from the duodeno-jejunal flexure and small intestine. The postero-inferior surface is covered by peritoneum, except over a small area close to the cardiac orifice; this area is limited by the lines of attachment of the **gastrophrenic ligament**, and lies in apposition with the Diaphragma, and frequently with the upper portion of the left suprarenal gland.

**Component Parts of the Stomach.**—The stomach is capable of subdivision into distinctive parts, and the divisions may be made on either anatomical or clinical grounds.

**Anatomical Subdivisions.**—A plane passing through the incisura angularis on the lesser curvature and the left limit of the opposed dilatation on the greater curvature divides the stomach into a left portion or **body** and a right or **pyloric portion**. The left portion of the body is known as the **fundus**, and is marked off from the remainder of the body by a plane passing horizontally through the cardiac orifice. The pyloric portion is divided by a plane through the sulcus intermedius at right angles to the long axis of this portion; the part to the right of this plane is the **pyloric antrum** (Fig. 972).

**Clinical Subdivisions.**—If the stomach be examined during the process of digestion it will be found divided by a muscular constriction into a large dilated left portion, and a narrow contracted tubular right portion. The constriction is in the body of the stomach, and does not follow any of the anatomical landmarks; indeed, it shifts gradually toward the left as digestion progresses, *i. e.*, more of the body is gradually absorbed into the tubular part. These two portions are known as the **fundus** and **pyloric portions**. It will be seen therefore that the clinical fundus includes the anatomical fundus and the proximal part of the body, while the clinical pyloric portion comprises the distal part of the body, and the anatomical pyloric part (Fig. 973).

**Position of the Stomach.**—The position of the stomach varies with the posture, with the amount of the stomach contents and with the condition of the intestines on which it rests. In the erect posture the empty stomach is somewhat J-shaped; the part above the cardiac orifice is usually distended with gas; the pylorus descends to the level of the second lumbar vertebra and the most dependent part of the stomach is at the level of the umbilicus. Variation in the amount of its contents affects mainly the cardiac portion, the pyloric portion remaining in a more or less contracted condition during the process of digestion. As the stomach fills it tends to expand forward and downward in the direction of least resistance, but when this is interfered with by a distended condition of the colon or intestines the fundus presses upward on the liver and Diaphragma and gives rise to the feelings of oppression and palpitation complained of in such cases. His<sup>1</sup> and Cunningham<sup>2</sup> have shown by hardening the viscera *in situ* that the contracted stomach has a sickle shape, the fundus looking directly backward. The surfaces are directed upward and downward, the upper surface having, however, a gradual downward slope to the right. The greater curvature is in front and at a slightly higher level than the lesser.

The position of the full stomach depends, as already indicated, on the state of the intestines; when these are empty the fundus expands vertically and also forward, the pylorus is displaced toward the right and the whole organ assumes an oblique position, so that its surfaces are directed more forward and backward. The lowest part of the stomach is at the pyloric vestibule, which reaches to the region of the umbilicus. Where the intestines interfere with the downward expansion of the fundus the stomach retains the horizontal position which is characteristic of the contracted viscus.

Examination of the stomach during life by x-rays has confirmed these findings, and has demonstrated that, in the erect posture, the full stomach usually presents a hook-like appearance, the long axis of the clinical fundus being directed downward, medialward, and forward toward the umbilicus, while the pyloric portion curves upward to the duodenopyloric junction.

**Interior of the Stomach.**—When examined after death, the stomach is usually fixed at some temporary stage of the digestive process. A common form is that shown in Fig. 974. If the viscus be laid open by a section through the plane of its two curvatures, it is seen to consist of two segments: (a) a large globular portion on the left and (b) a narrow tubular part on the

<sup>1</sup> Archiv für Anatomie und Physiologie, anat. Abth., 1903.

<sup>2</sup> Transactions of the Royal Society of Edinburgh, vol. xlv, part i.



right. These correspond to the clinical subdivisions of fundus and pyloric portions already described, and are separated by a constriction which indents the body and greater curvature, but does not involve the lesser curvature. To the left of the cardiac orifice is the *incisura cardiaca*: the projection of this notch into the cavity of the stomach increases as the organ distends, and has been supposed to act as a valve preventing regurgitation into the oesophagus. In the pyloric portion are seen: (a) the elevation corresponding to the *incisura angularis*, and (b) the circular projection from the duodenopyloric constriction which forms the pyloric valve; the separation of the pyloric antrum from the rest of the pyloric part is scarcely indicated.

The **pyloric valve** (*valvula pylori*) is formed by a reduplication of the mucous membrane of the stomach, covering a muscular ring composed of a thickened portion of the circular layer of the muscular coat. Some of the deeper longitudinal fibres turn in and interlace with the circular fibres of the valve.




FIG. 974.—Interior of the stomach.

**Structure.**—The wall of the stomach consists of four coats: **serous, muscular, areolar, and mucous**, together with vessels and nerves.

The **serous coat** (*tunica serosa*) is derived from the peritoneum, and covers the entire surface of the organ, excepting along the greater and lesser curvatures at the points of attachment of the greater and lesser omenta; here the two layers of peritoneum leave a small triangular space, along which the nutrient vessels and nerves pass. On the posterior surface of the stomach, close to the cardiac orifice, there is also a small area uncovered by peritoneum, where the organ is in contact with the under surface of the Diaphragm.

The **muscular coat** (*tunica muscularis*) (Figs. 975, 976) is situated immediately beneath the serous covering, with which it is closely connected. It consists of three sets of fibres: longitudinal, circular, and oblique.

The **longitudinal fibres** (*stratum longitudinale*) are the most superficial, and are arranged in two sets. The first set consists of fibres continuous with the longitudinal fibres of the oesophagus; they radiate in a stellate manner from the cardiac orifice and are practically all lost before the pyloric portion is reached. The second set commences on the body of the stomach and passes to the right, its fibres becoming more thickly distributed as they approach the pylorus. Some of the more superficial fibres of this set pass on to the duodenum, but the deeper fibres dip inward and interlace with the circular fibres of the pyloric valve.

The **circular fibres** (*stratum circulare*) form a uniform layer over the whole extent of the stomach beneath the longitudinal fibres. At the pylorus they are most abundant, and are aggregated into a circular ring, which projects into the lumen, and forms, with the fold of mucous membrane covering its surface, the **pyloric valve**. They are continuous with the circular fibres of the oesophagus, but are sharply marked off from the circular fibres of the duodenum.

The **oblique fibres** (*fibrae obliquae*) internal to the circular layer, are limited chiefly to the cardiac end of the stomach, where they are disposed as a thick uniform layer, covering both surfaces, some passing obliquely from left to right, others from right to left, around the cardiac end.

The **areolar or submucous coat** (*tela submucosa*) consists of a loose, areolar tissue, connecting the mucous and muscular layers.

The **mucous membrane** (*tunica mucosa*) is thick and its surface is smooth, soft, and velvety. In the fresh state it is of a pinkish tinge at the pyloric end, and of a red or reddish-brown color




FIG. 975.—The longitudinal and circular muscular fibres of the stomach, viewed from above and in front. (Spalteholz.)

over the rest of its surface. In infancy it is of a brighter hue, the vascular redness being more marked. It is thin at the cardiac extremity, but thicker toward the pylorus. During the contracted state of the organ it is thrown into numerous plaits or rugæ, which, for the most part,




FIG. 976.—The oblique muscular fibres of the stomach, viewed from above and in front. (Spalteholz.)

have a longitudinal direction, and are most marked toward the pyloric end of the stomach, and along the greater curvature (Fig. 974). These folds are entirely obliterated when the organ becomes distended.

**Structure of the Mucous Membrane.**—When examined with a lens, the inner surface of the mucous membrane presents a peculiar honeycomb appearance from being covered with small shallow depressions or alveoli, of a polygonal or hexagonal form, which vary from 0.12 to 0.25 mm. in diameter. These are the ducts of the gastric glands, and at the bottom of each may be seen one or more minute orifices, the openings of the gland tubes. The surface of the mucous membrane is covered by a single layer of columnar epithelium with occasional goblet cells. This epithelium commences very abruptly at the cardiac orifice, where there is a sudden transition from the stratified epithelium of the oesophagus. The epithelial lining of the gland ducts is of the same character and is continuous with the general epithelial lining of the stomach (Fig. 979).

**The Gastric Glands.**—The gastric glands are of three kinds: (a) **pyloric**, (b) **cardiac**, and (c) **fundus** or **oxyntic glands**. They are tubular in character, and are formed of a delicate basement-membrane, consisting of flattened transparent endothelial cells lined by epithelium. The **pyloric glands** (Fig. 978) are found in the pyloric portion of the stomach. They consist of two or three short closed tubes opening into a common duct or mouth. These tubes are wavy, and are about one-half the length of the duct. The duct is lined by columnar cells, continuous with the epithelium lining the surface of the mucous membrane of the stomach, the tubes by shorter and more cubical cells which are finely granular. The **cardiac glands** (Fig. 977), few in number, occur close to the cardiac orifice. They are of two kinds: (1) simple tubular




FIG. 977.—Section of mucous membrane of human stomach, near the cardiac orifice. (v. Ebner, after J. Schaffer.)  $\times 45$ . c. Cardiac glands. d. Their ducts. cr. Gland similar to the intestinal glands, with goblet cells. mm. Mucous membrane. m. Muscularis mucosae. m'. Muscular tissue within the mucous membrane.

glands resembling those of the pyloric end of the stomach, but with short ducts; (2) compound racemose glands resembling the duodenal glands. The **fundus glands** (Fig. 979) are found in the body and fundus of the stomach; they are simple tubes, two or more of which open into a single duct. The duct, however, in these glands is shorter than in the pyloric variety, sometimes not amounting to more than one-sixth of the whole length of the gland; it is lined throughout by columnar epithelium. The gland tubes are straight and parallel to each other. At the point where they open into the duct, which is termed the neck, the epithelium alters, and consists of short columnar or polyhedral, granular cells, which almost fill the tube, so that the lumen becomes suddenly constricted and is continued down as a very fine channel. They are known as the **chief or central cells** of the glands. Between these cells and the basement-membrane, larger oval cells, which stain deeply with eosin, are found; these cells are studded throughout the tube at intervals, giving it a beaded or varicose appearance. These are known as the **parietal or oxyntic cells**, and they are connected with the lumen by fine channels which run into their substance. Between the glands the mucous membrane consists of a connective-tissue frame-work, with lymphoid tissue. In places, this latter tissue, especially in early life, is collected into little masses, which to a certain extent resemble the solitary nodules of the intestine, and are termed the **lenticular glands** of the stomach. They are not, however, so distinctly circumscribed as the solitary nodules. Beneath the mucous membrane, and between it and the submucous coat, is a thin stratum of involuntary muscular fibre (*muscularis mucosae*), which in some parts



consists only of a single longitudinal layer; in others of two layers, an inner circular and an outer longitudinal.

**Vessels and Nerves.**—The arteries supplying the stomach are: the left gastric, the right gastric and right gastroepiploic branches of the hepatic, and the left gastroepiploic and short gastric branches of the lienal. They supply the muscular coat, ramify in the submucous coat, and are finally distributed to the mucous membrane. The arrangement of the vessels in the mucous membrane is somewhat peculiar. The arteries break up at the base of the gastric tubules into a plexus of fine capillaries which run upward between the tubules, anastomosing with each other, and ending in a plexus of larger capillaries, which surround the mouths of the tubes, and also form hexagonal meshes around the ducts. From these the veins arise, and pursue a straight course downward, between the tubules, to the submucous tissue; they end either in the lienal and superior mesenteric veins, or directly in the portal vein. The lymphatics are numerous: they consist of a superficial and a deep set, and pass to the lymph glands found along the two curvatures of the organ (page 792). The nerves are the terminal branches of the right and left




FIG. 978.—A pyloric gland, from a section of the dog's stomach. (Ebstein.) *m*. Mouth. *n*. Neck. *tr*. A deep portion of a tubule cut transversely.




FIG. 979.—A fundus gland. *A*. Transverse section of gland.

vagi, the former being distributed upon the back, and the latter upon the front part of the organ. A great number of branches from the celiac plexus of the sympathetic are also distributed to it. Nerve plexuses are found in the submucous coat and between the layers of the muscular coat as in the intestine. From these plexuses fibrils are distributed to the muscular tissue and the mucous membrane.

**Applied Anatomy.**—Operations on the stomach are frequently performed. By *gastrotomy* is meant an incision into the stomach for the removal of a foreign body, the opening being immediately afterward closed—in contradistinction to *gastrostomy*, the making of a more or less permanent fistulous opening. *Gastrotomy* is probably best performed by an incision in the linea alba, especially if the foreign body be large, but may be performed by an incision over the foreign body itself, where this can be felt, or by one of the incisions for *gastrostomy* mentioned below. The peritoneal cavity is opened, and the point at which the stomach is to be incised decided upon. This portion is then brought out of the abdominal wound, and gauze is carefully packed around it. The stomach is now opened by a transverse incision and the foreign body extracted. The wound in the stomach is then closed by Lembert's sutures, *i. e.*, by sutures passed through

the peritoneal and muscular coats in such a way that the peritoneal surfaces on each side of the wound are brought into apposition. In *gastrostomy*, the incision is commenced opposite the eighth left intercostal space, 5 cm. from the median line, and carried downward for 7.5 cm. By this incision the fibres of the Rectus abdominis are exposed, and these are separated in the same line. The posterior layer of the sheath, the Transversus muscle and transversalis fascia, and the peritoneum are then divided, and the peritoneal cavity opened. The anterior wall of the stomach is now seized and drawn out of the wound, and a silk suture passed through its muscular and serous coats at the point selected for opening the viscus. This is held by an assistant so that a long conical diverticulum of the stomach protrudes from the external wound, and the parietal peritoneum and the posterior layer of the sheath of the Rectus are sutured to it. A second incision is made through the skin, over the margin of the costal cartilage, above and a little to the outer side of the first incision. A tract is made under the skin through the subcutaneous tissue from the one opening to the other, and the diverticulum of the stomach is drawn along this tract by means of the suture inserted into it, so that its apex appears at the second opening. A small perforation is now made into the stomach through this protruding apex, and its margins are carefully and accurately sutured to the edge of the external wound. The remainder of this incision and the whole of the first incision are then closed in the ordinary way and the wound dressed.

In cases of gastric ulcer perforation sometimes takes place, and this was formerly regarded as an almost fatal complication. In the present day, by opening the abdomen and closing the perforation, which is generally situated on the anterior surface of the stomach, a considerable number of cases are cured, provided the operation is done not longer than twelve or fifteen hours after the perforation has taken place. The opening is best closed by bringing the peritoneal surfaces on either side into apposition by means of Lembert's sutures. Free drainage of the peritoneal cavity should be established at the same time.

Excision of the pylorus has occasionally been performed, but the results of this operation are by no means favorable, and, in cases of cancer of the pylorus, before operative proceedings are undertaken, the tumor has become so fixed and has so far implicated surrounding parts that removal of the pylorus is impossible and gastroenterostomy has to be substituted. The object of this operation is to make a fistulous communication between the stomach, on the cardiac side of the disease, and the small intestine, as high up as is possible. In cases of cancer of the stomach involving other parts than the pylorus, the question of removing the whole or greater part of the stomach has to be considered. This operation has been performed by Schlatter and others with success.

Hypertrophy and spasm of the circumferential muscular coat of the pylorus coming on during the first few weeks or months of life, and somewhat erroneously described as *congenital hypertrophic stenosis of the pylorus*, is a serious disorder of infancy. It is characterized by abdominal pains and obstinate vomiting coming on after food has been given. Gastric peristalsis can be observed by inspection of the child's epigastrium after it has been fed and before vomiting has occurred. Progressive wasting for want of nourishment and death from exhaustion tend to ensue. Treatment should be by washing out the stomach, and the administration at frequent intervals of small quantities of easily digested food, so as to minimize irritation of the gastric mucous membrane. Surgical interference entailing a severe operation, gives favorable results in a small proportion of cases.

The stomach is seldom ruptured from external violence on account of its protected position. If it occurs, it is when the organ is distended with food. The stomach is sometimes injured in gunshot wounds. There is intense shock and severe pain, localized at first at the seat of the injury, but soon radiating over the whole abdomen. The treatment consists of opening the peritoneal cavity, clearing away all the extruded contents of the stomach, and repairing the rent.

### The Small Intestine (*Intestinum Tenue*).

The **small intestine** is a convoluted tube, extending from the pylorus to the colic valve, where it ends in the large intestine. It is about 6 metres long,<sup>1</sup> and gradually diminishes in size from its commencement to its termination. It is contained in the central and lower part of the abdominal cavity, and is surrounded above and at the sides by the large intestine; a portion of it extends below the superior aperture of the pelvis and lies in front of the rectum. It is in relation, in front, with the greater omentum and abdominal parietes, and is connected to the vertebral

<sup>1</sup> Treves states that, in one hundred cases, the average length of the small intestine in the adult male was 22 feet 6 inches, and in the adult female 23 feet 4 inches: but that it varies very much, the extremes in the male being 31 feet 10 inches, and 15 feet 6 inches. He states that in the adult the length of the bowel is independent of age, height, and weight.



column by a fold of peritoneum, the **mesentery**. The small intestine is divisible into three portions: the **duodenum**, the **jejunum**, and the **ileum**.

The **Duodenum** (Fig. 980) has received its name from being about equal in length to the breadth of twelve fingers (25 cm.). It is the shortest, the widest, and the most fixed part of the small intestine, and has no mesentery, being only partially covered by peritoneum. Its course presents a remarkable curve, somewhat of the shape of an imperfect circle, so that its termination is not far removed from its starting-point.

In the adult the course of the duodenum is as follows: commencing at the pylorus it passes backward, upward, and to the right, beneath the quadrate lobe of the liver to the neck of the gall-bladder, varying slightly in direction according to the degree of distension of the stomach: it then takes a sharp curve and descends along the right margin of the head of the pancreas, for a variable distance, generally to the level of the upper border of the body of the fourth lumbar vertebra. It now takes a second bend, and passes from right to left across the vertebral column,




FIG. 980.—The duodenum and pancreas.

having a slight inclination upward; and on the left side of the vertebral column it ascends for about 2.5 cm., and then ends opposite the second lumbar vertebra in the jejunum. As it unites with the jejunum it turns abruptly forward, forming the **duodenojejunal flexure**. From the above description it will be seen that the duodenum may be divided into four portions: **superior**, **descending**, **horizontal**, and **ascending**.

**Relations.**—The **superior portion** (*pars superior; first portion*) is about 5 cm. long. Beginning at the pylorus, it ends at the neck of the gall-bladder. It is the most movable of the four portions. It is almost completely covered by peritoneum, but a small part of its posterior surface near the neck of the gall-bladder and the inferior vena cava is uncovered; the upper border of its first half has the hepatoduodenal ligament attached to it, while to the lower border of the same segment the greater omentum is connected. It is in such close relation with the gall-bladder that it is usually found to be stained by bile after death, especially on its anterior surface. It is in relation above and in front with the quadrate lobe of the liver and the gall-

bladder; behind with the gastroduodenal artery, the common bile duct, and the portal vein; and below and behind with the head and neck of the pancreas.

The **descending portion** (*pars descendens*; *second portion*) is from 7 to 10 cm. long, and extends from the neck of the gall-bladder, on a level with the first lumbar vertebra, along the right side of the vertebral column as low as the upper border of the body of the fourth lumbar vertebra. It is crossed in its middle third by the transverse colon, the posterior surface of which is uncovered by peritoneum and is connected to the duodenum by a small quantity of connective tissue. The supra- and infracolic portions are covered in front by peritoneum, the infracolic part by the right leaf of the mesentery. Posteriorly the descending portion of the duodenum is not covered by peritoneum. The descending portion is in relation, in front, from above downward, with the duodenal impression on the right lobe of the liver, the transverse colon, and the small intestine; behind, it has a variable relation to the front of the right kidney in the neighborhood of the hilus, and is connected to it by loose areolar tissue; the renal vessels, the inferior vena cava, and the Psoas below, are also behind it. At its medial side is the head of the pancreas, and the common



FIG. 981.—Interior of the descending portion of the duodenum, showing bile papilla.

bile duct; to its lateral side is the right colic flexure. The common bile duct and the pancreatic duct together perforate the medial side of this portion of the intestine obliquely (Figs. 981 and 1014), some 7 to 10 cm. below the pylorus; the accessory pancreatic duct sometimes pierces it about 2 cm. above and slightly in front of these.

The **horizontal portion** (*pars horizontalis*; *third or preaortic or transverse portion*) is from 5 to 7.5 cm. long. It begins at the right side of the upper border of the fourth lumbar vertebra and passes from right to left, with a slight inclination upward, in front of the great vessels and crura of the Diaphragma, and ends in the ascending portion in front of the abdominal aorta. It is crossed by the superior mesenteric vessels and the mesentery. Its front surface is covered by peritoneum, except near the middle line, where it is crossed by the superior mesenteric vessels. Its posterior surface is uncovered by peritoneum, except toward its left extremity, where the posterior layer of the mesentery may sometimes be found covering it to a variable extent. This surface rests upon the right crus of the Diaphragma, the inferior vena cava, and the aorta. The upper surface is in relation with the head of the pancreas.

The **ascending portion** (*pars ascendens*; *fourth portion*) of the duodenum is about 2.5 cm long. It ascends on the left side of the aorta, as far as the level of the upper border of the second lumbar vertebra, where it turns abruptly forward to become the jejunum, forming the **duodenojejunal flexure**. It lies in front of the left Psoas major and left renal vessels, and is covered in front, and partly at the sides, by peritoneum continuous with the left portion of the mesentery.

The superior part of the duodenum, as stated above, is somewhat movable, but the rest is practically fixed, and is bound down to neighboring viscera and the posterior abdominal wall by the peritoneum. In addition to this, the ascending part of the duodenum and the duodenojejunal flexure are fixed by a structure to which the name of *Musculus suspensorius duodeni* has been given. This structure commences in the connective tissue around the coeliac artery and left crus of the Diaphragma, and passes downward to be inserted into the superior border of the duodenojejunal curve and a part of the ascending duodenum, and from this it is continued into the mesentery. It possesses, according to Treitz, plain muscular fibres mixed with the fibrous tissue of which it is principally made up. It is of little importance as a muscle, but acts as a suspensory ligament.

**Vessels and Nerves.**—The **arteries** supplying the duodenum are the right gastric and superior pancreaticoduodenal branches of the hepatic, and the inferior pancreaticoduodenal branch of the superior mesenteric. The **veins** end in the lienal and superior mesenteric. The **nerves** are derived from the coeliac plexus.

**Jejunum and Ileum.**—The remainder of the small intestine from the end of the duodenum is named **jejunum** and **ileum**; the former term being given to the upper two-fifths and the latter to the lower three-fifths. There is no morphological line of distinction between the two, and the division is arbitrary; but at the same time the character of the intestine gradually undergoes a change from the commencement of the jejunum to the end of the ileum, so that a portion of the bowel taken from these two situations would present characteristic and marked differences. These are briefly as follows:

The **Jejunum** (*intestinum jejunum*) is wider, its diameter being about 4 cm., and is thicker, more vascular, and of a deeper color than the ileum, so that a given length weighs more. The circular folds (*valvulae conniventes*) of its mucous membrane are large and thickly set, and its villi are larger than in the ileum. The aggregated lymph nodules are almost absent in the upper part of the jejunum, and in the lower part are less frequently found than in the ileum, and are smaller and tend to assume a circular form. By grasping the jejunum between the finger and thumb the circular folds can be felt through the walls of the gut; these being absent in the lower part of the ileum, it is possible in this way to distinguish the upper from the lower part of the small intestine.

The **Ileum** (*intestinum ileum*) is narrow, its diameter being 3.75 cm., and its coats thinner and less vascular than those of the jejunum. It possesses but few circular folds, and they are small and disappear entirely toward its lower end, but aggregated lymph nodules (Peyer's patches) are larger and more numerous. The jejunum for the most part occupies the umbilical and left iliac regions, while the ileum occupies chiefly the umbilical, hypogastric, right iliac, and pelvic regions. The terminal part of the ileum usually lies in the pelvis, from which it ascends over the right Psoas and right iliac vessels; it ends in the right iliac fossa by opening into the medial side of the commencement of the large intestine. The jejunum and ileum are attached to the posterior abdominal wall by an extensive fold of peritoneum, the **mesentery**, which allows the freest motion, so that each coil can accommodate itself to changes in form and position. The mesentery is fan-shaped; its posterior border or root, about 15 cm. long, is attached to the posterior abdominal wall from the left side of the body of the second lumbar vertebra to the right sacro-iliac articulation, crossing successively the horizontal part of the duodenum, the

aorta, the inferior vena cava, the ureter, and right Psoas muscle (Fig. 966). Its breadth between its vertebral and intestinal borders averages about 20 cm., and is greater in the middle than at its upper and lower ends. According to Lockwood it tends to increase in breadth as age advances. Between the two layers of which it is composed are contained bloodvessels, nerves, lacteals, and lymph glands, together with a variable amount of fat.




FIG. 982.—Section of duodenum of cat. (After Schäfer.)  $\times 60$ .

**Meckel's Diverticulum** (*diverticulum ilei*).—This consists of a pouch which projects from the lower part of the ileum in about 2 per cent. of subjects. Its average position is about 1 meter above the colic valve, and its average length about 5 cm. Its calibre is generally similar to that of the ileum, and its blind extremity may be free or may be connected with the abdominal wall or with some other portion of the intestine by a fibrous band. It represents the remains of the proximal part of the vitelline duct, the duct of communication between the yolk-sac and the primitive digestive tube in early fetal life.

**Structure.**—The wall of the small intestine (Fig. 982) is composed of four coats: **serous, muscular, areolar, and mucous.**

The **serous coat** (*tunica serosa*) is derived from the peritoneum. The superior portion of the duodenum is almost completely surrounded by this membrane near its pyloric end, but is only



covered in front at the other extremity; the descending portion is covered by it in front, except where it is carried off by the transverse colon; and the inferior portion lies behind the peritoneum which passes over it without being closely incorporated with the other coats of this part of the intestine, and is separated from it in and near the middle line by the superior mesenteric vessels. The rest of the small intestine is surrounded by the peritoneum, excepting along its attached or mesenteric border; here a space is left for the vessels and nerves to pass to the gut.

The **muscular coat** (*tunica muscularis*) consists of two layers of fibres: an external, longitudinal, and an internal, circular layer. The *longitudinal fibres* are thinly scattered over the surface of the intestine, and are more distinct along its free border. The *circular fibres* form a thick, uniform layer, and are composed of plain muscle cells of considerable length. The muscular coat is thicker at the upper than at the lower part of the small intestine.

The **areolar or submucous coat** (*tela submucosa*) connects together the mucous and muscular layers. It consists of loose, filamentous areolar tissue containing bloodvessels, lymphatics, and nerves.

The **mucous membrane** (*tunica mucosa*) is thick and highly vascular at the upper part of the small intestine, but somewhat paler and thinner below. It consists of the following structures: next the areolar or submucous coat is a double layer of unstripped muscular fibres, outer longitudinal and inner circular, the **muscularis mucosae**; internal to this is a quantity of retiform tissue, enclosing in its meshes lymph corpuscles, and in this the bloodvessels and nerves ramify; lastly, a basement-membrane, supporting a single layer of epithelial cells, which throughout the intestine are columnar in character. The cells are granular in appearance, and each possesses a clear oval nucleus. At their superficial or unattached ends they present a distinct layer of highly refracting material, marked by vertical striæ, the **striated border**.

The mucous membrane presents for examination the following structures, contained within it or belonging to it:

Circular folds.

Villi.

Intestinal glands.

Duodenal glands.

Solitary lymphatic nodules.

Aggregated lymphatic nodules.

The **circular folds** (*plicae circulares* [Kerkringi]; *valvulae conniventes*; *valves of Kerkring*) are large valvular flaps projecting into the lumen of the bowel. They are composed of reduplications of the mucous membrane, the two layers of the fold being bound together by submucous tissue; unlike the folds in the stomach, they are permanent, and are not obliterated when the intestine is distended. The majority extend transversely around the cylinder of the intestine for about one-half or two-thirds of its circumference, but some form complete circles, and others have a spiral direction; the latter usually extend a little more than once around the bowel, but occasionally two or three times. The larger folds are about 8 mm. in depth at their broadest part; but the greater number are of smaller size. The larger and smaller folds alternate with each other. They are not found at the commencement of the duodenum, but begin to appear about 2.5 or 5 cm. beyond the pylorus. In the lower part of the descending portion, below the point where the bile and pancreatic ducts enter the intestine, they are very large and closely approximated. In the horizontal and ascending portions of the duodenum and upper half of the jejunum they are large and numerous, but from this point, down to the middle of the ileum, they diminish considerably in size. In the lower part of the ileum they almost entirely disappear; hence the comparative thinness of this portion of the intestine, as compared with the duodenum and jejunum. The circular folds retard the passage of the food along the intestines, and afford an increased surface for absorption.

The **intestinal villi** (*villi intestinales*) are highly vascular processes, projecting from the mucous membrane of the small intestine throughout its whole extent, and giving to its surface a velvety appearance. They are largest and most numerous in the duodenum and jejunum, and become fewer and smaller in the ileum.

*Structure of the villi* (Figs. 983, 984).—The essential parts of a villus are: the lacteal vessel, the bloodvessels, the epithelium, the basement-membrane, and the muscular tissue of the mucosa, all being supported and held together by retiform lymphoid tissue.

The *lacteals* are in some cases double, and in some animals multiple, but usually there is a single vessel. Situated in the axis of the villus, each commences by dilated cecal extremities near to, but not quite at, the summit of the villus. The walls are composed of a single layer of endothelial cells.

The *muscular fibres* are derived from the muscularis mucosae, and are arranged in longitudinal bundles around the lacteal vessel, extending from the base to the summit of the villus, and giving off, laterally, individual muscle cells, which are enclosed by the reticulum, and by it are attached to the basement-membrane and to the lacteal.

The *bloodvessels* (Fig. 985) form a plexus under the basement membrane, and are enclosed in the reticular tissue.

These structures are surrounded by the *basement-membrane*, which is made up of a stratum of endothelial cells, and upon this is placed a layer of *columnar epithelium*, the characteristics



of which have been described. The *retiform tissue* forms a net-work (Fig. 984) in the meshes of which a number of leucocytes are found.




FIG. 983.—Vertical section of a villus from the dog's small intestine.  $\times 80$ .

FIG. 984.—Transverse section of a villus, from the human intestine. (v. Ebner.)  $\times 350$ . *a*. Basement membrane, here somewhat shrunken away from the epithelium. *b*. Lacteal. *c*. Columnar epithelium. *d*. Its striated border. *e*. Goblet cells. *f*. Leucocytes in epithelium. *f'*. Leucocytes below epithelium. *g*. Bloodvessels. *h*. Muscle cells cut across.

The **intestinal glands** (*glandulae intestinales* [Lieberkühn]; *crypts of Lieberkühn*) (Fig. 986) are found in considerable numbers over every part of the mucous membrane of the small intestine.




FIG. 985.—Villi of small intestine, showing bloodvessels and lymphatic vessels. (Cadiat.)

They consist of minute tubular depressions of the mucous membrane, arranged perpendicularly to the surface, upon which they open by small circular apertures. They may be seen with the aid

of a lens, their orifices appearing as minute dots scattered between the villi. Their walls are thin, consisting of a basement membrane lined by columnar epithelium, and covered on their exterior by capillary vessels.

The **duodenal glands** (*glandulae duodenales* [Brunneri]; *Brunner's glands*) are limited to the duodenum (Fig. 982), and are found in the submucous areolar tissue. They are largest and most numerous near the pylorus, forming an almost complete layer in the superior portion and upper half of the descending portions of the duodenum. They then begin to diminish in number, and practically disappear at the junction of the duodenum and jejunum. They are small compound acinotubular glands consisting of a number of alveoli lined by short columnar epithelium and opening by a single duct on the inner surface of the intestine.

The **solitary lymphatic nodules** (*noduli lymphatici solitarii*; *solitary glands*) are found scattered throughout the mucous membrane of the small intestine, but are most numerous in the lower part of the ileum. Their free surfaces are covered with rudimentary villi, except at the summits, and each gland is surrounded by the openings of the intestinal glands. Each consists of a dense interlacing retiform tissue closely packed with lymph-corpuscles, and permeated with an abundant capillary network. The interspaces of the retiform tissue are continuous with larger lymph spaces which surround the gland, through which they communicate with the lacteal system. They are situated partly in the submucous tissue, partly in the mucous membrane, where they form slight projections of its epithelial layer (see Fig. 998).

The **aggregated lymphatic nodules** (*noduli lymphatici aggregati*; *Peyer's patches*; *Peyer's glands*; *agminated follicles*; *tonsillae intestinales*) (Fig. 987) form circular or oval patches, from twenty to thirty in number, and varying in length from 2 to 10 cm. They are largest and most numerous in the ileum. In the lower part of the jejunum they are small, circular, and few in number. They are occasionally seen in the duodenum. They are placed lengthwise in the intestine, and are situated in the portion of the tube most distant from the attachment of the mesentery. Each patch is formed of a group of solitary lymphatic nodules covered with mucous membrane, but the patches do not, as a rule, possess villi on their free surfaces. They are best marked in the



FIG. 986.—An intestinal gland from the human intestine. (Flemming.)




FIG. 987.—Vertical section of a human aggregated lymphatic nodule, injected through its lymphatic canals. *a*. Villi with their chyle passages. *b*. Intestinal glands. *c*. Muscularis mucosae. *d*. Cupola or apex of solitary nodule. *e*. Mesial zone of nodule. *f*. Base of nodule. *g*. Points of exit of the lacteals from the villi, and entrance into the true mucous membrane. *h*. Retiform arrangement of the lymphatics in the mesial zone. *i*. Course of the latter at the base of the nodule. *k*. Confluence of the lymphatics opening into the vessels of the submucous tissue. *l*. Follicular tissue of the latter.

young subject, become indistinct in middle age, and sometimes disappear altogether in advanced life. They are freely supplied with bloodvessels (Fig. 988), which form an abundant

plexus around each follicle and give off fine branches permeating the lymphoid tissue in the interior of the follicle. The lymphatic plexuses are especially abundant around these patches.

**Vessels and Nerves.**—The jejunum and ileum are supplied by the **superior mesenteric artery**, the intestinal branches of which, having reached the attached border of the bowel, run between the serous and muscular coats, with frequent inosculations to the free border, where they also anastomose with other branches running around the opposite surface of the gut. From these




FIG. 988.—Transverse section through the equatorial plane of three aggregated lymphatic nodules from the rabbit.




FIG. 989.—The myenteric plexus from the rabbit.  $\times 50$ .

vessels numerous branches are given off, which pierce the muscular coat, supplying it and forming an intricate plexus in the submucous tissue. From this plexus minute vessels pass to the glands and villi of the mucous membrane. The **veins** have a similar course and arrangement to the arteries. The **lymphatics** of the small intestine (lacteals) are arranged in two sets, those of the mucous membrane and those of the muscular coat. The lymphatics of the villi commence in these structures in the manner described above. They form an intricate plexus in the mucous

and submucous tissue, being joined by the lymphatics from the lymph spaces at the bases of the solitary nodules, and from this pass to larger vessels at the mesenteric border of the gut. The lymphatics of the muscular coat are situated to a great extent between the two layers of muscular fibres, where they form a close plexus; throughout their course they communicate freely with the lymphatics from the mucous membrane, and empty themselves in the same manner as these into the origins of the lacteal vessels at the attached border of the gut.



FIG. 990.—The plexus of the submucosa from the rabbit.  $\times 50$ .

The **nerves** of the small intestines are derived from the plexuses of sympathetic nerves around the superior mesenteric artery. From this source they run to the **mesenteric plexus** (*Auerbach's plexus*) (Fig. 989) of nerves and ganglia situated between the circular and longitudinal muscular fibres from which the nervous branches are distributed to the muscular coats of the intestine. From this a secondary plexus, the **plexus of the submucosa** (*Meissner's plexus*) (Fig. 990) is derived, and is formed by branches which have perforated the circular muscular fibres. This plexus lies in the submucous coat of the intestine; it also contains ganglia from which nerve fibres pass to the muscularis mucosae and to the mucous membrane. The nerve bundles of the submucous plexus are finer than those of the myenteric plexus.

### The Large Intestine (*Intestinum Crassum*).

The **large intestine** extends from the end of the ileum to the anus. It is about 1.5 metres long, being one-fifth of the whole extent of the intestinal canal. Its calibre is largest at its commencement at the cecum, and gradually diminishes



as far as the rectum, where there is a dilatation of considerable size just above the anal canal. It differs from the small intestine in its greater calibre, its more fixed position, its sacculated form, and in possessing certain appendages to its external coat, the **appendices epiploicae**. Further, its longitudinal muscular fibres do not form a continuous layer around the gut, but are arranged in three **longitudinal bands** or **taeniae**. The large intestine, in its course, describes an arch which surrounds the convolutions of the small intestine. It commences in the right iliac region, in a dilated part, the **cecum**. It ascends through the right lumbar and hypochondriac regions to the under surface of the liver; it here takes a bend, the **right colic flexure**, to the left and passes transversely across the abdomen on the confines of the epigastric and umbilical regions, to the left hypochondriac region; it then bends again, the **left colic flexure**, and descends through the left lumbar and iliac regions to the pelvis, where it forms a bend called the **sigmoid flexure**; from this it is continued along the posterior wall of the pelvis to the anus. The large intestine is divided into the **cecum**, **colon**, **rectum**, and **anal canal**.




FIG. 991.—The cecum and vermiform process, with their arteries.

The **Cecum** (*intestinum caecum*) (Fig. 991), the commencement of the large intestine, is the large blind pouch situated below the colic valve. Its blind end is directed downward, and its open end upward, communicating directly with the colon, of which this blind pouch appears to be the beginning or head, and hence the old name of **caput caecum coli** was applied to it. Its size is variously estimated by different authors, but on an average it may be said to be 6.25 cm. in length and 7.5 in breadth. It is situated in the right iliac fossa, above the lateral half of the inguinal ligament: it rests on the Iliacus and Psoas major, and usually lies in contact with the anterior abdominal wall, but the greater omentum and, if the cecum be empty, some coils of small intestine may lie in front of it. As a rule, it is entirely enveloped by peritoneum, but in a certain number of cases (5 per cent., Berry) the peritoneal covering is not complete, so that the upper part of the posterior surface is uncovered and connected to the iliac fascia by connective tissue. The cecum lies quite free in the abdominal cavity and enjoys a considerable amount of movement, so that

it may become herniated down the right inguinal canal, and has occasionally been found in an inguinal hernia on the left side. The cecum varies in shape, but, according to Treves, in man it may be classified under one of four types. In early fetal life it is short, conical, and broad at the base, with its apex turned upward and medialward toward the ileocolic junction. It then resembles the cecum of some monkeys, *e. g.*, mangabey monkey. As the fetus grows the cecum increases in length more than in breadth, so that it forms a longer tube than in the primitive form and without the broad base, but with the same inclination of the apex toward the ileocolic junction. This form is seen in other monkeys, *e. g.*, the spider monkey. As development goes on, the lower part of the tube ceases to grow and the upper part becomes greatly increased, so that at birth there is a narrow tube, the vermiform process, hanging from a conical projection, the cecum. This is the infantile form, and as it persists throughout life in about 2 per cent. of cases, it is regarded by Treves as the *first* of his four types of human ceca. The cecum is conical and the appendix rises from its apex. The three longitudinal bands start from the appendix and are equidistant from each other. In the second type, the conical cecum has become quadrate by the growing out of a sacculi on either side of the anterior longitudinal band. These sacculi are of equal size, and the appendix arises from between them, instead of from the apex of a cone. This type is found in about 3 per cent. of cases. The *third* type is the normal type of man. Here the two sacculi, which in the second type were uniform, have grown at unequal rates: the right with greater rapidity than the left. In consequence of this an apparently new apex has been formed by the growing downward of the right sacculi, and the original apex, with the appendix attached, is pushed over to the left toward the ileocolic junction. The three longitudinal bands still start from the base of the vermiform process, but they are now no longer equidistant from each other, because the right sacculi has grown between the anterior and posterolateral bands, pushing them over to the left. This type occurs in about 90 per cent. of cases. The *fourth* type is merely an exaggerated condition of the third; the right sacculi is still larger, and at the same time the left sacculi has become atrophied, so that the original apex of the cecum, with the vermiform process, is close to the ileocolic junction, and the anterior band courses medialward to the same situation. This type is present in about 4 per cent. of cases.

The **Vermiform Process** or **Appendix** (*processus vermiformis*) (Fig. 991) is a long, narrow, worm-shaped tube, which starts from what was originally the apex of the cecum, and may pass in one of several directions: upward behind the cecum; to the left behind the ileum and mesentery; or downward into the lesser pelvis. It varies from 2 to 20 cm. in length, its average being about 8.3 cm. It is retained in position by a fold of peritoneum (mesenteriole), derived from the left leaf of the mesentery. This fold, in the majority of cases, is more or less triangular in shape, and as a rule extends along the entire length of the tube. Between its two layers and close to its free margin lies the appendicular artery (Fig. 991). The canal of the vermiform process is small, extends throughout the whole length of the tube, and communicates with the cecum by an orifice which is placed below and behind the ileocecal opening. It is sometimes guarded by a semilunar valve formed by a fold of mucous membrane, but this is by no means constant.

**Structure.**—The coats of the vermiform process are the same as those of the intestine: serous, muscular, submucous, and mucous. The **serous coat** forms a complete investment for the tube, except along the narrow line of attachment of its mesenteriole in its proximal two-thirds. The **longitudinal muscular fibres** do not form three bands as in the greater part of the large intestine, but invest the whole organ, except at one or two points where both the longitudinal and circular fibres are deficient so that the peritoneal and submucous coats are contiguous over small areas.

The **circular muscle fibres** form a much thicker layer than the longitudinal fibres, and are separated from them by a small amount of connective tissue. The **submucous coat** is well marked, and contains a large number of masses of lymphoid tissue which cause the mucous



membrane to bulge into the lumen and so render the latter of small size and irregular shape. The **mucous membrane** is lined by columnar epithelium and resembles that of the rest of the large intestine, but the intestinal glands are fewer in number (Fig. 992).




FIG. 992.—Transverse section of human vermiform process.  $\times 20$ .

**The Colic Valve** (*valvula coli*; *ileocecal valve*) (Fig. 993).—The lower end of the ileum ends by opening into the medial and back part of the large intestine, at the point of junction of the cecum with the colon. The opening is guarded by a valve, consisting of two segments or lips, which project into the lumen of the large intestine. If the intestine has been inflated and dried, the lips are of a semilunar shape. The upper one, nearly horizontal in direction, is attached by its convex border




FIG. 993.—Interior of the cecum and lower end of ascending colon, showing colic valve.

to the line of junction of the ileum with the colon; the lower lip, which is longer and more concave, is attached to the line of junction of the ileum with the cecum. At the ends of the aperture the two segments of the valve coalesce, and are continued as narrow membranous ridges around the canal for a short distance, forming the **frenula of the valve**. The left or anterior end of the aperture is rounded; the right or posterior is narrow and pointed. In the fresh condition, or in specimens which

have been hardened *in situ*, the lips project as thick cushion-like folds into the lumen of the large gut, while the opening between them may present the appearance of a slit or may be somewhat oval in shape.

Each lip of the valve is formed by a reduplication of the mucous membrane and of the circular muscular fibres of the intestine, the longitudinal fibres and peritoneum being continued uninterruptedly from the small to the large intestine.

The surfaces of the valve directed toward the ileum are covered with villi, and present the characteristic structure of the mucous membrane of the small intestine; while those turned toward the large intestine are destitute of villi, and marked with the orifices of the numerous tubular glands peculiar to the mucous membrane of the large intestine. These differences in structure continue as far as the free margins of the valve. It is generally maintained that this valve prevents reflux from the cecum into the ileum, but in all probability it acts as a sphincter around the end of the ileum and prevents the contents of the ileum from passing too quickly into the cecum.

The **Colon** is divided into four parts: the **ascending**, **transverse**, **descending**, and **sigmoid**.

The **Ascending Colon** (*colon ascendens*) is smaller in calibre than the cecum, with which it is continuous. It passes upward, from its commencement at the cecum, opposite the colic valve, to the under surface of the right lobe of the liver, on the right of the gall-bladder, where it is lodged in a shallow depression, the **colic impression**; here it bends abruptly forward and to the left, forming the **right colic (hepatic) flexure** (Fig. 980). It is retained in contact with the posterior wall of the abdomen by the peritoneum, which covers its anterior surface and sides, its posterior surface being connected by loose areolar tissue with the Iliacus, Quadratus lumborum, aponeurotic origin of Transversus abdominis, and with the front of the lower and lateral part of the right kidney. Sometimes the peritoneum completely invests it, and forms a distinct but narrow mesocolon.<sup>1</sup> It is in relation, in front, with the convolutions of the ileum and the abdominal parietes.

The **Transverse Colon** (*colon transversum*) the longest and most movable part of the colon, passes with a downward convexity from the right hypochondriac region across the abdomen, opposite the confines of the epigastric and umbilical zones, into the left hypochondriac region, where it curves sharply on itself beneath the lower end of the spleen, forming the **left colic (splenic) flexure**. In its course it describes an arch, the concavity of which is directed backward and a little upward; toward its splenic end there is often an abrupt U-shaped curve which may descend lower than the main curve. It is almost completely invested by peritoneum, and is connected to the inferior border of the pancreas by a large and wide duplicature of that membrane, the **transverse mesocolon**. It is in relation, by its upper surface, with the liver and gall-bladder, the greater curvature of the stomach, and the lower end of the spleen; by its under surface, with the small intestines; by its anterior surface, with the anterior layers of the greater omentum and the abdominal parietes; its posterior surface is in relation from right to left with the descending portion of the duodenum, the head of the pancreas, and some of the convolutions of the jejunum and ileum.

The **left colic or splenic flexure** (Fig. 980) is situated at the junction of the transverse and descending parts of the colon, and is in relation with the lower end of the spleen and the tail of the pancreas; the flexure is so acute that the end of the transverse colon usually lies in contact with the front of the descending colon. It lies

<sup>1</sup> Treves states that, after a careful examination of one hundred subjects, he found that in fifty-two there was neither an ascending nor a descending mesocolon. In twenty-two there was a descending mesocolon, but no trace of a corresponding fold on the other side. In fourteen subjects there was a mesocolon to both the ascending and the descending segments of the bowel; while in the remaining twelve there was an ascending mesocolon, but no corresponding fold on the left side. It follows, therefore, that in performing lumbar colotomy a mesocolon may be expected upon the left side in 36 per cent. of all cases, and on the right in 26 per cent.—The Anatomy of the Intestinal Canal and Peritoneum in Man, 1885, p. 55.

at a higher level than, and on a plane posterior to, the right colic flexure, and is attached to the Diaphragma, opposite the tenth and eleventh ribs, by a peritoneal fold, named the **phrenicocolic ligament**, which assists in supporting the lower end of the spleen (see page 1157).

The **Descending Colon**<sup>1</sup> (*colon descendens*) passes downward through the left hypochondriac and lumbar regions along the lateral border of the left kidney. At the lower end of the kidney it turns medialward toward the lateral border of the Psoas, and then descends, in the angle between Psoas and Quadratus lumborum, to the crest of the ilium, where it ends in the iliac colon. The peritoneum covers its anterior surface and sides, while its posterior surface is connected by areolar tissue with the lower and lateral part of the left kidney, the aponeurotic origin of the Transversus abdominis, and the Quadratus lumborum (Fig. 980). It is smaller in calibre and more deeply placed than the ascending colon, and is more frequently covered with peritoneum on its posterior surface than the ascending colon (Treves). In front of it are some coils of small intestine.




FIG. 994.—Iliac colon, sigmoid or pelvic colon, and rectum seen from the front, after removal of pubic bones and bladder.

The **Iliac Colon** (Fig. 994) is situated in the left iliac fossa, and is about 12 to 15 cm. long. It begins at the level of the iliac crest, where it is continuous with the descending colon, and ends in the sigmoid colon at the superior aperture of the lesser pelvis. It curves downward and medialward in front of the Iliacus and Psoas, and, as a rule, is covered by peritoneum on its sides and anterior surface only.

The **Sigmoid Colon** (*colon sigmoideum*; *pelvic colon*; *sigmoid flexure*) (Fig. 994) forms a loop which averages about 40 cm. in length, and normally lies within the pelvis, but on account of its freedom of movement it is liable to be displaced into

<sup>1</sup> In the Basle nomenclature the descending colon is the portion between the left colic flexure and the superior aperture of the lesser pelvis; it is, however, convenient to still describe its lowest part as the iliac colon.

the abdominal cavity. It begins at the superior aperture of the lesser pelvis, where it is continuous with the iliac colon, and passes transversely across the front of the sacrum to the right side of the pelvis; it then curves on itself and turns toward the left to reach the middle line at the level of the third piece of the sacrum, where it bends downward and ends in the rectum. It is completely surrounded by peritoneum, which forms a mesentery (**sigmoid mesocolon**), which diminishes in length from the centre toward the ends of the loop, where it disappears, so that the loop is fixed at its junctions with the iliac colon and rectum, but enjoys a considerable range of movement in its central portion. *Behind* the sigmoid colon are the external iliac vessels, the left Piriformis, and left sacral plexus of nerves; in *front*, it is separated from the bladder in the male, and the uterus in the female, by some coils of the small intestine.




FIG. 995.—The posterior aspect of the rectum exposed by removing the lower part of the sacrum and the coccyx.

The **Rectum** (*intestinum rectum*) (Fig. 995) is continuous above with the sigmoid colon, while below it ends in the anal canal. From its origin at the level of the third sacral vertebra it passes downward, lying in the sacrococcygeal curve, and extends for about 2.5 cm. in front of, and a little below, the tip of the coccyx, as far as the apex of the prostate. It then bends sharply backward into the anal canal. It therefore presents two antero-posterior curves: an upper, with its con-

vexity backward, and a lower, with its convexity forward. Two lateral curves are also described, one to the right opposite the junction of the third and fourth sacral vertebræ, and the other to the left, opposite the left sacrococcygeal articulation; they are, however, of little importance. The rectum is about 12 cm. long, and at its commencement its calibre is similar to that of the sigmoid colon, but near its termination it is dilated to form the **rectal ampulla**. The rectum has no sacculations comparable to those of the colon, but when the lower part of the rectum is contracted, its mucous membrane is thrown into a number of folds, which are longitudinal in direction and are effaced by the distension of the gut. Besides these there are certain permanent transverse folds, of a semilunar shape, known as **Houston's valves** (Fig. 996). They are usually three in number; sometimes a fourth is found, and occasionally only two are present. One is situated near the commencement of the rectum, on the right side; a second extends inward from the left side of the tube, opposite the middle of the sacrum; a third, the largest and most constant, projects backward from the forepart of the rectum, opposite the fundus of the urinary bladder. When a fourth is present, it is situated nearly 2.5 cm. above the anus on the left and posterior wall of the tube. These folds are about 12 mm. in width, and contain some of the circular fibres of the gut. In the empty state of the intestines they overlap each other, as Houston remarks, so effectually as to require considerable manoeuvring to conduct a bougie or the finger along the canal. Their use seems to be, "to support the weight of fecal matter, and prevent its urging toward the anus, where its presence always excites a sensation demanding its discharge."<sup>1</sup>

The peritoneum is related to the upper two-thirds of the rectum, covering at first its front and sides, but lower down its front only; from the latter it is reflected on to the seminal vesicles in the male and the posterior vaginal wall in the female.

The level at which the peritoneum leaves the anterior wall of the rectum to be reflected on to the viscus in front of it is of considerable importance from a surgical point of view, in connection with the removal of the lower part of the rectum. It is higher in the male than in the female. In the former the height of the rectovesical excavation is about 7.5 cm., *i. e.*, the height to which an ordinary index finger can reach from the anus. In the female the height of the rectouterine excavation is about 5.5 cm. from the anal orifice. The rectum is surrounded by a dense tube of fascia derived from the fascia endopelvina, but fused behind with the fascia covering the sacrum and coccyx. The facial tube is loosely attached to the rectal wall by areolar tissue in order to allow of distension of the viscus.

**Relations of the Rectum.**—The upper part of the rectum is in relation, *behind*, with the superior hemorrhoidal vessels, the left Piriformis, and left sacral plexus of nerves, which separate it from the pelvic surfaces of the sacral vertebræ; in its lower part it lies directly on the sacrum, coccyx, and Levatores ani, a dense fascia alone intervening; *in front*, it is separated above, in the male, from the fundus of the bladder; in the female, from the intestinal surface of the uterus and its




FIG. 996.—Coronal section of rectum and anal canal.

<sup>1</sup> Paterson ("The Form of the Rectum," *Journal of Anatomy and Physiology*, vol. xliii) utilises the third fold for the purpose of dividing the rectum into an upper and a lower portion; he considers the latter "to be just as much a duct as the narrower anal canal below," and maintains that, under normal conditions, it does not contain feces except during the act of defecation.



appendages, by some convolutions of the small intestine, and frequently by the sigmoid colon; *below*, it is in relation in the male with the triangular portion of the fundus of the bladder, the vesiculæ seminales, and ductus deferentes, and more anteriorly with the posterior surface of the prostate; in the female, with the posterior wall of the vagina.

The **Anal Canal** (*pars analis recti*) (Fig. 997), or terminal portion of the large intestine, begins at the level of the apex of the prostate, is directed downward and

backward, and ends at the anus. It forms an angle with the lower part of the rectum, and measures from 2.5 to 4 cm. in length. It has no peritoneal covering, but is invested by the Sphincter ani internus, supported by the Levatores ani, and surrounded at its termination by the Sphincter ani externus. In the empty condition it presents the appearance of an antero-posterior longitudinal slit. Behind it is a mass of muscular and fibrous tissue, the **anococcygeal body** (Symington); in front of it, in the male, but separated by connective tissue from it, are the membranous portion and bulb of the urethra, and the fascia of the urogenital diaphragm; and in the female it is separated from the lower end of the vagina by a mass of muscular and fibrous tissue, named the **perineal body**.

The lumen of the anal canal presents, in its upper half, a number of vertical folds, produced by an infolding of the mucous membrane and some of




FIG. 997.—Coronal section through the anal canal. (Symington.) B. Cavity of urinary bladder. V.D. Ductus deferens. S.V. Seminal vesicle. R. Second part of rectum. A.C. Anal canal. L.A. Levator ani. I.S. Sphincter ani internus. E.S. Sphincter ani externus.

the muscular tissue. They are known as the **rectal columns** [*Morgagni*] (Fig. 996), and are separated from one another by furrows (**rectal sinuses**), which end below in small valve-like folds, termed **anal valves**, which join together the lower ends of the rectal columns.

**Structure of the Colon.**—The large intestine has four coats: **serous, muscular, areolar, and mucous.**

The **serous coat** (*tunica serosa*) is derived from the peritoneum, and invests the different portions of the large intestine to a variable extent. The cecum is completely covered by the serous membrane, except in about 5 per cent. of cases where the upper part of the posterior surface is uncovered. The ascending, descending, and iliac parts of the colon are usually covered only in front and at the sides; a variable amount of the posterior surface is uncovered.<sup>1</sup> The transverse colon is almost completely invested, the parts corresponding to the attachment of the greater omentum and transverse mesocolon being alone excepted. The sigmoid colon is entirely surrounded. The rectum is covered above on its anterior surface and sides; below, on its anterior aspect only; the anal canal is entirely devoid of any serous covering. In the course of the colon the peritoneal coat is thrown into a number of small pouches filled with fat, called **appendices epiploicæ**. They are most numerous on the transverse colon.

The **muscular coat** (*tunica muscularis*) consists of an external longitudinal, and an internal circular, layer of non-striped muscular fibres.

The **longitudinal fibres** do not form a continuous layer over the whole surface of the large intestine. In the cecum and colon they are especially collected into three flat longitudinal bands (*taeniae coli*), each of about 12 mm. in width; one, the posterior, is placed along the attached border of the intestine; the anterior, the largest, corresponds along the arch of the colon to the attachment of the greater omentum, but is in front in the ascending, descending, and iliac parts of the colon, and in the sigmoid colon; the third, or lateral band, is found on the medial side of the ascending and descending parts of the colon, and on the under aspect of the transverse colon.

<sup>1</sup> See footnote, p. 1180.

These bands are shorter than the other coats of the intestine, and serve to produce the sacculi which are characteristic of the cecum and colon; accordingly, when they are dissected off, the tube can be lengthened, and its sacculated character becomes lost. In the sigmoid colon the longitudinal fibres become more scattered; and around the rectum they spread out and form a layer, which completely encircles this portion of the gut, but is thicker on the anterior and posterior surfaces, where it forms two bands, than on the lateral surfaces. In addition, two bands of plain muscular tissue arise from the second and third coccygeal vertebræ, and pass downward and forward to blend with the longitudinal muscular fibres on the posterior wall of the anal canal. These are known as the **Rectococcygeal muscles**.

The *circular fibres* form a thin layer over the cecum and colon, being especially accumulated in the intervals between the sacculi; in the rectum they form a thick layer, and in the anal canal they become numerous, and constitute the *Sphincter ani internus*.

The **areolar coat** (*tela submucosa*; *submucous coat*) connects the muscular and mucous layers closely together.

The **mucous membrane** (*tunica mucosa*) in the cecum and colon, is pale, smooth, destitute of villi, and raised into numerous *crenate* folds which correspond to the intervals between the sacculi. In the rectum it is thicker, of a darker color, more vascular, and connected loosely to the muscular coat, as in the œsophagus.




FIG. 998.—Section of mucous membrane of human rectum. (Sobotta.)  $\times 60$ .

As in the small intestine, the mucous membrane (Fig. 998) consists of a muscular layer, the *muscularis mucosæ*; a quantity of retiform tissue in which the vessels ramify; a basement-membrane and epithelium which is of the columnar variety, and resembles the epithelium found in the small intestine. The mucous membrane of the large intestine presents for examination glands and solitary lymphatic nodules.

The glands of the great intestine are minute tubular prolongations of the mucous membrane arranged perpendicularly, side by side, over its entire surface; they are longer, more numerous, and placed in much closer apposition than those of the small intestine; and they open by minute rounded orifices upon the surface, giving it a cribriform appearance. Each gland is lined by short columnar epithelium and contains numerous goblet cells.

The **solitary lymphatic nodules** (*noduli lymphatici solitarii*) (Fig. 998) of the large intestine are most abundant in the cecum and vermiform process, but are irregularly scattered also over the rest of the intestine. They are similar to those of the small intestine.

**Vessels and Nerves.**—The **arteries** supplying the colon are derived from the colic and sigmoid branches of the mesenteric arteries. They give off large branches, which ramify between and supply the muscular coats, and after dividing into small vessels in the submucous tissue, pass to the mucous membrane. The rectum is supplied by the superior hemorrhoidal branch of the inferior mesenteric, and the anal canal by the middle hemorrhoidal from the hypogastric, and the inferior hemorrhoidal from the internal pudendal artery. The superior hemorrhoidal, the continuation of the superior mesenteric, divides into two branches, which run down either side of the rectum to within about 12.5 cm. of the anus; they here split up into about six branches, which pierce the muscular coat and descend between it and the mucous membrane in a longi-

tudinal direction, parallel with each other as far as the Sphincter ani internus, where they anastomose with the other hemorrhoidal arteries and form a series of loops around the anus. The **veins** of the rectum commence in a plexus of vessels which surrounds the anal canal. In the vessels forming this plexus are smaller saccular dilatations just within the margin of the anus; from the plexus about six vessels of considerable size are given off. These ascend between the muscular and mucous coats for about 12.5 cm., running parallel to each other; they then pierce the muscular coat, and, by their union, form a single trunk, the superior hemorrhoidal vein. This arrangement is termed the **hemorrhoidal plexus**; it communicates with the tributaries of the middle and inferior hemorrhoidal veins, at its commencement, and thus a communication is established between the systemic and portal circulations. The **lymphatics** of the large intestine are described on page 792. The **nerves** are derived from the sympathetic plexuses around the branches of the superior and inferior mesenteric arteries. They are distributed in a similar way to those found in the small intestine.

**Applied Anatomy.**—The small intestine is much exposed to injury, but, in consequence of elasticity and the ease with which one coil glides over another, it is not so frequently ruptured as would otherwise be the case. Any part of it may be ruptured, but probably the most common situation is the horizontal portion of the duodenum, on account of its being more fixed than other portions of the bowel, and because it is situated in front of the bodies of the vertebrae, so that if this portion of the intestine is struck by a sharp blow, as from the kick of a horse, it is unable to glide out of the way, but is compressed against the bone and so lacerated. Wounds of the intestine sometimes occur. If the wound is a small puncture, under, it is said, 6 mm. in length, no extravasation of the contents of the bowel takes place; the mucous membrane becomes everted and plugs the little opening. The small intestine, and most frequently the ileum, may become strangulated by internal bands, or through apertures, normal or abnormal. The bands may be formed in several different ways: they may be old peritoneal adhesions from previous attacks of peritonitis; or an adherent omentum from the same cause; or the band may be formed by Meckel's diverticulum, which has contracted adhesions at its distal extremity; or it may be the result of the abnormal attachment of some normal structure, as the adhesion of two appendices epiploicae, or an adherent vermiform process or uterine tube. Intussusception, most commonly an invagination of the small intestine into the large, may take place; it may attain great size, and it is not uncommon in these cases to find the colic valve projecting from the anus. Stricture, the impaction of foreign bodies, and twisting of the gut (*volvulus*) may also lead to intestinal obstruction.

Resection of a portion of the intestine may be required in cases of gangrene; for the removal of new growth in the bowel; in dealing with artificial anus; and in cases of rupture. The operation is termed *enterectomy*, and is performed as follows: the abdomen having been opened and the amount of bowel requiring removal having been determined upon, the intestine must be clamped on either side of this portion in order to prevent the escape of any of its contents during the operation. The portion of the bowel is then separated above and below by means of scissors. If the portion resected is small, it may be simply removed from the mesentery at its attachment, and the bleeding vessels tied; but if it be large it will be necessary to take away a triangular piece of the mesentery, and, having secured the vessels, suture the cut edges of this structure together. In doing this, care must be taken not to leave any intestine projecting beyond the line of the section of mesentery, as gangrene is very likely to occur in the projecting part if this is done. The surgeon then proceeds to unite the cut ends of the bowel together by what is termed end-to-end anastomosis. There are many ways of doing this, which may be divided into two classes, one where the anastomosis is made by means of some mechanical appliance, such as Murphy's button, or one of the forms of decalcified bone bobbin; and the other, where the operation is performed by suturing the ends of the bowel in such a manner that the peritoneum covering the two divided ends is brought into contact, so that speedy union may ensue.

The vermiform process is very liable to become inflamed, because it contains a relatively large amount of lymphoid tissue, which is prone to bacterial infection. In many cases the inflammation is set up by the impaction in it of a solid mass of feces or a foreign body, or by the inspissation of its mucous secretion in catarrhal conditions. The inflammation may result in ulceration and perforation, or if very acute in gangrene of the process. These conditions generally require immediate operative interference, and in chronic cases with recurring attacks of inflammation it is always advisable to remove this diverticulum of the bowel. In incising the abdominal wall for this operation, the muscles should be split in the direction of their fibres rather than cut across in order to prevent subsequent weakening of the abdominal parietes and the occurrence of a ventral hernia. After the process has been removed it is better to suture the planes of the abdominal wall separately.

In external hernia the ileum is the portion of bowel most frequently herniated. When a part of the large intestine is involved it is usually the cecum, and this may occur even on the left side. In some few cases the vermiform process has been the part implicated in strangulated hernia.

Chronic ulcer of the duodenum is sometimes met with, probably produced by the same causes as chronic ulcer of the stomach. It may perforate and set up a rapidly fatal peritonitis, or it

may open into one of the large duodenal vessels and cause death from hemorrhage. An acute ulcer sometimes, but rarely, follows extensive burns of the skin.

The calibre of the large intestine gradually diminishes from the cecum, which has the greatest diameter of any part of the bowel, to the point of junction of the sigmoid colon with the rectum. At or a little below this point stricture most commonly occurs, and diminishes in frequency as one proceeds upward to the cecum. When distended by some obstruction low down, the outline of the large intestine can be defined throughout nearly the whole of its course—all, in fact, except the right and left colic flexures, which are more deeply placed; the distension is most obvious in the flanks and on the front of the abdomen just above the umbilicus. The cecum, however, is the portion of the bowel which becomes most distended. It may assume enormous dimensions, and has been known to give way from the distension, causing fatal peritonitis. The right colic flexure and the right extremity of the transverse colon are in close relationship with the liver, and abscess of this viscus sometimes bursts into the gut in this situation. The gall-bladder may become adherent to the colon, and gallstones may find their way into the latter and may become impacted or may be discharged per anum. The mobility of the sigmoid colon renders it more liable to become the seat of a volvulus or twist than any other part of the intestine. It generally occurs in patients who have been the subjects of habitual constipation, and in whom, therefore, the mesocolon is elongated. The gut at this part, being loaded with feces, falls over the part below, and so gives rise to the twist.

**Hernia.**—The two chief sites at which external hernia may take place are the inguinal region and the femoral canal. The description of the inguinal canal and its relations will be found on page 508, and that of the femoral canal on page 712. Some points in regard to the disposition of the peritoneum in these regions may, however, be recapitulated here.

Between the upper margin of the front of the pelvis and the umbilicus, the peritoneum, when viewed from behind, will be seen to be raised into five folds, with intervening depressions, by more or less prominent bands which converge to the umbilicus (Fig. 962). The middle umbilical ligament, situated in the middle line, is covered by a fold of peritoneum known as the **middle umbilical fold**. On either side of this a fold of peritoneum around the obliterated umbilical artery forms the **lateral umbilical fold**. To either side of these three cords is the inferior epigastric artery covered by the **epigastric fold**. Between these raised folds are depressions constituting the so-called **foveæ**. The most medial, between the middle and lateral umbilical folds, is known as the **supravesical fovea**. The intermediate one is situated medial to the plica epigastrica, and is termed the **medial inguinal fovea**. The third is lateral to the plica epigastrica, and is known as the **lateral inguinal fovea**. Occasionally the inferior epigastric artery corresponds in position to the obliterated hypogastric artery, and then there is but one fold on each side of the middle line. In the usual position of the parts, the floor of the lateral inguinal fovea corresponds to the abdominal inguinal ring, and into this fovea an oblique inguinal hernia descends. Medial to the epigastric fold are the medial inguinal and the supravesical foveæ, and through either of these a direct hernia may descend. The whole of the space between the inferior epigastric artery, the margin of the Rectus abdominis, and the inguinal ligament is known as **Hesselbach's triangle**. Below the level of the inguinal ligament is a small depression corresponding to the position of the femoral ring. It is known as the **femoral fovea**, and into it a femoral hernia descends.

**Inguinal Hernia.**—Inguinal hernia is that form of protrusion which makes its way through the abdominal wall in the inguinal region. There are two principal varieties of it: lateral or oblique, and medial or direct.

In *oblique inguinal hernia* the intestine escapes from the abdominal cavity at the abdominal inguinal ring, pushing before it a pouch of peritoneum which forms the hernial sac. As it enters the inguinal canal it receives an investment from the extraperitoneal tissue and is enclosed in the infundibuliform fascia. In passing along the inguinal canal it displaces upward the arched fibres of the Transversus and Obliquus internus, and receives a covering of Cremaster muscle and cremasteric fascia. It then passes along the front of the spermatic cord and escapes from the inguinal canal at the subcutaneous inguinal ring, becoming invested by intercrural fascia. Lastly it descends into the scrotum, receiving coverings from the superficial fascia and the integument.

The seat of stricture in oblique inguinal hernia is at either the abdominal or the subcutaneous inguinal ring; most frequently in the latter situation. If it is situated at the subcutaneous ring, the division of a few fibres at one point of the circumference is all that is necessary for the replacement of the hernia. If at the abdominal ring, it is necessary to divide the aponeurosis of the Obliquus externus so as to lay open the inguinal canal, in dividing the aponeurosis the incision should be directed parallel to the inguinal ligament, and the constriction at the abdominal ring should then be divided directly upward.

When the intestine passes along the inguinal canal and escapes from the subcutaneous ring into the scrotum, it is called *complete oblique inguinal* or *scrotal hernia*. If the intestine does not escape from the subcutaneous ring, but is retained in the inguinal canal, it is called *incomplete inguinal hernia* or *bubonocoele*. In each of these cases the coverings which invest it will depend upon the extent to which it descends in the inguinal canal.

There are some other varieties of oblique inguinal hernia (Fig. 999) depending upon congenital defects in the saccus vaginalis, the pouch of peritoneum which precedes the descent of the testis. Normally this pouch is closed before birth, closure commencing at two points, viz., at the abdominal inguinal ring and at the top of the epididymis, and gradually extending until the whole of the intervening portion is converted into a fibrous cord. From failure in the completion of this

process, variations in the relation of the hernial protrusion to the testis and tunica vaginalis are produced; these constitute distinct varieties of inguinal hernia, viz., the hernia of the funicular process and the complete congenital variety.

Where the saccus vaginalis remains patent throughout, the cavity of the tunica vaginalis communicates directly with that of the peritoneum. The intestine descends along this pouch into the cavity of the tunica vaginalis which constitutes the sac of the hernia, and the gut lies in contact with the testis. Though this form of hernia is termed *complete congenital*, the term does not imply that the hernia existed at birth, but merely that a condition is present which may allow of the descent of the hernia at any moment. As a matter of fact, congenital herniæ frequently do not appear until adult life.

Where the processus vaginalis is occluded at the lower point only, i. e., just above the testis, the intestine descends into the pouch of peritoneum as far as the testis, but is prevented




FIG. 999.—Varieties of oblique inguinal hernia.

from entering the sac of the tunica vaginalis by the septum which has formed between it and the pouch. This is known as *hernia into the funicular process* or *incomplete congenital hernia*; it differs from the former in that instead of enveloping the testis it lies above it.

In *direct inguinal hernia* the protrusion makes its way through some part of Hesselbach's triangle, either through (a) the lateral part, where only extraperitoneal tissue and transversalis fascia intervene between the peritoneum and the aponeurosis of the Obliquus externus; or through (b) the inguinal aponeurotic falx which stretches across the medial two-thirds of the triangle between the artery and the middle line. In the former the hernial protrusion escapes from the abdomen on the lateral side of the inguinal falx, pushes before it the peritoneum, extraperitoneal tissue, and transversalis fascia, and enters the inguinal canal. It passes along nearly the whole length of the canal and finally emerges from the subcutaneous ring, receiving an investment from the intercrural fascia. The coverings of this form of hernia are similar to those of the oblique form, except that a portion derived from the general layer of transversalis fascia replaces the infundibuliform fascia.

In the second form, which is the more frequent, the hernia is either forced through the fibres of the inguinal falx, or the falx is gradually distended in front of it so as to form a complete investment for it. The intestine then enters the lower end of the inguinal canal, escapes at the subcutaneous ring, lying on the medial side of the cord, and receives additional coverings from the intercrural fascia, the superficial fascia and the integument. The coverings of this form therefore differ from those of the oblique form in that the inguinal falx is substituted for the Cremaster, and the infundibuliform fascia is replaced by a portion of the general layer of the transversalis fascia.

The seat of stricture in both varieties of direct hernia is usually found either at the neck of the sac or at the subcutaneous ring. In that form which perforates the inguinal falx it not infrequently occurs at the edges of the fissure through which the gut passes. In all cases of inguinal hernia, whether direct or oblique, it is proper to divide the stricture directly upward; by cutting in this direction the incision is made parallel to the inferior epigastric artery—lateral to it in the oblique variety, medial to it in the direct form of hernia; all chance of wounding the vessel is thus avoided. Direct inguinal hernia is of much less frequent occurrence than oblique, and is found more often in men than in women. The main differences in position between it and the oblique form are: (a) it is placed over the pubis and not in the course of the inguinal canal; (b) the inferior epigastric artery runs on the lateral or iliac side of the neck of the sac; and (c) the spermatic cord lies along its lateral and posterior sides, not directly behind it as in oblique inguinal hernia.



**Femoral Hernia.**—In femoral hernia the protrusion of the intestine takes place through the femoral ring. As already described (page 712), this ring is closed by the femoral septum, a partition of modified extraperitoneal tissue; it is therefore a weak spot in the abdominal wall, and especially in the female, where the ring is larger and where profound changes are produced in the tissues of the abdomen by pregnancy. Femoral hernia is therefore more common in women than in men.

When a portion of intestine is forced through the femoral ring, it carries before it a pouch of peritoneum, which forms the hernial sac. It receives an investment from the extraperitoneal tissue or femoral septum, and descends along the femoral canal, or inner compartment of the sheath of the femoral vessels, as far as the fossa ovalis; at this point it changes its course, being prevented from extending farther down the sheath on account of the narrowing of the latter, and its close contact with the vessels, and also the close attachment of the superficial fascia and femoral sheath to the lower part of the circumference of the fossa ovalis. The tumor is consequently directed forward, pushing before it the fascia cribrosa, and then curves upward over the inguinal ligament and the lower part of the aponeurosis of the *Obliquus externus*, being covered by the superficial fascia and integument. While the hernia is contained in the femoral canal it is usually of small size, owing to the resisting nature of the surrounding parts, but when it escapes from the fossa ovalis into the loose areolar tissue of the groin it becomes considerably enlarged. The direction taken by a femoral hernia is at first downward, then forward and upward; in the application of taxis for the reduction of a femoral hernia therefore, pressure should be directed in the reverse order.

The coverings of a femoral hernia from within outward are: peritoneum, femoral septum, femoral sheath, fascia cribrosa, superficial fascia, and integument. Sir Astley Cooper has described an investment for femoral hernia under the name of *fascia propria*, lying immediately external to the peritoneal sac but frequently separated from it by some adipose tissue. Surgically it is important to remember the frequent existence of this layer on account of the ease with which an inexperienced operator may mistake the fascia for the peritoneal sac and the contained fat for omentum, as there is often a great excess of subperitoneal fatty tissue enclosed in the "*fascia propria*." In many cases it resembles a fatty tumor, but on further dissection the true hernial sac will be found in the centre of the mass of fat. The *fascia propria* is merely modified extraperitoneal tissue which has been thickened to form a membranous sheet by the pressure of the hernia.

When the intestine descends along the femoral canal only as far as the fossa ovalis the condition is known as *incomplete femoral hernia*. The small size of the protrusion in this form of hernia, on account of the firm and resisting nature of the canal in which it is contained, renders it an exceedingly dangerous variety of the disease, from the extreme difficulty of detecting the existence of the swelling, especially in corpulent subjects. The coverings of an incomplete femoral hernia would be from without inward: integument, superficial fascia, superior cornu of falciform margin of the fossa ovalis, femoral sheath, femoral septum, and peritoneum.

The seat of stricture of a femoral hernia varies: it may be in the peritoneum at the neck of the hernial sac; in the greater number of cases it is at the point of junction of the falciform margin of the fossa ovalis with the free edge of the lacunar ligament; or it may be at the margin of the fossa ovalis. The stricture should in every case be divided in a direction upward and medialward for a distance of about 4 to 6 mm. All vessels or other structures of importance in relation to the neck of the sac will thus be avoided.

The pubic tubercle forms an important landmark in serving to differentiate the inguinal from the femoral variety of hernia. The inguinal protrusion is above and medial to the tubercle, while the femoral is below and lateral to it.

There are several details of practical interest in connection with the mesentery which merit notice. (1) The depth of the mesentery—that is to say, the distance from its parietal to its intestinal attachment—is normally less than 20 cm., generally nearer 15 cm.; but under certain abnormal conditions it may become elongated, and this would appear to favor the occurrence of hernia of the intestine. (2) Not only may the depth of the mesentery be increased, but its point of attachment to the posterior abdominal wall may yield, and descend over the lumbar vertebræ. This condition, which is known under the name of *enteroptosis*, usually occurs in women who have borne many children, and is attended with general relaxation of the abdominal parietes. It produces a characteristic appearance, the abdomen being prominent and pendulous below, while above, it is flattened and constricted. (3) Holes are sometimes present in the mesentery, and these may be congenital, or may be the result of injury. They are of practical importance, since a knuckle of intestine may become herniated into one of them, causing acute strangulation. (4) The lymph glands contained between the two layers of the mesentery are frequently the seat of tuberculous deposit, especially in children.

The colon frequently requires opening in cases of intestinal obstruction, and by some surgeons this operation is performed in cases of cancer of the rectum as soon as the disease is recognized, in the hope that the symptoms may be relieved by removing the irritation produced by the passage of fecal matter over the diseased surface. The operation of colostomy may be performed

either in the iliac or lumbar region; but iliac colostomy has in the present day entirely superseded the lumbar operation. The main reason for preferring this operation is that a spur-shaped process of the mesocolon can be formed, which prevents any fecal matter finding its way past the artificial anus, and the greater ease in maintaining cleanliness. The sigmoid colon being entirely surrounded by peritoneum, a coil can be drawn out of the wound and opened, leaving the attachment of the mesocolon to form a spur, much as it does in an artificial anus caused by sloughing of the intestine after a strangulated hernia, and this prevents any fecal matter finding its way from the gut above the opening into that below. The operation is performed by making an incision 5 to 7 cm. long from a point 2.5 cm. medial to the anterior superior iliac spine, parallel to the inguinal ligament. The various muscular layers are cut through, and the peritoneum opened; the sigmoid colon is now sought for, pulled out of the wound, and fixed by passing a needle threaded with carbolized silk first through the mesocolon close to the gut, and then through the abdominal wall. The wound is dressed, and about the second day the protruding coil of intestine is opened.

The surgical anatomy of the rectum is of considerable importance. There may be congenital malformations due to arrest of, or imperfection in, development. Thus, there may be no proctodæal invagination (see page 174), and consequently a complete absence of the anus; or the hind-gut may be imperfectly developed, and there may be an absence of the rectum, though the anus is developed; or the ectodermal invagination may not communicate with the termination of the hind-gut from want of solution of continuity in the septum which in early fetal life exists between the two. The mucous membrane is thick and but loosely connected to the muscular coat beneath, and thus favors prolapse, especially in children. The vessels of the rectum are arranged, as mentioned above, longitudinally, and are contained in the loose cellular tissue between the mucous and muscular coats, and receive no support from surrounding tissues, and this favors varicosity. Moreover, the veins, after running upward in a longitudinal direction for about 12.5 cm. in the submucous tissue, pierce the muscular coats, and are liable to become constricted at this spot by the contraction of the muscular wall of the gut. In addition to this there are no valves in the superior hemorrhoidal veins, and the vessels of the rectum are placed in a dependent position, and are liable to be pressed upon and obstructed by hardened feces. The anatomical arrangement, therefore, of the hemorrhoidal vessels explains the great tendency to the occurrence of piles. The presence of the Sphincter ani externus is of surgical importance, since it is the constant contraction of this muscle which prevents an ischiorectal abscess from healing, and causes it to become a fistula. Also the reflex contraction of this muscle is the cause of the severe pain complained of in fissure of the anus. The relations of the peritoneum to the bowel are of importance in connection with the operation of removal of the rectum for malignant disease. This membrane gradually leaves the rectum as it descends into the pelvis; first leaving its posterior surface, then the sides, and then the anterior surface, to become reflected, in the male on to the posterior wall of the bladder, forming the rectovesical excavation, and in the female on to the posterior wall of the vagina, forming rectouterine excavation. The rectovesical excavation extends to within 7.5 cm. from the anus. Within recent years much more extensive operations have been done for the removal of cancer of the rectum, and in these the peritoneal cavity has necessarily been opened. If, in these cases, the opening is plugged with antiseptic gauze until the operation is completed and then the edges of the wound in the peritoneum are accurately brought together with sutures, no evil result appears to follow. For cases of cancer of the rectum which are too low to be reached by abdominal section, and too high to be removed by the perineum, Kraske has devised an operation which goes by his name. The patient is placed on his right side and an incision is made from the last piece of the sacrum to the anus. The soft parts are now separated from the back of the sides of the sacrum and coccyx, and the sacrotuberous and sacrospinous ligaments are separated. The coccyx is removed, and if necessary a small piece of the sacrum, and the edges of the wound being now forcibly drawn outward, a considerable length of the rectum is brought into view, and the diseased portion can be removed, leaving the anal portion of the gut, if healthy. The two divided ends of the gut can sometimes be approximated and sutured together, the posterior part being left open for drainage.

The loose connective tissue around the rectum is occasionally the site of an abscess, the active focus of which, however, may be located elsewhere. This form of abscess may be described as the *superior pelvic rectal*; it is placed above the pelvic diaphragm but beneath the peritoneum. The acute variety is generally due to ulceration or perforation of the bowel (possibly produced by a foreign body) above the level of attachment of the Levator ani. The abscess may also occur above a stricture (simple or malignant) of the rectum; occasionally it arises from suppuration around the prostate, and more rarely follows abscess of the vesiculæ seminales. Chronic abscesses also appear in the same region either from caries of the anterior surface of the sacrum or from caseation of the presacral lymph glands, while in other cases an abscess finds its way down into the pelvis from disease of the anterior surfaces of the bodies of the lumbar vertebrae.

**The Liver (Hepar).**

The liver is the largest gland in the body, and is situated in the upper and right parts of the abdominal cavity, occupying almost the whole of the right hypochondrium, the greater part of the epigastrium, and not uncommonly extending into the left hypochondrium as far as the mammary line. In the male it weighs from 1.4 to 1.6 kilogram., in the female from 1.2 to 1.4 kilogram. It is relatively much larger in the fetus than in the adult, constituting, in the former, about one-eighteenth, and in the latter about one thirty-sixth of the entire body weight. Its greatest transverse measurement is from 20 to 22.5 cm. Vertically, near its lateral or right surface, it measures about 15 to 17.5 cm., while its greatest antero-posterior diameter is on a level with the upper end of the right kidney, and is from 10 to 12.5 cm. Opposite the vertebral column its measurement from before backward is reduced to about 7.5 cm. Its consistence is that of a soft solid; it is, however, friable and easily lacerated; its color is a dark reddish brown, and its specific gravity is 1.05.

To obtain a correct idea of its shape it must be hardened *in situ*, and it will then be seen to present the appearance of a wedge, the base of which is directed to the right and the thin edge toward the left. Symington describes its shape as that "of a right-angled triangular prism with the right angle rounded off."

**Surfaces.**—The liver possesses five surfaces, viz., **superior, inferior, anterior, posterior, and right lateral.** A sharp, well-defined margin divides the inferior from the superior, anterior, and right lateral surfaces, but the other surfaces are separated from one another by rounded borders. The superior and anterior surfaces are attached to the Diaphragma and anterior abdominal wall by a triangular or falciform fold of peritoneum, the **falciform ligament**, in the free margin of which is a rounded cord, the **ligamentum teres (obliterated umbilical vein)**. The line of attachment of the falciform ligament divides the liver into two parts, termed the **right and left lobes**, the right being much the larger. The inferior and posterior surfaces are divided into five lobes by five fossæ, which are arranged in the form of the letter H. The left limb of the H marks on these surfaces the division of the liver into right and left lobes; it is known as the **left sagittal fossa**, and consists of two parts, viz., the **fossa for the umbilical vein** in front and the **fossa for the ductus venosus** behind. The right limb of the H is formed in front by the **fossa for the gall-bladder**, and behind by the **fossa for the inferior vena cava**; these two fossæ are separated from one another by a band of liver substance, termed the **caudate process**. The bar connecting the two limbs of the H is the **porta (transverse fissure)**; in front of it is the **quadrate lobe**, behind it the **caudate lobe**.

The **superior surface (facies superior)** (Fig. 1000) comprises a part of both lobes, and, as a whole, is convex, and fits under the vault of the Diaphragma; its central part, however, presents a shallow depression, which corresponds with the position of the pericardium on the upper surface of the Diaphragma. It is separated from the anterior, posterior, and right lateral surfaces by rounded borders. Its left extremity is separated from the under surface by a prominent sharp margin. Except along the lines of attachment of the falciform ligament it is completely covered by peritoneum.

The **anterior surface** is large, triangular in shape, and also comprises a part of both lobes. It is directed forward, and the greater part of it is in contact with the Diaphragma, which separates it on the right from the sixth to the tenth ribs and their cartilages, and on the left from the seventh and eighth costal cartilages. Its middle part lies behind the xiphoid process, and, in the angle between the diverging rib cartilage of opposite sides, is in contact with the abdominal wall. It is separated from the inferior surface by a sharp margin, and from the superior and right lateral surfaces by rounded borders. It is completely covered by peritoneum except along the line of attachment of the falciform ligament.

The **right lateral surface** is covered by peritoneum, and is convex from before backward and slightly so from above downward. It is directed toward the right side, forming the base of the wedge, and lies against the lateral portion of the Diaphragm, which separates it from the lower part of the pleura and lung, outside which are the right costal arches from the seventh to the eleventh inclusive.




FIG. 1000.—The superior, anterior, and right lateral surfaces of the liver. (From model by His.)

The **inferior surface** (*facies inferior; visceral surface*) (Figs. 1001 1002) is uneven, concave, directed downward, backward, and to the left, and is in relation with the stomach and duodenum, the right colic flexure, and the right kidney and suprarenal gland. The surface is almost completely invested by peritoneum; the only parts devoid of this covering are where the gall-bladder is attached to the liver, and at the porta hepatis where the two layers of the lesser omentum are separated from each other by the bloodvessels and ducts of the liver. The inferior surface of the left lobe presents behind and to the left the **gastric impression**, moulded over the antero-superior surface of the stomach, and to the right of this a rounded eminence, the **tuber omentale**, which fits into the concavity of the lesser curvature of the stomach and lies in front of the anterior layer of the lesser omentum. The under surface of the right lobe is divided into two unequal portions by the fossa for the gall-bladder; the portion to the left, the smaller of the two, is the **quadrate lobe**, and is in relation with the pyloric end of the stomach, the superior portion of the duodenum, and the transverse colon. The portion of the under surface of the right lobe to the right of the fossa for the gall-bladder presents two impressions, one situated behind the other, and separated by a ridge. The anterior of these two impressions, the **colic impression**, is shallow and is produced by the right colic flexure; the posterior, the **renal impression**, is deeper and is occupied by the upper part of the right kidney and lower part of the right suprarenal gland. Medial to the renal impression is a third and slightly marked impression, lying between it and the neck of the gall-bladder. This is caused by the descending portion of the duodenum, and is known as the **duodenal impression**. Just in front of the inferior vena cava is a narrow strip of liver tissue, the **caudate process**, which connects the right inferior angle of the caudate lobe to the under surface of the right lobe. It forms the upper boundary of the epiploic foramen of the peritoneum.

The **posterior surface** (*facies posterior*) (Fig. 1002) is rounded and broad behind the right lobe; but narrow on the left. Over a large part of its extent it is not covered by peritoneum; this uncovered portion is about 7.5 cm. broad at its widest




FIG. 1001.—Inferior surface of the liver. (From model by His.)

part, and is in direct contact with the Diaphragma. It is marked off from the upper surface by the line of reflection of the upper layer of the coronary ligament, and from the under surface by the line of reflection of the lower layer of the coronary




FIG. 1002.—Posterior and inferior surfaces of the liver. (From model by His.)

ligament. The central part of the posterior surface presents a deep concavity which is moulded on the vertebral column and crura of the Diaphragma. To the right of this the inferior vena cava is lodged in its fossa between the uncovered



area and the caudate lobe. Close to the right of this fossa and immediately above the renal impression is a small triangular depressed area, the **suprarenal impression**, the greater part of which is devoid of peritoneum; it lodges the right suprarenal gland. To the left of the inferior vena cava is the **caudate lobe**, which lies between the fossa for the vena cava and the fossa for the ductus venosus. Its lower end projects and forms part of the posterior boundary of the porta; on the right, it is connected with the under surface of the right lobe of the liver by the **caudate process**, and on the left it presents an elevation, the **papillary process**. Its posterior surface rests upon the Diaphragma, being separated from it merely by the upper part of the omental bursa. To the left of the fossa for the ductus venosus is a groove in which lies the antrum cardiacum of the œsophagus.

The **anterior border** (*margo anterior*) is thin and sharp, and marked opposite the attachment of the falciform ligament by a deep notch, the **umbilical notch**, and opposite the cartilage of the ninth rib by a second notch for the fundus of the gall-bladder. In adult males this border generally corresponds with the lower margin of the thorax in the right mammary line; but in women and children it usually projects below the ribs.

The **left extremity of the liver** is thin and flattened from above downward.

**Fossæ.**—The **left sagittal fossa** (*fossa sagittalis sinistra; longitudinal fissure*) is a deep groove, which extends from the notch on the anterior margin of the liver to the upper border of the posterior surface of the organ; it separates the right and left lobes. The porta joins it, at right angles, and divides it into two parts. The anterior part, or **fossa for the umbilical vein**, lodges the umbilical vein in the fetus, and its remains (the ligamentum teres) in the adult; it lies between the quadrate lobe and the left lobe of the liver, and is often partially bridged over by a prolongation of the hepatic substance, the **pons hepatis**. The posterior part, or **fossa for the ductus venosus**, lies between the left lobe and the caudate lobe; it lodges in the fetus, the ductus venosus, and in the adult a slender fibrous cord, the **ligamentum venosum**, the obliterated remains of that vessel.

The **porta** or **transverse fissure** (*porta hepatis*) is a short but deep fissure, about 5 cm. long, extending transversely across the under surface of the left portion of the right lobe, nearer its posterior surface than its anterior border. It joins nearly at right angles with the left sagittal fossa, and separates the quadrate lobe in front from the caudate lobe and process behind. It transmits the portal vein, the hepatic artery and nerves, and the hepatic duct and lymphatics. The hepatic duct lies in front and to the right, the hepatic artery to the left, and the portal vein behind and between the duct and artery.

The **fossa for the gall-bladder** (*fossa vesicae felleae*) is a shallow, oblong fossa, placed on the under surface of the right lobe, parallel with the left sagittal fossa. It extends from the anterior free margin of the liver, which is notched by it, to the right extremity of the porta.

The **fossa for the inferior vena cava** (*fossa venae cavae*) is a short deep depression, occasionally a complete canal in consequence of the substance of the liver surrounding the vena cava. It extends obliquely upward on the posterior surface between the caudate lobe and the bare area of the liver, and is separated from the porta by the caudate process. On slitting open the inferior vena cava the orifices of the hepatic veins will be seen opening into this vessel at its upper part, after perforating the floor of this fossa.

**Lobes.**—The **right lobe** (*lobus hepatis dexter*) is much larger than the left; the proportion between them being as six to one. It occupies the right hypochondrium, and is separated from the left lobe on its upper and anterior surfaces by the falciform ligament; on its under and posterior surfaces by the left sagittal fossa; and in front by the umbilical notch. It is of a somewhat quadrilateral form, its under and posterior surfaces being marked by three fossæ: the porta and the

fossæ for the gall-bladder and inferior vena cava, which separate its left part into two smaller lobes; the **quadrate** and **caudate lobes**. The impressions on the right lobe have already been described.

The **quadrate lobe** (*lobus quadratus*) is situated on the under surface of the right lobe, bounded in front by the anterior margin of the liver; behind by the porta; on the right, by the fossa for the gall-bladder; and on the left, by the fossa for the umbilical vein. It is oblong in shape, its antero-posterior diameter being greater than its transverse.

The **caudate lobe** (*lobus caudatus*; *Spigelian lobe*) is situated upon the posterior surface of the right lobe of the liver, opposite the tenth and eleventh thoracic vertebræ. It is bounded, below, by the porta; on the right, by the fossa for the inferior vena cava; and, on the left, by the fossa for the ductus venosus. It looks backward, being nearly vertical in position; it is longer from above downward than from side to side, and is somewhat concave in the transverse direction. The **caudate process** is a small elevation of the hepatic substance extending obliquely lateralward, from the lower extremity of the caudate lobe to the under surface of the right lobe. It is situated behind the porta, and separates the fossa for the gall-bladder from the commencement of the fossa for the inferior vena cava.

The **left lobe** (*lobus hepatis sinister*) is smaller and more flattened than the right. It is situated in the epigastric and left hypochondriac regions. Its upper surface is slightly convex and is moulded on to the Diaphragma; its under surface presents the cardiac impression and omental tuberosity, already referred to page 1192.

**Ligaments.**—The liver is connected to the under surface of the Diaphragma and to the anterior wall of the abdomen by five ligaments; four of these—the **falciform**, the **coronary**, and the two **lateral**—are peritoneal folds; the fifth, the **round ligament**, is a fibrous cord, the obliterated umbilical vein. The liver is also attached to the lesser curvature of the stomach by the hepatogastric and to the duodenum by the hepatoduodenal ligament (see page 1156).

The **falciform ligament** (*ligamentum falciforme hepatis*) is a broad and thin antero-posterior peritoneal fold, falciform in shape, its base being directed downward and backward, its apex upward and backward. It is situated in an antero-posterior plane, but lies obliquely so that one surface faces forward and is in contact with the peritoneum behind the right Rectus and the Diaphragma, while the other is directed backward and is in contact with the left lobe of the liver. It is attached by its left margin to the under surface of the Diaphragma, and the posterior surface of the sheath of the right Rectus as low down as the umbilicus; by its right margin it extends from the notch on the anterior margin of the liver, as far back as the posterior surface. It is composed of two layers of peritoneum closely united together. Its base or free edge contains between its layers the round ligament and the parumbilical veins.

The **coronary ligament** (*ligamentum coronarium hepatis*) consists of an upper and a lower layer. The **upper layer** is formed by the reflection of the peritoneum from the upper margin of the bare area of the liver to the under surface of the Diaphragma, and is continuous with the right layer of the falciform ligament. The **lower layer** is reflected from the lower margin of the bare area on to the right kidney and suprarenal gland, and is termed the **hepatorenal ligament**.

The **triangular ligaments** (*lateral ligaments*) are two in number, right and left. The **right triangular ligament** (*ligamentum triangulare dextrum*) is situated at the right extremity of the bare area, and is a small fold which passes to the Diaphragma, being formed by the apposition of the upper and lower layers of the coronary ligament. The **left triangular ligament** (*ligamentum triangulare sinistrum*) is a fold of some considerable size, which connects the posterior part of the upper surface of the left lobe to the Diaphragma; its anterior layer is continuous with the left layer of the falciform ligament.

The **round ligament** (*ligamentum teres hepatis*) is a fibrous cord resulting from the obliteration of the umbilical vein. It ascends from the umbilicus, in the free margin of the falciform ligament, to the umbilical notch of the liver, from which it may be traced in its proper fossa on the inferior surface of the liver to the porta, where it becomes continuous with the *ligamentum venosum*.




FIG. 1003.—Longitudinal section of a hepatic vein.  
(After Kiernan.)




FIG. 1004.—Longitudinal section of a small portal vein and canal. (After Kiernan.)

**Vessels and Nerves.**—The vessels connected with the liver are: the **hepatic artery**, the **portal vein**, and the **hepatic veins**.

The **hepatic artery** and **portal vein**, accompanied by numerous nerves, ascend to the porta, between the layers of the lesser omentum. The **bile duct** and the lymphatic vessels descend from the porta between the layers of the same omentum. The relative positions of the three structures are as follows: the bile duct lies to the right, the hepatic artery to the left, and the




FIG. 1005.—Section of injected liver (dog).

portal vein behind and between the other two. They are enveloped in a loose areolar tissue, the **fibrous capsule of Glisson**, which accompanies the vessels in their course through the portal canals in the interior of the organ (Fig. 1004).

The **hepatic veins** (Fig. 1003) convey the blood from the liver, and are described on page 764. They have very little cellular investment, and what there is binds their parietes closely to the

walls of the canals through which they run; so that, on section of the organ, they remain widely open and are solitary, and may be easily distinguished from the branches of the portal vein, which are more or less collapsed, and always accompanied by an artery and duct.

The **lymphatic vessels** of the liver are described on page 792.

The **nerves** of the liver, derived from the left vagus and sympathetic, enter at the porta and accompany the vessels and ducts to the interlobular spaces. Here, according to Korolkow, the medullated fibres are distributed almost exclusively to the coats of the bloodvessels; while the non-medullated enter the lobules and ramify between the cells.

**Structure of the Liver.**—The substance of the liver is composed of lobules, held together by an extremely fine areolar tissue, in which ramify the portal vein, hepatic ducts, hepatic artery, hepatic veins, lymphatics, and nerves; the whole being invested by a serous and a fibrous coat.

The **serous coat** (*tunica serosa*) is derived from the peritoneum, and invests the greater part of the surface of the organ. It is intimately adherent to the fibrous coat.

The **fibrous coat** (*capsula fibrosa* [Glisson]; *areolar coat*) lies beneath the serous investment, and covers the entire surface of the organ. It is difficult of demonstration, excepting where the serous coat is deficient. At the porta it is continuous with the fibrous capsule of Glisson, and on the surface of the organ with the areolar tissue separating the lobules.

The **lobules** (*lobuli hepatis*) form the chief mass of the hepatic substance; they may be seen either on the surface of the organ, or by making a section through the gland, as small granular bodies, about the size of a millet-seed, measuring from 1 to 2.5 mm. in diameter. In the human subject their outlines are very irregular; but in some of the lower animals (for example, the pig) they are well-defined, and, when divided transversely, have polygonal outlines. The bases of the lobules are clustered around the smallest radicles (*sublobular*) of the hepatic veins, to which each is connected (Fig. 1003) by means of a small branch which issues from the centre of the lobule (*intralobular*). The remaining part of the surface of each lobule is imperfectly isolated from the surrounding lobules by a thin stratum of areolar tissue, in which is contained a plexus of vessels, the **interlobular plexus**, and ducts. In some animals, as the pig, the lobules are completely isolated from one another by the interlobular areolar tissue (Fig. 1006).

If one of the sublobular veins be laid open, the bases of the lobules may be seen through the thin wall of the vein on which they rest, arranged in a form resembling a tessellated pavement, the centre of each polygonal space presenting a minute aperture, the mouth of an intralobular vein (Fig. 1003).

**Microscopic Appearance** (Fig. 1006).—Each lobule consists of a mass of cells, **hepatic cells**, arranged in irregular radiating columns between which are the blood channels (*sinusoids*). These convey the blood from the circumference to the centre of the lobule, and end in the **intralobular vein**, which runs through its centre, to open at its base into one of the **sublobular veins**. Between the cells are also the minute bile capillaries. Therefore, in the lobule there are all the essentials of a secreting gland; that is to say: (1) **cells**, by which the secretion is formed; (2) **blood-vessels**, in close relation with the cells, containing the blood from which the secretion is derived; (3) **ducts**, by which the secretion, when formed, is carried away.

1. The **hepatic cells** are polyhedral in form. They vary in size from 12 to 25 $\mu$  in diameter. They contain one or sometimes two distinct nuclei. The nucleus exhibits an intranuclear net-work and one or two refractile nucleoli. The cells usually contain granules; some of which are protoplasmic, while others consist of glycogen, fat, or an iron compound. In the lower vertebrates, e. g., frog, the cells are arranged in tubes with the bile duct forming the lumen and bloodvessels externally. According to Delépine, evidences of this arrangement can be found in the human liver.

2. The **Bloodvessels**.—The blood in the capillary plexus around the liver cells is brought to the liver principally by the portal vein, but also to a certain extent by the hepatic artery.

The **hepatic artery**, entering the liver at the porta with the portal vein and hepatic duct, ramifies with these vessels through the portal canals. It gives off **vaginal branches**, which ramify




FIG. 1006.—A single lobule of the liver of a pig.  $\times 60$ .

in the fibrous capsule of Glisson, and appear to be destined chiefly for the nutrition of the coats of the vessels and ducts. It also gives off **capsular branches**, which reach the surface of the organ, ending in its fibrous coat in stellate plexuses. Finally, it gives off **interlobular branches**, which form a plexus outside each lobule, to supply the walls of the interlobular veins and the accompanying bile ducts. From this plexus lobular branches enter the lobule and end in the net-work of sinusoids between the cells.

The **portal vein** also enters at the porta, and runs through the portal canals (Fig. 1007), enclosed in Glisson's capsule, dividing in its course into branches, which finally break up into a plexus, the **interlobular plexus**, in the interlobular spaces. These branches receive the vaginal

and capsular veins, corresponding to the vaginal and capsular branches of the hepatic artery. Thus it will be seen that all the blood carried to the liver by the portal vein and hepatic artery finds its way into the interlobular plexus. From this plexus the blood is carried into the lobule by fine branches which converge from the circumference to the




FIG. 1007.—Section across portal canal of pig.  $\times 250$ .




FIG. 1008.—Bile capillaries of rabbit, shown by Golgi's method.  $\times 450$ .

centre of the lobule, and are connected by transverse branches (Fig. 1005). The walls of these small vessels are incomplete so that the blood is brought into direct relationship with the liver cells. The lining endothelium consists of irregularly branched, disconnected cells (*stellate cells of Kupffer*). Moreover, according to Herring and Simpson, minute channels penetrate the liver cells themselves, conveying the constituents of the blood into their substance. It will be seen that the blood capillaries of the liver lobule differ structurally from capillaries elsewhere. Developmentally they are formed by the growth of the columns of liver cells into large blood spaces or sinusoids, and hence they have received the name of "sinusoids." Arrived at the centre of the lobule, the sinusoids empty themselves into one vein, of considerable size, which runs down the centre of the lobule from apex to base, and is called the **intralobular vein**. At the base of the lobule this vein opens directly into the **sublobular vein**, with which the lobule is connected. The sublobular veins unite to form larger and larger trunks, and end at last in the hepatic veins, these converge to form three large trunks which open into the inferior vena cava while that vessel is situated in its fossa on the posterior surface of the liver.

3. The **bile ducts** commence by little passages in the liver cells which communicate with canaliculi termed **intercellular biliary passages** (*bile capillaries*). These passages are merely little channels or spaces left between the contiguous surfaces of two cells, or in the angle where three or more liver cells meet (Fig. 1008), and they are always separated from the blood capillaries by at least half the width of a liver cell. The channels thus formed radiate to the circumference of the lobule, and open into the interlobular bile ducts which run in Glisson's capsule, accompanying the portal vein and hepatic artery (Fig. 1007). These join with other ducts to form two main trunks, which leave the liver at the transverse fissure, and by their union form the **hepatic duct**.

*Structure of the Ducts.*—The walls of the biliary ducts consist of a connective-tissue coat, in which are muscle cells, arranged both circularly and longitudinally, and an epithelial layer, consisting of short columnar cells resting on a distinct basement-membrane.

**Excretory Apparatus of the Liver.**—The excretory apparatus of the liver consists of (1) the **hepatic duct**, formed by the junction of the two main ducts, which



pass out of the liver at the porta; (2) the **gall-bladder**, which serves as a reservoir for the bile; (3) the **cystic duct**, or the duct of the gall-bladder; and (4) the **common bile duct**, formed by the junction of the hepatic and cystic ducts.

**The Hepatic Duct** (*ductus hepaticus*).—Two main trunks of nearly equal size issue from the liver at the porta, one from the right, the other from the left lobe; these unite to form the hepatic duct, which passes downward and to the right for about 4 cm., between the layers of the lesser omentum, where it is joined at an acute angle by the cystic duct, and so forms the common bile duct. The hepatic duct is accompanied by the hepatic artery and portal vein.

**The Gall-bladder** (*vesica fellea*) (Fig. 1009).—The gall-bladder is a conical or pear-shaped musculomembranous sac, lodged in a fossa on the under surface of the right lobe of the liver, and extending from near the right extremity of the porta to the anterior border of the organ. It is from 7 to 10 cm. in length, 2.5 cm. in breadth at its widest part, and holds from 30 to 35 c.c. It is divided into a fundus, body, and neck. The **fundus**, or broad extremity, is directed downward, forward, and to the right, and projects beyond the anterior border of the liver; the **body** and **neck** are directed upward and backward to the left. The upper surface of the gall-bladder is attached to the liver by connective tissue and vessels. The under surface is covered by peritoneum, which is reflected on to it from the surface of the liver. Occasionally the whole of the organ is invested by the serous membrane, and is then connected to the liver by a kind of mesentery.

**Relations.**—The **body** is in relation, by its upper surface, with the liver; by its under surface, with the commencement of the transverse colon; and farther back usually with the upper end of the descending portion of the duodenum, but sometimes with the superior portion of the duodenum or pyloric end of the stomach. The **fundus** is completely invested by peritoneum; it is in relation, in front, with the abdominal parietes, immediately below the ninth costal cartilage; behind with the transverse colon. The **neck** is narrow, and curves upon itself like the letter S; at its point of connection with the cystic duct it presents a well-marked constriction.

**Structure** (Fig. 1010).—The gall-bladder consists of three coats: **serous**, **fibromuscular**, and **mucous**.

The **external** or **serous coat** (*tunica serosa vesicae felleae*) is derived from the peritoneum; it completely invests the fundus, but covers the body and neck only on their under surfaces.

The **fibromuscular coat** (*tunica muscularis vesicae felleae*), a thin but strong layer forming the frame-work of the sac, consists of dense fibrous tissue, which interlaces in all directions, and is mixed with plain muscular fibres, disposed chiefly in a longitudinal direction, a few running transversely.

The **internal** or **mucous coat** (*tunica mucosa vesicae felleae*) is loosely connected with the fibrous layer. It is generally of a yellowish-brown color, and is elevated into minute rugæ. Opposite the neck of the gall-bladder the mucous membrane projects inward in the form of oblique ridges or folds, forming a sort of spiral valve.

The mucous membrane is continuous through the hepatic duct with the mucous membrane lining the ducts of the liver, and through the common bile duct with the mucous membrane of the duodenum. It is covered with columnar epithelium, and secretes mucin; in some animals it secretes a nucleoprotein instead of mucin.




FIG. 1009.—The gall-bladder and bile ducts laid open. (Spalteholz.)

The **Cystic Duct** (*ductus cysticus*).—The cystic duct about 4 cm. long, runs backward, downward, and to the left from the neck of the gall-bladder, and joins the hepatic duct to form the common bile duct. The mucous membrane lining its interior is thrown into a series of crescentic folds, from five to twelve in number, similar to those found in the neck of the gall-bladder. They project into the duct in regular succession, and are directed obliquely around the tube, presenting much the appearance of a continuous spiral valve. When the duct is distended, the spaces between the folds are dilated, so as to give to its exterior a twisted appearance.




FIG. 1010.—Transverse section of gall-bladder.

The **Common Bile Duct** (*ductus choledochus*).—The common bile duct is formed by the junction of the cystic and hepatic ducts; it is about 7.5 cm. long, and of the diameter of a goose-quill.

It descends along the right border of the lesser omentum behind the superior portion of the duodenum, in front of the portal vein, and to the right of the hepatic artery; it then runs in a groove near the right border of the posterior surface of the head of the pancreas; here it is situated in front of the inferior vena cava, and is occasionally completely imbedded in the pancreatic substance. At its termination it lies for a short distance along the right side of the terminal part of the pancreatic duct and passes with it obliquely between the mucous and muscular coats. The two ducts unite and open by a common orifice upon the summit of the duodenal papilla, situated at the medial side of the descending portion of the duodenum, a little below its middle and about 7 to 10 cm. from the pylorus (Fig. 1015). The short tube formed by the union of the two ducts is dilated into an ampulla, the **ampulla of Vater**.

**Structure.**—The coats of the large biliary ducts are an **external** or **fibrous**, and an **internal** or **mucous**. The **fibrous coat** is composed of strong fibroareolar tissue, with a certain amount of muscular tissue, arranged, for the most part, in a circular manner around the duct. The **mucous coat** is continuous with the lining membrane of the hepatic ducts and gall-bladder, and also with that of the duodenum; and, like the mucous membrane of these structures, its epithelium is of the columnar variety. It is provided with numerous mucous glands, which are lobulated and open by minute orifices scattered irregularly in the larger ducts.

**Applied Anatomy.**—On account of its large size, its fixed position, and its friability, the liver is more frequently ruptured than any of the other abdominal viscera. The rupture may vary from a slight scratch to an extensive and complete laceration of its substance, dividing it into two parts. Sometimes an internal rupture, without laceration of the peritoneal covering, takes place, and such injuries are most susceptible of repair; but small tears of the surface may also heal; when, however, the laceration is extensive, death usually takes place from hemorrhage, on account of the fact that the hepatic veins are contained in rigid canals in the liver substance and are unable to contract, and are moreover unprovided with valves. The liver may also be torn by the end of a broken rib perforating the Diaphragma. It may be injured by stabs or

other punctured wounds, and when these are inflicted through the chest wall the pleural and peritoneal cavities may both be opened up, and both lung and liver wounded. In cases of wound of the liver from the front, hernia of a part of this viscus may take place, but generally can be easily replaced. In cases of laceration of the liver, when there is evidence that bleeding is going on, the abdomen must be opened, the laceration sought for, and the bleeding arrested. This may be done temporarily by introducing the forefinger into the epiploic foramen and placing the thumb on the lesser omentum, and compressing the hepatic artery and portal vein between the two. The margins of the laceration, if small, can be brought together and sutured by means of a blunt curved needle passed from one side of the wound to the other. All sutures must be passed before any are tied, and this must be done with the greatest gentleness, as the liver substance is very friable. When the laceration is extensive it must be packed with gauze, the end of which is allowed to hang out of the external wound.

Abscess of the liver is of not infrequent occurrence. The so-called *tropical abscess* is due to absorption from the intestine of the amœba of dysentery, which reaches the liver through the portal system and causes the formation of a large chronic abscess; this may open in many different ways on account of the relations of the liver to other organs. Thus it has been known to burst into the lungs when the pus is coughed up, or into the stomach when the pus is vomited; it may burst into the colon, or duodenum; or, by perforating the Diaphragma, it may empty itself into the pleural cavity. It often makes its way forward, and points on the anterior abdominal wall, and finally it may burst into the peritoneal or pericardial cavities. Abscesses of the liver frequently require opening, and this must be done by an incision in the abdominal wall, in the thoracic wall, or in the lumbar region, according to the direction in which the abscess is tracking. The incision through the abdominal wall is to be preferred when possible. The abdominal wall is incised over the swelling, and, unless the peritoneum is adherent, gauze is packed all around the exposed liver surface, the abscess opened, and a large drainage-tube inserted.

*Hydatid cysts* are more often found in the liver than in any of the other viscera. The reason of this is not far to seek. The embryo of the egg of the tœnia echinococcus, being liberated in the stomach by the disintegration of its shell, bores its way through the gastric walls and usually enters a bloodvessel, and is carried by the blood stream to the hepatic capillaries, where its onward course is arrested, and where it undergoes development into the fully formed hydatid.

*Ptosis of the liver*, or *hepatoptosis*, from abnormal laxity of its ligaments and failure of the support it usually receives from the subjacent viscera, is an occasional cause of various nervous and gastro-intestinal disturbances. It has been very fully described by Glénard and his pupils. In women who have used very tight corsets and in men who have worn tightly buckled belts, the lower margin of the right lobe may become elongated by the pressure, producing an abnormal lobe known as the *linguiform* or *Riedel's lobe*. This may cause indefinite abdominal symptoms suggesting dyspepsia or disease of the gall-bladder; and if discovered accidentally, a Riedel's lobe may be mistaken for a tumor of the right kidney, of the right suprarenal gland, of the transverse colon or pancreas, or even of the vermiform process.

The gall-bladder may become distended in cases of obstruction of its duct or the common bile duct, or from a collection of gall-stones in its interior, thus forming a large tumor. The swelling is pear-shaped, and projects downward and forward to the umbilicus. It moves with respiration, since it is attached to the liver. To relieve this condition, the gall-bladder must be opened (*cholecystotomy*) and the gall-stones removed. The operation is performed by an incision, 5 to 7 cm. long, through the lateral part of the right Rectus, commencing at the costal margin. The peritoneal cavity is opened, and, the tumor having been found, gauze is packed around it to protect the peritoneal cavity, and it is aspirated. When the contained fluid has been evacuated the flaccid bladder is drawn out of the abdominal wound and its wall incised; any gall-stones in the bladder are now removed. If the case is one of obstruction of the duct, an attempt must be made to dislodge the stone by manipulation through the wall of the duct; or it may be crushed from without by the fingers or carefully padded forceps. If this does not succeed, the safest plan is to incise the duct, extract the stone, and close the incision by fine sutures in two layers. After all obstruction has been removed, the edges of the incision in the gall-bladder may be sutured to the posterior sheath of the Rectus and a fistulous communication established between the gall-bladder and the exterior, a drainage-tube being inserted into the cavity; this fistulous opening usually closes in the course of a few weeks. The gall-bladder may be completely removed if it be quite certain that no cause for biliary obstruction remain: this is also done for primary malignant growth of the viscus.

### The Pancreas (Figs. 1011, 1012).

**Dissection.**—The pancreas may be exposed for dissection in three different ways: (1) By raising the liver, drawing down the stomach, and tearing through the gastrohepatic omentum, and the ascending layer of the transverse mesocolon. (2) By raising the stomach, the arch of the colon, and greater omentum, and then dividing the inferior layer of the transverse mesocolon

and raising its ascending layer. (3) By dividing the two layers of peritoneum, which descend from the greater curvature of the stomach to form the greater omentum; turning the stomach upward, and then cutting through the ascending layer of the transverse mesocolon (see Fig. 961).




FIG. 1011.—Transverse section through the middle of the first lumbar vertebra, showing the relations of the pancreas. (Braune.)




FIG. 1012.—The duodenum and pancreas.

The **pancreas** is a compound racemose gland, analogous in its structures to the salivary glands, though softer and less compactly arranged than those organs.

It is long and irregularly prismatic in shape; its right extremity, being broad, is called the **head**, and is connected to the main portion of the organ, or **body**, by a slight constriction, the **neck**; while its left extremity gradually tapers to form the **tail**. It is situated transversely across the posterior wall of the abdomen, at the back of the epigastric and left hypochondriac regions. Its length varies from 12.5 to 15 cm., and its weight from 60 to 100 gm.

**Relations.**—The **Head** (*caput pancreatis*) is flattened from before backward, and is lodged within the curve of the duodenum. Its upper border is overlapped by the superior part of the duodenum and its lower overlaps the horizontal part; its right and left borders overlap in front, and insinuate themselves behind, the descending and ascending parts of the duodenum respectively. The angle of junction of the lower and left lateral borders forms a prolongation, termed the **uncinate process**. In the groove between the duodenum and the right lateral and lower borders in front are the anastomosing superior and inferior pancreaticoduodenal arteries; the common bile duct descends behind, close to the right border, to its termination in the descending part of the duodenum.




FIG. 1013.—The pancreas and duodenum from behind. (From model by His.)

**Anterior Surface.**—The greater part of the right half of this surface is in contact with the transverse colon, only areolar tissue intervening. From its upper part the **neck** springs, its right limit being marked by a groove for the gastroduodenal artery. The lower part of the right half, below the transverse colon, is covered by peritoneum continuous with the inferior layer of the transverse mesocolon, and is in contact with the coils of the small intestine. The superior mesenteric artery passes down in front of the left half across the uncinate process; the superior mesenteric vein runs upward on the right side of the artery and, behind the neck, joins with the lienal vein to form the portal vein.

**Posterior Surface.**—The posterior surface is in relation with the inferior vena cava, the common bile duct, the renal veins, the right crus of the Diaphragma, and the aorta.

The **Neck** springs from the right upper portion of the front of the head. It is about 2.5 cm. long, and is directed at first upward and forward, and then upward



and to the left to join the body; it is somewhat flattened from above downward and backward. Its antero-superior surface supports the pylorus; its postero-inferior surface is in relation with the commencement of the portal vein; on the right it is grooved by the gastroduodenal artery.

The **Body** (*corpus pancreatis*) is somewhat prismatic in shape, and has three surfaces: **anterior**, **posterior**, and **inferior**.

The **anterior surface** (*facies anterior*) is somewhat concave; and is directed forward and upward: it is covered by the postero-inferior surface of the stomach which rests upon it, the two organs being separated by the omental bursa. Where it joins the neck there is a well-marked prominence, the **tuber omentale**, which abuts against the posterior surface of the lesser omentum.

The **posterior surface** (*facies posterior*) is devoid of peritoneum, and is in contact with the aorta, the lienal vein, the left kidney and its vessels, the left suprarenal gland, the origin of the superior mesenteric artery, and the crura of the Diaphragma.

The **inferior surface** (*facies inferior*) is narrow on the right but broader on the left, and is covered by peritoneum; it lies upon the duodenojejunal flexure and on some coils of the jejunum; its left extremity rests on the left colic flexure.

The **superior border** (*margo superior*) is blunt and flat to the right; narrow and sharp to the left, near the tail. It commences on the right in the omental tuberosity, and is in relation with the coeliac artery, from which the hepatic artery courses to the right just above the gland, while the lienal artery runs toward the left in a groove along this border.

The **anterior border** (*margo anterior*) separates the anterior from the inferior surface, and along this border the two layers of the transverse mesocolon diverge from one another; one passing upward over the anterior surface, the other backward over the inferior surface.

The **inferior border** (*margo inferior*) separates the posterior from the inferior surface; the superior mesenteric vessels emerge under its right extremity.

The **Tail** (*cauda pancreatis*) is narrow; it extends to the left as far as the lower part of the gastric surface of the spleen, lying in the phrenicocolic ligament, and it is in contact with the left colic flexure.

Birmingham described the body of the pancreas as projecting forward as a prominent ridge into the abdominal cavity and forming part of a shelf on which the stomach lies. "The portion of the pancreas to the left of the middle line has a very considerable antero-posterior thickness; as a result the anterior surface is of considerable extent; it looks strongly upward, and forms a large and important part of the shelf. As the pancreas extends to the left toward the spleen it crosses the upper part of the kidney, and is so moulded on to it that the top of the kidney forms an extension inward and backward of the upper surface of the pancreas and extends the bed in this direction. On the other hand, the extremity of the pancreas comes in contact with the spleen in such a way that the plane of its upper surface runs with little interruption upward and backward into the concave gastric surface of the spleen, which completes the bed behind and to the left, and, running upward, forms a partial cap for the wide end of the stomach.<sup>1</sup>

The **Pancreatic Duct** (*ductus pancreaticus* [*Wirsungi*]; *duct of Wirsung*) extends transversely from left to right through the substance of the pancreas (Fig. 1014). It commences by the junction of the small ducts of the lobules situated in the tail of the pancreas, and, running from left to right through the body, it receives the ducts of the various lobules composing the gland. Considerably augmented in size, it reaches the neck, and turning downward, backward, and to the right, it comes into relation with the common bile duct, which lies to its right side; leaving the head of the gland, it passes very obliquely through the mucous and muscular coats of the duodenum,

<sup>1</sup> Journal of Anatomy and Physiology, pt. 1, xxxi, 102.

and ends by an orifice common to it and the common bile duct upon the summit of the duodenal papilla, situated at the medial side of the descending portion of the duodenum, 7.5 to 10 cm. below the pylorus. The pancreatic duct, near the duodenum, is about the size of an ordinary quill. Sometimes the pancreatic duct and the common bile duct open separately into the duodenum. Frequently there is an additional duct, which is given off from the pancreatic duct in the neck of the pancreas and opens into the duodenum about 2.5 cm. above the duodenal papilla. It receives the ducts from the lower part of the head, and is known as the **accessory pancreatic duct** (*duct of Santorini*).




FIG. 1014.—The pancreatic duct.

**Structure** (Fig. 1015).—In structure, the pancreas resembles the salivary glands. It differs from them, however, in certain particulars, and is looser and softer in its texture. It is not enclosed in a distinct capsule, but is surrounded by areolar tissue, which dips into its interior, and connects together the various lobules of which it is composed. Each lobule, like the lobules of the salivary glands, consists of one of the ultimate ramifications of the main duct, ending in a number of cecal pouches or alveoli, which are tubular and somewhat convoluted. The minute ducts connected with the alveoli are narrow and lined with flattened cells. The alveoli are almost completely filled with secreting cells, so that scarcely any lumen is visible. In some animals spindle-shaped cells occupy the centre of the alveolus and are known as the **centro-acinar cells of Langerhans**. These are prolongations of the terminal ducts. The true secreting cells which line the wall of the alveolus are very characteristic. They are columnar in shape and present two zones: an outer one, clear and finely striated next the basement-membrane, and an inner granular one next the lumen. In hardened specimens the outer zone stains deeply with various dyes, whereas the inner zone stains slightly. During activity the granular zone gradually diminishes in size, and when exhausted is only seen as a small area next to the lumen. During the resting stages it gradually increases until it forms nearly three-fourths of the cell. In some of the secreting cells of the pancreas is a spherical mass, staining more easily than the rest of the cell; this is termed the **paranucleus**, and is believed to be an extension from the nucleus. The connective tissue between the alveoli presents in certain parts collections of cells, which are termed **interalveolar cell islets** (*islands of Langerhans*). The cells of these stain lightly with hematoxylin or carmine, and are more or less polyhedral in shape, forming a net-work in which ramify many capillaries. There are two main types of cell in the islets, distinguished as A-cells and B-cells according to the special staining reactions of the granules they contain. The cell

islets have been supposed to produce the internal secretion of the pancreas which is necessary for carbohydrate metabolism, but numerous researches have so far failed to elucidate their real function.

The walls of the pancreatic duct are thin, consisting of two coats, an external fibrous and an internal mucous; the latter is smooth, and furnished near its termination with a few scattered follicles.

**Vessels and Nerves.**—The **arteries** of the pancreas are derived from the lienal, and the pancreaticoduodenal branches of the hepatic and superior mesenteric. Its **veins** open into the

lienal and superior mesenteric veins. Its **lymphatics** are described on page 793. Its **nerves** are filaments from the lienal plexus.

**Applied Anatomy.**—Inflammation of the pancreas has of late years received considerable attention. It appears to be due to infection of the pancreatic ducts by microorganisms from the duodenum in cases of gastroduodenal catarrh, or from the biliary passages in which a gall-stone is lodged. Acute cases usually terminate fatally and are frequently of the hemorrhagic type; chronic inflammation of the pancreas produces few symptoms of disease unless it is extensive, when attacks of abdominal pain, loss of appetite, progressive weakness and wasting, and the passage of whitish fatty motions, are likely to follow. Extensive fibrosis of the pancreas also one of the commonest lesions found post mortem in cases of diabetes mellitus. Cysts of the pancreas are sometimes met with. They may be the result of traumatism, when they




FIG. 1015.—Section of pancreas of dog.  $\times 250$ .

generally contain blood, or they may be due to retention from obstruction of a duct, or from pressure on the main duct by a gall-stone. They may attain a large size, and cause symptoms by pressing on the stomach, Diaphragma, or common bile duct. They generally push their way forward between the stomach and transverse colon, and may then be felt as a definite tumor in the middle line of the upper part of the abdomen. The tumor is fixed and does not move with respiration. The treatment consists in opening the abdomen in the middle line, incising the cyst, evacuating its contents, and fixing its walls to the deeper layers of the abdominal wall. Drainage in the left loin, just below the last rib, can sometimes be established. When they are situated in the tail of the pancreas they have been removed. The pancreas is often the seat of cancer; this usually affects the head, and therefore speedily involves the common bile duct, leading to persistent jaundice; or it may press upon the portal vein, causing ascites, or involve the stomach, causing pyloric obstruction. It has been said that the pancreas is the only abdominal viscus which has never been found in a hernial protrusion; but even this organ has been found in company with other viscera, in rare cases of diaphragmatic hernia.

## THE UROGENITAL APPARATUS (APPARATUS UROGENITALIS; UROGENITAL ORGANS).

The urogenital apparatus consists of (a) the **urinary organs** for the secretion and discharge of the urine, and (b) the **genital organs**, which are concerned with the process of reproduction.

### THE URINARY ORGANS.

The urinary organs comprise the **kidneys**, which secrete the urine, the **ureters**, or ducts, which convey urine to the **urinary bladder**, where it is for a time retained; and the **urethra**, through which it is discharged from the body.

#### The Kidneys (Renes).

The **kidneys** are situated in the posterior part of the abdomen, one on either side of the vertebral column, behind the peritoneum, and surrounded by a mass of fat

and loose areolar tissue. Their upper extremities are on a level with the upper border of the twelfth thoracic vertebra, their lower extremities on a level with the third lumbar. The right kidney is usually slightly lower than the left, probably on account of the vicinity of the liver. The long axis of each kidney is directed downward and lateralward; the transverse axis backward and lateralward.

Each kidney is about 11.25 cm. in length, 5 to 7.5 cm. in breadth, and rather more than 2.5 cm. in thickness. The left is somewhat longer, and narrower, than the right. The weight of the kidney in the adult male varies from 125 to 170 gm., in the adult female from 115 to 155 gm. The combined weight of the two kidneys in proportion to that of the body is about 1 to 240.

The kidney has a characteristic form, and presents for examination two surfaces, two borders, and an upper and lower extremity.




FIG. 1016.—The anterior surfaces of the kidneys, showing the areas of contact of neighboring viscera.

**Relations.**—The **anterior surface** (*facies anterior*) (Figs. 1012 and 1016) of each kidney is convex, and looks forward and lateralward. Its relations to adjacent viscera differ so completely on the two sides that separate descriptions are necessary.

**Anterior Surface of Right Kidney.**—A narrow portion at the upper extremity is in relation with the right suprarenal gland. A large area just below this and involving about three-fourths of the surface, lies in the renal impression on the inferior surface of the liver, and a narrow but somewhat variable area near the medial border is in contact with the descending part of the duodenum. The lower part of the anterior surface is in contact laterally with the right colic flexure, and medially, as a rule, with the small intestine. The areas in relation with the liver and small intestine are covered by peritoneum; the suprarenal, duodenal, and colic areas are devoid of peritoneum.

**Anterior Surface of Left Kidney.**—A small area along the upper part of the medial border is in relation with the left suprarenal gland, and close to the lateral border is a long strip in contact with the renal impression on the spleen. A somewhat quadrilateral field, about the middle of the anterior surface, marks the site of contact with the body of the pancreas, on the deep surface of which are the lienal vessels. Above this is a small triangular portion, between the suprarenal and splenic areas, in contact with the postero-inferior surface of the stomach. Below the pancreatic area the lateral part is in relation with the left colic flexure,



the medial with the small intestine. The areas in contact with the stomach and spleen are covered by the peritoneum of the omental bursa, while that in relation




FIG. 1017.—The posterior surfaces of the kidneys, showing areas of relation to the parietes.

to the small intestine is covered by the peritoneum of the general cavity; behind the latter are some branches of the left colic vessels. The suprarenal, pancreatic, and colic areas are devoid of peritoneum.




FIG. 1018.—The relations of the kidneys from behind.

The **Posterior Surface** (*facies posterior*) (Figs. 1017, 1018).—The posterior surface of each kidney is directed backward and medialward. It is imbedded in areolar



and fatty tissue and entirely devoid of peritoneal covering. It lies upon the Diaphragma, the medial and lateral lumbocostal arches, the Psoas major, the Quadratus lumborum, and the tendon of the Transversus abdominis, the subcostal, and one or two of the upper lumbar arteries, and the last thoracic, iliohypogastric, and ilioinguinal nerves. The right kidney rests upon the twelfth rib, the left usually on the eleventh and twelfth. The Diaphragma separates the kidney from the pleura, which dips down to form the phrenicocostal sinus, but frequently the muscular fibres of the Diaphragma are defective or absent over a triangular area immediately above the lateral lumbocostal arch, and when this is the case the perinephric areolar tissue is in contact with the diaphragmatic pleura.

**Borders.**—The **lateral border** (*margo lateralis*; *external border*) is convex, and is directed toward the postero-lateral wall of the abdomen. On the left side it is in contact at its upper part, with the spleen.

The **medial border** (*margo medialis*; *internal border*) is concave in the centre and convex toward either extremity; it is directed forward and a little downward. Its central part presents a deep longitudinal fissure, bounded by prominent overhanging anterior and posterior lips. This fissure is named the **hilus**, and transmits the vessels, nerves, and ureter. Above the hilus the medial border is in relation with the suprarenal gland; below the hilus, with the ureter.

**Extremities.**—The **superior extremity** (*extremitas superior*) is thick and rounded, and is nearer the median line than the lower; it is surmounted by the suprarenal gland, which covers also a small portion of the anterior surface.

The **inferior extremity** (*extremitas inferior*) is smaller and thinner than the superior and farther from the median line. It extends to within 5 cm. of the iliac crest.

The relative position of the main structures in the hilus is as follows: the vein is in front, the artery in the middle, and the ureter behind and directed downward. Frequently, however, branches of both artery and vein are placed behind the ureter.

**Fixation of the Kidney** (Figs. 1019, 1020).—The kidney and its vessels are imbedded in a mass of fatty tissue, termed the **adipose capsule**, which is thickest at the margins of the kidney and is prolonged through the hilus into the renal sinus. The kidney and the adipose capsule are enclosed in a sheath of fibrous tissue continuous with the subperitoneal fascia, and named the **renal fascia**. At the lateral border of the kidney the renal fascia splits into an anterior and a posterior layer. The anterior layer is carried medialward in front of the kidney and its vessels, and is continuous over the aorta with the corresponding layer of the opposite side. The posterior layer extends medialward behind the kidney and blends with the fascia on the Quadratus lumborum and Psoas major, and through this fascia is attached to the vertebral column. Above the suprarenal gland the two layers of the renal fascia fuse,




FIG. 1019.—Sagittal section through posterior abdominal wall, showing the relations of the capsule of the kidney. (After Gerota).

and unite with the fascia of the Diaphragma; below they remain separate, and are gradually lost in the subperitoneal fascia of the iliac fossa. The renal fascia is connected to the fibrous tunic of the kidney by numerous trabeculæ, which traverse the adipose capsule, and are strongest near the lower end of the organ. Behind the fascia renalis is a considerable quantity of fat, which constitutes the **paranephric body**. The kidney is held in position partly through the attachment of the renal fascia and partly by the apposition of the neighboring viscera.




FIG. 1020.—Transverse section, showing the relations of the capsule of the kidney. (After Gerota.)

**General Structure of the Kidney.**—The kidney is invested by a fibrous tunic, which forms a firm, smooth covering to the organ. The tunic can be easily stripped off, but in doing so numerous fine processes of connective tissue and small bloodvessels are torn through. Beneath this coat a thin wide-meshed net-work of unstriated muscular fibre forms an incomplete covering to the organ. When the capsule is stripped off, the surface of the kidney is found to be smooth and even and of a deep red color. In infants fissures extending for some depth may be seen on the surface of the organ, a remnant of the lobular construction of the gland. The kidney is dense in texture, but is easily lacerable by mechanical force. If a vertical section of the kidney be made from its convex to its concave border, and the loose tissue and fat removed from around the vessels and the excretory duct, it will be seen that the kidney consists of a central cavity surrounded at all parts but one by the proper kidney substance (Fig. 1021). This central cavity is called the **renal sinus**, and is lined by a prolongation of the fibrous tunic, which is continued around the lips of the hilus. Through the hilus the bloodvessels of the kidney and its excretory duct pass, and therefore these structures, upon entering or leaving the kidney, are contained within the sinus. The excretory duct or **ureter** begins by several short truncated branches termed **calices**, which unite to form two or three short tubes; these in turn expand into a wide funnel-shaped sac named the **renal pelvis**, from the neck of which the ureter issues. The calices and pelvis lie within the sinus; the bloodvessels of the kidney, after passing through the hilus, are also contained in the sinus, lying between its lining membrane and the excretory apparatus.

The kidney is composed of an internal **medullary** and an external **cortical substance**.

The **medullary substance** (*substantia medullaris*) consists of a series of red-colored striated conical masses, termed the **renal pyramids**, the bases of which are directed toward the circumference of the kidney, while their apices converge toward the renal sinus, where they form prominent papillæ projecting into the interior of the calices; each calyx receives from one to three papillæ.

The **cortical substance** (*substantia corticalis*) is reddish brown in color and soft and granular in consistence. It lies immediately beneath the fibrous tunic, arches over the bases of the pyramids, and dips in between adjacent pyramids toward the renal sinus. The parts dipping in between the pyramids are named the **renal columns** (Bertini), while the portions which connect the renal columns to each other and intervene between the bases of the pyramids and the fibrous tunic are called the **cortical arches** (indicated between A and A' in Fig. 1021). If the cortex be examined with a lens, it will be seen to consist of a series of lighter-colored, conical areas, termed the radiate part, and a darker-colored intervening substance, which from the complexity of its structure is named the convoluted part. The rays gradually taper toward the circumference of the kidney, and consist of a series of outward prolongations from the base of each renal pyramid.

The cortical and medullary substances, so dissimilar in appearance, are very similar in structure, being made up of renal tubules and bloodvessels, united and bound together by a connecting stroma.

**Minute Anatomy.**—The **renal tubules** (Fig. 1022), of which the kidney is for the most part made up, commence in the cortical substance, and after pursuing a very circuitous course through the cortical and medullary substances, finally end at the apices of the renal pyramids by open mouths, so that the fluid which they contain is emptied, through the calices, into the pelvis of the kidney. If the surface of one of the papillæ be examined with a lens, it will be seen to be studded over with minute openings, the orifices of the




FIG. 1021.—Vertical section of kidney.




FIG. 1022.—Scheme of renal tubule and its vascular supply.

renal tubules, from sixteen to twenty in number, and if pressure be made on a fresh kidney, urine will be seen to exude from these orifices. The tubules commence in the convoluted part and renal columns as the **Malpighian bodies**, which are small rounded masses of a deep red color, varying in size, but of an average of about 0.2 mm. in diameter. Each of these little bodies is composed of two parts: a central glomerulus of vessels, called a **Malpighian tuft**, and a membranous envelope, the **Malpighian capsule** (*capsule of Bowman*), which is the small pouch-like commencement of a renal tubule.

The **Malpighian tuft** (*vascula glomerulus*) is a lobulated net-work of convoluted capillary bloodvessels, held together by scanty connective tissue. This capillary net-work is derived from a small arterial twig, the *afferent vessel*, which enters the capsule, generally at a point opposite to that at which the latter is connected with the tubule; and the resulting vein, the *efferent vessel*, emerges from the capsule at the same point. The afferent vessel is usually the larger of the two (Fig. 1023). The **Malpighian or Bowman's capsule**, which surrounds the glomerulus, is formed of a hyaline membrane, supported by a small amount of connective tissue, which is continuous with the connective tissue of the tube. It is lined on its inner surface by a layer of squamous epithelial cells, which are reflected from the lining membrane on to the glomerulus, at the point of entrance or exit of the afferent and efferent vessels. The whole surface of the glomerulus is covered with a continuous layer of the same cells, on a delicate supporting membrane (Fig. 1024). Thus between the glomerulus and the capsule a space is left, forming a cavity lined by a continuous layer of squamous cells; this cavity varies in size according to the state of secretion and the amount of fluid present in it. In the fetus and young subject the lining epithelial cells are polyhedral or even columnar.



FIG. 1023.—Distribution of bloodvessels in cortex of kidney.



FIG. 1024.—Malpighian body.

The **renal tubules**, commencing in the Malpighian bodies, present, during their course, many changes in shape and direction, and are contained partly in the medullary and partly in the cortical substance. At their junction with the Malpighian capsule they exhibit a somewhat constricted portion, which is termed the **neck**. Beyond this the tubule becomes convoluted, and pursues a considerable course in the cortical substance constituting the **proximal convoluted tube**. After a time the convolutions disappear, and the tube approaches the medullary substance in a more or less spiral manner; this section of the tubule has been called the **spiral tube**. Throughout this portion of their course the renal tubules are contained entirely in the cortical substance, and present a fairly uniform calibre. They now enter the medullary substance, suddenly become much smaller, quite straight in direction, and dip down for a variable depth into the pyramids, constituting the **descending limb of Henle's loop**. Bending on themselves, they form what is termed the **loop of Henle**, and reascending, they become suddenly enlarged, forming the **ascending limb of Henle's loop**, and reënter the cortical substance. This portion of the tubule ascends for a short distance, when it again becomes dilated, irregular, and angular. This section is termed the **zigzag tubule**; it ends in a convoluted tube, which resembles the proximal convoluted tubule, and is called the **distal convoluted tubule**. This again terminates in a narrow **junctional tube**, which enters the straight or collecting tube.

The **straight or collecting tubes** commence in the radiate part of the cortex, where they receive the curved ends of the distal convoluted tubules. They unite at short intervals with one another, the resulting tubes presenting a considerable increase in calibre, so that a series of comparatively large tubes passes from the bases of the rays into the renal pyramids. In the medulla the tubes of each pyramid converge to join a central tube (*duct of Bellini*) which finally opens on the summit of one of the papillæ; the contents of the tube are therefore discharged into one of the calices.

*Structure of the Renal Tubules.*—The renal tubules consist of a basement membrane lined with epithelium. The epithelium varies considerably in different sections of the tubule. In the neck

the epithelium is continuous with that lining the Malpighian capsule, and like it consists of flattened cells each containing an oval nucleus (Fig. 1026). The two convoluted tubules, the spiral and zigzag tubules and the ascending limb of Henle's loop, are lined by a type of epithelium which is histologically the same in all. The cells are somewhat columnar in shape and dovetail into one another of their lateral aspect. Each has a striated border next the lumen of the tube, its inner part is granular and its outer portion vertically striated. The nucleus is spherical and situated about the centre of the cell. In the descending limb of Henle's loop the epithelium resembles that found in the Malpighian capsule and the commencement of the tube, consisting of flat, clear epithelial plates, each with an oval nucleus (Fig. 1025). The nuclei alternate on opposite surfaces of the tubule so that the lumen remains fairly constant.

In the straight tube the epithelium is clear and cubical: in its papillary portion the cells are distinctly columnar and transparent (Fig. 1026).

**The Renal Bloodvessels.**—The kidney is plentifully supplied with blood (Fig. 1027) by the renal artery, a large offset of the abdominal aorta. Before it enters the kidney, each artery divides into four or five branches which at the hilus lie mainly between the renal vein and ureter, the vein being in front, the ureter behind; one branch usually lies behind the ureter. Each vessel gives off some small branches to the suprarenal glands, to the ureter, and to the surrounding cellular tissue and muscles. Frequently a second renal artery, termed the *inferior renal*, is given off from the abdominal aorta at a lower level, and supplies the lower portion of the kidney, while occasionally an additional artery enters the upper part of the kidney. The branches of the renal artery, while in the sinus, give off a few twigs for the nutrition of the surrounding tissues, and end in the *arteriae propriae renales*, which enter the kidney proper in the renal columns. Two of these pass to each renal pyramid, and run along its sides for its entire length, giving off in their course the afferent vessels of the Malpighian bodies in the renal



FIG. 1025. — Longitudinal section of descending limb of Henle's loop. *a*. Membrana propria. *b*. Epithelium.




FIG. 1026. — Section of cortex of human kidney.

columns. Having arrived at the bases of the pyramids, they form arterial arches or arcades which lie in the boundary zone between the bases of the pyramids and the cortical arches, and break up into two distinct sets of branches devoted to the supply of the remaining portions of the kidney.

The *first set*, the *interlobular arteries* (Fig. 1022), are given off at right angles from the side of the arterial arcade looking toward the cortical substance, and pass directly outward between



the medullary rays to reach the fibrous tunic, where they end in the capillary net-work of this part. These vessels do not anastomose with each other, but form what are called *end-arteries*. In their outward course they give off lateral branches; these are the *afferent vessels* for the Malpighian bodies (see page 1212); they enter the capsule, and end in the Malpighian tufts. From each tuft the corresponding *efferent vessel* arises, and, having made its egress from the capsule near to the point where the afferent vessel enters, breaks up into a number of branches, which form a dense *plexus* around the adjacent urinary tubes.

The **second set of branches** from the arterial arcades supply the renal pyramids, which they enter at their bases; and, passing straight through their substance to their apices, terminate in the venous plexuses found in that situation. They are called the *arteriae rectae*. The efferent vessels from the glomeruli nearest the medulla break up into leashes of straight vessels (*false arteriae rectae*) which pass down into the medulla and join the plexus of vessels there (Fig. 1022).

The **renal veins** arise from three sources, viz., the veins beneath the fibrous tunic, the plexuses around the convoluted tubules in the cortex, and the plexuses situated at the apices of the renal pyramids. The veins beneath the fibrous tunic (*venae stellatae*) are stellate in arrangement, and are derived from the capillary net-work, into which the terminal branches of the interlobular arteries break up. These join to form the *interlobular veins*, which pass inward between the rays, receive branches from the plexuses around the convoluted tubules, and, having arrived at the bases of the renal pyramids, join with the *venae rectae*, next to be described.




FIG. 1027.—Transverse section of pyramidal substance of kidney of pig, the bloodvessels of which are injected. *a*. Large collecting tube, cut across, lined with cylindrical epithelium. *b*. Branch of collecting tube, cut across, lined with cubical epithelium. *c*, *d*. Henle's loops cut across. *e*. Bloodvessels cut across. *D*. Connective tissue ground substance.

The *venae rectae* are branches from the plexuses at the apices of the medullary pyramids, formed by the terminations of the *arteriae rectae*. They run outward in a straight course between the tubes of the medullary substance, and joining, as above stated, the interlobular veins, form venous arcades; these in turn unite and form veins which pass along the sides of the pyramids (Fig. 1022).

These vessels, *venae propriae renales*, accompany the arteries of the same name, running along the entire length of the sides of the pyramids, and quit the kidney substance to enter the sinus. In this cavity they join the corresponding veins from the other pyramids to form the *renal vein*, which emerges from the kidney at the hilus and opens into the inferior vena cava; the left vein is longer than the right, and crosses in front of the abdominal aorta.

The **lymphatics** of the kidney are described on page 793.

**Nerves of the Kidney.**—The nerves of the kidney, although small, are about fifteen in number. They have small ganglia developed upon them, and are derived from the renal plexus, which is formed by branches from the coeliac plexus, the lower and outer part of the coeliac ganglion and aortic plexus, and from the lesser and lowest splanchnic nerves. They communicate with the spermatic plexus, a circumstance which may explain the occurrence of pain in the testis in affections of the kidney. They accompany the renal artery and its branches, and are distributed to the bloodvessels and to the cells of the urinary tubules.

**Connective Tissue** (*intertubular stroma*).—Although the tubules and vessels are closely packed, a small amount of connective tissue, continuous with the fibrous tunic, binds them firmly together and supports the bloodvessels, lymphatics, and nerves.

**Applied Anatomy.**—Malformations of the kidney are not uncommon. There may be an entire absence of one kidney, but, according to Morris, the number of these cases is "excessively small": or there may be congenital atrophy of one kidney, when the kidney is very small, but usually healthy in structure. These cases are of great importance, and must be duly taken into

account when nephrectomy is contemplated. A more common malformation is where the two kidneys are fused together. They may be joined together only at their lower ends by means of a thick mass of renal tissue, so as to form a horseshoe-shaped body, or they may be completely united, forming a disk-like kidney, from which two ureters descend into the bladder. These fused kidneys are generally situated in the middle line of the abdomen, but may be misplaced as well. In some mammals, *e. g.*, ox and bear, the kidney consists of a number of distinct lobules; this lobulated condition is characteristic of the kidney of the human fetus, and traces of it may persist in the adult. Sometimes the pelvis is duplicated, while a double ureter is not very uncommon. In some rare instances a third kidney may be present.

One or both kidneys may be misplaced as a congenital condition, and remain fixed in this abnormal position. They are then very often misshapen. They may be situated higher, though this is very uncommon, or lower than normal or removed farther from the vertebral column than usual; or they may be displaced into the iliac fossa, over the sacroiliac joint, on to the promontory of the sacrum, or into the pelvis between the rectum and bladder or by the side of the uterus. In these latter cases they may give rise to very serious trouble. The kidney may also be misplaced as a congenital condition, but may not be fixed; it is then known as a *floating kidney*. It is believed to be due to the fact that the kidney is completely enveloped by peritoneum which then passes backward to the vertebral column as a double layer, forming a mesonephron which permits of movement taking place. The kidney may also be misplaced as an acquired condition; in these cases the kidney is mobile in the tissues by which it is surrounded, moving with the capsule in the perinephric tissues. This condition is known as *movable kidney*, and is more common in the female than in the male. It occurs in badly nourished people, or in those who have become emaciated from any cause. It must not be confounded with the *floating kidney*, which is a congenital condition due to the development of a mesonephron. The two conditions cannot, however, be distinguished until the abdomen is opened or the kidney explored from the loin.

Injuries of the kidney are generally due to some severe crushing force, as from being run over by a heavy wagon or cart, or from the abdomen being compressed between the buffers of two railway carriages. When a laceration occurs on the posterior surface of the organ, infiltration of blood and urine takes place into the retroperitoneal connective tissue; this is often followed by suppuration, and death may ensue from septic poisoning. When the laceration is in front, the peritoneum may be torn and extravasation of blood and urine take place into the peritoneal cavity. Death may occur from hemorrhage or peritonitis. Occasionally, when rupture involves the pelvis of the kidney or the commencement of the ureter, this duct may become blocked, and hydronephrosis follow. Sometimes the kidney may be bruised by blows in the loin, or by being compressed between the lower ribs and the ilium when the body is violently bent forward. This is followed by a little transient hematuria, which, however, speedily passes off.

The loose cellular tissue around the kidney may be the seat of suppuration, constituting *perinephric abscess*. This may be due to injury, to disease of the kidney itself, or to extension of inflammation from neighboring parts. The abscess tends to point externally in the groin or loin.

Tumors of the kidney, of which perhaps sarcoma is the most common, may be recognized by their position; by the resonant colon lying in front of them; and by their rounded outline not presenting a notched anterior margin like the spleen, with which they are most likely to be confounded.

The *hypernephroma*, a benign or malignant tumor arising from the suprarenal gland, or from suprarenal "rests" or inclusions in the cortex or medulla of the kidney, is not infrequent. When occurring in children it is often associated with precocious growth of the body generally and of the hair and sexual organs in particular. Arising, as it often does, in the kidney, a hypernephroma may be indistinguishable from a true renal tumor so far as the physical signs and symptoms go; it is really, however, a tumor of the suprarenal gland substance.

The examination of the kidney should be bimanual; that is to say, one hand should be placed in the flank and firm pressure made forward; while the other hand is buried in the abdominal wall, over the situation of the organ. Manipulation of the kidney frequently produces a peculiar sickening sensation, sometimes with faintness.

The kidney may require exposure for exploration or the evacuation of pus (*nephrotomy*); it may be incised for the removal of stone (*nephrolithotomy*); it may be sutured when movable or floating (*nephrorrhaphy*); or it may be removed (*nephrectomy*). It may be exposed either by a lumbar or an abdominal incision; except in cases of very large tumors, a lumbar incision is best, as it has the advantages of not opening the peritoneum, and of affording admirable drainage. An oblique incision should be made, starting at the lateral border of the *Sacrospinalis*, 1.25 cm. below the last rib and directed downward and forward toward a point 2.5 cm. in front of the anterior superior spine of the ilium. The structures divided are the skin, the superficial fascia with the cutaneous nerves, the deep fascia, the posterior border of the *Obliquus externus abdominis*, and the outer border of the *Latissimus dorsi*; the *Obliquus internus* and the posterior aponeurosis of the *Transversus abdominis*; the lateral border of the *Quadratus lumborum*; the deep layer of the lumbodorsal fascia and the transversalis fascia. The fatty tissue around the

kidney is now exposed to view, and must be separated by the fingers, or a director, in order to reach the kidney. The operations of nephrolithotomy, for the removal of calculi from the kidney, and nephrotomy, or incision of the kidney for abscess, etc., are generally performed by the lumbar incision. This route is also generally chosen for nephrectomy, especially if the organ is thought to contain pus. The abdominal operation is best performed by an incision through the lateral part of the Rectus abdominis on the side of the kidney to be removed; the kidney is then reached from the lateral side of the colon, ascending or descending, as the case may be, and thus the vessels of the colon are not interfered with. The incision commencing just below the costal arch is made of varying length, according to the size of the kidney. The abdominal cavity having been opened, the intestines are drawn medialward and the peritoneum covering the kidney to the lateral side of the colon is incised, so that the fingers can be introduced behind the peritoneum. The kidney must now be enucleated, and the vessels firmly ligatured and divided, the ureter being tied separately. The particular advantage of the abdominal operation is that the condition of the other kidney can be ascertained by manual examination, before the removal of the diseased kidney is finally decided upon; and further, involvement of neighboring structure by a new-growth, rendering removal impossible, can only be discovered by the abdominal route.

Nephrorrhaphy is the name given to the operation for fixing a movable kidney. The kidney is reached by the lumbar incision, and its posterior surface denuded of its adipose capsule. Three stitches of medium thickness are passed through the transversalis fascia and muscles and through the cortical substance of the kidney, securing a good hold of it. When these sutures are tied, the kidney is tightly anchored in position; cases which are seen sometime afterward seem, however, to show that it does not always remain fixed.

### The Ureters.

The **ureters** are the two tubes which convey the urine from the kidneys to the urinary bladder. Each commences within the sinus of the corresponding kidney as a number of short cup-shaped tubes, termed **calices**, which encircle the renal papillæ. Since a single calyx may enclose more than one papilla the calices are generally fewer in number than the pyramids—the former varying from seven to thirteen, the latter from eight to eighteen. The calices join to form two or three short tubes, and these unite to form a funnel-shaped dilatation, wide above and narrow below, named the **renal pelvis**, which is situated partly inside and partly outside the renal sinus. It is usually placed on a level with the spinous process of the first lumbar vertebra.

The **Ureter Proper** measures from 25 to 30 cm. in length, and is a thick-walled narrow cylindrical tube which is directly continuous near the lower end of the kidney with the tapering extremity of the renal pelvis. It runs downward and medialward in front of the Psoas major and, entering the pelvic cavity, finally opens into the fundus of the bladder.

The **abdominal part** (*pars abdominalis*) lies behind the peritoneum on the medial part of the Psoas major, and is crossed obliquely by the internal spermatic vessels. It enters the pelvic cavity by crossing either the termination of the common, or the commencement of the external, iliac vessels.

At its origin the **right** ureter is usually covered by the descending part of the duodenum, and in its course downward lies to the right of the inferior vena cava, and is crossed by the right colic and ileocolic vessels, while near the superior aperture of the pelvis it passes behind the lower part of the mesentery and the terminal part of the ileum. The **left** ureter is crossed by the left colic vessels, and near the superior aperture of the pelvis passes behind the sigmoid colon and its mesentery.

The **pelvic part** (*pars pelvina*) runs at first downward on the lateral wall of the pelvic cavity, along the anterior border of the greater sciatic notch and under cover of the peritoneum. It lies in front of the hypogastric artery medial to the obturator nerve and the umbilical, obturator, inferior vesical, and middle hemorrhoidal arteries. Opposite the lower part of the greater sciatic foramen it inclines medialward, and reaches the lateral angle of the bladder, where it is situated in front of the upper end of the seminal vesicle and at a distance of about 5 cm. from the opposite ureter; here the ductus deferens crosses to its medial side, and

the vesical veins surround it. Finally, the ureters run obliquely for about 2 cm. through the wall of the bladder and open by slit-like apertures into the cavity of the viscus at the lateral angles of the trigone. When the bladder is distended the openings of the ureters are about 5 cm. apart, but when it is empty and contracted the distance between them is diminished by one-half. Owing to their oblique course through the coats of the bladder, the upper and lower walls of the terminal portions of the ureters become closely applied to each other when the viscus is distended, and, acting as valves, prevent regurgitation of urine from the bladder.

In the **female**, the ureter forms, as it lies in relation to the wall of the pelvis, the posterior boundary of a shallow depression named the **ovarian fossa**, in which the ovary is situated. It then runs medialward and forward on the lateral aspect of the cervix uteri and upper part of the vagina to reach the fundus of the bladder. In this part of its course it is accompanied for about 2.5 cm. by the uterine artery, which then crosses in front of the ureter and ascends between the two layers of the broad ligament. The ureter is distant about 2 cm. from the side of the cervix of the uterus. The ureter is sometimes duplicated on one or both sides, and the two tubes may remain distinct as far as the fundus of the bladder. On rare occasions they open separately into the bladder cavity.

**Structure** (Fig. 1028).—The ureter is composed of three coats: **fibrous**, **muscular**, and **mucous coats**.

The **fibrous coat** (*tunica adventitia*) is continuous at one end with the fibrous tunic of the kidney on the floor of the sinus; while at the other it is lost in the fibrous structure of the bladder.

In the renal pelvis the **muscular coat** (*tunica muscularis*) consists of two layers, longitudinal and circular: the longitudinal fibres become lost upon the sides of the papillæ at the extremities of the calices; the circular fibres may be traced surrounding the medullary substance in the same situation. In the ureter proper the muscular fibres are very distinct, and are arranged in three layers: an external longitudinal, a middle circular, and an internal, less distinct than the other two, but having a general longitudinal direction. According to Kölliker this internal layer is found only in the neighborhood of the bladder.

The **mucous coat** (*tunica mucosa*) is smooth, and presents a few longitudinal folds which become effaced by distension. It is continuous with the mucous membrane of the bladder below, while it is prolonged over the papillæ of the kidney above. Its epithelium is of a transitional character, and resembles that found in the bladder (see Fig. 1034). It consists of several layers of cells, of which the innermost—that is to say, the cells in contact with the urine—are somewhat flattened, with concavities on their deep surfaces into which the rounded ends of the cells of the second layer fit. These, the intermediate cells, more or less resemble columnar epithelium, and are pear-shaped, with rounded internal extremities which fit into the concavities of the cells of the first layer, and narrow external extremities which are wedged in between the cells of the third layer. The external or third layer consists of conical or oval cells varying in number in different parts, and presenting processes which extend down into the basement-membrane. Beneath the epithelium, and separating it from the muscular coats, is a dense layer of fibrous tissue containing many elastic fibres.

**Vessels and Nerves.**—The **arteries** supplying the ureter are branches from the renal, internal spermatic, hypogastric, and inferior vesical.

The **nerves** are derived from the inferior mesenteric, spermatic, and pelvic plexuses.




FIG. 1028.—Transverse section of ureter.

**Applied Anatomy.**—Rupture of the ureter is not a common accident, but occasionally occurs. If it be torn completely across, the urine collects in the retroperitoneal tissues; if it be not completely divided, the lumen of the tube may become strictured and hydronephrosis or pyonephrosis result. The ureter may be accidentally wounded in some pelvic operations, such as removal of the uterus; if this should happen the divided ends must be sutured together, or failing to accomplish this an attempt may be made to implant the upper end into the bladder or rectum. If this cannot be carried out the only alternative is to remove the kidney immediately.

Stones not uncommonly become impacted in the ureter. These may occur at any part, but most commonly either at the point where the tube is crossing the pelvic brim or at the termination, where it is passing obliquely through the muscular wall of the bladder. In the former case, an incision with its centre opposite, and 2.5 cm. internal to, the anterior superior iliac spine, dividing all the structures down to the peritoneum, enables the operator to reach the ureter by pushing the unopened peritoneum inward; the stone can then be felt in the ureter, the wall of which is incised, and the stone extracted, free drainage being provided for the escaping urine. When the stone is impacted at the vesical end of the tube a preliminary incision into the bladder is required, and by scratching through the mucous membrane overlying it the calculus can be removed.

### The Urinary Bladder (*Vesica Urinaria*; **Bladder**) (Fig. 1029).

The **urinary bladder** is a musculomembranous sac which acts as a reservoir for the urine; and as its size, position, and relations vary according to the amount of fluid it contains, it is necessary to study it as it appears (*a*) when *empty*, and (*b*)




FIG. 1029.—Median sagittal section of male pelvis.

when *distended*. In both conditions the position of the bladder varies with the condition of the rectum, being pushed upward and forward when the rectum is distended.

**The Empty Bladder.**—When hardened *in situ*, the empty bladder has the form of a flattened tetrahedron, with its vertex tilted forward. It presents a fundus,



a vertex, a superior and an inferior surface. The **fundus** (Fig. 1041) is triangular in shape, and is directed downward and backward toward the rectum, from which it is separated by the rectovesical fascia, the vesiculæ seminales, and the terminal portions of the ductus deferentes. The **vertex** is directed forward toward the upper part of the symphysis pubis, and from it the middle umbilical ligament is continued upward on the back of the anterior abdominal wall to the umbilicus. The peritoneum is carried by it from the vertex of the bladder on to the abdominal wall to form the middle umbilical fold. The **superior surface** is triangular, bounded on either side by a lateral border which separates it from the inferior surface, and behind by a posterior border, represented by a line joining the two ureters, which intervenes between it and the fundus. The lateral borders extend from the ureters to the vertex, and from them the peritoneum is carried to the walls of the pelvis. On either side of the bladder the peritoneum shows a depression, named the **para-vesical fossa** (Fig. 963). The superior surface is directed upward, is covered by peritoneum, and is in relation with the sigmoid colon and some of the coils of the small intestine. When the bladder is empty and firmly contracted, this surface is convex and the lateral and posterior borders are rounded; whereas if the bladder be relaxed it is concave, and the interior of the viscus, as seen in a median sagittal section, presents the appearance of a V-shaped slit with a shorter posterior and a longer anterior limb—the apex of the V corresponding with the internal orifice of the urethra. The **inferior surface** is directed downward and is uncovered by peritoneum. It may be divided into a posterior or prostatic area and two infero-lateral surfaces. The prostatic area is somewhat triangular: it rests upon and is in direct continuity with the base of the prostate; and from it the urethra emerges. The infero-lateral portions of the inferior surface are directed downward and lateralward: in front, they are separated from the symphysis pubis by a mass of fatty tissue which is named the **retropubic pad**; behind, they are in contact with the fascia which covers the Levatores ani and Obturatores interni.

When the bladder is empty it is placed entirely within the pelvis, below the level of the obliterated hypogastric arteries, and below the level of those portions of the ductus deferentes which are in contact with the lateral wall of the pelvis; after they cross the ureters the ductus deferentes come into contact with the fundus of the bladder. As the viscus fills, its fundus, being more or less fixed, is only slightly depressed; while its superior surface gradually rises into the abdominal cavity, carrying with it its peritoneal covering, and at the same time rounding off the posterior and lateral borders.

**The Distended Bladder.**—When the bladder is moderately full it contains about 0.5 litre and assumes an oval form; the long diameter of the oval measures about 12 cm. and is directed upward and forward. In this condition it presents a postero-superior, an antero-inferior, and two lateral surfaces, a fundus and a summit. The **postero-superior surface** is directed upward and backward, and is covered by peritoneum: behind, it is separated from the rectum by the rectovesical excavation, while its anterior part is in contact with the coils of the small intestine. The **antero-inferior surface** is devoid of peritoneum, and rests, below, against the pubic bones, above which it is in contact with the back of the anterior abdominal wall. The lower parts of the lateral surfaces are destitute of peritoneum, and are in contact with the lateral walls of the pelvis. The line of peritoneal reflection from the lateral surface is raised to the level of the obliterated hypogastric artery. The **fundus** undergoes little alteration in position, being only slightly lowered. It exhibits, however, a narrow triangular area, which is separated from the rectum merely by the rectovesical fascia. This area is bounded below by the prostate, above by the rectovesical fold of peritoneum, and laterally by the ductus deferentes. The ductus deferentes frequently come in contact with each other above the prostate, and under such circumstances the lower part of the triangular area is obliterated.

ated. The line of reflection of the peritoneum from the rectum to the bladder appears to undergo little or no change when the latter is distended; it is situated about 10 cm. from the anus. The **summit** is directed upward and forward above the point of attachment of the middle umbilical ligament, and hence the peritoneum which follows the ligament, forms a pouch of varying depth between the summit of the bladder, and the anterior abdominal wall.




FIG. 1030.—Sagittal section through the pelvis of a newly born male child.

**The Bladder in the Child** (Figs. 1030, 1031).—In the newborn child the internal urethral orifice is at the level of the upper border of the symphysis pubis; the bladder therefore lies relatively at a much higher level in the infant than in the




FIG. 1031.—Sagittal section through the pelvis of a newly born female child.

adult. Its anterior surface "is in contact with about the lower two-thirds of that part of the abdominal wall which lies between the symphysis pubis and the umbilicus" (Symington<sup>1</sup>). Its fundus is clothed with peritoneum as far as the level

<sup>1</sup> The Anatomy of the Child.

of the internal orifice of the urethra. Although the bladder of the infant is usually described as an abdominal organ, Symington has pointed out that only about one-half of it lies above the plane of the superior aperture of the pelvis. Disse maintains that the internal urethral orifice sinks rapidly during the first three years, and then more slowly until the ninth year, after which it remains stationary until puberty, when it again slowly descends and reaches its adult position.

**The Female Bladder** (Fig. 1032).—In the female, the bladder is in relation behind with the uterus and the upper part of the vagina. It is separated from the anterior surface of the body of the uterus by the vesicouterine excavation, but below the level of this excavation it is connected to the front of the cervix uteri and the upper part of the anterior wall of the vagina by areolar tissue. When the bladder is empty the uterus rests upon its superior surface. The female bladder is said by some to be more capacious than that of the male, but probably the opposite is the case.




FIG. 1032.—Median sagittal section of female pelvis.

**Ligaments.**—The bladder is connected to the pelvic wall by the fascia endopelvina. In front this fascial attachment is strengthened by a few muscular fibres, the **Pubovesicales**, which extend from the back of the pubic bones to the front of the bladder; behind, other muscular fibres run from the fundus of the bladder to the sides of the rectum, in the sacrogenital folds, and constitute the **Rectovesicales**.

The vertex of the bladder is joined to the umbilicus by the remains of the urachus which forms the **middle umbilical ligament**, a fibromuscular cord, broad at its attachment to the bladder but narrowing as it ascends.

From the superior surface of the bladder the peritoneum is carried off in a series of folds which are sometimes termed the **false ligaments of the bladder**. Anteriorly there are three folds: the **middle umbilical fold** on the middle umbilical ligament,

and two **lateral umbilical folds** on the obliterated hypogastric arteries. The reflections of the peritoneum on to the side walls of the pelvis form the lateral false ligaments, while the sacrogenital folds constitute posterior false ligaments.

**Interior of the Bladder** (Fig. 1033).—The mucous membrane lining the bladder is, over the greater part of the viscus, loosely attached to the muscular coat, and appears wrinkled or folded when the bladder is contracted: in the distended condition of the bladder the folds are effaced. Over a small triangular area, termed the **trigonum vesicae**, immediately above and behind the internal orifice of the urethra, the mucous membrane is firmly bound to the muscular coat, and is always smooth. The anterior angle of the trigonum vesicae is formed by the internal orifice of the urethra: its postero-lateral angles by the orifices of the ureters. Stretching behind the latter openings is a slightly curved ridge, the **torus uretericus**, forming the base of the trigone and produced by an underlying bundle of non-striped muscular




FIG. 1033.—The interior of bladder.

fibres. The lateral parts of this ridge extend beyond the openings of the ureters, and are named the **plicae uretericae**; they are produced by the terminal portions of the ureters as they traverse obliquely the bladder wall. When the bladder is illuminated the torus uretericus appears as a pale band and forms an important guide during the operation of introducing a catheter into the ureter.

The **orifices of the ureters** are placed at the postero-lateral angles of the trigonum vesicae, and are usually slit-like in form. In the contracted bladder they are about 2.5 cm. apart and about the same distance from the internal urethral orifice; in the distended viscus these measurements may be increased to about 5 cm.

The **internal urethral orifice** is placed at the apex of the trigonum vesicae, in the most dependent part of the bladder, and is usually somewhat crescentic in form; the mucous membrane immediately behind it presents a slight elevation, the **uvula vesicae**, caused by the middle lobe of the prostate.



**Structure (Fig. 1034).**—The bladder is composed of the four coats: **serous, muscular, submucous, and mucous coats.**

The **serous coat** (*tunica serosa*) is a partial one, and is derived from the peritoneum. It invests the superior surface and the upper parts of the lateral surfaces, and is reflected from these on to the abdominal and pelvic walls.

The **muscular coat** (*tunica muscularis*) consists of three layers of unstriated muscular fibres: an external layer, composed of fibres having for the most part a longitudinal arrangement; a middle layer, in which the fibres are arranged, more or less, in a circular manner; and an internal layer, in which the fibres have a general longitudinal arrangement.

The fibres of the external layer arise from the posterior surface of the body of the pubis in both sexes (*musculi pubovesicales*), and in the male from the adjacent part of the prostate and its capsule. They pass, in a more or less longitudinal manner, up the inferior surface of the bladder, over its vertex, and then descend along its fundus to become attached to the prostate in the male, and to the front of the vagina in the female. At the sides of the bladder the fibres are arranged obliquely and intersect one another. This layer has been named the **Detrusor urinae muscle.**

The fibres of the middle circular layer are very thinly and irregularly scattered on the body of the organ, and, although to some extent placed transversely to the long axis of the bladder, are for the most part arranged obliquely. Toward the lower part of the bladder, around the internal urethral orifice, they are disposed in a thick circular layer, forming the **Sphincter vesicae**, which is continuous with the muscular fibres of the prostate.

The **internal longitudinal layer** is thin, and its fasciculi have a reticular arrangement, but with a tendency to assume for the most part a longitudinal direction. Two bands of oblique fibres, originating behind the orifices of the ureters, converge to the back part of the prostate, and are inserted by means of a fibrous process, into the middle lobe of that organ. They are the **muscles of the ureters**, described by Sir C. Bell, who supposed that during the contraction of the bladder they serve to retain the oblique direction of the ureters, and so prevent the reflux of the urine into them.

The **submucous coat** (*tela submucosa*) consists of a layer of areolar tissue, connecting together the muscular and mucous coats, and intimately united to the latter.

The **mucous coat** (*tunica mucosa*) is thin, smooth, and of a pale rose color. It is continuous above through the ureters with the lining membrane of the renal tubules, and below with that of the urethra. The loose texture of the submucous layer allows the mucous coat to be thrown into folds or *rugae* when the bladder is empty. Over the trigonum vesicae the mucous membrane is closely attached to the muscular coat, and is not thrown into folds, but is smooth and flat. The epithelium covering it is of the transitional variety, consisting of a superficial layer of polyhedral flattened cells, each with one, two, or three nuclei; beneath these is a stratum of large club-shaped cells, with their narrow extremities directed downward and wedged in between smaller spindle-shaped cells, containing oval nuclei (Fig. 1034). The epithelium varies according as the bladder is distended or contracted. In the former condition the superficial cells are flattened and those of the other layers are shortened; in the latter they present the appearance described above. There are no true glands in the mucous membrane of the bladder, though certain mucous follicles which exist, especially near the neck of the bladder, have been regarded as such.

**Vessels and Nerves.**—The **arteries** supplying the bladder are the superior, middle, and inferior vesical, derived from the anterior trunk of the hypogastric. The obturator and inferior gluteal arteries also supply small visceral branches to the bladder, and in the female additional branches are derived from the uterine and vaginal arteries.

The **veins** form a complicated plexus on the inferior surface, and fundus near the prostate, and end in the hypogastric veins.

The **lymphatics** are described on page 793.

The **nerves** of the bladder are (1) fine medullated fibres from the third and fourth sacral nerves, and (2) non-medullated fibres from the hypogastric plexus. They are connected with ganglia in the outer and submucous coats and are finally distributed, all as non-medullated fibres, to the muscular layer and epithelial lining of the viscus.




FIG. 1034.—Vertical section of bladder wall.



**Applied Anatomy.**—A defect of development, in which the bladder is implicated, is known under the name of *extroversion of the bladder*. In this condition the lower part of the abdominal wall and the anterior wall of the bladder are wanting, so that the fundus of the bladder presents on the abdominal surface, and is pushed forward by the pressure of the viscera within the abdomen, forming a red vascular tumor on which the openings of the ureters are visible. The penis, except the glans, is rudimentary and is cleft on its dorsal surface, exposing the floor of the urethra, a condition known as *epispadias*. The pelvic bones are also arrested in development (see page 344).

The bladder may be ruptured by violence applied to the abdominal wall, when the viscus is distended, without any injury to the bony pelvis, or it may be torn in cases of fracture of the pelvis. The rupture may be either intraperitoneal or extraperitoneal: that is, may implicate the superior surface of the bladder in the former case, or one of the other surfaces in the latter. Until recently intraperitoneal rupture was uniformly fatal, but now abdominal section and suturing the rent with Lembert's suture is resorted to, with a very considerable amount of success. The sutures are inserted only through the peritoneal and muscular coats in such a way as to bring the serous surfaces at the margins of the wound into apposition, and one is inserted just beyond each end of the wound. The bladder should be tested as to whether it is water-tight before closing the external incision.

The muscular coat of the bladder undergoes hypertrophy in cases in which there is any obstruction to the flow of urine. Under these circumstances the bundles of which the muscular coat consists become much increased in size, and, interlacing in all directions, give rise to what is known as the *fasciculated bladder*. Between these muscular bundles the mucous membrane may bulge out, forming *sacculi*, constituting the *sacculated bladder*, and in these little pouches phosphatic concretions may collect, forming *encysted calculi*. The mucous membrane is very loosely attached, except over the trigone, to allow of the distension of the viscus.

Various forms of tumor have been found springing from the wall of the bladder. The commonest innocent tumor is the villous papilloma. Of the malignant tumors, epithelioma is the most common, but sarcoma is occasionally found in the bladder of children.

In doubtful cases the cystoscope proves a valuable aid in diagnosis. This instrument consists of a tube in which is fixed a small electric light, the wires of which run through the shaft of the instrument. Upon introducing this down the urethra, the bladder can be examined with the eye and a villous growth or other tumor, a calculus, or an ulcer can be detected; or the orifices of the ureters can be examined, and renal hematuria diagnosed, and it can be definitely settled from which kidney the blood comes. Again, the presence of minute tuberculous ulceration near the mouth of the ureter on the affected side may establish the diagnosis, not only of tuberculous kidney, but also of the side in which the disease is located. The cystoscope can be used to catheterize the ureter, for the purpose of obtaining a specimen of urine from either kidney, or to ascertain the condition of both kidneys where it is proposed to remove one. Ureteric bougies opaque to x-rays can be passed up and photographed.

Puncture of the bladder may be performed either above the symphysis pubis or through the rectum, in both cases without wounding the peritoneum. The former plan is generally to be preferred, since in puncture by the rectum a permanent fistula may be left from abscess forming between the rectum and the bladder; or pelvis cellulitis may be set up; moreover, it is exceedingly inconvenient to keep a cannula in the rectum. In some cases, in performing this operation the rectovesical excavation of the peritoneum has been wounded, inducing fatal peritonitis. Puncture through the rectum, therefore, has been almost completely abandoned in favor of the suprapubic route.

Access to the bladder, for the purpose of removing calculi or an enlarged prostate, is almost always effected by the suprapubic route, the old perineal operation being now rarely resorted to. In the female, owing to the shortness of the urethra, and its ready dilatibility, calculi and foreign bodies and new growths, when of small size, may be removed by the urethral route.

Suprapubic cystotomy is performed by first injecting ten or twelve ounces of some weak antiseptic fluid into the bladder. Then, with or without distending the rectum, a vertical median incision, from 7 to 10 cm. in length, is made in the hypogastric region immediately above the symphysis, and extended between the *Pyramidales* and *Recti* until the *transversalis fascia* is reached. This is divided and some fatty tissue exposed (space of Retzius). Upon separating this, the inferior surface of the bladder will be exposed and will be recognized by its muscular fibres. A needle should be passed through its coat on either side of the spot selected for the opening, and two long pieces of silk inserted. The bladder is incised between these stays, which are held by an assistant and form a useful guide to the opening in the bladder when the fluid has escaped.

It is important that the bladder should be emptied by catheter as a routine measure in women, prior to operations on the lower part of the abdomen or pelvis. Neglect of this precaution has, not uncommonly, led to that viscus being opened by accident. Women especially are apt to acquire an atonic distension of the bladder, and the fact that some quantity of urine has been passed immediately before operation is no guarantee that the viscus is not distended. If the accident should occur, the bladder wall must be carefully sutured before the peritoneum is opened.

**The Male Urethra (Urethra Virilis) (Fig. 1035).**

The **male urethra** extends from the internal urethral orifice in the urinary bladder to the external urethral orifice at the end of the penis. It presents a double curve in the ordinary relaxed state of the penis (Fig. 1030). Its length varies from 17.5 to 20 cm.; and it is divided into three portions, the **prostatic**, **membranous**, and **cavernous**, the structure and relations of which are essentially different. Except during the passage of the urine or semen, the greater part of the urethral canal is a mere transverse cleft or slit, with its upper and under surfaces in contact; at the external orifice the slit is vertical, in the membranous portion irregular or stellate, and in the prostatic portion somewhat arched.

The **prostatic portion** (*pars prostatica*), the widest and most dilatable part of the canal, is about 3 cm. long. It runs almost vertically through the prostate from its base to its apex, lying nearer its anterior than its posterior surface; the form of the canal is spindle-shaped, being wider in the middle than at either extremity, and narrowest below, where it joins the membranous portion. A transverse section of the canal as it lies in the prostate is horse-shoe-shaped, with the convexity directed forward.

Upon the posterior wall or floor is a narrow longitudinal ridge, the **urethral crest** (*verumontanum*), formed by an elevation of the mucous membrane and its subjacent tissue. It is from 15 to 17 mm. in length, and about 3 mm. in height, and contains, according to Kobelt, muscular and erectile tissue. When distended, it may serve to prevent the passage of the semen backward into the bladder. On either side of the crest is a slightly depressed fossa, the **prostatic sinus**, the floor of which is perforated by numerous apertures, the **orifices of the prostatic ducts** from the lateral lobes of the prostate; the ducts of the middle lobe open behind the crest. At the forefront of the urethral crest, below its summit, is a median elevation, the **colliculus seminalis**, upon or within the margins of which are the orifices of the prostatic utricle and the slit-like openings of the ejaculatory ducts. The **prostatic utricle** (*sinus pocularis*) forms a cul-de-sac about 6 mm. long, which runs upward and backward in the substance of the prostate behind the middle lobe. Its walls are composed of fibrous tissue, muscular fibres, and mucous




FIG. 1035.—The male urethra laid open on its anterior (upper) surface.

membrane, and numerous small glands open on its inner surface. It was called by Weber the *uterus masculinus*, from its being developed from the united lower ends of the atrophied Müllerian ducts, and therefore homologous with the uterus and vagina in the female.

The **membranous portion** (*pars membranacea*) is the shortest, least dilatable, and, with the exception of the external orifice, the narrowest part of the canal. It extends downward and forward, with a slight anterior concavity, between the apex of the prostate and the bulb of the urethra, perforating the urogenital diaphragm about 2.5 cm. below and behind the pubic symphysis. The hinder part of the urethral bulb lies in apposition with the inferior fascia of the urogenital diaphragm, but its upper portion diverges somewhat from this fascia: the anterior wall of the membranous urethra is thus prolonged for a short distance in front of the urogenital diaphragm; it measures about 2 cm. in length, while the posterior wall which is between the two fasciæ of the diaphragm is only 1.25 cm. long.

The membranous portion of the urethra is completely surrounded by the fibres of the Sphincter urethrae membranaceæ. In front of it the deep dorsal vein of the penis enters the pelvis between the transverse ligament of the pelvis and the arcuate pubic ligament; on either side near its termination are the bulbourethral glands.

The **cavernous portion** (*pars cavernosa; penile or spongy portion*) is the longest part of the urethra, and is contained in the corpus cavernosum urethrae. It is about 15 cm. long, and extends from the termination of the membranous portion to the external urethral orifice. Commencing below the inferior fasciæ of the urogenital diaphragm it passes forward and upward to the front of the symphysis pubis; and then, in the flaccid condition of the penis, it bends downward and forward. It is narrow, and of uniform size in the body of the penis, measuring about 6 mm. in diameter; it is dilated behind, within the bulb, and again anteriorly within the glans penis, where it forms the *fossa navicularis urethrae*.

The **external urethral orifice** (*orificium urethrae externum; meatus urinarius*) is the most contracted part of the urethra; it is a vertical slit, about 6 mm. long, bounded on either side by two small labia.

The lining membrane of the urethra, especially on the floor of the cavernous portion, presents the orifices of numerous mucous glands and follicles situated in the submucous tissue, and named the **urethral glands** (*Littre*). Besides these there are a number of small pit-like recesses, or *lacunæ*, of varying sizes. Their orifices are directed forward, so that they may easily intercept the point of a catheter in its passage along the canal. One of these lacunæ, larger than the rest, is situated on the upper surface of the fossa navicularis; it is called the *lacuna magna*. The bulbo-urethral glands open into the cavernous portion about 2.5 cm. in front of the inferior fascia of the urogenital diaphragm.

**Structure.**—The urethra is composed of mucous membrane, supported by a submucous tissue which connects it with the various structures through which it passes.

The **mucous coat** forms part of the genito-urinary mucous membrane. It is continuous with the mucous membrane of the bladder, ureters, and kidneys; externally, with the integument covering the glans penis; and is prolonged into the ducts of the glands which open into the urethra, viz., the bulbo-urethral glands and the prostate; and into the ductus deferentes and vesiculæ seminales, through the ejaculatory ducts. In the cavernous and membranous portions the mucous membrane is arranged in longitudinal folds when the tube is empty. Small papillæ are found upon it, near the external urethral orifice; its epithelial lining is of the columnar variety except near the external orifice, where it is squamous and stratified.

The **submucous tissue** consists of a vascular erectile layer; outside this is a layer of unstriped muscular fibres, arranged in a circular direction, which separates the mucous membrane and submucous tissue from the tissue of the corpus cavernosum urethrae.

**Applied Anatomy.**—The urethra may be ruptured by the patient falling astride of any hard substance and striking his perineum, so that the urethra is crushed against the pubic arch. Bleeding will at once take place from the urethra, and this, together with the bruising in the

perineum and the history of the accident, will point to the nature of the injury. Rupture of the urethra is due in other cases to the perforation of a periurethral abscess. Extravasation of urine most frequently takes place into the perineum in front of the inferior fascia of the urogenital diaphragm, *i. e.*, under the fascia of Colles. Both these layers of fascia are attached firmly to the ischiopubic rami. It is clear, therefore, that when extravasation of fluid takes place between them, it cannot pass backward, because the two layers are continuous with each other around the Transversus perinaei muscles; it cannot extend laterally, on account of the connection of both these layers to the rami of the pubis and ischium; it cannot find its way into the pelvis, because the opening into this cavity is closed by the urogenital diaphragm, and, therefore, so long as these two layers remain intact, the only direction in which the fluid can make its way is forward into the areolar tissue of the scrotum and penis, and thence on to the anterior wall of the abdomen.

Gonorrhœa is an acute and very prevalent inflammatory infection of the mucous membrane of the urethra. The causative organisms (gonococci) pass through the mucous membrane into the submucous tissue, and most serious complications and results may follow. In most cases the disease remains limited to the part of the urethra in front of the urogenital diaphragm, but in some (about 10 per cent.) the "posterior urethra" becomes involved in the process, leading to an inflammation of the openings of the prostatic follicles. Such a condition is apt to continue as a very chronic form of prostatitis, and in many cases the infection will spread along the ductus deferens, giving rise to epididymitis.

The anatomy of the urethra is of considerable importance in connection with the passage of instruments into the bladder. Otis was the first to point out that the urethra is capable of great dilatability, so that, excepting through the external urethral orifice, an instrument corresponding to 18 English gauge (29 French) can usually be passed without damage. The external orifice of the urethra is not so dilatable, and therefore may require slitting. A recognition of this dilatability caused Bigelow to very considerably modify the operation for crushing a stone in the bladder. In passing catheters, especially fine ones, the point of the instrument should be kept as far as possible along the upper wall of the canal, as otherwise it is very liable to enter one of the lacunæ.

Stricture of the urethra is a disease of very common occurrence, and is generally situated in the cavernous part of the urethra, just in front of the membranous portion, but in a very considerable number of cases in the antescrotal part of the canal. The stricture usually results from the contraction of inflammatory products in the submucous tissue, the result, in the vast majority of all cases, of a prolonged gleet following gonorrhœa. Urethral stricture, however, follows rupture of that tube resulting from falls on the perineum, and in this variety is very dense, and is a most unsatisfactory condition with regard to treatment. Congenital stricture is also occasionally met with, and in such cases multiple strictures may be present throughout the whole length of the cavernous portion.

Congenital defects of the urethra occur occasionally. The one most frequently met with is where there is a cleft on the floor of the urethra owing to an arrest of union in the middle line. This is known as *hypospadias*, and the cleft may vary in extent. The simplest and by far the most common form is where the deficiency is confined to the glans penis. The urethra ends at the point where the extremity of the prepuce joins the body of the penis, in a small valve-like opening. The prepuce is also cleft on its under surface and forms a sort of hood over the glans. There is a depression on the glans in the position of the normal meatus. This condition produces no disability and requires no treatment. In more severe cases the cavernous portion of the urethra is cleft throughout its entire length, and the opening of the urethra is at the point of junction of the penis and scrotum. The under surface of the penis in the middle line presents a furrow lined by a moist mucous membrane, on either side of which is often more or less dense fibrous tissue stretching from the glans to the opening of the urethra, which prevents complete erection taking place. Great discomfort is induced during micturition, and sexual connection is impossible. The condition may be remedied by a series of plastic operations. The worst form of this condition is where the urethra is deficient as far back as the perineum, and the scrotum is cleft. The penis is small and bound down between the two halves of the scrotum, so as to resemble an hypertrophied clitoris. The testes are often retained. The condition of parts, therefore, very much resembles the external organs of generation of the female, and many children the victims of this malformation have been brought up as girls. The halves of the scrotum, deficient of testes, resemble the labia, the cleft between them looks like the orifice of the vagina, and the diminutive penis is taken for an enlarged clitoris. There is no remedy for this condition.

A much more uncommon form of malformation is where there is an apparent deficiency of the upper wall of the urethra; this is named *epispadias*. The deficiency may vary in extent; when it is complete the condition is associated with extroversion of the bladder. In less extensive cases, where there is no extroversion, there is an infundibuliform opening into the bladder. The penis is usually dwarfed and turned upward, so that the glans lies over the opening.

### The Female Urethra (*Urethra Muliebris*) (Fig. 1032).

The **female urethra** is a narrow membranous canal, about 4 cm. long, extending from the internal to the external urethral orifice. It is placed behind the symphysis pubis, imbedded in the anterior wall of the vagina, and its direction is obliquely downward and forward; it is slightly curved with the concavity directed forward. Its diameter when undilated is about 6 mm. It perforates the fasciæ of the urogenital diaphragm, and its external orifice is situated directly in front of the vaginal opening and about 2.5 cm. behind the glans clitoridis. The lining membrane is thrown into longitudinal folds, one of which, placed along the floor of the canal, is termed the **urethral crest**. Many small urethral glands open into the urethra.

**Structure.**—The urethra consists of three coats: **muscular**, **erectile**, and **mucous**.

The **muscular coat** is continuous with that of the bladder; it extends the whole length of the tube, and consists of circular fibres. In addition to this, between the superior and inferior fasciæ of the urogenital diaphragm, the female urethra is surrounded by the *Sphincter urethræ membranaceæ*, as in the male.

A **thin layer of spongy erectile tissue**, containing a plexus of large veins, intermixed with bundles of unstriped muscular fibres, lies immediately beneath the mucous coat.

The **mucous coat** is pale; it is continuous externally with that of the vulva, and internally with that of the bladder. It is lined by stratified squamous epithelium, which becomes transitional near the bladder. Its external orifice is surrounded by a few mucous follicles.

### THE MALE GENITAL ORGANS (*ORGANA GENITALIA VIRILIA*).

The male genitals include the **testes**, the **ductus deferentes**, the **vesiculæ seminales**, the **ejaculatory ducts**, and the **penis**, together with the following accessory structures, viz., the **prostate** and the **bulbourethral glands**.

#### The Testes and Their Coverings (Fig. 1036).

The **testes** are two glandular organs, which secrete the semen; they are suspended in the scrotum by the spermatic cords. At an early period of fetal life the testes are contained in the abdominal cavity, behind the peritoneum. Before birth they descend to the inguinal canal, along which they pass with the spermatic cord, and, emerging at the subcutaneous inguinal ring, they descend into the scrotum, becoming invested in their course by coverings derived from the serous, muscular, and fibrous layers of the abdominal parietes, as well as by the scrotum.

The **coverings of the testes** are, the

Skin	} Scrotum.	Cremaster.
Dartos tunic		Infundibuliform fascia.
Intercrural fascia.		Tunica vaginalis.

The **Scrotum** is a cutaneous pouch which contains the testes and parts of the spermatic cords. It is divided on its surface into two lateral portions by a ridge or **raphé**, which is continued forward to the under surface of the penis, and backward, along the middle line of the perineum to the anus. Of these two lateral portions the left hangs lower than the right, to correspond with the greater length of the left spermatic cord. Its external aspect varies under different circumstances: thus, under the influence of warmth, and in old and debilitated persons, it becomes elongated and flaccid; but, under the influence of cold, and in the young and robust, it is short, corrugated, and closely applied to the testes.

The scrotum consists of two layers, the **integument** and the **dartos tunic**.

The **Integument** is very thin, of a brownish color, and generally thrown into folds or **rugæ**. It is provided with sebaceous follicles, the secretion of which has a



peculiar odor, and is beset with thinly scattered, crisp hairs, the roots of which are seen through the skin.

The **Dartos Tunic** (*tunica dartos*) is a thin layer of non-striped muscular fibres, continuous, around the base of the scrotum, with the two layers of the superficial fascia of the groin and the perineum; it sends inward a septum, which divides the scrotal pouch into two cavities for the testes, and extends between the raphé and the under surface of the penis, as far as its root.

The dartos tunic is closely united to the skin externally, but connected with the subjacent parts by delicate areolar tissue, upon which it glides with the greatest facility.




FIG. 1036.—Transverse section through the left side of the scrotum and the left testis. The sac of the tunica vaginalis is represented in a distended condition. (Diagrammatic.) (Delépine.)

The **Intercrural Fascia** (*intercolumnar or external spermatic fascia*) is a thin membrane, prolonged downward around the surface of the cord and testis (see page 501). It is separated from the dartos tunic by loose areolar tissue.

The **Cremaster** consists of scattered bundles of muscular fibres connected together into a continuous covering by intermediate areolar tissue (see page 504).

The **Infundibuliform Fascia** (*tunica vaginalis communis [testis et funiculi spermatici]*) is a thin layer, which loosely invests the cord; it is a continuation downward of the transversalis fascia (see page 508).

The **Tunica Vaginalis** is described with the testes.

**Vessels and Nerves.**—The **arteries** supplying the coverings of the testes are: the superficial and deep external pudendal branches of the femoral, the superficial perineal branch of the internal pudendal, and the cremasteric branch from the inferior epigastric. The **veins** follow the course of the corresponding arteries. The **lymphatics** end in the inguinal lymph glands. The **nerves** are the ilioinguinal and lumboinguinal branches of the lumbar plexus, the two superficial perineal branches of the internal pudendal nerve, and the pudendal branch of the posterior femoral cutaneous nerve.

The **Inguinal Canal** (*canalis inguinalis*) is described on page 508.

The **Spermatic Cord** (*funiculus spermaticus*) extends from the abdominal inguinal ring, where the structures of which it is composed converge, to the back part of the testis. In the abdominal wall the cord passes obliquely along the inguinal canal, lying at first beneath the Obliquus internus, and upon the fascia

transversalis; but nearer the pubis, it rests upon the inguinal and lacunar ligaments, having the aponeurosis of the *Obliquus externus* in front of it, and the inguinal falx behind it. It then escapes at the subcutaneous ring, and descends nearly vertically into the scrotum. The left cord is rather longer than the right, consequently the left testis hangs somewhat lower than its fellow.

**Structure of the Spermatic Cord.**—The spermatic cord is composed of arteries, veins, lymphatics, nerves, and the excretory duct of the testis. These structures are connected together by areolar tissue, and invested by the layers brought down by the testis in its descent.

The **arteries of the cord** are: the internal and external spermatics; and the artery to the ductus deferens.

The *internal spermatic artery*, a branch of the abdominal aorta, escapes from the abdomen at the abdominal inguinal ring, and accompanies the other constituents of the spermatic cord along the inguinal canal and through the subcutaneous inguinal ring into the scrotum. It then descends to the testis, and, becoming tortuous, divides into several branches, two or three of which accompany the ductus deferens and supply the epididymis, anastomosing with the artery of the ductus deferens: the others supply the substance of the testis.

The *external spermatic artery* is a branch of the inferior epigastric artery. It accompanies the spermatic cord and supplies the coverings of the cord, anastomosing with the internal spermatic artery.

The *artery of the ductus deferens*, a branch of the superior vesical, is a long, slender vessel, which accompanies the ductus deferens, ramifying upon its coats, and anastomosing with the internal spermatic artery near the testis.

The **spermatic veins** emerge from the back of the testis, and receive tributaries from the epididymis: they unite and form a convoluted plexus, the **plexus pampiniformis**, which forms the chief mass of the cord; the vessels composing this plexus are very numerous, and ascend along the cord in front of the ductus deferens; below the subcutaneous inguinal ring they unite to form three or four veins, which pass along the inguinal canal, and, entering the abdomen through the abdominal inguinal ring, coalesce to form two veins. These again unite to form a single vein, which opens on the right side into the inferior vena cava, at an acute angle, and on the left side into the left renal vein, at a right angle.

The **lymphatic vessels** are described on page 794.

The **nerves** are the spermatic plexus from the sympathetic, joined by filaments from the pelvic plexus which accompany the artery of the ductus deferens.

**Applied Anatomy.**—The scrotum forms an admirable covering for the protection of the testes. These bodies, lying suspended and loose in the cavity of the scrotum and surrounded by serous membrane, are capable of great mobility, and can therefore easily slip about within the scrotum and thus avoid injuries from blows or squeezes. The skin of the scrotum is very elastic and capable of great distension, and on account of the looseness and amount of subcutaneous tissue, the scrotum becomes greatly enlarged in cases of cedema, to which this part is especially liable as a result of its dependent position. The scrotum is occasionally the seat of epithelioma; this is no doubt due to the rugæ on its surface, which favor the lodgement of dirt, and this, producing irritation, is the exciting cause of the disease. The disease is very much less common than it used to be; this is probably due to the better hygienic conditions of the working classes. The scrotum is also the part most frequently affected by elephantiasis.

On account of the looseness of the subcutaneous tissue, large extravasations of blood may take place from very slight injuries. It is therefore generally recommended never to apply leeches to the scrotum, since they may lead to ecchymosis, but rather to puncture one or more of the superficial veins of the scrotum in cases where local blood-letting from this part is judged to be desirable. The muscular fibre in the dartos tunic causes contraction and considerable diminution in the size of a wound of the scrotum, as after the operation of castration, and are of assistance in keeping the edges together, and covering the exposed parts.

The **Testes** are suspended in the scrotum by the spermatic cords, the left testis hanging somewhat lower than its fellow. The average dimensions of the testis are from 4 to 5 cm. in length, 2.5 cm. in breadth, and 3 cm. in the antero-posterior diameter; its weight varies from 10.5 to 14 gm. Each testis is of an oval form (Fig. 1037), compressed laterally, and having an oblique position in the scrotum; the upper extremity is directed forward and a little lateralward; the lower, backward and a little medialward; the anterior convex border looks forward and downward, the posterior or straight border, to which the cord is attached, backward and upward.

The anterior border and lateral surfaces, as well as both extremities of the organ,

are convex, free, smooth, and invested by the visceral layer of the tunica vaginalis. The posterior border, to which the cord is attached, receives only a partial investment from that membrane. Lying upon the lateral edge of this posterior border is a long, narrow, flattened body, named the **epididymis**.

The **epididymis** consists of a central portion or **body**; an upper enlarged extremity, the **head** (*globus major*); and a lower pointed extremity, the **tail** (*globus minor*), which is continuous with the ductus deferens, the **duct of the testis**. The head is intimately connected with the upper end of the testis by means of the efferent ductules of the gland; the tail is connected with the lower end by cellular tissue, and a reflection of the tunica vaginalis. The lateral surface, head and tail of the epididymis are free and covered by the serous membrane; the body is also completely invested by it, excepting along its posterior border; while between the body and the testis is a pouch, named the **sinus of the epididymis** (*digital fossa*). The epididymis is connected to the back of the testis by a fold of the serous membrane.




FIG. 1037.—The right testis, exposed by laying open the tunica vaginalis.

**Appendages of the Testis and Epididymis.**—On the upper extremity of the testis, just beneath the head of the epididymis, is a minute oval, sessile body, the **appendix of the testis** (*hydatid of Morgagni*); it is the remnant of the upper end of the Müllerian duct. On the head of the epididymis is a second small stalked appendage (sometimes duplicated); it is named the **appendix of the epididymis** (*pedunculated hydatid*), and is usually regarded as a detached efferent duct.

The testis is invested by three tunics: the **tunica vaginalis**, **tunica albuginea**, and **tunica vasculosa**.

The **Tunica Vaginalis** (*tunica vaginulis propria testis*) is the serous covering of the testis. It is a pouch of serous membrane, derived from the saccus vaginalis of the peritoneum, which in the fetus preceded the descent of the testis from the abdomen into the scrotum. After its descent, that portion of the pouch which extends from the abdominal inguinal ring to near the upper part of the gland becomes obliterated; the lower portion remains as a shut sac, which invests the surface of the testis, and is reflected on to the internal surface of the scrotum; hence it may be described as consisting of a **visceral** and **parietal lamina**.

The **visceral lamina** (*lamina visceralis*) covers the greater part of the testis and epididymis, connecting the latter to the testis by means of a distinct fold. From

the posterior border of the gland it is reflected on to the internal surface of the scrotum.

The **parietal lamina** (*lamina parietalis*) is far more extensive than the visceral, extending upward for some distance in front and on the medial side of the cord, and reaching below the testis. The inner surface of the tunica vaginalis is smooth, and covered by a layer of endothelial cells. The interval between the visceral and parietal laminæ constitutes the cavity of the tunica vaginalis.

The obliterated portion of the saccus vaginalis may generally be seen as a fibro-cellular thread lying in the loose areolar tissue around the spermatic cord; sometimes this may be traced as a distinct band from the upper end of the inguinal canal, where it is connected with the peritoneum, down to the tunica vaginalis; sometimes it gradually becomes lost on the spermatic cord. Occasionally no trace of it can be detected. In some cases it happens that the pouch of peritoneum does not become obliterated, but the sac of the peritoneum communicates with the tunica vaginalis. This may give rise to one of the varieties of oblique inguinal hernia (page 1187). In other cases the pouch may contract, but not become entirely obliterated; it then forms a minute canal leading from the peritoneum to the tunica vaginalis.

The **Tunica Albuginea** is the fibrous covering of the testis. It is a dense membrane, of a bluish-white color, composed of bundles of white fibrous tissue which interlace in every direction. It is covered by the tunica vaginalis, except at the points of attachment of the epididymis to the testis, and along its posterior border, where the spermatic vessels enter the gland. It is applied to the tunica vasculosa over the glandular substance of the testis, and, at its posterior border, is reflected into the interior of the gland, forming an incomplete vertical septum, called the **mediastinum testis** (*corpus Highmori*).

The **mediastinum testis** extends from the upper to near the lower extremity of the gland, and is wider above than below. From its front and sides numerous imperfect septa (*trabeculae*) are given off, which radiate toward the surface of the organ, and are attached to the tunica albuginea. They divide the interior of the organ into a number of incomplete spaces which are somewhat cone-shaped, being broad at their bases at the surface of the gland, and becoming narrower as they converge to the mediastinum. The mediastinum supports the vessels and duct of the testis in their passage to and from the substance of the gland.

The **Tunica Vasculosa** is the vascular layer of the testis, consisting of a plexus of bloodvessels, held together by delicate areolar tissue. It clothes the inner surface of the tunica albuginea and the different septa in the interior of the gland, and therefore forms an internal investment to all the spaces of which the gland is composed.

**Structure.**—The glandular structure of the testis consists of numerous lobules. Their number, in a single testis, is estimated by Berres at 250, and by Krause at 400. They differ in size according to their position, those in the middle of the gland being larger and longer. The lobules (Fig. 1038) are conical in shape, the base being directed toward the circumference of the organ, the apex toward the mediastinum. Each lobule is contained in one of the intervals between the fibrous septa which extend between the mediastinum testis and the tunica albuginea, and consists of from one to three, or more, minute convoluted tubes, the **tubuli seminiferi**. The tubules may be separately unravelled, by careful dissection under water, and may be seen to commence either by free cecal ends or by anastomotic loops. They are supported by loose connective tissue which contains here and there groups of "interstitial cells" containing yellow pigment granules. The total number of tubules is estimated by Lauth at 840, and the average length of each is 70 to 80 cm. Their diameter varies from 0.12 to 0.3 mm. The tubules are pale in color in early life, but in old age they acquire a deep yellow tinge from containing much fatty matter. Each tubule consists of a basement layer formed of laminated connective tissue containing numerous elastic fibres with flattened cells between the layers and covered externally by a layer of flattened epithelioid cells. Within the basement-membrane are epithelial cells arranged in several irregular layers, which are not always clearly separated, but which may be arranged in three different groups (Fig. 1039). Among these cells may be seen the **spermatozoa** in different

stages of development. (1) Lining the basement membrane and forming the outer zone is a layer of cubical cells, with small nuclei; some of these enlarge to become **spermatogonia**. The nucleus of some of the spermatogonia may be seen to be in process of indirect division (*karyokinesis*, page 34), and in consequence of this daughter cells are formed, which constitute the second zone. (2) Within this first layer is to be seen a number of larger polyhedral cells, with clear nuclei, arranged in two or three layers; these are the **intermediate cells** or **spermatocytes**. Most of these cells are in a condition of karyokinetic division, and the cells which result from this division form those of the next layer, the **spermatoblasts** or **spermatids**. (3) The third layer of cells consists of the spermatoblasts or spermatids, and each of these, without further subdivision, becomes a **spermatozoön**. The spermatids are small polyhedral cells, the nucleus of each of which contains half the usual number of chromosomes. In addition to these three layers of cells others are seen, which are termed the **supporting cells** (*cells of Sertoli*). They are elongated and columnar, and project inward from the basement membrane toward the lumen of the tube. As development of the spermatozoa proceeds the latter group themselves around the inner extremities of the supporting cells. The nuclear portion of the spermatid, which is partly imbedded in the supporting cell, is differentiated to form the head of the spermatozoön, while part of the cell protoplasm forms the middle piece and the tail is produced by an outgrowth from the double centriole of the cell. Ultimately the heads are liberated and the spermatozoa are set free. The structure of the spermatozoa is described on pages 80, 81.

In the apices of the lobules, the tubules become less convoluted, assume a nearly straight course, and unite together to form from twenty to thirty larger ducts, of about 0.5 mm. in diameter, and these, from their straight course, are called **tubuli recti** (Fig. 1038).

The **tubuli recti** enter the fibrous tissue of the mediastinum, and pass upward and backward, forming, in their ascent, a close net-work of anastomosing tubes which are merely channels in the fibrous stroma, lined by flattened epithelium, and having no proper walls; this constitutes the **rete testis**. At the upper end of the mediastinum, the vessels of the rete testis terminate in from twelve to fifteen or twenty ducts, the **ductuli efferentes**; they perforate the tunica albuginea, and carry the seminal fluid from the testis to the epididymis. Their course is at first straight; they then become enlarged, and exceedingly convoluted, and form a series of conical masses,




FIG. 1038.—Vertical section of the testis, to show the arrangement of the ducts.




FIG. 1039.—Transverse section of a tubule of the testis of a rat.  $\times 250$ .

the **coni vasculosi**, which together constitute the head of the epididymis. Each cone consists of a single convoluted duct, from 15 to 20 cm. in length, the diameter of which gradually decreases from the testis to the epididymis. Opposite the bases of the cones the efferent vessels open at narrow intervals into a single duct, which constitutes, by its complex convolutions, the body and tail of the epididymis. When the convolutions of this tube are unravelled, it measures upward of 6 metres in length; it increases in diameter and thickness as it approaches the ductus



deferens. The convolutions are held together by fine areolar tissue, and by bands of fibrous tissue.

The tubuli recti have very thin walls; like the channels of the rete testis they are lined by a single layer of flattened epithelium. The ductuli efferentes and the tube of the epididymis have walls of considerable thickness, on account of the presence in them of muscular tissue, which is principally arranged in a circular manner. These tubes are lined by columnar ciliated epithelium (Fig. 1040).

**Applied Anatomy.**—The testis, developed in the lumbar region, may be arrested or delayed in its transit to the scrotum. It may be retained in the abdomen; or it may be arrested at the abdominal inguinal ring, or in the inguinal canal; or it may just pass out of the subcutaneous inguinal ring without finding its way to the bottom of the scrotum. When retained in the abdomen it gives rise to no symptoms, other than the absence of the testis from the scrotum; but when it is retained in the inguinal canal it is subjected to pressure and may become inflamed and painful. The retained testis is probably functionally useless; so that a man in whom both testes are retained (*anorchism*) is sterile, though he may not be impotent. The absence of one testis is termed *monorchism*. When a testis is retained in the inguinal canal it is often complicated with a congenital hernia, the funicular process of the peritoneum not being obliterated. In addition to the cases above described, where there is some arrest in the descent of the testis, this organ may descend through the inguinal canal, but may miss the scrotum and assume some abnormal position. The most common form is where the testis, emerging at the subcutaneous inguinal ring, slips down between the scrotum and thigh and comes to rest in the perineum. This is known as *perineal ectopia testis*. With all varieties of abnormality in the position of the testis, it is very common to find concurrently a congenital hernia, or, if a hernia be not actually present, the funicular process is usually patent, and almost invariably so if the testis is in the inguinal canal.




FIG. 1040.—Section of epididymis of guinea-pig.  $\times 255$ .

The testis, finally reaching the scrotum, may occupy an abnormal position in it. It may be inverted, so that its posterior or attached border is directed forward and the tunica vaginalis is situated behind. Should a hydrocele occur, and tapping be resorted to, the trocar may be thrust into the testis, if the operation is performed in the ordinary way, and care is not taken beforehand to ascertain the position of the gland.

A number of instances of torsion of the spermatic cord, resulting in acute strangulation of the testis, have been recorded. In some it has been attributed to a strain or twist, and in several patients the condition has been associated with a late descent of the organ. Symptoms of this condition closely simulate those of a strangulated hernia. In consequence of the torsion the circulation is partly arrested and the organ swells and becomes acutely painful, and the condition may be accompanied with shock and vomiting. Gangrene of the testis, however, rarely follows, and the condition, if left without operation, ends in atrophy of the organ. Torsion of the body of the testis also sometimes occurs within the tunica vaginalis in those cases in which a persistent mesorchium is present.

Fluid collections of a serous character are very frequently found in the scrotum. To these the term *hydrocele* is applied. The most common form is the ordinary *vaginal hydrocele*, in which the fluid is contained in the sac of the tunica vaginalis, which is separated, in its normal condition, from the peritoneal cavity by the whole extent of the inguinal canal. In another form, the *congenital hydrocele*, the fluid is in the sac of the tunica vaginalis, but this cavity communicates with the general peritoneal cavity, its tubular process remaining pervious. A third variety,

known as an *infantile hydrocele*, occurs in those cases where the tubular process becomes obliterated only at its upper part, at or near the abdominal inguinal ring. It resembles the vaginal hydrocele, except as regards its shape, the collection of fluid extending up the cord into the inguinal canal. Fourthly, the funicular process may become obliterated both at the abdominal inguinal ring and above the epididymis, leaving a central unobliterated portion, which may become distended with fluid, giving rise to a condition known as the *encysted hydrocele of the cord*.

*Encysted hydrocele of the epididymis* or *spermatocele* is the name given to a cyst found in connection with the head of the epididymis. Among its contents are found, in many instances, a varying number of spermatozoa, and it is probably a retention cyst of one of the tubules.

The testis frequently requires removal for malignant disease; in tuberculous disease; in cases of large *hernia testis*, and in some instances of incompletely descended or misplaced testes. The operation of castration was formerly performed for enlargement of the prostate, but has now been entirely abandoned in favor of the direct operation of the enlarged prostate. Castration is in most cases best carried out by the "high" operation, an incision being made through the skin and fascia in the region of the subcutaneous inguinal ring. The testis, with its deeper coverings, is then pushed up into the wound and separated from the scrotal tissues. The cord is then isolated, and an aneurism needle, armed with a ligature, passed through it, as high as it is thought necessary, and the cord tied and divided. In cases of malignant and tuberculous disease, it is desirable to open the inguinal canal and tie the cord as near the abdominal ring as possible. When removing the testis in this manner the tunica vaginalis is not opened and its folds of reflection to the scrotal tissues do not need division. The whole of the tunica vaginalis is thus removed with the cord and its coverings.

Acute inflammation of the testis, or *orchitis*, is common in gonorrhœa; a chronic fibrosing form of orchitis is frequent in syphilis, and leads to shrinkage and hardening of the testis. In *tabes dorsalis* the testis often becomes quite insensitive to pressure, which, in the healthy adult, readily produces a severe and peculiar sickening sensation.

### The Ductus Deferens (Vas Deferens; Seminal Duct).

The **ductus deferens**, the excretory duct of the testis, is the continuation of the canal of the epididymis. Commencing at the lower part of the tail of the epididymis it is at first very tortuous, but gradually becoming less twisted it ascends along the posterior border of the testis and medial side of the epididymis, and, as a constituent of the spermatic cord, traverses the inguinal canal to the abdominal inguinal ring. Here it separates from the other structures of the cord, curves around the lateral side of the inferior epigastric artery, and ascends for about 2.5 cm. in front of the external iliac artery. It is next directed backward and slightly downward, and, crossing the external iliac vessels obliquely, enters the pelvic cavity, where it lies between the peritoneal membrane and the lateral wall of the pelvis, and descends on the medial side of the obliterated umbilical artery and the obturator nerve and vessels. It then crosses in front of the ureter, and, reaching the medial side of this tube, bends to form an acute angle, and runs medialward and slightly forward between the fundus of the bladder and the upper end of the seminal vesicle. Reaching the medial side of the seminal vesicle, it is directed downward and medialward in contact with it, gradually approaching the opposite ductus. Here it lies between the fundus of the bladder and the rectum, where it is enclosed, together with the seminal vesicle, in a sheath derived from the rectovesical portion of the fascia endopelvina. Lastly, it is directed downward to the base of the prostate, where it becomes greatly narrowed, and is joined at an acute angle by the duct of the seminal vesicle to form the ejaculatory duct, which traverses the prostate behind its middle lobe and opens into the prostatic portion of the urethra, close to the orifice of the prostatic utricle. The ductus deferens presents a hard and cord-like sensation to the fingers, and is of cylindrical form; its walls are dense, and its canal is extremely small. At the fundus of the bladder it becomes enlarged and tortuous, and this portion is termed the **ampulla**. A small triangular area of the fundus of the bladder, between the ductus deferentes laterally and the bottom of the rectovesical excavation of peritoneum above, is in contact with the rectum.

**Ductuli Aberrantes.**—A long narrow tube, the **ductulus aberrans inferior** (*vas aberrans of Haller*), is occasionally found connected with the lower part of the canal of the epididymis, or with the commencement of the ductus deferens. Its length varies from 3.5 to 35 cm., and it may become dilated toward its extremity; more commonly it retains the same diameter throughout. Its structure is similar to that of the ductus deferens. Occasionally it is found unconnected with the epididymis. A second tube, the **ductulus aberrans superior**, occurs in the head of the epididymis; it is connected with the rete testis.

**Paradidymis** (*organ of Giraldés*).—This term is applied to a small collection of convoluted tubules, situated in front of the lower part of the cord above the head of the epididymis. These tubes are lined with columnar ciliated epithelium, and probably represent the remains of a part of the Wolffian body.

**Structure.**—The ductus deferens consists of three coats: (1) an **external or areolar coat**; (2) a **muscular coat** which in the greater part of the tube consists of two layers of unstriped muscular fibre: an outer, longitudinal in direction, and an inner, circular; but in addition to these, at the commencement of the ductus, there is a third layer, consisting of longitudinal fibres, placed internal to the circular stratum, between it and the mucous membrane; (3) an **internal or mucous coat**, which is pale, and arranged in longitudinal folds. The mucous coat is lined by columnar epithelium which is non-ciliated throughout the greater part of the tube; a variable portion of the testicular end of the tube is lined by two strata of columnar cells and the cells of the superficial layer are ciliated.

### The Vesiculæ Seminales (Seminal Vesicles) (Fig. 1041).

The **vesiculæ seminales** are two lobulated membranous pouches, placed between the fundus of the bladder and the rectum, serving as reservoirs for the semen, and secreting a fluid to be added to the secretion of the testes. Each sac is somewhat




FIG. 1041.—Fundus of the bladder with the vesiculæ seminales.

pyramidal in form, the broad end being directed backward, upward and lateralward. It is usually about 7.5 cm. long, but varies in size, not only in different individuals, but also in the same individual on the two sides. The **anterior surface** is in contact with the fundus of the bladder, extending from near the termination of the ureter to the base of the prostate. The **posterior surface** rests upon the rectum, from which it is separated by the rectovesical fascia. The **upper extremities** of the two vesicles diverge from each other, and are in relation with the ductus deferentes and the terminations of the ureters, and are partly covered by peritoneum. The **lower**

**extremities** are pointed, and converge toward the base of the prostate, where each joins with the corresponding ductus deferens to form the ejaculatory duct. Along the medial margin of each vesicle runs the ampulla of the ductus deferens.

Each vesicle consists of a single tube, coiled upon itself, and giving off several irregular cecal diverticula; the separate coils, as well as the diverticula, are connected together by fibrous tissue. When uncoiled, the tube is about the diameter of a quill, and varies in length from 10 to 15 cm.; it ends posteriorly in a cul-de-sac; its anterior extremity becomes constricted into a narrow straight duct, which joins with the corresponding ductus deferens to form the ejaculatory duct.

**Structure.**—The vesiculæ seminales are composed of three coats: an **external or areolar coat**; a **middle or muscular coat** thinner than in the ductus deferens and arranged in two layers, an outer longitudinal and inner circular; an **internal or mucous coat**, which is pale, of a whitish brown color, and presents a delicate reticular structure. The epithelium is columnar, and in the diverticula goblet cells are present, the secretion of which increases the bulk of the seminal fluid.

**Vessels and Nerves.**—The **arteries** supplying the vesiculæ seminales are derived from the middle and inferior vesical and middle hemorrhoidal. The **veins** and **lymphatics** accompany the arteries. The **nerves** are derived from the pelvic plexuses.

**Applied Anatomy.**—The vesiculæ seminales are often the seat of an extension of the disease in cases of tuberculosis of the testis, and should always be examined from the rectum, before deciding to perform castration in this affection. They also become affected in chronic posterior urethritis of gonorrhoeal origin.

### The Ejaculatory Ducts (Ductus Ejaculatorii) (Fig. 1042).

The **ejaculatory ducts** are two in number, one on either side of the middle line. Each is formed by the union of the duct from the vesicula seminalis with the ductus deferens, and is about 2 cm. long.

They commence at the base of the prostate, and run forward and downward between its middle and lateral lobes, and along the sides of the prostatic utricle, to end by separate slit-like orifices close to or just within the margins of the utricle. The ducts diminish in size, and also converge, toward their terminations.

**Structure.**—The coats of the ejaculatory ducts are extremely thin. They are: an **outer fibrous layer**, which is almost entirely lost after the entrance of the ducts into the prostate; a **layer of muscular fibres** consisting of a thin outer circular, and an inner longitudinal, layer; and **mucous membrane**.




FIG. 1042.—Vesiculæ seminales and ampullæ of ductus deferentes, seen from the front. The anterior walls of the left ampulla, left seminal vesicle, and prostatic urethra have been cut away.

### The Penis.

The **penis** is a pendulous organ suspended from the front and sides of the pubic arch and containing the greater part of the urethra. In the flaccid condition it is cylindrical in shape, but when erect assumes the form of a triangular prism with rounded angles, one side of the prism forming the dorsum. It is composed of three cylindrical masses of cavernous tissue bound together by fibrous tissue and covered with skin. Two of the masses are lateral, and are known as the **corpora cavernosa penis**; the third is median, and is termed the **corpus cavernosum urethrae** (Figs. 1043, 1044).

The **Corpora Cavernosa Penis** form the greater part of the substance of the penis. For their anterior three-fourths they lie in intimate apposition with one another, but behind they diverge in the form of two tapering processes, known as the **crura**, which are firmly connected to the rami of the pubic arch. Traced from behind forward, each crus begins by a blunt-pointed process in front of the tuberosity of the ischium. Just before it meets its fellow it presents a slight enlargement, named by Kobelt the **bulb of the corpus cavernosum penis**. Beyond this point the crus undergoes a constriction and merges into the corpus cavernosum proper,

which retains a uniform diameter to its anterior end. Each corpus cavernosum penis ends abruptly in a rounded extremity some distance from the point of the penis.

The corpora cavernosa penis are surrounded by a strong fibrous envelope consisting of superficial and deep fibres. The superficial fibres are longitudinal in direction, and form a single tube which encloses both corpora; the deep fibres are arranged circularly around each corpus, and form by their junction in the median plane the **septum of the penis**. This is thick and complete behind, but is imperfect in front, where it consists of a series of vertical bands arranged like the teeth of a comb; it is therefore named the **septum pectiniforme**.

The **Corpus Cavernosum Urethrae** (*corpus spongiosum*) contains the urethra.




FIG. 1043.—The constituent cavernous cylinders of the penis. The glans and anterior part of the corpus cavernosum urethrae are detached from the corpora cavernosa penis and turned to one side.




FIG. 1044.—Transverse section of the penis.

Behind, it is expanded to form the urethral bulb, and lies in apposition with the inferior fascia of the urogenital diaphragm, from which it receives a fibrous investment. The urethra enters the bulb nearer to the upper than to the lower surface. On the latter there is a median sulcus, from which a thin fibrous septum projects into the substance of the bulb and divides it imperfectly into two lateral lobes or hemispheres.

The portion of the corpus cavernosum urethrae in front of the bulb lies in a groove on the under surface of the conjoined corpora cavernosa penis. It is cylindrical in form and tapers slightly from behind forward. Its anterior end is expanded in the form of an obtuse cone, flattened from above downward. This expansion, termed the **glans penis**, is moulded on the rounded ends of the corpora cavernosa



penis, extending farther on their upper than on their lower surfaces. At the summit of the glans is the slit-like vertical external urethral orifice. The circumference of the base of the glans forms a rounded projecting border, the **corona glandis**, overhanging a deep **retroglandular sulcus**, behind which is the **neck** of the penis.

For descriptive purposes it is convenient to divide the penis into three regions: the **root**, the **body**, and the **extremity**.

The **root** (*radix penis*) of the penis is triradiate in form, consisting of the diverging crura, one on either side, and the median urethral bulb. Each crus is covered by the Ischiocavernosus, while the bulb is surrounded by the Bulbocavernosus. The root of the penis lies in the perineum between the inferior fascia of the urogenital diaphragm and the fascia of Colles. In addition to being attached to the fasciæ and the pubic rami, it is bound to the front of the symphysis pubis by the fundiform and suspensory ligaments. The **fundiform ligament** springs from the front of the sheath of the Rectus abdominis and the linea alba; it splits into two fasciculi which encircle the root of the penis. The upper fibres of the **suspensory ligament** pass downward from the lower end of the linea alba, and the lower fibres from the symphysis pubis; together they form a strong fibrous band, which extends to the upper surface of the root, where it blends with the fascial sheath of the organ.

The **body** (*corpus penis*) extends from the root to the ends of the corpora cavernosa penis, and in it these corpora cavernosa are intimately bound to one another. A shallow groove which marks their junction on the upper surface lodges the deep dorsal vein of the penis, while a deeper and wider groove between them on the under surface contains the corpus cavernosum urethrae. The body is ensheathed by fascia, which is continuous above with the fascia of Scarpa, and below with the dartos tunic of the scrotum and the fascia of Colles.

The **extremity** is formed by the glans penis, the expanded anterior end of the corpus cavernosum urethrae. It is separated from the body by the constricted neck, which is overhung by the corona glandis.

The integument covering the penis is remarkable for its thinness, its dark color, its looseness of connection with the deeper parts of the organ, and its absence of adipose tissue. At the root of the penis it is continuous with that over the pubes, scrotum, and perineum. At the neck it leaves the surface and becomes folded upon itself to form the **prepuce** or **foreskin**. The internal layer of the prepuce is directly continuous, along the line of the neck, with the integument over the glans. Immediately behind the external urethral orifice it forms a small secondary reduplication, attached along the bottom of a depressed median raphé, which extends from the meatus to the neck; this fold is termed the **frenulum** of the prepuce. The integument covering the glans is continuous with the urethral mucous membrane at the orifice; it is devoid of hairs, but projecting from its free surface are a number of small, highly sensitive papillæ. On the corona and neck numerous small glands, the **preputial glands**, have been described.<sup>1</sup> They secrete a sebaceous material of very peculiar odor, which probably contains casein, and readily undergoes decomposition.

The prepuce covers a variable amount of the glans, and is separated from it by a potential sac—the **preputial sac**—which presents two shallow fossæ, one on either side of the frenulum.

**Structure of the Penis.**—From the internal surface of the fibrous envelope of the corpora cavernosa penis, as well as from the sides of the septum, numerous bands or cords are given off, which cross the interior of these corpora cavernosa in all directions, subdividing them into a number of separate compartments, and giving the entire structure a spongy appearance (Fig. 1044). These bands and cords are called **trabeculæ**, and consist of white fibrous tissue, elastic fibres, and plain muscular fibres. In them are contained numerous arteries and nerves. The component fibres which form the trabeculæ are larger and stronger around the circumference than

<sup>1</sup> Stieda (Comptes-rendus du XII Congrès International de Médecine, Moscow, 1897) asserts that glands are never found on the corona glandis, and that what have hitherto been mistaken for glands are really large papillæ.

at the centres of the corpora cavernosa; they are also thicker behind than in front. The interspaces (cavernous spaces), on the contrary, are larger at the centre than at the circumference, their long diameters being directed transversely. They are filled with blood, and are lined by a layer of flattened cells similar to the endothelial lining of veins.

The fibrous envelope of the corpus cavernosum urethrae is thinner, whiter in color, and more elastic than that of the corpora cavernosa penis. The trabeculae are more delicate, nearly uniform in size, and the meshes between them smaller than in the corpora cavernosa penis: their long diameters, for the most part, corresponding with that of the penis. The external envelope or outer coat of the corpus cavernosum urethrae is formed partly of unstripped muscular fibres, and a layer of the same tissue immediately surrounds the canal of the urethra.

**Vessels and Nerves.**—The arteries bringing the blood to the cavernous spaces are the deep arteries of the penis and branches from the dorsal arteries of the penis, which perforate the fibrous capsule, along the upper surface, especially near the forepart of the organ. On entering the cavernous structure the arteries divide into branches, which are supported and enclosed by the trabeculae. Some of these arteries end in a capillary net-work, the branches of which open directly

into the cavernous spaces; others assume a tendril-like appearance, and form convoluted and somewhat dilated vessels, which were named by Müller **helicine arteries**. They open into the spaces, and from them are also given off small capillary branches to supply the trabecular structure. They are bound down in the spaces by fine fibrous processes, and are most abundant in the back part of the corpora cavernosa (Fig. 1045).

The blood from the cavernous spaces is returned by a series of vessels, some of which emerge in considerable numbers from the base of the glans penis and converge on the dorsum of the organ to form the deep dorsal vein; others pass out on the upper surface of the corpora cavernosa and join the same vein; some emerge from the under surface of the corpora cavernosa penis and receiving branches from the corpus cavernosum urethrae, wind around the sides of the penis to end in the deep dorsal vein; but the greater number pass out at the root of the penis and join the prostatic plexus.



FIG. 1045.—Section of corpus cavernosum penis in a non-distended condition. (Cadiau.) *a*. Trabeculae of connective tissue, with many elastic fibres and bundles of plain muscular tissue, some of which are cut across (*c*). *b*. Blood sinuses.

The lymphatic vessels of the penis are described on page 794.

The nerves are derived from the pudendal nerve and the pelvic plexuses. On the glans and bulb some filaments of the cutaneous nerves have Pacinian bodies connected with them, and, according to Krause, many of them end in peculiar end-bulbs (see page 1069).

**Applied Anatomy.**—The penis occasionally requires removal for malignant disease. Usually, removal of the antescrotal portion is all that is necessary, but sometimes it is requisite to remove the whole organ from its attachment to the rami of the pubes and ischia. The former operation is performed by cutting through the corpora cavernosa penis from the dorsum, and then separating the corpus cavernosum urethrae from them, dividing it at a level nearer the glans penis. The mucous membrane of the urethra is then slit up, and the edges of the flap attached to the external skin, in order to prevent contraction of the orifice, which might otherwise take place. The vessels which require ligature are the deep and the dorsal arteries of the penis, and the artery of the septum. When the entire organ requires removal, the patient is placed in the lithotomy position, and an incision is made through the skin and subcutaneous tissue around the root of the penis, and carried down through the median line of the scrotum as far as the perineum. The two halves of the scrotum are then separated from each other, and a catheter having been introduced into the bladder as a guide, the corpus cavernosum urethrae below the urogenital diaphragm is separated from the corpora cavernosa penis and divided, the catheter having been withdrawn. The suspensory ligament is now severed and the crura separated from the bone with a periosteum scraper, and the whole penis removed. The membranous portion of the urethra, which has not been removed, is now to be attached to the skin at the posterior extremity of the incision in the perineum. The remainder of the wound is closed, free drainage being provided for.

**The Prostate (Prostata; Prostate Gland).**

The **prostate** is a firm, partly glandular and partly muscular body, which is placed immediately below the internal urethral orifice and around the commencement of the urethra. It is situated in the pelvic cavity, below the lower part of the symphysis pubis, above the superior fascia of the urogenital diaphragm, and in front of the rectum, through which it may be distinctly felt, especially when enlarged. It is about the size of a chestnut and somewhat conical in shape, and presents for examination a **base**, an **apex**, an **anterior**, a **posterior**, and two **lateral surfaces**.

The **base** (*basis prostatae*) is directed upward, and is applied to the inferior surface of the bladder. The greater part of this surface is directly continuous with the bladder wall; the urethra penetrates it nearer its anterior than its posterior border.

The **apex** (*apex prostatae*) is directed downward, and is in contact with the superior fascia of the urogenital diaphragm.

**Surfaces.**—The **posterior surface** (*facies posterior*) is flattened from side to side and slightly convex from above downward; it is separated from the rectum by its sheath and some loose connective tissue, and is distant about 4 cm. from the anus. Near its upper border there is a depression through which the two ejaculatory ducts enter the prostate. This depression serves to divide the posterior surface into a lower larger and an upper smaller part. The upper smaller part constitutes the **middle lobe** of the prostate and intervenes between the ejaculatory ducts and the urethra; it varies greatly in size, and in some cases is destitute of glandular tissue. The lower larger portion sometimes presents a shallow median furrow, which imperfectly separates it into a **right** and a **left lateral lobe**: these form the main mass of the gland and are directly continuous with each other behind the urethra. In front of the urethra they are connected by a band which is named the **isthmus**: this consists of the same tissues as the capsule and is devoid of glandular substance.

The **anterior surface** (*facies anterior*) measures about 2.5 cm. from above downward but is narrow and convex from side to side. It is placed about 2 cm. behind the pubic symphysis, from which it is separated by a plexus of veins and a quantity of loose fat. It is connected to the pubic bone on either side by the puboprostatic ligaments. The urethra emerges from this surface a little above and in front of the apex of the gland.

The **lateral surfaces** are prominent, and are covered by the anterior portions of the Levatores ani, which are, however, separated from the gland by a plexus of veins.

The prostate measures about 4 cm. transversely at the base, 2 cm. in its antero-posterior diameter, and 3 cm. in its vertical diameter. Its weight is about 8 gm. It is held in its position by the puboprostatic ligaments; by the superior fascia of the urogenital diaphragm, which invests the prostate and the commencement of the membranous portion of the urethra; and by the anterior portions of the Levatores ani, which pass backward from the pubis and embrace the sides of the prostate. These portions of the Levatores ani, from the support they afford to the prostate, are named the **Levatores prostatae**.

The prostate is perforated by the urethra and the ejaculatory ducts. The urethra usually lies along the junction of its anterior with its middle third. The ejaculatory ducts pass obliquely downward and forward through the posterior part of the prostate, and open into the prostatic portion of the urethra.

**Structure** (Fig. 1046).—The prostate is immediately enveloped by a thin but firm fibrous capsule, distinct from that derived from the fascia endopelvina, and separated from it by a plexus of veins. This capsule is firmly adherent to the prostate and is structurally continuous with the stroma of the gland, being composed of the same tissues, viz.: non-striped muscle and fibrous

tissue. The substance of the prostate is of a pale reddish-gray color, of great density, and not easily torn. It consists of glandular substance and muscular tissue.

The **muscular tissue** according to Kölliker, constitutes the proper stroma of the prostate; the connective tissue being very scanty, and simply forming between the muscular fibres, thin trabeculae, in which the vessels and nerves of the gland ramify. The muscular tissue is arranged as follows: immediately beneath the fibrous capsule is a dense layer, which forms an investing sheath for the gland; secondly, around the urethra, as it lies in the prostate, is another dense layer of circular fibres, continuous above with the internal layer of the muscular coat of the bladder, and blending below with the fibres surrounding the membranous portion of the urethra. Between these two layers strong bands of muscular tissue, which decussate freely, form meshes in which the glandular structure of the organ is imbedded. In that part of the gland which is situated in front of the urethra the muscular tissue is especially dense, and there is here little or no gland tissue; while in that part which is behind the urethra the muscular tissue presents a wide-meshed structure, which is densest at the base of the gland—that is, near the bladder—becoming looser and more sponge-like toward the apex of the organ.




FIG. 1046.—Transverse section of normal prostate through the middle of the urethral crest, from a subject aged nineteen years. (Taylor). *a.* Longitudinal section of ducts leading from the lobules of the prostatic glands. *b.* Urethral crest. *c.* Prostatic utricle. *d.* Urethra. *e.* Ejaculatory ducts. *f.* Arteries, veins, and venous sinuses in sheath of prostate. *g.* Nerve trunks in sheath. *h.* Point of origin of fibromuscular bands encircling urethra. *i.* Zone of striated voluntary muscle on superior surface.

The **glandular substance** is composed of numerous follicular pouches the lining of which frequently shows papillary elevations. The follicles open into elongated canals, which join to form from twelve to twenty small excretory ducts. They are connected together by areolar tissue, supported by prolongations from the fibrous capsule and muscular stroma, and enclosed in a delicate capillary plexus. The epithelium which lines the canals and the terminal vesicles is of the columnar variety. The prostatic ducts open into the floor of the prostatic portion of the urethra, and are lined by two layers of epithelium, the inner layer consisting of columnar and the outer of small cubical cells. Small colloid masses, known as **amyloid bodies** are often found in the gland tubes.

**Vessels and Nerves.**—The **arteries** supplying the prostate are derived from the internal pudendal, inferior vesical, and middle hemorrhoidal. Its veins form a plexus around the sides and base of the gland; they receive in front the dorsal vein of the penis, and end in the hypogastric veins. The **nerves** are derived from the pelvic plexus.

**Applied Anatomy.**—By means of the finger introduced into the rectum, the surgeon detects enlargement or other disease of the prostate; he can feel the apex of the gland, which is the guide to Cock's operation for stricture; he is enabled also by the same means to direct the point of a catheter, when its introduction is attended with difficulty either from injury or disease of the membranous or prostatic portions of the urethra. When the finger is introduced into the bowel the surgeon may, in some cases, especially in boys, learn the position, as well as the size, of a

calculus in the bladder; and in the operation for its removal, if, as is not infrequently the case, it should be lodged behind an enlarged prostate, it may be displaced from its position by pressing upward the fundus of the bladder from the rectum. The prostate is occasionally the seat of supuration, due to either gonorrhea or tuberculous disease. The gland is enveloped in a dense, unyielding capsule, which determines the course of the abscess, and also explains the great pain which is present in the acute form of the disease. The abscess most frequently bursts into the urethra, the direction in which there is least resistance, but may burst into the rectum, or more rarely in the perineum. In advanced life the prostate sometimes becomes considerably enlarged and projects into the bladder so as to impede the passage of the urine. According to Messer's researches, conducted at Greenwich Hospital, it would seem that such obstruction exists in 20 per cent. of all men over sixty years of age. In some cases the condition affects principally the lateral lobes, which may undergo considerable enlargement without causing much inconvenience. In other cases it would seem that the middle lobe enlarges most, and even a small enlargement of this lobe may act injuriously, by forming a sort of valve over the internal urethral orifice, preventing the passage of the urine; and the more the patient strains, the more completely will it block the opening into the urethra. In consequence of the enlargement of the prostate, a pouch is formed at the base of the bladder behind the projection, in which urine collects, and from which it cannot be entirely expelled. For this condition *prostatectomy* is sometimes done. The bladder is opened by an incision above the symphysis pubis, the mucous membrane of the post-prostatic pouch is scratched through, and the finger is then introduced into the space between the true capsule of the prostate and outer capsule formed by the fascia endopelvina. Separation in this plane is then carried out below and laterally until the apex of the gland is reached. The whole of the work is done with the finger, which is gradually swept around the sides until the anterior surface is reached and freed. The gland is then, by traction, displaced into the bladder and removed, usually carrying with it the greater portion of the mucous membrane of the prostatic urethra. Hemorrhage, which may be considerable at times, is checked by hot irrigations, and the bladder is temporarily drained. Very satisfactory results have followed this operation.

The prostate can be reached from the perineum, and in some cases the enlarged gland has been removed by this route, but the perineal approach is not usually employed except in the case of abscess of or about the gland.

#### **The Bulbourethral Glands (*Glandulae Bulbourethrales*; Cowper's Glands).**

The bulbourethral glands are two small, rounded, and somewhat lobulated bodies, of a yellow color, about the size of peas, placed behind and lateral to the membranous portion of the urethra, between the two layers of the fascia of the urogenital diaphragm. They lie close above the bulb, and are enclosed by the transverse fibres of the Sphincter urethrae membranaceae. Their existence is said to be constant: they gradually diminish in size as age advances.

The excretory duct of each gland, nearly 2.5 cm. long, passes obliquely forward beneath the mucous membrane, and opens by a minute orifice on the floor of the cavernous portion of the urethra about 2.5 cm. in front of the urogenital diaphragm.

**Structure.**—Each gland is made up of several lobules, held together by a fibrous investment. Each lobule consists of a number of acini, lined by columnar epithelial cells, opening into one duct, which joins with the ducts of other lobules outside the gland to form the single excretory duct.

#### **THE FEMALE GENITAL ORGANS (*ORGANA GENITALIA MULIEBRIA*).**

The female genital organs consist of an internal and an external group. The internal organs are situated within the pelvis, and consist of the ovaries, the uterine tubes, the uterus, and the vagina. The external organs are placed below the urogenital diaphragm and below and in front of the pubic arch. They comprise the mons pubis, the labia majora et minora pudendi, the clitoris, the bulbus vestibuli, and the greater vestibular glands.

#### **The Ovaries (*Ovaria*).**

The ovaries are homologous with the testes in the male. They are two nodular bodies, situated one on either side of the uterus in relation to the lateral wall of the pelvis, and attached to the back of the broad ligament of the uterus, behind



and below the uterine tubes (Fig. 1047). The ovaries are of a grayish-pink color, and present either a smooth or a puckered uneven surface. They are each about 4 cm. in length, 2 cm. in width, and about 8 mm. in thickness, and weigh from 2 to 3.5 gm. Each ovary presents a lateral and a medial surface, an upper or tubal and a lower or uterine extremity, and an anterior or mesovarium and a posterior free border. It lies in a shallow depression, named the **ovarian fossa**, on the lateral wall of the pelvis; this fossa is bounded above by the external iliac vessels, in front by the obliterated umbilical artery, and behind by the ureter. The exact position of the ovary has been the subject of considerable difference of opinion, and the description here given applies to the ovary of the nulliparous woman. The ovary becomes displaced during the first pregnancy, and probably never again returns to its original position. In the erect posture the long axis of the ovary is vertical. The *tubal extremity* is near the external iliac vein; to it is attached the ovarian fimbria of the uterine tube and a fold of peritoneum, the **suspensory ligament of the ovary**, which is directed upward over the iliac vessels and contains the ovarian




FIG. 1047.—Uterus and right broad ligament, seen from behind. The broad ligament has been spread out and the ovary drawn downward.

vessels. The *uterine end* is directed downward toward the pelvic floor, it is usually narrower than the tubal, and is attached to the lateral angle of the uterus, immediately behind the uterine tube, by a rounded cord termed the **ligament of the ovary**, which lies within the broad ligament and contains some non-striped muscular fibres. The *lateral surface* is in contact with the parietal peritoneum, which lines the ovarian fossa; the *medial surface* is to a large extent covered by the fimbriated extremity of the uterine tube. The *mesovarian border* is straight and is directed toward the obliterated umbilical artery, and is attached to the back of the broad ligament by a short fold named the **mesovarium**. Between the two layers of this fold the bloodvessels and nerves pass to reach the hilus of the ovary. The *free border* is convex, and is directed toward the ureter. The uterine tube arches over the ovary, running upward in relation to its mesovarian border, then curving over its tubal pole, and finally passing downward on its free border and medial surface.

**Epoöphoron** (*parovarium*; *organ of Rosenmüller*) (Figs. 1047, 1048).—The epoöphoron lies in the mesosalpinx between the ovary and the uterine tube, and consists of a few short tubules (**ductuli transversi**) which converge toward the ovary

while their opposite ends open into a rudimentary duct, the **ductus longitudinalis epoöphori** (*duct of Gärtner*).

**Paroöphoron.**—The paroöphoron consists of a few scattered rudimentary tubules, best seen in the child, situated in the broad ligament between the epoöphoron and the uterus.




FIG. 1048.—Adult ovary, epoöphoron, and uterine tube. (From Farre, after Kobelt.) *a, a.* Epoöphoron formed from the upper part of the Wolffian body. *b.* Remains of the uppermost tubes sometimes forming hydatids. *c.* Middle set of tubes. *d.* Some lower atrophied tubes. *e.* Atrophied remains of the Wolffian duct. *f.* The terminal bulb or hydatid. *h.* The uterine tube. *i.* Hydatid attached to the extremity. *l.* The ovary.

The ductuli transversi of the epoöphoron and the tubules of the paroöphoron are remnants of the tubules of the Wolffian body or mesonephros; the ductus longitudinalis epoöphori is a persistent portion of the Wolffian duct.

In the fetus, the ovaries are situated, like the testes, in the lumbar region, near the kidneys, but they gradually descend into the pelvis (page 187).

**Structure** (Fig. 1049).—The surface of the ovary is covered by a layer of columnar cells which constitutes the **germinal epithelium of Waldeyer**. This epithelium gives to the ovary a dull gray color as compared with the shining smoothness of the peritoneum; and the transition between the squamous epithelium of the peritoneum and the columnar cells which cover the ovary is usually marked by a line around the anterior border of the ovary. The ovary consists of a number of vesicular ovarian follicles imbedded in the meshes of a stroma or frame-work.

The **stroma** is a peculiar soft tissue, abundantly supplied with bloodvessels, consisting for the most part of spindle-shaped cells with a small amount of ordinary connective tissue. These cells have been regarded by some anatomists as unstriped muscle cells, which, indeed, they most resemble; by others as connective-tissue cells. On the surface of the organ this tissue is much condensed, and forms a layer (**tunica albuginea**) composed of short connective-tissue fibres, with fusiform cells between them. The stroma of the ovary may contain interstitial cells resembling those of the testis.

**Vesicular Ovarian Follicles** (*Graafian follicles*).—Upon making a section of an ovary, numerous round transparent vesicles of various sizes are to be seen; they are the follicles, or ovisacs containing the ova. Immediately beneath the superficial covering is a layer of stroma, in which are a large number of minute vesicles, of uniform size, about 0.25 mm. in diameter. These are the follicles in their earliest condition, and the layer where they are found has been termed the **cortical layer**. They are especially numerous in the ovary of the young child. After puberty, and during the whole of the child-bearing period, large and mature, or almost mature follicles are also found in the cortical layer in small numbers, and also “corpora lutea,” the remains of




FIG. 1049.—Section of the ovary. (After Schrön.) 1. Outer covering. 1'. Attached border. 2. Central stroma. 3. Peripheral stroma. 4. Bloodvessels. 5. Vesicular follicles in their earliest stage. 6, 7, 8. More advanced follicles. 9. An almost mature follicle. 9'. Follicle from which the ovum has escaped. 10. Corpus luteum.

follicles which have burst and are undergoing atrophy and absorption. Beneath this superficial stratum, other large and more or less mature follicles are found imbedded in the ovarian stroma. These increase in size as they recede from the surface toward a highly vascular stroma in the centre of the organ, termed the **medullary substance** (*zona vasculosa of Waldeyer*). This stroma forms the tissue of the hilus by which the ovary is attached, and through which the bloodvessels enter: it does not contain any follicles.

The larger follicles (Fig. 1050) consist of an external fibrovascular coat, connected with the surrounding stroma of the ovary by a net-work of bloodvessels; and an internal coat, which consists of several layers of nucleated cells, called the **membrana granulosa**.

At one part of the mature follicle the cells of the **membrana granulosa** are collected into a mass which projects into the cavity of the follicle. This is termed the **discus proligerus**, and in it the ovum is imbedded.<sup>1</sup> The follicle contains a transparent albuminous fluid.

The development and maturation of the follicles and ova continue uninterruptedly from puberty to the end of the fruitful period of woman's life, while their formation commences before birth. Before puberty the ovaries are small and the follicles contained in them are disposed in a comparatively thick layer in the cortical substance; here they present the appearance of a large number of minute closed vesicles, constituting the early condition of the follicles; many, however, never attain full develop-




FIG. 1050.—Section of vesicular ovarian follicle of cat.  $\times 50$ .

ment, but shrink and disappear. At puberty the ovaries enlarge and become more vascular, the follicles are developed in greater abundance, and their ova are capable of fecundation.

**Discharge of the Ovum.**—The follicles, after attaining a certain stage of development, gradually approach the surface of the ovary and burst; the ovum and fluid contents of the follicle are liberated on the exterior of the ovary, and carried into the uterine tube by currents set up by the movements of the cilia covering the mucous membrane of the fimbriae.

**Corpus Luteum.**—After the discharge of the ovum the lining of the follicle is thrown into folds, and vascular processes grow inward from the surrounding tissue. In this way the space is filled up and the corpus luteum formed. It consists at first of a radial arrangement of yellow cells with bloodvessels and lymphatic spaces, and later it merges with the surrounding stroma.

**Vessels and Nerves.**—The **arteries** of the ovaries and uterine tubes are the ovarian from the aorta. Each anastomoses freely in the mesosalpinx, with the uterine artery, gives some branches to the uterine tube, and others which traverse the mesovarium and enter the hilus of the ovary. The **veins** emerge from the hilus in the form of a plexus, the **pampiniform plexus**; the ovarian vein is formed from this plexus, and leaves the pelvis in company with the artery. The **nerves** are derived from the hypogastric or pelvic plexus, and from the ovarian plexus, the uterine tube receiving a branch from one of the uterine nerves.

**Applied Anatomy.**—The inflammations which affect the ovary are merely an extension of those from the tube. Ovarian new formations are of common occurrence, and are either solid or cystic; the former being the less common. The *ovarian cysts* in the majority of cases are cystadenomata which may assume enormous dimensions; in rarer instances they form from the tubules at the hilus of the ovary or those of the organ of Rosenmüller; in other instances a clear watery cyst forms between the layers of the broad ligament. An ovarian cyst, once diagnosed, should always be removed, as it is liable to become affected by suppuration, torsion of its pedicle, or other serious complications. The operation for its removal, badly termed *ovariotomy*, consists in opening the abdomen, and reducing the size of the cyst when large by tapping it before its withdrawal from the abdomen; the pedicle is then clamped with a large forceps, and the cyst is cut free. This pedicle must then be transfixed and securely ligatured by an interlocking ligature, which will not slip off. The pedicle consists of an elongated part of the broad ligament, including the uterine tube and ovarian artery, and a great number of large veins. Ovariectomy for a simple uncomplicated cyst presents no special difficulties, but, in cases where there are old adhesions implicating the small intestines, it may present very great difficulties.

<sup>1</sup> For a description of the ovum, see page 77.



**The Uterine Tube (Tuba Uterina [Fallopian]; Fallopian Tube; Oviduct).**  
(Figs. 1047, 1051).

The **uterine tubes** convey the ova from the ovaries to the cavity of the uterus. They are two in number, one on either side, situated in the upper margin of the broad ligament, and extending from the superior angle of the uterus to the side of the pelvis. Each tube is about 10 cm. long, and is described as consisting of three portions: (1) the **isthmus**, or medial constricted third; (2) the **ampulla**, or intermediate dilated portion, which curves over the ovary; and (3) the **infundibulum**, with its **abdominal ostium**, surrounded by **fimbriæ**, one of which, the **ovarian fimbria**,




FIG. 1051.—Female pelvis and its contents, seen from above and in front.

is attached to the ovary. The uterine tube is directed lateralward as far as the uterine pole of the ovary, and then ascends along the mesovarian border of the ovary to the tubal pole, over which it arches; finally it turns downward and ends in relation to the free border and medial surface of the ovary. The uterine opening is minute, and will only admit a fine bristle; the abdominal opening is somewhat larger. In connection with the fimbriæ of the uterine tube, or with the broad ligament close to them, there are frequently one or more small pedunculated vesicles. These are termed the **appendices vesiculosæ** (*hydatids of Morgagni*).

**Structure.**—The uterine tube consists of three coats: **serous**, **muscular**, and **mucous**. The **external or serous coat** is peritoneal. The **middle or muscular coat** consists of an external longitudinal and an internal circular layer of non-striped muscular fibres continuous with those of the uterus. The **internal or mucous coat** is continuous with the mucous lining of the uterus, and, at the abdominal ostium of the tube, with the peritoneum. It is thrown into longitudinal folds, which in the ampulla are much more extensive than in the isthmus. The lining epithelium is columnar and ciliated. This form of epithelium is also found on the inner surface of the fimbriæ. While on the outer or serous surfaces of these processes the epithelium gradually merges into the endothelium of the peritoneum.

**Applied Anatomy.**—The majority of the diseases of the uterine tube are due to infection which have spread by way of the vagina and uterus, and the disease often does not stop at the uterine tube, but passes on to the peritoneum, giving rise to acute general peritonitis, or a localized condition termed *perimetritis* that may be acute or chronic. Perimetritis is often followed by various painful conditions, which are due to the peritoneal adhesions resulting from the

inflammation of the serous membrane, and which persist throughout life. Tubal inflammation (*salpingitis*) is usually the result of an infection either by the gonococcus or by septic organisms implanted at the time of labor or abortion. In many cases the fimbriated ends of the tubes become closed by adhesions, pus collects in the tubes, and a *pyosalpinx* results.

Fertilization of the ovum is believed (page 82) to occur in the tube, and the fertilized ovum is then normally passed on into the uterus; the ovum, however, may adhere to an undergo development in the uterine tube, giving rise to the commonest variety of *ectopic gestation*. In such cases the amnion and chorion are formed, but a true decidua is never present; and the gestation usually ends by extrusion of the ovum through the abdominal ostium, although it is not uncommon for the tube to rupture into the peritoneal cavity, this being accompanied by severe hemorrhage, and needing surgical interference.

### The Uterus (Womb) (Figs. 1047, 1051, 1052).

The **uterus** is a hollow, thick-walled, muscular organ situated deeply in the pelvic cavity between the bladder and rectum. Into its upper part the uterine tubes open, one on either side, while below, its cavity communicates with that of




FIG. 1052.—Median sagittal section of female pelvis.

the vagina. When the ova are discharged from the ovaries they are carried to the uterine cavity through the uterine tubes. If an ovum be fertilized it imbeds itself in the uterine wall and is normally retained in the uterus until prenatal development is completed, the uterus undergoing changes in size and structure to accommodate itself to the needs of the growing embryo (see page 98). After parturition the uterus returns almost to its former condition, but certain traces of its enlargement remains. It is necessary, therefore, to describe as the type-form the adult virgin uterus, and then to consider the modifications which are effected as a result of pregnancy.



*In the virgin state* the uterus is flattened antero-posteriorly and is pyriform in shape, with the apex directed downward and backward. It lies between the bladder in front and the pelvic or sigmoid colon and rectum behind, and is completely within the pelvis, so that its base is below the level of the superior pelvic aperture. Its upper part is suspended by the broad and the round ligaments, while its lower portion is imbedded in the fibrous tissue of the pelvis.

The long axis of the uterus usually lies approximately in the axis of the superior pelvic aperture, but as the organ is freely movable its position varies with the state of distension of the bladder and rectum. Except when much displaced by a fully distended bladder, it forms a forward angle with the vagina, since the axis of the vagina corresponds to the axes of the cavity and inferior aperture of the pelvis.

The uterus measures about 7.5 cm. in length, 5 cm. in breadth, at its upper part, and nearly 2.5 cm. in thickness; it weighs from 30 to 40 gm. It is divisible into two portions. On the surface, about midway between the apex and base, is a slight constriction, known as the **isthmus**, and corresponding to this in the interior is a narrowing of the uterine cavity, the **internal orifice** of the uterus. The portion above the isthmus is termed the **body**, and that below, the **cervix**. The part of the body which lies above a plane passing through the points of entrance of the uterine tubes is known as the **fundus**.

**Body** (*corpus uteri*).—The body gradually narrows from the fundus to the isthmus.

The **vesical** or **anterior surface** (*facies vesicalis*) is flattened and covered by peritoneum, which is reflected on to the bladder to form the vesicouterine excavation. The surface lies in apposition with the bladder.

The **intestinal** or **posterior surface** (*facies intestinalis*) is convex transversely and is covered by peritoneum, which is continued down on to the cervix and vagina. It is in relation with the sigmoid colon, from which it is usually separated by some coils of small intestine.

The **fundus** (*fundus uteri*) is convex in all directions, and covered by peritoneum continuous with that on the vesical and intestinal surfaces. On it rest some coils of small intestine, and occasionally the distended sigmoid colon.

The **lateral margins** (*margo lateralis*) are slightly convex. At the upper end of each the uterine tube pierces the uterine wall. Below and in front of this point the round ligament of the uterus is fixed, while behind it is the attachment of the ligament of the ovary. These three structures lie within a fold of peritoneum which is reflected from the margin of the uterus to the wall of the pelvis, and is named the **broad ligament**.

**Cervix** (*cervix uteri*; *neck*).—The cervix is the lower constricted segment of the uterus. It is somewhat conical in shape, with its truncated apex directed downward and backward, but is slightly wider in the middle than either above or below. Owing to its relationships, it is less freely movable than the body, so that the latter may bend on it. The long axis of the cervix is therefore seldom in the same straight line as the long axis of the body. The long axis of the uterus as a whole presents the form of a curved line with its concavity forward, or in extreme cases may present an angular bend at the region of the isthmus.

The cervix projects through the anterior wall of the vagina, which divides it into an upper, supravaginal portion, and a lower, vaginal portion.

The **supravaginal portion** (*portio supravaginalis [cervicis]*) is separated in front from the bladder by fibrous tissue (**parametrium**), which extends also on to its sides and lateralward between the layers of the broad ligaments. The uterine arteries reach the margins of the cervix in this fibrous tissue, while on either side the ureter runs downward and forward in it at a distance of about 2 cm. from the cervix. *Posteriorly*, the supravaginal cervix is covered by peritoneum, which is prolonged

below on to the posterior vaginal wall, when it is reflected on to the rectum, forming the rectouterine excavation. It is in relation with the rectum, from which it may be separated by coils of small intestine.

The **vaginal portion** (*portio vaginalis [cervicis]*) of the cervix projects free into the anterior wall of the vagina between the anterior and posterior fornices. On its rounded extremity is a small, depressed, somewhat circular aperture, the **external orifice of the uterus**, through which the cavity of the cervix communicates with that of the vagina. The external orifice is bounded by two lips, an anterior and a posterior, of which the anterior is the shorter and thicker, although, on account of the slope of the cervix, it projects lower than the posterior. Normally, both lips are in contact with the posterior vaginal wall.

**Interior of the Uterus** (Fig. 1053).—The cavity of the uterus is small in comparison with the size of the organ.

The **Cavity of the Body** (*cavum uteri*) is a mere slit, flattened antero-posteriorly. It is triangular in shape, the base being formed by the internal surface of the fundus between the orifices of the uterine tubes, the apex by the internal orifice of the uterus through which the cavity of the body communicates with the canal of the cervix.




FIG. 1053.—Posterior half of uterus and upper part of vagina.

The **Canal of the Cervix** (*canalis cervicis uteri*) is somewhat fusiform, flattened from before backward, and broader at the middle than at either extremity. It communicates above through the internal orifice with the cavity of the body, and below through the external orifice with the vaginal cavity. The wall of the canal presents an anterior and a posterior longitudinal ridge, from each of which proceed a number of small oblique columns, the **palmate folds**, giving the appearance of branches from the stem of a tree; to this arrangement the name **arbor vitae uterina** is applied. The folds on the two

walls are not exactly opposed, but fit between one another so as to close the cervical canal.

The total length of the uterine cavity from the external orifice to the fundus is about 6.25 cm.

**Ligaments.**—The ligaments of the uterus are eight in number: one **anterior**; one **posterior**; two **lateral** or broad; two **uterosacral**; and two **round ligaments**.

The **anterior ligament** consists of the vesicouterine fold of peritoneum, which is reflected on to the bladder from the front of the uterus, at the junction of the cervix and body.

The **posterior ligament** consists of the rectovaginal fold of peritoneum, which is reflected from the back of the posterior fornix of the vagina on to the front of the rectum. It forms the bottom of a deep pouch called the **rectouterine excavation**, which is bounded in front by the posterior wall of the uterus, the supravaginal cervix, and the posterior fornix of the vagina; behind, by the rectum; and laterally by two crescentic folds of peritoneum which pass backward from the cervix uteri on either side of the rectum to the posterior wall of the pelvis. These folds are named the **sacrogenital** or **rectouterine folds**. They contain a considerable amount of fibrous tissue and non-striped muscular fibres which are attached to the front of the sacrum and constitute the **uterosacral ligaments**.

The two **lateral** or **broad ligaments** (*ligamentum latum uteri*) pass from the sides of the uterus to the lateral walls of the pelvis. Together with the uterus they form

a septum across the female pelvis, dividing that cavity into two portions. In the anterior part is contained the bladder; in the posterior part the rectum, and in certain conditions some coils of the small intestine and a part of the sigmoid colon. Between the two layers of each broad ligament are contained: (1) the uterine tube superiorly; (2) the round ligament of the uterus; (3) the ovary and its ligament; (4) the epoöphoron and paroöphoron; (5) connective tissue; (6) unstriped muscular fibre; and (7) bloodvessels and nerves. The portion of the broad ligament which stretches from the uterine tube to the level of the ovary is known by the name of the **mesosalpinx**. Between the fimbriated extremity of the tube and the lower attachment of the broad ligament is a concave rounded margin, called the **infundibulopelvic ligament**.

The **round ligaments** (*ligamentum teres uteri*) are two flattened bands between 10 and 12 cm. in length, situated between the layers of the broad ligament in front of and below the uterine tubes. Commencing on either side at the lateral angle of the uterus, this ligament is directed forward, upward, and lateralward over the external iliac vessels. It then passes through the abdominal inguinal ring and along the inguinal canal to the labium majus, in which it becomes lost. The round ligaments consists principally of muscular tissue, prolonged from the uterus; also of some fibrous and areolar tissue, besides bloodvessels, lymphatics; and nerves, enclosed in a duplicature of peritoneum, which, in the fetus, is prolonged in the form of a tubular process for a short distance into the inguinal canal. This process is called the **canal of Nuck**. It is generally obliterated in the adult, but sometimes remains pervious even in advanced life. It is analogous to the saccus vaginalis, which precedes the descent of the testis.

In addition to the ligaments just described, there is a band named the **ligamentum transversalis colli** (Mackenrodt) on either side of the cervix uteri. It is attached to the side of the cervix uteri and to the vault and lateral fornix of the vagina, and is continuous externally with the fibrous tissue which surrounds the pelvic bloodvessels.

The form, size, and situation of the uterus vary at different periods of life and under different circumstances.




FIG. 1054.—Sagittal section through the pelvis of a newly born female child.

*In the fetus* the uterus is contained in the abdominal cavity, projecting beyond the superior aperture of the pelvis (Fig. 1054). The cervix is considerably larger than the body.

*At puberty* the uterus is pyriform in shape, and weighs from 14 to 17 gm. It has descended into the pelvis, the fundus being just below the level of the superior aperture of this cavity. The palmate folds are distinct, and extend to the upper part of the cavity of the organ.

The position of the uterus in the adult is liable to considerable variation, depending chiefly on the condition of the bladder and rectum. When the bladder is empty the entire uterus is directed forward, and is at the same time bent on itself at the junction of the body and cervix, so that the body lies upon the bladder. As the latter fills, the uterus gradually becomes more and more erect, until with a fully distended bladder the fundus may be directed backward toward the sacrum.

During menstruation the organ is enlarged, more vascular, and its surfaces rounder; the external orifice is rounded, its labia swollen, and the lining membrane of the body thickened, softer, and of a darker color. According to Sir J. Williams, at each recurrence of menstruation, a molecular disintegration of the mucous membrane takes place, which leads to its complete removal, only the bases of the glands imbedded in the muscle being left. At the cessation of menstruation, a fresh mucous membrane is formed by a proliferation of the remaining structures.

During pregnancy the uterus becomes enormously enlarged, and in the eighth month reaches the epigastric region. The increase in size is partly due to growth of preëxisting muscle, and partly to development of new fibres.

After parturition the uterus nearly regains its usual size, weighing about 42 gm.; but its cavity is larger than in the virgin state, its vessels are tortuous, and its muscular layers are more defined; the external orifice is more marked, and its edges present one or more fissures.

In old age the uterus becomes atrophied, and paler and denser in texture; a more distinct constriction separates the body and cervix. The internal orifice is frequently, and the external orifice occasionally, obliterated, while the lips almost entirely disappear.

**Structure.**—The uterus is composed of three coats: an **external** or **serous**, a **middle** or **muscular**, and an **internal** or **mucous**.

The **serous coat** (*tunica serosa*) is derived from the peritoneum; it invests the fundus and the whole of the intestinal surface of the uterus; but covers the vesical surface only as far as the junction of the body and cervix. In the lower fourth of the intestinal surface the peritoneum, though covering the uterus, is not closely connected with it, being separated from it by a layer of loose cellular tissue and some large veins.

The **muscular coat** (*tunica muscularis*) forms the chief bulk of the substance of the uterus. In the virgin it is dense, firm, of a grayish color, and cuts almost like cartilage. It is thick opposite the middle of the body and fundus, and thin at the orifices of the uterine tubes. It consists of bundles of unstriated muscular fibres, disposed in layers, intermixed with areolar tissue, blood-vessels, lymphatic vessels, and nerves. The layers are three in number: external, middle, and internal. The external and middle layers constitute the muscular coat proper, while the inner layer is a greatly hypertrophied muscularis mucosae. During pregnancy the muscular tissue becomes more prominently developed, the fibres being greatly enlarged.

The external layer, placed beneath the peritoneum, is disposed as a thin plane on the vesical and intestinal surfaces. It consists of fibres which pass transversely across the fundus, and, converging at each lateral angle of the uterus, are continued on to the uterine tube, the round ligament, and the ligament of the ovary: some passing at each side into the broad ligament, and others running backward from the cervix into the sacrouterine ligaments. The middle layer of fibres presents no regularity in its arrangement, being disposed longitudinally, obliquely, and transversely. It contains most bloodvessels. The internal or deep layer consists of circular fibres arranged in the form of two hollow cones, the apices of which surround the orifices of the uterine tubes, their bases intermingling with one another on the middle of the body of the uterus. At the internal orifice these circular fibres form a distinct sphincter.

The **mucous membrane** (*tunica mucosa*) (Fig. 1055) is smooth, and closely adherent to the subjacent tissue. It is continuous through the fimbriated extremity of the uterine tubes, with the peritoneum; and, through the external uterine orifice, with the lining of the vagina.

In the body of the uterus the mucous membrane is smooth, soft, of a pale red color, lined by columnar ciliated epithelium, and presents, when viewed with a lens, the orifices of numerous tubular follicles, arranged perpendicularly to the surface. The structure of the corium differs from that of ordinary mucous membranes, and consists of an embryonic nucleated and highly cellular form of connective tissue in which run numerous large lymphatics. In it are the tube-like **uterine glands**, lined by ciliated columnar epithelium. They are of small size in the unimpregnated uterus, but shortly after impregnation become enlarged and elongated, presenting a contorted or waved appearance (see page 98).

In the cervix the mucous membrane is sharply differentiated from that of the uterine cavity. It is thrown into numerous oblique ridges, which diverge from an anterior and posterior longitudinal raphé. In the upper two-thirds of the canal, the mucous membrane is provided with numerous deep glandular follicles, which secrete a clear viscid alkaline mucus; and, in addition, extending through the whole length of the canal is a variable number of little cysts, presumably follicles which have become occluded and distended with retained secretion. They are called the **ovula Nabothi**. The mucous membrane covering the lower half of the cervical canal presents numerous papillæ. The epithelium of the upper two-thirds is cylindrical and ciliated, but below

this it loses its cilia, and gradually changes to stratified squamous epithelium close to the external orifice. On the vaginal surface of the cervix the epithelium is similar to that lining the vagina, viz., stratified squamous.




FIG. 1055.—Vertical section of mucous membrane of human uterus. (Sobotta.)

**Vessels and Nerves.**—The arteries of the uterus are the uterine, from the hypogastric; and the ovarian, from the abdominal aorta (Fig. 1056). They are remarkable for their tortuous




FIG. 1056.—The arteries of the internal organs of generation of the female, seen from behind. (After Hyrtl.)

course in the substance of the organ, and for their frequent anastomoses. The termination of the ovarian artery meets that of the uterine artery, and forms an anastomotic trunk from which branches are given off to supply the uterus, their disposition being circular. The veins are of



large size, and correspond with the arteries. They end in the uterine plexuses. In the impregnated uterus the arteries carry the blood to, and the veins convey it away from, the intervillous space of the placenta (see page 100). The **lymphatics** are described on page 795. The **nerves** are derived from the hypogastric and ovarian plexuses, and from the third and fourth sacral nerves.

**Applied Anatomy.**—A certain amount of anteversion and retroversion of the uterus can take place without the condition being regarded as pathological, but when the degree of flexion becomes considerable it must be regarded as a morbid condition. This is especially true of retroversion and retroflexion. The former is a falling back of the whole uterus, so that the cervix points upward toward the pubes, and the latter is a bending backward of the body, the cervix remaining in its normal position. The two conditions are usually combined. Prolapse of the uterus is another common infirmity. The organ sinks to an abnormally low level in the pelvis, and sometimes protrudes beyond the vulva. This is due to the supporting mechanism of the uterus being insufficient to sustain the strain thrown upon it.

The uterus may require removal in cases of malignant disease or for fibroid tumors. Carcinoma is the most common form of malignant disease of the uterus, though cases of sarcoma do occur. It may show itself either as a columnar carcinoma or as a squamous carcinoma; the former commencing either in the cervix or body of the uterus, the latter always commencing in the epithelial cells of the mucous covering of the vaginal surface of the cervix. Cancer of the body or of the cervix may be treated in the early stage, before fixation has taken place, by removal of the uterus, either through the vagina or by means of abdominal section, but if the body be much enlarged the former operation is impossible. Vaginal hysterectomy is performed by placing the patient in the lithotomy position and introducing a large duck-bill speculum. The cervix is then seized with a volsellum and pulled down as far as possible, and the mucous membrane of the vagina incised around the cervix and as near to it as the disease will allow, especially in front, where the ureters are in danger of being wounded. The rectouterine excavation is then opened sufficiently to allow of the introduction of the two forefingers, by means of which the opening is dilated laterally as far as the sacro-uterine ligaments. A somewhat similar proceeding is adopted in front, but here the bladder has to be separated from the wall of the uterus for about 2.5 cm. before the vesicouterine fold of peritoneum can be reached. This is done by carefully burrowing upward with a director and stripping the tissues off the uterine wall. When the vesicouterine pouch has been opened and the aperture dilated laterally, the uterus remains attached only by the broad ligaments, in which are contained the vessels that supply the uterus. Before division of the ligaments, these vessels have to be dealt with. The forefinger of the left hand is introduced into the rectouterine excavation, and an aneurism needle, armed with a long silk ligature, is inserted into the vesicouterine pouch, and is pushed through the broad ligament about 2.5 cm. above its lower level and at some distance from the uterus. One end of the ligature is now pulled through the anterior opening, and in this way we have the lowest 2.5 cm. of the broad ligament, in which is contained the uterine artery (Fig. 1056), enclosed in a ligature. This is tied tightly, and the operation is repeated on the other side. The broad ligament is then divided on either side, between the ligature and the uterus, to the extent to which it has been constricted. By traction on the volsellum which grasps the cervix, the uterus can be pulled considerably further down in the vagina, and a second 2.5 cm. of the broad ligament is treated in a similar way. This second ligature will embrace the pampiniform plexus of veins, and, when the broad ligament has been divided on either side, it will be found that a third ligature can be made to pass over the uterine tube and top of the broad ligament, after the uterus has been dragged down as far as possible. After the third ligature has been tied and the structures between it and the uterus divided, this organ will be freed from all its connections and can be removed from the vagina. The third ligature will contain the ovarian artery, between the ovary and the uterus, as it lies below the uterine tube. The vagina is then sponged out and lightly dressed with gauze; no sutures being used.

In the treatment of uterine fibroids which require operative interference, removal of the whole of the uterus, together with the tumors, through an abdominal incision gives the most satisfactory results; for, if the tumor is large, its size acts as a barrier to its safe delivery through the pelvis and genital passages. After the abdomen has been opened the uterine vessels are secured and the broad ligaments divided in a manner similar to that employed in vaginal hysterectomy, except that the proceeding is commenced from above. When the first two ligatures have been tied, and the broad ligament divided, it will be found that the uterus can be raised out of the pelvis. A transverse incision is now made through the peritoneum, where it is reflected from the front of the uterus on to the back of the bladder, and the serous membrane peeled from the surface of the uterus until the vagina is reached. The anterior wall of this canal is then cut across. The uterus is now turned forward and the peritoneum at the bottom of the rectouterine excavation incised transversely, and the posterior wall of the vagina cut across, until it meets the incision on the anterior wall. The uterus is now almost free, and is held only by the lower part of the broad ligament on either side, containing the uterine artery. A third ligature is made to encircle this as close to the uterus as possible, the position of the ureter

being always kept in mind, and, after having been tied, the structures are divided between the ligature and the uterus. The organ can now be removed. The vagina is plugged with gauze, and the external wound closed in the usual way. The vagina acts as a drain, and therefore the opening into it is not sutured.

Inflammation of the cellular tissue surrounding the cervix occasionally takes place. Laceration of the cervix by instruments or by the fetal head frequently occurs, opening up the cellular planes and so exposing them to any infection that may be present. An inflammatory mass forms in the cellular tissue between the layers of the broad ligament or of the uterosacral ligaments, and the condition is termed *pelvic cellulitis* or *parametritis*. This condition is usually confined to one side of the pelvis, forming a large inflammatory mass which pushes the uterus over to the opposite side. It does not always remain localized, however, but may spread widely, surrounding the rectum or the neck of the bladder, or mounting into the iliac fossa, or even to the perinephric cellular tissue. The condition may resolve or an abscess may form. In the former condition the cicatrization of the inflammatory products often produces displacements of the uterus toward the affected side of the pelvis, or stricture of the rectum when that viscus has been surrounded by the process. When suppuration ensues, the pus may burst into the bladder, vagina, or rectum, or it may present above the inguinal ligament, or it may mount to the anterior abdominal wall in front of the bladder or to the posterior abdominal wall between the iliac crest and last rib. The abscess may, moreover, make its way into the buttock by passing out of the pelvis through the greater sciatic foramen, or it may pass down between the fibres of the Levator ani and appear as a secondary ischiorectal abscess.

### The Vagina (Fig. 1052).

The **vagina** extends from the vestibule to the uterus, and is situated behind the bladder and in front of the rectum; it is directed upward and backward, its axis forming with that of the uterus an angle of over  $90^\circ$ , opening forward. Its walls are ordinarily in contact, and the usual shape of its lower part on transverse section is that of an H, the transverse limb being slightly curved forward or backward, while the lateral limbs are somewhat convex toward the median line; its middle part has the appearance of a transverse slit. Its length is 6 to 7.5 cm. along its anterior wall, and 9 cm. along its posterior wall. It is constricted at its commencement, dilated in the middle, and narrowed near its uterine extremity; it surrounds the vaginal portion of the cervix uteri, a short distance from the external orifice of the uterus, its attachment extending higher up on the posterior than on the anterior wall of the uterus. To the recess behind the cervix the term **posterior fornix** is applied, while the smaller recesses in front and at the sides are called the **anterior** and **lateral fornices**.

**Relations.**—The **anterior surface** of the vagina is in relation with the fundus of the bladder, and with the urethra. Its **posterior surface** is separated from the rectum by the rectouterine excavation in its upper fourth, and by the rectovesical fascia in its middle two-fourths; the lower fourth is separated from the anal canal by the perineal body. Its sides are enclosed between the Levatores ani muscles. As the terminal portions of the ureters pass forward and medialward to reach the fundus of the bladder, they run close to the lateral fornices of the vagina, and as they enter the bladder are slightly in front of the anterior fornix.

**Structure.**—The vagina consists of an **internal mucous lining** and a **muscular coat** separated by a layer of erectile tissue.

The **mucous membrane** (*tunica mucosa*) is continuous above with that lining the uterus. Its inner surface presents two longitudinal ridges, one on its anterior and one on its posterior wall. These ridges are called the **columns of the vagina** and from them numerous transverse ridges or rugæ extend outward on either side. These rugæ are divided by furrows of variable depth, giving to the mucous membrane the appearance of being studded over with conical projections or papillæ; they are most numerous near the orifice of the vagina, especially before parturition. The epithelium covering the mucous membrane is of the stratified squamous variety. The submucous tissue is very loose, and contains numerous large veins which by their anastomoses form a plexus, together with smooth muscular fibres derived from the muscular coat; it is regarded by Gussenbauer as an erectile tissue. It contains a number of mucous crypts, but no true glands.

The **muscular coat** (*tunica muscularis*) consists of two layers: an external longitudinal, which is by far the stronger, and an internal circular layer. The longitudinal fibres are continuous with the superficial muscular fibres of the uterus. The strongest fasciculi are those attached to the rectovesical fascia on either side. The two layers are not distinctly separable from each other, but are connected by oblique decussating fasciculi, which pass from the one layer to the

other. In addition to this, the vagina at its lower end is surrounded by a band of striped muscular fibres, the **Bulbocavernosus** (see page 520).

External to the muscular coat is a layer of connective tissue, containing a large plexus of bloodvessels.

The **erectile tissue** consists of a layer of loose connective tissue, situated between the mucous membrane and the muscular coat; imbedded in it is a plexus of large veins, and numerous bundles of unstriped muscular fibres, derived from the circular muscular layer. The arrangement of the veins is similar to that found in other erectile tissues.

### The External Genital Organs (*Partes Genitales Externae Muliebres*) (Fig. 1057).

The **external genital organs** of the female are: the **mons pubis**, the **labia majora et minora pedundi**, the **clitoris**, the **vestibule of the vagina**, the **bulb of the vestibule**, and the **greater vestibular glands**. The term **pudendum** or **vulva**, as generally applied, includes all these parts.




FIG. 1057.—External genital organs of female. The labia minora have been drawn apart.

The **Mons Pubis** (*commissura labiorum anterior; mons Veneris*), the rounded eminence in front of the pubic symphysis, is formed by a collection of fatty tissue beneath the integument. It becomes covered with hair at the time of puberty.

The **Labia Majora** (*labia majora pudendi*) are two prominent longitudinal cutaneous folds which extend downward and backward from the mons pubis and form the lateral boundaries of a fissure or cleft, the **pudendal cleft** or **rima**, into which the vagina and urethra open. Each labium has two surfaces, an outer, pigmented and covered with strong, crisp hairs; and an inner, smooth and beset with large sebaceous follicles. Between the two there is a considerable quantity of areolar tissue, fat, and a tissue resembling the dartos tunic of the scrotum, besides vessels,

nerves, and glands. The labia are thicker in front, where they form by their meeting the **anterior labial commissure**. Posteriorly they are not really joined, but appear to become lost in the neighboring integument, ending close to, and nearly parallel with, each other. Together with the connecting skin between them, they form the **posterior labial commissure** or posterior boundary of the pudendum. The interval between the posterior commissure and the anus, from 2.5 to 3 cm. in length, constitutes the **perineum**. The labia majora correspond to the scrotum in the male.

The **Labia Minora** (*labia minora pudendi; nymphæ*) are two small cutaneous folds, situated between the labia majora, and extending from the clitoris obliquely downward, lateralward, and backward for about 4 cm. on either side of the orifice of the vagina, between which and the labia majora they end; in the virgin the posterior ends of the labia minora are usually joined across the middle line by a fold of skin, named the **frenulum of the labia** or **fourchette**. Anteriorly, each labium minus divides into two portions: the upper division passes above the clitoris to meet its fellow of the opposite side, forming a fold which overhangs the glans clitoridis, and is named the **preputium clitoridis**; the lower division passes beneath the clitoris and becomes united to its under surface, forming, with its fellow of the opposite side, the **frenulum of the clitoris**. On the opposed surfaces of the labia minora are numerous sebaceous follicles.

The **Clitoris** is an erectile structure, homologous with the penis. It is situated beneath the anterior labial commissure, partially hidden between the anterior ends of the labia minora. It consists of two corpora cavernosa, composed of erectile tissue enclosed in a dense layer of fibrous membrane, united together along their medial surfaces by an incomplete fibrous pectiniform septum; each corpus is connected to the rami of the pubis and ischium by a crus; the **free extremity** (*glans clitoridis*) is a small rounded tubercle, consisting of spongy erectile tissue, and highly sensitive. The clitoris is provided like the penis, with a suspensory ligament, and with two small muscles, the Ischiocavernosi, which are inserted into the crura of the clitoris.

The **Vestibule** (*vestibulum vaginae*).—The cleft between the labia minora and behind the glans clitoridis is named the **vestibule of the vagina**: in it are seen the urethral and vaginal orifices and the openings of the ducts of the greater vestibular glands.

The **external urethral orifice** (*orificium urethrae externum; urinary meatus*) is placed about 2.5 cm. behind the glans clitoridis and immediately in front of that of the vagina; it usually assumes the form of a short, sagittal cleft with slightly raised margins.

The **vaginal orifice** is a median slit below and behind the opening of the urethra; its size varies inversely with that of the **hymen**.

The **hymen** is a thin fold of mucous membrane situated at the orifice of the vagina; the inner surfaces of the fold are normally in contact with each other, and the vaginal orifice appears as a cleft between them. The hymen varies much in shape. When stretched, its commonest form is that of a ring, generally broadest posteriorly; sometimes it is represented by a semilunar fold, with its concave margin turned toward the pubes. Occasionally it is cribriform, or its free margin forms a membranous fringe. It may be entirely absent, or may form a complete septum across the lower end of the vagina; the latter condition is known as an **imperforate hymen**. It may persist after copulation, so that it cannot be considered as a test of virginity. When the hymen has been ruptured, small rounded elevations known as the **carunculæ hymeneales** are found as its remains. Between the hymen and the frenulum of the labia is a shallow depression, named the **navicular fossa**.

The **Bulb of the Vestibule** (*bulbus vestibuli; vaginal bulb*) is the homologue of the bulb and adjoining part of the corpus cavernosum urethrae of the male, and

consists of two elongated masses of erectile tissue, placed one on either side of the vaginal orifice and united to each other in front by a narrow median band termed the **pars intermedia**. Each lateral mass measures a little over 2.5 cm. in length. Their posterior ends are expanded and are in contact with the greater vestibular glands; their anterior ends are tapered and joined to one another by the **pars intermedia**; their deep surfaces are in contact with the inferior fascia of the urogenital diaphragm; superficially they are covered by the **Bulbocavernosus**.

The **Greater Vestibular Glands** (*glandula vestibularis major* [*Bartholini*]; *Bartholin's glands*) are the homologues of the bulbo-urethral glands in the male. They consist of two small, roundish bodies of a reddish-yellow color, situated one on either side of the vaginal orifice in contact with the posterior end of each lateral mass of the bulb of the vestibule. Each gland opens by means of a duct, about 2 cm. long, immediately lateral to the hymen, in the groove between it and the labium minus.

### **The Mammae (Mammary Gland; Breasts).**

The **mammae** secrete the milk, and are accessory glands of the generative system. They exist in the male as well as in the female; but in the former only in the rudimentary state, unless their growth is excited by peculiar circumstances. In the female they are two large hemispherical eminences lying within the superficial fascia and situated on the front and sides of the chest; each extends from the second rib above to the sixth rib below, and from the side of the sternum to near the mid-axillary line. Their weight and dimensions differ at different periods of life, and in different individuals. Before puberty they are of small size, but enlarge as the generative organs become more completely developed. They increase during pregnancy and especially after delivery, and become atrophied in old age. The left mamma is generally a little larger than the right. The deep surface of each is nearly circular, flattened, or slightly concave, and has its long diameter directed upward and lateralward toward the axilla; it is separated from the fascia covering the *Pectoralis major*, *Serratus anterior*, and *Obliquus externus abdominis* by loose connective tissue. The subcutaneous surface of the mamma is convex, and presents, just below the centre, a small conical prominence, the **papilla**.

The **Mammary Papilla** or **Nipple** (*papilla mammae*) is a cylindrical or conical eminence situated about the level of the fourth intercostal space. It is capable of undergoing a sort of erection from mechanical excitement, a change mainly due to the contraction of its muscular fibres. It is of a pink or brownish hue, its surface wrinkled and provided with secondary papillæ; and it is perforated by from fifteen to twenty orifices, the apertures of the lactiferous ducts. The base of the mammary papilla is surrounded by an **areola**. In the virgin the areola is of a delicate rosy hue; about the second month after impregnation it enlarges and acquires a darker tinge, and as pregnancy advances it may assume a dark brown or even black color. This color diminishes as soon as lactation is over, but is never entirely lost throughout life. These changes in the color of the areola are of importance in forming a conclusion in a case of suspected first pregnancy. Near the base of the papilla, and upon the surface of the areola, are numerous large sebaceous glands, the **areolar glands**, which become much enlarged during lactation, and present the appearance of small tubercles beneath the skin. These glands secrete a peculiar fatty substance, which serves as a protection to the integument of the papilla during the act of sucking. The mammary papilla consists of numerous vessels, intermixed with plain muscular fibres, which are principally arranged in a circular manner around the base: some few fibres radiating from base to apex.

**Structure** (Figs. 1058, 1059).—The mamma consists of gland tissue; of fibrous tissue, connecting its lobes; and of fatty tissue in the intervals between the lobes. The gland tissue, when freed from fibrous tissue and fat, is of a pale reddish color, firm in texture, flattened from before



backward and thicker in the centre than at the circumference. The subcutaneous surface of the mamma presents numerous irregular processes which project toward the skin and are joined to it by bands of connective tissue. It consists of numerous lobes, and these are composed of lobules, connected together by areolar tissue, bloodvessels, and ducts. The smallest lobules consist of a cluster of rounded alveoli, which open into the smallest branches of the lactiferous ducts; these ducts unite to form larger ducts, and these end in a single canal, corresponding with




FIG. 1058.—Dissection of the lower half of the mamma during the period of lactation. (Luschka.)

one of the chief subdivisions of the gland. The number of excretory ducts varies from fifteen to twenty; they are termed the **tubuli lactiferi**. They converge toward the areola, beneath which they form dilatations or **ampullae**, which serve as reservoirs for the milk, and, at the base of the papillae, become contracted, and pursue a straight course to its summit, perforating it by separate orifices considerably narrower than the ducts themselves. The ducts are composed of areolar tissue containing longitudinal and transverse elastic fibres; muscular fibres are entirely absent; they are lined by columnar epithelium resting on a basement-membrane. The epithelium of the mamma differs according to the state of activity of the organ. In the gland of a woman who is not pregnant or suckling, the alveoli are very small and solid, being filled with a mass of granular polyhedral cells. During pregnancy the alveoli enlarge, and the cells undergo rapid multiplication. At the commencement of lactation, the cells in the centre of the alveolus undergo fatty degeneration, and are eliminated in the first milk, as **colostrum corpuscles**. The peripheral cells of the alveolus remain, and form a single layer of granular, short columnar cells, with spherical nuclei, lining the basement membrane. The cells, during the state of activity of the gland, are capable of forming, in their interior, oil globules, which are then ejected into the lumen of the alveolus, and constitute the milk globules. When the acini are distended by the accumulation of the secretion the lining epithelium becomes flattened.




FIG. 1059.—Section of portion of mamma.

The **fibrous tissue** invests the entire surface of the mamma, and sends down septa between its lobes, connecting them together.

The **fatty tissue** covers the surface of the gland, and occupies the interval between its lobes. It usually exists in considerable abundance, and determines the form and size of the gland. There is no fat immediately beneath the areola and papilla.

**Vessels and Nerves.**—The arteries supplying the mammae are derived from the thoracic branches of the axillary, the intercostals, and the internal mammary. The veins describe an anastomotic circle around the base of the papilla, called by Haller the *circulus venosus*. From this, large branches transmit the blood to the circumference of the gland, and end in the axillary and internal mammary veins. The lymphatics are described on page 797. The nerves are derived from the anterior and lateral cutaneous branches of the fourth, fifth, and sixth thoracic nerves.

**Applied Anatomy.**—The ducts descending from the mammary papilla radiate through the gland, and when an incision is made into the breast the scalpel should be directed radially, from the centre to the periphery, so that it may not pass across the ducts. A milk duct may become obstructed and distended, forming a tumor known as a *galactoceles*. Abscess frequently occurs about the mamma, and most often in women who are lactating, especially those who have cracks or fissures about the papilla. The abscess may lie between the septa, in the gland tissue itself; or it may lie beneath the skin by the side of the papilla and superficial to the mamma or it may form beneath it, between the mamma and the deep fascia. Free incision, radiating from the papilla, is required in such cases.

Cystic formation of many different kinds is commonly seen in the mamma; in some cases it is due to dilatation of the larger ducts or of the lymph spaces throughout the gland; in others the cysts occur in new growths of the mamma, or as the result of obstruction of the smaller ducts by chronic inflammatory processes.

Malignant growths are seen more often in the mamma than in any other organ; they are of great variety, but the commonest is the spheroidal-celled cancer, the cells of which are intermingled with a varying amount of fibrous tissue. A hard contracting tumor mass results, which drags on the fibrous septa between the lobes so that fixation or retraction of the papilla ensues, and sooner or later the malignant infiltration invades the surrounding gland tissues, the skin, the deep fascia and Pectorales, and even the chest wall and pleura. The lymph glands beneath the Pectorales and those situated toward the apex of the axilla become early involved with secondary malignant deposit, and later the supraclavicular glands enlarge. In other cases the mediastinal glands may be involved, when the disease is situated on the medial side of the papilla.

The operation for removal of a mamma affected with malignant disease should be an extensive procedure, with the object of extirpating all fascial planes and lymphatic structures that may be infected. The incision commences below, over the upper part of the sheath of the Rectus, encloses the mamma by an ellipse, and is then continued on toward the apex of the axilla. The skin is reflected on both sides of the incision; anteriorly, until the sternum is reached, and posteriorly to the posterior boundary of the axilla. The origin of the sternal portion of the Pectoralis major is then divided and turned outward. The Pectoralis minor is next seen, and its origin is then divided in a similar manner. The whole of the muscular and fascial planes of the front of the chest are thus separated *en masse*, carrying with them the mamma and the skin covering it. The insertions of the two Pectorales have next to be divided, and finally the axillary lymph glands and fat are removed from the axillary vessels in one piece with the mass of tissue already detached. This is done by first freely exposing the whole length of the axillary vein and then, with a blunt instrument, peeling the structures off the vein from above downward, from the point where they are crossed by the Subclavius muscle to the lower border of the axilla. In this part of the operation many branches of both vein and artery require ligature. The only thing which then remains to be divided is the deep fascia along the posterior axillary wall. The wound is then closed, drainage is provided, and firm pressure is applied with the dressings. It will be noted that the clavicular portion of the Pectoralis major is left intact, as it is of considerable service for the subsequent movements of the arm, the utility of which is but slightly impaired.

### THE DUCTLESS GLANDS.

There are certain organs which are very similar to secreting glands, but differ from them in one essential particular, viz., they do not possess any ducts by which their secretion is discharged. These organs are known as **ductless glands**. They are capable of *internal secretion*—that is to say, of forming, from materials brought to them in the blood, substances which have a certain influence upon the nutritive and other changes going on in the body. This secretion is carried into the blood stream, either directly by the veins or indirectly through the medium of the lymphatics.

These glands include the **thyroid** and the **parathyroids**, the **thymus**, the **spleen**, the **suprarenal glands**, and the **glomus caroticum** and **glomus coccygeum**, which will

be described in this section. They also include the **lymph glands**, which have already been described in the section on Angiology; and the **pineal gland** and **hypophysis cerebri** described in the section on Neurology.

**THE THYROID GLAND (GLANDULA THYREIODEA; THYROID BODY).**  
(Fig. 1060).

The **thyroid gland** is a highly vascular organ, situated at the front and sides of the neck; it consists of right and left lobes connected across the middle line by a narrow portion, the **isthmus**. Its weight is somewhat variable, but is usually about 30 grams. It is slightly heavier in the female, in whom it becomes enlarged during menstruation and pregnancy.




FIG. 1060.—The thyroid gland and its relations.

The **lobes** (*lobuli gl. thyreoideae*) are conical in shape, the apex of each being directed upward and lateralward as far as the junction of the middle with the lower third of the thyroid cartilage; the base looks downward, and is on a level with the fifth or sixth tracheal ring. Each lobe is about 5 cm. long; its greatest width is about 3 cm., and its thickness about 2 cm. The **lateral** or **superficial surface** is convex, and covered by the skin, the superficial and deep fasciæ, the Sternocleidomastoideus, the superior belly of the Omohyoideus, the Sternohyoideus and Sternothyroideus, and beneath the last muscle by the pretracheal layer of the deep fascia, which forms a capsule for the gland. The **deep** or **medial surface** is moulded over the underlying structures, viz., the thyroid and cricoid cartilages, the trachea, the Constrictor pharyngis inferior and posterior part of the Cricothyroideus, the œsophagus (particularly on the left side of the neck), the superior and inferior thyroid arteries, and the recurrent nerves. The **anterior border** is thin, and inclines obliquely from above downward toward the middle line of the neck, while the

posterior border is thick and overlaps the common carotid artery, and, as a rule, the parathyroids.

The **isthmus** (*isthmus gl. thyroidea*) connects together the lower thirds of the lobes; it measures about 1.25 cm. in breadth, and the same in depth, and usually covers the second and third rings of the trachea. Its situation and size present, however, many variations. In the middle line of the neck it is covered by the skin and fascia, and close to the middle line, on either side, by the *Sternothyroideus*. Across its upper border runs an anastomotic branch uniting the two superior thyroid arteries; at its lower border are the inferior thyroid veins. Sometimes the isthmus is altogether wanting.

A third lobe, of conical shape, called the **pyramidal lobe**, frequently *arises* from the upper part of the isthmus, or from the adjacent portion of either lobe, but most commonly the left, and ascends as far as the hyoid bone. It is occasionally quite detached, or may be divided into two or more parts.

A fibrous or muscular band is sometimes found attached, above, to the body of the hyoid bone, and below to the isthmus of the gland, or its pyramidal lobe. When muscular, it is termed the **Levator glandulae thyroideae**.

Small detached portions of thyroid tissue are sometimes found in the vicinity of the lateral lobes or above the isthmus; they are called **accessory thyroid glands** (*glandulae thyroideae accessoriae*).




FIG. 1061.—Section of thyroid gland of sheep.  $\times 160$ .

**Structure.**—The thyroid gland is invested by a thin capsule of connective tissue, which projects into its substance and imperfectly divides it into masses of irregular form and size. When the organ is cut into, it is of a brownish-red color, and is seen to be made up of a number of closed vesicles, containing a yellow glairy fluid, and separated from each other by intermediate connective tissue (Fig. 1061).

The vesicles of the thyroid of the adult animal are generally closed spherical sacs; but in some young animals, *e. g.*, young dogs, the vesicles are more or less tubular and branched. This appearance is supposed to be due to the mode of growth of the gland, and merely indicates that an increase in the number of vesicles is taking place. Each vesicle is lined by a single layer of cubical epithelium. There does not appear to be a basement-membrane, so that the epithelial cells are in direct contact with the connective-tissue reticulum which supports the acini. The vesicles are of various sizes and shapes, and contain as a normal product a viscid, homogeneous, semifluid, slightly yellowish, colloid material; red corpuscles are found in it in various stages of disintegration and decolorization, the yellow tinge being probably due to the hemoglobin, which is thus set free from the colored corpuscles. The colloid material contains an iodine compound, *iodothylin*, and is readily stained by eosin. It passes out between the cubical cells and is absorbed into the blood or lymph.

**Vessels and Nerves.**—The **arteries** supplying the thyroid gland are the superior and inferior thyroids and sometimes an additional branch (*thyroidea ima*) from the innominate artery or the arch of the aorta, which ascends upon the front of the trachea. The arteries are remarkable for their large size and frequent anastomoses. The **veins** form a plexus on the surface of the

gland and on the front of the trachea; from this plexus the superior, middle, and inferior thyroid veins arise; the superior and middle end in the internal jugular, the inferior in the innominate vein. The capillary bloodvessels form a dense plexus in the connective tissue around the vesicles, between the epithelium of the vesicles and the endothelium of the lymphatics, which surround a greater or smaller part of the circumference of the vesicle. The **lymphatic vessels** run in the interlobular connective tissue, not uncommonly surrounding the arteries which they accompany, and communicate with a net-work in the capsule of the gland; they may contain colloid material. They end in the thoracic and right lymphatic trunks. The **nerves** are derived from the middle and inferior cervical ganglia of the sympathetic.

**Applied Anatomy.**—An enlargement of the thyroid gland is called a goitre. The swelling may take the form of a diffuse hypertrophy of the whole gland, giving rise to the *parenchymatous goitre*, this being mainly due to the hypertrophy of the thyroid follicles themselves; in other cases a *fibroid* form of goitre is produced owing to the increase in the interstitial connective tissue; in others, again, the vascular changes may preponderate, and many large pulsating vessels may be present. Much more commonly, however, the enlargement is due to adenomatous new growth in the substance of the thyroid; these tumors are always innocent, and tend to destroy life only by pressure on the air passages. A single tumor is the rule, but in some instances a very large number may be present. They tend to show marked mucoid degeneration, and so become converted into cyst-adenomata, and finally into what appear to be simple cysts. These tumors may attain an enormous size and may involve practically the whole gland. Malignant tumor-growth more rarely attacks the organ.

When, in spite of treatment, a goitre continues to grow, and especially when there are commencing symptoms of tracheal pressure, operative interference becomes necessary. This is not difficult, if an encapsulated tumor is to be dealt with, provided the anatomical layers covering it are remembered. In such a case it is necessary to make an incision suited to the size and situation of the tumor, and having divided the deep cervical fascia, to retract the Sternocleidomastoideus or divide it if necessary. The Sternohyoideus and Sternothyroideus next require division, or in some cases their fibres may be separated and drawn asunder, and beneath is found the ensheathing capsule derived from the pretracheal fascia; this requires division, and exposes the true capsule of the thyroid gland. In the case of an adenoma or cyst, this true capsule then needs incision before the tumor can be effectually shelled out, and this is usually accomplished with very little hemorrhage, and without any of the main vessels of the gland requiring ligature.

Partial extirpation of the thyroid, viz., the removal of one lateral lobe with division of the isthmus, may be required in cases of parenchymatous goitre, and in the diffuse form of adenomatous disease. It is a more radical proceeding, and carries with it a much greater risk from hemorrhage; there is also a danger of wounding the recurrent nerve. The whole gland must never be removed, as such a procedure is followed by the development of myxedema. In hemithyroidectomy a free incision is indicated—dividing muscles, if necessary—to expose the true gland capsule, but at the same time avoiding injury to the large vessels which lie beneath it. The superior and inferior pedicles containing the respective thyroid arteries are then isolated and clamped on either side and divided between the clamps. The half gland is then turned over toward the middle line, and the isthmus ligatured and divided. Some venous bleeding is apt to occur from connections with the tracheal veins, and must be stopped. The pedicles are then securely ligatured and the wound closed. In dealing with the inferior thyroid artery, the position of the recurrent nerve must be borne in mind, so as not to ligature or divide it. Temporary aphonia, not uncommonly follows from bruising of the nerve, and if nothing more serious has occurred soon passes off.

### THE PARATHYROID GLANDS.

The **parathyroid glands** are small brownish-red bodies, situated as a rule between the posterior borders of the lateral lobes of the thyroid gland and its capsule. They differ from it in structure, being composed of masses of cells arranged in a more or less columnar fashion with numerous intervening capillaries. They measure on an average about 6 mm. in length, and from 3 to 4 mm. in breadth, and usually present the appearance of flattened oval disks. They are divided, according to their situation, into **superior** and **inferior**. The superior, usually two in number, are the more constant in position, and are situated, one on either side, at the level of the lower border of the cricoid cartilage, behind the junction of the pharynx and œsophagus. The inferior, also usually two in number, may be applied to the lower edge of the lateral lobes, or placed at some little distance below the thyroid gland, or found in relation to one of the inferior thyroid veins.<sup>1</sup>

<sup>1</sup> Consult an article "Concerning the Parathyroid Glands," by D. A. Welsh, *Journal of Anatomy and Physiology*, vol. xxxii.



In man, they number four as a rule; fewer than four were found in less than 1 per cent. of over a thousand persons (Pepere<sup>1</sup>), but more than four in over 33 per cent. of 122 bodies examined by Civalleri. In addition, numerous minute islands of parathyroid tissue may be found scattered in the connective tissue and fat of the neck around the parathyroid glands proper, and quite distinct from them.

**Structure.**—Microscopically the parathyroids consist of intercommunicating columns of cells supported by connective tissue containing a rich supply of blood capillaries. Most of the cells are clear, but some, larger in size, contain oxyphil granules. Vesicles containing colloid have been described as occurring in the parathyroid, but the observation has not been confirmed.

**Applied Anatomy.**—No doubt the parathyroid glands produce an internal secretion essential to the well-being of the human economy; but it is still a matter of dispute what symptoms of disease are produced by their removal and suppression of their secretion. Pepere believes that they show signs of exceptional activity during pregnancy, and that parathyroid insufficiency is a main factor in the production of tetany in infants and adults, of eclampsia, and of certain sorts of fits.

### THE THYMUS (THYMUS GLANDS) (Fig. 1062).

The **thymus** is a temporary organ, attaining its largest size at the time of puberty (Hammar), when it ceases to grow, gradually dwindles, and almost disappears. If examined when its growth is most active, it will be found to consist of two lateral lobes placed in close contact along the middle line, situated partly in the thorax, partly in the neck, and extending from the fourth costal cartilage upward, as high as the lower border of the thyroid gland. It is covered by the sternum, and by the origins of the Sternohyoidei and Sternothyreoidi.




FIG. 1062.—The thymus of a full-time fetus, exposed *in situ*.

Below, it rests upon the pericardium, being separated from the aortic arch and great vessels by a layer of fascia. In the neck it lies on the front and sides of the trachea, behind the Sternohyoidei and Sternothyreoidi. The two lobes generally differ in size; they are occasionally united, so as to form a single mass; and sometimes separated by an intermediate lobe. The thymus is of a pinkish-gray color, soft, and lobulated on its surfaces. It is about 5 cm. in length, 4 cm. in breadth below, and about 6 mm. in thickness. At birth it weighs about 15 grams.

**Structure.**—Each lateral lobe is composed of numerous lobules held together by delicate areolar tissue; the entire gland being enclosed in an investing capsule of a similar but denser structure. The primary lobules vary in size from that of a pin's head to that of a small pea, and are made up of a number of small nodules or follicles, which are irregular in shape and are more or less fused together, especially toward the interior of the gland. Each follicle is from 1 to 2 mm.

<sup>1</sup> Consult *Le Ghiandole paratiroidi*, by A. Pepere, Turin, 1906.

in diameter and consists of a medullary and a cortical portion, and these differ in many essential particulars from each other. The **cortical portion** is mainly composed of lymphoid cells, supported by a network of finely branched cells, which is continuous with a similar network in the medullary portion. This network forms an adventitia to the bloodvessels. In the **medullary portion** the reticulum is coarser than in the cortex, the lymphoid cells are relatively fewer in number, and there are found peculiar nest-like bodies, the concentric corpuscles of Hassall. These concentric corpuscles are composed of a central mass, consisting of one or more granular cells, and of a capsule which is formed of epithelioid cells (Fig. 1063). They are the remains of the epithelial tubes which grow out from the third branchial pouches of the embryo to form the thymus.




FIG. 1063.—Minute structure of thymus. Follicle of injected thymus from calf, four days old, slightly diagrammatic, magnified about 50 diameters. The large vessels are disposed in two rings, one of which surrounds the follicle, the other lies just within the margin of the medulla. (Watney.) A and B. From thymus of camel, examined without addition of any reagent. Magnified about 400 diameters. A. Large colorless cell, containing small oval masses of hemoglobin. Similar cells are found in the lymph glands, spleen, and medulla of bone. B. Colored blood corpuscles.

Each follicle is surrounded by a vascular plexus, from which vessels pass into the interior, and radiate from the periphery toward the centre, forming a second zone just within the margin of the medullary portion. In the centre of the medullary portion there are very few vessels, and they are of minute size.

Watney has made the important observation that hemoglobin is found in the thymus, either in cysts or in cells situated near to, or forming part of, the concentric corpuscles. This hemoglobin occurs as granules or as circular masses exactly resembling colored blood corpuscles. He has also discovered, in the lymph issuing from the thymus, similar cells to those found in the gland, and, like them, containing hemoglobin in the form of either granules or masses. From these facts he arrives at the conclusion that the gland is one source of the colored blood corpuscles. More recently Schaffer has observed actual nucleated red-blood corpuscles in the thymus.

**Vessels and Nerves.**—The **arteries** supplying the thymus are derived from the internal mammary, and from the superior and inferior thyroids. The **veins** end in the left innominate vein, and in the thyroid veins. The **lymphatics** are described on page 779. The **nerves** are exceedingly minute; they are derived from the vagi and sympathetic. Branches from the descendens hypoglossi and phrenic reach the investing capsule, but do not penetrate into the substance of the gland.

**Applied Anatomy.**—Sudden death—*thymus death*—with heart-failure, and with or without acute respiratory embarrassment, has been recorded in a number of infants and children in whom the thymus was considerably enlarged and the lymphatic tissues throughout the body showed general hypertrophy, but who showed no other evidence of disease. Such deaths have often occurred during the administration of anesthetics, particularly chloroform. How far the enlarged thymus was responsible for the death of these patients, and, if it was responsible, how far its action was mechanical, are points that have been much disputed. Short of producing this sudden death, it appears that thymic enlargement may cause attacks of respiratory stridor, or noisy and difficult breathing, and spasmodic attacks of asthma—*thymic asthma*—which may be frequently repeated and may even result in death. Primary tumors of the thymus are rare forms of mediastinal new growth, and are usually dermoids or lymphosarcomas.

### THE SPLEEN (LIEN). 1✓4✓

The **spleen** is situated principally in the left hypochondriac region, but its superior extremity extends into the epigastric region; it lies between the fundus of the stomach and the Diaphragm. It is the largest of the ductless glands, and is of an oblong, flattened form, soft, of very friable consistence, highly vascular, and of a dark purplish color.

**Relations.**—The **diaphragmatic surface** (*facies diaphragmatica*; *external or phrenic surface*) is convex, smooth, and is directed upward, backward, and to the left, except at its upper end, where it is directed slightly medialward. It is in relation with the under surface of the Diaphragm, which separates it from the ninth, tenth, and eleventh ribs of the left side, and the intervening lower border of the left lung and pleura.

The **visceral surface** (Fig. 1064) is divided by a ridge into an **anterior or gastric** and a **posterior or renal** portion.




FIG. 1064.—The visceral surface of the spleen.

The **gastric surface** (*facies gastrica*), which is directed forward, upward, and medialward, is broad and concave, and is in contact with the posterior wall of the stomach; and below this with the tail of the pancreas. It presents near its medial border a long fissure, termed the hilus. This is pierced by several irregular apertures, for the entrance and exit of vessels and nerves.

The **renal surface** (*facies renalis*) is directed medialward and downward. It is somewhat flattened, is considerably narrower than the gastric surface, and is in relation with the upper part of the anterior surface of the left kidney and occasionally with the left suprarenal gland.

The **superior extremity** (*extremitas superior*) is directed toward the vertebral column, where it lies on a level with the eleventh thoracic vertebra. The **lower extremity** or **colic surface** (*extremitas inferior*) is flat, triangular in shape, and rests upon the left flexure of the colon and the phrenicocolic ligament, and is generally in contact with the tail of the pancreas. The **anterior border** (*margo anterior*) is free, sharp, and thin, and is often notched, especially below; it separates the diaphragmatic from the gastric surface. The **posterior border** (*margo posterior*), more rounded and blunter than the anterior, separates the renal from the diaphragmatic surface; it corresponds to the lower border of the eleventh rib and lies between the Diaphragma and left kidney. The **intermediate margin** is the ridge which separates the renal and gastric surfaces. The **inferior border** (*internal border*) separates the diaphragmatic from the colic surface.

The spleen is almost entirely surrounded by peritoneum, which is firmly adherent to its capsule. It is held in position by two folds of this membrane. One, the **phrenicolienal ligament**, is derived from the peritoneum, where the wall of the general peritoneal cavity comes into contact with the omental bursa between the left kidney and the spleen; the lienal vessels pass between its two layers (Fig. 965). The other fold, the **gastrolienal ligament**, is also formed of two layers, derived from the general peritoneal cavity and the omental bursa respectively, where they meet between the spleen and stomach (Fig. 965); the short gastric and left gastroepiploic branches of the lienal artery run between its two layers. The lower end of the spleen is supported by the phrenicocolic ligament (see page 1157).

The size and weight of the spleen are liable to very extreme variations at different periods of life, in different individuals, and in the same individual under different conditions. *In the adult*, it is usually about 12 cm. in length, 7 cm. in breadth, and 3 or 4 cm. in thickness, and weighs about 200 grams. *At birth*, its weight, in proportion to the entire body, is almost equal to what is observed in the adult, being as 1 to 350; while in the adult it varies from 1 to 320 and 400. *In old age*, the organ not only diminishes in weight, but decreases considerably in proportion to the entire body, being as 1 to 700. The size of the spleen is increased during and after digestion, and varies according to the state of nutrition of the body, being large in highly fed, and small in starved animals. In malarial fever it becomes much enlarged, weighing occasionally as much as 9 kilos.

Frequently in the neighborhood of the spleen, and especially in the gastrolienal ligament and greater omentum, small nodules of splenic tissue may be found, either isolated or connected to the spleen by thin bands of splenic tissue. They are known as **accessory spleens** (*lien accessorius; supernumerary spleen*). They vary in size from that of a pea to that of a plum.

**Structure.**—The spleen is invested by two coats: an **external serous** and an **internal fibro-elastic coat**.

The **external or serous coat** (*tunica serosa*) is derived from the peritoneum; it is thin, smooth, and in the human subject intimately adherent to the fibroelastic coat. It invests the entire organ, except at the hilus and along the lines of reflection of the phrenicolienal and gastrolienal ligaments.

The **fibroelastic coat** (*tunica albuginea*) invests the organ, and at the hilus is reflected inward upon the vessels in the form of sheaths. From these sheaths, as well as from the inner surface of the fibroelastic coat, numerous small fibrous bands, **trabeculae** (Fig. 1065), are given off in all directions; these uniting, constitute the frame-work of the spleen. The spleen therefore consists of a number of small spaces or **areolae**, formed by the trabeculae; in these areolae is contained the **splenic pulp**.

The fibroelastic coat, the sheaths of the vessels, and the trabeculae, are composed of white and yellow elastic fibrous tissues, the latter predominating. It is owing to the presence of the elastic tissue that the spleen possesses a considerable amount of elasticity, which allows of the very great variations in size that it presents under certain circumstances. In addition to these constituents of this tunic, there is found in man a small amount of non-striped muscular fibre; and in some mammalia, *e. g.*, dog, pig, and cat, a large amount, so that the trabeculae appear to consist chiefly of muscular tissue.

The **splenic pulp** (*pulpa lienis*) is a soft mass of a dark reddish-brown color, resembling grumous blood; it consists of a fine reticulum of fibres, continuous with those of the trabeculae, to which are applied flat, branching cells. The meshes of the reticulum are filled with blood, in which, however, the white corpuscles are found to be in larger proportion than they are in ordinary blood. Large rounded cells, termed **splenic cells**, are also seen; these are capable of amoeboid movement, and often contain pigment and red-blood corpuscles in their interior. The cells of the reticulum each possess a round or oval nucleus, and like the splenic cells, they may contain pigment granules in their cytoplasm; they do not stain deeply with carmine, and in this respect differ from the cells of the Malpighian bodies. In the young spleen, giant cells may also be found, each containing numerous nuclei or one compound nucleus. Nucleated red-blood corpuscles have also been found in the spleen of young animals.

**Bloodvessels of the Spleen.**—The **lienal artery** is remarkable for its large size in proportion to the size of the organ, and also for its tortuous course. It divides into six or more branches, which enter the hilus of the spleen and ramify throughout its substance (Fig. 1066), receiving



sheaths from an involution of the external fibrous tissue. Similar sheaths also invest the nerves and veins.

Each branch runs in the transverse axis of the organ, from within outward, diminishing in size during its transit, and giving off in its passage smaller branches, some of which pass to the anterior, others to the posterior part. These ultimately leave the trabecular sheaths, and terminate in the proper substance of the spleen in small tufts or pencils of minute arterioles, which open into the interstices of the reticulum formed by the branched sustentacular cells. Each of the larger branches of the artery supplies chiefly that region of the organ in which the branch ramifies, having no anastomosis with the majority of the other branches.




FIG. 1065.—Transverse section of the spleen, showing the trabecular tissue and the splenic vein and its tributaries.

The **arterioles** supported by the minute trabeculae, traverse the pulp in all directions in bundles (*pencil*) of straight vessels. Their trabecular sheaths gradually undergo a transformation, become much thickened, and converted into adenoid tissue; the bundles of connective tissue becoming looser and their fibrils more delicate, and containing in their interstices an abundance of lymph corpuscles (W. Müller).



FIG. 1066.—Transverse section of the human spleen, showing the distribution of the splenic artery and its branches.

The altered coat of the arterioles, consisting of adenoid tissue, presents here and there thickenings of a spheroidal shape, the **lymphatic nodules** (*Malpighian bodies of the spleen*). These bodies vary in size from about 0.25 mm. to 1 mm. in diameter. They are merely local expansions or hyperplasias of the adenoid tissue, of which the external coat of the smaller arteries of the spleen



is formed. They are most frequently found surrounding the arteriole, which thus seems to tunnel them, but occasionally they grow from one side of the vessel only, and present the appearance of a sessile bud growing from the arterial wall. In transverse sections, the artery, in the majority of cases, is found in an excentric position. These bodies are visible to the naked eye on the surface of a fresh section of the organ, appearing as minute dots of a semiopaque whitish




FIG. 1067.—Transverse section of a portion of the spleen.

color in the dark substance of the pulp. In minute structure they resemble the adenoid tissue of lymph glands, consisting of a delicate reticulum, in the meshes of which lie ordinary lymphoid cells (Fig. 1067). The reticulum is made up of extremely fine fibrils, and is comparatively open in the centre of the corpuscle, becoming closer at its periphery. The cells which it encloses are possessed of amoeboid movement. When treated with carmine they become deeply stained, and can be easily distinguished from those of the pulp.




FIG. 1068.—Section of the spleen, showing the termination of the small bloodvessels.

The arterioles end by opening freely into the splenic pulp; their walls become much attenuated, they lose their tubular character, and the endothelial cells become altered, presenting a branched appearance, and acquiring processes which are directly connected with the processes of the reticular cells of the pulp (Fig. 1068). In this manner the vessels end, and the blood flowing through them finds its way into the interstices of the reticulated tissue of the splenic pulp. Thus

the blood passing through the spleen is brought into intimate relation with the elements of the pulp, and no doubt undergoes important changes.

After these changes have taken place the blood is collected from the interstices of the tissue by the rootlets of the veins, which begin much in the same way as the arteries end. The connective-tissue corpuscles of the pulp arrange themselves in rows, in such a way as to form an elongated space or sinus. They become elongated and spindle-shaped, and overlap each other at their extremities, and thus form a sort of endothelial lining of the path or sinus, which is the radicle of a vein. On the outer surfaces of these cells are seen delicate transverse lines or markings, which are due to minute elastic fibrillæ arranged in a circular manner around the sinus. Thus the channel obtains an external investment, and gradually becomes converted into a small vein, which after a short course acquires a coat of ordinary connective tissue, lined by a layer of flattened epithelial cells which are continuous with the supporting cells of the pulp. The smaller veins unite to form larger ones; these do not accompany the arteries, but soon enter the trabecular sheaths of the capsule, and by their junction form six or more branches, which emerge from the hilus, and, uniting, constitute the lienal vein, the largest radicle of the portal vein.

The **veins** are remarkable for their numerous anastomoses, while the arteries hardly anastomose at all.

The **lymphatics** are described on page 793.

The **nerves** are derived from the coeliac plexus and are chiefly non-medullated. They are distributed to the bloodvessels and to the smooth muscle of the capsule and trabeculæ.

**Applied Anatomy.**—Injury of the spleen is less common than that of the liver, on account of its protected situation and connections. It may be ruptured by direct or indirect violence; torn by a broken rib; or injured by a punctured or gunshot wound. When the organ is enlarged, the chance of rupture is increased. The great risk is hemorrhage, owing to the vascularity of the organ, and the absence of a proper system of capillaries. The injury is not, however, necessarily fatal, and this would appear to be due, in a great measure, to the contractile power of the capsule, which narrows the wound and prevents the escape of blood. In cases where the diagnosis is clear, and the symptoms indicate danger to life, laparotomy must be performed, and if the hemorrhage cannot be stayed by ordinary surgical methods, the spleen must be removed.

The spleen may become enormously enlarged in certain diseased conditions, such as ague, leukemia, syphilis, valvular disease of the heart, or without any obtainable history of previous disease. It may also become enlarged in lymphadenoma, as a part of a general blood-disease. In these cases the tumor may fill a considerable part of the abdomen and extend into the pelvis, and may be mistaken for ovarian or uterine new growth.

The spleen is sometimes the seat of cystic tumors, especially hydatids, and of abscess. These cases require treatment by incision and drainage; and in abscess great care must be taken, if there are no adhesions between the spleen and abdominal wall, to prevent the escape of any of the pus into the peritoneal cavity. If possible the operation should be performed in two stages. Sarcoma and carcinoma are occasionally found in the spleen, but very rarely as primary diseases.

Extirpation of the spleen has been performed for wounds or injuries, in floating spleen, in simple hypertrophy, in leukemic enlargement (but the operation is now considered unjustifiable in this condition), and in the case of enlargement due to certain obscure parasitic infections met with in hot climates. The incision is best made in the left semilunar line; the spleen is isolated from its surroundings and delivered from the abdomen; the pedicle is then transfixed and ligatured in two portions.

### THE SUPRARENAL GLANDS (GLANDULÆ SUPRARENALIS; ADRENAL CAPSULE) (Figs. 1069, 1070).

The **suprarenal glands** are two small flattened bodies of a yellowish color, situated at the back part of the abdomen, behind the peritoneum, and immediately above and in front of the upper end of each kidney; hence their name. The right one is somewhat triangular in shape, bearing a resemblance to a cocked hat; the left is more semilunar, usually larger, and placed at a higher level than the right. They vary in size in different individuals, being sometimes so small as to be scarcely detected: their usual size is from 3 to 5 cm. in length, rather less in width, and from 4 to 6 mm. in thickness. Their average weight is from 1.5 to 2.5 gm. each.

**Relations.**—The relations of the suprarenal glands differ on the two sides of the body.

The **right suprarenal** is situated behind the inferior vena cava and right lobe of the liver, and in front of the Diaphragma and upper end of the right kidney. It is roughly triangular in shape; its base, directed downward, is in contact with the medial and anterior aspects of the upper end

of the right kidney. It presents two surfaces for examination, an anterior and a posterior. The *anterior surface* looks forward and lateralward, and has two areas: a medial, narrow, and non-peritoneal, which lies behind the inferior vena cava; and a lateral, somewhat triangular, in contact with the liver. The upper part of the latter surface is devoid of peritoneum, and is in relation with the bare area of the liver near its lower and medial angle, while its inferior portion is covered by peritoneum, reflected on to it from the inferior layer of the coronary ligament; occasionally the duodenum overlaps the inferior portion. A little below the apex, and near the anterior border of the gland, is a short furrow termed the *hilus*, from which the suprarenal vein emerges to join the inferior vena cava. The *posterior surface* is divided into upper and lower parts by a curved ridge: the upper, slightly convex, rests upon the Diaphragm; the lower, concave, is in contact with the upper end and the adjacent part of the anterior surface of the kidney.




FIG. 1069.—Suprarenal glands viewed from the front.

The *left suprarenal*, slightly larger than the right, is crescentic in shape, its concavity being adapted to the medial border of the upper part of the left kidney. It presents a medial border, which is convex, and a lateral, which is concave; its upper end is narrow, and its lower rounded. Its *anterior surface* has two areas: an upper one, covered by the peritoneum of the omental bursa, which separates it from the cardiac end of the stomach, and sometimes from the superior extremity of the spleen; and a lower one, which is in contact with the pancreas and lienal artery, and is therefore not covered by the peritoneum. On the anterior surface, near its lower end, is a furrow or *hilus*, directed downward and forward, from which the suprarenal vein emerges. Its *posterior surface* presents a vertical ridge, which divides it into two areas; the lateral area rests on the kidney, the medial and smaller on the left crus of the Diaphragm.



FIG. 1070.—Suprarenal glands viewed from behind.

The surface of the suprarenal gland is surrounded by areolar tissue containing much fat, and closely invested by a thin fibrous capsule, which is difficult to remove on account of the numerous fibrous processes and vessels entering the organ through the furrows on its anterior surface and base.

Small *accessory suprarenals* (*glandulae suprarenales accessoriae*) are often to be found in the connective tissue around the suprarenals. The smaller of these, on section, show a uniform surface, but in some of the larger a distinct medulla can be made out.

**Structure.**—On section, the suprarenal gland is seen to consist of two portions (Fig. 1071): an *external or cortical* and an *internal or medullary*. The former constitutes the chief part of the organ, and is of a deep yellow color; the medullary substance is soft, pulpy, and of a dark red or brown color.

The **cortical portion** (*substantia corticalis*) consists of a fine connective-tissue net-work, in which is imbedded the glandular epithelium. The epithelial cells are polyhedral in shape and possess rounded nuclei; many of the cells contain coarse granules, others lipid globules. Owing to differences in the arrangement of the cells, three distinct zones can be made out: (1) the **zona glomerulosa**, situated beneath the capsule, consists of cells arranged in rounded groups, with here and there indications of an alveolar structure; the cells of this zone are very granular, and stain deeply. (2) The **zona fasciculata**, continuous with the zona glomerulosa, is composed of columns of cells arranged in a radial manner; these cells contain finer granules and in many instances globules of lipid material. (3) The **zona reticularis**, in contact with the medulla, consists of cylindrical masses of cells irregularly arranged; these cells often contain pigment granules which give this zone a darker appearance than the rest of the cortex.

The **medullary portion** (*substantia medullaris*) is extremely vascular, and is composed of a loose mesh-work of connective tissue surrounding a large plexus of sinusoidal venous spaces and containing non-striped muscular fibres. In addition to the veins, multinucleated masses of protoplasm are scattered throughout the medulla as well as many irregular-shaped cells containing pigment. The cell protoplasm has an especial affinity for chromic salts, which stain it a brown color. Such cells are therefore termed **chromaffin cells** (see page 133). This portion of the gland is richly supplied with non-medullated nerve fibres, and here and there sympathetic ganglia are found.




FIG. 1071.—Section of a part of a suprarenal gland. (Magnified.)

**Vessels and Nerves.**—The **arteries** supplying the suprarenal glands are numerous and of comparatively large size; they are derived from the aorta, the inferior phrenic, and the renal. They subdivide into minute branches previous to entering the cortical part of the gland, where they break up into capillaries which end in the venous plexus of the medullary portion.

The **suprarenal vein** returns the blood from the medullary venous plexus and receives several branches from the cortical substance; it emerges from the hilus of the gland and on the right side opens into the inferior vena cava, on the left into the renal vein.

The **lymphatics** end in the lumbar glands.

The **nerves** are exceedingly numerous, and are derived from the coeliac and renal plexuses, and, according to Bergmann, from the phrenic and vagus nerves. They enter the lower and medial part of the capsule, traverse the cortex, and end around the cells of the medulla. They have numerous small ganglia developed upon them in the medullary portion of the gland.

In connection with the development of the medulla from the sympathochromaffin tissue, it is to be noted that this portion of the gland secretes a substance, **adrenalin**, which has a powerful influence on those muscular tissues which are supplied by sympathetic fibres.

**Applied Anatomy.**—The suprarenal **cortex** is derived from the coelomic epithelium of the Wolffian ridge, and is connected with the sexual glands; it is related to growth and development in some way, and is often found to be hypertrophied in patients with chronic kidney disease and high blood-pressure. The **medulla**, on the other hand, is neuro-ectodermal in origin, and

closely connected with the sympathetic nervous system. When the suprarenal medulla is destroyed by tuberculosis, to which the glands are prone, or by the pressure of a new growth, the secretion of adrenalin becomes inadequate, and Addison's disease develops. Patients with Addison's disease become pigmented in various parts of the body, possibly from irritation of the sympathetic, and complain of great weakness, lack of energy, nausea, and severe attacks of vomiting. Their blood-pressure is low, the whole nervous system is depressed, and death follows after a period of months or years, usually from asthenia. Tumors derived from the suprarenal itself, or from misplaced suprarenal "rests" occurring in such organs as the kidney or liver, may be either benign or malignant, and are classed together under the name "hypernephroma." In children the malignant hypernephroma is often associated with obesity and precocity. The benign hypernephroma, or suprarenal adenoma, appears to produce no symptoms except those due to its slow enlargement.

#### THE CAROTID SKEINS (GLOMERA CAROTICA; CAROTID GLANDS; CAROTID BODIES.)

The **carotid skeins**, two in number, are situated one on either side of the neck, behind the common carotid artery at its point of bifurcation into the external and internal carotid trunks. They are reddish brown in color and oval in shape, the long diameter measuring about 5 mm.




FIG. 1072.—Section of part of human glomus caroticum. (Schaper.) Highly magnified. Numerous bloodvessels are seen in section among the gland cells.

Each is invested by a fibrous capsule and consists largely of spherical or irregular masses of cells (Fig. 1072), the masses being more or less isolated from one another by septa which extend inward from the deep surface of the capsule. The cells are polyhedral in shape, and each contains a large nucleus imbedded in finely granular protoplasm, which is stained yellow by chromic salts. Numerous nerve fibres, derived from the sympathetic plexus on the carotid artery, are distributed throughout the organ, and a net-work of large sinusoidal capillaries ramifies among the cells.

#### THE COCCYGEAL SKEIN (GLOMUS COCCYGEUM; COCCYGEAL GLAND OR BODY; LUSCHKA'S GLAND).

The **coccygeal skein** is placed in front of, or immediately below, the tip of the coccyx. It is about 2.5 mm. in diameter and is irregularly oval in shape; several smaller nodules are found around or near the main mass.

It consists of irregular masses of round or polyhedral cells (Fig. 1073), the cells of each mass being grouped around a dilated sinusoidal capillary vessel. Each cell



contains a large round or oval nucleus, the protoplasm surrounding which is clear, and is not stained by chromic salts.<sup>1</sup>




FIG. 1073.—Section of an irregular nodule of the glomus coccygeum. (Sertoli.)  $\times 85$ . The section shows the fibrous covering of the nodule, the bloodvessels within it, and the epithelial cells of which it is constituted.

Besides the ductless glands mentioned, reference may be made to a pair of small bodies, the **aortic bodies of Zuckerkandl**. These are found in the embryo, and persist until shortly after birth; they lie one on either side of the abdominal aorta between the superior mesenteric and common iliac arteries (see page 133). They consist essentially of masses of polygonal or cuboidal chromaffin cells imbedded in a wide-meshed capillary plexus.

<sup>1</sup> Consult the following article: "Über die menschliche Steissdrüse," von J. W. Thomson Walker, *Archiv für mikroskopische Anatomie und Entwicklungsgeschichte*, Band 64, 1904.

# SURFACE ANATOMY AND SURFACE MARKINGS.

## SURFACE ANATOMY OF THE HEAD AND NECK.

**Bones** (Fig. 1074).—Various bony surfaces and prominences on the skull can be easily identified by palpation. The **external occipital protuberance** is situated behind, in the middle line, at the junction of the skin of the neck with that of the head. The **superior nuchal line** runs lateralward from it on either side, while extending downward from it is the **median nuchal crest**, situated deeply at the bottom of the nuchal furrow. Above the superior nuchal lines the vault of the cranium




FIG. 1074.—Side view of head, showing surface relations of bones.

is thinly covered with soft structures, so that the form of this part of the head is almost that of the upper portion of the occipital, the parietal, and the frontal bones. The superior nuchal line can be followed lateralward to the mastoid portion of the temporal bone, from which the **mastoid process** projects downward and forward behind the ear. The anterior and posterior borders, the apex, and the external surface of this process are all available for superficial examination the anterior border lies immediately behind the concha, and the apex is on a level

with the lobule of the auricula. About 1 cm. below and in front of the apex of the mastoid process, the **transverse process of the atlas** can be distinguished. In front of the ear the **zygomatic arch** can be felt throughout its entire length; its posterior end is narrow and is situated a little above the level of the tragus; its anterior end is broad and is continued into the zygomatic bone. The lower border of the arch is more distinct than the upper, which is obscured by the attachment of the temporal fascia. In front, and behind, the upper border of the arch can be followed into the **superior temporal line**. In front, this line begins at the zygomatic process of the frontal bone as a curved ridge which runs at first forward and upward on the frontal bone, and then curving backward separates the forehead from the temporal fossa. It can then be traced across the parietal bone, where, though less marked, it can generally be recognized. Finally, it curves downward, and forward, and passing above the external acoustic meatus, ends in the posterior root of the zygomatic arch. Near the line of the greatest transverse diameter of the head are the **parietal eminences**, one on either side of the middle line; further forward, on the forehead, are the **frontal eminences**, which vary in prominence in different individuals and are frequently unsymmetrical. Below the frontal eminences the **superciliary arches**, which indicate the position of the frontal sinuses, can be recognized; as a rule they are small in the female and absent in children. In some cases the prominence of the superciliary arches is related to the size of the frontal sinuses, but frequently there is no such relationship. Situated between, and connecting the superciliary ridges, is a smooth, somewhat triangular area, the **glabella**, below which the **nasion** (*frontonasal suture*) can be felt as a slight depression at the root of the nose.

Below the nasion the **nasal bones**, scantily covered by soft tissues, can be traced to their junction with the nasal cartilages, and on either side of the nasal bone the complete outline of the **orbital margin** can be made out. At the junction of the medial and intermediate thirds of the supraorbital margin the **supraorbital notch**, when present, can be felt; close to the medial end of the infraorbital margin is a little tubercle which serves as a guide to the position of the lacrimal sac. Below and lateral to the orbit, on either side, is the **zygomatic bone** forming the prominence of the cheek; its posterior margin is easily palpable, and on it just above the level of the lateral palpebral commissure is the **zygomatic tubercle**. A slight depression, about 1 cm. above this tubercle, indicates the position of the **zygomaticofrontal suture**. Directly below the orbit a considerable part of the anterior surface of the maxilla and the whole of its alveolar process can be palpated. The outline of the **mandible** can be recognized throughout practically its entire extent; in front of the tragus and below the zygomatic arch is the condyle, and from this the posterior border of the ramus can be followed to the angle; from the angle to the symphysis the lower rounded border of the mandible can be easily traced; the lower part of the anterior border of the ramus and the alveolar process can be made out without difficulty. In the receding angle below the chin is the **hyoid bone**, and the finger can be carried along the bone to the tip of the greater cornu, which is on a level with the angle of the mandible: the greater cornu is most readily appreciated by making pressure on one side, when the cornu of the opposite side will be rendered prominent and can be felt distinctly beneath the skin.

**Joints and Muscles.**—The **temporomandibular articulation** is quite superficial, and is situated below the posterior end of the zygomatic arch, in front of the external acoustic meatus. Its position can be ascertained by defining the condyle of the mandible; when the mouth opens, the condyle advances out of the mandibular fossa on to the articular tubercle, and a depression is felt in the situation of the joint.

The outlines of the muscles of the head and face cannot be traced on the surface except in the case of the Masseter and Temporalis. The muscles of the scalp

are so thin that the outline of the bone is perceptible beneath them. Those of the face are small, covered by soft skin, and often by a considerable layer of fat, and their outlines are therefore concealed; they serve, however, to round off and smooth prominent borders, and to fill up what would otherwise be unsightly angular depressions. Thus the **Orbicularis oculi** rounds off the prominent margin of the orbit, and the **Procerus** fills in the sharp depression below the glabella. In like manner the **labial muscles** converging to the lips, and assisted by the superimposed fat, fill up the sunken hollow of the lower part of the face. When in action the facial muscles produce the various expressions, and in addition through the skin into numerous folds and wrinkles. The **Masseter** imparts fulness to the hinder part of the cheek; if firmly contracted, as when the teeth are clenched, its quadrilateral outline is plainly visible; the anterior border forms a prominent vertical ridge, behind which is a considerable fulness especially marked at the



FIG. 1075.—Anterolateral view of head and neck.

lower part of the muscle. The **Temporalis** is fan-shaped and fills the temporal fossa, substituting for the concavity a somewhat convex swelling, the anterior part of which, on account of the absence of hair on the overlying skin, is more marked than the posterior, and stands out in strong relief when the muscle is in action.

In the neck, the **Platysma** when contracted throws the skin into oblique ridges parallel with the fasciculi of the muscle. The **Sternocleidomastoides** has the most important influence on the surface form of the neck (Figs. 1075, 1076). When the muscle is at rest its anterior border forms an oblique rounded edge ending below in the sharp outline of the sternal head; the posterior border is only distinct for about 2 or 3 cm. above the middle of the clavicle. During contraction, the sternal head stands out as a sharply defined ridge, while the clavicular head is flatter and less prominent; between the two heads is a slight depression: the fleshy middle portion

of the muscle appears as an oblique elevation with a thick, rounded, anterior border, best marked in its lower part. The sternal heads of the two muscles are separated by a V-shaped depression, in which are the **Sternohyoideus** and **Sternothyroideus**.

Above the hyoid bone, near the middle line, the anterior belly of the **Digastricus** produces a slight convexity.

The anterior border of the **Trapezius** presents as a faint ridge running from the superior nuchal line, downward and forward to the junction of the intermediate and lateral thirds of the clavicle. Between the **Sternocleidomastoideus** and the **Trapezius** is the posterior triangle of the neck, the lower part of which appears as a shallow concavity—the **supraclavicular fossa**. In this fossa, the inferior belly of the **Omoxyoideus**, when in action, presents as a rounded cord-like elevation a little above, and almost parallel to, the clavicle.




FIG. 1076.—Front view of neck.

**Arteries.**—The positions of several of the larger arteries can be ascertained from their pulsations.

The **subclavian artery** can be felt by making pressure downward, backward, and medialward behind the clavicular head of the **Sternocleidomastoideus**; its **transverse cervical branch** may be detected parallel to, and about a finger's breadth above, the clavicle. The **common and external carotid arteries** can be recognized immediately beneath the anterior edge of the **Sternocleidomastoideus**. The **external maxillary artery** can be traced over the border of the mandible just in front of the anterior border of the **Masseter**, then about 1 cm. lateral to the angle of the mouth, and finally as it runs up the side of the nose. The pulsation of the **occipital artery** can be distinguished about 3 or 4 cm. lateral to the external occipital protuberance; that of the **posterior auricular** in the groove between the mastoid process and the auricula. The course of the **superficial temporal artery** can be readily followed across the posterior end of the zygomatic arch to a point about 3 to 5 cm. above this, where it divides into its frontal and parietal branches; the pulsation of the frontal branch is frequently visible on the side of the forehead. The **supraorbital artery** can usually be detected immediately above the supraorbital notch or foramen.



## SURFACE MARKINGS OF SPECIAL REGIONS OF HEAD AND NECK.

**The Cranium.—Scalp.**—The soft parts covering the upper surface of the skull form the scalp and comprise the following layers (Fig. 1077): (1) *skin*, (2) *subcutaneous tissue*, (3) *Occipitalis frontalis* and *galea aponeurotica*, (4) *subaponeurotic tissue*, (5) *pericranium*. The subcutaneous tissue consists of a close mesh-work of fibres, the meshes of which contain fatty tissue; the fibres bind the skin and galea aponeurotica firmly together, so that when the Occipitalis or the Frontalis is in action the skin moves with the aponeurosis. The subaponeurotic tissue, which intervenes between the galea aponeurotica and the pericranium, is much looser in texture, and permits the movement of the aponeurosis over the underlying bones.




FIG. 1077.—Diagrammatic section of scalp.

**Bony Landmarks** (Fig. 1074).—In addition to the bony points already described which can be determined by palpation, the following are utilized for surface markings:

*Auricular Point.*—The centre of the orifice of the external acoustic meatus.

*Preauricular Point.*—A point on the posterior root of the zygomatic arch immediately in front of the external acoustic meatus.

*Asterion.*—The point of meeting of the lambdoidal, mastoöccipital, and masto-parietal sutures; it lies 4 cm. behind and 12 mm. above the level of the auricular point.

*Pterion.*—The point where the great wing of the sphenoid joins the sphenoidal angle of the parietal; it is situated 35 mm. behind, and 12 mm. above, the level of the frontozygomatic suture.

*Inion.*—The external occipital protuberance.

*Lambda.*—The point of meeting of the lambdoidal and sagittal sutures; it is in the middle line about 6.5 cm. above the inion.

*Bregma.*—The meeting-point of the coronal and sagittal sutures; it lies at the point of intersection of the middle line of the scalp with a line drawn vertically upward through the preauricular point.

A line passing through the inferior margin of the orbit and the auricular point is known as **Reid's base line**. The lambdoidal suture can be indicated on either

side by the upper two-thirds of a line from the lambda to the tip of the mastoid process. The **sagittal suture** is in the line joining the lambda to the bregma. The position of the **coronal suture** on either side is sufficiently represented by a line joining the bregma to the centre of the zygomatic arch.

The floor of the middle fossa of the skull is at the level of the posterior three-fourths of the upper border of the zygomatic arch; the articular eminence of the temporal bone is opposite the foramen spinosum and the semilunar ganglion.




FIG. 1078.—Drawing of a cast by Cunningham to illustrate the relations of the brain to the skull.

**Brain** (Figs. 1078, 1079).—The general outline of the **cerebral hemisphere**, on either side, may be mapped out on the surface in the following manner. Starting from the nasion, a line drawn along the middle of the scalp to the inion represents the superior border. The line of the lower margin behind is that of the transverse sinus (see page 1282), or more roughly a line convex upward from the inion to the posterior root of the zygomatic process of the temporal bone; thence along the posterior two-thirds of the upper border of the zygomatic arch where the line turns up to the pterion; the front part of the lower margin extends from the pterion to the glabella about 1 cm. above the supraorbital margin. The **cerebellum** is so deeply situated that there is no reliable surface marking for it; a point 4 cm. behind and 1.5 cm. below the level of the auricular point is situated directly over it.

The relations of the principal fissures and gyri of the cerebral hemispheres to the surface of the scalp are of considerable practical importance, and several methods of indicating them have been devised. Necessarily these methods can

only be regarded as approximately correct, yet they are all sufficiently accurate for surgical purposes. The **longitudinal fissure** corresponds to the medial line of the scalp between the nasion and inion. In order to mark out the **lateral cerebral (Sylvian) fissure** a point, termed the Sylvian point, which practically corresponds to the pterion, is defined 35 mm. behind and 12 mm. above the level of the fronto-zygomatic suture; this point marks the spot where the lateral fissure divides. Another method of defining the Sylvian point is to divide the distance between the nasion and inion into four equal parts; from the junction of the third and fourth parts (reckoning from the front) draw a line to the frontozygomatic suture; from the junction of the first and second parts a line to the auricular point. These two lines intersect at the Sylvian point and the portion of the first line behind this point overlies the posterior ramus of the lateral cerebral fissure. The position




FIG. 1079.—Relations of the brain and middle meningeal artery to the surface of the skull. 1. Nasion. 2. Inion. 3. Lambda. 4. Lateral cerebral fissure. 5. Central sulcus. A.A. Reid's base line. B. Point for trephining the anterior branch of the middle meningeal artery. C. Suprameatal triangle. D. Sigmoid bend of the transverse sinus. E. Point for trephining over the straight portion of the transverse sinus, exposing dura mater of both cerebrum and cerebellum. Outline of cerebral hemisphere indicated in blue; course of middle meningeal artery in red.

of the posterior ramus can otherwise be obtained by joining the Sylvian point to a point 2 cm. below the summit of the parietal eminence. The anterior ascending ramus can be marked out by drawing a line upward at right angles to the line of the posterior ramus for 2 cm. and the anterior horizontal ramus by a line of the same length drawn horizontally forward—both from the Sylvian point. To define the **central sulcus (fissure of Rolando)** two points are taken; one is situated 1.25 cm. behind the centre of the line joining the nasion and inion; the second is at the intersection of the line of the posterior ramus of the lateral cerebral fissure with a line through the preauricular point at right angles to Reid's base line. The upper 9 cm. of the line joining these two points overlies the central sulcus and forms an angle, opening forward, of about 70° with the middle line of the scalp. An alternative method is to draw two perpendicular lines from Reid's base line to the top of the head; one from the preauricular point and the other from the posterior

border of the mastoid process at its root. A line from the upper end of the posterior line to the point where the anterior intersects the line of the posterior ramus of the lateral fissure indicates the position of the central sulcus. The **precentral** and **postcentral sulci** are practically parallel to the central sulcus; they are situated respectively about 15 mm. in front of, and behind, it. The **superior frontal sulcus** can be mapped out by a line drawn from the junction of the upper and middle thirds of the precentral sulcus, in a direction parallel with the longitudinal sulcus, to a point midway between the middle line of the forehead and the temporal line, 4 cm. above the supraorbital notch. The **inferior frontal sulcus** begins at the junction of the middle and lower thirds of the precentral sulcus, and follows the course of the superior temporal line.

The horizontal limb of the **intraparietal sulcus** begins from the junction of the lower with the middle third of the postcentral sulcus and curves backward parallel to the longitudinal fissure, midway between it and the parietal eminence; it then curves downward to end midway between the lambda and the parietal eminence. The external part of the **parietooccipital fissure** runs lateralward at right angles to the longitudinal fissure for about 2.5 cm. from a point 5 mm. in front of the lambda. If the line of the posterior ramus of the lateral cerebral fissure be continued back to the longitudinal fissure, the last 2.5 cm. of it will indicate the position of the parietooccipital fissure.

The **lateral ventricle** may be circumscribed by a quadrilateral figure. The upper limit is a horizontal line 5 cm. above the zygomatic arch; this defines the roof of the ventricle. The lower limit is a horizontal line 1 cm. above the zygomatic arch; it indicates the level of the end of the inferior horn. Two vertical lines, one through the junction of the anterior and middle thirds of the zygomatic arch, and the other 5 cm. behind the tip of the mastoid process, indicate the extent of the anterior horn in front and the posterior horn behind.

**Vessels.**—The line of the anterior division of the **middle meningeal artery** is equidistant from the frontozygomatic suture and the zygomatic arch; it is obtained by joining up the following points: (1) 2.5 cm., (2) 4 cm., and (3) 5 cm. from these two landmarks. The posterior division can be reached 2.5 cm. above the auricular point.

The position of the **transverse sinus** is obtained by taking two lines: the first from the inion to a point 2.5 cm. behind the auricular point; the second from the anterior end of the first to the tip of the mastoid process. The second line corresponds roughly to the line of reflection of the skin of the auricula behind, and its upper two-thirds represents the sigmoid part of the sinus. The first part of the sinus has a slight upward convexity, and its highest point is about 4 cm. behind and 1 cm. above the level of the auricular point. The width of the sinus is about 1 cm.

**The Face.—Air Sinuses** (Fig. 1080).—The frontal and maxillary sinuses vary so greatly in form and size that their surface markings must be regarded as only roughly approximate. To mark out the position of the **frontal sinus** three points are taken: (1) the nasion, (2) a point in the middle line 3 cm. above the nasion, (3) a point at the junction of the lateral and intermediate thirds of the supraorbital margin. By joining these a triangular field is described which overlies the greater part of the sinus. The outline of the **maxillary sinus** is irregularly quadrilateral and is obtained by joining up the following points: (1) the lacrimal tubercle, (2) a point on the zygomatic bone at the level of the inferior and lateral margins of the orbit, (3) and (4) points on the alveolar process above the last molar and the second premolar teeth respectively.

**External Maxillary Artery.**—The course of this artery on the face may be indicated by a line starting from the lower border of the mandible at the anterior margin of the Masseter, and running at first forward and upward to a point 1 cm. lateral



to the angle of the mouth, thence to the ala of the nose and upward to the medial commissure of the eye (Fig. 1081).

**Trigeminal Nerve.**—Terminal branches of this nerve, viz., the supraorbital branch of the ophthalmic, the infraorbital of the maxillary, and the mental of the mandibular emerge from corresponding foramina on the face (Fig. 1081). The supraorbital foramen is situated at the junction of the medial and intermediate thirds of the supraorbital margin. A line drawn from this foramen to the lower border of the mandible, through the interval between the two lower premolar teeth, passes over the infraorbital and mental foramina; the former lies about 1 cm. below the margin of the orbit, while the latter varies in position according to the age of the individual; in the adult it is midway between the upper and lower borders of the mandible, in the child it is nearer the lower border, while in the edentulous jaw of old age it is close to the upper margin.




FIG. 1080.—Outline of bones of face, showing position of air sinuses.




FIG. 1081.—Outline of side of face, showing chief surface markings.

The position of the sphenopalatine ganglion is indicated from the side by a point on the upper border of the zygomatic arch, 6 mm. from the margin of the zygomatic bone.

**Parotid Gland** (Fig. 1081).—The upper border of the parotid gland corresponds to the posterior two-thirds of the lower border of the zygomatic arch; the posterior border to the front of the external acoustic meatus, the mastoid process, and the anterior border of Sternocleidomastoideus. The inferior border is indicated by a line from the tip of the mastoid process to the junction of the body and greater cornu of the hyoid bone. In front, the anterior border extends for a variable distance on the superficial surface of the Masseter. The surface marking for the **parotid duct** is a line drawn across the face about a finger's breadth below the zygomatic arch, i. e., from the lower margin of the concha to midway between the red margin



of the lip and the ala of the nose; the duct ends opposite the second upper molar tooth and measures about 5 cm. in length.

**The Nose.**—The outlines of the nasal bones and the cartilages forming the external nose can be easily felt. The mobile portion of the nasal septum, formed by the medial crura of the greater alar cartilages and the skin, is easily distinguished between the nares. When the head is tilted back and a speculum introduced through the naris, the floor of the nasal cavity, the lower part of the nasal septum, and the anterior ends of the middle and inferior nasal conchæ can be examined. The opening of the nasolacrimal duct, which lies under cover of the front of the inferior nasal concha, is situated about 2.5 cm. behind the naris and 2 cm. above the level of the floor of the nasal cavity.




FIG. 1082.—The mouth cavity. The cheeks have been slit transversely and the tongue pulled forward.

**The Mouth.**—The orifice of the mouth is bounded by the lips, which are covered externally by the whitish skin and internally by the red mucous membrane. The size of the orifice varies considerably in different individuals, but seems to bear a close relationship to the size and prominence of the teeth; its angles usually correspond to the lateral borders of the canine teeth. Running down the centre of the outer surface of the upper lip is a shallow groove—the **philtrum**. If the lips be everted there can be seen, in the middle line of each, a small fold of mucous membrane—the **frenulum**—passing from the lip to the gum. By pulling the angle of the

mouth outward the mucous membrane of the cheek can be inspected, and on this, opposite the second molar tooth of the maxilla, is the little papilla which marks the orifice of the parotid duct.

In the floor of the mouth is the **tongue** (Fig. 1082). Its upper surface is convex and is marked along the middle line by a shallow sulcus; the anterior two-thirds are rough and studded with papillæ; the posterior third is smooth and tuberculated. The division between the anterior two-thirds and the posterior third is marked by a V-shaped furrow, the *sulcus terminalis*, which is situated immediately behind the line of the vallate papillæ.




FIG. 1083.—The mouth cavity. The apex of the tongue is turned upward, and on the right side a superficial dissection of its under surface has been made.

On the under surface of the tongue (Fig. 1083) the mucous membrane is smooth and devoid of papillæ. In the middle line, the mucous membrane extends to the floor of the mouth as a distinct fold—the *frenulum*—the free edge of which runs forward to the *symphysis menti*. Sometimes the *ranine vein* can be seen immediately beneath the mucous membrane, a little lateral to the *frenulum*. Close to the attachment of the *frenulum* to the floor of the mouth, the slit-like orifice of the *submaxillary duct* is visible on either side. Running backward and lateralward from the orifice of the *submaxillary duct* is the *plica sublingualis*, produced by the projection of the *sublingual gland* which lies immediately beneath the mucous membrane. The *plica* serves also to indicate the line of the *submaxillary duct* and of the *lingual nerve*. At the back of the mouth is the *isthmus faucium*, bounded above by the *palatine velum*, from the free margin of which the *uvula* projects downward in the middle line. On either side of the *isthmus* are the two *palatine arches*, the anterior formed by the *Glossopalatinus* and the posterior by the *Pharyn-*

gopalatinus. Between the two arches of either side is the palatine **tonsil**, above which is the small supratonsillar recess; the position of the tonsil corresponds to the angle of the mandible. When the mouth is opened widely, a tense band—the pterygomandibular raphé—can be seen and felt lateral to the glossopalatine arch. Its lower end is attached to the mandible behind the last molar tooth, and immediately below and in front of this the **lingual nerve** can be felt; the upper




FIG. 1084.—Front of nasal part of pharynx, as seen with the laryngoscope.

end of the ligament can be traced to the pterygoid hamulus. About 1 cm. in front of the hamulus and 1 cm. medial to the last molar tooth of the maxilla is the greater palatine foramen through which the descending palatine vessels and the anterior palatine nerve emerge. Behind the last molar tooth of the maxilla the coronoid process of the mandible is palpable.




FIG. 1085.—Laryngoscopic view of interior of larynx.

By tilting the head well back a portion of the posterior pharyngeal wall, corresponding to the site of the second and third cervical vertebræ, can be seen through the isthmus faucium. On introducing the finger the anterior surfaces of the upper cervical vertebræ can be felt through the thin muscular wall of the pharynx; if the finger be hooked round the palatine velum, the choanæ can be distinguished in front, and the pharyngeal ostium of the auditory tube on either side. The level of the choanæ is that of the atlas, while the palatine velum is opposite the body of the axis.

With the laryngoscope many other structures can be seen. In the nasal part of the pharynx (Fig. 1084), the choanæ, the nasal septum, the nasal conchæ, and the pharyngeal ostia of the auditory tubes can all be examined. Further down, the base of the tongue, the anterior surface of the epiglottis with the glossopiglottic and pharyngoepiglottic folds bounding the valleculæ, and the pyriform sinuses, are readily distinguished. Beyond these is the entrance to the larynx, bounded on either side by the aryepiglottic folds, in each of which are two rounded eminences corresponding to the corniculate and cuneiform cartilages.

Within the larynx (Fig. 1085) on either side are the ventricular and vocal folds (false and true vocal cords) with the ventricle between them. Still deeper are seen the cricoid cartilage and the anterior parts of some of the cartilaginous rings of the trachea, and sometimes, during deep inspiration, the bifurcation of the trachea.

**The Eye.**—The palpebral fissure is elliptical in shape, and varies in form in different individuals and in different races of mankind; normally it is oblique, in a direction upward and lateralward, so that the lateral commissure is on a slightly higher level than the medial. When the eyes are directed forward as in ordinary vision the upper part of the cornea is covered by the upper eyelid and its lower margin corresponds to the level of the free margin of the lower eyelid, so that usually the lower three-fourths are exposed.

At the medial commissure (Fig. 1086) are the caruncula lacrimalis and the plica semilunaris. When the lids are everted, the tarsal glands appear as a series of nearly straight parallel rows of light yellow granules. On the margins of the lids about 5 mm. from the medial commissure are two small openings—the **lacrimal puncta**; in the natural condition they are in contact with the conjunctiva of the bulb of the eye, so that it is necessary to evert the eyelids to expose them. The position of the lacrimal sac is indicated by a little tubercle which can be plainly felt on the lower margin of the orbit; the sac lies immediately above and medial to the tubercle. If the eyelids be drawn lateralward so as to tighten the skin at the medial commissure a prominent core can be felt beneath the tightened skin; this is the medial palpebral ligament, which lies over the junction of the upper with the lower two-thirds of the sac, thus forming a useful guide to its situation. The direction of the nasolacrimal duct is indicated by a line from the lacrimal sac to the first molar tooth of the maxilla; the length of the duct is about 12 or 13 mm.

On looking into the eye, the **iris** with its opening, the **pupil**, and the front of the lens can be examined, but for investigation of the **retina** an ophthalmoscope is necessary. With this the **lens**, the vessels of the **retina** the **optic disk**, and the macula lutea can all be inspected (Fig. 1087).

On the lateral surface of the nasal part of the frontal bone the pulley of the **Obliquus superior** can be easily reached by pushing the finger backward along the roof of the orbit; the tendon of the muscle can be traced for a short distance backward and lateralward from the pulley.




FIG. 1086.—Front of left eye with eyelids separated to show medial canthus.




FIG. 1087.—The interior of the posterior half of the left eyeball.

**The Ear.**—The various prominences and fossæ of the auricula (see page 1044) are visible (Fig. 1088). The opening of the **external acoustic meatus** is exposed by



FIG. 1088.—The auricula or pinna. Lateral surface.

drawing the tragus forward; at the orifice are a few short crisp hairs which serve to prevent the entrance of dust or of small insects; beyond this the secretion of the **ceruminous glands** serves to catch any small particles which may find their way into the meatus. The interior of the meatus can be examined through a speculum. At the line of junction of its bony and cartilaginous portions an obtuse angle is formed which projects into the antero-inferior wall and produces a narrowing of the lumen in this situation. The cartilaginous part, however, is connected to the bony part by fibrous tissue which renders the outer part of the meatus very movable, and therefore by drawing the auricula upward, backward, and slightly outward, the canal is rendered almost straight. In children the meatus is very short, and this should be remembered in introducing the speculum.

Through the speculum the greater part of the **tympanic membrane** (Fig. 1089) is visible. It is a pearly-gray membrane slightly glistening in the adult, placed obliquely so as to form with the floor of the meatus an angle of about  $55^\circ$ . At birth it is more horizontal and situated in almost the same plane as the base of the skull. The membrane is concave outward, and the point of deepest concavity—the **umbo**—is slightly below the centre. Running upward and slightly forward from the umbo is a reddish-yellow streak produced by the manubrium of the malleus. This streak ends above just below the roof of the meatus at a small white rounded prominence which is caused by the lateral process of the malleus projecting against the membrane. The anterior and posterior **malleolar folds** extend from the prominence to the circumference of the membrane and enclose the **pars flaccida**. Behind the streak caused by the manubrium of the malleus a second streak, shorter and very faint, can be distinguished; this is the **long crus**



of the incus. A narrow triangular patch extending downward and forward from the umbo reflects the light more brightly than any other part, and is usually described as the **cone of light**.




FIG. 1089.—The right tympanic membrane as seen through a speculum.




FIG. 1090.—Left temporal bone showing surface markings for the tympanic antrum (red), transverse sinus (blue), and facial nerve (yellow).

**Tympanic Antrum.**—The site of the tympanic antrum is indicated by the **suprameatal triangle** (Fig. 1090). This triangle is bounded above by the posterior root of the zygomatic arch; behind by a vertical line from the posterior border of the external acoustic meatus; in front and below by the upper margin of the meatus.

**The Neck** (Fig. 1091).—**Larynx and Trachea.**—In the receding angle below the chin, the **hyoid bone** (page 1276), situated opposite the fourth cervical vertebra, can easily be made out. A finger's breadth below it is the laryngeal prominence of the

**thyroid cartilage**; the space intervening between the hyoid bone and the thyroid cartilage is occupied by the **hyothyroid membrane**. The outlines of the thyroid cartilage are readily palpated; below its lower border is a depression corresponding to the middle **cricothyroid ligament**. The level of the vocal folds corresponds to the middle of the anterior margin of the thyroid cartilage. The anterior part of the cricoid cartilage forms an important landmark on the front of the neck; it lies opposite the sixth cervical vertebra, and indicates the junctions of pharynx with œsophagus, the larynx with trachea. Below the cricoid cartilage the **trachea** can be felt, though it is only in thin subjects that the separate rings can be distinguished; as a rule there are seven or eight rings above the jugular notch of the sternum, and of these the second, third, and fourth are covered by the isthmus of the thyroid gland.




FIG. 1091.—Side of neck, showing chief surface markings.

**Muscles.**—The posterior belly of **Digastricus** is marked out by a line from the tip of the mastoid process to the junction of the greater cornu and body of the hyoid bone; a line from this latter point to a point just lateral to the symphysis menti indicates the position of the anterior belly. The line of **Omothyroideus** begins at the lower border of the hyoid bone, curves downward and lateralward to cross **Sternocleidomastoideus** at the junction of its middle and lower thirds, *i. e.*, opposite the cricoid cartilage, and then runs more horizontally to the acromial end of the clavicle.

**Arteries.**—The position of the **common carotid artery** in the neck is indicated by a line drawn from the upper part of the sternal end of the clavicle to a point midway between the tip of the mastoid process and the angle of the mandible. From the clavicle to the upper border of the thyroid cartilage this line overlies the common carotid artery, beyond this it is over the external carotid. The **external carotid artery** may otherwise be marked out by the upper part of a line from the side of the cricoid cartilage to the front of the external acoustic meatus, arching the line slightly forward.

The points of origin of the main branches of the external carotid in the neck are all related to the tip of the greater cornu of the hyoid bone as follows: (1) the **superior thyroid**, immediately below it; (2) the **lingual**, on a level with it; (3) the **facial**, and (4) the **occipital** a little above and behind it.

The **subclavian artery** is indicated on the surface by a curved line, convex upward, from the sternoclavicular articulation to the middle of the clavicle. The highest point of the convexity is from 1 to 3 cm. above the clavicle.

**Veins.**—The surface marking for the **internal jugular vein** is slightly lateral and parallel to that for the common carotid artery. The position of the **external jugular vein** is marked out by a line from the angle of the mandible to the middle of the clavicle. A point on this line about 4 cm. above the clavicle indicates the spot where the vein pierces the deep fascia. The line of the **anterior jugular vein** begins close to the symphysis menti, runs downward parallel with and a little to one side of the middle line and, at a variable distance above the jugular notch, turns lateralward to the external jugular.

**Nerves.**—The **facial nerve** at its exit from the stylomastoid foramen is situated about 2.5 cm. from the surface, opposite the middle of the anterior border of the mastoid process; a horizontal line from this point to the ramus of the mandible overlies the stem of the nerve. To mark the site of the **accessory nerve** a line is drawn from the angle of the mandible to a point on the anterior border of Sternocleidomastoideus about 3 to 4 cm. below the apex of the mastoid process, or to the midpoint of the posterior border of the muscle; the line is continued across the posterior triangle to Trapezius.

The cutaneous branches of the cervical plexus as they emerge from the posterior border of Sternocleidomastoideus may be indicated as follows: the **lesser occipital** begins immediately above the midpoint of the border and runs along the border to the scalp; the **great auricular** and **cervical cutaneous** both start from the middle of the border, the former running upward toward the lobule of the auricula, the latter crossing Sternocleidomastoideus at right angles to its long axis; the **supra-clavicular** nerves emerge from immediately below the middle of the posterior border and run down over the clavicle. The **phrenic** nerve begins at the level of the middle of the thyroid cartilage and runs behind the clavicle about midway between the anterior and posterior borders of Sternocleidomastoideus.

The upper border of the **brachial plexus** is indicated by a line from the side of the cricoid cartilage to the middle of the clavicle.

**Submaxillary Gland.**—On either side of the neck the superficial portion of the submaxillary gland, as it lies partly under cover of the mandible, can be palpated.

### SURFACE ANATOMY OF THE BACK.

**Bones.**—The only subcutaneous parts of the vertebral column are the apices of the spinous processes. These are distinguishable at the bottom of a furrow which runs down the middle line of the back from the external occipital protuberance to the middle of the sacrum. In the **cervical region** the furrow is broad and ends below in a conspicuous projection caused by the spinous processes of the seventh cervical and first thoracic vertebræ. Above this, the spinous process of the sixth cervical vertebra sometimes forms a projection; the other cervical spinous processes are sunken, but that of the axis can be felt. In the **thoracic region** the furrow is shallow and during stooping disappears, and then the spinous processes become more or less visible; the markings produced by them are small and close together. In the **lumbar region** the furrow is deep and the situations of the spinous processes are frequently indicated by little pits or depressions, especially when the muscles in the loins are well-developed. In the **sacral region** the furrow is shallower, presenting a flattened area which ends below at the most prominent part of the dorsal surface of the sacrum, *i. e.*, the spinous process of the third sacral vertebra. At the bottom of the sacral furrow the irregular dorsal surface of the bone may be felt, and below this, in the deep groove running to the anus, the **coccyx**.

The only other portions of the vertebral column which can be felt from the surface are the transverse processes of the first, sixth, and seventh cervical vertebræ.

**Muscles.**—The muscles proper of the back are so obscured by those of the upper extremity (Fig. 1092) that they have very little influence on surface form. The **Splenii** by their divergence serve to broaden out the upper part of the back of the neck and produce a fulness in this situation. In the loin the **Sacrospinales**, bound




FIG. 1092.—Surface anatomy of the back.

down by the lumbodorsal fascia, form rounded vertical eminences which determine the depth of the spinal furrow and taper below to a point on the dorsal surface of the sacrum. The continuations of the **Sacrospinales** in the lower thoracic region form flattened planes which are gradually lost on passing upward.

SURFACE MARKINGS OF THE BACK.

**Bony Landmarks.**—In order to identify any particular spinous process it is customary to count from the prominence caused by the seventh cervical and first




FIG. 1093.—Diagram showing the relation of the medulla spinalis to the dorsal surface of the trunk. The bones are outlined in red.

Level of body of	No. of nerve.	Level of tip of spine of	Level of body of	No. of nerve.	Level of tip of spine of
C. 1	C. 1	..	T. 8	T. 9	7 T.
2	{ 2	..	9	10	8
3	{ 3	1 C.	10	11	9
4	4	2	..	12	10
5	5	3	11	L. 1	11
6	6	4	..	2	..
7	7	5	12	{ 3	..
..	8	6	..	{ 4	12
7	T. 1	7	..	{ 5	..
T. 1	2	1 T.	L. 1	{ S. 1	..
2	3	..	..	{ 2	..
3	4	2	..	{ 3	..
4	5	3	..	{ 4	1 L.
5	6	4	..	{ 5	..
6	7	5	L. 2	C. 1	..
7	8	6	..	..	..



thoracic; of these the latter is the more prominent. The root of the spine of the scapula is on a level with the tip of the spinous process of the third thoracic vertebra, and the inferior angle with that of the seventh. The highest point of the iliac crest is on a level with the spinous process of the fourth lumbar, and the posterior superior iliac spine with that of the second sacral.

The transverse process of the atlas is about 1 cm. below and in front of the apex of the mastoid process. The transverse process of the sixth cervical vertebra is opposite the cricoid cartilage; below it is the transverse process of the seventh and occasionally a cervical rib.




FIG. 1094.—Sagittal section of vertebral canal to show the lower end of the medulla spinalis and the filum terminale. (Testut.) *L<sub>1</sub>*, *L<sub>5</sub>*. First and fifth lumbar vertebrae. *S<sub>1</sub>*. Second sacral vertebra. 1. Dura mater. 2. Lower part of subarachnoid cavity. 3. Lower extremity of medulla spinalis. 4. Filum terminale internum, and 5, Filum terminale externum. 6. Attachment of filum terminale to first segment of coccyx.




FIG. 1095.—Scheme showing the relations of the regions of attachment of the spinal nerves to the vertebral spinous processes. (After Reid.)

**Medulla Spinalis.**—The position of the lower end of the medulla spinalis varies slightly with the movements of the vertebral column, but, in the adult, in the upright posture it is usually at the level of the spinous process of the second lumbar vertebra (Fig. 1093); at birth it lies at the level of the fourth lumbar.

The **subdural** and **subarachnoid cavities** end below opposite the spinous process of the third sacral vertebra (Fig. 1094).

**Spinal Nerves** (Fig. 1095).—The table on page 1293, after Macalister, shows the relations which the places of attachment of the nerves to the medulla spinalis present to the bodies and spinous processes of the vertebræ.

### SURFACE ANATOMY OF THE THORAX.

**Bones.**—The skeleton of the thorax is to a very considerable extent covered by muscles, so that in the strongly developed muscular subject it is for the most part concealed. In the emaciated subject, however, the ribs, especially in the lower and lateral regions, stand out as prominent ridges with the sunken intercostal spaces between them.

In the middle line, in front, the superficial surface of the **sternum** can be felt throughout its entire length at the bottom of a furrow, the sternal furrow, situated between the *Pectorales majores*. These muscles overlap the anterior surface somewhat, so that the whole width of the sternum is not subcutaneous, and this overlapping is greatest opposite the middle of the bone; the furrow, therefore, is wide at its upper and lower parts but narrow in the middle. At the upper border of the manubrium sterni is the **jugular notch**: the lateral parts of this notch are obscured by the tendinous origins of the *Sternocleidomastoidei*, which appear as oblique cords narrowing and deepening the notch. Lower down on the subcutaneous surface is a well-defined transverse ridge, the **sternal angle**; it denotes the junction of the manubrium and body. From the middle of the sternum the sternal furrow spreads out and ends at the junction of the body with the xiphoid process. Immediately below this is the **infrasternal notch**; between the sternal ends of the seventh costal cartilages, and below the notch, is a triangular depression, the epigastric fossa, in which the **xiphoid process** can be felt.

On either side of the sternum the costal cartilages and ribs on the front of the thorax are partly obscured by the *Pectoralis major*, through which, however, they can be felt as ridges with yielding intervals between them corresponding to the intercostal spaces. Of these spaces, that between the second and third ribs is the widest, the next two are somewhat narrower, and the remainder, with the exception of the last two, are comparatively narrow.

Below the lower border of the *Pectoralis major* on the front of the chest, the broad flat outlines of the ribs as they descend, and the more rounded outlines of the costal cartilages, are often visible. The lower boundary of the front of the thorax, which is most plainly seen by bending the body backward, is formed by the xiphoid process, the cartilages of the seventh, eighth, ninth, and tenth ribs, and the ends of the cartilages of the eleventh and twelfth ribs.

On either side of the thorax, from the axilla downward, the flattened external surfaces of the ribs may be defined. Although covered by muscles, all the ribs, with the exception of the first, can generally be followed without difficulty over the front and sides of the thorax. The first rib being almost completely covered by the clavicle can only be distinguished in a small portion of its extent.

At the back, the angles of the ribs lie on a slightly marked oblique line on either side of, and some distance from, the spinous processes of the vertebræ. The line diverges somewhat as it descends, and lateral to it is a broad convex surface caused by the projection of the ribs beyond their angles. Over this surface, except where covered by the scapula, the individual ribs can be distinguished.

**Muscles.**—The surface muscles covering the thorax belong to the musculature of the upper extremity (Figs. 1096, 1100), and will be described in that section (page 1319). There is, however, an area of practical importance bounded by these muscles. It is limited above by the lower border of *Trapezius*, below by the upper border of *Latissimus dorsi*, and laterally by the vertebral border of the scapula; the

floor is partly formed by *Pectoralis major*. If the scapula be drawn forward by folding the arm across the chest, and the trunk bent forward, parts of the sixth and seventh ribs and the interspace between them become subcutaneous and available for auscultation. The space is therefore known as the **triangle of auscultation**.




FIG. 1006. —The left side of the thorax.

**Mamma.** The size of the mamma is subject to great variations. In the adult nulliparous female, it extends vertically from the second to the sixth rib, and transversely from the side of the sternum to the midaxillary line. In the male and in the nulliparous female the **mammary papilla** is situated in the fourth interspace about 9 or 10 cm. from the middle line, or 2 cm. from the costochondral junction.

#### SURFACE MARKINGS OF THE THORAX.

**Bony Landmarks.** The second costal cartilage corresponding to the sternal angle is so readily found that it is used as a starting-point from which to count the ribs. The lower border of the *Pectoralis major* at its attachment corresponds to the fifth rib; the uppermost visible digitation of *Serratus anterior* indicates the sixth rib.

The jugular notch is in the same horizontal plane as the lower border of the body of the second thoracic vertebra; the sternal angle is at the level of the fifth thoracic vertebra, while the junction between the body and xiphoid process of the sternum corresponds to the fibrocartilage between the ninth and tenth thoracic vertebræ.

The influence of the obliquity of the ribs on horizontal levels in the thorax is well shown by the following line. "If a horizontal line be drawn around the body at the level of the inferior angle of the scapula, while the arms are at the sides, the

line would cut the sternum in front between the fourth and fifth ribs, the fifth rib, in the nipple line, and the ninth rib at the vertebral column." (Treves).

**Diaphragma.**—The shape and variations of the Diaphragma as seen by skiagraphy have already been described (page 497).

**Surface Lines.**—For clinical purposes, and for convenience of description, the surface of the thorax has been mapped out by arbitrary lines (Fig. 1101). On the front of the thorax the most important vertical lines are the **midsternal**, the middle line of the sternum; and the **mammary**, which runs vertically downward from a point midway between the centre of the jugular notch and the tip of the acromion. This latter line, if prolonged, is practically continuous with the lateral line on the front of the abdomen. Other vertical lines on the front of the thorax are the **lateral sternal** along the sternal margin, and the **parasternal** midway between the lateral sternal and the mammary.

On either side of the thorax the **anterior** and **posterior axillary lines** are drawn vertically from the corresponding axillary folds; the **midaxillary line** runs downward from the apex of the axilla.

On the posterior surface of the thorax the **scapular line** is drawn vertically through the inferior angle of the scapula.




FIG. 1097.—Front of thorax, showing surface relations of bones, lungs (purple), pleura (blue), and heart (red outline). P. Pulmonary valve. A. Aortic valve. B. Bicuspid valve. T. Tricuspid valve.

**Pleuræ** (Figs. 1097, 1098).—The lines of reflection of the pleuræ can be indicated on the surface. On the *right* side the line begins at the sternoclavicular articulation and runs downward and medialward to the midpoint of the junction between the manubrium and body of the sternum. It then follows the midsternal line to the lower end of the body of the sternum or on to the xiphoid process, where it turns lateralward and downward across the seventh sternocostal articulation. It crosses the eighth costochondral junction in the **mammary line**, the tenth rib in the **mid-axillary line**, and is prolonged thence to the spinous process of the twelfth thoracic vertebra.

On the *left* side, beginning at the sternoclavicular articulation, it reaches the midpoint of the junction between the manubrium and body of the sternum, and extends down the midsternal line in contact with that of the opposite side to the level of the fourth costal cartilage. It then diverges lateralward and is continued downward slightly lateral to the sternal border, as far as the sixth costal cartilage. Running downward and lateralward from this point it crosses the seventh costal cartilage, and from this onward it is similar to the line on the right side, but at a slightly lower level.

**Lungs** (Figs. 1097, 1098).—The **apex** of the lung is situated in the neck above the medial third of the clavicle. The height to which it rises above the clavicle varies very considerably, but is generally about 2.5 cm. It may, however, extend as high as 4 or 5 cm., or, on the other hand, may scarcely project above the level of this bone.




FIG. 1098.—Side of thorax, showing surface markings for bones, lungs (purple), pleura (blue), and spleen (green).

In order to mark out the **anterior borders** of the lungs a line is drawn from each apex point—2.5 cm. above the clavicle and rather nearer the anterior than the posterior border of *Sternocleidomastoideus*—downward and medialward across the sternoclavicular articulation and manubrium sterni until it meets, or almost meets, its fellow of the other side at the midpoint of the junction between the manubrium and body of the sternum. From this point the two lines run downward, practically along the midsternal line, as far as the level of the fourth costal cartilages. The continuation of the anterior border of the *right* lung is marked by a prolongation of its line vertically downward to the level of the sixth costal cartilage, and then it turns lateralward and downward. The line on the *left* side curves lateralward and downward across the fourth sternocostal articulation to reach the parasternal line at the fifth costal cartilage, and then turns medialward and downward to the sixth sternocostal articulation.



In the position of expiration the **lower border** of the lung may be marked by a slightly curved line with its convexity downward, from the sixth sternocostal junction to the tenth thoracic spinous process. This line crosses the mammary line at the sixth, and the midaxillary line at the eighth rib.

The **posterior borders** of the lungs are indicated by lines drawn from the level of the spinous process of the seventh cervical vertebra, down either side of the vertebral column, across the costovertebral joints, as low as the spinous process of the tenth thoracic vertebra.

The position of the **oblique fissure** in either lung can be shown by a line drawn from the spinous process of the second thoracic vertebra around the side of the thorax to the sixth rib in the mammary line; this line corresponds roughly to the line of the vertebral border of the scapula when the hand is placed on the top of the head. The **horizontal fissure** in the right lung is indicated by a line drawn from the midpoint of the preceding, or from the point where it cuts the midaxillary line, to the midsternal line at the level of the fourth costal cartilage.

**Trachea.**—This may be marked out on the back by a line from the spinous process of the sixth cervical to that of the fourth thoracic vertebra where it bifurcates; from its bifurcation the two bronchi are directed downward and lateralward. In front, the point of bifurcation corresponds to the sternal angle.

**Œsophagus.**—The extent of the œsophagus may be indicated on the back by a line from the sixth cervical to the level of the ninth thoracic spinous process, 2.5 cm. to the left of the middle line.

**Heart.**—The outline of the heart in relation to the front of the thorax (Figs 1097, 1099) can be represented by a quadrangular figure. The apex of the heart is first determined, either by its pulsation or as a point in the fifth interspace, 9 cm. to the left of the midsternal line. The other three points are: (a) the seventh right sternocostal articulation; (b) a point on the upper border of the third right costal cartilage 1 cm. from the right lateral sternal line; (c) a point on the lower border of the second left costal cartilage 2.5 cm. from the left lateral sternal line. A line joining the apex to point (a) and traversing the junction of the body of the sternum with the xiphoid process represents the lowest limit of the heart—its acute margin. The right and left borders are represented respectively by lines joining (a) to (b) and the apex to (c); both lines are convex lateralward, but the convexity is more marked on the right where its summit is 4 cm. distant from the midsternal line opposite the fourth costal cartilage.

A portion of the area of the heart thus mapped out is uncovered by lung, and therefore gives a dull note on percussion; the remainder being overlapped by lung gives a more or less resonant note. The former is known as the area of superficial cardiac dulness, the latter as the area of deep cardiac dulness. The area of superficial cardiac dulness is somewhat triangular; from the apex of the heart two lines are drawn to the midsternal line, one to the level of the fourth costal cartilage, the other to the junction between the body and xiphoid process; the portion of the midsternal line between these points is the base of the triangle. Latham lays down the following rule as a sufficient practical guide for the definition of the area of superficial dulness. "Make a circle of two inches in diameter around a point midway between the nipple and the end of the sternum."

The **coronary sulcus** can be indicated by a line from the third left, to the sixth right, sternocostal joint. The **anterior longitudinal sulcus** is a finger's breadth to the right of the left margin of the heart.

The position of the various orifices is as follows: The **pulmonary orifice** is situated in the upper angle of the third left sternocostal articulation; the **aortic orifice** is a little below and medial to this, close to the articulation. The **left atrio-ventricular opening** is opposite the fourth costal cartilage, and rather to the left of the midsternal line; the **right atrioventricular opening** is a little lower, opposite

the fourth interspace of the right side. The lines indicating the atrioventricular openings are slightly below and parallel to the line of the coronary sulcus.

**Arteries.**—The line of the **ascending aorta** begins slightly to the left of the midsternal line opposite the third costal cartilage and extends upward and to the right to the upper border of the second right costal cartilage. The beginning of the **aortic arch** is indicated by a line from this latter point to the midsternal line about 2.5 cm. below the jugular notch. The point on the midsternal line is opposite the summit of the arch, and a line from it to the right sternoclavicular articulation represents the site of the **innominate artery**, while another line from a point slightly to the left of it and passing through the left sternoclavicular articulation indicates the position of the **left common carotid artery** in the thorax.




FIG. 1099.—Diagram showing relations of opened heart to front of thoracic wall. *Ant.* Anterior segment of tricuspid valve. *A.O.* Aorta. *A.P.* Anterior papillary muscle. *In.* Innominate artery. *L.C.C.* Left common carotid artery. *L.S.* Left subclavian artery. *L.V.* Left ventricle. *P.A.* Pulmonary artery. *R.A.* Right atrium. *R.V.* Right ventricle. *V.S.* Ventricular septum.

The **internal mammary artery** descends behind the first six costal cartilages about 1 cm. from the lateral sternal line.

**Veins.**—The line of the **right innominate vein** crosses the right sternoclavicular joint and the upper border of the first right costal cartilage about 1 cm. from the lateral sternal line; that of the **left innominate vein** extends from the left sternoclavicular articulation to meet the right at the upper border of the first right costal cartilage. The junction of the two lines indicates the origin of the **superior vena cava**, the line of which is continued vertically down to the level of the third right costal cartilage. The end of the **inferior vena cava** is situated opposite the upper margin of the sixth right costal cartilage about 2 cm. from the midsternal line.

## SURFACE ANATOMY OF THE ABDOMEN.

**Skin.**—The skin of the front of the abdomen is thin. In the male it is often thickly hair-clad, especially toward the lower part of the middle line; in the female the hairs are confined to the pubes. Just below the line of the iliac crest, especially marked in fat subjects, is a shallow groove termed the *iliac furrow*, while in the site of the inguinal ligament a sharper fold known as the *fold of the groin* is easily distinguishable.

After distension of the abdomen from pregnancy or other causes the skin commonly presents transverse white lines which are quite smooth, being destitute of papillæ; these are known as *striae gravidarum* or *striae albicantes*. The *linea nigra* of pregnancy is often seen as a pigmented brown streak in the middle line between the umbilicus and symphysis pubis.

In the middle line of the front of the abdomen is a shallow furrow which extends from the junction between the body of the sternum with the xiphoid process to a short distance below the umbilicus; it corresponds to the *linea alba*. The umbilicus is situated in the middle line, but it varies in position as regards its height; in an adult subject it is always placed above the middle point of the body, and in a normal well-nourished subject is from 2 to 2.5 cm. above the level of the tubercles of the iliac crests.

**Bones.**—The bones in relation with the surface of the abdomen are (1) the lower part of the vertebral column and the lower ribs and (2) the pelvis; the former have already been described (page 1291), the latter will be considered with the lower limb.

**Muscles** (Fig. 1100).—The only muscles of the abdomen which have any considerable influence on surface form are the *Obliquus externus* and the *Rectus*. The upper digitations of origin of *Obliquus externus* are well-marked in a muscular subject, interdigitating with those of *Serratus anterior*; the lower digitations are covered by the border of *Latissimus dorsi* and are not visible. The attachment of the *Obliqui externus* and *internus* to the crest of the ilium forms a thick oblique roll which determines the *iliac furrow*. Sometimes on the front of the lateral region of the abdomen an undulating line marks the passing of the muscular fibres of the *Obliquus externus* into its aponeurosis. The lateral margin of the *Obliquus externus* is separated from that of the *Latissimus dorsi* by a small triangular interval—the *lumbar triangle*—the base of which is formed by the iliac crest, and its floor by *Obliquus internus*.

The lateral margin of *Rectus abdominis* is indicated by the *linea semilunaris*, which may be exactly defined by putting the muscle into action. The surface of the *Rectus* presents three transverse furrows, the *tendinous inscriptions*: the upper two of these, viz., one opposite, or a little below, the tip of the xiphoid process, and the other midway between this point and the umbilicus, are usually well-marked; the third, opposite the umbilicus, is not so distinct. Between the two *Recti* the *linea alba* can be palpated from the xiphoid process to a point just below the umbilicus; it is represented by a distinct dip between the muscles: beyond this the muscles are in apposition.

**Vessels.**—In thin subjects the pulsation of the *abdominal aorta* can be readily felt by making deep pressure in the middle line above the umbilicus.

**Viscera.**—Under normal conditions the various portions of the *digestive tube* cannot be identified by simple palpation. Peristalsis of the coils of small intestine can be observed in some persons with extremely thin abdominal walls when some degree of constipation exists. In cases of constipation it is sometimes possible to trace portions of the great intestine by feeling the fecal masses within the gut. In thin persons with relaxed abdominal walls the *iliac colon* can be felt in the left

iliac region—rolling under the fingers when empty and forming a distinct tumor when distended.

The greater part of the liver lies under cover of the lower ribs and their cartilages, but in the epigastric fossa it comes in contact with the abdominal wall. The




FIG. 1100.—Surface anatomy of the front of the thorax and abdomen.

position of the liver varies according to the posture of the body. In the erect posture in the adult male the edge of the liver projects about 1 cm. below the lower margin of the right costal cartilages, and its inferior margin can often be felt in this situation if the abdominal wall is thin. In the supine position the liver

recedes above the margin of the ribs and cannot then be detected by the finger; in the prone position it falls forward and is then generally palpable in a patient with loose and lax abdominal walls. Its position varies with the respiratory movements; during a deep inspiration it descends below the ribs; in expiration it is raised. Pressure from without, as in tight lacing, by compressing the lower part of the chest, displaces the liver considerably, its anterior edge frequently extending as low as the crest of the ilium. Again its position varies greatly with the state of the stomach and intestines; when these are empty the liver descends, when they are distended it is pushed upward.

The **pancreas** can sometimes be felt, in emaciated subjects, when the stomach and colon are empty, by making deep pressure in the middle line about 7 or 8 cm. above the umbilicus.

The **kidneys** being situated at the back of the abdominal cavity and deeply placed cannot be palpated unless enlarged or misplaced.

#### ✓ SURFACE MARKINGS OF THE ABDOMEN.

**Bony Landmarks.**—Above, the chief bony markings are the xiphoid process, the lower six costal cartilages, and the anterior ends of the lower six ribs. The junction between the body of the sternum and the xiphoid process is on the level of the tenth thoracic vertebra. Below, the main landmarks are the symphysis pubis and the pubic crest and tubercle, the anterior superior iliac spine, and the iliac crest.

**Muscles** (Fig. 1106).—The Rectus lies between the linea alba and the linea semilunaris; the former is indicated by the middle line, the latter by a curved line, convex lateralward, from the tip of the cartilage of the ninth rib to the pubic tubercle; at the level of the umbilicus the linea semilunaris is about 7 cm. from the middle line. The line indicating the junction of the muscular fibres of Obliquus externus with its aponeurosis extends from the tip of the ninth costal cartilage to a point just medial to the anterior superior iliac spine.

The **umbilicus** is at the level of the fibrocartilage between the third and fourth lumbar vertebræ.

The **subcutaneous inguinal ring** is situated 1 cm. above and lateral to the pubic tubercle; the **abdominal inguinal ring** lies 1 to 2 cm. above the middle of the inguinal ligament. The position of the **inguinal canal** is indicated by a line joining these two points.

**Surface Lines.**—For convenience of description of the viscera and of reference to morbid conditions of the contained parts, the abdomen is divided into nine regions, by imaginary planes, two horizontal and two sagittal, the edges of the planes being indicated by lines drawn on the surface of the body (Fig. 1101). In the older method the upper, or subcostal, horizontal line encircles the body at the level of the lowest points of the tenth costal cartilages; the lower, or intertubercular, is a line carried through the highest points of the iliac crests seen from the front, *i. e.*, through the tubercles on the iliac crests about 5 cm. behind the anterior superior spines. An alternative method is that of Addison, who adopts the following lines:

(1) An upper transverse, the **transpyloric**, halfway between the jugular notch and the upper border of the symphysis pubis; this indicates the margin of the transpyloric plane, which in most cases cuts through the pylorus, the tips of the ninth costal cartilages and the lower border of the first lumbar vertebra; (2) a lower transverse line midway between the upper transverse and the upper border of the symphysis pubis; this is termed the **transtubercular**, since it practically corresponds to that passing through the iliac tubercles; behind, its plane cuts the body of the fifth lumbar vertebra.



By means of these horizontal planes the abdomen is divided into three zones named from above, the **subcostal**, **umbilical**, and **hypogastric zones**. Each of these is further subdivided into three regions by the two sagittal planes, which are indicated on the surface by a right and a left lateral line drawn vertically through points halfway between the anterior superior iliac spines and the middle line. The middle region of the upper zone is called the **epigastric**, and the two lateral regions




FIG. 1101.—Surface lines of the front of the thorax and abdomen.

the **right** and **left hypo-chondriac**. The central region of the middle zone is the **umbilical**, and the two lateral regions the **right** and **left lumbar**. The middle region of the lower zone is the **hypogastric** or **pubic**, and the lateral are the **right** and **left iliac** or **inguinal**. The middle regions, viz., **epigastric**, **umbilical**, and **pubic**, can each be divided into right and left portions by the middle line. In the following description of the viscera the regions marked out by Addison's lines are those referred to.

**Stomach** (Fig. 1103).—The shape of the stomach is constantly undergoing alteration; it is affected by the particular phase of the process of gastric digestion, by




FIG. 1102.—Radiographs of a moderately distended stomach, showing the influence of posture. (Modified from Herta.) A. With the patient in the erect posture. B. With the patient lying down.

the state of the surrounding viscera, and by the amount and character of its contents. Its position also varies with that of the body (Fig. 1102), so that it is




FIG. 1103.—Front of abdomen, showing surface markings for liver, stomach, and great intestine.

impossible to indicate it on the surface with any degree of accuracy. The measurements given refer to a moderately filled stomach with the body in the supine position.

The cardiac orifice is opposite the seventh left costal cartilage about 2.5 cm. from the side of the sternum; it corresponds to the level of the tenth thoracic vertebra. The pyloric orifice is on the transpyloric line about 1 cm. to the right of the middle line, or alternately 5 cm. below the seventh right sternocostal articulation; it is at the level of the first lumbar vertebra. A curved line, convex downward and to the left, joining these points indicates the lesser curvature. In the left lateral line the fundus of the stomach reaches as high as the fifth interspace or the sixth costal cartilage, a little below the apex of the heart. To indicate the greater curvature a curved line is drawn from the cardiac orifice to the summit of the fundus, thence downward and to the left, finally turning medialward to the pyloric orifice, but passing, on its way, through the intersection of the left lateral with the transpyloric line. The portion of the stomach which is in contact with the abdominal wall can be represented roughly by a triangular area the base of which is formed by a line drawn from the tip of the tenth left costal cartilage to the tip of the ninth right cartilage, and the sides by two lines drawn from the end of the eighth left costal cartilage to the ends of the base line.




FIG. 1104.—Front of abdomen, showing surface markings for duodenum, pancreas, and kidneys. *A A'*. Plane through joint between body and xiphoid process of sternum. *B B'*. Plane midway between *A A'* and transpyloric plane. *C C'*. Plane midway between transpyloric and transtuberular planes.

A space of some clinical importance—the **space of Traube**—overlies the stomach and may be thus indicated. It is semilunar in outline and lies within the following boundaries: the lower edge of the left lung, the anterior border of the spleen, the left costal margin and the inferior margin of the left lobe of the liver.

**Duodenum** (Fig. 1104).—The superior part is horizontal and extends from the pylorus to the right lateral line; the descending part is situated medial to the right lateral line, from the transpyloric line to a point midway between the transpyloric and transtuberular lines. The horizontal part runs with a slight upward slope from the end of the descending part to the left of the middle line; the ascending part is vertical, and reaches the transpyloric line, where it ends in the duodenojejunal flexure, about 2.5 cm. to the left of the middle line.

**Small Intestine.**—The coils of small intestine occupy the front of the abdomen. For the most part the coils of the jejunum are situated on the left side, *i. e.*, in the left lumbar and iliac regions, and in the left half of the umbilical region. The coils of the ileum lie toward the right in the right lumbar and iliac regions, in the right

half of the umbilical region, and in the hypogastric region; a portion of the ileum is within the pelvis. The end of the ileum, *i. e.*, the **ileocolic junction**, is slightly below and medial to the intersection of the right lateral and transtubercular lines.

**Cecum and Vermiform Process.**—The **cecum** is in the right iliac and hypogastric regions; its position varies with its degree of distension, but the midpoint of a line drawn from the right anterior superior iliac spine to the upper margin of the symphysis pubis will mark approximately the middle of its lower border.

The position of the base of the **vermiform process** is indicated by a point on the lateral line on a level with the anterior superior iliac spine.

**Ascending Colon.**—The ascending colon passes upward through the right lumbar region, lateral to the right lateral line. The **right colic flexure** is situated in the upper and right angle of intersection of the subcostal and right lateral lines.

**Transverse Colon.**—The transverse colon crosses the abdomen on the confines of the umbilical and epigastric regions, its lower border being on a level slightly above the umbilicus, its upper border just below the greater curvature of the stomach.

**Descending Colon.**—The **left colic flexure** is situated in the upper left angle of the intersection between the left lateral and transpyloric lines. The descending colon courses down through the left lumbar region, lateral to the left lateral line, as far as the iliac crest (see footnote p. 1181).

**Iliac Colon.**—The line of the iliac colon is from the end of the descending colon to the left lateral line at the level of the anterior superior iliac spine.

**Liver** (Fig. 1103).—The upper limit of the right lobe of the liver, in the middle line, is at the level of the junction between the body of the sternum and the xiphoid process; on the right side the line must be carried upward as far as the fifth costal cartilage in the mammary line, and then downward to reach the seventh rib at the side of the thorax. The upper limit of the left lobe can be defined by continuing this line downward and to the left to the sixth costal cartilage, 5 cm. from the middle line. The lower limit can be indicated by a line drawn 1 cm. below the lower margin of the thorax on the right side as far as the ninth costal cartilage, thence obliquely upward to the eighth left costal cartilage, crossing the middle line just above the transpyloric plane and finally, with a slight left convexity, to the end of the line indicating the upper limit.

According to Birmingham the limits of the normal liver may be marked out on the surface of the body in the following manner. Take three points: (a) 1.25 cm. below the right nipple; (b) 1.25 cm. below the tip of the tenth rib; (c) 2.5 cm. below the left nipple. Join (a) and (c) by a line slightly convex upward; (a) and (b) by a line slightly convex lateralward; and (b) and (c) by a line slightly convex downward.

The fundus of the **gall-bladder** approaches the surface behind the anterior end of the ninth right costal cartilage close to the lateral margin of the Rectus abdominis.

**Pancreas** (Fig. 1104).—The pancreas lies in front of the second lumbar vertebra. Its head occupies the curve of the duodenum and is therefore indicated by the same lines as that viscus; its neck corresponds to the pylorus. Its body extends along the transpyloric line, the bulk of it lying above this line to the tail which is in the left hypochondriac region slightly to the left of the lateral line and above the transpyloric.

**Spleen** (Figs. 1098, 1105).—To map out the spleen the tenth rib is taken as representing its long axis; vertically it is situated between the upper border of the ninth and the lower border of the eleventh ribs. The highest point is 4 cm. from the middle line of the back at the level of the tip of the ninth thoracic spinous process; the lowest point is in the midaxillary line at the level of the first lumbar spinous process.

**Kidneys** (Figs. 1104, 1105).—The right kidney usually lies about 1 cm. lower than the left, but for practical purposes similar surface markings are taken for each.

On the front of the abdomen the upper pole lies midway between the plane of the lower end of the body of the sternum and the transpyloric plane, 5 cm. from the middle line.




FIG. 1105.—Back of lumbar region, showing surface markings for kidneys, ureters, and spleen. The lower portions of the lung and pleura are shown on the right side.

The lower pole is situated midway between the transpyloric and intertubercular planes, 7 cm. from the middle line. The hilus is on the transpyloric plane, 5 cm. from the middle line. Round these three points a kidney-shaped figure 4 cm. to 5 cm. broad is drawn, two thirds of which lie medial to the lateral line. To indicate the position of the kidney from the back, the parallelogram of Morris is used; two vertical lines are drawn, the first 2.5 cm., the second 9.5 cm. from the middle line; the parallelogram is completed by two horizontal lines drawn respectively at the levels of the tips of the spinous process of the eleventh thoracic and the lower border of the spinous process of the

third lumbar vertebra. The hilus is 5 cm. from the middle line at the level of the spinous process of the first lumbar vertebra.




FIG. 1106.—Front of abdomen, showing surface markings for arteries and inguinal canal.

**Ureters.**—On the front of the abdomen, the line of the ureter runs from the hilus of the kidney to the pubic tubercle; on the back, from the hilus vertically downward, passing practically through the posterior superior iliac spine (Fig. 1105).



**Vessels** (Fig. 1106).—The **inferior epigastric artery** can be marked out by a line from a point midway between the anterior superior iliac spine and the pubic symphysis to the umbilicus. This line also indicates the lateral boundary of **Hesselbach's triangle**—an area of importance in connection with inguinal hernia; the other boundaries are the lateral edge of Rectus abdominis, and the medial half of the inguinal ligament. The line of the **abdominal aorta** begins in the middle line about 4 cm. above the transpyloric line and extends to a point 2 cm. below and to the left of the umbilicus—or more accurately to a point 2 cm. to the left of the middle line on a line which passes through the highest points of the iliac crests (*AA'*, Fig. 1106). The point of termination of the abdominal aorta corresponds to the level of the fourth lumbar vertebra; a line drawn from it to a point midway between the anterior superior iliac spine and the symphysis pubis indicates the common and external iliac arteries. The **common iliac** is represented by the upper third of this line, the **external iliac** by the remaining two-thirds.

Of the larger branches of the abdominal aorta, the **coeliac artery** is 4 cm., the **superior mesenteric** 2 cm. above the transpyloric line; the **renal arteries** are 2 cm. below the same line. The **inferior mesenteric** artery is 4 cm. above the bifurcation of the abdominal aorta.

**Nerves**.—The thoracic nerves on the anterior abdominal wall are represented by lines continuing those of the bony ribs. The termination of the seventh nerve is at the level of the xiphoid process, the tenth reaches the vicinity of the umbilicus, the twelfth ends about midway between the umbilicus and the upper border of the symphysis pubis. The first lumbar is parallel to the thoracic nerves; its iliohypogastric branch becomes cutaneous above the subcutaneous inguinal ring; its ilioinguinal branch at the ring.

#### SURFACE ANATOMY OF THE PERINEUM.

**Skin**.—In the middle line of the posterior part of the perineum and about 4 cm. in front of the tip of the coccyx is the anal orifice. The junction of the mucous membrane of the anal canal with the skin of the perineum is marked by a white line which indicates also the line of contact of the external and internal Sphincters. In the anterior part of the perineum the external genital organs are situated. The skin covering the scrotum is rough and corrugated, but over the penis it is smooth; extending forward from the anus on to the scrotum and penis is a median ridge which indicates the scrotal raphé. In the **female** are seen the skin reduplications forming the labia majora and minora laterally, the frenulum of the labia behind, and the prepuce of the clitoris in front; still more anteriorly is the mons pubis.

**Bones**.—In the antero-lateral boundaries of the perineum, the whole outline of the pubic arch can be readily traced ending in the ischial tuberosities. Behind in the middle line is the tip of the coccyx.

**Muscles and Ligaments**.—The margin of the **Gluteus maximus** forms the posterolateral boundary, and in thin subjects, by pressing deeply, the sacrotuberous ligament can be felt through the muscle. The only other muscles influencing surface form are the **Ischiocavernosus** covering the crus penis, which lies on the side of the pubic arch, and the **Sphincter ani externus**, which, in action, closes the anal orifice and causes a puckering of the skin around it.

#### SURFACE MARKINGS OF THE PERINEUM.

A line drawn transversely across in front of the ischial tuberosities divides the perineum into a posterior or rectal, and an anterior or urogenital, triangle. This line passes through the central point of the perineum, which is situated about

2.5 cm. in front of the centre of the anal aperture or, in the male, midway between the anus and the reflection of the skin on to the scrotum.

**Rectum and Anal Canal.**—A finger inserted through the anal orifice is grasped by the Sphincter ani externus, passes into the region of the Sphincter ani internus, and higher up encounters the resistance of the Puborectalis; beyond this it may reach the lowest of the transverse rectal folds. In front, the urethral bulb and membranous part of the urethra are first identified, and then about 4 cm. above the anal orifice the prostate is felt; beyond this the vesiculæ seminales, if enlarged, and the fundus of the bladder, when distended, can be recognized. On either side is the ischiorectal fossa. Behind are the anococcygeal body, the pelvic surfaces of the coccyx and lower end of the sacrum, and the sacrospinous ligaments (Fig 1107).




FIG. 1107.—Median sagittal section of male pelvis.

In the female the posterior wall and fornix of the vagina, and the cervix and body of the uterus can be felt in front, while somewhat laterally the ovaries can just be reached.

**Male Urogenital Organs.**—The *corpora cavernosa penis* can be followed backward to the crura which are attached to the sides of the pubic arch. The *glans penis*, covered by the prepuce, and the external urethral orifice can be examined, and the course of the urethra traced along the under surface of the penis to the bulb which is situated immediately in front of the central point of the perineum. Through the wall of the *scrotum* on either side the *testis* can be palpated; it lies toward the back of the scrotum, and along its posterior border the *epididymis* can be felt; passing upward along the medial side of the epididymis is the *spermatic cord*, which can be traced upward to the subcutaneous inguinal ring.

By means of a sound the general topography of the urethra and bladder can

be investigated; with the urethroscope the interior of the urethra can be illuminated and viewed directly; with the cystoscope the interior of the bladder is in a similar manner illuminated for visual examination. In the bladder the main points to which attention is directed are the **trigone**, the **torus uretericus**, the **plicae uretericae**, and the openings of the **ureters** and **urethra** (see Fig. 1033).




FIG. 1108.—External genital organs of female. The labia minora have been drawn apart.

**Female Urogenital Organs.**—In the **puddendal cleft** (Fig. 1108) between the labia minora are the openings of the **vagina** and **urethra**. In the virgin the vaginal opening is partly closed by the **hymen**—after coitus the remains of the hymen are represented by the **carunculae hymeneales**. Between the hymen and the frenulum of the labia is the **fossa navicularis**, while in the groove between the hymen and the labium minus, on either side, the small opening of the **greater vestibular (Bartholin's) gland** can be seen. These glands when enlarged can be felt on either side of the posterior part of the vaginal orifice. By inserting a finger into the vagina the following structures can be examined through its wall (Fig. 1109). Behind, from below upward, are the **anal canal**, the **rectum**, and the **rectouterine excavation**. Projecting into the roof of the vagina is the vaginal portion of the **cervix uteri** with the external uterine orifice; in front of and behind the cervix the anterior and posterior **vaginal fornices** respectively can be examined. With the finger in the vagina and the other hand on the abdominal wall the whole of the **cervix** and **body of the uterus**, the **uterine tubes**, and the **ovaries** can be palpated. If a speculum be introduced into the vagina, the walls of the passage, the vaginal portion of the cervix, and the external uterine orifice can all be exposed for visual examination.

The external urethral orifice lies in front of the vaginal opening; the angular gap in which it is situated between the two converging labia minora is termed the

**vestibule.** The urethral canal in the female is very dilatable and can be explored with the finger. About 2.5 cm. in front of the external orifice of the urethra are the **glans** and **prepuce of the clitoris**, and still farther forward is the **mons pubis**.




FIG. 1109.—Median sagittal section of female pelvis.

### ✓ SURFACE ANATOMY OF THE UPPER EXTREMITY.

**Skin.**—The skin covering the shoulder and arm is smooth and very movable on the underlying structures. In the axilla there are numerous hairs and many sudoriferous and sebaceous glands. Over the medial side and front of the forearm the skin is thin and smooth, and contains few hairs but many sudoriferous glands; over the lateral side and back of the arm and forearm it is thicker, denser, and contains more hairs but fewer sudoriferous glands. In the region of the olecranon it is thick and rough, and is very loosely connected to the underlying tissue so that it falls into transverse wrinkles when the forearm is extended. At the front of the wrist there are three transverse furrows in the skin; they correspond respectively from above downward to the positions of the styloid process of the ulna, the wrist-joint, and the midcarpal joint.

The skin of the palm of the hand differs considerably from that of the forearm. At the wrist it suddenly becomes hard and dense and covered with a thick layer of epidermis; on the thenar eminence these characteristics are less marked than elsewhere. In spite of its hardness and density the skin of the palm is exceedingly sensitive and very vascular, but it is destitute of hairs and sebaceous glands. It is tied down by fibrous bands along the lines of flexion of the digits, exhibiting certain furrows of a permanent character. One of these, starting in front of the

wrist at the tuberosity of the navicular bone, curves around the thenar eminence and ends on the radial border of the hand a little above the metacarpophalangeal joint of the index finger. A second line begins at the end of the first and extends obliquely across the palm to reach the ulnar border about the middle of the fifth metacarpal bone. A third line begins at the ulnar border about 2.5 cm. distal to the end of the second and extends across the heads of the fifth, fourth, and third metacarpal bones. The proximal segments of the fingers are joined to one another on the volar aspect by folds of skin constituting the "web" of the fingers; these folds extend across about the level of the centres of the proximal phalanges and their free margins are continuous with the transverse furrows at the roots of the fingers. Since the web is confined to the volar aspect the fingers appear shorter when viewed from in front than from behind.

Over the fingers and thumb the skin again becomes thinner, especially at the flexures of the joints (where it is crossed by transverse furrows) and over the terminal phalanges; it is disposed on numerous ridges in consequence of the arrangement of the papillæ in it. These ridges form, in different individuals, distinctive and permanent patterns which can be used for purposes of identification. The superficial fascia in the palm of the hand is made up of dense fibro-fatty tissue which binds the skin so firmly to the palmar aponeurosis that very little movement is permitted between the two.

On the back of the hand and fingers the subcutaneous tissue is lax, so that the skin is freely movable on the underlying parts. Over the interphalangeal joints the skin is very loose and is thrown into transverse wrinkles when the fingers are extended.

**Bones.**—The **clavicle** can be felt throughout its entire length. The enlarged sternal extremity projects above the upper margin of the sternum at the side of the jugular notch, and from this the body of the bone can be traced lateralward immediately under the skin. The medial part is convex forward, but the surface is partially obscured by the attachments of Sternocleidomastoideus and Pectoralis major; the lateral third is concave forward and ends at the acromion of the scapula in a slight enlargement. The clavicle is almost horizontal when the arm is lying by the side, although in muscular subjects it may incline a little upward at its acromial end, which is on a plane posterior to the sternal end.

The only parts of the **scapula** that are truly subcutaneous are the spine and acromion, but the coracoid process, the vertebral border, the inferior angle, and to a lesser extent the axillary border can also be readily defined. The acromion and spine are easily recognizable throughout their entire extent, forming with the clavicle the arch of the shoulder. The acromion forms the point of the shoulder; it joins the clavicle at an acute angle—the acromial angle—slightly medial to, and behind the tip of the acromion. The spine can be felt as a distinct ridge, marked on the surface as an oblique depression which becomes less distinct and ends in a slight dimple a little lateral to the spinous processes of the vertebræ. Below this point the vertebral border can be traced downward and lateralward to the inferior angle, which can be identified although covered by Latissimus dorsi. From the inferior angle the axillary border can usually be traced upward through its thick muscular covering, forming with its enveloping muscles the posterior fold of the axilla. The coracoid process is situated about 2 cm. below the junction of the intermediate and lateral thirds of the clavicle; it is covered by the anterior border of Deltoideus, and thus lies a little lateral to the infraclavicular fossa or depression which marks the interval between the Pectoralis major and Deltoideus.

The **humerus** is almost entirely surrounded by muscles, and the only parts which are strictly subcutaneous are small portions of the medial and lateral epicondyles; in addition to these, however, the tubercles and a part of the head of the bone can be felt under the skin and muscles by which they are covered. Of these,



the greater tubercle forms the most prominent bony point of the shoulder, extending beyond the acromion; it is best recognized when the arm is lying passive by the side, for if the arm be raised it recedes under the arch of the shoulder. The lesser tubercle, directed forward, is medial to the greater and separated from it by the intertubercular groove, which can be made out by deep pressure. When the arm is abducted the lower part of the head of the humerus can be examined by pressing deeply in the axilla. On either side of the elbow-joint and just above it are the medial and lateral epicondyles. Of these, the former is the more prominent, but the medial supracondylar ridge passing upward from it is much less marked than the lateral, and as a rule is not palpable; occasionally, however, the hook-shaped supracondylar process (page 312) is found on this border. The position of the lateral epicondyle is best seen during semiflexion of the forearm, and is indicated by a depression; from it the strongly marked lateral supracondylar ridge runs upward.

The most prominent part of the **ulna**, the olecranon, can always be identified at the back of the elbow-joint. When the forearm is flexed the upper quadrilateral surface is palpable, but during extension it recedes into the olecranon fossa. During extension the upper border of the olecranon is slightly above the level of the medial epicondyle and nearer to this than to the lateral; when the forearm is fully flexed the olecranon and the epicondyles form the angles of an equilateral triangle. On the back of the olecranon is a smooth triangular subcutaneous surface, and running down the back of the forearm from the apex of this triangle the prominent dorsal border of the ulna can be felt in its whole length: it has a sinuous outline, and is situated in the middle of the back of the limb above; but below, where it is rounded off, it can be traced to the small subcutaneous surface of the styloid process on the medial side of the wrist. The styloid process forms a prominent tubercle continuous above with the dorsal border and ending below in a blunt apex at the level of the wrist-joint; it is most evident when the hand is in a position midway between supination and pronation. When the forearm is pronated another prominence, the head of the ulna, appears behind and above the styloid process.

Below the lateral epicondyle of the humerus a portion of the head of the **radius** is palpable; its position is indicated on the surface by a little dimple, which is best seen when the arm is extended. If the finger be placed in this dimple and the semiflexed forearm be alternately pronated and supinated the head of the radius will be felt distinctly, rotating in the radial notch. The upper half of the body of the bone is obscured by muscles; the lower half, though not subcutaneous, can be readily examined, and if traced downward is found to end in a lozenge-shaped convex surface on the lateral side of the base of the styloid process; this is the only subcutaneous part of the bone, and from its lower end the apex of the styloid process bends medialward toward the wrist. About the middle of the dorsal surface of the lower end of the radius is the dorsal radial tubercle, best perceived when the wrist is slightly flexed; it forms the lateral boundary of the oblique groove for the tendon of *Extensor pollicis longus*.

On the front of the wrist are two subcutaneous eminences, one, on the radial side, the larger and flatter, produced by the tuberosity of the **navicular** and the ridge on the **greater multangular**; the other, on the ulnar side, by the **pisiform**. The tuberosity of the navicular is distal and medial to the styloid process of the radius, and is most clearly visible when the wrist-joint is extended; the ridge on the greater multangular is about 1 cm. distal to it. The pisiform is about 1 cm. distal to the lower end of the ulna and just distal to the level of the styloid process of the radius; it is crossed by the uppermost crease which separates the front of the forearm from the palm of the hand. The rest of the volar surface of the bony carpus is covered by tendons and the transverse carpal ligament, and is entirely concealed, with the exception of the hamulus of the **hamate bone**, which, however, is difficult to

define. On the dorsal surface of the carpus only the **triangular bone** can be clearly made out.

Distal to the carpus the dorsal surfaces of the **metacarpal bones**, covered by the Extensor tendons, except the fifth, are visible only in very thin hands; the dorsal surface of the fifth is, however, subcutaneous throughout almost its whole length. Slightly lateral to the middle line of the hand is a prominence, frequently well-marked, but occasionally indistinct, formed by the styloid process of the third metacarpal bone; it is situated about 4 cm. distal to the dorsal radial tubercle. The heads of the metacarpal bones can be plainly seen and felt, rounded in contour and standing out in bold relief under the skin when the fist is clenched; the head of the third is the most prominent. In the palm of the hand the metacarpal bones are covered by muscles, tendons, and aponeuroses, so that only their heads can be distinguished. The base of the metacarpal bone of the thumb, however, is prominent dorsally, distal to the styloid process of the radius; the body of the bone is easily palpable, ending at the head in a flattened prominence, in front of which are the sesamoid bones.

The enlarged ends of the **phalanges** can be easily felt. When the digits are bent the proximal phalanges form prominences, which in the joints between the first and second phalanges are slightly hollow, but flattened and square-shaped in those between the second and third.

**Articulations.**—The **sternoclavicular joint** is subcutaneous, and its position is indicated by the enlarged sternal extremity of the clavicle, lateral to the long cord-like sternal head of Sternocleidomastoideus. If this muscle be relaxed a depression between the end of the clavicle and the sternum can be felt, defining the exact position of the joint.

The position of the **acromioclavicular joint** can generally be ascertained by determining the slightly enlarged acromial end of the clavicle which projects above the level of the acromion; sometimes this enlargement is so considerable as to form a rounded eminence.

The **shoulder-joint** is deeply seated and cannot be palpated. If the forearm be slightly flexed a curved crease or fold with its convexity downward is seen in front of the elbow, extending from one epicondyle to the other; the **elbow-joint** is slightly distal to the centre of the fold. The position of the **radiohumeral joint** can be ascertained by feeling for a slight groove or depression between the head of the radius and the capitulum of the humerus, at the back of the elbow-joint.

The position of the **proximal radioulnar joint** is marked on the surface at the back of the elbow by the dimple which indicates the position of the head of the radius. The site of the **distal radioulnar joint** can be defined by feeling for the slight groove at the back of the wrist between the prominent head of the ulna and the lower end of the radius, when the forearm is in a state of almost complete pronation.

Of the three transverse skin furrows on the front of the wrist, the middle corresponds fairly accurately with the **wrist-joint**, while the most distal indicates the position of the **midcarpal articulation**.

The **metacarpophalangeal** and **interphalangeal joints** are readily available for surface examination; the former are situated just distal to the prominences of the knuckles, the latter are sufficiently indicated by the furrows on the volar, and the wrinkles on the dorsal surfaces.

**Muscles** (Figs. 1075, 1110, 1111).—The anterior border of the **Trapezius** presents as a slight ridge running downward and forward from the superior nuchal line of the occipital bone to the junction of the intermediate and lateral thirds of the clavicle. The inferior border of the muscle forms an undulating ridge passing downward and medialward from the root of the spine of the scapula to the spinous process of the twelfth thoracic vertebra.

the greater tubercle forms the most prominent bony point of the shoulder, extending beyond the acromion; it is best recognized when the arm is lying passive by the side, for if the arm be raised it recedes under the arch of the shoulder. The lesser tubercle, directed forward, is medial to the greater and separated from it by the intertubercular groove, which can be made out by deep pressure. When the arm is abducted the lower part of the head of the humerus can be examined by pressing deeply in the axilla. On either side of the elbow-joint and just above it are the medial and lateral epicondyles. Of these, the former is the more prominent, but the medial supracondylar ridge passing upward from it is much less marked than the lateral, and as a rule is not palpable; occasionally, however, the hook-shaped supracondylar process (page 312) is found on this border. The position of the lateral epicondyle is best seen during semiflexion of the forearm, and is indicated by a depression; from it the strongly marked lateral supracondylar ridge runs upward.

The most prominent part of the **ulna**, the olecranon, can always be identified at the back of the elbow-joint. When the forearm is flexed the upper quadrilateral surface is palpable, but during extension it recedes into the olecranon fossa. During extension the upper border of the olecranon is slightly above the level of the medial epicondyle and nearer to this than to the lateral; when the forearm is fully flexed the olecranon and the epicondyles form the angles of an equilateral triangle. On the back of the olecranon is a smooth triangular subcutaneous surface, and running down the back of the forearm from the apex of this triangle the prominent dorsal border of the ulna can be felt in its whole length: it has a sinuous outline, and is situated in the middle of the back of the limb above; but below, where it is rounded off, it can be traced to the small subcutaneous surface of the styloid process on the medial side of the wrist. The styloid process forms a prominent tubercle continuous above with the dorsal border and ending below in a blunt apex at the level of the wrist-joint; it is most evident when the hand is in a position midway between supination and pronation. When the forearm is pronated another prominence, the head of the ulna, appears behind and above the styloid process.

Below the lateral epicondyle of the humerus a portion of the head of the **radius** is palpable; its position is indicated on the surface by a little dimple, which is best seen when the arm is extended. If the finger be placed in this dimple and the semiflexed forearm be alternately pronated and supinated the head of the radius will be felt distinctly, rotating in the radial notch. The upper half of the body of the bone is obscured by muscles; the lower half, though not subcutaneous, can be readily examined, and if traced downward is found to end in a lozenge-shaped convex surface on the lateral side of the base of the styloid process; this is the only subcutaneous part of the bone, and from its lower end the apex of the styloid process bends medialward toward the wrist. About the middle of the dorsal surface of the lower end of the radius is the dorsal radial tubercle, best perceived when the wrist is slightly flexed; it forms the lateral boundary of the oblique groove for the tendon of *Extensor pollicis longus*.

On the front of the wrist are two subcutaneous eminences, one, on the radial side, the larger and flatter, produced by the tuberosity of the **navicular** and the ridge on the **greater multangular**; the other, on the ulnar side, by the **pisiform**. The tuberosity of the navicular is distal and medial to the styloid process of the radius, and is most clearly visible when the wrist-joint is extended; the ridge on the greater multangular is about 1 cm. distal to it. The pisiform is about 1 cm. distal to the lower end of the ulna and just distal to the level of the styloid process of the radius; it is crossed by the uppermost crease which separates the front of the forearm from the palm of the hand. The rest of the volar surface of the bony carpus is covered by tendons and the transverse carpal ligament, and is entirely concealed, with the exception of the hamulus of the **hamate bone**, which, however, is difficult to

where it presents a somewhat flattened form. Above, its anterior border presents a slightly curved eminence which forms the lateral boundary of the infraclavicular fossa; below, it is closely united with the *Pectoralis major*. Its posterior border is thin, flattened, and scarcely marked above, but is thicker and more prominent below. The insertion of *Deltoides* is marked by a depression on the lateral side of the middle of the arm.

Of the scapular muscles the only one which influences surface form is the *Teres major*; it assists the *Latissimus dorsi* in forming the thick, rounded, posterior axillary fold.

When the arm is raised the *Coracobrachialis* reveals itself as a narrow elevation emerging from under cover of the anterior axillary fold and running medial to the body of the humerus.

On the front and medial aspects of the arm is the prominence of the *Biceps brachii*, bounded on either side by an intermuscular depression. It determines the contour of the front of the arm and extends from the anterior axillary fold to the bend of the elbow; its upper tendons are concealed by the *Pectoralis major* and *Deltoides*, and its lower tendon sinks into the anticubital fossa. When the muscle is fully contracted it presents a globular form, and the *lacertus fibrosus* attached to its tendon of insertion becomes prominent as a sharp ridge running downward and medialward.

On either side of the *Biceps brachii* at the lower part of the arm the *Brachialis* is discernible. Laterally it forms a narrow eminence extending some distance up the arm; medially it exhibits only a little fulness above the elbow.

On the back of the arm the long head of the *Triceps brachii* may be seen as a longitudinal eminence, emerging from under cover of *Deltoides* and gradually passing into the flattened plane of the tendon of the muscle at the lower part of the back of the arm. When the muscle is in action the medial and lateral heads become prominent.

On the front of the elbow are two muscular elevations, one on either side, separate above but converging below so as to form the medial and lateral boundaries of the anticubital fossa. The medial elevation consists of the *Pronator teres* and the *Flexors*, and forms a fusiform mass, pointed above at the medial epicondyle and gradually tapering off below. The *Pronator teres* is the most lateral of the group, while the *Flexor carpi radialis*, lying to its medial side, is the most prominent and may be traced downward to its tendon, which is situated nearer to the radial than to the ulnar border of the front of the wrist and medial to the radial artery. The *Palmaris longus* presents no surface marking above, but below, its tendon stands out when the muscle is in action as a sharp, tense cord in front of the middle of the wrist. The *Flexor digitorum sublimis* does not directly influence surface form; the position of its four tendons on the front of the lower part of the forearm is indicated by an elongated depression between the tendons of *Palmaris longus* and *Flexor carpi ulnaris*. The *Flexor carpi ulnaris* determines the contour of the medial border of the forearm, and is separated from the *Extensor* group of muscles by the ulnar furrow produced by the subcutaneous dorsal border of the ulna; its tendon is evident along the ulnar border of the lower part of the forearm, and is most marked when the hand is flexed and adducted.

The elevation forming the lateral side of the anticubital fossa consists of the *Brachioradialis*, the *Extensors* and the *Supinator*; it occupies the lateral and a considerable part of the dorsal surface of the forearm in the region of the elbow, and forms a fusiform mass which is altogether on a higher level than that produced by the medial elevation. Its apex is between the *Triceps brachii* and *Brachialis* some distance above the elbow-joint; it acquires its greatest breadth opposite the lateral epicondyle, and below this shades off into a flattened surface. About the middle of the forearm it divides into two diverging longitudinal eminences. The

The lateral border of the **Latissimus dorsi** (Fig. 1096) may be traced, when the muscle is in action, as a rounded edge starting from the iliac crest and slanting obliquely forward and upward to the axilla, where it takes part with the **Teres major** in forming the posterior axillary fold.




FIG. 1110.—Front of right upper extremity.

The **Pectoralis major** (Fig. 1100) conceals a considerable part of the thoracic wall in front. Its sternal origin presents a border which bounds, and determines the width of the sternal furrow. The upper margin is generally well-marked medially and forms the medial boundary of a triangular depression, the *infraclavicular fossa*, which separates the **Pectoralis major** from the **Deltoideus**; it gradually becomes less marked as it approaches the tendon of insertion and is closely blended with the **Deltoideus**. The lower border of **Pectoralis major** forms the rounded anterior axillary fold. Occasionally a gap is visible between the clavicular and sternal parts of the muscle.




FIG. 1111.—Back of right upper extremity.

When the arm is raised the lowest slip of origin of **Pectoralis minor** produces a fulness just below the anterior axillary fold and serves to break the sharp outline of the lower border of **Pectoralis major**.

The origin of the **Serratus anterior** (Figs. 1096, 1100) causes a very characteristic surface marking. When the arm is abducted the lower five or six serrations form a zigzag line with a general convexity forward; when the arm is by the side the highest visible serration is that attached to the fifth rib.

The **Deltoideus** with the prominence of the upper end of the humerus produces the rounded contour of the shoulder; it is rounded and fuller in front than behind,



where it presents a somewhat flattened form. Above, its anterior border presents a slightly curved eminence which forms the lateral boundary of the infraclavicular fossa; below, it is closely united with the *Pectoralis major*. Its posterior border is thin, flattened, and scarcely marked above, but is thicker and more prominent below. The insertion of *Deltoides* is marked by a depression on the lateral side of the middle of the arm.

Of the scapular muscles the only one which influences surface form is the *Teres major*; it assists the *Latissimus dorsi* in forming the thick, rounded, posterior axillary fold.

When the arm is raised the *Coracobrachialis* reveals itself as a narrow elevation emerging from under cover of the anterior axillary fold and running medial to the body of the humerus.

On the front and medial aspects of the arm is the prominence of the *Biceps brachii*, bounded on either side by an intermuscular depression. It determines the contour of the front of the arm and extends from the anterior axillary fold to the bend of the elbow; its upper tendons are concealed by the *Pectoralis major* and *Deltoides*, and its lower tendon sinks into the anticubital fossa. When the muscle is fully contracted it presents a globular form, and the *lacertus fibrosus* attached to its tendon of insertion becomes prominent as a sharp ridge running downward and medialward.

On either side of the *Biceps brachii* at the lower part of the arm the *Brachialis* is discernible. Laterally it forms a narrow eminence extending some distance up the arm; medially it exhibits only a little fulness above the elbow.

On the back of the arm the long head of the *Triceps brachii* may be seen as a longitudinal eminence, emerging from under cover of *Deltoides* and gradually passing into the flattened plane of the tendon of the muscle at the lower part of the back of the arm. When the muscle is in action the medial and lateral heads become prominent.

On the front of the elbow are two muscular elevations, one on either side, separate above but converging below so as to form the medial and lateral boundaries of the anticubital fossa. The medial elevation consists of the *Pronator teres* and the *Flexors*, and forms a fusiform mass, pointed above at the medial epicondyle and gradually tapering off below. The *Pronator teres* is the most lateral of the group, while the *Flexor carpi radialis*, lying to its medial side, is the most prominent and may be traced downward to its tendon, which is situated nearer to the radial than to the ulnar border of the front of the wrist and medial to the radial artery. The *Palmaris longus* presents no surface marking above, but below, its tendon stands out when the muscle is in action as a sharp, tense cord in front of the middle of the wrist. The *Flexor digitorum sublimis* does not directly influence surface form; the position of its four tendons on the front of the lower part of the forearm is indicated by an elongated depression between the tendons of *Palmaris longus* and *Flexor carpi ulnaris*. The *Flexor carpi ulnaris* determines the contour of the medial border of the forearm, and is separated from the *Extensor* group of muscles by the ulnar furrow produced by the subcutaneous dorsal border of the ulna; its tendon is evident along the ulnar border of the lower part of the forearm, and is most marked when the hand is flexed and adducted.

The elevation forming the lateral side of the anticubital fossa consists of the *Brachioradialis*, the *Extensors* and the *Supinator*; it occupies the lateral and a considerable part of the dorsal surface of the forearm in the region of the elbow, and forms a fusiform mass which is altogether on a higher level than that produced by the medial elevation. Its apex is between the *Triceps brachii* and *Brachialis* some distance above the elbow-joint; it acquires its greatest breadth opposite the lateral epicondyle, and below this shades off into a flattened surface. About the middle of the forearm it divides into two diverging longitudinal eminences. The

lateral eminence consists of the **Brachioradialis** and the **Extensores carpi radiales longus** and **brevis**, and descends from the lateral supracondylar ridge in the direction of the styloid process of the radius. The medial eminence comprises the **Extensor digitorum communis**, **Extensor digiti quinti proprius**, and the **Extensor carpi ulnaris**; it begins at the lateral epicondyle of the humerus as a tapering mass which is separated above from the **Anconaeus** by a well-marked furrow, and below from the **Pronator teres** and **Flexor** group by the ulnar furrow. The medial border of the **Brachioradialis** starts as a rounded elevation above the lateral epicondyle; lower down the muscle forms a prominent mass on the radial side of the upper part of the forearm; below it tapers to its tendon, which may be traced to the styloid process of the radius. The **Anconaeus** presents as a triangular slightly elevated area, immediately lateral to the subcutaneous surface of the olecranon and differentiated from the **Extensor** group by an oblique depression; the upper angle of the triangle is at the dimple over the lateral epicondyle.

At the lower part of the back of the forearm in the interval between the two diverging eminences is an oblique elongated swelling; full above but flattened and partially subdivided below; it is caused by the **Abductor pollicis longus** and the **Extensor pollicis brevis**. It crosses the dorsal and lateral surfaces of the radius to the radial side of the wrist-joint, whence it is continued on to the dorsal surface of the thumb as a ridge best marked when the thumb is extended.

The tendons of most of the **Extensor** muscles can be seen and felt on the back of the wrist. Laterally is the oblique ridge produced by the **Extensor pollicis longus**. The **Extensor carpi radialis longus** is scarcely palpable, but the **Extensor carpi radialis brevis** can be identified as a vertical ridge emerging from under the ulnar border of the tendon of the **Extensor pollicis longus** when the wrist is extended. Medial to this the **Extensor** tendons of the fingers can be felt, the **Extensor digiti quinti proprius** being separated from the tendons of the **Extensor digitorum communis** by a slight furrow.

The muscles of the hand are principally concerned, as regards surface form, in producing the thenar and hypothenar eminences, and cannot be individually distinguished; the thenar eminence, on the radial side, is larger and rounder than the hypothenar, which is a long narrow elevation along the ulnar side of the palm. When the **Palmaris brevis** is in action it produces a wrinkling of the skin over the hypothenar eminence and a dimple on the ulnar border. On the back of the hand the **Interossei dorsales** give rise to elongated swellings between the metacarpal bones; the first forms a prominent fusiform bulging when the thumb is adducted, the others are not so marked.

**Arteries.**—Above the middle of the clavicle the pulsation of the **subclavian artery** can be detected by pressing downward, backward, and medialward against the first rib. The pulsation of the **axillary artery** as it crosses the second rib can be felt below the middle of the clavicle just medial to the coracoid process; along the lateral wall of the axilla the course of the artery can be easily followed close to the medial border of **Coracobrachialis**. The **brachial artery** can be recognized in practically the whole of its extent, along the medial margin of the **Biceps**; in the upper two-thirds of the arm it lies medial to the humerus, but in the lower third is more directly on the front of the bone. Over the lower end of the radius, between the styloid process and **Flexor carpi radialis**, a portion of the **radial artery** is superficial and is used clinically for observations on the pulse.

**Veins.**—The superficial veins of the upper extremity are easily rendered visible by compressing the proximal trunks; their arrangement is described on pages 747 to 749.

**Nerves.**—The uppermost trunks of the **brachial plexus** are palpable for a short distance above the clavicle as they emerge from under the lateral border of **Sterno-**

cleidomastoideus; the larger nerves derived from the plexus can be rolled under the finger against the lateral axillary wall but cannot be identified. The **ulnar nerve** can be detected in the groove behind the medial epicondyle of the humerus.

### SURFACE MARKINGS OF THE UPPER EXTREMITY.

**Bony Landmarks.**—The bony landmarks as described above are so readily available for surface recognition that no special measurements are required to indicate them. It may be noted, however, that the medial angle of the scapula is applied to the second rib, while the inferior angle lies against the seventh. The intertubercular groove of the humerus is vertically below the acromioclavicular joint when the arm hangs by the side with the palm of the hand forward.

**Articulations.**—The **acromioclavicular joint** is situated in a plane passing sagittally through the middle line of the front of the arm. The line of the **elbow-joint** is not straight; the radiohumeral portion is practically at right angles to the long axis of the humerus and is situated about 2 cm. distal to the lateral epicondyle; the ulnohumeral portion is oblique, and its medial end is about 2.5 cm. distal to the medial epicondyle. The position of the **wrist-joint** can be indicated by drawing a curved line, with its convexity upward, between the styloid processes of the radius and ulna; the summit of the convexity is about 1 cm. above the centre of a straight line joining the two processes.

**Muscles.**—The only muscles of the upper extremity which occasionally require definition by surface lines are the Trapezius, the Latissimus dorsi, and the Pectorales major and minor. The antero-superior border of **Trapezius** is indicated by a line from the superior nuchal line about 3 cm. lateral to the external occipital protuberance to the junction of the intermediate and lateral thirds of the clavicle; the line of the lower border extends from the spinous process of the twelfth thoracic vertebra to the vertebral border of the scapula at the root of the spine. The upper border of **Latissimus dorsi** is almost horizontal, running from the spinous process of the seventh thoracic vertebra to the inferior angle of the scapula and thence somewhat obliquely to the intertubercular sulcus of the humerus; the lower border corresponds roughly to a line drawn from the iliac crest about 2 cm. from the lateral margin of the Sacrospinalis to the intertubercular sulcus. The upper margin of **Pectoralis major** extends from the middle of the clavicle to the surgical neck of the humerus; its lower border is practically in the line of the fifth rib and reaches from the fifth costochondral junction to the middle of the anterior border of Deltoideus. The two lines indicating the borders of **Pectoralis minor** begin at the coracoid process of the scapula and extend to the third and fifth ribs respectively, just lateral to the corresponding costal cartilages. On the front of the elbow-joint a triangular space—the **anticubital fossa**—is mapped out for convenience of reference. The base of the triangle is a line joining the medial and lateral epicondyles, while the sides are formed respectively by the salient margins of the Brachioradialis and Pronator teres.

**Mucous Sheaths.**—On the volar surfaces of the wrist and hand the mucous sheaths of the Flexor tendons (Fig. 1112) can be indicated as follows. The sheath for Flexor pollicis longus extends from about 3 cm. above the upper edge of the transverse carpal ligament to the terminal phalanx of the thumb. The common sheath for the Flexores digitorum reaches about 3.5 to 4 cm. above the upper edge of the transverse carpal ligament and extends on the palm of the hand to about the level of the centres of the metacarpal bones. The sheath for the tendons to the little finger is continued from the common sheath to the base of the terminal phalanx of this finger; the sheaths for the tendons of the other fingers are separated from the common sheath by an interval; they begin opposite the necks of the meta-

carpal bones and extend to the terminal phalanges. The mucous sheaths of the Extensor tendons are shown in Fig. 1113 (see also page 550).




FIG. 1112.—The mucous sheaths of the tendons on the front of the wrist and digits.

**Arteries** (Fig. 1114).—The course of the **axillary artery** can be marked out by abducting the arm to a right angle and drawing a line from the middle of the clavicle to the point where the tendon of the Pectoralis major crosses the prominence of the Coracobrachialis. Of the branches of the axillary artery, the origin of the **thoracoacromial** corresponds to the point where the artery crosses the upper border of Pectoralis minor; the **lateral thoracic** takes practically the line of the lower border of Pectoralis minor; the **subscapular** is sufficiently indicated by

the axillary border of the scapula; the **scapular circumflex** is given off the sub-scapular opposite the midpoint of a line joining the tip of the acromion to the lower edge of the deltoid tuberosity, while the **humeral circumflex** arteries arise from the axillary about 2 cm. above this. The position of the **brachial artery** is




FIG. 1113.—The mucous sheaths of the tendons on the back of the wrist.

marked by a line drawn from the junction of the anterior and middle thirds of the distance between the anterior and posterior axillary folds to a point midway between the epicondyles of the humerus and continued distally for 2.5 cm., at which point the artery bifurcates. With regard to the branches of the brachial



artery—the **profunda** crosses the back of the humerus at the level of the insertion of **Deltoidaeus**; the **nutrient** is given off opposite the middle of the body of the humerus; a line from this point to the back of the medial condyle represents the **superior ulnar collateral**; the **inferior ulnar collateral** is given off about 5 cm. above the fold of the elbow-joint and runs directly medialward.




FIG. 1114.—Front of right upper extremity, showing surface markings for bones, arteries, and nerves.

The position of the **radial artery** in the forearm is represented by a line from the lateral margin of the Biceps tendon in the centre of the antecubital fossa to the medial side of the front of the styloid process of the radius when the limb is in the position of supination. The situation of the distal portion of the artery is indicated by continuing this line around the radial side of the wrist to the proximal end of the first intermetacarpal space.




FIG. 1115.—Back of right upper extremity, showing surface markings for bones and nerves.

On account of the curved direction of the **ulnar artery**, two lines are required to indicate its course; one is drawn from the front of the medial epicondyle to the radial side of the pisiform bone; the lower two-thirds of this line represents two-thirds of the artery; the upper third is represented by a second line from the centre of the hollow in front of the elbow-joint to the junction of the upper and middle thirds of the first line.

The **superficial volar arch** (Fig. 1116) can be indicated by a line starting from the radial side of the pisiform bone and curving distalward and lateralward as far as the base of the thumb, with its convexity toward the fingers. The summit of the arch is usually on a level with the ulnar border of the outstretched thumb. The **deep volar arch** is practically transverse, and is situated about 1 cm. nearer to the carpus.

**Nerves** (Figs. 1114, 1115).—In the arm the line of the **median nerve** is practically the same as that for the brachial artery; at the bend of the elbow the nerve is medial to the artery. The course of the nerve in the forearm is marked by a line starting from a point just medial to the centre of one joining the epicondyles, and extending to the lateral margin of the tendon of *Palmaris longus* at the wrist.

The **ulnar nerve** follows the line of the brachial artery in the upper half of the arm, but at the middle of the arm it diverges and descends to the back of the medial epicondyle. In the forearm it is represented by a line from the front of the medial epicondyle to the radial side of the pisiform bone.

The course of the **radial nerve** can be indicated by a line from just below the posterior axillary fold, to the lateral side of the humerus at the junction of its middle and lower thirds; thence it passes vertically downward on the front of the arm to the level of the lateral epicondyle. The course of the **superficial radial nerve** is represented by a continuation of this line downward to the junction of the middle and lower thirds of the radial artery; it then crosses the radius and runs distalward to the dorsum of the base of the first metacarpal bone.

The **axillary nerve** crosses the humerus about 2 cm. above the centre of a line joining the tip of the acromion to the lower edge of the deltoid tuberosity.




FIG. 1116.—Palm of left hand, showing position of skin creases and bones, and surface markings for the volar arches.

## SURFACE ANATOMY OF THE LOWER EXTREMITY.

**Skin.**—The skin of the thigh, especially in the hollow of the groin and on the medial side, is thin, smooth and elastic, and contains few hairs except on the neighborhood of the pubis. Laterally it is thicker and the hairs are more numerous. The junction of the skin of the thigh with that on the front of the abdomen is marked by a well-defined furrow which indicates the site of the inguinal ligament; the furrow presents a general convexity downward, but its medial half, which is the better marked, is nearly straight. The skin over the buttock is fairly thick and is characterized by its low sensibility and slight vascularity; as a rule it is destitute of conspicuous hairs except toward the post-anal furrow, where in some males they are abundantly developed. An almost transverse fold—the **gluteal fold**—crosses the lower part of the buttock; it practically bisects the lower margin of the *Glutæus maximus* and is most evident during extension of the hip-joint. The skin over the front of the knee is covered by thickened epidermis; it is loose and thrown into transverse wrinkles when the leg is extended. The skin of the leg

is thin, especially on the medial side, and is covered with numerous large hairs. On the dorsum of the foot the skin is thin, loosely connected to subjacent parts, and contains few hairs, on the plantar surface, and especially over the heel, the epidermis is of great thickness, and here, as in the palm of the hand, there are neither hairs nor sebaceous glands.

**Bones.**—The **hip bones** are largely covered with muscles, so that only at a few points do they approach the surface. In front the anterior superior iliac spine is easily recognized, and in thin subjects stands out as a prominence at the lateral end of the fold of the groin; in fat subjects its position is indicated by an oblique depression, at the bottom of which the bony process can be felt. Proceeding upward and backward from this process the sinuously curved iliac crest can be traced to the posterior superior iliac spine, the site of which is indicated by a slight depression; on the outer lip of the crest, about 5 cm. behind the anterior superior spine, is the prominent iliac tubercle. In thin subjects the pubic tubercle is very apparent, but in the obese it is obscured by the pubic fat; it can, however, be detected by following up the tendon of origin of Adductor longus. Another part of the bony pelvis which is accessible to touch is the ischial tuberosity, situated beneath the Glutaeus maximus, and, when the hip is flexed, easily felt, as it is then uncovered by muscle.

The **femur** is enveloped by muscles, so that in fairly muscular subjects the only accessible parts are the lateral surface of the greater trochanter and the lower expanded end of the bone. The site of the greater trochanter is generally indicated by a depression, owing to the thickness of the Glutaei medius and minimus which project above it; when, however, the thigh is flexed, and especially if it be crossed over the opposite one, the trochanter produces a blunt eminence on the surface. The lateral condyle is more easily felt than the medial; both epicondyles can be readily identified, and at the upper part of the medial condyle the sharp adductor tubercle can be recognized without difficulty. When the knee is flexed a portion of the patellar surface is uncovered and is palpable.

The anterior surface of the **patella** is subcutaneous. When the knee is extended the medial border of the bone is a little more prominent than the lateral, and if the Quadriceps femoris be relaxed the bone can be moved from side to side. When the joint is flexed the patella recedes into the hollow between the condyles of the femur and the upper end of the tibia, and becomes firmly applied to the femur.

A considerable portion of the **tibia** is subcutaneous. At the upper end the condyles can be felt just below the knee; the medial condyle is broad and smooth, and merges into the subcutaneous surface of the body below; the lateral is narrower and more prominent, and on it, about midway between the apex of the patella and the head of the fibula, is the tubercle for the attachment of the iliotibial band. In front of the upper end of the bone, between the condyles, is an oval eminence, the tuberosity, which is continuous below with the anterior crest of the bone. This crest can be identified in the upper two-thirds of its extent as a flexuous ridge, but in the lower third it disappears and the bone is concealed by the tendons of the muscles on the front of the leg. Medial to the anterior crest is the broad surface, slightly encroached on by muscles in front and behind. The medial malleolus forms a broad prominence, situated at a higher level and somewhat farther forward than the lateral malleolus; it overhangs the medial border of the arch of the foot; its anterior border is nearly straight, its posterior presents a sharp edge which forms the medial margin of the groove for the tendon of Tibialis posterior.

The only subcutaneous parts of the **fibula** are the head, the lower part of the body, and the lateral malleolus. The head lies behind and lateral to the lateral condyle of the tibia, and presents as a small prominent pyramidal eminence slightly above the level of the tibial tuberosity; its position can be readily located by

following downward the tendon of *Biceps femoris*. The lateral malleolus is a narrow elongated prominence, from which the lower third or half of the lateral surface of the body of the bone can be traced upward.

On the dorsum of the tarsus the individual bones cannot be distinguished, with the exception of the head of the *talus*, which forms a rounded projection in front of the ankle-joint when the foot is forcibly extended. The whole dorsal surface of the foot has a smooth convex outline, the summit of which is the ridge formed by the head of the *talus*, the *navicular*, the second cuneiform, and the second metatarsal bone; from this it inclines gradually lateralward, and rapidly medialward. On the medial side of the foot the medial process of the tuberosity of the *calcaneus* and the ridge separating the posterior from the medial surface of the bone are distinguishable; in front of this, and below the medial malleolus, is the *susten-taculum tali*. The tuberosity of the *navicular* is palpable about 2.5 to 3 cm. in front of the medial malleolus.

Farther forward, the ridge formed by the base of the *first metatarsal bone* can be obscurely felt, and from this the body of the bone can be traced to the expanded head; beneath the base of the first phalanx is the medial sesamoid bone. On the lateral side of the foot, the most posterior bony point is the lateral process of the tuberosity of the *calcaneus*, with the ridge separating the posterior from the lateral surface of the bone. In front of this the greater part of the lateral surface of the *calcaneus* is subcutaneous; on it, below and in front of the lateral malleolus, the trochlear process, when present, can be felt. Farther forward the base of the *fifth metatarsal bone* is prominent, and from it the body and expanded head can be traced.

As in the case of the metacarpals, the dorsal surfaces of the *metatarsal bones* are easily defined, although their heads do not form prominences; the plantar surfaces are obscured by muscles. The *phalanges* in their whole extent are readily palpable.

**Articulations.**—The *hip-joint* is deeply seated and cannot be palpated.

The interval between the *tibia* and *femur* can always be easily felt; if the *knee-joint* be extended this interval is on a higher level than the apex of the *patella*, but if the joint be slightly flexed it is directly behind the apex. When the knee is semiflexed, the medial borders of the *patella* and of the medial condyle of the *femur*, and the upper border of the medial condyle of the *tibia*, bound a triangular depressed area which indicates the position of the joint.




FIG. 1117.—Front and medial aspect of right thigh.




FIG. 1118.—Back of left lower extremity.

The **ankle-joint** can be felt on either side of the Extensor tendons, and during extension of the joint the superior articular surface of the talus presents below the anterior border of the lower end of the tibia.

**Muscles.**—Of the muscles of the thigh, those of the anterior femoral region (Fig. 1117) contribute largely to surface form. The **Tensor fasciae latae** produces a broad elevation immediately below the anterior part of the iliac crest and behind the anterior superior iliac spine; from its lower border a groove caused by the iliotibial band extends downward to the lateral side of the knee-joint. The upper portion of **Sartorius** constitutes the lateral boundary of the femoral triangle, and, when the muscle is in action, forms a prominent oblique ridge which is continued below into a flattened plane and then gradually merges into a general fullness on the medial side of the knee-joint. When the Sartorius is not in action, a depression exists between the Quadriceps femoris and the Adductors, and extends obliquely downward and medialward from the apex of the femoral triangle to the side of the knee. In the angle formed by the divergence of Sartorius and Tensor fasciae latae, just below the anterior superior iliac spine, the **Rectus femoris** appears, and in a muscular subject its borders can be clearly defined when the muscle is in action. The **Vastus lateralis** forms a long flattened plane traversed by the groove of the iliotibial band. The **Vastus medialis** gives rise to a considerable



prominence on the medial side of the lower half of the thigh; this prominence increases toward the knee and ends somewhat abruptly with a full curved outline. The **Vastus intermedius** is completely hidden. The Adductores cannot be differentiated from one another, with the exception of the upper tendon of Adductor longus and the lower tendon of Adductor magnus. When the **Adductor longus** is in action its upper tendon stands out as a prominent ridge running obliquely downward and lateralward from the neighborhood of the pubic tubercle, and forming the medial border of the femoral triangle. The lower tendon of **Adductor magnus** can be distinctly felt as a short ridge extending downward between the Sartorius and Vastus medialis to the adductor tubercle. The adductores fill in the triangular space at the upper part of the thigh, between the femur and the pelvis, and to them is due the contour of the medial border of the thigh, the **Gracilis** contributing largely to the smoothness of the outline.

The **Glutæus maximus** (Fig. 1118) forms the full rounded outline of the buttock; it is more prominent behind, compressed in front, and ends at its tendinous insertion in a depression immediately behind the greater trochanter; its lower border crosses the gluteal fold obliquely downward and lateralward. The upper part of **Glutæus medius** is visible, but its lower part with **Glutæus minimus** and the external rotators are completely hidden. From beneath the lower margin of **Glutæus maximus** the hamstrings appear; at first they are narrow and not well-defined, but as they descend they become more prominent and eventually divide into two well-marked ridges formed by their tendons; these constitute the upper boundaries of the popliteal fossa. The tendon of **Biceps femoris** is a thick cord running to the head of the fibula; the tendons of the **Semimembranosus** and **Semitendinosus** as they run medialward to the tibia are separated by a slight furrow; the **Semitendinosus** is the more medial, and can be felt in certain positions of the limb as a sharp cord, while the **Semimembranosus** is thick and rounded. The **Gracilis** is situated a little in front of them.

The **Tibialis anterior** (Fig. 1119) presents a fusiform enlargement at the lateral side of the tibia and projects beyond the anterior crest of the bone; its tendon can be traced on the front of the tibia and ankle-joint and thence along the medial side of the foot to the base of the first metatarsal bone. The fleshy fibres of **Peronæus longus** are strongly marked at the upper part of the lateral side of the leg; it is separated by furrows from **Extensor digitorum longus** in front and **Soleus** behind. Below, the fleshy fibres end abruptly in a tendon which overlaps the more flattened




FIG. 1119.—Lateral aspect of right leg.

elevation of **Peronæus brevis**; below the lateral malleolus the tendon of **Peronæus brevis** is the more marked.

On the dorsum of the foot (Fig. 1120) the tendons emerging from beneath the transverse and cruciate crural ligaments spread out and can be distinguished as follows: the most medial and largest is **Tibialis anterior**, the next is **Extensor hallucis proprius**, then **Extensor digitorum longus** dividing into four tendons, to the second, third, fourth, and fifth toes, and lastly **Peronæus tertius**. The **Extensor digitorum brevis** produces a rounded outline on the dorsum of the foot and a fulness in front of the lateral malleolus. The **Interossei dorsales** bulge between the metatarsal bones.




FIG. 1120.—The mucous sheaths of the tendons around the ankle. Lateral aspect.

At the back of the knee is the popliteal fossa, bounded above by the tendons of the hamstrings and below by the **Gastrocnemius**. Below this fossa is the prominent fleshy mass of the calf of the leg produced by **Gastrocnemius** and **Soleus** (Fig. 1118). When these muscles are in action the borders of **Gastrocnemius** form two well-defined curved lines which converge to the tendocalcaneus; the medial border is the more prominent. At the same time the edges of **Soleus** can be seen forming, on either side of **Gastrocnemius**, curved eminences, of which the lateral is the longer. The fleshy mass of the calf ends somewhat abruptly in the tendocalcaneus, which tapers in the upper three-fourths of its extent but widens out slightly below. Behind the medial border of the lower part of the tibia (Fig. 1121) a well-defined ridge is produced by the tendon of **Tibialis posterior** during contraction of the muscle.

On the sole of the foot the **Abductor digiti quinti** forms a narrow rounded elevation on the lateral side, and the **Abductor hallucis** a lesser elevation on the medial side. The **Flexor digitorum brevis**, bound down by the plantar aponeurosis, is not very apparent; it produces a flattened form, and the thickened skin underlying it is thrown into numerous wrinkles.

**Arteries.**—The **femoral artery** as it crosses the brim of the pelvis is readily felt; in its course down the thigh its pulsation becomes gradually more difficult of recognition. When the knee is flexed the pulsation of the **popliteal artery** can easily be detected in the popliteal fossa.

On the lower part of the front of the tibia the **anterior tibial artery** becomes superficial and can be traced over the ankle into the **dorsalis pedis**; the latter can be followed to the proximal end of the first intermetatarsal space. The pulsation of the **posterior tibial artery** becomes evident near the lower end of the back of the tibia, and is easily detected behind the medial malleolus.




FIG. 1121.—The mucous sheaths of the tendons around the ankle. Medial aspect.

**Veins.**—By compressing the proximal trunks, the venous arch on the dorsum of the foot, together with the great and small saphenous veins leading from it (see page 756), are rendered visible.

**Nerves.**—The only nerve of the lower extremity which can be located by palpation is the **common peroneal** as it winds around the lateral side of the neck of the fibula.

#### SURFACE MARKINGS OF THE LOWER EXTREMITY.

**Bony Landmarks.**—The anterior superior iliac spine is at the level of the sacral promontory—the posterior at the level of the spinous process of the second sacral vertebra. A horizontal line through the highest points of the iliac crests passes also through the spinous process of the fourth lumbar vertebra, while, as already pointed out (page 1303), the transtubercular plane through the tubercles on the iliac crests cuts the body of the fifth lumbar vertebra. The upper margin of the greater sciatic notch is opposite the spinous process of the third sacral vertebra, and slightly below this level is the posterior inferior iliac spine. The surface markings of the posterior inferior iliac spine and the ischial spine are both situated in a line which joins the posterior superior iliac spine to the outer part of the ischial tuberosity; the posterior inferior spine is 5 cm. and the ischial spine 10 cm. below the posterior superior spine; the ischial spine is opposite the first piece of the coccyx.

With the body in the erect posture the line joining the pubic tubercle to the top of the greater trochanter is practically horizontal; the middle of this line overlies the acetabulum and the head of the femur.

A line used for clinical purposes is that of Nélaton (Fig. 1122), which is drawn from the anterior superior iliac spine to the most prominent part of the ischial tuberosity; it crosses the centre of the acetabulum and the upper border of the

greater trochanter. Another surface marking of clinical importance is **Bryant's triangle**, which is mapped out thus: a line from the anterior superior iliac spine to the top of the greater trochanter forms the base of the triangle; its sides are formed respectively by a horizontal line from the anterior superior iliac spine and a vertical line from the top of the greater trochanter.




FIG. 1122.—Nélaton's line and Bryant's triangle.

**Articulations.**—The posterior superior iliac spine overlies the centre of the **sacroiliac articulations**.

The **hip-joint** may be indicated, as described above, by the centre of a horizontal line from the pubic tubercle to the top of the greater trochanter; or more generally, it is below and slightly lateral to the middle of the inguinal ligament. The **knee-joint** is superficial and requires no surface marking. The level of the **ankle-joint** is that of a transverse line about 1 cm. above the level of the tip of the medial malleolus. If the foot be forcibly extended, the head of the talus appears as a rounded prominence on the medial side of the dorsum; just in front of this prominence and behind the tuberosity of the navicular is the **talonavicular joint**. The **calcaneocuboid joint** is situated midway between the lateral malleolus and the prominent base of the fifth metatarsal bone; the line indicating it is parallel to that of the **talonavicular joint**. The line of the **fifth tarsometatarsal joint** is very oblique; it starts from the projection of the base of the fifth metatarsal bone, and if continued would pass through the head of the first metatarsal. The lines of the **fourth and third tarsometatarsal joints** are less oblique. The **first tarsometatarsal joint** corresponds to a groove which can be felt by making firm pressure on the medial border of the foot 2.5 cm. in front of the tuberosity of the navicular bone; the position of the **second tarsometatarsal joint** is 1.25 cm. behind this. The **metatarsophalangeal joints** are about 2.5 cm. behind the webs of the corresponding toes.

**Muscles.**—None of the muscles require any special surface lines to indicate them, but there are three intermuscular spaces which occasionally require definition, viz., the femoral triangle, the adductor canal, and the popliteal fossa.

The **femoral triangle** is bounded above by the inguinal ligament, laterally by the medial border of Sartorius, and medially by the medial border of Adductor longus. In the triangle is the fossa ovalis, through which the great saphenous vein dips to join the femoral; the centre of this fossa is about 4 cm. below and lateral to the pubic tubercle, its vertical diameter measures about 4 cm. and its transverse about 1.5 cm. The femoral ring is about 1.25 cm. lateral to the pubic tubercle.

The **adductor canal** occupies the medial part of the middle third of the thigh; it begins at the apex of the femoral triangle and lies deep to the vertical part of Sartorius. The **popliteal fossa** is bounded: above and medially by the tendons of Semimembranosus and Semitendinosus; above and laterally by the tendon of Biceps femoris; below and medially by the medial head of Gastrocnemius; below and laterally by the lateral head of Gastrocnemius and the Plantaris.

**Mucous Sheaths.**—The positions of the mucous sheaths around the tendons about the ankle-joints are sufficiently indicated in Figs. 1120, 1121 (see also page 586).




FIG. 1123.—Left gluteal region, showing surface markings for arteries and sciatic nerve.

**Arteries.**—The points of emergence of the three main arteries on the buttock, viz., the superior and inferior gluteals and the internal pudendal, may be indicated in the following manner (Fig. 1123). With the femur slightly flexed and rotated inward, a line is drawn from the posterior superior iliac spine to the posterior superior angle of the greater trochanter; the point of emergence of the **superior gluteal artery** from the upper part of the greater sciatic foramen corresponds to the junction of the upper and middle thirds of this line. A second line is drawn from the posterior superior iliac spine to the outer part of the ischial tuberosity; the junction of its lower with its middle third marks the point or emergence of the **inferior gluteal** and **internal pudendal** arteries from the lower part of the greater sciatic foramen. The course of the **femoral artery** (Fig. 1124) is represented by the upper two-thirds of a line from a point midway between the anterior superior iliac spine and the symphysis pubis to the adductor tubercle, with the thigh abducted and rotated outward; the **profunda femoris** arises from it about 1 to 5 cm. below the inguinal ligament. The course of the upper part of the **popliteal artery** (Fig. 1126) is indicated by a line from the lateral margin of Semimembranosus at the junction of the middle and lower thirds of the thigh, obliquely downward to the middle of



the popliteal fossa; from this point it runs vertically downward for about 2.5 cm. or to the level of a line through the lower part of the tibial tuberosity. The line indicating the **anterior tibial artery** (Fig. 1125) is drawn from the medial side of the head of the fibula to a point midway between the malleoli; the artery begins about 3 cm. below the head of the fibula. The **dorsalis pedis artery** is represented on the dorsum of the foot by a line from the centre of the interval between the malleoli to the proximal end of the first intermetatarsal space.




FIG. 1124.—Front of right thigh, showing surface markings for bones, femoral artery and femoral nerve.




FIG. 1125.—Lateral aspect of right leg, showing surface markings for bones, anterior tibial and dorsalis pedis arteries, and deep peroneal nerve.

The course of the **posterior tibial artery** (Fig. 1126) can be shown by a line from the end of the popliteal artery, *i. e.*, 2.5 cm. below the centre of the popliteal fossa, to midway between the tip of the medial malleolus and the centre of the convexity of the heel; its main branch, the **peroneal artery**, begins about 7 or 8 cm. below the level of the knee-joint and follows the line of the fibula to the back of the lateral malleolus. The **medial and lateral plantar arteries** begin from the end of the posterior tibial; the medial extends to the middle of the plantar surface of the ball of the great toe, the lateral to within a finger's breadth of the tuberosity of the fifth metatarsal bone; from this latter point the **plantar arch** crosses the foot transversely to the proximal end of the first intermetatarsal space.

**Veins.**—The line of the **great saphenous vein** is from the front of the medial malleolus to the centre of the fossa ovalis; the **small saphenous vein** runs from the back of the lateral malleolus to the centre of the popliteal fossa.




FIG. 1126.—Back of left lower extremity, showing surface markings for bones, vessels, and nerves.

**Nerves.**—The course of the **sciatic nerve** (Fig. 1126) can be indicated by a line from a point midway between the outer border of the ischial tuberosity and the posterior superior angle of the greater trochanter to the upper angle of the popliteal fossa. The continuation of this line vertically through the centre of the popliteal fossa represents the position of the **tibial nerve**, while the **common peroneal nerve** follows the line of the tendon of Biceps femoris. The lines for the **deep peroneal nerve** and the continuation of the **tibial nerve** corresponds respectively to those for the anterior and posterior tibial arteries.

# A GLOSSARY OF THE INTERNATIONAL OR BASLE ANATOMICAL NOMENCLATURE.

## OSTEOLOGY.

### TERMINOLOGY ADOPTED IN TEXT

#### *Vertebral Column*

#### **Vertebrae**

Vertebral arch  
Vertebral foramen  
Pedicel  
Vertebral notch  
Costal demifacet  
Facet for tubercle of rib

#### **Atlas**

Facet for odontoid process

#### **Axis**

Odontoid process

#### **Sacrum**

Lateral part  
Sacral tuberosity  
  
Middle sacral crest  
  
Lateral sacral crests  
  
Sacral articular crests  
  
Vertebral canal

#### **Sternum**

Jugular notch  
Body  
Sternal angle  
Xiphoid process  
Anterior surface of sternum

#### **Ribs**

Costal groove

#### *Cranial Bones*

#### **Occipital bone**

Squama  
Highest nuchal line  
Superior nuchal line  
Inferior nuchal line  
Sagittal sulcus

Lateral part  
Hypoglossal canal  
Condylod canal  
Basilar part  
Superior border  
Upper half of inferior border

### BASLE TERMINOLOGY

#### *Columna Vertebralis*

#### **Vertebrae**

Arcus vertebrae  
Foramen vertebrale  
Radix arcus vertebrae  
Incisura vertebralis  
Fovea costalis  
Fovea costalis transversalis

#### **Atlas**

Fovea dentis

#### **Epistropheus**

Dens

#### **Os Sacrum**

Pars lateralis  
Tuberositas sacralis  
  
Crista sacralis media  
  
Cristae sacrales laterales  
  
Cristae sacrales articulares  
  
Canalis sacralis

#### **Sternum**

Incisura jugularis  
Corpus  
Angulus sterni  
Processus xiphoideus  
Planum sternale

#### **Costae**

Sulcus costae

#### *Ossa Cranii*

#### **Os occipitale**

Squama occipitalis  
Linea nuchae suprema  
Linea nuchae superior  
Linea nuchae inferior  
Sulcus sagittalis

Pars lateralis  
Canalis hypoglossi  
Canalis condyloideus  
Pars basilaris  
Margo lambdoideus  
Margo mastoideus

### OLD TERMINOLOGY

#### *Spinal Column*

#### **Vertebrae**

Neural arch  
Spinal foramen  
Pedicel  
Intervertebral notch  
Demifacet for head of rib  
Facet for tubercle of rib

#### **Atlas**

Facet for odontoid process

#### **Axis**

Odontoid process

#### **Sacrum**

Lateral mass  
Rough surface for posterior sacroiliac ligament  
Spinous processes of sacral vertebrae  
Transverse processes of sacral vertebrae  
Articular processes of sacral vertebrae  
Sacral canal

#### **Sternum (Breast bone)**

Suprasternal notch  
Gladiolus  
Angulus Ludovici  
Ensiform or xiphoid process  
Anterior surface of sternum

#### **Ribs**

Subcostal groove

#### *Cranial Bones*

#### **Occipital bone**

Tabular portion  
Highest curved line  
Superior curved line  
Inferior curved line  
Groove for superior longitudinal sinus  
Condylar portion  
Anterior condylod foramen  
Posterior condylod foramen  
Basilar process  
Superior border  
Upper half of inferior border

## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

**Parietal bone**

External surface  
Parietal eminence  
Temporal lines  
Internal surface  
Sagittal sulcus

Sagittal border  
Squamous border  
Frontal border  
Occipital border  
Frontal angle  
Sphenoidal angle  
Occipital angle  
Mastoid angle  
Groove for transverse sinus

**Frontal bone**

Squama  
External surface  
Orbital part  
Frontal eminence  
Zygomatic process  
Nasal part  
Frontal spine  
Internal surface  
Sagittal sulcus

**Temporal bone**

Squama  
Articular tubercle  
Mandibular fossa  
Petrotympenic fissure  
Mastoid notch  
Sigmoid sulcus  
Eminentia arcuata

Hiatus of facial canal  
Trigeminal impression

Internal acoustic meatus  
Canal for facial nerve  
Tympanic canaliculus

Mastoid canaliculus

Vaginal process

Tympanomastoid fissure  
Angles of petrous part  
Septum canalis musculotubarii  
Semicanalisis m. tensoris tympani  
Semicanalisis tubae auditivae  
Tympanic part  
External acoustic meatus

**Sphenoidal bone**

Chiasmatic groove  
Tuberculum sellae  
Fossa hypophyseos  
Sphenoidal crest  
Great wings  
Spina angularis  
Small wings  
Infratemporal crest  
Pterygoid canal  
Lateral pterygoid plate

Medial pterygoid plate

Sphenoidal conchae  
Pterygoid hamulus  
Pharyngeal canal

**Ethmoidal bone**

Cribiform plate  
Perpendicular plate  
Ethmoidal labyrinth  
Lamina papyracea  
Uncinate process  
Middle nasal concha  
Superior nasal concha

**Os parietale**

Facies parietalis  
Tuber parietale  
Lineae temporales  
Facies cerebialis  
Sulcus sagittalis

Margo sagittalis  
Margo squamosus  
Margo frontalis  
Margo occipitalis  
Angulus frontalis  
Angulus sphenoidalis  
Angulus occipitalis  
Angulus mastoideus  
Sulcus transversus

**Os frontale**

Squama frontalis  
Facies frontalis  
Pars orbitalis  
Tuber frontale  
Processus zygomaticus  
Pars nasalis  
Spina frontalis  
Facies cerebialis  
Sulcus sagittalis

**Os temporale**

Squama temporalis  
Tuberculum articulare  
Fossa mandibularis  
Fissura petrotympanica  
Incisura mastoidea  
Sulcus sigmoideus  
Eminentia arcuata

Hiatus canalis facialis  
Impressio trigemini

Meatus acusticus internus  
Canalis facialis [Fallopil]  
Canaliculus tympanicus

Canaliculus mastoideus

Vagina processus styloidei

Fissura tympanomastoidea  
Anguli pyramidis  
Septum canalis musculotubarii  
Semicanalisis m. tensoris tympani  
Semicanalisis tubae auditivae  
Pars tympanica  
Meatus acusticus externus

**Os sphenoidale**

Sulcus chiasmatis  
Tuberculum sellae  
Fossa hypophyseos  
Crista sphenoidalis  
Alae magna  
Spina angularis  
Alae parva  
Crista infratemporalis  
Canalis pterygoideus [Vidil]  
Lamina lateralis processus pterygoidei  
Lamina medialis processus pterygoidei  
Conchae sphenoidales  
Hamulus pterygoideus  
Canalis pharyngeus

**Os ethmoidale**

Lamina cribrosa  
Lamina perpendicularis  
Labyrinthus ethmoidalis  
Lamina papyracea  
Processus uncinatus  
Concha nasalis media  
Concha nasalis superior

**Parietal bone**

External surface  
Parietal eminence  
Temporal ridges  
Internal surface  
Groove for superior longitudinal sinus  
Superior border  
Inferior border  
Anterior border  
Posterior border  
Antero-superior angle  
Antero-inferior angle  
Postero-superior angle  
Postero-inferior angle  
Groove for lateral sinus

**Frontale bone**

Frontal or vertical portion  
External surface  
Horizontal part  
Frontal eminence  
External angular process  
Internal angular process  
Nasal spine  
Internal surface  
Groove for superior longitudinal sinus

**Temporal bone**

Squamous portion  
Eminentia articularis  
Glenoid cavity  
Glaserian fissure  
Digastric fossa  
Fossa sigmoidea  
Eminence for superior semicircular canal  
Hiatus Fallopii  
Impression for Gasserian ganglion  
Internal auditory meatus  
Aqueduct of Fallopius  
Canal for tympanic branch of glossopharyngeal nerve  
Canal for auricular branch of vagus  
Vaginal process of temporal bone  
Auricular fissure  
Borders of petrous part  
Processus cochleariformis  
Canal for Tensor tympani  
Bony part of Eustachian tube  
Tympanic plate  
External auditory meatus

**Sphenoid bone**

Optic groove  
Olivary eminence  
Pituitary fossa  
Ethmoidal crest  
Great wings  
Spinous process  
Small wings  
Pterygoid ridge  
Vidian canal  
External pterygoid plate  
Internal pterygoid plate  
Sphenoidal turbinated processes  
Hamular process  
Pterygopalatine canal

**Ethmoid bone**

Horizontal lamina  
Vertical plate  
Lateral mass  
Os planum  
Unciform process  
Middle turbinated process  
Superior turbinated process



## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

*Facial Bones**Ossa Faciei**Facial Bones***Nasal bones**

Groove for branch of nasociliary nerve

**Ossa nasalia**

Sulcus ethmoidalis

**Nasal bones**

Groove for nasal nerve

**Maxilla**

Anterior surface  
Infratemporal surface  
Alveolar canals  
Conchal crest  
Maxillary sinus  
Zygomatic process  
Frontal process  
Ethmoidal crest  
Palatine process  
Incisive foramen  
Incisive canal  
Os incisivum or premaxilla

**Maxilla**

Facies anterior  
Facies infratemporalis  
Canales alveolares  
Crista conchalis  
Sinus maxillaris  
Processus zygomaticus  
Processus frontalis  
Crista ethmoidalis  
Processus palatinus  
Foramen incisivum  
Canalis incisivum  
Os incisivum

**Superior maxillary bone; Upper jaw**

Facial or external surface  
Zygomatic surface  
Posterior dental canals  
Inferior turbinated crest  
Antrum of Highmore  
Malar process  
Nasal process  
Superior turbinated crest  
Palatal process  
Anterior palatine foramen  
Foramen of Stensen  
Premaxilla

**Lacrimal bone**

Posterior lacrimal crest  
Lacrimal hamulus

**Os lacrimale**

Crista lacrimalis posterior  
Hamulus lacrimalis

**Lacrimal bone**

Lacrimal crest  
Hamular process

**Zygomatic bone**

Malar surface  
Temporal surface  
Zygomaticofacial foramen  
Zygomaticotemporal foramen  
  
Frontosphenoidal process  
Zygomaticoörbital foramen

**Os zygomaticum**

Facies malaris  
Facies temporalis  
Foramen zygomaticofaciale  
Foramen zygomaticotem-  
porale  
Processus frontosphenoidalis  
Foramen zygomaticoorbitale

**Malar bone**

External surface  
Internal surface  
  
Malar foramina  
  
Frontal process  
Temporomalar canal

**Palatine bone**

Horizontal part  
Vertical part  
Conchal crest  
Ethmoidal crest  
Pterygopalatine canal  
Pyramidal process  
Lesser palatine foramina

**Os palatinum**

Pars horizontalis  
Pars perpendicularis  
Crista conchalis  
Crista ethmoidalis  
Canalis pterygopalatinus  
Processus pyramidalis  
Foramina palatina minora

**Palate bone**

Horizontal plate  
Perpendicular plate  
Inferior turbinated crest  
Superior turbinated crest  
Posterior palatine canal  
Tuberosity  
Accessory palatine foramina

**Inferior nasal concha****Concha nasalis inferior****Turbinated bone****Mandible**

Oblique line  
Mental spine  
Mylohyoid line  
Ramus  
Mandibular foramen  
Mandibular canal  
Mandibular notch

**Mandibula**

Linea obliqua  
Spina mentalis  
Linea mylohyoidea  
Ramus mandibulae  
Foramen mandibulare  
Canalis mandibulae  
Incisura mandibulae

**Inferior maxillary bone; Lower jaw**

External oblique line  
Genial tubercle  
Internal oblique line  
Perpendicular portions  
Inferior dental foramen  
Inferior dental canal  
Sigmoid notch

**Hyoïd bone**

Body  
Greater cornua  
Lesser cornua

**Os hyoideum**

Corpus ossei hyoidei  
Cornua majora  
Cornua minora

**Lingual bone**

Basihyal  
Thyrohyals  
Ceratohyals

*Skull**Cranium**Skull*

Sutural bones  
Greater palatine foramen  
Foramen lacerum  
Infratemporal fossa  
Inferior orbital fissure  
Pterygopalatine fossa  
Superior orbital fissure  
Nasal cavity  
Anterior nasal aperture  
Choanae

Ossa saturarum  
Foramen palatinum majus  
Foramen lacerum  
Fossa infratemporalis  
Fissura orbitalis inferior  
Fossa pterygopalatina  
Fissura orbitalis superior  
Cavum nasi  
Apertura piriformis  
Choanae

Wormian bones  
Posterior palatine foramen  
Foramen lacerum medium  
Zygomatic fossa  
Sphenomaxillary fissure  
Sphenomaxillary fossa  
Sphenoidal fissure  
Nasal fossa  
Anterior aperture of nose  
Posterior nares

*Bones of Upper Extremity**Ossa Extremitatis Superioris**Bones of Upper Extremity*

Shoulder girdle

Cingulum extremitatis superioris

Shoulder girdle

**Clavicle**

Coracoid tuberosity  
Costal tuberosity  
Sternal extremity  
Acromial extremity

**Clavicula**

Tuberositas coracoidea  
Tuberositas costalis  
Extremitas sternalis  
Extremitas acromialis

**Clavicle; Collar bone**

Conoid tubercle  
Rhomboid impression  
Internal extremity  
Outer extremity

TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Scapula</b>	<b>Scapula</b>	<b>Scapula; Shoulder blade</b>
Supraspinatous fossa	Fossa supraspinata	Supraspinous fossa
Infraspinatous fossa	Fossa infraspinata	Infraspinous fossa
Scapular notch	Incisura scapulae	Suprascapular notch
Medial angle	Angulus medialis	Superior angle
Lateral angle	Angulus lateralis	External angle
<b>Humerus</b>	<b>Humerus</b>	<b>Humerus; Arm bone</b>
Greater tubercle	Tuberculum majus	Greater tuberosity
Lesser tubercle	Tuberculum minus	Lesser tuberosity
Intertubercular groove	Sulcus intertubercularis	Bicipital groove
Crest of greater tubercle	Crista tuberculi majoris	External lip of bicipital groove
Crest of lesser tubercle	Crista tuberculi minoris	Internal lip of bicipital groove
Body	Corpus	Shaft
Lateral border	Margo lateralis	External border
Radial sulcus	Sulcus nervi radialis	Musculospiral groove
Medial border	Margo medialis	Internal border
Antero-lateral surface	Facies anterior lateralis	External surface
Antero-medial surface	Facies anterior medialis	Internal surface
Capitulum	Capitulum	Capitellum
Lateral epicondyle	Epicondylus lateralis	External condyle
Medial epicondyle	Epicondylus medialis	Internal condyle
<b>Ulna</b>	<b>Ulna</b>	<b>Ulna; Elbow bone</b>
Olecranon	Olecranon	Olecranon process
Tuberosity	Tuberositas ulnae	Tubercle
Semilunar notch	Incisura semilunaris	Greater sigmoid cavity
Radial notch	Incisura radialis	Lesser sigmoid cavity
Body	Corpus	Shaft
Volar border	Margo volaris	Anterior border
Dorsal border	Margo dorsalis	Posterior border
Interosseous crest	Crista interossea	External or interosseous border
Volar surface	Facies volaris	Anterior surface
Dorsal surface	Facies dorsalis	Posterior surface
Medial surface	Facies medialis	Internal surface
<b>Radius</b>	<b>Radius</b>	<b>Radius</b>
Radial tuberosity	Tuberositas radii	Bicipital tuberosity
Body	Corpus	Shaft
Volar border	Margo volaris	Anterior border
Dorsal border	Margo dorsalis	Posterior border
Interosseous crest	Crista interossea	Medial border
Volar surface	Facies volaris	Anterior surface
Dorsal surface	Facies dorsalis	Posterior surface
Lateral surface	Facies lateralis	External surface
Ulnar notch	Incisura ulnaris	Sigmoid cavity
<b>Carpus</b>	<b>Ossa Carpi</b>	<b>Carpus</b>
Navicular bone	Os naviculare manus	Scaphoid
Lunate bone	Os lunatum	Semilunar
Triangular bone	Os triquetrum	Cuneiform
Greater multangular bone	Os multangulum majus	Trapezium
Lesser multangular bone	Os multangulum minor	Trapezoid
Capitate bone	Os capitatum	Os magnum
Hamate bone	Os hamatum	Unciform
Hamulus	Hamulus oss. hamati	Unciform process
<i>Bones of Lower Extremity</i>	<i>Ossa Extremitatis Inferioris</i>	<i>Bones of Lower Extremity</i>
Pelvic girdle	Cingulum extremitatis inferioris	Pelvic girdle
<b>Hip-bone</b>	<b>Os coxae</b>	<b>Os innominatum</b>
Posterior gluteal line	Linea gluteae posterior	Superior curved line
Anterior gluteal line	Linea gluteae anterior	Middle curved line
Inferior gluteal line	Linea gluteae inferior	Inferior curved line
Arcuate line	Linea arcuata	Iliac part of iliopectineal line
Iliac tuberosity	Tuberositas iliaca	Rough surface for posterior sacroiliac ligament
Ischial spine	Spina ischiadica	Spine of ischium
Greater sciatic notch	Incisura ischiadica major	Greater sacrosciatic notch
Lesser sciatic notch	Incisura ischiadica minor	Lesser sacrosciatic notch
Superior ramus	Ramus superior ossis ischii	Descending ramus
Inferior ramus	Ramus inferior ossis ischii	Ascending ramus
Pubic tubercle	Tuberculum pubicum	Spine of pubis
Superior ramus	Ramus superior ossis pubis	Ascending ramus
Inferior ramus	Ramus inferior ossis pubis	Descending ramus
Acetabulum	Acetabulum	Cotyloid cavity
Obturator foramen	Foramen obturatum	Thyroid foramen
Pectineal line	Pecten ossis pubis	Pubic part of iliopectineal line
Glenoidal labrum	Labrum glenoidale	Cotyloid ligament
Acetabular notch	Incisura acetabuli	Cotyloid notch

## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

**Pelvis**

Linea terminalis  
Greater pelvis  
Lesser pelvis  
Superior aperture of pelvis  
Inferior aperture of pelvis

**Pelvis**

Linea terminalis  
Pelvis major  
Pelvis minor  
Apertura pelvis minoris superior  
Apertura pelvis minoris inferior

**Pelvis**

Circumference of inlet of true pelvis  
False pelvis  
True pelvis  
Pelvic inlet  
Pelvic outlet

**Femur**

Greater trochanter  
Trochanteric fossa  
Lesser trochanter  
Intertrochanteric line

Intertrochanteric crest  
Body  
Gluteal tuberosity  
Lateral condyle  
Medial condyle  
Intercondyloid fossa  
Medial epicondyle  
Lateral epicondyle  
Patellar surface

**Femur**

Trochanter major  
Fossa trochanterica  
Trochanter minor  
Linea intertrochanterica

Crista intertrochanterica  
Corpus  
Tuberositas glutea  
Condylus lateralis  
Condylus medialis  
Fossa intercondylea  
Epicondylus medialis  
Epicondylus lateralis  
Facies patellaris

**Femur; Thigh bone**

Great trochanter  
Digital fossa  
Small trochanter  
Anterior intertrochanteric or spiral line  
Posterior intertrochanteric line  
Shaft  
Gluteal ridge  
External condyle  
Internal condyle  
Intercondyloid notch  
Inner tuberosity  
Outer tuberosity  
Trochlea

**Tibia**

Medial condyle  
Lateral condyle  
Intercondyloid eminence  
Tuberosity  
Body  
Anterior crest  
Medial border  
Interosseous crest  
Medial surface  
Lateral surface  
Popliteal line  
Malleolar sulcus

**Tibia**

Condylus medialis  
Condylus lateralis  
Eminentia intercondyloidea  
Tuberositas tibiae  
Corpus  
Crista anterior  
Crista medialis  
Crista interossea  
Facies medialis  
Facies lateralis  
Linea poplitea  
Sulcus malleolaris

**Tibia; Shin bone**

Inner tuberosity  
Outer tuberosity  
Spine of tibia  
Tubercle  
Shaft  
Anterior border  
Internal border  
External border  
Internal surface  
External surface  
Oblique line of tibia  
Groove for tendons of Tibialis posterior and Flexor digitorum longus

**Fibula**

Apex of head  
Body  
Interosseous crest  
Lateral malleolus

**Fibula**

Apex capituli fibulae  
Corpus  
Crista interossea  
Malleolus lateralis

**Fibula; Calf bone**

Styloid process  
Shaft  
Antero-internal border  
External malleolus or distal extremity

**Tarsus**

Calcaneus  
Tuberosity  
Medial process  
Lateral process  
Trochlear process  
Talus  
Navicular bone  
First cuneiform bone  
Second cuneiform bone  
Third cuneiform bone

**Ossa Tarsi**

Calcaneus  
Tuber calcanei  
Processus medialis  
Processus lateralis  
Processus trochlearis  
Talus  
Os naviculare pedis  
Os cuneiforme primum  
Os cuneiforme secundum  
Os cuneiforme tertium

**Tarsus**

Os calcis  
Tuberosity  
Inner tubercle  
Outer tubercle  
Peroneal tubercle  
Astragalus or ankle bone  
Scaphoid bone  
Internal cuneiform  
Middle cuneiform  
External cuneiform

## SYNDESMOLOGY.

Synarthrosis  
Amphiarthrosis  
Diarthrosis  
Ginglymus  
Trochoid or Pivot joint  
Condyloid articulation  
Articulation by reciprocal reception  
Enarthrosis  
Arthrodia

Synarthrosis  
Amphiarthrosis  
Diarthrosis  
Ginglymus  
Articulatio trochoidea  
Articulatio ellipsoidea  
Articulatio sellaris  
Enarthrosis  
Arthrodia

Immovable articulations  
Slightly movable articulations  
Freely movable articulations  
Hinge-joint  
Rotary joint  
Condyloid articulation  
Saddle-joint  
Ball-and-socket joints  
Gliding joints

TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Articulations of the vertebral column and cranium</b>	<b>Ligamenta columnae vertebralis et cranii</b>	<b>Articulations of the spine and cranium</b>
Anterior longitudinal ligament	Lig. longitudinale anterius	Anterior common ligament
Posterior longitudinal ligament	Lig. longitudinale posterius	Posterior common ligament
Intervertebral fibrocartilages	Fibrocartilagine intervertebrales	Intervertebral disks
Ligamenta flava	Ligg. flava	Ligamenta subflava
Supraspinal ligament	Lig. supraspinale	Supraspinous ligament
Interspinal ligaments	Ligg. interspinalia	Interspinal ligaments
Cruciate ligament of the atlas	Lig. cruciatum atlantis	Cruciform ligament
Anterior atlantoöccipital membrane	Membrana atlantoöccipitalis anterior	Anterior atlantoöccipital ligament
Posterior atlantoöccipital membrane	Membrana atlantoöccipitalis posterior	Posterior atlantoöccipital ligament
Membrana tectoria	Membrana tectoria	Occipitoaxial ligament
Alar ligaments	Ligg. alaria	Odontoid or check ligaments
<b>Articulation of the mandible</b>	<b>Articulatio mandibularis</b>	<b>Temporomandibular articulation</b>
Temporomandibular ligament	Lig. temporomandibulare	External lateral ligament
Sphenomandibular ligament	Lig. sphenomandibulare	Internal lateral ligament
Articular disk	Discus articularis	Articular meniscus
Stylomandibular ligament	Lig. stylomandibulare	Stylomaxillary ligament
<b>Articulations of the heads of the ribs</b>	<b>Articulationes capitulorum</b>	<b>Costocentral articulations</b>
Radiate ligament	Lig. capituli costae radiatum	Anterior costovertebral or stellate ligament
Interarticular ligament	Lig. capituli costae interarticularae	Intraarticular ligament
<b>Costotransverse articulations</b>	<b>Articulationes costotransversariae</b>	<b>Costotransverse articulations</b>
Anterior costotransverse ligament	Lig. costotransversarium anterius	Anterior superior ligament
Ligament of the neck of the rib	Lig. colli costae	Middle costotransverse ligament
Ligament of the tubercle of the rib	Lig. tuberculi costae	Posterior costotransverse ligament
<b>Sternocostal articulations</b>	<b>Articulationes sternocostales</b>	<b>Chondrosternal articulations</b>
Radiate sternocostal ligaments	Ligg. sternocostalia radiata	Chondrosternal or sternocostal ligaments
Interarticular sternocostal ligament	Lig. sternocostale interarticularae	Intraarticular chondrosternal ligament
Costoxiphoid ligaments	Ligg. costoxiphoidea	Chondroxiphoid ligaments
<b>Interchondral articulations</b>	<b>Articulationes interchondrales</b>	<b>Articulations of the cartilages of the ribs with each other</b>
<b>Articulations of the pelvis</b>	<b>Ligg. cinguli extremitatis inferioris</b>	<b>Articulations of the pelvis</b>
Sacroterous ligament	Lig. sacrotuberosum	Great or posterior sacrosciatic ligament
Sacrospinous ligament	Lig. sacrospinosum	Small or anterior sacrosciatic ligament
Sacrococcygeal symphysis	Symphysis sacrococcygea	Articulation of the sacrum and coccyx
Lateral sacrococcygeal ligament	Lig. sacrococcygeum laterale	Intertransverse ligament
Pubic symphysis	Symphysis ossium pubis	Articulation of the pubic bones
Greater sciatic foramen	Foramen ischiadicum majus	Great sacrosciatic foramen
Lesser sciatic foramen	Foramen ischiadicum minus	Small sacrosciatic foramen
Pubic arcuate ligament	Lig. arcuatum pubis	Subpubic ligament
Interpubic fibrocartilaginous lamina	Lamina fibrocartilaginea interpubica	Interpubic disk
<b>Sternoclavicular articulation</b>	<b>Articulatio sternoclaviculare</b>	<b>Sternoclavicular articulation</b>
Costoclavicular ligament	Lig. costoclaviculare	Rhomboid ligament
Articular disk	Discus articularis	Interarticular fibrocartilage
<b>Acromioclavicular articulation</b>	<b>Articulatio acromioclavicularis</b>	<b>Scapuloclavicular articulation</b>
<b>Ligaments of the scapula</b>	<b>Ligg. cinguli extremitatis superioris</b>	<b>Ligaments of the scapula</b>
Superior transverse ligament	Lig. transversum scapulae superius	Suprascapular ligament
Inferior transverse ligament	Lig. transversum scapulae inferius	Spinoglenoid ligament
<b>Humeral articulation</b>	<b>Articulatio humeri</b>	<b>Shoulder-joint</b>
Glenoidal labrum	Labrum glenoidale	Glenoid ligament
<b>Elbow-joint</b>	<b>Articulatio cubiti</b>	<b>Elbow-joint</b>
Ulnar collateral ligament	Lig. collaterale ulnare	Internal lateral ligament
Radial collateral ligament	Lig. collaterale radiale	External lateral ligament

TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Proximal radioulnar articulation</b>	<b>Articulatio radioulnaris proximalis</b>	<b>Superior radioulnar joint</b>
Annular ligament	Lig. annulare radii	Orbicular ligament
Oblique cord	Chorda obliqua	Oblique ligament
<b>Distal radioulnar articulation</b>	<b>Articulatio radioulnaris distalis</b>	<b>Inferior radioulnar joint</b>
Articular disk	Discus articularis	Triangular articular disk
<b>Radiocarpal articulation</b>	<b>Articulatio radiocarpeae</b>	<b>Wrist-joint</b>
Volar radiocarpal ligament	Lig. radiocarpeum volare	Anterior ligament of the radiocarpal joint
Dorsal radiocarpal ligament	Lig. radiocarpeum dorsale	Posterior ligament of the radiocarpal joint
Ulnar collateral ligament	Lig. collaterale carpi ulnare	Internal lateral ligament
Radial collateral ligament	Lig. collaterale carpi radiale	External lateral ligament
<b>Intercarpal articulations</b>	<b>Articulationes intercarpeae</b>	<b>Carpal joints</b>
Volar ligaments	Ligg. intercarpea volaria	Palmar ligaments
<b>Intermetacarpal articulations</b>	<b>Articulationes intermetacarpeae</b>	<b>Articulations of metacarpal bones with each other</b>
Transverse metacarpal ligament	Lig. capitulum (oss. metacarpalium) transversa	Transverse metacarpal ligament
<b>Metacarpophalangeal articulations</b>	<b>Articulationes metacarpophalangeae</b>	<b>Metacarpophalangeal joints</b>
Volar ligaments	Ligg. metacarpophalangeae volaria	Glenoid ligament of Cruveilhier; palmar or vaginal ligaments
Collateral ligaments	Ligg. collateralia	Lateral ligaments
<b>Articulation of the digits</b>	<b>Articulationes digitorum manus</b>	<b>Articulation of the phalanges</b>
<b>Coxal articulation</b>	<b>Articulatio coxae</b>	<b>Hip-joint</b>
Articular capsule	Capsula articularis	Capsular ligament
Iliofemoral ligament	Lig. iliofemorale	Y-ligament; ligament of Bigelow
Pubocapsular ligament	Lig. pubocapsulare	Pubofemoral band
Ischiocapsular ligament	Lig. ischiocapsulare	Ligament of Bertin
Glenoid labrum	Labrum glenoidale	Cotyloid ligament
Transverse acetabular ligament	Lig. transversum acetabuli	Transverse ligament
<b>Knee-joint</b>	<b>Articulatio genu</b>	<b>Knee-joint</b>
Articular capsule	Capsula articularis	Capsular ligament
Patellar retinacula	Retinacula patellae	Lateral patellar ligaments
Oblique popliteal ligament	Lig. popliteum obliquum	Posterior ligament
Tibial collateral ligament	Lig. collaterale tibiale	Internal lateral ligament
Fibular collateral ligament	Lig. collaterale fibulare	External lateral or long external lateral ligament
Cruciate ligaments	Ligg. cruciata genu	Crucial ligaments
Anterior cruciate ligament	Lig. cruciatum anterius	External crucial ligament
Posterior cruciate ligament	Lig. cruciatum posterius	Internal crucial ligament
Menisci	Menisci	Semilunar fibrocartilages
Medial meniscus	Meniscus medialis	Internal semilunar cartilage
Lateral meniscus	Meniscus lateralis	External semilunar cartilage
Alar folds	Plicae alares	Ligamenta alaria
Patellar fold	Plica synovialis patellaris	Ligamentum mucosum
<b>Tibiofibular articulation</b>	<b>Articulatio tibiofibularis</b>	<b>Superior tibiofibular articulation</b>
Articular capsule	Capsula articularis	Capsular ligament
Ligaments of head of fibula	Ligg. capituli fibulae	Anterior and posterior superior tibiofibular ligaments
<b>Interosseous membrane</b>	<b>Membrana interossea cruris</b>	<b>Middle tibiofibular ligament</b>
<b>Tibiofibular syndesmosis</b>	<b>Syndesmosis tibiofibulare</b>	<b>Inferior tibiofibular articulation</b>
Anterior ligament	Lig. malleoli lateralis anterius	Anterior inferior ligament
Posterior ligament	Lig. malleoli lateralis posterius	Posterior inferior ligament
<b>Talocrural articulation</b>	<b>Articulatio talocruralis</b>	<b>Ankle-joint; tibiotarsal articulation</b>
Articular capsule	Capsula articularis	Capsular ligament
Deltoid ligament	Lig. deltoideum	Internal lateral ligament
Anterior talofibular ligament	Lig. talofibulare anterius	Anterior fasciculus
Posterior talofibular ligament	Lig. talofibulare posterius	Posterior fasciculus
Calcaneofibular ligament	Lig. calcaneofibulare	Middle fasciculus
<b>Intertarsal articulations</b>	<b>Articulationes intertarsae</b>	<b>Articulations of the tarsus</b>



TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Talocalcaneal articulation</b>	<b>Articulatio talocalcanea</b>	<b>Articulation of calcaneus and astragalus; calcaneo-astragaloid articulation</b>
Articular capsule	Capsula articularis	Capsular ligament
Anterior talocalcaneal ligament	Lig. talocalcaneum anterius	Anterior calcaneo-astragaloid ligament
Posterior talocalcaneal ligament	Lig. talocalcaneum posterius	Posterior calcaneo-astragaloid ligament
Lateral talocalcaneal ligament	Lig. talocalcaneum laterale	External calcaneo-astragaloid ligament
Medial talocalcaneal ligament	Lig. talocalcaneum mediale	Internal calcaneo-astragaloid ligament
<b>Talocalcaneonavicular articulation</b>	<b>Articulatio talocalcaneonavicularis</b>	<b>Talocalcaneonavicular articulation</b>
Articular capsule	Capsula articularis	Capsular ligament
Dorsal talonavicular ligament	Lig. talonaviculare dorsale	Superior astragalonavicular ligament
<b>Calcaneocuboid articulation</b>	<b>Articulatio calcaneocuboides</b>	<b>Articulation of calcaneus with cuboid</b>
Articular capsule	Capsula articularis	Capsular ligament
Dorsal calcaneocuboid ligament	Lig. calcaneocuboides dorsale	Superior calcaneocuboid ligament
Bifurcated ligament	Lig. bifurcatum	
Calcaneonavicular part of	Pars calcaneonavicularis	Superior calcaneonavicular ligament
Calcaneocuboid part of	Pars calcaneocuboid	Internal calcaneocuboid ligament
Long plantar ligament	Lig. plantare longum	Long calcaneocuboid or superficial long plantar ligament
Plantar calcaneocuboid ligament	Lig. calcaneocuboides plantare	Short plantar ligament
Plantar calcaneonavicular ligament	Lig. calcaneonaviculare plantare	Inferior calcaneonavicular ligament
<b>Cuneonavicular articulation</b>	<b>Articulatio cuneonavicularis</b>	<b>Articulation of navicular with cuneiform bone</b>
<b>Articulation of the digits</b>	<b>Articulationes digitorum pedis</b>	<b>Articulations of the phalanges</b>

## MYOLOGY.

Epicranius	Epicranius	Occipitofrontalis
Galea aponeurotica	Galea aponeurotica	Epicranial aponeurosis
Orbicularis oculi	Orbicularis oculi	Orbicularis palpebrarum
Lacrimal part	Pars lacrimalis	Tensor tarsi
Corrugator	Corrugator	Corrugator supercilii
Procerus	Procerus	Pyramidalis nasi
Nasalis	Nasalis	Compressor naris
Depressor septi	Depressor septi	Depressor alae nasi
Quadratus labii superioris	Quadratus labii superioris	
Zygomatic head	Caput zygomaticum	Zygomaticus minor
Infraorbital head	Caput infraorbitale	Levator labii superioris
Angular head	Caput angulare	Levator labii superioris alaeque nasi
Caninus	Caninus	Levator anguli oris
Zygomaticus	Zygomaticus	Zygomaticus major
Mentalis	Mentalis	Levator menti
Quadratus labii inferioris	Quadratus labii inferioris	Depressor labii inferioris; Quadratus menti
Triangularis	Triangularis	Depressor anguli oris
Pterygomandibular raphé		Pterygomandibular ligament
Parotidomasseteric fascia	Fascia parotidomasseterica	Masseteric fascia
Temporalis	Temporalis	Temporal
Pterygoideus externus	Pterygoideus externus	External pterygoid
Pterygoideus internus	Pterygoideus internus	Internal pterygoid
Fascia colli	Fascia colli	Deep cervical fascia
Sternocleidomastoideus	Sternocleidomastoideus	Sternomastoid
Digastricus	Digastricus	Digastric
Stylohyoideus	Stylohyoideus	Stylohyoid
Mylohyoideus	Mylohyoideus	Mylohyoid
Geniohyoideus	Geniohyoideus	Geniohyoid
Sternohyoideus	Sternohyoideus	Sternohyoid
Omohyoideus	Omohyoideus	Omohyoid
Sternothyreoideus	Sternothyreoideus	Sternothyroid
Thyreohyoideus	Thyreohyoideus	Thyrohyoid
Longus capitis	Longus capitis	Rectus capitis anticus major
Rectus capitis anterior	Rectus capitis anterior	Rectus capitis anticus minor

## TERMINOLOGY ADOPTED IN TEXT

Scalenus anterior  
 Scalenus posterior  
 Lumbodorsal fascia  
  
 Splenius cervicis  
 Sacrospinalis  
 Iliocostalis  
     " lumborum  
     " dorsi  
     " cervicis  
 Longissimus  
     " dorsi  
     " cervicis  
     " capitis  
 Spinalis dorsi  
     " cervicis  
     " capitis  
 Semispinalis dorsi  
     " cervicis  
     " capitis  
  
 Multifidus  
 Rotatores  
 Intertransversarii  
 Rectus capitis posterior major  
 Rectus capitis posterior minor  
 Obliquus capitis inferior  
 Obliquus capitis superior  
 Intercostales  
 Intercostales externi  
 Intercostales interni  
 Subcostales  
 Transversus thoracis  
 Serratus posterior superior  
 Serratus posterior inferior  
 Diaphragma  
     Medial crus  
     Intermediate crus  
     Lateral crus  
 Medial lumbocostal arch  
  
 Lateral lumbocostal arch  
  
 Obliquus externus abdominis  
 Subcutaneous inguinal ring  
     Superior crus  
     Inferior crus  
 Intercrural fibres  
 Inguinal ligament  
  
 Lacunar ligament  
  
 Reflected inguinal ligament  
  
 Obliquus internus abdominis  
 Transversus abdominis  
 Inguinal aponeurotic falx  
  
 Tendinous inscriptions  
 Linea semicircularis  
 Abdominal inguinal ring  
 Inguinal canal  
 Superior fascia of pelvic dia-  
     phragm  
 Inferior fascia of pelvic dia-  
     phragm  
 Tendinous arch of pelvic fascia  
 Sphincter ani externus  
 Sphincter ani internus  
 Transversus perinae superficialis  
 Bulbocavernosus  
  
 Ischiocavernosus  
 Urogenital diaphragm  
 Superior fascia of urogenital  
     diaphragm  
 Inferior fascia of urogenital  
     diaphragm  
 Transversus perinae pro-  
     fundus  
 Sphincter urethrae mem-  
     branaceae  
 Levator scapulae  
 Pectoral fascia

## BASLE TERMINOLOGY

Scalenus anterior  
 Scalenus posterior  
 Fascia lumbodorsalis  
  
 Splenius cervicis  
 Sacrospinalis  
 Iliocostalis  
     " lumborum  
     " dorsi  
     " cervicis  
 Longissimus  
     " dorsi  
     " cervicis  
     " capitis  
 Spinalis dorsi  
     " cervicis  
     " capitis  
 Semispinalis dorsi  
     " cervicis  
     " capitis  
  
 Multifidus  
 Rotatores  
 Intertransversarii  
 Rectus capitis posterior major  
 Rectus capitis posterior minor  
 Obliquus capitis inferior  
 Obliquus capitis superior  
 Intercostales  
 Intercostales externi  
 Intercostales interni  
 Subcostales  
 Transversus thoracis  
 Serratus posterior superior  
 Serratus posterior inferior  
 Diaphragma  
     Crus mediale  
     Crus intermedium  
     Crus laterale  
 Arcus lumbocostalis medialis  
     [Halleri]  
 Arcus lumbocostalis lateralis  
     [Halleri]  
 Obliquus externus abdominis  
 Annulus inguinalis subcutaneus  
     Crus superior  
     Crus inferior  
 Fibrae intercrurales  
 Ligamentum inguinale [Pou-  
     parti]  
 Ligamentum lacunare [Gimber-  
     nati]  
 Ligamentum inguinale reflexum  
     [Collesi]  
 Obliquus internus abdominis  
 Transversus abdominis  
 Falx aponeurotica inguinalis  
  
 Inscriptiones tendineae  
 Linea semicircularis [Douglasi]  
 Annulus inguinalis abdominalis  
 Canalis inguinalis  
 Fascia diaphragmatis pelvis  
     superior  
 Fascia diaphragmatis pelvis  
     inferior  
 Arcus tendineus fasciae pelvis  
 Sphincter ani externus  
 Sphincter ani internus  
 Transversus perinae superficialis  
 Bulbocavernosus  
  
 Ischiocavernosus  
 Diaphragma urogenitale  
 Fascia diaphragmatis urogeni-  
     talis superior  
 Fascia diaphragmatis urogeni-  
     talis inferior  
 Transversus perinae pro-  
     fundus  
 Sphincter urethrae mem-  
     branaceae  
 Levator scapulae  
 Fascia pectoralis

## OLD TERMINOLOGY

Scalenus anticus  
 Scalenus posticus  
 Lumbar aponeurosis and ver-  
     tebral fascia  
 Splenius colli  
 Erector spinae  
 Iliocostalis  
     Sacrolumbalis  
     Musculus accessorius  
     Cervicalis ascendens  
 Longissimus dorsi  
     " dorsi  
     Transversalis cervicis  
     Trachelomastoideus  
 Spinalis dorsi  
     " colli  
 Biventer cervicis  
 Semispinalis dorsi  
     " colli  
  
 Complexus  
 Multifidus spinae  
 Rotatores spinae  
 Intertransversales  
 Rectus capitis posticus major  
 Rectus capitis posticus minor  
 Obliquus inferior  
 Obliquus superior  
 Intercostal  
 External intercostal  
 Internal intercostal  
 Infracostales  
 Triangularis sterni  
 Serratus posticus superior  
 Serratus posticus inferior  
 Diaphragm  
     {Crura and origins from  
       arcuate ligaments  
 Internal arcuate ligament  
  
 External arcuate ligament  
  
 External or descending oblique  
 External abdominal ring  
     Internal pillar  
     External pillar  
 Intercolumnar fibres  
 Poupart's ligament  
  
 Gimbernati's ligament  
  
 Triangular fascia  
  
 Internal or ascending oblique  
 Transversalis abdominis  
 Conjoined tendon of Internal  
     oblique and Transversalis  
 Lineae transversae  
 Fold of Douglas  
 Internal or deep abdominal ring  
 Spermatic canal  
 Visceral layer of pelvic fascia  
  
 Anal fascia  
  
 White line of pelvic fascia  
 External sphincter ani  
 Internal sphincter ani  
 Transversus perinae  
 Ejaculator urinae or Sphincter  
     vaginae  
 Erector penis vel clitoridis  
 Constrictor urethrae  
 Deep layer of triangular liga-  
     ment  
 Superficial layer of triangular  
     ligament  
  
 Constrictor urethrae  
  
 Levator anguli scapulae  
 Deep fascia of anterior thoracic  
     region

## TERMINOLOGY ADOPTED IN TEXT

Coracoclavicular fascia  
Serratus anterior  
Deltoideus  
Brachial fascia  
Biceps brachii  
Lactertus fibrosus  
Brachialis  
Triceps brachii  
Medial head  
Long head  
Lateral head  
Antibrachial fascia  
Pronator teres  
Humeral head  
Ulnar head  
Brachioradialis  
Extensor carpi radialis longus  
Extensor carpi radialis brevis  
Extensor digiti quinti proprius  
Supinator  
Abductor pollicis longus  
Extensor pollicis brevis  
  
Extensor pollicis longus  
  
Extensor indicis proprius  
Transverse carpal ligament  
Dorsal carpal ligament  
Mucous sheaths  
Palmar aponeurosis  
Superficial transverse ligament  
Abductor pollicis brevis  
Abductor digiti quinti  
Flexor digiti quinti brevis  
Opponens digiti quinti  
Interossei dorsales  
Interossei volares  
Psoas major  
Psoas minor  
Fascia cribrosa  
Fossa ovalis  
Iliotibial band  
Tensor fasciae latae  
Quadriceps femoris  
Rectus femoris  
Vastus lateralis  
Vastus medialis  
Vastus intermedius  
Articularis genu  
Biceps femoris  
Tibialis anterior  
Extensor hallucis longus  
Tendo calcaneus  
Tibialis posterior  
Transverse crural ligament  
  
Cruciate crural ligament  
  
Lacinate ligament  
Superior peroneal retinaculum  
  
Plantar aponeurosis  
Quadratus plantae  
Adductor hallucis  
Abductor digiti quinti  
Flexor digiti quinti brevis  
Interossei dorsales  
Interossei plantares

## BASLE TERMINOLOGY

Fascia coracoclavicularis  
Serratus anterior  
Deltoideus  
Fascia brachii  
Biceps brachii  
Lactertus fibrosus  
Brachialis  
Triceps brachii  
Caput mediale  
Caput longum  
Caput laterale  
Fascia antibrachii  
Pronator teres  
Caput humerale  
Caput ulnare  
Brachioradialis  
Extensor carpi radialis longus  
Extensor carpi radialis brevis  
Extensor digiti quinti proprius  
Supinator  
Abductor pollicis longus  
Extensor pollicis brevis  
  
Extensor pollicis longus  
  
Extensor indicis proprius  
Lig. carpi transversum  
Lig. carpi dorsale  
Vaginae mucosae  
Aponeurosis palmaris  
Fasciculi transversi  
Abductor pollicis brevis  
Abductor digiti quinti  
Flexor digiti quinti brevis  
Opponens digiti quinti  
Interossei dorsales  
Interossei volares  
Psoas major  
Psoas minor  
Fascia cribrosa  
Fossa ovalis  
Tractus iliotibialis  
Tensor fasciae latae  
Quadriceps femoris  
Rectus femoris  
Vastus lateralis  
Vastus medialis  
Vastus intermedius  
Articularis genu  
Biceps femoris  
Tibialis anterior  
Extensor hallucis longus  
Tendo calcaneus [Achillis]  
Tibialis posterior  
Lig. transversum cruris  
  
Lig. cruciatum cruris  
  
Lig. laciniatum  
Retinaculum mm. peroneorum superius  
Aponeurosis plantaris  
Quadratus plantae  
Adductor hallucis  
Abductor digiti quinti  
Flexor digiti quinti brevis  
Interossei dorsales  
Interossei plantares

## OLD TERMINOLOGY

Costocoracoid membrane  
Serratus magnus  
Deltoid  
Deep fascia of arm  
Biceps; Biceps flexor cubiti  
Bicipital fascia  
Brachialis anticus  
Triceps; Triceps extensor cubiti  
Inner head  
Long head  
Outer head  
Deep fascia of forearm  
Pronator radii teres  
Humeral head  
Coronoid head  
Supinator longus  
Extensor carpi radialis longior  
Extensor carpi radialis brevior  
Extensor minimi digiti  
Supinator brevis  
Extensor ossis metacarpi pollicis  
Extensor primi internodii pollicis  
Extensor secundi internodii pollicis  
Extensor indicis  
Anterior annular ligament  
Posterior annular ligament  
Synovial sheaths  
Palmar fascia  
Superficial transverse ligament  
Abductor pollicis  
Abductor minimi digiti  
Flexor brevis minimi digiti  
Opponens minimi digiti  
Dorsal interossei  
Palmar interossei  
Psoas magnus  
Psoas parvus  
Cribiform fascia  
Saphenous opening  
Iliotibial band  
Tensor fasciae femoris  
Quadriceps extensor  
Rectus femoris  
Vastus externus  
Vastus internus  
Crureus  
Subcrureus  
Biceps  
Tibialis anticus  
Extensor proprius hallucis  
Tendo Achillis  
Tibialis posticus  
Upper part of anterior annular ligament  
Lower part of anterior annular ligament  
Internal annular ligament  
External annular ligament  
  
Plantar fascia  
Flexor accessorius  
Adductor obliquus hallucis  
Abductor minimi digiti  
Flexor brevis minimi digiti  
Dorsal interossei  
Plantar interossei

## ANGIOLOGY.

## Heart

Coronary sulcus  
Anterior longitudinal sulcus  
Posterior longitudinal sulcus  
  
Atrium  
Sinus venarum

## Cor

Sulcus coronarius  
Sulcus longitudinalis anterior  
Sulcus longitudinalis posterior  
  
Atrium  
Sinus venarum

## Heart

Auriculoventricular groove  
Anterior interventricular groove  
Posterior interventricular groove  
Auricle  
Sinus venosus

## TERMINOLOGY ADOPTED IN TEXT

**Heart (continued)**

Auricula  
Valve of inferior vena cava  
  
Valve of coronary sinus  
  
Limbus fossae ovalis  
Intervenous tubercle  
Tricuspid valve  
    Anterior cusp  
    Posterior cusp  
    Medial cusp  
Trabeculae carneae  
Nodules of semilunar valves  
  
Bicuspid valve  
Aortic sinuses  
Ventricular septum

**Arteries**

Pulmonary artery  
Ascending aorta  
Right coronary artery  
Left coronary artery  
Arch of aorta  
Innominate artery  
Common carotid artery  
External carotid artery  
Superior thyroid artery  
    Hyoïd branch  
    Sternocleidomastoid branch  
Lingual artery  
    Hyoïd branch  
    A. dorsalis linguae  
    A. profunda linguae  
  
External maxillary artery  
    Inferior labial artery  
    Superior labial artery  
Sternocleidomastoid artery  
Descending branch of occipital artery  
Anterior tympanic artery  
Accessory meningeal branch  
Inferior alveolar artery  
Buccinator artery  
Posterior superior alveolar artery  
Caroticotympanic branch  
  
Artery of pterygoid canal  
Sphenopalatine artery  
Medial palpebral arteries  
Anterior choroidal artery  
Dorsal nasal artery  
Arterial circle of Willis  
Meningeal branch of vertebrae  
Posterior spinal artery  
Anterior spinal artery  
Internal auditory artery  
Thyrocervical trunk  
Transverse scapular artery  
Transverse cervical artery  
    Ascending branch  
    Descending branch  
Pericardiophrenic artery  
Costocervical trunk  
Highest intercostal artery }  
Highest thoracic artery }  
Thoracoacromial artery

    Deltoid branch  
Lateral thoracic artery  
Scapular circumflex artery  
Posterior humeral circumflex artery  
Anterior humeral circumflex artery  
A. profunda brachii  
    Radial collateral artery  
  
Superior ulnar collateral artery  
Inferior ulnar collateral artery

## BASLE TERMINOLOGY

**Cor (continued)**

Auricula  
Valvula venae cavae inferioris [Eustachii]  
Valvula sinus coronarii [Thebesii]  
Limbus fossae ovalis  
Tuberculum intervenosum  
Valvula tricuspidalis  
    Cuspus anterior  
    Cuspus posterior  
    Cuspus medialis  
Trabeculae carneae  
Noduli valvularum semilunarium [Arantii]  
Valvula bicuspidalis [mitralis]  
Sinus aortae [Valsalvae]  
Septum ventriculorum

**Arteriae**

A. pulmonalis  
Aorta ascendens  
A. coronaria (cordis) dextra  
A. coronaria (cordis) sinistra  
Arcus aortae  
A. anonyma  
A. carotis communis  
A. carotis externa  
A. thyroidea superior  
    Ramus hyoideus  
    Ramus sternocleidomastoideus  
A. lingualis  
    Ramus hyoideus  
    A. dorsalis linguae  
    A. profunda linguae  
  
A. maxillaris externa  
    A. labialis inferior  
    A. labialis superior  
A. sternomastoidea  
Ramus descendens a. occipitalis  
  
A. tympanica anterior  
Ramus meningeus accessorius  
A. alveolaris inferior  
A. buccinatoria  
A. alveolaris superior posterior  
  
Ramus caroticotympanicus  
  
A. canalis pterygoidei [Vidii]  
A. sphenopalatina  
Aa. palpebrales mediales  
A. chorioidea  
A. dorsalis nasi  
Circulus arteriosus [Willisii]  
Ramus meningeus  
A. spinalis posterior  
A. spinalis anterior  
A. auditiva interna  
Truncus thyrocervicalis  
A. transversa scapulae  
A. transversa colli  
    Ramus ascendens  
    Ramus descendens  
A. pericardiophrenica  
Truncus costocervicalis }  
A. intercostalis suprema }  
A. thoracalis suprema  
A. thoracoacromialis

    Ramus deltoideus  
A. thoracalis lateralis  
A. circumflexa scapulae  
A. circumflexa humeri posterior  
  
A. circumflexa humeri anterior  
  
A. profunda brachii  
    A. collateralis radialis  
  
A. collateralis ulnaris superior  
A. collateralis ulnaris inferior

## OLD TERMINOLOGY

**Heart (continued)**

Auricular appendix  
Eustachian valve  
  
Thebesian valve  
  
Annulus ovalis  
Tubercle of Lower  
Tricuspid valve  
    Infundibular cusp  
    Marginal cusp  
    Septal cusp  
Columnae carneae  
Corpora Arantii  
  
Mitral valve  
Sinuses of Valsalva  
Interventricular septum

**Arteries**

Pulmonary artery  
Ascending aorta  
Right coronary artery  
Left coronary artery  
Transverse aorta  
Brachiocephalic artery  
Common carotid artery  
External carotid artery  
Superior thyroid artery  
    Infrahyoid branch  
    Sternomastoid branch  
Lingual artery  
    Suprahyoid branch  
    Rami dorsalis linguae  
    Ranine artery; deep lingual artery  
Facial artery  
    Inferior coronary artery  
    Superior coronary artery  
Sternomastoid artery  
Arteria princeps cervicis  
  
Tympanic artery  
Small meningeal artery  
Inferior dental artery  
Buccal artery  
Alveolar or posterior dental artery  
Tympanic branch of internal carotid artery  
Vidian artery  
Nasopalatine artery  
Internal palpebral arteries  
Choroid artery  
Nasal artery  
Circle of Willis  
Posterior meningeal branch  
Dorsal spinal artery  
Ventral spinal artery  
Auditory artery  
Thyroid axis  
Suprascapular artery  
Transversalis colli artery  
    Superficial cervical artery  
    Posterior scapular artery  
A. comes nervi phrenici  
Superior intercostal artery  
Superior thoracic artery  
Acromiothoracic artery; thoracic axis  
    Humeral branch  
Long thoracic artery  
Dorsalis scapulae artery  
Posterior circumflex artery  
  
Anterior circumflex artery  
  
Superior profunda artery  
Ant. branch of sup. profunda artery  
Inferior profunda artery  
Anastomotica magna artery

## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

**Arteries (continued)**

Volar carpal branch  
 Superficial volar branch  
 Dorsal carpal branch  
 Dorsal metacarpal arteries  
*A. volaris indicis radialis*  
 Deep volar arch  
 Volar metacarpal arteries  
 Volar interosseous artery  
 Dorsal interosseous artery  
 Volar carpal branch of ulnar  
 Dorsal carpal branch of ulnar  
 Deep volar branch of ulnar  
 Superficial volar arch  
 Common volar digital arteries  
 Proper volar digital arteries  
 Coeliac artery  
   Left gastric artery  
   Right gastric artery  
   Lienal artery  
   Short gastric arteries  
 Intestinal arteries  
 Middle suprarenal artery  
 Internal spermatic arteries  
 Hypogastric artery  
 Internal pudendal artery  
   Perineal artery  
   Posterior scrotal arteries  
   Deep artery of penis  
 Inferior gluteal artery  
 Superior gluteal artery  
 Inferior epigastric artery  
   External spermatic artery  
 Femoral canal  
 Femoral ring  
 Femoral septum  
 Femoral triangle

Adductor canal  
 Superficial external pudendal artery  
 Deep external pudendal artery  
 Profunda femoris artery  
 Lateral femoral circumflex artery  
 Medial femoral circumflex artery  
 Highest genicular artery  
 Sural arteries  
 Superior genicular arteries  
 Middle genicular artery  
 Inferior genicular arteries  
 Anterior medial malleolar artery  
 Anterior lateral malleolar artery  
 Lateral tarsal artery  
 Arcuate artery  
 Dorsal metatarsal arteries  
 Deep plantar artery  
 Peroneal artery  
   Perforating branch  
   Lateral calcaneal  
   Posterior medial malleolar artery  
   Medial calcaneal  
 Medial plantar artery  
 Lateral plantar artery  
 Plantar metatarsal arteries  
 Plantar digital arteries

**Veins**

Great cardiac vein  
 Small cardiac vein  
 Oblique vein of left atrium  
  
 Ligament of left vena cava  
 Smallest cardiac veins  
 Anterior facial vein  
 Posterior facial vein  
 Deep cervical vein  
  
 Middle cerebral vein  
 Internal cerebral veins  
 Great cerebral vein  
 Terminal vein  
 Superior sagittal sinus

**Arteriae (continued)**

Ramus carpeus volaris  
 Ramus volaris superficialis  
 Ramus carpens dorsalis  
*Aa. metacarpeae dorsales*  
*A. volaris indicis radialis*  
 Arcus volaris profundus  
*Aa. metacarpeae volares*  
*A. interossea volaris*  
*A. interossea dorsalis*  
 Ramus carpeus volaris  
 Ramus carpeus dorsalis  
 Ramus volaris profundus  
 Arcus volaris superficialis  
*Aa. digitales volares communes*  
*Aa. digitales volares propriae*  
*A. coeliaca*  
   *A. gastrica sinistra*  
   *A. gastrica dextra*  
   *A. lienalis*  
   *Aa. gastricae breves*  
*Aa. intestinales*  
*A. suprarenalis media*  
*A. spermaticae internae*  
*A. hypogastrica*  
*A. pudenda interna*  
   *A. perinei*  
   *Aa. scrotales posteriores*  
   *A. profunda penis*  
*A. glutaea inferior*  
*A. glutaea superior*  
*A. epigastrica inferior*  
   *A. spermatica externa*  
 Canalis femoralis  
 Annulus femoralis  
 Septum femorale [Cloqueti]  
 Trigonum femorale [fossa Scarpae major]  
 Canalis adductorius [Hunteri]  
*A. pudenda externa superficialis*  
*A. pudenda externa profunda*  
*A. profunda femoris*  
*A. circumflexa femoris lateralis*  
*A. circumflexa femoris medialis*  
*A. genu suprema*  
*Aa. surales*  
*Aa. genu superiores*  
*A. genu media*  
*Aa. genu inferiores*  
*A. malleolaris anterior medialis*  
*A. malleolaris anterior lateralis*  
*A. tarsea lateralis*  
*A. arcuata*  
*Aa. metatarsae dorsales*  
 Ramus plantaris profundus  
*A. peronaea*  
   Ramus perforans  
   Ramus calcaneus lateralis  
   *A. malleolaris posterior medialis*  
   Rami calcanei mediales  
*A. plantaris medialis*  
*A. plantaris lateralis*  
*Aa. metatarsae plantares*  
*Aa. digitales plantares*

**Venae**

*V. cordis magna*  
*V. cordis parva*  
*V. obliqua atrii sinistri* [Marshalli]  
*Lig. venae cavae sinistrae*  
*Vv. cordis minimae*  
*V. facialis anterior*  
*V. facialis posterior*  
*V. cervicalis profunda*  
  
*V. cerebri media*  
*Vv. cerebri internae*  
*V. cerebri magna* [Galenii]  
*V. terminalis*  
 Sinus sagittalis superior

**Arteries (continued)**

Anterior radial carpal artery  
 Superficialis volae artery  
 Posterior radial carpal artery  
 Dorsal interosseous arteries  
 Radialis indicis artery  
 Deep palmar arch  
 Palmar interosseous arteries  
 Anterior interosseous artery  
 Posterior interosseous artery  
 Anterior ulnar carpal artery  
 Posterior ulnar carpal artery  
 Profunda branch  
 Superficial palmar arch  
 Palmar digital arteries  
 Collateral digital arteries  
 Coeliac axis  
   Gastric or coronary artery  
   Pyloric artery  
   Splenic artery  
   Vasa brevia  
 Vasa intestini tenuis  
 Middle capsular artery  
 Spermatic arteries  
 Internal iliac artery  
 Internal pudic artery  
   Superficial perineal artery  
   Superficial perineal arteries  
   Artery to corpus cavernosum  
 Sciatic artery  
 Gluteal artery  
 Deep epigastric artery  
   Cremasteric artery  
 Crural canal  
 Crural ring  
 Septum crurale  
 Scarpa's triangle

Hunter's canal  
 Superficial external pudic artery  
  
 Deep external pudic artery  
 Deep femoral artery  
 External circumflex artery  
 Internal circumflex artery  
 Anastomotica magna artery  
 Inferior muscular arteries  
 Superior articular arteries  
 Azygos articular artery  
 Inferior articular arteries  
 Internal malleolar artery  
 External malleolar artery  
 Tarsal artery  
 Metatarsal artery  
 Dorsal interosseous arteries  
 Communicating artery  
 Peroneal artery  
   Anterior peroneal artery  
   External calcaneal  
   Internal malleolar artery  
   Internal calcaneal  
 Internal plantar artery  
 External plantar artery  
 Digital branches  
 Collateral digital branches

**Veins**

Left coronary vein  
 Right coronary vein  
 Oblique vein of Marshall  
  
 Vestigial fold of Marshall  
 Veins of Thebesius  
 Facial vein  
 Temporomaxillary vein  
 Posterior vertebral or posterior deep cervical vein  
 Superficial Sylvian vein  
 Veins of Galen  
 Great vein of Galen  
 Vein of corpus striatum  
 Superior longitudinal sinus



## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

**Veins (continued)**

Inferior sagittal sinus  
Transverse sinus  
Confluence of the sinuses  
Basilar plexus  
Innominate veins  
Highest intercostal vein  
Azygos vein  
Hemiazygos vein  
Accessory hemiazygos vein  
External vertebral venous plexus  
  
Internal vertebral venous plexus  
Great saphenous vein  
Small saphenous vein  
Inferior epigastric vein  
Hypogastric vein  
Superior gluteal veins  
Inferior gluteal veins  
Pudendal plexus  
Lienal vein  
Coronary vein

**Lymphatic vessels**

Cisterna chyli  
Posterior auricular glands  
  
Anterior auricular glands  
  
Deep facial glands  
  
Hypogastric glands  
Inferior gastric glands  
  
Pancreaticolienal glands  
  
Sternal glands

**Venae (continued)**

Sinus sagittalis inferior  
Sinus transversus  
Confluens sinuum  
Plexus basilaris  
Vv. anonymae  
V. intercostalis suprema  
V. azygos  
V. hemiazygos  
V. hemiazygos accessoria  
Plexus venosi vertebralis  
  externi  
Plexus venosi vertebralis interni  
V. saphena magna  
V. saphena parva  
V. epigastrica inferior  
V. hypogastrica  
Vv. glutaee superiores  
Vv. glutaee inferiores  
Plexus pudendalis  
V. lienalis  
V. coronaria ventriculi

**Vasa lymphatici**

Cisterna chyli  
Lymphoglandulae auriculares  
  posteriores  
Lymphoglandulae auriculares  
  anteriores  
Lymphoglandulae faciales profunda  
Lymphoglandulae hypogastricae  
Lymphoglandulae gastricae  
  inferiores  
Lymphoglandulae pancreaticolienales  
Lymphoglandulae sternales

**Veins (continued)**

Inferior longitudinal sinus  
Lateral sinus  
Torcular Herophili  
Transverse or basilar sinus  
Brachiocephalic veins  
Superior intercostal vein  
Vena azygos major  
Vena azygos minor inferior  
Vena azygos minor superior  
Extraspinal veins  
  
Intraspinal veins  
Internal or long saphenous vein  
External or short saphenous vein  
Deep epigastric vein  
Internal iliac vein  
Gluteal veins  
Sciatic veins  
Vesicoprostatic plexus  
Splenic vein  
Gastric vein

**Lymphatic vessels**

Receptaculum chyli  
Mastoid glands  
  
Superficial parotid or preauricular glands  
Internal maxillary glands  
  
Internal iliac glands  
Right gastroepiploic gland  
  
Splenic glands  
  
Internal mammary glands

## NEUROLOGY.

**Medulla spinalis**

Funiculi of medulla spinalis  
Columns of gray substance  
Anterior column  
Lateral column  
Posterior column  
Dorsal nucleus  
  
Anterior cerebrospinal fasciculus  
Anterior proper fasciculus  
  
Lateral cerebrospinal fasciculus  
Cerebellospinal fasciculus  
Superficial antero-lateral fasciculus  
Lateral proper fasciculus  
  
Fasciculus gracilis  
Fasciculus cuneatus

**Rhombencephalon**

Medulla oblongata  
Anterior median fissure  
Posterior median fissure  
Olive  
Tubercle of Rolando  
Spinal tract of trigeminal nerve  
Lemniscus  
Decussation of lemniscus  
Cerebellospinal fasciculus  
Medial longitudinal fasciculus  
  
Horizontal sulcus [of cerebellum]  
Quadrangular lobule  
Folium vermis

**Medulla spinalis**

Funiculi medullae spinalis  
Columnae griseae  
Columna anterior  
Columna lateralis  
Columna posterior  
Nucleus dorsalis [Stillings, Clarkii]  
Fasciculus cerebrospinalis anterior  
Fasciculus anterior proprius [Flechsigi]  
Fasciculus cerebrospinalis lateralis  
Fasciculus cerebellospinalis  
Fasciculus anterolateralis superficialis [Gowersi]  
Fasciculus lateralis proprius [Flechsigi]  
Fasciculus gracilis [Golli]  
Fasciculus cuneatus [Burdachi]

**Rhombencephalon**

Medulla oblongata  
Fissura mediana anterior  
Fissura mediana posterior  
Olive  
Tuber cinereum  
Tractus spinalis n. trigemini  
Lemniscus  
Decussatio lemniscorum  
Fasciculus cerebellospinalis  
Fasciculus longitudinalis medialis  
Sulcus horizontalis [cerebelli]  
  
Lobulus quadrangularis  
Folium vermis

**Spinal cord**

Columns of spinal cord  
Horns of gray matter  
Anterior cornu  
Lateral cornu  
Posterior cornu  
Clarke's column

Direct pyramidal tract  
Anterior basis bundle

Crossed pyramidal tract  
Direct cerebellar tract  
Gowers' tract.

Lateral basis bundle

Column of Goll  
Column of Burdach

**Hind-brain**

Spinal bulb  
Ventral or ventromedian fissure  
Dorsal or dorsomedian fissure  
Olivary body  
Tubercle of Rolando  
Spinal root of fifth cranial nerve  
Fillet  
Sensory decussation  
Direct cerebellar tract  
Posterior longitudinal bundle  
  
Great horizontal fissure  
  
Ant. and post. crescentic lobes  
Folium cacuminis; cacuminal lobe

## TERMINOLOGY ADOPTED IN TEXT

**Rhombencephalon** (*continued*)

Superior semilunar lobule  
Nodule  
Uvula  
Tonsillæ  
Tuber vermis  
Inferior semilunar lobule

Brachia conjunctiva  
Brachia pontis  
Restiform bodies  
Anterior medullary velum

Posterior medullary velum  
Tænia of fourth ventricle  
Rhomboid fossa  
Medial eminence  
Colliculus facialis  
Area acustica  
Medullary striæ  
Ala cinerea

**Mesencephalon**

Cerebral peduncle  
Base of peduncle  
Substantia nigra  
Inferior colliculus  
Superior colliculus  
Cerebral aqueduct

**Prosencephalon**

Thalami  
Intermediate mass  
Medial geniculate body

Lateral geniculate body

Pineal body  
Corpus subthalamicum  
Corpora mamillaria  
Hypophysis  
Optic chiasma

*Cerebral hemisphere*

Longitudinal fissure  
Lateral cerebral fissure  
Central sulcus  
Cingulate sulcus  
Anterior central gyrus

Superior frontal gyrus  
Middle frontal gyrus  
Inferior frontal gyrus  
Intraparietal sulcus  
Posterior central gyrus

Inferior parietal lobule  
Fusiform gyrus  
Transverse temporal gyri  
Insula  
Cingulate gyrus  
Callosal sulcus  
Hippocampal fissure  
Subcallosal gyrus  
Supracallosal gyrus  
Fascia dentata hippocampi  
Body of corpus callosum  
Calcar avis  
Anterior cornu of lateral ventricle  
Posterior cornu of lateral ventricle  
Inferior cornu of lateral ventricle  
Hippocampus  
Caudate nucleus  
Lentiform nucleus  
Frontal part of internal capsule  
Occipital part of internal capsule  
Stria terminalis

## BASLE TERMINOLOGY

**Rhombencephalon** (*continued*)

Lobulus semilunaris superior  
Nodulus vermis  
Uvula vermis  
Tonsilla cerebelli  
Tuber vermis  
Lobulus semilunaris inferior

Brachia conjunctiva [cerebelli]  
Brachia pontis  
Corpus restiformes  
Velum medullare anterius

Velum medullare posterius  
Tænia ventriculi quarti  
Fossa rhomboidea  
Eminentia medialis  
Colliculus facialis  
Area acustica  
Striæ medullares  
Ala cinerea

**Mesencephalon**

Pedunculus cerebri  
Basis pedunculi  
Substantia nigra  
Colliculus inferior  
Colliculus superior  
Aquaeductus cerebri

**Prosencephalon**

Thalami  
Massa intermedia  
Corpus geniculatum mediale

Corpus geniculatum laterale

Corpus pineale  
Corpus subthalamicum  
Corpora mamillaria  
Hypophysis  
Chiasma opticum

*Hemisphaerium*

Fissura cerebri longitudinalis  
Fissura cerebri lateralis [Sylvii]  
Sulcus centralis [Rolandi]  
Sulcus cinguli  
Gyrus centralis anterior

Gyrus frontalis superior  
Gyrus frontalis medius  
Gyrus frontalis inferior  
Sulcus interparietalis  
Gyrus centralis posterior

Lobulus parietalis inferior  
Gyrus fusiformis  
Gyri temporales transversi  
Insula  
Gyrus cinguli  
Sulcus corporis callosi  
Fissura hippocampi  
Gyrus subcallosus  
Indusium griseum  
Fascia dentata hippocampi  
Truncus corporis callosi  
Calcar avis  
Cornu anterius

Cornu posterius

Cornu inferius

Hippocampus  
Nucleus caudatus  
Nucleus lentiformis  
Pars frontalis capsulae internae  
Pars occipitalis capsulae internae  
Stria terminalis

## OLD TERMINOLOGY

**Hind-brain** (*continued*)

Postero-superior lobule  
Nodular lobe  
Uvular lobe  
Amygdaline nucleus  
Tuber valvulae  
Slender and postero-inferior lobules  
Superior cerebellar peduncles  
Middle cerebellar peduncles  
Inferior cerebellar peduncles  
Valve of Vieussens; superior medullary velum  
Inferior medullary velum  
Ligula  
Floor of fourth ventricle  
Fasciculus teres  
Eminentia teres  
Trigonum acusticum  
Striæ acusticae  
Trigonum vagi

**Mid-brain**

Crus cerebri  
Crusta or pes  
Intercalatum  
Inferior quadrigeminal body  
Superior quadrigeminal body  
Aquaduct of Sylvius

**Fore-brain**

Optic thalamus  
Middle commissure  
Internal geniculate body; post-geniculatum  
External geniculate body; pre-geniculatum  
Epiphysis  
Nucleus of Luys  
Corpus albicans  
Pituitary body  
Optic commissure

*Cerebral hemisphere*

Great longitudinal fissure  
Fissure of Sylvius  
Fissure of Rolando  
Callosomarginal fissure  
Ascending frontal convolution; precentral gyre  
Suprafrontal gyre  
Medifrontal gyre  
Subfrontal gyre  
Intraparietal fissure  
Ascending parietal convolution; postcentral gyre  
Subparietal district or lobule  
Occipitotemporal convolution  
Gyri of Heschl  
Island of Reil  
Callosal convolution  
Callosal sulcus  
Dentate fissure  
Peduncle of corpus callosum  
Gyrus epicallous  
Gyrus dentatus  
Body of corpus callosum  
Hippocampus minor  
Anterior horn; precornu

Postcornu

Descending horn; medicornu

Hippocampus major  
Caudatum  
Lenticular nucleus  
Anterior limb of internal capsule  
Posterior limb of internal capsule  
Taenia semicircularis

## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

**Prosencephalon (continued)***Cerebral hemisphere*

Optic radiation  
Column of fornix  
Thalamomammillary fasciculus  
Crura of fornix  
Septum pellucidum  
Cavity of septum pellucidum  
Tela chorioidea of third ventricle  
Tela chorioidea of fourth ventricle  
Choroid plexus of lateral ventricle

**Meninges**

Cerebral dura mater  
Spinal dura mater  
Subarachnoid cavity  
Cisterna cerebellomedullaris  
Cisterna interpeduncularis  
Arachnoid granulations  
Cerebral pia mater  
Spinal pia mater

**Cerebral nerves**

Olfactory nerves  
Optic nerve  
Oculomotor nerve  
Trochlear nerve  
Trigeminal nerve  
Semilunar ganglion  
Nasociliary nerve  
Ciliary ganglion  
  
Maxillary nerve  
Middle meningeal nerve  
Zygomatic nerve  
Zygomaticotemporal branch  
  
Zygomaticofacial branch  
Posterior superior alveolar branches  
Middle superior alveolar branch  
Anterior superior alveolar branch  
Inferior palpebral branches  
Superior labial branches  
Sphenopalatine ganglion  
Greater superficial petrosal nerve  
Deep petrosal nerve  
Nerve of pterygoid canal  
Orbital branches  
Palatine nerves  
Mandibular nerve  
Nervus spinosus  
Buccinator nerve  
Inferior alveolar nerve  
Abducent nerve  
Facial nerve  
Sensory part of facial nerve  
Genicular ganglion  
Nerve to Stapedius  
Zygomatic branches  
Buccal branches  
Acoustic nerve  
Vestibular root  
Cochlear root  
Glossopharyngeal nerve  
Superior ganglion  
Petrous ganglion  
Tympanic nerve  
Vagus nerve

Jugular ganglion  
Ganglion nodosum

Meningeal branch  
Auricular branch

**Prosencephalon (continued)***Hemisphaerium*

Radiatio occipitothalamica  
Columna fornicis  
Fasciculus thalamomammillaris  
Crus fornicis  
Septum pellucidum  
Cavum septi pellucidi  
Tela chorioidea ventriculi tertii  
Tela chorioidea ventriculi quarti  
Plexus chorioideus ventriculus lateralis

**Meninges**

Dura mater encephali  
Dura mater spinalis  
Cavum subarachnoideale  
Cisterna cerebellomedullaris  
Cisterna interpeduncularis  
Granulationes arachnoidales  
Pia mater encephali  
Pia mater spinalis

**Nervi cerebrales**

Nn. olfactorii  
N. opticus  
N. oculomotorius  
N. trochlearis  
N. trigeminus  
Ganglion semilunare [Gasserii]  
N. nasociliaris  
Ganglion ciliare  
  
N. maxillaris  
N. meningeus medius  
N. zygomaticus  
Ramus zygomaticotemporalis  
  
Ramus zygomaticofacialis  
Rami alveolares superiores posteriores  
Ramus alveolaris superior medius  
Ramus alveolaris superior anteriores  
Rami palpebrales inferiores  
Rami labiales superiores  
Ganglion sphenopalatinum  
N. petrosus superficialis major  
  
N. petrosus profundus  
N. canalis pterygoidei [Vidui]  
Rami orbitales  
Nn. palatini  
N. mandibularis  
N. spinosus  
N. buccinatorius  
N. alveolaris inferior  
N. abducens  
N. facialis  
N. intermedius  
Ganglion geniculi  
N. stapedius  
Rami zygomatici  
Rami buccales  
N. acusticus  
Radix vestibularis  
Radix cochlearis  
N. glossopharyngeus  
Ganglion superius  
Ganglion petrosum  
N. tympanicus  
N. vagus

Ganglion jugulare  
Ganglion nodosum

Ramus meningeus  
Ramus auricularis

**Fore-brain (continued)***Cerebral hemisphere*

Optic radiation  
Anterior pillar of fornix  
Bundle of Vicq d'Asyr  
Posterior pillar of fornix  
Septum lucidum  
Pseudocole; fifth ventricle  
Velum interpositum

Tela chorioidea inferior

Paraplexus

**Meninges**

Dura of brain  
Spinal dura  
Subarachnoid space  
Cisterna magna  
Cisterna basalis  
Pachionian bodies  
Pia of brain  
Pia of cord

**Cranial nerves**

First nerve  
Second nerve  
Third nerve  
Fourth nerve  
Fifth nerve  
Gasserian ganglion  
Nasal nerve  
Ophthalmic or lenticular ganglion  
Superior maxillary nerve  
Meningeal or dural branch  
Temporomalar nerve  
Temporal branch; orbital nerve  
Malar branch  
Posterior superior dental branches  
Middle superior dental branch  
  
Anterior superior dental branch  
Palpebral branches  
Labial branches  
Ganglion of Meckel  
Large superficial petrosal nerve  
Large deep petrosal nerve  
Vidian nerve  
Ascending branches  
Descending branches  
Inferior maxillary nerve  
Recurrent or meningeal branch  
Long buccal nerve  
Inferior dental nerve

**Sixth nerve****Seventh nerve**

Pars intermedia of Wrisberg  
Geniculate ganglion  
Tympanic branch  
Malar branches  
Infraorbital branches

**Eighth nerve; auditory nerve**

Vestibular nerve  
Cochlear nerve

**Ninth nerve**

Jugular ganglion  
Inferior ganglion  
Nerve of Jacobson

**Tenth nerve; pneumogastric nerve**

Ganglion of root  
Ganglion of trunk; inferior ganglion  
Dural branch  
Nerve of Arnold

TERMINOLOGY ADOPTED IN TEXT	BASIS TERMINOLOGY	OLD TERMINOLOGY
<b>Cerebral nerves (continued)</b>	<b>Nervi cerebrales (continued)</b>	<b>Cranial nerves (continued)</b>
Vagus nerve	N. vagus	Tenth nerve; pneumogastric nerve
Recurrent nerve	N. recurrens	Inferior or recurrent laryngeal nerve
Superior cardiac branches	Rami cardiaci superiores	Cervical cardiac branches
Inferior cardiac branches	Rami cardiaci inferiores	Thoracic cardiac branches
Anterior bronchial branches	Rami bronchiales anteriores	Anterior or ventral pulmonary branches
Posterior bronchial branches	Rami bronchiales posteriores	Posterior or dorsal pulmonary branches
Oesophageal plexus	{ Plexus oesophageus anterior } { Plexus oesophageus posterior }	Plexus gulæ
Accessory nerve	N. accessorius	Eleventh nerve; spinal accessory nerve
Cerebral part	Ramus internus	Accessory portion
Spinal part	Ramus externus	Spinal portion
Hypoglossal nerve	N. hypoglossi	Twelfth nerve
<b>Spinal nerves</b>	<b>Nervi spinales</b>	<b>Spinal nerves</b>
Posterior divisions	Rami posteriores	Posterior divisions
Medial branch	Ramus medialis	Internal branch
Lateral branch	Ramus lateralis	External branch
Greater occipital nerve	N. occipitalis major	Great occipital nerve
Anterior divisions	Rami anteriores	Anterior divisions
Smaller occipital nerve	N. occipitalis minor	Small occipital nerve
Anterior branch	Ramus anterior	Facial branch
Posterior branch	Ramus posterior	Mastoid branch
Cutaneous cervical nerve	N. cutaneus colli	Superficial or transverse cervical nerve
Supraclavicular nerves	Nn. supraclaviculares	Descending branches
Anterior supraclavicular nerves	Nn. supraclaviculares anteriores	Suprasternal nerves
Middle supraclavicular nerves	Nn. supraclaviculares medii	Supraclavicular nerves
Posterior supraclavicular nerves	Nn. supraclaviculares posteriores	Supra-acromial nerves
Brachial plexus	Plexus brachialis	Brachial plexus
Lateral cord	Fasciculus lateralis	Outer cord
Medial cord	Fasciculus medialis	Inner cord
Posterior cord	Fasciculus posterior	Posterior cord
Dorsal scapular nerve	N. dorsalis scapulae	Nerve to Rhomboidei; posterior scapular nerve
Long thoracic nerve	N. thoracalis longus	External respiratory nerve of Bell
Lateral and medial anterior thoracic nerves	Nn. thoracales anteriores	Internal and external anterior thoracic nerves
Thoracodorsal nerve	N. thoracodorsalis	Long subscapular nerve
Axillary nerve	N. axillaris	Circumflex nerve
Lateral brachial cutaneous nerve	N. cutaneus brachii lateralis	Cutaneous branch of circumflex nerve
Lateral antibrachial cutaneous nerve	N. cutaneus antibrachii lateralis	Cutaneous branch of musculocutaneous nerve
Volar branch	Ramus volaris	Anterior branch
Dorsal branch	Ramus dorsalis	Posterior branch
Medial antibrachial cutaneous nerve	N. cutaneus antibrachii medialis	Internal cutaneous nerve
Volar branch	Ramus volaris	Anterior branch
Ulnar branch	Ramus ulnaris	Posterior branch
Medial brachial cutaneous nerve	N. cutaneus brachii medialis	Lesser internal cutaneous nerve
Volar interosseous nerve	N. interosseus volaris	Anterior interosseous nerve
Proper volar digital nerves	Nn. digitales volares proprii	Collateral branches of digital nerves
Radial nerve	N. radialis	Musculospiral nerve
Posterior brachial cutaneous nerve	N. cutaneus brachii posterior	Internal cutaneous branch of musculospiral nerve
Dorsal antibrachial cutaneous nerve	N. cutaneus antibrachii dorsalis	External cutaneous branches of musculospiral nerve
Superficial branch of radial nerve	Ramus superficialis	Radial nerve
Deep branch of radial nerve	Ramus profundus	Posterior interosseous nerve
Dorsal interosseous nerve	N. interosseus dorsalis	Lumbosacral cord
Lumbosacral trunk	Truncus lumbosacralis	Iliohypogastric nerve
Iliohypogastric nerve	N. iliohypogastricus	Iliac branch
Lateral cutaneous branch	Ramus cutaneus lateralis	Hypogastric branch
Anterior cutaneous branch	Ramus cutaneus anterior	Genitocrural nerve
Genitofemoral nerve	N. genitofemoralis	Genital branch
External spermatic nerve	N. spermaticus externus	Femoral or crural branch
Lumboinguinal nerve	N. lumboinguinalis	External cutaneous nerve
Lateral femoral cutaneous nerve	N. cutaneus femoralis lateralis	Anterior crural nerve
Femoral nerve	N. femoralis	Middle cutaneous nerve
Intermediate cutaneous nerve	Ramus cutaneus anterior	Long or internal saphenous nerve
Saphenous nerve	N. saphenus	Patellar branch
Infrapatellar branch	Ramus infrapatellaris	

TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Spinal nerves</b> ( <i>continued</i> )	<b>Nervi spinales</b> ( <i>continued</i> )	<b>Spinal nerves</b> ( <i>continued</i> )
Posterior femoral cutaneous nerve	N. cutaneus femoralis posterior	Small sciatic nerve
Sciatic nerve	N. ischiadicus	Great sciatic nerve
Tibial nerve	N. tibialis	Internal popliteal nerve
Medial sural cutaneous nerve	N. cutaneus surae medialis	Nervus communicans tibialis
Sural nerve	N. suralis	Short saphenous nerve
Medial plantar nerve	N. plantaris medialis	Internal plantar nerve
Lateral plantar nerve	N. plantaris lateralis	External plantar nerve
Common peroneal nerve	N. peronaeus communis	External popliteal nerve
Lateral sural cutaneous nerve	N. cutaneus surae lateralis	Lateral cutaneous branch
Peroneal anastomotic branch	Ramus anastomoticus peronaeus	Nervus communicans fibularis
Deep peroneal nerve	N. peronaeus profundus	Anterior tibial nerve
Superficial peroneal nerve	N. peronaeus superficialis	Musculocutaneous nerve
Medial dorsal cutaneous nerve	N. cutaneus dorsalis medialis	Internal dorsal cutaneous branch
Intermediate dorsal cutaneous nerve	N. cutaneus dorsalis intermedius	External dorsal cutaneous branch
Pudendal nerve	N. pudendus	Internal pudic nerve
Posterior scrotal nerves	Nn. scrotales posteriores	Superficial peroneal nerves
<b>Sympathetic system</b>	<b>Systema nervorum sympathicum</b>	<b>Sympathetic system</b>
Sympathetic trunks	Truncus sympathicus	Gangliated cord
Internal carotid plexus	Plexus caroticus internus	Carotid plexus
Ansa subclavia [Vieussenii]	Ansa subclavia [Vieussenii]	Ansa Vieussenii
Middle cardiac nerve	N. cardiacus medius	Great cardiac nerve
Greater splanchnic nerve	N. splanchnicus major	Great splanchnic nerve
Lowest splanchnic nerve	N. splanchnicus imus	Least splanchnic nerve
Cardiac plexus	Plexus cardiacus	Superficial and deep cardiac plexuses
Posterior coronary plexus	Plexus coronarius posterior	Left coronary plexus
Anterior coronary plexus	Plexus coronarius anterior	Right coronary plexus
Coeliac plexus	Plexus coeliacus	Solar plexus
Coeliac ganglia	Ganglia coeliaca	Semilunar ganglia
Superior gastric plexus	Plexus gastricus superior	Gastric or coronary plexus
Abdominal aortic plexus	Plexus aorticus abdominis	Aortic plexus
Lesser cavernous nerves	Nn. cavernosi penis minores	Small cavernous nerves
Greater cavernous nerve	N. cavernosus penis major	Large cavernous plexus

## PERIPHERAL ORGANS OF THE SPECIAL SENSES.

<b>Organ of Taste</b>	<b>Organon gustus</b>	<b>Organs of taste</b>
Gustatory calyculi	Calyculi gustatorii	Taste-buds
<b>Organ of smell</b>	<b>Organon olfactus</b>	<b>The nose</b>
External nose	Nasus externus	Outer nose
Lateral cartilage	Cartilago nasi lateralis	Upper lateral cartilage
Greater alar cartilage	Cartilago alaris major	Lower lateral cartilage
Lesser alar cartilages	Cartilagine alares minores	Sesamoid cartilages
Nasal cavity	Cavum nasi	Nasal fossa
Choanae	Choanae	Posterior nares
Accessory sinuses of nose	Sinus paranasales	Accessory sinuses of nose
Maxillary sinus	Sinus maxillaris	Antrum of Highmore
<b>Organ of sight</b>	<b>Organon visus</b>	<b>The eye</b>
Bulb of eye	Bulbus oculi	Eyeball
Sinus venosus sclerae	Sinus venosus sclerae	Canal of Schlemm
Corneal epithelium	Epithelium corneae	Anterior layer
Anterior elastic lamina	Lamina elastica anterior	Anterior limiting layer; Bowman's membrane
Posterior elastic lamina	Lamina elastica posterior	Membrane of Descemet; membrane of Demours
Spaces of the angle of the iris	Spatia anguli iridis	Spaces of Fontana
Endothelium of the anterior chamber	Endothelium camerae anterioris	Posterior layer; corneal endothelium
Zonula ciliaris	Zonula ciliaris [Zinni]	Zonule of Zinn
Spatia zonularis	Spatia zonularis	Canal of Petit
Rectus medialis	M. rectus medialis	Rectus internus
Rectus lateralis	M. rectus lateralis	Rectus externus
Ligament or tendon of Zinn	Annulus tendineus communis [Zinni]	Ligament or tendon of Zinn
Fascia bulbi	Fascia bulbi [Tenonij]	Capsule of Ténon
Lateral palpebral commissure	Commissura palpebrarum lateralis	External canthus
Medial palpebral commissure	Commissura palpebrarum medialis	Internal canthus



TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Organ of sight</b> ( <i>continued</i> )	<b>Organon visus</b> ( <i>continued</i> )	<b>The eye</b> ( <i>continued</i> )
Superior tarsus	Tarsus superior	Superior tarsal plate
Inferior tarsus	Tarsus inferior	Inferior tarsal plate
Orbital septum	Septum orbitale	Palpebral ligaments
Medial palpebral ligament	Lig. palpebrale mediale	Internal tarsal ligament
Lateral palpebral raphe	Raphe palpebralis lateralis	External tarsal ligament
Tarsal glands	Glandulae tarsales [Meibomi]	Meibomian glands
Lacrimal ducts	Ductus lacrimales	Lacrimal canals
Nasolacrimal duct	Ductus nasolacrimalis	Nasal duct
<b>Organ of hearing</b>	<b>Organon auditus</b>	<b>The ear</b>
Auricula	Auricula	Pinna
Fossa triangularis	Fossa triangularis	Fossa of antihelix
Scapha	Scapha	Fossa of helix
Auricularis anterior	M. auricularis anterior	Attrahens aurem
Auricularis superior	M. auricularis superior	Attollens aurem
Auricularis posterior	M. auricularis posterior	Retrahens aurem
External acoustic meatus	Meatus acusticus externus	External auditory meatus
Tegmental wall	Paries tegmentalis	Roof of tympanic cavity
Jugular wall	Paries jugularis	Floor of tympanic cavity
Membranous wall	Paries membranacea	Outer wall
Petrotympenic fissure	Fissura petrotympanicus	Glaserian fissure
Labyrinthic wall	Paries labyrinthica	Inner wall
Fenestra vestibuli	Fenestra vestibuli	Fenestra ovalis
Fenestra cochleae	Fenestra cochleae	Fenestra rotunda
Prominence of facial canal	Prominentia canalis facialis	Prominence of aqueduct of Fallopius
Mastoid wall	Paries mastoidea	Posterior wall
Tympanic antrum	Antrum tympanicum	Mastoid antrum
Pyramidal eminence	Eminentia pyramidalis	Pyramid
Carotid wall	Paries carotica	Anterior wall
Auditory tube	Tuba auditiva	Eustachian tube
Anterior process [of malleus]	Processus anterior [Folii]	Processus gracilis
Lateral process [of malleus]	Processus lateralis	Processus brevis
Short crus [of incus]	Crus breve	Short process
Long crus [of incus]	Crus longum	Long process
Lenticular process [of incus]	Processus lenticularis	Os orbiculare
Recessus sphaericus	Recessus sphaericus	Recessus hemisphericus
Recessus ellipticus	Recessus ellipticus	Recessus hemiellipticus
Lateral semicircular canal	Canalis semicircularis lateralis	External semicircular canal
Ductus reuniens	Ductus reuniens	Canalis reuniens
Semicircular ducts	Ductus semicirculares	Membranous semicircular canals
Ductus cochlearis	Ductus cochlearis	Membranous cochlea or scala media
Vestibular membrane	Membrana vestibularis [Reissneri]	Reissner's membrane
Spiral organ of Corti	Organon spirale [Cortii]	Organ of Corti
Vestibular ganglion	Ganglion vestibulare	Ganglion of Scarpa
Spiral ganglion of cochlea	Ganglion spirale cochleae	Ganglion of Corti
<b>Common integument</b>	<b>Integumentum commune</b>	<b>Skin</b>

## SPLANCHNOLOGY.

<b>Respiratory apparatus</b>	<b>Apparatus respiratorius</b>	<b>Respiratory system</b>
Laryngeal prominence	Prominentia laryngea	Pomum Adami
Corniculate cartilages	Cartilagine corniculatae [Santorini]	Cartilages of Santorini
Cuneiform cartilages	Cartilagine cuneiformes	Cartilages of Wrisberg
Tubercle of epiglottis	Tuberculum epiglotticum	Cushion of epiglottis
Hyothyroid membrane	Membrana hyothyroidea	Thyrohyoid membrane
Lateral hyothyroid ligament	Lig. hyothyroideum laterale	Lateral thyrohyoid ligament
Conus elasticus	Conus elasticus	Cricothyroid membrane
Middle cricothyroid ligament	Lig. cricothyroideum medium	Central part of cricothyroid membrane
Ventricular folds	Plicae ventriculares	Superior or false vocal cords
Ventricular ligament	Lig. ventriculare	Superior thyroarytenoid ligament
Vocal folds	Plicae vocales	Inferior or true vocal cords
Vocal ligament	Lig. vocale	Inferior thyroarytenoid ligament
Ventricle of the larynx	Ventriculus laryngis [Morgagni]	Laryngeal sinus
Appendix of laryngeal ventricle	Appendix ventriculi laryngis	Laryngeal sacculae
Rima glottidis	Rima glottidis	Rima glottidis
Intermembranous part	Pars intermembranacea	Glottis vocalis
Intercartilaginous part	Pars intercartilaginea	Glottis respiratoria
Vocalis muscle	M. vocalis	Inner portion of Thyroarytenoid

## TERMINOLOGY ADOPTED IN TEXT

## BASLE TERMINOLOGY

## OLD TERMINOLOGY

**Respiratory apparatus** (*continued*)

Cricothyreoideus  
Cricoarytenoideus posterior  
Cricoarytenoideus lateralis  
Thyreothyreoideus  
Cupula pleurae  
Pulmonary ligament  
Costal surface  
Mediastinal surface

**Apparatus respiratorius** (*continued*)

M. cricothyreoideus  
M. cricoarytenoideus posterior  
M. cricoarytenoideus lateralis  
M. thyreoarytaenoideus  
Cupula pleurae  
Lig. pulmonale  
Facies costalis  
Facies mediastinalis

**Respiratory system** (*continued*)

Cricothyroid  
Posterior cricoarytenoid  
Lateral cricoarytenoid  
Thyroarytenoid  
Cervical pleura  
Ligamentum latum pulmonis  
External or thoracic surface  
Inner surface

**Digestive apparatus**

Mouth  
Glossopalatine arch  
Pharyngopalatine arch  
Levator veli palatini  
Tensor veli palatini  
Musculus uvulae  
Glossopalatinus  
Pharyngopalatinus  
Incisor teeth  
Premolar teeth  
Dens serotinus  
Deciduous teeth  
Dentin  
Crusta petrosa  
Root of tongue  
Papillae vallatae  
Apex of tongue  
Inferior surface of tongue  
Genioglossus  
Longitudinalis linguae superior  
Longitudinalis linguae inferior  
Transversus linguae  
Verticalis linguae  
Anterior lingual gland

Accessory parotid gland  
Parotid duct  
Submaxillary duct  
Smaller sublingual duct  
Larger sublingual ducts  
Nasal part of pharynx  
Pharyngeal recess

Palatine tonsil  
Pterygomandibular raphé  
Constrictor pharyngis inferior

Constrictor pharyngis medius

Constrictor pharyngis superior

**Peritoneum**

Omental bursa  
Rectouterine excavation

Epiploic foramen  
Lesser omentum

Greater omentum

Vesicouterine excavation  
Gastrolial ligament  
Phrenicocolial ligament  
Phrenicocolic ligament  
Mesenteriole of vermiform process

**Digestive tube**

Stomach  
Circular folds

Intestinal glands

Duodenal glands

Solitary lymphatic nodules  
Aggregated lymphatic nodules

Vermiform process

**Apparatus digestorius**

Cavum oris  
Arcus glossopalatinus  
Arcus pharyngopalatinus  
M. levator veli palatini  
M. tensor veli palatini  
M. uvulae  
M. glossopalatinus  
M. pharyngopalatinus  
Dentes incisivi  
Dentes praemolares  
Dens serotinus  
Dentes decidui  
Substantia eburnea  
Substantia ossea  
Radix linguae  
Papillae vallatae  
Apex linguae  
Facies inferior linguae  
M. genioglossus  
M. longitudinalis linguae superior  
M. longitudinalis linguae inferior  
M. transversus linguae  
M. verticalis linguae  
Gl. lingualis anterior [Blandini, Nuhn]

Glandula parotis accessoria  
Ductus parotideus [Stenonis]  
Ductus submaxillaris  
Ductus sublingualis major  
Ductus sublinguales minores  
Pars nasalis pharyngis  
Recessus pharyngeus [Rosenmueller]

Tonsilla palatina  
Raphe pterygomandibularis  
M. constrictor pharyngis inferior  
M. constrictor pharyngis medius  
M. constrictor pharyngis superior

**Peritoneum**

Bursa omentalis  
Excavatio rectouterina [cavum Douglasi]

Foramen epiploicum [Winslow]  
Omentum minus

Omentum majus

Excavatio vesicouterina  
Lig. gastrolialle  
Lig. phrenicocolialle  
Lig. phrenicocolic  
Mesenteriolium processus vermiformis

**Tubus digestorius**

Ventriculus  
Plicae circulares

Glandulae intestinales [Lieberkuhn]

Glandulae duodenales (Brunneri)

Noduli lymphatici solitarii  
Noduli lymphatici aggregati [Peyer]

Processus vermiformis

**Organs of digestion**

Oral or buccal cavity  
Anterior pillar of fauces  
Posterior pillar of fauces  
Levator palati  
Tensor palati  
Axygos uvulae  
Palatoglossus  
Palatopharyngeus  
Incisive or cutting teeth  
Biscupid teeth  
Wisdom tooth  
Temporary or milk-teeth  
Ivory of teeth  
Cement of teeth  
Base of tongue  
Circumvallate papillae  
Tip of tongue  
Under surface of tongue  
Geniohyoglossus  
Superior lingualis  
Inferior lingualis  
Transverse lingualis  
Vertical lingualis  
Gland of Nuhn

Socia parotidis  
Stensen's duct  
Wharton's duct  
Bartholin's duct  
Ducts of Rivinus  
Nasopharynx  
Fossa of Rosenmüller

Tonsil  
Pterygomandibular ligament  
Inferior constrictor

Middle constrictor

Superior constrictor

**Peritoneum**

Lesser peritoneal sac  
Pouch of Douglas

Foramen of Winslow  
Small omentum; gastrohepatic omentum

Great omentum; gastrocolic omentum

Uterovesical pouch  
Gastrosplenic omentum  
Lienorenal ligament  
Phreno- or costocolic ligament  
Mesoappendix

**Alimentary canal**

Stomach; Gaster  
Valvulae conniventes; valves of Kerkring  
Crypts of Lieberkuhn)

Brunner's glands

Solitary glands  
Peyer's patches or glands

Vermiform appendix

TERMINOLOGY ADOPTED IN TEXT	BASLE TERMINOLOGY	OLD TERMINOLOGY
<b>Digestive apparatus</b> ( <i>continued</i> )	<b>Apparatus digestorius</b> ( <i>continued</i> )	<b>Organs of digestion</b> ( <i>continued</i> )
<i>Digestive tube</i>	<i>Tubus digestorius</i>	<i>Alimentary canal</i>
Colic valve	Valvula coli	Iliocaecal valve
Right colic flexure	Flexura colica dextra	Hepatic flexure
Left colic flexure	Flexura colica sinistra	Splenic flexure
Descending colon	Colon descendens	Descending colon
Iliac colon	Colon sigmoideum	Iliac colon
Sigmoid colon	Plicae transversales recti	Pelvic colon
Transverse rectal folds	Pars analis recti	Houston's valves
Anal canal	Columnnae rectales [Morgagni]	Anal canal
Rectal columns	Hepar	Columns of Morgagni
Liver	Facies inferior	Liver
Inferior surface	Fossa sagittalis sinistra	Visceral surface
Left sagittal fossa	Porta hepatis	Longitudinal fissure
Porta hepatis	Lobus caudatus	Transverse fissure of liver
Caudate lobe	Processus caudatus	Spigelian lobe
Caudate process	Capsula fibrosa [Glissoni]	Caudate lobe
Fibrous coat	Ductus pancreaticus [Wirsungi]	Areolar coat
Pancreatic duct	Ductus pancreaticus accessorius [Santorini]	Duct of Wirsung
Accessory pancreatic duct		Duct of Santorini
<b>Urogenital apparatus</b>	<b>Apparatus urogenitalis</b>	<b>Urogenital organs</b>
Kidneys	Renes	Kidneys
Urinary bladder	Vesica urinaria	Bladder
Urethral crest	Crista urethralis	Verumontanum
Prostatic utricle	Utriculus prostaticus	Sinus pocularis
Urethral glands	Glandulae urethrales	Glands of Littre
Head of epididymis	Caput epididymis	Globulus major
Tail of epididymis	Cauda epididymis	Globus minor
Sinus of epididymis	Sinus epididymis	Digital fossa
Appendix of testis	Appendix testis [Morgagni]	Hydatid of Morgagni
Appendix of epididymis	Ductus deferens	Pedunculated hydatid
Ductus deferens	Corpus cavernosum urethrae	Vas deferens; seminal duct
Corpus cavernosum urethrae	Prostata	Corpus spongiosum
Prostate	Glandula bulbourethralis [Cow-peri]	Prostate gland
Bulbourethral gland	Epoöphoron	Cowper's gland
Epoöphoron	Folliculi oophori vesiculosi [Graaf]	Parovarium; organ of Rosenmüller
Vesicular ovarian follicles	Tuba uterina [Fallopil]	Graafian follicles
Uterine tube	Orificium internum uteri	Fallopian tube; oviduct
Internal uterine orifice	Orificium externum uteri	Internal os
External uterine orifice	Pudendum muliebre	External os
Pudendum	Mons pubis	Vulva
Mons pubis	Labia minora pudendi	Mons Veneris
Labia minora	Orificium urethrae externum	Nymphæ
External urethral orifice	Bulbus vestibuli	Urinary meatus
Bulb of the vestibule	Glandula vestibularis major [Bartholini]	Vaginal bulb
Greater vestibular gland	Mammæ	Bartholin's gland; commissura labiorum anterior
Mammæ		Mammary glands; breasts
<i>Ductless glands</i>	<i>Ductless glands</i>	<i>Ductless glands</i>
Thyroid gland	Glandula thyreoidea	Thyroid body
Thymus	Thymus	Thymus gland
Spleen	Lien	Spleen
Suprarenal glands	Glandulae suprarenalis	Adrenal capsule
Carotid skeins	Glomera carotica	Carotid body or glands
Coccygeal skein	Glomus coccygeum	Coccygeal gland or body; Luschka's gland

# INDEX.

- A**
- ABDOMEN**, 1140  
 apertures in walls of, 1147  
 boundaries of, 1147  
 fascia of, 498  
     triangular, 502  
 lymph glands of, 785  
 muscles of, 498  
     dissection of, 498, 503, 504, 505  
     regions of, 1147  
     surface anatomy of, 1301  
     markings of, 1303  
**Abdominal aorta**, 686  
     applied anatomy of, 687  
     branches of, 689, 690  
     surface markings of, 1309  
**aortic plexus**, 1004  
 muscles, 498  
     ring, deep, 508  
     external, 500  
     inguinal, 508  
     internal, 508  
     wall, lymphatic vessels of, 787  
**Abducent nerve**, 927  
     applied anatomy of, 929  
**Abductor digiti quinti muscle**  
     (foot), 588  
     (hand), 554  
     hallucis muscle, 587  
     indicus muscle, 556  
     minimi digiti muscle, 554  
     pollicis brevis muscle, 552  
     longus muscle, 545  
     muscle, 552  
**Aberrant ducts of testis**, 1236  
**Accelerator urinae muscle**, 518  
**Accessory hemiazygos vein**, 753  
     nerve, 944  
     applied anatomy of, 945  
     cerebral part of, 944  
     spinal part of, 945  
     obturator nerve, 980  
     olivary nuclei, 830  
     organs of digestive tube, 1109  
     of eye, 1034  
     pancreatic duct, 1205  
     part of parotid gland, 1133  
     processes, 205  
     pudendal artery, 704  
     sinuses of nose, 1014  
     applied anatomy of, 1015  
     spleens, 1267  
     thyroid glands, 1263  
**Acetabular fossa**, 339  
     notch, 339  
**Acetabulum**, 340  
**Achromatic spindle**, 36  
**Acoustic meatus**, external, 244,  
     283, 1046  
     development of, 141  
     internal, 241, 291  
     nerve, 934, 1046  
     applied anatomy of, 936  
     development of, 141  
     nuclei of, 836, 935  
**Acromioclavicular joint**, 411  
     applied anatomy of, 413  
     movements of, 413  
**Acromioclavicular joint**, surface  
     anatomy of, 1315, 1319  
**Acromion**, 306  
**Acromiothoracic artery**, 670  
**Adamantoblasts**, 1123  
**Adductor brevis muscle**, 568  
     canal, 713  
     hallucis muscle, 589  
     longus muscle, 567  
     magnus muscle, 568  
     obliquus hallucis muscle, 589  
     pollicis muscle, 554  
     pollicis obliquus muscle, 554  
     transversus muscle, 554  
     transversus pollicis muscle, 554  
     tubercle, 348  
**Adenoid tissue**, 45  
**Adipose capsule of kidney**, 1209  
     tissue, 42  
**Adminiculum lineae albae**, 507  
**Adrenal capsule**, 1270  
**Adrenalin**, 1272  
**Afferent nerves**, 803  
     vessels of kidney, 1214  
**After-birth**, 101  
**Agger nasi**, 260  
**Aggregated lymphatic nodules**,  
     1175  
**Agminated follicles**, 1175  
**Air cells**, ethmoidal, 253, 1014  
     mastoid, 240  
**Air sinuses of nose**, 1014  
     of skull, 196  
**Ala cinerea**, 848  
     lobuli centralis, 838  
     nasi, 1008  
     oss. illi, 333  
**Alae of ethmoid**, 252  
     of sacrum, 208  
     of vomer, 269  
**Alar cartilages of nose**, 1009  
     lamina, 119  
**Alcock, canal of**, 511  
**Alimentary canal**, 1109  
**Allantoic vessels**, 93  
**Allantois**, 93  
**Alveolar arch**, 260  
     arteries, 640, 641  
     border of mandible, 272  
     canals, 257  
     index, 296  
     nerves, 918, 923  
     point, 260, 296  
     process of maxilla, 260  
**Alveoli**, formation of, 1124  
**Alveus**, 881, 887  
**Amacrine cells of retina**, 1028  
**Amnion**, 96  
     false, 96  
**Amniotic cavity**, 96  
     ectoderm, 95  
     fold, 96  
**Amphiarthroses**, 381  
**Ampulla of ductus deferens**, 1235  
     rectal, 1183  
     of uterine tube, 1247  
     of Vater, 1200  
**Ampullæ of semicircular canals**,  
     1058  
     of tubuli lactiferi, 1259  
**Amygdala**, 883  
**Amygdaline nucleus**, 839  
**Anal canal or anal part of rectum**,  
     1184  
     development of, 172  
     lymphatic vessels of, 792  
     membrane of, 174  
     valves of, 1184  
     fascia, 511  
**Anaphase of karyokinesis**, 36  
**Anastomoses of arteries**, 619  
     around elbow-joint, 675  
     knee-joint, 721  
     crucial, 717  
**Anastomotic branch of inferior  
 gluteal artery**, 706  
**Anastomotica magna of brachial  
 artery**, 675  
     of femoral artery, 718  
**Anatomical neck of humerus**, 309  
**Anconæus muscle**, 544  
**Angiology**, 595  
**Angle of Louis**, 218 *note*  
     iridial or filtration, 1019  
     of mandible, 273  
     of pubis, 338  
     of rib, 222  
     sacrovertebral, 206  
     of sternum, 218  
     subscapular, 305  
**Angular artery**, 635  
     gyrus, 871  
     movement, 383  
     vein, 733  
**Angulus Ludovici**, 218  
**Animal cell**, 33  
**Ankle bone**, 366  
**Ankle-joint**, 449  
     applied anatomy of, 452  
     movements of, 451  
     relations of tendons and vessels  
     to, 451  
     surface anatomy of, 1326  
     markings of, 1330  
**Annular ligament**, 547, 550  
     of ankle, 584, 585  
     of radius, 422  
     of wrist, anterior, 547  
     posterior, 550  
**Annulus fibrosus** [of intervertebral  
 fibrocartilage], 335, 386  
     inguinalis abdominis, 508  
     subcutaneus, 500  
     ovalis, 608  
     tendineus communis, 1035  
**Anococcygeal body**, 1184  
     nerves, 992  
     raphe, 516  
**Ansa hypoglossi**, 957  
     lentiformis, 882, 884  
     subclavia [Vicusseri], 998  
**Anterior annular ligament**, 547,  
     584  
     basis bundle, 815  
     calcaneostragaloid ligament,  
     452  
     circumflex artery, 672  
     common ligament, 384  
     condyloid foramen, 229  
     cornu of medulla spinalis, 809

- Anterior costovertebral ligament, 396  
 crural nerve, 980  
 inferior ligament, 448  
 intercostal arteries, 664  
 interosseous artery, 680  
 nerve, 965  
 ligament, 426  
 peroneal artery, 726  
 pillar of fauces, 1112  
 pillars of fornix, 886  
 pulmonary nerves, 943  
 radial carpal artery, 678  
 radioulnar ligament, 424  
 superior dental nerve, 919  
 ligament, 398, 448  
 talotibial ligament, 450  
 temporal artery, 638  
 tibial nerve, 990  
 ulnar carpal artery, 682
- Anterior-lateral ganglionic arteries', 653  
 muscles of abdomen, 498
- Antero-medial ganglionic arteries, 652
- Antibrachial fascia, 536
- cutaneous nerve, dorsal, 969  
 lateral, 963  
 medial, 964
- Anticlinal vertebra, 202 *note*
- Anticubital fossa, 672
- Antihelix, 1044
- Antitragicus muscle, 1046
- Antitragus, 1044, 1145
- Antrum cardiacum*, 1145, 1161  
 of Highmore, 259, 1015  
 pyloric, 1162, 1163  
 tympanic, 240, 1052  
 entrance to, 1052
- Anus, 1110  
 lymphatic vessels of, 792
- Aorta, 621  
 abdominal, 686  
 applied anatomy of, 687  
 branches of, 688  
*abdominalis*, 686  
 arch of, 623  
 applied anatomy of, 624  
 branches of, 625  
 peculiarities of, 624  
 of branches of, 625  
*ascendens*, 621  
 ascending, 621  
 bulb of, 622  
 coarctation of, 624  
 descending, 683  
*thoracalis*, 683  
*rami mediastinales*, 685  
*pericardiaci*, 685  
 thoracic, 683  
 applied anatomy of, 683  
 branches of, 685  
 transverse, 623
- Aortæ, anterior ventral, 152  
 dorsal, 154  
 primitive, 144
- Aortic arches, 152  
 bodies, 133, 1274  
 hiatus, 495  
 isthmus, 154, 623  
 lymph glands, 787  
 opening of heart, 612  
 plexus, 1004  
 semilunar valves, 612  
 septum, 150  
 sinuses, 612  
 spindle, 624  
 vestibule, 612
- Aorticorenal ganglion, 1003
- Apertura pelvis [minoris] inferior*, 341  
 superior, 340  
*tympanica canaliculi chordæ*, 1049
- Aperture, anterior nasal, 294
- Apertures in walls of abdomen, 1147
- Apex cordis*, 605  
 of fibula, 359  
 of heart, 605  
*linguae*, 1126  
 of nose, 1008  
*oss. sacri*, 208  
*prostatæ*, 1241  
*pulmonis*, 1101
- Aponeurosis, 463  
 epicranial, 466  
 lumbar, 486  
 of obliquus externus, 499  
 palatine, 1112  
 palmar, 550  
*palmaris*, 550  
 pharyngeal, 1143  
 plantar, 586  
*plantaris*, 586  
 suprahyoid, 481
- Apparatus digestorius*, 1109  
*lacrimalis*, 1041  
*respiratorius*, 1079  
*urogenitalis*, 1206
- Appendages of testis, 1231
- Appendices epiploicæ*, 1157  
*vesiculosæ*, 1247
- Appendicular artery, 693  
 skeleton, 195
- Appendix, auricular, left, 610  
 right, 606  
 ensiform, 220  
 of epididymis, 1231  
 of testis, 1231  
 of ventricle of larynx, 1086  
*ventriculi laryngis*, 1086  
 vermiform, 1178  
 xiphoid, 220
- Applied anatomy of abdominal  
 aorta, 687  
 of abducent nerve, 929  
 of accessory nerve, 945  
 of acoustic nerve, 936  
 of acromioclavicular joint, 413  
 of adductor longus muscle, 569  
 of ankle-joint, 452  
 of anterior facial vein, 733  
 tibial artery, 722  
 of arch of aorta, 624  
 of arteries, 619  
 of ascending pharyngeal artery, 638  
 of atrioventricular bundle, 614  
 of auditory tube, 1056  
 of axilla, 667  
 of axillary artery, 670  
 fascia, 526  
 glands, 781  
 vein, 750  
 of axygos veins, 754  
 of biceps brachii muscle, 535  
 of bone, 59  
 of bones of foot, 375  
 of forearm, 321  
 of hand, 332  
 of leg, 361  
 of pelvis, 344  
 of skull, 297  
 of brachial artery, 673  
 plexus, 970  
 of brain, 899  
 of branches of hypogastric or internal iliac artery, 708  
 of bulb of eye, 1031  
 of carpal bones, 332  
 of cavernous sinus, 745  
 of cerebellum, 844  
 of cervical fascia, 478  
 glands, 779  
 plexus, 958  
 ribs, 226
- Applied anatomy of clavicle, 303  
 of common carotid artery, 627  
 iliac artery, 700  
 peroneal nerve, 993  
 of conjunctiva, 1043  
 of coronary arteries, 623  
 of deltoid muscle, 531  
 of descending aorta, 683  
 palatine artery, 642  
 of dorsalis pedis artery, 724  
 of elbow-joint, 421  
 of emissary veins, 747  
 of extensor tendons of fingers, 546  
 of external acoustic meatus, 1048  
 carotid artery, 630  
 ear, 1048  
 iliac artery, 708  
 jugular vein, 736  
 maxillary artery, 635  
 of eyelids, 1042  
 of facial artery, 635  
 nerve, 933  
 vein, anterior, 733  
 of fascia of axilla, 526  
 of psoas and iliacus, 562  
 of femoral artery, 715  
 of femur, 352  
 of fibula, 361  
 of fingers, 551  
 flexor sheaths of, 552  
 of gall-bladder, 1116  
 of gluteal arteries, 708  
 of gums, 1112  
 of hamstring tendons, 575  
 of heart, 614  
 of hemorrhoidal venous plexus, 761  
 of hip-joint, 437  
 of humerus, 313  
 of hyoid bone, 277  
 of hypogastric artery, 701  
 of hypoglossal nerve, 947  
 of iliac fascia, 562  
 of inferior epigastric artery, 710  
 vena cava, 762  
 of inguinal and subinguinal glands, 784  
 of innominate artery, 626  
 of intercostal arteries, 686  
 nerves, 974  
 of internal capsule, 895  
 carotid artery, 647  
 ear, 1068  
 iliac artery, 701  
 jugular vein, 737  
 mammary artery, 666  
 of intervertebral fibrocartilages, 386  
 of intestines, 1186  
 of ischiorectal fossa, 516  
 of kidneys, 1214  
 of knee-joint, 446  
 of labyrinth of ear, 1068  
 of lacrimal apparatus, 1043  
 of laryngeal nerves, 943  
 of larynx, 1093  
 of lineal artery, 691  
 of lingual artery, 652  
 of liver, 1200  
 of lumbar plexus, 992  
 of lungs, 1108  
 of lymphatic system, 770  
 of mammae, 1260  
 of mediastinal cavity, 1101  
 of medulla oblongata, 833  
 spinalis, 820  
 of meninges, 907  
 of mesenteric arteries, 696  
 lymph glands, 789  
 of metacarpal bones, 332  
 of metatarsal bones, 375



- Applied anatomy of metatarsophalangeal joint of great toe, 459
- of middle meningeal artery, 640
- of motor and sensory tracts, 899
- of muscles, 462
- of lower extremity, 592
- ocular, 1038
- of palate, 1115
- of upper extremity, 556
- of vertebral column, 492
- of nasal cavities, 1015
- of nose, 1015
- of oculomotor nerve, 913
- of oesophagus, 1146
- of olfactory nerves, 909
- of optic nerve, 911
- of ovaries, 1246
- of palate, 299, 1115
- of palatine tonsils, 1141
- of palmar aponeurosis, 551
- arches, 682
- of pancreas, 1206
- of parametrium, 1255
- of parathyroid glands, 1264
- of patella, 355
- of pelvis, 344
- of penis, 1240
- of pericardium, 603
- of peritoneal fossæ, 1161
- of pharynx, 1143
- of pigment, 46
- of plantar arch, 728
- calcaneonavicular ligament, 456
- of pleura, 1098
- of pons, 836
- of popliteal artery, 719
- lymph glands, 784
- of portal system of veins, 767
- of posterior tibial artery, 725
- of pronator teres muscle, 537
- of prostate, 1242
- of prostatic venous plexus, 761
- of proximal radioulnar articulation, 423
- of psoas major muscle, 562
- of pulmonary artery, 621
- of quadriceps femoris muscle, 567
- of radial artery, 676
- nerve, 970
- of radius, 321
- of recti muscles of eye, 1038
- of rectus femoris muscle, 567
- of ribs, 225
- of sacral plexus, 993
- of salivary glands, 1138
- of saphenous veins, 747
- of scalp, 466
- of scapula, 309
- of sciatic or inferior gluteal artery, 708
- nerve, 993
- of scrotum, 1230
- of serratus anterior muscle, 530
- of sheath of psoas muscle, 562
- of shoulder-joint, 417
- of skull, 297
- of spermatic veins, 762
- of spinal arteries, 661
- of spleen, 1270
- of splenic or lienal artery, 691
- of sternoclavicular joint, 411
- of sternocleidomastoideus muscle, 479
- of sternum, 225
- of stomach, 1167
- of subclavian artery, 657
- Applied anatomy of superior thyroid artery, 631
- vena cava, 754
- of suprarenal glands, 1272
- of sympathetic nervous system, 1005
- of tarsal bones, 375
- joints, 457
- of teeth, 1125
- of temporal artery, 638
- of temporomandibular joint, 396
- of tendons of leg and foot, 583
- of testis, 1234
- of thoracic aorta, 683
- duct, 773
- nerves, 974
- of thorax, 226
- of thymus, 1266
- of thyroid gland, 1263
- of tibia, 361
- of tongue, 1130, 1132
- of trachea, 1093
- of tracheobronchial glands, 798
- of triceps brachii muscle, 536
- of trigeminal nerve, 925
- of trochlear nerve, 914
- of tympanic cavity, 1056
- of ulna, 321
- of ulnar artery, 680
- of ureter, 1218
- of urethra, 1226
- of urinary bladder, 1224
- of uterus, 1254
- of vagus nerve, 943
- of veins in front of elbow, 749
- of vena cava, inferior, 762
- superior, 754
- median cubiti, 749
- of vertebral column, 214
- joints, 393
- of vesiculæ seminales, 1237
- of volar arches, 682
- of wrist-joint, 428
- Aquaeductus cerebri*, 854
- cochleæ*, 243, 1060
- Fallopian*, 242, 1058
- vestibuli*, 242, 280
- Aqueduct, cerebral, 854
- of cochlea, 243, 1060
- of Sylvius, 821, 854
- Aqueous humor, 1030
- Arachnoid, 903
- granulations, 905
- structure of, 906
- villi, 905
- Arachnoidea encephali*, 903
- spinalis*, 903
- Arantii, corpus, 610, 612
- Arbor vitæ [of cerebellum]*, 839
- uterina*, 1250
- Arch, alveolar, 260
- of aorta, 623
- applied anatomy of, 624
- branches of, 625
- peculiarities of, 625
- of atlas, anterior, 199
- axillary, 524
- carotid, 153
- crural, deep, 509
- glossopalatine, 1112
- lumbocostal, 495
- palmar, deep, 679
- superficial, 682
- pharyngopalatine, 1112
- plantar, 727
- pubic, 341
- of a vertebra, 197
- volar, deep, 679
- superficial, 682
- zygomatic, 282
- Arches, aortic, 144, 153
- branchial or visceral, 108
- Arches of fauces, 1112
- of foot, 459
- of soft palate, 1112
- superciliary, 234, 278, 282
- Arcuate artery, 724
- fibres, 831, 832
- ligaments, 495
- line of ilium, 335
- nucleus, 831
- Arcus aortæ*, 623
- cartilaginis cricoidæ*, 1081
- glossopalatinus*, 1112
- lumbocostalis lateralis [Halleri]*, 495
- medialis [Halleri]*, 495
- parietooccipitalis*, 871
- pharyngopalatinus*, 1112
- volaris profundus*, 679
- superficialis*, 682
- Area acustica*, 848, 935
- cribrosa media*, 241
- superior*, 242
- facialis*, 242
- olfactory, 111
- oval, of Flechsig, 818
- parolfactoria*, 875
- pericardial, 87
- postrema, 848
- proamniotic, 87
- Areas of cerebral cortex, 894
- of Cohnheim, 66
- vascular, 141
- Areola of mamma, 1258
- Areolæ of bone, 57, 58
- Areolar glands, 1258
- tissue, 40
- Arm bone, 309
- fascia of, 534
- muscles of, 533
- dissection of, 533
- Arnold's nerve, 941
- Arrectores pilorum muscle, 1077
- Arteria alveolaris inferior*, 640
- superior posterior*, 641
- angularis*, 635
- anonyma*, 625
- arcuata*, 724
- audiliva interna*, 661
- auricularis posterior*, 636
- ramus auricularis*, 636
- occipitalis*, 637
- profundus*, 640
- axillaris*, 668
- basilaris*, 661
- rami ad pontem*, 661
- brachialis*, 672
- rami musculares*, 675
- buccinatoria*, 641
- bulbi urethrae*, 705
- canalis pterygoidei*, 642, 648
- carotis communis*, 627
- externa*, 630
- interna*, 645
- ramus caroticotympanicus*, 648
- centralis retinae*, 650, 1029
- cerebelli inferior anterior*, 661
- posterior*, 661
- superior*, 661
- cerebri anterior*, 651
- media*, 652
- posterior*, 662
- cervicalis ascendens*, 663
- profunda*, 666
- chorioidea*, 653
- circumflexa femoris lateralis*, 716
- medialis*, 717
- humeri anterior*, 672
- posterior*, 671
- ilium profunda*, 710
- superficialis*, 716
- scapulae*, 671
- coeliaca*, 688
- colica dextra*, 694

- Arteria colica media*, 694  
*sinistra*, 695  
*collateralis ulnaris inferior*, 675  
*superior*, 674  
*comes nervi phrenici*, 664  
*comilans nervi ischiadici*, 706  
*communicans anterior*, 652  
*posterior*, 653  
*coronaria [cordis] dextra*, 622  
*sinistra*, 623  
*cystica*, 691  
*dorsalis hallucis*, 724  
*nasi*, 650  
*pedis*, 724  
*ramus plantaris profundus*, 725  
*epigastrica inferior*, 709  
*superficialis*, 715  
*superior*, 666  
*femoralis*, 710  
*rami musculares*, 716  
*frontalis*, 650  
*gastrica dextra*, 689  
*sinistra*, 688  
*gastroduodenalis*, 690  
*gastroepiploica dextra*, 690  
*sinistra*, 691  
*genu media*, 720  
*suprema*, 718  
*glutea inferior*, 706  
*ramus iliacus*, 707  
*lumbalis*, 707  
*superior*, 707  
*haemorrhoidalis inferior*, 704  
*media*, 701  
*superior*, 696  
*hepatica*, 689  
*hypogastrica*, 700  
*ileocolica*, 693  
*iliaca externa*, 708  
*iliolumbalis*, 706  
*infraorbitalis*, 641  
*interossea communis*, 680  
*dorsalis*, 681  
*volaris*, 680  
*labialis inferior*, 634  
*superior*, 634  
*lacrimalis*, 649  
*laryngea inferior*, 662  
*superior*, 631  
*lienalis*, 691  
*rami pancreatici*, 691  
*lingualis*, 631  
*rami dorsales linguae*, 632  
*ramus hyoideus*, 632  
*malleolaris anterior lateralis*, 723  
*medialis*, 723  
*posterior medialis*, 727  
*mammaria interna*, 664  
*rami intercostales*, 664  
*perforantes*, 666  
*sternales*, 664  
*masseterica*, 641  
*maxillaris externa*, 633  
*rami glandulares*, 634  
*ramus tonsillaris*, 634  
*interna*, 638  
*rami pterygoidei*, 641  
*ramus meningeus accessorius*, 640  
*mediana*, 680  
*meningeae anterior*, 648  
*media*, 640  
*mesenterica inferior*, 694  
*superior*, 691  
*musculophrenica*, 666  
*nutricia fibulae*, 726  
*humeri*, 672  
*tibiae*, 726  
*obturatoria*, 702  
*occipitalis*, 635  
*rami musculares*, 636  
*ramus auricularis*, 636  
*descendens*, 636
- Arteria occipitalis, ramus meningeus*, 636  
*ophthalmica*, 648  
*palatina ascendens*, 634  
*descendens*, 642  
*pancreatica magna*, 691  
*pancreaticoduodenalis inferior*, 690  
*superior*, 690  
*perforans prima*, 717  
*secunda*, 717  
*tertia*, 717  
*pericardiophrenica*, 664  
*perinei*, 705  
*peronea*, 726  
*ramus calcaneus lateralis*, 726  
*communicans*, 726  
*perforans*, 726  
*pharyngea ascendens*, 637  
*rami pharyngei*, 637  
*plantaris lateralis*, 727  
*medialis*, 727  
*poplitea*, 718  
*princeps cervicis*, 636  
*hallucis*, 728  
*pollicis*, 678  
*profunda brachii*, 674  
*femoris*, 716  
*penis*, 705  
*pudenda externa profunda*, 716  
*superficialis*, 716  
*interna*, 703  
*pulmonalis*, 620  
*ramus dexter*, 620  
*sinister*, 621  
*radialis*, 676  
*rami musculares*, 678  
*perforantes*, 679  
*ramus carpeus dorsalis*, 678  
*volaris*, 678  
*volaris superficialis*, 678  
*recurrens radialis*, 678  
*tibialis anterior*, 723  
*posterior*, 724  
*recurrentes ulnaris anterior*, 680  
*posterior*, 680  
*sacralis lateralis*, 707  
*media*, 698  
*sphenopalatina*, 642  
*spinalis anterior*, 660  
*posterior*, 660  
*sternocleidomastoidea*, 636  
*stylomastoidea*, 636  
*subclavia*, 655  
*sublingualis*, 632  
*submental*, 634  
*subscapularis*, 671  
*supraorbitalis*, 649  
*tarsae lateralis*, 724  
*temporalis media*, 638  
*superficialis*, 637  
*rami auriculares anteriores*, 638  
*ramus frontalis*, 638  
*parietalis*, 638  
*thoracalis lateralis*, 671  
*suprema*, 670  
*thoracoacromialis*, 670  
*thyreoidea ima*, 626  
*inferior*, 662  
*rami oesophagei*, 663  
*tracheales*, 662  
*superior*, 631  
*ramus cricothyreoideus*, 631  
*hyoideus*, 631  
*sternocleidomastoideus*, 631  
*tibialis anterior*, 722  
*rami musculares*, 723  
*posterior*, 725  
*rami calcanei medialis*, 727  
*ramus communicans*, 727  
*transversa colli*, 663  
*ramus ascendens*, 664
- Arteria transversa colli, ramus descendens*, 664  
*faciei*, 638  
*scapulae*, 663  
*tympánica anterior*, 639  
*inferior*, 637  
*ulnaris*, 679  
*rami musculares*, 682  
*ramus carpeus dorsalis*, 682  
*volaris*, 682  
*volaris profundus*, 682  
*urethralis*, 705  
*uterina*, 701  
*vaginalis*, 702  
*vertebralis*, 659  
*rami spinales*, 660  
*ramus meningeus*, 660  
*vesicalis inferior*, 701  
*medialis*, 701  
*superior*, 701  
*volaris indicis radialis*, 679  
*Arteriae bronchiales*, 685  
*ciliares*, 650  
*digitales volares communes*, 682  
*propriae*, 682  
*gastricae breves*, 691  
*genu inferiores*, 721  
*superiores*, 720  
*iliacae communes*, 698  
*intercostales*, 685  
*intestinales*, 692  
*lumbales*, 698  
*metacarpeae volares*, 679  
*metatarsae plantares*, 728  
*oesophageae*, 685  
*ovaricae*, 697  
*palpebrales mediales*, 650  
*phrenicae inferiores*, 697  
*propriae renales*, 1213  
*rectae*, 1214  
*renales*, 696  
*sigmoideae*, 695  
*spermaticae internae*, 697  
*suprarenales mediae*, 696  
*surales*, 720  
*tarsae mediales*, 724  
*tunica adventitia*, 597  
*intima*, 596  
*media*, 596  
*Arterial mesocardium*, 603  
*Artery or Arteries, abdominal*  
*aorta*, 686  
*accessory pudendal*, 704  
*meningeal*, 640  
*acromiothoracic*, 670  
*alveolar*, 640, 641  
*anastomoses of*, 619  
*anastomotic branch of inferior gluteal*, 706  
*anastomotica magna, of brachial*, 675  
*of femoral*, 718  
*angular*, 635  
*anterior cerebral*, 651  
*choroidal*, 653  
*ciliary*, 650  
*communicating*, 651  
*humeral circumflex*, 672  
*inferior cerebellar*, 661  
*meningeal*, 648  
*spinal*, 660  
*tibial*, 722  
*tympanic*, 639  
*antero-lateral ganglionic*, 653  
*antero-medial ganglionic*, 652  
*aorta*, 622  
*abdominal*, 686  
*arch of*, 623  
*ascending*, 622  
*descending*, 683  
*thoracic*, 683  
*appendicular*, 693  
*applied anatomy of*, 619  
*arcuate*, 724  
*articular*, 720, 721

- Artery or Arteries, ascending cervical, 663  
 palatine, 634  
 pharyngeal, 637  
 auditory, 661  
 internal, 661  
 auricular, anterior, 638  
 deep, 640  
 of occipital, 637  
 posterior, 636  
 axillary, 668  
 azygos, of knee, 720  
 of vagina, 702  
 basilar, 661  
 brachial, 672  
 brachiocephalic, 625  
 of brain, 653  
 bronchial, 685, 1108  
 buccal, 641  
 buccinator, 641  
 bulbar, 661  
 calcaneal, 726, 727  
 calcaneal, 726, 727  
 capsular, middle, 696  
 caroticotympanic, 648  
 carotid, common, 627  
 external, 630  
 internal, 645  
 carpal, dorsal, 678  
 radial, 678  
 ulnar, 682  
 volar, 678, 682  
 cavernous, 648  
 cecal, of ileocolic, 693  
 central, of retina, 650, 1029  
 cerebellar, 661  
 cerebral, anterior, 651  
 middle, 652  
 posterior, 662  
 of cerebral hemorrhage, 653  
 cervical, ascending, 663  
 deep, 666  
 superficial, 664  
 transverse, 663  
 choroid, 653  
 choroidal, 653, 662  
 ciliary, 650  
 circle of Willis, 653  
 circumflex, femoral, 716, 717  
 humeral, 671, 672  
 coccygeal of inferior gluteal, 706  
 cochlear, 1068  
 coeliac, 688  
 colic, 694, 695  
 comitans nervi ischiadici, 706  
 phrenici, 664  
 common carotid, 627  
 iliac, 698  
 interosseous, 680  
 communicating, anterior, 651  
 of dorsalis pedis, 725  
 posterior, 653  
 coronary, of heart, 622  
 of lips, 634  
 of stomach, 688  
 of corpus cavernosum, penis, 705  
 costocervical trunk, 666  
 cremasteric, 709  
 cricothyroid, 631  
 cystic, 691  
 deep auricular, 640  
 epigastric, 709  
 external pudendal, 716  
 iliac circumflex, 710  
 palmar arch, 679  
 of penis, 703  
 plantar, 725  
 temporal, 641  
 volar branch of ulnar, 682  
 dental, inferior, 640  
 posterior, 641  
 descending aorta, 683  
 development of, 141, 151
- Artery or Arteries, descending branch of occipital, 636  
 palatine, 642  
 digital, foot, 728  
 hand, 682  
 volar, 682  
 distribution of, 619  
 dorsal carpal of radial, 678  
 of ulnar, 682  
 interosseous, 681  
 metacarpal, 678  
 nasal, 650  
 of penis, 706  
 dorsales linguae, 632  
 dorsalis hallucis, 724  
 pedis, 724  
 scapulae, 671  
 of ductus deferens, 701  
 epigastric, deep or inferior, 709  
 superficial, 715  
 superior, 666  
 ethmoidal, 650  
 external carotid, 630  
 iliac, 708  
 maxillary, 633  
 plantar, 727  
 pudendal, 716  
 facial, 633  
 transverse, 638  
 femoral, 710  
 circumflex, 716, 717  
 fibular, 723  
 frontal, 650  
 ganglionic, 652, 653, 662  
 gastric, 688, 689, 691  
 gastroduodenal, 690  
 gastroepiploic, 690, 691  
 genicular, 718, 720, 721  
 gluteal, 706, 707  
 of head and neck, 626  
 helicine, 1240  
 hemorrhoidal, inferior, 704  
 middle, 701  
 superior, 696  
 hepatic, 688  
 highest genicular, 718  
 intercostal, 666  
 thoracic, 670  
 humeral circumflex, 671, 672  
 hypogastric, 700  
 obliterated, 700  
 ileal, of ileocolic, 693  
 ileocolic, 693  
 iliac circumflex, deep, 710  
 superficial, 716  
 common, 698  
 external, 708  
 internal, 700  
 iliofemoral, 706  
 inferior alveolar, 640  
 articular of knee, 721  
 cerebellar, 661  
 epigastric, 709  
 gluteal, 706  
 hemorrhoidal, 704  
 labial, 634  
 laryngeal, 662  
 mesenteric, 694  
 pancreaticoduodenal, 692  
 phrenic, 697  
 profunda, 674  
 thyroid, 662  
 tympanic, 637  
 ulnar collateral, 675  
 infrahyoid, 631  
 infraorbital, 641  
 infrascapular, 671  
 innominate, 625  
 intercostal, 685, 686  
 branches of internal mammary, 664  
 highest, 666  
 superior, 666  
 interlobular, of kidney, 1213  
 internal auditory, 661, 1068
- Artery or Arteries, internal carotid, 645  
 iliac, 700  
 mammary, 664  
 maxillary, 638  
 plantar, 727  
 pudendal or pudic, 703  
 spermatic, 697  
 interosseous, common, 680  
 anterior, 680  
 dorsal, 681  
 palmar, 679  
 posterior, 681  
 volar, 680  
 intestinal, 692  
 labial, 634  
 of labyrinth, 1068  
 lacrimal, 649  
 laryngeal, inferior, 662  
 superior, 631  
 lateral calcaneal, 726  
 femoral circumflex, 716  
 nasal, 635  
 palpebral, 649  
 sacral, 707  
 tarsal, 724  
 left colic, 695  
 gastric, 688  
 gastroepiploic, 691  
 lienal, 691  
 lingual, 631  
 deep, 632  
 long ciliary, 650  
 thoracic, 671  
 of lower extremity, 710  
 lumbar, 698  
 malleolar, 723  
 internal, 727  
 mammary, internal, 664  
 masseteric, 641  
 maxillary, external, 633  
 internal, 638  
 medial palpebral, 650  
 mediana, 680  
 mediastinal, from aorta, 685  
 from internal mammary, 664  
 medidural, 640  
 medullary, 661  
 meningeal, accessory, 640  
 anterior, 648  
 of ascending pharyngeal, 637  
 middle, 640  
 of occipital, 636  
 small, 640  
 of vertebral, 660  
 mesenteric, inferior, 694  
 superior, 691  
 metatarsal, 724  
 middle cerebral, 652  
 genicular, 720  
 hemorrhoidal, 701  
 meningeal, 640  
 sacral, 698  
 mode of division of, 619  
 of origin of branches, 619  
 musculophrenic, 664  
 mylohyoid, 641  
 nasal, 650  
 dorsal, 650  
 lateral, 635  
 nasopalatine, 642  
 nerves of, 598  
 obturator, 702  
 occipital, 635  
 cesophageal of aorta, 685  
 of inferior thyroid, 663  
 ophthalmic, 648  
 ovarian, 697  
 palatine, ascending, 634  
 of ascending pharyngeal, 637  
 descending, 642  
 palmar arch, deep, 679  
 superficial, 682  
 palpebral, 649, 650  
 internal, 650

- Artery or Arteries, pancreatic, of  
 lienal, 691  
 pancreaticoduodenal, 690  
 parvidural, 640  
 perforating, of foot, 728  
 of hand, 679  
 of internal mammary, 666  
 of thigh, 717  
 pericardiac, 664, 685  
 pericardiophrenic, 664  
 perineal, 705  
 superficial, 705  
 peroneal, 726  
 anterior, 726  
 pharyngeal, ascending, 637  
 of internal maxillary, 642  
 phrenic, inferior, 697  
 superior, 686  
 plantar, 727  
 deep, 725  
 lateral (external), 727  
 medial (internal), 727  
 metatarsal, 728  
 pontine, 661  
 popliteal, 718  
 posterior auricular, 636  
 cerebral, 662  
 communicating, 653  
 humeral circumflex, 671  
 inferior cerebellar, 661  
 meningeal, from vertebral,  
 660  
 scapular, 664  
 scrotal, 705  
 superior alveolar, 641  
 tibial, 725  
 postero-medial ganglionic, 653,  
 662  
 princeps cervicis, 636  
 pollicis, 678  
 profunda, 674  
 brachii, 674  
 cervicalis, 666  
 femoris, 716  
 linguae, 632  
 superior, 674  
 of pterygoid canal, 642, 648  
 pudendal, external, 716  
 internal, 703  
 in female, 706  
 in male, 703  
 pudic, external, 716  
 internal, 703  
 pulmonary, 620  
 pyloric, 689  
 radial, 676  
 recurrent, 678  
 radialis indicis, 679  
 ranine, 632  
 recurrent, of hand, 679  
 interosseous, 682  
 radial, 678  
 tibial, 722, 723  
 ulnar, 680  
 renal, 696  
 right colic, 694  
 gastric, 689  
 gastroepiploic, 691  
 sacral, lateral, 707  
 middle, 693  
 scapular circumflex, 671  
 posterior, 664  
 transverse, 663  
 sciatic, 706  
 scrotal, posterior, 705  
 sheaths of, 597  
 short ciliary, 650  
 gastric, 691  
 sigmoid, 695  
 spermatic, 697  
 external, 709  
 internal, 697  
 sphenopalatine, 642  
 spinal, 660  
 splenic, 691
- Artery or Arteries, sternal, 660  
 sternocleidomastoid, 631, 636  
 sternomastoid, 631, 636  
 striate, 653  
 structure of, 596  
 stylomastoid, 636  
 subclavian, 655  
 subcostal, 686  
 sublingual, 632  
 submaxillary, 634  
 submental, 634  
 subscapular, 671  
 superficial cervical, 664  
 epigastric, 715  
 external pudendal, 716  
 iliac circumflex, 716  
 palmar arch, 682  
 temporal, 637  
 volar, 678  
 arch, 682  
 superior articular, of knee,  
 720  
 cerebellar, 661  
 epigastric, 666  
 gluteal, 707  
 hemorrhoidal, 696  
 intercostal, 666  
 labial, 634  
 laryngeal, 631  
 mesenteric, 691  
 phrenic, 686  
 profunda, 674  
 thoracic, 670  
 thyroid, 631  
 tympanic, 640  
 ulnar collateral, 674  
 vesical, 701  
 superhyoid, 632  
 supraorbital, 649  
 suprarenal, 696, 697, 698  
 suprascapular, 663  
 sural, 720  
 systemic distribution of, 619  
 tarsal, 724  
 temporal, 638  
 deep, 641  
 middle, 638  
 superficial, 637  
 thoracic, 670, 671  
 aorta, 683  
 axis, 670  
 highest, 670  
 lateral, 671  
 superior, 670  
 thoracoacromial, 670  
 thyroidea ima, 626  
 thyrocervical trunk, 662  
 thyroid axis, 662  
 inferior, 662  
 superior, 631  
 tibial, anterior, 722  
 posterior, 725  
 recurrent, 723  
 tonsillar, 634  
 transversa colli, 663  
 transverse cervical, 663  
 facial, 638  
 perineal, 705  
 scapular, 663  
 transversalis colli, 663  
 of trunk, 683  
 tympanic, 637, 639, 640  
 ulnar, 679  
 recurrent, 680  
 umbilical, in fetus, 616  
 of upper extremity, 655  
 urethral, 705  
 of urethral bulb, 705  
 uterine, 701  
 vaginal, 702  
 vasa aberrantia, 673  
 brevia, 691  
 intestini tenuis, 692  
 vertebral, 659  
 vesical, 701
- Artery or Arteries, vestibular,  
 1068  
 Vidian, 642, 648  
 volar arch, deep, 679  
 superficial, 682  
 carpal, 678  
 digital, common, 682  
 interosseous, 680  
 metacarpal, 679  
 proper, 682  
 volaris indicis radialis, 679
- Arterioles, 595  
 Arthrodia, 382  
 Articular arteries, 720, 721  
 capsules, 379  
 cartilage, 48  
 disk of acromioclavicular joint,  
 412  
 of distal radioulnar joint, 377  
 of sternoclavicular joint, 410  
 of temporomandibular joint,  
 395  
 end bulbs, 1069  
 lamella of bone, 379  
 meniscus, 395  
 processes of vertebrae, 197  
 tubercle of temporal bone, 237,  
 280
- Articulatio acromioclavicularis*,  
 411  
*allantoepistropheica*, 388  
*calcaneocuboida*, 454  
*coxae*, 432  
*cubiti*, 418  
*cuneonavicularis*, 456  
*ellipsoidea*, 382  
*genu*, 438  
*humeri*, 414  
*mandibularis*, 393  
*radiocarpea*, 425  
*radioulnaris*, 422  
*distalis*, 423  
*proximalis*, 422  
*sacroiliaca*, 404  
*sellaris*, 382  
*sternoclavicularis*, 409  
*talocalcanea*, 452  
*talocalcaneonavicularis*, 454  
*talocruralis*, 449  
*tibiofibularis*, 448  
*trochoidea*, 382
- Articulation or Articulations, 379  
 acromioclavicular, 411  
 amphiarthroses, 381  
 of ankle, 449  
 atlantooccipital, 392  
 of atlas with axis or epistro-  
 pheus, 388  
 with occipital bone, 392  
 calcaneocuboid, 454  
 calcaneonavicular, 455  
 of calcaneus and astragalus,  
 452  
 with the cuboid, 454  
 carpometacarpal, 429  
 of carpus, 427  
 of cartilages of ribs with each  
 other, 401  
 classification of, 380  
 condyloid, 382  
 costocentral, 396  
 costochondral, 401  
 costosternal, 399  
 costotransverse, 397  
 costovertebral, 396  
 coxal, 432  
 cuboideonavicular, 455  
 cuneocuboid, 457  
 cuneonavicular, 456  
 diarthroses, 381  
 of digits, 431, 549  
 of elbow, 418  
 gomphosis, 381  
 of hip, 432  
 humeral, 414

- Articulation or Articulations, im-**  
movable, 380  
inferior, 423  
intercarpal, 427  
interchondral, 401  
intercuneiform, 457  
intermetacarpal, 430  
intermetatarsal, 458  
intertarsal, 452  
of knee, 438  
of lower extremity, 432  
of mandible, 393  
metacarpophalangeal, 430  
metatarsophalangeal, 459  
movable, 381  
freely, 381  
slightly, 381  
movements of, 383  
of navicular with cuneiform  
bones, 456  
of pelvis, 404  
with vertebral column, 403  
of phalanges of foot, 459  
of hand, 431  
of pubic bones, 406  
symphysis, 406  
radiocarpal, 425  
radioulnar, distal, 423  
proximal, 422  
by reciprocal reception, 382  
sacrococcygeal symphysis, 406  
sacroiliac, 404  
of sacrum and coccyx, 406  
scapuloclavicular, 411  
schindylesis, 381  
shoulder, 414  
sternoclavicular, 409  
sternocostal, 399  
of sternum, 401  
sutura, 380, 381  
symphysis, 381  
pubis, 406  
synarthroses, 380  
synchondrosis, 381  
syndesmosis, 381  
talocalcaneal, 453  
talocalcaneonavicular, 454  
talocrural, 449  
tarsometatarsal, 457  
of tarsus, 452  
temporomandibular, 393  
tibiofibular, 448  
syndesmosis, 448  
tibiotarsal, 449  
of trunk, 384  
of upper extremity, 409  
of vertebral arches, 386  
bodies, 384  
column, 384  
with cranium, 392  
with pelvis, 403  
of wrist, 425
- Articulationes capitulorum**, 396  
**carpomelacarpeae**, 429  
**pollicis**, 429  
**costotransversariae**, 397  
**costovertebrales**, 396  
**digitorum manus**, 431  
**pedis**, 459  
**intercarpeae**, 427  
**interchondrales**, 401  
**intermetacarpeae**, 430  
**intermetatarsaeae**, 458  
**intertarsaeae**, 452  
**metatarsophalangeae**, 459  
**ossiculorum auditus**, 1054  
**sternocostales**, 399  
**tarsometatarsaeae**, 457
- Aryepiglottic fold**, 1085  
**Aryepiglotticus muscle**, 1089  
**Arytaenoideus muscle**, 1088  
**Arytenoid cartilages**, 1081  
glands, 1090  
swellings, 177
- Ascending aorta**, 621
- Ascending cervical artery**, 664  
colon, 1180  
frontal convolution, 869  
lumbar vein, 753  
oblique muscle, 503  
palatine artery, 634  
parietal convolution, 871  
pharyngeal artery, 637  
applied anatomy of, 638  
ramus of ischium, 337  
of os pubis, 337
- Association fibres of cerebral  
hemispheres**, 890  
neurons, 811
- Asterion**, 282, 296
- Astragalus**, 366  
ossification of, 374
- Atavistic epiphyses**, 59
- Atlantooccipital articulation**, 392
- Atlas**, 199  
development of anterior arch  
of, 104  
ossification of, 210
- Atresia, congenital, of pupil**, 136
- Atria of bronchi**, 1106
- Atrial canal**, 145
- Atrioventricular bundle of His**,  
614  
groove of heart, 604  
opening, left, 611  
right, 609
- Atrium dextrum**, 606  
of heart, left, 610  
primitive, 145  
right, 606  
of nasal fossa, 1011  
**sinistrum**, 610
- Attic or epitympanic recess**, 240,  
1049
- Attolens aurem muscle**, 1045
- Attraction sphere**, 34
- Attrahens aurem muscle**, 1045
- Auditory artery**, 661  
internal, 661  
canal, external, 1046  
meatus, external, 1046  
nerve, 934  
ossicles, 1053  
development of, 140  
pit, 138  
plate, 138  
teeth of Huschke, 1065  
tube, 1052  
cartilaginous portion of, 1052  
isthmus of, 1053  
osseous portion of, 1052  
pharyngeal ostium of, 1189  
tonsil of, 1053  
torus tubarius or cushion of,  
1052, 1140  
veins, 1068  
vesicle, 138
- Auerbach's plexus**, 1176
- Auricle, left**, 610  
right, 606
- Auricula dextra**, 606  
of ear, 1044  
cartilage of, 1044  
development of, 141  
ligaments of, 1044  
muscles of, 1045  
vessels and nerves of, 1046  
of heart, left, 610  
right, 606  
**sinistra**, 610
- Auricular appendix, left**, 610  
right, 606  
artery, anterior, 638  
deep, 640  
of occipital, 636  
posterior, 636  
lymph glands, 774  
nerves, anterior, 923  
great, 956  
posterior, 933
- Auricular nerves of vagus**, 941  
point, 296  
surface of ilium, 335  
of sacrum, 208  
tubercle of Darwin, 1044  
vein, posterior, 734
- Auricularis muscles**, 1045
- Auriculotemporal nerve**, 923
- Auriculoventricular groove**, 604
- Auris interna**, 1057
- Auscultation, triangle of**, 524
- Axes of pelvis**, 342
- Axial filament of spermatozoön**,  
81  
skeleton, 195
- Axilla**, 667  
applied anatomy of, 667  
dissection of, 525  
fascia of, 526
- Axillary arch**, 524  
artery, 668  
applied anatomy of, 669  
branches of, 670  
surface markings of, 1318  
lymph glands, 780  
nerve, 961  
sheath, 668  
vein, 750  
applied anatomy of, 750
- Axis, celiac**, 688  
of lens, 1031  
optic, 1017  
thoracic, 670  
thyroid, 662  
vertebra, 200  
ossification of, 210
- Axis-cylinder process**, 71
- Axon of nerve cells**, 71
- Azygos arteries of vagina**, 702  
artery, articular, 720  
uvulae muscle, 1114  
vein, 753  
applied anatomy of, 754
- B**
- Back, muscles of, deep**, 485  
dissection of, 485
- Baillarger, band of**, 883, 891
- Ball-and-socket joint**, 382
- Band of Baillarger**, 883, 891  
of Bechterew, 893  
of Gennari, 893  
of Giacomini, 875  
iliotibial, 563  
moderator, 610
- Bare area of liver**, 1151
- Bartholin, duct of**, 1137  
glands of, 190, 1258
- Basal column, posterior**, 813  
knobs of Englemann, 38  
lamina, 119  
optic nucleus of Meynert, 861  
plate of placenta, 100  
ridge, or cingulum of tooth,  
1117  
vein, 740
- Base of cerebral peduncle**, 849  
of heart, 605  
of sacrum, 208  
of skull, inferior surface, 278  
upper surface of, 288
- Basement membranes**, 45
- Basichromatin**, 34
- Basihyal of hyoid bone**, 275
- Basilar artery**, 661  
crest, 1064  
membrane, 1065  
part of occipital bone, 230  
plexus, 746  
sinus, 746
- Basilic vein**, 748  
median, 747
- Basion**, 281, 296



- Basis bundle, anterior, 815**  
 lateral, 817  
*cordis*, 605  
*oss. sacri*, 208  
*pedunculi*, 849  
*prostatee*, 1241  
*pulmonis*, 1102
- Basivertebral veins, 755**
- Basket cells of cerebellum, 642**
- Bechterew, band of, 893**  
 nucleus of, 836, 935
- Bed of stomach, 1163**
- Bell, nerve of, 957, 960**
- Bellini, duct of, 1212**
- Bertin, ligament of, 433**
- Betz, giant cells of, 891**
- Biceps brachii muscle, 534**  
 femoris muscle, 574  
 flexor cubiti muscle, 534  
 muscle, 534
- Bicipital fascia, 535**  
 groove, 311  
 ridges, 311
- Bicuspid teeth, 1118**  
 valve, 612
- Bigelow, Y-shaped ligament of, 433**
- Bile capillaries, 1198**  
 ducts, 1198, 1200  
 structure of, 1200
- Bipolar cells of retina, 1028**
- Bird's nest of cerebellum, 839**
- Biventer cervicis muscle, 489**
- Biventral lobes of cerebellum, 839**
- Bladder, 1218**  
 gall, 1199  
 urinary, 1218  
 applied anatomy of, 1224  
 in child, 1220  
 development of, 188  
 distended, 1219  
 empty, 1218  
 female, 1221  
 interior of, 1222  
 ligaments of, 1221  
 lymphatic vessels of, 793  
 structure of, 1223  
 trigone of, 1222  
 vessels and nerves of, 1223
- Blandin, glands of, 1131**
- Blastodermic vesicle, 85**
- Blastopore, 86**
- Blood, composition of, 61**  
 corpuscles, 61  
 development of, 141  
 origin of, 192  
 course of, in an adult, 595  
 in fetus, 616  
 liquor sanguinis, 61  
 plasma, 61  
 platelets, 64
- Blood islands, 142**
- Bochdalek, cornucopia of, 846**
- Body or Bodies, anococcygeal, 1184**  
 aortic, of Zuckerkandl, 1274  
 carotid, 1273  
 cavities, development of, 178  
 ciliary, 1023  
 coccygeal, 1273  
 geniculate, 858  
 Malpighian, of kidney, 1212  
 of spleen, 1268  
 olivary, 824  
 of penis, 1239  
 perineal, 1184  
 pituitary, 861  
 polar, 79  
 restiform, 841  
 of stomach, 1163  
 thyroid, 1261  
 trapezoid, 835  
 of uterus, 1249  
 of a vertebra, 197
- Body-stalk, 92, 96**
- Bone or Bones, 50**  
 ankle, 366  
 applied anatomy of, 59  
 arm, 309  
 articular lamella of, 379  
 astragalus, 366  
 atlas, 199  
 axis, 200  
 breast, 216  
 calcaneus, 362  
 calf, 359  
 canaliculi of, 54  
 cancellous tissue of, 50  
 capitate, 327  
 carpal, 323  
 cells, 55  
 chemical composition of, 55  
 classes of, viz., long, flat, mixed  
 or irregular, short, 195  
 clavicle, 307  
 coccyx, 209  
 collar, 301  
 compact tissue of, 50  
 cranial, 227  
 cuboid, 367  
 cuneiform, of carpus, 324  
 of tarsus, 369  
 diploë of, 196  
 of ear, 1053  
 of elbow, 314  
 eminences and depressions of, 196  
 epistropheus, 200  
 ethmoid, 251  
 ethmoidal, 251  
 facial, 255  
 femur, 345  
 fibula, 359  
 flat, 196  
 of foot, 362  
 frontal, 233  
 hamate, 328  
 of hand, 323  
 Haversian canals of, 53  
 systems of, 53  
 hip, 333  
 humerus, 309  
 hyoid, 275  
 ilium, 333  
 incus, 1054  
 inferior nasal conchæ, 268  
 innominate, 333  
 interparietal, 231  
 ischium, 336  
 lacrimal, 263  
 lesser, 263  
 lacunæ of, 54  
 lamellæ of, 54  
 lingual, 275  
 long, 195  
 of lower extremity, 333  
 jaw, 271  
 lunate, 323  
 lymphatics of, 53  
 malar, 263  
 malleus, 1053  
 mandible, 271  
 marrow of, 51  
 maxilla, 256  
 medullary artery of, 52  
 membrane of, 51  
 metacarpal, 329  
 metatarsal, 371  
 minute anatomy of, 53  
 multangular, greater, 326  
 lesser, 327  
 nasal, 255  
 navicular, of carpus, 323  
 of tarsus, 368  
 nerves of, 52  
 number of, in body, 195  
 nutrient artery of, 52  
 occipital, 227  
 os calcis, 362  
 coxæ, 333
- Bone or Bones, os magnum, 327**  
 ossification of, 56  
 palate, 265  
 palatine, 265  
 parietal, 231  
 patella, 354  
 pelvic, 340  
 perforating fibres of, 54  
 periosteum of, 51  
 phalanges of foot, 373  
 of hand, 337  
 pisiform, 326  
 pubis, 337  
 radius, 319  
 ribs, 220  
 sacrum, 206  
 scaphoid, 323, 368  
 scapula, 304  
 semilunar, 323  
 sesamoid, 376  
 shin, 355  
 short, 196  
 sphenoid, 245  
 sphenoidal, 245  
 conchæ, 250  
 stapes, 1054  
 sternum, 216  
 structure and physical properties of, 50  
 surfaces of, 196  
 sutural, 255  
 talus, 366  
 tarsal, 362  
 temporal, 237  
 thigh, 345  
 tibia, 355  
 trapezium, 326  
 trapezoid, 327  
 triangular, 324  
 turbinated, 268  
 ulna, 314  
 unciform, 328  
 of upper extremity, 301  
 jaw, 256  
 vertebra prominens, 201  
 vertebrae, cervical, 198  
 lumbar, 204  
 thoracic, 201  
 sacral and coccygeal, 205  
 vessels of, 52  
 vomer, 269  
 Wormian, 255  
 zygomatic, 263
- Bowman, capsule of, 1212**  
 glands of, 1012  
 membrane of, 1020  
 muscle of, 1023
- Brachia conjunctiva of cerebellum, 841**  
 of corpora quadrigemina, 853  
 pontis, 841
- Brachial artery, 672**  
 applied anatomy of, 673  
 branches of, 674  
 peculiarities of, 672  
 surface marking of, 1321  
 cutaneous nerve, lateral, 962  
 medial, 964  
 posterior, 969  
 fascia, 534  
 plexus, 958  
 applied anatomy of, 970  
 veins, 750
- Brachialis anticus muscle, 535**
- Brachiocephalic artery, 625**  
 veins, 751
- Brachioradialis muscle, 542**
- Brain, arteries of, 653**  
 commissures of, 856  
 development of, 120  
 dissection of, 821  
 divisions of, 821  
 dura of, 900  
 meninges of, 900

- Brain, pia of, 906  
 surface markings of, 1280  
 veins of, 739  
 weight of, 894  
 Branchial arches, 108  
 grooves, 108  
 Breadth index of skull, 296  
 Breast bone, 216  
 Breasts or mammae, 1258  
 development of, 116  
 Bregma, 238, 277, 296  
 Bregmatic fontanelle, 294  
 Bridge of nose, 1008  
 Brim of pelvis, 340  
 Broad ligaments of uterus, 1154, 1250  
 Broca, cap of, 870  
 gyrus of, 870  
 limbic lobe of, 873  
 parolfactory area of, 874  
 Bronchi, 1091  
 Branchial arteries, 685, 1108  
 nerves, 943  
 veins, 754, 1108  
 Bronchomediastinal trunks, 798  
*Bronchus dextra*, 1092  
 divisions of, 1105  
 eparterial, 1105  
 hyparterial, 1105  
 intrapulmonary, 1106  
 left, 1092  
 right, 1092  
*sinister*, 1092  
 Brunner's glands, 1175  
 Bryant's triangle, 1330  
 Buccal artery, 641  
 branches of facial nerve, 933  
 cavity, 1110  
 glands, 1111  
 nerve, long, 922  
 Buccinator artery, 641  
 muscle, 470  
 nerve, 922  
 Bucconasal membrane, 112  
 Buccopharyngeal fascia, 477  
 membrane, 86  
 Bulb of aorta, 622  
 of corpus cavernosum penis, 1238  
 of eye, 1017  
 olfactory, 874, 893  
 of posterior cornu, 879  
 spinal, 822  
 vaginal, 1257  
 of vestibule, 1257  
 Bulbar arteries, 661  
 Bulbocavernosus muscle, 518, 520  
 Bulbourethral glands of Cowper, 190, 1243  
 Bulbs of internal jugular vein, 736  
*Bulbus cordis*, 145  
*oculi*, 1017  
*olfactorius*, 874  
*vestibuli*, 1257  
*Bulla ethmoidalis*, 294, 1011  
 Bundle of His, 69  
 oval, 119  
 of Vieq d'Azyr, 857, 860, 886  
 Burdach, tract of, 808, 817  
 Burns' space, 477  
 Bursa, omental, 1152, 1155  
 development of, 170  
*omentalis*, 1155  
 pharyngeal, 1139  
 prepatellar, 566  
 Bursae beneath gluteus maximus, 570  
 mucosae, 380  
 near knee-joint, 443  
 shoulder-joint, 415
- C**
- CACUMINAL lobe, 838  
*Calamus scriptorius*, 847, 726  
 Calcaneal arteries, 726, 727  
 Calcanean arteries, lateral, 726  
 medial, 727  
 nerve, medial, 988  
 sulcus, 365  
 tuberosity, 365  
 Calcaneostragaloid articulation, 452  
 ligaments, 452, 453  
 Calcaneocuboid ligaments, 454  
 Calcaneonavicular ligaments, 455  
 Calcaneotibial ligament, 450  
 Calcaneus, 362  
 ossification of, 374  
*Calcar avis*, 879  
*femorale*, 351  
 Calcarine fissure, 869  
 Calf bone, 359  
 Calices of kidney, 1210, 1216  
 Callosal convolution, 873  
 fissure, 873, 876  
 Callosomarginal fissure, 869  
 Camper, fascia of, 498  
 Canaliculi of bone, 53  
 dental, 1119  
 Canaliculus, inferior tympanic, 243, 280  
 mastoid, 243, 280  
*Canalis centralis cochleae*, 242  
*craniopharyngeus*, 251  
*reunians* [of Hensen], 1062, 1064  
 Canal or Canals, adductor, 713  
 Alcock's, 511  
 alimentary, 1109  
 alveolar, 257  
 atrial, 145  
 auditory, external, 1046  
 carotid, 242, 280  
 central, of medulla spinalis, 810  
 of cervix of uterus, 1250  
 condyloid, 230  
 craniopharyngeal, 166, 251  
 ethmoidal, 235, 253  
 femoral, 712  
 Haversian, of bone, 53  
 of Huguier, 238, 932, 1050  
 Hunter's, 713  
 hyaloid, 1030  
 hypoglossal, 229  
 incisive, 261, 278  
 infraorbital, 258  
 inguinal, 508  
 lacrimal, 1041  
 mandibular, 273  
 neural, 88  
 neurenteric, 88  
 of Nuck, 187, 1251  
 of Petit, 1030  
 pharyngeal, 278  
 pterygoid, 280  
 pterygopalatine, 258, 267  
 sacral, 208  
 of Schlemm, 1018  
 semicircular, 1058  
 membranous, 1062  
 spermatic, 508  
 spiral, of modiolus, 1060  
 vertebral, 208  
*Canales semicirculares ossei*, 1058  
 Canaliculus innominatus of Arnold, 248, note  
*Canalis adductorius*, 713  
*centralis* [medulla spinalis], 810  
*cervicis uteri*, 1250  
*inguinalis*, 508, 1229  
*sacralis*, 208  
*semicircularis lateralis*, 1059  
 posterior, 1059  
 superior, 1059  
 Cancellous tissue of bone, 50  
 Canine eminence, 257  
 fossa, 257  
 teeth, 1117  
 Caninus muscle, 470  
 Canthi of eyelids, 1038  
 Cap of Broca, 870  
 Capillaries, 598  
 bile, 1198  
 structure of, 598  
 Capitate bone, 327  
*Capitulum fibulae*, 359  
*humeri*, 312  
*mallei*, 1053  
*stapedis*, 1054  
*Capsula articularis*. See Individual joints.  
*cricothyraenoidea*, 1084  
*externa*, 884  
*extrema*, 883  
*interna*, 883  
*lentis*, 1030  
*vasculosa lentis*, 136  
 Capsular artery, middle, 696  
 Capsule, adipose, of kidney, 1209  
 adrenal, 1270  
 of Bowman, 1212  
 of brain, 883, 884  
 of Glisson, 1156, 1196  
 of lens, 1030  
 of Ténon, 1037  
*Caput caecum coli*, 1177  
*femoris*, 345  
*humeri*, 309  
*pancreatis*, 1203  
*taili*, 367  
 Cardiac cycle, 615  
 ganglion of Wrisberg, 1002  
 glands of stomach, 1166  
 muscular tissue, 68  
 nerves, cervical, 942  
 great, 997  
 from sympathetic, 997  
 thoracic, 943  
 from vagus, 942  
 notch, 1104  
 orifice of stomach, 1161  
 plexus of nerves, 1001  
 veins, 730  
 Cardinal veins, 157  
 Caroticoclinoid foramen, 249, 290  
 ligament, 251  
 Caroticotympanic artery, 648  
 nerve, 946, 1056  
 Carotid arch, 153  
 artery, common, 627  
 applied anatomy of, 629  
 branches of (occasional), 629  
 peculiarities of, 628  
 surface markings of, 1290  
 external, 630  
 applied anatomy of, 630  
 branches of, 630  
 surface markings of, 1290  
 internal, 645  
 applied anatomy of, 647  
 branches of, 648  
 peculiarities of, 647  
 bodies, 1273  
 canal, 242, 280  
 ganglion, 996  
 glands, 1273  
 groove, 247, 290  
 nerve, internal, 995  
 nerves from glossopharyngeal, 939  
 plexus, 996  
 internal, 996  
 sheath, 477  
 skins, 134, 1273  
 triangles, 643  
 tubercle, 199  
 Carpal arteries from radial, 678  
 from ulnar, 682  
 bones, 323  
 net-work, 678  
 Carpometacarpal articulations, 429  
 Carpus, 323  
 applied anatomy of, 332

- Carpus**, articulations of, 427  
ossification of, 331  
surface form of, 1315
- Cartilage or Cartilages**, articular, 48  
arytenoid, 1081  
of auricula, 1044  
cells, 47  
cellular, 47  
corniculate, 1081  
costal, 48, 224  
cricoid, 1081  
cuneiform, 1082  
of epiglottis, 1082  
epiphysial, 57  
ethmovomerine, 270  
histology of, 47  
hyaline, 47  
intrathyroid, 1080  
lacunae, 47  
of larynx, 1079  
structure of, 1082  
lateral, lower, 1009  
upper, 1009  
of nose, 1008, 1009  
Meckel's, 109, 273  
parachordal, 106  
permanent, 47  
of pinna, 1044  
of Santorini, 1081  
of septum of nose, 1009  
sesamoid, 1009  
temporary, 47  
thyroid, 1080  
trabeculae cranii, 106  
of trachea, 1092  
vomeronasal, 1012  
white fibro-, 49  
of Wrisberg, 1082
- Cartilagineae alares minores**, 1009
- arytaenoideae**, 1081  
**corniculatae**, 1081  
**costales**, 224  
**cuneiformes**, 1082  
**laryngis**, 1079  
**nasi**, 1008
- Cartilaginous ear capsules**, 107  
vertebral column, 104
- Cartilago alaris major**, 1009  
**crus laterale**, 1009  
**mediale**, 1009  
**auriculae**, 1044  
**cricoidea**, 1081  
**epiglottica**, 1082  
**nasi lateralis**, 1009  
**septi nasi**, 1008  
**thyreoidea**, 1080  
**triticea**, 1083
- Caruncula lacrimalis**, 1041
- Carunculae hymenales**, 1257
- Cauda equina**, 806  
**helicis**, 1044  
**pancreatis**, 1204
- Caudal fold of embryo**, 92
- Caudate lobe of liver**, 1195  
nucleus, 881  
process of liver, 1195
- Caudatum**, 881
- Cavernous arteries**, 648  
nerves of penis, 1005  
plexus, 996  
portion of urethra, 1226  
sinuses, 744  
applied anatomy of, 745  
nerves in, 928  
spaces of penis, 1240
- Cavity or Cavities**, amniotic, 96  
body or coelom, 88  
buccal, 1110  
cotyloid, 339  
glenoid, 307  
of lesser pelvis, 341  
mediastinal, 1098, 1100, 1101  
of mouth proper, 1110  
nasal, 292, 1010
- Cavity or Cavities**, oral, 1110  
peritoneal, 1149  
of septum pellucidum, 887  
sigmoid, of radius, 321  
of ulna, 313, 318  
subarachnoid, 904  
subdural, 903  
of thorax, 600  
tympanic, 1049  
of uterus, 1250
- Carum conchae**, 1044
- laryngis**, 1085  
**Meckelii**, 914  
**nasi**, 292, 1010  
**oris**, 1110  
**proprium**, 1110  
**septi pellucidi**, 887  
**subarachnoideale**, 904  
**tympani, paries carotica**, 1052  
**labyrinthica**, 1050  
**mastoidea**, 1051  
**tympanum**, 1049  
**paries jugularis**, 1049  
**membranacea**, 1049  
**tegumentalis**, 1049  
**uteri**, 1250
- Cecal arteries**, 693  
fossae, 1159
- Cecum**, 1177  
lymphatic vessels of, 792
- Cell or Cells**, animal, 33  
basket, of cerebellum, 842  
of Betz, 891  
of bone, 55  
centro-acinar of Langerhans, 1205  
chalice, 37  
chromaffin, 1272  
clasmotocytes, 41  
of Claudius, 1067  
definition of, 33  
of Deiters, 1067  
divisions of, 34  
of Dogiel, 950  
enamel, 1123  
fat, 42  
germinal, of medulla spinalis, 117  
giant, 51  
of Betz, 891  
goblet, 37  
of Golgi, 892  
granule, 41  
gustatory, 1007  
of Hensen, 1067  
lamellar, 41  
of Martinotti, 892  
intermediate, 88  
Mastzellen, 41  
membrane, 34  
mesamorphoid, 142  
nerve, 70  
nucleus of, 34  
olfactory, 1012  
pigment, 42  
plasma, 41  
prickle, 39  
of Purkinje, 842  
reproduction of, 34  
of Sertoli, 1233  
of spinal ganglia, 803, 949  
splenic, 1267  
structure of, 33  
wandering, 42
- Cell mass**, inner, 84
- Cella**, 877
- Cellulae ethmoidales**, 1014
- Cellular cartilage**, 47
- Cement of teeth**, 1121  
formation of, 1124
- Central artery of retina**, 650  
canal of medulla spinalis, 810  
cells of fundus glands, 1166  
fissure, 868
- Central gray stratum of cerebral aqueduct**, 854  
ligament of medulla spinalis, 907  
lobe, 873  
nervous system, 801  
part of lateral ventricle, 877  
sulcus, 868  
tendinous point of perineum, 518  
tendon of diaphragma, 495
- Centres**, higher visual, 864, 909  
lower visual, 909  
of ossification, 57, 864
- Centrifugal nerve fibres**, 803
- Centriole**, 34  
bodies of ovum, 78  
of spermatozoön, 80, 81
- Centripetal nerve fibres**, 803
- Centroacinar cells of Langerhans**, 1205
- Centrosome**, 34
- Centrosphere**, 34
- Centrum ovale majus**, 876  
**minus**, 876
- Cephalic flexure**, ventral, of  
embryonic brain, 121  
fold of embryo, 92  
index, 296  
portion of sympathetic system, 995  
vein, 747  
accessory, 748
- Ceratohyal of hyoid bone**, 277
- Cerebellar artery**, anterior inferior, 661  
posterior inferior, 661  
superior, 661  
fasciculus, direct, 813  
notches, 837  
peduncles, 841  
tract, direct, 816  
of Flechsigs, 816, 828  
veins, 739
- Cerebelloolivary fasciculus**, 830
- Cerebellospinal tract of Löwenthal**, 815
- Cerebellum**, 836  
applied anatomy of, 844  
**brachia, conjunctiva**, 841  
**pontis**, 840  
development of, 124  
**fibrae propriae**, 842  
gray substance of, 842  
lobes of, 836  
**nucleus dentatus**, 844  
peduncles of, 841  
structure of, 839  
surfaces of, 837, 838  
vermis of, 836  
white substance of, 839
- Cerebral arteries**, anterior, 651  
middle, 652  
posterior, 662  
aqueduct, 854  
cortex, nerve cells of, 891  
nerve fibres of, 892  
structure of, 891  
types of, 893  
dura mater, 900  
fissure, lateral, 867  
hemispheres, 865  
borders of, 866, 867  
development of, 128  
fibers of, association, 890  
commissural, 890  
projection, 890  
transverse, 890  
fissures of, 867  
gray substance of, 891  
gyri of, 869  
interior of, 875  
lobes of, 869  
localization of, 894  
poles of, 867

- Cerebral hemispheres, structure  
 of, 889  
 sulci of, 867  
 surfaces of, 867  
 white substance of, 889  
 peduncles, 848  
 structure of, 848  
 nerves, 907  
 abducent, 927  
 accessory, 944  
 acoustic, 934  
 development of, 131  
 facial, 929  
 glossopharyngeal, 937  
 hypoglossal, 945  
 oculomotor, 911  
 olfactory, 908  
 optic, 909  
 trigeminal, 914  
 trochlear, 913  
 vagus, 940  
 veins, 739  
 ventricles, 845, 864, 877  
 vesicles, 88, 120  
 Cerebroolivary fasciculus, 830  
 Cerebrospinal fasciculus, 815  
 fibres of internal capsule, 884  
 fluid, 905  
 Ceruminous glands, 1047  
 Cervical artery, ascending, 663  
 deep, 666  
 superficial, 664  
 transverse, 663  
 branch of facial nerve, 933  
 cardiac nerves, 942  
 enlargement of medulla  
 spinalis, 808  
 fascia, 476  
 applied anatomy of, 478  
 flexure of embryonic brain, 121  
 ganglion, 997, 998  
 lymph glands, 778  
 applied anatomy of, 780  
 muscles, lateral, 475  
 superficial, dissection of, 475  
 nerve, 957  
 cutaneous or transverse, 957  
 of facial, 933  
 nerves, 951  
 divisions of, anterior, 954  
 posterior, 951  
 pleura, 1095  
 plexus, 954  
 applied anatomy of, 958  
 branches of, 956, 957  
 posterior, 957  
 portion of sympathetic, 996  
 rib, 201  
 applied anatomy of, 226  
 vein, deep, 738  
 posterior, 738  
 vertebrae, 198  
 Cervicalis ascendens muscle, 488  
 Cervix uteri, 1249  
 portio supravaginalis, 1249  
 vaginalis, 1250  
 of uterus, 1249  
 Chalice cells, 37  
 Chambers of eye, 1024  
 Chassaignac's tubercle, 199  
 Check ligaments, 393  
 of eye, 1038  
 Cheeks, 1110  
 Chest, 216  
 Chiasma, optic, 862, 909  
 opticum, 862, 909  
 Chiasmatic groove, 246, 290  
 Choane, 278, 294, 1010  
 Chondrin, 50  
 Chondrocranium, 106  
 Chondroglossus muscle, 1129  
 Chondromucoid, 50  
 Chondrosternal ligament, 399  
 intra-articular, 400  
 Chondroxiphoid ligaments, 401  
 Chorda obliqui, 423  
 tympani nerve, 932  
 Chordae tendineae [left ventricle],  
 612  
 [right ventricle], 610  
 Willis, 741  
 Chordal furrow, 91  
 portion of base of skull, 106  
 Chorioidea, 1021  
 lamina choriocapillaris, 1022  
 vasculosa, 1022  
 Chorion, 99  
 frondosum, 100  
 laeve, 99  
 Chorionic villi, 99  
 Choroid artery, 653  
 coat of eyeball, 1021  
 structure of, 1021  
 plexuses of fourth ventricle,  
 846  
 of lateral ventricle, 887  
 of third ventricle, 864  
 vein, 740  
 Choroidal artery, anterior, 653  
 posterior, 662  
 fissure, 135, 888  
 Chromaffin cells, 1272  
 organs, 133  
 Chromatin, 34  
 Chromatolysis, 72  
 Chromosomes, 34  
 Chyle, 768  
 Chyliferous vessels, 768  
 Cilia, 1038  
 Ciliaris muscle, 1023  
 Ciliary arteries, 650  
 body, 1023  
 ganglion, 917  
 glands, 1039  
 muscle, 1023  
 nerves, 916, 917  
 processes, 1023  
 Ciliated epithelium, 37  
 Cingulate gyrus, 873  
 sulcus, 869  
 Cingulum of cerebral hemisphere,  
 890  
 of teeth, 1125  
 Circle, arterial, of Willis, 653  
 Circular folds of small intestine,  
 1173  
 sinus, 746  
 sulcus, 869, 873  
 Circulating fluids, 61  
 blood, 61  
 lymph, 64  
 Circulation of blood in adult, 595  
 in fetus, 616, 650  
 Circulus arteriosus major, 1025  
 minor, 1025  
 major [iris], 650, 1025  
 minor [iris], 650, 1025  
 venosus [mammary], 1260  
 Circumduction, 383  
 Circumferential fibrocartilage, 50  
 Circumflex artery, femoral, lateral,  
 716  
 medial, 717  
 humeral, anterior, 672  
 posterior, 671  
 nerve, 961  
 Circuminsular fissure, 869  
 Circumvallate papillae, 1127  
 Cisterna basalis, 904  
 chyli, 772  
 cerebellomedullaris, 904  
 chiasmatis, 904  
 fossae cerebri lateralis, 905  
 interpeduncularis, 904  
 magna, 904  
 pontis, 904  
 venae magnae cerebri, 905  
 Cisternae subarachnoid, 904  
 subarachnoidales, 904  
 Clarke's column, 813  
 Clasmatocytes, 41  
 Claudius, cells of, 1067  
 Claustum, 882  
 Clava, 824  
 Clavicle, 301  
 applied anatomy of, 303  
 ossification of, 303  
 peculiarities of, in sexes, 303  
 structure of, 303  
 surface anatomy of, 1313  
 Clavicula, 301  
 Clavipectoral fascia, 528  
 Cleft palate, 299  
 Clinging fibres of cerebellum, 844  
 Clinoid processes, anterior, 249,  
 290  
 middle, 246, 290  
 posterior, 246, 290  
 Clitoris, 1257  
 frenulum of, 1257  
 glans of, 1257  
 prepuce of, 1257  
 Clivus of sphenoid, 246  
 monticuli of cerebellum, 838  
 Cloaca, ectodermal, 172  
 entodermal, 172  
 pelvic portion of, 188  
 phallic portion of, 188  
 vesicourethral portion of, 188  
 Cloacal membrane, 172  
 duct, 172  
 tubercle, 190  
 Cloquet, lymph gland of, 783  
 Closing membranes, 108  
 Coarctation of aorta, 624  
 Coccygeal arteries, 706  
 body, 1273  
 cornua, 209  
 gland, 1273  
 nerve, division of, anterior, 982  
 posterior, 954  
 plexus, 992  
 skein, 1273  
 Coccygeus muscle, 514  
 Coccyx, 209  
 ossification of, 212  
 Cochlea, 1059  
 aqueduct of, 243, 280, 1060  
 cupula of, 1059, 1060  
 hamulus laminae spiralis, 1060  
 helicotrema of, 1060  
 modiolus of, 1060  
 scale of, 1060  
 spiral canal of, 1060  
 lamina of, osseous, 1060  
 secondary, 1060  
 vessels of, 1068  
 Cochlear artery, 1068  
 nerve, 935, 1068  
 nuclei, 836, 935  
 root of acoustic nerve, 935  
 Cochleariform process, 243, 1052  
 Coeliac artery, 688  
 axis, 688  
 branches of vagus nerve, 943  
 ganglion, 1002  
 plexus, 1002  
 Cog-tooth of malleus, 1053  
 Cohnheim, areas of, 66  
 Colic arteries of ileocolic, 794  
 artery, left, 695  
 middle, 694  
 right, 694  
 flexures, right and left, 1180  
 impression, 1192  
 valve, 1179  
 Collagen, 44  
 Collar bone, 301  
 Collateral circulation, 619  
 eminence, 881  
 fissure, 869  
 ganglia, 995  
 Collecting tubes of kidney, 1212  
 Colles, fascia of, 337, 499, 517  
 Colliculi, inferior, 853, 854

- Colliculi, superior, 853, 854  
 Colliculus of arytenoid cartilage, 1081  
   *facialis*, 848  
   *inferior*, 854  
   *nervi optici*, 1027  
   *superior*, 854  
 Collum anatomicum, 309  
   *femoris*, 345  
   *mallei*, 1053  
   *tali*, 367  
 Coloboma, 135  
 Colon, 1180  
   *ascendens*, 1180  
   *ascending*, 1180  
   *descendens*, 1181  
   *descending*, 1181  
   *iliac*, 1181  
   left or splenic flexure of, 1180  
   *pelvic*, 1181  
   right or hepatic flexure of, 1180  
   *sigmoid*, 1181  
   *sigmoideum*, 1181  
   structure of, 1184  
   *tela submucosa*, 1185  
   *transversum*, 1180  
   *tunica mucosa*, 1185  
     *muscularis*, 1184  
     *serosa*, 1184  
   vessels and nerves of, 1185  
 Colored lines of Retzius, 1120  
   or red corpuscles, 61  
 Colorless corpuscles, 62  
 Colostrum corpuscles, 1259  
 Columna anterior [*medulla spinalis*], 809  
   *formicis*, 886  
   *lateralis* [*medulla spinalis*], 809  
   *nasi*, 1008  
   *posterior* [*medulla spinalis*], 890  
   *vertebralis*, 196  
 Columnae carnae, 610  
 Columnar epithelium, 37  
 Columns of Clarke, 813  
   of fornix, 886  
   of medulla spinalis, 811, 812, 813  
   rectal, of Morgagni, 1184  
   renal, 1211  
   of vagina, 1255  
   vertebral, 196, 212  
 Comes nervi phrenici, 664  
 Comitans nervi ischiadici, 706  
 Comma-shaped fasciculus, 817  
 Commissura labiorum anterior, 1256  
   *palpebrarum lateralis*, 1038  
   *medialis*, 1038  
 Commissural fibres of cerebral hemispheres, 890  
 Commissure of brain, 856  
   anterior, 131, 887  
   middle or gray, 856  
   posterior, 127, 860  
   of corpus callosum, 131  
   habenular, 859  
   hippocampal, 886  
   of Gudden, 909  
   of labia majora, 1257  
   of medulla spinalis, anterior and posterior gray, 810  
   anterior white, 808  
   optic, 862  
 Commissures, palpebral, 1038  
 Common bile duct, 1200  
   lymphatics of, 793  
   carotid artery, 627  
   dental germ, 1121  
   iliac arteries, 698  
   glands, 786  
   veins, 763  
   integument, 1071  
   interosseous artery, 680  
   peroneal nerve, 989  
 Communicans fibularis nerve, 990  
 Communicans tibialis nerve, 988  
 Communicantes cervicales, nerves, 957  
 Communicating artery, anterior, 651  
   from dorsalis pedis, 725  
   posterior, 653  
 Compact tissue of bone, 50  
 Comparison of bones of hand and foot, 375  
 Complexus muscle, 489  
 Compressor naris muscle, 469  
 Concha of auricula, 1044  
   *carum conchae*, 1044  
   *cymba conchae*, 1044  
   nasal, inferior, 268  
   articulations of, 269  
   ossification of, 269  
   middle, 254  
   superior, 254  
   *nasalis inferior*, 268  
 Conchae, sphenoidal, 250  
   *sphenoidales*, 250  
 Conchal crest, 258, 266  
 Condyle of mandible, 293  
 Condyles of femur, 349  
   occipital, 230  
   of tibia, 355  
 Condylod articulation, 382  
   canal, 230  
   foramen, anterior, 229  
   fossa, 230, 287  
   process of mandible, 273  
 Cone of attraction, 83  
   bipolars of retina, 1028  
   granules of retina, 1029  
   of origin of axon, 72  
 Cones of retina, 1029  
 Confluence of sinuses, 229, 743  
 Confluens sinuum, 743  
 Coni vasculosi, 1233  
 Conical papillae, 1128  
 Conjoined tendon of internal oblique and transversalis muscles, 505  
 Conjugate diameter of pelvis, 341  
 Conjunctiva, 1040  
   applied anatomy of, 1042  
 Connecting fibrocartilages, 50  
 Connective tissues, 40  
   adipose, 42  
   areolar, 40  
   development of, 47  
   lymphatics of, 46  
   mucous, 44  
   nerves of, 46  
   proper, 40  
   retiform, 40  
   vessels of, 46  
   white fibrous, 40  
   yellow elastic, 40  
 Connective tissue corpuscles, 40  
   extraperitoneal, 509  
 Conoid ligament, 412  
   tubercle, 301  
 Constriction, duodenopyloric, 1162  
 Constrictor muscles, 1141, 1142  
   pharyngis inferior muscle, 1141  
   medius muscle, 1142  
   superior muscle, 1142  
   urethrae muscle, 520, 521  
 Contractile fibre-cells, 68  
 Conus arteriosus, 608  
   *elasticus* [larynx], 1083  
   *medullaris*, 806  
 Convoluted tubes of kidney, 1212  
 Convolution, callosal, 873  
   frontal, ascending, 869  
   occipitotemporal, 871  
   parietal, ascending, 871  
 Cooper, ligament of, 502  
 Copula, 164  
 Cor, 603  
 Coracoacromial ligament, 413  
 Coracobrachialis muscle, 534  
 Coracoclavicular fascia, 528  
 Coracohumeral ligament, 414  
 Coracoid process, 307  
   tuberosity, 301  
 Cord, gangliated, 995  
   spermatic, 1229  
   spinal, 805  
   umbilical, 96  
   vocal, false, 1085  
   inferior, 1086  
   superior, 1085  
   true, 1086  
 Corium or cutis vera, 1074  
   layers of, 1074  
   *stratum papillare*, 1074  
   *reticulare*, 1074  
 Cornea, 1018  
   structure of, 1019  
 Corneal corpuscles, 1020  
   endothelium, 1021  
   epithelium, 1019  
   spaces, 1020  
 Corniculate cartilages, 1081  
 Cornu anterius, 878  
   *inferior*, 879  
   of medulla spinalis, 809  
   *posterius*, 879  
 Cornua of coccyx, 209  
   of hyoid bone, 275  
   of lateral ventricles, 878, 879  
   *majora* [os hyoidei], 275  
   *minora* [os hyoidei], 277  
   of sacrum, 207  
   of thyroid cartilage, 1080  
 Cornucommissural fasciculus, 817  
 Cornucopia of Bochdalek, 846  
 Corona glandis, 1239  
   *radiata* [brain], 884  
   [ovum], 79  
 Coronal suture, 277, 282  
 Coronary artery of heart, 622  
   applied anatomy of, 623  
   peculiarities of, 623  
   of lips, 634  
   of stomach, 688  
   ligament of liver, 1151  
   ligaments of knee, 442  
   plexuses, 1002, 1004  
   sinus, 730  
   opening of, 608  
   sulcus of heart, 604  
   veins, 730  
   of stomach, 766  
 Coronoid fossa, 313  
   process of mandible, 273  
   of ulna, 315  
 Corpora cavernosa clitoridis, 1257  
   *penis*, 1238  
   bulbs of, 1238  
   crura of, 1238  
   *mamillaria*, 860  
   *quadrigenina*, 853  
   brachia of, 853  
   structure of, 854  
 Corpus albicans, 860  
   *Arantii*, 610, 612  
   *callosum*, 865, 876  
   development of, 131  
   genu of, 876  
   peduncle of, 875  
   rostrum of, 876  
   splenium of, 876  
   cavernosum, artery to, 705  
   *urethrae*, 1237  
   *ciliare*, 1023  
   *femoris*, 348  
   *fibulae*, 359  
   *formicis*, 886  
   *geniculatum laterale*, 858  
   *mediale*, 858  
   Highmori, 1232  
   *humeri*, 811  
   *incudis*, 1054  
   *luteum*, 1246



- Corpus maxillae*, 256  
*oss. hyoidei*, 275  
*ili*, 333  
*ischi*, 336  
*pubis*, 337  
*pancreatis*, 1204  
*facies anterior*, 1204  
*inferior*, 1204  
*posterior*, 1204  
*margo anterior*, 1204  
*inferior*, 1204  
*superior*, 1204  
*papillare [corium]*, 1074  
*penis*, 1239  
*pineale*, 859  
*radii*, 320  
*resiformes*, 830, 841  
*sphenoidalis*, 246  
*spongiosum*, 1238  
*sterni*, 218  
*striatum*, 729, 881  
*vein of*, 885  
*subthalamicum*, 860  
*tali*, 367  
*tibiae*, 356  
*ulnae*, 318  
*uteri*, 1249  
*facies intestinalis*, 1249  
*vesicalis*, 1249  
*margo lateralis*, 1249  
*vertebrae*, 197  
*vitreum*, 1030  
*Corpuscles*, colored, 61  
*development of*, 142  
*colorless*, 62  
*connective tissue*, 40  
*genital*, 1069  
*of Golgi and Mazzoni*, 1069  
*of Grandry*, 1069  
*of Hassall*, 1265  
*of Herbst*, 1069  
*Pacinian*, 1069  
*of Ruffini*, 1070  
*of Wagner and Meissner*, 1070  
*Corrugator cutis ani muscle*, 516  
*muscle*, 468  
*supercilii muscle*, 468  
*Cortex of cerebellum*, 842  
*of cerebrum*, 891  
*Corti, ganglion of*, 1060, 1068  
*organs of*, 1065  
*pillars or rods of*, 1065  
*spiral organ of*, 1065  
*tunnel of*, 1065  
*Cortical arches of kidney*, 1211  
*arterial system of brain*, 654  
*portion of suprarenal gland*, 1272  
*substance of kidney*, 1211  
*of lens*, 1031  
*visual centre*, 909  
*Corticostriate fibres*, 882  
*Costae*, 220  
*Costal cartilages*, 48, 224  
*element or process*, 199  
*groove*, 222  
*pleura*, 1095  
*tuberosity*, 303  
*Costocentral articulation*, 396  
*Costocervical trunk*, 666  
*Costochondral articulations*, 401  
*Costocoracoid ligament*, 528  
*membrane*, 528  
*Costomediastinal sinus*, 1097  
*Costosternal articulations*, 399  
*Costotransverse articulations*, 397  
*ligaments*, 399  
*Costovertebral articulations*, 396  
*ligament, anterior*, 396  
*Cotyloid cavity*, 339  
*ligament*, 339, 434  
*Covering bones*, 107  
*Coverings of direct inguinal hernia*, 1188  
*Coverings of femoral hernia*, 1189  
*of oblique inguinal hernia*, 1187  
*of ovum*, 79  
*of testes*, 1228  
*Cowper's glands*, 190, 1243  
*Coxal articulation*, 432  
*applied anatomy of*, 437  
*movements of*, 435  
*muscles in relation to*, 435  
*Cranial bones*, 227  
*fossa, anterior*, 288  
*middle*, 290  
*posterior*, 291  
*nerve*, 907  
*Craniology*, 295  
*Craniopharyngeal canal*, 166  
*Cranium*, 227  
*bones of*, 227  
*breadth of*, 296  
*development of*, 105  
*fissures in, congenital*, 255  
*height of*, 296  
*horizontal circumference of*, 296  
*length of*, 296  
*longitudinal arc of*, 296  
*Cremaster muscle*, 504  
*Cremasteric artery*, 709  
*fascia*, 504  
*Crescents of Gianuzzi*, 1137  
*Crest or Crests, basilar*, 1064  
*conchal*, 258, 266  
*ethmoidal*, 260, 267  
*frontal*, 235  
*of ilium*, 336  
*incisor*, 261  
*infratemporal*, 248, 282  
*internal occipital*, 228, 292  
*intertrochanteric*, 348  
*lacrimal*, 260, 263  
*nasal*, 261, 266  
*neural*, 88, 120  
*obturator*, 338  
*of pubis*, 338  
*of right atrium*, 606, 607  
*sphenoidal*, 247  
*supramastoid*, 237  
*of tibia*, 356  
*of tubercles of humerus*, 309  
*urethral, in female*, 1228  
*in male*, 1225  
*Cribriform plate of ethmoid*, 252  
*Cricoaerthyraenoideus lateralis muscle*, 1088  
*posterior muscle*, 1088  
*Cricoaerthyraenoid ligament*, 1084  
*muscles*, 1088  
*Cricoid cartilage*, 1081  
*Cricothyroideus muscle*, 1088  
*Cricothyroid artery*, 631  
*ligament, middle*, 1083  
*membrane*, 1083  
*muscle*, 1088  
*Cricotracheal ligament*, 1083  
*Crista arcuata [arytenoid cartilage]*, 1081  
*colli costae*, 222  
*falciformis*, 241  
*galli*, 252  
*terminalis [of His]*, 146  
*vestibuli*, 1058  
*Crossed commissural fibres*, 811  
*pyramidal tract*, 815  
*Crosses of Ranvier*, 75  
*Crown of a tooth*, 1118  
*Crucial anastomosis*, 717  
*ligaments*, 441  
*Cruciate crural ligament*, 584  
*eminence of occipital bone*, 228  
*ligament of atlas*, 390  
*ligaments of knee*, 441  
*Crura cerebri*, 848  
*of diaphragma*, 495  
*of fornix*, 887  
*of penis*, 1238  
*Crura of stapes*, 1054  
*of subcutaneous inguinal ring*, 500  
*Crural arch, deep*, 509  
*muscles, anterior, dissection of*, 578  
*lateral, dissection of*, 582  
*posterior, dissection of*, 578, 579, 581  
*nerve, anterior*, 980  
*septum*, 712  
*sheath*, 710  
*Crureus muscle*, 566  
*Crus cerebri*, 848  
*commune [semicircular canals]*, 1059  
*fornicis*, 887  
*helicis*, 1044  
*penis*, 1238  
*Crusta or pes of cerebral peduncle*, 849  
*petrosa of teeth*, 1121  
*formation of*, 1121  
*Cruveilhier, glenoid ligaments of*, 430, 459  
*Crypts of Lieberkühn*, 1174  
*Crystalline lens*, 1030  
*cortical substance of*, 1031  
*development of*, 136  
*nucleus of*, 1031  
*Cuboid bone*, 367  
*Cuboidonaviclar articulation*, 457  
*Culmen monticuli [cerebellum]*, 838  
*Cuneate nucleus*, 825  
*tubercle*, 825  
*Cuneiform bone of carpus*, 324  
*of tarsus, first*, 369  
*second*, 369  
*third*, 370  
*cartilages*, 1082  
*tubercle*, 1085  
*Cuneocuboid articulation*, 457  
*Cuneonavicular articulation*, 456  
*Cuneus*, 871  
*Cup, optic*, 134  
*Cupula of cochlea*, 1060  
*of pleura*, 1095  
*Curvatura ventriculi major*, 1162  
*minor*, 1162  
*Curvatures of stomach*, 1161  
*Curved lines of ilium*, 333  
*Curves of vertebral column*, 212  
*Cushion of auditory tube*, 1139  
*of epiglottis*, 1082  
*Cushions, endocardial*, 148  
*Cusps of bicuspid valve*, 612  
*of tricuspid valve*, 609  
*Cutaneous cervical nerve*, 957  
*nerve, external*, 977  
*internal*, 964, 981  
*lesser*, 964  
*middle*, 980  
*Cuticle*, 1071  
*Cuticula dentis*, 1123  
*Cutis plate*, 102  
*vera or corium*, 1074  
*Cutting teeth*, 1117  
*Cuvier, ducts of*, 157  
*Cycle, cardiac*, 615  
*Cylindrical epithelium*, 37  
*Cymba conchas*, 1044  
*Cystic artery*, 691  
*duct*, 1200  
*vein*, 767  
*Cyton*, 72  
*Cytoplasm*, 33  
*Cytotrophoblast*, 85
- D**
- Dacryon*, 287, 296  
*Dartos tunic*, 1228

- Darwin, auricular tubercle of, 1044  
 Daughter chromosomes, 36  
 Decidua, 98  
   basalis, 98  
   capsularis, 98  
   parietalis, 98  
   placentalis, 98  
   stratum compactum of, 98  
   spongiosum of, 98  
   unaltered or boundary layer of, 98  
 Decidual cells, 98  
 Decussation of lemniscus, 827  
   partial, of optic nerves, 909  
   pyramidal, 822  
 Deep abdominal ring, 508  
   artery of penis, 703  
   auricular artery, 640  
   cerebral veins, 740  
   cervical artery, 666  
     fascia, 476  
     lymph glands, 778  
     vein, 738  
   crural arch, 509  
   epigastric artery, 709  
     vein, 760  
   external pudic artery, 716  
   fascia of arm, 534  
     of forearm, 536  
   femoral artery, 716  
   iliac circumflex vein, 760  
   lingual artery, 632  
   muscles of back, 485  
   palmar arch, 679  
   peroneal nerve, 990  
   petrosal nerve, 919  
   plantar artery, 725  
   Sylvian vein, 740  
   temporal arteries, 641  
     nerves, 922  
   transverse fascia of leg, 580  
 Degeneration, Wallerian, 815  
 Deglutition, 1114  
 Deiters, cells of, 1067  
   nucleus of, 836, 935  
 Deltoid ligament, 450  
   muscle, 530  
   tubercle, 302  
   tuberosity, 312  
 Deltoideus muscle, 530  
 Demilunes of Heidenhain, 1137  
 Demours, membrane of, 1020  
 Dendrons of nerve cells, 72  
*Dens*, or odontoid process of axis, 199  
   *serotinus*, 1118  
 Dental artery, inferior, 640  
   posterior, 641  
   canaliculi, 1120  
   formulæ, 1116  
   furrow, 1122  
   germs, 1121  
   lamina, 1121  
   nerve, inferior, 923  
   pulp, 1119  
   sac, 1123  
 Dentate fissure, 874  
   gyrus, 874  
   ligament, 907  
*Dentes*, 1115  
   *canini*, 1117  
   *decidui*, 1118  
   *incisivi*, 1117  
   *molares*, 1118  
   *permanentes*, 1117  
   *praemolares*, 1118  
 Dentin, 1119  
   formation of, 1123  
   intertubular, 1120  
   secondary, 1121  
 Dentinal canaliculi, 1120  
   fibres, 1120  
   matrix, 1120  
   sheath of Neumann, 1120  
 Dentinal tubules, 1120  
 Depressions for arachnoid granulations, 232  
 Depressor alae nasi muscle, 469  
   anguli oris muscle, 470  
   labii inferioris muscle, 470  
   septi muscle, 469  
 Dermal bones, 107  
 Dermic coat of hair follicle, 1076  
 Dermis, 1074  
 Descemet, membrane of, 1020  
 Descendens cervicalis nerve, 957  
 Descending aorta, 683  
   colon, 1181  
   comma-shaped fasciculus, 817  
   oblique muscle, 499  
   palatine artery, 642  
   process of lacrimal bone, 263  
   ramus of hypoglossal nerve, 947  
     of ischium, 337  
     of os pubis, 338  
 Descent of testis, 186  
 Detrusor urinae muscle, 1223  
 Deutoplasm, 78  
 Development of adipose tissue, 42  
   of allantois, 93  
   of amnion, 94  
   of anal canal, 172  
   of arteries, 152  
   of body cavities, 178  
   of brain, 120  
   of branchial or visceral arches, 108  
   of cerebral nerves, 132  
   of chorion, 99  
   of chromaffin organs, 133  
   of deciduous teeth, 1121  
   of digestive tube, 162  
   of ear, 138  
   of external organs of generation, 190  
   of eye, 134  
   of face, 111  
   of fetal membranes, 93  
   of glands of skin, 116  
   of heart, 143  
   of hypophysis cerebri, 166  
   of joints, 115  
   of kidney, 187  
   of limbs, 113  
   of liver, 174  
   of lymphatic system, 161  
   of mammae, 116  
   of medulla spinalis, 117  
   of mouth, 163  
   of muscles, 116  
   of nervous system, 117  
   of neural groove and tube, 88  
   of nose, 111  
   of notochord, 90  
   of ovaries, 184  
   of palate, 112  
   of palatine tonsils, 165  
   of pancreas, 175  
   of parathyroid glands, 166  
   of parietes, 102  
   of permanent teeth, 1124  
   of pharyngeal pouches, 108  
   of placenta, 100  
   of primitive segments, 91  
   streak, 86  
   of prostate, 189  
   of rectum, 172  
   of respiratory organs, 176  
   of ribs, 104  
   of salivary glands, 164  
   of skeleton, 102  
   of skin, 116  
   of skull, 105  
   of spinal nerves, 119  
   of spleen, 176  
   of sternum, 105  
   of suprarenal glands, 134  
   of sympathetic system, 133  
   of teeth, 1121  
 Development of testis, 186  
   of thymus, 165  
   of thyroid gland, 165  
   of tongue, 164  
   of umbilical cord, 96  
   of urethra, 190  
   of urinary bladder, 188  
   and generative organs, 180  
   of vascular system, 141  
   of veins, 155  
   of vertebral column, 102  
   of visceral arches, 108  
   of yolk-sac, 93  
 Diameters of pelvis, 341, 342  
 Diaphragm, muscles of, 493  
   pelvic, 510, 1146  
   urogenital, 519  
 Diaphragma, 493  
   lymphatic vessels of, 798  
   sellae, 901  
 Diaphragmatic lymph glands, 796  
   part of pelvic fascia, 511  
   pleura, 1095  
   surface of heart, 605  
 Diaphysis, 59  
 Diarthroses, 381  
 Diaster, 36  
 Diencephalon, 126, 855  
 Digastric fossa, 239  
   muscle, 480  
   nerve, from facial, 933  
   triangle, 644  
 Digastric muscle, 480  
 Digestion, organs of, 1109  
 Digestive apparatus, 1109  
   development of, 162, 168  
   tube, 1109  
 Digital arteries, foot, 728  
   from superficial volar arch, hand, 682  
   682  
   fossa of epididymis, 1231  
   of femur, 347  
   nerves of lateral plantar, 989  
   of medial plantar, 988  
   of median, 965  
   of musculocutaneous, 964  
   of radial, 969  
   of ulnar, 967  
   vaginal ligaments, 540  
   veins of foot, 756  
   of hand, 747  
 Digits, articulations of, 431  
 Dilator naris anterior muscle, 469  
   posterior muscle, 469  
   pupillae muscle, 1025  
   tubae muscle, 1053  
 Diploë, 196  
 Diploic veins, 738  
   frontal, 738  
   occipital, 739  
   temporal, 738  
 Direct cerebellar fasciculus, 813  
   tract, 828  
   of Flechsig, 816, 828  
   inguinal hernia, 1188  
   pyramidal tract, 815  
 Discharge of ovum, 1246  
*Discus articularis*, 395  
   *proligerus*, 1246  
 Disk, interpubic, 407  
   optic, 1027  
 Disks, tactile, of Merkel, 1069  
 Dissection of axilla, 525  
   of brain, 821  
   of crural muscles, 578, 579, 581, 582  
   of encephalon, 821  
   of femoral muscles, medial, 567  
   posterior, 574  
   of geniohyoideus muscle, 481  
   of infrahyoid muscles, 482  
   of left atrium, 610  
   ventricle, 611

- Dissection of medulla spinalis, 805  
 of mesenteric artery, inferior, 695  
   superior, 692  
 of muscles of abdomen, 498, 503, 504, 505  
   of arm, 533  
   of back, 485  
   of eyelids, 467  
   of foot, 587, 588  
   of forearm, 536, 539, 542  
   of gluteal region, 569, 572  
   of iliac region, 559  
   of leg, 576, 578, 579, 581, 582  
   of mouth, 469  
   of palate, 1114  
   of scalp, 464  
   of shoulder, 530, 531  
   of thigh, 562  
 of pectoral region, 525  
 of popliteal fossa, 718  
 of pterygoidei muscles, 474  
 of rectus abdominis muscle, 505  
 of right auricle, 607  
 of ventricle, 609  
 of superficial cervical muscle, 475  
 of suprahyoid muscles, 480  
 of temporal muscle, 473  
*Diverticulum ilei*, 1172  
 Meckel's, 93, 1172  
 Divisions of bronchi, 1105  
   of cells, 34  
 Dobie's line, 66  
 Dogiel, cells of, 950  
 Dorsal aortæ, 154  
   artery of penis, 706  
   carpal artery, of radial, 678  
     of ulnar, 682  
   ligament, 550  
   cutaneous nerve, intermediate, 990  
     lateral, 988  
     medial, 990  
   fissure of medulla oblongata, 822  
   interosseus muscles, 555, 591  
   interosseous artery, 681  
   nerve, 970  
   lamina, 119  
   mesogastrium, 168  
   metacarpal arteries, 678  
   veins, 750  
   nasal artery, 650  
   nerve of penis, 992  
   peripheral band, 818  
   pulmonary nerves, 943  
   scapular nerve, 960  
   spinal artery, 660  
   veins of penis, 761  
   venous arch of foot, 756  
   net-work of hand, 747  
   vestibular nucleus, 836  
*Dorsalis hallucis artery*, 724  
*linguae artery*, 632  
*pedis artery*, 724  
   applied anatomy of, 724  
   branches of, 724  
   peculiarities of, 724  
   surface markings of, 1332  
*scapulae artery*, 671  
 Dorsopitrochlearis brachii muscle, 524  
 Dorsomedian fissure of medulla oblongata, 822  
*Dorsum ilii*, 333  
*linguae*, 1126  
*nasi*, 1008  
*scapulae*, 305  
*sellae*, 246, 290  
 Douglas, pouch of, 1151  
 Drum, 1049  
 Duct or Ducts, accessory pancreatic, 1205  
   of Bartholin, 1137  
   of Bellini, 1212  
   of bulbourethral glands, 1243  
   cloacal, 172  
   common bile, 1200  
   of Cuvier, 157  
   cystic, 1200  
   ejaculatory, 1237  
   frontonasal, 236  
   of Gärtner, 1245  
   hepatic, 1199  
   lacrimal, 1041  
   lactiferous, 1258  
   of liver, 1198  
   lymphatic, right, 772  
   Müllerian, 182  
   nasolacrimal or nasal, 1042  
   pancreatic, 1204, 1205  
   parotid, 1135  
   pronephric, 180  
   prostatic, 1241  
   orifices of, 1225  
   of Rivinus, 1137  
   of Santorini, 1205  
   semicircular, 1062  
   seminal, 1235  
   Skene's, 190  
   Stensen's, 1135  
   sublingual, 1137  
   submaxillary, 1136  
   thoracic, 771  
   thyroglossal, 165, 1127  
   vitelline, 92  
   Wharton's, 1136  
   of Wirsung, 1204  
   Wolffian, 180  
 Ductless glands, 1260  
   aortic bodies of Zuckerkandl, 1274  
   carotid skeins, 1273  
   coccygeal skein, 1273  
   lien, 1266  
   parathyroids, 1263  
   spleen, 1266  
   suprarenals, 1270  
   thymus, 1264  
   thyroid, 1261  
*Ductuli aberrantes* [testis], 1236  
*efferentes* [testis], 1233  
*transversi* [epoöphoron], 1244  
*Ductus arteriosus*, 616  
*choledochus*, 1200  
*cochlearis*, 1063  
*cysticus*, 1200  
*deferens*, 1235  
   ampulla of, 1235  
   structure of, 1236  
*ejaculatorii*, 1237  
*endolymphaticus*, 1058, 1062  
*hepaticus*, 1199  
*lacrimalis*, 1041  
*longitudinalis epoöphori*, 1245  
*lymphaticus dexter*, 772  
*nasolacrimalis*, 1042  
*pancreaticus* [Wirsungi], 1204  
*parotideus*, 1135  
*Santorini*, 1205  
*semicirculares*, 1062  
*submaxillaris*, 1136  
*thoracicus*, 771  
*utriculosaccularis*, 1062  
*venosus*, 156, 618  
   development of, 156  
   fossa for, 1194  
   obliterated, 765  
 Duodenal fossæ, 1158  
   glands, 1175  
   impression, 1192  
 Duodenojejunal flexure, 1171  
   fold, 1159  
   fossa, 1159  
 Duodenomesocolic fold, 1158  
 Duodenopyloric constriction, 1162  
 Duodenum, 1169  
   ascending portion, 1171  
   descending portion, 1170  
   horizontal portion, 1170  
   lymphatic vessels of, 792  
   superior portion, 1169  
   suspensory muscle of, 1171  
   vessels and nerves of, 1171  
 Dura of brain, 900  
   mater, cerebral, 900  
     arteries of, 902  
     endosteal layer of, 902  
     meningeal layer of, 902  
     nerves of, 902  
     processes of, 900  
     veins of, 902  
   encephali, 900  
   spinal, 902  
     structure of, 903  
   spinalis, 902  
 Dural nerve, 941
- E**
- EAR, 1043  
   auricula of, 1044  
   muscles of, 1045  
   cartilaginous capsules of, 107  
   cochlea, 1059  
   development of, 138  
   external, 1043  
   internal, or labyrinth, 1057  
     applied anatomy of, 1068  
   meatus acusticus externus, 1046  
   membranous labyrinth, 1061  
   middle, 1049  
   osseous labyrinth, 1057  
   pinna of, 1044  
   semicircular canals of, 1058  
   tympanic cavity of, 1049  
     applied anatomy of, 1056  
     muscles of, 1055  
     ossicles of, 1053  
     vessels and nerves of, 1056  
   vestibule of, 1058  
 Eberstaller, medial frontal sulcus of, 870  
 Ectoderm, 86, 87  
 Ectodermal cloaca, 172  
 Efferent nerves, 803  
 Eighth nerve, 934  
 Ejaculator urinae muscle, 518  
 Ejaculatory ducts, 1237  
 Elastic fibrocartilage, 50  
   laminae of cornea, 1020  
   membrane of larynx, 1083  
   tissue, yellow, 44  
 Elastin, 44  
 Elbow bone, 314  
 Elbow-joint, 418  
   anastomoses around, 675  
   applied anatomy of, 421  
   movements of, 420  
   surface anatomy of, 1315  
   markings of, 1319  
   vessels and nerves of, 420  
 Eleidin, 39  
 Eleventh nerve, 944  
 Embryo, form of, at different stages, 191  
   separation of, 92  
 Embryology, 77  
 Embryonic disk, 86  
   pole, 85  
 Eminence, canine, 257  
   collateral, 881  
   cruciate, 228  
   frontal, 234, 278, 282  
   hypothenar, 546  
   iliopectineal, 336  
   intercondyloid, of tibia, 355

- Eminence, medial, of rhomboid fossa, 847  
 parietal, 231, 277, 282  
 pyramidal, of pons, 833  
 of tympanic cavity, 1052  
 thenar, 546  
 Eminences and depressions of bones, 196  
*Eminentia arcuata*, 241  
*articularis*, 237  
*collateralis*, 881  
*pyramidalis*, 1052  
*saccularis*, 861  
 Emissary veins, 746  
 Enamel cells, 1123  
 droplet, 1123  
 epithelium, 1123  
 fibres or prisms, 1120  
 organ, 1123  
 of teeth, 1120  
 formation of, 1123  
 Enarthrosis, 382  
 Encephalon, 821  
 dissection of, 821  
 End-arteries, 1214  
 End-bulbs of Krause, 1069  
 End-plates, motor, of Kühne, 803  
 Endocardial cushions, 148  
 Endocardium, 613  
 Endognathion, 299  
 Endolymph, 1061  
 Endomysium, 64  
 Endoneurium, 802  
 Endoskeleton, 195  
 Endosteal layer of dura mater, 902  
 Endothelium, 37  
*cameras anterioris*, 1021  
 corneal, 1021  
 Engelmann, basal knobs of, 38  
 Enlargements of medulla spinalis, 808  
 Ensisiform appendix, 220  
 Entoderm, 85  
 Entodermal cloaca, 172  
 Entrance of larynx, 1085  
 Eosinophil corpuscles, 63  
 Eparterial branch of right bronchus, 1092, 1105  
 Ependymal layer, 117  
 Epicardium, 613  
 Epicondyles of humerus, 313  
 Epicranial aponeurosis, 466  
 Epidermic coat of hair follicle, 1077  
 Epidermis, development of, 116  
 structure of, 1071  
 Epididymis, 1231  
 Epidural space, 903  
 Epigastric artery, deep or inferior, 709  
 applied anatomy of, 710  
 peculiarities, 709  
 surfacemarkings of, 1309  
 superficial, 717  
 superior, 666  
 fold, 1187  
 lymph glands, 786  
 region, 1147  
 vein, deep, 760  
 superficial, 756  
 Epiglottis, 1082  
 tubercle or cushion of, 1082  
 Epimysium, 64  
 Epineurium, 801  
 Epiotic centre of temporal bone, 245  
 Epiphyses, atavistic, 59  
 pressure, 59  
 traction, 59  
 Epiphyseal cartilage, 57  
 Epiphysis, 59, 859  
 Epiploic foramen, 176, 1155  
 glands, right, 788  
*Epistropheus*, 200  
*Epithalamus*, 127, 859  
*fasciculus retroflexus* [of Meynert], 859  
*ganglion habenulae*, 859  
 pineal body, 859  
 structure of, 860  
 posterior commissure, 860  
 nucleus of, 860  
*trigonum habenulae*, 859  
 Epithelial cells, 36  
 Epithelium, 36  
 ciliated, 37  
 columnar, 37  
*corneae*, 1019  
 cylindrical, 37  
 enamel, 1123  
 germinal, of Waldeyer, 184, 1245  
 glandular, 37  
 pavement, 37  
 simple, 37  
 stratified, 39  
 of cornea, 1019  
 transitional, 40, 1223  
 Epitympanic recess, 240, 1049  
 Eponychium, 1075  
 Epoöphoron, 181, 1244  
 Equator of lens, 1031  
 Erector clitoridis muscle, 521  
 penis muscle, 518  
 spinæ or sacrospinalis muscle, 488  
 Eruption of teeth, 1124  
 Erythroblasts, 51  
 Erythrocytes, 61  
 Ethmoid bone, 251  
 Ethmoidal arteries, 650  
 bone, 251  
 articulations of, 255  
 cribriform plate of, 252  
 crest, 260, 267  
 foramina, 287  
 horizontal lamina, 252  
 labyrinth or lateral mass of, 253  
 lamina papyracea of, 253  
 os planum of, 253  
 ossification of, 254  
 perpendicular plate of, 252  
 uncinatè process of, 253  
 vertical plate, 252  
 canals, 235, 253  
 cells, 253, 1014  
 notch, 235  
 plate, 107  
 process of inferior nasal concha, 268  
 spine, 246, 290  
 Ethmiovomerine cartilage, 270  
 Eustachian tube, 1052  
 valve, 607, 608  
 Excavation, rectouterine, 1151  
 vesicouterine, 1152  
 Exner, plexus of, 893  
 Exognathion, 299  
 Exoskeleton, 195  
 Extensor carpi radialis brevis muscle, 542  
 longus muscle, 542  
 ulnaris muscle, 544  
 coccygis muscle, 490  
 digiti quinti proprius muscle, 544  
 digitorum brevis muscle, 586  
 communis muscle, 544  
 longus muscle, 577  
 hallucis longus muscle, 577  
 indicis muscle, 546  
 proprius muscle, 546  
 minimi digiti muscle, 544  
 ossis metacarpi pollicis muscle, 545  
 pollicis brevis muscle, 545  
 longus muscle, 545  
 Extensor primi internodii pollicis muscle, 545  
 proprius hallucis muscle, 577  
 secundi internodii pollicis muscle, 545  
 Exterior of skull, 277  
 External abdominal ring, 500  
 arcuate ligament, 495  
 auditory canal, 1046  
 meatus, 1046  
 calcaneal artery, 726  
 calcaneoastragaloid ligament, 453  
 canthus of eyelids, 1038  
 circumflex artery, 716  
 cutaneous nerve, 977  
 geniculate body, 858  
 intercostal muscles, 492  
 lateral ligament, 394, 419, 426  
 ligament of malleus, 1055  
 malleolar artery, 723  
 oblique muscle, 499  
 plantar artery, 727  
 nerve, 989  
 popliteal nerve, 989  
 pterygoid muscle, 474  
 pudic arteries, 716  
 respiratory nerve of Bell, 960  
 saphenous vein, 757  
 semilunar fibrocartilage, 442  
 spermatic fascia, 1229  
 sphincter ani muscle, 516  
 Extraspinal veins, 754  
*Extremitas acromialis [clavicula]*, 303  
*sternalis [clavicula]*, 303  
 Extremity of penis, 1239  
 Extrinsic muscles of tongue, 1129  
 Eye, 1017  
 Eyeball or bulb of eye, 1017  
 accessory organs of, 1034  
 applied anatomy of, 1031  
 aqueous humor, 1030  
 capsule of Ténon, 1037  
 chambers of, 1024  
 choroid, 1021  
 ciliary body, 1023  
 muscle, 1023  
 processes, 1023  
 conjunctiva, 1040  
 cornea, 1018  
 crystalline lens, 1030  
 development of, 134  
 fascia bulbi, 1037  
 fibrous tunic, 1017  
 hyaloid membrane, 1030  
 iris, 1024  
*membrana pupillaris*, 136  
*orbiculus ciliaris*, 1023  
 pupil, 1024  
 refracting media, 1030  
 retina, 1026  
 pigmented layer of, 1027  
 proper, 1027  
 supporting frame-work of, 1029  
 sclera, 1017  
 tunics of, 1017  
 vascular, 1021  
 uvea, 1025  
 vessels and nerves of, 1031  
 vitreous body, 1030  
 Eyebrows, 1038  
 Eyelashes, 1038  
 Eyelids, 1038  
 applied anatomy of, 1042  
 canthus of, 1038  
 development of, 137  
 muscles of, dissection of, 467  
 structure of, 1039  
 surface anatomy of, 1287  
 tarsal of, 1039  
 Eye-teeth, 1118

**F**

**FACE**, bones of, 255  
 development of, 111  
 lymphatics of, 774  
 surface anatomy of, 1282  
**Facial artery**, 633  
   transverse, 638  
 bones, 255  
 canal, 241  
   hiatus of, 241  
   prominence of, 1052  
 lymph glands, 775  
 nerve, 929  
   applied anatomy of, 933  
 vein, anterior, 733  
   applied anatomy of, 733  
   common, 733  
   deep, 733  
   posterior, 734  
   transverse, 734  
**Falciform ligament of liver**, 1150  
   1195  
   margin of fossa ovalis, 564  
   process of sacrotuberous ligament, 405  
**Fallopian tubes**, 1247  
**Fallopian aqueduct of**, prominence of, 1051  
**False ligaments of bladder**, 1221  
   pelvis, 340  
   ribs, 220  
   vocal cords, 1085  
**Falx aponeurotica inguinalis**, 505  
**cerebelli**, 900  
**cerebri**, 900  
**Fascia or Fasciæ**, 463  
   of abdomen, 498  
   triangular, 502  
   anal, 511  
   of ankle, 584  
   antibrachial, 536  
   antibrachii, 536  
   of arm, 534  
   axillary, 526  
   bicipital, 535  
   brachial, 534  
   brachii, 534  
   bucopharyngeal, 477  
   bulbi, 1037  
   of Camper, 498  
   cervical, 475, 476  
   clavicular, 528  
   of Colles, 337, 499, 517  
   colli, 476  
   applied anatomy of, 478  
   coracoclavicular, 528  
   coracoclavicularis, 528  
   cremasteric, 504  
   cribrosa, 563  
   cruris, 576  
   deep, 464  
   of deltoideus, 530  
   dentata hippocampi, 875  
   diaphragmatic part of pelvic, 511  
   dorsal, of foot, 586  
   endopelvic, 512  
   of forearm, 536  
   general description of, 463  
   of hand, 546  
   iliaca, 560  
   iliopectineal, 560  
   infrapinnata, 533  
   infrapinnatus, 533  
   infundibuliform, 508  
   intercolumnar, 1229  
   intercostal, 492  
   intercural, 501  
   lata, 563  
   falciform margin of, 564  
   fossa ovalis of, 564  
   iliotibial tract or band of, 563  
   of leg, 576  
   deep transverse, 580

**Fascia or Fasciæ**, lumbar, 486  
 masseteric, 472  
 of obturator internus, 510  
 orbital, 1038  
 palmar, 550  
 parotideomasseteric, 472  
 pectoral, 526  
 pelvic, 510  
 plantar, 586  
 pretracheal, 477  
 prevertebral, 477  
 propria of femoral hernia, 1189  
 of piriformis, 511  
 of psoas and iliacus, 559  
 of quadratus lumborum, 510  
 rectal, 518  
 rectovesical, 512  
 renal, 1209  
 of Scarpa, 499  
 Sibson's, 1096  
 spermatic, external, 501, 1229  
 subscapular, 531  
 subscapularis, 531  
 superficial, 463  
 supraspinata, 532  
 supraspinatus, 532  
 temporal, 473  
 of thigh, 562  
 of thoracic region, 526  
 transversalis, 508  
 triangular, of abdomen, 502  
 of upper extremity, 522  
 of urogenital diaphragm, 519, 520, 521  
   region, 517  
   vesical, 512  
**Fasciculi**, intrafusal, 1071  
 longitudinales, 834  
**Fasciculus**, anterior proper, 815  
 cerebelloolivary, 830  
 cerebellospinal, 816, 828  
 cerebroolivary, 830  
 cerebrospinal, 815  
 cerebrospinalis anterior, 815  
   lateralis, 815  
   comma-shaped, 817  
   cornucommissural, 817  
   cuneatus, 817  
   gracilis, 817  
   lateral proper, 817  
   lateralis proprius, 817  
   of Lissauer, 817  
   longitudinal, inferior, 891  
   medial, 851  
   posterior, 851  
   superior, 891  
 occipitofrontal, 891  
 olfactory, 887  
 olivospinal, 816  
 perpendicular, 891  
 retroflexus of Meynert, 859  
 rubrospinal, 816  
 secondary sensory, 817  
 solitarius, 833  
 spinocerebellar, 816  
   ventral, 817  
 spinoolivary, 830  
 spinotectal, 817  
 spinothalamic, 817  
 superficial antero-lateral, 816  
 tectospinal, 815, 816  
 thalamomamillary, 886  
 uncinate, 890  
 vestibulospinal, 815  
**Fasciola cinerea**, 875  
**Fat or adipose tissue**, 42  
 cells, 42  
**Fauces**, arches or pillars of, 1112  
 isthmus of, 1112  
**Female genital organs**, 1243  
   bulb of vestibule, 1256  
   carunculae hymeneales, 1257  
   clitoris, 1257  
   development of, 180

**Female genital organs**, epo-  
 ophoron, 1244  
 fourchette, 1257  
 glands of Bartholin, 1258  
   greater vestibular, 1257  
 hymen, 1257  
 labia majora, 1256  
   minora, 1257  
 mons pubis, 1256  
 navicular fossa, 1257  
 ovaries, 1243  
 uterine tubes, 1247  
 uterus or womb, 1248  
 vagina, 1255  
 vestibule, 1257  
 pronucleus, 80  
 urethra, 1228  
**Femoral artery**, 710  
   applied anatomy of, 715  
   branches of, 715  
   deep, 716  
   peculiarities of, 714  
   surface marking of, 1331  
 canal, 712  
 circumflex arteries, 716, 717  
 cutaneous nerve, anterior, 981  
   lateral, 977  
   posterior, 985  
 fossa, 712  
 fovea, 1187  
 hernia, 1189  
 muscles, medial, dissection of, 567  
   posterior, dissection of, 594  
 nerve, 980  
   applied anatomy of, 992  
 ring, 712  
 septum, 712  
 sheath, 710  
 triangle, 565, 712  
 vein, 758  
**Femur**, 345  
   applied anatomy of, 352  
   articulations of, 352  
   condyles of, 349  
   head of, 345  
   neck of, 345  
   ossification of, 352  
   spiral line of, 348  
   structure of, 350  
   surface anatomy of, 1324  
   trochanters of, 346, 347  
**Fenestra cochleæ**, 1051  
 ovalis, 1051  
 rotunda, 1051  
 vestibuli, 1051  
**Fenestrated membrane of Henle**, 44  
**Fertilization of ovum**, 82  
**Fetal heart**, peculiarities of, 161  
 membranes, 93  
**Fetus**, circulation in, 616  
 foramen ovale in, 149, 616  
 valve of inferior vena cava in, 616  
 vascular system in, peculiarities of, 615  
**Fibræ intercrurales**, 501  
 pontis profundæ, 834  
 superficiales, 834  
 propriæ [cerebellum], 842  
**Fibre cells**, contractile, 68  
**Fibres**, arcuate, 831  
 dental, 1120  
 intercolumnar, 501  
 intercrural, 501  
 intrafusal, 1071  
 of muscles, 64  
 nerve, 70  
 of Purkinje, 69  
 of Remak, 76  
 sustentacular, of Müller, 1029  
 of Tomes, 1120  
**Fibrocartilage**, 49  
 circumferential, 50



- Fibrocartilage, connecting, 50  
interarticular, 49  
intervertebral, 385  
semilunar, of knee, 442  
stratiform, 50  
yellow or elastic, 50
- Fibrocartilaginous lamina, interpubic, 407
- Fibrous capsule of Glisson, 1196  
pericardium, 601  
rings of heart, 613  
sheaths of flexor tendons of fingers, 540  
of toes, 588  
tissue, white, 43  
tunic of kidney, 1210
- Fibula, 359  
applied anatomy of, 361  
articulations of, 361  
ossification of, 361  
surface form of, 1324
- Fibular artery, 723  
collateral ligament of knee-joint, 440
- Fifth metacarpal bone, 330  
metatarsal bone, 372  
nerve, 914  
ventricle, 887
- Filiform papillae of tongue, 1128
- Fillet, 852  
lateral, 853  
mesial, 853
- Filtration angle of eye, 1019
- Filum terminale*, 807
- Fimbria hippocampi*, 887  
ovarian, 1247
- Fimbriae of uterine tube, 1247
- Fimbriodentate fissure, 875, 887
- First cuneiform bone, 369  
dorsal metacarpal artery, 678  
metatarsal artery, 724  
metacarpal bone, 329  
metatarsal bone, 371  
nerve, 908
- Fissura antitragohelicina*, 1044  
*calcarina*, 869  
*cerebri lateralis* [*Sylvii*], 867  
*longitudinalis*, 865  
*collateralis*, 869  
*hippocampi*, 874  
*mediana anterior* [medullae oblongatae], 822  
spinalis], 808  
*posterior* [medullae oblongatae], 822  
*parietooccipitalis*, 868  
*petrotympanica*, 1049  
*prima* [cerebellum], 124  
[rhinencephalon], 875  
*secunda* [cerebellum], 124
- Fissure or Fissures, anterior median of medulla spinalis, 808  
callosomarginal, 869  
central, 868  
of cerebellum, 837, 838  
development of, 125  
floccular, 125  
horizontal, 837  
postcentral, 838  
postnodular, 838  
postpyramidal, 839  
precentral, 838  
preclival, 838  
prepyramidal, 838  
of cerebrum, 867  
calcarine, 869  
callosal, 873, 876  
collateral, 869  
development of, 131  
external rhinal, 128  
fimbriodentate, 875, 887  
hippocampal, 130, 814  
interlobular, 867  
lateral, 130, 867  
longitudinal, 865
- Fissure or Fissures of cerebrum, parietooccipital, 868  
of Rolando, 868  
of Sylvius, 867  
transverse, 889  
choroidal, 135, 888  
circuminsular, 869  
congenital, of cranium, 255  
dentate, 874  
Glaserian, 238, 1040  
of liver, longitudinal, 1194  
transverse, 1194  
longitudinal, great, 865  
of lungs, 1104  
of medulla oblongata, 822  
orbital, inferior, 284, 288  
superior, 249, 288, 290  
petrooccipital, 280, 291  
petrosphenoidal, 280  
petrotympanic, 238, 280, 1049  
pterygoid, 250  
pterygomaxillary, 284  
of Rolando, 868  
sphenomaxillary, 284  
of Sylvius, 867  
tympanomastoid, 280  
vestibular, 1060
- Fixation of kidney, 1209  
of muscles, 462
- Flat bones, 196
- Flechsigs, cerebellar tract of, 816, 828  
oval area of, 818
- Flexor accessorius muscle, 589  
brevis minimi digiti muscle, 554, 590  
carpi radialis muscle, 537  
ulnaris muscle, 538  
digiti quinti brevis muscle of foot, 590  
of hand, 554  
digitorum brevis muscle, 588  
longus muscle, 581  
profundus muscle, 540  
sublimis muscle, 539  
hallucis brevis muscle, 589  
longus muscle, 581  
pollicis brevis muscle, 553  
longus muscle, 540
- Flexure, cervical, 121  
colic, left, 1180  
right, 1180  
hepatic, 1180  
pontine, 121  
splenic, 1180  
ventral cephalic, 121
- Floating ribs, 221
- Floccular fissure, 125
- Flocculus, 839
- Floor of fourth ventricle, 847
- Floor-plate, 117
- Fluid, cerebrospinal, 905
- Fluids, circulating, 61
- Fold or Folds, amniotic, 96  
aryepiglottic, 1085  
caudal, 92  
cephalic, 92  
duodenojejunal, 1159  
epigastric, 1187  
gastropancreatic, 1156  
glossoepiglottic, 1082, 1126  
ileoceclic, 1160  
malleolar, 1050  
rectouterine, 1250  
sacrogenital, 1153, 1250  
salpingopalatine, 1139  
salpingopharyngeal, 1139  
transverse, of rectum, 1183  
of Treves, 1160  
umbilical, 1187, 1221, 1222  
ventricular, of larynx, 1085  
vestigial, of Marshall, 159, 603  
vocal, of larynx, 1086
- Folium cacuminis*, 838  
*vermis*, 838
- Follicle of hair, 1076
- Follicles, agminated, 1175  
Graafian, or vesicular ovarian, 1245
- Fontana, spaces of, 1021
- Fontanelles, 294
- Foot, arches of, 459  
fascia of, 586  
muscles of, 586  
dissection of, 587, 588  
ossification of bones of, 374  
phalanges of, articulations of, 459  
skeleton of, 362  
applied anatomy of, 375  
surface anatomy of, 1325
- Foramen, caroticoclinoid, 249, 290  
cecum of frontal bone, 235  
of medulla oblongata, 822  
of tongue, 165, 1126  
condyloid, anterior, 229  
epiploicum, 170, 1155  
of Huschke, 244, 245  
incisive, 261, 278  
infraorbital, 257, 286  
interventricular, 865, 887  
intervertebral, 197  
jugular, 280, 291  
lacerum, 280, 291  
magnum, 227, 230, 288, 291  
Majendii, 847  
mandibular, 272  
mastoid, 239, 282  
mental, 271, 286  
of Monro, 865, 887  
obturator, 339  
optic, 246, 250, 290  
ovale of heart, 149, 616  
of sphenoid, 248, 280, 291  
palatine, 278  
parietal, 277  
rotundum, 248, 291  
sciatic, 406  
singulare, 242  
sphenopalatine, 267  
spinous, 248, 280, 291  
sternal, 220  
stylomastoid, 243, 280  
supraorbital, 235, 286, 288  
supratrochlear, 313  
thyroid, 339  
transversarium, 198  
vena-caval, 497  
vertebral, 197  
Vesalii, 248, 291  
of Winslow, 170, 689, 1155  
zygomatofacial, 263, 286  
zygomatocorbital, 264  
zygomatocotemporal, 263, 282
- Foramina, ethmoidal, 287  
intervertebral, 197  
for olfactory nerves, 252  
in roof of fourth ventricle, 847  
sacral, 206, 208  
of Scarpa, 261, 278  
of Stensen, 261, 278  
Thebesii, 608  
*venarum minimarum*, 608
- Forceps, anterior, 877  
posterior, 877
- Forearm, fascia of, 536,  
muscles of, 536  
dissection of, 536, 539, 542
- Forebrain, 90, 125, 855
- Foregut, 92, 162
- Foreskin, 1239
- Form of embryo at different stages, 191
- Formatio grisea*, 833  
of medulla spinalis, 809  
*reticularis alba*, 833
- Fornicolumns, 886
- Fornix of brain, 885  
body of, 886  
columns of, 886

- Fornix of brain, crura of, 887  
 development of, 131  
 pillars of, 886, 887  
 of conjunctiva, 1041
- Fossa or Fossæ, acetabular, 339  
 anticubital, 672  
 canine, 257  
 cecal, 1159, 1160  
 cochlearis, 1058  
 condyloid, 230, 281  
 coronoid, 313  
*cranii anterior*, 288  
   *media*, 290  
   *posterior*, 291  
 digastric, 239  
 digital, of epididymis, 1231  
   of femur, 347  
 for ductus venosus, 1194  
 duodenal, 1158  
 duodenojejunal, 1159  
 femoral, 712  
 for gall-bladder, 1194  
 glenoid, 238  
 hyaloid, 1030  
 hypophyseos, 246, 290  
 ileocecal, 1159, 1160  
 iliac, 335  
 incisive, 256, 271  
 incudis, 1052  
 for inferior vena cava, 1194  
 infraspinal, 305  
 infratemporal, 283  
*infratemporalis*, 283  
 intercondyloid, of femur, 349  
   of tibia, 356  
 interpeduncular, 848, 865  
 intersigmoid, 1160  
 ischiorectal, 515  
*ischiorectalis*, 515  
 jugular, 243  
 lacrimal, 235, 286  
 of liver, 1194  
 mandibular, 238, 280, 283  
 mastoid, 238  
 nasal, 1010  
*navicularis* [urethra], 1226  
   [vulva], 1257  
 occipital, inferior, 292  
 olecranon, 313  
 ovalis of fascia lata, 564  
   of heart, 608  
 ovarian, 1154, 1244  
 pararectal, 1153  
 paravesical, 1153  
 pericecal, 1159  
 peritoneal, 1157  
 popliteal, 718  
 pterygoid, 250  
*pterygopalatina*, 284  
*pterygopalatine*, 284  
 radial, 312  
 retrocecal, 1160  
 retroperitoneal, 1157  
 rhomboid, 847  
*rhomboidea*, 847  
 of Rosenmüller, 1138, 1139  
*sagittalis sinistra* [liver], 1194  
 scaphoid, 250, 278  
 of skull, anterior, 288  
   middle, 290  
   posterior, 291  
 sphenomaxillary, 284  
 subarcuate, 242  
 subscapular, 304  
 supraspinatous, 305  
 supratonsillar, 1139  
 Sylvian, 131  
 temporal, 282  
*temporalis*, 282  
*triangularis*, 1044  
 trochanteric, 347  
 for umbilical vein, 1194  
*venae cavae*, 1194  
 vermian, 228  
*vesicae felleae*, 1194
- Fossa or Fossæ, zygomatic, 272
- Fountain decussation of Meynert, 854
- Fourchette, 1257
- Fourth metacarpal bone, 330  
 metatarsal bone, 372  
 nerve, 913  
 ventricle, 845  
   floor of, 847
- Fovea capitis femoris*, 345  
*centralis retinae*, 1026, 1029  
   structure of, 1029  
*dentis*, 199  
 femoral, 1187  
 inguinal, 1187  
 of rhomboid fossa, 848  
 supravesical, 1187  
 trochlear, 235, 286
- Foveolæ, Howship's, 52
- Fracture of bones of foot, 375  
   of hand, 332  
   of clavicle, 303  
   of femur, 353, 592  
   of fibula, 593  
   of humerus, 313, 557  
   of mandible, 300  
   of maxilla, 300  
   of nasal bone, 300  
   of olecranon, 321, 558  
   of patella, 355, 593  
   of pelvis, 344  
   Pott's, 593  
   of radius, 321, 558  
   of ribs, 225  
   of scapula, 309  
   of skull, 297  
   of sternum, 225  
   of tibia, 361, 593  
   of ulna, 321, 558  
   of zygomatic arch, 300
- Free nerve-endings, 1069
- Freely movable joints, 381
- Frenula of colic valve, 1179  
 of lips, 1110
- Frenulum of clitoris, 1257  
 of labia minora, 1257  
 linguae, 1126  
 of prepuce, 1239  
 veli, 853
- Frontal air sinuses, 235, 1014  
 artery, 650  
 bone, 233  
   articulations of, 237  
   orbital or horizontal part of, 235  
   ossification of, 237  
   squama of, 234  
   structure of, 236  
 convolution, ascending, 869  
 crest, 235  
 eminences, 234, 278, 282  
 gyri, 869, 870  
 lobe, 869  
 nerve, 916  
 operculum, 873  
 process of maxilla, 260  
 sulci, 869  
 suture, 234, 278  
 vein, 732
- Frontoethmoidal suture, 288
- Frontomaxillary suture, 287
- Frontonasal duct, 236  
 process, 111
- Frontopontine fibres, 850
- Frontosphenoidal process of zygomatic bone, 264
- Fundiform ligament of penis, 1239
- Fundus glands of stomach, 1163  
 tympani, 1049  
 of uterus, 1249
- Fungiform papillæ of tongue, 1128
- Funiculi of medulla spinalis, 814, 815
- Funiculus separans*, 848  
*spermaticus*, 1229
- Furcal nerve, 975
- Furcula, 164, 177
- Furrow, chordal, 91  
 dental, 1122  
 iliac, 1213  
 nasoöptic, 112, 137  
 sternal, 1208
- Furrowed band of cerebellum, 839
- Fusiform gyrus, 871, 872

## G

- Galea aponeurotica*, 466
- Galen, veins of, 740
- Gall-bladder, 1199  
 applied anatomy of, 1201  
 fossa for, 1194  
 lymphatic vessels of, 793  
 structure of, 1199
- Gangliated cord, 995
- Ganglion or Ganglia, 803  
 aorticorenal, 1003  
 cardiac, of Wrisberg, 1002  
 carotid, 996  
 cervical, 997, 998  
*cervicale inferius*, 998  
   *medium*, 997  
   *superius*, 997  
*ciliare*, 917  
 ciliary, 917  
 coeliac, 1002  
*coeliaca*, 1002  
 collateral, 995  
 of Corti, 1060, 1068  
 Gasserian, 914  
 genicular, 930  
*geniculi*, 930  
 of glossopharyngeal, 937  
*habenulae*, 859  
 impar, 1001  
 inferior, 939  
 interpeduncular, 848, 851  
 jugular, 938, 941  
*jugulare*, 941  
 Langley's, 1138  
 lenticular, 917  
 Meckel's, 919  
*nodosum*, 941  
 ophthalmic, 917  
 otic, 924  
*oticum*, 924  
*petrosus*, 939  
 petrous, 939  
 phrenicum, 1004  
 ridge or neural crest, 88, 120  
 of Scarpa, 1068  
 semilunar, of abdomen, 1002  
   of trigeminal nerve, 914  
*semilunare* [Gasseri], 914  
*sphenopalatine*, 919  
*sphenopalatinum*, 919  
   *rami nasales posteriores inferiores*, 921  
   *superiores*, 921  
   *orbitales*, 920  
 spinal, 948  
*spinale*, 948  
 spiral, of cochlea, 1068  
 splanchnic, 999  
*submaxillare*, 925  
 submaxillary, 925  
 superior, of glossopharyngeal, 938  
   mesenteric, 1004  
   *superius*, 938  
   of vagus, 940  
   vestibular, 1068  
   of Wrisberg, 1002
- Ganglionic arterial system of brain, 654

- Ganglionic arteries, antero-lateral, 653  
     antero-medial, 652  
     postero-lateral, 662  
     postero-medial, 653, 662  
     layer of retina, 1028  
 Gärtner, duct of, 182, 1245  
 Gasserian ganglion, 914  
 Gaster, 1161  
 Gastric arteries, short, 691  
     artery, left, 688  
     right, 689  
     glands, 1166  
     impression, 1192  
     lymph glands, 788  
     nerves from vagus, 943  
     plexuses from sympathetic, 1004  
     from vagus, 943  
     veins, short, 766  
 Gastrocnemius muscle, 578  
 Gastrocolic ligament, 1152  
     omentum, 1157  
 Gastroduodenal artery, 690  
 Gastroepiploic arteries, 690, 691  
     veins, 766  
 Gastrohepatic omentum, 1156  
 Gastrolial ligament, 1155  
 Gastrophrenic ligament, 1163  
 Gemellus inferior muscle, 573  
     superior muscle, 573  
 General sensations, peripheral terminations of nerve of, 1069  
 Generation, development of external organs of, 190  
 Genicular arteries, 718, 720, 721  
 ganglion of facial nerve, 930  
 Genuiculate bodies, 858  
 Geniculum of facial nerve, 930  
     of internal capsule, 883  
 Genioglossus muscle, 1129  
 Geniohyoglossus muscle, 1129  
 Geniohyoid muscle, 481  
 Geniohyoideus muscle, 481  
     dissection of, 481  
 Genital cord, 184  
     corpuscles, 1069  
     organs of female, 1243  
         external, 1256  
         of male, 1228  
     glands, 184  
     ridge, 184  
     swellings, 190  
     tubercle, 190  
 Genitocrural nerve, 977  
 Genitofemoral nerve, 977,  
 Gennari, band of, 891, 893  
 Genu of corpus callosum, 876  
     of internal capsule, 883  
 Gerlach, tube tonsil of, 1053  
 Germ, dental, 1121, 1122  
 Germ centres, 77  
 Germinal cells, 77  
     epithelium, 184, 1245  
     path, 185  
     spot, 77  
     vesicle, 77  
 Giacomini, band of, 875  
 Giant cells, 51  
     of Betz, 891  
 Gianuzzi, crescents of, 1137  
 Gimbernat's ligament, 502  
*Gingivae*, 1111  
 Ginglymus, 382  
 Giraldès, organ of, 1236  
 Girdle of inferior extremity, 301  
     pelvic, 301  
     shoulder, 301  
     of superior extremity, 301  
 Glabella, 234, 278, 296  
 Gladiolus, 218  
 Gland or Glands, accessory, of  
     mouth, 1138  
     part of parotid, 1134  
     anterior lingual, 1131  
     arytenoid, 1091  
     of Bartholin, 1258  
     of Blandin, 1131  
     of Bowman, 1012  
     Brunner's, 1175  
     buccal, 1111  
     bulbourethral, 1243  
     carotid, 1273  
     ceruminous, 1047  
     ciliary, 1039  
     coccygeal, 1273  
     Cowper's, 1243  
     ductless, 1260  
     duodenal, 1175  
     gastric, 1166  
     genital, 184  
     intestinal, 1174  
     labial, 1110  
     lacrimal, 1041  
     of larynx, 1090  
     lenticular, of stomach, 1166  
     of Littre, 1226  
     Luschka's, 1273  
     mammary, 1258  
     Meibomian, 1040  
     molar, 1111  
     of Nuhn, 1131  
     oesophageal, 1146  
     palatal, 1112  
     parathyroid, 1263  
     parotid, 1133  
     Peyer's, 1175  
     preputial, 1239  
     prostate, 1241  
     salivary, 1133  
     sebaceous, 1078  
     solitary, 1175  
     sublingual, 1137  
     submaxillary, 1135  
     sudoriferous, 1078  
     suprarenal, 1270  
     sweat, 1078  
     tarsal, 1040  
     thymus, 1264  
     thyroid, 1261  
     of tongue, 1131  
     trachoma, 1041  
     urethral, 1226  
     uterine, 1252  
     vestibular, greater, 1258  
*Glandula lacrimalis*, 1041  
     *sublingualis*, 1137  
     *submaxillaris*, 1135  
     *thyroidea*, 1261  
     *vestibularis major* [Bartholini], 1258  
*Glandulae bulbourethrales*, 1243  
     *duodenales* [Brunneri], 1175  
     *intestinales* [Lieberkuhni], 1174  
     *labiales*, 1110  
     *oesophageae*, 1146  
     Pacchioni, 905  
     *parotis*, 1133  
     *sebaceae*, 1078  
     *sudoriferae*, 1078  
     *suprarenales accessoriae*, 1271  
     *suprarenalis*, 1270  
     *tarsales* [Meibomi], 1040  
     *thyroideae accessoriae*, 1262  
 Glandular epithelium, 37  
*Glans clitoridis*, 1257  
     *penis*, 1238  
 Glaserian fissure, 238, 1049  
 Glenohumeral ligaments, 415  
 Glenoid cavity, 307  
     fossa, 238  
     ligament of Cruveilhier, 430, 459  
     of shoulder, 415  
 Glenoidal labrum of hip-joint, 434  
     of shoulder-joint, 415  
 Gliding joints, 382  
 Gliding movement, 383  
 Glisson's capsule, 1156, 1196  
 Globular processes of His, 111  
*Globus major* [epididymis], 1231  
     *minor* [epididymis], 1231  
     *pallidus*, 882  
*Glomera carotica*, 1273  
*Glomus coccygeum*, 1273  
 Glossoepiglottic folds, 1082, 1126  
 Glossopalatine arch, 1112  
 Glossopalatinus muscle, 1114,  
     1129 *note*  
 Glossopharyngeal nerve, 937  
*Glottis respiratoria*, 1087  
     *vocalis*, 1087  
     rima of, 1087  
 Gluteus maximus muscle, 569  
     medius muscle, 570  
     minimus muscle, 570  
 Gluteal artery, inferior, 706  
     superior, 707  
     lines of ilium, 333  
     muscles, 569  
     nerve, inferior, 985  
     superior, 984  
     region, muscles of, dissection  
         of, 569, 572  
     tuberosity, 348  
     veins, 760  
 Gnathic index, 296  
 Goblet cells, 37  
 Golgi, cells of, 892  
     organs of, 1070  
 Golgi and Mazzoni, corpuscles of, 1069  
 Goll, tract of, 808, 817  
 Gomphosis, 381  
 Gonion, 296  
 Gower's, tract of, 816  
 Graafian follicles, 1245  
     structure of, 1245  
 Gracile nucleus, 824  
 Gracilis muscle, 567  
 Grandry, tactile corpuscles of, 1069  
 Granular layer of dentin, 1119  
*Granulationes arachnoideales*, 905  
 Granulations, arachnoid, 905  
 Granule cells, 41  
 Gray commissure of brain, 856  
     commissures of medulla spinalis, 810  
     or gelatinous nerve fibres, 76  
     substance of cerebellum, 842  
     of cerebral hemispheres, 891  
     of medulla oblongata, 829  
     spinalis, 809  
 Great auricular nerve, 956  
     cardiac nerve, 997  
     vein, 730  
     cerebral vein, 740  
     longitudinal fissure, 865  
     omentum, 1157  
     sacrosciatic ligament, 404  
     saphenous vein, 656  
     splanchnic nerve, 998  
     transverse fissure of brain, 889  
     wings of sphenoid, 248  
 Greater cavernous nerve, 1005  
     curvature of stomach, 1162  
     multangular bone, 326  
     occipital nerve, 951  
     omentum, 1157  
     palatine foramen, 278  
     pelvis, 340  
     peritoneal sac, 1150  
     sciatic foramen, 406  
     notch, 336  
     sigmoid cavity, 315  
     superficial petrosal nerve, 919, 931  
     trochanter, 347  
     vestibular glands, 190, 1258  
 Groove, atrioventricular, 604  
     auriculoventricular, 604

Groove, bicipital, 311  
 carotid, 247, 290  
 chiasmatic, 246, 290  
 costal, 222  
 infraorbital, 258  
 interatrial, 604  
 intertubercular, of humerus, 311  
 lacrimal, 258, 287  
 musculospiral, 311  
 mylohyoid, 272  
 neural, 88  
 obturator, 339  
 occipital, 239  
 optic, 246  
 primitive, 86  
 pterygopalatine, 250  
 for radial nerve, 311  
 vertebral, 214  
*Gubernaculum dentis*, 1124  
*testis*, 186  
 Gudden, commissure of, 909  
 Gullet, 1140  
 Gums, 1111  
     applied anatomy of, 1112  
 Gustatory calyculi, 1007  
     cells, 1007  
     hair, 1008  
     pore, 1007  
 Gyre, medifrontal, 870  
     precentral, 869  
     subfrontal, 870  
     superfrontal, 869  
 Gyri of brain, 869  
     angular, 871  
     of Broca, 870  
     central, anterior, 869  
         posterior, 871  
     cingulate, 874  
     cuneus, 871  
     dentate, 875  
     frontal, 869, 870  
     fusiform, 871, 872  
     hippocampal, 874  
     of insula, 873  
     of limbic lobe, 873  
     lingual, 871  
     occipital, 871  
     orbital, 870  
     precuneus, 871  
     quadrate, 871  
     straight, 870  
     subcallosal, 875  
     superior parietal lobule, 871  
     supracallosal, 875  
     supramarginal, 871  
     temporal, 872  
         transverse, of Heschl, 872  
     uncus, 874  
*Gyrus centralis anterior*, 869  
     posterior, 871  
     cinguli, 873  
     dentatus, 875  
     epicallosus, 875  
*frontalis inferior*, 870  
     medius, 870  
     superior, 869  
*hippocampi*, 874  
     marginal, 870  
     subcallosus, 875

H

HABENULAR commissure, 859  
 Hair cells of spiral organ of Corti, 1067  
 Hairs, 1075  
     cuticle of, 1077  
     follicle of, 1076  
     gustatory, 1076  
     olfactory, 1076  
     roots of, 1076  
     scapus or shaft, 1076  
     structure of, 1076  
 Haller, vas abe

Hamate bone, 328  
 Hamstring muscles, 574  
     tendons, applied anatomy of, 575  
 Hamulus of hamate bone, 328  
     lacrimal, 263  
     *laminae spiralis*, 1060  
     pterygoid, 250, 278  
 Hand, muscles of, 546  
     dissection of, 546  
     phalanges of, articulations of, 431  
     skeleton of, 323  
     surface anatomy of, 1315  
         markings of, 1318  
 Hard palate, 1112  
 Harrison's sulcus, 226  
 Hasner, plica lacrimalis of, 1042  
 Hassal, corpuscles of, 1265  
 Haversian canals of bone, 53  
     systems of bone, 53  
 Head, arteries of, 626  
     lymphatics of, 774  
     muscles of, 464  
     veins of, 732  
 Head-cap of spermatozoön, 81  
 Hearing, organ of, 1043  
 Heart, 603  
     applied anatomy of, 614  
     arteries of, 614  
     atrioventricular bundle of His, 614  
         node, 614  
     atrium, left, 610  
         right, 606  
     component parts of, 604  
     development of, 143-145  
     endocardium, 613  
     fibres of atria, 614  
         of ventricles, 614  
     fibrous rings of, 613  
     lymphatic vessels of, 798  
     nerves of, 615  
     sinoatrial node of, 614  
     size and weight of, 604  
     structure of, 613  
     surface marking of, 1299  
     *trigonum fibrosum*, 613  
     veins of, 730  
     ventricle, left, 611  
         right, 608  
 Heidenhain, demilunes of, 1137  
 Height index of skull, 296  
 Helicine arteries, 1240  
 Helicis major muscle, 1045  
     minor muscle, 1045  
 Helicotrema, 1060  
 Helix, 1044  
 Hemiazygos vein, 753  
     accessory, 753  
 Hemispheres, cerebellar, 836  
     cerebral, 865  
 Hemorrhoidal artery, inferior, 704  
     middle, 701  
     superior, 696  
     nerve, inferior, 991  
     plexuses of nerves, 1005  
     vein, middle, 760  
         superior, 766  
     venous plexus, 761  
         applied anatomy of, 761  
 Henle, loop of, 1212  
 Henle's layer of hair follicle, 1077  
 Hensen, canalis reuniens of, 1064  
     knot of, 86  
     lines of, 66  
     stripe of, 1067  
     supporting cells of, 1067  
*Hepar*, 1191  
     *fibrosa* [Glissoni], 1197

*Hepar, tunica serosa*, 1197  
 Hepatic artery, 689  
     branches of vagus nerve, 943  
     cells, 1197  
     cylinders, 174  
     duct, 1199  
     flexure of colon, 1180  
     lymph glands, 788  
     plexus, 1004  
     veins, 764  
 Hepatoduodenal ligament, 1151, 1156  
 Hepatogastric ligament, 1151, 1156  
 Hepatorenal ligament, 1151  
 Herbst, corpuscles of, 1069  
 Hernia, complete congenital, 1188  
     femoral, 1189  
     into funicular process, 1188  
     inguinal, 1187  
         direct, 1188  
         oblique, 1187  
     scrotal, 1187  
 Herophilus, torcular of, 743  
 Heschl, gyri of, 872  
 Hesselbach, interfoveolar ligament of, 505  
     triangle of, 1187, 1309  
 Hiatus, aortic, 495  
     of facial canal, 241  
     oesophageal, 496  
     semilunaris, 293, 1011  
 Higher or cortical visual centres, 864, 909  
 Highest intercostal artery, 666  
     veins, 753  
     nuchal line, 227  
     thoracic artery, 670  
 Highmore, antrum of, 259, 1015  
 Hilus of kidney, 1209  
     of lung, 1102  
     of spleen, 1266  
 Hind-brain, 122, 821  
 Hind-gut, 92, 162  
 Hinge-joint, 382  
 Hip bone, 333  
     articulations of, 340  
     ossification of, 340  
     structure of, 340  
     surface anatomy of, 1324  
 Hip-joint, 432  
     applied anatomy of, 437  
     movements of, 435  
     muscles in relation with, 435  
     surface marking of, 1330  
 Hippocampal commissure, 886  
     fissure, 130, 874  
     gyrus, 874  
 Hippocampus, 130, 880  
     major, 880  
 His, atrioventricular bundle of, 614  
     globular processes of, 111  
 Holoblastic ova, 84  
 Horizontal cells of retina, 1028  
     part of palatine bone, 266  
     semicircular canal, 1059  
     sulcus of cerebellum, 837  
 Houston's valves of rectum, 1188  
 Howship's foveolæ, 52  
 Hugnier, canal of, 238, 932  
 Humeral articulation, 411  
     applied anatomy  
         bursæ in relation  
         movements of, 411  
         vessels and nerv 1195  
     circumflex arterie  
 Humerus, 309 399  
     applied anatom of elbow-joint,  
     articulations of,  
     ossification of, 31, 426  
     structure of, 313  
     surface anatomy  
 Humor, aqueous synx, 1085  
 Hunter's canal

of, 1313  
 to, 315  
 es of, 416  
 s, 671, 672  
 of, 313  
 313  
 3  
 of, 1313  
 030





- Ligament or Ligaments, alar, 393**  
 of ankle, 450, 451  
 annular, of ankle, 584, 585  
 of radius, 422  
 of stapes, 1055  
 of wrist, 547, 550  
 anterior, 426  
 inferior, 448  
 longitudinal, 384  
 superior, 398, 448  
 apical odontoid, 393  
 arcuate, 495  
 atlantoaxial, 389  
 atlantooccipital, 392  
 membrane, posterior, 392  
 of auricle or pinna, 1044  
 of Bertin, 433  
 bifurcated, 454, 455  
 of Bigelow, 433  
 of bladder, 1221  
 broad, of uterus, 1250  
 calcaneoastragaloid, 452, 453  
 calcaneocuboid, 454  
 calcaneofibular, 451  
 calcaneonavicular, plantar, 455  
 calcaneotibial, 450  
 capsular. *See* Individual Joints.  
 caroticooclinoid, 251  
 carpometacarpal, 429  
 of carpus, 427, 428  
 central, of medulla spinalis, 907  
 check, 393  
 of eye, 1038  
 chondrosternal, 399  
 intra-articular, 400  
 chondroxipoid, 401  
 common, anterior, 384  
 posterior, 385  
 conoid, 412  
 of Cooper, 502  
 coracoacromial, 413  
 coracoclavicular, 412  
 coracohumeral, 415  
 coronary, of knee, 442  
 of liver, 1150, 1151, 1195  
 costoclavicular, 410  
 costocoracoid, 528  
 costotransverse, 397, 398  
 middle, 399  
 posterior, 399  
 costovertebral, anterior, 396  
 costoxipoid, 401  
 cotyloid, 339, 434  
 cricoarytenoid, posterior, 1084  
 cricotracheal, 1083  
 crucial, 441  
 cruciate, of atlas, 390  
 crural, 584  
 of knee, 441  
 cuboideonavicular, 457  
 cuneocuboid, 457  
 cuneonavicular, 455  
 deltoid, of ankle-joint, 450  
 dentate, 907  
 digital vaginal, 540  
 dorsal carpal, 550  
 radiocarpal, 425  
 radioulnar, 424  
 of elbow, 418, 419  
 falciform, of liver, 1150, 1195  
 fibular collateral, of knee-joint, 440  
 fundiform, of penis, 1239  
 gastrocolic, 1151  
 gastrolleinal, 1155  
 gastrophrenic, 1163  
 Gimbernat's, 502  
 glenohumeral, 415  
 glenoid, 414  
 of Cruveilhier, 430, 459  
 of shoulder-joint, 415  
 glenoidal labrum of hip-joint, 434  
 of shoulder-joint, 415  
 hepatoduodenal, 1151, 1156
- Ligament or Ligaments, hepato-**  
 gastric, 1151, 1156  
 hepatorenal, 1151, 1195  
 of Hesselbach, 505  
 of hip-joint, 432  
 hyoepiglottic, 1083  
 iliofemoral, 432  
 iliolumbar, 404  
 iliiochanteric, 433  
 of incus, 1055  
 inferior transverse of scapula, 413  
 infundibulopelvic, 1251  
 inguinal, 502  
 reflected, 502  
 interarticular, of ribs, 397  
 sternocostal, 400  
 intercarpal, 427  
 intercentral, 384  
 interchondral, 401  
 interclavicular, 410  
 interclinoid, 251  
 intercuneiform, 457  
 interfoveolar, 505  
 intermetacarpal, 430  
 intermetatarsal, 458  
 interosseous, 399  
 interphalangeal, 431, 459  
 interpubic fibrocartilaginous lamina, 407  
 interspinal, 387  
 interspinous, 387  
 intersternal, 401  
 intertarsal, 452  
 intertransverse, 387, 406  
 intra-articular, 397  
 ischiocapsular, 433  
 of knee-joint, 438  
 lacinate, 585  
 lacunar, 502  
 of larynx, 1082  
 lateral atlantooccipital, 392  
 external, 394, 419, 426  
 internal, 395, 418, 426  
 of uterus, 1250  
 left triangular, of liver, 1151  
 of left vena cava, 603  
 long plantar, 454  
 of Mackenrodt, 1251  
 of malleus, 1055  
 medial palpebral, 468  
 metacarpophalangeal, 430  
 metatarsophalangeal, 459  
 middle cricothyroid, 1083  
 mucosum, of knee, 443  
 of neck of rib, 399  
 nuchae, 387  
 oblique cord, 423  
 popliteal, 439  
 sacroiliac, 404  
 occipitoaxial, 393  
 odontoid, 393  
 orbicular, 422  
 of ovary, 1244  
 palmar, 427, 429  
 palpebral, 1039  
 pectinate, of iris, 1021  
 of pelvis, 404  
 phrenicocolic, 1157  
 phrenicolieneal, 1155  
 phrenicopericardiac, right, 762  
 of pinna or auricle, 1044  
 plantar, long, 454  
 posterior, 426  
 cricoarytenoid, 1084  
 inferior, 448  
 of knee, 439  
 longitudinal, 385  
 superior, 448  
 Poupart's, 502  
 pterygomandibular, 471  
 pterygospinous, 251, 477  
 pubic, 407  
 pubocapsular, 433  
 pubofemoral, 433
- Ligament or Ligaments, pulmo-**  
 nary, 1095, 1097  
 quadrate, 423  
 radial collateral, of elbow-joint, 419  
 of wrist-joint, 425  
 radiate, 396  
 sternocostal, 399  
 of radiocarpal joint, 425  
 radioulnar, 424  
 reflected inguinal, 502  
 rhomboid, 410  
 round, of liver, 1195  
 of uterus, 1251  
 sacrococcygeal, 406  
 sacroiliac, 404  
 sacrosclatic, 404, 405  
 sacrospinous, 405  
 sacrotuberous, 404  
 of scapula, 413  
 of shoulder-joint, 414  
 sphenomandibular, 395, 477  
 spinoglenoid, 413  
 spiral, of ductus cochlearis, 1064  
 stellate, 396  
 sternoclavicular, 410  
 sternocostal, 399  
 sternopericardiac, 602  
 of sternum, 400  
 structure of, 379  
 stylohyoid, 481  
 stylomandibular, 395, 477  
 subpubic, 407  
 superficial transverse of fingers, 551  
 superior transverse of scapula, 413  
 suprascapular, 413  
 supraspinal, 387  
 supraspinous, 387  
 suspensory, of axilla, 526  
 of eye, 1038  
 of lens, 1030  
 of liver, 1195  
 of mamma, 526  
 of ovary, 1244  
 of penis, 1239  
 talocalcaneal, 452, 453  
 talonavicular, dorsal, 454  
 talotibial, 450  
 tarsometatarsal, 457  
 of tarsus, 452  
 temporomandibular, 393  
 tendo oculi, 468  
 teres, of hip, 454  
 thyroarytenoid, inferior, 1086  
 thyroepiglottic, 1084  
 thyrohyoid, 1082, 1083  
 tibial collateral, of knee-joint, 439  
 tibiofibular, 448  
 tibionavicular, 450  
 transversalis colli/uteri, 1251  
 transverse acetabular, 434  
 of atlas, 389  
 carpal, 547  
 crural, 584  
 humeral, 415  
 inferior, 449  
 of knee, 442  
 metacarpal, 430  
 metatarsal, 458  
 of pelvis, 520  
 of scapula, 413  
 trapezoid, 412  
 triangular, of liver, 1195  
 of urethra, 519  
 of tubercle of rib, 399  
 ulnar collateral, of elbow-joint, 418  
 of wrist-joint, 426  
 uterosacral, 1250  
 of uterus, 1250  
 ventricular, of larynx, 1085

- Ligament or Ligaments of vertebrae**, 384  
 volar carpal, 547  
 metacarpophalangeal, 430  
 radiocarpal, 426  
 radioulnar, 424  
 of Wrisberg, 442  
 of wrist-joint, 425, 426  
 Y-shaped, of Bigelow, 433  
 of Zinn, 1035
- Ligamenta accessoria plantaria**, 459  
*alaris*, 393  
*auricularis* [Valsalva], 1044  
*basium* [oss. metacarp.] *dorsalis*, 430  
   *interossea*, 430  
   *volaria*, 430  
 [oss. metatars.] *dorsalis*, 458  
   *interossea*, 458  
   *plantaria*, 458  
*carpometacarpeae dorsalis*, 429  
   *volaria*, 429  
*collateralis*, 459  
*costoziphoidea*, 401  
*cruciata genu*, 441  
*cuneometatarsea interossea*, 458  
*intercarpea dorsalis*, 427  
   *interossea*, 427  
   *volaria*, 427  
*intercuneiformia interossea*, 457  
   *plantaria*, 457  
*interspinalia*, 387  
*intertransversaria*, 387  
*navicularicuneiformia dorsalis*, 456  
   *plantaria*, 456  
*ossiculorum auditus*, 1054  
*sternocostalis radiata*, 399  
*suspensoria* [of mamma], 526  
*tarsometatarsea dorsalis*, 457  
   *plantaria*, 458  
*vocales*, 1086
- Ligamentous action of muscles**, 383  
 applied anatomy of, 383
- Ligamentum acromioclaviculare**, 411  
*annulare baseos stapedis*, 1055  
   *radii*, 422  
*arcuatum pubis*, 407  
*arteriosum*, 621  
*bifurcatum*, 454  
*calcaneocuboideum dorsale*, 454  
   *plantare*, 454  
*calcaneofibulare*, 451  
*calcaneonaviculare plantare*, 455  
*capituli costae interarticulare*, 397  
   *radiatum*, 396  
*capitulorum* [oss. metacarpalium] *interosseum*, 430  
*carpi dorsale*, 550  
   *transversum*, 547  
*collaterale fibulare*, 440  
   *radiale*, 419, 426  
   *tibiale*, 439  
   *ulnare*, 418, 426  
*colli costae*, 399  
*conoidum*, 412  
*coracoclaviculare*, 413  
*coracohumerale*, 414  
*coronarium hepatis*, 1195  
*costoclaviculare*, 410  
*costotransversarium anterius*, 398  
   *posterius*, 398  
*cricoarytenoideum posterius*, 1084  
*cricothyreoideum medium*, 1083  
*cricotracheale*, 1083  
*cruciatum anterius*, 441  
   *posterius*, 441
- Ligamentum cuboideonaviculare dorsale**, 457  
   *plantare*, 457  
*delloideum*, 450  
*denticulatum*, 907  
*falciforme hepatis*, 1195  
*hyoepiglotticum*, 1083  
*hyothyreoideum laterale*, 1083  
   *medium*, 1082  
*iliofemorale*, 433  
*iliolumbale*, 404  
*incudis posterius*, 1055  
   *superius*, 1055  
*inguinale* [Pourpart], 502  
   *reflexum* [Collier], 502  
*interclaviculare*, 410  
*ischiocapsulare*, 433  
*lacunare* [Gimbernati], 502  
*latum pulmonis*, 1097  
   *uteri*, 1250  
*longitudinale anterius*, 384  
   *posterius*, 385  
*mallei anterius*, 1055  
   *laterale*, 1055  
   *superius*, 1055  
*malleoli lateralis anterius*, 448  
   *posterius*, 448  
*mucosum*, 443  
*nuchae*, 587  
*patellae*, 439  
*plantare longum*, 454  
*pophiteum obliquum*, 430  
*pubicum superius*, 407  
*pubocapsulare*, 433  
*pulmonale*, 1097  
*radiocarpeum dorsale*, 426  
   *volare*, 426  
*sacroccygeum anterius*, 406  
   *laterale*, 406  
   *posterius*, 406  
*sacroiliacum anterius*, 404  
   *interosseus*, 404  
   *posterius*, 404  
*sacrospinosum*, 405  
*sacrofibulare*, 404  
*sphenomandibulare*, 395  
*sternoclaviculare*, 410  
*sternocostale interarticulare*, 400  
*stylomandibulare*, 395  
*supraspinale*, 387  
*talocalcaneum anterius*, 452  
   *interosseum*, 453  
   *laterale*, 453  
   *mediale*, 453  
   *posterius*, 453  
*talofibulare anterius*, 450  
   *posterius*, 451  
*talonaviculare dorsale*, 454  
*temporomandibulare*, 394  
*teres femoris*, 434  
   *hepatis*, 1196  
   *uteri*, 1251  
*thyroepiglotticum*, 1084  
*transversalis colli uteri*, 1251  
*transversum acetabuli*, 434  
   *atlantis*, 389  
   *crus inferius*, 390  
   *superius*, 390  
*cruris*, 584  
*genu*, 442  
*scapulae inferius*, 413  
   *superius*, 413  
*trapezoideum*, 412  
*triangulare dextrum*, 1195  
   *sinistrum*, 1195  
*tuberculi costae*, 399  
*venosum*, 1196
- Ligature of arteries. See each Artery.**
- Ligulae**, 846
- Limbic lobe**, 873
- Limbs, development of**, 113
- Limbus fossae ovalis**, 608  
*laminae spiralis*, 1065
- Limiting membranes of retina**, 1029
- Line or Lines, arcuate, of ilium**, 335  
 colored, of Retzius, 1120  
 curved, of ilium, 333  
 gluteal, of ilium, 333  
 incremental, of Salter, 1120  
 intercondyloid, 350  
 intertrochanteric, 348  
 mylohyoid, 272  
 Nélaton's, 1239  
 nuchal, 227, 281  
 oblique, of fibula, 360  
   of mandible, 271  
   of radius, 320  
 pectineal, 348  
 popliteal, of tibia, 357  
 of Schreger, 1120  
 spiral, of femur, 348  
 temporal, 231, 235, 278, 282
- Linea alba**, 507  
*aspera*, 348  
*quadrata*, 348  
*semicircularis*, 507  
*splendens*, 907
- Lineae semilunares**, 507
- Lingua**, 1125  
*facies inferior*, 1126  
*tunica mucosa*, 1131
- Lingual artery**, 631  
 applied anatomy of, 632  
 deep, 632  
 bone, 275  
 branches of glossopharyngeal nerve, 939  
 gyrus, 871  
 lamina, 1121  
 lymph glands, 775  
 nerve, 923  
 tonsil, 1131  
 veins, 736
- Lingula of cerebellum**, 837  
 of mandibula, 272  
 of sphenoid, 247, 290
- Linin**, 34
- Lip, tympanic**, 1065  
 vestibular, 1065
- Lips**, 1110
- Liquor amnii**, 95  
 sanguinis, 61
- Lissauer, fasciculus of**, 817
- Littre, urethral glands of**, 1226
- Liver**, 1191  
 applied anatomy of, 1200  
 bare area of, 1151  
 bile ducts of, 1198  
   common, 1200  
 cystic duct, 1200  
 development of, 174  
 excretory apparatus of, 1198  
 fissures of, longitudinal, 1194  
 fossae of, 1194  
 gall-bladder, 1199  
 hepatic artery, 689, 1197  
   cells, 1197  
   duct, 1198  
   veins, 764  
 ligaments of, 1195  
 lobes of, 1194, 1195  
 lobules of, 1197  
 lymphatic vessels of, 792  
 nerves of, 1196  
 portal vein, 764, 1198  
 structure of, 1197  
 surface markings of, 1307  
 surfaces of, 1191  
 vessels of, 1196
- Lobe or Lobes, cacuminal**, 838  
 of cerebellum, 836  
 of cerebral hemisphere, 869  
   frontal, 869  
   insula, 873  
   limbic, 873  
   occipital, 871

- Lobe or Lobes of cerebral hemisphere, olfactory, 874**  
   parietal, 870  
   precuneus, 871  
   quadrate, 871  
   temporal, 871  
   of liver, 1194, 1195  
   of lung, 1105  
   nodular, 839  
   Spigelian, 1195  
   of thymus, 1264  
   of thyroid gland, 1261  
   tuberal, 839  
   uvular, 839
- Lobule of auricula, 1044**  
   paracentral, 870  
   parietal, 871  
   postero-inferior, 839  
   postero-superior, 838
- Lobules of liver, 1195**  
   of testes, 1232
- Lobuli glandulae thyroideae, 1261**  
   hepatis, 1197
- Lobulus centralis, 838**  
   parietalis inferior, 871  
   superior, 871  
   semilunaris inferior, 839  
   superior, 838
- Lobus caudatus, 1195**  
   clivi, 838  
   culminis, 838  
   frontalis, 869  
   hepatis dexter, 1194  
   sinister, 1195  
   noduli, 839  
   occipitalis, 871  
   olfactorius, 874  
   parietalis, 870  
   pyramidis, 839  
   quadratus, 1195  
   semilunaris, 838  
   temporalis, 871  
   tuberis, 839  
   uvulae, 839
- Localization, cerebral, 894**
- Lockwood, tendon of, 1035**
- Locus coeruleus, 848**
- Long bones, 195**  
   buccal nerve, 922  
   calcaneocuboid ligament, 454  
   ciliary nerves, 916  
   external lateral ligament, 440  
   or internal saphenous nerve, 981  
   root of ciliary ganglion, 916  
   saphenous nerve, 981  
   vein, 756  
   subscapular nerve, 961  
   thoracic artery, 671  
   nerve, 960
- Longissimus capitis muscle, 489**  
   cervicis muscle, 488  
   dorsi muscle, 488
- Longitudinal fasciculus, inferior, 891**  
   posterior, 851  
   superior, 891  
   fissure, cerebral, 865  
   great, 865  
   of liver, 1194  
   sinuses, 740, 741  
   striae, lateral and medial, 875  
   sulci of heart, 604
- Longitudinalis linguae inferior muscle, 1130**  
   superior muscle, 1130
- Longus capitis muscle, 484**  
   colli muscle, 403
- Loop of Henle, 1212**
- Löwenthal, cerebellospinal tract of, 815**
- Lower extremity, arteries of, 710**  
   articulations of, 432  
   bones of, 333  
   lymphatic vessels of, 782
- Lower extremity, muscles of, 559**  
   surface anatomy of, 1323  
   markings of, 1329  
   veins of, 755  
   jaw, bones of, 271  
   lateral cartilage, 1009  
   visual centres, 864, 909
- Lower, tubercle of, 608**
- Lumbar aponeurosis, 486**  
   arteries, 698  
   enlargement of medulla spinalis, 808  
   fascia, 486  
   lymph glands, 787  
   nerves, divisions of, anterior, 974  
   posterior, 953  
   plexus of nerves, 975  
   applied anatomy of, 992  
   regions of abdomen, 1147  
   triangle, 524  
   vein, ascending, 753, 763  
   veins, 763  
   vertebrae, 204
- Lumbocostal arch, 495**
- Lumbodorsal fascia, 486**
- Lumbosacral plexus, 974**  
   trunk, 975
- Lumbricales muscles of foot, 589**  
   of hand, 555
- Lunate bone, 323**  
   surface of acetabulum, 339
- Lung-buds, 177**
- Lungs, 1101**  
   applied anatomy of, 1108  
   development of, 177  
   fissures and lobes of, 1104  
   nerves of, 1107  
   root of, 1105  
   structure of, 1106  
   surface markings of, 1298  
   vessels of, 1107
- Lunulae of nails, 1075**  
   of semilunar valves, 610
- Luschka's gland, 1273**
- Luts, nucleus of, 860**
- Lymph, 64**  
   capillaries, 64  
   path, 770  
   sacs, 161  
   sinus, 770
- Lymph Gland or Glands of abdomen, 785**  
   aortic, 787  
   applied anatomy of, 770  
   auricular, 774, 775  
   axillary, 780  
   buccinator, 775  
   cervical, anterior, 778, 779  
   of Cloquet, 783  
   deltoideopectoral, 779  
   diaphragmatic, 797  
   epigastric, 786  
   facial, 775  
   deep, 775  
   gastric, 788  
   gastroepiploic, right, 788  
   of head, 774  
   hepatic, 788  
   hypogastric, 786  
   iliac, 786  
   ileocolic, 789  
   infraorbital, 775  
   inguinal, 783  
   applied anatomy of, 784  
   intercostal, 797  
   lingual, 775  
   of lower extremity, 782  
   lumbar, 787  
   mammary, internal, 796  
   mastoid, 774  
   maxillary, 775  
   mediastinal, 798  
   mesenteric, 789, 791  
   mesocolic, 789
- Lymph Gland or Glands of neck, 778**  
   obturator, 787  
   occipital, 774  
   pancreaticoduodenal, 792  
   pancreaticolienal, 768  
   pararectal, 791  
   paratracheal, 779  
   parietal of abdomen and pelvis, 786  
   parotid, 775  
   of pelvis, 785  
   popliteal, 782  
   applied anatomy of, 784  
   preauricular, 775  
   principal gland of tongue, 778  
   retropharyngeal, 776  
   of Rosenmüller, 783  
   sacral, 787  
   splenic, 788  
   Stahr, middle gland of, 778  
   sternal, 796  
   structure of, 769  
   sublingual, 783  
   submaxillary, 778  
   submental, 778  
   suprahoid, 778  
   supramandibular, 775  
   supratrochlear, 779  
   of thorax, 796  
   tibial, anterior, 782  
   tracheobronchial, 798  
   of upper extremity, 779, 780  
   visceral of abdomen and pelvis, 787
- Lymphatic duct, right, 772**  
   nodules, aggregated, 1175  
   solitary, 1175  
   of spleen, 1268  
   system, 768  
   trunk, bronchomediastinal, 798  
   intestinal, 772  
   jugular, 772, 773  
   lumbar, 772  
   subclavian, 772, 773  
   vessels, 768  
   of abdominal viscera, 791  
   wall, 787  
   of anal canal and anus, 792  
   applied anatomy of, 770  
   of auricula and external acoustic meatus, 776  
   of cecum, 792  
   of colon, 792  
   of common bile-duct, 793  
   development of, 161  
   of diaphragma, 798  
   of ductus deferens, 794  
   of duodenum, 792  
   of external genitals, 787  
   of face, 776  
   of gall-bladder, 793  
   of gluteal region, 784  
   of heart, 798  
   of ileum, 792  
   of jejunum, 792  
   of kidney, 793  
   lacteals, 768  
   of larynx, 779  
   of liver, 792  
   of lower extremity, 784  
   of lungs, 799  
   of mamma, 797  
   of mouth, 777  
   of nasal cavities, 776  
   of neck, 779  
   of oesophagus, 800  
   of ovary, 795  
   of palatine tonsil, 777  
   of pancreas, 793  
   of pelvis, 787  
   of perineum, 787  
   of pharynx, 779  
   of pleura, 800

- Lymphatic vessels of prostate,** 794  
 of rectum, 792  
 of reproductive organs, 794  
 of scalp, 776  
 of spleen, 793  
 of stomach, 792  
 structure of, 768  
 of suprarenal glands, 793  
 of testes, 794  
 of thoracic viscera, 799  
 wall, 797  
 of thymus, 800  
 of thyroid gland, 779  
 of tongue, 778  
 of upper extremity, 781  
 of ureter, 793  
 of urethra, 794  
 of urinary organs, 793  
 of uterine tubes, 795  
 of uterus, 795  
 of vagina, 795  
 of vermiform process, 792  
 of vesiculæ seminales, 795
- Lymphocyte,** 63
- Lymphoglandulae,** 768  
*auriculares anteriores,* 775  
*posteriores,* 774  
*axillares,* 780  
*cervicales profundae,* 778  
*superficiales,* 778  
*epigastricae,* 786  
*faciales profundae,* 775  
*gastricae inferiores,* 788  
*superiores,* 788  
*hepaticae,* 788  
*hypogastricae,* 786  
*inguinales,* 783  
*intercostales,* 797  
*linguales,* 775  
*lumbales,* 787  
*mediastinales anteriores,* 798  
*posteriores,* 798  
*mesentericae,* 789  
*mesocolicae,* 791  
*occipitales,* 774  
*pancreatocolicænales,* 788  
*popliteae,* 782  
*sternales,* 796  
*subinguinales profundae,* 783  
*superficiales,* 783  
*submaxillares,* 778  
*tibialis anterior,* 782
- Lymphoid tissue,** 45
- Lyra of fornix,** 886
- M**
- MACFARLANE, suprameatal triangle** of, 238
- Mackenrodt, ligament of,** 1251
- Macula acustica sacculi,** 1062  
*utriculi,* 1062  
*cribrosa media,* 1058  
*superior,* 1058  
*lutea,* 1026, 1029  
 structure of, 1029
- Majendie, foramen of,** 847, 905
- Malar bone,** 263  
 process of maxilla, 260
- Male genital organs,** 1228  
 bulbourethral glands, 190, 1243  
*ductus deferens,* 1235  
 ejaculatory duct, 1237  
 penis, 1237  
 prostate, 1241  
 testes and their coverings, 1228  
*vesiculæ seminales,* 1236  
 pronucleus, 83  
 urethra, 1225
- Malleolar arteries,** 723  
 internal, 727
- Malleolar folds, anterior and posterior,** 1050  
 sulcus, 360
- Malleolus, lateral,** 360  
 medial, 358, 359
- Malleus,** 1053  
 development of, 141  
 ligaments of, 1055
- Malpighian bodies of kidney,** 1212  
 of spleen, 1268  
 capsules of kidney, 1212  
 tufts of kidney, 1212
- Mamillary process,** 205
- Mammæ,** 1258  
 applied anatomy of, 1260  
 development of, 116  
 lymphatic vessels of, 797  
 nerves of, 1260  
 papilla or nipple of, 1258  
 structure of, 1258  
 vessels of, 1260
- Mammary artery, external,** 671  
 internal, 664  
 gland, 1258  
 internal, 796  
 veins, internal, 751
- Mandible,** 271  
 angle of, 273  
 articulations of, 274  
 body of, 271  
 changes in, due to age, 275  
 condyloid process of, 273  
 coronoid process of, 273  
 ossification of, 273  
 ramus of, 272
- Mandibula,** 271
- Mandibular arch,** 109,  
 branches of facial nerve, 933  
 canal, 273  
 foramen, 272  
 fossa, 238, 280, 283  
 nerve, 921  
 notch, 273
- Mantle layer,** 117
- Manubrium of malleus,** 1053  
 of sternum, 216
- Margin, supraorbital,** 234
- Marginal gyrus,** 870  
 layer, 117  
 veins of foot, 756
- Margins of heart,** 606
- Marrow of bone,** 51
- Marshall, oblique vein of,** 159, 603, 731  
 vestigial fold of, 159, 603, 731
- Martinotti, cells of,** 892,
- Massa intermedia,** 856, 865
- Masses, lateral, of atlas,** 200
- Masseter muscle,** 472
- Masseteric artery,** 641  
 fascia, 472  
 nerve, 921
- Mastoid canaliculus,** 243, 280  
 cells, 240  
 foramen, 239, 282  
 fossa, 238  
 glands, 774  
 notch, 239, 280  
 portion of temporal bone, 239  
 process, 239
- Mastzellen,** 41
- Matrix of nail,** 1075
- Maturation of ovum,** 79
- Maxilla,** 256  
 articulations of, 262  
 changes in, due to age, 262  
 ossification of, 262
- Maxillary artery, external,** 633  
 applied anatomy of, 635  
 peculiarities of, 635  
 internal, 638  
 glands, internal, 775  
 nerve, 917  
 inferior, 921
- Maxillary process of inferior nasa**  
 concha, 268  
 of palatine bone, 267  
 of zygomatic bone, 265  
 processes of fetus, 109  
 sinus, 259, 1015  
 tuberosity, 257  
 vein, internal, 734
- Meatus acusticus externa,** 1046  
*externus cartilagineus,* 1047  
*osseus,* 1047
- auditory, external,** 1046
- external acoustic,** 244, 283,  
 1046  
 applied anatomy of, 1048  
 internal, 244, 291  
 urinarius, 1226  
 urinary, 1257
- Meatuses of nose,** 293, 1010, 1011
- Mechanism of pelvis,** 408  
 of respiration, 497  
 of thorax, 401
- Meckel's cartilages,** 109, 273  
 diverticulum, 93, 1172  
 ganglion, 919
- Media, refracting, of bulb of eye,** 1030
- Medial geniculate body,** 858  
 longitudinal fasciculus, 851  
 wall of nasal cavity, 1012
- Median antibrachial vein,** 749  
 basilic vein, 747  
 nerve, 965
- Mediastinal arteries from aorta,** 685  
 from internal mammary, 664  
 cavity, 1098  
 anterior, 1100  
 applied anatomy of, 1101  
 middle, 1101  
 posterior, 1101  
 superior, 1098  
 lymph glands, 798  
 pleura, 1095
- Mediastinum testis,** 1232
- Mediocornu,** 879
- Mediodural artery,** 640
- Medifrontal gyre,** 870
- Medulla of hair,** 1077  
*oblongata,* 822  
 anterior district of, 822  
 applied anatomy of, 833  
 arcuate fibres of, 830  
 development of, 123  
*fasciculus cuneatus,* 827  
*gracilis,* 827  
 fissures and sulci of, 822  
 gray substance of, 829  
*formatio reticularis,* 832  
 lateral district of, 823  
 olive of, 824  
 posterior district of, 824  
 pyramid of, 823  
 restiform bodies of, 830  
 structure of, 826
- spinalis,** 805  
 anterior white commissure of, 808  
 applied anatomy of, 820  
 central canal of, 810  
 columns of, 809  
 development of, 805  
 dissection of, 805  
 distribution of nerve cells in, 811  
 enlargements of, 808  
 fissures of, 808  
 gray commissures of, 810  
 substance of, 809  
*ligamentum denticulatum,* 905  
 meninges of, 900  
 applied anatomy of, 907  
 neuroglia of, 809  
 sulci of, 808  
 veins of, 755

- Medulla spinalis*, white substance of, 814
- Medullary artery of bone, 52
- lamina, lateral, 856
- medial, 857
- laminae of lentiform nucleus, 881
- membrane of bone, 51
- portion of suprarenal gland, 1272
- segments of nerves, 75
- sheath of nerve-fibres, 73
- spaces of bone, 58
- substance of kidney, 1210
- velum, 842, 845
- Medullated nerve-fibres, 73
- Meibomian glands, 1040
- Meissner's plexus, 1176
- tactile corpuscles, 1070
- Melanin, 46
- Membrana atlantooccipitalis anterior*, 392
- posterior*, 392
- granulosa* [of Graafian follicle], 1246
- hyothyreoides*, 1082
- interossea antebrachii*, 423
- cruris*, 448
- pupillaris*, 1026
- tectorias* [of atlas and occipital bone], 393
- Membrane, anal, 174
- arachnoid, 903
- atlantooccipital, 392
- basilar, 1063, 1065
- of Bowman, 1020
- costocoracoid, 528
- cricothyroid, 1083
- of Demours, 1020
- of Descemet, 1020
- elastic, of larynx, 1083
- fenestrated, 596
- hyaloid, 1030
- hyoglossal, 1132
- hyothyroid, 1082
- intercostal, 492
- interosseous, of forearm, 423
- of leg, 448
- Jacob's, 1029
- of Krause, 66
- limiting, 1029
- medullary, of bone, 51
- of Nasmyth, 1123
- nuclear, 34
- obturator, 572
- pharyngeal, 163
- pupillary, 136, 1026
- of Reissner, 1063
- tectorial, of ductus cochlearis, 1067
- thyrohyoid, 1082
- tympanic, 1050
- structure of, 1050
- vestibular, 1063
- vitelline, 83
- Membranes, basement, 45
- of brain and medulla spinalis, 900
- fetal, 93
- synovial, 379
- Membranous cochlea, 1063
- cranium, 106
- labyrinth, 1061
- portion of urethra, 1226
- semicircular canals, 1062
- vertebral column, 102
- Meningeal artery, accessory, 640
- anterior, 643
- from ascending pharyngeal, 637
- middle, 640
- applied anatomy of, 640
- surface marking of, 1281
- from occipital, 636
- from vertebral, 660
- Meningeal branch of spinal nerve, 951
- layer of dura mater, 902
- nerve from hypoglossal, 947
- from maxillary, 917
- Meninges of brain and medulla spinalis, 900
- Menisci, 49
- of knee-joint, 441
- Meniscus, articular, 395
- lateralis*, 442
- medialis*, 442
- Mental foramen, 271, 286
- nerve, 924
- point, 296
- protuberance, 271
- spines, 271
- tubercle, 271
- Mentalis muscle, 470
- Merkel, tactile disks of, 1069
- Meroblastic ova, 84
- Mesamceboid cells, 142
- Mesencephalon, 90, 125, 848
- Mesenteric artery, inferior, 694
- dissection of, 695
- superior, 691
- dissection of, 692, 695
- lymph glands, 789
- plexuses of nerves, 1004, 1005
- veins, 766
- Mesenteries, 1156
- mesentery proper, 1157
- sigmoid mesocolon, 1153, 1157
- transverse mesocolon, 1157
- Mesenteriole of vermiform process, 1178
- Mesenterium*, 1157
- Mesocardium, arterial, 603
- venous, 603
- Mesocolic lymph glands, 789
- Mesocolon, sigmoid, 1153, 1157
- transverse, 1157
- sigmoideum*, 1157
- transversum*, 1157
- Mesoderm, 88
- formation of, 86
- Mesogastrium, 168
- Mesognathion, 299
- Mesonephros, 180
- Mesorchium, 184
- Mesosalphinx, 1251
- Mesovarium, 184, 1244
- Metacarpal bones, 329
- applied anatomy of, 332
- articulations of, 331
- characteristics of, 329
- ossification of, 332
- Metacarpophalangeal articulations, 430
- Metacarpus, 329
- Metanephros, 187
- Metaphase of karyokinesis, 36
- Metatarsal arteries, 724
- bones, 371
- characteristics of, 371
- veins, 758
- Metatarsophalangeal articulations, 459
- Metatarsus, 371
- ossification of, 374
- Metathalamus, 127, 858
- Metencephalon, 122
- Metopic suture, 234
- Meynert, basal optic nucleus of, 861
- fasciculus retroflexus of, 859
- fountain decussation of, 854
- substantia innominata of, 884
- Microcytes, 62
- Mid-brain, 90, 126, 848
- Mid-carpal joint, 427
- Middle capsular artery, 696
- cerebellar peduncles, 841
- commissure of brain, 856
- constrictor muscle, 1142
- Middle costotransverse ligament, 399
- cutaneous nerve, 980
- dental nerve, 919
- subscapular nerve, 961
- thyrohyoid ligament, 1082
- tibiofibular ligament, 448
- Milk teeth, 1118
- Mitochondria sheath, 81
- Mitral cells, 894, 1013
- orifice, 611
- valve, 612
- Moderator band, 610
- Modiolus of cochlea, 1060
- Molar glands, 1111
- teeth, 1118
- Molecular layer of cortex of cerebellum, 842
- of cerebrum, 891
- Monakow, rubrospinal, tract of, 816
- Monaster or mother star, 36
- Monro, foramen of, 865, 887
- sulcus of, 125, 865
- Mons pubis*, 1256
- Veneris, 1256
- Morgagni, hydatid of, 182, 1231, 1247
- rectal columns of, 1184
- sinus of, 1142
- Morula, 84
- Moss fibres, 844
- Mother star or monaster, 36
- Motor areas of cerebral cortex, 894
- end-plates, 803
- nerves, 803
- neurons, lower and upper, 896, 897
- tract, 896
- Mouth, 1110
- development of, 163
- lymphatics of, 777
- mucous membrane of, 1110
- muscles of, dissection of, 469
- Movable articulations, 381
- Movements admitted in joints, 383
- Mucigen, 37
- Mucous glands of tongue, 1131
- sheaths, 380
- of tendons around ankle, 586
- on back of wrist, 550
- on front of wrist, 548
- tissue, 44
- Müller, orbitalis muscle of, 1037
- sustentacular fibres of, 1029
- Müllerian duct, 182
- eminence, 182
- Multangular bone, greater, 326
- lesser, 327
- Multicuspid teeth, 1118
- Multifidus muscle, 489
- spinæ muscle, 489
- Muscle or Muscles of abdomen, 498
- abductor hallucis*, 587
- digiti quinti* (foot), 588
- (hand), 554
- indicus*, 556
- minimi digiti*, 554
- pollicis*, 552
- 554*
- 518*
- accessory*
- of foot, 589
- adductor brevis*, 568
- hallucis*, 589
- longus*, 567
- magnus*, 568
- obliquus hallucis*, 589
- pollicis*, 554



- Muscle or Muscles, adductor pollicis obliquus, 554**  
*transversus, 554*  
 of anal region, 515  
*anconaeus, 544*  
 anterior crural, 576  
   femoral, 562  
   vertebral, 483  
 anterolateral, of abdomen, 498  
*antitragicus, 1046*  
 applied anatomy of, 410  
 of arm, 533  
*arrectores pilorum, 1077*  
*articularis genu or subcrureus, 566*  
*aryepiglotticus, 1089*  
*arytaenoideus, 1088*  
*attollens aurem, 1045*  
*attrahens aurem, 1045*  
 of auricula or pinna, 1045  
*auricularis, 1045*  
 axillary arch, 524  
*azygos uvulae, 1114*  
*biceps, 534*  
   *brachii, 534*  
   *femoris, 574*  
   flexor cubiti, 534  
*biventer cervicis, 489*  
 Bowman's, 1023  
*brachialis, 535*  
   *anticus, 535*  
*brachioradialis, 542*  
*buccinator, 470*  
*bulbocavernosus, 518, 520*  
*caninus, 470*  
 cardiac, 68  
 cervical, 475  
*cervicalis ascendens, 488*  
*chondroglossus, 1130*  
*ciliaris, 1023*  
*coccygeus, 514*  
 columns, 65  
*complexus, 489*  
*compressor naris, 469*  
   *urethrae, 520*  
 constrictors, 1141, 1142  
   *pharyngis inferior, 1141*  
   *medius, 1142*  
   *superior, 1142*  
   *urethrae, 521*  
*coracobrachialis, 534*  
*corrugator, 468*  
   *cutis ani, 516*  
   *supercilii, 468*  
*cremaster, 504*  
*cricoarytaenoideus, 1088*  
*cricoarytenoid, 1088*  
*cricothyroideus, 1088*  
*cricothyroid, 1088*  
*crureus, 566*  
 deep, of back, 485  
 deltoid, 530  
*deltoides, 530*  
 depressor alae nasi, 469  
   *anguli oris, 470*  
   labii inferioris, 470  
   *septi, 469*  
*detrusor urinae, 1223*  
 development of, 69, 116  
*diaphragma, 493*  
*digastric, 480*  
*digastricus, 480*  
*dilatator naris, 469*  
   *pupillae, 1025*  
   *tubae, 1053*  
 dorsal antibrachial, 542  
*dorsoepitrochlearis brachii, 524*  
*ejaculator urinae, 518*  
*epicranius, 465*  
*erector clitoridis, 521*  
   *penis, 518*  
   *spinae, 488*  
 extensor carpi radialis brevior, 542  
   *brevis, 542*
- Muscle or Muscles, extensor carpi radialis longior, 542**  
*longus, 542*  
*ulnaris, 544*  
*coccygis, 490*  
*digiti quinti proprius, 544*  
*digitorum brevis, 586*  
   *communis, 544*  
   *longus, 577*  
*hallucis longus, 577*  
*indidis, 546*  
   *proprius, 546*  
*minimi digiti, 544*  
*ossis metacarpi pollicis, 545*  
*pollicis brevis, 545*  
   *longus, 545*  
 primi internodii pollicis, 545  
 proprius hallucis, 577  
 secunda internodii pollicis, 545  
 external sphincter ani, 516  
   of eyelids, 467  
 fasciculi of, 64  
 fibres of, 64  
 fixation, 462  
*flexor accessorius, 589*  
   *brevis minimi digiti, 554, 590*  
   *carpi radialis, 537*  
   *ulnaris, 539*  
   *digiti quinti brevis [of foot], 590*  
     [*of hand*], 554  
   *digitorum brevis, 588*  
     *longus, 581*  
     *profundus, 540*  
     *sublimis, 539*  
   *hallucis brevis, 589*  
     *longus, 581*  
   *pollicis brevis, 553*  
     *longus, 540*  
 of foot, 586  
 of forearm, 536  
 form of, 461  
*frontalis, 466*  
*gastrocnemius, 578*  
*gemellus, 573*  
*genioglossus, 1129*  
*geniohyoglossus, 1129*  
*geniohyoid, 481*  
*geniohyoideus, 481*  
*glossopalatinus, 1114, 1129 note*  
*glutaeus maximus, 569*  
   *medius, 570*  
   *minimus, 570*  
 of gluteal region, 569  
*gracilis, 567*  
 hamstring, 574  
 of hand, 546  
   dissection of, 546  
 of head, 464  
*helicis major, 1045*  
   *minor, 1045*  
*hyoglossus, 1129*  
 of iliac region, 559  
*iliacus, 561*  
*iliococcygeus, 514*  
*iliocostalis, 488*  
   *cervicis, 488*  
   *dorsi, 488*  
   *lumborum, 488*  
*iliosacralis, 514*  
*incisivus labii inferioris, 472*  
   *superioris, 472*  
*infracostal, 492*  
*infrahyoid, 480*  
*infraspinalis, 533*  
 insertion of, 462  
*intercostal, 492*  
*intercostales, 492*  
 intermediate volar, 555  
 internal sphincter ani, 516  
 interossei, dorsal, 591  
   of foot, 590  
   of hand, 555  
   plantar, 591
- Muscle or Muscles, interspinales, 490**  
*intertransversales, 490*  
*intertransversarii, 490*  
 involuntary, 67  
*ischiocavernosus, 518, 520*  
 of larynx, 1088  
 lateral cervical, 475  
   crural, 582  
   vertebral, 484  
   volar, 552  
*latissimus dorsi, 524*  
 of leg, 576  
*levator anguli oris, 470*  
   *scapulae, 525*  
   *ani, 513*  
   *glandulae thyreoideae, 1262*  
   *menti, 470*  
   *palati, 1113*  
   *palpebrae superioris, 1034*  
   *prostaticae, 514*  
   *scapulae, 525*  
   *veli palatini, 1113*  
*levator costarum, 493*  
*lingualis, 1130*  
*longissimus capitis, 489*  
   *cervicis, 488*  
   *dorsi, 488*  
*longitudinalis linguae, 1130*  
*longus capitis, 484*  
   *colli, 483*  
 of lower extremity, 559  
*lumbricales [of foot], 589*  
   [*of hand*], 555  
 lymphatics of, 67  
*masseter, 472*  
 of mastication, 472  
*medial femoral, 567*  
   *volar, 554*  
*mentalis, 470*  
 of mouth, 469  
*multifidus, 489*  
   *spinae, 489*  
*mylohyoid, 481*  
*mylohyoideus, 481*  
*nasalis, 469*  
*nasolabialis, 472*  
 nerves and vessels of, 67  
 of nose, 468  
 oblique, 499, 503  
   inferior, 1036  
   superior, 1035  
*obliquus auriculae, 1046*  
   *capitis, 491*  
   *externus abdominis, 499*  
   inferior, 491  
   *internus abdominis, 503*  
   oculi inferior, 1036  
   superior, 1035  
   superior, 491  
*obturator externus, 573*  
   *internus, 572*  
*occipitalis, 466*  
*occipitofrontalis, 465*  
 ocular, 1034  
*omohyoid, 482*  
*omohyoideus, 482*  
*opponens digiti quinti [of foot], 590*  
   [*of hand*], 555  
   *minimi digiti, 555*  
   *pollicis, 553*  
*orbicularis oculi, 467*  
   *oris, 471*  
   *palpebrarum, 467*  
 orbitalis of H. Müller, 1037  
 origin of, 462  
 of palate, 1113  
*palatoglossus, 1114, 1129 note*  
*palatopharyngeus, 1114*  
*palmaris brevis, 554*  
   *longus, 538*  
*pectineus, 567*  
*pectoralis major, 526*  
   *minor, 528*

- Muscle or Muscles of pelvis, 510  
 perineal, superficial transverse, 518, 520  
 of perineum, 514  
*peroneus brevis*, 583  
   *longus*, 582  
   *tertius*, 578  
*pharyngopalatinus*, 1114  
 of pharynx, 1141  
 of pinna or auricula, 1045  
*piriformis*, 571  
 plain, 67  
 plantar, first layer, 587  
   fourth layer, 590  
   second layer, 589  
   third layer, 589  
*plantaris*, 579  
 plate, 102  
*platysma*, 475  
*popliteus*, 581  
 posterior crural, 578  
 femoral, 574  
*procerus*, 469  
*pronator quadratus*, 540  
*teres*, 537  
*psaos magnus*, 560  
   *major*, 560  
   *minor*, 561  
   *parvus*, 561  
 pterygoid, 474  
*pterygoideus externus*, 474  
   *internus*, 474  
*pubococcygeus*, 514  
*puborectalis*, 514  
*pubovesicales*, 1221  
*pyramidalis abdominis*, 507  
   *nasi*, 469  
*quadratus femoris*, 573  
*labii superioris*, 469  
   *inferioris*, 470  
   *lumborum*, 510  
   *menti*, 470  
   *plantae*, 589  
*quadriceps extensor*, 565  
   *femoris*, 565  
*recti* [of eyeball], 1035  
*rectococcygeal*, 1185  
*rectovesicales*, 1221  
*rectus abdominis*, 506  
   *capitis anterior*, 484  
     *lateralis*, 484  
     *posterior major*, 491  
       *minor*, 491  
   *anticus major*, 484  
     *minor*, 484  
   *posticus major*, 491  
     *minor*, 491  
   *femoris*, 565  
*retrahens aurem*, 1045  
*rhomboideus major*, 525  
   *minor*, 525  
*risorius*, 472  
*rotatores*, 490  
   *spinae*, 490  
*sacrospinalis*, 488  
*salpingopharyngeus*, 1143  
 sarcoous elements of, 66  
*sartorius*, 565  
*scalenus anterior*, 484  
   *anticus*, 484  
   *medius*, 484  
   *posterior*, 485  
   *posticus*, 485  
 of scalp, 464  
*semimembranosus*, 575  
*semispinalis capitis*, 489  
   *cervicis*, 489  
   *colli*, 489  
   *dorsi*, 489  
*semilendinosus*, 575  
*serratus anterior*, 529  
   *magnus*, 529  
   *posterior inferior*, 493  
   *superior*, 493  
   *posticus inferior*, 493
- Muscle or Muscles, serratus pos-  
 titicus superior, 493  
*soleus*, 579  
 sphincter ani, 516  
   *externus*, 516  
   *internus*, 516  
   *pupillae*, 1025  
   *recti*, 514  
   *urethrae membranaceae*, 520,  
     521  
   *vaginae*, 520  
   *vesicae*, 1223  
*spinalis capitis*, 489  
   *cervicis*, 489  
   *colli*, 489  
   *dorsi*, 489  
*splenius capitis*, 486  
   *cervicis*, 487  
   *colli*, 487  
*stapedius*, 1055  
*sternocleidomastoideus*, 478  
*sternohyoid*, 482  
*sternohyoideus*, 482  
*sternomastoid*, 478  
*sternothyreoides*, 482  
*sternothyroid*, 482  
 striped, 64  
   structure of, 64  
*styloglossus*, 1130  
*stylohyoid*, 481  
*stylohyoideus*, 481  
*stylopharyngeus*, 1142  
*subanconeus*, 536  
*subclavius*, 528,  
*subcostales*, 492  
*subcrureus*, 566  
*suboccipital*, 490  
*subscapularis*, 531  
*superficial cervical*, 475  
*supinator*, 544  
   *brevis*, 544  
   *longus*, 542  
*suprahyoid*, 480  
*supraspinatus*, 532  
 suspensory, of duodenum, 1171  
 synergic, 462  
 temporal, 473  
*temporalis*, 473  
 tendons of, 463  
*tensor fasciae femoris*, 565  
   *latae*, 565  
   *palati*, 1113  
   *tarsi*, 468  
   *tympani*, 1055  
   *veli palatini*, 1113  
*teres major*, 533  
   *minor*, 533  
 of thigh, 562  
 of thorax, 492  
*thyrocartylenoideus*, 1089  
*thyroepiglotticus*, 1090  
*thyrohyoideus*, 482  
*thyroarytenoid*, 1089  
*thyrohyoid*, 482  
*tibialis anterior*, 576  
   *anticus*, 576  
   *posterior*, 582  
 of tongue, 1044  
*trachealis*, 1093  
*trachelomastoideus*, 489  
*tragicus*, 1046  
*transversalis*, 504  
   *cervicis*, 488  
*transversus auriculae*, 1046  
   *abdominis*, 504  
   *linguae*, 1130  
   *menti*, 470  
   *nuchae*, 466  
   *pedis*, 589  
   *perinaei*, 518, 520  
     *profundus*, 521, 522  
     *superficialis* [in female], 520  
       [in male], 518  
   *thoracis*, 492  
*trapezius*, 522
- Muscle or Muscles, *triangularis*,  
 470  
*sterni*, 492  
*triceps*, 535  
*brachii*, 535  
   *extensor cubiti*, 535  
   *surae*, 579  
 of trunk, 485  
 of tympanic cavity, 1055  
 of upper extremity, 522  
 of ureters, 1222  
 unstriped, 67  
   structure of, 67  
 urogenital region [female], 520  
   [male], 517  
 of uvula, 1114  
*vastus externus*, 566  
   *intermedius*, 566  
   *internus*, 566  
   *lateralis*, 566  
   *medialis*, 566  
 vertebral, anterior, 483  
   *lateral*, 484  
*verticalis linguae*, 1130  
*vocalis*, 1089  
 volar antibrachial, 537  
 voluntary, 64  
*zygomatikus*, 470  
   *major*, 470
- Muscular fibres of heart, 613  
 process of arytenoid cartilage,  
   1081  
 tissue, 64, 68  
 triangle, 483, 643  
*Muscularis mucosae*, 1173  
*Musculi oculi*, 1034  
*ossiculorum auditus*, 1055  
*papillares* [of left ventricle], 612  
   [of right ventricle], 610  
*pectinati* [of left auricle], 611  
   [of right auricle], 607  
*pubovesicales*, 1223
- Musculocutaneous nerve of arm,  
 962  
 of leg, 990
- Musculophrenic artery, 666
- Musculospiral groove, 311
- nerve, 968
- Musculus accessorius*, 488  
*ciliaris*, 1023  
*incisivus labii inferioris*, 472  
   *superioris*, 472  
*nasolabialis*, 472  
*suspensorius duodeni*, 1171  
*uvulae*, 1114
- Myelencephalon, 122
- Myelocytes, 51
- Myeloplaxes, 51
- Mylohyoid artery, 641  
 groove, 272  
 line, 272  
 muscle, 481  
 nerve, 924
- Mylohyoideus muscle, 481
- Myocardium, 613
- Myocel, 91
- Myology, 461
- N
- NAILS, 1075
- Nares, 1008, 1009
- Nasal aperture, anterior, 294  
 artery, 650  
   *lateral*, 635  
 bones, 255  
   articulations of, 256  
   ossification of, 256  
 cartilages, 1008  
 cavities, 292, 1010  
   applied anatomy of, 1015  
   arteries of, 1012  
   lymphatic vessels of, 776  
   mucous membrane of, 1012

- Nasal cavities, nerves of, 1012,**  
 1013  
 veins of, 1013  
 vestibule of, 1010  
 concha, inferior, 268  
 middle, 254  
 superior, 254  
 crest, 261, 266  
 duct, 1042  
 fossa, 1010  
 index, 296  
 laminae, 111  
 mucous membrane, 1012  
 nerve from ophthalmic, 916  
 nerves from nasopalatine gan-  
 glion, 921  
 notch of frontal bone, 235  
 of maxilla, 257  
 part of frontal bone, 235  
 of pharynx, 1138, 1139  
 process of frontal bone, 235  
 of maxilla, 260  
 processes of fetus, 111  
 septum, 293, 1012  
 spine, anterior, 257, 262  
 of frontal bone, 235  
 posterior, 266, 278
- Nasalis muscle, 469**  
**Nasion, 235, 285, 296**  
**Nasmyth's membrane, 1123**  
**Nasociliary nerve, 916**  
**Nasofrontal vein, 745**  
**Nasolabialis muscle, 472**  
**Nasolacrimal duct, 1042**  
**Nasoöptic furrow, 112, 137**  
**Nasopalatine nerve, 921**  
 recess, 1012  
**Nasopharynx, 1139**  
**Nasus externus, 1008**  
**Navicular bone of carpus, 323**  
 of tarsus, 368  
 fossa, 1257
- Neck, lymphatic glands of, 778**  
 vessels of, 779  
 muscles of, 475  
 triangles of, 642  
 veins of, 734
- Nélaton's line, 1329**  
**Neopallium, 128**  
**Nerve cells, 70**  
 of cerebellar cortex, 842  
 of cerebral cortex, 891  
 of medulla spinalis, 811, 812  
 endings, free, 813, 1069  
 fasciculi of medulla spinalis,  
 814  
 fibres of cerebral cortex,  
 892  
 medullated, 73  
 non-medullated, 76  
 posterior, 948  
 roots, anterior, 948
- Nerve or Nerves, abducent, 927**  
 accessory, 944  
 acoustic, 934, 1067  
 alveolar, anterior superior, 919  
 middle, 919  
 posterior, 918  
 inferior, 922  
 anococcygeal, 992  
 anterior crural, 979  
 interosseous, 965  
 superior alveolar, 919  
 thoracic, 961  
 tibial, 990  
 antibrachial cutaneous, 963,  
 964  
 Arnold's, 941  
 auditory, 934  
 auricular, great, 956  
 of auriculotemporal, 923  
 posterior, 933  
 of vagus, 941  
 auriculotemporal, 923  
 axillary, 961
- Nerve or Nerves of Bell, 960**  
 brachial cutaneous, lateral, 962  
 medial, 964  
 posterior, 969  
 bronchial, 943  
 buccal, of facial, 933  
 long, 922  
 buccinator, 922  
 calcanean, medial, 988  
 cardiac, cervical, 942  
 great, 997  
 of sympathetic, 997  
 thoracic, 943  
 of vagus, 942  
 caroticotympanic, 996, 1056  
 carotid of glossopharyngeal,  
 939  
 cavernous, of penis, 1005  
 cerebral, 907  
 abducent, 927  
 accessory, 944  
 acoustic, 934  
 facial, 929  
 glossopharyngeal, 937  
 hypoglossal, 945  
 oculomotor, 911  
 olfactory, 908  
 optic, 909  
 trigeminal, 914  
 trochlear, 913  
 vagus, 940  
 cerebrospinal, structure of, 801  
 cervical, 957  
 cutaneous, 957  
 divisions of, anterior, 954  
 posterior, 951  
 of facial, 933  
 transverse, 957  
 chorda tympani, 932, 1056  
 ciliary, 916, 917  
 circumflex, 961, 954, 953, 985  
 coccygeal, division of, anterior,  
 982  
 posterior, 954  
 cochlear, 935, 1068  
 coeliac, of vagus, 943  
 cranial, 907  
 crural, anterior, 980  
 cutaneous cervical, 957  
 external, 977  
 internal, 964, 981  
 lesser, 964  
 middle, 980  
 deep branch of radial, 970  
 of ulnar, 968  
 peroneal, 990  
 petrosal, 919  
 temporal, 921  
 descending ramus of hypo-  
 glossal, 947  
 development of, 119, 131  
 digastric, from facial, 933  
 digital, of lateral plantar, 988  
 of medial plantar, 988  
 of median, 966  
 of radial, 970  
 of superficial peroneal, 990  
 of ulnar, 968  
 dorsal antibrachial cutaneous,  
 969  
 branch of ulnar, 967  
 cutaneous, lateral, 988  
 medial, 990  
 of penis, 992  
 scapular, 960  
 of dura mater, 902  
 dural, 941  
 eighth, 934  
 eleventh, 944  
 end-organs of, 1069  
 endoneurium of, 802  
 epineurium of, 801  
 external nasal, 919  
 plantar, 989  
 popliteal, 989
- Nerve or Nerves, external saphenous, 988**  
 spermatic, 977  
 facial, 929  
 femoral, 980  
 cutaneous, anterior, 980  
 lateral, 977  
 posterior, 985  
 fifth, 914  
 first, 908  
 fourth, 913  
 frontal, 916  
 ganglia of, 803  
 gastric branches of vagus, 943  
 genitocrural, 977  
 genitofemoral, 977  
 glossopharyngeal, 937  
 gluteal, 984, 985  
 great auricular, 956  
 greater occipital, 951  
 splanchnic, 998  
 superficial petrosal, 919  
 hemorrhoidal, inferior, 991  
 hepatic branches of vagus, 943  
 hypoglossal, 945  
 iliohypogastric, 976  
 ilioinguinal, 977  
 incisive, 924  
 inferior dental, 924  
 infraorbital, 917 *note*  
 infrapatellar, 981  
 infratrochlear, 916  
 intercostal, 972  
 intercostobrachial, 973  
 intermedius of Wrisberg, 929  
 internal cutaneous, of arm, 964  
 carotid, 996  
 plantar, 998  
 popliteal, 987  
 saphenous, 981  
 interosseous, dorsal, 970  
 volar, 965  
 Jacobson's, 939, 1056  
 jugular, 997  
 labial, superior, 919  
 lacrimal, 915  
 laryngeal, 942  
 laryngopharyngeal of sympa-  
 thetic, 997  
 lateral antibrachial cutaneous,  
 963, 964  
 brachial cutaneous, 962  
 femoral cutaneous, 977  
 plantar, 984  
 lesser splanchnic, 999  
 lingual, 923  
 of glossopharyngeal, 940  
 long ciliary, 916  
 saphenous, 981  
 subscapular, 961  
 thoracic, 960  
 lowest splanchnic, 999  
 lumbar, divisions of, anterior,  
 974  
 posterior, 953  
 lumboinguinal, 977  
 lumbosacral trunk, 975  
 mandibular, 921  
 of facial, 933  
 masseteric, 921  
 maxillary, 917  
 inferior, 921  
 medial antibrachial cutaneous,  
 964  
 brachial cutaneous, 964  
 sural cutaneous, 998  
 plantar, 998  
 median, 965  
 meningeal, of hypoglossal, 947  
 of maxillary, 917  
 middle, 917  
 of spinal nerves, 947  
 of vagus, 941  
 mental, 924  
 motor, 803

- Nerve or Nerves, musculocutaneous, of arm, 962  
of leg, 990  
musculospiral, 968  
mylohyoid, 924  
nasal, of ophthalmic, 916  
from sphenopalatine ganglion, 921  
nasociliary, 916  
nasopalatine, 921  
ninth, 937  
obturator, 979  
accessory, 980  
occipital, greater, 951  
smaller, 956  
third, 951  
oculomotor, 911  
oesophageal, 943  
olfactory, 908  
ophthalmic, 915  
optic, 909  
orbital, 917  
their relation, in cavernous sinus, 928  
in orbit, 928  
in superior orbital fissure, 928  
origins of, 803  
palatine, 920, 921  
palmar cutaneous, of median, 965  
of ulnar, 967  
palpebral, inferior, 919  
perforating cutaneous, 991  
perineurium of, 801  
plexus of, 802  
peroneal, 989, 990  
petrosal, deep, 919, 996  
external, 997  
greater superficial, 919  
smaller superficial, 1056  
large, deep, 919  
superficial, 919, 931  
pharyngeal, of glossopharyngeal, 940  
of sphenopalatine ganglion, 921  
of vagus, 942  
phrenic, 957  
plantar, 988, 989  
pneumogastric, 940  
popliteal, external, 989  
internal, 987  
of pterygoid canal, 920, 996  
to pterygoideus internus, 921  
externus, 922  
pterygopalatine, 921  
pudendal, 991  
inferior, 985  
pudic, 991  
internal, 991  
pulmonary, 943  
radial, 970  
rami communicantes, gray and white, 949, 950, 995  
recurrent, 942  
respiratory, of Bell, 957  
to rhomboids, 960  
roots, 818, 948  
sacral, 982  
saphenous, 981  
internal, 981  
short, 988  
sciatic, 985  
scrotal, posterior, 991  
second, 909  
seventh, 929  
short ciliary, 917  
sixth, 927  
smaller occipital, 956  
spermatic, external, 977  
sphenopalatine branches of maxillary, 918  
spinal, 947  
accessory, 944
- Nerve or Nerves, spinal, development of, 119  
divisions of, anterior primary, 954  
posterior primary, 951  
roots of, 818, 948  
spinosus, 921  
splanchnic, 998, 999  
to stapedius, 932  
stylohyoid, 933  
to subclavius, 960  
suboccipital, 951, 954  
subscapular, 961  
superior labial, 919  
superficial branch of radial, 969  
of ulnar, 968  
supra-acromial, 957  
supraclavicular, 957  
supraorbital, 916  
suprascapular, 960  
suprasternal, 957  
supratrochlear, 916  
sural, 998  
sympathetic, 994  
structure of, 803  
of taste, 1008  
temporal, deep, 922  
of facial, 933  
temporomalar, 917  
tenth, 940  
terminations of, 803  
third, 911  
thoracic, divisions of, anterior, 972  
posterior, 952  
lateral anterior, 961  
medial anterior, 961  
thoracodorsal, 961  
thyrohyoid, 947  
tibial, 987  
anterior, 990  
of tongue, 1132  
tonsillar, 940  
transverse cervical, 957  
trifacial, 914  
trigeminal, 914  
trochlear, 913  
twelfth, 945  
tympenic, of glossopharyngeal, 939, 1056  
ulnar, 967  
collateral, 969  
of urethral bulb, 992  
vagus, 940  
vestibular, 935, 1068  
Vidian, 920, 996  
volar digital, 966  
interosseous, 965, 968  
of Wrisberg, 964  
zygomatic, 917  
of facial, 933  
zygomaticofacial, 918  
zygomaticotemporal, 918
- Nervi anococcygei*, 992  
*auriculares anteriores*, 923  
*carotici externi*, 997  
*cavernosi penis minores*, 1005  
*cerebrales*, 907  
*cervicales*, 951, 954  
*ramus lateralis*, 951  
*medialis*, 951  
*ciliares longi*, 916  
*chunium inferiores*, 985  
*coccygeus*, 954, 982  
*communicantes cervicales*, 957  
*digitales dorsales hallucis*, 990  
*plantares communes*, 988  
*proprii*, 988  
*ethmoidales*, 916  
*intercostales*, 972  
*rami cutanei laterales*, 973  
*labiales anteriores*, 974  
*posteriores*, 953  
*lumbales*, 953  
*nervorum*, 802
- Nervi olfactorii*, 908  
*palatini*, 920  
*sacrales*, 953, 982  
*sphenopalatini*, 918  
*spinales*, 947  
*radix anterior*, 948  
*posterior*, 948  
*rami anteriores*, 954  
*posteriores*, 957  
*subscapulares*, 961  
*supraclaviculares anteriores*, 957  
*medii*, 957  
*posteriores*, 957  
*temporales profundi*, 922  
*thoracales*, 952  
*anteriores*, 961, 972  
*ramus lateralis*, 953  
*medialis*, 952
- Nervous system, description of, 801  
development of, 117  
tissue, 69
- Nervus abducens*, 927  
*accessorius*, 944  
*ramus externus*, 945  
*internus*, 944  
*acusticus*, 934, 1067  
*radix cochlearis*, 935  
*vestibularis*, 935  
*alveolaris inferior*, 923  
*auricularis magnus*, 956  
*posterior*, 933  
*auriculotemporalis*, 923  
*rami parotidei*, 923  
*temporales superficiales*, 923  
*azillaris*, 961  
*buccinatorius*, 922  
*canalis pterygoidei*, 920  
*cardiacus inferior*, 998  
*medius*, 997  
*superior*, 997  
*caroticotympanicus inferior*, 939  
*superior*, 939  
*cavernous penis major*, 1005  
*cochlearis*, 1068  
*chunium inferior medialis*, 991  
*communicans fibularis*, 990  
*tibialis*, 988  
*cutaneus antebrachii dorsalis*, 969  
*lateralis*, 964  
*medialis*, 964  
*ramus ulnaris*, 964  
*volaris*, 964  
*brachii medialis*, 964  
*posterior*, 969  
*colli*, 957  
*rami inferiores*, 957  
*ramus superior*, 957  
*dorsalis intermedius*, 990  
*medialis*, 990  
*femoris lateralis*, 977  
*posterior*, 985  
*rami perineales*, 985  
*surae lateralis*, 990  
*medialis*, 988  
*descendens cervicales*, 957  
*dorsalis penis*, 992  
*scapulae*, 960  
*facialis*, 929  
*rami buccales*, 933  
*temporales*, 933  
*zygomatici*, 933  
*ramus colli*, 933  
*digestricus*, 933  
*marginalis mandibulae*, 933  
*stylohyoideus*, 933  
*femoralis*, 980  
*frontalis*, 916  
*furcalis*, 975  
*genitofemoralis*, 977  
*glossopharyngeus*, 937  
*ganglion inferius*, 939  
*superius*, 938

- Nervus glossopharyngeus*, rami  
*linguales*, 940  
*pharyngei*, 940  
*tonsillares*, 940  
*ramus stylopharyngeus*, 940  
*gluteus inferior*, 985  
*superior*, 984  
*haemorrhoidalis inferior*, 991  
*hyoglossus*, 945  
*ramus descendens*, 947  
*thyrohyoideus*, 947  
*iliohypogastricus*, 976  
*ramus lateralis*, 977  
*ilioinguinalis*, 977  
*infratrochlearis*, 916  
*intermedius* [of Wrisberg], 929  
*interosseus dorsalis*, 970  
*volaris*, 965  
*ischiadicus*, 985  
*rami articulares*, 985  
*musculares*, 985  
*lacrimalis*, 915  
*laryngeus superior*, 942  
*ramus externus*, 942  
*internus*, 942  
*lingualis*, 923  
*lumboinguinalis*, 977  
*mandibularis*, 921  
*massetericus*, 921  
*maxillaris*, 917  
*rami alveolares superiores*  
*posteriores*, 917  
*labialis superiores*, 919  
*nasales externi*, 919  
*palpebrales inferiores*, 919  
*ramus alveolaris superior an-*  
*teriores*, 919  
*medius*, 919  
*meatus auditorii externi*, 923  
*medianus*, 965  
*rami musculares*, 965  
*ramus cutaneus palmaris n.*  
*mediani*, 965  
*meningeus medius*, 917  
*musculocutaneus*, 962  
*ramus dorsalis*, 964  
*volaris*, 964  
*mylohyoideus*, 923  
*nasociliaris*, 916  
*obturatorius*, 979  
*accessorius*, 980  
*ramus anterior*, 979  
*posterior*, 980  
*occipitalis major*, 951  
*minor*, 956  
*oculomotorius*, 911  
*ophthalmicus*, 915  
*opticus*, 909  
*palatinus anterior*, 920  
*medius*, 920  
*posterior*, 921  
*perinei*, 991  
*peroneus communis*, 989  
*rami articulares*, 990  
*profundus*, 990  
*petrosus profundus*, 919  
*superficialis major*, 919  
*phrenicus*, 957  
*plantaris lateralis*, 989  
*ramus profundus*, 989  
*superficialis*, 989  
*medialis*, 988  
*pterygoideus externus*, 922  
*internus*, 921  
*pubendus*, 991  
*radialis*, 968  
*rami musculares*, 969  
*ramus superficialis*, 969  
*recurrens*, 942  
*saphenus*, 961  
*spermaticus externus*, 977  
*spinosus*, 921  
*splanchnicus imus*, 999  
*major*, 998  
*minor*, 999
- Nervus stapedius*, 932  
*subscapularis*, 960  
*supraorbitalis*, 916  
*supratrochlearis*, 916  
*thoracalis longus*, 960  
*thoracodorsalis*, 961  
*tibialis*, 987  
*rami articulares*, 987  
*calcanei mediales*, 988  
*musculares*, 987  
*trigeminus*, 914  
*trochlearis*, 913  
*tympanicus*, 939  
*ulnaris*, 967  
*rami musculares*, 967  
*ramus cutaneus palmaris*, 967  
*dorsalis manus*, 967  
*profundus*, 968  
*superficialis*, 968  
*volaris manus*, 968  
*vagus*, 940  
*rami bronchiales anteriores*,  
943  
*posteriores*, 943  
*cardiaci inferiores*, 943  
*superiores*, 942  
*coeliaci*, 943  
*gastrici*, 943  
*hepatici*, 943  
*oesophagei*, 943  
*ramus auricularis*, 941  
*meningeus*, 941  
*pharyngeus*, 942  
*vestibularis*, 1068  
*zygomatikus*, 917  
*ramus zygomaticofacialis*, 918  
*zygomaticotemporalis*, 918
- Net-work, carpal, dorsal, 678  
volar, 678  
malleolar lateral, 724  
medial, 723
- Neumann, dentinal sheath of,  
1120
- Neural arch, 197  
canal, 88  
crest, 88, 120  
folds, 88  
groove, 88  
tube, 88
- Neurenteric canal, 88
- Neuroblasts, 118
- Neurocentral synchondrosis, 210
- Neuroglia, 70  
of cord, 810
- Neurokeratin, 75
- Neurolemma, 75
- Neurology, 801
- Neuromeres, 806
- Neuromuscular spindles, 1071
- Neuron theory, 805
- Neurons, motor, lower, 897  
upper, 896  
sensory, highest, 899  
intermediate, 899  
lowest, 899
- Neurotendinous spindles, 1070
- Neutrophil colorless corpuscles,  
62
- Nidus avis of cerebellum, 839
- Ninth nerve, 937
- Nipple or papilla of mamma, 1258
- Nissl's granules, 72
- Node, atrioventricular, 614  
sinoatrial, 614
- Nodes of Ranvier, 75
- Nodular lobe, 839
- Nodule of cerebellum, 839
- Noduli lymphatici aggregati, 1175  
solitarii, 1175, 1185
- Nodus vermis, 839
- Non-medullated nerve fibres, 76
- Normæ of skull, basalis, 278  
frontalis, 285  
lateralis, 281  
occipitalis, 284
- Normæ of skull, verticalis, 277
- Normoblasts, 51
- Nose, 1008  
accessory sinuses of, 1014  
alar cartilages of, 1009  
applied anatomy of, 1015  
arteries of, 1009, 1012  
cartilage of septum of, 1008  
cartilaginous frame-work of,  
1008  
cavities of, 1010  
development of, 111  
external, 1008  
lateral cartilage of, 1009  
lymphatics of, 776  
mucous membrane of, 1012  
muscles of, 468  
nerves of, 1013  
veins of, 1013
- Notch, acetabular, 339  
cardiac, 1104  
cerebellar, anterior, 837  
posterior, 837  
ethmoidal, 235  
intertragic, 1044  
jugular, 230  
lacrimal, 257  
mandibular, 273  
mastoid, 239, 280  
nasal, of frontal, 235  
of maxilla, 257  
parietal, 239  
preoccipital, 867  
presternal, 217  
of Rivinus, 1049  
scapular, 306  
sciatic, 336  
sphenopalatine, 268  
superior thyroid, 1080  
supraorbital, 235, 286, 288  
ulnar, of radius, 321  
umbilical, of liver, 1194  
vertebral, 197
- Notochord, 90
- Nuchal line, 227, 281
- Nuck, canal of, 187, 1251
- Nuclear layer of cerebellar cortex,  
843  
layers of retina, 1028  
matrix, 34  
membrane, 34  
substance, 34
- Nucleated sheath of Schwann,  
73
- Nuclei of cochlear nerve, 836, 935  
of glossopharyngeal and vagus  
nerves, 829  
of oculomotor nerve, 911  
olivary, 830  
of origin of motor nerves, 908  
pontis, 835, 908  
of termination of sensory  
nerves, 908  
of trigeminal nerve, 835, 855  
of vestibular nerve, 836, 935
- Nucleoli, 34
- Nucleus of abducent nerve, 835  
of accessory nerve, 830, 944  
ambiguus, 829  
amygdalæ, 883  
amygdaline, 839  
arcuatus, 831  
of Bechterew, 836, 935  
caudate, 881  
caudatus, 881  
of a cell, 34  
of Darkschewitsch, 860  
of Deiters, 836, 935  
dentatus [of cerebellum], 844  
dorsalis, 813  
emboliformis, 844  
of facial nerve, 836, 929  
fastigii, 844  
globosus, 844  
of hypoglossal nerve, 829



Nucleus, inferior central, 833  
*intercalatus*, 848  
 of lateral lemniscus, 935  
*lateralis*, 833  
 of lens, 1031  
 lenticular, 881  
 lentiform, 881  
*lentiformis*, 881  
 of Luys, 860  
 of medial longitudinal fascicu-  
 lus, 851  
*nervus abducentis*, 835  
*acustici*, 836  
*facialis*, 836  
*trigemini*, 835  
 of oculomotor nerve, 855, 911  
*olivaris superior*, 835  
 olivary, 830, 835  
 of posterior commissure, 860  
 pulposus, 104  
 red, 850  
 of Roller, 833  
 segmentation, 84  
 sensory, 930  
 trapezoid, 835  
 of trochlear nerve, 855, 913  
 of vagus nerve, 829  
 Nuel, space of, 1067  
 Nuhn, glands of, 1131  
 Nutrient artery of bone, 52  
 Nutritive yolk, 78  
 Nymphæ, 1257

O

OBELION, 278, 296  
 Obex, 846  
 Oblique cord, 423  
 inguinal hernia, 1187  
 ligament, 423  
 line of fibula, 360  
 of mandible, 271  
 of radius, 320  
 muscles, 499, 503  
 inferior, 1036  
 superior, 1035  
 popliteal ligament, 439  
 ridge of clavicle, 302  
 sinus of pericardium, 603  
 vein of left atrium, 603, 731  
 of Marshall, 603, 731  
 Obliquus auriculæ muscle, 1046  
 capitis inferior muscle, 491  
 superior muscle, 491  
 externus abdominis muscle, 499  
 inferior muscle, 491  
 internus abdominis muscle,  
 503  
 oculi inferior muscle, 1036  
 superior muscle, 1035  
 superior muscle, 491  
 Obliterated ductus venosus, 765  
 hypogastric artery, 700  
 umbilical vein, 765, 1150  
 Obturator artery, 702  
 peculiarities of, 703  
 crest, 338  
 externus muscle, 573  
 foramen, 339  
 groove, 339  
 internus muscle, 572  
 fascia of, 510  
 lymph gland, 787  
 membrane, 572  
 nerve, 979  
 accessory, 980  
 applied anatomy of, 992  
 tubercle, 339  
 vein, 760  
 Occipital artery, 635  
 bone, 227  
 articulations of, 231  
 basilar part of, 230  
 lateral parts of, 229

Occipital bone, ossification of, 231  
 squama of, 227  
 structure of, 231  
 condyles, 229  
 crest, internal, 228, 292  
 fossæ, 228  
 groove, 239, 280  
 lobe, 871  
 lymph glands, 774  
 nerve, 951, 956  
 point, 296  
 protuberance, 227, 228, 282  
 sinus, 743  
 sulcus, 871  
 triangle, 483, 645  
 vein, 734  
 Occipitoaxial ligaments, 393  
 Occipitofrontal fasciculus, 891  
 Occipitofrontalis muscle, 465  
 Occipitomastoid suture, 282  
 Occipitotemporal convolution,  
 871  
 Ocular muscles, 1034  
 applied anatomy of, 1038  
 Oculomotor sulcus, 849  
 nerve, 911  
 applied anatomy of, 913  
 Odontoblasts, 1119, 1123  
 Odontoid ligaments, 393  
 process of axis, 200  
 Oesophageal arteries, 663, 685  
 glands, 1146  
 hiatus in diaphragm, 496  
 nerves, 943  
 plexus, 943  
 Oesophagus, 1144  
 abdominal portion of, 1145  
 applied anatomy of, 1146  
 cervical portion of, 1144  
 lymphatic vessels of, 800  
 nerves of, 1146  
 structure of, 1145  
*tela submucosa*, 1145  
 thoracic portion of, 1144  
*tunica mucosa*, 1146  
*muscularis*, 1145  
 vessels of, 1146  
 Olecranon, 315  
 fossa, 313  
 Olfactory areas, 111  
 bulb, 874, 893  
 structure of, 894  
 cells, 1012  
 fasciculus, 887  
 hair, 1012  
 lobe, 874  
 nerves, 908  
 applied anatomy of, 909  
 development of, 134  
 pits, 111  
 sulcus, 870  
 tract, 874  
 trigone, 875  
 Oliva, 824  
 Olive, 824  
 peduncle of, 830  
 Olivary body, 824  
 nucleus, 830, 835  
 Omental bursa, 1152, 1155  
 boundaries of, 1155, 1156  
 recess, 1156  
 Omentum, gastrocolic, 1157  
 gastrohepatic, 1156  
 greater, 1157  
 lesser, 1156  
*majus*, 1157  
*minus*, 1156  
 small, 1156  
 Omohyoid muscle, 482  
 Omohyoideus muscle, 482  
 Ontogeny, 77  
 Oocytes, primary, 77  
 secondary, 80  
 Oögonia, 77  
 Oöplasm, 77

Opening of aorta in left ventricle,  
 612  
 aortic, in diaphragma, 495  
 atrioventricular, left, 611  
 right, 609  
 caval, in diaphragma, 495  
 of coronary sinus, 608  
 of inferior vena cava, 607  
 cesophageal, in diaphragma,  
 496  
 of pulmonary artery, 609  
 veins, 611  
 saphenous, 562  
 of superior cava, 607  
 of thorax, 601  
 Openings in diaphragma, 495  
 in roof of fourth ventricle, 847  
 Opercula of insula, 873  
 Ophryon, 296  
 Ophthalmic artery, 648  
 ganglion, 917  
 nerve, 915  
 veins, 745  
 Opisthion, 281, 296  
 Opisthotic centre of temporal  
 bone, 244  
 Opponens digiti quinti muscle,  
 555  
 minimi digiti muscle, 555  
 pollicis muscle, 553  
 Optic axis, 1017  
 chiasma, 862, 909  
 commissure, 862  
 cup, 134  
 disk, 1027  
 foramen, 246, 250, 290  
 groove, 246  
 nerve, 909  
 applied anatomy of, 911  
 radiations, 857, 864  
 recess, 865  
 stalk, 126, 134  
 thalamus, 855  
 tracts, 863, 909  
 vesicle, 126, 134  
 Ora serrata, 1026, 1029  
 Oral cavity, 1110  
 part of pharynx, 1139  
 Orbicular ligament, 422  
 Orbicularis oculi muscle, 467  
 lacrimal part, 468  
 orbital part, 468  
 palpebral part, 468  
 oris muscle, 471  
 palpebrarum muscle, 467  
 Orbiculus ciliaris muscle, 1023  
*Orbitæ*, 286  
 Orbits, 286  
 relation of nerves in, 928  
 Orbital fascia, 1038  
 fissure, inferior, 284, 288  
 superior, 249, 288, 290  
 gyri, 870  
 index, 296  
 nerve, 917  
 operculum, 873  
 plates, 235  
 process of palatine bone, 267  
 of zygomatic bone, 264  
 septum, 1039  
 sulcus, 870  
 vein, 734  
 Orbitalis muscle of H. Müller,  
 1037  
 Orbitosphenoids, 249  
 Organ, enamel, 1123  
 of Giralès, 1236  
 of hearing, 1043  
 of Rosenmüller, 181, 1244  
 of sight, 1017  
 of smell, 1008  
 spiral, of Corti, 1065  
*Organa genitalia muliebria*, 1243  
*virilia*, 1228  
*oculi accessoria*, 1034



Pretracheal fascia, 477  
Prevertebral fascia, 477  
part of base of skull, 106  
Prickle cells, 39  
Primary areolæ of bone, 59  
oöcytes, 77.

## 1391

Pelvis, male and female, differences between, 443  
 mechanism of, 408  
*minor*, 340  
 position of, 342  
 renal, 1216  
 superior aperture or inlet of, 340  
 surface anatomy of, 1324  
**Penis**, 1237  
 applied anatomy of, 1240  
 body of, 1239  
*corona glandis*, 1239  
*corpora cavernosa*, 1238  
*corpus cavernosum urethrae*, or  
   corpus spongiosum, 238  
   crura of, 1238  
 deep artery of, 705  
 dorsal artery of, 706  
   veins of, 761  
 extremity of, 1239  
 fundiform ligament of, 1239  
 glands, 1238  
 nerves of, 1240  
 prepuce or foreskin of, 1239  
 root of, 1239  
*septum pectiniforme*, 1238  
 structure of, 1239  
 suspensory ligament of, 1239  
**Perforated substance**, anterior, 875

ores, 1250  
 Parumbilical veins, 767  
 Patella, 354  
     applied anatomy of, 355  
     articulations of, 355  
     movements of, 444  
     ossification of, 355  
     structure of, 355  
     surface anatomy of, 1324  
 Patellar plexus, 979, 981  
     retinacula, 439  
     surface of femur, 350  
 Pavement epithelium, 37  
 Pectinate ligament of iris, 1021  
 Pectineal line, 348  
 Pectineus muscle, 567  
 Pectiniforme septum, 1238  
 Pectoral region, dissection of, 525  
 Pectoralis major muscle, 426  
     minor muscle, 428  
 Peculiar thoracic vertebrae, 203,  
     204  
 Peculiarities of fetal heart, 161  
 Pedicles of a vertebra, 197  
 Peduncle of carpus callosum, 875  
     of olive, 830  
 Peduncles of cerebellum, 841  
     cerebral, 848  
*Pedunculus cerebri*, 848  
 Pelvic colon, 1181  
     diaphragm, 510  
     fascia of, 510  
     fascia, 510  
     endopelvic part of, 512  
     girdle, 301  
     plexuses, 1005  
     portion of sympathetic cord,  
         1001

- Perforating arteries, of hand, 679
  - from internal mammary, 666
  - from plantar, 728
  - from profunda femoris, 717
- cutaneous nerve, 991
- fibres of Sharpey, 54
- Perforator of spermatozoön, 81
- Pericardiac arteries, 664, 685
- Pericardiophrenic artery, 664
- Pericardial area, 87
- pleura, 1095
- Pericardium, 601
  - applied anatomy of, 603
  - diverticula of, 602
  - fibrous, 601
  - nerves of, 603
  - oblique sinus of, 603
  - relations of, 601
  - serous, 602
  - structure of, 601
  - transverse sinus of, 603
  - vessels of, 602
  - vestigial fold of, 603
- Pericecal folds, 1159
  - possæ, 1159
- Perichondrium, 47
- Perilymph, 1061
- Perimysium, 64
- Perineal arteries, 705
  - body, 1184
  - branch of fourth sacral nerve, 992
  - muscle, superficial transverse, 518, 520
  - nerve, 991
- Perineum, boundaries of, 514
  - central tendinous point of, 518
  - lymphatic vessels of, 787
  - muscles of, 514
- Perineurium, 801
- Periosteum, 51
- Peripheral end-organs
  - nervous system, 87

*Organon auditus*, 1043  
*gustus*, 1007  
*olfactorius*, 1008  
*spirale* [Corti's] 1065  
*visus*,  
*Organon* 1:  
*ge*

*Ossa sesamoidea*, 376  
*tarsi*, 362  
*Ossein*, 56  
*Ossicles auditory*, 1053

Ovum, corona radiata of, 78  
 coverings of, 77  
 discharge of, 1246  
 fertilization of, 82  
 focal spot of, 78

Peritoneum, 1149  
 epiploic foramen of, 1155  
 lesser sac of, 1155  
 ligaments, 1156  
 main cavity or greater sac of, 1150  
   horizontal disposition of,  
     in lower abdomen, 1154  
     in pelvis, 1153  
     in upper abdomen, 1154  
     vertical disposition of, 1150  
 mesenteries, 1157  
 omenta, 1156  
 omental bursa of, 1155  
   vertical disposition of, 1152  
 parietal portion of, 1149  
 visceral portion of, 1149  
 Permanent cartilage, 47  
   choanae, 113  
   kidney, 187  
   teeth, 1117  
     development of, 1124  
*Peronaeus brevis* muscle, 583  
*longus* muscle, 582  
*tertius* muscle, 578  
*Peroneal* artery, 726  
   anterior, 726  
   peculiarities of, 726  
   nerve, common, 989  
     applied anatomy of, 993  
     deep, 990  
     superficial, 990  
   retinacula, 585  
   septa, 576  
   tubercle, 165  
*Perpendicular fasciculus*, 891  
   line of ulna, 318  
   plate of ethmoid, 252  
*Pes* or base of cerebral peduncle, 849  
   *hippocampi*, 881  
*Petit*, canal of, 1030  
   triangle of, 124  
*Petrooccipital fissure*, 280  
*Petrosal* nerve, deep, 919  
   external, 997  
   large deep, 919  
     superficial, 919, 931  
   superficial, greater, 919, 931  
   smaller, 1056  
   process, 246  
   sinuses, 736, 746  
*Petrosphenoidal fissure*, 280  
*Petrosquamous* sinus, 743  
   suture, 241, 243  
*Petrotympenic fissure*, 238, 280  
*Petrous* ganglion, 938  
   portion of temporal bone, 241  
*Peyer's* glands, 1175  
   patches, 1175  
*Phalangeal* processes of Corti's  
   rods, 1067  
*Phalanges digitorum manus*, 331  
*Phalangealis*, 373  
   of foot, 373  
     articulations of, 459  
     ossification of, 374  
   of hand, 331  
     articulations of, 431  
     ossification of, 332  
*Pharyngeal* aponeurosis, 1143  
   artery, ascending, 637  
   bursa, 1139  
   bones, 108  
     ne, 163  
   glossopharyngeal,  
   pharyngeal arch,  
   pharyngeal gan-

*Pharyngeal* tubercle, 230, 280  
   veins, 737  
*Pharyngopalatine* arch, 1112  
*Pharyngopalatinus* muscle, 1114  
*Pharynx*, 1138  
   aponeurosis of, 1143  
   applied anatomy of, 1143  
   development of, 168  
   laryngeal part of, 1141  
   lymphatic vessels of, 779  
   mucous coat of, 1143  
   muscles of, 1141  
   nasal part of, 1139  
   oral part of, 1139  
   structure of, 1143  
*Philtrum*, 472  
*Phrenic* artery, inferior, 697  
   superior, 686  
   nerve, 957  
   plexus of nerves, 1003  
   vein, inferior, 764  
     superior, 751  
*Phrenicocolic* ligament, 1157  
*Phrenicocostal* sinus, 1097  
*Phrenicocolic* ligament, 1155  
*Phrenicopericardiac* ligament,  
   right, 762  
*Phylogeny*, 77  
*Pia* of brain, 906  
   of cord, 906  
   mater, cerebral, 906  
     *encephali*, 906  
     *spinalis*, 906  
   spinal, 906  
*Pigment*, 46  
   of iris, 1025  
   of skin, 1074  
*Pigmentary* layer of retina, 1027  
*Pigmented* connective-tissue  
   cells, 46  
   epithelial cells, 46  
*Pili*, 1075  
*Pillars of Corti*, 1065  
   of external abdominal ring, 500  
   of fauces, 1112  
   of fornix, 886, 887  
*Pineal* body, 859  
   development of, 859  
   structure of, 860  
   eye of lizards, 860  
   recess, 127, 865  
*Pinna*, 1044  
   cartilage of, 1044  
   ligaments of, 1044  
*Piriformis* muscle, 571  
   fascia of, 511  
*Pisiform* bone, 326  
*Pisohamate* ligament, 427  
*Pisometacarpal* ligament, 427  
*Pits*, olfactory, 111  
*Pituitary* body, 861  
*Pivot-joint*, 382  
*Placenta*, 100  
   circulation through, 101, 616  
   cotyledons of, 101  
   fetal portion of, 100  
   maternal portion of, 100  
   previa, 101  
   separation of, 101  
*Plain* muscle, 67  
*Plane*, intertubercular, 1147  
   subcostal, 1147  
   transpyloric, 1147  
*Plantar* aponeurosis, 586  
   arch, 727  
     applied anatomy of, 728  
     arteries, 727  
   cutaneous venous arch, 756  
   net-work, 728

*Plantaris* muscle, 579  
*Planum nile*, 227  
*occipital*, 27  
*Plasma* cell  
*Plate* or *Pl.* cribriform, of eth.  
   moidal, 2  
   ethmoidal, 207  
   orbital, conal, 285  
   perpendicular, of ethmoidal,  
     252  
   pterygoid sphenoidal, 250  
   tarsal, 10  
*Platelets* of od, 64  
*Platysma* m. 475  
*Pleura*, 1092  
   applied anatomy of 1098  
   cavity of, 15  
   cervical, 15  
   costal, 108  
   cupula of, 95  
   diaphragm, c, 109  
   lymphatic vessels of, 800  
   mediastinal, 095  
   nerves of, 17  
   parietal, 10  
   pericardial, 95  
   pulmonary, 095  
   reflections of 1095  
   structure of 097  
   surface markings of 1297  
   vessels of, 17  
*Plexiform* layer of retina, 1028  
*Plexus*, aortic abdominal, 1004  
   Auerbach's, 176  
   basilar, 746  
   brachial, 958  
   cardiac, 1001  
   carotid, internal, 96  
   cavernous, 96  
   cervical, 954  
     posterior, 61  
   choroid of fourth ventricle, 84  
   of lateral ventricle, 887  
   of third ventricle, 864  
   coccygeal, 992  
   coeliac, 1002  
   of cornea, 102  
   coronary, 1002, 100  
   of Exner, 893  
   gastric, 1004  
   hemorrhoidal, 100  
   venous, 761  
   hepatic, 1004  
   hypogastric, 1035  
   infraorbital, 919  
   lienal, 1004  
   lumbar, 975  
   lumbosacral, 974  
   Meissner's, 1176  
   mesenteric, 1004, 100  
   myenteric, 1176  
   oesophageal, 943  
   ovarian, 1004  
   parotid, 930  
   patellar, 979, 9  
   pelvic, 1005  
   pharyngeal, 943  
   phrenic, 1003  
   prostatic, 100  
   pudendal, 9  
   venous,  
   pulmonary,  
   renal, 100  
   sacral, 98  
   solar, 1002  
   spermatic, 10  
   splenic, 1004  
   of submucosa  
   subhepatic, 10

- Plexus of veins, vesicoprostatic, 761  
 vesical, 1005  
 venous, 761  
*Plexus aorticus abdominalis*, 1004  
*arteriae ovaricae*, 1004  
*brachialis*, 958  
*cardiacus*, 1001  
*caroticus internus*, 996  
*cavernosus*, 996  
*cervicalis*, 954  
*ramus anterior*, 956  
*posterior*, 957  
*chorioideus ventriculi lateralis*, 887  
*tertii*, 888  
*coeliacus*, 1002  
*coronarius anterior*, 1002  
*posterior*, 1002  
*gastricus superior*, 1004  
*hepaticus*, 1004  
*hypogastricus*, 1005  
*lienalis*, 1004  
*lumbalis*, 975  
*lumbosacralis*, 974  
*mesentericus inferior*, 1005  
*phrenicus*, 1003  
*prostaticus*, 1005  
*puddendus*, 991  
*renal*, 1004  
*sacralis*, 982  
*spermaticus*, 1004  
*suprarenalis*, 1004  
*trunci basilaris*, 746  
*haemorrhoidalis*, 761  
*pterygoideus*, 734  
*puddendus*, 761  
*vertebrales externi*, 754  
*interni*, 755  
*vesicalis*, 761  
*Plica circulares* [Kerkringi], 1173  
*fimbriata* [tongue], 1126  
*gubernatrix*, 186  
 lacrimalis of Hasner, 1042  
*semilunaris* [conjunctiva], 1041  
 [tonsil], 1140  
*sublingualis*, 1137  
*triangularis* [tonsil], 1140  
*vascularis*, 186  
*ventriculares* [laryngis], 1085  
*vesicalis transversa*, 1153  
*Plicae uretericae*, 1222  
 vocales, 1086  
 Pneumogastric nerve, 940  
 Polar bodies or polocytes, 79  
 Poles of cerebral hemispheres, 867  
 of eyeball, 1017  
 of lens, 1031  
 Polymorphonuclear leucocytes, 62  
 Polyspermy, 83  
*Pomum Ad. Al. Pasco.*  
*Pons*, 833  
 applied anat., 836  
 development of, 124  
 hepatis, 1194  
 structure of, 834  
 Varoli, 833  
*Ponticulus* [auricula], 1044  
 Pontine arteries, 661  
 Popliteal artery, 718  
 applied anatomy of, 719  
 branches of, 720  
 Paries., 719  
 marking of, 1331  
*Parolfact.*, 718  
*Paroöphorol.*, 718  
 Parotid duct, 1157  
 gland, 1133  
 accessory pa., 989  
 applied anat., 989  
 nerves of, 113, 348  
 structure of, 581  
 surface mar., 581  
 Pore, gustatory, 1007  
 Porta of liver, 1194  
 Portal vein, 764  
 applied anatomy of, 767  
 development of, 764  
 Position of pelvis, 342  
 Postanal gut, 174  
 Postaxial borders of limbs, 114  
 Postcentral sulcus, 870  
 Postcornu, 879  
 Posterior annular ligament, 550  
 calcaneostragaloid ligament, 453  
 circumflex artery, 671  
 common ligament, 385  
 cornu of medulla spinalis, 809  
 costotransverse ligament, 399  
 cricoarytenoid muscle, 1088  
 deep cervical vein, 738  
 dental artery, 641  
 inferior ligament, 448  
 interosseous artery, 681  
 nerve, 970  
 ligament, 426  
 pillar of fauces, 1112  
 pulmonary nerves, 943  
 radial carpal artery, 678  
 radioulnar ligament, 424  
 sacrosciatic ligament, 404  
 scapular artery, 664  
 nerve, 960  
 superior ligament, 448  
 talotibial ligament, 450  
 temporal artery, 638  
 ulnar carpal artery, 682  
 vertebral vein, 738  
 Postero-inferior lobule, 839  
 Postero-lateral ganglionic arteries, 662  
 Postero-medial ganglionic arteries, 653, 662  
 Postero-superior lobule, 838  
 Postgemina, 854  
 Postnodular fissure, 838  
 Postpartum hemorrhage, 101  
 Postpyramidal fissure, 839  
 Postsphenoid part of sphenoid, 251  
 Pott's fracture, 593  
 Pouch of Douglas, 1151  
 of Prussak, 1055  
 of Rathke, 166  
 Pouches, pharyngeal, 108  
 Poupart's ligament, 502  
*Praeputium clitoridis*, 1257  
 Preauricular lymph glands, 775  
 point, 1279  
 sulcus of ilium, 335, 336  
 Preaxial borders of limbs, 114  
 Precentral gyre, 869  
 sulcus, 869  
 Prechordal portion of base of fetal skull, 106  
 Preclival fissure, 869  
 Precommissure, 887  
 Precornu, 878  
 Precuneus, 871  
 Pregemina, 854  
 Pregnancy, abdominal, 83  
 ovarian, 83  
 tubal, 83  
 Premaxilla, 261  
 Premolar teeth, 1118  
 Preoccipital notch, 867  
 Prepatellar bursa, 566  
 Prepuce of clitoris, 1257  
 of penis, 1239  
 development of, 190  
 Preputial glands, 1239  
 sac, 1239  
 Prepyramidal fissure, 838, 839  
 tract, 816  
 Presphenoid, 251  
 Pressure epiphyses, 59  
 Presternal notch, 217  
 Pretracheal fascia, 477  
 Prevertebral fascia, 477  
 part of base of skull, 106  
 Prickle cells, 39  
 Primary areolae of bone, 59  
 oocytes, 77  
 spermatocytes, 82  
 Primitive aortae, 143  
 atrium, 145, 149  
 costal arches, 104  
 digestive tube, 92  
 fibrillae of Schultze, 74  
 groove, 86  
 jugular veins, 157  
 ova, 184  
 palate, 112  
 segments, 91  
 sheath of nerve fibre, 75  
 streak, 86  
 urogenital ostium, 190  
 ventricle of heart, 145  
 Princeps cervicis artery, 636  
 pollicis artery, 678  
*Prismata adamantina*, 1120  
 Proammon, 87  
 Procerus muscle, 469  
 Process or Processes, accessory, of vertebrae, 205  
 alveolar, 260  
 articular, of vertebrae, 197  
 ciliary, 1023  
 clinoid, anterior, 249, 290  
 middle, 246, 290  
 posterior, 246, 290  
 condyloid, of mandible, 273  
 coracoid, 307  
 coronoid, of mandible, 273  
 of ulna, 315  
 costal, 199  
 descending, of lacrimal, 263  
 of dura mater, 900  
 ethmoidal, of inferior nasal concha, 268  
 frontal, of maxilla, 260  
 frontonasal, 111  
 frontosphenoidal, of zygomatic, 264  
 globular, of His, 111  
 intrajugular, 230  
 jugular, 230, 281  
 lacrimal, of inferior nasal concha, 268  
 lateral nasal, 111  
 lenticular, of incus, 1055  
 malar, of maxilla, 260  
 mamillary, of vertebrae, 205  
 mastoid, 239  
 maxillary, of fetus, 112  
 of inferior nasal concha, 268  
 of palatine bone, 267  
 of zygomatic bone, 265  
 muscular, of arytenoid, 1081  
 nasal, of frontal bone, 235  
 of maxilla, 260  
 odontoid, of axis or epistropheus, 200  
 orbital, of palatine bone, 267  
 of zygomatic bone, 264  
 palatal, of maxilla, 260  
 palatine, of fetus, 112  
 of maxilla, 260  
 papillary, of liver, 1194  
 paramastoid, 230  
 petrosal, 246  
 phalangeal, of Corti's rods, 1067  
 pterygoid, of sphenoidal bone, 250  
 pyramidal, of palatine bone, 267, 278  
 sphenoidal, of palatine bone, 268  
 of septal cartilage of nose, 1009  
 turbinated, 250  
 spinous, of ilium, 336



- Process or Processes, spinous, of  
vertebræ, 197  
styloid, of fibula, 359  
of radius, 321  
of temporal bone, 244, 280  
of ulna, 319  
temporal, of zygomatic, 265  
transverse, of vertebræ, 197  
trochlear, of calcaneus, 365  
uncinate, of ethmoid, 253  
vaginal, of sphenoid, 250  
of temporal, 243, 244  
vermiform, 1178  
vocal, of arytenoid, 1081  
xiphoid, 220  
zygomatic, of frontal, 235  
of maxilla, 260  
of temporal bone, 237
- Processus alveolaris* [maxillæ], 260  
*brevis* [malleus], 1054  
*ciliare*, 1023  
*cochleariformis*, 243, 1052  
*condyloideus* [mandibulæ], 273  
*coracoideus* [scapulæ], 307  
*coronoideus* [mandibulæ], 273  
[ulnare], 315  
*frontalis* [maxillæ], 260  
*gracilis* [malleus], 1053  
*orbitalis* [os palatinum], 267  
*palatinus* [maxillæ], 260  
*pterygoidei*, 250  
*pyramidalis* [os palatinum], 267  
*spinous*, 197  
*splenoidalis* [os palatinum], 268  
*transversi*, 197  
*tubarius*, 250  
*vermiformis*, 1178  
*xiphoides*, 220  
*zygomaticus*, 260
- Proctodeum, 174  
Prodentin, 1124  
Profunda arteries, 674  
brachii artery, 674  
cervicalis artery, 666  
femoris artery, 716  
vein, 759  
linguae artery, 632  
Projection fibres of cerebral hemispheres, 889  
Prominence of aqueduct of Fallopius, 1051  
of facial canal, 1051  
laryngeal, 1080  
*Prominentia canalis facialis*, 1051  
*Promontorium*, 1051  
Promontory of tympanic cavity, 1051  
Pronator quadratus muscle, 540  
teres muscle, 537  
Pronephric duct, 180  
Pronephros, 180  
Pronucleus, female, 80  
male, 83  
Proötic centre of temporal bone, 244  
Prophase of karyokinesis, 35  
Prosencephalon, 88, 125, 855  
*Prostata*, 1241  
*facies anterior*, 1241  
*posterior*, 1241  
Prostate, 1241  
applied anatomy of, 1242  
development of, 189  
gland, 1241  
lobes of, 1241  
lymphatic vessels of, 794  
nerves of, 1242  
structure of, 1241  
vessels of, 1242  
Prostatic ducts, orifices of, 1225  
plexus of nerves, 1005  
portion of urethra, 1225  
sinus, 1225  
utricle, 1225
- Prosthion, 296  
Prothrombin, 64  
Protoplasm, 33  
Protoplasmic process of nerve cells, 72  
Protuberance, mental, 271  
occipital, 227, 228, 282  
Prussak, pouch of, 1055  
Psalterium, 886  
Pseudocele, 887  
Pseudonucleoli, 34  
Pseudopodium, 63  
Psoas magnus muscle, 560  
major muscle, 560  
applied anatomy of, 562  
fascia covering, 559  
minor muscle, 561  
parvus muscle, 561  
Pterion, 249, 282, 296  
ossicle, 255  
Pterotic centre of temporal bone, 245  
Pterygoid canal, 250, 278  
fissure, 250  
fossa of sphenoid, 250  
hamulus, 250, 278  
muscles, 474  
plates, 250  
plexus of veins, 734  
processes of sphenoid, 250  
tubercle, 250  
Pterygoidei muscles, dissection of, 474  
Pterygoideus externus muscle, 474  
internus muscle, 474  
Pterygomandibular ligament, 471  
raphe, 471  
Pterygomaxillary fissure, 284  
Pterygopalatine canal, 258, 267  
fossa, 284  
groove, 250  
nerve, 921  
Pterygospinous ligament, 251, 477  
Pubic arch, 341  
bones, articulation of, 406  
ligaments, 407  
region, 1147  
tubercle or spine, 338  
vein, 760  
Pubis, 337  
angle of, 338  
body of, 337  
crest of, 338  
iliopectineal eminence of, 338  
obturator crest of, 338  
rami of, 337  
symphysis of, 406  
tubercle or spine of, 338  
Pubocapsular ligament, 433  
Pubococcygeus muscle, 514  
Pubofemoral ligament, 433  
Puborectalis muscle, 514  
Pubovesicales muscles, 1221  
Pudendal artery, accessory, 704  
external, 761  
internal, in female, 706  
in male, 703  
cleft or rima, 1170  
nerve, 991  
inferior, 985  
plexus, nervous, 991  
venous, 761  
veins, internal, 760  
Pudendum, 1256  
Pudic arteries, external, 716  
internal, 703  
nerve, internal, 991  
veins, internal, 760  
Pulmonary artery, 620  
applied anatomy of, 621  
opening of, in right ventricle, 609  
ligaments, 1095, 1097
- Pulmonary nerves, 943  
pleura, 1095  
semilunar valves, 610  
veins, 730  
openings of, in left atrium, 611  
*Pulmones*, 1101  
*facies costalis*, 1102  
*mediastinalis*, 1102  
*margo anterior*, 1104  
*inferior*, 1103  
*posterior*, 1103  
Pulp cavity of teeth, 1119  
dental, 1119  
of spleen, 1267  
Pulvinar, 855  
Puncta lacrimalia, 1041  
vasculosa, 875  
Pupil, 1024  
congenital atresia of, 136  
Pupillary membrane, 136, 1026  
Purkinje, cells of, 842  
fibres of, 69  
Putamen, 882  
Pyloric antrum, 1162, 1163  
artery, 689  
glands, 1166  
orifice of stomach, 1162  
part of stomach, 1162, 1163  
valve, 1164  
vein, 766  
Pyramid, 1052  
of cerebellum, 839  
of medulla oblongata, 823  
of temporal bone, 241  
of vestibule, 1058  
Pyramidal cells of cerebral cortex, 891  
decussation, 823  
eminence of tympanic cavity, 1052  
lobe of thyroid gland, 1261  
process of palatine bone, 267, 278  
tract, crossed, 815  
direct, 815  
Pyramidalis muscle, 507  
nasi muscle, 469  
Pyramids, renal, 1210  
*Pyramis medullæ oblongatæ*, 823

## Q

- QUADRATE lobe of liver, 1195  
Quadratus femoris muscle, 573  
labii inferioris muscle, 470  
superioris muscle, 469  
lumborum muscle, 510  
fascia covering, 510  
menti muscle, 470  
plantæ muscle, 589  
Quadriceps extensor muscle, 565  
femoris muscle, 565  
Quadrigeminal bodies, 853

## R

- RADIAL artery, 676  
applied anatomy of, 676  
branches of, 678  
carpal, 678  
peculiarities of, 676  
recurrent, 678  
surface marking of, 1322  
fibres of cerebral cortex, 893  
fossa, 312  
nerve, 968  
sulcus, 311  
tuberosity, 320  
Radialis indicis artery, 679  
Radiate ligament, 396  
sternocostal ligaments, 399  
Radiocarpal articulation, 425

- Radiocarpal articulation**, applied anatomy of, 426  
movements of, 426
- Radioulnar articulation**, distal, 423  
movements of, 425  
proximal, 422  
movements, 423  
ligaments, 424  
union, middle, 423
- Radius**, 319  
applied anatomy of, 321  
articulations of, 321  
grooves on lower end of, 321  
oblique line of, 320  
ossification of, 321  
sigmoid cavity of, 321  
structure of, 321  
surface anatomy of, 1314  
tuberosity of, 320  
ulnar notch of, 321
- Radix arcus vertebræ**, 197  
*linguae*, 1126  
*penis*, 1239  
*pili*, 1075  
*pulmonis*, 1105
- Rami communicantes**, 949, 950, 995  
of ischium, 337  
of pubis, 337
- Ramus inferior ossis ischii**, 337  
*pubis*, 338  
of mandible, 272  
*mandibulae*, 272  
*superior oss. ischii*, 337  
*pubis*, 337
- Ranine artery**, 632  
vein, 736
- Ranvier**, crosses of, 75  
nodes of, 75
- Raphé**, anococcygeal, 516  
lateral palpebral, 468  
of medulla, 822  
of palate, 1112  
pterygomandibular, 471  
of scrotum, 1228
- Rathke**, pouch of, 166
- Receptaculum chyli**, 772
- Recess**, epitympanic, 240, 1049  
nasopalatine, 1012  
omental, 1156  
optic, 865  
pharyngeal, 1139  
pineal, 127, 865  
sphenothmoidal, 293, 1010
- Recesses**, lateral, of fourth ventricle, 845  
peritoneal, 1157  
of Trötsch, 1055
- Recessus ellipticus**, 1058  
*infundibuli*, 864  
*intersigmoideus*, 1160  
*pinealis*, 127, 865  
*saciformis*, 425  
*sphaericus*, 1058  
*suprapinealis*, 865
- Reciprocal reception**, articulation by, 382
- Rectal ampulla**, 1183  
columns of Morgagni, 1184  
layer of pelvic fascia, 513
- Rectococcygeal muscles**, 1185
- Rectouterine folds**, 1250
- Rectovesical excavation**, 1151  
folds, 1153  
layer of pelvic fascia, 512
- Rectovesicales muscles**, 1221
- Rectum**, 1182  
ampulla of, 1183  
anal part of, 1184  
development of, 172  
Houston's valves of, 1183  
lymphatic vessels of, 792  
relations of, 1183  
surgical anatomy of, 1190
- Rectus abdominis muscle**, 506  
dissection of, 505  
sheath of, 506  
*capitis anterior muscle*, 484  
*anticus major muscle*, 484  
*minor muscle*, 484  
*lateralis muscle*, 484  
*posterior major muscle*, 491  
*minor muscle*, 491  
*femoris muscle*, 565  
muscles of eyeball, 1035
- Recurrent artery**, interosseous, 682  
radial, 678  
tibial, 722, 723  
ulnar, 680  
branches from deep volar arch, 679  
laryngeal nerve, 942  
nerve, 942
- Red corpuscles**, 61  
nucleus, 850
- Reflected inguinal ligament**, 502
- Reflections of pleurae**, 1095
- Refracting media of eye**, 1030
- Region**, iliac, 1147  
lumbar, 1147  
pubic, 1147
- Regions of abdomen**, 1147
- Reil**, island of, 873
- Reissner**, vestibular membrane of, 1063
- Renal arteries**, 696  
columns, 1211  
fascia, 1209  
impression, 1192  
pelvis, 1210, 1216  
plexus, 1004  
pyramids, 1210  
sinus, 1210  
tubules, 1212  
veins, 764  
vessels, afferent and efferent, 1212, 1214
- Renes**, 1206  
*extremilas inferior*, 1209  
*superior*, 1209  
*facies anterior*, 1207  
*posterior*, 1208  
*margo lateralis*, 1209  
*medialis*, 1209  
*substantia corticalis*, 1211  
*medullaris*, 1210  
*vascula glomerulus*, 1212
- Reproduction of cells**, 34
- Respiration**, mechanism of, 497
- Respiratory apparatus**, 1079  
development of, 177  
nerve of Bell, 957, 960  
system, 1079
- Restiform bodies of medulla**, 841
- Rete canalis hypoglossi**, 746  
*foraminis ovalis*, 747  
*testis*, 1233
- Retia venosa vertebrarum**, 755
- Reticular lamina**, 1067  
layer of skin, 1074  
tissue, 44
- Reticularis alba**, 833  
*grisea*, 833
- Retiform tissue**, 44
- Retina**, 1026  
central artery of, 650  
development of, 135  
*fovea centralis*, 1026  
layers of, 1027  
*macula lutea*, 1026  
*membrana limitans interna*, 1029  
*externa*, 1029  
*ora serrata*, 1026  
structure of, 1027  
supporting frame-work of, 1029
- Retinacula of hip-joint**, 432  
patellar, 439
- Retinacula peroneal**, 585
- Retrahens aurem muscle**, 1045
- Retrocecal fossa**, 1160
- Retroglandular sulcus of penis**, 1239
- Retroperitoneal fossæ**, 1157
- Retropharyngeal lymph glands**, 776  
space, 477
- Retropubic pad**, 1219
- Retzius**, colored lines of, 1121
- Rhinal fissure**, external, 128
- Rhinencephalon**, 128, 874
- Rhodopsin**, or visual purple, 46, 1026
- Rhombencephalon**, 90, 122, 821
- Rhombic grooves**, 124  
lip, 123
- Rhomboid fossa**, 847  
impression, 303  
ligament, 410
- Rhomboideus major muscle**, 525  
*minor muscle*, 525
- Rhomboids**, nerve to, 960
- Ribs**, 220  
applied anatomy of, 179  
common characteristics of, 221  
development of, 104  
false, 220  
floating or vertebral, 221  
ossification of, 224  
peculiar, 223  
structure of, 224  
true, 220  
vertebrochondral, 221  
vertebrosternal, 220
- Ridge**, ganglion, 88, 120  
supracondylar, lateral, 311  
medial, 312  
trapezoid or oblique, 302
- Ridges**, bicipital, 311
- Right atrium**, dissection of, 607  
auricle, 606  
auricular appendix, 606  
coronary plexus, 1002  
veins, 730  
gastroepiploic glands, 788  
ventricle, dissection of, 609
- Rima glottidis**, 1087  
of mouth, 1110  
*palpebrarum*, 1038  
pudendal, 1256
- Ring**, abdominal, external, 500  
internal, 508  
femoral, 712  
inguinal, abdominal, 508  
subcutaneous, 500  
tympanic, 245
- Rings**, fibrous, of heart, 613
- Risorius muscle**, 472
- Rivinus**, ducts of, 1137  
notch of, 1049
- Rod-bipolars of retina**, 1028
- Rod-granules of retina**, 1029
- Rods and cones**, layer of, 1029  
of Corti, 1065  
of retina, 1029
- Rolando**, fissure of, 868  
substantia gelatinosa of, 809  
tubercle of, 825
- Roller**, nucleus of, 833
- Roof plate**, 117
- Root of lung**, 1105  
of penis, 1239
- Root-sheaths of hair**, 1077
- Roots of spinal nerves**, 818, 948  
of teeth, 1116  
of zygomatic process, 237
- Rosenmüller**, fossa of, 1138, 1139  
lymph gland of, 783  
organ of, 181, 1244
- Rostrum of corpus callosum**, 876  
sphenoidal, 247
- Rotary joint**, 382
- Rotation**, movement of, 383

Rotatores muscles, 490  
 spinæ muscle, 490  
 Round ligament of liver, 1195  
 of uterus, 1251  
 Ruffini, corpuscles of, 1070  
 Rust-colored layer of cerebellar  
 cortex, 843

## S

- Sac, dental, 1123  
 lacrimal, 1041  
 of peritoneum, greater, 1150  
 lesser, 1152  
 preputial, 1239  
 Saccule, laryngeal, 1086  
 of vestibule, 1062  
*Sacculus*, 1062  
*Saccus lacrimalis*, 1042  
*vaginalis*, 186  
 Sacral arteries, lateral, 707  
 artery, middle, 698  
 canal, 208  
 cornua, 207  
 crests, 207, 208  
 foramina, 206, 208  
 groove, 207  
 hiatus, 207  
 lymph glands, 787  
 nerves, divisions of, anterior,  
 982  
 posterior, 953  
 nucleus of medulla spinalis, 813  
 plexus, 982  
 applied anatomy of, 992  
 tuberosity, 208  
 veins, 760, 762  
 Sacrococcygeal ligaments, 406  
 Sacrogenital folds, 1153, 1250  
 Sacroiliac articulation, 404  
 ligaments, 404, 405  
 Sacrosciatic ligaments, 404, 405  
 Sacrospinalis muscle, 480  
 Sacrovertebral angle, 206  
 Sacrum, 206  
 ala of, 208  
 apex of, 208  
 articulations of, 208  
 auricular surface of, 208  
 base of, 208  
 ossification of, 212  
 structure of, 208  
 variations of, 209  
 Saddle-joint, 382  
 Sagittal fossa of liver, 1194  
 sinus, inferior, 741  
 superior, 740  
 sulcus, 228, 232, 235  
 suture, 232, 277  
 Salivary glands, 1133  
 development of, 164  
 parotid, 1133  
 structure of, 1137  
 sublingual, 1135  
 submaxillary, 1135  
 Salpingopalatine fold, 1139  
 Salpingopharyngeal fold, 1139  
 Salpingopharyngeus muscle, 1143  
 Salter, incremental lines of, 1120  
 Santorini, cartilages of, 1081  
 duct of, 1205  
 Saphenous nerve, 981  
 external, 988  
 internal, 981  
 long, 981  
 short, 988  
 opening, 564  
 veins, 756, 757  
 applied anatomy of, 757  
 Sarcolemma, 64  
 Sarcomere, 66  
 Sarcoplasm, 65  
 Sarcostyles, 65  
 Sarcous elements of muscles, 66  
 Sartorius muscle, 565  
*Scala media* [cochlea], 1063  
*tympani*, 1060  
*vestibuli*, 1060  
 Scalene tubercle, 224  
 Scalenus anterior muscle, 484  
 anticus muscle, 484  
 medius muscle, 484  
 posterior muscle, 485  
 posticus muscle, 485  
 Scalp, applied anatomy of, 466  
 lymphatic vessels of, 776  
 muscles of, dissection of, 464  
 skin of, 465  
 Scapha, 1044  
 Scaphoid bone, 323, 368  
 fossa of sphenoid, 250, 278  
 Scapula, 304  
 acromion of, 306  
 applied anatomy of, 309  
 articulations of, 309  
 coracoid process of, 307  
 glenoid cavity of, 307  
 ligaments of, 412  
 ossification of, 308  
 spine of, 306  
 structure of, 308  
 surface anatomy of, 1313  
 surfaces of, 304, 305  
 Scapular arteries, 663, 664  
 circumflex artery, 671  
 nerve, posterior, 960  
 notch, 307  
 Scapuloclavicular articulation,  
 411  
 Scapus or shaft of hair, 1077  
*pili*, 1077  
 Scarpa, fascia of, 499  
 foramina of, 261, 278  
 ganglion of, 1068  
 triangle of, 712  
 Schindylesis, 381  
 Schlemm, canal of, 1018  
 Schreger, lines of, 1120  
 Schultze, primitive fibrillæ of, 74  
 Schwann, white matter of, 75  
 Sciatic artery, 706  
 foramen, 406  
 nerve, 985  
 applied anatomy of, 993  
 small, 985  
 notch, 336  
 veins, 760  
 Sclera, 1017  
 structure of, 1018  
 Scleral spur, 1019  
 Scleratogenous layer, 102  
 Sclerocorneal junction, 1018  
 Sclerotome, 102  
 Scrotal arteries, posterior, 705  
 nerves, posterior, 991  
 Scrotum, 1228  
 applied anatomy of, 1230  
 dartos tunic of, 1229  
 integument of, 1228  
 nerves of, 1229  
 raphe of, 1228  
 vessels of, 1229  
 Sebaceous glands, 1078  
 Second cuneiform bone, 369  
 metacarpal bone, 329  
 metatarsal bone, 372  
 nerve, 909  
 Secondary areolæ of bone, 58  
 dentin, 1121  
 oöcytes, 80  
 sensory fasciculus, 817  
 spermatocytes, 82  
 tympanic membrane, 1051  
 Secretion, internal, 1260  
 Segment, internodal, 75  
 of Lantermann, 75  
 medullary, 75  
 Segmentation of cells, 34  
 of fertilized ovum, 84  
 Segmentation nucleus, 84  
 Segments, primitive, 91  
 spinal, 806  
*Sella turcica*, 246, 290  
*Semicanalis m. tensoris tympani*,  
 243, 1052  
*tubæ auditivæ*, 243, 1052  
 Semicircular canals, bony, 1058  
 membranous, 1062  
 ducts, 1062  
 structure of, 1063  
 Semilunar bone, 323  
 fibrocartilages of knee, 441, 442  
 ganglion of abdomen, 1002  
 of trigeminal nerve, 914  
 lobules of cerebellum, 838, 839  
 Semimembranosus muscle, 575  
 Seminal duct, 1235  
 vesicles, 1236  
 Semispinalis capitis muscle, 489  
 cervicis muscle, 489  
 colli muscle, 489  
 dorsi muscle, 489  
 Semitendinosus muscle, 575  
 Sensations, general, peripheral  
 terminations of nerves of,  
 1069  
 Senses, organs of, 1007  
 development of, 117  
 special, peripheral organs of,  
 1007  
 Sensory areas of cerebral cortex,  
 894  
 decussation, 827  
 neurons, lower and upper, 896,  
 897  
 tract, 897  
 Separation of embryo, 92  
 Septum, aortic, 150  
*canalis musculotubarii*, 243,  
 1052  
 crural, 712  
*femorale*, 712  
 inferius of heart, 149  
*intermedium*, 148  
 interventricular, 612  
*lucidum*, 887  
*mobile nasi*, 1009  
*nasi*, 293  
 of nose, 293, 1012  
 orbital, 1039  
*pectiniforme penis*, 1238  
*pellucidum*, 887  
 cavity of, 887  
*primum*, 149  
*secundum*, 149  
*spurium*, 146  
 subarachnoid, 905  
 of tongue, 1132  
*transversum*, 178  
 of semicircular ducts, 1063  
 urorectal, 172  
 ventricular, 149, 612  
*ventriculorum*, 612  
 Serosa, or false amnion, 96  
 Serous glands of tongue, 1131  
 pericardium, 602  
 Serratus anterior muscle, 529  
 magnus muscle, 529  
 posterior inferior muscle, 493  
 superior muscle, 493  
 posticus inferior muscle, 493  
 superior muscle, 493  
 Sertoli, cells of, 1233  
 Sesamoid bones, 376  
 cartilages, 1009  
 Seventh nerve, 929  
 Shaft of hair, 1077  
 Sheath or Sheaths of arteries, 597  
 carotid, 477  
 crural, 710  
 dental, of Neumann, 1120  
 femoral, 710  
 fibrous, of flexor tendons, 540  
 of flexor tendons of fingers, 540

- Sheath or Sheaths of flexor tendons of toes, 588  
 mucous, 380  
 of tendons around ankle, 586  
 on back of wrist, 550  
 in front of wrist, 548  
 of rectus abdominis muscle, 506
- Shin bone, 355
- Short bones, 196  
 calcaneocuboid ligament, 454  
 gastric veins, 766  
 plantar ligament, 454  
 saphenous nerve, 988  
 vein, 757
- Shoulder blade, 304  
 girdle, 301  
 muscles of, 530  
 dissection of, 530, 531
- Shoulder-joint, 414  
 applied anatomy of, 417  
 bursa near, 415  
 movements of, 416  
 vessels and nerves of, 416
- Sibson's fascia, 1096
- Sight, organ of, 1017
- Sigmoid arteries, 695  
 cavity of radius, 321  
 of ulna, 315, 318  
 colon, 1181  
 flexure, 1181  
 mesocolon, 1153  
 sinus, 743  
 sulcus, 240
- Simple epithelium, 36  
 papillæ of tongue, 1128
- Sinuses or Sinuses, accessory, of nose, 1014  
 aortic, 612  
 basilar, 746  
 cavernous, 744  
 cervicalis, 110  
 circular, 746  
 confluence of, 743  
 coronary, 730  
 costomediastinal, 1097  
 cranial, 234 *note*  
 of dura mater, 740  
 of epididymis, 1231  
 of external jugular vein, 735  
 frontal, 235, 1014  
 intercavernous, 746  
 laryngeal, 1086  
 lateral, 742  
 longitudinal, superior, 740, 741  
 maxillary, 259, 1015  
 of Morgagni, 1142  
 occipital, 743  
 of pericardium, 603  
 petrosal, 746  
 petrosquamous, 743  
 phrenicocostal, 1097  
 pocularis, 1225  
 prostatic, 1225  
 pyriformis, 1141  
 renal, 1210  
 rhomboidalis, 88  
 sagittal, 740, 741  
 septum, 146  
 sigmoid, 743  
 sphenoidal, 247, 1014  
 sphenoparietal, 744  
 straight, 741  
 tentorial, 742  
 tonsillaris, 111  
 transverse, 742, 746  
 urogenital, 188  
 of Valsalva, 610, 612  
 venarum, 606  
 venosus, 145
- Sinus or Sinuses, cavernosus, 744*  
 coronarius, 730  
 duræ matriæ, 740  
 frontales, 1014  
 intercavernosi, 746  
 maxillaris, 295, 1015
- Sinus or Sinuses, occipitalis, 743*  
 paranasales, 1014  
 petrosus inferior, 736, 746  
 superior, 746  
 rectus, 741  
 sagittalis inferior, 741  
 superior, 740  
 sphenoidales, 1014  
 tarsi, 362, 367  
 transversus, 742  
 venosus, 606  
 sclerae, 1018
- Sinusoids of Minot, 599
- Sixth nerve, 927
- Skein, or spirem, 35  
 coccygeal, 1273
- Skeins, carotid, 1273
- Skeletal muscular tissue, 64
- Skeleton, 195  
 development of, 102
- Skene's duct, 190
- Skin, 1071  
 appendages of, 1075  
 hairs, 1075  
 nails, 1075  
 sebaceous glands, 1078  
 sudoriferous or sweat glands, 1078  
 arteries of, 1074  
 corium or cutis vera, 1074  
 development of, 116  
 epidermis or cuticle, 1071  
 furrows of, 1072  
 nerves of, 1074  
 papillary layer of, 1074  
 reticular layer of, 1074  
 of scalp, dissection of, 465  
 stratum corneum, 1072  
 mucosum, 1072  
 true, 1074
- Skull, 226  
 applied anatomy of, 297  
 development of, 105  
 differences in, due to age, 294  
 diseases of, 298  
 exterior of, 277  
 fossa of, anterior, 288  
 middle, 290  
 posterior, 291  
 interior of, 288  
*norma basalis, 278*  
*frontalis, 285*  
*lateralis, 281*  
*occipitalis, 284*  
*verticalis, 277*  
 sexual differences in, 295  
 surface anatomy of, 1275  
 tables of, 196  
 upper surface of base of, 288
- Skull-cap, inner surface of, 288
- Slightly movable joints, 381
- Small cardiac vein, 730  
 cavernous nerves, 1005  
 intestine, 1168  
 areolar or submucous coat of, 1173  
 circular folds of, 1173  
 duodenum, 1169  
 glands of, 1175  
 ileum, 1171  
 jejunum, 1171  
 lymphatic nodules of, aggregated, 1175  
 solitary, 1175  
 vessels of, 792
- Meckel's diverticulum of, 1178
- mucous membrane of, 1173
- muscular coat of, 1173
- nerves of, 1176
- Peyer's glands of, 1175
- serous coat of, 1172
- valvulae conniventes of, 1173*
- vessels of, 1176
- villi of, 1173
- Small saphenous vein, 757  
 sciatic nerve, 985  
 wings of sphenoid, 249
- Smaller occipital nerve, 956
- Smallest cardiac veins, 731
- Smell, organ of, 1008
- Soft palate, 1112  
 aponeurosis of, 1112  
 arches or pillars of, 1112  
 muscles of, 1113
- Solar plexus, 1002
- Sole of foot, muscles of, first layer, 587  
 fourth layer, 590  
 second layer, 589  
 third layer, 589
- Soleus muscle, 579
- Solitary cells of medulla spinalis, 813  
 glands, 1175
- Somatic cells, 77  
 fibres of spinal nerves, 950  
 layer of mesoderm, 88
- Somatopleure, 88
- Space or Spaces, of angle of iris, 1021  
 of Burns, 477  
 corneal, 1020  
 epidural, 993  
 interpleural, 1098  
 of Fontana, 1021  
 intercostal, 221  
 interglobular, 1120  
 of Nuel, 1067  
 popliteal, 718  
 retropharyngeal, 477  
 of Retzius, 1224  
 subarachnoid, 904  
 suprasternal, 477
- Spatia zonularis, 1030*
- Spatium perichorioidale, 1017*
- Special dental germ, 1122  
 end-organs of nerves, 1069
- Spermatic artery, internal, 697  
 canal, 608  
 cord, 1229  
 applied anatomy of, 1230  
 structure of, 1230  
 fascia, external, 501, 1229  
 plexus of nerves, 1004  
 applied anatomy of, 1004  
 veins, 763  
 applied anatomy of, 763
- Spermatids, 82, 1233
- Spermatoblasts, 1233
- Spermatoocytes, 82, 1233
- Spermatogonia, 82, 1233
- Spermatozoön 80, 1233  
 body or connecting piece of, 81  
 formation of, 1233  
 head of, 80  
 neck of, 80  
 perforator of, 81  
 tail of, 82
- Sphenoethmoidal recess, 293, 1010  
 suture, 288
- Sphenofrontal suture, 282, 288
- Sphenoid bone, 245
- Sphenoidal air sinuses, 247, 1014  
 bone, 245  
 articulations of, 251  
 body of, 246  
 ossification of, 251  
 pterygoid processes of, 250  
 wings of, great, 248  
 small, 249
- conchæ, 250
- crest, 247
- process of palatine bone, 268  
 of septal cartilage of nose, 1009
- rostrum, 247
- spine, 248, 280
- turbinate processes, 250

- Sphenomandibular ligament, 395, 477
- Sphenomaxillary fissure, 284  
fossa, 284
- Sphenopalatine artery, 642  
foramen, 267  
ganglion, 919  
nerves, 918  
notch, 268
- Sphenoparietal sinus, 744  
suture, 282
- Sphenosquamosal suture, 282
- Sphenozygomatic suture, 282
- Sphincter ani externus muscle, 516  
internus muscle, 516  
pupillae muscle, 1025  
recti muscle, 514  
urethrae membranaceae muscle, 520, 521  
vaginae muscle, 520
- Spigelian lobe of liver, 1195
- Spina angularis* [sphenoid], 248, 280  
*helicia*, 1044  
*scapulae*, 306  
*vestibuli*, 146
- Spinal, accessory nerve, 944  
arteries, 660  
bulb, 822  
column, 196  
cord, 805  
dura of, 902  
pia of, 906  
ganglia, 948  
structure of, 949  
nerves, 947  
arrangement into groups, 947  
connections with sympathetic, 949  
development of, 81  
divisions of, 951  
anterior, 954  
posterior, 951  
points of emergence of, 947  
roots of, 818, 948  
size and direction of, 949  
somatic fibres of, 950  
structure of, 950  
sympathetic fibres of, 950  
segments, 806
- Spinalis capitis muscle, 489  
cervicis muscle, 489  
colli muscle, 489  
dorsi muscle, 489
- Spindle, achromatic, 36  
aortic, 624  
neuromuscular, 1071  
neurotendinous, 1070
- Spine or Spines, ethmoidal, 246, 290  
of frontal bone, 235  
iliac, 336  
ischial, 336  
mental, 271  
nasal, anterior, 257, 262, 286  
posterior, 266, 278  
pubic, 338  
of scapula, 306  
sphenoidal, 248, 280  
suprameatal, 244, 283  
of tibia, 355  
trochlear, 235
- Spinoglenoid ligament, 413
- Spinoolivary fasciculus, 830
- Spinotectal fasciculus, 817
- Spinothalamic fasciculus, 817
- Spinous process of a vertebra, 197
- Spiral canal of modiolus, 1060  
ligament, 1064  
line of femur, 348  
organ of Corti, 1065  
thread of spermatozoön, 81  
tube of kidney, 1212
- Spirem or skein, 35
- Splanchnic fibres of spinal nerves, 950  
layer of mesoderm, 88  
nerves, 998, 999
- Splanchnology, 979
- Splanchnopleure, 88
- Spleen or lien, 1266  
accessory, 1267  
applied anatomy of, 1270  
bloodvessels of, 1267  
development of, 176  
lymphatic nodules of, 1268  
vessels of, 793  
Malpighian bodies of, 1268  
relations of, 1266  
size and weight of, 1267  
structure of, 1267  
supernumerary, 1267  
surface marking of, 1307
- Splenic centre of ossification, 274
- Splenic artery, 691  
distribution of, 1267  
cells, 1267  
glands, 788  
flexure of colon, 1180  
plexus, 1004  
pulp, 1267  
vein, 765
- Splenium of corpus callosum, 876
- Splenius capitis muscle, 486  
cervicis muscle, 487  
colli muscle, 487
- Spongiblasts, 118
- Spongioplasm, 34
- Spring ligament, 456
- Spur of malleus, 1053  
scleral, 1019
- Squama, frontal, 233  
*frontalis*, 234  
occipital, 227  
*occipitalis*, 227  
temporal, 237  
*temporalis*, 237
- Squamosal suture, 282
- Squamous epithelium, 37
- Stahr, middle gland of, 778
- Stalks, optic, 126, 134  
of thalamus, 857, 858
- Stapedius muscle, 1055
- Stapes, 1054  
annular ligament of, 1055  
*crus anterior*, 1054  
*posterius*, 1054  
development of, 141
- Stellate ligament, 396  
veins of kidney, 1214
- Stensen, duct of, 1135  
foramina of, 261, 278
- Stephanion, 282, 296
- Sternal angle, 218  
end of clavicle, 303  
foramen, 220  
furrow, 1295  
glands, 796  
plate, 105
- Sternebræ, 216
- Sternoclavicular articulation, 409  
applied anatomy of, 411  
movements of, 411  
surface anatomy of, 1315
- Sternocleidomastoid artery, 631, 636
- Sternocleidomastoideus muscle, 478
- Sternocostal ligaments, 399  
surface of heart, 605
- Sternohyoid muscle, 482
- Sternohyoideus muscle, 482
- Sternomastoid artery, 631, 636  
muscle, 478
- Sternopericardiac ligaments, 602
- Sternothyreoides muscle, 482
- Sternothyroid muscle, 482
- Sternum, 216
- Sternum, applied anatomy of, 225  
articulations of, 220  
development of, 105  
ossification of, 220  
structure of, 220
- Stomach, 1161  
applied anatomy of, 1167  
bed, 1163  
body of, 1163  
cardiac glands of, 1166  
orifice of, 1161  
component parts of, 1163  
curvatures of, 1162  
development of, 168  
fundus of, 1163  
glands of, 1166  
*incisura angularis*, 1162  
interior of, 1163  
lymphatic vessels of, 792  
mucous membrane of, 1165  
muscular coat of, 1164  
nerves of, 1167  
openings of, 1161  
position of, 1163  
pyloric antrum, 1162, 1163  
glands, 1166  
orifice, 1162  
valve, 1164  
serous coat of, 1164  
shape and position of, 1161  
structure of, 1164  
subdivisions of, anatomical, 1163  
clinical, 1163  
*sulcus intermedius*, 1162  
surface marking of, 1295  
surfaces of, 1161  
teeth, 1118  
vessels of, 1167
- Stomodeum, 163
- Straight gyrus, 870  
sinus, 741  
tubes of kidney, 1212
- Strands of posterior nerve root, 819
- Stratified epithelium, 39
- Stratiform fibrocartilage, 50
- Stratum cinereum*, 854  
*compactum* [decidual], 98  
*corneum*, 1072  
*dorsale*, 860  
*germinativum*, 1073  
*granulosum*, 1073  
*intermedium* [choroid], 1022  
*lemnisci*, 854  
*lucidum*, 1073  
*mucosum*, 1072, 1073  
*opticum* [retina], 1027  
[superior colliculus], 854  
*spongiosum* [decidual], 98  
*zonale*, 854, 855
- Streak, primitive, 86
- Stria terminalis*, 855, 885  
*vascularis*, 1064
- Striae acusticae*, 935  
*gravidarum*, 1301  
longitudinal, lateral and medial, 875  
*medullares* [rhomboid fossa], 848, 935
- Striate arteries, 653  
veins, inferior, 740
- Stripe of Hensen, 1067
- Striped muscle, 64
- Stroma, intertubular, of kidney, 1214  
of iris, 1025  
of ovary, 1245
- Styloglossus muscle, 1130
- Stylohyal part of styloid process, 244
- Stylohyoid ligament, 481  
muscle, 481  
nerve, from facial, 933
- Stylohyoideus muscle, 481



- Styloid process of fibula, 359  
   of radius, 321  
   of temporal bone, 244, 280  
   of ulna, 319  
 Stylomandibular ligament, 477  
 Stylomastoid artery, 636  
   foramen, 243, 280  
 Stylopharyngeus muscle, 1142  
 Subanconeus muscle, 536  
 Subarachnoid cavity, 904  
   cisternæ, 904  
   septum, 905  
   space, 904  
 Subarcuate fossa, 242  
 Subcallosal gyrus, 875  
 Subcardinal veins, 157  
 Subclavian arteries, 655  
   applied anatomy of, 657  
   branches of, 659  
   first part of left, 655  
   of right, 655  
   peculiarities of, 657  
   second portion of, 656  
   surface anatomy of, 1278  
   marking of, 1291  
   third portion of, 656  
   triangle, 483, 645  
   vein, 750  
 Subclavius muscle, 528  
   nerve to, 960  
 Subcostal arteries, 686  
   zone, 1147  
 Subcostales muscles, 492  
 Subcureus or articularis genu muscle, 566  
 Subcutaneous inguinal ring, 500  
 Subdural cavity, 903  
 Subepithelial plexus of cornea, 1021  
 Subfrontal gyre, 870  
 Sublingual lymph glands, 783  
 Sublingual artery, 632  
   gland, 1137  
   vessels and nerves of, 1137  
 Sublobular veins, 1197  
 Submaxillary artery, 634  
   duct, 1136  
   ganglion, 925  
   gland, 1135  
   vessels and nerves of, 1137  
   lymph glands, 778  
   triangle, 481, 644  
 Submental artery, 634  
   lymph glands, 778  
   triangle, 481  
 Subnasal point, 296  
 Suboccipital muscles, 490  
   nerve, 951  
   triangle, 491, 660  
 Subparietal sulcus, 871  
 Subperitoneal connective tissue, 509  
 Subpleural mediastinal plexus, 664  
 Subpubic ligament, 407  
 Subsartorial plexus, 981  
 Subscapular angle, 305  
   artery, 671  
   fascia, 531  
   fossa, 304  
   nerves, 961  
 Subscapularis muscle, 531  
 Subserous areolar tissue, 1149  
 Substance, perforated, anterior, 874  
   posterior, 848  
*Substantia adamantina*, 1120  
   *alba*, 814  
   *eburnea*, 1119  
   *ferruginea*, 848  
   *gelatinosa centralis*, 810  
     of Rolando, 809  
   nerve cells in, 813  
   *grisea centralis*, 809  
   innominate of Meynert, 884  
*Substantia nigra*, 850  
   *ossea*, 1121  
   *perforata anterior*, 875  
   *propria* [cornea], 1019  
 Subthalamic tegmental region, 860  
 Successional permanent teeth, 1124  
 Suctorial pad, 471  
 Sudoriferous glands, 1078  
 Sulci and fissures of cerebral hemisphere, 867  
   development of, 131  
   of medulla, oblongata, 822  
   spinalis, 808  
 Sulcus, anterior longitudinal, of heart, 604  
   *antihelicis transversus*, 1044  
   *arteria vertebralis*, 199  
   *basilaris*, 833  
   *calcaneal*, 365  
   *central*, 868  
   *centralis* [Rolandi], 868  
   *cingulate*, 869  
   *cinguli*, 869  
   *circular*, 869, 873  
   *circularis corneæ*, 1019  
   coronary, of heart, 604  
   frontal, 869  
   horizontal, of cerebellum, 837  
   *intermedius* [stomach], 1162  
   intraparietal, 870  
   lateral cerebral, 849  
   of cerebral peduncle, 849  
   *limitans* [rhomboid fossa], 847, 848  
   *lunatus*, 871 *note*  
   malleolar, 360  
   medial frontal, of Eberstaller, 870  
   median, of rhomboid fossa, 847  
   of tongue, 1126  
   *medianus posterior*, 808  
   of Monro, 125, 865  
   occipital, 871  
   oculomotor, 849  
   olfactory, 870  
   orbital, 870  
   paramedial, 870  
   postcentral, 870  
   posterior longitudinal, of heart, 604  
   preauricular, of ilium, 335, 336  
   precentral, 869  
   radial, 311  
   retroglandular, 1239  
   sagittalis, 228, 232, 235  
   sigmoid, 240  
   *spiralis externus*, 1064  
   *internus*, 1065  
   subparietal, 871  
   tali, 367  
   temporal, inferior, 872  
   middle, 872  
   superior, 872  
   terminal, of right atrium, 606  
   of tongue, 1126  
   *tubæ auditivæ*, 249, 280  
   tympanic, 243, 1050  
   *valleculæ*, 838  
 Superadded permanent teeth, 1124  
*Supercilia*, 1038  
 Superciliary arches, 278, 234, 282  
 Superficial cervical artery, 664  
   lymph glands 778  
   muscle, 475  
   dissection of, 475  
   nerve, 957  
   epigastric artery, 715  
   external pudendal artery, 716  
   pudic artery, 716  
   iliac circumflex artery, 716  
   long plantar ligament, 454  
   palmar arch, 682  
 Superficial perineal artery, 705  
   peroneal nerve, 990, 991  
   Sylvian vein, 739  
   temporal artery, 637  
     applied anatomy of, 638  
   vein, 733  
   transverse ligament of hand, 551  
   perineal muscle, 518, 520  
   volar artery, 678  
 Superficialis volæ artery, 678  
 Superfrontal gyre, 869  
 Superior articular arteries, 720  
   calcaneocuboid ligament, 454  
   cerebellar peduncles, 841  
   constrictor muscle, 1142  
   dental nerve, 918  
   intercostal artery, 666  
   lingualis muscle, 1130  
   longitudinal sinus, 740  
   maxillary nerve, 917  
   medullary velum, 842  
   nasal concha, 254  
   nuchal line, 227  
   oblique muscle, 1035  
   orbital fissure, 249, 288  
   petrosal sinus, 746  
   profunda artery, 674  
   sagittal sinus, 740  
   semicircular canal, 1059  
   tarsal plate, 1039  
   thoracic artery, 670  
   tibiofibular articulation, 448  
   tympanic artery, 640  
   vesical artery, 701  
   vocal cords, 1085  
 Supernumerary spleen, 1267  
 Supinator brevis muscle, 544  
   longus muscle, 542  
   muscle, 544  
 Supra-acromial nerves, 957  
 Supporting cells of Hensen, 1067  
   of Sertoli, 1233  
   frame-work of retina, 1029  
 Supracallosal gyrus, 875  
 Supraclavicular branches of brachial plexus, 960  
   nerves, 957  
 Supracondylar process, 312 *note*  
   ridges, 311, 312  
 Supraglenoid tuberosity, 307  
 Suprahyoid aponeurosis, 481  
   artery, 632  
   lymph glands, 778  
   muscles, 480  
   dissection of, 480  
   triangle, 481, 644  
 Supramarginal gyrus, 871  
 Supramastoid crest, 237  
 Suprameatal spine, 244, 283  
   triangle, 238, 283  
 Supraorbital artery, 649  
   foramen, 235, 286, 288  
   margin, 234  
   nerve, 916  
   notch, 235, 286, 288  
   vein, 732  
 Suprarenal arteries, inferior, 697  
   middle, 696  
   superior, 698  
   glands, 1270  
   applied anatomy of, 1272  
   development of, 134  
   lymphatic vessels of, 793  
   nerves of, 1272  
   structure of, 1271  
   vessels of, 1272  
   impression, 1194  
   plexus, 1004  
   veins, 764  
 Suprascapular artery, 663  
   ligament, 413  
   nerve, 960  
 Supraspinal ligament, 387  
 Supraspinatus fascia, 532

Supraspinatus fossa, 305  
 Supraspinatus muscle, 532  
 Supraspinous ligament, 387  
 Suprasternal nerves, 957  
   space, 477  
 Supratonsillar fossa, 1139  
 Supratrochlear foramen, 313  
   nerve, 916  
 Sural arteries, 720  
   cutaneous nerve, medial, 988  
   nerve, 988  
 Surface anatomy and surface  
   markings of abdomen,  
   1303  
     regions of, 1303  
     surface lines of, 1303  
 accessory nerve, 1291  
 acoustic meatus, external,  
   1228  
 acromioclavicular joint, 1315,  
   1319  
 adductor canal, 1331  
 ankle-joint, 1326, 1330  
 anterior tibial artery, 1329,  
   1332  
 aorta, abdominal 1301, 1309  
   ascending, 1300  
 aortic arch, 1300  
 auscultation, triangle of,  
   1296  
 axillary artery, 1318, 1320  
   nerve, 1323  
 back, 1291  
 bones of cranium, 1279  
   of lower extremity, 1324  
   of thorax, 1296  
   of upper extremity, 1312  
 brachial artery, 1318, 1321  
   plexus, 1291, 1318  
 brain, 1280  
 Bryant's triangle, 1330  
 calcaneus, 1325  
 carpal bones, 1315  
 caruncular lacrimalis, 1287  
 cecum, 1307  
 cerebellum, 1280  
 cerebral hemisphere, 1280  
 cervical cutaneous nerve,  
   1291  
 clavicle, 1313  
 coeliac artery, 1309  
 colon, ascending, 1307  
   descending, 1307  
   iliac, 1307  
   transverse, 1307  
 common carotid artery, 1290  
   iliac artery, 1309  
   peroneal nerve, 1329, 1334  
 deep peroneal nerve, 1334  
 deltoideus muscle, 1316  
 diaphragma, 1297  
 dorsalis pedis artery, 1329,  
   1332  
 duodenum, 1306  
 ear, 1288  
 elbow-joint, 1319  
 epigastric artery, inferior,  
   1309  
 external carotid artery, 1290  
   main branches of,  
   1290  
   iliac artery, 1309  
 eye, 1287  
 facial nerve, 1291  
 femoral artery, 1328, 1331  
   triangle 1331  
 femur, 1324  
 fibula, 1324  
 fissures of brain, 1281  
 fold of groin, 1301  
 frontal sinus, 1282  
 gall-bladder, 1307  
 gluteal arteries, 1331  
   fold, 1323  
 great auricular nerve, 1291

Surface anatomy and surface  
   markings of head and neck,  
   1275  
 heart, 1299  
   coronary sulcus, 1299  
   longitudinal sulcus, an-  
   terior, 1299  
   orifices of, 1299  
 Hesselbach's triangle, 1309  
 hip bones, 1324  
 hip-joint, 1325, 1330  
 humeral circumflex artery,  
   1321  
 humerus, 1313  
 hyoid bone, 1289  
 ileocolic junction, 1307  
 iliac artery, common, 1309  
   external, 1309  
   furrow, 1301  
 infrasternal notch, 1295  
 inguinal rings and canal  
   1303  
 innominate artery, 1300  
   veins, 1300  
 internal pudendal artery,  
   1331  
 intestines, 1306, 1307  
 joints of fingers, 1315  
   of foot, 1330  
 jugular notch, 1295, 1297  
   veins, 1291  
 kidneys, 1308  
 knee-joint, 1300, 1325  
 lacrimal puncta, 1287  
   sac, 1187  
 larynx, 1287, 1289  
 lateral plantar artery, 1332  
   thoracic artery, 1320  
   ventricle of brain, 1282  
 latissimus dorsi, 1316, 1319  
 left common carotid artery,  
   in thorax, 1300  
 lesser occipital nerve, 1291  
 linea semilunaris, 1301  
 liver, 1302, 1307  
 lower extremity, 1323  
 lumbar triangle, 1301  
 lungs, 1298  
 mamma, 1296  
 mammary artery, internal,  
   1300  
 maxillary artery, external,  
   1282  
   sinus, 1282  
 medial plantar artery, 1332  
 median nerve, 1323  
 medulla spinalis, 1294  
 mesenteric arteries, 1309  
 metacarpal bones, 1315  
 middle meningeal artery,  
   1282  
 mouth, 1284  
 mucous sheaths around  
   ankle, 1331  
   of wrist and hand, 1319  
 muscles of abdomen, 1303  
   of arm, 1316  
   of buttock, 1326  
   of foot, 1327, 1328  
   of forearm, 1317  
   of head and neck, 1276,  
   1277, 1289  
   of hand, 1318  
   of leg, 1328  
   of thigh, 1326  
 nasal part of pharynx, 1287  
 nasolacrimal duct, 1287  
 neck, 1291  
 Nélaton's line, 1329  
 nose, 1284  
 œsophagus, 1299  
 palatine arches, 1285  
 palmar or volar arches, 1322  
 palpebral fissure, 1287  
 pancreas, 1303, 1307

Surface anatomy and surface  
   markings of parotid duct,  
   1283  
   gland, 1283  
   patella, 1324  
 pectoralis major muscle,  
   1316, 1319  
   minor muscle, 1316, 1319  
 pelvis, 1324  
 perineum, 1309  
 peroneal artery, 1332  
   nerves, 1334  
 phalanges of foot, 1325  
   of hand, 1315  
 phrenic nerve, 1291  
 plantar arch, 1332  
   arteries, 1332  
 pleura, 1297  
 plica semilunaris, 1287  
 popliteal artery, 1328  
   fossa, 1331  
 posterior tibial artery, 1329,  
   1332  
 profunda brachii artery, 1321  
   femoris artery, 1331  
 pupil, 1287  
 radial artery, 1318, 1322  
   nerve, 1323  
 radioulnar joints, 1315  
 radius, 1314  
 rectum and anal canal, 1310  
 Reid's base line, 1279  
 renal arteries, 1309  
 sacroiliac joint, 1330  
 saphenous veins, 1334  
 scapula, 1313  
 scapular circumflex artery,  
   1321  
 sciatic nerve, 1334  
 serratus anterior muscle, 1316  
 shoulder-joint, 1315  
 spinal nerves, 1295  
 spleen, 1307  
 sternal angle, 1295, 1297  
 sternoclavicular joint, 1315  
 sternocleidomastoid muscle,  
   1277  
 stomach, 1305  
 striæ gravidarum or albi-  
   cantes, 1301  
 subclavian artery, 1291, 1318  
 subdural and subarachnoid  
   cavities, 1294  
 submaxillary gland, 1291  
 subscapular artery, 1320  
 supraclavicular nerves, 1291  
 talus, 1325  
 tarsus and foot, 1325  
 temporomandibular joint,  
   1276  
 tendinous inscriptions of rec-  
   tus abdominis, 1301  
 thoracoacromial artery, 1320  
 thorax, 1295  
   surface lines of, 1296  
 tibia, 1324  
 tibial nerve, 1334  
 tongue, 1285  
 tonsil, 1286  
 trachea, 1289, 1299  
 transverse sinus, 1282  
 trapezius, 1319  
 trigeminal nerve, 1283  
 tympanic antrum, 1289  
   membrane, 1288  
 ulna, 1314  
 ulnar artery, 1322  
   collateral arteries, 1322  
   nerve, 1319, 1323  
 umbilicus, 1301, 1303  
 upper extremity, 1312  
 urogenital organs, female,  
   1311  
   male, 1310  
 vena cava, inferior, 1300

Surface anatomy and surface markings of vena cava, superior, 1300  
vermiform process, 1307  
vertebral column, 1291  
volar or palmar arches, 1322  
wrist and hand, 1314  
wrist-joint, 1314, 1319  
Suspensory ligament of axilla, 526  
of eye, 1038  
of lens, 1030  
of ovary, 1244  
of penis, 1239  
Sustentacular fibres of Müller, 1029  
*Sustentaculum lienis*, 1157  
 *tali*, 365  
*Sutura dentata*, 381  
 *harmonia*, 381  
 *limbosa*, 381  
 *notha*, 381  
 *serrata*, 381  
 *squamosa*, 381  
 *vera*, 381  
Sutural bones, 255  
applied anatomy of, 255  
Suture, coronal, 277, 282  
frontal, 278  
frontoethmoidal, 288  
frontomaxillary, 287  
frontozygomatic, 282  
interparietal, 233  
lambdoidal, 230, 232, 277, 282  
metopic, 234  
occipitomastoid, 282  
parietomastoid, 282  
petrooccipital, 291  
petrosquamous, 241, 243  
sagittal, 277  
sphenothmoidal, 288  
sphenofrontal, 282, 288  
sphenoparietal, 282  
sphenopetrosal, 290  
sphenosquamosal, 282  
sphenozygomatic, 282  
squamosal, 282  
zygomaticofrontal, 282  
zygomaticomaxillary, 288  
zygomaticotemporal, 282  
Sweat glands, 1078  
Swellings, genital, 190  
Sylvian fossa, 131  
veins, 739, 740  
Sylvius, aqueduct of, 821, 854  
fissure of, 867  
Sympathetic fibres of spinal nerves, 949  
nerves, 994  
connections with spinal nerves, 995  
plexuses, 1001  
cardiac, 1001  
coeliac, 1002  
hypogastric, 1005  
pelvic, 1005  
solar, 1002  
system, abdominal portion of, 1001  
applied anatomy of, 1005  
cephalic portion of, 995  
cervical portion of, 996  
development of, 133  
pelvic portion of, 1001  
thoracic portion of, 998  
trunks, 995  
Symphysis of mandible, 271  
 *ossium pubis*, 406  
 *pubis*, 406  
 *sacrococcygea*, 406  
Synarthroses, 380  
Synchondrosis, 381  
neurocentral, 210  
Synchytotrophoblast, 85  
Syncytium, 85  
Syndesmology, 379

Syndesmosis, 381  
 *tibiofibularis*, 448  
Synergic muscles, 462  
Synovia, 380  
Synovial membrane, 380. See  
also Individual Joints.  
Systemic circulation, 595  
veins, 729  
Systems, Haversian, 53

T

TABLES of the skull, 196  
Tactile corpuscles of Golgi and  
Mazzoni, 1069  
of Grandry, 1069  
of Pacini, 1069  
of Ruffini, 1070  
of Wagner and Meissner, 1070  
*Taenia pontis*, 833  
 *semicircularis*, 885  
 *thalami*, 856  
 *ventriculi quarti*, 846  
*Taenia coli*, 1184  
of fourth ventricle, 846  
of muscular coat of large intestine, 1177  
Talocalcaneal articulation, 452  
Talocalcaneonavicular articulation, 454  
Talotibial ligaments, 450  
Talus, 366  
ossification of, 374  
Tangential fibres of cerebral cortex, 892  
Tapetum of choroid, 1022  
of corpus callosum, 877  
Tarsal arteries, 724  
bones, 362  
glands, 1040  
plates, 1039  
Tarsi of eyelids, 1039  
Tarsometatarsal articulations, 457  
Tarsus, 362  
applied anatomy of, 375.  
articulations of, 452  
inferior, 1039  
ossification of, 374  
superior, 1039  
surface markings of, 1330  
synovial membranes of, 458  
Taste, nerves of, 1008  
organ of, 1007  
Taste-buds, 1007  
Tectorial membrane of ductus cochlearis, 1067  
Teeth, 1115  
applied anatomy of, 1125  
bicuspid, 1118  
canine, 117, 1118  
cement or crusta petrosa of, 1121  
crown of, 1117  
cutting, 1117  
deciduous, 1118  
dental canaliculi of, 1120  
dentin of, 1119  
development of, 1121  
enamel of, 1120  
eruption of, 1124  
eye, 1118  
general characters of, 1113  
incisive, 1117  
incisors, 1117  
ivory of, 1119  
milk, 1118  
molar, 1118  
multicuspid, 1118  
necks of, 1116  
permanent, 1117  
successional, 1124  
superadded, 1124

Teeth, premolar, 1118  
pulp cavity of, 1119  
roots of, 1116  
stomach, 1118  
structure of, 1119  
 *substantia adamantina* of, 1120  
 *eburnea* of, 1119  
 *ossea* of, 1121  
temporary, 1118  
wisdom, 1118  
Tegmen tympani, 240, 1049  
Tegmental part of pons, 835  
Tegmentum, 850  
*Tela chorioidea* [fourth ventricle], 846  
[third ventricle], 888  
Telencephalon, 126, 127, 865  
Telophase of karyokinesis, 36  
Temporal artery, deep, 641  
middle, 638  
superficial, 637  
bone, 237  
articulations of, 245  
mastoid portion of, 239  
ossification of, 244  
petrous portion of, 241  
pyramid of, 241  
squama of, 237  
structure of, 244  
tympanic part of, 243  
fascia, 473  
fossa, 282  
gyri, 872  
lines, 231, 235, 278, 282  
lobe, 871  
muscle, 473  
dissection of, 473  
nerves of auriculotemporal, 923  
deep, 922  
of facial, 933  
operculum, 873  
process of zygomatic bone, 265  
veins, 733  
Temporalis muscle, 473  
Temporary teeth, 1118  
Temporomalar nerve, 917  
Temporomandibular articulation, 393  
applied anatomy of, 396  
surface anatomy of, 1276  
Temporomaxillary vein, 734  
Tendinous arch of pelvic fascia, 512  
inscriptions of rectus abdominis muscle, 506  
Tendo Achillis, 579  
calcaneus, 579  
oculi, 468  
ligament, 468  
Tendon, central, of diaphragma, 495  
conjoined, of internal oblique and transversalis muscles, 504  
of conus arteriosus, 608  
structure of, 44  
superior, of Lockwood, 1035  
of Zinn, 1035  
Tendons, 463  
on back of wrist, relations of, 550  
Tendril fibres of cerebellum, 844  
Tenon, capsule of, 1037  
Tensor fasciae femoris muscle, 565  
 *latae* muscle, 565  
 *palati* muscle, 1113  
 *tarsi* muscle, 468  
tympani muscle, 1055  
semicanal for, 243, 1052  
veli palatini muscle, 1113  
Tenth nerve, 940  
Tentorial sinus, 741  
*Tentorium cerebelli*, 901  
Teres major muscle, 533  
minor muscle, 533

- Terminal crest of right atrium, 606, 607  
 sulcus of right atrium, 606, vein, 740  
 ventricle, 119, 810
- Terminations of motor nerves, 803  
 of nerves of general sensations, 1069
- Testes, 1228, 1230  
 appendages of, 1231  
 applied anatomy of, 1234  
 coni vasculosi of, 1233  
 coverings of, 1228  
 descent of, 186  
 development of, 186  
*ductuli efferentes*, 1233  
*ductus deferens*, 1235  
*gubernaculum testis*, 186  
 lobules of, 1232  
 lymphatic vessels of, 794  
 mediastinum testis, 1232  
*rete testis*, 1233  
 structure of, 1232  
*tubuli recti*, 1233  
*seminiferi*, 1232  
*tunica albuginea*, 1232  
*vaginalis*, 1231  
*vasculosa*, 1232
- Thalamencephalon, 855
- Thalami, 126, 855  
 connections of, 857  
 development of, 126  
 intermediate mass of, 126, 856  
 stalks of, 857, 858  
 structure of, 856  
 surfaces of, 855, 856
- Thalamomamillary fasciculus, 886
- Thebesius, foramina of, 608  
 valve of, 608, 730  
 veins of, 731
- Thenar eminence, 546
- Thigh bone, 345  
 fascia lata of, 563  
 superficial, 562  
 muscles of, 562  
 dissection of, 562
- Third cuneiform bone, 370  
 metacarpal bone, 330  
 metatarsal bone, 372  
 nerve, 911  
 trochanter, 348  
 ventricle of brain, 864  
 choroid plexuses of, 864
- Thoracic aorta, 683  
 applied anatomy of, 683  
 peculiarities of, 683  
 arteries, 670, 671  
 axis, 670  
 cardiac nerves, 943  
 duct, 771  
 applied anatomy of, 773  
 nerves, anterior, 961  
 applied anatomy of, 974  
 divisions of, anterior, 972  
 posterior, 952  
 portion of gangliated cord, 998  
 vertebræ, 201
- Thoracoacromial artery, 670
- Thoracodorsal nerve, 961
- Thoracoepigastric vein, 756
- Thorax, 216  
 boundaries of, 216  
 cavity of, 600  
 lower opening of, 216, 601  
 lymph glands of, 796  
 lymphatic vessels of, 797, 798  
 mechanism of, 401  
 muscles of, 492  
 parts passing through lower opening of, 601  
 upper opening of, 601  
 skeleton of, 216  
 surface anatomy of, 1295  
 markings of, 1296
- Thorax, upper opening of, 216, 601
- Thromboplastin, 64
- Thumb, carpometacarpal articulation of, 429
- Thymus, 1264  
 applied anatomy of, 1266  
 development of, 165  
 glands, 1264  
 lymphatic vessels of, 800  
 nerves of, 1265  
 structure of, 1264  
 vessels of, 1265
- Thyreoaerytaenoideus muscle, 1089
- Thyreohyoideus muscle, 482  
 nerve to, 947
- Thyreoides ima artery, 626
- Thyroarytenoid ligaments, inferior, 1086  
 muscle, 1089
- Thyrocerivical trunk, 662
- Thyroepiglottic ligament, 1084  
 muscle, 1090
- Thyroglossal duct, 165, 1127
- Thyrohyals of hyoid bone, 275
- Thyrohyoid ligament, lateral, 1083  
 middle, 1082  
 membrane, 1082  
 muscle, 482
- Thyroid artery, inferior, 662  
 superior, 631  
 applied anatomy of, 631  
 axis, 662  
 body, 1261  
 cartilage, 1080  
 foramen, 339  
 gland, 1261  
 applied anatomy of, 1263  
 development of, 165  
 isthmus of, 1261  
 lobes of, 1261  
 lymphatic vessels of, 779  
 nerves of, 1262  
 pyramidal lobe of, 1262  
 structure of, 1262  
 vessels of, 1262  
 notch, superior, 1080  
 veins, inferior, 751  
 middle, 737  
 superior, 737
- Thyroids, accessory, 1262
- Tibia, 355  
 applied anatomy of, 361  
 articulations of, 359  
 condyles of, 355  
 ossification of, 359  
 spine of, 355  
 surface anatomy of, 1324  
 tuberosity of, 356
- Tibial artery, anterior, 722  
 applied anatomy of, 722  
 branches of, 722  
 peculiarities of, 722  
 surface marking of, 1332  
 posterior, 725  
 applied anatomy of, 725  
 branches of, 725  
 peculiarities of, 725  
 surface marking of, 1332  
 recurrent, anterior, 723  
 posterior, 722  
 collateral ligament of knee-joint, 439  
 nerve, 987  
 anterior, 990  
 surfaces of femur, 350  
 veins, 758
- Tibialis anterior muscle, 576  
 anticus muscle, 576  
 posterior muscle, 582
- Tibiofibular articulation, 448  
 ligament, middle, 448  
 syndesmosis, 448
- Tibionavicular ligament, 450
- Tibiotalar articulation, 449
- Tissue, adenoid, 45  
 adipose, 42  
 areolar, 40  
 connective, 40  
 lymphoid, 45  
 mucous, 44  
 muscular, 64  
 nervous, 69  
 retiform or reticular, 44  
 white fibrous, 43  
 yellow elastic, 44
- Tomes' fibres, 1120
- Tongue, 1125  
 applied anatomy of, 1132  
 development of, 164  
 frenulum of, 1126  
 glands of, 1131  
 lymph gland of, 778  
 lymphatic vessels of, 778  
 mucous membrane of, 1131  
 muscles of, 1128  
 nerves of, 1132  
 papillæ of, 1127  
 septum of, 1132  
 structure of, 1131  
 vessels of, 1132
- Tonsil, 1139  
 lingual, 1131  
 pharyngeal, 1139
- Tonsilla cerebelli*, 839
- Tonsillae intestinales*, 1175  
*palatinae*, 1139
- Tonsillar artery, 634  
 nerves from glossopharyngeal, 940  
 sinus, 1140
- Tonsils, palatine, 1139  
 applied anatomy of, 1141  
 development of, 165  
 lymphatic vessels of, 777  
 nerves of, 1141  
 structure of, 1141  
 vessels of, 1141
- Torcular Herophili, 229, 743
- Torus of auditory tube, 1139  
*utereticus*, 1222  
*uterinus*, 1154
- Trabeculae carneae* [left ventricle], 612  
 [right ventricle], 610  
*cranii*, 106  
 of penis, 1239  
 of spleen, 1267  
 of testis, 1232
- Trachea, 1091  
 applied anatomy of, 1093  
 nerves of, 1093  
 relations of, 1092  
 structure of, 1092  
 vessels of, 1093
- Trachealis muscle, 1093
- Trachelomastoideus muscle, 489
- Tracheobronchial glands, 798
- Tracheotomy, 1094
- Trachoma glands, 1041
- Tract or Tracts, anterior basis bundle, 815  
 of Burdach, 808, 817  
 cerebellar, of Flechsig, 816  
 cerebellospinal, 815  
 comma, 817  
 dorsal peripheral band, 818  
 of Goll, 808, 817  
 of Gowers, 816  
 lateral basis bundle, 817  
 of Löwenthal, 815  
 motor, 896  
 olfactory, 874  
 optic, 863, 909  
 prepyramidal, 816  
 pyramidal, crossed, 815  
 direct, 815  
 sensory, 897

- Traction epiphyses, 59  
*Tractus iliobibialis*, 563  
*olfactorius*, 874  
*peduncularis transversus*, 850  
   *note*  
   *solitarius*, 128  
   *spiralis foraminosus*, 242, 1060  
 Tragicus muscle, 1046  
 Tragus, 1044  
 Transitional epithelium, 40  
 Transpyloric plane, 1147  
 Transversa colli artery, 663  
 Transversalis cervicis muscle, 488  
   colli artery, 663  
   fascia, 508  
   muscle, 504  
 Transverse acetabular ligament  
   of hip-joint, 434  
   aorta, 623  
   carpal ligament, 547  
   cervical arteries, 663, 664  
   nerve, 957  
   colon, 1180  
   crural ligament, 584  
   facial artery, 638  
   vein, 734  
   fibres of cerebral hemispheres,  
     890  
   fissure of brain, 889  
   of liver, 1194  
   folds of rectum, 1183  
   ligament of atlas, 389  
   of fingers, 551  
   humeral, 415  
   of knee, 442  
   metacarpal, 430  
   metatarsal, 458  
   of pelvis, 520  
   ligaments of scapula, 413  
   lingualis muscle, 1130  
   mesocolon, 1157  
   occipital sulcus, 871  
   process of a vertebra, 197  
   scapular artery, 663  
   sinus, 746  
   of pericardium, 603  
   temporal gyri, 872  
 Transversus abdominis muscle,  
   504  
   auriculæ muscle, 1046  
   linguæ muscle, 1130  
   menti muscle, 470  
   nuchæ muscle, 466  
   pedis muscle, 589  
   perinaei muscle, 518  
   profundus muscle in female,  
     521  
   in male, 520  
   superficialis muscle, in fe-  
     male, 520  
   in male, 518  
   thoracis muscle, 492  
 Trapezium, 326  
 Trapezus muscle, 522  
 Trapezoid, 327  
   body, 835  
   ligament, 412  
   nucleus, 835  
   ridge, 302  
 Treves, bloodless fold of, 1160  
 Triangle of auscultation, 524  
   Bryant's, 1330  
   carotid, 481, 483, 643  
   digastric, 480, 644  
   femoral, 565, 712  
   of Hesselbach, 1187, 1309  
   lumbar, 524  
   muscular, 483, 643  
   of neck, 642, 644  
   occipital, 483, 645  
   of Petit, 524  
   Scarpa's, 712  
   subclavian, 483, 645  
   submaxillary, 481, 644  
   submental, 481  
   Triangle, suboccipital, 491, 660  
   suprahyoid, 481, 644  
   suprameatal, 238, 283  
 Triangular articular disk, 424  
   bone, 324  
   fascia of abdomen, 502  
   ligament, 519  
   of liver, 1151  
 Triangularis muscle, 470  
   sterni muscle, 492  
 Triceps brachii muscle, 535  
   extensor cubiti muscle, 535  
   muscle, 535  
   suræ muscle, 579  
 Tricuspid valve, 609  
 Trifacial nerve, 914  
 Trigeminal impression, 241  
   nerve, 914  
   applied anatomy of, 925  
   surface marking of, 1283  
 Trigone, olfactory, 875  
 Trigonum collaterale, 881  
   femorale, 712  
   habenulae, 859  
   hypoglossi, 848  
   olfactorium, 875  
   vagi, 829  
   vesicae, 1222  
 Trochanter, greater, 347  
   lesser, 348  
   major, 347  
   minor, 348  
   third, 348  
 Trochanteric fossa, 347  
 Trochlea of humerus, 312  
 Trochlear fovea, 235, 286  
   nerve, 913  
   applied anatomy of, 914  
   process of calcaneus, 365  
   spine, 235  
 Trochoid joint, 382  
 Trolard, anastomotic vein of, 739  
 Tröltsch, recess of, 1055  
 Trophoblast, 84  
 True nucleoli, 34  
   pelvis, 340  
   skin, 1074  
   vocal cords, 1086  
 Truncus arteriosus, 145, 150  
   costocervicalis, 666  
   sympathicus, 995  
   thyrocervicalis, 662  
 Trunk, arteries of, 683  
   articulations of, 384  
   costocervical, 666  
   thyrocervical, 662  
 Tuba auditiva, 1052  
   *par cartilaginea*, 1052  
   *ossea*, 1052  
   *uterina [Fallopii]*, 1247  
 Tube, auditory, 1052  
   tonsil of, 1053  
   digestive, 1109  
   Eustachian, 1052  
   Fallopian, 1247  
   neural, 88  
   uterine, 1247  
 Tuber cinereum, 825  
   frontale, 234  
   omental [liver], 1192  
   [pancreas], 1204  
   parietale, 231  
   valvulae, 839  
   vermis [cerebellum], 839  
 Tuberal lobe, 839  
 Tubercle, adductor, 348  
   articular, of temporal bone,  
     237, 280  
   auricular, of Darwin, 1044  
   carotid, or Chassaignac's, 199  
   conoid, 301  
   cuneate, 825  
   cuneiform, 1085  
   deltoid, 302  
   of epiglottis, 1082  
   Tubercle of femur, 348  
   of humerus, 309  
   intervenous, 608  
   jugular, 230  
   lacrimal, 260  
   of Lower, 608  
   mental, 271  
   obturator, 339  
   peroneal, 365  
   pharyngeal, 230, 280  
   pterygoid, 250  
   pubic, 338  
   of rib, 222  
   of Rolando, 825  
   scalene, 224  
 Tuberculum acusticum, 848, 935  
   anterior, 199  
   caroticum, 199  
   impar, 164  
   intervenosum, 608  
   majus [humeri], 309  
   minus [humeri], 309  
   posterius, 199  
   sellae, 246, 290  
 Tuberosity, calcaneal, 365  
   coracoid, 301  
   costal, 303  
   of cuboid, 368  
   deltoid, 312  
   of fifth metatarsal bone, 372  
   gluteal, 348  
   iliac, 335  
   infraglenoid, 307  
   of ischium, 337  
   maxillary, 257  
   of navicular bone, 369  
   of palatine bone, 267  
   radial, 320  
   supraglenoid, 307  
   of tibia, 356  
   of ulna, 315  
 Tubules, renal, 1212  
 Tubuli lactiferi, 1259  
   recti [testis], 1233  
   seminiferi, 1232  
 Tuft, Malpighian, 1212  
 Tunic, dartos, 1228  
   fibrous, of kidney, 1210  
 Tunica adventitia, 597  
   albuginea [ovary], 1245  
   [testis], 1232  
   conjunctiva bulbi, 1041  
   dartos, 1229  
   elastica externa, 597  
   fibrosa oculi, 1017  
   intima, 596  
   media, 596  
   serosa, 1149  
   vaginalis, 1231  
   communis [testis et funiculi  
     spermatice], 1229  
   development of, 187  
   propria testis, 1231  
   lamina parietalis, 1232  
   visceralis, 1231  
   vasculosa [testis], 1232  
   oculi, 1021  
 Tunics of eyeball, 1017  
 Tunnel of Corti, 1065  
 Turbinate bone, 268  
   processes, sphenoidal, 250  
 Turner, intraparietal sulcus of,  
   870  
 Twelfth nerve, 945  
 Tympanic antrum, 240  
   entrance to, 1051  
   artery, 639  
   from ascending pharyngeal,  
     637  
   from internal maxillary,  
     639  
   canaliculus, inferior, 243, 280  
   cavity, 1049  
   applied anatomy of, 1056  
   arteries of, 1056



- Tympanic cavity, attic or epitympanic recess of, 1049  
 carotid or anterior wall of, 1052  
 development of, 141  
 jugular wall or floor of, 1049  
 labyrinthine or medial wall of, 1050  
 mastoid or posterior wall of, 1051  
 membranous or lateral wall of, 1049  
 mucous membrane of, 1055  
 muscles of, 1055  
 nerves of, 1056  
 ossicles of, 1053  
 tegmental wall or roof of, 1049  
 vessels of, 1056  
 lip, 1065  
 membrane, 1050  
 nerves of, 1050  
*pars flaccida*, 1050  
 secondary, 1051  
 structure of, 1050  
 vessels of, 1050  
 nerve (Jacobson's), 939, 1056  
 plexus, 939, 1056  
 ring, 245  
 sulcus, 243, 1047, 1050  
 Tympanohyal part of styloid process, 244  
 Tympanomastoid fissure, 243, 280  
 Tympanum, 1049
- U**
- ULNA, 314  
 applied anatomy of, 321  
 articulations of, 321  
 coronoid process of, 315  
 olecranon of, 315  
 ossification of, 319  
 radial notch of, 318  
 semilunar notch of, 315  
 sigmoid cavities of, 318  
 structure of, 319  
 styloid process of, 319  
 surface anatomy of, 1314  
 tuberosity of, 315  
 Ulnar artery, 679  
 applied anatomy of, 680  
 branches of, 680  
 carpal, 682  
 collateral, 674, 675  
 branch of radial nerve, 969  
 peculiarities of, 679  
 recurrent, 680  
 surface marking of, 1322  
 notch of radius, 321  
 Ultimobranchial bodies, 166  
 Umbilical arteries in fetus, 99, 616  
 cord, 96  
 folds, 1187, 1221, 1222  
 fossa of liver, 1194  
 notch of liver, 1194  
 veins, 100, 145, 156  
 obliterated, 765, 1150  
 zone, 1147  
 Umbilicus, 507  
 Umbilic of membrana tympani, 1050  
 Uneiform bone, 328  
 Uncinate fasciculus, 890  
 process of head of pancreas, 1203  
 Uncus, 874  
 Ungual phalanges, 331, 373  
 Unguis, 1075  
 Unstriped muscle, 67  
 Upper extremity, arteries of, 655  
 articulations of, 409  
 bones of, 301  
 lymphatics of, 779  
 muscles and fasciae of, 522  
 surface markings of, 1319  
 veins of, 747  
 jaw, bones of, 256  
 lateral cartilage, 1009  
 motor neurons, 896  
 Urachus, 189  
 Ureter, 1216  
 abdominal part of, 1216  
 arteries of, 1217  
 lymphatic vessels of, 793  
 muscles of, 1223  
 nerves of, 1217  
 orifices of, 1222  
*pars abdominalis*, 1216  
*pelvina*, 1216  
 pelvic part of, 1216  
 structure of, 1217  
*tunica adventitia*, 1217  
*mucosa*, 1217  
 Urethra, development of, 190  
 female, 1228  
 male, 1225  
 applied anatomy of, 1226  
 cavernous portion of, 1226  
 crest or verumontanum of, 1225  
 lymphatic vessels of, 794  
 membranous portion of, 1226  
 prostatic portion of, 1225  
 sinus of, 1225  
 structure of, 1226  
*muliebris*, 1228  
*virilis*, 1225  
*pars cavernosa*, 1226  
*membranacea*, 1226  
*prostatica*, 1225  
 Urethral artery, 705  
 bulb, 1226  
 crest, in female, 1228  
 in male, 1225  
 glands, 1226  
 orifice, external, 1226, 1257  
 internal, 1222  
 plate, 190  
 Urinary bladder, male, 1218  
 female, 1221  
*meatus*, 1257  
 organs, 1206  
 development of, 180  
 lymphatic vessels of, 793  
 Urogenital apparatus, 1206  
 diaphragm, 519  
 fold, 181  
 organs, 1206  
 ostium, primitive, 190  
 Urorectal septum, 172  
 Uterine artery, 701  
 glands, 1252  
 plexus of nerves, 1005  
 plexuses of veins, 761  
 tube, 1247  
 abdominal ostium of, 1247  
 ampulla of, 1247  
*appendices vesiculosae*, 1247  
 applied anatomy, 1247  
 development of, 182  
*fimbriae*, 1247  
 infundibulum of, 1247  
 isthmus of, 1247  
 Uterosacral ligaments, 1250  
 Uterus, 1248  
 in adult, 1252  
 after parturition, 1252  
 applied anatomy of, 1254  
 body of, 1249  
 cervix of, 1249  
 development of, 182  
 during menstruation, 1252  
 pregnancy, 1252  
 in fetus, 1251  
 form, size, and situation of, 1251  
 Uterus, fundus of, 1249  
 interior of, 1250  
 isthmus of, 1249  
 ligaments of, 1250  
 lymphatic vessels of, 795  
 masculinus, or prostatic utricle, 1225, 1226  
 nerves of, 1253  
 in old age, 1252  
 at puberty, 1251  
 structure of, 1252  
*tunica mucosa*, 1252  
*muscularis*, 1252  
 vessels of, 1253  
 virgin state of, 1249  
 Utricle, prostatic, 1226  
 of vestibule, 1062  
 Utriculus, 1062  
 Uvea, 1025  
 Uvula of cerebellum, 839  
 palatine, 1112  
*vermis*, 839  
*vesicae*, 1222  
 Uvular lobe, 839
- V**
- VAGINA, 1255  
 columns of, 1255  
 fornices of, 1255  
 lymphatic vessels of, 795  
 structure of, 1255  
*tunica mucosa*, 1255  
*muscularis*, 1255  
*Vaginae mucosae*, 380  
 Vaginal artery, 702  
 bulb, 1257  
 orifice, 1257  
 plexus of nerves, 1005  
 plexuses of veins, 762  
 process of temporal bone, 243, 244  
 processes of sphenoid bone, 250  
 Vagus nerve, 940  
 applied anatomy of, 943  
 ganglion of root of, 941  
 of trunk of, 941  
 nuclei of, 829, 940  
*Vallecula cerebelli*, 837  
 Vallecule of tongue, 1082  
 Vallum, 1128  
 Valsalva, sinuses of, 610, 612  
 Valve, bicuspid, 612  
 colic, 1179  
 of coronary sinus, 608, 730  
 Eustachian, 607, 608  
 ileocolic, 1179  
 of inferior vena cava, 607, 762  
 mitral, 612  
 pyloric, 1164  
 Thebesian, 608, 730  
 tricuspid, 609  
 of Vieussens, 842  
 Valves, anal, 1184  
 of heart, development of, 151  
 of Houston, 1183  
 of Kerkring, 1173  
 of lymphatics, 768, 769  
 right and left venous, 146  
 semilunar aortic, 612  
 pulmonary, 610  
 of veins, 599  
*Valvula bicuspidalis [metralis]*, 612  
*coli*, 1179  
*sinus coronarii [Thebesii]*, 608  
*tricuspidalis*, 609  
*venae cavae inferioris*, 608  
*Valvulae conniventes*, 1173  
 Vas aberrans of Haller, 1236  
*deferens*, 1235  
*spirale*, 1065  
*Vasa aberrantia* [from brachial artery], 673  
*afferentia* [lymph glands], 770

- Vasa brevia arteries, 691  
*efferentia* [lymph glands], 770  
*intestini tenuis* arteries, 692  
*vasorum* [arteries], 597  
   [veins], 600  
 Vascular areas of yolk-sac, 141  
   capsule of lens, 136  
   system, changes in, at birth, 618  
     development of, 141  
     peculiarities in fetus, 615  
 Vasomotor nerve fibres, 802  
 Vastus externus muscle, 566  
   intermedius muscle, 566  
   internus muscle, 566  
   lateralis muscle, 566  
   medialis muscle, 566  
 Vater, ampulla of, 1200  
 Vein or Veins, of abdomen, 759  
   anastomotic, of Labbe, 739  
   angular, 733  
   auditory, internal, 1067  
   auricular, posterior, 734  
   axillary, 750  
   azygos, 753  
   basal, 740  
   basilic, 748  
     median, 747  
   basivertebral, 755  
   brachial, 750  
   brachiocephalis, 751  
   of brain, 739  
   bronchial, 754, 1108  
   cardiac, 730  
     anterior, 731  
     great, 730  
     small, 730  
     smallest, 731  
   cardinal, 157  
   cava, inferior, 762  
     superior, 753  
   cephalic, 747  
     accessory, 748  
   cerebellar, 740  
   cerebral, 739, 740  
     anterior, 740  
     choroid, 740  
     deep middle, 740  
     external, 739  
     great, 740  
     inferior, 739  
     internal, 740  
     middle, 739  
     superior, 739  
     terminal, 740  
   cervical, deep, 738  
   choroid, 740  
   coats of, 599  
   comitans, of hypoglossal nerve, 736  
   common facial, 733  
     iliac, 762  
       peculiarities of, 762  
   coronary, 730  
     of stomach, 766  
   of corpus striatum, 885  
   cystic, 767  
   deep cerebral, 740  
     facial, 733  
     of forearm, 750  
     of hand, 750  
     of lower extremity, 758  
     of upper extremity, 750  
   development of, 154  
   digital, of foot, 756  
     of hand, 747  
   diploic, 738  
   dorsal digital, 747  
     metacarpal, 747, 750  
     of penis, 761  
   emissary, 746  
     applied anatomy of, 747  
   epigastric, 760  
     deep, 760  
     superficial, 756  
   of medulla spinalis, 755  
   mesenteric, 766  
   metatarsal, 758  
   middle cardiac, 731  
     sacral, 762  
   nasofrontal, 745  
   of neck, 734  
   oblique, of left atrium [Marshalli], 159, 603, 731  
   obturator, 760  
   occipital, 734  
   ophthalmic, 745  
   orbital, 734  
   ovarian, 764  
   palpebral, 733  
   pancreatic, 766  
   pancreaticoduodenal, 766  
   parumbilical, 767  
   of pelvis, 759  
   penis, dorsal of, 761  
   peroneal, 758  
   pharyngeal, 737  
   phrenic, inferior, 764  
   of lower extremity, 756  
     applied anatomy of, 757  
   of upper extremity, 747  
     applied anatomy of, 749  
   superior cava, 753  
     mesenteric, 766  
     phrenic, 751  
   supraorbital, 733  
   suprarenal, 764  
   Sylvian, 739, 740  
   systemic, 730  
   temporal, 733  
   temporomaxillary, 734  
   terminal, 740  
   of Thebesius, 731  
   thoracoepigastric, 756  
   of thorax, 751  
   thyroid, inferior, 751  
     middle, 737  
     superior, 737  
   tibial, 758  
   transverse cervical, 735  
     facial, 734  
     scapular, 735  
   Trolard, great anastomotic of, 739  
   umbilical, 100, 145  
     obliterated, 765, 1150  
   of upper extremity, 747  
   uterine plexuses, 761  
   vaginal plexuses, 762  
   valves of, 599  
   vena azygos major, 753  
     minor inferior, 753  
   cava, inferior, 762  
     superior, 753  
   vertebral anterior, 738  
     plexuses, 754  
     posterior, 738  
   of vertebral column, 754  
   vesical plexus, 761  
   vesicoprostatic plexus of, 761  
   visceral, 155  
   vitelline, 144, 155  
   volar digital, 747, 750  
     metacarpal, 750  
 Velamentous insertion of umbilical cord, 102  
 Velum interpositum, 888

- Velum medullare anterius*, 842  
     *posterius*, 842  
     medullary, 842, 845  
     palatine, 1112
- Vena angularis*, 733  
*anonyma dextra*, 751  
     *sinistra*, 751  
     *auricularis posterior*, 734  
     *axillaris*, 750  
     *azygos*, 753  
         *major*, 753  
         *minor inferior*, 753  
         *superior*, 753  
     *basilica*, 748  
     *capitis lateralis*, 160  
         *medialis*, 160  
     *cava inferior*, 762  
         applied anatomy of, 762  
         development of, 157  
         fossa for, 1194  
         peculiarities of, 762  
         valve of, 762  
         *superior*, 753  
         applied anatomy of, 754  
         development of, 157  
         surface marking of, 1300  
     *caval foramen in diaphragm*, 496  
     *cephalica accessoria*, 748  
     *cerebri magna*, 740  
         *media*, 739  
     *cervicalis profunda*, 738  
     *circumflexa ilium profunda*, 760  
     *comitans of hypoglossal nerve*, 733, 736  
     *cordis magna*, 730  
         *media*, 731  
         *parva*, 736  
     *coronaria ventriculi*, 766  
     *corporis striata*, 740  
     *cystica*, 767  
     *epigastrica inferior*, 760  
     *facialis anterior*, 733  
         *posterior*, 734  
     *femoralis*, 758  
     *frontalis*, 732  
     *gastroepiploica dextra*, 766  
         *sinistra*, 766  
     *haemorrhoidalis media*, 760  
     *hemiazzygos*, 753  
     *accessoria*, 753  
     *hypogastrica*, 760  
     *iliaca, externa*, 759  
     *intercostalis suprema dextra*, 753  
         *sinister*, 753  
     *jugularis anterior*, 736  
         *externa*, 734  
         *interna*, 736  
         *posterior*, 736  
     *linealis*, 765  
     *magna [Galen]*, 740, 889  
     *maxillaris interna*, 734  
     *mediana antibrachii*, 749  
     *cubiti*, 747  
     *mesenterica inferior*, 766  
         *superior*, 766  
     *obliqua atrii sinistri [Marshall]*, 731  
     *obturatoria*, 760  
     *occipitalis*, 734  
     *ophthalmica inferior*, 746  
         *superior*, 745  
     *poplitea*, 758  
     *portae*, 764  
     *posterior ventriculi sinistri*, 731  
     *profunda femoris*, 759  
     *saphena magna*, 756  
         *parva*, 757  
     *subclavia*, 750  
     *supraorbitalis*, 733  
     *temporalis superficialis*, 733  
     *terminalis*, 740  
     *thyreoidea superioris*, 737  
     *vertebralis*, 738  
*Venae advehentes*, 155
- Venae anonymae*, 751  
     *basivertebrales*, 755  
     *brachiales*, 750, 754  
     *cerebelli inferiores*, 740  
         *superiores*, 740  
     *cerebri*, 739  
         *inferiores*, 739  
         *internae*, 740  
         *superiores*, 739  
     *comitantes*, 729  
     *cordis*, 730  
         *minimae*, 608  
     *digitales plantares*, 758  
     *diploicae*, 738  
     *dorsales penis*, 761  
     *Galen*, 889  
     *gastricae breves*, 766  
     *glutinae inferiores*, 760  
         *superiores*, 760  
     *hepaticae*, 764  
     *iliacae communes*, 762  
     *intervertebrales*, 755  
     *linguales*, 736  
     *lumbales*, 763  
     *mammariae internae*, 751  
     *ovariae*, 764  
     *pancreaticae*, 766  
     *pancreaticoduodenales*, 766  
     *parumbilicales*, 767  
     *pharyngeae*, 737  
     *phrenicae inferiores*, 764  
     *propriae renales*, 1214  
     *pulmonales*, 736  
     *rectae [kidney]*, 1214  
     *renales*, 764  
     *revehentes*, 156  
     *sacrales laterales*, 760  
         *mediales*, 762  
     *spermaticae*, 763  
     *spinales*, 755  
     *stellatae [kidney]*, 1214  
     *suprarenales*, 764  
     *thyreoideae inferiores*, 751  
     *tibialis anteriores*, 758  
         *posteriores*, 758  
     *vorticosae*, 1022, 1031
- Venesection*, 749
- Venous arch, dorsal*, 756  
     *plantar cutaneous*, 756  
     *lacunae of dura mater*, 741  
     *mesocardium*, 603  
     *plexus, ovarian*, 764, 1246  
     *pampiniform*, 763, 1230, 1246  
     *pharyngeal*, 737  
     *pterygoid*, 734  
     *pudendal*, 761  
     *spermatic*, 763, 1230  
     *uterine*, 761  
     *vaginal*, 762  
     *sinuses*, 727  
         of *dura mater*, 740  
         *valves, right and left*, 146
- Ventral aortae*, 145  
     *cochlear nucleus*, 836  
     *fissure of medulla oblongata*, 822  
     *lamina*, 119  
     *mesogastrium*, 168  
     *pulmonary nerves*, 943  
     *spinal artery*, 660
- Ventricle of fornix*, 886  
     *fourth, floor of*, 847  
     of *mid-brain*, 854  
     *terminal, of medulla spinalis*, 810  
     of *Verga*, 886
- Ventricles of brain, fourth*, 845  
     *lateral*, 877  
     *third*, 864  
     of *heart, left*, 611  
     *primitive*, 145  
     *right*, 608  
     of *larynx*, 1086
- Ventricular folds of larynx*, 1085  
     *ligament of larynx*, 1085
- Ventricular septum*, 149, 612
- Ventriculus*, 1161  
     *dexter*, 608  
     *laryngis [Morgagni]*, 1086  
     *lateralis*, 877  
         *pars centralis*, 877  
     *quartus*, 845  
     *tela submucosa*, 1165  
     *tertius*, 864  
     *tunica mucosa*, 1165  
         *muscularis*, 1164  
             *fibrae obliquae*, 1164  
             *stratum circularis*, 1164  
             *longitudinale*, 1164  
         *serosa*, 1164
- Ventromedian fissure of medulla oblongata*, 822
- Verga, ventricle of*, 886
- Vermian fossa*, 228
- Vermiform process or appendix*, 1178  
     *structure of*, 1178
- Vermis of cerebellum*, 837
- Vernix caseosa*, 116
- Vertebra, antitlinal*, 202 *note*  
     *prominens*, 201  
     *ossification of*, 211
- Vertebrae*, 196  
     *cervical*, 198  
     *cervicales*, 198  
     *characteristics of*, 197  
     *coccygeal*, 205  
     *ligaments of*, 384-386  
     *lumbales*, 204  
     *lumbar*, 204  
     *ossification of*, 210  
     *sacral*, 205  
     *sacrales*, 205  
     *structure of*, 197  
     *thoracales*, 201  
     *thoracic*, 201
- Ventral arch*, 197  
     *arches, articulations of*, 386  
     *artery*, 659  
     *canal*, 214  
     *column*, 196, 212  
         *applied anatomy of*, 214  
         *articulations of*, 384  
         *curves of*, 212  
         *ossification of*, 210  
         *surface form of*, 1293  
         *veins of*, 754  
     *foramen*, 197  
     *groove*, 214  
     *notches*, 197  
     *part of base of skull*, 106  
     *ribs*, 221  
     *vein*, 738  
     *venous plexuses*, 754
- Vertical index of skull*, 296  
     *lingualis muscle*, 1130  
     *part of palatine bone*, 266
- Verticalis linguae muscle*, 1130
- Verumontanum*, 1225
- Vesica fellea*, 1199  
     *tunica mucosa*, 1199  
         *muscularis*, 1199  
         *serosa*, 1199  
     *urinaria*, 1218  
     *tela submucosa*, 1223  
     *tunica mucosa*, 1223  
         *muscularis*, 1223  
         *serosa*, 1223
- Vesical artery*, 701  
     *layer of pelvic fascia*, 512  
     *plexus of nerves*, 1005  
         of *veins*, 761
- Vesicle, auditory*, 138  
     *blastodermic*, 85  
     *germinal*, 78  
     *lens*, 134  
     *optic*, 126, 134
- Vesicles, cerebral*, 88, 120
- Vesicoprostatic plexus of veins*, 761

Vesicouterine excavation, 1152  
*Vesiculae seminales*, 1236  
     applied anatomy of, 1237  
     lymphatic vessels of, 794, 795  
     nerves of, 1237  
     structure of, 1237  
     vessels of, 1237  
 Vesicular ovarian follicles, 1245  
 Vestibular arteries, 1068  
     bulb, 1257  
     fissure, 1060  
     ganglion, 1068  
     glands, greater, 1258  
     lip, 1065  
     membrane, 1063  
     nerve, 935, 1068  
         nuclei of, 836, 935  
     root of acoustic nerve, 935  
 Vestibule, aortic, 612  
     of internal ear, 1058  
     of larynx, 1085  
     of mouth, 110  
     of nasal cavity, 1010  
     of omental bursa, 1156  
     of vagina, 1257  
 Vestibulospinal tract, 815  
*Vestibulum*, 1058  
     *oris*, 1100  
     *vaginae*, 1257  
 Vestigial fold of Marshall, 731  
     of pericardium, 603  
 Vicq d'Azyr, bundle of, 857, 860, 886  
 Vidian artery, 642, 648  
     nerve, 920  
 Vieussens, valve of, 842  
 Villi, arachnoid, 905  
     of chorion, 99  
     of intestine, 1173  
*Vinula brevis*, 540  
*longa*, 540  
*tendina*, 540  
 Visceral arches, 108  
     veins, 155  
 Visual area of cortex, 893  
     centres, higher or cortical, 864, 909  
         lower, 864, 909  
         purple, 1026  
 Visuopsychic, area, 893  
 Visuosensory area, 893  
 Vitelline circulation, 93, 143  
     duct, 168  
     fluid, 93  
     membrane, 83  
     veins, 144, 156  
 Vitreous body of eye, 1030  
     development of, 136  
     table of skull, 196  
 Vocal cords, false, 1085  
     inferior, 1086  
     superior, 1085  
     true, 1086  
     folds, 1086  
     process of arytenoid cartilage, 1081  
 Vocalis muscle, 1089  
 Voice, organs of, 1079  
 Volar arch, deep, 679

Volar arch, superficial, 682,  
     applied anatomy of, 682  
     surface markings of, 1322  
     branch of ulnar nerve, 968  
     carpal artery, 678  
     ligament, 547  
     net-work, 678  
     digital arteries, 682  
         nerves, 965  
     interosseous artery, 680  
         nerve, 965  
     metacarpal arteries, 679  
     veins, 750  
     venous arches, 750  
 Volaris indicis radialis artery, 679  
 Voluntary muscles, 64  
 Vomer, 269  
     articulations of, 271  
     ossification of, 270  
 Vomer nasal cartilage, 1012  
     organs, 113, 1012  
 Vulva, 1256

W

WAGNER and Meissner, corpuscles of, 1070  
 Waldeyer, germinal epithelium of, 184  
     odontoblasts of, 1119  
     zona vasculosa of, 1246  
 Wallerian degeneration, 815  
 Wandering cells, 42  
 Wharton, duct of, 1136  
     jelly of, 97  
 White fibrocartilage, 49  
     fibrous tissue, 43  
     line of pelvic fascia, 512  
     nerve fibres, 73  
     nervous substance, 70  
         of cerebellum, 839  
         of cerebral hemispheres, 889  
         of medulla spinalis, 814  
         of Schwann, 73  
 Willis, circle of, 653  
 Windpipe, 1091  
 Wings of sphenoid, 248, 249  
 Winslow, foramen of, 170, 689, 1155  
 Wirsung, duct of, 1204  
 Wisdom teeth, 1118  
 Wolffian body, 181  
     bulbs, 191  
     duct, 137  
     tubules, 180  
 Womb, 1248  
 Wormian bones, 255  
     applied anatomy of, 255  
 Wrisberg, cardiac ganglion of, 1002  
     cartilages of, 1082  
     ligament of, 442  
     nerve of, 964  
     nervus intermedius of, 929  
 Wrist-joint, 425  
     applied anatomy of, 426  
     surface anatomy of, 1319

X

XIPHOID appendix, 220  
     process, 220

Y

Y-SHAPED cartilage of acetabulum, 340  
     ligament of Bigelow, 433  
 Yellow elastic fibrocartilage, 50  
     tissue, 44  
     spot of retina, 1026, 1029  
 Yolk, formative, 78  
     nutritive, 78  
 Yolk-sac, 93  
 Yolk-stalk, 168

Z

ZIGZAG tubule, 1212  
 Zinn, ligament or tendon of, 1035  
     zonule of, 1030  
*Zona arcuata*, 1065  
*fasciculata*, 1272  
*glomerulosa*, 1272  
*incerta*, 860  
*orbicularis*, 432  
*pectinata*, 1065  
*pellucida*, 79  
*reticularis*, 1272  
*striata*, 79  
*vasculosa* [ovary], 1246  
     of Waldeyer, 1246  
 Zones of abdomen, 1147  
*Zonula ciliaris*, 1030  
 Zonule of Zinn, 1030  
 Zygomatic arch, 282  
     bone, 263  
         articulations of, 265  
         foramina of, 264  
         frontosphenoidal process of, 264  
         maxillary process of, 265  
         orbital process of, 264  
         ossification of, 265  
         temporal process of, 265  
         branch of facial nerve, 933  
         fossa, 273  
         nerve, 917  
         process of frontal bone, 235  
         of maxilla, 260  
         of temporal bone, 237  
 Zuckerkandl, aortic bodies of, 1274  
 Zygomaticofacial foramen, 263, 286  
     nerve, 918  
 Zygomaticofrontal suture, 282  
 Zygomaticoörbital foramina, 264  
 Zygomaticotemporal foramen, 263, 282  
     nerve, 918  
     suture, 282  
 Zygomaticus muscle, 470

MAY 4 - 1915





















**BOUND**

SEP 6 1968 Sept 6. 18

UNIV. OF MICHIGAN  
LIBRARY

UNIVERSITY OF MICHIGAN



3 9015 06801 8871

